AUTHENTICATED
U.S. GOVERNMENT
INFORMATION
GPO

Subpart E—Procedures for Testing Physical (Design) and Performance Characteristics of Reference Methods and Class I and Class II Equivalent Methods for $PM_{2.5}$ or $PM_{10-2.5}$

SOURCE: 62 FR 38799, July 18, 1997, unless otherwise noted.

§ 53.50 General provisions.

(a) A candidate method for $PM_{2.5}$ or $PM_{10-2.5}$ described in an application for a FRM or FEM determination submitted under § 53.4 shall be determined by the EPA to be a FRM or a Class I, II, or III FEM on the basis of the definitions for such methods given in § 53.1. This subpart sets forth the specific tests that must be carried out and the test results, evidence, documentation, and other materials that must be provided to EPA to demonstrate that a $PM_{2.5}$ or $PM_{10-2.5}$ sampler associated with a candidate reference method or Class I or Class II equivalent method meets all design and performance specifications set forth in appendix L or O, respectively, of part 50 of this chapter as well as additional requirements specified in this subpart E. Some or all of these tests may also be applicable to a candidate Class III equivalent method or analyzer, as may be determined under § 53.3(b)(3).

(b) *$PM_{2.5}$ methods*—(1) *Reference method.* A sampler associated with a candidate reference method for $PM_{2.5}$ shall be subject to the provisions, specifications, and test procedures prescribed in §§ 53.51 through 53.58.

(2) *Class I method.* A sampler associated with a candidate Class I equivalent method for $PM_{2.5}$ shall be subject to the provisions, specifications, and test procedures prescribed in all sections of this subpart.

(3) *Class II method.* A sampler associated with a candidate Class II equivalent method for $PM_{2.5}$ shall be subject to the provisions, specifications, and test procedures prescribed in all applicable sections of this subpart, as specified in subpart F of this part or as specified in § 53.3(a)(3).

(c) *$PM_{10-2.5}$ methods*—(1) *Reference method.* A sampler associated with a reference method for $PM_{10-2.5}$, as specified in appendix O to part 50 of this chapter, shall be subject to the requirements in this paragraph (c)(1).

(i) The $PM_{2.5}$ sampler of the $PM_{10-2.5}$ sampler pair shall be verified to be either currently designated under this part 53 as a FRM for $PM_{2.5}$, or shown to meet all requirements for designation as a FRM for $PM_{2.5}$, in accordance with this part 53.

(ii) The PM_{10C} sampler of the $PM_{10-2.5}$ sampler pair shall be verified to be of like manufacturer, design, configuration, and fabrication to the $PM_{2.5}$ sampler of the $PM_{10-2.5}$ sampler pair, except for replacement of the particle size separator specified in section 7.3.4 of appendix L to part 50 of this chapter with the downtube extension as specified in Figure O–1 of appendix O to part 50 of this chapter.

(iii) For samplers that meet the provisions of paragraphs (c)(1)(i) and (ii) of this section, the candidate $PM_{10-2.5}$ reference method may be determined to be a FRM without further testing.

(2) *Class I method.* A sampler associated with a Class I candidate equivalent method for $PM_{10-2.5}$ shall meet the requirements in this paragraph (c)(2).

(i) The $PM_{2.5}$ sampler of the $PM_{10-2.5}$ sampler pair shall be verified to be either currently designated under this part 53 as a FRM or Class I FEM for $PM_{2.5}$, or shown to meet all requirements for designation as a FRM or Class I FEM for $PM_{2.5}$, in accordance with this part 53.

(ii) The PM_{10c} sampler of the $PM_{10-2.5}$ sampler pair shall be verified to be of similar design to the $PM_{10-2.5}$ sampler and to meet all requirements for designation as a FRM or Class I FRM for $PM_{2.5}$, in accordance with this part 53, except for replacement of the particle size separator specified in section 7.3.4 of appendix L to part 50 of this chapter with the downtube extension as specified in Figure O–1 of appendix O to part 50 of this chapter.

(iii) For samplers that meet the provisions of paragraphs (c)(2)(i) and (ii) of this section, the candidate $PM_{10-2.5}$ method may be determined to be a Class I FEM without further testing.

(3) *Class II method.* A sampler associated with a Class II candidate equivalent method for $PM_{10-2.5}$ shall be subject to the applicable requirements of this subpart E, as described in § 53.3(a)(5).

(d) The provisions of § 53.51 pertain to test results and documentation required to demonstrate compliance of a candidate method sampler with the design specifications set forth in 40 CFR part 50, appendix L or O, as applicable. The test procedures prescribed in §§ 53.52 through 53.59 pertain to performance tests required to demonstrate compliance of a candidate method sampler with the performance specifications set forth in 40 CFR part 50, appendix L or O, as applicable, as well as additional requirements specified in this subpart E. These latter test procedures shall be used to test the performance of candidate samplers against the performance specifications and requirements specified in each procedure and summarized in table E–1 of this subpart.

(e) Test procedures prescribed in § 53.59 do not apply to candidate reference method samplers. These procedures apply primarily to candidate Class I or Class II equivalent method samplers for $PM_{2.5}$ or $PM_{10-2.5}$ that have a sample air flow path configuration upstream of the sample filter that is modified from that specified for the FRM sampler, as set forth in 40 CFR part 50, appendix L, Figures L–1 to L–29 or 40 CFR part 50 appendix O, Figure O–1, if applicable, such as might be necessary to provide for sequential sample capability. The additional tests determine the adequacy of aerosol transport through any altered components or supplemental devices that are used in a candidate sampler upstream of the filter. In addition to the other test procedures in this subpart, these test procedures shall be used to further test the performance of such an equivalent method sampler against the performance specifications given in the procedure and summarized in table E–1 of this subpart.

(f) A 10-day operational field test of measurement precision is required under § 53.58 for both FRM and Class I FEM samplers for $PM_{2.5}$. This test requires collocated operation of three candidate method samplers at a field test site. For candidate FEM samplers, this test may be combined and carried out concurrently with the test for comparability to the FRM specified under § 53.34, which requires collocated operation of three FRM samplers and three candidate FEM samplers.

(g) All tests and collection of test data shall be performed in accordance with the requirements of reference 1, section 4.10.5 (ISO 9001) and reference 2, part B, (section 6) and Part C, (section 7) in appendix A of this subpart. All test data and other documentation obtained specifically from or pertinent to these tests shall be identified, dated, signed by the analyst performing the test, and submitted to EPA in accordance with subpart A of this part.

[71 FR 61289, Oct. 17, 2006]

§ 53.51 Demonstration of compliance with design specifications and manufacturing and test requirements.

(a) *Overview.* (1) Paragraphs (a) through (f) of this section specify certain documentation that must be submitted and tests that are required to demonstrate that samplers associated with a designated FRM or FEM for $PM_{2.5}$ or $PM_{10-2.5}$ are properly manufactured to meet all applicable design and performance specifications and have been properly tested according to all applicable test requirements for such designation. Documentation is required to show that instruments and components of a $PM_{2.5}$ or $PM_{10-2.5}$ sampler are manufactured in an ISO 9001-registered facility under a quality system that meets ISO–9001 requirements for manufacturing quality control and testing.

(2) In addition, specific tests are required by paragraph (d) of this section to verify that critical features of FRM samplers—the particle size separator and the surface finish of surfaces specified to be anodized—meet the specifications of 40 CFR part 50, appendix L or appendix O, as applicable. A checklist is required to provide certification by an ISO-certified auditor that all performance and other required tests have been properly and appropriately conducted, based on a reasonable and appropriate sample of the actual operations or their documented records. Following designation of the method,

another checklist is required initially to provide an ISO-certified auditor's certification that the sampler manufacturing process is being implemented under an adequate and appropriate quality system.

(3) For the purposes of this section, the definitions of ISO 9001-registered facility and ISO-certified auditor are found in § 53.1. An exception to the reliance by EPA on ISO-certified auditors is the requirement for the submission of the operation or instruction manual associated with the candidate method to EPA as part of the application. This manual is required under § 53.4(b)(3). The EPA has determined that acceptable technical judgment for review of this manual may not be assured by ISO-certified auditors, and approval of this manual will therefore be performed by EPA.

(b) *ISO registration of manufacturing facility*. The applicant must submit documentation verifying that the samplers identified and sold as part of a designated $PM_{2.5}$ or $PM_{10-2.5}$ FRM or FEM will be manufactured in an ISO 9001-registered facility and that the manufacturing facility is maintained in compliance with all applicable ISO 9001 requirements (reference 1 in appendix A of this subpart). The documentation shall indicate the date of the original ISO 9001 registration for the facility and shall include a copy of the most recent certification of continued ISO 9001 facility registration. If the manufacturer does not wish to initiate or complete ISO 9001 registration for the manufacturing facility, documentation must be included in the application to EPA describing an alternative method to demonstrate that the facility meets the same general requirements as required for registration to ISO–9001. In this case, the applicant must provide documentation in the application to demonstrate, by required ISO-certified auditor's inspections, that a quality system is in place which is adequate to document and monitor that the sampler system components and final assembled samplers all conform to the design, performance and other requirements specified in this part and in 40 CFR part 50, appendix L.

(c) *Sampler manufacturing quality control*. The manufacturer must ensure that all components used in the manufacture of $PM_{2.5}$ or $PM_{10-2.5}$ samplers to be sold as part of a FRM or FEM and that are specified by design in 40 CFR part 50, appendix L or O (as applicable), are fabricated or manufactured exactly as specified. If the manufacturer's quality records show that its quality control (QC) and quality assurance (QA) system of standard process control inspections (of a set number and frequency of testing that is less than 100 percent) complies with the applicable QA provisions of section 4 of reference 4 in appendix A of this subpart and prevents nonconformances, 100 percent testing shall not be required until that conclusion is disproved by customer return or other independent manufacturer or customer test records. If problems are uncovered, inspection to verify conformance to the drawings, specifications, and tolerances shall be performed. Refer also to paragraph (e) of this section—final assembly and inspection requirements.

(d) *Specific tests and supporting documentation required to verify conformance to critical component specifications*— (1) *Verification of $PM_{2.5}$ (WINS) impactor jet diameter*. For samplers utilizing the WINS impactor particle size separator specified in paragraphs 7.3.4.1, 7.3.4.2, and 7.3.4.3 of appendix L to part 50 of this chapter, the diameter of the jet of each impactor manufactured for a $PM_{2.5}$ or $PM_{10-2.5}$ sampler under the impactor design specifications set forth in 40 CFR part 50, appendix L, shall be verified against the tolerance specified on the drawing, using standard, NIST-traceable ZZ go/no go plug gages. This test shall be a final check of the jet diameter following all fabrication operations, and a record shall be kept of this final check. The manufacturer shall submit evidence that this procedure is incorporated into the manufacturing procedure, that the test is or will be routinely implemented, and that an appropriate procedure is in place for the disposition of units that fail this tolerance test.

(2) *VSCC separator*. For samplers utilizing the BGI VSCC™ Very Sharp Cut Cyclone particle size separator specified in paragraph 7.3.4.4 of appendix L to part 50 of this chapter, the VSCC

manufacturer shall identify the critical dimensions and manufacturing tolerances for the device, develop appropriate test procedures to verify that the critical dimensions and tolerances are maintained during the manufacturing process, and carry out those procedures on each VSCC manufactured to verify conformance of the manufactured products. The manufacturer shall also maintain records of these tests and their results and submit evidence that this procedure is incorporated into the manufacturing procedure, that the test is or will be routinely implemented, and that an appropriate procedure is in place for the disposition of units that fail this tolerance test.

(3) *Verification of surface finish.* The anodization process used to treat surfaces specified to be anodized shall be verified by testing treated specimen surfaces for weight and corrosion resistance to ensure that the coating obtained conforms to the coating specification. The specimen surfaces shall be finished in accordance with military standard specification 8625F, Type II, Class I (reference 4 in appendix A of this subpart) in the same way the sampler surfaces are finished, and tested, prior to sealing, as specified in section 4.5.2 of reference 4 in appendix A of this subpart.

(e) *Final assembly and inspection requirements.* Each sampler shall be tested after manufacture and before delivery to the final user. Each manufacturer shall document its post-manufacturing test procedures. As a minimum, each test shall consist of the following: Tests of the overall integrity of the sampler, including leak tests; calibration or verification of the calibration of the flow measurement device, barometric pressure sensor, and temperature sensors; and operation of the sampler with a filter in place over a period of at least 48 hours. The results of each test shall be suitably documented and shall be subject to review by an ISO-certified auditor.

(f) *Manufacturer's audit checklists.* Manufacturers shall require an ISO-certified auditor to sign and date a statement indicating that the auditor is aware of the appropriate manufacturing specifications contained in 40 CFR part 50, appendix L or O (as applicable), and the test or verification requirements in this subpart. Manufacturers shall also require an ISO-certified auditor to complete the checklists, shown in figures E–1 and E–2 of this subpart, which describe the manufacturer's ability to meet the requirements of the standard for both designation testing and product manufacture.

(1) *Designation testing checklist.* The completed statement and checklist as shown in figure E–1 of this subpart shall be submitted with the application for FRM or FEM determination.

(2) *Product manufacturing checklist.* Manufacturers shall require an ISO-certified auditor to complete a Product Manufacturing Checklist (figure E–2 of this subpart), which evaluates the manufacturer on its ability to meet the requirements of the standard in maintaining quality control in the production of FRM or FEM devices. The completed checklist shall be submitted with the application for FRM or FEM determination.

[71 FR 61290, Oct. 17, 2006]

§ 53.52 Leak check test.

(a) *Overview.* In section 7.4.6 of 40 CFR part 50, appendix L, the sampler is required to include the facility, including components, instruments, operator controls, a written procedure, and other capabilities as necessary, to allow the operator to carry out a leak test of the sampler at a field monitoring site without additional equipment. This test procedure is intended to test the adequacy and effectiveness of the sampler's leak check facility. Because of the variety of potential sampler configurations and leak check procedures possible, some adaptation of this procedure may be necessary to accommodate the specific sampler under test. The test conditions and performance specifications associated with this test are summarized in table E–1 of this subpart. The candidate test sampler must meet all test parameters and test specifications to successfully pass this test.

(b) *Technical definitions.* (1) External leakage includes the total flow rate of external ambient air which enters the sampler other than through the sampler inlet and which passes through

any one or more of the impactor, filter, or flow rate measurement components.

(2) Internal leakage is the total sample air flow rate that passes through the filter holder assembly without passing through the sample filter.

(c) *Required test equipment.* (1) Flow rate measurement device, range 70 mL/min to 130 mL/min, 2 percent certified accuracy, NIST-traceable.

(2) Flow rate measurement adaptor (40 CFR part 50, appendix L, figure L-30) or equivalent adaptor to facilitate measurement of sampler flow rate at the top of the downtube.

(3) Impermeable membrane or disk, 47 mm nominal diameter.

(4) Means, such as a micro-valve, of providing a simulated leak flow rate through the sampler of approximately 80 mL/min under the conditions specified for the leak check in the sampler's leak check procedure.

(5) Teflon sample filter, as specified in section 6 of 40 CFR part 50, appendix L.

(d) *Calibration of test measurement instruments.* Submit documentation showing evidence of appropriately recent calibration, certification of calibration accuracy, and NIST-traceability (if required) of all measurement instruments used in the tests. The accuracy of flow rate meters shall be verified at the highest and lowest pressures and temperatures used in the tests and shall be checked at zero and one or more non-zero flow rates within 7 days of use for this test.

(e) *Test setup.* (1) The test sampler shall be set up for testing as described in the sampler's operation or instruction manual referred to in §53.4(b)(3). The sampler shall be installed upright and set up in its normal configuration for collecting PM samples, except that the sample air inlet shall be removed and the flow rate measurement adaptor shall be installed on the sampler's downtube.

(2) The flow rate control device shall be set up to provide a constant, controlled flow rate of 80 mL/min into the sampler downtube under the conditions specified for the leak check in the sampler's leak check procedure.

(3) The flow rate measurement device shall be set up to measure the controlled flow rate of 80 mL/min into the sampler downtube under the conditions specified for the leak check in the sampler's leak check procedure.

(f) *Procedure.* (1) Install the impermeable membrane in a filter cassette and install the cassette into the sampler. Carry out the internal leak check procedure as described in the sampler's operation/instruction manual and verify that the leak check acceptance criterion specified in table E–1 of this subpart is met.

(2) Replace the impermeable membrane with a Teflon filter and install the cassette in the sampler. Remove the inlet from the sampler and install the flow measurement adaptor on the sampler's downtube. Close the valve of the adaptor to seal the flow system. Conduct the external leak check procedure as described in the sampler's operation/instruction manual and verify that the leak check acceptance criteria specified in table E–1 of this subpart are met.

(3) Arrange the flow control device, flow rate measurement device, and other apparatus as necessary to provide a simulated leak flow rate of 80 mL/min into the test sampler through the downtube during the specified external leak check procedure. Carry out the external leak check procedure as described in the sampler's operation/instruction manual but with the simulated leak of 80 mL/min.

(g) *Test results.* The requirements for successful passage of this test are:

(1) That the leak check procedure indicates no significant external or internal leaks in the test sampler when no simulated leaks are introduced.

(2) That the leak check procedure properly identifies the occurrence of the simulated external leak of 80 mL/min.

[62 FR 38799, July 18, 1997, as amended at 71 FR 61291, Oct. 17, 2006]

§ 53.53 Test for flow rate accuracy, regulation, measurement accuracy, and cut-off.

(a) *Overview.* This test procedure is designed to evaluate a candidate sampler's flow rate accuracy with respect to the design flow rate, flow rate regulation, flow rate measurement accuracy, coefficient of variability measurement accuracy, and the flow rate

cut-off function. The tests for the first four parameters shall be conducted over a 6-hour time period during which reference flow measurements are made at intervals not to exceed 5 minutes. The flow rate cut-off test, conducted separately, is intended to verify that the sampler carries out the required automatic sample flow rate cut-off function properly in the event of a low-flow condition. The test conditions and performance specifications associated with this test are summarized in table E–1 of this subpart. The candidate test sampler must meet all test parameters and test specifications to successfully pass this test.

(b) *Technical definitions.* (1) Sample flow rate means the quantitative volumetric flow rate of the air stream caused by the sampler to enter the sampler inlet and pass through the sample filter, measured in actual volume units at the temperature and pressure of the air as it enters the inlet.

(2) The flow rate cut-off function requires the sampler to automatically stop sample flow and terminate the current sample collection if the sample flow rate deviates by more than the variation limits specified in table E–1 of this subpart (±10 percent from the nominal sample flow rate) for more than 60 seconds during a sample collection period. The sampler is also required to properly notify the operator with a flag warning indication of the out-of-specification flow rate condition and if the flow rate cut-off results in an elapsed sample collection time of less than 23 hours.

(c) *Required test equipment.* (1) Flow rate meter, suitable for measuring and recording the actual volumetric sample flow rate at the sampler downtube, with a minimum range of 10 to 25 L/min, 2 percent certified, NIST-traceable accuracy. Optional capability for continuous (analog) recording capability or digital recording at intervals not to exceed 30 seconds is recommended. While a flow meter which provides a direct indication of volumetric flow rate is preferred for this test, an alternative certified flow measurement device may be used as long as appropriate volumetric flow rate corrections are made based on measurements of actual ambient temperature and pressure conditions.

(2) Ambient air temperature sensor, with a resolution of 0.1 °C and certified to be accurate to within 0.5 °C (if needed). If the certified flow meter does not provide direct volumetric flow rate readings, ambient air temperature measurements must be made using continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(3) Barometer, range 600 mm Hg to 800 mm Hg, certified accurate to 2 mm Hg (if needed). If the certified flow meter does not provide direct volumetric flow rate readings, ambient pressure measurements must be made using continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(4) Flow measurement adaptor (40 CFR part 50, appendix L, figure L-30) or equivalent adaptor to facilitate measurement of sample flow rate at the sampler downtube.

(5) Valve or other means to restrict or reduce the sample flow rate to a value at least 10 percent below the design flow rate (16.67 L/min). If appropriate, the valve of the flow measurement adaptor may be used for this purpose.

(6) Means for creating an additional pressure drop of 55 mm Hg in the sampler to simulate a heavily loaded filter, such as an orifice or flow restrictive plate installed in the filter holder or a valve or other flow restrictor temporarily installed in the flow path near the filter.

(7) Teflon sample filter, as specified in section 6 of 40 CFR part 50, appendix L (if required).

(d) *Calibration of test measurement instruments.* Submit documentation showing evidence of appropriately recent calibration, certification of calibration accuracy, and NIST-traceability (if required) of all measurement instruments used in the tests. The accuracy of flow-rate meters shall be verified at the highest and lowest pressures and temperatures used in the tests and shall be checked at zero and at least one flow rate within ±3 percent of 16.7 L/min within 7 days prior to use for this test. Where an instrument's measurements are to be recorded with

an analog recording device, the accuracy of the entire instrument-recorder system shall be calibrated or verified.

(e) *Test setup.* (1) Setup of the sampler shall be as required in this paragraph (e) and otherwise as described in the sampler's operation or instruction manual referred to in §53.4(b)(3). The sampler shall be installed upright and set up in its normal configuration for collecting PM samples. A sample filter and (or) the device for creating an additional 55 mm Hg pressure drop shall be installed for the duration of these tests. The sampler's ambient temperature, ambient pressure, and flow rate measurement systems shall all be calibrated per the sampler's operation or instruction manual within 7 days prior to this test.

(2) The inlet of the candidate sampler shall be removed and the flow measurement adaptor installed on the sampler's downtube. A leak check as described in the sampler's operation or instruction manual shall be conducted and must be properly passed before other tests are carried out.

(3) The inlet of the flow measurement adaptor shall be connected to the outlet of the flow rate meter.

(4) For the flow rate cut-off test, the valve or means for reducing sampler flow rate shall be installed between the flow measurement adaptor and the downtube or in another location within the sampler such that the sampler flow rate can be manually restricted during the test.

(f) *Procedure.* (1) Set up the sampler as specified in paragraph (e) of this section and otherwise prepare the sampler for normal sample collection operation as directed in the sampler's operation or instruction manual. Set the sampler to automatically start a 6-hour sample collection period at a convenient time.

(2) During the 6-hour operational flow rate portion of the test, measure and record the sample flow rate with the flow rate meter at intervals not to exceed 5 minutes. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, ambient temperature and pressure shall be measured at the same frequency as that of the certified flow rate measurements. Note and record the actual start and stop times for the 6-hour flow rate test period.

(3) Following completion of the 6-hour flow rate test period, install the flow rate reduction device and change the sampler flow rate recording frequency to intervals of not more than 30 seconds. Reset the sampler to start a new sample collection period. Manually restrict the sampler flow rate such that the sampler flow rate is decreased slowly over several minutes to a flow rate slightly less than the flow rate cut-off value (15.0 L/min). Maintain this flow rate for at least 2.0 minutes or until the sampler stops the sample flow automatically. Manually terminate the sample period, if the sampler has not terminated it automatically.

(g) *Test results.* At the completion of the test, validate the test conditions and determine the test results as follows:

(1) *Mean sample flow rate.* (i) From the certified measurements (Q_{ref}) of the test sampler flow rate obtained by use of the flow rate meter, tabulate each flow rate measurement in units of L/min. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, each measured flow rate shall be corrected using its corresponding temperature and pressure measurement values. Calculate the mean flow rate for the sample period ($Q_{ref,ave}$) as follows:

EQUATION 1

$$Q_{ref,ave} = \frac{\sum_{i=1}^{n} Q_{ref,i}}{n}$$

where:

n equals the number of discrete certified flow rate measurements over the 6-hour test period.

(ii)(A) Calculate the percent difference between this mean flow rate value and the design value of 16.67 L/min, as follows:

EQUATION 2

$$\% \text{ Difference} = \frac{Q_{ref,ave} - 16.67}{16.67} \text{ x } 100\%$$

(B) To successfully pass the mean flow rate test, the percent difference calculated in Equation 2 of this paragraph (g)(1)(ii) must be within ±5 percent.

(2) *Sample flow rate regulation.* (i) From the certified measurements of the test sampler flow rate, calculate the sample coefficient of variation (CV) of the discrete measurements as follows:

EQUATION 3

$$\%CV_{ref} = \frac{1}{Q_{ref,ave}} x \sqrt{\frac{\sum_{i=1}^{n} Q_{ref,i}^2 - \frac{1}{n}\left(\sum_{i-1}^{n} Q_{ref,i}\right)^2}{n-1}} x\ 100\%$$

(ii) To successfully pass the flow rate regulation test, the calculated coefficient of variation for the certified flow rates must not exceed 2 percent.

(3) *Flow rate measurement accuracy.* (i) Using the mean volumetric flow rate reported by the candidate test sampler at the completion of the 6-hour test period ($Q_{ind,ave}$), determine the accuracy of the reported mean flow rate as:

EQUATION 4

$$\%\ \text{Difference} = \frac{|Q_{ind,ave} - Q_{ref,ave}|}{Q_{ref,ave}} x\ 100\%$$

(ii) To successfully pass the flow rate measurement accuracy test, the percent difference calculated in Equation 4 of this paragraph (g)(3) shall not exceed 2 percent.

(4) *Flow rate coefficient of variation measurement accuracy.* (i) Using the flow rate coefficient of variation indicated by the candidate test sampler at the completion of the 6-hour test ($\%CV_{ind}$), determine the accuracy of this reported coefficient of variation as:

EQUATION 5

$$\text{Difference}\ (\%) = |\%CV_{ind} - \%CV_{ref}|$$

(ii) To successfully pass the flow rate CV measurement accuracy test, the absolute difference in values calculated in Equation 5 of this paragraph (g)(4) must not exceed 0.3 (CV%).

(5) *Flow rate cut-off.* (i) Inspect the measurements of the sample flow rate during the flow rate cut-off test and determine the time at which the sample flow rate decreased to a value less than the cut-off value specified in table E–1 of this subpart. To pass this test, the sampler must have automatically stopped the sample flow at least 30 seconds but not more than 90 seconds after the time at which the sampler flow rate was determined to have decreased to a value less than the cut-off value.

(ii) At the completion of the flow rate cut-off test, download the archived data from the test sampler and verify that the sampler's required Flow-out-of-spec and Incorrect sample period flag indicators are properly set.

[62 FR 38799, July 18, 1997, as amended at 71 FR 61291, Oct. 17, 2006]

§ 53.54 Test for proper sampler operation following power interruptions.

(a) *Overview.* (1) This test procedure is designed to test certain performance parameters of the candidate sampler during a test period in which power interruptions of various duration occur. The performance parameters tested are:

(i) Proper flow rate performance of the sampler.

(ii) Accuracy of the sampler's average flow rate, CV, and sample volume measurements.

(iii) Accuracy of the sampler's reported elapsed sampling time.

(iv) Accuracy of the reported time and duration of power interruptions.

(2) This test shall be conducted during operation of the test sampler over a continuous 6-hour test period during which the sampler's flow rate shall be measured and recorded at intervals not to exceed 5 minutes. The performance parameters tested under this procedure, the corresponding minimum performance specifications, and the applicable test conditions are summarized in table E–1 of this subpart. Each performance parameter tested, as described or determined in the test procedure, must meet or exceed the associated performance specification to successfully pass this test.

(b) *Required test equipment.* (1) Flow rate meter, suitable for measuring and

recording the actual volumetric sample flow rate at the sampler downtube, with a minimum range of 10 to 25 L/min, 2 percent certified, NIST-traceable accuracy. Optional capability for continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes is recommended. While a flow meter which provides a direct indication of volumetric flow rate is preferred for this test, an alternative certified flow measurement device may be used as long as appropriate volumetric flow rate corrections are made based on measurements of actual ambient temperature and pressure conditions.

(2) Ambient air temperature sensor (if needed for volumetric corrections to flow rate measurements), with a resolution of 0.1 °C, certified accurate to within 0.5 °C, and continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(3) Barometer (if needed for volumetric corrections to flow rate measurements), range 600 mm Hg to 800 mm Hg, certified accurate to 2 mm Hg, with continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(4) Flow measurement adaptor (40 CFR part 50, appendix L, figure L-30) or equivalent adaptor to facilitate measurement of sample flow rate at the sampler downtube.

(5) Means for creating an additional pressure drop of 55 mm Hg in the sampler to simulate a heavily loaded filter, such as an orifice or flow restrictive plate installed in the filter holder or a valve or other flow restrictor temporarily installed in the flow path near the filter.

(6) Teflon sample filter, as specified in section 6 of 40 CFR part 50, appendix L (if required).

(7) Time measurement system, accurate to within 10 seconds per day.

(c) *Calibration of test measurement instruments.* Submit documentation showing evidence of appropriately recent calibration, certification of calibration accuracy, and NIST-traceability (if required) of all measurement instruments used in the tests. The accuracy of flow rate meters shall be verified at the highest and lowest pressures and temperatures used in the tests and shall be checked at zero and at least one flow rate within ±3 percent of 16.7 L/min within 7 days prior to use for this test. Where an instrument's measurements are to be recorded with an analog recording device, the accuracy of the entire instrument-recorder system shall be calibrated or verified.

(d) *Test setup.* (1) Setup of the sampler shall be performed as required in this paragraph (d) and otherwise as described in the sampler's operation or instruction manual referred to in §53.4(b)(3). The sampler shall be installed upright and set up in its normal configuration for collecting PM samples. A sample filter and (or) the device for creating an additional 55 mm Hg pressure drop shall be installed for the duration of these tests. The sampler's ambient temperature, ambient pressure, and flow measurement systems shall all be calibrated per the sampler's operating manual within 7 days prior to this test.

(2) The inlet of the candidate sampler shall be removed and the flow measurement adaptor installed on the sample downtube. A leak check as described in the sampler's operation or instruction manual shall be conducted and must be properly passed before other tests are carried out.

(3) The inlet of the flow measurement adaptor shall be connected to the outlet of the flow rate meter.

(e) *Procedure.* (1) Set up the sampler as specified in paragraph (d) of this section and otherwise prepare the sampler for normal sample collection operation as directed in the sampler's operation or instruction manual. Set the sampler to automatically start a 6-hour sample collection period at a convenient time.

(2) During the entire 6-hour operational flow rate portion of the test, measure and record the sample flow rate with the flow rate meter at intervals not to exceed 5 minutes. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, ambient temperature and pressure shall be measured at the same frequency as that of the certified flow rate measurements. Note and record the actual start and stop times for the 6-hour flow rate test period.

(3) During the 6-hour test period, interrupt the AC line electrical power to the sampler 5 times, with durations of 20 seconds, 40 seconds, 2 minutes, 7 minutes, and 20 minutes (respectively), with not less than 10 minutes of normal electrical power supplied between each power interruption. Record the hour and minute and duration of each power interruption.

(4) At the end of the test, terminate the sample period (if not automatically terminated by the sampler) and download all archived instrument data from the test sampler.

(f) *Test results.* At the completion of the sampling period, validate the test conditions and determine the test results as follows:

(1) *Mean sample flow rate.* (i) From the certified measurements (Q_{ref}) of the test sampler flow rate, tabulate each flow rate measurement in units of L/min. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, each measured flow rate shall be corrected using its corresponding temperature and pressure measurement values. Calculate the mean flow rate for the sample period ($Q_{ref,ave}$) as follows:

EQUATION 6

$$Q_{ref,ave} = \frac{\sum_{i=1}^{n} Q_{ref,i}}{n}$$

where:

n equals the number of discrete certified flow rate measurements over the 6-hour test period, excluding flow rate values obtained during periods of power interruption.

(ii)(A) Calculate the percent difference between this mean flow rate value and the design value of 16.67 L/min, as follows:

EQUATION 7

$$\%\ \text{Difference} = \frac{Q_{ref,ave} - 16.67}{16.67} \text{ x } 100\%$$

(B) To successfully pass this test, the percent difference calculated in Equation 7 of this paragraph (f)(1)(ii) must be within ±5 percent.

(2) *Sample flow rate regulation.* (i) From the certified measurements of the test sampler flow rate, calculate the sample coefficient of variation of the discrete measurements as follows:

EQUATION 8

$$\%CV_{ref} = \frac{1}{Q_{ref,ave}} \text{x} \sqrt{\frac{\sum_{i=1}^{n} Q_{ref,i}^2 - \frac{1}{n}\left(\sum_{i-1}^{n} Q_{ref,i}\right)^2}{n-1}} \text{x } 100\%$$

(ii) To successfully pass this test, the calculated coefficient of variation for the certified flow rates must not exceed 2 percent.

(3) *Flow rate measurement accuracy.* (i) Using the mean volumetric flow rate reported by the candidate test sampler at the completion of the 6-hour test ($Q_{ind,ave}$), determine the accuracy of the reported mean flow rate as:

EQUATION 9

$$\%\ \text{Difference} = \frac{|Q_{ind,ave} - Q_{ref,ave}|}{Q_{ref,ave}} \text{ x } 100\%$$

(ii) To successfully pass this test, the percent difference calculated in Equation 9 of this paragraph (f)(3) shall not exceed 2 percent.

(4) *Flow rate CV measurement accuracy.* (i) Using the flow rate coefficient of variation indicated by the candidate test sampler at the completion of the 6-hour test ($\%CV_{ind}$), determine the accuracy of the reported coefficient of variation as:

EQUATION 10

$$\text{Difference}\ (\%) = |\%CV_{ind} - \%CV_{ref}|$$

(ii) To successfully pass this test, the absolute difference in values calculated in Equation 10 of this paragraph (f)(4) must not exceed 0.3 (CV%).

(5) Verify that the sampler properly provided a record and visual display of the correct year, month, day-of-month, hour, and minute with an accuracy of ±2 minutes, of the start of each power interruption of duration greater than 60 seconds.

(6) Calculate the actual elapsed sample time, excluding the periods of electrical power interruption. Verify that

the elapsed sample time reported by the sampler is accurate to within ±20 seconds for the 6-hour test run.

(7) Calculate the sample volume as $Q_{ref.ave}$ multiplied by the sample time, excluding periods of power interruption. Verify that the sample volume reported by the sampler is within 2 percent of the calculated sample volume to successfully pass this test.

(8) Inspect the downloaded instrument data from the test sampler and verify that all data are consistent with normal operation of the sampler.

[62 FR 38799, July 18, 1997; 63 FR 7714, Feb. 17, 1998, as amended at 71 FR 61291, Oct. 17, 2006]

§ 53.55 Test for effect of variations in power line voltage and ambient temperature.

(a) *Overview*. (1) This test procedure is a combined procedure to test various performance parameters under variations in power line voltage and ambient temperature. Tests shall be conducted in a temperature-controlled environment over four 6-hour time periods during which reference temperature and flow rate measurements shall be made at intervals not to exceed 5 minutes. Specific parameters to be evaluated at line voltages of 105 and 125 volts and temperatures of −20 °C and +40 °C are as follows:

(i) Sample flow rate.

(ii) Flow rate regulation.

(iii) Flow rate measurement accuracy.

(iv) Coefficient of variability measurement accuracy.

(v) Ambient air temperature measurement accuracy.

(vi) Proper operation of the sampler when exposed to power line voltage and ambient temperature extremes.

(2) The performance parameters tested under this procedure, the corresponding minimum performance specifications, and the applicable test conditions are summarized in table E–1 of this subpart. Each performance parameter tested, as described or determined in the test procedure, must meet or exceed the associated performance specification given. The candidate sampler must meet all specifications for the associated $PM_{2.5}$ or $PM_{10-2.5}$ method (as applicable) to pass this test procedure.

(b) *Technical definition*. Sample flow rate means the quantitative volumetric flow rate of the air stream caused by the sampler to enter the sampler inlet and pass through the sample filter, measured in actual volume units at the temperature and pressure of the air as it enters the inlet.

(c) *Required test equipment*. (1) Environmental chamber or other temperature-controlled environment or environments, capable of obtaining and maintaining temperatures at −20 °C and =40 °C as required for the test with an accuracy of ±2 °C. The test environment(s) must be capable of maintaining these temperatures within the specified limits continuously with the additional heat load of the operating test sampler in the environment. Henceforth, where the test procedures specify a test or environmental ''chamber,'' an alternative temperature-controlled environmental area or areas may be substituted, provided the required test temperatures and all other test requirements are met.

(2) Variable voltage AC power transformer, range 100 Vac to 130 Vac, with sufficient current capacity to operate the test sampler continuously under the test conditions.

(3) Flow rate meter, suitable for measuring and recording the actual volumetric sample flow rate at the sampler downtube, with a minimum range of 10 to 25 actual L/min, 2 percent certified, NIST-traceable accuracy. Optional capability for continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes is recommended. While a flow meter which provides a direct indication of volumetric flow rate is preferred for this test, an alternative certified flow measurement device may be used as long as appropriate volumetric flow rate corrections are made based on measurements of actual ambient temperature and pressure conditions.

(4) Ambient air temperature recorder, range −30 °C to =50 °C, with a resolution of 0.1 °C and certified accurate to within 0.5 °C. Ambient air temperature measurements must be made using continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(5) Barometer, range 600 mm Hg to 800 mm Hg, certified accurate to 2 mm Hg. If the certified flow rate meter does not provide direct volumetric flow rate readings, ambient pressure measurements must be made using continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(6) Flow measurement adaptor (40 CFR part 50, appendix L, figure L-30) or equivalent adaptor to facilitate measurement of sampler flow rate at the sampler downtube.

(7) Means for creating an additional pressure drop of 55 mm Hg in the sampler to simulate a heavily loaded filter, such as an orifice or flow restrictive plate installed in the filter holder or a valve or other flow restrictor temporarily installed in the flow path near the filter.

(8) AC RMS voltmeter, accurate to 1.0 volt.

(9) Teflon sample filter, as specified in section 6 of 40 CFR part 50, appendix L (if required).

(d) *Calibration of test measurement instruments.* Submit documentation showing evidence of appropriately recent calibration, certification of calibration accuracy, and NIST-traceability (if required) of all measurement instruments used in the tests. The accuracy of flow rate meters shall be verified at the highest and lowest pressures and temperatures used in the tests and shall be checked at zero and at least one flow rate within ±3 percent of 16.7 L/min within 7 days prior to use for this test. Where an instrument's measurements are to be recorded with an analog recording device, the accuracy of the entire instrument-recorder system shall be calibrated or verified.

(e) *Test setup.* (1) Setup of the sampler shall be performed as required in this paragraph (e) and otherwise as described in the sampler's operation or instruction manual referred to in § 53.4(b)(3). The sampler shall be installed upright and set up in the temperature-controlled chamber in its normal configuration for collecting PM samples. A sample filter and (or) the device for creating an additional 55 mm Hg pressure drop shall be installed for the duration of these tests. The sampler's ambient temperature, ambient pressure, and flow measurement systems shall all be calibrated per the sampler's operating manual within 7 days prior to this test.

(2) The inlet of the candidate sampler shall be removed and the flow measurement adaptor installed on the sampler's downtube. A leak check as described in the sampler's operation or instruction manual shall be conducted and must be properly passed before other tests are carried out.

(3) The inlet of the flow measurement adaptor shall be connected to the outlet of the flow rate meter.

(4) The ambient air temperature recorder shall be installed in the test chamber such that it will accurately measure the temperature of the air in the vicinity of the candidate sampler without being unduly affected by the chamber's air temperature control system.

(f) *Procedure.* (1) Set up the sampler as specified in paragraph (e) of this section and otherwise prepare the sampler for normal sample collection operation as directed in the sampler's operation or instruction manual.

(2) The test shall consist of four test runs, one at each of the following conditions of chamber temperature and electrical power line voltage (respectively):

(i) −20 °C ±2 °C and 105 ±1 Vac.

(ii) −20 °C ±2 °C and 125 ±1 Vac.

(iii) =40 °C ±2 °C and 105 ±1 Vac.

(iv) =40 °C ±2 °C and 125 ±1 Vac.

(3) For each of the four test runs, set the selected chamber temperature and power line voltage for the test run. Upon achieving each temperature setpoint in the chamber, the candidate sampler and flow meter shall be thermally equilibrated for a period of at least 2 hours prior to the test run. Following the thermal conditioning time, set the sampler to automatically start a 6-hour sample collection period at a convenient time.

(4) During each 6-hour test period:

(i) Measure and record the sample flow rate with the flow rate meter at intervals not to exceed 5 minutes. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, ambient temperature and pressure shall be measured at

the same frequency as that of the certified flow rate measurements. Note and record the actual start and stop times for the 6-hour flow rate test period.

(ii) Determine and record the ambient (chamber) temperature indicated by the sampler and the corresponding ambient (chamber) temperature measured by the ambient temperature recorder specified in paragraph (c)(4) of this section at intervals not to exceed 5 minutes.

(iii) Measure the power line voltage to the sampler at intervals not greater than 1 hour.

(5) At the end of each test run, terminate the sample period (if not automatically terminated by the sampler) and download all archived instrument data from the test sampler.

(g) *Test results.* For each of the four test runs, examine the chamber temperature measurements and the power line voltage measurements. Verify that the temperature and line voltage met the requirements specified in paragraph (f) of this section at all times during the test run. If not, the test run is not valid and must be repeated. Determine the test results as follows:

(1) *Mean sample flow rate.* (i) From the certified measurements (Q_{ref}) of the test sampler flow rate, tabulate each flow rate measurement in units of L/min. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, each measured flow rate shall be corrected using its corresponding temperature and pressure measurement values. Calculate the mean flow rate for each sample period ($Q_{ref,ave}$) as follows:

EQUATION 11

$$Q_{ref,ave} = \frac{\sum_{i=1}^{n} Q_{ref,i}}{n}$$

where:

n equals the number of discrete certified flow rate measurements over each 6-hour test period.

(ii)(A) Calculate the percent difference between this mean flow rate value and the design value of 16.67 L/min, as follows:

EQUATION 12

$$\%\ \text{Difference} = \frac{Q_{ref,ave} - 16.67}{16.67} \text{ x } 100\%$$

(B) To successfully pass this test, the percent difference calculated in Equation 12 of this paragraph (g)(1)(ii) must be within ±5 percent for each test run.

(2) *Sample flow rate regulation.* (i) From the certified measurements of the test sampler flow rate, calculate the sample coefficient of variation of the discrete measurements as follows:

EQUATION 13

$$\%CV_{ref} = \frac{1}{Q_{ref,ave}} \text{ x } \sqrt{\frac{\sum_{i=1}^{n} Q_{ref,i}^2 - \frac{1}{n}\left(\sum_{i-1}^{n} Q_{ref,i}\right)^2}{n-1}} \text{ x } 100\%$$

(ii) To successfully pass this test, the calculated coefficient of variation for the certified flow rates must not exceed 2 percent.

(3) *Flow rate measurement accuracy.* (i) Using the mean volumetric flow rate reported by the candidate test sampler at the completion of each 6-hour test ($Q_{ind,ave}$), determine the accuracy of the reported mean flow rate as:

EQUATION 14

$$\%\ \text{Difference} = \frac{|Q_{ind,ave} - Q_{ref,ave}|}{Q_{ref,ave}} \text{ x } 100\%$$

(ii) To successfully pass this test, the percent difference calculated in Equation 14 of this paragraph (g)(3) shall not exceed 2 percent for each test run.

(4) *Flow rate coefficient of variation measurement accuracy.* (i) Using the flow rate coefficient of variation indicated by the candidate test sampler ($\%CV_{ind}$), determine the accuracy of the reported coefficient of variation as:

EQUATION 15

$$\text{Difference } \% = |\%CV_{ind} - \%CV_{ref}|$$

(ii) To successfully pass this test, the absolute difference calculated in Equation 15 of this paragraph (g)(4) must not exceed 0.3 (CV%) for each test run.

(5) *Ambient temperature measurement accuracy.* (i) Calculate the absolute

value of the difference between the mean ambient air temperature indicated by the test sampler and the mean ambient (chamber) air temperature measured with the ambient air temperature recorder as:

Equation 16

$$T_{diff} = \left| T_{ind,ave} - T_{ref,ave} \right|$$

Where:

$T_{ind,ave}$ = The mean ambient air temperature indicated by the test sampler, °C; and

$T_{ref,ave}$ = The mean ambient air temperature measured by the reference temperature instrument, °C.

(ii) The calculated temperature difference must be less than 2 °C for each test run.

(6) *Sampler functionality*. To pass the sampler functionality test, the following two conditions must both be met for each test run:

(i) The sampler must not shutdown during any portion of the 6-hour test.

(ii) An inspection of the downloaded data from the test sampler verifies that all the data are consistent with normal operation of the sampler.

[62 FR 38799, July 18, 1997, as amended at 71 FR 61291, Oct. 17, 2006]

§ 53.56 Test for effect of variations in ambient pressure.

(a) *Overview*. (1) This test procedure is designed to test various sampler performance parameters under variations in ambient (barometric) pressure. Tests shall be conducted in a pressure-controlled environment over two 6-hour time periods during which reference pressure and flow rate measurements shall be made at intervals not to exceed 5 minutes. Specific parameters to be evaluated at operating pressures of 600 and 800 mm Hg are as follows:

(i) Sample flow rate.

(ii) Flow rate regulation.

(iii) Flow rate measurement accuracy.

(iv) Coefficient of variability measurement accuracy.

(v) Ambient pressure measurement accuracy.

(vi) Proper operation of the sampler when exposed to ambient pressure extremes.

(2) The performance parameters tested under this procedure, the corresponding minimum performance specifications, and the applicable test conditions are summarized in table E–1 of this subpart. Each performance parameter tested, as described or determined in the test procedure, must meet or exceed the associated performance specification given. The candidate sampler must meet all specifications for the associated $PM_{2.5}$ or $PM_{10-2.5}$ method (as applicable) to pass this test procedure.

(b) *Technical definition*. Sample flow rate means the quantitative volumetric flow rate of the air stream caused by the sampler to enter the sampler inlet and pass through the sample filter, measured in actual volume units at the temperature and pressure of the air as it enters the inlet.

(c) *Required test equipment*. (1) Hypobaric chamber or other pressure-controlled environment or environments, capable of obtaining and maintaining pressures at 600 mm Hg and 800 mm Hg required for the test with an accuracy of 5 mm Hg. Henceforth, where the test procedures specify a test or environmental chamber, an alternative pressure-controlled environmental area or areas may be substituted, provided the test pressure requirements are met. Means for simulating ambient pressure using a closed-loop sample air system may also be approved for this test; such a proposed method for simulating the test pressure conditions may be described and submitted to EPA at the address given in § 53.4(a) prior to conducting the test for a specific individual determination of acceptability.

(2) Flow rate meter, suitable for measuring and recording the actual volumetric sampler flow rate at the sampler downtube, with a minimum range of 10 to 25 L/min, 2 percent certified, NIST-traceable accuracy. Optional capability for continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes is recommended. While a flow meter which provides a direct indication of volumetric flow rate is preferred for this test, an alternative certified flow measurement device may be used as long as appropriate volumetric

flow rate corrections are made based on measurements of actual ambient temperature and pressure conditions.

(3) Ambient air temperature recorder (if needed for volumetric corrections to flow rate measurements) with a range −30 °C to =50 °C, certified accurate to within 0.5 °C. If the certified flow meter does not provide direct volumetric flow rate readings, ambient temperature measurements must be made using continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(4) Barometer, range 600 mm Hg to 800 mm Hg, certified accurate to 2 mm Hg. Ambient air pressure measurements must be made using continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(5) Flow measurement adaptor (40 CFR part 50, appendix L, figure L–30) or equivalent adaptor to facilitate measurement of sampler flow rate at the sampler downtube.

(6) Means for creating an additional pressure drop of 55 mm Hg in the sampler to simulate a heavily loaded filter, such as an orifice or flow restrictive plate installed in the filter holder or a valve or other flow restrictor temporarily installed in the flow path near the filter.

(7) Teflon sample filter, as specified in section 6 of 40 CFR part 50, appendix L (if required).

(d) *Calibration of test measurement instruments.* Submit documentation showing evidence of appropriately recent calibration, certification of calibration accuracy, and NIST-traceability (if required) of all measurement instruments used in the tests. The accuracy of flow rate meters shall be verified at the highest and lowest pressures and temperatures used in the tests and shall be checked at zero and at least one flow rate within ±3 percent of 16.7 L/min within 7 days prior to use for this test. Where an instrument's measurements are to be recorded with an analog recording device, the accuracy of the entire instrument-recorder system shall be calibrated or verified.

(e) *Test setup.* (1) Setup of the sampler shall be performed as required in this paragraph (e) and otherwise as described in the sampler's operation or instruction manual referred to in §53.4(b)(3). The sampler shall be installed upright and set up in the pressure-controlled chamber in its normal configuration for collecting PM samples. A sample filter and (or) the device for creating an additional 55 mm Hg pressure drop shall be installed for the duration of these tests. The sampler's ambient temperature, ambient pressure, and flow measurement systems shall all be calibrated per the sampler's operating manual within 7 days prior to this test.

(2) The inlet of the candidate sampler shall be removed and the flow measurement adaptor installed on the sampler's downtube. A leak check as described in the sampler's operation or instruction manual shall be conducted and must be properly passed before other tests are carried out.

(3) The inlet of the flow measurement adaptor shall be connected to the outlet of the flow rate meter.

(4) The barometer shall be installed in the test chamber such that it will accurately measure the air pressure to which the candidate sampler is subjected.

(f) *Procedure.* (1) Set up the sampler as specified in paragraph (e) of this section and otherwise prepare the sampler for normal sample collection operation as directed in the sampler's operation or instruction manual.

(2) The test shall consist of two test runs, one at each of the following conditions of chamber pressure:

(i) 600 mm Hg.

(ii) 800 mm Hg.

(3) For each of the two test runs, set the selected chamber pressure for the test run. Upon achieving each pressure setpoint in the chamber, the candidate sampler shall be pressure-equilibrated for a period of at least 30 minutes prior to the test run. Following the conditioning time, set the sampler to automatically start a 6-hour sample collection period at a convenient time.

(4) During each 6-hour test period:

(i) Measure and record the sample flow rate with the flow rate meter at intervals not to exceed 5 minutes. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, ambient temperature and pressure shall be measured at

the same frequency as that of the certified flow rate measurements. Note and record the actual start and stop times for the 6-hour flow rate test period.

(ii) Determine and record the ambient (chamber) pressure indicated by the sampler and the corresponding ambient (chamber) pressure measured by the barometer specified in paragraph (c)(4) of this section at intervals not to exceed 5 minutes.

(5) At the end of each test period, terminate the sample period (if not automatically terminated by the sampler) and download all archived instrument data for the test run from the test sampler.

(g) *Test results.* For each of the two test runs, examine the chamber pressure measurements. Verify that the pressure met the requirements specified in paragraph (f) of this section at all times during the test. If not, the test run is not valid and must be repeated. Determine the test results as follows:

(1) *Mean sample flow rate.* (i) From the certified measurements (Q_{ref}) of the test sampler flow rate, tabulate each flow rate measurement in units of L/min. If ambient temperature and pressure corrections are necessary to calculate volumetric flow rate, each measured flow rate shall be corrected using its corresponding temperature and pressure measurement values. Calculate the mean flow rate for the sample period ($Q_{ref,ave}$) as follows:

EQUATION 17

$$Q_{ref,ave} = \frac{\sum_{i=1}^{n} Q_{ref,i}}{n}$$

where:

n equals the number of discrete certified flow measurements over the 6-hour test period.

(ii)(A) Calculate the percent difference between this mean flow rate value and the design value of 16.67 L/min, as follows:

EQUATION 18

$$\%\ \text{Difference} = \frac{Q_{ref,ave} - 16.67}{16.67} \text{ x } 100\%$$

(B) To successfully pass this test, the percent difference calculated in Equation 18 of this paragraph (g)(1) must be within ±5 percent for each test run.

(2) *Sample flow rate regulation.* (i) From the certified measurements of the test sampler flow rate, calculate the sample coefficient of variation of the discrete measurements as follows:

EQUATION 19

$$\%CV_{ref} = \frac{1}{Q_{ref,ave}} \text{ x } \sqrt{\frac{\sum_{i=1}^{n} Q_{ref,i}^2 - \frac{1}{n}\left(\sum_{i-1}^{n} Q_{ref,i}\right)^2}{n-1}} \text{ x } 100\%$$

(ii) To successfully pass this test, the calculated coefficient of variation for the certified flow rates must not exceed 2 percent.

(3) *Flow rate measurement accuracy.* (i) Using the mean volumetric flow rate reported by the candidate test sampler at the completion of each 6-hour test ($Q_{ind,ave}$), determine the accuracy of the reported mean flow rate as:

EQUATION 20

$$\%\ \text{Difference} = \frac{|Q_{ind,ave} - Q_{ref,ave}|}{Q_{ref,ave}} \text{ x } 100\%$$

(ii) To successfully pass this test, the percent difference calculated in Equation 20 of this paragraph (g)(3) shall not exceed 2 percent for each test run.

(4) *Flow rate CV measurement accuracy.* (i) Using the flow rate coefficient of variation indicated by the candidate test sampler at the completion of the 6-hour test ($\%CV_{ind}$), determine the accuracy of the reported coefficient of variation as:

EQUATION 21

$$\text{Difference}\ (\%) = |\%CV_{ind} - \%CV_{ref}|$$

(ii) To successfully pass this test, the absolute difference in values calculated in Equation 21 of this paragraph (g)(4) must not exceed 0.3 (CV%) for each test run.

(5) *Ambient pressure measurement accuracy*. (i) Calculate the absolute difference between the mean ambient air pressure indicated by the test sampler and the ambient (chamber) air pressure measured with the reference barometer as:

EQUATION 22

$$P_{diff} = |P_{ind,ave} - P_{ref,ave}|$$

where:

$P_{ind,ave}$ = mean ambient pressure indicated by the test sampler, mm Hg; and

$P_{ref,ave}$ = mean barometric pressure measured by the reference barometer, mm Hg.

(ii) The calculated pressure difference must be less than 10 mm Hg for each test run to pass the test.

(6) *Sampler functionality*. To pass the sampler functionality test, the following two conditions must both be met for each test run:

(i) The sampler must not shut down during any part of the 6-hour tests; and

(ii) An inspection of the downloaded data from the test sampler verifies that all the data are consistent with normal operation of the sampler.

[62 FR 38799, July 18, 1997; 63 FR 7714, Feb. 17, 1998, as amended at 71 FR 61292, Oct. 17, 2006]

§ 53.57 Test for filter temperature control during sampling and post-sampling periods.

(a) *Overview*. This test is intended to measure the candidate sampler's ability to prevent excessive overheating of the PM sample collection filter (or filters) under conditions of elevated solar insolation. The test evaluates radiative effects on filter temperature during a 4-hour period of active sampling as well as during a subsequent 4-hour non-sampling time period prior to filter retrieval. Tests shall be conducted in an environmental chamber which provides the proper radiant wavelengths and energies to adequately simulate the sun's radiant effects under clear conditions at sea level. For additional guidance on conducting solar radiative tests under controlled conditions, consult military standard specification 810–E (reference 6 in appendix A of this subpart). The performance parameters tested under this procedure, the corresponding minimum performance specifications, and the applicable test conditions are summarized in table E–1 of this subpart. Each performance parameter tested, as described or determined in the test procedure, must meet or exceed the associated performance specification to successfully pass this test.

(b) *Technical definition*. Filter temperature control during sampling is the ability of a sampler to maintain the temperature of the particulate matter sample filter within the specified deviation (5 °C) from ambient temperature during any active sampling period. Post-sampling temperature control is the ability of a sampler to maintain the temperature of the particulate matter sample filter within the specified deviation from ambient temperature during the period from the end of active sample collection by the sampler until the filter is retrieved from the sampler for laboratory analysis.

(c) *Required test equipment*. (1) Environmental chamber providing the means, such as a bank of solar-spectrum lamps, for generating or simulating thermal radiation in approximate spectral content and intensity equivalent to solar insulation of 1000 ±50 W/m^2 inside the environmental chamber. To properly simulate the sun's radiative effects on the sampler, the solar bank must provide the spectral energy distribution and permitted tolerances specified in table E–2 of this subpart. The solar radiation source area shall be such that the width of the candidate sampler shall not exceed one-half the dimensions of the solar bank. The solar bank shall be located a minimum of 76 cm (30 inches) from any surface of the candidate sampler. To meet requirements of the solar radiation tests, the chamber's internal volume shall be a minimum of 10 times that of the volume of the candidate sampler. Air velocity in the region of the sampler must be maintained continuously during the radiative tests at 2.0 ±0.5 m/sec.

(2) Ambient air temperature recorder, range −30 °C to =50 °C, with a resolution of 0.1 °C and certified accurate to within 0.5 °C. Ambient air temperature measurements must be made using continuous (analog) recording capability or digital recording at intervals not to exceed 5 minutes.

(3) Flow measurement adaptor (40 CFR part 50, appendix L, figure L-30) or equivalent adaptor to facilitate measurement of sampler flow rate at the sampler downtube.

(4) Miniature temperature sensor(s), capable of being installed in the sampler without introducing air leakage and capable of measuring the sample air temperature within 1 cm of the center of the filter, downstream of the filter; with a resolution of 0.1 °C, certified accurate to within 0.5 °C, NIST-traceable, with continuous (analog) recording capability or digital recording at intervals of not more than 5 minutes.

(5) Solar radiometer, to measure the intensity of the simulated solar radiation in the test environment, range of 0 to approximately 1500 W/m^2. Optional capability for continuous (analog) recording or digital recording at intervals not to exceed 5 minutes is recommended.

(6) Sample filter or filters, as specified in section 6 of 40 CFR part 50, appendix L.

(d) *Calibration of test measurement instruments.* Submit documentation showing evidence of appropriately recent calibration, certification of calibration accuracy, and NIST-traceability (if required) of all measurement instruments used in the tests. The accuracy of flow rate meters shall be verified at the highest and lowest pressures and temperatures used in the tests and shall be checked at zero and at least one flow rate within ±3 percent of 16.7 L/min within 7 days prior to use for this test. Where an instrument's measurements are to be recorded with an analog recording device, the accuracy of the entire instrument-recorder system shall be calibrated or verified.

(e) *Test setup.* (1) Setup of the sampler shall be performed as required in this paragraph (e) and otherwise as described in the sampler's operation or instruction manual referred to in § 53.4(b)(3). The sampler shall be installed upright and set up in the solar radiation environmental chamber in its normal configuration for collecting PM samples (with the inlet installed). The sampler's ambient and filter temperature measurement systems shall be calibrated per the sampler's operating manual within 7 days prior to this test. A sample filter shall be installed for the duration of this test. For sequential samplers, a sample filter shall also be installed in each available sequential channel or station intended for collection of a sequential sample (or at least five additional filters for magazine-type sequential samplers) as directed by the sampler's operation or instruction manual.

(2) The miniature temperature sensor shall be temporarily installed in the test sampler such that it accurately measures the air temperature 1 cm from the center of the filter on the downstream side of the filter. The sensor shall be installed such that no external or internal air leakage is created by the sensor installation. The sensor's dimensions and installation shall be selected to minimize temperature measurement uncertainties due to thermal conduction along the sensor mounting structure or sensor conductors. For sequential samplers, similar temperature sensors shall also be temporarily installed in the test sampler to monitor the temperature 1 cm from the center of each filter stored in the sampler for sequential sample operation.

(3) The solar radiant energy source shall be installed in the test chamber such that the entire test sampler is irradiated in a manner similar to the way it would be irradiated by solar radiation if it were located outdoors in an open area on a sunny day, with the radiation arriving at an angle of between 30° and 45° from vertical. The intensity of the radiation received by all sampler surfaces that receive direct radiation shall average 1000 ±50 W/m^2, measured in a plane perpendicular to the incident radiation. The incident radiation shall be oriented with respect to the sampler such that the area of the sampler's ambient temperature sensor (or temperature shield) receives full, direct radiation as it would or could during normal outdoor installation. Also, the temperature sensor must not be shielded or shaded from the radiation by a sampler part in a way that would not occur at other normal insulation angles or directions.

(4) The solar radiometer shall be installed in a location where it measures thermal radiation that is generally

representative of the average thermal radiation intensity that the upper portion of the sampler and sampler inlet receive. The solar radiometer shall be oriented so that it measures the radiation in a plane perpendicular to its angle of incidence.

(5) The ambient air temperature recorder shall be installed in the test chamber such that it will accurately measure the temperature of the air in the chamber without being unduly affected by the chamber's air temperature control system or by the radiant energy from the solar radiation source that may be present inside the test chamber.

(f) *Procedure.* (1) Set up the sampler as specified in paragraph (e) of this section and otherwise prepare the sampler for normal sample collection operation as directed in the sampler's operation or instruction manual.

(2) Remove the inlet of the candidate test sampler and install the flow measurement adaptor on the sampler's downtube. Conduct a leak check as described in the sampler's operation or instruction manual. The leak test must be properly passed before other tests are carried out.

(3) Remove the flow measurement adaptor from the downtube and re-install the sampling inlet.

(4) Activate the solar radiation source and verify that the resulting energy distribution prescribed in table E–2 of this subpart is achieved.

(5) Program the test sampler to conduct a single sampling run of 4 continuous hours. During the 4-hour sampling run, measure and record the radiant flux, ambient temperature, and filter temperature (all filter temperatures for sequential samplers) at intervals not to exceed 5 minutes.

(6) At the completion of the 4-hour sampling phase, terminate the sample period, if not terminated automatically by the sampler. Continue to measure and record the radiant flux, ambient temperature, and filter temperature or temperatures for 4 additional hours at intervals not to exceed 5 minutes. At the completion of the 4-hour post-sampling period, discontinue the measurements and turn off the solar source.

(7) Download all archived sampler data from the test run.

(g) *Test results.* Chamber radiant flux control. Examine the continuous record of the chamber radiant flux and verify that the flux met the requirements specified in table E–2 of this subpart at all times during the test. If not, the entire test is not valid and must be repeated.

(1) *Filter temperature measurement accuracy.* (i) For each 4-hour test period, calculate the absolute value of the difference between the mean filter temperature indicated by the sampler (active filter) and the mean filter temperature measured by the reference temperature sensor installed within 1 cm downstream of the (active) filter as:

EQUATION 23

$$T_{diff,filter} = |T_{ind,filter} - T_{ref,filter}|$$

where:

$T_{ind,filter}$ = mean filter temperature indicated by the test sampler, °C; and

$T_{ref,filter}$ = mean filter temperature measured by the reference temperature sensor, °C.

(ii) To successfully pass the indicated filter temperature accuracy test, the calculated difference between the measured means ($T_{diff,filter}$) must not exceed 2 °C for each 4-hour test period.

(2) *Ambient temperature measurement accuracy.* (i) For each 4-hour test period, calculate the absolute value of the difference between the mean ambient air temperature indicated by the test sampler and the mean ambient air temperature measured by the reference ambient air temperature recorder as:

EQUATION 24

$$T_{diff,ambient} = |T_{ind,ambient} - T_{ref,ambient}|$$

where:

$T_{ind,ambient}$ = mean ambient air temperature indicated by the test sampler, °C; and

$T_{ref,ambient}$ = mean ambient air temperature measured by the reference ambient air temperature recorder, °C.

(ii) To successfully pass the indicated ambient temperature accuracy test, the calculated difference between the measured means ($T_{diff,ambient}$) must not exceed 2 °C for each 4-hour test period.

(3) *Filter temperature control accuracy.* (i) For each temperature measurement interval over each 4-hour test period, calculate the difference between the filter temperature indicated by the reference temperature sensor and the ambient temperature indicated by the test sampler as:

EQUATION 25

$$T_{diff} = T_{ref,filter} - T_{ind,ambient}$$

(ii) Tabulate and inspect the calculated differences as a function of time. To successfully pass the indicated filter temperature control test, the calculated difference between the measured values must not exceed 5 °C for any consecutive intervals covering more than a 30–minute time period.

(iii) For sequential samplers, repeat the test calculations for each of the stored sequential sample filters. All stored filters must also meet the 5 °C temperature control test.

[62 FR 38799, July 18, 1997; 63 FR 7714, Feb. 17, 1998, as amended at 71 FR 61292, Oct. 17, 2006]

§ 53.58 Operational field precision and blank test.

(a) *Overview.* This test is intended to determine the operational precision of the candidate sampler during a minimum of 10 days of field operation, using three collocated test samplers. Measurements of PM are made at a test site with all of the samplers and then compared to determine replicate precision. Candidate sequential samplers are also subject to a test for possible deposition of particulate matter on inactive filters during a period of storage in the sampler. This procedure is applicable to both reference and equivalent methods. In the case of equivalent methods, this test may be combined and conducted concurrently with the comparability test for equivalent methods (described in subpart C of this part), using three reference method samplers collocated with three candidate equivalent method samplers and meeting the applicable site and other requirements of subpart C of this part.

(b) *Technical definition.* (1) Field precision is defined as the standard deviation or relative standard deviation of a set of PM measurements obtained concurrently with three or more collocated samplers in actual ambient air field operation.

(2) Storage deposition is defined as the mass of material inadvertently deposited on a sample filter that is stored in a sequential sampler either prior to or subsequent to the active sample collection period.

(c) *Test site.* Any outdoor test site having $PM_{2.5}$ (or $PM_{10-2.5}$, as applicable) concentrations that are reasonably uniform over the test area and that meet the minimum level requirement of paragraph (g)(2) of this section is acceptable for this test.

(d) *Required facilities and equipment.* (1) An appropriate test site and suitable electrical power to accommodate three test samplers are required.

(2) Teflon sample filters, as specified in section 6 of 40 CFR part 50, appendix L, conditioned and preweighed as required by section 8 of 40 CFR part 50, appendix L, as needed for the test samples.

(e) *Test setup.* (1) Three identical test samplers shall be installed at the test site in their normal configuration for collecting PM samples in accordance with the instructions in the associated manual referred to in § 53.4(b)(3) and also in accordance with applicable supplemental guidance provided in reference 3 in appendix A of this subpart. The test samplers' inlet openings shall be located at the same height above ground and between 2 (1 for samplers with flow rates less than 200 L/min.) and 4 meters apart horizontally. The samplers shall be arranged or oriented in a manner that will minimize the spatial and wind directional effects on sample collection of one sampler on any other sampler.

(2) Each test sampler shall be successfully leak checked, calibrated, and set up for normal operation in accordance with the instruction manual and with any applicable supplemental guidance provided in reference 3 in appendix A of this subpart.

(f) *Test procedure.* (1) Install a conditioned, preweighed filter in each test sampler and otherwise prepare each sampler for normal sample collection. Set identical sample collection start and stop times for each sampler. For

sequential samplers, install a conditioned, preweighed specified filter in each available channel or station intended for automatic sequential sample filter collection (or at least five additional filters for magazine-type sequential samplers), as directed by the sampler's operation or instruction manual. Since the inactive sequential channels are used for the storage deposition part of the test, they may not be used to collect the active PM test samples.

(2) Collect either a nominal 24-hour or 48-hour atmospheric PM sample simultaneously with each of the three test samplers.

(3) Following sample collection, retrieve the collected sample from each sampler. For sequential samplers, retrieve the additional stored (blank, unsampled) filters after at least 5 days (120 hours) storage in the sampler if the active samples are 24-hour samples, or after at least 10 days (240 hours) if the active samples are 48-hour samples.

(4) Determine the measured PM mass concentration for each sample in accordance with the applicable procedures prescribed for the candidate method in appendix L or appendix O, as applicable, of part 50 of this chapter, and in accordance with the associated manual referred to in §53.4(b)(3) and supplemental guidance in reference 2 in appendix A of this subpart. For sequential samplers, also similarly determine the storage deposition as the net weight gain of each blank, unsampled filter after the 5-day (or 10-day) period of storage in the sampler.

(5) Repeat this procedure to obtain a total of 10 sets of any combination of (nominal) 24-hour or 48-hour PM measurements over 10 test periods. For sequential samplers, repeat the 5-day (or 10-day) storage test of additional blank filters once for a total of two sets of blank filters.

(g) *Calculations.* (1) Record the PM concentration for each test sampler for each test period as $C_{i,j,}$ where i is the sampler number (i = 1,2,3) and j is the test period (j = 1,2, * * * 10).

(2)(i) For each test period, calculate and record the average of the three measured PM concentrations as $C_{ave,j}$ where j is the test period using equation 26 of this section:

Equation 26

$$C_{ave,j} = \frac{1}{3} \times \sum_{i=1}^{3} C_{i,j}$$

(ii) If $C_{ave,j} < 3$ μg/m³ for any test period, data from that test period are unacceptable, and an additional sample collection set must be obtained to replace the unacceptable data.

(3)(i) Calculate and record the precision for each of the 10 test periods, as the standard deviation, using equation 27 of this section:

Equation 27

$$P_j = \sqrt{\frac{\sum_{i=1}^{3} C_{i,j}^2 - \frac{1}{3}\left(\sum_{i=1}^{3} C_{i,j}\right)^2}{2}}$$

(ii) For each of the 10 test periods, also calculate and record the precision as the relative standard deviation, in percent, using equation 28 of this section:

Equation 28

$$RP_j = 100\% \times \frac{P_j}{C_{ave,j}}$$

(h) *Test results.* (1) The candidate method passes the precision test if *either* P_j or RP_j is less than or equal to the corresponding specification in table E–1 of this subpart for all 10 test periods.

(2) The candidate sequential sampler passes the blank filter storage deposition test if the average net storage deposition weight gain of each set of blank filters (total of the net weight gain of each blank filter divided by the number of filters in the set) from each test sampler (six sets in all) is less than 50 μg.

[71 FR 61292, Oct. 17, 2006,as amended at 72 FR 32208, June 12, 2007]

§ 53.59 Aerosol transport test for Class I equivalent method samplers.

(a) *Overview.* This test is intended to verify adequate aerosol transport

through any modified or air flow splitting components that may be used in a Class I candidate equivalent method sampler such as may be necessary to achieve sequential sampling capability. This test is applicable to all Class I candidate samplers in which the aerosol flow path (the flow path through which sample air passes upstream of sample collection filter) differs significantly from that specified for reference method samplers as specified in 40 CFR part 50, appendix L or appendix O, as applicable. The test requirements and performance specifications for this test are summarized in table E–1 of this subpart.

(b) *Technical definitions.* (1) Aerosol transport is the percentage of a laboratory challenge aerosol which penetrates to the active sample filter of the candidate equivalent method sampler.

(2) The active sample filter is the exclusive filter through which sample air is flowing during performance of this test.

(3) A no-flow filter is a sample filter through which no sample air is intended to flow during performance of this test.

(4) A channel is any of two or more flow paths that the aerosol may take, only one of which may be active at a time.

(5) An added component is any physical part of the sampler which is different in some way from that specified for a reference method sampler in 40 CFR part 50, appendix L or appendix O, as applicable, such as a device or means to allow or cause the aerosol to be routed to one of several channels.

(c) *Required facilities and test equipment.* (1) Aerosol generation system, as specified in § 53.62(c)(2).

(2) Aerosol delivery system, as specified in § 53.64(c)(2).

(3) Particle size verification equipment, as specified in § 53.62(c)(3).

(4) Fluorometer, as specified in § 53.62(c)(7).

(5) Candidate test sampler, with the inlet and impactor or impactors removed, and with all internal surfaces of added components electroless nickel coated as specified in § 53.64(d)(2).

(6) Filters that are appropriate for use with fluorometric methods (e.g., glass fiber).

(d) *Calibration of test measurement instruments.* Submit documentation showing evidence of appropriately recent calibration, certification of calibration accuracy, and NIST-traceability (if required) of all measurement instruments used in the tests. The accuracy of flow rate meters shall be verified at the highest and lowest pressures and temperatures used in the tests and shall be checked at zero and at least one flow rate within ±3 percent of 16.7 L/min within 7 days prior to use for this test. Where an instrument's measurements are to be recorded with an analog recording device, the accuracy of the entire instrument-recorder system shall be calibrated or verified.

(e) *Test setup.* (1) The candidate test sampler shall have its inlet and impactor or impactors removed. The lower end of the down tube shall be reconnected to the filter holder, using an extension of the downtube, if necessary. If the candidate sampler has a separate impactor for each channel, then for this test, the filter holder assemblies must be connected to the physical location on the sampler where the impactors would normally connect.

(2) The test particle delivery system shall be connected to the sampler downtube so that the test aerosol is introduced at the top of the downtube.

(f) *Test procedure.* (1) All surfaces of the added or modified component or components which come in contact with the aerosol flow shall be thoroughly washed with 0.01 N NaOH and then dried.

(2) Generate aerosol. (i) Generate aerosol composed of oleic acid with a uranine fluorometric tag of 3 ±0.25 μm aerodynamic diameter using a vibrating orifice aerosol generator according to conventions specified in § 53.61(g).

(ii) Check for the presence of satellites and adjust the generator to minimize their production.

(iii) Calculate the aerodynamic particle size using the operating parameters of the vibrating orifice aerosol generator. The calculated aerodynamic diameter must be 3 ±0.25 μm aerodynamic diameter.

(3) Verify the particle size according to procedures specified in § 53.62(d)(4)(i).

(4) Collect particles on filters for a time period such that the relative error

of the resulting measured fluorometric concentration for the active filter is less than 5 percent.

(5) Determine the quantity of material collected on the active filter using a calibrated fluorometer. Record the mass of fluorometric material for the active filter as $M_{active\ (i)}$ where i = the active channel number.

(6) Determine the quantity of material collected on each no-flow filter using a calibrated fluorometer. Record the mass of fluorometric material on each no-flow filter as $M_{no\text{-}flow}$.

(7) Using 0.01 N NaOH, wash the surfaces of the added component or components which contact the aerosol flow. Determine the quantity of material collected using a calibrated fluorometer. Record the mass of fluorometric material collected in the wash as M_{wash}.

(8) Calculate the aerosol transport as:

EQUATION 29

$$T_{(i)} = \frac{M_{active}}{M_{active+}M_{wash+}\sum M_{no\text{-}flow}} \times 100\%$$

where:

i = the active channel number.

(9) Repeat paragraphs (f)(1) through (8) of this section for each channel, making each channel in turn the exclusive active channel.

(g) *Test results.* The candidate Class I sampler passes the aerosol transport test if $T_{(i)}$ is at least 97 percent for each channel.

[62 FR 38799, July 18, 1997, as amended at 71 FR 61293, Oct. 17, 2006]

TABLE E–1 TO SUBPART E OF PART 53—SUMMARY OF TEST REQUIREMENTS FOR REFERENCE AND CLASS I EQUIVALENT METHODS FOR $PM_{2.5}$ AND $PM_{10-2.5}$

Subpart E procedure	Performance test	Performance specification	Test conditions	Part 50, appendix L reference
§ 53.52 Sample leak check test.	Sampler leak check facility.	External leakage: 80 mL/min, max. Internal leakage: 80 mL/min, max.	Controlled leak flow rate of 80 mL/min.	Sec. 7.4.6.
§ 53.53 Base flow rate test.	Sample flow rate ..... 1. Mean ..... 2. Regulation ..... 3. Meas accuracy ..... 4. CV accuracy ..... 5. Cut-off	1. 16.67 ± 5%, L/min ..... 2. 2%, max ..... 3. 2%, max ..... 4. 0.3% max ..... 5. Flow rate cut-off if flow rate deviates more than 10% from design flow rate for >60 ± 30 seconds.	(a) 6-hour normal operational test plus flow rate cut-off test. (b) Normal conditions ..... (c) Additional 55 mm Hg pressure drop to simulate loaded filter. (d) Variable flow restriction used for cut-off test.	Sec. 7.4.1. Sec. 7.4.2. Sec. 7.4.3. Sec. 7.4.4. Sec. 7.4.5.
§ 53.54 Power interruption test.	Sample flow rate ..... 1. Mean ..... 2. Regulation ..... 3. Meas. accuracy ..... 4. CV accuracy ..... 5. Occurrence time of power interruptions. 6. Elapsed sample time 7. Sample volume	1. 16.67 ± 5%, L/min ..... 2. 2%, max ..... 3. 2%, max ..... 4. 0.3% max ..... 5. ± 2 min if >60 seconds. 6. ± 20 seconds ..... 7. ± 2%, max	(a) 6-hour normal operational test. (b) Nominal conditions ..... (c) Additional 55 mm Hg pressure drop to simulate loaded filter. (d) 6 power interruptions of various durations.	Sec. 7.4.1. Sec. 7.4.2. Sec. 7.4.3. Sec. 7.4.5. Sec. 7.4.12. Sec. 7.4.13. Sec. 7.4.15.4. Sec. 7.4.15.5.
§ 53.55 Temperature and line voltage test.	Sample flow rate ..... 1. Mean ..... 2. Regulation ..... 3. Meas. accuracy ..... 4. CV accuracy ..... 5. Temperature meas. accuracy. 6. Proper operation.	1. 16.67 ± 5%, L/min ..... 2. 2%, max ..... 3. 2%, max ..... 4. 0.3% max ..... 5. 2 °C	(a) 6-hour normal operational test. (b) Normal conditions ..... (c) Additional 55 mm Hg pressure drop to simulate loaded filter. (d) Ambient temperature at −20 and +40 °C. (e) Line voltage: 105 Vac to 125 Vac.	Sec. 7.4.1. Sec. 7.4.2. Sec. 7.4.3. Sec. 7.4.5. Sec. 7.4.8. Sec. 7.4.15.1.

Subpart E procedure	Performance test	Performance specification	Test conditions	Part 50, appendix L reference
§ 53.56 Barometric pressure effect test.	Sample flow rate ..... 1. Mean ..... 2. Regulation ..... 3. Meas. accuracy ..... 4. CV accuracy ..... 5. Pressure meas. accuracy. 6. Proper operation.	1. 16.67 ± 5%, L/min ..... 2. 2%, max ..... 3. 2%, max ..... 4. 0.3% max ..... 5. 10 mm Hg	(a) 6-hour normal operational test. (b) Normal conditions ..... (c) Additional 55 mm Hg pressure drop to simulate loaded filter. (d) Barometric pressure at 600 and 800 mm Hg.	Sec. 7.4.1. Sec. 7.4.2. Sec. 7.4.3. Sec. 7.4.5. Sec. 7.4.9.
§ 53.57 Filter temperature control test.	1. Filter temp. meas. accuracy. 2. Ambient temp. meas. accuracy. 3. Filter temp. control accuracy, sampling and non-sampling.	1. 2 °C ..... 2. 2 °C ..... 3. Not more than 5 °C above ambient temp. for more than 30 min.	(a) 4-hour simulated solar radiation, sampling. (b) 4-hour simulated solar radiation, non-sampling. (c) Solar flux of 1000 ± 50 W/m^2.	Sec. 7.4.8. Sec. 7.4.10. Sec. 7.4.11.
§ 53.58 Field precision test.	1. Measurement precision. 2. Storage deposition test for sequential samplers.	1. P_j < 2 μg/m^3 or RP_j < 5%. 2. 50 μg max. average weight gain/blank filter.	(a) 3 collocated samplers at 1 site for at least 10 days. (b) $PM_{2.5}$ conc. > 3 μg/m^3 ... (c) 24- or 48-hour samples (d) 5- or 10-day storage period for inactive stored filters.	Sec. 5.1. Sec. 7.3.5. Sec. 8. Sec. 9. Sec. 10.
The Following Requirement Is Applicable to Class I Candidate Equivalent Methods Only				
§ 53.59 Aerosol transport test.	Aerosol transport	97%, min. for all channels..	Determine aerosol transport through any new or modified components with respect to the reference method sampler before the filter for each channel.	

[72 FR 32208, June 12, 2007]

TABLE E–2 TO SUBPART E OF PART 53—SPECTRAL ENERGY DISTRIBUTION AND PERMITTED TOLERANCE FOR CONDUCTING RADIATIVE TESTS

Characteristic	Spectral Region			
	Ultraviolet		Visible	Infrared
Bandwidth (μm)	0.28 to 0.32	0.32 to 0.40	0.40 to 0.78	0.78 to 3.00
Irradiance (W/m^2)	5	56	450 to 550	439
Allowed Tolerance	±35%	±25%	±10%	±10%

[62 FR 38799, July 18, 1997; 63 FR 7714, Feb. 17, 1998]

FIGURE E–1 TO SUBPART E OF PART 53—DESIGNATION TESTING CHECKLIST

DESIGNATION TESTING CHECKLIST

Auditee _____ Auditor signature _____ Date _____

Compliance Status: Y = Yes N = No NA = Not applicable/Not available				
Verification			Verified by Direct Observation of Process or of Documented Evidence: Performance, Design or Application Spec. Corresponding to Sections of 40 CFR Part 53 or 40 CFR Part 50, Appendix L	Verification Comments (Includes documentation of who, what, where, when, why) (Doc. #, Rev. #, Rev. Date)
Y	N	NA		
			Performance Specification Tests Sample flow rate coefficient of variation (§ 53.53) (L–7.4.3)	
			Filter temperature control (sampling) (§ 53.57) (L–7.4.10)	

Compliance Status: Y = Yes N = No NA = Not applicable/Not available				Verification Comments (Includes documentation of who, what, where, when, why) (Doc. #, Rev. #, Rev. Date)
Verification			Verified by Direct Observation of Process or of Documented Evidence: Performance, Design or Application Spec. Corresponding to Sections of 40 CFR Part 53 or 40 CFR Part 50, Appendix L	
Y	N	NA		
			Elapsed sample time accuracy (§ 53.54) (L–7.4.13)	
			Filter temperature control (post sampling) (§ 53.57) (L–7.4.10)	
			Application Specification Tests	
			Field Precision (§ 53.58) (L–5.1)	
			Meets all Appendix L requirements (part 53, subpart A, § 53.2(a)(3)) (part 53, subpart E, § 53.51(a),(d))	
			Filter Weighing (L–8)	
			Field Sampling Procedure (§ 53.30, .31, .34)	
			Design Specification Tests	
			Filter (L–6)	
			Range of Operational Conditions (L–7.4.7)	
The Following Requirements Apply Only to Class I Candidate Equivalent Methods				
			Aerosol Transport (§ 53.59)	

FIGURE E–2 TO SUBPART E OF PART 53—PRODUCT MANUFACTURING CHECKLIST

PRODUCT MANUFACTURING CHECKLIST

Auditee Auditor signature Date

Compliance Status: Y = Yes N = No NA = Not applicable/Not available				Verification Comments (Includes documentation of who, what, where, when, why) (Doc. #, Rev. #, Rev. Date)
Verification			Verified by Direct Observation of Process or of Documented Evidence: Performance, Design or Application Spec. Corresponding to Sections of 40 CFR Part 53 or 40 CFR Part 50, Appendix L	
Y	N	NA		
			Performance Specification Tests	
			Assembled operational performance (Burn-in test) (§ 53.53)	
			Sample flow rate (§ 53.53) (L–7.4.1, L–7.4.2)	
			Sample flow rate regulation (§ 53.53) (L–7.4.3)	
			Flow rate and average flow rate measurement accuracy (§ 53.53) (L–7.4.5)	
			Ambient air temperature measurement accuracy (§ 53.55) (L–7.4.8)	
			Ambient barometric pressure measurement accuracy (§ 53.56) (L–7.4.9)	
			Sample flow rate cut-off (§ 53.53) (L–7.4.4)	
			Sampler leak check facility (§ 53.52) (L–7.4.6)	
			Application Specification Tests	
			Flow rate calibration transfer standard (L-9.2)	
			Operational /Instructional manual (L-7.4.18)	
			Design Specification Tests	
			Impactor (jet width) (§ 53.51(d)(1)) (L-7.3.4.1)	

Compliance Status: Y = Yes N = No NA = Not applicable/Not available				Verification Comments (Includes documentation of who, what, where, when, why) (Doc. #, Rev. #, Rev. Date)
Verification			Verified by Direct Observation of Process or of Documented Evidence: Performance, Design or Application Spec. Corresponding to Sections of 40 CFR Part 53 or 40 CFR Part 50, Appendix L	
Y	N	NA		
			Surface finish (§ 53.51(d)(2)) (L-7.3.7)	

APPENDIX A TO SUBPART E OF PART 53—REFERENCES

(1) American National Standard Quality Systems—Model for Quality Assurance in Design, Development, Production, Installation, and Servicing, ANSI/ISO/ASQC Q9001–1994. Available from American Society for Quality, P.O. Box 3005, Milwaukee, WI 53202 (*http://qualitypress.asq.org*).

(2) American National Standard Quality Systems for Environmental Data and Technology Programs—Requirements with guidance for use, ANSI/ASQC E4–2004. Available from American Society for Quality, P.O. Box 3005, Milwaukee, WI 53202 (*http://qualitypress.asq.org*).

(3) Quality Assurance Guidance Document 2.12. Monitoring $PM_{2.5}$ in Ambient Air Using Designated Reference or Class I Equivalent Methods. U.S. EPA, National Exposure Research Laboratory, Research Triangle Park, NC, November 1998 or later edition. Currently available at *http://www.epa.gov/ttn/amtic/pmqainf.html*.

(4) Military standard specification (mil. spec.) 8625F, Type II, Class 1 as listed in Department of Defense Index of Specifications and Standards (DODISS), available from DODSSP-Customer Service, Standardization Documents Order Desk, 700 Robbins Avenue, Building 4D, Philadelphia, PA 1911-5094.

(5) Quality Assurance Handbook for Air Pollution Measurement Systems, Volume IV: Meteorological Measurements. Revised March, 1995. EPA–600/R–94–038d. Available from National Technical Information Service, Springfield, VA 22161, (800–553–6847, *http://www.ntis.gov*). NTIS number PB95–199782INZ.

(6) Military standard specification (mil. spec.) 810-E as listed in Department of Defense Index of Specifications and Standards (DODISS), available from DODSSP-Customer Service, Standardization Documents Order Desk, 700 Robbins Avenue, Building 4D, Philadelphia, PA 1911-5094.

[62 FR 38799, July 18, 1997, as amended at 71 FR 61295, Oct. 17, 2006]

Subpart F—Procedures for Testing Performance Characteristics of Class II Equivalent Methods for $PM_{2.5}$

SOURCE: 62 FR 38814, July 18, 1997, unless otherwise noted.

§ 53.60 General provisions.

(a) This subpart sets forth the specific requirements that a $PM_{2.5}$ sampler associated with a candidate Class II equivalent method must meet to be designated as an equivalent method for $PM_{2.5}$. This subpart also sets forth the explicit test procedures that must be carried out and the test results, evidence, documentation, and other materials that must be provided to EPA to demonstrate that a sampler meets all specified requirements for designation as an equivalent method.

(b) A candidate method described in an application for a FRM or FEM determination submitted under § 53.4 shall be determined by the EPA to be a Class II candidate equivalent method on the basis of the definition of a Class II FEM in § 53.1.

(c) Any sampler associated with a Class II candidate equivalent method (Class II sampler) must meet all applicable requirements for FRM samplers or Class I FEM samplers specified in subpart E of this part, as appropriate. Except as provided in § 53.3(a)(3), a Class II $PM_{2.5}$ sampler must meet the additional requirements as specified in paragraph (d) of this section.

(d) Except as provided in paragraphs (d)(1), (2), and (3) of this section, all Class II samplers are subject to the additional tests and performance requirements specified in § 53.62 (full wind tunnel test), § 53.65 (loading test), and § 53.66 (volatility test). Alternative tests and performance requirements, as described in paragraphs (d)(1), (2), and (3) of this section, are optionally available for certain Class II samplers which