AUTHENTICATED
U.S. GOVERNMENT
INFORMATION
GPO

by § 57.202(a) after receipt of the supplementary information. Such amendment shall require compliance with the new SO_2 SIP limit as expeditiously as practicable in accordance with § 57.201(d)(3). The issuing agency, if not EPA, shall promptly submit its determination and any necessary NSO amendments to EPA.

(c) EPA shall take action to approve or disapprove the issuing agency's determination and NSO amendment, if any, within a reasonable time after receipt of such determination and amendment.

(d) If EPA disapproves the issuing agency's determination or NSO amendment, or if a smelter fails to submit any supplementary information as required under paragraph (a), EPA and/or the issuing agency shall take appropriate remedial action. EPA shall take appropriate remedial action if the issuing agency does not make any determination and amendment required by this section within the time contemplated by § 57.202(a).

Subpart C—Constant Controls and Related Requirements

§ 57.301 General requirements.

Each NSO shall require an interim level of sulfur dioxide constant controls to be operated at the smelter, unless a waiver of this requirement has been granted to the owner under subpart H of this part. Except as otherwise provided in § 57.304, the interim constant controls shall be properly operated and maintained at all times. The NSO shall require the following gas streams to be treated by interim constant controls:

(a) In copper smelters, off-gases from fluidized bed roasters, flash furnaces, NORANDA reactors, electric furnaces and copper converters;

(b) In lead smelters, off-gases from the front end of the sintering machine and any other sinter gases which are recirculated;

(c) In zinc smelters, off-gases from mult-hearth roasters, flash roasters and fluidized bed roasters; and

(d) In all primary nonferrous smelters, all other strong SO_2 streams.

(e) In all primary nonferrous smelters, any other process streams which were regularly or intermittently treated by constant controls at the smelter as of August 7, 1977.

§ 57.302 Performance level of interim constant controls.

(a) *Maximum feasible efficiency*. Each NSO shall require: that the smelter operate its interim constant control systems at their maximum feasible efficiency, including the making of any improvements necessary to correct the effects of any serious deficiencies; that the process and control equipment be maintained in the way best designed to ensure such operation; and that process operations be scheduled and coordinated to facilitate treatment of process gas streams to the maximum possible extent. Maximum feasible efficiency shall be expressed in the NSO in the form of a limitation on the concentration of SO_2 in the tail gas of each individual control system in combination with an appropriate averaging period, as provided below in paragraphs (b) and (c) of this section.

(b) *The limitation level for SO_2 concentration in the control system tail gas*. The level at which the concentration limitation is set shall take into account fluctuations in the strength and volume of process off-gases to the extent that those fluctuations affect the SO_2 content of the tail gas and cannot be avoided by improved scheduling and coordination of process operations. The limitation shall exclude the effect of any increase in emissions caused by process or control equipment malfunction. The limitation shall take into account unavoidable catalyst deterioration in sulfuric acid plants, but may prescribe the frequency of catalyst screening or replacement. The NSO shall also prohibit the smelter owner from using dilution air to meet the limitation.

(c) *Averaging period*. (1) The averaging period shall be derived in combination with the concentration limitation and shall take into account the same factors described in paragraph (b). The averaging period established under this paragraph should generally not exceed the following:

(i) For sulfuric acid plants on copper smelters, 12-hour running average;

(ii) For sulfuric acid plants on lead smelters, 6-hour running average;

(iii) For sulfuric acid plants on zinc smelters, 2-hour running average;

(iv) For dimethylaniline (DMA) scrubbing units on copper smelters, 2-hour running average.

(2) A different averaging period may be established if the applicant demonstrates that such a period is necessary in order to account for the factors described in paragraph (b) of this section: Provided, that the period is enforceable and satisfies the criteria of paragraph (a) of this section.

(d) *Improved performance.* (1) The performance level representing maximum feasible efficiency for any existing control system (e.g., a sulfuric acid plant or a DMA scrubber) shall require the correction of the effects of any serious deficiencies in the system. For the purpose of this paragraph, at least the following problems shall constitute serious deficiencies in acid plants:

(i) Heat exchangers and associated equipment inadequate to sustain efficient, autothermal operation at the average gas strengths and volumes received by the acid plant during routine process equipment operation;

(ii) Failure to completely fill all available catalyst bed stages with sufficient catalyst;

(iii) Inability of the gas pre-treatment system to prevent unduly frequent plugging or fouling (deterioration) of catalyst or other components of the acid plant; or

(iv) Blower capacity inadequate to permit the treatment of the full volume of gas which the plant could otherwise accommodate, or in-leakage of air into the flues leading to the plant, to the extent that this inadequacy results in bypassing of gas around the plant.

(2) Notwithstanding any contrary provisions of §57.304(c) (malfunction demonstration), no excess emissions (as defined in §57.304(a)) shall be considered to have resulted from a malfunction in the constant control system if the smelter owner has not upgraded serious deficiencies in the constant control system in compliance with the requirements of §57.302(d)(1), unless the smelter owner demonstrates under §57.304(c) that compliance with those requirements would not have affected the magnitude of the emission.

(e) *Multiple control devices.* (1) At any smelter where off-gas streams are treated by various existing control systems (e.g., multiple acid plants or a DMA scrubber and an acid plant), the NSO shall require the use of those systems in the combination that will result in the maximum feasible net SO_2 removal.

(2) To the extent that compliance with this requirement is demonstrated by the smelter operator to result in excess emissions during unavoidable start up and shut down of the control systems, those excess emissions shall not constitute violations of the NSO.

§ 57.303 Total plantwide emission limitation.

(a) *Calculation of the emission limitation.* Each NSO shall contain a requirement limiting the total allowable emissions from the smelter to the level which would have been associated with production at the smelter's maximum production capacity (as defined in §57.103(r)) as of August 7, 1977. This limitation shall be expressed in units of mass per time and shall be calculated as the sum of uncontrolled process and fugitive emissions, and emissions from any control systems (operating at the efficiency prescribed under §57.302). These emission rates may be derived from either direct measurements or appropriately documented mass balance calculations.

(b) *Compliance with the emission limitation.* Each NSO shall require the use of specific, enforceable testing methods and measurement periods for determining compliance with the limitation established under paragraph (a) of this section.

§ 57.304 Bypass, excess emissions and malfunctions.

(a) *Definition of excess emissions.* For the purposes of this subpart, any emissions greater than those permitted by the NSO provisions established under §57.302 (performance level of interim constant controls) or §57.303 (plantwide emission limitation) of this subpart shall constitute excess emissions. Emission of any gas stream identified under §57.301 (a), (b), (c), (d) or (e) of

this subpart that is not treated by a sulfur dioxide constant control system shall also constitute an excess emission under this subpart.

(b) *The excess emission report.* Each NSO shall require the smelter to report all excess emissions to the issuing agency, as provided in § 57.305(b). The report shall include the following:

(1) Identity of the stack or other emission points where the excess emissions occurred;

(2) Magnitude of the excess emissions expressed in the units of each applicable emission limitation, as well as the operating data, documents, and calculations used in determining the magnitude of the excess emissions;

(3) Time and duration of the excess emissions;

(4) Identity of the equipment causing the excess emissions;

(5) Nature and cause of such excess emissions;

(6) Steps taken to limit the excess emissions, and when those steps were commenced;

(7) If the excess emissions were the result of a malfunction, the steps taken to remedy the malfunction and to prevent the recurrence of such malfunction; and

(8) At the smelter owner's election, the demonstration specified in paragraph (c) of this section.

(c) *Malfunction demonstration.* Except as provided in § 57.302(e)(2) or in paragraph (d) or (e) of this section, any excess emission shall be a violation of the NSO unless the owner demonstrates in the excess emissions report required under paragraph (b) of this section that the excess emission resulted from a malfunction (or an unavoidable start up and shut down resulting from a malfunction) and that:

(1) The air pollution control systems, process equipment, or processes were at all times maintained and operated, to the maximum extent practicable, in a manner consistent with good practice for minimizing emissions;

(2) Repairs were made as expeditiously as practicable, including the use of off-shift labor and overtime;

(3) The amount and duration of the excess emissions were minimized to the maximum extent practicable during periods of such emissions; and

(4) The excess emissions were not part of a recurring pattern indicative of serious deficiencies in, or inadequate operation, design, or maintenance of, the process or control equipment.

(d) *Scheduled maintenance exception.* Excess emissions occurring during scheduled maintenance shall not constitute violations of the NSO to the extent that:

(1) The expected additional annual sulfur dioxide removal by any control system (including associated process changes) for which construction had not commenced (as defined in 40 CFR 60.2 (g) and (i)) as of August 7, 1977 and which the smelter owner agrees to install and operate under subpart F, would have offset such excess emissions if the system had been in operation throughout the year in which the maintenance was performed;

(2) The system is installed and operated as provided in the NSO provisions established under subpart F; and

(3) The system performs at substantially the expected efficiency and reliability subsequent to its initial break-in period.

(e) An NSO may provide that excess emissions which occur during acid plant start-up as the result of the cooling of acid plant catalyst due to the unavailability of process gas to an acid plant during a prolonged SCS curtailment or scheduled maintenance are not excess emissions. If the NSO does so provide, it shall also require the use of techniques or practices designed to minimize these excess emissions, such as the sealing of the acid plant during prolonged curtailments, the use of auxiliary heat or SO_2 injected during the curtailment, or the preheating of the acid plant before start-up of the process equipment it serves.

(f) Requirements for a smelter with constant controls that applies for a waiver.

(1) If a smelter that has some interim constant controls applies for a waiver in accordance with subpart H, the following requirements shall apply pending action on the waiver application and following final action granting or approving a waiver:

(i) The NSO shall require the smelter to implement maintenance and operation measures designed to reduce to

the maximum extent feasible the potential for bypass of existing interim constant controls.

(ii) Upon application for a waiver under subpart H, the smelter shall submit to the issuing agency for its approval and to EPA proposed maintenance and operation measures for compliance with the requirements of paragraph (i).

(iii) The remainder of this subpart shall apply except that: (A) The emission limitations required under this subpart shall be based only on existing constant control equipment as upgraded through the improved maintenance and operation required by this paragraph, and (B) bypass of existing controls shall not constitute excess emissions, provided the maintenance and operation requirements and emission limitations prescribed by the NSO are satisfied.

(2) After any denial of a waiver by the issuing Agency, or any disapproval by EPA of a waiver granted by the issuing agency, the NSO shall be amended consistent with the requirements of this subpart and § 57.702.

§ 57.305 Compliance monitoring and reporting.

(a) *Monitoring.* (1) Each NSO shall require compliance with the control system performance requirements established pursuant to this subpart to be determined through the use of continuous monitors for measuring SO_2 concentration.

(i) Such monitors must be installed, operated and maintained in accordance with the performance specifications and other requirements contained in appendix D to 40 CFR part 52 or part 60. The monitors must take and record at least one measurement of SO_2 concentration from the effluent of each control system in each 15-minute period. Failure of the monitors to record at least 95% of the 15-minute periods in any 30-day period shall constitute a violation of the NSO.

(ii) The sampling point shall be located at least 8 stack diameters (diameter measured at sampling point) downstream and 2 diameters upstream from any flow disturbance such as a bend, expansion, constriction, or flame, unless another location is approved by the Administrator.

(iii) The sampling point for monitoring emissions shall be in the duct at the centroid of the cross section if the cross sectional area is less than 4.645m^2 (50 ft^2) or at a point no closer to the wall than 0.914m (3 ft) if the cross sectional area is 4.645m^2 (50 ft^2) or more. The monitor sample point shall be in an area of small spatial concentration gradient and shall be representative of the concentration in the duct.

(iv) The measurement system(s) installed and used pursuant to this paragraph shall be subject to the manufacturer's recommended zero adjustment and calibration procedures at least once per 24-hour operating period unless the manufacturer specifies or recommends calibration at shorter intervals, in which case such specifications or recommendations shall be followed. Records of these procedures shall be made which clearly show instrument readings before and after zero adjustment and calibration.

(2) Each NSO shall require the monitoring of any ducts or flues used to bypass gases, required under this subpart to be treated by constant controls, around the smelter's sulfur dioxide constant control system(s) for ultimate discharge to the atmosphere. Such monitoring shall be adequate to disclose the time of the bypass, its duration, and the approximate volume and SO_2 concentration of gas bypassed.

(b) *Reporting.* (1) Each NSO shall require that the smelter maintain a record of all measurements required under paragraph (a) of this section. Results shall be summarized monthly and shall be submitted to the issuing agency within 15 days after the end of each month. The smelter owner shall retain a record of such measurements for one year after the NSO period terminates.

(2) Each NSO shall require that the smelter maintain a record of all measurements and calculations required under § 57.303(b). Results shall be summarized on a monthly basis and shall be submitted to the issuing agency at 6-month intervals. The smelter owner shall retain a record of such measurements and calculations for at least one year after the NSO terminates.

(3) The report required under § 57.304(b) shall accompany the report required under paragraph (b)(1) of this section.

(c) *Quality assurance and continuous data*—(1) *Quality assurance.* Each NSO shall require that the smelter submit a plan for quality assurance to the issuing agency for approval and that all monitoring performed by continuous monitors shall be verified for quality assurance by the smelter. Such plans must follow current EPA guidelines for quality assurance, in order to be approvable.

(2) *Continuous data.* Manual source testing methods equivalent to 40 CFR part 60, appendix A shall be used to determine compliance if the continuous monitoring system malfunctions.

Subpart D—Supplementary Control System Requirements

§ 57.401 General requirements.

Except as provided in subpart E, each NSO shall require the smelter owner to prevent all violations of the NAAQS in the smelter's designated liability area (DLA) through the operation of an approved supplementary control system (SCS).

§ 57.402 Elements of the supplementary control system.

Each supplementary control system shall contain the following elements:

(a) *Air quality monitoring network.* An approvable SCS shall include the use of appropriate ambient air quality monitors to continuously measure the concentration of sulfur dioxide in the air in the smelter's DLA.

(1) The monitors shall be located at all points of expected SO_2 concentrations necessary to anticipate and prevent possible violations of NAAQS anywhere in the smelter's DLA. The determination of the locations where such concentrations may occur shall take into account all recorded or probable meteorological and operating conditions (including bypassing of control equipment), as well as the presence of other sources of SO_2 significantly affecting SO_2 concentrations in the DLA.

(2) The number and location of sites shall be based on dispersion modeling, measured ambient air quality data, meteorological information, and the results of the continuing review required by paragraph (f) of this section. The system shall include the use of at least 7 fixed monitors unless the issuing agency determines, on the basis of a demonstration by the smelter owner, that the use of fewer monitors would not limit coverage of points of high SO_2 concentration or otherwise reduce the capability of the smelter owner to prevent any violations of the NAAQS in the smelter's DLA.

(3) All monitors shall be continuously operated and maintained and shall meet the performance specifications contained in 40 CFR part 53. The monitors shall be capable of routine real time measurement of maximum expected SO_2 concentrations for the averaging times of SO_2 NAAQS.

(b) *Meteorological network.* The SCS must have a meteorological assessment capability adequate to predict and identify local conditions requiring emission curtailment to prevent possible violations of the NAAQS. The meteorological assessment capability shall provide all forecast and current information necessary for successful use of the SCS operational manual required by paragraph (e) of this section.

(c) *Designated liability area.* The system shall be required to prevent all violations of the NAAQS within the smelter's DLA. The DLA of any smelter is the area within which the smelter's emissions may cause or significantly contribute to violations of the NAAQS for SO_2 when the smelter is operating at its maximum production capacity under any recorded or probable meterological conditions. The boundaries of that area shall be specified in the NSO.

(1) Unless an acceptable demonstration is made under paragraph (c)(2) of this section, the DLA shall be a circle with a center point at the smelter's tallest stack and a minimum radius as given in the following table:

RADIUS FOR SO_2 EMISSIONS AT MAXIMUM PRODUCTION CAPACITY [1]

Emissions rate in tons per hour	Emission rate in grains per sec.	Radius in kilometers
16 or less	4,000 or less	11
24	6,000	16