



# Code of Federal Regulations

---

## 49

**Parts 100 to 185**

Revised as of October 1, 2008

### Transportation

---

Containing a codification of documents  
of general applicability and future effect

As of October 1, 2008

*With Ancillaries*

Published by  
Office of the Federal Register  
National Archives and Records  
Administration

A Special Edition of the Federal Register

## U.S. GOVERNMENT OFFICIAL EDITION NOTICE



### Legal Status and Use of Seals and Logos

The seal of the National Archives and Records Administration (NARA) authenticates the Code of Federal Regulations (CFR) as the official codification of Federal regulations established under the Federal Register Act. Under the provisions of 44 U.S.C. 1507, the contents of the CFR, a special edition of the Federal Register, shall be judicially noticed. The CFR is prima facie evidence of the original documents published in the Federal Register (44 U.S.C. 1510).

It is prohibited to use NARA's official seal and the stylized Code of Federal Regulations logo on any republication of this material without the express, written permission of the Archivist of the United States or the Archivist's designee. Any person using NARA's official seals and logos in a manner inconsistent with the provisions of 36 CFR part 1200 is subject to the penalties specified in 18 U.S.C. 506, 701, and 1017.

### Use of ISBN Prefix

This is the Official U.S. Government edition of this publication and is herein identified to certify its authenticity. Use of the 0-16 ISBN prefix is for U.S. Government Printing Office Official Editions only. The Superintendent of Documents of the U.S. Government Printing Office requests that any reprinted edition clearly be labeled as a copy of the authentic work with a new ISBN.



U.S. GOVERNMENT PRINTING OFFICE

U.S. Superintendent of Documents • Washington, DC 20402-0001

<http://bookstore.gpo.gov>

Phone: toll-free (866) 512-1800; DC area (202) 512-1800

# Table of Contents

|                                                                                                         |                  |
|---------------------------------------------------------------------------------------------------------|------------------|
| Explanation .....                                                                                       | <i>Page</i><br>v |
| Title 49:                                                                                               |                  |
| Subtitle B—Other Regulations Relating to Transportation                                                 |                  |
| Chapter I—Pipeline and Hazardous Materials Safety Administration,<br>Department of Transportation ..... | 5                |
| Finding Aids:                                                                                           |                  |
| Material Approved for Incorporation by Reference .....                                                  | 1175             |
| Table of CFR Titles and Chapters .....                                                                  | 1189             |
| Alphabetical List of Agencies Appearing in the CFR .....                                                | 1209             |
| List of CFR Sections Affected .....                                                                     | 1219             |

---

*Cite this Code:* CFR

*To cite the regulations in  
this volume use title,  
part and section num-  
ber. Thus, 49 CFR 105.5  
refers to title 49, part  
105, section 5.*

---

## Explanation

The Code of Federal Regulations is a codification of the general and permanent rules published in the Federal Register by the Executive departments and agencies of the Federal Government. The Code is divided into 50 titles which represent broad areas subject to Federal regulation. Each title is divided into chapters which usually bear the name of the issuing agency. Each chapter is further subdivided into parts covering specific regulatory areas.

Each volume of the Code is revised at least once each calendar year and issued on a quarterly basis approximately as follows:

|                                |                 |
|--------------------------------|-----------------|
| Title 1 through Title 16.....  | as of January 1 |
| Title 17 through Title 27..... | as of April 1   |
| Title 28 through Title 41..... | as of July 1    |
| Title 42 through Title 50..... | as of October 1 |

The appropriate revision date is printed on the cover of each volume.

### LEGAL STATUS

The contents of the Federal Register are required to be judicially noticed (44 U.S.C. 1507). The Code of Federal Regulations is prima facie evidence of the text of the original documents (44 U.S.C. 1510).

### HOW TO USE THE CODE OF FEDERAL REGULATIONS

The Code of Federal Regulations is kept up to date by the individual issues of the Federal Register. These two publications must be used together to determine the latest version of any given rule.

To determine whether a Code volume has been amended since its revision date (in this case, October 1, 2008), consult the “List of CFR Sections Affected (LSA),” which is issued monthly, and the “Cumulative List of Parts Affected,” which appears in the Reader Aids section of the daily Federal Register. These two lists will identify the Federal Register page number of the latest amendment of any given rule.

### EFFECTIVE AND EXPIRATION DATES

Each volume of the Code contains amendments published in the Federal Register since the last revision of that volume of the Code. Source citations for the regulations are referred to by volume number and page number of the Federal Register and date of publication. Publication dates and effective dates are usually not the same and care must be exercised by the user in determining the actual effective date. In instances where the effective date is beyond the cut-off date for the Code a note has been inserted to reflect the future effective date. In those instances where a regulation published in the Federal Register states a date certain for expiration, an appropriate note will be inserted following the text.

### OMB CONTROL NUMBERS

The Paperwork Reduction Act of 1980 (Pub. L. 96-511) requires Federal agencies to display an OMB control number with their information collection request.

Many agencies have begun publishing numerous OMB control numbers as amendments to existing regulations in the CFR. These OMB numbers are placed as close as possible to the applicable recordkeeping or reporting requirements.

#### OBSOLETE PROVISIONS

Provisions that become obsolete before the revision date stated on the cover of each volume are not carried. Code users may find the text of provisions in effect on a given date in the past by using the appropriate numerical list of sections affected. For the period before January 1, 1986, consult either the List of CFR Sections Affected, 1949–1963, 1964–1972, or 1973–1985, published in seven separate volumes. For the period beginning January 1, 1986, a “List of CFR Sections Affected” is published at the end of each CFR volume.

#### INCORPORATION BY REFERENCE

*What is incorporation by reference?* Incorporation by reference was established by statute and allows Federal agencies to meet the requirement to publish regulations in the Federal Register by referring to materials already published elsewhere. For an incorporation to be valid, the Director of the Federal Register must approve it. The legal effect of incorporation by reference is that the material is treated as if it were published in full in the Federal Register (5 U.S.C. 552(a)). This material, like any other properly issued regulation, has the force of law.

*What is a proper incorporation by reference?* The Director of the Federal Register will approve an incorporation by reference only when the requirements of 1 CFR part 51 are met. Some of the elements on which approval is based are:

- (a) The incorporation will substantially reduce the volume of material published in the Federal Register.
- (b) The matter incorporated is in fact available to the extent necessary to afford fairness and uniformity in the administrative process.
- (c) The incorporating document is drafted and submitted for publication in accordance with 1 CFR part 51.

Properly approved incorporations by reference in this volume are listed in the Finding Aids at the end of this volume.

*What if the material incorporated by reference cannot be found?* If you have any problem locating or obtaining a copy of material listed in the Finding Aids of this volume as an approved incorporation by reference, please contact the agency that issued the regulation containing that incorporation. If, after contacting the agency, you find the material is not available, please notify the Director of the Federal Register, National Archives and Records Administration, Washington DC 20408, or call 202-741-6010.

#### CFR INDEXES AND TABULAR GUIDES

A subject index to the Code of Federal Regulations is contained in a separate volume, revised annually as of January 1, entitled CFR INDEX AND FINDING AIDS. This volume contains the Parallel Table of Statutory Authorities and Agency Rules (Table I). A list of CFR titles, chapters, and parts and an alphabetical list of agencies publishing in the CFR are also included in this volume.

An index to the text of “Title 3—The President” is carried within that volume.

The Federal Register Index is issued monthly in cumulative form. This index is based on a consolidation of the “Contents” entries in the daily Federal Register.

A List of CFR Sections Affected (LSA) is published monthly, keyed to the revision dates of the 50 CFR titles.

## REPUBLICATION OF MATERIAL

There are no restrictions on the republication of material appearing in the Code of Federal Regulations.

## INQUIRIES

For a legal interpretation or explanation of any regulation in this volume, contact the issuing agency. The issuing agency's name appears at the top of odd-numbered pages.

For inquiries concerning CFR reference assistance, call 202-741-6000 or write to the Director, Office of the Federal Register, National Archives and Records Administration, Washington, DC 20408 or e-mail [fedreg.info@nara.gov](mailto:fedreg.info@nara.gov).

## SALES

The Government Printing Office (GPO) processes all sales and distribution of the CFR. For payment by credit card, call toll-free, 866-512-1800, or DC area, 202-512-1800, M-F 8 a.m. to 4 p.m. e.s.t. or fax your order to 202-512-2250, 24 hours a day. For payment by check, write to: US Government Printing Office – New Orders, P.O. Box 979050, St. Louis, MO 63197-9000. For GPO Customer Service call 202-512-1803.

## ELECTRONIC SERVICES

The full text of the Code of Federal Regulations, the LSA (List of CFR Sections Affected), The United States Government Manual, the Federal Register, Public Laws, Public Papers, Weekly Compilation of Presidential Documents and the Privacy Act Compilation are available in electronic format at [www.gpoaccess.gov/nara](http://www.gpoaccess.gov/nara) ("GPO Access"). For more information, contact Electronic Information Dissemination Services, U.S. Government Printing Office. Phone 202-512-1530, or 888-293-6498 (toll-free). E-mail, [gpoaccess@gpo.gov](mailto:gpoaccess@gpo.gov).

The Office of the Federal Register also offers a free service on the National Archives and Records Administration's (NARA) World Wide Web site for public law numbers, Federal Register finding aids, and related information. Connect to NARA's web site at [www.archives.gov/federal-register](http://www.archives.gov/federal-register). The NARA site also contains links to GPO Access.

RAYMOND A. MOSLEY,  
*Director,*  
*Office of the Federal Register.*  
*October 1, 2008.*





## THIS TITLE

Title 49—TRANSPORTATION is composed of nine volumes. The parts in these volumes are arranged in the following order: Parts 1–99, parts 100–185, parts 186–199, parts 200–299, parts 300–399, parts 400–599, parts 600–999, parts 1000–1199, part 1200 to End. The first volume (parts 1–99) contains current regulations issued under subtitle A—Office of the Secretary of Transportation; the second volume (parts 100–185) and the third volume (parts 186–199) contain the current regulations issued under chapter I—Pipeline and Hazardous Materials Safety Administration (DOT); the fourth volume (parts 200–299) contains the current regulations issued under chapter II—Federal Railroad Administration (DOT); the fifth volume (parts 300–399) contains the current regulations issued under chapter III—Federal Motor Carrier Safety Administration (DOT); the sixth volume (parts 400–599) contains the current regulations issued under chapter IV—Coast Guard (DHS), chapter V—National Highway Traffic Safety Administration (DOT); the seventh volume (parts 600–999) contains the current regulations issued under chapter VI—Federal Transit Administration (DOT), chapter VII—National Railroad Passenger Corporation (AMTRAK), and chapter VIII—National Transportation Safety Board; the eighth volume (parts 1000–1199) contains the current regulations issued under chapter X—Surface Transportation Board and the ninth volume (part 1200 to End) contains the current regulations issued under chapter X—Surface Transportation Board, chapter XI—Research and Innovative Technology Administration, and chapter XII—Transportation Security Administration, Department of Transportation. The contents of these volumes represent all current regulations codified under this title of the CFR as of October 1, 2008.

In the volume containing parts 100–185, see §172.101 for the Hazardous Materials Table. The Federal Motor Vehicle Safety Standards appear in part 571.

Redesignation tables for chapter III—Federal Motor Carrier Safety Administration, Department of Transportation and chapter XII—Transportation Security Administration, Department of Transportation appear in the Finding Aids section of the fifth and ninth volumes.

For this volume, Jonn V. Lilyea was Chief Editor. The Code of Federal Regulations publication program is under the direction of Michael L. White, assisted by Ann Worley.

# Title 49—Transportation

(This book contains parts 100 to 185)

---

## SUBTITLE B—OTHER REGULATIONS RELATING TO TRANSPORTATION

|                                                                                                      | <i>Part</i> |
|------------------------------------------------------------------------------------------------------|-------------|
| CHAPTER 1—Pipeline and Hazardous Materials Safety Administration, Department of Transportation ..... | 105         |



## Subtitle B—Other Regulations Relating to Transportation



# CHAPTER I—PIPELINE AND HAZARDOUS MATERIALS SAFETY ADMINISTRATION, DEPARTMENT OF TRANSPORTATION

---

## SUBCHAPTER A—HAZARDOUS MATERIALS AND OIL TRANSPORTATION

| <i>Part</i> |                                                                      | <i>Page</i> |
|-------------|----------------------------------------------------------------------|-------------|
| 105         | Hazardous Materials Program definitions and general procedures ..... | 7           |
| 106         | Rulemaking procedures .....                                          | 13          |
| 107         | Hazardous materials program procedures .....                         | 19          |
| 110         | Hazardous materials public sector training and planning grants ..... | 65          |

## SUBCHAPTER B—OIL TRANSPORTATION

|     |                                               |    |
|-----|-----------------------------------------------|----|
| 130 | Oil spill prevention and response plans ..... | 73 |
|-----|-----------------------------------------------|----|

## SUBCHAPTER C—HAZARDOUS MATERIALS REGULATIONS

|         |                                                                                                                                              |      |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------|------|
| 171     | General information, regulations, and definitions ..                                                                                         | 76   |
| 172     | Hazardous materials table, special provisions, hazardous materials communications, emergency response information, and training requirements | 121  |
| 173     | Shippers—general requirements for shipments and packagings .....                                                                             | 427  |
| 174     | Carriage by rail .....                                                                                                                       | 696  |
| 175     | Carriage by aircraft .....                                                                                                                   | 742  |
| 176     | Carriage by vessel .....                                                                                                                     | 742  |
| 177     | Carriage by public highway .....                                                                                                             | 802  |
| 178     | Specifications for packagings .....                                                                                                          | 824  |
| 179     | Specifications for tank cars .....                                                                                                           | 1059 |
| 180     | Continuing qualification and maintenance of packagings .....                                                                                 | 1116 |
| 181–185 | [Reserved]                                                                                                                                   |      |



## SUBCHAPTER A—HAZARDOUS MATERIALS AND OIL TRANSPORTATION

### PART 105—HAZARDOUS MATERIALS PROGRAM DEFINITIONS AND GENERAL PROCEDURES

#### Subpart A—Definitions

Sec.  
105.5 Definitions.

#### Subpart B—General Procedures

105.15 Defined terms used in this subpart.

##### OBTAINING GUIDANCE AND PUBLIC INFORMATION

105.20 Guidance and interpretations.  
105.25 Reviewing public documents.  
105.26 Obtaining records on file with  
PHMSA.  
105.30 Information made available to the  
public and request for confidential treat-  
ment.

##### SERVING DOCUMENTS

105.35 Serving documents in PHMSA pro-  
ceedings.  
105.40 Designated agents for non-residents.

##### SUBPOENAS

105.45 Issuing a subpoena.  
105.50 Serving a subpoena.  
105.55 Refusal to obey a subpoena.

AUTHORITY: 49 U.S.C. 5101–5127; 49 CFR 1.53.

SOURCE: 67 FR 42951, June 25, 2002, unless  
otherwise noted.

EDITORIAL NOTE: Nomenclature changes to  
part 105 appear at 70 FR 56087, Sept. 23, 2005.

#### Subpart A—Definitions

##### § 105.5 Definitions.

(a) This part contains the definitions for certain words and phrases used throughout this subchapter (49 CFR parts 105 through 110). At the beginning of each subpart, the Pipeline and Hazardous Materials Safety Administration (“PHMSA” or “we”) will identify the defined terms that are used within the subpart—by listing them—and refer the reader to the definitions in this part. This way, readers will know that PHMSA has given a term a precise meaning and will know where to look for it.

(b) Terms used in this part are defined as follows:

*Associate Administrator* means Associate Administrator for Hazardous Materials Safety, Pipeline and Hazardous Materials Safety Administration.

*Approval* means written consent, including a competent authority approval, from the Associate Administrator or other designated Department official, to perform a function that requires prior consent under subchapter C of this chapter (49 CFR parts 171 through 180).

*Competent Authority* means a national agency that is responsible, under its national law, for the control or regulation of some aspect of hazardous materials (dangerous goods) transportation. Another term for Competent Authority is “Appropriate authority” which is used in the International Civil Aviation Organization’s (ICAO) Technical Instructions for the Safe Transport of Dangerous Goods by Air. The Associate Administrator is the United States Competent Authority for purposes of 49 CFR part 107.

*Competent Authority Approval* means an approval by the competent authority that is required under an international standard (for example, the ICAO Technical Instructions for the Safe Transport of Dangerous Goods by Air and the International Maritime Dangerous Goods Code). Any of the following may be considered a competent authority approval if it satisfies the requirement of an international standard:

(1) A specific regulation in subchapter A or C of this chapter.

(2) A special permit or approval issued under subchapter A or C of this chapter.

(3) A separate document issued to one or more persons by the Associate Administrator.

*Federal hazardous material transportation law* means 49 U.S.C. 5101 *et seq.*

*File* or *Filed* means received by the appropriate PHMSA or other designated office within the time specified in a regulation or rulemaking document.



*Hazardous material* means a substance or material that the Secretary of Transportation has determined is capable of posing an unreasonable risk to health, safety, and property when transported in commerce, and has designated as hazardous under section 5103 of Federal hazardous materials transportation law (49 U.S.C. 5103). The term includes hazardous substances, hazardous wastes, marine pollutants, elevated temperature materials, materials designated as hazardous in the Hazardous Materials Table (see 49 CFR 172.101), and materials that meet the defining criteria for hazard classes and divisions in part 173 of subchapter C of this chapter.

*Hazardous Materials Regulations* or *HMR* means the regulations at 49 CFR parts 171 through 180.

*Indian tribe* has the same meaning given that term in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450b).

*Person* means an individual, firm, co-partnership, corporation, company, association, or joint-stock association (including any trustee, receiver, assignee, or similar representative); or a government or Indian tribe (or an agency or instrumentality of any government or Indian tribe) that transports a hazardous material to further a commercial enterprise or offers a hazardous material for transportation in commerce. Person does not include the following:

- (1) The United States Postal Service.
- (2) Any agency or instrumentality of the Federal government, for the purposes of 49 U.S.C. 5123 (civil penalties) and 5124 (criminal penalties).
- (3) Any government or Indian tribe (or an agency or instrumentality of any government or Indian tribe) that transports hazardous material for a governmental purpose.

*Political subdivision* means a municipality; a public agency or other instrumentality of one or more States, municipalities, or other political body of a State; or a public corporation, board, or commission established under the laws of one or more States.

*Preemption determination* means an administrative decision by the Associate Administrator that Federal hazardous materials law does or does not

void a specific State, political subdivision, or Indian tribe requirement.

*Regulations issued under Federal hazardous material transportation law* include this subchapter A (parts 105–110) and subchapter C (parts 171–180) of this chapter, certain regulations in chapter I (United States Coast Guard) of title 46, Code of Federal Regulations, and in chapters III (Federal Motor Carrier Safety Administration) and XII (Transportation Security Administration) of subtitle B of this title, as indicated by the authority citations therein.

*Special permit* means a document issued by the Associate Administrator under the authority of 49 U.S.C. 5117 permitting a person to perform a function that is not otherwise permitted under subchapter A or C of this chapter, or other regulations issued under 49 U.S.C. 5101 et seq. (e.g., Federal Motor Carrier Safety routing requirements). The terms “special permit” and “exemption” have the same meaning for purposes of subchapter A or C of this chapter or other regulations issued under 49 U.S.C. 5101 through 5127. An exemption issued prior to October 1, 2005 remains valid until it is past its expiration date, terminated by the Associate Administrator, or is issued as a special permit, whichever occurs first.

*State* means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, the Virgin Islands, American Samoa, Guam, or any other territory or possession of the United States designated by the Secretary.

*Transports* or *Transportation* means the movement of property and loading, unloading, or storage incidental to the movement.

*Waiver of Preemption* means a decision by the Associate Administrator to forego preemption of a non-Federal requirement—that is, to allow a State, political subdivision or Indian tribe requirement to remain in effect. The non-Federal requirement must provide at least as much public protection as the Federal hazardous materials transportation law and the regulations

issued under Federal hazardous materials transportation law, and may not unreasonably burden commerce.

[67 FR 42951, June 25, 2002, as amended at 68 FR 52846, Sept. 8, 2003; 70 FR 56087, Sept. 23, 2005; 70 FR 73158, Dec. 9, 2005]

### Subpart B—General Procedures

#### § 105.15 Defined terms used in this subpart.

The following defined terms (see subpart A of this part) appear in this subpart: Approval; Federal hazardous material transportation law; Hazardous material; Hazardous materials regulations; Indian tribe; Preemption determination; Special permit; State; Transportation; Waiver of preemption

[67 FR 42951, June 25, 2002, as amended at 70 FR 73159, Dec. 9, 2005]

#### OBTAINING GUIDANCE AND PUBLIC INFORMATION

#### § 105.20 Guidance and interpretations.

(a) *Hazardous materials regulations.* You can obtain information and answers to your questions on compliance with the hazardous materials regulations (49 CFR parts 171 through 180) and interpretations of those regulations by contacting PHMSA's Office of Hazardous Materials Safety as follows:

(1) Call the Hazardous Materials Information Center at 1-800-467-4922 (in Washington, DC, call (202) 366-4488). The Center is staffed from 9 a.m. through 5 p.m. Eastern time, Monday through Friday except Federal holidays. After hours, you can leave a recorded message and your call will be returned by the next business day.

(2) E-mail the Hazardous Materials Information Center at [infocntr@dot.gov](mailto:infocntr@dot.gov).

(3) Obtain hazardous materials safety information via the Internet at <http://www.phmsa.dot.gov>.

(4) Send a letter, with your return address and a daytime telephone number, to: Office of Hazardous Materials Standards, Pipeline and Hazardous Materials Safety Administration, Attn: PHH-10, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(b) *Federal hazardous materials transportation law and preemption.* You can

obtain information and answers to your questions on Federal hazardous materials transportation law, 49 U.S.C. 5101 *et seq.*, and Federal preemption of State, local, and Indian tribe hazardous material transportation requirements, by contacting PHMSA's Office of the Chief Counsel as follows:

(1) Call the office of the Chief Counsel at (202) 366-4400 from 9 a.m. to 5 p.m. Eastern time, Monday through Friday except Federal holidays.

(2) Access information from the Office of the Chief Counsel via the Internet at <http://www.phmsa.dot.gov>.

(3) Send a letter, with your return address and a daytime telephone number, to: Office of the Chief Counsel, Pipeline and Hazardous Materials Safety Administration, Attn: PHC-10, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(4) Contact the Office of the Chief Counsel for a copy of applications for preemption determinations, waiver of preemption determinations, and inconsistency rulings received by PHMSA before February 1, 1997.

[70 FR 56087, Sept. 23, 2005, as amended at 72 FR 55682, Oct. 1, 2007]

#### § 105.25 Reviewing public documents.

PHMSA is required by statute to make certain documents and information available to the public. You can review and copy publicly available documents and information at the locations described in this section.

(a) *DOT Docket Management System.* Unless a particular document says otherwise, the following documents are available for public review and copying at the Department of Transportation's Docket Management System, West Building Ground Floor, Room W12-140, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001, or for review and downloading through the Internet at <http://www.regulations.gov>.

(1) Rulemaking documents in proceedings started after February 1, 1997, including notices of proposed rulemaking, advance notices of proposed rulemaking, public comments, related FEDERAL REGISTER notices, final rules, appeals, and PHMSA's decisions in response to appeals.

## § 105.26

## 49 CFR Ch. I (10–1–08 Edition)

(2) Applications for special permits numbered DOT-E or DOT-SP 11832 and above. Also available are supporting data, memoranda of any informal meetings with applicants, related FEDERAL REGISTER notices, public comments, and decisions granting or denying applications for special permits.

(3) Applications for preemption determinations and waiver of preemption determinations received by PHMSA after February 1, 1997. Also available are public comments, FEDERAL REGISTER notices, and PHMSA's rulings, determinations, decisions on reconsideration, and orders issued in response to those applications.

(b) *Office of Pipeline and Hazardous Materials Safety Administration's Office of Hazardous Materials Safety.* (1) You may obtain documents (e.g., proposed and final rules, notices, letters of clarification, safety notices, DOT forms and other documents) by contacting the Hazardous Materials Information Center at 1-800-467-4922 or through the Internet at <http://www.phmsa.dot.gov>.

(2) Upon your written request, we will make the following documents and information available to you:

(i) Appeals under 49 CFR part 107 and PHMSA's decisions issued in response to those appeals.

(ii) Records of compliance order proceedings and PHMSA compliance orders.

(iii) Applications for approvals, including supporting data, memoranda of any informal meetings with applicants, and decisions granting or denying approvals applications.

(iv) Applications for special permits numbered below DOT-E or DOT-SP 11832 and related background information are available for public review and copying at the Office of Hazardous Materials Safety, Office of Hazardous Materials Special Permits and Approvals, U.S. Department of Transportation, PHH-30, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(v) Other information about PHMSA's hazardous materials program required by statute to be made available to the public for review and copying and any other information PHMSA decides should be available to the public.

(3) Your written request to review documents should include the following:

(i) A detailed description of the documents you wish to review.

(ii) Your name, address, and telephone number.

(4) Send your written request to: Associate Administrator for Hazardous Materials Safety, Pipeline and Hazardous Materials Safety Administration, Attn: PHH-1, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

[70 FR 56088, Sept. 23, 2005, as amended at 70 FR 73159, Dec. 9, 2005; 72 FR 55682, Oct. 1, 2007]

### § 105.26 Obtaining records on file with PHMSA.

To obtain records on file with PHMSA, other than those described in § 105.25, you must file a request with PHMSA under the Freedom of Information Act (FOIA) (5 U.S.C. 552). The procedures for filing a FOIA request are contained in 49 CFR part 7.

### § 105.30 Information made available to the public and request for confidential treatment.

When you submit information to PHMSA during a rulemaking proceeding, as part of your application for special permit or approval, or for any other reason, we may make that information publicly available unless you ask that we keep the information confidential.

(a) *Asking for confidential treatment.* You may ask us to give confidential treatment to information you give to the agency by taking the following steps:

(1) Mark "confidential" on each page of the original document you would like to keep confidential.

(2) Send us, along with the original document, a second copy of the original document with the confidential information deleted.

(3) Explain why the information you are submitting is confidential (for example, it is exempt from mandatory public disclosure under the Freedom of Information Act, 5 U.S.C. 552 or it is information referred to in 18 U.S.C. 1905).

(b) *PHMSA Decision*. PHMSA will decide whether or not to treat your information as confidential. We will notify you, in writing, of a decision to grant or deny confidentiality at least five days before the information is publicly disclosed, and give you an opportunity to respond.

[67 FR 42951, June 25, 2002, as amended at 70 FR 73159, Dec. 9, 2005]

#### SERVING DOCUMENTS

##### § 105.35 Serving documents in PHMSA proceedings.

(a) *Service by PHMSA*. We may serve the document by one of the following methods, except where a different method of service is specifically required:

(1) Registered or certified mail.

(i) If we serve a document by registered or certified mail, it is considered served when mailed.

(ii) An official United States Postal Service receipt from the registered or certified mailing is proof of service.

(iii) We may serve a person's authorized representative or agent by registered or certified mail, or in any other manner authorized by law. Service on a person's authorized agent is the same as service on the person.

(2) Personal service.

(3) Publication in the FEDERAL REGISTER.

(b) *Service by others*. If you are required under this subchapter to serve a person with a document, serve the document by one of the following methods, except where a different method of service is specifically required:

(1) Registered or certified mail.

(i) If you serve a document by registered or certified mail, it is considered served when mailed.

(ii) An official United States Postal Service receipt from the registered or certified mailing is proof of service.

(iii) You may serve a person's authorized representative or agent by registered or certified mail or in any other manner authorized by law. Service on a person's authorized agent is the same as service on the person.

(2) Personal service.

(3) Electronic service.

(i) In a proceeding under § 107.317 of this subchapter (an administrative law

judge proceeding), you may electronically serve documents on us.

(ii) Serve documents electronically through the Internet at <http://www.regulations.gov>.

[67 FR 42951, June 25, 2002, as amended at 72 FR 55682, Oct. 1, 2007]

##### § 105.40 Designated agents for non-residents.

(a) *General requirement*. If you are not a resident of the United States but are required by this subchapter or subchapter C of this chapter to designate a permanent resident of the United States to act as your agent and receive documents on your behalf, you must prepare a designation and file it with us.

(b) *Agents*. An agent:

(1) May be an individual, a firm, or a domestic corporation.

(2) May represent any number of principals.

(3) May not reassign responsibilities under a designation to another person.

(c) *Preparing a designation*. Your designation must be written and dated, and it must contain the following information:

(1) The section in the HMR that requires you to file a designation.

(2) A certification that the designation is in the correct legal form required to make it valid and binding on you under the laws, corporate bylaws, and other requirements that apply to designations at the time and place you are making the designation.

(3) Your full legal name, the principal name of your business, and your mailing address.

(4) A statement that your designation will remain in effect until you withdraw or replace it.

(5) The legal name and mailing address of your agent.

(6) A declaration of acceptance signed by your agent.

(d) *Address*. Send your designation to: Office of Hazardous Materials Special Permits and Approvals, Pipeline and Hazardous Materials Safety Administration, Attn: PHH-30, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(e) *Designations are binding*. You are bound by your designation of an agent,

## § 105.45

even if you did not follow all the requirements in this section, until we reject your designation.

[67 FR 42951, June 25, 2002, as amended at 70 FR 56088, Sept. 23, 2005; 70 FR 73159, Dec. 9, 2005; 72 FR 55682, Oct. 1, 2007]

### SUBPOENAS

#### § 105.45 Issuing a subpoena.

(a) *Subpoenas explained.* A subpoena is a document that may require you to attend a proceeding, produce documents or other physical evidence in your possession or control, or both. PHMSA may issue a subpoena either on its initiative or at the request of someone participating in a proceeding. Anyone who requests that PHMSA issue a subpoena must show that the subpoena seeks information that will materially advance the proceeding.

(b) *Attendance and mileage expenses.*

(1) If you receive a subpoena to attend a proceeding under this part, you may receive money to cover attendance and mileage expenses. The attendance and mileage fees will be the same as those paid to a witness in a proceeding in the district courts of the United States.

(2) If PHMSA issues a subpoena to you based upon a request, the requester must serve a copy of the original subpoena on you, as required in § 105.50. The requester must also include attendance and mileage fees with the subpoena unless the requester asks PHMSA to pay the attendance and mileage fees because of demonstrated financial hardship and PHMSA agrees to do so.

(3) If PHMSA issues a subpoena at the request of an officer or agency of the Federal government, the officer or agency is not required to include attendance and mileage fees when serving the subpoena. The officer or agency must pay the fees before you leave the hearing at which you testify.

#### § 105.50 Serving a subpoena.

(a) *Personal service.* Anyone who is not an interested party and who is at least 18 years of age may serve you with a subpoena and fees by handing the subpoena and fees to you, by leaving them at your office with the individual in charge, or by leaving them at your house with someone who lives

## 49 CFR Ch. I (10–1–08 Edition)

there and is capable of making sure that you receive them. If PHMSA issues a subpoena to an entity, rather than an individual, personal service is made by delivering the subpoena and fees to the entity's registered agent for service of process or to any officer, director or agent in charge of any of the entity's offices.

(b) *Service by mail.* You may be served with a copy of a subpoena and fees by certified or registered mail at your last known address. Service of a subpoena and fees may also be made by registered or certified mail to your agent for service of process or any of your representatives at that person's last known address.

(c) *Other methods.* You may be served with a copy of a subpoena by any method where you receive actual notice of the subpoena and receive the fees before leaving the hearing at which you testify.

(d) *Filing after service.* After service is complete, the individual who served a copy of a subpoena and fees must file the original subpoena and a certificate of service with the PHMSA official who is responsible for conducting the hearing.

#### § 105.55 Refusal to obey a subpoena.

(a) *Quashing or modifying a subpoena.* If you receive a subpoena, you can ask PHMSA to overturn ("quash") or modify the subpoena within 10 days after the subpoena is served on you. Your request must briefly explain the reasons you are asking for the subpoena to be quashed or modified. PHMSA may then do the following:

(1) Deny your request.

(2) Quash or modify the subpoena.

(3) Grant your request on the condition that you satisfy certain specified requirements.

(b) *Failure to obey.* If you disobey a subpoena, PHMSA may ask the Attorney General to seek help from the United States District Court for the appropriate District to compel you, after notice, to appear before PHMSA and give testimony, produce subpoenaed documents or physical evidence, or both.

**PART 106—RULEMAKING  
PROCEDURES****Subpart A—PHMSA Rulemaking  
Documents**

Sec.

- 106.5 Defined terms used in this subpart.
- 106.10 Process for issuing rules.
- 106.15 Advance notice of proposed rulemaking.
- 106.20 Notice of proposed rulemaking.
- 106.25 Revising regulations without first issuing an ANPRM or NPRM.
- 106.30 Final rule.
- 106.35 Interim final rule.
- 106.40 Direct final rule.
- 106.45 Tracking rulemaking actions.

**Subpart B—Participating in the Rulemaking  
Process**

- 106.50 Defined terms used in this subpart.
- 106.55 Public participation in the rulemaking process.

**WRITTEN COMMENTS**

- 106.60 Filing comments.
- 106.65 Required information for written comments.
- 106.70 Where and when to file comments.
- 106.75 Extension of time to file comments.

**PUBLIC MEETINGS AND OTHER PROCEEDINGS**

- 106.80 Public meeting procedures.
- 106.85 Requesting a public meeting.
- 106.90 Other rulemaking proceedings.

**PETITIONS FOR RULEMAKING**

- 106.95 Requesting a change to the regulations.
- 106.100 Required information for a petition for rulemaking.
- 106.105 PHMSA response to a petition for rulemaking.

**APPEALS**

- 106.110 Appealing a PHMSA action.
- 106.115 Required information for an appeal.
- 106.120 Appeal deadline.
- 106.125 Filing an appeal.
- 106.130 PHMSA response to an appeal.

AUTHORITY: 49 U.S.C. 5101–5127; 49 CFR 1.53.

SOURCE: 67 FR 42954, June 25, 2002, unless otherwise noted.

EDITORIAL NOTE: Nomenclature changes to part 106 appear at 70 FR 56088, Sept. 23, 2005.

**Subpart A—PHMSA Rulemaking  
Documents****§ 106.5 Defined terms used in this subpart.**

The following defined terms (see part 105, subpart A, of this subchapter) appear in this subpart: File; Person; State.

**§ 106.10 Process for issuing rules.**

(a) PHMSA (“we”) uses informal rulemaking procedures under the Administrative Procedure Act (5 U.S.C. 553) to add, amend, or delete regulations. To propose or adopt changes to a regulation, PHMSA may issue one or more of the following documents. We publish the following rulemaking documents in the FEDERAL REGISTER unless we name and personally serve a copy of a rule on every person subject to it:

- (1) An advance notice of proposed rulemaking.
- (2) A notice of proposed rulemaking.
- (3) A final rule.
- (4) An interim final rule.
- (5) A direct final rule.

(b) Each of the rulemaking documents in paragraph (a) of this section generally contains the following information:

- (1) The topic involved in the rulemaking document.
- (2) PHMSA’s legal authority for issuing the rulemaking document.
- (3) How interested persons may participate in the rulemaking proceeding (for example, by filing written comments or making oral presentations).
- (4) Whom to call if you have questions about the rulemaking document.
- (5) The date, time, and place of any public meetings being held to discuss the rulemaking document.
- (6) The docket number and regulation identifier number (RIN) for the rulemaking proceeding.

[67 FR 42954, June 25, 2002, as amended at 70 FR 56088, Sept. 23, 2005]

**§ 106.15 Advance notice of proposed rulemaking.**

An advance notice of proposed rulemaking (ANPRM) tells the public that PHMSA is considering an area for rulemaking and requests written comments on the appropriate scope of the rulemaking or on specific topics. An

## § 106.20

advance notice of proposed rulemaking may or may not include the text of potential changes to a regulation.

### **§ 106.20 Notice of proposed rulemaking.**

A notice of proposed rulemaking (NPRM) contains PHMSA's specific proposed regulatory changes for public comment and contains supporting information. It generally includes proposed regulatory text.

### **§ 106.25 Revising regulations without first issuing an ANPRM or NPRM.**

PHMSA may add, amend, or delete regulations without first issuing an ANPRM or NPRM in the following situations:

(a) We may go directly to a final rule or interim final rule if, for good cause, we find that a notice of proposed rulemaking is impracticable, unnecessary, or contrary to the public interest. We must place that finding and a brief statement of the reasons for it in the final rule or interim final rule.

(b) We may issue a direct final rule (see § 106.40).

### **§ 106.30 Final rule.**

A final rule sets out new regulatory requirements and their effective date. A final rule will also identify issues raised by commenters in response to the notice of proposed rulemaking and give the agency's response.

### **§ 106.35 Interim final rule.**

An interim final rule is issued without first issuing a notice of proposed rulemaking and accepting public comments and sets out new regulatory requirements and their effective date. PHMSA may issue an interim final rule if it finds, for good cause, that notice and public procedure are impracticable, unnecessary, or contrary to the public interest. PHMSA will clearly set out this finding in the interim final rule. After receiving and reviewing public comments, as well as any other relevant documents, PHMSA may revise the interim final rule and then issue a final rule.

### **§ 106.40 Direct final rule.**

A direct final rule makes regulatory changes and states that the regulatory

## 49 CFR Ch. I (10–1–08 Edition)

changes will take effect on a specified date unless PHMSA receives an adverse comment or notice of intent to file an adverse comment within the comment period—generally 60 days after the direct final rule is published in the FEDERAL REGISTER.

(a) *Actions taken by direct final rule.* We may use direct final rulemaking procedures to issue rules that do any of the following:

(1) Make minor substantive changes to regulations.

(2) Incorporate by reference the latest edition of technical or industry standards.

(3) Extend compliance dates.

(4) Make noncontroversial changes to regulations. We must determine and publish a finding that use of direct final rulemaking, in this situation, is in the public interest and unlikely to result in adverse comment.

(b) *Adverse comment.* An adverse comment explains why a rule would be inappropriate, or would be ineffective or unacceptable without a change. It may challenge the rule's underlying premise or approach. Under the direct final rule process, we do not consider the following types of comments to be adverse:

(1) A comment recommending another rule change, in addition to the change in the direct final rule at issue, unless the commenter states why the direct final rule would be ineffective without the change.

(2) A frivolous or irrelevant comment.

(c) *Confirmation of effective date.* We will publish a confirmation document in the FEDERAL REGISTER, generally within 15 days after the comment period closes, if we have not received an adverse comment or notice of intent to file an adverse comment. The confirmation document tells the public the effective date of the rule—either the date stated in the direct final rule or at least 30 days after the publication date of the confirmation document, whichever is later.

(d) *Withdrawing a direct final rule.* (1) If we receive an adverse comment or notice of intent to file an adverse comment, we will publish a document in

the FEDERAL REGISTER before the effective date of the direct final rule advising the public and withdrawing the direct final rule in whole or in part.

(2) If we withdraw a direct final rule because of an adverse comment, we may incorporate the adverse comment into a later direct final rule or may publish a notice of proposed rulemaking.

(e) *Appeal.* You may appeal PHMSA's issuance of a direct final rule (see § 106.115) only if you have previously filed written comments (see § 106.60) to the direct final rule.

#### § 106.45 Tracking rulemaking actions.

The following identifying numbers allow you to track PHMSA's rulemaking activities:

(a) *Docket number.* We assign an identifying number, called a docket number, to each rulemaking proceeding. Each rulemaking document that PHMSA issues in a particular rulemaking proceeding will display the same docket number. This number allows you to do the following:

(1) Associate related documents that appear in the FEDERAL REGISTER.

(2) Search the DOT Docket Management System ("DMS") for information on particular rulemaking proceedings—including notices of proposed rulemaking, public comments, petitions for rulemaking, appeals, records of additional rulemaking proceedings and final rules. There are two ways you can search the DMS:

(i) Visit the public docket room and review and copy any docketed materials during regular business hours. The DOT Docket Management System is located at the U.S. Department of Transportation, West Building Ground Floor, Room W12-140, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(ii) View and download docketed materials through the Internet at <http://www.regulations.gov>.

(b) *Regulation identifier number.* The Department of Transportation publishes a semiannual agenda of all current and projected Department of Transportation rulemakings, reviews of existing regulations, and completed actions. This semiannual agenda appears in the Unified Agenda of Federal

Regulations that is published in the FEDERAL REGISTER in April and October of each year. The semiannual agenda tells the public about the Department's—including PHMSA's—regulatory activities. The Department assigns a regulation identifier number (RIN) to each individual rulemaking proceeding in the semiannual agenda. This number appears on all rulemaking documents published in the FEDERAL REGISTER and makes it easy for you to track those rulemaking proceedings in both the FEDERAL REGISTER and the semiannual regulatory agenda itself, as well as to locate all documents in the Docket Management System pertaining to a particular rulemaking.

[70 FR 56088, Sept. 23, 2005, as amended at 72 FR 55682, Oct. 1, 2007]

### Subpart B—Participating in the Rulemaking Process

#### § 106.50 Defined terms used in this subpart.

The following defined terms (see part 105, subpart A, of this subchapter) appear in this subpart: File; Person; Political subdivision; State.

#### § 106.55 Public participation in the rulemaking process.

You may participate in PHMSA's rulemaking process by doing any of the following:

(a) File written comments on any rulemaking document that asks for comments, including an advance notice of proposed rulemaking, notice of proposed rulemaking, interim final rule, or direct final rule.

(b) Ask that we hold a public meeting in any rulemaking proceeding and participate in any public meeting that we hold.

(c) File a petition for rulemaking that asks us to add, amend, or delete a regulation.

(d) File an appeal that asks us to re-examine our decision to issue all or part of a final rule, interim final rule, or direct final rule.



## § 106.60

### WRITTEN COMMENTS

#### § 106.60 Filing comments.

Anyone may file written comments about proposals made in any rulemaking document that requests public comments, including any State government agency, any political subdivision of a State, and any interested person invited by PHMSA to participate in the rulemaking process.

#### § 106.65 Required information for written comments.

Your comments must be in English and must contain the following:

(a) The docket number of the rulemaking document you are commenting on, clearly set out at the beginning of your comments.

(b) Information, views, or arguments that follow the instructions for participation that appear in the rulemaking document on which you are commenting.

(c) All material that is relevant to any statement of fact in your comments.

(d) The document title and page number of any material that you reference in your comments.

#### § 106.70 Where and when to file comments.

(a) Unless you are told to do otherwise in the rulemaking document on which you are commenting, send your comments to us in either of the following ways:

(1) By mail to: Docket Management System, U.S. Department of Transportation, West Building Ground Floor, Room W12-140, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(2) Through the Internet at <http://www.regulations.gov>.

(b) Make sure that your comments reach us by the deadline set out in the rulemaking document on which you are commenting. We will consider late filed comments to the extent possible.

(c) We may reject comments that are not relevant to the rulemaking. We may reject comments you file electronically if you do not follow the elec-

## 49 CFR Ch. I (10-1-08 Edition)

tronic filing instructions at the DOT Web site.

[67 FR 42954, June 25, 2002, as amended at 69 FR 54044, Sept. 7, 2004; 72 FR 55682, Oct. 1, 2007]

#### § 106.75 Extension of time to file comments.

You may ask for more time to file comments on a rulemaking proceeding. If PHMSA grants your request, it is granted to all persons. We will notify the public of the extension by publishing a document in the FEDERAL REGISTER. If PHMSA denies your request, PHMSA will notify you of the denial. To ask for more time, you must do the following:

(a) File a request for extension at least ten days before the end of the comment period established in the rulemaking document.

(b) Show that you have good cause for the extension and that an extension is in the public interest.

(c) Include the docket number of the rulemaking document you are seeking additional time to comment on, clearly set out at the beginning of your request.

(d) Send your request to: Docket Management System, U.S. Department of Transportation, West Building Ground Floor, Room W12-140, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

[67 FR 42954, June 25, 2002, as amended at 72 FR 55682, Oct. 1, 2007]

### PUBLIC MEETINGS AND OTHER PROCEEDINGS

#### § 106.80 Public meeting procedures.

A public meeting is a non-adversarial, fact-finding proceeding conducted by a PHMSA representative. Generally, public meetings are announced in the FEDERAL REGISTER. Interested persons are invited to attend and to present their views to the agency on specific issues. There are no formal pleadings and no adverse parties, and any regulation issued afterward is not necessarily based exclusively on the record of the meeting. Sections 556 and 557 of the Administrative Procedure Act (5 U.S.C. 556 and 557) do not apply to public meetings under this part.

**§ 106.85 Requesting a public meeting.**

(a) You may ask for a public meeting by filing a written request with PHMSA no later than 20 days before the expiration of the comment period specified in the rulemaking document. Send your request for a public meeting to: Docket Management System, U.S. Department of Transportation, West Building Ground Floor, Room W12-140, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(b) PHMSA will review your request and, if you have shown good cause for a public meeting, we will grant it and publish a notice of the meeting in the FEDERAL REGISTER.

[67 FR 42954, June 25, 2002, as amended at 72 FR 55682, Oct. 1, 2007]

**§ 106.90 Other rulemaking proceedings.**

During a rulemaking proceeding, PHMSA may invite you to do the following:

- (a) Participate in a conference at which minutes are taken.
- (b) Make an oral presentation.
- (c) Participate in any other public proceeding to ensure that PHMSA makes informed decisions during the rulemaking process and to protect the public interest, including a negotiated rulemaking or work group led by a facilitator.

PETITIONS FOR RULEMAKING

**§ 106.95 Requesting a change to the regulations.**

You may ask PHMSA to add, amend, or delete a regulation by filing a petition for rulemaking as follows:

(a) For regulations in 49 CFR parts 110, 130, 171 through 180, submit the petition to: Office of Hazardous Materials Standards, Pipeline and Hazardous Materials Safety Administration, Attn: PHH-10, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(b) For regulations in 49 CFR parts 105, 106, or 107, submit the petition to: Office of the Chief Counsel, Pipeline and Hazardous Materials Safety Administration, Attn: PHC-10, U.S. Department of Transportation, East

Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

[70 FR 56089, Sept. 23, 2005, as amended at 72 FR 55683, Oct. 1, 2007]

**§ 106.100 Required information for a petition for rulemaking.**

(a) You must include the following information in your petition for rulemaking:

- (1) A summary of your proposed action and an explanation of its purpose.
- (2) The language you propose for a new or amended rule, or the language you would delete from a current rule.
- (3) An explanation of your interest in your proposed action and the interest of anyone you may represent.

(4) Information and arguments that support your proposed action, including relevant technical and scientific data available to you.

(5) Any specific cases that support or demonstrate the need for your proposed action.

(b) If the impact of your proposed action is substantial, and data or other information about that impact are available to you, we may ask that you provide information about the following:

(1) The costs and benefits of your proposed action to society in general, and identifiable groups within society in particular.

(2) The direct effects, including preemption effects under section 5125 of Federal hazardous materials transportation law, of your proposed action on States, on the relationship between the Federal government and the States, and on the distribution of power and responsibilities among the various levels of government. (See 49 CFR part 107, subpart C, regarding preemption.)

(3) The regulatory burden of your proposed action on small businesses, small organizations, small governmental jurisdictions, and Indian tribes.

(4) The recordkeeping and reporting burdens of your proposed action and whom they would affect.

(5) The effect of your proposed action on the quality of the natural and social environments.

## § 106.105

### § 106.105 PHMSA response to a petition for rulemaking.

We will review and respond to your petition for rulemaking as follows:

| If your petition is . . . | And if we determine that . . .                       | Then . . .                                                                     |
|---------------------------|------------------------------------------------------|--------------------------------------------------------------------------------|
| (a) Incomplete            | .....                                                | We may return your petition with a written explanation.                        |
| (b) Complete ..           | Your petition does not justify a rule-making action. | We will notify you in writing that we will not start a rule-making proceeding. |
| (c) Complete ..           | Your petition does justify a rule-making action.     | We will notify you in writing that we will start a rulemaking proceeding.      |

## APPEALS

### § 106.110 Appealing a PHMSA Action.

You may appeal the following PHMSA actions:

(a) PHMSA's issuance of a final rule or PHMSA's withdrawal of a notice of proposed rulemaking under the rule-making procedures in this part. However, you may appeal PHMSA's issuance of a direct final rule only if you previously filed comments to the direct final rule (see § 106.40(e)).

(b) Any PHMSA decision on a petition for rulemaking.

### § 106.115 Required information for an appeal.

(a) *Appeal of a final rule or withdrawal of a notice of proposed rulemaking.* If you appeal PHMSA's issuance of a final rule or PHMSA's withdrawal of a notice of proposed rulemaking, your appeal must include the following:

(1) The docket number of the rule-making you are concerned about, clearly set out at the beginning of your appeal.

(2) A brief statement of your concern about the final rule or the withdrawal of notice of proposed rulemaking at issue.

(3) An explanation of why compliance with the final rule is not practical, reasonable, or in the public interest.

(4) If you want PHMSA to consider more facts, the reason why you did not present those facts within the time given during the rulemaking process for public comment.

## 49 CFR Ch. I (10–1–08 Edition)

(b) *Appeal of a decision.* If you appeal PHMSA's decision on a petition for rulemaking, you must include the following:

(1) The contested aspects of the decision.

(2) Any new arguments or information.

### § 106.120 Appeal deadline.

(a) *Appeal of a final rule or withdrawal of a notice of proposed rulemaking.* If you appeal PHMSA's issuance of a final rule or PHMSA's withdrawal of a proposed rulemaking, your appeal document must reach us no later than 30 days after the date PHMSA published the regulation or the withdrawal notice in the FEDERAL REGISTER. After that time, PHMSA will consider your appeal to be a petition for rulemaking under § 106.100.

(b) *Appeal of a decision.* If you appeal PHMSA's decision on a petition for rulemaking, your appeal document must reach us no later than 30 days from the date PHMSA served you with written notice of PHMSA's decision.

[70 FR 56089, Sept. 23, 2005]

### § 106.125 Filing an appeal.

Send your appeal to: Docket Management System, U.S. Department of Transportation, West Building Ground Floor, Room W12–140, 1200 New Jersey Avenue, SE., Washington, DC 20590–0001.

[67 FR 42954, June 25, 2002, as amended at 72 FR 55682, Oct. 1, 2007]

### § 106.130 PHMSA response to an appeal.

Unless PHMSA provides otherwise, filing an appeal will not keep a final rule from becoming effective. We will handle an appeal according to the following procedures:

(a) *Appeal of a final rule or withdrawal of a notice of proposed rulemaking.* (1) We may consolidate your appeal with other appeals of the same rule.

(2) We may grant or deny your appeal, in whole or in part, without further rulemaking proceedings, unless granting your appeal would result in the issuance of a new final rule.

(3) If we decide to grant your appeal, we may schedule further proceedings and an opportunity to comment.

(4) PHMSA will notify you, in writing, of the action on your appeal within 90 days after the date that PHMSA published the final rule or withdrawal of notice of proposed rulemaking at issue in the FEDERAL REGISTER. If we do not issue a decision on your appeal within the 90-day period and we anticipate a substantial delay, we will notify you directly about the delay and will give you an expected decision date. We will also publish a notice of the delay in the FEDERAL REGISTER.

(b) *Appeal of a decision.* (1) We will not consider your appeal if it merely repeats arguments that PHMSA has previously rejected.

(2) PHMSA will notify you, in writing, of the action on your appeal within 90 days after the date that PHMSA served you with written notice of its decision on your petition for rulemaking. If we do not issue a decision on your appeal within the 90-day period, and we anticipate a substantial delay, we will notify you directly about the delay and will give you an expected decision date.

## PART 107—HAZARDOUS MATERIALS PROGRAM PROCEDURES

### Subpart A—Definitions

Sec.

107.1 Definitions.

### Subpart B—Special Permits

107.101 Purpose and scope.  
107.105 Application for special permit.  
107.107 Application for party status.  
107.109 Application for renewal.  
107.111 Withdrawal.  
107.113 Application processing and evaluation.  
107.117 Emergency processing.  
107.121 Modification, suspension or termination of special permit or grant of party status.  
107.123 Reconsideration.  
107.125 Appeal.  
107.127 Availability of documents for public inspection.

### Subpart C—Preemption

107.201 Purpose and scope.  
107.202 Standards for determining preemption.

### PREEMPTION DETERMINATIONS

107.203 Application.  
107.205 Notice.  
107.207 Processing.  
107.209 Determination.  
107.211 Petition for reconsideration.  
107.213 Judicial review.

### WAIVER OF PREEMPTION DETERMINATIONS

107.215 Application.  
107.217 Notice.  
107.219 Processing.  
107.221 Determination.  
107.223 Petition for reconsideration.  
107.227 Judicial review.

### Subpart D—Enforcement

107.301 Delegated authority for enforcement.  
107.303 Purpose and scope.  
107.305 Investigations.

### COMPLIANCE ORDERS AND CIVIL PENALTIES

107.307 General.  
107.309 Warning letters.  
107.310 Ticketing.  
107.311 Notice of probable violation.  
107.313 Reply.  
107.315 Admission of violations.  
107.317 Informal response.  
107.319 Request for a hearing.  
107.321 Hearing.  
107.323 ALJ's decision.  
107.325 Appeals.  
107.327 Compromise and settlement.  
107.329 Maximum penalties.  
107.331 Assessment considerations.

### CRIMINAL PENALTIES

107.333 Criminal penalties generally.  
107.335 Referral for prosecution.  
107.336 Limitation on fines and penalties.

### INJUNCTIVE ACTION

107.337 Injunctions generally.  
107.339 Imminent hazards.

### APPENDIX A TO SUBPART D OF PART 107—GUIDELINES FOR CIVIL PENALTIES

### Subpart E—Designation of Approval and Certification Agencies

107.401 Purpose and scope.  
107.402 Application for designation as an approval or certification agency.  
107.403 Designation of approval agencies.  
107.404 Conditions of designation.  
107.405 Termination of designation.

### Subpart F—Registration of Cargo Tank and Cargo Tank Motor Vehicle Manufacturers, Assemblers, Repairers, Inspectors, Testers, and Design Certifying Engineers

107.501 Scope.

## § 107.1

## 49 CFR Ch. I (10–1–08 Edition)

- 107.502 General registration requirements.
- 107.503 Registration statement.
- 107.504 Period of registration, updates, and record retention.

### Subpart G—Registration of Persons Who Offer or Transport Hazardous Materials

- 107.601 Applicability.
- 107.606 Exceptions.
- 107.608 General registration requirements.
- 107.612 Amount of fee.
- 107.616 Payment procedures.
- 107.620 Recordkeeping requirements.

### Subpart H—Approvals, Registrations and Submissions

- 107.701 Purpose and scope.
- 107.705 Registrations, reports, and applications for approval.
- 107.709 Processing of an application for approval, including an application for renewal or modification.
- 107.711 Withdrawal.
- 107.713 Approval modification, suspension or termination.
- 107.715 Reconsideration.
- 107.717 Appeal.

### Subpart I—Approval of Independent Inspection Agencies, Cylinder Requalifiers, and Non-domestic Chemical Analyses and Tests of DOT Specification Cylinders

- 107.801 Purpose and scope.
- 107.803 Approval of an independent inspection agency (IIA).
- 107.805 Approval of cylinder and pressure receptacle requalifiers.
- 107.807 Approval of non-domestic chemical analyses and tests.
- 107.809 Conditions of UN pressure receptacle approvals.

AUTHORITY: 49 U.S.C. 5101–5127, 44701; Pub. L. 101–410 section 4 (28 U.S.C. 2461 note); Pub. L. 104–121 sections 212–213; Pub. L. 104–134 section 31001; 49 CFR 1.45, 1.53.

EDITORIAL NOTE: Nomenclature changes to part 107 appear at 67 FR 61011, Sept. 27, 2002, 70 FR 56089, Sept. 23, 2005, and 70 FR 73159, Dec. 9, 2005.

### Subpart A—Definitions

#### § 107.1 Definitions.

All terms defined in 49 U.S.C. 5102 are used in their statutory meaning. Other terms used in this part are defined as follows:

*Acting knowingly* means acting or failing to act while

(1) Having actual knowledge of the facts giving rise to the violation, or

(2) Having the knowledge that a reasonable person acting in the same circumstances and exercising due care would have had.

*Administrator* means the Administrator, Pipeline and Hazardous Materials Safety Administration or his or her delegate.

*Applicant* means the person in whose name a special permit, approval, registration, a renewed or modified special permit or approval, or party status to a special permit is requested to be issued.

*Application* means a request under subpart B of this part for a special permit, a renewal or modification of a special permit, party status to a special permit, or a request under subpart H of this part for an approval, or renewal or modification of an approval.

*Approval* means written consent, including a competent authority approval, from the Associate Administrator or other designated Department official, to perform a function that requires prior consent under subchapter C of this chapter (49 CFR parts 171 through 180).

*Approval Agency* means an organization or a person designated by the PHMSA to certify packagings as having been designed, manufactured, tested, modified, marked or maintained in compliance with applicable DOT regulations.

*Associate Administrator* means the Associate Administrator for Hazardous Materials Safety, Pipeline and Hazardous Materials Safety Administration.

*Competent Authority* means a national agency that is responsible, under its national law, for the control or regulation of some aspect of hazardous materials (dangerous goods) transportation. Another term for Competent Authority is “Appropriate authority,” which is used in the International Civil Aviation Organization’s (ICAO) Technical Instructions for the Safe Transport of Dangerous Goods by Air. The Associate Administrator is the United States Competent Authority for purposes of this part 107.

*Competent Authority Approval* means an approval by the competent authority that is required under an international standard (for example, the

ICAO Technical Instructions for the Safe Transport of Dangerous Goods by Air and the International Maritime Dangerous Goods Code). Any of the following may be considered a competent authority approval if it satisfies the requirement of an international standard:

(1) A specific regulation in subchapter A or C of this chapter.

(2) A special permit or approval issued under subchapter A or C of this chapter.

(3) A separate document issued to one or more persons by the Associate Administrator.

*DOT or Department* means U.S. Department of Transportation.

*Federal hazardous material transportation law* means 49 U.S.C. 5101 *et seq.*

*Filed* means received by the appropriate PHMSA or other designated office within the time specified in a regulation or rulemaking document.

*Holder* means the person in whose name a special permit or approval has been issued.

*Imminent Hazard* means the existence of a condition which presents a substantial likelihood that death, serious illness, severe personal injury, or substantial endangerment to health, property, or the environment may occur before the reasonably foreseeable completion of an administrative hearing or other formal proceeding initiated to abate the risks of those effects.

*Incident* means an event resulting in the unintended and unanticipated release of a hazardous material or an event meeting incident reporting requirements in § 171.15 or § 171.16 of this chapter.

*Indian Tribe* has the same meaning given that term in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450b).

*Investigation* includes investigations authorized under 49 U.S.C. 5121 and inspections authorized under 49 U.S.C. 5118 and 5121.

*Manufacturing special permit* means a special permit from compliance with specified requirements that otherwise must be met before representing, marking, certifying (including requalifying, inspecting, and testing), selling or offering a packaging or container as meeting the requirements of sub-

chapter C of this chapter governing its use in the transportation in commerce of a hazardous material. A manufacturing special permit is a special permit issued to a manufacturer of packagings who does not offer for transportation or transport hazardous materials in packagings subject to the special permit.

*Party* means a person, other than a holder, authorized to act under the terms of a special permit.

*Person* means an individual, firm, co-partnership, corporation, company, association, or joint-stock association (including any trustee, receiver, assignee, or similar representative); or a government or Indian tribe (or an agency or instrumentality of any government or Indian tribe) that transports a hazardous material to further a commercial enterprise or offers a hazardous material for transportation in commerce. Person does not include the following:

(1) The United States Postal Service.

(2) Any agency or instrumentality of the Federal government, for the purposes of 49 U.S.C. 5123 (civil penalties) and 5124 (criminal penalties.)

(3) Any government or Indian tribe (or an agency or instrumentality of any government or Indian tribe) that transports hazardous material for a governmental purpose.

*Registration* means a written acknowledgment from the Associate Administrator that a registrant is authorized to perform a function for which registration is required under subchapter C of this chapter (e.g., registration in accordance with 49 CFR 178.503 regarding marking of packagings). For purposes of subparts A through E, "registration" does not include registration under subpart F or G of this part.

*Report* means information, other than an application, registration or part thereof, required to be submitted to the Associate Administrator pursuant to this subchapter, subchapter B or subchapter C of this chapter.

*Respondent* means a person upon whom the PHMSA has served a notice of probable violation.

*Special permit* means a document issued by the Associate Administrator under the authority of 49 U.S.C. 5117

permitting a person to perform a function that is not otherwise permitted under subchapter A or C of this chapter, or other regulations issued under 49 U.S.C. 5101 et seq. (e.g., Federal Motor Carrier Safety routing requirements). The terms “special permit” and “exemption” have the same meaning for purposes of subchapter A or C of this chapter or other regulations issued under 49 U.S.C. 5101 through 5127. An exemption issued prior to October 1, 2005 remains valid until it is past its expiration date, terminated by the Associate Administrator, or is issued as a special permit, whichever occurs first.

*State* means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, the Virgin Islands, American Samoa, Guam, or any other territory or possession of the United States designated by the Secretary.

*Transports or transportation* means the movement of property and loading, unloading, or storage incidental to the movement.

[Amdt. 107–3, 41 FR 38170, Sept. 9, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 107.1, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

## Subpart B—Special Permits

SOURCE: Amdt. 107–38, 61 FR 21095, May 9, 1996, unless otherwise noted.

### § 107.101 Purpose and scope.

This subpart prescribes procedures for the issuance, modification and termination of special permits from requirements of this subchapter, subchapter C of this chapter, or regulations issued under chapter 51 of 49 U.S.C.

### § 107.105 Application for special permit.

(a) *General.* Each application for a special permit or modification of a special permit must be written in English and must—

(1) Be submitted for timely consideration, at least 120 days before the requested effective date, in duplicate to:

Associate Administrator for Hazardous Materials Safety (Attention: Special Permits, PHH–31), Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590–0001. Alternatively, the application with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to: (202) 366–3753 or (202) 366–3308 or by electronic mail (e-mail) to: [Specialpermits@dot.gov](mailto:Specialpermits@dot.gov);

(2) State the name, street and mailing addresses, e-mail address optional, and telephone number of the applicant; if the applicant is not an individual, state the name, street and mailing addresses, e-mail address optional, and telephone number of an individual designated as an agent of the applicant for all purposes related to the application;

(3) If the applicant is not a resident of the United States, a designation of agent for service in accordance with § 105.40 of this part; and

(4) For a manufacturing special permit, a statement of the name and street address of each facility where manufacturing under the special permit will occur.

(b) *Confidential treatment.* To request confidential treatment for information contained in the application, the applicant shall comply with § 105.30(a).

(c) *Description of special permit proposal.* The application must include the following information that is relevant to the special permit proposal:

(1) A citation of the specific regulation from which the applicant seeks relief;

(2) Specification of the proposed mode or modes of transportation;

(3) A detailed description of the proposed special permit (e.g., alternative packaging, test, procedure or activity) including, as appropriate, written descriptions, drawings, flow charts, plans and other supporting documents;

(4) A specification of the proposed duration or schedule of events for which the special permit is sought;

(5) A statement outlining the applicant’s basis for seeking relief from compliance with the specified regulations and, if the special permit is requested for a fixed period, a description

of how compliance will be achieved at the end of that period;

(6) If the applicant seeks emergency processing specified in § 107.117, a statement of supporting facts and reasons;

(7) Identification and description of the hazardous materials planned for transportation under the special permit;

(8) Description of each packaging, including specification or special permit number, as applicable, to be used in conjunction with the requested special permit;

(9) For alternative packagings, documentation of quality assurance controls, package design, manufacture, performance test criteria, in-service performance and service-life limitations.

(10) When a Class 1 material is forbidden for transportation by aircraft except under a special permit (see Columns 9A and 9B in the table in 49 CFR 172.101), an applicant for a special permit to transport such Class 1 material on passenger-carrying or cargo-only aircraft with a maximum certificated takeoff weight of less than 12,500 pounds must certify that no person within the categories listed in 18 U.S.C. 842(i) will participate in the transportation of the Class 1 material.

(d) *Justification of special permit proposal.* The application must demonstrate that a special permit achieves a level of safety at least equal to that required by regulation, or if a required safety level does not exist, is consistent with the public interest. At a minimum, the application must provide the following:

(1) Information describing all relevant shipping and incident experience of which the applicant is aware that relates to the application;

(2) A statement identifying any increased risk to safety or property that may result if the special permit is granted, and a description of the measures to be taken to address that risk; and

(3) Either:

(i) Substantiation, with applicable analyses, data or test results, that the proposed alternative will achieve a level of safety that is at least equal to that required by the regulation from which the special permit is sought; or

(ii) If the regulations do not establish a level of safety, an analysis that identifies each hazard, potential failure mode and the probability of its occurrence, and how the risks associated with each hazard and failure mode are controlled for the duration of an activity or life-cycle of a packaging.

[Amdt. 107-38, 61 FR 21095, May 9, 1996, as amended at 62 FR 51556, Oct. 1, 1997; 65 FR 50457, Aug. 18, 2000; 65 FR 58618, Sept. 29, 2000; 67 FR 61010, 61011, Sept. 27, 2002; 68 FR 23841, May 5, 2003; 69 FR 6198, Feb. 10, 2004; 70 FR 56089, Sept. 23, 2005; 70 FR 73160, Dec. 9, 2005; 71 FR 54390, Sept. 14, 2006; 72 FR 55683, Oct. 1, 2007]

#### § 107.107 Application for party status.

(a) Any person eligible to apply for a special permit may apply to be made party to an application or an existing special permit, other than a manufacturing special permit.

(b) Each application filed under this section must—

(1) Be submitted in duplicate to: Associate Administrator for Hazardous Materials Safety (Attention: Special Permits, PHH-31), Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001. Alternatively, the application with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to: (202) 366-3753 or (202) 366-3308 or by electronic mail (e-mail) to: [Specialpermits@dot.gov](mailto:Specialpermits@dot.gov);

(2) Identify by number the special permit application or special permit to which the applicant seeks to become a party;

(3) State the name, street and mailing addresses, e-mail address (optional), and telephone number of the applicant; if the applicant is not an individual, state the name, street and mailing addresses, e-mail address (optional), and telephone number of an individual designated as the applicant's agent for all purposes related to the application;

(4) If the applicant is not a resident of the United States, provide a designation of agent for service in accordance with § 105.40 of this subchapter; and



## § 107.109

## 49 CFR Ch. I (10–1–08 Edition)

(5) For a Class 1 material that is forbidden for transportation by aircraft except under a special permit (see Columns 9A and 9B in the table in 49 CFR 172.101), an applicant for party status to a special permit to transport such Class 1 material on passenger-carrying or cargo-only aircraft with a maximum certificated takeoff weight of less than 12,500 pounds must certify that no person within the categories listed in 18 U.S.C. 842(i) will participate in the transportation of the Class 1 material.

(c) The Associate Administrator grants or denies an application for party status in the manner specified in § 107.113(e) and (f) of this subpart.

(d) A party to a special permit is subject to all terms of that special permit, including the expiration date. If a party to a special permit wishes to renew party status, the special permit renewal procedures set forth in § 107.109 apply.

[Amdt. 107–38, 61 FR 21095, May 9, 1996, as amended at 65 FR 50457, Aug. 18, 2000; 67 FR 61010, 61011, Sept. 27, 2002; 69 FR 6198, Feb. 10, 2004; 70 FR 56090, Sept. 23, 2005; 70 FR 73160, Dec. 9, 2005; 72 FR 55683, Oct. 1, 2007]

### § 107.109 Application for renewal.

(a) Each application for renewal of an exemption or special permit or party status to an exemption or special permit must:

(1) Be submitted in duplicate to: Associate Administrator for Hazardous Materials Safety (Attention: Special Permits, PHH–31), Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590–0001. Alternatively, the application with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to: (202) 366–3753 or (202) 366–3308 or by electronic mail (e-mail) to: [Specialpermits@dot.gov](mailto:Specialpermits@dot.gov);

(2) Identify by number the exemption or special permit for which renewal is requested;

(3) State the name, street and mailing addresses, e-mail address optional, and telephone number of the applicant; if the applicant is not an individual, state the name, street and mailing addresses, e-mail address optional, and

telephone number of an individual designated as an agent of the applicant for all purposes related to the application;

(4) Include either a certification by the applicant that the original application, as it may have been updated by any application for renewal, remains accurate and complete; or include an amendment to the previously submitted application as is necessary to update and assure the accuracy and completeness of the application, with certification by the applicant that the application as amended is accurate and complete; and

(5) Include a statement describing all relevant shipping and incident experience of which the applicant is aware in connection with the exemption or special permit since its issuance or most recent renewal. If the applicant is aware of no incidents, the applicant shall so certify. When known to the applicant, the statement should indicate the approximate number of shipments made or packages shipped, as the case may be, and number of shipments or packages involved in any loss of contents, including loss by venting other than as authorized in subchapter C.

(6) When a Class 1 material is forbidden for transportation by aircraft, except under an exemption or special permit (see Columns 9A and 9B in the table in 49 CFR 172.101), an application to renew an exemption or special permit to transport such Class 1 material on passenger-carrying or cargo-only aircraft with a maximum certificated takeoff weight of less than 12,500 pounds must certify that no person within the categories listed in 18 U.S.C. 842(i) will participate in the transportation of the Class 1 material.

(b) If at least 60 days before an existing exemption or special permit expires the holder files an application for renewal that is complete and conforms to the requirements of this section, the exemption will not expire until final administrative action on the application for renewal has been taken.

[70 FR 73160, Dec. 9, 2005, as amended at 72 FR 55683, Oct. 1, 2007]

### § 107.111 Withdrawal.

An application may be withdrawn at any time before a decision to grant or

deny it is made. Withdrawal of an application does not authorize the removal of any related records from the PHMSA dockets or files. Applications that are eligible for confidential treatment under § 105.30 will remain confidential after the application is withdrawn. The duration of this confidential treatment for trade secrets and commercial or financial information is indefinite, unless the party requesting the confidential treatment of the materials notifies the Associate Administrator that the confidential treatment is no longer required.

**§ 107.113 Application processing and evaluation.**

(a) The Associate Administrator reviews an application for special permit, modification of special permit, party to special permit, or renewal of an exemption or special permit to determine if it is complete and conforms with the requirements of this subpart. This determination will be made within 30 days of receipt of the application for special permit, modification of special permit, or party to special permit, and within 15 days of receipt of an application for renewal of an exemption or special permit. If an application is determined to be incomplete, the applicant is informed of the reasons.

(b) An application, that is not a renewal, party to, or emergency special permit application, and is determined to be complete is docketed. Notice of the application is published in the FEDERAL REGISTER, and an opportunity for public comment is provided. All comments received during the comment period are considered before final action is taken on the application.

(c) No public hearing or other formal proceeding is required under this subpart before the disposition of an application. Unless emergency processing under § 107.117 is requested and granted, applications are usually processed in the order in which they are filed.

(d) During the processing and evaluation of an application, the Associate Administrator may request additional information from the applicant. If the applicant does not respond to a written request for additional information within 30 days of the date the request was received, the application may be

deemed incomplete and denied. However, if the applicant responds in writing within the 30-day period requesting an additional 30 days within which it will gather the requested information, the Associate Administrator may grant the 30-day extension.

(e) The Associate Administrator may grant or deny an application, in whole or in part. In the Associate Administrator's discretion, an application may be granted subject to provisions that are appropriate to protect health, safety or property. The Associate Administrator may impose additional provisions not specified in the application or remove conditions in the application that are unnecessary.

(f) The Associate Administrator may grant an application on finding that—

(1) The application complies with this subpart;

(2) The application demonstrates that the proposed alternative will achieve a level of safety that:

(i) Is at least equal to that required by the regulation from which the special permit is sought, or

(ii) If the regulations do not establish a level of safety, is consistent with the public interest and adequately will protect against the risks to life and property inherent in the transportation of hazardous materials in commerce;

(3) The application states all material facts, and contains no materially false or materially misleading statement;

(4) The applicant meets the qualifications required by applicable regulations; and

(5) The applicant is fit to conduct the activity authorized by the exemption or special permit. This assessment may be based on information in the application, prior compliance history of the applicant, and other information available to the Associate Administrator.

(g) An applicant is notified in writing whether the application is granted or denied. A denial contains a brief statement of reasons.

(h) The initial exemption or special permit terminates according to its terms or, if not otherwise specified, 24 months from the date of issuance. A subsequent renewal of a special permit terminates according to its terms or, if not otherwise specified, 48 months

## § 107.117

## 49 CFR Ch. I (10–1–08 Edition)

after the date of issuance. A grant of party status to an exemption or special permit, unless otherwise stated, terminates on the date that the exemption or special permit expires.

(i) The Associate Administrator, on determining that an application concerns a matter of general applicability and future effect and should be the subject of rulemaking, may initiate rulemaking under part 106 of this chapter in addition to or instead of acting on the application.

(j) The Associate Administrator publishes in the FEDERAL REGISTER a list of all special permit grants, denials, and modifications and all special permit applications withdrawn under this section.

[Amdt. 107–38, 61 FR 21095, May 9, 1996, as amended at 67 FR 61011, Sept. 27, 2002; 70 FR 73161, Dec. 9, 2005]

### § 107.117 Emergency processing.

(a) An application is granted emergency processing if the Associate Administrator, on the basis of the application and any inquiry undertaken, finds that—

(1) Emergency processing is necessary to prevent significant injury to persons or property (other than the hazardous material to be transported) that could not be prevented if the application were processed on a routine basis; or

(2) Emergency processing is necessary for immediate national security purposes or to prevent significant economic loss that could not be prevented if the application were processed on a routine basis.

(b) Where the significant economic loss is to the applicant, or to a party in a contractual relationship to the applicant with respect to the activity to be undertaken, the Associate Administrator may deny emergency processing if timely application could have been made.

(c) A request for emergency processing on the basis of potential economic loss must reasonably describe and estimate the potential loss.

(d) An application submitted under this section must conform to § 107.105 to the extent that the receiving Department official deems necessary to process the application. An application

on an emergency basis must be submitted to the Department modal contact official for the initial mode of transportation to be utilized, as follows:

(1) *Certificate-Holding Aircraft*: The Federal Aviation Administration Civil Aviation Security Office that serves the place where the flight will originate or that is responsible for the aircraft operator's overall aviation security program. The nearest Civil Aviation Security Office may be located by calling the FAA Duty Officer, 202–267–3333 (any hour).

(2) *Noncertificate-Holding Aircraft (Those Which Operate Under 14 CFR Part 91)*: The Federal Aviation Administration Civil Aviation Security Office that serves the place where the flight will originate. The nearest Civil Aviation Security Office may be located by calling the FAA Duty Officer, 202–267–3333 (any hour).

(3) *Motor Vehicle Transportation*: Chief, Hazardous Materials Division, Federal Motor Carrier Safety Administration, U.S. Department of Transportation, Washington, DC 20590–0001, 202–366–6121 (day); 1–800–424–8802 (night).

(4) *Rail Transportation*: Staff Director, Hazardous Materials Division, Office of Safety Assurance and Compliance, Federal Railroad Administration, U.S. Department of Transportation, Washington, DC 20590–0001, 202–493–6248 or 202–493–6244 (day); 1–800–424–8802 (night).

(5) *Water Transportation*: Chief, Hazardous Materials Standards Division, Office of Operating and Environmental Standards, U.S. Coast Guard, U.S. Department of Homeland Security, Washington, DC 20593–0001; (202) 267–1217 (day); 1–800–424–8802 (night).

(e) On receipt of all information necessary to process the application, the receiving Department official transmits to the Associate Administrator, by the most rapid available means of communication, an evaluation as to whether an emergency exists under § 107.117(a) and, if appropriate, recommendations as to the conditions to be included in the special permit. If the Associate Administrator determines that an emergency exists under § 107.117(a) and that, with reference to the criteria of § 107.113(f), granting of

the application is in the public interest, the Associate Administrator grants the application subject to such terms as necessary and immediately notifies the applicant. If the Associate Administrator determines that an emergency does not exist or that granting of the application is not in the public interest, the applicant immediately is so notified.

(f) A determination that an emergency does not exist is not subject to reconsideration under § 107.123 of this part.

(g) Within 90 days following issuance of an emergency special permit, the Associate Administrator will publish, in the FEDERAL REGISTER, a notice of issuance with a statement of the basis for the finding of emergency and the scope and duration of the special permit.

[Amdt. 107-38, 61 FR 21095, May 9, 1996, as amended at 62 FR 51556, Oct. 1, 1997; 64 FR 51914, Sept. 27, 1999; 65 FR 58618, Sept. 29, 2000; 66 FR 45377, Aug. 28, 2001; 67 FR 61011, Sept. 27, 2002; 70 FR 56090, Sept. 23, 2005]

**§ 107.121 Modification, suspension or termination of special permit or grant of party status.**

(a) The Associate Administrator may modify an exemption, a special permit, or grant of party status on finding that:

(1) Modification is necessary so that the exemption or special permit reflects current statutes and regulations; or

(2) Modification is required by changed circumstances to meet the standards of § 107.113(f).

(b) The Associate Administrator may modify, suspend or terminate an exemption or special permit or grant of party status, as appropriate, on finding that:

(1) Because of a change in circumstances, the exemption, special permit, or party status no longer is needed or no longer would be granted if applied for;

(2) The application contained inaccurate or incomplete information, and the exemption, special permit, or party status would not have been granted had the application been accurate and complete;

(3) The application contained deliberately inaccurate or incomplete information; or

(4) The holder or party knowingly has violated the terms of the exemption, special permit or an applicable requirement of this chapter, in a manner demonstrating the holder or party is not fit to conduct the activity authorized by the exemption or special permit.

(c) Except as provided in paragraph (d) of this section, before an exemption, special permit, or grant of party status is modified, suspended or terminated, the Associate Administrator notifies the holder or party in writing of the proposed action and the reasons for it, and provides an opportunity to show cause why the proposed action should not be taken.

(1) The holder or party may file a written response that shows cause why the proposed action should not be taken within 30 days of receipt of notice of the proposed action.

(2) After considering the holder's or party's written response, or after 30 days have passed without response since receipt of the notice, the Associate Administrator notifies the holder or party in writing of the final decision with a brief statement of reasons.

(d) The Associate Administrator, if necessary to avoid a risk of significant harm to persons or property, may in the notification declare the proposed action immediately effective.

[Amdt. 107-38, 61 FR 21095, May 9, 1996, as amended at 70 FR 73161, Dec. 9, 2005]

**§ 107.123 Reconsideration.**

(a) An applicant for special permit, a special permit holder, or an applicant for party status to an exemption or special permit may request that the Associate Administrator reconsider a decision under § 107.113(g), § 107.117(e) or § 107.121(c) of this part. The request must—

(1) Be in writing and filed within 20 days of receipt of the decision;

(2) State in detail any alleged errors of fact and law;

(3) Enclose any additional information needed to support the request to reconsider; and

(4) State in detail the modification of the final decision sought.

## § 107.125

(b) The Associate Administrator grants or denies, in whole or in part, the relief requested and informs the requesting person in writing of the decision. If necessary to avoid a risk of significant harm to persons or property, the Associate Administrator may, in the notification, declare the action immediately effective.

[Amdt. 107-38, 61 FR 21095, May 9, 1996, as amended at 70 FR 73161, Dec. 9, 2005]

### § 107.125 Appeal.

(a) A person who requested reconsideration under § 107.123 and is denied the relief requested may appeal to the Administrator. The appeal must—

(1) Be in writing and filed within 30 days of receipt of the Associate Administrator's decision on reconsideration;

(2) State in detail any alleged errors of fact and law;

(3) Enclose any additional information needed to support the appeal; and

(4) State in detail the modification of the final decision sought.

(b) The Administrator, if necessary to avoid a risk of significant harm to persons or property, may declare the Associate Administrator's action effective pending a decision on appeal.

(c) The Administrator grants or denies, in whole or in part, the relief requested and informs the appellant in writing of the decision. The Administrator's decision is the final administrative action.

### § 107.127 Availability of documents for public inspection.

(a) Documents related to an application under this subpart, including the application itself, are available for public inspection, except as specified in paragraph (b) of this section, at the Office of the Associate Administrator for Hazardous Materials Safety, Pipeline and Hazardous Materials Safety Administration, Office of Hazardous Materials Special Permits and Approvals, U.S. Department of Transportation, East Building, PHH-30, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001. Office hours are 8:30 a.m. to 5 p.m., Monday through Friday, except Federal holidays when the office is closed. Copies of available documents may be obtained as provided in part 7 of this title. Documents numbered

## 49 CFR Ch. I (10-1-08 Edition)

11832 and above may also be viewed at the website address <http://www.regulations.gov>.

(b) Documents available for inspection do not include materials determined to be withheld from public disclosure under § 105.30 and in accordance with the applicable provisions of section 552(b) of title 5, United States Code, and part 7 of this title.

[Amdt. 107-38, 61 FR 21095, May 9, 1996, as amended at 65 FR 58618, Sept. 29, 2000; 66 FR 45377, Aug. 28, 2001; 67 FR 61011, Sept. 27, 2002; 70 FR 73162, Dec. 9, 2005; 72 FR 55683, Oct. 1, 2007]

## Subpart C—Preemption

### § 107.201 Purpose and scope.

(a) This subpart prescribes procedures by which:

(1) Any person, including a State, political subdivision, or Indian tribe, directly affected by a requirement of a State, political subdivision, or Indian tribe, may apply for a determination as to whether that requirement is preempted under 49 U.S.C. 5125.

(2) A State, political subdivision, or Indian tribe may apply for a waiver of preemption with respect to any requirement that the State, political subdivision, or Indian tribe acknowledges to be preempted by 49 U.S.C. 5125, or that has been determined by a court of competent jurisdiction to be so preempted.

(b) For purposes of this subpart “political subdivision” includes a municipality; a public agency or other instrumentality of one or more States, municipalities, or other political subdivisions of a State; or a public corporation, board, or commission established under the laws of one or more States.

(c) [Reserved]

(d) An application for a preemption determination that includes an application for a waiver of preemption will be treated and processed solely as an application for a preemption determination.

[Amdt. 107-3, 41 FR 38171, Sept. 9, 1976, as amended by Amdt. 107-24, 56 FR 8622, Feb. 28, 1991; Amdt. 107-25, 57 FR 20428, May 13, 1992; Amdt. 107-32, 59 FR 49130, Sept. 26, 1994; Amdt. 107-35, 60 FR 49108, Sept. 21, 1995; Amdt. 107-38, 61 FR 21098, May 9, 1996; 68 FR 52846, Sept. 8, 2003; 71 FR 30067, May 25, 2006]

**§ 107.202 Standards for determining preemption.**

(a) Except as provided in § 107.221 and unless otherwise authorized by Federal law, any requirement of a State or political subdivision thereof or an Indian tribe that concerns one of the following subjects and that is not substantively the same as any provision of the Federal hazardous materials transportation law, a regulation issued under the Federal hazardous material transportation law, or a hazardous material transportation security regulation or directive issued by the Secretary of Homeland Security that concerns that subject, is preempted:

(1) The designation, description, and classification of hazardous material.

(2) The packing, repacking, handling, labeling, marking, and placarding of hazardous material.

(3) The preparation, execution, and use of shipping documents pertaining to hazardous material and requirements related to the number, content, and placement of those documents.

(4) The written notification, recording, and reporting of the unintentional release in transportation of hazardous material.

(5) The design, manufacturing, fabrication, marking, maintenance, reconditioning, repairing, or testing of a packaging or a container which is represented, marked, certified, or sold as qualified for use in the transportation of hazardous material.

(b) Except as provided in § 107.221 and unless otherwise authorized by Federal law, any requirement of a State or political subdivision or Indian tribe is preempted if—

(1) It is not possible to comply with a requirement of the State, political subdivision, or Indian tribe and a requirement under the Federal hazardous material transportation law, a regulation issued under the Federal hazardous material transportation law, or a hazardous material transportation security regulation or directive issued by the Secretary of Homeland Security;

(2) The requirement of the State, political subdivision, or Indian tribe, as applied or enforced, is an obstacle to accomplishing and carrying out the Federal hazardous material transportation law, a regulation issued under

the Federal hazardous material transportation law, or a hazardous material transportation security regulation or directive issued by the Secretary of Homeland Security.

(3) It is preempted under 49 U.S.C. 5125 (c).

(c) A State, political subdivision, or Indian tribe may impose a fee related to transporting hazardous material only if the fee is fair and used for a purpose related to transporting hazardous material, including enforcement and planning, developing and maintaining a capability for emergency response.

(d) For purposes of this section, “substantively the same” means that the non-Federal requirement conforms in every significant respect to the Federal requirement. Editorial and other similar *de minimis* changes are permitted.

[Amdt. 107–24, 56 FR 8622, Feb. 28, 1991, as amended by Amdt. 107–25, 57 FR 20428, May 13, 1992; Amdt. 107–29, 58 FR 51527, Oct. 1, 1993; Amdt. 107–32, 59 FR 49130, Sept. 26, 1994; Amdt. 107–38, 61 FR 21098, May 9, 1996; Amdt. 107–39, 61 FR 51337, Oct. 1, 1996; 68 FR 52847, Sept. 8, 2003]

**PREEMPTION DETERMINATIONS****§ 107.203 Application.**

(a) With the exception of highway routing matters covered under 49 U.S.C. 5125(c), any person, including a State or political subdivision thereof or an Indian tribe, directly affected by any requirement of a State or political subdivision thereof or an Indian tribe, may apply to the Chief Counsel for a determination as to whether that requirement is preempted by § 107.202(a), (b), or (c).

(b) Each application filed under this section for a determination must:

(1) Be submitted to the Chief Counsel:

(i) By mail addressed to the Chief Counsel, Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, PHC–1, 1200 New Jersey Avenue, SE., Washington, DC 20590–0001;

(ii) By facsimile to 202–366–7041; or

(iii) Electronically to the Chief Counsel at [phmsachiefcounsel@dot.gov](mailto:phmsachiefcounsel@dot.gov).

## § 107.205

(2) Set forth the text of the State or political subdivision or Indian tribe requirement for which the determination is sought;

(3) Specify each requirement of the Federal hazardous materials transportation law, regulations issued under the Federal hazardous material transportation law, or hazardous material transportation security regulations or directives issued by the Secretary of Homeland Security with which the applicant seeks the State or political subdivision or Indian tribe requirement to be compared;

(4) Explain why the applicant believes the State or political subdivision or Indian tribe requirement should or should not be preempted under the standards of § 107.202; and

(5) State how the applicant is affected by the State or political subdivision or Indian tribe requirement.

(c) The filing of an application for a determination under this section does not constitute grounds for noncompliance with any requirement of the Federal hazardous materials transportation law, regulations issued under the Federal hazardous material transportation law, or hazardous material transportation security regulations or directives issued by the Secretary of Homeland Security.

(d) Once the Chief Counsel has published notice in the FEDERAL REGISTER of an application received under paragraph (a) of this section, no applicant for such determination may seek relief with respect to the same or substantially the same issue in any court until final action has been taken on the application or until 180 days after filing of the application, whichever occurs first. Nothing in § 107.203(a) prohibits a State or political subdivision thereof or Indian tribe, or any other person directly affected by any requirement of a State or political subdivision thereof or Indian tribe, from seeking a determination of preemption in any court of competent jurisdiction in lieu of apply-

## 49 CFR Ch. I (10–1–08 Edition)

ing to the Chief Counsel under paragraph (a) of this section.

[Amdt. 107–24, 56 FR 8622, Feb. 28, 1991, as amended by Amdt. 107–25, 57 FR 20428, May 13, 1992; Amdt. 107–32, 59 FR 49131, Sept. 26, 1994; Amdt. 107–38, 61 FR 21098, May 9, 1996; 68 FR 52847, Sept. 8, 2003; 71 FR 30067, May 25, 2006; 72 FR 55683, Oct. 1, 2007]

### § 107.205 Notice.

(a) If the applicant is other than a State, political subdivision, or Indian tribe, the applicant shall mail a copy of the application to the State, political subdivision, or Indian tribe concerned accompanied by a statement that the State, political subdivision, or Indian tribe may submit comments regarding the application to the Chief Counsel. The application filed with the Chief Counsel must include a certification that the applicant has complied with this paragraph and must include the names and addresses of each State, political subdivision, or Indian tribe official to whom a copy of the application was sent.

(b) The Chief Counsel will publish notice of, including an opportunity to comment on, an application in the FEDERAL REGISTER and may notify in writing any person readily identifiable as affected by the outcome of the determination.

(c) Each person submitting written comments to the Chief Counsel with respect to an application filed under this section must send a copy of the comments to the applicant and certify to the Chief Counsel that he or she has complied with this requirement. The Chief Counsel may notify other persons participating in the proceeding of the comments and provide an opportunity for those other persons to respond. Late-filed comments are considered so far as practicable.

[Amdt. 107–38, 61 FR 21098, May 9, 1996, as amended at 71 FR 30067, May 25, 2006]

### § 107.207 Processing.

(a) The Chief Counsel may initiate an investigation of any statement in an application and utilize in his or her evaluation any relevant facts obtained by that investigation. The Chief Counsel may solicit and accept submissions from third persons relevant to an application and will provide the applicant

an opportunity to respond to all third person submissions. In evaluating an application, the Chief Counsel may consider any other source of information. The Chief Counsel on his or her own initiative may convene a hearing or conference, if he or she considers that a hearing or conference will advance his or her evaluation of the application.

(b) The Chief Counsel may dismiss the application without prejudice if:

(1) He or she determines that there is insufficient information upon which to base a determination; or

(2) He or she requests additional information from the applicant and it is not submitted.

[Amdt. 107-3, 41 FR 38171, Sept. 9, 1976, as amended by Amdt. 107-24, 56 FR 8621, 8622, Feb. 28, 1991; Amdt. 107-38, 61 FR 21098, May 9, 1996; 71 FR 30067, May 25, 2006]

#### § 107.209 Determination.

(a) Upon consideration of the application and other relevant information received, the Chief Counsel issues a determination.

(b) The determination includes a written statement setting forth the relevant facts and the legal basis for the determination, and provides that any person aggrieved thereby may file a petition for reconsideration with the Chief Counsel.

(c) The Chief Counsel provides a copy of the determination to the applicant and to any other person who substantially participated in the proceeding or requested in comments to the docket to be notified of the determination. A copy of each determination is placed on file in the public docket. The Chief Counsel will publish the determination or notice of the determination in the FEDERAL REGISTER, at which time the determination becomes a final agency action.

(d) A determination issued under this section constitutes an administrative determination as to whether a particular requirement of a State or political subdivision or Indian tribe is preempted under the Federal hazardous materials transportation law. The fact that a determination has not been issued under this section with respect to a particular requirement of a State or political subdivision or Indian tribe

carries no implication as to whether the requirement is preempted under the Federal hazardous materials transportation law.

[Amdt. 107-24, 56 FR 8623, Feb. 28, 1991, as amended by Amdt. 107-25, 57 FR 20428, May 13, 1992; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; Amdt. 107-38, 61 FR 21098, May 9, 1996; 68 FR 52847, Sept. 8, 2003; 71 FR 30067, May 25, 2006]

#### § 107.211 Petition for reconsideration.

(a) Any person aggrieved by a determination issued under § 107.209 may file a petition for reconsideration. The petition must be filed with the Chief Counsel, in the same manner specified for filing an application in § 107.203(b), within 20 days of publication of the determination in the FEDERAL REGISTER.

(b) The petition must contain a concise statement of the basis for seeking review, including any specific factual or legal error alleged. If the petition requests consideration of information that was not previously made available to the Chief Counsel, the petition must include the reasons why such information was not previously made available.

(c) The petitioner shall mail a copy of the petition to each person who participated, either as an applicant or commenter, in the preemption determination proceeding, accompanied by a statement that the person may submit comments concerning the petition to the Chief Counsel within 20 days. The petition filed with the Chief Counsel must contain a certification that the petitioner has complied with this paragraph and include the names and addresses of all persons to whom a copy of the petition was sent. Late-filed comments are considered so far as practicable.

(d) The Chief Counsel will publish the decision on the petition for reconsideration or notice of the decision in the FEDERAL REGISTER, at which time the decision on the petition for reconsideration becomes a final agency action.

[Amdt. 107-25, 57 FR 20428, May 13, 1992, as amended by Amdt. 107-38, 61 FR 21099, May 9, 1996; 71 FR 30067, May 25, 2006]



## § 107.213

## 49 CFR Ch. I (10–1–08 Edition)

### § 107.213 Judicial review.

A party to a proceeding under § 107.203(a) may seek review of a determination of the Chief Counsel by filing a petition, within 60 days after the determination becomes final, in the United States Court of Appeals for the District of Columbia or in the Court of Appeals for the United States for the circuit in which the person resides or has its principal place of business.

[71 FR 30068, May 25, 2006]

#### WAIVER OF PREEMPTION DETERMINATIONS

### § 107.215 Application.

(a) With the exception of requirements preempted under 49 U.S.C. 5125(c), a State or political subdivision thereof, or Indian tribe may apply to the Chief Counsel for a waiver of preemption with respect to any requirement that the State or political subdivision thereof or Indian tribe acknowledges to be preempted under the Federal hazardous materials transportation law, or that has been determined by a court of competent jurisdiction to be so preempted. The Chief Counsel may waive preemption with respect to such requirement upon a determination that such requirement—

(1) Affords an equal or greater level of protection to the public than is afforded by the requirements of the Federal hazardous material transportation law or the regulations issued thereunder, and

(2) Does not unreasonably burden commerce.

(b) Each application filed under this section for a waiver of preemption determination must:

(1) Be submitted to the Chief Counsel:

(i) By mail addressed to the Chief Counsel, Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, PHC–1, 1200 New Jersey Avenue, SE., Washington, DC 20590–0001;

(ii) By facsimile to 202–366–7041; or

(iii) Electronically to the Chief Counsel at [phmsachiefcounsel@dot.gov](mailto:phmsachiefcounsel@dot.gov).

(2) Set forth the text of the State or political subdivision requirement for

which the determination is being sought;

(3) Include a copy of any court order and any ruling issued under § 107.209 having a bearing on the application;

(4) Contain an express acknowledgment by the applicant that the State, political subdivision, or Indian tribe requirement is preempted under Federal hazardous materials transportation law, unless it has been so determined by a court of competent jurisdiction or in a determination issued under § 107.209;

(5) Specify each requirement of the Federal hazardous materials transportation law that preempts the State, political subdivision, or Indian tribe requirement;

(6) State why the applicant believes the State, political subdivision or Indian tribe requirements affords an equal or greater level of protection to the public than is afforded by the requirements of the Federal hazardous material transportation law or the regulations issued thereunder;

(7) State why the applicant believes the State, political subdivision or Indian tribe requirement does not unreasonably burden commerce; and

(8) Specify what steps the State, political subdivision or Indian tribe is taking to administer and enforce effectively its inconsistent requirement.

[Amdt. 107–3, 41 FR 38171, Sept. 9, 1976, as amended by Amdt. 107–22, 55 FR 39978, Oct. 1, 1990; Amdt. 107–24, 56 FR 8621, 8623, Feb. 28, 1991; 56 FR 15510, Apr. 17, 1991; Amdt. 107–23, 56 FR 66156, Dec. 20, 1991; Amdt. 107–25, 57 FR 20428, May 13, 1992; Amdt. 107–32, 59 FR 49131, Sept. 26, 1994; Amdt. 107–38, 61 FR 21099, May 9, 1996; 68 FR 52847, Sept. 8, 2003; 71 FR 30068, May 25, 2006; 72 FR 55683, Oct. 1, 2007]

### § 107.217 Notice.

(a) The applicant shall mail a copy of the application and any subsequent amendments or other documents relating to the application to each person who is reasonably ascertainable by the applicant as a person who will be affected by the determination sought. The copy of the application must be accompanied by a statement that the person may submit comments regarding the application within 45 days. The

application must include a certification that the application has complied with this paragraph and must include the names and addresses of each person to whom the application was sent.

(b) Notwithstanding the provisions of paragraph (a) of this section, if the State or political subdivision determines that compliance with paragraph (a) of this section would be impracticable, the applicant shall:

(1) Comply with the requirements of paragraph (a) of this section with regard to those persons whom it is reasonable and practicable to notify; and

(2) Include with the application a description of the persons or class or classes of persons to whom notice was not sent.

(c) The Chief Counsel may require the applicant to provide notice in addition to that required by paragraphs (a) and (b) of this section, or may determine that the notice required by paragraph (a) of the section is not impracticable, or that notice should be published in the FEDERAL REGISTER. Late-filed comments are considered so far as practicable.

(d) The Chief Counsel may notify any other persons who may be affected by the outcome of a determination on the application.

(e) Any person submitting written comments with respect to an application filed under this section shall send a copy of the comments to the applicant. The person shall certify that he has complied with the requirements of this paragraph. The Chief Counsel may notify other persons participating in the proceeding of the comments and provide an opportunity for those other persons to respond.

[Amdt. 107-3, 41 FR 38171, Sept. 9, 1976, as amended by Amdt. 107-24, 56 FR 8621, Feb. 28, 1991; Amdt. 107-25, 57 FR 20429, May 13, 1992; Amdt. 107-38, 61 FR 21099, May 9, 1996; 71 FR 30068, May 25, 2006]

#### § 107.219 Processing.

(a) The Chief Counsel may initiate an investigation of any statement in an application and utilize in his or her evaluation any relevant facts obtained by that investigation. The Chief Counsel may solicit and accept submissions from third persons relevant to an appli-

cation and will provide the applicant an opportunity to respond to all third person submissions. In evaluating an application, the Chief Counsel on his or her own initiative may convene a hearing or conference, if he or she considers that a hearing or conference will advance his or her evaluation of the application.

(b) The Chief Counsel may dismiss the application without prejudice if:

(1) He or she determines that there is insufficient information upon which to base a determination;

(2) Upon his or her request, additional information is not submitted by the applicant; or

(3) The applicant fails to provide the notice required by § 107.217.

(c) The Chief Counsel will only consider an application for waiver of preemption determination if—

(1) The applicant State or political subdivision thereof or Indian tribe expressly acknowledges in its application that the State or political subdivision or Indian tribe requirement for which the determination is sought is inconsistent with the requirements of the Federal hazardous materials transportation law, regulations issued under the Federal hazardous material transportation law, or hazardous material transportation security regulations or directives issued by the Secretary of Homeland Security.

(2) The State or political subdivision thereof or Indian tribe requirement has been determined by a court of competent jurisdiction or in a ruling issued under § 107.209 to be inconsistent with the requirements of the Federal hazardous materials transportation law, regulations issued under the Federal hazardous material transportation law, or hazardous material transportation security regulations or directives issued by the Secretary of Homeland Security.

(d) When the Chief Counsel has received all substantive information it considers necessary to process an application for a waiver of preemption determination, it serves notice of that fact upon the applicant and all other persons who received notice of the proceeding pursuant to § 107.217.

## § 107.221

(e) To the extent possible, each application for a waiver of preemption determination will be acted upon in a manner consistent with the disposition of previous applications for waiver of preemption determinations.

[Amdt. 107-3, 41 FR 38171, Sept. 9, 1976, as amended by Amdt. 107-24, 56 FR 8621, 8623, Feb. 28, 1991; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; Amdt. 107-38, 61 FR 21099, May 9, 1996; 65 FR 58618, Sept. 29, 2000; 68 FR 52847, Sept. 8, 2003; 69 FR 54044, Sept. 7, 2004; 71 FR 30068, May 25, 2006]

### § 107.221 Determination.

(a) After considering the application and other relevant information received or obtained during the proceeding, the Chief Counsel issues a determination.

(b) The Chief Counsel may issue a waiver of preemption only on finding that the requirement of the State or political subdivision thereof or Indian tribe affords the public a level of safety at least equal to that afforded by the requirements of the Federal hazardous material transportation law or the regulations issued thereunder and does not unreasonably burden commerce. In determining if the requirement of the State or political subdivision thereof or Indian tribe unreasonably burdens commerce, the Chief Counsel considers:

(1) The extent to which increased costs and impairment of efficiency result from the requirement of the State or political subdivision thereof or Indian tribe.

(2) Whether the requirement of the State or political subdivision thereof or Indian tribe has a rational basis.

(3) Whether the requirement of the State or political subdivision thereof or Indian tribe achieves its stated purpose.

(4) Whether there is need for uniformity with regard to the subject concerned and if so, whether the requirement of the State or political subdivision thereof or Indian tribe competes or conflicts with those of other States or political subdivisions thereof or Indian tribes.

(c) The determination includes a written statement setting forth relevant facts and legal bases and providing that any person aggrieved by the determination may file a petition

## 49 CFR Ch. I (10-1-08 Edition)

for reconsideration with the Chief Counsel.

(d) The Chief Counsel provides a copy of the determination to the applicant and to any other person who substantially participated in the proceeding or requested in comments to the docket to be notified of the determination. A copy of the determination is placed on file in the public docket. The Chief Counsel will publish the determination or notice of the determination in the FEDERAL REGISTER, at which time the determination becomes a final agency action.

(e) A determination under this section constitutes an administrative finding of whether a particular requirement of a State or political subdivision thereof or Indian tribe is preempted under the Federal hazardous materials transportation law, or whether preemption is waived.

[Amdt. 107-38, 61 FR 21099, May 9, 1996, as amended at 68 FR 52848, Sept. 8, 2003; 71 FR 30068, May 25, 2006]

### § 107.223 Petition for reconsideration.

(a) Any person aggrieved by a determination under § 107.221 may file a petition for reconsideration. The petition must be filed with the Chief Counsel, in the same manner specified for filing an application in § 107.215(b), within 20 days of publication of the determination in the FEDERAL REGISTER.

(b) The petition must contain a concise statement of the basis for seeking review, including any specific factual or legal error alleged. If the petition requests consideration of information that was not previously made available to the Chief Counsel, the petition must include the reasons why such information was not previously made available.

(c) The petitioner shall mail a copy of the petition to each person who participated, either as an applicant or commenter, in the waiver of preemption proceeding, accompanied by a statement that the person may submit comments concerning the petition to the Chief Counsel within 20 days. The petition filed with the Chief Counsel must contain a certification that the petitioner has complied with this paragraph and include the names and addresses of all persons to whom a copy

of the petition was sent. Late-filed comments are considered so far as practicable.

(d) The Chief Counsel will publish the decision on the petition for reconsideration or notice of the decision in the FEDERAL REGISTER, at which time the decision on the petition for reconsideration becomes a final agency action.

[Amdt. 107-25, 57 FR 20429, May 13, 1992, as amended by Amdt. 107-38, 61 FR 21099, May 9, 1996; 71 FR 30068, May 25, 2006]

#### § 107.227 Judicial review.

A party to a proceeding under § 107.215(a) may seek review of a determination of the Chief Counsel by filing a petition, within 60 days after the determination becomes final, in the United States Court of Appeals for the District of Columbia or in the Court of Appeals for the United States for the circuit in which the person resides or has its principal place of business.

[71 FR 30068, May 25, 2006]

### Subpart D—Enforcement

SOURCE: Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, unless otherwise noted.

#### § 107.301 Delegated authority for enforcement.

Under redelegation from the Administrator, Pipeline and Hazardous Materials Safety Administration, the Associate Administrator for Hazardous Materials Safety and the Office of the Chief Counsel exercise their authority for enforcement of the Federal hazardous material transportation law, this subchapter, and subchapter C of this subchapter, in accordance with § 1.53 of this title.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-24, 56 FR 8621, Feb. 28, 1991; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994]

#### § 107.303 Purpose and scope.

This subchapter describes the various enforcement authorities exercised by the Associate Administrator for Hazardous Materials Safety and the Office of Chief Counsel and the associated sanctions and prescribes the procedures governing the exercise of those au-

thorities and the imposition of those sanctions.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-15, 51 FR 34986, Oct. 1, 1986; Amdt. 107-24, 56 FR 8621, Feb. 28, 1991]

#### § 107.305 Investigations.

(a) *General.* In accordance with its delegated authority under part 1 of this title, the Associate Administrator may initiate investigations relating to compliance by any person with any provisions of this subchapter or subchapter C of this chapter, or any special permit, approval, or order issued thereunder, or any court decree relating thereto. The Associate Administrator encourages voluntary production of documents in accordance with and subject to § 105.45, and hearings may be conducted, and depositions taken pursuant to 49 U.S.C. 5121(a). The Associate Administrator may conduct investigative conferences and hearings in the course of any investigation.

(b) *Investigations and Inspections.* Investigations under 49 U.S.C. 5121(a) are conducted by personnel duly authorized for that purpose by the Associate Administrator. Inspections under 49 U.S.C. 5121(c) are conducted by Hazardous Materials Enforcement Specialists or Hazardous Materials Compliance Investigators, also known as “hazmat investigators” or “investigators,” whom the Associate Administrator has designated for that purpose.

(1) An investigator will, on request, present his or her credentials for examination, but the credentials may not be reproduced.

(2) An investigator may administer oaths and receive affirmations in any matter under investigation by the Associate Administrator.

(3) An investigator may gather information by reasonable means including, but not limited to, interviews, statements, photocopying, photography, and video- and audio-recording.

(4) With concurrence of the Director, Office of Hazardous Materials Enforcement, Pipeline and Hazardous Materials Safety Administration, an investigator may issue a subpoena for the production of documentary or other

## § 107.307

tangible evidence if, on the basis of information available to the investigator, the documents and evidence materially will advance a determination of compliance with this subchapter or subchapter C. Service of a subpoena shall be in accordance with § 105.50. A person to whom a subpoena is directed may seek review of the subpoena by applying to the Office of Chief Counsel in accordance with § 105.55(a). A subpoena issued under this paragraph may be enforced in accordance with § 105.55(b).

(c) *Notification.* Any person who is the subject of an Associate Administrator investigation and who is requested to furnish information or documentary evidence is notified as to the general purpose for which the information or evidence is sought.

(d) *Termination.* When the facts disclosed by an investigation indicate that further action is unnecessary or unwarranted at that time, the person being investigated is notified and the investigative file is closed without prejudice to further investigation by the Associate Administrator.

(e) *Confidentiality.* Information received in an investigation under this section, including the identity of the person investigated and any other person who provides information during the investigation, shall remain confidential under the investigatory file exception, or other appropriate exception, to the public disclosure requirements of 5 U.S.C. 552.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-24, 56 FR 8621, Feb. 28, 1991; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; Amdt. 107-38, 61 FR 21099, May 9, 1996; 66 FR 45377, Aug. 28, 2001; 67 FR 61011, Sept. 27, 2002; 73 FR 4711, Jan. 28, 2008]

### COMPLIANCE ORDERS AND CIVIL PENALTIES

## § 107.307 General.

(a) When the Associate Administrator and the Office of Chief Counsel have reason to believe that a person is knowingly engaging or has knowingly engaged in conduct which is a violation of the Federal hazardous material transportation law or any provision of this subchapter or subchapter C of this chapter, or any exemption, special permit, or order issued thereunder, for

## 49 CFR Ch. I (10-1-08 Edition)

which the Associate Administrator or the Office of Chief Counsel exercise enforcement authority, they may—

(1) Issue a warning letter, as provided in § 107.309;

(2) Initiate proceedings to assess a civil penalty, as provided in either §§ 107.310 or 107.311;

(3) Issue an order directing compliance, regardless of whether a warning letter has been issued or a civil penalty assessed; and

(4) Seek any other remedy available under the Federal hazardous material transportation law.

(b) In the case of a proceeding initiated for failure to comply with an exemption or special permit, the allegation of a violation of a term or condition thereof is considered by the Associate Administrator and the Office of Chief Counsel to constitute an allegation that the special permit holder or party to the special permit is failing, or has failed to comply with the underlying regulations from which relief was granted by the special permit.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; Amdt. 107-36, 61 FR 7183, Feb. 26, 1996; 66 FR 45377, Aug. 28, 2001; 70 FR 73162, Dec. 9, 2005]

## § 107.309 Warning letters.

(a) The Associate Administrator may issue a warning letter to any person whom the Associate Administrator believes to have committed a probable violation of the Federal hazardous material transportation law or any provision of this subchapter, subchapter C of this chapter, or any special permit issued thereunder.

(b) A warning letter issued under this section includes:

(1) A statement of the facts upon which the Associate Administrator bases its determination that the person has committed a probable violation;

(2) A statement that the recurrence of the probable violations cited may subject the person to enforcement action; and

(3) An opportunity to respond to the warning letter by submitting pertinent

information or explanations concerning the probable violations cited therein.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-15, 51 FR 34986, Oct. 1, 1986; Amdt. 107-24, 56 FR 8621, Feb. 28, 1991; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; Amdt. 107-36, 61 FR 7183, Feb. 26, 1996; 66 FR 45377, Aug. 28, 2001]

#### § 107.310 Ticketing.

(a) For an alleged violation that does not have a direct or substantial impact on safety, the Associate Administrator may issue a ticket.

(b) The Associate Administrator issues a ticket by mailing it by certified or registered mail to the person alleged to have committed the violation. The ticket includes:

(1) A statement of the facts on which the Associate Administrator bases the conclusion that the person has committed the alleged violation;

(2) The maximum penalty provided for by statute, the proposed full penalty determined according to PHMSA's civil penalty guidelines and the statutory criteria for penalty assessment, and the ticket penalty amount; and

(3) A statement that within 45 days of receipt of the ticket, the person must pay the penalty in accordance with paragraph (d) of this section, make an informal response under § 107.317, or request a formal administrative hearing under § 107.319.

(c) If the person makes an informal response or requests a formal administrative hearing, the Associate Administrator forwards the inspection report, ticket and response to the Office of the Chief Counsel for processing under §§ 107.307-107.339, except that the Office of the Chief Counsel will not issue a Notice of Probable Violation under § 107.311. The Office of the Chief Counsel may impose a civil penalty that does not exceed the proposed full penalty set forth in the ticket.

(d) Payment of the ticket penalty amount must be made in accordance with the instructions on the ticket.

(e) If within 45 days of receiving the ticket the person does not pay the ticket amount, make an informal response, or request a formal administrative hearing, the person has waived the right to make an informal response or

request a hearing, has admitted the violation and owes the ticket penalty amount to PHMSA.

[Amdt. 107-36, 61 FR 7183, Feb. 26, 1996, as amended at 66 FR 45377, Aug. 28, 2001]

#### § 107.311 Notice of probable violation.

(a) The Office of Chief Counsel may serve a notice of probable violation on a person alleging the violation of one or more provisions of the Federal hazardous material transportation law or any provision of this subchapter or subchapter C of this chapter, or any special permit, or order issued thereunder.

(b) A notice of probable violation issued under this section includes the following information:

(1) A citation of the provisions of the Federal hazardous material transportation law, an order issued thereunder, this subchapter, subchapter C of this chapter, or the terms of any special permit issued thereunder which the Office of Chief Counsel believes the respondent is violating or has violated.

(2) A statement of the factual allegations upon which the demand for remedial action, a civil penalty, or both, is based.

(3) A statement of the respondent's right to present written or oral explanations, information, and arguments in answer to the allegations and in mitigation of the sanction sought in the notice of probable violation.

(4) A statement of the respondent's right to request a hearing and the procedures for requesting a hearing.

(5) In addition, in the case of a notice of probable violation proposing a compliance order, a statement of the proposed actions to be taken by the respondent to achieve compliance.

(6) In addition, in the case of a notice of probable violation proposing a civil penalty:

(i) A statement of the maximum civil penalty for which the respondent may be liable;

(ii) The amount of the preliminary civil penalty being sought by the Office of Chief Counsel, constitutes the maximum amount the Chief Counsel may seek throughout the proceeding; and

(iii) A description of the manner in which the respondent makes payment

## § 107.313

## 49 CFR Ch. I (10–1–08 Edition)

of any money due the United States as a result of the proceeding.

(c) The Office of Chief Counsel may amend a notice of probable violation at any time before issuance of a compliance order or an order assessing a civil penalty. If the Office of Chief Counsel alleges any new material facts or seeks new or additional remedial action or an increase in the amount of the proposed civil penalty, it issues a new notice of probable violation under this section.

[Amdt. 107–11, 48 FR 2651, Jan. 20, 1983, as amended at 50 FR 45730, Nov. 1, 1985; Amdt. 107–24, 56 FR 8624, Feb. 28, 1991; Amdt. 107–32, 59 FR 49131, Sept. 26, 1994; Amdt. 107–35, 60 FR 49108, Sept. 21, 1995; Amdt. 107–36, 61 FR 7184, Feb. 26, 1996]

### § 107.313 Reply.

(a) Within 30 days of receipt of a notice of probable violation, the respondent must either:

(1) Admit the violation under § 107.315;

(2) Make an informal response under § 107.317; or

(3) Request a hearing under § 107.319.

(b) Failure of the respondent to file a reply as provided in this section constitutes a waiver of the respondent's right to appear and contest the allegations and authorizes the Chief Counsel, without further notice to the respondent, to find the facts to be as alleged in the notice of probable violation and issue an order directing compliance or assess a civil penalty, or, if proposed in the notice, both. Failure to request a hearing under paragraph (a)(3) of this section constitutes a waiver of the respondent's right to a hearing.

(c) Upon the request of the respondent, the Office of Chief Counsel may, for good cause shown and filed within the 30 days prescribed in the notice of probable violation, extend the 30-day response period.

### § 107.315 Admission of violations.

(a) In responding to a notice of probable violation issued under § 107.311, the respondent may admit the alleged violations and agree to accept the terms of a proposed compliance order or to pay the amount of the preliminarily assessed civil penalty, or, if proposed in the notice, both.

(b) If the respondent agrees to the terms of a proposed compliance order, the Chief Counsel issues a final order prescribing the remedial action to be taken by the respondent.

(c) Payment of a civil penalty, when the amount of the penalty exceeds \$10,000, must be made by wire transfer, through the Federal Reserve Communications System (Fedwire), to the account of the U.S. Treasury. Detailed instructions on making payments by wire transfer may be obtained from the Financial Operations Division (AMZ–120), Federal Aviation Administration, Mike Monroney Aeronautical Center, P.O. Box 25082, Oklahoma City, OK 73125.

(d) Payment of a civil penalty, when the amount of the penalty is \$10,000 or less, must be made either by wire transfer, as set forth in paragraph (c) of this section, or certified check or money order payable to “U.S. Department of Transportation” and submitted to the Financial Operations Division (AMZ–120), Federal Aviation Administration, Mike Monroney Aeronautical Center, P.O. Box 25082, Oklahoma City, OK 73125.

[Amdt. 107–11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107–23, 57 FR 45453, Oct. 1, 1992; Amdt. 107–29, 58 FR 51527, Oct. 1, 1993; Amdt. 107–38, 61 FR 21100, May 9, 1996; 68 FR 52848, Sept. 8, 2003]

### § 107.317 Informal response.

(a) In responding to a notice of probable violation under § 107.311, the respondent may submit to the official who issued the notice, written explanations, information, or arguments in response to the allegations, the terms of a proposed compliance order, or the amount of the preliminarily assessed civil penalty.

(b) The respondent may include in his informal response a request for a conference. Upon the request of the respondent, the conference may be either in person or by telephone. A request for a conference must set forth the issues the respondent will raise at the conference.

(c) Upon receipt of a request for a conference under paragraph (b) of this section, the Chief Counsel's Office, in consultation with the Associate Administrator, arranges for a conference

as soon as practicable at a time and place of mutual convenience.

(d) The respondent's written explanations, information, and arguments as well as the respondent's presentation at a conference are considered by the Chief Counsel in reviewing the notice of probable violation. Based upon a review of the proceeding, the Chief Counsel may dismiss the notice of probable violation in whole or in part. If he does not dismiss it in whole, he issues an order directing compliance or assessing a civil penalty, or, if proposed in the notice, both.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-23, 56 FR 66157, Dec. 20, 1991; 66 FR 45377, Aug. 28, 2001]

#### § 107.319 Request for a hearing.

(a) In responding to a notice of probable violation under § 107.311, the respondent may request a formal administrative hearing on the record before an Administrative Law Judge (ALJ) obtained by the Office of the Chief Counsel.

(b) A request for a hearing under paragraph (a) of this section must:

(1) State the name and address of the respondent and of the person submitting the request if different from the respondent;

(2) State which allegations of violations, if any, are admitted; and

(3) State generally the issues to be raised by the respondent at the hearing. Issues not raised in the request are not barred from presentation at the hearing; and

(4) Be addressed to the official who issued the notice.

(c) After a request for a hearing that complies with the requirements of paragraph (b) of this section, the Chief Counsel obtains an ALJ to preside over the hearing and notifies the respondent of this fact. Upon assignment of an ALJ, further matters in the proceeding generally are conducted by and through the ALJ, except that the Chief Counsel and respondent may compromise or settle the case under § 107.327 of this subpart without order of the ALJ or voluntarily dismiss the case under Rule 41(a)(1) of the Federal Rules of Civil Procedure without order of the ALJ; in the event of such a compromise, settlement or dismissal, the

Chief Counsel expeditiously will notify the ALJ thereof.

(d) At any time after requesting a formal administrative hearing but prior to the issuance of a decision and final order by the ALJ, the respondent may withdraw such request in writing, thereby terminating the jurisdiction of the ALJ in the case. Such a withdrawal constitutes an irrevocable waiver of respondent's right to such a hearing on the facts, allegations, and proposed sanction presented in the notice of probable violation to which the request for hearing relates.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended at 48 FR 17094, Apr. 21, 1983; Amdt. No. 107-19, 54 FR 22899, May 30, 1989]

#### § 107.321 Hearing.

(a) To the extent practicable, the hearing is held in the general vicinity of the place where the alleged violation occurred or at a place convenient to the respondent. Testimony by witnesses shall be given under oath and the hearing shall be recorded verbatim.

(b) Hearings are conducted in accordance with the Federal Rules of Evidence and Federal Rules of Civil Procedure; however, the ALJ may modify them as he determines necessary in the interest of a full development of the facts. In addition, the ALJ may:

(1) Administer oaths and affirmations;

(2) Issue subpoenas as provided by § 105.45;

(3) Adopt procedures for the submission of motions, evidence, and other documents pertinent to the proceeding;

(4) Take or cause depositions to be taken;

(5) Rule on offers of proof and receive relevant evidence;

(6) Examine witnesses at the hearing;

(7) Convene, recess, reconvene, adjourn and otherwise regulate the course of the hearing;

(8) Hold conferences for settlement, simplification of the issues, or any other proper purpose; and

(9) Take any other action authorized by, or consistent with, the provisions of this subpart and permitted by law which may expedite the hearing or aid in the disposition of an issue raised therein.



## § 107.323

(c) The official who issued the notice of probable violation, or his representative, has the burden of proving the facts alleged therein.

(d) The respondent may appear and be heard on his own behalf or through counsel of his choice. The respondent or his counsel may offer relevant information including testimony which he believes should be considered in opposition to the allegations or which may bear on the sanction being sought and conduct such cross-examination as may be required for a full disclosure of the facts.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended at 67 FR 61011, Sept. 27, 2002]

### § 107.323 ALJ's decision.

(a) After consideration of all matters of record in the proceeding, the ALJ shall issue an order dismissing the notice of probable violation in whole or in part or granting the sanction sought by the Office of Chief Counsel in the notice. If the ALJ does not dismiss the notice of probable violation in whole, he issues an order directing compliance or assessing a civil penalty, or, if proposed in the notice, both. The order includes a statement of the findings and conclusions, and the reasons therefore, on all material issues of fact, law, and discretion.

(b) If, within 20 days of receipt of an order issued under paragraph (a) of this section, the respondent does not submit in writing his acceptance of the terms of an order directing compliance, or, where appropriate, pay a civil penalty, or file an appeal under § 107.325, the case may be referred to the Attorney General with a request that an action be brought in the appropriate United States District Court to enforce the terms of a compliance order or collect the civil penalty.

### § 107.325 Appeals.

(a) *Hearing proceedings.* A party aggrieved by an ALJ's decision and order issued under § 107.323, may file a written appeal in accordance with paragraph (c) of this section with the Administrator, Office of the Administrator, Pipeline and Hazardous Materials Safety Administration, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

## 49 CFR Ch. I (10-1-08 Edition)

(b) *Non-Hearing proceedings.* A respondent aggrieved by an order issued under § 107.317, may file a written appeal in accordance with paragraph (c) of this section with the Administrator, Office of the Administrator, Pipeline and Hazardous Materials Safety Administration, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(c) An appeal of an order issued under this subpart must:

(1) Be filed within 20 days of receipt of the order by the appealing party; and

(2) State with particularity the findings in the order that the appealing party challenges, and include all information and arguments pertinent thereto.

(d) If the Administrator, PHMSA, affirms the order in whole or in part, the respondent must comply with the terms of the decision within 20 days of the respondent's receipt thereof, or within the time prescribed in the order. If the respondent does not comply with the terms of the decision within 20 days of receipt, or within the time prescribed in the order, the case may be referred to the Attorney General for action to enforce the terms of the decision.

(e) The filing of an appeal stays the effectiveness of an order issued under § 107.317 or § 107.323. However, if the Administrator, PHMSA, determines that it is in the public interest, he may keep an order directing compliance in force pending appeal.

[70 FR 56090, Sept. 23, 2005, as amended at 72 FR 55683, Oct. 1, 2007]

### § 107.327 Compromise and settlement.

(a) At any time before an order issued under § 107.317 or § 107.323 is referred to the Attorney General for enforcement, the respondent or the Office of Chief Counsel may propose a compromise as follows:

(1) In civil penalty cases, the respondent or Chief Counsel may offer to compromise the amount of the penalty by submitting an offer for a specific amount to the other party. An offer of compromise by the respondent shall be submitted to the Chief Counsel who

may, after consultation with the Associate Administrator, accept or reject it.

(i) A compromise offer stays the running of any response period then outstanding.

(ii) If a compromise is agreed to by the parties, the respondent is notified in writing. Upon receipt of payment by Office of Chief Counsel, the respondent is notified in writing that acceptance of payment is in full satisfaction of the civil penalty proposed or assessed, and Office of Chief Counsel closes the case with prejudice to the respondent.

(iii) If a compromise cannot be agreed to, the respondent is notified in writing and is given 10 days or the amount of time remaining in the then outstanding response period, whichever is longer, to respond to whatever action was taken by the Office of Chief Counsel or the Administrator, PHMSA.

(2) In compliance order cases, the respondent may propose a consent agreement to the Chief Counsel. If the Chief Counsel accepts the agreement, he issues an order in accordance with its terms. If the Chief Counsel rejects the agreement, he directs that the proceeding continue. An agreement submitted to the Chief Counsel must include:

(i) A statement of any allegations of fact which the respondent challenges;

(ii) The reasons why the terms of a compliance order or proposed compliance order are or would be too burdensome for the respondent, or why such terms are not supported by the record in the case;

(iii) A proposed compliance order suitable for issuance by the Chief Counsel;

(iv) An admission of all jurisdictional facts; and

(v) An express waiver of further procedural steps and all right to seek judicial review or otherwise challenge or contest the validity of the order.

(b) Notwithstanding paragraph (a)(1) of this section, the respondent or Office of Chief Counsel may propose to settle the case. If the Chief Counsel agrees to a settlement, the respondent is notified

and the case is closed without prejudice to the respondent.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended at 50 FR 45730, Nov. 1, 1985; Amdt. 107-24, 56 FR 8621, Feb. 28, 1991; 56 FR 15510, Apr. 17, 1991; Amdt. 107-29, 58 FR 51527, Oct. 1, 1993; 66 FR 45377, Aug. 28, 2001]

#### § 107.329 Maximum penalties.

(a) A person who knowingly violates a requirement of the Federal hazardous material transportation law, an order issued thereunder, this subchapter, subchapter C of this chapter, or a special permit or approval issued under this subchapter applicable to the transportation of hazardous materials or the causing of them to be transported or shipped is liable for a civil penalty of not more than \$50,000 and not less than \$250 for each violation, except the maximum civil penalty is \$100,000 if the violation results in death, serious illness or severe injury to any person or substantial destruction of property, and a minimum \$450 civil penalty applies to a violation relating to training. When the violation is a continuing one, each day of the violation constitutes a separate offense.

(b) A person who knowingly violates a requirement of the Federal hazardous material transportation law, an order issued thereunder, this subchapter, subchapter C of this chapter, or a special permit or approval issued under this subchapter applicable to the design, manufacture, fabrication, inspection, marking, maintenance, reconditioning, repair or testing of a package, container, or packaging component which is represented, marked, certified, or sold by that person as qualified for use in the transportation of hazardous materials in commerce is liable for a civil penalty of not more than \$50,000 and not less than \$250 for each violation, except the maximum civil penalty is \$100,000 if the violation results in death, serious illness or severe injury to any person or substantial destruction of property, and a minimum \$450 civil penalty applies to a violation relating to training.

[71 FR 8487, Feb. 17, 2006]

#### § 107.331 Assessment considerations.

After finding a knowing violation under this subpart, the Office of Chief

### § 107.333

Counsel assesses a civil penalty taking the following into account:

- (a) The nature and circumstances of the violation;
- (b) The extent and gravity of the violation;
- (c) The degree of the respondent's culpability;
- (d) The respondent's prior violations;
- (e) The respondent's ability to pay;
- (f) The effect on the respondent's ability to continue in business; and
- (g) Such other matters as justice may require.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-30, 58 FR 50500, Sept. 27, 1993; Amdt. 107-38, 61 FR 21100, May 9, 1996]

#### CRIMINAL PENALTIES

### § 107.333 Criminal penalties generally.

A person who knowingly violates §171.2(l) of this title or willfully or recklessly violates a requirement of the Federal hazardous material transportation law or a regulation, order, special permit, or approval issued thereunder shall be fined under title 18, United States Code, or imprisoned for not more than 5 years, or both, except the maximum amount of imprisonment shall be 10 years in any case in which the violation involves the release of a hazardous material which results in death or bodily injury to any person.

[71 FR 8487, Feb. 17, 2006]

### § 107.335 Referral for prosecution.

If the Associate Administrator becomes aware of a possible willful violation of the Federal hazardous material transportation law, this subchapter, subchapter C of this chapter, or any special permit, or order issued thereunder, for which the Associate Administrator exercises enforcement responsibility, it shall report it to the Office of the Chief Counsel, Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, Washington, DC 20590-0001. If appropriate, the Chief Counsel refers the report to the Department of Jus-

### 49 CFR Ch. I (10-1-08 Edition)

tice for criminal prosecution of the offender.

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-22, 55 FR 39978, Oct. 1, 1990; Amdt. 107-24, 56 FR 8621, Feb. 28, 1991; 56 FR 15510, Apr. 17, 1991; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; Amdt. 107-35, 60 FR 49108, Sept. 21, 1995; 66 FR 45377, Aug. 28, 2001]

### § 107.336 Limitation on fines and penalties.

If a State or political subdivision or Indian tribe assesses any fine or penalty determined by the Secretary to be appropriate for a violation concerning a subject listed in §107.202(a), no additional fine or penalty may be assessed for such violation by any other authority.

[Amdt. 107-24, 56 FR 8624, Feb. 28, 1991]

#### INJUNCTIVE ACTION

### § 107.337 Injunctions generally.

Whenever it appears to the Office of Chief Counsel that a person has engaged, or is engaged, or is about to engage in any act or practice constituting a violation of any provision of the Federal hazardous material transportation law, this subchapter, subchapter C of this chapter, or any special permit, or order issued thereunder, for which the Office of Chief Counsel exercises enforcement responsibility, the Administrator, PHMSA, or his delegate, may request the Attorney General to bring an action in the appropriate United States District Court for such relief as is necessary or appropriate, including mandatory or prohibitive injunctive relief, interim equitable relief, and punitive damages as provided by 49 U.S.C. 5122(a).

[Amdt. 107-11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107-32, 59 FR 49131, Sept. 26, 1994]

### § 107.339 Imminent hazards.

Whenever it appears to the Office of the Chief Counsel that there is a substantial likelihood that death, serious illness, or severe personal injury will result from the transportation of a particular hazardous material or hazardous materials container, before a compliance order proceeding or other administrative hearing or formal proceeding to abate the risk of that harm

## Pipeline and Hazardous Materials Safety Admin., DOT Pt. 107, Subpt. D, App. A

can be completed, the Administrator, PHMSA, or his delegate, may bring an action under 49 U.S.C. 5122(b) in the appropriate United States District Court for an order suspending or restricting the transportation of that hazardous material or those containers or for such other equitable relief as is necessary or appropriate to ameliorate the hazard.

[Amdt. 107–11, 48 FR 2651, Jan. 20, 1983, as amended by Amdt. 107–15, 51 FR 34987, Oct. 1, 1986; Amdt. 107–32, 59 FR 49131, Sept. 26, 1994]

### APPENDIX A TO SUBPART D OF PART 107—GUIDELINES FOR CIVIL PENALTIES

I. This appendix sets forth the guidelines used by the Office of Hazardous Materials Safety (as of October 1, 2005) in making initial baseline determinations for recommending civil penalties. The first part of these guidelines is a list of baseline amounts or ranges for probable violations frequently cited in enforcement reports referred for action. Following the list of violations are general guidelines used by OHMS in making initial penalty determinations in enforcement cases.

#### II. LIST OF FREQUENTLY CITED VIOLATIONS

##### II—LIST OF FREQUENTLY CITED VIOLATIONS

| Violation description                                                                                                                                                                                                                           | Section or cite              | Baseline assessment                                                                      |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|------------------------------------------------------------------------------------------|
| <b>General Requirements</b>                                                                                                                                                                                                                     |                              |                                                                                          |
| A. Registration Requirements: Failure to register as an offeror or carrier of hazardous material and pay registration fee.                                                                                                                      | 107.608, 107.612 .....       | \$1,000 + \$500 each additional year.                                                    |
| B. Training Requirements:                                                                                                                                                                                                                       |                              |                                                                                          |
| 1. Failure to provide initial training to hazmat employees (general awareness, function-specific, safety, and security awareness training):                                                                                                     | 172.702                      |                                                                                          |
| a. More than 10 hazmat employees .....                                                                                                                                                                                                          | .....                        | \$700 and up each area.                                                                  |
| b. 10 hazmat employees or fewer .....                                                                                                                                                                                                           | .....                        | \$450 and up each area.                                                                  |
| 2. Failure to provide recurrent training to hazmat employees (general awareness, function-specific, safety, and security awareness training).                                                                                                   | 172.702 .....                | \$450 and up each area.                                                                  |
| 3. Failure to provide security training when a security plan is required but has not been developed.                                                                                                                                            | 172.702 .....                | Included in penalty for no security plan.                                                |
| 4. Failure to provide security training when a security plan has been developed but hazmat employees have not been trained concerning the security plan and its implementation.                                                                 | 172.702 .....                | \$2,500.                                                                                 |
| 5. Failure to create and maintain training records:                                                                                                                                                                                             | 172.704                      |                                                                                          |
| a. more than 10 hazmat employees .....                                                                                                                                                                                                          | .....                        | \$800 and up.                                                                            |
| b. 10 hazmat employees or fewer .....                                                                                                                                                                                                           | .....                        | \$500 and up.                                                                            |
| C. Security Plans:                                                                                                                                                                                                                              |                              |                                                                                          |
| 1. Failure to develop a security plan; failure to adhere to security plan:                                                                                                                                                                      | 172.800                      |                                                                                          |
| a. § 172.504 table 1 materials .....                                                                                                                                                                                                            | .....                        | \$7,500.                                                                                 |
| b. Packing Group I .....                                                                                                                                                                                                                        | .....                        | \$6,000.                                                                                 |
| c. Packing Group II .....                                                                                                                                                                                                                       | .....                        | \$4,500.                                                                                 |
| d. Packing Group III .....                                                                                                                                                                                                                      | .....                        | \$3,000.                                                                                 |
| 2. Incomplete security plan or incomplete adherence (one or more of four required elements missing).                                                                                                                                            | .....                        | One-quarter (25%) of above for each element.                                             |
| 3. Failure to update a security plan to reflect changing circumstances                                                                                                                                                                          | 172.802(b) .....             | One-third (33%) of baseline for no plan.                                                 |
| 4. Failure to put security plan in writing; failure to make all copies identical.                                                                                                                                                               | 172.800(b) .....             | One-third (33%) of baseline for no plan.                                                 |
| D. Notification to a Foreign Shipper: Failure to provide information of HMR requirements applicable to a shipment of hazardous materials within the United States, to a foreign offeror or forwarding agent at the place of entry into the U.S. | 171.12(a) .....              | \$1,500 to \$7,500 (corresponding to violations by foreign offeror or forwarding agent). |
| E. Expired Exemption or Special Permit: Offering or transporting a hazardous material, or otherwise performing a function covered by an exemption or special permit, after expiration of the exemption or special permit                        | 171.2(a), (b), (c), Various. | \$1,000 + \$500 each additional year.                                                    |

##### Offeror Requirements—All hazardous materials

A. Undeclared Shipment:

## II—LIST OF FREQUENTLY CITED VIOLATIONS—Continued

| Violation description                                                                                                                                                                                                                     | Section or cite                                          | Baseline assessment |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|---------------------|
| Offering for transportation a hazardous material without shipping papers, package markings, labels, or placards.                                                                                                                          | 172.200, 172.300, 172.400, 172.500.                      | \$15,000 and up.    |
| B. Shipping Papers:                                                                                                                                                                                                                       |                                                          |                     |
| 1. Failure to provide a shipping paper for a shipment of hazardous materials.                                                                                                                                                             | 172.201 .....                                            | \$3,000 to \$6,000. |
| 2. Failure to follow one or more of the three approved formats for listing hazardous materials on a shipping paper.                                                                                                                       | 172.201(a)(1) .....                                      | \$1,200.            |
| 3. Failure to retain shipping papers:                                                                                                                                                                                                     |                                                          |                     |
| a. by an offeror, for two years after the date the shipment is provided to the carrier (or 3 years if the material is a hazardous waste).                                                                                                 |                                                          |                     |
| b. by a carrier, for one year after the date the shipment is provided to the carrier (or 3 years if the material is a hazardous waste).                                                                                                   | 172.201(e), 174.24(b), 175.30(a), 176.24(b), 177.817(f). | \$1,000.            |
| 4. Failure to include a proper shipping name in the shipping description or using an incorrect proper shipping name.                                                                                                                      | 172.202 .....                                            | \$800 to \$1,600.   |
| 5. Failure to include a hazard class/division number in the shipping description.                                                                                                                                                         | 172.202 .....                                            | \$1,000 to \$2,000. |
| 6. Failure to include an identification number in the shipping description.                                                                                                                                                               | 172.202 .....                                            | \$1,000 to \$2,000. |
| 7. Using an incorrect hazard class/identification number: .....                                                                                                                                                                           | 172.202.                                                 |                     |
| a. that does not affect compatibility requirements .....                                                                                                                                                                                  |                                                          | \$800.              |
| b. that affects compatibility requirements .....                                                                                                                                                                                          |                                                          | \$3,000 to \$6,000. |
| 8. Using an incorrect identification number: .....                                                                                                                                                                                        | 172.202..                                                |                     |
| a. that does not change the response information .....                                                                                                                                                                                    |                                                          | \$800.              |
| b. that changes the response information .....                                                                                                                                                                                            |                                                          | \$3,000 to \$6,000. |
| 9. Failure to include the Packing Group, or using an incorrect Packing Group.                                                                                                                                                             | 172.202 .....                                            | \$1,200.            |
| 10. Using a shipping description that includes additional unauthorized information (extra or incorrect words).                                                                                                                            | 172.202 .....                                            | \$800.              |
| 11. Using a shipping description not in required sequence .....                                                                                                                                                                           | 172.202 .....                                            | \$500.              |
| 12. Using a shipping description with two or more required elements missing or incorrect:                                                                                                                                                 | 172.202.                                                 |                     |
| a. such that the material is misdescribed .....                                                                                                                                                                                           |                                                          | \$3,000.            |
| b. such that the material is misclassified .....                                                                                                                                                                                          |                                                          | \$6,000.            |
| 13. Failure to include the total quantity of hazardous material covered by a shipping description.                                                                                                                                        | 172.202(c) .....                                         | \$500.              |
| 14. Failure to list an exemption or special permit number in association with the shipping description.                                                                                                                                   | 172.203(a) .....                                         | \$800.              |
| 15. Failure to indicate "Limited Quantity" or "Ltd Qty" following the basic shipping description of a material offered for transportation as a limited quantity.                                                                          | 172.203(b) .....                                         | \$500.              |
| 16. Failure to include "RQ" in the shipping description to identify a material that is a hazardous substance.                                                                                                                             | 172.203(c)(2) .....                                      | \$500.              |
| 17. Failure to include a required technical name in parenthesis for a listed generic or "n.o.s." material.                                                                                                                                | 172.203(k) .....                                         | \$1,000.            |
| 18. Failure to include the required shipper's certification on a shipping paper.                                                                                                                                                          | 172.204 .....                                            | \$1,000.            |
| 19. Failure to sign the required shipper's certification on a shipping paper.                                                                                                                                                             | 172.204 .....                                            | \$800.              |
| C. Emergency Response Information Requirements:                                                                                                                                                                                           |                                                          |                     |
| 1. Providing or listing incorrect emergency response information with or on a shipping paper.                                                                                                                                             | 172.602.                                                 |                     |
| a. No significant difference in response .....                                                                                                                                                                                            |                                                          | \$800.              |
| b. Significant difference in response .....                                                                                                                                                                                               |                                                          | \$3,000 to \$6,000. |
| 2. Failure to include an emergency response telephone number on a shipping paper.                                                                                                                                                         | 172.604 .....                                            | \$2,600.            |
| 3. Failure to have the emergency response telephone number monitored while a hazardous material is in transportation or listing multiple telephone numbers (without specifying the times for each) that are not monitored 24 hours a day. | 172.604 .....                                            | \$1,300.            |
| 4. Listing an unauthorized emergency response telephone number on a shipping paper.                                                                                                                                                       | 172.604 .....                                            | \$2,600 to \$4,200. |
| 5. Listing an incorrect or non-working emergency response telephone number on a shipping paper.                                                                                                                                           | 172.604 .....                                            | \$1,300.            |
| 6. Failure to provide required technical information when the listed emergency response telephone number is contacted.                                                                                                                    | 172.604 .....                                            | \$1,300.            |
| D. Package Marking Requirements:                                                                                                                                                                                                          |                                                          |                     |
| 1. Failure to mark the proper shipping name on a package or marking an incorrect shipping name on a package.                                                                                                                              | 172.301(a) .....                                         | \$800 to \$1,600.   |
| 2. Failure to mark the identification number on a package .....                                                                                                                                                                           | 172.301(a) .....                                         | \$1,000 to \$2,000. |

Pipeline and Hazardous Materials Safety Admin., DOT Pt. 107, Subpt. D, App. A

II—LIST OF FREQUENTLY CITED VIOLATIONS—Continued

| Violation description                                                                                                                                                                                                                                              | Section or cite     | Baseline assessment |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------------------|
| 3. Marking a package with an incorrect identification number .....                                                                                                                                                                                                 | 172.301(a).         |                     |
| a. that does not change the response information .....                                                                                                                                                                                                             | .....               | \$800.              |
| b. that changes the response information .....                                                                                                                                                                                                                     | .....               | \$3,000 to \$6,000. |
| 4. Failure to mark the proper shipping name and identification number on a package.                                                                                                                                                                                | 172.301(a) .....    | \$3,000 to \$6,000. |
| 5. Marking a package with an incorrect shipping name and identification number.                                                                                                                                                                                    | 172.301(a).         |                     |
| a. that does not change the response information .....                                                                                                                                                                                                             | .....               | \$1,500 to \$3,000. |
| b. that changes the response information .....                                                                                                                                                                                                                     | .....               | \$3,000 to \$6,000. |
| 6. Failure to include the required technical name(s) in parenthesis for a listed generic or "n.o.s." entry.                                                                                                                                                        | 172.301(c) .....    | \$1,000.            |
| 7. Marking a package as containing hazardous material when it contains no hazardous material.                                                                                                                                                                      | 172.303(a) .....    | \$800.              |
| 8. Failure to locate required markings away from other markings that could reduce their effectiveness.                                                                                                                                                             | 172.304(a)(4) ..... | \$800.              |
| 9. Failure to mark a package containing liquid hazardous materials with required orientation marking.                                                                                                                                                              | 172.312 .....       | \$2,500 to \$3,500. |
| 10. Failure to mark "RQ" on a non-bulk package containing a hazardous substance.                                                                                                                                                                                   | 172.324(b) .....    | \$500.              |
| E. Package Labeling Requirements:                                                                                                                                                                                                                                  |                     |                     |
| 1. Failure to label a package .....                                                                                                                                                                                                                                | 172.400 .....       | \$5,000.            |
| 2. Placing a label that represents a hazard other than the hazard presented by the hazardous material in the package.                                                                                                                                              | 172.400 .....       | \$5,000.            |
| 3. Placing a label on a package that does not contain a hazardous material.                                                                                                                                                                                        | 172.401(a) .....    | \$800.              |
| 4. Failure to place a required subsidiary label on a package .....                                                                                                                                                                                                 | 172.402 .....       | \$500 to \$2,500.   |
| 5. Placing a label on a different surface of the package than, or away from, the proper shipping name.                                                                                                                                                             | 172.406(a) .....    | \$800.              |
| 6. Placing an improper size label on a package .....                                                                                                                                                                                                               | 172.407(c) .....    | \$800.              |
| 7. Placing a label on a package that does not meet color specification requirements (depending on the variance).                                                                                                                                                   | 172.407(d) .....    | \$600 to \$2,500.   |
| 8. Failure to provide an appropriate class or division number on a label.                                                                                                                                                                                          | 172.411 .....       | \$2,500.            |
| F. Placarding Requirements:                                                                                                                                                                                                                                        |                     |                     |
| Failure to properly placard a freight container or vehicle containing hazardous materials:.                                                                                                                                                                        | 172.504.            |                     |
| a. when Table 1 is applicable .....                                                                                                                                                                                                                                | .....               | \$1,000 to \$9,000. |
| b. when Table 2 is applicable .....                                                                                                                                                                                                                                | .....               | \$800 to \$7,200.   |
| G. Packaging Requirements:                                                                                                                                                                                                                                         |                     |                     |
| 1. Offering a hazardous material for transportation in an unauthorized non-UN standard or nonspecification packaging (includes failure to comply with the terms of an exemption or special permit authorizing use of a nonstandard or nonspecification packaging). | Various.            |                     |
| a. Packing Group I (and §172.504 Table I materials) .....                                                                                                                                                                                                          | .....               | \$9,000.            |
| b. Packing Group II .....                                                                                                                                                                                                                                          | .....               | \$7,000.            |
| c. Packing Group III .....                                                                                                                                                                                                                                         | .....               | \$5,000.            |
| 2. Offering a hazardous material for transportation in a self-certified packaging that has not been subjected to design qualification testing:.                                                                                                                    | 178.601 & Various.  |                     |
| a. Packing Group I (and §172.504 Table I materials) .....                                                                                                                                                                                                          | .....               | \$10,800.           |
| b. Packing Group II .....                                                                                                                                                                                                                                          | .....               | \$8,400.            |
| c. Packing Group III .....                                                                                                                                                                                                                                         | .....               | \$6,000.            |
| 3. Offering a hazardous material for transportation in a packaging that has been successfully tested to an applicable UN standard but is not marked with the required UN marking.                                                                                  | 178.503(a) .....    | \$3,600.            |
| 4. Failure to close a UN standard packaging in accordance with the closure instructions.                                                                                                                                                                           | 173.22(a)(4) .....  | \$2,500.            |
| 5. Offering a hazardous material for transportation in a packaging that leaks during conditions normally incident to transportation:                                                                                                                               | 173.24(b).          |                     |
| a. Packing Group I (and §172.504 Table I materials) .....                                                                                                                                                                                                          | .....               | \$12,000.           |
| b. Packing Group II .....                                                                                                                                                                                                                                          | .....               | \$9,000.            |
| c. Packing Group III .....                                                                                                                                                                                                                                         | .....               | \$6,000.            |
| 6. Overfilling or underfilling a package so that the effectiveness is substantially reduced:                                                                                                                                                                       | 173.24(b).          |                     |
| a. Packing Group I (and §172.504 Table I materials) .....                                                                                                                                                                                                          | .....               | \$9,000.            |
| b. Packing Group II .....                                                                                                                                                                                                                                          | .....               | \$6,000.            |
| c. Packing Group III .....                                                                                                                                                                                                                                         | .....               | \$3,000.            |
| 7. Offering a hazardous material for transportation after October 1, 1996, in an unauthorized non-UN standard packaging marked as manufactured to a DOT specification:                                                                                             | 171.14.             |                     |
| a. packaging meets DOT specification .....                                                                                                                                                                                                                         | .....               | \$3,000.            |
| b. packaging does not meet DOT specification .....                                                                                                                                                                                                                 | .....               | \$5,000 to \$9,000. |

## II—LIST OF FREQUENTLY CITED VIOLATIONS—Continued

| Violation description                                                                                                                                                                                                       | Section or cite              | Baseline assessment  |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|----------------------|
| 8. Failure to mark an overpack with a statement that the inside packages comply with prescribed specifications or standards when specification or standard packaging is required.                                           | 173.25(a)(4) .....           | \$3,000.             |
| 9. Filling an IBC or a portable tank (DOT, UN, or IM) that is out of test and offering hazardous materials for transportation in that IBC or portable tank.                                                                 | 173.32(a), 180.352, 180.605. |                      |
| a. All testing overdue .....                                                                                                                                                                                                | .....                        | \$3,500 to \$7,000.  |
| b. Only periodic (5 year) test overdue .....                                                                                                                                                                                | .....                        | \$3,500.             |
| c. Only intermediate periodic (2.5 year) tests overdue .....                                                                                                                                                                | .....                        | \$3,500.             |
| 10. Failure to provide the required outage in a portable tank that results in a release of hazardous materials.                                                                                                             | 173.32(f)(6) .....           | \$6,000 to \$12,000. |
| <b>Officer Requirements—Specific hazardous materials</b>                                                                                                                                                                    |                              |                      |
| A. Cigarette Lighters:                                                                                                                                                                                                      |                              |                      |
| Offering for transportation an unapproved cigarette lighter, lighter refill, or similar device, equipped with an ignition element and containing fuel.                                                                      | 173.21(i) .....              | \$7,500.             |
| B. Class 1—Explosives:                                                                                                                                                                                                      |                              |                      |
| 1. Failure to mark the package with the EX number for each substance contained in the package or, alternatively, indicate the EX number for each substance in association with the description on the shipping description. | 172.320 .....                | \$1,200.             |
| 2. Offering an unapproved explosive for transportation:                                                                                                                                                                     | .....                        | 173.54,              |
| a. Div. 1.3 and 1.4 fireworks meeting the chemistry requirements (quantity and type) of APA Standard 87–1.                                                                                                                  | 173.56(b) .....              | \$5,000 to \$10,000. |
| b. All other explosives (including forbidden) .....                                                                                                                                                                         | .....                        | \$10,000 and up.     |
| 3. Offering a leaking or damaged package of explosives for transportation.                                                                                                                                                  | 173.54(c) .....              | \$10,000 and up.     |
| 4. Packaging explosives in the same outer packaging with other materials.                                                                                                                                                   | 173.61 .....                 | \$2,500 to \$5,000.  |
| C. Class 7—Radioactive Materials:                                                                                                                                                                                           |                              |                      |
| 1. Failure to include required additional entries, or providing incorrect information for these additional entries.                                                                                                         | 172.203(d) .....             | \$1,000 to \$3,000.  |
| 2. Failure to mark the gross mass on the outside of a package of Class 7 material that exceeds 110 pounds.                                                                                                                  | 172.310(a) .....             | \$800.               |
| 3. Failure to mark each package in letters at least 13 mm (½ inch) high with the words "Type A" or "Type B" as appropriate.                                                                                                 | 172.310(b) .....             | \$800.               |
| 4. Placing a label on Class 7 material that understates the proper label category.                                                                                                                                          | 172.403 .....                | \$5,000.             |
| 5. Placing a label on Class 7 material that fails to contain (or has erroneous) entries for the name of the radionuclide(s), activity, and transport index.                                                                 | 172.403(g) .....             | \$2,000 to \$4,000.  |
| 6. Failure to meet one or more of the general design requirements for a package used to ship a Class 7 material.                                                                                                            | 173.410 .....                | \$5,000.             |
| 7. Failure to comply with the industrial packaging (IP) requirements when offering a Class 7 material for transportation.                                                                                                   | 173.411 .....                | \$5,000.             |
| 8. Failure to provide a tamper-indicating device on a Type A package used to ship a Class 7 material.                                                                                                                       | 173.412(a) .....             | \$2,000.             |
| 9. Failure to meet the additional design requirements of a Type A package used to ship a Class 7 material.                                                                                                                  | 173.412(b)–(i) .....         | \$5,000.             |
| 10. Failure to meet the performance requirements for a Type A package used to ship a Class 7 material.                                                                                                                      | 173.412(j)–(l) .....         | \$8,400.             |
| 11. Offering a DOT specification 7A packaging without maintaining complete documentation of tests and an engineering evaluation or comparative data:                                                                        | 173.415(a), 173.461          |                      |
| a. Tests and evaluation not performed .....                                                                                                                                                                                 | .....                        | \$8,400.             |
| b. Complete records not maintained .....                                                                                                                                                                                    | .....                        | \$2,000 to \$5,000.  |
| 12. Offering any Type B, Type B(U), Type B(M) packaging that failed to meet the approved DOT, NRC or DOE design, as applicable.                                                                                             | 173.416 .....                | \$9,000.             |
| 13. Offering a Type B packaging without holding a valid NRC approval certificate:                                                                                                                                           | 173.471(a).                  |                      |
| a. Never having obtained one .....                                                                                                                                                                                          | .....                        | \$3,000.             |
| b. Holding an expired certificate .....                                                                                                                                                                                     | .....                        | \$1,000.             |
| 14. Failure to meet one or more of the special requirements for a package used to ship uranium hexafluoride.                                                                                                                | 173.420 .....                | \$10,800.            |
| 15. Offering Class 7 material for transportation as a limited quantity without meeting the requirements for limited quantity.                                                                                               | 173.421(a) .....             | \$4,000.             |
| 16. Offering a multiple-hazard limited quantity Class 7 material without addressing the additional hazard.                                                                                                                  | 173.423(a) .....             | \$500 to \$2,500.    |

Pipeline and Hazardous Materials Safety Admin., DOT Pt. 107, Subpt. D, App. A

II—LIST OF FREQUENTLY CITED VIOLATIONS—Continued

| Violation description                                                                                                                                                                                                                                                                                                | Section or cite                           | Baseline assessment  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|----------------------|
| 17. Offering Class 7 low specific activity (LSA) materials or surface contaminated objects (SCO) with an external dose rate that exceeds an external radiation level of 1 rem/hr at 3 meters from the unshielded material.                                                                                           | 173.427(a)(1) .....                       | \$6,000.             |
| 18. Offering Class 7 LSA materials or SCO as exclusive use without providing specific instructions to the carrier for maintenance of exclusive use shipment controls.                                                                                                                                                | 173.427(a)(6) .....                       | \$1,000.             |
| 19. Offering in excess of Type A quantity of a Class 7 material in a Type A packaging.                                                                                                                                                                                                                               | 173.431 .....                             | \$12,000.            |
| 20. Offering a package that exceeds the permitted limits for surface radiation or transport index.                                                                                                                                                                                                                   | 173.441 .....                             | \$10,000 and up.     |
| 21. Offering a package without determining the level of removable external contamination, or that exceeds the limit for removable external contamination.                                                                                                                                                            | 173.443 .....                             | \$5,000 and up.      |
| 22. Storing packages of radioactive material in a group with a total transport index more than 50.                                                                                                                                                                                                                   | 173.447(a) .....                          | \$5,000 and up.      |
| 23. Offering for transportation or transporting aboard a passenger aircraft any single package or overpack of Class 7 material with a transport index greater than 3.0.                                                                                                                                              | 173.448(e) .....                          | \$5,000 and up.      |
| 24. Exporting a Type B, Type B(U), Type B(M), or fissile package without obtaining a U.S. Competent Authority Certificate or, after obtaining a U.S. Competent Authority Certificate, failing to submit a copy to the national competent authority of each country into or through which the package is transported. | 173.471(d) .....                          | \$3,000.             |
| 25. Offering special form radioactive materials without maintaining a complete safety analysis or Certificate of Competent Authority.                                                                                                                                                                                | 173.476(a), (b) .....                     | \$2,500.             |
| D. Class 2—Compressed Gases in Cylinders:                                                                                                                                                                                                                                                                            |                                           |                      |
| 1. Filling and offering a cylinder with compressed gas when the cylinder is out of test.                                                                                                                                                                                                                             | 173.301(a)(6) .....                       | \$4,200 to \$10,400. |
| 2. Failure to check each day the pressure of a cylinder charged with acetylene that is representative of that day's compression, after the cylinder has cooled to a settled temperature, or failure to keep a record of this test for 30 days.                                                                       | 173.303(d) .....                          | \$5,000.             |
| 3. Offering a limited quantity of a compressed gas in a metal container for the purpose of propelling a nonpoisonous material and failure to heat the cylinder until the pressure is equivalent to the equilibrium pressure at 130 °F, without evidence of leakage, distortion, or other defect.                     | 173.306(a)(3), (h) .....                  | \$1,500 to \$6,000.  |
| <b>Manufacturing, Reconditioning, Retesting Requirements</b>                                                                                                                                                                                                                                                         |                                           |                      |
| A. Third-Party Packaging Certifiers (General):                                                                                                                                                                                                                                                                       |                                           |                      |
| Issuing a certification that directs the packaging manufacturer to improperly mark a packaging (e.g., steel drum to be marked UN 4G).                                                                                                                                                                                | 171.2(e), 178.2(b), 178.3(a), 178.503(a). | \$500 per item.      |
| B. Packaging Manufacturers (General):                                                                                                                                                                                                                                                                                |                                           |                      |
| 1. Failure of a manufacturer or distributor to notify each person to whom the packaging is transferred of all the requirements not met at the time of transfer, including closure instructions.                                                                                                                      | 178.2(c) .....                            | \$2,500.             |
| 2. Failure to insure a packaging certified as meeting the UN standard is capable of passing the required performance testing.                                                                                                                                                                                        | 178.601(b).                               |                      |
| a. Packing Group I (and § 172.504 Table 1 materials) .....                                                                                                                                                                                                                                                           | .....                                     | \$10,800.            |
| b. Packing Group II .....                                                                                                                                                                                                                                                                                            | .....                                     | \$8,400.             |
| c. Packing Group III .....                                                                                                                                                                                                                                                                                           | .....                                     | \$6,000.             |
| 3. Certifying a packaging as meeting a UN standard when design qualification testing was not performed.                                                                                                                                                                                                              | 178.601(d).                               |                      |
| a. Packing Group I (and § 172.504 table 1 materials) .....                                                                                                                                                                                                                                                           | .....                                     | \$10,800.            |
| b. Packing Group II .....                                                                                                                                                                                                                                                                                            | .....                                     | \$8,400.             |
| c. Packing Group III .....                                                                                                                                                                                                                                                                                           | .....                                     | \$6,000.             |
| 4. Failure to conduct periodic retesting on UN standard packaging (depending on length of time and Packing Group).                                                                                                                                                                                                   | 178.601(e) .....                          | \$2,000 to \$10,800. |
| 5. Failure to properly conduct testing for UN standard packaging (e.g., testing with less weight than marked on packaging; drop testing from lesser height than required; failing to condition fiberboard boxes before design test):                                                                                 |                                           |                      |
| a. Design qualification testing .....                                                                                                                                                                                                                                                                                | 178.601(d) .....                          | \$2,000 to \$10,800. |
| b. Periodic retesting .....                                                                                                                                                                                                                                                                                          | 178.601(e) .....                          | \$500 to \$10,800.   |
| 6. Marking, or causing the marking of, a packaging with the symbol of a manufacturer or packaging certifier other than the company that actually manufactured or certified the packaging.                                                                                                                            | 178.2(b), 178.3(a), 178.503(a)(8).        | \$7,200.             |
| 7. Failure to maintain testing records .....                                                                                                                                                                                                                                                                         | 178.601(l).                               |                      |



## II—LIST OF FREQUENTLY CITED VIOLATIONS—Continued

| Violation description                                                                                                                                                                                                 | Section or cite                                                       | Baseline assessment  |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------|----------------------|
| a. Design qualification testing .....                                                                                                                                                                                 | .....                                                                 | \$1,000 to \$5,000.  |
| b. Periodic retesting .....                                                                                                                                                                                           | .....                                                                 | \$500 to \$2,000.    |
| 8. Improper marking of UN certification .....                                                                                                                                                                         | 178.503 .....                                                         | \$500 per item.      |
| 9. Manufacturing DOT specification packaging after October 1, 1994 that is not marked as meeting a UN performance standard.                                                                                           | 171.14.                                                               |                      |
| a. If packaging does meet DOT specification .....                                                                                                                                                                     | .....                                                                 | \$3,000.             |
| b. If packaging does not meet DOT specification .....                                                                                                                                                                 | .....                                                                 | \$6,000 to \$10,800. |
| C. Drum Manufacturers & Reconditioners:                                                                                                                                                                               |                                                                       |                      |
| 1. Failure to properly conduct production leakproofness test on a new or reconditioned drum.                                                                                                                          | 178.604(b), (d),<br>173.28(b)(2)(i).                                  |                      |
| a. Improper testing .....                                                                                                                                                                                             | .....                                                                 | \$2,000.             |
| b. No testing performed .....                                                                                                                                                                                         | .....                                                                 | \$3,000 to \$5,000.  |
| 2. Marking an incorrect registration number on a reconditioned drum ..                                                                                                                                                | 173.28(b)(2)(ii).                                                     |                      |
| a. Incorrect number .....                                                                                                                                                                                             | .....                                                                 | \$800.               |
| b. Unauthorized use of another reconditioner's number .....                                                                                                                                                           | .....                                                                 | \$7,200.             |
| 3. Representing, marking, or certifying a drum as a reconditioned UN standard packaging when the drum does not meet a UN standard.                                                                                    | 173.28(c), (d) .....                                                  | \$6,000 to \$10,800. |
| 4. Representing, marking, or certifying a drum as altered from one UN standard to another, when the drum has not actually been altered.                                                                               | 173.28(d) .....                                                       | \$500.               |
| D. IBC and Portable Tank Regualification:                                                                                                                                                                             |                                                                       |                      |
| 1. Failure to properly mark an IBC or portable tank with the most current retest and/or inspection information.                                                                                                       | 180.352(e),<br>178.703(b),<br>180.605(k).                             | \$500 per item.      |
| 2. Failure to keep complete and accurate records of IBC or portable tank retest and reinspection.                                                                                                                     | 180.352(f), 180.605(l).                                               |                      |
| a. No records kept .....                                                                                                                                                                                              | .....                                                                 | \$4,000.             |
| b. Incomplete or inaccurate records .....                                                                                                                                                                             | .....                                                                 | \$1,000 to \$3,000.  |
| 3. Failure to make reinspection and retest records available to a DOT representative upon request.                                                                                                                    | 180.352(f), 49 U.S.C.<br>5121(b)(2).                                  | \$1,000.             |
| E. Cylinder Manufacturers & Rebuilders:                                                                                                                                                                               |                                                                       |                      |
| 1. Manufacturing, representing, marking, certifying, or selling a DOT high-pressure cylinder that was not inspected and verified by an approved independent inspection agency.                                        | Various .....                                                         | \$7,500 to \$15,000. |
| 2. Failure to have a registration number or failure to mark the registration number on the cylinder.                                                                                                                  | Various .....                                                         | \$800.               |
| 3. Marking another company's number on a cylinder .....                                                                                                                                                               | Various .....                                                         | \$7,200.             |
| 4. Failure to mark the date of manufacture or lot number on a DOT-39 cylinder.                                                                                                                                        | 178.65(j) .....                                                       | \$3,000.             |
| 5. Failure to have a chemical analysis performed in the U.S. for a material manufactured outside the U.S./failure to obtain a chemical analysis from the foreign manufacturer.                                        | Various .....                                                         | \$5,000.             |
| 6. Failure to meet wall thickness requirements .....                                                                                                                                                                  | Various .....                                                         | \$7,500 to \$15,000. |
| 7. Failure to heat treat cylinders prior to testing .....                                                                                                                                                             | Various .....                                                         | \$5,000 to \$15,000. |
| 8. Failure to conduct a complete visual internal examination .....                                                                                                                                                    | Various .....                                                         | \$2,500 to \$6,200.  |
| 9. Failure to conduct a hydrostatic test, or conducting a hydrostatic test with inaccurate test equipment.                                                                                                            | Various .....                                                         | \$2,500 to \$6,200.  |
| 10. Failure to conduct a flattening test .....                                                                                                                                                                        | Various .....                                                         | \$7,500 to \$15,000. |
| 11. Failure to conduct a burst test on a DOT-39 cylinder .....                                                                                                                                                        | 178.65(f)(2) .....                                                    | \$5,000 to \$15,000. |
| 12. Failure to have inspections and verifications performed by an inspector.                                                                                                                                          | Various .....                                                         | \$7,500 to \$15,000. |
| 13. Failure to maintain required inspector's reports .....                                                                                                                                                            | Various.                                                              |                      |
| a. No reports at all .....                                                                                                                                                                                            | .....                                                                 | \$5,000.             |
| b. Incomplete or inaccurate reports .....                                                                                                                                                                             | .....                                                                 | \$1,000 to \$4,000.  |
| 14. Representing a DOT-4 series cylinder as repaired or rebuilt to the requirements of the HMR without being authorized by the Associate Administrator.                                                               | 180.211(a) .....                                                      | \$6,000 to \$10,800. |
| F. Cylinder Regualification:                                                                                                                                                                                          |                                                                       |                      |
| 1. Failure to remark as DOT 3AL an aluminum cylinder manufactured under a former exemption or special permit.                                                                                                         | 173.23(c) .....                                                       | \$800.               |
| 2. Certifying or marking as retested a nonspecification cylinder .....                                                                                                                                                | 180.205(a) .....                                                      | \$800.               |
| 3. Failure to have retester's identification number (RIN) .....                                                                                                                                                       | 180.205(b) .....                                                      | \$4,000.             |
| 4. Failure to have current authority due to failure to renew a retester's identification number (RIN).                                                                                                                | 180.205(b) .....                                                      | \$2,000.             |
| 5. Failure to have a retester's identification number and marking another RIN on a cylinder.                                                                                                                          | 180.205(b) .....                                                      | \$7,200.             |
| 6. Marking a RIN before successfully completing a hydrostatic retest ..                                                                                                                                               | 180.205(b) .....                                                      | \$800.               |
| 7. Representing, marking, or certifying a cylinder as meeting the requirements of an exemption or special permit when the cylinder was not maintained or retested in accordance with the exemption or special permit. | 171.2(c), (e),<br>178.205(c), Applicable Exemption or Special Permit. | \$2,000 to \$6,000.  |
| 8. Failure to conduct a complete visual external and internal examination.                                                                                                                                            | 180.205(f) .....                                                      | \$2,100 to \$5,200.  |

Pipeline and Hazardous Materials Safety Admin., DOT Pt. 107, Subpt. D, App. A

II—LIST OF FREQUENTLY CITED VIOLATIONS—Continued

| Violation description                                                                                                                                                                                                                                                                                                                                   | Section or cite                                          | Baseline assessment  |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|----------------------|
| 9. Failure to conduct visual inspection or hydrostatic retest .....                                                                                                                                                                                                                                                                                     | 180.205(f) & (g) .....                                   | \$4,200 to \$10,400. |
| 10. Performing hydrostatic retesting without confirming the accuracy of the test equipment.                                                                                                                                                                                                                                                             | 180.205(g)(3) .....                                      | \$2,100 to \$5,200.  |
| 11. Failure to hold hydrostatic test pressure for 30 seconds or sufficiently longer to allow for complete expansion.                                                                                                                                                                                                                                    | 180.205(g)(5) .....                                      | \$3,100.             |
| 12. Failure to perform a second retest, after equipment failure, at a pressure increased by the lesser of 10% or 100 psi (includes exceeding 90% of test pressure prior to conducting a retest).                                                                                                                                                        | 180.205(g) .....                                         | \$3,100.             |
| 13. Failure to condemn a cylinder when required (e.g., permanent expansion of 10% [5% for certain exemption or special permit cylinders], internal or external corrosion, denting, bulging, evidence of rough usage).                                                                                                                                   | 180.205(i) .....                                         | \$6,000 to \$10,800. |
| 14. Failure to properly mark a condemned cylinder or render it incapable of holding pressure.                                                                                                                                                                                                                                                           | 180.205(i)(2) .....                                      | \$800.               |
| 15. Failure to notify the cylinder owner in writing when a cylinder has been condemned.                                                                                                                                                                                                                                                                 | 180.205(i)(2) .....                                      | \$1,000.             |
| 16. Failure to perform hydrostatic retesting at the minimum specified test pressure.                                                                                                                                                                                                                                                                    | 180.209(a)(1) .....                                      | \$2,100 to \$5,200.  |
| 17. Marking a star on a cylinder that does not qualify for that mark .....                                                                                                                                                                                                                                                                              | 180.209(b) .....                                         | \$2,000 to \$4,000.  |
| 18. Marking a "+" sign on a cylinder without determining the average or minimum wall stress by calculation or reference to CGA Pamphlet C-5.                                                                                                                                                                                                            | 173.302a(b) .....                                        | \$2,000 to \$4,000.  |
| 19. Marking a cylinder in or on the sidewall when not permitted by the applicable specification.                                                                                                                                                                                                                                                        | 180.213(b) .....                                         | \$6,000 to \$10,800. |
| 20. Failure to maintain legible markings on a cylinder .....                                                                                                                                                                                                                                                                                            | 180.213(b)(1) .....                                      | \$800.               |
| 21. Marking a DOT 3HT cylinder with a steel stamp other than a low-stress steel stamp.                                                                                                                                                                                                                                                                  | 180.213(c)(2) .....                                      | \$6,000 to \$10,800. |
| 22. Improper marking of the RIN or retest date on a cylinder .....                                                                                                                                                                                                                                                                                      | 180.213(d) .....                                         | \$800.               |
| 23. Marking an FRP cylinder with steel stamps in the FRP area of the cylinder such that the integrity of the cylinder is compromised.                                                                                                                                                                                                                   | Applicable Exemption or Special Permit.                  | \$6,000 to \$10,800. |
| 24. Failure to maintain current copies of 49 CFR, DOT exemption or special permits, and CGA Pamphlets applicable to inspection, retesting, and marking activities.                                                                                                                                                                                      | 180.215(a) .....                                         | \$600 to \$1,200.    |
| 25. Failure to keep complete and accurate records of cylinder reinspection and retest.                                                                                                                                                                                                                                                                  | 180.215(b).                                              |                      |
| a. No records kept .....                                                                                                                                                                                                                                                                                                                                | .....                                                    | \$4,000.             |
| b. Incomplete or inaccurate records .....                                                                                                                                                                                                                                                                                                               | .....                                                    | \$1,000 to \$3,000.  |
| 26. Failure to report in writing a change in name, address, ownership, test equipment, management, or retester personnel.                                                                                                                                                                                                                               | 171.2(c) & (e), Approval Letter.                         | \$600 to \$1,200.    |
| <b>Carrier Requirements</b>                                                                                                                                                                                                                                                                                                                             |                                                          |                      |
| A. Incident Notification:                                                                                                                                                                                                                                                                                                                               |                                                          |                      |
| 1. Failure to give immediate notification of a reportable hazardous materials incident.                                                                                                                                                                                                                                                                 | 171.15 .....                                             | \$3,000.             |
| 2. Failure to file a written hazardous material incident report within 30 days following an unintentional release of hazardous materials in transportation (or other reportable incident).                                                                                                                                                              | 171.16 .....                                             | \$500 to \$2,500.    |
| B. Shipping Papers:                                                                                                                                                                                                                                                                                                                                     |                                                          |                      |
| Failure to retain shipping papers for 375 days after a hazardous material (or 3 years for a hazardous waste) is accepted by the initial carrier.                                                                                                                                                                                                        | 174.24(b),<br>175.30(a)(2),<br>176.24(b),<br>177.817(f). | \$1,000.             |
| C. Stowage/transportation Requirements:                                                                                                                                                                                                                                                                                                                 |                                                          |                      |
| 1. Transporting packages of hazardous material that have not been secured against movement.                                                                                                                                                                                                                                                             | Various .....                                            | \$3,000.             |
| 2. Failure to properly segregate hazardous materials .....                                                                                                                                                                                                                                                                                              | Various .....                                            | \$7,500 and up.      |
| 3. Transporting explosives in a motor vehicle containing metal or other articles or materials likely to damage the explosives or any package in which they are contained, without segregating in different parts of the load or securing them in place in or on the motor vehicle and separated by bulkheads or other suitable means to prevent damage. | 177.835(i) .....                                         | \$5,200.             |
| 4. Transporting railway track torpedoes outside of flagging kits, in violation of DOT-E 7991.                                                                                                                                                                                                                                                           | 171.2(b) & (e) .....                                     | \$7,000.             |
| 5. Transporting Class 7 (radioactive) material having a total transport index greater than 50.                                                                                                                                                                                                                                                          | 177.842(a) .....                                         | \$5,000 and up.      |
| 6. Transporting Class 7 (radioactive) material without maintaining the required separation distance.                                                                                                                                                                                                                                                    | 177.842(b) .....                                         | \$5,000 and up.      |
| 7. Failure to comply with requirements of an exemption or special permit authorizing the transportation of Class 7 (radioactive) material having a total transportation index of 50.                                                                                                                                                                    | 171.2(b) & (e).                                          |                      |

## II—LIST OF FREQUENTLY CITED VIOLATIONS—Continued

| Violation description                                         | Section or cite | Baseline assessment |
|---------------------------------------------------------------|-----------------|---------------------|
| a. Failure to have the required radiation survey record ..... | .....           | \$5,000.            |
| b. Failure to have other required documents .....             | .....           | \$500 each.         |
| c. Other violations .....                                     | .....           | \$5,000 and up.     |

## III. CONSIDERATION OF STATUTORY CRITERIA

A. These guidelines are used by the Office of Hazardous Materials Safety (OHMS) in setting initial proposed penalties for hazmat violations. They indicate baseline amounts or ranges for probable violations frequently cited in enforcement reports and set forth general OHMS policy for considering statutory criteria.

B. The initial baseline determination partially considers the nature, extent, circumstances, and gravity of the alleged violation. That determination then is adjusted to consider all other evidence concerning the nature, extent, circumstances, and gravity of the alleged violation; degree of culpability; history of prior violations; ability to pay; effect of the penalty on ability to continue to do business; and such other matters as justice may require (a major component of which is corrective action taken by a respondent to prevent a recurrence of similar violations). In making a penalty recommendation, the baseline or range may be increased or decreased on the basis of evidence pertaining to these factors.

C. The following miscellaneous factors are used to implement one or more of the statutory assessment criteria.

## IV. MISCELLANEOUS FACTORS AFFECTING PENALTY AMOUNTS

## A. Corrective Action

1. A proposed penalty is mitigated for documented corrective action of alleged violations taken by a respondent. Corrective action may occur: (1) After an inspection and before a Notice of Probable Violation (NOPV) is issued; (2) on receipt of an NOPV; or (3) after receipt of an NOPV (possibly after it is solicited by an PHMSA attorney). In general, corrective action may reduce a penalty up to 25%. Mitigation may be taken into account in the referral memo or may be recommended prior to issuance of an Order by PHMSA's Chief Counsel.

2. The two primary factors in determining the penalty reduction are extent and timing of the corrective action. In other words, mitigation will be determined on the basis of how much corrective action was taken and when it was taken. Systemic action to prevent future violations is given greater consideration than action simply to remedy violations identified during the inspection.

3. Mitigation is applied to individual violations. Thus, in a case with two violations, if corrective action for the first violation is more extensive than for the second, the penalty for the first will be mitigated more than that for the second.

## B. Respondents That Re-Ship

A shipper that reships materials received from another company, in the same packaging and without opening or altering the package, independently is responsible for ensuring that the shipment complies with Federal hazmat law, and independently may be subject to enforcement action if the package does not comply. Nevertheless, the reshipper is considered to have a lesser level of responsibility for compliance in those respects in which it reasonably relies on the compliance of the package as received. In most cases of this type, OHMS will discount the applicable baseline standard by about 25%. The specific knowledge and expertise of all parties must be considered in discounting for reliance on a prior shipper. This discount is applied before any consideration of mitigation based on corrective action.

## C. Penalty Increases for Multiple Counts

Under the Federal hazmat law, 49 U.S.C. 5123(a), each violation of the HMR and each day of a continuing violation (except for violations pertaining to packaging manufacture or qualification) is subject to a civil penalty of up to \$50,000 or \$100,000 for a violation occurring on or after August 10, 2005. Absent aggravating factors, OHMS, in its exercise of discretion, ordinarily will apply a single penalty for multiple counts or days of violation. In a number of cases, particularly those involving shippers, an inspector may cite two or more similar packaging violations for different hazardous materials. For example, the inspector may cite the same marking violation for two or more packages. OHMS usually will consider those additional violations as counts of the same violation and will not recommend multiples of the same baseline penalty. Rather, OHMS usually will recommend the baseline penalty for a single violation, increased by 25% for each additional violation.

## D. Financial Considerations

1. Mitigation is appropriate when the baseline penalty would (1) exceed an amount that the respondent is able to pay, or (2) have an

adverse effect on the respondent's ability to continue in business. These criteria relate to a respondent's entire business, and not just the product line or part of its operations involved in the violation(s). Beyond the overall financial size of the respondent's business, the relevant items of information on a respondent's balance sheet include the current ratio (current assets to current liabilities), the nature of current assets, and net worth (total assets minus total liabilities).

2. These figures are considered on a case-by-case basis. In general, however, a current ratio close to or below 1.0 means that the company may have difficulty in paying a large penalty, and may justify reduction of the penalty or an installment payment plan. A small amount of cash on hand representing limited liquidity, even with substantial other current assets (such as accounts receivable or inventory), may warrant a short-term payment plan. Respondent's income statement also will be reviewed to determine whether a payment plan is appropriate.

3. Many companies are able to continue in business for extended periods of time with a small or negative net worth, and many respondents have paid substantial civil penalties in installments even though net worth was negative. For this reason, negative net worth alone does not always warrant reduction of a proposed penalty or even, in the absence of factors discussed above, a payment plan.

4. In general, an installment payment plan may be justified where reduction of a proposed penalty is not, but the appropriateness of either (or both) will depend on the circumstances of the case. The length of a payment plan should be as short as possible, but the plan may consider seasonal fluctuations in a company's income if the company's business is seasonal (e.g., swimming pool chemical sales, fireworks sales) or if the company has documented specific reasons for current non-liquidity.

5. Evidence of financial condition is used only to decrease a penalty, and not to increase it.

#### *E. Penalty Increases for Prior Violations*

The baseline penalty presumes an absence of prior violations. If prior violations exist, generally they will serve to increase a proposed penalty. The general standards for increasing a baseline proposed penalty on the basis of prior violations are as follows:

1. For each prior civil or criminal enforcement case—25% increase over the pre-mitigation recommended penalty.

2. For each prior ticket—10% increase over the pre-mitigation recommended penalty.

3. A baseline proposed penalty will not be increased more than 100% on the basis of prior violations.

4. A case or ticket of prior violations initiated in a calendar year more than six years

before the calendar year in which the current case is initiated normally will not be considered in determining a proposed penalty for the current violation(s).

#### *F. Penalty Increases for Use of Expired Special Permits*

Adjustments to the base line figures for use of expired special permits can be made depending on how much material has been shipped during the period between the expiration date and the renewal date. If the company previously has been found to have operated under an expired special permit, the penalty is normally doubled. If the company has been previously cited for other violations, the penalty generally will be increased by about 25%.

[Amdt. 107-33, 60 FR 12141, Mar. 6, 1995, as amended by Amdt. 107-40, 62 FR 2972, 2977, Jan. 21, 1997; 62 FR 51556, Oct. 1, 1997; 65 FR 58618, Sept. 29, 2000; 66 FR 45180, Aug. 28, 2001; 68 FR 52848, 52855, Sept. 8, 2003; 69 FR 54044, Sept. 7, 2004; 70 FR 56090, Sept. 23, 2005; 70 FR 73162, Dec. 9, 2005; 71 FR 8487, Feb. 17, 2006]

## **Subpart E—Designation of Approval and Certification Agencies**

### **§ 107.401 Purpose and scope.**

(a) This subpart establishes procedures for the designation of agencies to issue approval certificates and certifications for types of packagings designed, manufactured, tested, or maintained in conformance with the requirements of this subchapter, subchapter C of this chapter, and standards set forth in the United Nations (U.N.) Recommendations (Transport of Dangerous Goods). Except for certifications of compliance with U.N. packaging standards, this subpart does not apply unless made applicable by a rule in subchapter C of this chapter.

(b) The Associate Administrator may issue approval certificates and certifications addressed in paragraph (a) of this section.

[Amdt. 107-31, 50 FR 10062, Mar. 13, 1985, as amended by Amdt. 107-23, 56 FR 66157, Dec. 20, 1991; 66 FR 45377, Aug. 28, 2001]

### **§ 107.402 Application for designation as an approval or certification agency.**

(a) Any organization or person seeking designation as an approval or certification agency shall apply in writing to the Associate Administrator for

## § 107.403

Hazardous Materials Safety (PHH-32), Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington DC 20590-0001. Alternatively, the application with any attached supporting documentation in an appropriate format may be submitted by facsimile (fax) to: (202) 366-3753 or (202) 366-3308 or by electronic mail (e-mail) to: *approvals@dot.gov*. Each application must be signed and certified to be correct by the applicant or, if the applicant is an organization, by an authorized officer or official representative of the organization. Any false statement or representation, or the knowing and willful concealment of a material fact, may subject the applicant to prosecution under the provisions of 18 U.S.C. 1001, result in the denial or termination of a designation.

(b) Each application for designation must be in English and include the following information:

(1) Name and address of the applicant, including place of incorporation if a corporation. In addition, if the applicant is not a resident of the United States, the name and address of a permanent resident of the United States designated in accordance with §105.40 to serve as agent for service of process.

(2) If the applicant's principal place of business is in a country other than the United States, a copy of the designation from the Competent Authority of that country delegating to the applicant an approval or designated agency authority for the type of packaging for which a DOT designation is sought, and a statement that the Competent Authority also delegates similar authority to U.S. Citizens or organizations having designations under this subpart from the PHMSA.

(3) A listing, by DOT specification (or special permit) number, or U.N. designation, of the types of packagings for which approval authority is sought.

(4) A personnel qualifications plan listing the qualifications that the applicant will require of each person to be used in the performance of each packaging approval or certification function. As a minimum, these qualifications must include:

(i) The ability to review and evaluate design drawings, design and stress calculations;

(ii) A knowledge of the applicable regulations of subchapter C of this chapter and, when applicable, U.N. standards; and

(iii) The ability to conduct or monitor and evaluate test procedures and results; and

(iv) The ability to review and evaluate the qualifications of materials and fabrication procedures.

(5) A statement that the applicant will perform its functions independent of the manufacturers and owners of the packagings concerned.

(6) A statement that the applicant will allow the Associate Administrator or his representative to inspect its records and facilities in so far as they relate to the approval or certification of specification packagings and shall cooperate in the conduct of such inspections.

(c) The applicant shall furnish any additional information relevant to the applicant's qualifications, if requested by the Associate Administrator.

[Amdt. 107-13, 50 FR 10062, Mar. 13, 1985; 50 FR 16089, Apr. 24, 1985, as amended by Amdt. 107-22, 55 FR 39978, Oct. 1, 1990; Amdt. 107-23, 56 FR 66157, Dec. 20, 1991; 66 FR 45377, Aug. 28, 2001; 67 FR 61011, Sept. 27, 2002; 70 FR 56090, Sept. 23, 2005; 72 FR 55683, Oct. 1, 2007]

## § 107.403 Designation of approval agencies.

(a) If the Associate Administrator determines that an application contains all the required information, the applicant is sent a letter of designation and assigned an identification code.

(b) If the Associate Administrator determines that an application does not contain all the required information, the application is denied and the applicant is sent a written notice containing all the reasons for the denial.

(c) Within 30 days of an initial denial of an application under paragraph (b) of this section, the applicant may file an amended application. If after considering the amended application, the Associate Administrator determines that it should be denied, he notifies the applicant, and the denial constitutes the final action of the Associate Administrator on the application. Within 60 days of receipt of the final denial the applicant may appeal the denial to the Administrator, PHMSA, setting forth

in writing where the Associate Administrator for Hazardous Materials Safety erred in this determination.

[Amdt. 107-13, 50 FR 10062, Mar. 13, 1985, as amended by Amdt. 107-23, 56 FR 66157, Dec. 20, 1991; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; 66 FR 45377, Aug. 28, 2001]

#### § 107.404 Conditions of designation.

(a) Each designation made under this subpart contains the following conditions:

(1) The designated approval or certification agency may use only testing equipment that it has determined, through personal inspection, to be suitable for the purpose.

(2) Each approval certificate and certification issued by the designated approval agency must contain the name and identification code of the approval agency.

(3) Each approval certificate and certification must be in a format acceptable to the Associate Administrator.

(b) The designated approval agency shall notify the Associate Administrator within 20 days after the date there is any change in the information submitted under § 107.402.

(c) The designated approval agency shall comply with all of the terms and conditions stated in its letter of designation under the subpart.

(d) Nothing in this part relieves a manufacturer or owner of a packaging of responsibility for compliance with any of the applicable requirements of this title.

[Amdt. 107-13, 50 FR 10062, Mar. 13, 1985, as amended by Amdt. 107-23, 56 FR 66157, Dec. 20, 1991; 66 FR 45377, Aug. 28, 2001]

#### § 107.405 Termination of designation.

(a) Any designation issued under § 107.403 of this subchapter may be suspended or terminated if the Associate Administrator determines that:

(1) The application for designation contained a misrepresentation, or the applicant willfully concealed a material fact.

(2) The approval agency failed to comply with a term or condition stated in the agency's letter of designation.

(3) The Competent Authority of an approval agency of a country outside the United States has failed to initiate,

maintain or recognize a qualified U.S. approval agency.

(b) Before a designation is suspended or terminated, the Associate Administrator shall give to the approval agency:

(1) Written notice of the facts or conduct believed to warrant suspension or termination of the designation.

(2) Sixty days in which to show in writing why the designation should not be suspended or terminated.

[Amdt. 107-13, 50 FR 10062, Mar. 13, 1985, as amended by Amdt. 107-23, 56 FR 66157, Dec. 20, 1991; 66 FR 45377, Aug. 28, 2001]

### Subpart F—Registration of Cargo Tank and Cargo Tank Motor Vehicle Manufacturers, Assemblers, Repairers, Inspectors, Testers, and Design Certifying Engineers

#### § 107.501 Scope.

(a) This subpart establishes a registration procedure for persons who are engaged in the manufacture, assembly, inspection and testing, certification, or repair of a cargo tank or a cargo tank motor vehicle manufactured in accordance with a DOT specification under subchapter C of this chapter or under terms of a special permit issued under this part.

(b) Persons engaged in continuing qualification and maintenance of cargo tanks and cargo tank motor vehicles must be familiar with the requirements set forth in part 180, subpart E, of this chapter.

[Amdt. 107-20, 55 FR 37047, Sept. 7, 1990]

#### § 107.502 General registration requirements.

(a) *Definitions:* For purposes of this subpart—

(1) *Assembly* means the performance of any of the following functions when the function does not involve welding on the cargo tank wall:

(i) The mounting of one or more tanks or cargo tanks on a motor vehicle or to a motor vehicle suspension component;

(ii) The installation of equipment or components necessary to meet the specification requirements prior to the

## § 107.503

certification of the cargo tank motor vehicle; or

(iii) The installation of linings, coatings, or other materials to the inside of a cargo tank wall.

(2) The terms *Authorized Inspector*, *Cargo tank*, *Cargo tank motor vehicle*, *Design Certifying Engineer*, *Registered Inspector*, and *Person* are defined in §171.8 of this chapter.

(3) The terms *cargo tank wall* and *manufacturer* are defined in §178.320(a), and *repair* is defined in §180.403 of this chapter.

(b) No person may engage in the manufacture, assembly, certification, inspection or repair of a cargo tank or cargo tank motor vehicle manufactured under the terms of a DOT specification under subchapter C of this chapter or a special permit issued under this part unless the person is registered with the Department in accordance with the provisions of this subpart. A person employed as an inspector or design certifying engineer is considered to be registered if the person's employer is registered.

(c) A person who performs functions which are subject to the provisions of this subpart may perform only those functions which have been identified to the Department in accordance with the procedures of this subpart.

(d) Registration statements must be in English, contain all of the information required by this subpart, and be submitted to: FMCSA Hazardous Materials Division—MC-ECH, West Building, MC-ECH, 1200 New Jersey Avenue, SE., Washington, DC 20590.

(e) Upon determination that a registration statement contains all the information required by this subpart, the Department will send the registrant a letter confirming receipt of the registration application and assigning a registration number to that person. A separate registration number will be assigned for each cargo tank manufacturing, assembly, repair facility or

## 49 CFR Ch. I (10–1–08 Edition)

other place of business identified by the registrant.

[Amdt. 107–20, 54 FR 25003, June 12, 1989; 55 FR 37047, Sept. 7, 1990, as amended by Amdt. 107–22, 55 FR 39978, Oct. 1, 1990; Amdt. 107–23, 56 FR 66157, Dec. 20, 1991; Amdt. 107–28, 58 FR 46873, Sept. 3, 1993; Amdt. 107–39, 61 FR 51337, Oct. 1, 1996; 67 FR 61011, Sept. 27, 2002; 68 FR 19273, Apr. 18, 2003; 72 FR 55683, Oct. 1, 2007]

### § 107.503 Registration statement.

(a) Each registration statement must be in English and contain the following information:

(1) Name;

(2) Street address, mailing address and telephone number for each facility or place of business;

(3) A statement indicating whether the facility uses mobile testing/inspection equipment to perform inspections, tests, or repairs at a location other than the address listed in paragraph (a)(2) of this section.

(4) A statement signed by the person responsible for compliance with the applicable requirements of this chapter, certifying knowledge of those requirements and that each employee who is a Registered Inspector or Design Certifying Engineer meets the minimum qualification requirements set forth in §171.8 of this chapter for “Registered Inspector” or “Design Certifying Engineer”. The following language may be used.

I certify that all Registered Inspectors and Design Certifying Engineers used in performance of the prescribed functions meet the minimum qualification requirements set forth in 49 CFR 171.8, that I am the person responsible for ensuring compliance with the applicable requirements of this chapter, and that I have knowledge of the requirements applicable to the functions to be performed.

(5) A description of the specific functions to be performed on cargo tanks or cargo tank motor vehicles, e.g.:

(i) Manufacture,

(ii) Assembly,

(iii) Inspection and testing (specify type, e.g., external or internal visual inspection, lining inspection, hydrostatic pressure test, leakage test, thickness test),

(iv) Certification,

(v) Repair, or

(vi) Equipment manufacture;

(6) An identification of the types of DOT specification and special permit cargo tanks or cargo tank motor vehicles which the registrant intends to manufacture, assemble, repair, inspect, test or certify;

(7) A statement indicating whether the registrant employs Registered Inspectors or Design Certifying Engineers to conduct certification, inspection or testing functions addressed by this subpart. If the registrant engages a person who is not an employee of the registrant to perform these functions, provide the name, address and registration number of that person; and

(8) If the registrant is not a resident of the United States, the name and address of a permanent resident of the United States designated in accordance with §105.40 to serve as agent for service of process.

(b) In addition to the information required under paragraph (a) of this section, each person who manufactures a cargo tank or cargo tank motor vehicle must submit a copy of the manufacturer's current ASME Certificate of Authorization for the use of the ASME "U" stamp.

(c) In addition to the information required under paragraph (a) of this section, each person who repairs a cargo tank or cargo tank motor vehicle must submit a copy of the repair facility's current National Board Certificate of Authorization for the use of the "R" stamp or ASME Certificate of Authorization for the use of the ASME "U" stamp. Any person who repairs MC-series cargo tanks which are not certified to the ASME Code must submit a copy of the National Board or ASME Certificate of Authorization to PHMSA before June 30, 1992.

[Amdt. 107-20, 54 FR 25003, June 12, 1989; 55 FR 37047, Sept. 7, 1990; 57 FR 365, Jan. 6, 1992; Amdt. 107-32, 59 FR 49131, Sept. 26, 1994; Amdt. 107-39, 61 FR 51337, Oct. 1, 1996; 63 FR 52846, Oct. 1, 1998; 68 FR 19273, Apr. 18, 2003]

**§ 107.504 Period of registration, updates, and record retention.**

(a) Registration will be for a maximum of six years from the date of the original registration.

(b) Any correspondence with the Department must contain the registrant's name and registration number.

(c) A registration must be renewed every six years or within thirty days of reissuance of an ASME or National Board Certification, whichever occurs first, by submitting an up-to-date registration statement containing the information prescribed by §107.503. Any person initially registered under the provisions of §107.502 and who is in good standing is eligible for renewal.

(d) A registrant shall provide written notification to the Department within thirty days of any of the following occurrences:

(1) Any change in the registration information submitted under §107.503;

(2) Replacement of the person responsible for compliance with the requirements in §107.503(a)(4). If this occurs, the registrant shall resubmit the required certification;

(3) Loss of ASME or National Board Certificate of Authorization; or

(4) A change in function; such as, from assembly to manufacture, an addition of a function, or a change to the types of inspections, tests or certifications of cargo tanks or cargo tank motor vehicles.

(e) Each registrant shall maintain a current copy of the registration information submitted to the Department and a current copy of the registration number identification received from the Department at the location identified in §107.503(a)(2) during such time the person is registered with the Department and for two years thereafter.

(f) The issuance of a registration number under this subpart is not an approval or endorsement by the Department of the qualifications of any person to perform the specified functions.

[Amdt. 107-20, 54 FR 25003, June 12, 1989; 55 FR 37048, Sept. 7, 1990, as amended by Amdt. 107-20, 56 FR 27875, June 17, 1991; Amdt. 107-37, 61 FR 18931, Apr. 29, 1996; 71 FR 54390, Sept. 14, 2006]

**Subpart G—Registration of Persons Who Offer or Transport Hazardous Materials**

SOURCE: Amdt. No. 107-26, 57 FR 30630, July 9, 1992, unless otherwise noted.



## § 107.601

## 49 CFR Ch. I (10–1–08 Edition)

### § 107.601 Applicability.

(a) The registration and fee requirements of this subpart apply to any person who offers for transportation, or transports, in foreign, interstate or intrastate commerce—

(1) A highway route-controlled quantity of a Class 7 (radioactive) material, as defined in § 173.403 of this chapter;

(2) More than 25 kg (55 pounds) of a Division 1.1, 1.2, or 1.3 (explosive) material (see § 173.50 of this chapter) in a motor vehicle, rail car or freight container;

(3) More than one L (1.06 quarts) per package of a material extremely toxic by inhalation (i.e., “material poisonous by inhalation,” as defined in § 171.8 of this chapter, that meets the criteria for “hazard zone A,” as specified in §§ 173.116(a) or 173.133(a) of this chapter);

(4) A shipment of a quantity of hazardous materials in a bulk packaging (see § 171.8 of this chapter) having a capacity equal to or greater than 13,248 L (3,500 gallons) for liquids or gases or more than 13.24 cubic meters (468 cubic feet) for solids;

(5) A shipment in other than a bulk packaging of 2,268 kg (5,000 pounds) gross weight or more of one class of hazardous materials for which placarding of a vehicle, rail car, or freight container is required for that class, under the provisions of subpart F of part 172 of this chapter; or

(6) Except as provided in paragraph (b) of this section, a quantity of hazardous material that requires placarding, under provisions of subpart F of part 172 of this chapter.

(b) Paragraph (a)(6) of this section does not apply to those activities of a farmer, as defined in § 171.8 of this chapter, that are in direct support of the farmer’s farming operations.

(c) In this subpart, the term “shipment” means the offering or loading of hazardous material at one loading facility using one transport vehicle, or the transport of that transport vehicle.

[65 FR 7309, Feb. 14, 2000, as amended at 67 FR 61011, Sept. 27, 2002]

### § 107.606 Exceptions.

(a) The following are excepted from the requirements of this subpart:

(1) An agency of the Federal government.

(2) A State agency.

(3) An agency of a political subdivision of a State.

(4) An Indian tribe.

(5) An employee of any of those entities in paragraphs (a)(1) through (a)(4) of this section with respect to the employee’s official duties.

(6) A hazmat employee (including, for purposes of this subpart, the owner-operator of a motor vehicle that transports in commerce hazardous materials, if that vehicle at the time of those activities, is leased to a registered motor carrier under a 30-day or longer lease as prescribed in 49 CFR part 376 or an equivalent contractual agreement).

(7) A person domiciled outside the United States, who offers solely from a location outside the United States, hazardous materials for transportation in commerce, *provided* that the country of which such a person is a domiciliary does not require persons domiciled in the United States, who solely offer hazardous materials for transportation to the foreign country from places in the United States, to file a registration statement or to pay a registration fee.

(b) Upon making a determination that persons domiciled in the United States, who offer hazardous materials for transportation to a foreign country solely from places in the United States, must file registration statements or pay fees to that foreign country, the U.S. Competent Authority will provide notice of such determination directly to the Competent Authority of that foreign country and by publication in the FEDERAL REGISTER. Persons who offer hazardous materials for transportation to the United States from that foreign country must file a registration statement and pay the required fee no later than 60 days following publication of the determination in the FEDERAL REGISTER.

[Amdt 107–34, 60 FR 27233, May 23, 1995, as amended at 63 FR 52847, Oct. 1, 1998; 72 FR 24538, May 3, 2007]

**§ 107.608 General registration requirements.**

(a) Each person subject to this subpart must submit a complete and accurate registration statement on DOT Form F 5800.2 not later than June 30 for each registration year, or in time to comply with paragraph (b) of this section, whichever is later. Each registration year begins on July 1 and ends on June 30 of the following year.

(b) No person required to file a registration statement may transport a hazardous material or cause a hazardous material to be transported or shipped, unless such person has on file, in accordance with § 107.620, a current Certificate of Registration in accordance with the requirements of this subpart.

(c) A registrant whose name or principal place of business has changed during the year of registration must notify PHMSA of that change by submitting an amended registration statement not later than 30 days after the change.

(d) Copies of DOT Form F 5800.2 and instructions for its completion may be obtained from the Hazardous Materials Registration Program, PHH-60, U.S. Department of Transportation, Washington, DC 20590-0001, by calling 617-494-2545 or 202-366-4109, or via the Internet at <http://hazmat.dot.gov>.

(e) If the registrant is not a resident of the United States, the registrant must attach to the registration statement the name and address of a permanent resident of the United States, designated in accordance with § 105.40, to serve as agent for service of process.

[Amdt. No. 107-26, 57 FR 30630, July 9, 1992, as amended by Amdt. 107-31, 59 FR 32932, June 27, 1994; 65 FR 7309, Feb. 14, 2000; 67 FR 61011, Sept. 27, 2002; 70 FR 56090, Sept. 23, 2005; 72 FR 55683, Oct. 1, 2007]

**§ 107.612 Amount of fee.**

(a) *Registration year 1999-2000 and earlier.* For all registration years through 1999-2000, each person subject to the requirements of § 107.601(a)(1)-(5) of this subpart must pay an annual fee of \$300 (which includes a \$50 processing fee).

(b) *Registration years 2000-2001, 2001-2002 and 2002-2003.* For the registration years 2000-2001, 2001-2002, and 2002-2003, each person subject to the require-

ments of this subpart must pay an annual fee as follows:

(1) *Small business.* Each person that qualifies as a small business under criteria specified in 13 CFR part 121 applicable to the North American Industry Classification System (NAICS) code that describes that person's primary commercial activity must pay an annual fee of \$275 and the processing fee required by paragraph (b)(3) of this section.

(2) *Other than a small business.* Each person that does not meet criteria specified in paragraph (b)(1) of this section must pay an annual fee of \$1,975 and the processing fee required by paragraph (b)(3) of this section.

(3) *Processing fee.* The processing fee is \$25 for each registration statement filed. A single statement may be filed for one, two, or three registration years as provided in § 107.616(c).

(c) *Registration years 2003-2004, 2004-2005 and 2005-2006.* For registration years 2003-2004, 2004-2005, and 2005-2006, each person subject to the requirements of this subpart must pay an annual registration fee as follows:

(1) *Small business.* Each person that qualifies as a small business, under criteria specified in 13 CFR part 121 applicable to the North American Industry Classification System (NAICS) code that describes that person's primary commercial activity, must pay an annual registration fee of \$125 and the processing fee required by paragraph (c)(4) of this section.

(2) *Not-for-profit organization.* Each not-for-profit organization must pay an annual registration fee of \$125 and the processing fee required by paragraph (c)(4) of this section. A not-for-profit organization is an organization exempt from taxation under 26 U.S.C. 501(a).

(3) *Other than a small business or not-for-profit organization.* Each person that does not meet the criteria specified in paragraph (c)(1) or (c)(2) of this section must pay an annual registration fee of \$275 and the processing fee required by paragraph (c)(4) of this section.

(4) *Processing fee.* The processing fee is \$25 for each registration statement filed. A single statement may be filed for one, two, or three registration years as provided in § 107.616(c).

(d) *Registration years 2006–2007 and following.* For each registration year beginning with 2006–2007, each person subject to the requirements of this subpart must pay an annual fee as follows:

(1) *Small business.* Each person that qualifies as a small business, under criteria specified in 13 CFR part 121 applicable to the North American Industry Classification System (NAICS) code that describes that person's primary commercial activity, must pay an annual registration fee of \$250 and the processing fee required by paragraph (d)(4) of this section.

(2) *Not-for-profit organization.* Each not-for-profit organization must pay an annual registration fee of \$250 and the processing fee required by paragraph (d)(4) of this section. A not-for-profit organization is an organization exempt from taxation under 26 U.S.C. 501(a).

(3) *Other than a small business or not-for-profit organization.* Each person that does not meet the criteria specified in paragraph (d)(1) or (d)(2) of this section must pay an annual registration fee of \$975 and the processing fee required by paragraph (d)(4) of this section.

(4) *Processing fee.* The processing fee is \$25 for each registration statement filed. A single statement may be filed for one, two, or three registration years as provided in § 107.616(c).

[65 FR 7309, Feb. 14, 2000, as amended at 67 FR 58345, Sept. 16, 2002; 68 FR 1345, Jan. 9, 2003]

**§ 107.616 Payment procedures.**

(a) Each person subject to the requirements of this subpart must mail the registration statement and payment in full to the U.S. Department of Transportation, Hazardous Materials Registration, P.O. Box 70985, Charlotte, NC 28272–0985, or submit the statement and payment electronically through the Department's e-Commerce Internet site. Access to this service is provided at <http://hazmat.dot.gov/regs/register/register.htm>. A registrant required to file an amended registration statement under § 107.608(c) must mail it to the same address or submit it through the same Internet site.

(b) Payment must be made by certified check, cashier's check, personal check, or money order in U.S. funds and drawn on a U.S. bank, payable to

the U.S. Department of Transportation and identified as payment for the "Hazmat Registration Fee," or by completing an authorization for payment by credit card or other electronic means of payment acceptable to the Department on the registration statement or as part of an Internet registration as provided in paragraph (a) of this section.

(c) Payment must correspond to the total fees properly calculated in the "Amount Due" block of the DOT form F 5800.2. A person may elect to register and pay the required fees for up to three registration years by filing one complete and accurate registration statement.

[Amdt. 107–26, 57 FR 30630, July 9, 1992, as amended by Amdt. 107–26, 58 FR 12545, Mar. 5, 1993; 65 FR 7310, Feb. 14, 2000; 67 FR 58345, Sept. 16, 2002; 68 FR 1346, Jan. 9, 2003; 71 FR 54390, Sept. 14, 2006; 72 FR 24538, May 3, 2007]

**§ 107.620 Recordkeeping requirements.**

(a) Each person subject to the requirements of this subpart, or its agent designated under § 107.608(e), must maintain at its principal place of business for a period of three years from the date of issuance of each Certificate of Registration:

(1) A copy of the registration statement filed with PHMSA; and

(2) The Certificate of Registration issued to the registrant by PHMSA.

(b) After January 1, 1993, each motor carrier subject to the requirements of this subpart must carry a copy of its current Certificate of Registration issued by PHMSA or another document bearing the registration number identified as the "U.S. DOT Hazmat Reg. No." on board each truck and truck tractor (not including trailers and semi-trailers) used to transport hazardous materials subject to the requirements of this subpart. The Certificate of Registration or document bearing the registration number must be made available, upon request, to enforcement personnel.

(c) In addition to the requirements of paragraph (a) of this section, after January 1, 1995, each person who transports by vessel a hazardous material subject to the requirements of this subpart must carry on board the vessel a

copy of its current Certificate of Registration or another document bearing the current registration number identified as the “U.S. DOT Hazmat Reg. No.”

(d) Each person subject to this subpart must furnish its Certificate of Registration (or a copy thereof) and all other records and information pertaining to the information contained in the registration statement to an authorized representative or special agent of DOT upon request.

[Amdt. No. 107-26, 57 FR 30630, July 9, 1992, as amended at 57 FR 37902, August 21, 1992; Amdt. 107-26, 58 FR 12545, Mar. 5, 1993; Amdt. 107-31, 59 FR 32932, June 27, 1994]

### Subpart H—Approvals, Registrations and Submissions

SOURCE: Amdt. 107-38, 61 FR 21100, May 9, 1996, unless otherwise noted.

#### § 107.701 Purpose and scope.

(a) This subpart prescribes procedures for the issuance, modification and termination of approvals, and the submission of registrations and reports, as required by this chapter.

(b) The procedures of this subpart are in addition to any requirements in subchapter C of this chapter applicable to a specific approval, registration or report. If compliance with both a specific requirement of subchapter C of this chapter and a procedure of this subpart is not possible, the specific requirement applies.

(c) Registration under subpart F or G of this part is not subject to the procedures of this subpart.

[Amdt. 107-38, 61 FR 21100, May 9, 1996; Amdt. 107-38, 61 FR 27948, June 3, 1996]

#### § 107.705 Registrations, reports, and applications for approval.

(a) A person filing a registration, report, or application for an approval, or a renewal or modification of an approval subject to the provisions of this subpart must—

(1) File the registration, report, or application with the Associate Administrator for Hazardous Materials Safety (Attention: Approvals, PHH-32), Pipeline and Hazardous Materials Safety Administration, U.S. Department of

Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001. Alternatively, the document with any attached supporting documentation in an appropriate format may be filed by facsimile (fax) to: (202) 366-3753 or (202) 366-3308 or by electronic mail (e-mail) to: [approvals@dot.gov](mailto:approvals@dot.gov).

(2) Identify the section of the chapter under which the registration, report, or application is made;

(3) If a report is required by an approval, a registration or a special permit, identify the approval, registration or special permit number;

(4) Provide the name, street and mailing addresses, e-mail address optional, and telephone number of the person on whose behalf the registration, report, or application is made and, if different, the person making the filing;

(5) If the person on whose behalf the filing is made is not a resident of the United States, provide a designation of agent for service in accordance with § 105.40;

(6) Provide a description of the activity for which the registration or report is required; and

(7) Provide additional information as requested by the Associate Administrator, if the Associate Administrator determines that a filing lacks pertinent information or otherwise does not comply with applicable requirements.

(b) In addition to the provisions in paragraph (a) for an approval, an application for an approval, or an application for modification or renewal of an approval, the applicant must provide—

(1) A description of the activity for which the approval is required;

(2) The proposed duration of the approval;

(3) The transport mode or modes affected, as applicable;

(4) Any additional information specified in the section containing the approval; and

(5) For an approval which provides exceptions from regulatory requirements or prohibitions—

(i) Identification of any increased risk to safety or property that may result if the approval is granted, and specification of the measures that the

## § 107.709

## 49 CFR Ch. I (10–1–08 Edition)

applicant considers necessary or appropriate to address that risk; and

(ii) Substantiation, with applicable analyses or evaluations, if appropriate, demonstrating that the proposed activity will achieve a level of safety that is at least equal to that required by the regulation.

(c) For an approval with an expiration date, each application for renewal or modification must be filed in the same manner as an original application. If a complete and conforming renewal application is filed at least 60 days before the expiration date of an approval, the Associate Administrator, on written request from the applicant, will issue a written extension to permit operation under the terms of the expired approval until a final decision on the application for renewal has been made. Operation under an expired approval is prohibited absent a written extension. This paragraph does not limit the authority of the Associate Administrator to modify, suspend or terminate an approval under § 107.713.

(d) To request confidential treatment for information contained in the application, the applicant shall comply with § 105.30(a).

[Amdt. 107–38, 61 FR 21100, May 9, 1996, as amended at 65 FR 50457, Aug. 18, 2000; 67 FR 61011, Sept. 27, 2002; 70 FR 56090, Sept. 23, 2005; 70 FR 73162, Dec. 9, 2005; 72 FR 55683, Oct. 1, 2007]

### **§ 107.709 Processing of an application for approval, including an application for renewal or modification.**

(a) No public hearing or other formal proceeding is required under this subpart before the disposition of an application.

(b) At any time during the processing of an application, the Associate Administrator may request additional information from the applicant. If the applicant does not respond to a written request for additional information within 30 days of the date the request was received, the application may be deemed incomplete and denied. However, if the applicant responds in writing within the 30-day period requesting an additional 30 days within which it will gather the requested information, the Associate Administrator may grant the 30-day extension.

(c) The Associate Administrator may grant or deny an application, in whole or in part. At the Associate Administrator's discretion, an application may be granted subject to provisions that are appropriate to protect health, safety and property. The Associate Administrator may impose additional provisions not specified in the application, or delete conditions in the application which are unnecessary.

(d) The Associate Administrator may grant an application on finding that—

(1) The application complies with this subpart;

(2) The application demonstrates that the proposed activity will achieve a level of safety that—

(i) Is at least equal to that required by the regulation, or

(ii) If the regulations do not establish a level of safety, is consistent with the public interest and adequately will protect against the risks to life and property inherent in the transportation of hazardous materials in commerce;

(3) The application states all material facts, and contains no materially false or materially misleading statement;

(4) The applicant meets the qualifications required by applicable regulations; and

(5) The applicant is fit to conduct the activity authorized by the approval, or renewal or modification of approval. This assessment may be based on information in the application, prior compliance history of the applicant, and other information available to the Associate Administrator.

(e) Unless otherwise specified in this chapter or by the Associate Administrator, an approval in which a term is not specified does not expire.

(f) The Associate Administrator notifies the applicant in writing of the decision on the application. A denial contains a brief statement of reasons.

### **§ 107.711 Withdrawal.**

An application may be withdrawn at any time before a decision to grant or deny it is made. Withdrawal of an application does not authorize the removal of any related records from the PHMSA dockets or files. Applications

that are eligible for confidential treatment under §105.30 will remain confidential after the application is withdrawn. The duration of this confidential treatment for trade secrets and commercial or financial information is indefinite, unless the party requesting the confidential treatment of the materials notifies the Associate Administrator that the confidential treatment is no longer required.

[Amdt. 107-38, 61 FR 21100, May 9, 1996, as amended at 67 FR 61011, Sept. 27, 2002]

**§ 107.713 Approval modification, suspension or termination.**

(a) The Associate Administrator may modify an approval on finding that—

(1) Modification is necessary to conform an existing approval to relevant statutes and regulations as they may be amended from time to time; or

(2) Modification is required by changed circumstances to enable the approval to continue to meet the standards of § 107.709(d).

(b) The Associate Administrator may modify, suspend or terminate an approval, as appropriate, on finding that—

(1) Because of a change in circumstances, the approval no longer is needed or no longer would be granted if applied for;

(2) The application contained inaccurate or incomplete information, and the approval would not have been granted had the application been accurate and complete;

(3) The application contained deliberately inaccurate or incomplete information; or

(4) The holder knowingly has violated the terms of the approval or an applicable requirement of this chapter in a manner demonstrating lack of fitness to conduct the activity for which the approval is required.

(c) Except as provided in paragraph (d) of this section, before an approval is modified, suspended or terminated, the Associate Administrator notifies the holder in writing of the proposed action and the reasons for it, and provides an opportunity to show cause why the proposed action should not be taken.

(1) The holder may file a written response with the Associate Adminis-

trator within 30 days of receipt of notice of the proposed action.

(2) After considering the holder's or party's written response, or after 30 days have passed without response since receipt of the notice, the Associate Administrator notifies the holder in writing of the final decision with a brief statement of reasons.

(d) The Associate Administrator, if necessary to avoid a risk of significant harm to persons or property, may in the notification declare the proposed action immediately effective.

**§ 107.715 Reconsideration.**

(a) An applicant or a holder may request that the Associate Administrator reconsider a decision under § 107.709(f) or § 107.713(c). The request must:

(1) Be in writing and filed within 20 days of receipt of the decision;

(2) State in detail any alleged errors of fact and law;

(3) Enclose any additional information needed to support the request to reconsider; and

(4) State in detail the modification of the final decision sought.

(b) The Associate Administrator considers newly submitted information on a showing that the information could not reasonably have been submitted during application processing.

(c) The Associate Administrator grants or denies, in whole or in part, the relief requested and informs the requesting person in writing of the decision.

**§ 107.717 Appeal.**

(a) A person who requested reconsideration under § 107.715 may appeal to the Administrator the Associate Administrator's decision on the request. The appeal must:

(1) Be in writing and filed within 30 days of receipt of the Associate Administrator's decision on reconsideration;

(2) State in detail any alleged errors of fact and law;

(3) Enclose any additional information needed to support the appeal; and

(4) State in detail the modification of the final decision sought.

(b) The Administrator, if necessary to avoid a risk of significant harm to persons or property, may declare the

## § 107.801

Associate Administrator's action effective pending a decision on appeal.

(c) The Administrator grants or denies, in whole or in part, the relief requested and informs the appellant in writing of the decision on appeal. The Administrator's decision on appeal is the final administrative action.

### **Subpart I—Approval of Independent Inspection Agencies, Cylinder Requalifiers, and Non-domestic Chemical Analyses and Tests of DOT Specification Cylinders**

SOURCE: 67 FR 51639, Aug. 8, 2002, unless otherwise noted.

#### **§ 107.801 Purpose and scope.**

(a) This subpart prescribes procedures for—

(1) A person who seeks approval to be an independent inspection agency to perform tests, inspections, verifications and certifications of DOT specification cylinders or UN pressure receptacles as required by parts 178 and 180 of this chapter;

(2) A person who seeks approval to engage in the requalification (*e.g.* inspection, testing, or certification), rebuilding, or repair of a cylinder manufactured in accordance with a DOT specification or a pressure receptacle in accordance with a UN standard, under subchapter C of this chapter or under the terms of a special permit issued under this part;

(3) A person who seeks approval to perform the manufacturing chemical analyses and tests of DOT specification cylinders, special permit cylinders, or UN pressure receptacles outside the United States.

(b) No person may engage in a function identified in paragraph (a) of this section unless approved by the Associate Administrator in accordance with the provisions of this subpart. Each person must comply with the applicable requirements in this subpart. In addition, the procedural requirements in subpart H of this part apply to the filing, processing, and termi-

## 49 CFR Ch. I (10–1–08 Edition)

nation of an approval issued under this subpart.

[67 FR 51639, Aug. 8, 2002, as amended at 71 FR 33873, June 12, 2006]

#### **§ 107.803 Approval of an independent inspection agency (IIA).**

(a) *General.* Prior to performing cylinder inspections and verifications required by parts 178 and 180 of this chapter, a person must apply to the Associate Administrator for an approval as an independent inspection agency. A person approved as an independent inspection agency is not an PHMSA agent or representative.

(b) *Criteria.* No applicant for approval as an independent inspection agency may be engaged in the manufacture of cylinders for use in the transportation of hazardous materials, or be directly or indirectly controlled by, or have a financial involvement with, any entity that manufactures cylinders for use in the transportation of hazardous materials, except for providing services as an independent inspector.

(c) *Application information.* Each applicant must submit an application in conformance with § 107.705 containing the information prescribed in § 107.705(a). In addition, the application must contain the following information:

(1) Name and address of each facility where tests and inspections are to be performed.

(2) Detailed description of the inspection and testing facilities to be used by the applicant.

(3) Detailed description of the applicant's qualifications and ability to perform the inspections and to verify the inspections required by part 178 of this chapter or under the terms of a special permit issued under this part.

(4) Name, address, and principal business activity of each person having any direct or indirect ownership interest in the applicant greater than three percent and any direct or indirect ownership interest in each subsidiary or division of the applicant.

(5) Name of each individual whom the applicant proposes to employ as an inspector and who will be responsible for certifying inspection and test results, and a statement of that person's qualifications.

(6) An identification or qualification number assigned to each inspector who is supervised by a certifying inspector identified in paragraph (c)(3) of this section.

(7) A statement that the applicant will perform its functions independent of the manufacturers and owners of the cylinders.

(8) If the applicant's principal place of business is in a country other than the United States, the Associate Administrator may approve the applicant on the basis of an approval issued by the Competent Authority of the country of manufacture. The Competent Authority must maintain a current listing of approved IIAs and their identification marks. The applicant must provide a copy of the designation from the Competent Authority of that country delegating to the applicant an approval or designated agency authority for the type of packaging for which a DOT or UN designation is sought; and

(9) The signature of the person certifying the approval application and the date on which it was signed.

(d) *Facility inspection.* Upon the request of the Associate Administrator, the applicant must allow the Associate Administrator or the Associate Administrator's designee to inspect the applicant's facilities and records. The person seeking approval must bear the cost of the inspection.

(e) After approval, the Associate Administrator may authorize, upon request, the independent inspection agency to perform other inspections and functions for which the Associate Administrator finds the applicant to be qualified. Such additional authorizations will be noted on each inspection agency's approval documents.

[67 FR 51639, Aug. 8, 2002, as amended at 68 FR 24659, May 8, 2003; 71 FR 33873, June 12, 2006]

#### **§ 107.805 Approval of cylinder and pressure receptacle requalifiers.**

(a) *General.* A person must meet the requirements of this section to be approved to inspect, test, certify, repair, or rebuild a cylinder in accordance with a DOT specification or a UN pressure receptacle under subpart C of part 178 or subpart C of part 180 of this chap-

ter, or under the terms of a special permit issued under this part.

(b) *Independent Inspection Agency Review.* Each applicant must arrange for an independent inspection agency, approved by the Associate Administrator pursuant to this subpart, to perform a review of its inspection or requalification operation. The person seeking approval must bear the cost of the inspection. A list of approved independent inspection agencies is available from the Associate Administrator at the address listed in § 107.705. Assistance in obtaining an approval is available from the same address.

(c) *Application for approval.* If the inspection performed by an independent inspection agency is completed with satisfactory results, the applicant must submit a letter of recommendation from the independent inspection agency, an inspection report, and an application containing the information prescribed in § 107.705(a). In addition, the application must contain—

(1) The name of the facility manager;

(2) The types of DOT specification or special permit cylinders, or UN pressure receptacles that will be inspected, tested, repaired, or rebuilt at the facility;

(3) A certification that the facility will operate in compliance with the applicable requirements of subchapter C of this chapter; and

(4) The signature of the person making the certification and the date on which it was signed.

(d) *Issuance of requalifier identification number (RIN).* The Associate Administrator issues a RIN as evidence of approval to requalify DOT specification or special permit cylinders, or UN pressure receptacles if it is determined, based on the applicant's submission and other available information, that the applicant's qualifications and, when applicable, facility are adequate to perform the requested functions in accordance with the criteria prescribed in subpart C of part 180 of this subchapter.

(e) *Expiration of RIN.* Unless otherwise provided in the issuance letter, an approval expires five years from the date of issuance, provided the applicant's facility and qualifications are



maintained at or above the level observed at the time of inspection by the independent inspection agency, or at the date of the certification in the application for approval for requalifiers only performing inspections made under § 180.209(g) of this chapter.

(f) *Exceptions.* Notwithstanding the requirements in paragraphs (b) and (c) of this section, a person who only performs inspections in accordance with § 180.209(g) of this chapter may submit an application that, in addition to the information prescribed in § 107.705(a), identifies the DOT specification/special permit cylinders to be inspected; certifies the requalifier will operate in compliance with the applicable requirements of subchapter C of this chapter; certifies the persons performing inspections have been trained and have the information contained in each applicable CGA pamphlet incorporated by reference in § 171.7 of this chapter applicable to the requalifiers' activities; and includes the signature of the person making the certification and the date on which it was signed. Each person must comply with the applicable requirements in this subpart. In addition, the procedural requirements in subpart H of this part apply to the filing, processing and termination of an approval issued under this subpart. After May 31, 2004, no person may requalify a DOT specification/special permit cylinder in accordance with § 180.209(g) of this chapter unless that person has been issued a RIN as provided in paragraph (d) of this section.

(g) Each holder of a current RIN shall report in writing any change in its name, address, ownership, testing equipment, or management or personnel performing any function under this section, to the Associate Administrator (PHH-32) within 20 days of the change.

[67 FR 51639, Aug. 8, 2002, as amended at 68 FR 24659, May 8, 2003; 68 FR 55544, Sept. 26, 2003; 70 FR 56090, Sept. 23, 2005; 70 FR 73162, Dec. 9, 2005; 71 FR 33873, June 12, 2006]

#### **§ 107.807 Approval of non-domestic chemical analyses and tests.**

(a) *General.* A person who seeks to manufacture DOT specification or special permit cylinders outside the United States must seek an approval

from the Associate Administrator to perform the chemical analyses and tests of those cylinders outside the United States.

(b) *Application for approval.* Each applicant must submit an application containing the information prescribed in § 107.705(a). In addition, the application must contain—

(1) The name, address, and a description of each facility at which cylinders are to be manufactured and chemical analyses and tests are to be performed;

(2) Complete details concerning the dimensions, materials of construction, wall thickness, water capacity, shape, type of joints, location and size of openings and other pertinent physical characteristics of each specification or special permit cylinder for which approval is being requested, including calculations for cylinder wall stress and wall thickness, which may be shown on a drawing or on separate sheets attached to a descriptive drawing;

(3) The name of the independent inspection agency to be used; and

(4) The signature of the person making the certification and the date on which it was signed.

(c) *Facility inspections.* Upon the request of the Associate Administrator, the applicant must allow the Associate Administrator or the Associate Administrator's designee to inspect the applicant's cylinder manufacturing and testing facilities and records, and must provide such materials and cylinders for analyses and tests as the Associate Administrator may specify. The applicant or holder must bear the cost of the initial and subsequent inspections, analyses, and tests.

#### **§ 107.809 Conditions of UN pressure receptacle approvals.**

(a) Each approval issued under this subpart contains the following conditions:

(1) Upon the request of the Associate Administrator, the applicant or holder must allow the Associate Administrator or the Associate Administrator's designee to inspect the applicant's pressure receptacle manufacturing and testing facilities and records, and must provide such materials and pressure receptacles for analyses and tests as the

Associate Administrator may specify. The applicant or holder must bear the cost of the initial and subsequent inspections, analyses, and tests.

(2) Each holder must comply with all of the terms and conditions stated in the approval letter issued under this subpart.

(b) In addition to the conditions specified in §107.713, an approval may be denied or if issued, suspended or terminated if the Competent Authority of the country of manufacture fails to initiate, maintain or recognize an IIA approved under this subpart; fails to recognize UN standard packagings manufactured in accordance with this subchapter; or implements a condition or limitation on United States citizens or organizations that is not required of its own citizenry.

[71 FR 33874, June 12, 2006]

## **PART 110—HAZARDOUS MATERIALS PUBLIC SECTOR TRAINING AND PLANNING GRANTS**

Sec.

110.1 Purpose.

110.5 Scope.

110.7 Control Number under the Paperwork Reduction Act.

110.10 Eligibility.

110.20 Definitions.

110.30 Grant application.

110.40 Activities eligible for funding.

110.50 Disbursement of Federal funds.

110.60 Cost sharing for planning and training.

110.70 Financial administration.

110.80 Procurement.

110.90 Grant monitoring, reports, and records retention.

110.100 Enforcement.

110.110 After-grant requirements.

110.120 Deviation from this part.

110.130 Disputes.

AUTHORITY: 49 U.S.C. 5101–5127; 49 CFR 1.53.

SOURCE: Amdt. 110–1, 57 FR 43067, Sept. 17, 1992, unless otherwise noted.

EDITORIAL NOTE: Nomenclature changes to part 110 appear at 70 FR 56090, Sept. 23, 2005.

### **§ 110.1 Purpose.**

This part sets forth procedures for reimbursable grants for public sector planning and training in support of the emergency planning and training efforts of States, Indian tribes, and local communities to deal with hazardous

materials emergencies, particularly those involving transportation. These grants will enhance the implementation of the Emergency Planning and Community Right-to-Know Act of 1986 (42 U.S.C. 11001).

### **§ 110.5 Scope.**

(a) This part applies to States and Indian tribes and contains the program requirements for public sector training and planning grants to support hazardous materials emergency planning and training efforts.

(b) The requirements contained in 49 CFR part 18, “Uniform Administrative Requirements for Grants and Cooperative Agreements to State and Local Governments”, apply to grants issued under this part.

(c) Copies of standard forms and OMB circulars referenced in this part are available from the HMTUSA Grants Manager, Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington DC 20590–0001.

[Amdt. 110–1, 57 FR 43067, Sept. 17, 1992, as amended at 72 FR 55683, Oct. 1, 2007]

### **§ 110.7 Control Number under the Paperwork Reduction Act.**

The Office of Management and Budget control number assigned to collection of information in §§ 110.30, 110.70, 110.80, and 110.90 is 2137–0586.

### **§ 110.10 Eligibility.**

This part applies to States and Indian tribes. States may apply for planning and training grants. Federally-recognized Indian tribes may apply for training grants.

### **§ 110.20 Definitions.**

Unless defined in this part, all terms defined in 49 U.S.C. 5102 are used in their statutory meaning and all terms defined in 49 CFR part 18 and OMB Circular A–102, with respect to administrative requirements for grants, are used as defined therein. Other terms used in this part are defined as follows:

*Allowable costs* means those costs that are: eligible, reasonable, necessary, and allocable to the project permitted by the appropriate Federal cost principles, and approved in the grant.

## § 110.30

*Associate Administrator* means the Associate Administrator for Hazardous Materials Safety, Pipeline and Hazardous Materials Safety Administration.

*Budget period* means the period of time specified in the grant agreement during which the project manager may expend or obligate project funds.

*Cost review* means the review and evaluation of costs to determine reasonableness, allocability, and allowability.

*Indian country* means Indian country as defined in 18 U.S.C. 1151. That section defines Indian country as all land within the limits of any reservation under the jurisdiction of the U.S. Government, notwithstanding the issuance of any patent, and, including rights-of-way running through the reservation; all dependent Indian communities within the borders of the United States whether within the original or subsequently acquired territory thereof, and whether within or without the limits of a State; and all Indian allotments, the Indian titles to which have not been extinguished, including rights-of-way running through the same.

*Indian tribe* means a tribe “Federally-recognized” by the Secretary of the Interior under 25 CFR 272.2.

*Local Emergency Planning Committee (LEPC)* means a committee appointed by the State Emergency Response Commission under section 301(c) of the Emergency Planning and Community Right-to-Know Act of 1986 (42 U.S.C. 11001(c)) that includes at a minimum, representatives from each of the following groups or organizations: elected State and local officials; law enforcement, firefighting, civil defense, first aid, health, local environmental, hospital, and transportation personnel; broadcast and print media; community groups; and owners and operators of facilities subject to the emergency planning requirements.

*National curriculum* means the curriculum required to be developed under 49 U.S.C. 5115 and necessary to train public sector emergency response and preparedness teams, enabling them to comply with performance standards as stated in 49 U.S.C. 5115(c).

*Political subdivision* means a county, municipality, city, town, township,

## 49 CFR Ch. I (10–1–08 Edition)

local public authority (including any public and Indian housing agency under the United States Housing Act of 1937 (42 U.S.C. 1401 *et seq.*), school district, special district, intrastate district, council of governments (whether or not incorporated as a nonprofit corporation under State law), any other regional or interstate government entity, or any agency or instrumentality of a local government.

*Project* means the activities and tasks identified in the grant agreement.

*Project manager* means the State or Indian tribal official designated in a grant as the recipient agency’s principal program contact with the Federal Government.

*Project officer* means the Federal official designated in a grant as the program contact with the project manager. The project officer is responsible for monitoring the project.

*Project period* means the length of time specified in a grant for completion of all work associated with that project.

*State Emergency Response Commission (SERC)* means the State Emergency Response Commission appointed by the Governor of each State and Territory under the Emergency Planning and Community Right-to-Know Act of 1986.

*Statement of Work* means that portion of a grant that describes the purpose and scope of activities and tasks to be carried out as part of the proposed project.

[Amdt. 110–1, 57 FR 43067, Sept. 17, 1992, as amended by Amdt. 110–3, 59 FR 49132, Sept. 26, 1994; 66 FR 45377, Aug. 28, 2001]

### § 110.30 Grant application.

(a) *General.* An applicant for a planning or training grant shall use only the standard application forms approved by the Office of Management and Budget (OMB) (SF-424 and SF-424A) under the Paperwork Reduction Act of 1980 (44 U.S.C. 3502). Applicants are required to submit an original and two copies of the application package to: Grants Manager, Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590–0001. Applications received on or before January 1st and July 1st of each year

will be considered in that cycle of the semi-annual review and award process. An initial round of the review and award process will consider applications received on or before November 15, 1992. Requests and continuation applications must include an original and two copies of the affected pages; previously submitted pages with information that is still current do not have to be resubmitted. The application must include the following:

(1) Application for Federal Assistance for non-construction programs (SF-424) and Budget sheets (SF-424A). A single application may be used for both planning and training if the budgets for each are entered separately on all budget sheets.

(2) For States, a letter from the Governor designating the State agency that is authorized to apply for a grant and to provide the written certifications required to receive a grant.

(3) For Indian tribes, a letter from the tribal government, governing body, or tribal council to the effect that the applicant is authorized to apply for a grant and to provide the written certifications required to receive a grant.

(4) A written statement explaining whether the State or tribe assesses and collects fees on the transportation of hazardous materials and whether such assessments or fees are used solely to carry out purposes related to the transportation of hazardous materials.

(5) A statement designating a project manager and providing the name, position, address and phone number of that individual who will be responsible for coordinating the funded activities with other agencies/organizations.

(6) A project narrative statement of the goals and objectives of the proposed project, project design, and long range plans. The proposed grant project and budget periods may be one or more years.

(7) A statement of work in support of the proposed project that describes and sets priorities for the activities and tasks to be conducted, the costs associated with each activity, the number and types of deliverables and products to be completed, and a schedule for implementation.

(8) A description of the major items of costs needed to implement the state-

ment of work and a copy of any cost or price analysis if conducted.

(9) *Drug-Free Workplace Certification.* The applicant must certify as specified in appendix C of 49 CFR part 29 that it will comply with the Drug-Free Workplace Act of 1988 (Pub. L. 100-690, title V, subtitle D; 51 U.S.C. 701 *et seq.*).

(10) *Anti-Lobbying Certification.* The applicant must certify as specified in appendix A of 49 CFR part 20 that no Federal funds will be expended to pay any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress (section 319 of Pub. L. 101-121, 31 U.S.C. 1352).

(11) *Debarment and Suspension Certification.* The applicant must certify as specified in subpart G of 49 CFR part 29 that it will not make an award or permit any award to any party which is debarred or suspended or is otherwise excluded from or ineligible for participation in Federal assistance programs.

(b) *Planning.* In addition to the requirements specified in paragraph (a) of this section, eligible State applicants must include the following in their application package:

(1) A written certification that the State is complying with sections 301 and 303 of the Emergency Planning and Community Right-to-Know Act of 1986, including a brief explanation of how compliance has been achieved.

(2) A written statement specifying the aggregate expenditure of funds of the State, exclusive of Federal funds, for each of its last five fiscal years for developing, improving, and implementing emergency plans under the Emergency Planning and Community Right-to-Know Act of 1986, including an explanation specifying the sources of these funds. A written certification that the State's aggregate expenditures, as defined by the State, of funds for this purpose, exclusive of Federal funds, will not fall below the average level of its expenditures for its last five fiscal years. The applicant may not claim any of these expenditures for cost-sharing.

(3) A written statement agreeing to make at least 75 percent of the Federal funds awarded available to LEPCs and

## § 110.30

## 49 CFR Ch. I (10–1–08 Edition)

an explanation of how the applicant intends to make such funds available to them for developing, improving, or implementing emergency plans.

(4) Designation of a project manager to serve as contact for coordinating planning funds under this program.

(5) A project narrative statement of the goals and objectives of each proposed project, including the following:

(i) A background statement describing the applicant's long-term goals and objectives with respect to:

(A) The current abilities and authorities of the applicant's program for preparedness planning;

(B) The need to sustain or increase program capability;

(C) Current degree of participation in or intention to assess the need for a regional hazardous materials emergency response team; and

(D) The impact that the grant will have on the program.

(ii) A discussion of whether the applicant's program currently knows, or intends to assess, transportation flow patterns of hazardous materials within the State and between that State and another State.

(iii) A schedule for implementing the proposed grant activities.

(iv) A statement describing the ways in which planning will be monitored by the project manager.

(v) A statement indicating that all members of the State Emergency Response Commission were provided the opportunity to review the grant application.

(c) *Training.* In addition to the requirements specified in paragraph (a) of this section, eligible State and Indian tribe applicants must include the following in their application package:

(1) For a State applicant, a written certification explaining how the State is complying with sections 301 and 303 of the Emergency Planning and Community Right-to-Know Act.

(2) A written statement specifying the aggregate expenditure of funds of the State or Indian tribe, exclusive of Federal funds, for each of its last five fiscal years for training public sector employees to respond to accidents and incidents involving hazardous materials, including an explanation specifying the sources of these funds. A

written certification that the applicant's aggregate expenditure, as defined by the State or tribe, of funds for this purpose, exclusive of Federal funds, will not fall below the average level of its expenditures for its last five fiscal years. The applicant may not claim any of these expenditures for cost-sharing purposes.

(3) For a State applicant, a written statement agreeing to make at least 75 percent of the Federal funds awarded available for the purpose of training public sector employees employed or used by political subdivisions. A State applicant may elect to pass all or some portion of the grant on to political subdivisions for this purpose. The applicant must include a specific explanation of how it intends to meet this requirement.

(4) Designation of a primary point of contact for coordinating training funded under this program. Identification of a single repository for copies of course materials delivered under the grant as specified in §110.90 of this part.

(5) A project narrative statement of the long-range goals and objectives of each proposed project, including the following:

(i) A background statement describing:

(A) The current hazardous materials training program(s);

(B) Training audience, including numbers and levels of training and accreditation program for each level or criterion required to advance to the next level;

(C) Estimated total number of persons to be trained under the proposed project;

(D) The ways in which training grants will support the integrated delivery of training to meet the needs of individualized geographic and resource needs and time considerations of local responders. When appropriate, a statement describing how the proposed project will accommodate the different training needs for rural versus urban environments; and

(E) The impact that the grant and the National Curriculum will have on the program.

(ii) A statement describing how the National Curriculum will be used or

modified to train public sector employees at the local level to respond to accidents and incidents involving hazardous materials.

(iii) A statement describing the ways in which effectiveness of training will be monitored by the project manager, including, but not limited to, examinations, critiques, and instructor evaluations.

(iv) A schedule for implementing the proposed training grant activities.

(v) A statement indicating that all members of the State or Tribal Emergency Response Commission were provided the opportunity to review the grant application.

[Amdt. 110-1, 57 FR 43067, Sept. 17, 1992, as amended by Amdt. 110-3, 59 FR 49132, Sept. 26, 1994; 70 FR 73162, Dec. 9, 2005; 72 FR 55683, Oct. 1, 2007]

#### § 110.40 Activities eligible for funding.

(a) *Planning.* Eligible State applicants may receive funding for the following activities:

(1) Development, improvement, and implementation of emergency plans required under the Emergency Planning and Community Right-to-Know Act of 1986, as well as exercises which test the emergency plan. Enhancement of emergency plans to include hazard analysis as well as response procedures for emergencies involving transportation of hazardous materials, including radioactive materials.

(2) An assessment to determine flow patterns of hazardous materials within a State, between a State and another State or Indian country, and development and maintenance of a system to keep such information current.

(3) An assessment of the need for regional hazardous materials emergency response teams.

(4) An assessment of local response capabilities.

(5) Conduct of emergency response drills and exercises associated with emergency preparedness plans.

(6) Provision of technical staff to support the planning effort.

(7) Additional activities the Associate Administrator deems appropriate to implement the scope of work for the proposed project plan and approved in the grant.

(b) *Training.* Eligible State and Indian tribe applicants may receive funding for the following activities:

(1) An assessment to determine the number of public sector employees employed or used by a political subdivision who need the proposed training and to select courses consistent with the National Curriculum.

(2) Delivery of comprehensive preparedness and response training to public sector employees. Design and delivery of preparedness and response training to meet specialized needs. Financial assistance for trainees and for the trainers, if appropriate, such as tuition, travel expenses to and from a training facility, and room and board while at the training facility.

(3) Emergency response drills and exercises associated with training, a course of study, and tests and evaluation of emergency preparedness plans.

(4) Expenses associated with training by a person (including a department, agency, or instrumentality of a State or political subdivision thereof or an Indian tribe) and activities necessary to monitor such training including, but not limited to examinations, critiques and instructor evaluations.

(5) Provision of staff to manage the training effort designed to result in increased benefits, proficiency, and rapid deployment of local and regional responders.

(6) Additional activities the Associate Administrator deems appropriate to implement the scope of work for the proposed project and approved in the grant.

[Amdt. 110-1, 57 FR 43067, Sept. 17, 1992, as amended by 66 FR 45377, Aug. 28, 2001]

#### § 110.50 Disbursement of Federal funds.

(a) Preaward expenditures may not be reimbursed.

(b) Reimbursement may not be made for a project plan unless approved in the grant award.

(c) If a recipient agency seeks additional funds, the amendment request will be evaluated on the basis of needs, performance and availability of funds. An existing grant is not a commitment of future Federal funding.

## **§ 110.60**

## **49 CFR Ch. I (10–1–08 Edition)**

### **§ 110.60 Cost sharing for planning and training.**

(a) The recipient agency must provide 20 percent of the direct and indirect costs of all activities covered under the grant award program with non-Federal funds. Recipients may either use cash (hard-match), in-kind (soft-match) contributions, or a combination of in-kind plus hard-match to meet this requirement. In-kind (soft-match) contributions are in addition to the maintenance of effort required of recipients of grant awards. The types of contributions allowed are as follows:

(1) Any funds from a State, local, or other non-Federal source used for an eligible activity as defined in § 110.40 in this part.

(2) The dollar equivalent value of an eligible activity as defined in § 110.40 of this part provided by a State, local, or other non-Federal source.

(3) The value of participants' salary while attending a planning or training activity contained in the approved grant application provided by a State, local, or other non-Federal source.

(4) Additional types of in-kind contributions the Associate Administrator deems appropriate.

(b) Funds used for matching purposes under any other Federal grant or cooperative agreement may not be used for matching purposes. The funds expended by a recipient agency to qualify for the grant may not be used for cost-sharing purposes.

(c) Acceptable contributions for matching and cost sharing purposes must conform to 49 CFR part 18.

[Amdt. 110–1, 57 FR 43067, Sept. 17, 1992, as amended by Amdt. 110–3, 59 FR 49132, Sept. 26, 1994; 66 FR 45377, Aug. 28, 2001]

### **§ 110.70 Financial administration.**

(a) A State must expend and account for grant funds in accordance with State laws and procedures for expending and accounting for its own funds. Fiscal control and accounting procedures of the State, as well as its subgrantees and cost-type contractors, must be sufficient to:

(1) Permit the preparation of reports required by 49 CFR part 18 and this part, including the tracing of funds provided for planning to a level of expenditure adequate to establish that at

least 75 percent of the funds provided were made available to LEPCs for developing, improving, and implementing emergency plans; and the tracing of funds provided for training to a level of expenditure adequate to establish that at least 75 percent of the funds provided were made available for the purposes of training public sector employees employed or used by political subdivisions.

(2) Permit the tracing of funds to a level of expenditure adequate to establish that such funds have not been used in violation of the restrictions and prohibitions of applicable statutes.

(b) The financial management systems of Indian tribes and any subgrantees must meet the standards of 49 CFR 18.20, including the ability to trace funds provided for training to a level of expenditure adequate to establish that at least 75 percent of the funds provided were made available for the purposes of training public sector employees employed or used by political subdivisions.

(c) Advances shall be made to States and Indian tribes consistent with 49 CFR part 18 and 31 CFR part 205. The Associate Administrator shall base these advances on demonstrated need, which will be determined on a case-by-case basis, considering such factors as State/Tribal budget constraints and reductions in amounts budgeted for hazardous materials activities. To obtain an advance, a State or Indian tribe must comply with the following requirements:

(1) A letter from the Governor or Tribal leader or their designee is required specifying the extenuating circumstances requiring the funding advance for the grant;

(2) The maximum advance request may not be more than \$25,000 for each State or Indian tribe;

(3) Recipients of advance funding must obligate those funds within 3 months of receipt;

(4) Advances including interest will be deducted from the initial reimbursement to the State or Indian tribe; and

(5) The State or Indian tribe will have its allocation of current grant funds reduced and will not be permitted to apply for future grant funds

until the advance is covered by a request for reimbursement. For example, if \$25,000 is advanced for personnel costs, this advance would be deducted from the initial reimbursement in the year the advance was made.

(d) To be allowable, costs must be eligible, reasonable, necessary, and allocable to the approved project in accordance with OMB Circular A-87 and included in the grant award. Costs incurred prior to the award of any grant are not allowable. Recipient agencies are responsible for obtaining audits in accordance with the Single Audit Act of 1984 (31 U.S.C. 7501), 49 CFR part 90, and OMB Circular A-128. Audits shall be made by an independent auditor in accordance with generally accepted government auditing standards covering financial and compliance audits. The Associate Administrator may audit a recipient agency at any time.

[Amdt. 110-1, 57 FR 43067, Sept. 17, 1992, as amended by 66 FR 45377, Aug. 28, 2001]

#### **§ 110.80 Procurement.**

Project managers shall use procurement procedures and practices which reflect applicable State laws and regulations and Federal requirements as specified in 49 CFR 18.36.

#### **§ 110.90 Grant monitoring, reports, and records retention.**

(a) *Grant monitoring.* Project managers are responsible for managing the day-to-day operations of grant, subgrant and contract-supported activities. Project managers must monitor performance of supported activities to assure compliance with applicable Federal requirements and achievement of performance goals. Monitoring must cover each program, function, activity, or task covered by the grant. Monitoring and reporting requirements for planning and training are contained in this part; general grant reporting requirements are specified in 49 CFR 18.40.

(b) *Reports.* (1) The project manager shall submit a performance report at the completion of an activity for which reimbursement is being requested or with a request to amend the grant. The final performance report is due 90 days after the expiration or termination of the grant.

(2) Project managers shall submit an original and two copies of all performance reports. Performance reports for planning and training must include comparison of actual accomplishments to the stated goals and objectives established for the performance period, and the reasons for not achieving those goals and objectives, if applicable.

(3) Project managers shall report developments or events that occur between the required performance reporting dates which have significant impact upon the planning and training activity such as:

(i) Problems, delays, or adverse conditions which will impair the ability to meet the objective of the grant; and

(ii) Favorable developments which enable meeting time schedules and objectives sooner or at less cost than anticipated or producing more beneficial results than originally planned.

(4) Financial reporting, except as provided in § 110.70 and 49 CFR 18.41, shall be supplied quarterly using Standard Form 270, Request for Advance or Reimbursement, to report the status of funds. The project manager shall report separately on planning and training.

(c) *Records retention.* In accordance with 49 CFR 18.42, all financial and programmatic records, supporting documents, statistical records, training materials, and other documents generated under a grant shall be maintained by the project manager for three years from the date the project manager submits the final financial status report (SF 269) or Request for Advance or Reimbursement (SF 270). The project manager shall designate a repository and single-point of contact for planning and for training, or both, for these purposes. If any litigation, claim, negotiation, audit or other action involving the records has been started before the expiration of the 3-year period, the records must be retained until completion of the action and resolution of all issues which arise from it, or until the end of the regular 3-year period, whichever is later.

#### **§ 110.100 Enforcement.**

If a recipient agency fails to comply with any term of an award (whether



## **§ 110.110**

stated in a Federal statute or regulation, an assurance, a State plan or application, a notice of award, or elsewhere) a noncompliance action may be taken as specified in 40 CFR 18.43. The recipient agency may appeal any such actions as specified in 49 CFR part 18. Costs incurred by the recipient agency during a suspension or after termination of an award are not allowable unless the Associate Administrator authorizes it in writing. Grant awards may be terminated in whole or in part with the consent of the recipient at any agreed upon effective date, or by the recipient upon written notification.

[Amdt. 110-1, 57 FR 43067, Sept. 17, 1992, as amended by 66 FR 45377, Aug. 28, 2001]

### **§ 110.110 After-grant requirements.**

The Associate Administrator will close out the award upon determination that all applicable administrative actions and all required work of the grant are complete in accordance with subpart D of 49 CFR part 18. The project manager must submit all financial, performance, and other reports required as a condition of the grant, within 90 days after the expiration or termination of the grant. This time frame may be extended by the Asso-

## **49 CFR Ch. I (10-1-08 Edition)**

ciate Administrator for Hazardous Materials Safety for cause.

[Amdt. 110-1, 57 FR 43067, Sept. 17, 1992, as amended by 66 FR 45377, Aug. 28, 2001]

### **§ 110.120 Deviation from this part.**

Recipient agencies may request a deviation from the non-statutory provisions of this part. The Associate Administrator will respond to such requests in writing. If appropriate, the decision will be included in the grant agreement. Request for deviations from part 110 must be submitted to: Grants Manager, Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

[Amdt. 110-1, 57 FR 43067, Sept. 17, 1992, as amended by Amdt. 110-3, 59 FR 49132, Sept. 26, 1994; 66 FR 45377, Aug. 28, 2001; 72 FR 55683, Oct. 1, 2007]

### **§ 110.130 Disputes.**

Disputes should be resolved at the lowest level possible, beginning with the project manager and the project officer. If an agreement cannot be reached, the Administrator, PHMSA, will serve as the dispute resolution official, whose decision will be final.

## SUBCHAPTER B—OIL TRANSPORTATION

### PART 130—OIL SPILL PREVENTION AND RESPONSE PLANS

Sec.

130.1 Purpose.

130.2 Scope.

130.3 General requirements.

130.5 Definitions.

130.11 Communication requirements.

130.21 Packaging requirements.

130.31 Response plans.

130.33 Response plan implementation.

AUTHORITY: 33 U.S.C. 1321.

SOURCE: Amdt. 130-2, 61 FR 30541, June 17, 1996, unless otherwise noted.

#### § 130.1 Purpose.

This part prescribes prevention, containment and response planning requirements of the Department of Transportation applicable to transportation of oil by motor vehicles and rolling stock.

#### § 130.2 Scope.

(a) The requirements of this part apply to—

(1) Any liquid petroleum oil in a packaging having a capacity of 3,500 gallons or more; and

(2) Any liquid petroleum or non-petroleum oil in a quantity greater than 42,000 gallons per packaging.

(b) The requirements of this part have no effect on—

(1) The applicability of the Hazardous Materials Regulations set forth in subchapter C of this chapter; and

(2) The discharge notification requirements of the United States Coast Guard (33 CFR part 153) and EPA (40 CFR part 110).

(c) The requirements of this part do not apply to—

(1) Any mixture or solution in which oil is in a concentration by weight of less than 10 percent.

(2) Transportation of oil by aircraft or vessel.

(3) Any petroleum oil carried in a fuel tank for the purpose of supplying fuel for propulsion of the transport vehicle to which it is attached.

(4) Oil transport exclusively within the confines of a non-transportation-related or terminal facility in a vehicle

not intended for use in interstate or intrastate commerce (see 40 CFR part 112, appendix A).

(d) The requirements in § 130.31(b) of this part do not apply to mobile marine transportation-related facilities (see 33 CFR part 154).

#### § 130.3 General requirements.

No person may offer or accept for transportation or transport oil subject to this part unless that person—

(a) Complies with this part; and

(b) Has been instructed on the applicable requirements of this part.

#### § 130.5 Definitions.

In this subchapter: *Animal fat* means a non-petroleum oil, fat, or grease derived from animals, not specifically identified elsewhere in this part.

*Contract or other means* is:

(1) A written contract with a response contractor identifying and ensuring the availability of the necessary personnel or equipment within the shortest practicable time;

(2) A written certification by the owner or operator that the necessary personnel or equipment can and will be made available by the owner or operator within the shortest practicable time; or

(3) Documentation of membership in an oil spill response organization that ensures the owner's or operator's access to the necessary personnel or equipment within the shortest practicable time.

*EPA* means the U.S. Environmental Protection Agency.

*Liquid* means a material that has a vertical flow of over two inches (50 mm) within a three-minute period, or a material having one gram or more liquid separation, when determined in accordance with the procedures specified in ASTM D 4359-84, "Standard Test Method for Determining Whether a Material is a Liquid or a Solid," 1990 edition, which is incorporated by reference.

NOTE: This incorporation by reference has been approved by the Director of the Federal Register in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. A copy may be obtained

## § 130.11

## 49 CFR Ch. I (10–1–08 Edition)

from the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103. Copies may be inspected at the Office of Hazardous Materials Safety, Office of Hazardous Materials Standards, Room 8422, DOT headquarters building, 400 7th St., SW, Washington, DC 20590, or at the National Archives and Records Administration (NARA). For information on the availability of this material at NARA, call 202-741-6030, or go to: [http://www.archives.gov/federal\\_register/code\\_of\\_federal\\_regulations/ibr\\_locations.html](http://www.archives.gov/federal_register/code_of_federal_regulations/ibr_locations.html).

*Maximum extent practicable* means the limits of available technology and the practical and technical limits on an owner or operator of an onshore facility in planning the response resources required to provide the on-water recovery capability and the shoreline protection and cleanup capability to conduct response activities for a worst-case discharge of oil in adverse weather.

*Non-petroleum oil* means any animal fat, vegetable oil or other non-petroleum oil.

*Oil* means oil of any kind or in any form, including, but not limited to, petroleum, fuel oil, sludge, oil refuse, and oil mixed with wastes other than dredged spoil.

NOTE: This definition does not include hazardous substances (see 40 CFR part 116).

*Other non-petroleum oil* means a non-petroleum oil of any kind that is not an animal fat or vegetable oil.

*Packaging* means a receptacle and any other components or materials necessary for the receptacle to perform its containment function in conformance with the packaging requirements of this part. A compartmented tank is a single packaging.

*Person* means an individual, firm, corporation, partnership, association, State, municipality, commission, or political subdivision of a State, or any interstate body, as well as a department, agency, or instrumentality of the executive, legislative or judicial branch of the Federal Government.

*Petroleum oil* means any oil extracted or derived from geological hydrocarbon deposits, including fractions thereof.

*Qualified individual* means an individual familiar with the response plan, trained in his or her responsibilities in implementing the plan, and authorized, on behalf of the owner or operator, to

initiate all response activities identified in the plan, to enter into response-related contracts and obligate funds for such contracts, and to act as a liaison with the on-scene coordinator and other responsible officials. The qualified individual must be available at all times the owner or operator is engaged in transportation subject to part 130 (alone or in conjunction with an equally qualified alternate), must be fluent in English, and must have in his or her possession documentation of the required authority.

*Transports or Transportation* means any movement of oil by highway or rail, and any loading, unloading, or storage incidental thereto.

*Vegetable oil* means a non-petroleum oil or fat derived from plant seeds, nuts, kernels or fruits, not specifically identified elsewhere in this part.

*Worst-case discharge* means “the largest foreseeable discharge in adverse weather conditions,” as defined at 33 U.S.C. 1321(a)(24). The largest foreseeable discharge from a motor vehicle or rail car is the capacity of the cargo container. The term “maximum potential discharge,” used in § 130.31(a), is synonymous with “worst-case discharge.”

[Amdt. 130–2, 61 FR 30541, June 17, 1996, as amended by 66 FR 45378, Aug. 28, 2001; 67 FR 61011, Sept. 27, 2002; 69 FR 18803, Apr. 9, 2004]

### § 130.11 Communication requirements.

(a) No person may offer oil subject to this part for transportation unless that person provides the person accepting the oil for transportation a document indicating the shipment contains oil.

(b) No person may transport oil subject to this part unless a readily available document indicating that the shipment contains oil is in the possession of the transport vehicle operator during transportation.

(c) A material subject to the requirements of this part need not be specifically identified as oil when the shipment document accurately describes the material as: aviation fuel, diesel fuel, fuel oil, gasoline, jet fuel, kerosene, motor fuel, or petroleum.

### § 130.21 Packaging requirements.

Each packaging used for the transportation of oil subject to this part

must be designed, constructed, maintained, closed, and loaded so that, under conditions normally incident to transportation, there will be no release of oil to the environment.

**§ 130.31 Response plans.**

(a) After September 30, 1993, no person may transport oil subject to this part unless that person has a current basic written plan that:

(1) Sets forth the manner of response to discharges that may occur during transportation;

(2) Takes into account the maximum potential discharge of the contents from the packaging;

(3) Identifies private personnel and equipment available to respond to a discharge;

(4) Identifies the appropriate persons and agencies (including their telephone numbers) to be contacted in regard to such a discharge and its handling, including the National Response Center; and

(5) For each motor carrier, is retained on file at that person's principal place of business and at each location where dispatching of motor vehicles occurs; and for each railroad, is retained on file at that person's principal place of business and at the dispatcher's office.

(b) After February 18, 1993, no person may transport an oil subject to this part in a quantity greater than 1,000 barrels (42,000 gallons) unless that person has a current comprehensive written plan that:

(1) Conforms with all requirements specified in paragraph (a) of this section;

(2) Is consistent with the requirements of the National Contingency Plan (40 CFR part 300) and Area Contingency Plans;

(3) Identifies the qualified individual having full authority to implement removal actions, and requires immediate communications between that indi-

vidual and the appropriate Federal official and the persons providing spill response personnel and equipment;

(4) Identifies, and ensures by contract or other means the availability of, private personnel (including address and phone number), and the equipment necessary to remove, to the maximum extent practicable, a worst case discharge (including a discharge resulting from fire or explosion) and to mitigate or prevent a substantial threat of such a discharge;

(5) Describes the training, equipment testing, periodic unannounced drills, and response actions of facility personnel, to be carried out under the plan to ensure the safety of the facility and to mitigate or prevent the discharge, or the substantial threat of such a discharge; and

(6) Is submitted, and resubmitted in the event of any significant change, to the Federal Railroad Administrator (for tank cars), or to the Federal Highway Administrator (for cargo tanks) at East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

(Approved by the Office of Management and Budget under control number 2137-0591)

[Amdt. 130-2, 61 FR 30541, June 17, 1996, as amended at 72 FR 55683, Oct. 1, 2007]

**§ 130.33 Response plan implementation.**

If, during transportation of oil subject to this part, a discharge occurs—into or on the navigable waters of the United States; on the adjoining shorelines to the navigable waters; or that may affect natural resources belonging to, appertaining to, or under the exclusive management authority of, the United States—the person transporting the oil shall implement the plan required by § 130.31, in a manner consistent with the National Contingency Plan, 40 CFR part 300, or as otherwise directed by the Federal on-scene coordinator.

## SUBCHAPTER C—HAZARDOUS MATERIALS REGULATIONS

### PART 171—GENERAL INFORMATION, REGULATIONS, AND DEFINITIONS

Sec.

#### Subpart A—Applicability, General Requirements, and North American Shipments

- 171.1 Applicability of Hazardous Materials Regulations (HMR) to persons and functions.
- 171.2 General requirements.
- 171.3 Hazardous waste.
- 171.4 Marine pollutants.
- 171.6 Control numbers under the Paperwork Reduction Act.
- 171.7 Reference material.
- 171.8 Definitions and abbreviations.
- 171.9 Rules of construction.
- 171.10 Units of measure.
- 171.11 [Reserved]
- 171.12 North American Shipments.
- 171.12a [Reserved]
- 171.14 Transitional provisions for implementing certain requirements.

#### Subpart B—Incident Reporting, Notification, BOE Approvals and Authorization

- 171.15 Immediate notice of certain hazardous materials incidents.
- 171.16 Detailed hazardous materials incident reports.
- 171.17–171.18 [Reserved]
- 171.19 Approvals or authorizations issued by the Bureau of Explosives.
- 171.20 Submission of Examination Reports.
- 171.21 Assistance in investigations and special studies.

#### Subpart C—Authorization and Requirements for the Use of International Transport Standards and Regulations

- 171.22 Authorization and conditions for the use of international standards and regulations.
- 171.23 Requirements for specific materials and packagings transported under the ICAO Technical Instructions, IMDG Code, Transport Canada TDG Regulations, or the IAEA Regulations.
- 171.24 Additional requirements for the use of the ICAO Technical Instructions.
- 171.25 Additional requirements for the use of the IMDG Code.
- 171.26 Additional requirements for the use of the IAEA Regulations.

AUTHORITY: 49 U.S.C. 5101–5128, 44701; 49 CFR 1.45 and 1.53; Pub. L. 101–410 section 4 (28

U.S.C. 2461 note); Pub. L. 104–134 section 31001.

EDITORIAL NOTE: Nomenclature changes to part 171 appear at 70 FR 56090, Sept. 23, 2005.

#### Subpart A—Applicability, General Requirements, and North American Shipments

##### § 171.1 Applicability of Hazardous Materials Regulations (HMR) to persons and functions.

Federal hazardous materials transportation law (49 U.S.C. 5101 *et seq.*) directs the Secretary of Transportation to establish regulations for the safe and secure transportation of hazardous materials in commerce, as the Secretary considers appropriate. The Secretary is authorized to apply these regulations to persons who transport hazardous materials in commerce. In addition, the law authorizes the Secretary to apply these regulations to persons who cause hazardous materials to be transported in commerce. The law also authorizes the Secretary to apply these regulations to persons who manufacture or maintain a packaging or a component of a packaging that is represented, marked, certified, or sold as qualified for use in the transportation of a hazardous material in commerce. Federal hazardous material transportation law also applies to anyone who indicates by marking or other means that a hazardous material being transported in commerce is present in a package or transport conveyance when it is not, and to anyone who tampers with a package or transport conveyance used to transport hazardous materials in commerce or a required marking, label, placard, or shipping description. Regulations prescribed in accordance with Federal hazardous materials transportation law shall govern safety aspects, including security, of the transportation of hazardous materials that the Secretary considers appropriate. In 49 CFR 1.53, the Secretary delegated authority to issue regulations for the safe and secure transportation of hazardous materials in commerce to the Pipeline and Hazardous

Materials Safety Administrator. The Administrator issues the Hazardous Materials Regulations (HMR; 49 CFR Parts 171 through 180) under that delegated authority. This section addresses the applicability of the HMR to packagings represented as qualified for use in the transportation of hazardous materials in commerce and to pre-transportation and transportation functions.

(a) *Packagings.* Requirements in the HMR apply to each person who manufactures, fabricates, marks, maintains, reconditions, repairs, or tests a packaging or a component of a packaging that is represented, marked, certified, or sold as qualified for use in the transportation of a hazardous material in commerce, including each person under contract with any department, agency, or instrumentality of the executive, legislative, or judicial branch of the Federal government who manufactures, fabricates, marks, maintains, reconditions, repairs, or tests a packaging or a component of a packaging that is represented, marked, certified, or sold as qualified for use in the transportation of a hazardous material in commerce.

(b) *Pre-transportation functions.* Requirements in the HMR apply to each person who offers a hazardous material for transportation in commerce, causes a hazardous material to be transported in commerce, or transports a hazardous material in commerce and who performs or is responsible for performing a pre-transportation function, including each person performing pre-transportation functions under contract with any department, agency, or instrumentality of the executive, legislative, or judicial branch of the Federal government. Pre-transportation functions include, but are not limited to, the following:

- (1) Determining the hazard class of a hazardous material.
- (2) Selecting a hazardous materials packaging.
- (3) Filling a hazardous materials packaging, including a bulk packaging.
- (4) Securing a closure on a filled or partially filled hazardous materials package or container or on a package or container containing a residue of a hazardous material.

(5) Marking a package to indicate that it contains a hazardous material.

(6) Labeling a package to indicate that it contains a hazardous material.

(7) Preparing a shipping paper.

(8) Providing and maintaining emergency response information.

(9) Reviewing a shipping paper to verify compliance with the HMR or international equivalents.

(10) For each person importing a hazardous material into the United States, providing the shipper with timely and complete information as to the HMR requirements that will apply to the transportation of the material within the United States.

(11) Certifying that a hazardous material is in proper condition for transportation in conformance with the requirements of the HMR.

(12) Loading, blocking, and bracing a hazardous materials package in a freight container or transport vehicle.

(13) Segregating a hazardous materials package in a freight container or transport vehicle from incompatible cargo.

(14) Selecting, providing, or affixing placards for a freight container or transport vehicle to indicate that it contains a hazardous material.

(c) *Transportation functions.* Requirements in the HMR apply to transportation of a hazardous material in commerce and to each person who transports a hazardous material in commerce, including each person under contract with any department, agency, or instrumentality of the executive, legislative, or judicial branch of the Federal government who transports a hazardous material in commerce. Transportation of a hazardous material in commerce begins when a carrier takes physical possession of the hazardous material for the purpose of transporting it and continues until the package containing the hazardous material is delivered to the destination indicated on a shipping document, package marking, or other medium, or, in the case of a rail car, until the car is delivered to a private track or siding. For a private motor carrier, transportation of a hazardous material in commerce begins when a motor vehicle driver takes possession of a hazardous

## § 171.1

## 49 CFR Ch. I (10–1–08 Edition)

material for the purpose of transporting it and continues until the driver relinquishes possession of the package containing the hazardous material at its destination and is no longer responsible for performing functions subject to the HMR with respect to that particular package. Transportation of a hazardous material in commerce includes the following:

(1) *Movement.* Movement of a hazardous material by rail car, aircraft, motor vehicle, or vessel (except as delegated by Department of Homeland Security Delegation No. 0170 at 2(103)).

(2) *Loading incidental to movement of a hazardous material.* Loading of packaged or containerized hazardous material onto a transport vehicle, aircraft, or vessel for the purpose of transporting it, including blocking and bracing a hazardous materials package in a freight container or transport vehicle, and segregating a hazardous materials package in a freight container or transport vehicle from incompatible cargo, when performed by carrier personnel or in the presence of carrier personnel. For a bulk packaging, loading incidental to movement is filling the packaging with a hazardous material for the purpose of transporting it when performed by carrier personnel or in the presence of carrier personnel (except as delegated by Department of Homeland Security Delegation No. 0170 at 2(103)), including transloading.

(3) *Unloading incidental to movement of a hazardous material.* Removing a package or containerized hazardous material from a transport vehicle, aircraft, or vessel; or for a bulk packaging, emptying a hazardous material from the bulk packaging after the hazardous material has been delivered to the consignee when performed by carrier personnel or in the presence of carrier personnel or, in the case of a private motor carrier, while the driver of the motor vehicle from which the hazardous material is being unloaded immediately after movement is completed is present during the unloading operation. (Emptying a hazardous material from a bulk packaging while the packaging is on board a vessel is subject to separate regulations as delegated by Department of Homeland Security Delegation No. 0170 at 2(103).)

Unloading incidental to movement includes transloading.

(4) *Storage incidental to movement of a hazardous material.* Storage of a transport vehicle, freight container, or package containing a hazardous material by any person between the time that a carrier takes physical possession of the hazardous material for the purpose of transporting it until the package containing the hazardous material has been delivered to the destination indicated on a shipping document, package marking, or other medium, or, in the case of a private motor carrier, between the time that a motor vehicle driver takes physical possession of the hazardous material for the purpose of transporting it until the driver relinquishes possession of the package at its destination and is no longer responsible for performing functions subject to the HMR with respect to that particular package.

(i) Storage incidental to movement includes—

(A) Storage at the destination shown on a shipping document, including storage at a transloading facility, provided the original shipping documentation identifies the shipment as a through-shipment and identifies the final destination or destinations of the hazardous material; and

(B) A rail car containing a hazardous material that is stored on track that does not meet the definition of “private track or siding” in §171.8, even if the car has been delivered to the destination shown on the shipping document.

(ii) Storage incidental to movement does not include storage of a hazardous material at its final destination as shown on a shipping document.

(d) *Functions not subject to the requirements of the HMR.* The following are examples of activities to which the HMR do not apply:

(1) Storage of a freight container, transport vehicle, or package containing a hazardous material at an offeror facility prior to a carrier taking possession of the hazardous material for movement in transportation in commerce or, for a private motor carrier, prior to a motor vehicle driver

taking physical possession of the hazardous material for movement in transportation in commerce.

(2) Unloading of a hazardous material from a transport vehicle or a bulk packaging performed by a person employed by or working under contract to the consignee following delivery of the hazardous material by the carrier to its destination and departure from the consignee's premises of the carrier's personnel or, in the case of a private carrier, departure of the driver from the unloading area.

(3) Storage of a freight container, transport vehicle, or package containing a hazardous material after its delivery by a carrier to the destination indicated on a shipping document, package marking, or other medium, or, in the case of a rail car, storage of a rail car on private track.

(4) Rail and motor vehicle movements of a hazardous material exclusively within a contiguous facility boundary where public access is restricted, except to the extent that the movement is on or crosses a public road or is on track that is part of the general railroad system of transportation, unless access to the public road is restricted by signals, lights, gates, or similar controls.

(5) Transportation of a hazardous material in a motor vehicle, aircraft, or vessel operated by a Federal, state, or local government employee solely for noncommercial Federal, state, or local government purposes.

(6) Transportation of a hazardous material by an individual for non-commercial purposes in a private motor vehicle, including a leased or rented motor vehicle.

(7) Any matter subject to the postal laws and regulations of the United States.

(e) *Requirements of other Federal agencies.* Each facility at which pre-transportation or transportation functions are performed in accordance with the HMR may be subject to applicable standards and regulations of other Federal agencies.

(f) *Requirements of state and local government agencies.* (1) Under 49 U.S.C. 5125, a requirement of a state, political subdivision of a state, or an Indian tribe is preempted, unless otherwise

authorized by another Federal statute or DOT issues a waiver of preemption, if—

(i) Complying with both the non-Federal requirement and Federal hazardous materials transportation law, the regulations issued under Federal hazardous material transportation law or a hazardous material transportation security regulation or directive issued by the Secretary of Homeland Security is not possible;

(ii) The non-Federal requirement, as applied or enforced, is an obstacle to accomplishing and carrying out Federal hazardous materials transportation law, the regulations issued under Federal hazardous material transportation law, or a hazardous material transportation security regulation or directive issued by the Secretary of Homeland Security;

(iii) The non-Federal requirement is not substantively the same as a provision of Federal hazardous materials transportation law, the regulations issued under Federal hazardous material transportation law, or a hazardous material transportation security regulation or directive issued by the Secretary of Homeland Security with respect to—

(A) The designation, description, and classification of hazardous material;

(B) The packing, repacking, handling, labeling, marking, and placarding of hazardous material;

(C) The preparation, execution, and use of shipping documents related to hazardous material and requirements related to the number, contents, and placement of those documents;

(D) The written notification, recording, and reporting of the unintentional release of hazardous material; or

(E) The design, manufacturing, fabricating, marking, maintenance, reconditioning, repairing, or testing of a package or container represented, marked, certified, or sold as qualified for use in transporting hazardous material.

(iv) A non-Federal designation, limitation or requirement on highway routes over which hazardous material may or may not be transported does not comply with the regulations in subparts C and D of part 397 of this title; or



## § 171.2

## 49 CFR Ch. I (10–1–08 Edition)

(v) A fee related to the transportation of a hazardous material is not fair or is used for a purpose that is not related to transporting hazardous material, including enforcement and planning, developing, and maintaining a capability for emergency response.

(2) Subject to the limitations in paragraph (f)(1) of this section, each facility at which functions regulated under the HMR are performed may be subject to applicable laws and regulations of state and local governments and Indian tribes.

(3) The procedures for DOT to make administrative determinations of preemption are set forth in subpart E of part 397 of this title with respect to non-Federal requirements on highway routing (paragraph (f)(1)(iv) of this section) and in subpart C of part 107 of this chapter with respect to all other non-Federal requirements.

(g) *Penalties for noncompliance.* Each person who knowingly violates a requirement of the Federal hazardous material transportation law, an order issued under Federal hazardous material transportation law, subchapter A of this chapter, or a special permit or approval issued under subchapter A or C of this chapter is liable for a civil penalty of not more than \$50,000 and not less than \$250 for each violation, except the maximum civil penalty is \$100,000 if the violation results in death, serious illness or severe injury to any person or substantial destruction of property, and a minimum \$450 civil penalty applies to a violation relating to training. When a violation is a continuing one and involves transporting of hazardous material or causing them to be transported, each day of the violation is a separate offense. Each person who knowingly violates § 171.2(l) or willfully or recklessly violates a provision of the Federal hazardous material transportation law, an order issued under Federal hazardous material transportation law, subchapter A of this chapter, or a special permit or approval issued under subchapter A or C of this chapter, shall be fined under title 18, United States Code, or imprisoned for not more than 5 years, or both, except the maximum amount of imprisonment shall be 10 years in any case in which a violation

involves the release of a hazardous material which results in death or bodily injury to any person.

[68 FR 61937, Oct. 30, 2003; 70 FR 20031, Apr. 15, 2005, as amended at 70 FR 73162, Dec. 9, 2005; 71 FR 8488, Feb. 17, 2006; 71 FR 44931, Aug. 8, 2006]

### § 171.2 General requirements.

(a) Each person who performs a function covered by this subchapter must perform that function in accordance with this subchapter.

(b) Each person who offers a hazardous material for transportation in commerce must comply with all applicable requirements of this subchapter, or an exemption or special permit, approval, or registration issued under this subchapter or under subchapter A of this chapter. There may be more than one offeror of a shipment of hazardous materials. Each offeror is responsible for complying with the requirements of this subchapter, or an exemption or special permit, approval, or registration issued under this subchapter or subchapter A of this chapter, with respect to any pre-transportation function that it performs or is required to perform; however, each offeror is responsible only for the specific pre-transportation functions that it performs or is required to perform, and each offeror may rely on information provided by another offeror, unless that offeror knows or, a reasonable person, acting in the circumstances and exercising reasonable care, would have knowledge that the information provided by the other offeror is incorrect.

(c) Each person who performs a function covered by or having an effect on a specification or activity prescribed in part 178, 179, or 180 of this subchapter, an approval issued under this subchapter, or an exemption or special permit issued under subchapter A of this chapter, must perform the function in accordance with that specification, approval, an exemption or special permit, as appropriate.

(d) No person may offer or accept a hazardous material for transportation in commerce or transport a hazardous material in commerce unless that person is registered in conformance with subpart G of part 107 of this chapter, if applicable.

(e) No person may offer or accept a hazardous material for transportation in commerce unless the hazardous material is properly classed, described, packaged, marked, labeled, and in condition for shipment as required or authorized by applicable requirements of this subchapter or an exemption or special permit, approval, or registration issued under this subchapter or subchapter A of this chapter.

(f) No person may transport a hazardous material in commerce unless the hazardous material is transported in accordance with applicable requirements of this subchapter, or an exemption or special permit, approval, or registration issued under this subchapter or subchapter A of this chapter. Each carrier who transports a hazardous material in commerce may rely on information provided by the offeror of the hazardous material or a prior carrier, unless the carrier knows or, a reasonable person, acting in the circumstances and exercising reasonable care, would have knowledge that the information provided by the offeror or prior carrier is incorrect.

(g) No person may represent, mark, certify, sell, or offer a packaging or container as meeting the requirements of this subchapter governing its use in the transportation of a hazardous material in commerce unless the packaging or container is manufactured, fabricated, marked, maintained, reconditioned, repaired, and retested in accordance with the applicable requirements of this subchapter. No person may represent, mark, certify, sell, or offer a packaging or container as meeting the requirements of an exemption, a special permit, approval, or registration issued under this subchapter or subchapter A of this chapter unless the packaging or container is manufactured, fabricated, marked, maintained, reconditioned, repaired, and retested in accordance with the applicable requirements of the exemption, special permit, approval, or registration issued under this subchapter or subchapter A of this chapter. The requirements of this paragraph apply whether or not the packaging or container is used or to be used for the transportation of a hazardous material.

(h) The representations, markings, and certifications subject to the prohibitions of paragraph (g) of this section include:

(1) Specification identifications that include the letters “ICC”, “DOT”, “CTC”, “MC”, or “UN”;

(2) Exemption, special permit, approval, and registration numbers that include the letters “DOT”, “EX”, “M”, or “R”; and

(3) Test dates associated with specification, registration, approval, retest, exemption, or special permit markings indicating compliance with a test or retest requirement of the HMR, or an exemption, special permit, approval, or registration issued under the HMR or under subchapter A of this chapter.

(i) No person may certify that a hazardous material is offered for transportation in commerce in accordance with the requirements of this subchapter unless the hazardous material is properly classed, described, packaged, marked, labeled, and in condition for shipment as required or authorized by applicable requirements of this subchapter or an exemption or special permit, approval, or registration issued under this subchapter or subchapter A of this chapter. Each person who offers a package containing a hazardous material for transportation in commerce in accordance with the requirements of this subchapter or an exemption or special permit, approval, or registration issued under this subchapter or subchapter A of this chapter, must assure that the package remains in condition for shipment until it is in the possession of the carrier.

(j) No person may, by marking or otherwise, represent that a container or package for transportation of a hazardous material is safe, certified, or in compliance with the requirements of this chapter unless it meets the requirements of all applicable regulations issued under Federal hazardous material transportation law.

(k) No person may, by marking or otherwise, represent that a hazardous material is present in a package, container, motor vehicle, rail car, aircraft, or vessel if the hazardous material is not present.

(l) No person may alter, remove, deface, destroy, or otherwise unlawfully

### § 171.3

tamper with any marking, label, placard, or description on a document required by Federal hazardous material transportation law or the regulations issued under Federal hazardous material transportation law. No person may alter, deface, destroy, or otherwise unlawfully tamper with a package, container, motor vehicle, rail car, aircraft, or vessel used for the transportation of hazardous materials.

(m) No person may falsify or alter an exemption or special permit, approval, registration, or other grant of authority issued under this subchapter or subchapter A of this chapter. No person may offer a hazardous material for transportation or transport a hazardous material in commerce under an exemption or special permit, approval, registration or other grant of authority issued under this subchapter or subchapter A of this chapter if such grant of authority has been altered without the consent of the issuing authority. No person may represent, mark, certify, or sell a packaging or container under an exemption or special permit, approval, registration or other grant of authority issued under this subchapter or subchapter A of this chapter if such grant of authority has been altered without the consent of the issuing authority.

[68 FR 61937, Oct. 30, 2003, as amended at 70 FR 43643, July 28, 2005; 70 FR 73162, Dec. 9, 2005]

#### § 171.3 Hazardous waste.

(a) No person may offer for transportation or transport a hazardous waste (as defined in § 171.8 of this subchapter) in interstate or intrastate commerce except in accordance with the requirements of this subchapter.

(b) No person may accept for transportation, transport, or deliver a hazardous waste for which a manifest is required unless that person:

(1) Has marked each motor vehicle used to transport hazardous waste in accordance with § 390.21 of this title even though placards may not be required;

(2) Complies with the requirements for manifests set forth in § 172.205 of this subchapter; and

(3) Delivers, as designated on the manifest by the generator, the entire

### 49 CFR Ch. I (10–1–08 Edition)

quantity of the waste received from the generator or a transporter to:

(i) The designated facility or, if not possible, to the designated alternate facility;

(ii) The designated subsequent carrier; or

(iii) A designated place outside the United States.

NOTE: Federal law specifies penalties up to \$250,000 fine for an individual and \$500,000 for a company and 5 years imprisonment for the willful discharge of hazardous waste at other than designated facilities. 49 U.S.C. 5124.

(c) If a discharge of hazardous waste or other hazardous material occurs during transportation, and an official of a State or local government or a Federal agency, acting within the scope of his official responsibilities, determines that immediate removal of the waste is necessary to prevent further consequence, that official may authorize the removal of the waste without the preparation of a manifest. [NOTE: In such cases, EPA does not require carriers to have EPA identification numbers.]

NOTE 1: EPA requires shippers (generators) and carriers (transporters) of hazardous wastes to have identification numbers which must be displayed on hazardous waste manifests. See 40 CFR parts 262 and 263. (Identification number application forms may be obtained from EPA regional offices.)

NOTE 2: In 40 CFR part 263, the EPA sets forth requirements for the cleanup of releases of hazardous wastes.

[Amdt. 171–53, 45 FR 34586, May 22, 1980, as amended by Amdt. 171–53, 45 FR 74648, Nov. 10, 1980; Amdt. 171–78, 49 FR 10510, Mar. 20, 1984; Amdt. 171–107, 54 FR 40068, Sept. 29, 1989; Amdt. 171–111, 55 FR 52466, Dec. 21, 1990; 56 FR 66157, Dec. 20, 1991; Amdt. 171–2, 59 FR 49132, Sept. 26, 1994; Amdt. 171–141, 61 FR 21102, May 9, 1996; 73 FR 57004, Oct. 1, 2008]

#### § 171.4 Marine pollutants.

(a) Except as provided in paragraph (c) of this section, no person may offer for transportation or transport a marine pollutant, as defined in § 171.8, in intrastate or interstate commerce except in accordance with the requirements of this subchapter.

(b) The requirements of this subchapter for the transportation of marine pollutants are based on the provisions of Annex III of the 1973 International Convention for Prevention of

## Pipeline and Hazardous Materials Safety Admin., DOT

## § 171.6

Pollution from Ships, as modified by the Protocol of 1978 (MARPOL 73/78).

(c) *Exceptions.* Except when all or part of the transportation is by vessel, the requirements of this subchapter specific to marine pollutants do not apply to non-bulk packagings transported by motor vehicle, rail car or aircraft.

[Amdt. 171-116, 57 FR 52934, Nov. 5, 1993, as amended by Amdt. 107-39, 61 FR 51337, Oct. 1, 1996; 73 FR 4712, Jan. 28, 2008]

### § 171.6 Control numbers under the Paperwork Reduction Act.

(a) *Purpose and scope.* This section collects and displays the control numbers assigned to the HMR collections of information by the Office of Management and Budget (OMB) under the Paperwork Reduction Act of 1995. This section complies with the requirements

of 5 CFR 1320.7(f), 1320.12, 1320.13 and 1320.14 (OMB regulations implementing the Paperwork Reduction Act of 1995) for the display of control numbers assigned by OMB to collections of information of the HMR.

(b) *OMB control numbers.* The table in paragraph (b)(2) of this section sets forth the control numbers assigned to collection of information in the HMR by the Office of Management and Budget (OMB) under the Paperwork Reduction Act of 1995.

(1) Column 1 lists the OMB control number assigned to the HMR collections of information. Column 2 contains the Report Title of the approved collection of information. Column 3 lists the part(s) or section(s) in 49 CFR identified or described in the collection of information.

(2) Table.

| Current OMB control No. | Title                                                                      | Title 49 CFR part or section where identified and described                                                                                                                                                                  |
|-------------------------|----------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 2137-0014 .....         | Cargo Tank Specification Requirements .....                                | §§ 107.503, 107.504, 178.320, 178.337, 178.338, 178.345, 180.407, 180.409, 180.413, 180.417.                                                                                                                                 |
| 2137-0018 .....         | Inspection and Testing of Portable Tanks and Intermediate Bulk Containers. | §§ 173.24, 173.32, 178.3, 178.255, 178.273, 178.274, 178.703, 178.801, 180.352, 180.605.                                                                                                                                     |
| 2137-0022 .....         | Testing, Inspection, and Marking Requirements for Cylinders.               | §§ 173.302a, 173.303, 173.304, 173.309, 178.2, 178.3, 178.35, 178.44, 178.45, 178.46, 178.57, 178.59, 178.60, 178.61, 178.68, 180.205, 180.209, 180.211, 180.213, 180.215, Appendix C to Part 180.                           |
| 2137-0034 .....         | Hazardous Materials Shipping Papers and Emergency Response Information.    | §§ 172.200, 172.201, 172.202, 172.203, 172.204, 172.505, 172.600, 172.602, 172.604, 172.606, 173.6, 173.7, 173.22, 173.56, 174.24, 174.26, 174.114, 175.30, 175.31, 175.33, 176.24, 176.27, 176.30, 176.36, 176.89, 177.817. |
| 2137-0039 .....         | Hazardous Materials Incidents Reports .....                                | §§ 171.15, 171.16, 171.21.                                                                                                                                                                                                   |
| 2137-0051 .....         | Rulemaking and Special Permit Petitions .....                              | §§ 105.30, 105.40, 106.95, 106.110, 107.105, 107.107, 107.109, 107.113, 107.117, 107.121, 107.123, 107.125, 107.205, 107.211, 107.215, 107.217, 107.219, 107.221, 107.223.                                                   |
| 2137-0510 .....         | RAM Transportation Requirements .....                                      | Part 173, Subpart I, §§ 173.22, 173.411, 173.415, 173.416, 173.417, 173.457, 173.471, 173.472, 173.473, 173.476.                                                                                                             |
| 2137-0542 .....         | Flammable Cryogenic Liquids .....                                          | §§ 173.318, 177.816, 177.840, 180.405.                                                                                                                                                                                       |

§ 171.7

49 CFR Ch. I (10–1–08 Edition)

| Current OMB control No. | Title                                                                                                                               | Title 49 CFR part or section where identified and described                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|-------------------------|-------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 2137–0557 .....         | Approvals for Hazardous Materials                                                                                                   | §§ 107.402, 107.403, 107.405, 107.502, 107.503, 107.705, 107.713, 107.715, 107.717, 107.803, 107.805, 107.807, 110.30, 172.101, 172.102, Special Provisions 19, 26, 53, 55, 60, 105, 118, 121, 125, 129, 131, 133, 136, B45, B55, B61, B69, B77, B81, N10, N72, 173.2a, 173.4, 173.7, 173.21, 173.22, 173.24, 173.31, 173.38, 173.51, 173.56, 173.58, 173.59, 173.124, 173.128, 173.159, 173.166, 173.171, 173.214, 173.222, 173.224, 173.225, 173.245, 173.301, 173.305, 173.306, 173.314, 173.315, 173.316, 173.318, 173.334, 173.340, 173.411, 173.433, 173.457, 173.471, 173.472, 173.476, 174.50, 174.63, 175.8, 175.85, 175.701, 175.703, 176.168, 176.340, 176.704, 178.3, 178.35, 178.47, 178.53, 178.273, 178.274, 178.503, 178.509, 178.605, 178.606, 178.608, 178.801, 178.813, 180.213.                    |
| 2137–0559 .....         | (Rail Carriers and Tank Car Tank Requirements) Requirements for Rail Tank Car Tanks—Transportation of Hazardous Materials by Rail.. | §§ 172.102, Special provisions: B45, B46, B55, B61, B69, B77, B78, B81; 173.10, 173.31, 174.20, 174.50, 174.63, 174.104, 174.114, 174.204, 179.3, 179.4, 179.5, 179.6, 179.7, 179.11, 179.18, 179.22, 179.100–9, 179.100–12, 179.100–13, 179.100–16, 179.100–17, 179.102–4, 179.102–17, 179.103–1, 179.103–2, 179.103–3, 179.103–5, 179.200–10, 179.200–14, 179.200–15, 179.200–16, 179.200–17, 179.200–19, 179.201–3, 179.201–8, 179.201–9, 179.220–4, 179.220–7, 179.220–8, 179.220–13, 179.220–15, 179.220–17, 179.220–18, 179.220–20, 179.220–22, 179.300–3, 179.300–7, 179.300–9, 179.300–12, 179.300–13, 179.300–15, 179.300–20, 179.400–3, 179.400–4, 179.400–11, 179.400–13, 179.400–16, 179.400–17, 179.400–19, 179.400–20, 179.500–5, 179.500–8, 179.500–12, 179.500–18, 180.505, 180.509, 180.515, 180.517. |
| 2137–0572 .....         | Testing Requirements for Non-Bulk Packaging ..                                                                                      | §§ 178.2, 178.601.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 2137–0582 .....         | Container Certification Statement .....                                                                                             | §§ 176.27, 176.172.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| 2137–0586 .....         | Hazardous Materials Public Sector Training and Planning Grants.                                                                     | Part 110.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| 2137–0591 .....         | Response Plans for Shipments of Oil .....                                                                                           | Part 130.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| 2137–0595 .....         | Cargo Tank Motor Vehicles in Liquefied Compressed Gas Service.                                                                      | §§ 173.315, 178.337–8, 178.337–9, 180.405, 180.416.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| 2137–0612 .....         | Hazardous Materials Security Plans .....                                                                                            | Part 172, Subpart I, §§ 172.800, 172.802, 172.804.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 2137–0613 .....         | Subsidiary Hazard Class and Number/Type of Packagings.                                                                              | §§ 172.202, 172.203                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| 2137–0620 .....         | Inspection and Testing of Meter Provers .....                                                                                       | Part 173, Subpart A, § 173.5a.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| 2137–0621 .....         | Requirements for United Nations (UN) Cylinders                                                                                      | §§ 173.301, 173.304, 173.304b, 178.69, 178.70, 178.74, 178.75, 180.207, 180.209, 180.212, 180.215, 180.217.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |

[Amdt. 171–111, 56 FR 66157, Dec. 20, 1991, as amended at 57 FR 1877, Jan. 16, 1992; Amdt. 171–121, 58 FR 51527, Oct. 1, 1993; Amdt. 171–137, 61 FR 33254, June 26, 1996; 62 FR 51558, Oct. 1, 1997; 64 FR 51915, Sept. 27, 1999; 64 FR 61220, Nov. 10, 1999; 65 FR 58619, Sept. 29, 2000; 67 FR 61012, Sept. 27, 2002; 67 FR 51640, Aug. 8, 2002; 68 FR 31628, May 28, 2003; 68 FR 45010, July 31, 2003; 69 FR 54045, Sept. 7, 2004; 70 FR 33379, June 8, 2005; 70 FR 56090, Sept. 23, 2005; 70 FR 73163, Dec. 9, 2005; 71 FR 54391, Sept. 14, 2006; 72 FR 55683, Oct. 1, 2007]

§ 171.7 Reference material.

(a) *Matter incorporated by reference—*  
(1) *General.* There is incorporated, by reference in parts 170–189 of this sub-

chapter, matter referred to that is not specifically set forth. This matter is hereby made a part of the regulations in parts 170–189 of this subchapter. The

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 171.7**

matter subject to change is incorporated only as it is in effect on the date of issuance of the regulation referring to that matter. The material listed in paragraph (a)(3) has been approved for incorporation by reference by the Director of the Federal Register in accordance with 5 U.S.C 552(a) and 1 CFR part 51. Material is incorporated as it exists on the date of the approval and a notice of any change in the material will be published in the FEDERAL REGISTER. Matters referenced by footnote are included as part of the regulations of this subchapter.

(2) *Accessibility of materials.* All incorporated matter is available for inspection at:

(i) The Office of Hazardous Materials Safety, Office of Hazardous Materials Standards, East Building, PHH-10, 1200

New Jersey Avenue, SE., Washington, DC 20590-0001; and

(ii) The National Archives and Records Administration (NARA). For information on the availability of this material at NARA, call 202-741-6030, or go to: [http://www.archives.gov/federal\\_register/code\\_of\\_federal\\_regulations/ibr\\_locations.html](http://www.archives.gov/federal_register/code_of_federal_regulations/ibr_locations.html).

(3) *Table of material incorporated by reference.* The following table sets forth material incorporated by reference. The first column lists the name and address of the organization from which the material is available and the name of the material. The second column lists the section(s) of this subchapter, other than §171.7, in which the matter is referenced. The second column is presented for information only and may not be all inclusive.

| Source and name of material                                                                                                                                                                                                                                                                                                           | 49 CFR reference  |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
| <i>Air Transport Association of America</i> , 1301 Pennsylvania Avenue, N.W., Washington, DC 20004-1707:<br>ATA Specification No. 300 Packaging of Airline Supplies, Revision 19, July 31, 1996 .....                                                                                                                                 | 172.102.          |
| <i>The Aluminum Association</i> , 420 Lexington Avenue, New York, NY 10017:<br>Aluminum Standards and Data, Seventh Edition, June 1982 .....                                                                                                                                                                                          | 172.102; 178.65.  |
| <i>American National Standards Institute, Inc.</i> , 25 West 43rd Street, New York, NY 10036:<br>ANSI/ASHRAE 15-94, Safety Code for Mechanical Refrigeration .....                                                                                                                                                                    | 173.306; 173.307. |
| ANSI B16.5-77, Steel Pipe Flanges, Flanged Fittings .....                                                                                                                                                                                                                                                                             | 178.360-4.        |
| ANSI N14.1 Uranium Hexafluoride—Packaging for Transport, 1971, 1982, 1987, 1990, 1995 and 2001 Editions.                                                                                                                                                                                                                              | 173.417; 173.420. |
| <i>American Petroleum Institute</i> , 1220 L Street, NW, Washington, D.C. 20005-4070:<br>API Recommended Practice Closures of Underground Petroleum Storage Tanks, 3rd Edition, March 1996.                                                                                                                                           | 172.102.          |
| <i>American Pyrotechnics Association (APA)</i> , P.O. Box 30438, Bethesda, MD 20824, (301) 907-8181, <a href="http://www.americanpyro.com">www.americanpyro.com</a> :<br>APA Standard 87-1, Standard for Construction and Approval for Transportation of Fireworks, Novelties, and Theatrical Pyrotechnics, December 1, 2001 version. | 173.56.           |
| <i>American Society of Mechanical Engineers</i> , ASME International, 22 Law Drive, P.O. Box 2900, Fairfield, NJ 07007-2900:                                                                                                                                                                                                          |                   |

| Source and name of material                                                                                                                                                                                                      | 49 CFR reference                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ASME Code, Sections II (Parts A and B), V, VIII (Division 1), and IX of 1998 Edition of American Society of Mechanical Engineers Boiler and Pressure Vessel Code.                                                                | 172.102; 173.24b;<br>173.32; 173.306;<br>173.315; 173.318;<br>173.420; 178.245–<br>1; 178.245–3;<br>178.245–4;<br>178.245–6;<br>178.245–7;<br>178.255–1;<br>178.255–2;<br>178.255–14;<br>178.255–15;<br>178.273; 178.274;<br>178.276; 178.277;<br>178.320; 178.337–<br>1; 178.337–2;<br>178.337–3;<br>178.337–4;<br>178.337–6;<br>178.337–16;<br>178.337–18;<br>178.338–1;<br>178.338–2;<br>178.338–3;<br>178.338–3;<br>178.338–4;<br>178.338–5;<br>178.338–6;<br>178.338–13;<br>178.338–16;<br>178.338–18;<br>178.338–19;<br>178.345–1;<br>178.345–2;<br>178.345–3;<br>178.345–4;<br>178.345–7;<br>178.345–14;<br>178.345–15;<br>178.346–1;<br>178.347–1;<br>178.348–1;<br>179.400–3;<br>180.407. |
| Pipeline Transportation Systems for Liquid Hydrocarbons and other Liquids, Chapters II, III, IV, V and VI, ASME B31.4–1998 Edition.                                                                                              | 173.5a.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| <i>American Society for Testing and Materials</i> , 100 Barr Harbor Drive, West Conshohocken, PA 19428:<br>Noncurrent ASTM Standards are available from: Engineering Societies Library, 354 East 47th Street, New York, NY 10017 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| ASTM A 20/A 20M–93a Standard Specification for General Requirements for Steel Plates for Pressure Vessels.                                                                                                                       | 178.337–2;<br>179.102–4;<br>179.102–1;<br>179.102–17.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| ASTM A 47–68 Malleable Iron Castings .....                                                                                                                                                                                       | 179.200–15.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| ASTM A 240/A 240M–99b Standard Specification for Heat-Resisting Chromium and Chromium-Nickel Stainless Steel Plate, Sheet and Strip for Pressure Vessels.                                                                        | 178.57; 178.358–5;<br>179.100–7;<br>179.100–10;<br>179.102–1;<br>179.102–4;<br>179.102–17;<br>179.200–7;<br>179.201–5;<br>179.220–7;<br>179.300–7;<br>179.400–5.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| ASTM A 242–81 Standard Specification for High-Strength Low-Alloy Structural Steel .....                                                                                                                                          | 178.338–2.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| ASTM A 262–93a Standard Practices for Detecting Susceptibility to Intergranular Attack in Austenitic Stainless Steels.                                                                                                           | 179.100–7;<br>179.200–7;<br>179.201–4.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| ASTM A 285–78 Pressure Vessel Plates, Carbon Steel, Low- and Intermediate-Tensile Strength                                                                                                                                       | 179.300–7.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| ASTM A 300–58 Steel Plates for Pressure Vessels for Service at Low Temperatures .....                                                                                                                                            | 178.337–2.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |

Pipeline and Hazardous Materials Safety Admin., DOT

§ 171.7

| Source and name of material                                                                                                                                                                   | 49 CFR reference                                                                                                                                                |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ASTM A 302/A 302M-93 Standard Specification for Pressure Vessel Plates, Alloy Steel, Manganese-Molybdenum and Manganese-Molybdenum Nickel.                                                    | 179.100-7;<br>179.200-7;<br>179.220-7.                                                                                                                          |
| ASTM A 333-67 Seamless and Welded Steel Pipe for Low-Temperature Service .....                                                                                                                | 178.45.                                                                                                                                                         |
| ASTM A 370-94 Standard Test 179.102-1; 179.102-4; Methods and Definitions for Mechanical Testing of Steel Products.                                                                           | 179.102-17.                                                                                                                                                     |
| ASTM A 441-81 Standard Specification for High-Strength Low-Alloy Structural Manganese Vanadium Steel.                                                                                         | 178.338-2.                                                                                                                                                      |
| ASTM A 514-81 Standard Specification for High-Yield Strength Quenched and Tempered Alloy Steel Plate, Suitable for Welding.                                                                   | 178.338-2.                                                                                                                                                      |
| ASTM A 515/A 515M-03 Standard Specification for Pressure Vessel Plates, Carbon Steel, for Intermediate- and Higher-Temperature Service.                                                       | 179.300-7.                                                                                                                                                      |
| ASTM A 516/A 516M-90 Standard Specification for Pressure Vessel Plates, Carbon Steel, for Moderate and Lower-Temperature Service.                                                             | 178.337-2;<br>179.100-7;<br>179.102-1;<br>179.102-2;<br>179.102-4;<br>179.102-17;<br>179.200-7;<br>179.220-7;<br>179.300-7.                                     |
| ASTM A 537/A 537M-91 Standard Specification for Pressure Vessel Plates, Heat-Treated, Carbon-Manganese-Silicon Steel.                                                                         | 179.100-7;<br>179.102-4;<br>179.102-17.                                                                                                                         |
| ASTM A 572-82 Standard Specification for High-Strength Low-Alloy Columbium-Vanadium Steels of Structural Quality.                                                                             | 178.338-2.                                                                                                                                                      |
| ASTM A 588-81 Standard Specification for High-Strength Low-Alloy Structural Steel with 50 Ksi Minimum Yield Point to 4 in. Thick.                                                             | 178.338-2.                                                                                                                                                      |
| ASTM A 606-75 Standard Specification for Steel Sheet and Strip Hot-Rolled and Cold-Rolled, High-Strength, Low-Alloy, with Improved Atmospheric Corrosion Resistance, 1975 (Re-approved 1981). | 178.338-2.                                                                                                                                                      |
| ASTM A 607-98 Standard Specification for Steel, Sheet and Strip, High-Strength, Low-Alloy, Columbium or Vanadium, or Both, Hot-Rolled and Cold-Rolled.                                        | 178.338-2.                                                                                                                                                      |
| ASTM A 612-72a High Strength Steel Plates for Pressure Vessels for Moderate and Lower Temperature Service.                                                                                    | 178.337-2.                                                                                                                                                      |
| ASTM A 633-79a Standard Specification for Normalized High-Strength Low-Alloy Structural Steel, 1979 Edition.                                                                                  | 178.338-2.                                                                                                                                                      |
| ASTM A 715-81 Standard Specification for Steel Sheet and Strip, Hot-Rolled, High-Strength, Low-Alloy with Improved Formability, 1981.                                                         | 178.338-2.                                                                                                                                                      |
| ASTM A 1008/A 1008M-03 Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy and High Strength Low-Alloy with Improved Formability.               | 178.338-2;<br>178.345-2                                                                                                                                         |
| ASTM A 1011/A 1011M-03a Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low Alloy and High Strength Low-Alloy with Improved Formability.     | 178.338-2;<br>178.345-2                                                                                                                                         |
| ASTM B 162-93a Standard Specification for Nickel Plate, Sheet, and Strip .....                                                                                                                | 173.249; 179.200-7.                                                                                                                                             |
| ASTM B 209-93 Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate .....                                                                                                    | 179.100-7;<br>179.200-7;<br>179.220-7.                                                                                                                          |
| ASTM B 221-76 Aluminum Alloy Extruded Bars, Rods, Shapes, and Tubes .....                                                                                                                     | 178.46.                                                                                                                                                         |
| ASTM B 557-84 Tension Testing Wrought and Cast Aluminum and Magnesium-Alloy Products ..                                                                                                       | 178.46.                                                                                                                                                         |
| ASTM B 580-79 Standard Specification for Anodic Oxide Coatings on Aluminum, (Re-approved 2000).                                                                                               | 173.316; 173.318;<br>178.338-17.                                                                                                                                |
| ASTM D 1238-90b Standard Test Method for Flow Rates of Thermoplastics for Extrusion Plastometer.                                                                                              | 173.225.                                                                                                                                                        |
| ASTM D 1709-01 Standard Text Methods for Impact Resistance of Plastic Film by the Free-Falling Dart Method.                                                                                   | 173.197.                                                                                                                                                        |
| ASTM D 1835-97 Standard Specification for Liquefied Petroleum (LP) Gases .....                                                                                                                | 180.209.                                                                                                                                                        |
| ASTM D 1838-64 Copper Strip Corrosion by Liquefied Petroleum (LP) Gases .....                                                                                                                 | 173.315.                                                                                                                                                        |
| ASTM D 1922-00a Standard Test Method for Propagation Tear Resistance of Plastic Film and Thin Sheeting by Pendulum Method.                                                                    | 173.197.                                                                                                                                                        |
| ASTM D 4206-96 Standard Test Method for Sustained Burning of Liquid Mixtures Using the Small Scale Open-Cup Apparatus.                                                                        | 173.120.                                                                                                                                                        |
| ASTM D 4359-90 Standard Test Method for Determining Whether a Material is a Liquid or a Solid.                                                                                                | 171.8.                                                                                                                                                          |
| ASTM E 8-99 Standard Test Methods for Tension Testing of Metallic Materials .....                                                                                                             | 178.36; 178.37;<br>178.38; 178.39;<br>178.44; 178.45;<br>178.50; 178.51;<br>178.53; 178.55;<br>178.56; 178.57;<br>178.58; 178.59;<br>178.60; 178.61;<br>178.68. |
| ASTM E 23-98 Standard Test Methods for Notched Bar Impact Testing of Metallic Materials .....                                                                                                 | 178.57.                                                                                                                                                         |



| Source and name of material                                                                                                                                                      | 49 CFR reference                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ASTM E 112–88 Standard Test Methods for Determining Average Grain Size .....                                                                                                     | 178.44.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| ASTM E 112–96 Standard Test Methods for Determining Average Grain Size, 1996 Edition .....                                                                                       | 178.274; Part 178,<br>appendix A.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| ASTM E 114–95 Standard Practice for Ultrasonic Pulse-Echo Straight-Beam Examination by the<br>Contact Method.                                                                    | 178.45.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| ASTM E 213–98 Standard Practice for Ultrasonic Examination of Metal Pipe and Tubing .....                                                                                        | 178.45.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| <i>American Water Works Association</i> , 1010 Vermont Avenue, N.W., Suite 810, Washington, DC 20005:                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| AWWA Standard C207–55, Steel Pipe Flanges, 1955 .....                                                                                                                            | 178.360–4.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
| <i>American Welding Society</i> , 550 N.W. Le Jeune Road, Miami, Florida 33126:                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| AWS Code B 3.0; Standard Qualification Procedure; 1972 (FRB 3.0–41, rev. May 1973) .....                                                                                         | 178.356–2,<br>178.358–2.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| AWS Code D 1.0; Code for Welding in Building Construction (FR D 1.0–66, 1966) .....                                                                                              | 178.356–2,<br>178.358–2.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| <i>Association of American Railroads</i> , American Railroads Building, 50 F Street, NW., Washington, DC<br>20001:                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| AAR Manual of Standards and Recommended Practices, Section C—Part III, Specifications for<br>Tank Cars, Specification M–1002, (AAR Specifications for Tank Cars), December 2000. | 173.31; 174.63;<br>179.6; 179.7;<br>179.15; 179.16;<br>179.20; 179.22;<br>179.100–9;<br>179.100–10;<br>179.100–12;<br>179.100–13;<br>179.100–14;<br>179.100–18;<br>179.101–1;<br>179.102–1;<br>179.102–4;<br>179.102–17;<br>179.103–5;<br>179.200–7;<br>179.200–9;<br>179.200–10;<br>179.200–11;<br>179.200–13;<br>179.200–17;<br>179.200–22;<br>179.201–6;<br>179.220–6;<br>179.220–7;<br>179.220–10;<br>179.220–11;<br>179.220–14;<br>179.220–18;<br>179.220–26;<br>179.300–9;<br>179.300–10;<br>179.300–15;<br>179.300–17;<br>179.400–5;<br>179.400–6;<br>179.400–8;<br>179.400–11;<br>179.400–12;<br>179.400–15;<br>179.400–18;<br>179.400–20;<br>179.400–25;<br>180.509; 180.513;<br>180.515; 180.517. |
| AAR Manual of Standards and Recommended Practices, Section I, Specially Equipped Freight<br>Car and Intermodal Equipment, 1988.                                                  | 174.55; 174.63.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| AAR Specifications for Design, Fabrication and Construction of Freight Cars, Volume 1, 1988 ....                                                                                 | 179.16.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| <i>Chlorine Institute, Inc.</i> , 1300 Wilson Boulevard, Arlington, VA 22209                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| Chlorine Institute Emergency Kit “A” for 100-lb. & 150 lb. Chlorine Cylinders (with the exception<br>of repair method using Device 8 for side leaks), Edition 10, June 2003.     | 173.3                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| Chlorine Institute Emergency Kit “B” for Chlorine Ton Containers (with the exception of repair<br>method using Device 9 for side leaks), Edition 9, June 2003.                   | 173.3                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| Type 1½ JQ 225, Dwg., H51970, Revision F, November 1996; or Type 1½ JQ 225, Dwg.<br>H50155, Revision H, November 1996.                                                           | 173.315.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| Section 3, Pamphlet 57, Emergency Shut-Off Systems for Bulk Transfer of Chlorine, Edition 4,<br>October 2003.                                                                    | 177.840.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| Section 3, Pamphlet 166, Angle Valve Guidelines for Chlorine Bulk Transportation, 1st Edition,<br>October 2002.                                                                  | 178.337–9.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 171.7**

| Source and name of material                                                                                                                                                                                                                      | 49 CFR reference                                                                                                                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|
| Standard Chlorine Angle Valve Assembly, Dwg. 104-8, July 1993 .....                                                                                                                                                                              | 178.337-9.                                                                                                                         |
| Excess Flow Valve with Removable Seat, Dwg. 101-7, July 1993 .....                                                                                                                                                                               | 178.337-8.                                                                                                                         |
| Excess Flow Valve with Removable Basket, Dwg. 106-6, July 1993 .....                                                                                                                                                                             | 178.337-8.                                                                                                                         |
| Standards for Housing and Manway Covers for Steel Cargo Tanks, Dwgs. 137-1 and 137-2, September 1, 1982.                                                                                                                                         | 178.337-10.                                                                                                                        |
| Typical Manway Arrangement Chlorine Cargo Tank, Dwg 137-5, November 1996 .....                                                                                                                                                                   | 178.337-10.                                                                                                                        |
| Canadian General Standards Board, Place du Portage III, 6B1 11 .....                                                                                                                                                                             | 171.12                                                                                                                             |
| Laurier Street, Gatineau, Quebec, Canada K1A 1G6                                                                                                                                                                                                 |                                                                                                                                    |
| National Standard of Canada (CAN/CGSB 43.147—2005) Construction, Modification, Qualification, Maintenance, and Selection and Use of Means of Containment for the Handling, Offering for Transport, or Transportation of Dangerous Goods by Rail. |                                                                                                                                    |
| <i>Compressed Gas Association, Inc.</i> , 4221 Walney Road, 5th Floor, Chantilly, Virginia 20151:                                                                                                                                                |                                                                                                                                    |
| CGA Pamphlet C-3, Standards for Welding on Thin-Walled Steel Cylinders, 1994 .....                                                                                                                                                               | 178.47; 178.50;<br>178.51; 178.53;<br>178.55; 178.56;<br>178.57; 178.58;<br>178.59; 178.60;<br>178.61; 178.65;<br>178.68; 180.211. |
| CGA C-5, Cylinder Service Life—Seamless Steel High Pressure Cylinders, 1991 (reaffirmed 1995) .....                                                                                                                                              | 173.302a.                                                                                                                          |
| CGA Pamphlet C-6, Standards for Visual Inspection of Steel Compressed Gas Cylinders, 1993                                                                                                                                                        | 173.3, 173.198,<br>180.205, 180.209,<br>180.211, 180.411,<br>180.519.                                                              |
| CGA Pamphlet C-6.1, Standards for Visual Inspection of High Pressure Aluminum Compressed Gas Cylinders, 2002, Fourth Edition.                                                                                                                    | 180.205; 180.209                                                                                                                   |
| CGA Pamphlet C-6.2, Guidelines for Visual Inspection and Requalification of Fiber Reinforced High Pressure Cylinders, 1996, Third Edition.                                                                                                       | 180.205.                                                                                                                           |
| CGA Pamphlet C-6.3, Guidelines for Visual Inspection and Requalification of Low Pressure Aluminum Compressed Gas Cylinders, 1991.                                                                                                                | 180.205; 180.209.                                                                                                                  |
| CGA C-7, Guide to Preparation of Precautionary Labeling and Marking of Compressed Gas Containers, Appendix A, issued 2004 (8th Edition).                                                                                                         | 172.400a.                                                                                                                          |
| CGA Pamphlet C-8, Standard for Requalification of DOT-3HT Cylinder Design, 1985 .....                                                                                                                                                            | 180.205; 180.209.                                                                                                                  |
| CGA Pamphlet C-11, Recommended Practices for Inspection of Compressed Gas Cylinders at Time of Manufacture, 2001, Third Edition.                                                                                                                 | 178.35.                                                                                                                            |
| CGA Pamphlet C-12, Qualification Procedure for Acetylene Cylinder Design, 1994 .....                                                                                                                                                             | 173.301; 173.303;<br>178.59; 178.60.                                                                                               |
| CGA Pamphlet C-13, Guidelines for Periodic Visual Inspection and Requalification of Acetylene Cylinders, 2000, Fourth Edition.                                                                                                                   | 173.303; 180.205;<br>180.209.                                                                                                      |
| CGA Pamphlet C-14, Procedures for Fire Testing of DOT Cylinder Pressure Relief Device Systems, 1979.                                                                                                                                             | 173.301; 173.323.                                                                                                                  |
| CGA Pamphlet G-2.2 Tentative Standard Method for Determining Minimum of 0.2% Water in Anhydrous Ammonia, 1985.                                                                                                                                   | 173.315.                                                                                                                           |
| CGA Pamphlet G-4.1, Cleaning Equipment for Oxygen Service, 1985 .....                                                                                                                                                                            | 178.338-15.                                                                                                                        |
| CGA Pamphlet P-20, Standard for the Classification of Toxic Gas Mixtures, 1995 .....                                                                                                                                                             | 173.115.                                                                                                                           |
| CGA S-1.1, Pressure Relief Device Standards—Part 1—Cylinders for Compressed Gases, 2005 (with the exception of paragraph 9.1.1.1), Twelfth Edition.                                                                                              | 173.301, 173.304a<br>178.75.                                                                                                       |
| CGA Pamphlet S-1.2, Safety Relief Device Standards Part 2—Cargo and Portable Tanks for Compressed Gases, 1980.                                                                                                                                   | 173.315; 173.318;<br>178.276; 178.277.                                                                                             |
| CGA S-7, Method for Selecting Pressure Relief Devices for Compressed Gas Mixtures in Cylinders, 2005.                                                                                                                                            | 173.301.                                                                                                                           |
| CGA Technical Bulletin TB-2, Guidelines for Inspection and Repair of MC-330 and MC-331 Cargo Tanks, 1980.                                                                                                                                        | 180.407; 180.413.                                                                                                                  |
| <i>Department of Defense (DOD)</i> , 2461 Eisenhower Avenue, Alexandria, VA 22331:                                                                                                                                                               |                                                                                                                                    |
| DOD TB 700-2; NAVSEAINST 8020.8B; AFTO 11A-1-47; DLAR 8220.1: Explosives Hazard Classification Procedures, January 1998.                                                                                                                         | 173.56.                                                                                                                            |
| Packaging of Hazardous Material, DLAD 4145.41/ AR 700-143/AFJI 24-210/NAVSUPINST 4030.55B/MCO 4030.40B, January 14, 2000.                                                                                                                        | 173.7                                                                                                                              |
| <i>Department of Energy (USDOE)</i> , 100 Independence Avenue SW., Washington, DC 20545:                                                                                                                                                         |                                                                                                                                    |
| USDOE publications available from: Superintendent of Documents, Government Printing Office (GPO) or The National Technical Information Service (NTIS).                                                                                           |                                                                                                                                    |
| USDOE, CAPE-1662, Revision 1, and Supplement 1, Civilian Application Program Engineering Drawings, April 6, 1988.                                                                                                                                | 178.356-1;<br>178.356-2;<br>178.358-1;<br>178.358-2;<br>178.358-3;<br>178.358-4.                                                   |
| USDOE, Material and Equipment Specification No. SP-9, Rev. 1, and Supplement—Fire Resistant Phenolic Foam, March 28, 1968.                                                                                                                       | 178.356-2;<br>178.358-2.                                                                                                           |
| USDOE, KSS-471, November 30, 1986—Proposal for Modifications to U.S. Department of Transportation Specification 21PF-1, Fire and Shock Resistant Phenolic Foam—Insulated Metal Overpack.                                                         | 178.358-1;<br>178.358-3.                                                                                                           |
| <i>General Services Administration</i> , Specification Office, Room 6662, 7th and D Street, S.W., Washington, DC 20407:                                                                                                                          |                                                                                                                                    |

| Source and name of material                                                                                                                                                                                                                                                                      | 49 CFR reference                                                                                                                               |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------|
| Federal Specification RR-C-901D, Cylinders, Compressed Gas: Seamless Shatterproof, High Pressure DOT 3AA Steel, and 3AL Aluminum, February 21, 2003 (Superseding RR-C-901C, 1981).                                                                                                               | 173.302; 173.336;<br>173.337.                                                                                                                  |
| <i>Institute of Makers of Explosives</i> , 1120 19th Street NW., Suite 310, Washington, DC 20036–3605: IME Safety Library Publication No. 22 (IME Standard 22), Recommendation for the Safe Transportation of Detonators in a Vehicle with Certain Other Explosive Materials, May 1993.          | 173.63; 177.835.                                                                                                                               |
| <i>International Atomic Energy Agency (IAEA)</i> , P.O. Box 100, Wagramer Strasse 5, A–1400 Vienna, Austria: Also available from: Bernan Associates, 4611–F Assembly Drive, Lanham, MD 20706–4391, USA; or Renouf Publishing Company, Ltd., 812 Proctor Avenue, Ogdensburg, New York 13669, USA. |                                                                                                                                                |
| IAEA, Regulations for the Safe Transport of Radioactive Material, (IAEA Regulations), 1996 Edition (Revised), No. TS-R-1 (ST-1, Revised).                                                                                                                                                        | 171.22; 171.23;<br>171.26, 173.415,<br>173.416, 173.417,<br>173.473                                                                            |
| <i>International Civil Aviation Organization (ICAO)</i> , P.O. Box 400, Place de l'Aviation Internationale, 1000 Sherbrooke Street West, Montreal, Quebec, Canada H3A 2R2:                                                                                                                       |                                                                                                                                                |
| ICAO Technical Instructions available from: INTEREG, International Regulations, Publishing and Distribution Organization, P.O. Box 60105, Chicago, IL 60660.                                                                                                                                     |                                                                                                                                                |
| Technical Instructions for the Safe Transport of Dangerous Goods by Air (ICAO Technical Instructions), 2007–2008 Edition.                                                                                                                                                                        | 171.8; 171.22;<br>171.23; 171.24;<br>175.33; 172.202;<br>172.401; 172.512;<br>172.602; 173.320;<br>175.33; 178.3.                              |
| International Electrotechnical Commission (IEC) 3, rue de Varembe, P.O. Box 131, CH–1211, GENEVA 20, Switzerland:                                                                                                                                                                                |                                                                                                                                                |
| Fuel cell technologies—Part 6–1: Micro fuel cell power systems—Safety, IEC/PAS 62282–6–1:2006(E), First Edition 2006–02, with Corrigendum 1, First Edition 2007–04.                                                                                                                              | § 175.10.                                                                                                                                      |
| <i>International Maritime Organization (IMO)</i> , 4 Albert Embankment, London, SE17SR, United Kingdom or New York Nautical Instrument & Service Corporation, 140 West Broadway, New York, NY 10013:                                                                                             |                                                                                                                                                |
| International Convention for the Safety of Life at Sea, (SOLAS) Amendments 2000, Chapter II–2/Regulation 19, 2001.                                                                                                                                                                               | 176.63; 176.84.                                                                                                                                |
| International Maritime Dangerous Goods Code (IMDG Code), 2006 Edition, Incorporating Amendment 33–06 (English Edition), Volumes 1 and 2.                                                                                                                                                         | 171.22; 171.23;<br>171.25; 172.202;<br>172.401; 172.502;<br>172.602; 173.21;<br>176.2; 176.5;<br>176.11; 176.27;<br>176.30; 178.3;<br>178.274. |
| <i>International Organization for Standardization</i> , Case Postale 56, CH–1211, Geneve 20, Switzerland; Also available from: ANSI 25 West 43rd Street, New York, NY 10036                                                                                                                      |                                                                                                                                                |
| ISO 535–1991(E) Paper and board—Determination of water absorptiveness—Cobb method .....                                                                                                                                                                                                          | 178.516; 178.707;<br>178.708.                                                                                                                  |
| ISO 1496–1: 1990 (E)—Series 1 freight containers—Specification and testing, Part 1: General cargo containers. Fifth Edition, (August 15, 1990).                                                                                                                                                  | 173.411                                                                                                                                        |
| ISO 1496–3—Series 1 freight containers—Specification and testing—Part 3: Tank containers for liquids, gases and pressurized dry bulk, Fourth edition, March 1995, (E).                                                                                                                           | 178.74; 178.75;<br>178.274.                                                                                                                    |
| ISO 2431–1984(E) Standard Cup Method .....                                                                                                                                                                                                                                                       | 173.121.                                                                                                                                       |
| ISO 2592–1973(E) Petroleum products—Determination of flash and fire points—Cleveland open cup method.                                                                                                                                                                                            | 173.120.                                                                                                                                       |
| ISO 2919–1980(E) Sealed radioactive sources—Classification .....                                                                                                                                                                                                                                 | 173.469.                                                                                                                                       |
| ISO 3036–1975(E) Board—Determination of puncture resistance .....                                                                                                                                                                                                                                | 178.708.                                                                                                                                       |
| ISO 3574–1986(E) Cold-reduced carbon steel sheet of commercial and drawing qualities .....                                                                                                                                                                                                       | 178.503; Part 178,<br>appendix C.                                                                                                              |
| ISO 3807–2, Cylinders for acetylene—Basic requirements—Part 2: Cylinders with fusible plugs, First edition, March 2000, (E).                                                                                                                                                                     | 173.303; 178.71.                                                                                                                               |
| ISO 4126–1 Safety valves—Part 1: General Requirements, December 15, 1991, First Edition .....                                                                                                                                                                                                    | 178.274.                                                                                                                                       |
| ISO 6406, Gas cylinders—Seamless steel gas cylinders—Periodic inspection and testing, Second edition, February 2005, (E).                                                                                                                                                                        | 180.207.                                                                                                                                       |
| ISO 6892 Metallic materials—Tensile testing, July 15, 1984, First Edition .....                                                                                                                                                                                                                  | 178.274.                                                                                                                                       |
| ISO 7225, Gas cylinders—Precautionary labels, Second Edition, July 2005, (E) .....                                                                                                                                                                                                               | 178.71.                                                                                                                                        |
| ISO 7866, Gas cylinders—Refillable seamless aluminum alloy gas cylinders—Design, construction and testing, First edition, June 1999, (E).                                                                                                                                                        | 178.71.                                                                                                                                        |
| ISO 8115 Cotton bales—Dimensions and density, 1986 Edition .....                                                                                                                                                                                                                                 | 172.102.                                                                                                                                       |
| ISO 9809–1: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 1: Quenched and tempered steel cylinders with tensile strength less than 1 100 MPa., First edition, June 1999, (E).                                                                      | 178.71; 178.75.                                                                                                                                |
| ISO 9809–2: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 2: Quenched and tempered steel cylinders with tensile strength greater than or equal to 1 100 MPa., First edition, June 2000, (E).                                                       | 178.71; 178.75.                                                                                                                                |
| ISO 9809–3: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 3: Normalized steel cylinders, First edition, December 2000, (E).                                                                                                                        | 178.71; 178.75.                                                                                                                                |

Pipeline and Hazardous Materials Safety Admin., DOT

§ 171.7

| Source and name of material                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 49 CFR reference                                                                                                                                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|
| ISO 9978:1992(E)—Radiation protection—Sealed radioactive sources—Leakage test methods. First Edition, (February 15, 1992).                                                                                                                                                                                                                                                                                                                                                                                        | 173.469.                                                                                                                                           |
| ISO 10297, Gas cylinders—Refillable gas cylinder valves—Specification and type testing, First edition, May 1999, (E).                                                                                                                                                                                                                                                                                                                                                                                             | 173.301b, 178.71.                                                                                                                                  |
| ISO 10461, Gas cylinders—Seamless aluminum—alloy gas cylinders—Periodic inspection and testing, Second edition, February 2005, (E).                                                                                                                                                                                                                                                                                                                                                                               | 180.207.                                                                                                                                           |
| ISO 10462, Gas cylinders—Transportable cylinders for dissolved acetylene—Periodic inspection and maintenance, Second edition, February 2005, (E).                                                                                                                                                                                                                                                                                                                                                                 | 180.207.                                                                                                                                           |
| ISO 11114-1, Transportable gas cylinders—Compatibility of cylinder and valve materials with gas contents—Part 1: Metallic materials, First edition, October 1997, (E).                                                                                                                                                                                                                                                                                                                                            | 173.301b; 178.71.                                                                                                                                  |
| ISO 11114-2, Transportable gas cylinders—Compatibility of cylinder and valve materials with gas contents—Part 2: Non-metallic materials, First edition, December 2000, (E).                                                                                                                                                                                                                                                                                                                                       | 173.301b; 178.71.                                                                                                                                  |
| ISO 11117, Gas cylinders—Valve protection caps and valve guards for industrial and medical gas cylinders—Design, construction and tests, First edition, August 1998, (E).                                                                                                                                                                                                                                                                                                                                         | 173.301b.                                                                                                                                          |
| ISO 11118, Gas cylinders—Non-refillable metallic gas cylinders—Specification and test methods, First edition, October 1999, (E).                                                                                                                                                                                                                                                                                                                                                                                  | 178.71.                                                                                                                                            |
| ISO 11119-1, Gas cylinders—Gas cylinders of composite construction—Specification and test methods—Part 1: Hoop-wrapped composite gas cylinders, First edition, May 2002, (E).                                                                                                                                                                                                                                                                                                                                     | 178.71.                                                                                                                                            |
| ISO 11119-2, Gas cylinders—Gas cylinders of composite construction—Specification and test methods—Part 2: Fully wrapped fibre reinforced composite gas cylinders with load-sharing metal liners, First edition, May 2002, (E).                                                                                                                                                                                                                                                                                    | 178.71.                                                                                                                                            |
| ISO 11119-3, Gas cylinders of composite construction—Specification and test methods—Part 3: Fully wrapped fibre reinforced composite gas cylinders with non-load-sharing metallic or non-metallic liners, First edition, September 2002, (E).                                                                                                                                                                                                                                                                     | 178.71.                                                                                                                                            |
| ISO 11120, Gas cylinders—Refillable seamless steel tubes of water capacity between 150 L and 3000 L—Design, construction and testing, First edition, March 1999, (E).                                                                                                                                                                                                                                                                                                                                             | 178.71; 178.75.                                                                                                                                    |
| ISO 11621, Gas cylinders—Procedures for change of gas service, First edition, April 1997, (E) ..                                                                                                                                                                                                                                                                                                                                                                                                                  | 173.302, 173.336, 173.337.                                                                                                                         |
| ISO 11623, Transportable gas cylinders—Periodic inspection and testing of composite gas cylinders, First edition, March 2002, (E).                                                                                                                                                                                                                                                                                                                                                                                | 180.207.                                                                                                                                           |
| <i>National Board of Boiler and Pressure Vessel Inspectors</i> , 1055 Crupper Avenue, Columbus, Ohio 43229: National Board Inspection Code, A Manual for Boiler and Pressure Vessel Inspectors, NB-23, 1992 Edition.                                                                                                                                                                                                                                                                                              | 180.413.                                                                                                                                           |
| <i>National Fire Protection Association</i> , Batterymarch Park, Quincy, MA 02269: NFPA 58-Liquefied Petroleum Gas Code, 2001 Edition .....                                                                                                                                                                                                                                                                                                                                                                       | 173.315.                                                                                                                                           |
| <i>National Institute of Standards and Technology</i> , Department of Commerce, 5285 Port Royal Road, Springfield, VA 22151: USDC, NBS Handbook H-28 (1957), 1957 Handbook of Screw-Thread Standards for Federal Services, December 1966 Edition.                                                                                                                                                                                                                                                                 | 179.2; 178.45; 178.46.                                                                                                                             |
| <i>Organization for Economic Cooperation and Development (OECD)</i> , OECD Publications and Information Center, 2001 L Street, N.W., Suite 700, Washington, DC 20036: OECD Guideline for Testing of Chemicals, No. 404 "Acute Dermal Irritation/Corrosion," 1992 .....                                                                                                                                                                                                                                            | 173.137.                                                                                                                                           |
| <i>Transport Canada</i> , TDG Canadian Government Publishing Center, Supply and Services, Canada, Ottawa, Ontario, Canada K1A 0S9: Transportation of Dangerous Goods Regulations (Transport Canada TDG Regulations), August 2001 including Clear Language Amendments SOR/2001-286, Amendment 1 (SOR/2002-306) August 8, 2002; Amendment 2 (SOR/2003-273) July 24, 2003; Amendment 3 (SOR/2003-400) December 3, 2003; Amendment 4 (SOR/2005-216) July 13, 2005; and Amendment 5 (SOR/2005-279) September 21, 2005. | 171.12; 171.22; 171.23; 172.401; 172.502; 172.519; 172.602; 173.31; 173.32; 173.33                                                                 |
| <i>Truck Trailer Manufacturers Association</i> , 1020 Princess Street, Alexandria, Virginia 22314: TTMA RP No. 61-98, Performance of manhole and/or Fill Opening Assemblies on MC 306, DOT 406, Non-ASME MC 312 and Non-ASME DOT 412 Cargo Tanks, June 1, 1998.                                                                                                                                                                                                                                                   | 180.405.                                                                                                                                           |
| TTMA RP No. 81-97, Performance of Spring Loaded Pressure Relief Valves on MC 306, MC 307, MC 312, DOT 406, DOT 407, and DOT 412 Tanks, July 1, 1997 Edition.                                                                                                                                                                                                                                                                                                                                                      | 178.345-10; 178.346-3.                                                                                                                             |
| TTMA TB No. 107, Procedure for Testing In-Service Unmarked and/or Uncertified MC 306 and Non-ASME MC 312 Type Cargo Tank Manhole Covers, June 1, 1998 Edition.                                                                                                                                                                                                                                                                                                                                                    | 180.405.                                                                                                                                           |
| <i>United Nations</i> , United Nations Sales Section, New York, NY 10017: UN Recommendations on the Transport of Dangerous Goods, Fourteenth revised edition (2005), Volumes I and II.                                                                                                                                                                                                                                                                                                                            | 171.8; 171.12; 172.202; 172.401; 172.502; 173.22; 173.24; 173.24b; 173.40; 173.56; 173.192; 173.197; 173.302b; 173.304b; 178.75; 178.274; 178.801. |
| UN Recommendations on the Transport of Dangerous Goods, Manual of Tests and Criteria, Fourth revised edition, (2003), and Addendum 2, (2004).                                                                                                                                                                                                                                                                                                                                                                     | 172.102; 173.21; 173.56; 173.57; 173.58; 173.115; 173.124; 173.125; 173.127; 173.128; 173.137; 173.185; Part 173, appendix H; 178.274.             |

| Source and name of material                                                                                                                                                                             | 49 CFR reference |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|
| United States Enrichment Corporation, Inc. (USEC):<br>USEC Inc., 6903 Rockledge Drive, Bethesda, MD 20817.<br>USEC–651—Good Handling Practices for Uranium Hexafluoride, Revision 8, January 1999 ..... | 173.417          |

(b) *List of informational materials not requiring incorporation by reference.* The materials listed in this paragraph do not require approval for incorporation by reference and are included for informational purposes. These materials may be used as noted in those sections in which the material is referenced.

| Source and name of material                                                                                                                                                                                                                                                                                                                                                                               | 49 CFR reference                           |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------|
| <i>American Biological Safety Association</i><br>1202 Allanson Road, Mundelein, IL 60060<br>Risk Group Classification for Infectious Agents, 1998 .....                                                                                                                                                                                                                                                   | 173.134                                    |
| <i>American Institute of Chemical Engineers (AIChE)</i> ,<br>3 Park Avenue New York, NY 10016–5991<br>Process Safety Progress Journal, Vol. 21, No. 2.<br>Example of a Test Method for Venting Sizing: OPPSD/SPI Methodology .....                                                                                                                                                                        | Note to § 173.225(h)(3)(vi).               |
| <i>American Society for Testing and Materials</i> , 100 Barr Harbor Drive, West Conshohocken, PA 19428:<br>Noncurrent ASTM Standards are available from: Engineering Societies Library, 354 East 47th Street, New York, NY 10017<br>ASTM E 380–89 Standards for Metric Practice .....                                                                                                                     | 171.10                                     |
| <i>Association of American Railroads</i> ,<br>American Railroads Building, 50 F Street, NW., Washington, DC 20001<br>AAR Catalog Nos. SE60CHT; SE60CC; SE60CHTE; SE60CE; SE60DC; SE60DE .....                                                                                                                                                                                                             | 179.14                                     |
| AAR Catalog Nos. SE67CC; SE67CE; SE67BHT; SE67BC; SE67BHTE; SE67BE .....                                                                                                                                                                                                                                                                                                                                  | 179.14                                     |
| AAR Catalog Nos. SE68BHT; SE68BC; SE68BHTE; SE68BE .....                                                                                                                                                                                                                                                                                                                                                  | 179.14                                     |
| AAR Catalog Nos. SE69AHT; SE69AE .....                                                                                                                                                                                                                                                                                                                                                                    | 179.14                                     |
| AAR Catalog Nos. SF70CHT; SF70CC; SF70CHTE; SF70CE .....                                                                                                                                                                                                                                                                                                                                                  | 179.14                                     |
| AAR Catalog Nos. SF73AC; SF73AE; SF73AHT; SF73AHTE .....                                                                                                                                                                                                                                                                                                                                                  | 179.14                                     |
| AAR Catalog Nos. SF79CHT; SF79CC; SF79CHTE; SF79CE .....                                                                                                                                                                                                                                                                                                                                                  | 179.14                                     |
| <i>Bureau of Explosives</i> ,<br>Hazardous Materials Systems (BOE), Association of American Railroads, American Railroads Building, 50 F Street, NW., Washington, DC 20001<br>Fetterley's Formula (The Determination of the Relief Dimensions for Safety Valves on Containers in which Liquefied gas is charged and when the exterior surface of the container is exposed to a temperature of 1,200 °F.). | 173.315                                    |
| Pamphlet 6, Illustrating Methods for Loading and Bracing Carload and Less-Than-Carload Shipments of Explosives and Other Dangerous Articles, 1962.                                                                                                                                                                                                                                                        | 174.55; 174.101; 174.112; 174.115; 174.290 |
| Pamphlet 6A (includes appendix No. 1, October 1944 and appendix 2, December 1945), Illustrating Methods for Loading and Bracing Carload and Less-Than-Carload Shipments of Loaded Projectiles, Loaded Bombs, etc., 1943.                                                                                                                                                                                  | 174.101; 174.290                           |
| Pamphlet 6C, Illustrating Methods for Loading and Bracing Trailers and Less-Than-Trailer Shipments of Explosives and Other Dangerous Articles Via Trailer-on-Flatcar (TOFC) or Container-on-Flatcar (COFC), 1985.                                                                                                                                                                                         | 174.55; 174.63; 174.101; 174.112; 174.115  |
| Emergency Handling of Hazardous Materials in Surface Transportation, 1989 .....                                                                                                                                                                                                                                                                                                                           | 171.7                                      |
| <i>Centers for Disease Control and Prevention</i><br>1600 Clifton Road, Atlanta, GA 30333<br>Biosafety in Microbiological and Biomedical Laboratories, Fourth Edition, April 1999 .....                                                                                                                                                                                                                   | 173.134                                    |
| Compressed Gas Association, Inc., 4221 Walney Road, 5th Floor, Chantilly, Virginia 20151<br>CGA C–1.1, Personnel Training and Certification Guidelines for Cylinder Requalification By the Volumetric Expansion Method, 2004, First Edition.                                                                                                                                                              | 180.209                                    |
| <i>National Institutes of Health</i><br>Bethesda, MD 20892<br>NIH Guidelines for Research Involving Recombinant DNA Molecules (NIH Guidelines), January 2001, Appendix B.                                                                                                                                                                                                                                 | 173.134                                    |
| <i>Pantone Incorporated</i><br>590 Commerce Boulevard, Carlstadt, New Jersey 07072–3098<br>Pantone® Formula guide coated/uncoated, Second Edition 2004 .....                                                                                                                                                                                                                                              | 172.407, 172.519                           |
| <i>Society of Plastics Industries, Inc.</i> ,<br>Organic Peroxide Producers Safety Division, 1275 K Street, NW., Suite 400, Washington, DC 20005<br>Self Accelerating Decomposition Temperature Test, 1972 .....                                                                                                                                                                                          | 173.21                                     |

[Amdt. 171–111, 55 FR 52466, Dec. 21, 1990; 71 FR 78611, Dec. 29, 2006]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 171.7, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

EDITORIAL NOTE: At 68 FR 19273, Apr. 18, 2003, §171.7(a)(3) was amended by removing the entry for “TTMA TB No. 81” under “Truck Trailer Manufacturers Association”. The amendment could not be incorporated because that entry does not exist.

### § 171.8 Definitions and abbreviations.

In this subchapter,

*Administrator* means the Administrator, Pipeline and Hazardous Materials Safety Administration.

*Aerosol* means any non-refillable receptacle containing a gas compressed, liquefied or dissolved under pressure, the sole purpose of which is to expel a nonpoisonous (other than a Division 6.1 Packing Group III material) liquid, paste, or powder and fitted with a self-closing release device allowing the contents to be ejected by the gas.

*Aggregate lithium content* means the sum of the grams of lithium content or equivalent lithium content contained by the cells comprising a battery.

*Agricultural product* means a hazardous material, other than a hazardous waste, whose end use directly supports the production of an agricultural commodity including, but not limited to a fertilizer, pesticide, soil amendment or fuel. An *agricultural product* is limited to a material in Class 3, 8 or 9, Division 2.1, 2.2, 5.1, or 6.1, or an ORM-D material.

*Approval* means a written authorization, including a competent authority approval, from the Associate Administrator or other designated Department official, to perform a function for which prior authorization by the Associate Administrator is required under subchapter C of this chapter (49 CFR parts 171 through 180.)

*Approved* means approval issued or recognized by the Department unless otherwise specifically indicated in this subchapter.

*Asphyxiant gas* means a gas which dilutes or replaces oxygen normally in the atmosphere.

*Associate Administrator* means the Associate Administrator for Hazardous Materials Safety, Pipeline and Hazardous Materials Safety Administration.

*Atmospheric gases* means air, nitrogen, oxygen, argon, krypton, neon and xenon.

*Authorized Inspection Agency* means: (1) A jurisdiction which has adopted

and administers one or more sections of the ASME Boiler and Pressure Vessel Code as a legal requirement and has a representative serving as a member of the ASME Conference Committee; or (2) an insurance company which has been licensed or registered by the appropriate authority of a State of the United States or a Province of Canada to underwrite boiler and pressure vessel insurance in such State or Province.

*Authorized Inspector* means an Inspector who is currently commissioned by the National Board of Boiler and Pressure Vessel Inspectors and employed as an Inspector by an Authorized Inspection Agency.

*Bag* means a flexible packaging made of paper, plastic film, textiles, woven material or other similar materials.

*Bar* means 1 BAR = 100 kPa (14.5 psi).

*Barge* means a non-selfpropelled vessel.

*Biological product*. See §173.134 of this subchapter.

*Biological substances, Category B*. See §173.134 of this subchapter.

*Bottle* means an inner packaging having a neck of relatively smaller cross section than the body and an opening capable of holding a closure for retention of the contents.

*Bottom shell* means that portion of a tank car tank surface, excluding the head ends of the tank car tank, that lies within two feet, measured circumferentially, of the bottom longitudinal center line of the tank car tank.

*Box* means a packaging with complete rectangular or polygonal faces, made of metal, wood, plywood, reconstituted wood, fiberboard, plastic, or other suitable material. Holes appropriate to the size and use of the packaging, for purposes such as ease of handling or opening, or to meet classification requirements, are permitted as long as they do not compromise the integrity of the packaging during transportation, and are not otherwise prohibited in this subchapter.

## § 171.8

## 49 CFR Ch. I (10–1–08 Edition)

*Break-bulk* means packages of hazardous materials that are handled individually, palletized, or unitized for purposes of transportation as opposed to bulk and containerized freight.

*Btu* means British thermal unit.

*Bulk packaging* means a packaging, other than a vessel or a barge, including a transport vehicle or freight container, in which hazardous materials are loaded with no intermediate form of containment and which has:

(1) A maximum capacity greater than 450 L (119 gallons) as a receptacle for a liquid;

(2) A maximum net mass greater than 400 kg (882 pounds) and a maximum capacity greater than 450 L (119 gallons) as a receptacle for a solid; or

(3) A water capacity greater than 454 kg (1000 pounds) as a receptacle for a gas as defined in §173.115 of this subchapter.

*Bundle of cylinders* means assemblies of UN cylinders fastened together and interconnected by a manifold and transported as a unit. The total water capacity for the bundle may not exceed 3,000 L, except that a bundle intended for the transport of gases in Division 2.3 is limited to a water capacity of 1,000 L.

*Bureau of Explosives* means the Bureau of Explosives (B of E) of the Association of American Railroads.

*C* means Celsius or Centigrade.

*Captain of the Port (COTP)* means the officer of the Coast Guard, under the command of a District Commander, so designated by the Commandant for the purpose of giving immediate direction to Coast Guard law enforcement activities within an assigned area. As used in this subchapter, the term *Captain of the Port* includes an authorized representative of the Captain of the Port.

*Carfloat* means a vessel that operates on a short run on an irregular basis and serves one or more points in a port area as an extension of a rail line or highway over water, and does not operate in ocean, coastwise, or ferry service.

*Cargo aircraft only* means an aircraft that is used to transport cargo and is not engaged in carrying passengers. For purposes of this subchapter, the terms *cargo aircraft only*, *cargo-only air-*

*craft* and *cargo aircraft* have the same meaning.

*Cargo tank* means a bulk packaging that:

(1) Is a tank intended primarily for the carriage of liquids or gases and includes appurtenances, reinforcements, fittings, and closures (for the definition of a tank, *see* 49 CFR 178.320, 178.337–1, or 178.338–1, as applicable);

(2) Is permanently attached to or forms a part of a motor vehicle, or is not permanently attached to a motor vehicle but which, by reason of its size, construction or attachment to a motor vehicle is loaded or unloaded without being removed from the motor vehicle; and

(3) Is not fabricated under a specification for cylinders, intermediate bulk containers, multi-unit tank car tanks, portable tanks, or tank cars.

*Cargo tank motor vehicle* means a motor vehicle with one or more cargo tanks permanently attached to or forming an integral part of the motor vehicle.

*Cargo vessel* means: (1) Any vessel other than a passenger vessel; and

(2) Any ferry being operated under authority of a change of character certificate issued by a Coast Guard Officer-in-Charge, Marine Inspection.

*Carrier* means a person who transports passengers or property in commerce by rail car, aircraft, motor vehicle, or vessel.

*CC* means closed-cup.

*Character of vessel* means the type of service in which the vessel is engaged at the time of carriage of a hazardous material.

*Class* means hazard class. *See hazard class.*

*Class 1.* *See* §173.50 of this subchapter.

*Class 2.* *See* §173.115 of this subchapter.

*Class 3.* *See* §173.120 of this subchapter.

*Class 4.* *See* §173.124 of this subchapter.

*Class 5.* *See* §173.128 of this subchapter.

*Class 6.* *See* §173.132 of this subchapter.

*Class 7.* *See* §173.403 of this subchapter.

*Class 8.* *See* §173.136 of this subchapter.

*Class 9.* See §173.140 of this subchapter.

*Closure* means a device which closes an opening in a receptacle.

*COFC* means container-on-flat-car.

*Combination packaging* means a combination of packaging, for transport purposes, consisting of one or more inner packagings secured in a non-bulk outer packaging. It does not include a composite packaging.

*Combustible liquid.* See §173.120 of this subchapter.

*Commerce* means trade or transportation in the jurisdiction of the United States within a single state; between a place in a state and a place outside of the state; or that affects trade or transportation between a place in a state and place outside of the state.

*Compatibility group letter* means a designated alphabetical letter used to categorize different types of explosive substances and articles for purposes of stowage and segregation. See §173.52 of this subchapter.

*Competent Authority* means a national agency responsible under its national law for the control or regulation of a particular aspect of the transportation of hazardous materials (dangerous goods). The term *Appropriate Authority*, as used in the ICAO Technical Instructions (IBR, see §171.7), has the same meaning as *Competent Authority*. For purposes of this subchapter, the Associate Administrator is the Competent Authority for the United States.

*Composite packaging* means a packaging consisting of an outer packaging and an inner receptacle, so constructed that the inner receptacle and the outer packaging form an integral packaging. Once assembled it remains thereafter an integrated single unit; it is filled, stored, shipped and emptied as such.

*Compressed gas.* See §173.115 of this subchapter.

*Consignee* means the person or place shown on a shipping document, package marking, or other media as the location to which a carrier is directed to transport a hazardous material.

*Consumer commodity* means a material that is packaged and distributed in a form intended or suitable for sale through retail sales agencies or instrumentalities for consumption by individuals for purposes of personal care or

household use. This term also includes drugs and medicines.

*Containership* means a cargo vessel designed and constructed to transport, within specifically designed cells, portable tanks and freight containers which are lifted on and off with their contents intact.

*Corrosive material.* See §173.136 of this subchapter.

*Crate* means an outer packaging with incomplete surfaces.

*Crewmember* means a person assigned to perform duty in an aircraft during flight time.

*Cryogenic liquid.* See §173.115(g) of this subchapter.

*Cultures and stocks.* See §173.134 of this subchapter.

*Cylinder* means a pressure vessel designed for pressures higher than 40 psia and having a circular cross section. It does not include a portable tank, multi-unit tank car tank, cargo tank, or tank car.

*Dangerous when wet material.* See §173.124 of this subchapter.

*Design Certifying Engineer* means a person registered with the Department in accordance with subpart F of part 107 of this chapter who has the knowledge and ability to perform stress analysis of pressure vessels and otherwise determine whether a cargo tank design and construction meets the applicable DOT specification. A *Design Certifying Engineer* meets the knowledge and ability requirements of this section by meeting any one of the following requirements:

(1) Has an engineering degree and one year of work experience in cargo tank structural or mechanical design;

(2) Is currently registered as a professional engineer by appropriate authority of a state of the United States or a province of Canada; or

(3) Has at least three years' experience in performing the duties of a Design Certifying Engineer prior to September 1, 1991.

*Designated facility* means a hazardous waste treatment, storage, or disposal facility that has been designated on the manifest by the generator.

*District Commander* means the District Commander of the Coast Guard, or his authorized representative, who



## § 171.8

## 49 CFR Ch. I (10–1–08 Edition)

has jurisdiction in the particular geographical area.

*Division* means a subdivision of a hazard class.

*DOD* means the U.S. Department of Defense.

*Domestic transportation* means transportation between places within the United States other than through a foreign country.

*DOT* or *Department* means U.S. Department of Transportation.

*Drum* means a flat-ended or convex-ended cylindrical packaging made of metal, fiberboard, plastic, plywood, or other suitable materials. This definition also includes packagings of other shapes made of metal or plastic (e.g., round taper-necked packagings or pail-shaped packagings) but does not include cylinders, jerricans, wooden barrels or bulk packagings.

*Elevated temperature material* means a material which, when offered for transportation or transported in a bulk packaging:

(1) Is in a liquid phase and at a temperature at or above 100°C (212°F);

(2) Is in a liquid phase with a flash point at or above 38°C (100°F) that is intentionally heated and offered for transportation or transported at or above its flash point; or

(3) Is in a solid phase and at a temperature at or above 240°C (464°F).

*Engine* means a locomotive propelled by any form of energy and used by a railroad.

*EPA* means U.S. Environmental Protection Agency.

*Equivalent lithium content* means, for a lithium-ion cell, the product of the rated capacity, in ampere-hours, of a lithium-ion cell times 0.3, with the result expressed in grams. The equivalent lithium content of a battery equals the sum of the grams of equivalent lithium content contained in the component cells of the battery.

*Etiologic agent*. See § 173.134 of this subchapter.

*EX number* means a number preceded by the prefix “EX”, assigned by the Associate Administrator, to an item that has been evaluated under the provisions of § 173.56 of this subchapter.

*Explosive*. See § 173.50 of this subchapter.

*F* means degree Fahrenheit.

*Farmer* means a person engaged in the production or raising of crops, poultry, or livestock.

*Federal hazardous material transportation law* means 49 U.S.C. 5101 *et seq.*

*Ferry vessel* means a vessel which is limited in its use to the carriage of deck passengers or vehicles or both, operates on a short run on a frequent schedule between two points over the most direct water route, other than in ocean or coastwise service, and is offered as a public service of a type normally attributed to a bridge or tunnel.

*Filling density* has the following meanings:

(1) For compressed gases in cylinders, see § 173.304a(a)(2) table note 1.

(2) For compressed gases in tank cars, see § 173.314(c) table note 1.

(3) For compressed gases in cargo tanks and portable tanks, see § 173.315(a) table note 1.

(4) For cryogenic liquids in cylinders, except hydrogen, see § 173.316(c)(1).

(5) For hydrogen, cryogenic liquid in cylinders, see § 173.316(c)(3) table note 1.

(6) For cryogenic liquids in cargo tanks, see § 173.318(f)(1).

(7) For cryogenic liquids in tank cars, see § 173.319(d)(1).

*Flammable gas*. See § 173.115 of this subchapter.

*Flammable liquid*. See § 173.120 of this subchapter.

*Flammable solid*. See § 173.124 of this subchapter.

*Flash point*. See § 173.120 of this subchapter.

*Freight container* means a reusable container having a volume of 64 cubic feet or more, designed and constructed to permit being lifted with its contents intact and intended primarily for containment of packages (in unit form) during transportation.

*Fuel cell* means an electrochemical device that converts the energy of the chemical reaction between a fuel, such as hydrogen or hydrogen rich gases, alcohols, or hydrocarbons, and an oxidant, such as air or oxygen, to direct current (d.c.) power, heat, and other reaction products.

*Fuel cell cartridge* or *Fuel cartridge* means a removable article that contains and supplies fuel to the micro fuel cell power unit or internal reservoir, not to be refilled by the user.

**Fuel cell system** means a fuel cell with an installed fuel cell cartridge together with wiring, valves, and other attachments that connect the fuel cell or cartridge to the device it powers. The fuel cell or cartridge may be so constructed that it forms an integral part of the device or may be removed and connected manually to the device.

**Fuel tank** means a tank other than a cargo tank, used to transport flammable or combustible liquid, or compressed gas for the purpose of supplying fuel for propulsion of the transport vehicle to which it is attached, or for the operation of other equipment on the transport vehicle.

**Fumigated lading.** See §§ 172.302(g) and 173.9.

**Gas** means a material which has a vapor pressure greater than 300 kPa (43.5 psia) at 50 °C (122 °F) or is completely gaseous at 20 °C (68 °F) at a standard pressure of 101.3 kPa (14.7 psia).

**Gross weight** or **Gross mass** means the weight of a packaging plus the weight of its contents.

**Hazard class** means the category of hazard assigned to a hazardous material under the definitional criteria of part 173 of this subchapter and the provisions of the § 172.101 table. A material may meet the defining criteria for more than one hazard class but is assigned to only one hazard class.

**Hazard zone** means one of four levels of hazard (Hazard Zones A through D) assigned to gases, as specified in § 173.116(a) of this subchapter, and one of two levels of hazards (Hazard Zones A and B) assigned to liquids that are poisonous by inhalation, as specified in § 173.133(a) of this subchapter. A hazard zone is based on the LC50 value for acute inhalation toxicity of gases and vapors, as specified in § 173.133(a).

**Hazardous material** means a substance or material that the Secretary of Transportation has determined is capable of posing an unreasonable risk to health, safety, and property when transported in commerce, and has designated as hazardous under section 5103 of Federal hazardous materials transportation law (49 U.S.C. 5103). The term includes hazardous substances, hazardous wastes, marine pollutants, elevated temperature materials, mate-

rials designated as hazardous in the Hazardous Materials Table (see 49 CFR 172.101), and materials that meet the defining criteria for hazard classes and divisions in part 173 of subchapter C of this chapter.

**Hazardous substance** for the purposes of this subchapter, means a material, including its mixtures and solutions, that—

(1) Is listed in the appendix A to § 172.101 of this subchapter;

(2) Is in a quantity, in one package, which equals or exceeds the reportable quantity (RQ) listed in the appendix A to § 172.101 of this subchapter; and

(3) When in a mixture or solution—

(i) For radionuclides, conforms to paragraph 7 of the appendix A to § 172.101.

(ii) For other than radionuclides, is in a concentration by weight which equals or exceeds the concentration corresponding to the RQ of the material, as shown in the following table:

| RQ pounds (kilograms) | Concentration by weight |         |
|-----------------------|-------------------------|---------|
|                       | Percent                 | PPM     |
| 5000 (2270) .....     | 10                      | 100,000 |
| 1000 (454) .....      | 2                       | 20,000  |
| 100 (45.4) .....      | 0.2                     | 2,000   |
| 10 (4.54) .....       | 0.02                    | 200     |
| 1 (0.454) .....       | 0.002                   | 20      |

The term does not include petroleum, including crude oil or any fraction thereof which is not otherwise specifically listed or designated as a hazardous substance in appendix A to § 172.101 of this subchapter, and the term does not include natural gas, natural gas liquids, liquefied natural gas, or synthetic gas usable for fuel (or mixtures of natural gas and such synthetic gas).

**Hazardous waste**, for the purposes of this chapter, means any material that is subject to the Hazardous Waste Manifest Requirements of the U.S. Environmental Protection Agency specified in 40 CFR part 262.

**Hazmat** means a hazardous material.

**Hazmat employee** means: (1) A person who is:

(i) Employed on a full-time, part time, or temporary basis by a hazmat employer and who in the course of such

full time, part time or temporary employment directly affects hazardous materials transportation safety;

(ii) Self-employed (including an owner-operator of a motor vehicle, vessel, or aircraft) transporting hazardous materials in commerce who in the course of such self-employment directly affects hazardous materials transportation safety;

(iii) A railroad signalman; or

(iv) A railroad maintenance-of-way employee.

(2) This term includes an individual, employed on a full time, part time, or temporary basis by a hazmat employer, or who is self-employed, who during the course of employment:

(i) Loads, unloads, or handles hazardous materials;

(ii) Designs, manufactures, fabricates, inspects, marks, maintains, reconditions, repairs, or tests a package, container, or packaging component that is represented, marked, certified, or sold as qualified for use in transporting hazardous material in commerce.

(iii) Prepares hazardous materials for transportation;

(iv) Is responsible for safety of transporting hazardous materials;

(v) Operates a vehicle used to transport hazardous materials.

*Hazmat employer* means:

(1) A person who employs or uses at least one hazmat employee on a full-time, part time, or temporary basis; and who:

(i) Transports hazardous materials in commerce;

(ii) Causes hazardous materials to be transported in commerce; or

(iii) Designs, manufactures, fabricates, inspects, marks, maintains, reconditions, repairs or tests a package, container, or packaging component that is represented, marked, certified, or sold by that person as qualified for use in transporting hazardous materials in commerce;

(2) A person who is self-employed (including an owner-operator of a motor vehicle, vessel, or aircraft) transporting materials in commerce; and who:

(i) Transports hazardous materials in commerce;

(ii) Causes hazardous materials to be transported in commerce; or

(iii) Designs, manufactures, fabricates, inspects, marks, maintains, reconditions, repairs or tests a package, container, or packaging component that is represented, marked, certified, or sold by that person as qualified for use in transporting hazardous materials in commerce; or

(3) A department, agency, or instrumentality of the United States Government, or an authority of a State, political subdivision of a State, or an Indian tribe; and who:

(i) Transports hazardous materials in commerce;

(ii) Causes hazardous materials to be transported in commerce; or

(iii) Designs, manufactures, fabricates, inspects, marks, maintains, reconditions, repairs or tests a package, container, or packaging component that is represented, marked, certified, or sold by that person as qualified for use in transporting hazardous materials in commerce.

*Hermetically sealed* means closed by fusion, gasketing, crimping, or equivalent means so that no gas or vapor can enter or escape.

*Household waste* means any solid waste (including garbage, trash, and sanitary waste from septic tanks) derived from households (including single and multiple residences, hotels and motels, bunkhouses, ranger stations, crew quarters, campgrounds, picnic grounds, and day-use recreation areas). This term is not applicable to consolidated shipments of household hazardous materials transported from collection centers. A collection center is a central location where household waste is collected.

*HMR* means the Hazardous Materials Regulations, Parts 171 through 180 of this chapter.

*IAEA* means International Atomic Energy Agency.

*IATA* means International Air Transport Association.

*ICAO* means International Civil Aviation Organization.

*IMO* means International Maritime Organization.

*Incorporated by reference* or *IBR* means a publication or a portion of a publication that is made a part of the

regulations of this subchapter. See § 171.7.

*Infectious substance (etiologic agent).* See § 173.134 of this subchapter.

*Inner packaging* means a packaging for which an outer packaging is required for transport. It does not include the inner receptacle of a composite packaging.

*Inner receptacle* means a receptacle which requires an outer packaging in order to perform its containment function. The inner receptacle may be an inner packaging of a combination packaging or the inner receptacle of a composite packaging.

*Intermediate bulk container* or *IBC* means a rigid or flexible portable packaging, other than a cylinder or portable tank, which is designed for mechanical handling. Standards for IBCs manufactured in the United States are set forth in subparts N and O of part 178 of this subchapter.

*Intermediate packaging* means a packaging which encloses an inner packaging or article and is itself enclosed in an outer packaging.

*Intermodal container* means a freight container designed and constructed to permit it to be used interchangeably in two or more modes of transport.

*Intermodal portable tank* or *IM portable tank* means a specific class of portable tanks designed primarily for international intermodal use.

*International transportation* means transportation—

(1) Between any place in the United States and any place in a foreign country;

(2) Between places in the United States through a foreign country; or

(3) Between places in one or more foreign countries through the United States.

*Irritating material.* See § 173.132(a)(2) of this subchapter.

*Jerrican* means a metal or plastic packaging of rectangular or polygonal cross-section.

*Large packaging* means a packaging that—

(1) Consists of an outer packaging which contains articles or inner packagings;

(2) Is designated for mechanical handling;

(3) Exceeds 400 kg net mass or 450 liters (118.9 gallons) capacity;

(4) Has a volume of not more than 3 m<sup>3</sup> (see § 178.801(i) of this subchapter); and

(5) Conforms to the requirements for the construction, testing and marking of large packagings as specified in the UN Recommendations, Chapter 6.6 (incorporated by reference; see § 171.7).

*Limited quantity*, when specified as such in a section applicable to a particular material, means the maximum amount of a hazardous material for which there is a specific labeling or packaging exception.

*Lighter* means a mechanically operated flame-producing device employing an ignition device and containing a Class 3 or a Division 2.1 material. For design, capacity, and filling density requirements for lighters containing a Division 2.1 material, see § 173.308.

*Lighter refill* means a pressurized container that does not contain an ignition device but does contain a release device and is intended for use as a replacement cartridge in a lighter or to refill a lighter with a Division 2.1 flammable gas fuel. For capacity limits, see § 173.306(h) of this subchapter.

*Liquid* means a material, other than an elevated temperature material, with a melting point or initial melting point of 20 °C (68 °F) or lower at a standard pressure of 101.3 kPa (14.7 psia). A viscous material for which a specific melting point cannot be determined must be subjected to the procedures specified in ASTM D 4359 “Standard Test Method for Determining Whether a Material is Liquid or Solid” (IBR, see § 171.7).

*Liquid phase* means a material that meets the definition of liquid when evaluated at the higher of the temperature at which it is offered for transportation or at which it is transported, not at the 38°C (100°F) temperature specified in ASTM D 4359 (IBR, see § 171.7).

*Lithium content* means the mass of lithium in the anode of a lithium metal or lithium alloy cell. The lithium content of a battery equals the sum of the grams of lithium content contained in the component cells of the battery. For a lithium-ion cell see the definition for “equivalent lithium content”.

## § 171.8

## 49 CFR Ch. I (10–1–08 Edition)

*Loading incidental to movement* means loading by carrier personnel or in the presence of carrier personnel of packaged or containerized hazardous material onto a transport vehicle, aircraft, or vessel for the purpose of transporting it, including the loading, blocking and bracing a hazardous materials package in a freight container or transport vehicle, and segregating a hazardous materials package in a freight container or transport vehicle from incompatible cargo. For a bulk packaging, *loading incidental to movement* means filling the packaging with a hazardous material for the purpose of transporting it. *Loading incidental to movement* includes transloading.

*Magazine vessel* means a vessel used for the receiving, storing, or dispensing of explosives.

*Magnetic material.* See § 173.21(d) of this subchapter.

*Marine pollutant,* means a material which is listed in appendix B to § 172.101 of this subchapter (also see § 171.4) and, when in a solution or mixture of one or more marine pollutants, is packaged in a concentration which equals or exceeds:

(1) Ten percent by weight of the solution or mixture for materials listed in the appendix; or

(2) One percent by weight of the solution or mixture for materials that are identified as severe marine pollutants in the appendix.

*Marking* means a descriptive name, identification number, instructions, cautions, weight, specification, or UN marks, or combinations thereof, required by this subchapter on outer packagings of hazardous materials.

*Material of trade* means a hazardous material, other than a hazardous waste, that is carried on a motor vehicle—

(1) For the purpose of protecting the health and safety of the motor vehicle operator or passengers;

(2) For the purpose of supporting the operation or maintenance of a motor vehicle (including its auxiliary equipment); or

(3) By a private motor carrier (including vehicles operated by a rail carrier) in direct support of a principal business that is other than transportation by motor vehicle.

*Material poisonous by inhalation* means:

(1) A gas meeting the defining criteria in § 173.115(c) of this subchapter and assigned to Hazard Zone A, B, C, or D in accordance with § 173.116(a) of this subchapter;

(2) A liquid (other than as a mist) meeting the defining criteria in § 173.132(a)(1)(iii) of this subchapter and assigned to Hazard Zone A or B in accordance with § 173.133(a) of this subchapter; or

(3) Any material identified as an inhalation hazard by a special provision in column 7 of the § 172.101 table.

*Maximum allowable working pressure* or MAWP: For DOT specification cargo tanks used to transport liquid hazardous materials, see § 178.320(a) of this subchapter.

*Maximum capacity* means the maximum inner volume of receptacles or packagings.

*Maximum net mass* means the allowable maximum net mass of contents in a single packaging, or as used in subpart M of part 178 of this subchapter, the maximum combined mass of inner packaging, and the contents thereof.

*Metered delivery service* means a cargo tank unloading operation conducted at a metered flow rate of 378.5 L (100 gallons) per minute or less through an attached delivery hose with a nominal inside diameter of 3.175 cm (1¼ inches) or less.

*Miscellaneous hazardous material.* See § 173.140 of this subchapter.

*Mixture* means a material composed of more than one chemical compound or element.

*Mode* means any of the following transportation methods; rail, highway, air, or water.

*Motor vehicle* includes a vehicle, machine, tractor, trailer, or semitrailer, or any combination thereof, propelled or drawn by mechanical power and used upon the highways in the transportation of passengers or property. It does not include a vehicle, locomotive, or car operated exclusively on a rail or rails, or a trolley bus operated by electric power derived from a fixed overhead wire, furnishing local passenger transportation similar to street-railway service.

*Movement* means the physical transfer of a hazardous material from one geographic location to another by rail car, aircraft, motor vehicle, or vessel.

*Multiple-element gas container or MEGC* means assemblies of UN cylinders, tubes, or bundles of cylinders interconnected by a manifold and assembled within a framework. The term includes all service equipment and structural equipment necessary for the transport of gases.

*Name of contents* means the proper shipping name as specified in §172.101 of this subchapter.

*Navigable waters* means, for the purposes of this subchapter, waters of the United States, including the territorial seas.

*Non-bulk packaging* means a packaging which has:

(1) A maximum capacity of 450 L (119 gallons) or less as a receptacle for a liquid;

(2) A maximum net mass of 400 kg (882 pounds) or less and a maximum capacity of 450 L (119 gallons) or less as a receptacle for a solid; or

(3) A water capacity of 454 kg (1000 pounds) or less as a receptacle for a gas as defined in §173.115 of this subchapter.

*Nonflammable gas.* See §173.115 of this subchapter.

*N.O.S.* means not otherwise specified.

*N.O.S. description* means a shipping description from the §172.101 table which includes the abbreviation *n.o.s.*

*NPT* means an American Standard taper pipe thread conforming to the requirements of NBS Handbook H-28 (IBR, see §171.7).

*NRC (non-reusable container)* means a packaging (container) whose reuse is restricted in accordance with the provisions of §173.28 of this subchapter.

*Occupied caboose* means a rail car being used to transport non-passenger personnel.

*Officer in Charge, Marine Inspection* means a person from the civilian or military branch of the Coast Guard designated as such by the Commandant and who under the supervision and direction of the Coast Guard District Commander is in charge of a designated inspection zone for the performance of duties with respect to the enforcement and administration of

title 52, Revised Statutes, acts amendatory thereof or supplemental thereto, rules and regulations thereunder, and the inspection required thereby.

*Offshore supply vessel* means a cargo vessel of less than 500 gross tons that regularly transports goods, supplies or equipment in support of exploration or production of offshore mineral or energy resources.

*Operator* means a person who controls the use of an aircraft, vessel, or vehicle.

*Organic peroxide.* See §173.128 of this subchapter.

*ORM* means other regulated material. See §173.144 of this subchapter.

*Outage* or *ullage* means the amount by which a packaging falls short of being liquid full, usually expressed in percent by volume.

*Outer packaging* means the outermost enclosure of a composite or combination packaging together with any absorbent materials, cushioning and any other components necessary to contain and protect inner receptacles or inner packagings.

*Overpack*, except as provided in subpart K of part 178 of this subchapter, means an enclosure that is used by a single consignor to provide protection or convenience in handling of a package or to consolidate two or more packages. *Overpack* does not include a transport vehicle, freight container, or aircraft unit load device. Examples of overpacks are one or more packages:

(1) Placed or stacked onto a load board such as a pallet and secured by strapping, shrink wrapping, stretch wrapping, or other suitable means; or

(2) Placed in a protective outer packaging such as a box or crate.

*Oxidizer.* See §173.127 of this subchapter.

*Oxidizing gas* means a gas which may, generally by providing oxygen, cause or contribute to the combustion of other material more than air does.

*Oxygen generator (chemical)* means a device containing chemicals that upon activation release oxygen as a product of chemical reaction.

*Package* or *Outside Package* means a packaging plus its contents. For radioactive materials, see §173.403 of this subchapter.

*Packaging* means a receptacle and any other components or materials necessary for the receptacle to perform its containment function in conformance with the minimum packing requirements of this subchapter. For radioactive materials packaging, see § 173.403 of this subchapter.

*Packing group* means a grouping according to the degree of danger presented by hazardous materials. Packing Group I indicates great danger; Packing Group II, medium danger; Packing Group III, minor danger. See § 172.101(f) of this subchapter.

*Passenger* (With respect to vessels and for the purposes of part 176 only) means a person being carried on a vessel other than:

- (1) The owner or his representative;
- (2) The operator;
- (3) A bona fide member of the crew engaged in the business of the vessel who has contributed no consideration for his carriage and who is paid for his services; or
- (4) A guest who has not contributed any consideration directly or indirectly for his carriage.

*Passenger-carrying aircraft* means an aircraft that carries any person other than a crewmember, company employee, an authorized representative of the United States, or a person accompanying the shipment.

*Passenger vessel* means—

- (1) A vessel subject to any of the requirements of the International Convention for the Safety of Life at Sea, 1974, which carries more than 12 passengers;
- (2) A cargo vessel documented under the laws of the United States and not subject to that Convention, which carries more than 16 passengers;
- (3) A cargo vessel of any foreign nation that extends reciprocal privileges and is not subject to that Convention and which carries more than 16 passengers; and
- (4) A vessel engaged in a ferry operation and which carries passengers.

*Person* means an individual, corporation, company, association, firm, partnership, society, joint stock company; or a government, Indian tribe, or authority of a government or tribe offering a hazardous material for transportation in commerce or transporting a

hazardous material to support a commercial enterprise. This term does not include the United States Postal Service or, for purposes of 49 U.S.C. 5123 and 5124, a Department, agency, or instrumentality of the government.

*Person who offers or offeror* means:

- (1) Any person who does either or both of the following:

- (i) Performs, or is responsible for performing, any pre-transportation function required under this subchapter for transportation of the hazardous material in commerce.

- (ii) Tenders or makes the hazardous material available to a carrier for transportation in commerce.

- (2) A carrier is not an offeror when it performs a function required by this subchapter as a condition of acceptance of a hazardous material for transportation in commerce (e.g., reviewing shipping papers, examining packages to ensure that they are in conformance with this subchapter, or preparing shipping documentation for its own use) or when it transfers a hazardous material to another carrier for continued transportation in commerce without performing a pre-transportation function.

*PHMSA* means the Pipeline and Hazardous Materials Safety Administration, U.S. Department of Transportation, Washington, DC 20590.

*Placarded car* means a rail car which is placarded in accordance with the requirements of part 172 of this subchapter.

*Poisonous gas*. See § 173.115 of this subchapter.

*Poisonous materials*. See § 173.132 of this subchapter.

*Portable tank* means a bulk packaging (except a cylinder having a water capacity of 1000 pounds or less) designed primarily to be loaded onto, or on, or temporarily attached to a transport vehicle or ship and equipped with skids, mountings, or accessories to facilitate handling of the tank by mechanical means. It does not include a cargo tank, tank car, multi-unit tank car tank, or trailer carrying 3AX, 3AAX, or 3T cylinders.

*Preferred route or Preferred highway* is a highway for shipment of *highway route controlled quantities* of radioactive materials so designated by a State

routing agency, and any Interstate System highway for which an alternative highway has not been designated by such State agency as provided by § 397.103 of this title.

*Pre-transportation function* means a function specified in the HMR that is required to assure the safe transportation of a hazardous material in commerce, including—

(1) Determining the hazard class of a hazardous material.

(2) Selecting a hazardous materials packaging.

(3) Filling a hazardous materials packaging, including a bulk packaging.

(4) Securing a closure on a filled or partially filled hazardous materials package or container or on a package or container containing a residue of a hazardous material.

(5) Marking a package to indicate that it contains a hazardous material.

(6) Labeling a package to indicate that it contains a hazardous material.

(7) Preparing a shipping paper.

(8) Providing and maintaining emergency response information.

(9) Reviewing a shipping paper to verify compliance with the HMR or international equivalents.

(10) For each person importing a hazardous material into the United States, providing the shipper with timely and complete information as to the HMR requirements that will apply to the transportation of the material within the United States.

(11) Certifying that a hazardous material is in proper condition for transportation in conformance with the requirements of the HMR.

(12) Loading, blocking, and bracing a hazardous materials package in a freight container or transport vehicle.

(13) Segregating a hazardous materials package in a freight container or transport vehicle from incompatible cargo.

(14) Selecting, providing, or affixing placards for a freight container or transport vehicle to indicate that it contains a hazardous material.

*Primary hazard* means the hazard class of a material as assigned in the § 172.101 table.

*Private track* or *Private siding* means:

(i) Track located outside of a carrier's right-of-way, yard, or terminals where

the carrier does not own the rails, ties, roadbed, or right-of-way, or

(ii) Track leased by a railroad to a lessee, where the lease provides for, and actual practice entails, exclusive use of that trackage by the lessee and/or a general system railroad for purpose of moving only cars shipped to or by the lessee, and where the lessor otherwise exercises no control over or responsibility for the trackage or the cars on the trackage.

*Proper shipping name* means the name of the hazardous material shown in Roman print (not italics) in § 172.101 of this subchapter.

*Psi* means pounds per square inch.

*Psia* means pounds per square inch absolute.

*Psig* means pounds per square inch gauge.

*Public vessel* means a vessel owned by and being used in the public service of the United States. It does not include a vessel owned by the United States and engaged in a trade or commercial service or a vessel under contract or charter to the United States.

*Pyrophoric liquid*. See § 173.124(b) of this subchapter.

*Radioactive materials*. See § 173.403 of this subchapter for definitions relating to radioactive materials.

*Rail car* means a car designed to carry freight or non-passenger personnel by rail, and includes a box car, flat car, gondola car, hopper car, tank car, and occupied caboose.

*Railroad* means a person engaged in transportation by rail.

*Receptacle* means a containment vessel for receiving and holding materials, including any means of closing.

*Registered Inspector* means a person registered with the Department in accordance with subpart F of part 107 of this chapter who has the knowledge and ability to determine whether a cargo tank conforms to the applicable DOT specification. A *Registered Inspector* meets the knowledge and ability requirements of this section by meeting any one of the following requirements:

(1) Has an engineering degree and one year of work experience relating to the testing and inspection of cargo tanks;



## § 171.8

## 49 CFR Ch. I (10–1–08 Edition)

(2) Has an associate degree in engineering and two years of work experience relating to the testing and inspection of cargo tanks;

(3) Has a high school diploma (or General Equivalency Diploma) and three years of work experience relating to the testing and inspection of cargo tanks; or

(4) Has at least three years' experience performing the duties of a Registered Inspector prior to September 1, 1991.

*Regulated medical waste.* See § 173.134 of this subchapter.

*Reportable quantity (RQ)* for the purposes of this subchapter means the quantity specified in column 2 of the appendix to § 172.101 for any material identified in column 1 of the appendix.

*Research* means investigation or experimentation aimed at the discovery of new theories or laws and the discovery and interpretation of facts or revision of accepted theories or laws in the light of new facts. Research does not include the application of existing technology to industrial endeavors.

*Residue* means the hazardous material remaining in a packaging, including a tank car, after its contents have been unloaded to the maximum extent practicable and before the packaging is either refilled or cleaned of hazardous material and purged to remove any hazardous vapors.

*SADT* means self-accelerated decomposition temperature. See § 173.21(f) of this subchapter.

*Salvage packaging* means a special packaging conforming to § 173.3 of this subchapter into which damaged, defective, leaking, or non-conforming hazardous materials packages, or hazardous materials that have spilled or leaked, are placed for purposes of transport for recovery or disposal.

*SCF* (standard cubic foot) means one cubic foot of gas measured at 60 °F. and 14.7 psia.

*Secretary* means the Secretary of Transportation.

*Self-defense spray* means an aerosol or non-pressurized device that:

(1) Is intended to have an irritating or incapacitating effect on a person or animal; and

(2) Meets no hazard criteria other than for Class 9 (for example, a pepper

spray; see § 173.140(a) of this subchapter) and, for an aerosol, Division 2.1 or 2.2 (see § 173.115 of this subchapter), except that it may contain not more than two percent by mass of a tear gas substance (e.g., chloroacetophenone (CN) or o-chlorobenzylmalonitrile (CS); see § 173.132(a)(2) of this subchapter.)

*Settled pressure* means the pressure exerted by the contents of a UN pressure receptacle in thermal and diffusive equilibrium.

*Sharps.* See § 173.134 of this subchapter.

*Shipping paper* means a shipping order, bill of lading, manifest or other shipping document serving a similar purpose and prepared in accordance with subpart C of part 172 of this chapter.

*Siftproof packaging* means a packaging impermeable to dry contents, including fine solid material produced during transportation.

*Single packaging* means a non-bulk packaging other than a combination packaging.

*Solid* means a material which is not a gas or a liquid.

*Solution* means any homogeneous liquid mixture of two or more chemical compounds or elements that will not undergo any segregation under conditions normal to transportation.

*Special permit* means a document issued by the Associate Administrator under the authority of 49 U.S.C. 5117 permitting a person to perform a function that is not otherwise permitted under subchapter A or C of this chapter, or other regulations issued under 49 U.S.C. 5101 et seq. (e.g., Federal Motor Carrier Safety routing requirements). The terms “special permit” and “exemption” have the same meaning for purposes of subchapter A or C of this chapter or other regulations issued under 49 U.S.C. 5101 through 5127. An exemption issued prior to October 1, 2005 remains valid until it is past its expiration date, terminated by the Associate Administrator, or issued as a special permit, whichever occurs first.

*Specification packaging* means a packaging conforming to one of the specifications or standards for packagings in part 178 or part 179 of this subchapter.

*Spontaneously combustible material.* See § 173.124(b) of this subchapter.

*Stabilized* means that the hazardous material is in a condition that precludes uncontrolled reaction. This may be achieved by methods such as adding an inhibiting chemical, degassing the hazardous material to remove dissolved oxygen and inerting the air space in the package, or maintaining the hazardous material under temperature control.

*State* means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, the Virgin Islands, American Samoa, Guam, or any other territory or possession of the United States designated by the Secretary.

*State-designated route* means a preferred route selected in accordance with U.S. DOT "Guidelines for Selecting Preferred Highway Routes for Highway Route Controlled Quantities of Radioactive Materials" or an equivalent routing analysis which adequately considers overall risk to the public.

*Storage incidental to movement* means storage of a transport vehicle, freight container, or package containing a hazardous material by any person between the time that a carrier takes physical possession of the hazardous material for the purpose of transporting it in commerce until the package containing the hazardous material is physically delivered to the destination indicated on a shipping document, package marking, or other medium, or, in the case of a private motor carrier, between the time that a motor vehicle driver takes physical possession of the hazardous material for the purpose of transporting it in commerce until the driver relinquishes possession of the package at its destination and is no longer responsible for performing functions subject to the HMR with respect to that particular package.

(1) *Storage incidental to movement* includes—

(i) Storage at the destination shown on a shipping document, including storage at a transloading facility, provided the shipping documentation identifies the shipment as a through-shipment and identifies the final destination

or destinations of the hazardous material; and

(ii) Rail cars containing hazardous materials that are stored on track that does not meet the definition of "private track or siding" in § 171.8, even if those cars have been delivered to the destination shown on the shipping document.

(2) Storage incidental to movement does not include storage of a hazardous material at its final destination as shown on a shipping document.

*Stowage* means the act of placing hazardous materials on board a vessel.

*Strong outside container* means the outermost enclosure which provides protection against the unintentional release of its contents under conditions normally incident to transportation.

*Subsidiary hazard* means a hazard of a material other than the primary hazard. (See *primary hazard*).

*Table in § 172.101 or § 172.101 table* means the Hazardous Materials Table in § 172.101 of this subchapter.

*Technical name* means a recognized chemical name or microbiological name currently used in scientific and technical handbooks, journals, and texts. Generic descriptions are authorized for use as technical names provided they readily identify the general chemical group, or microbiological group. Examples of acceptable generic chemical descriptions are organic phosphate compounds, petroleum aliphatic hydrocarbons and tertiary amines. For proficiency testing only, generic microbiological descriptions such as bacteria, mycobacteria, fungus, and viral samples may be used. Except for names which appear in subpart B of part 172 of this subchapter, trade names may not be used as technical names.

*TOFC* means trailer-on-flat-car.

*Top shell* means the tank car tank surface, excluding the head ends and bottom shell of the tank car tank.

*Toxin.* See § 173.134 of this subchapter.

*Trailership* means a vessel, other than a carfloat, specifically equipped to carry motor transport vehicles and fitted with installed securing devices to tie down each vehicle. The term *trailership* includes *Roll-on/Roll-off (RO/RO)* vessels.

## § 171.8

## 49 CFR Ch. I (10–1–08 Edition)

*Train* means one or more engines coupled with one or more rail cars, except during switching operations or where the operation is that of classifying and assembling rail cars within a railroad yard for the purpose of making or breaking up trains.

*Trainship* means a vessel other than a rail car ferry or carfloat, specifically equipped to transport railroad vehicles, and fitted with installed securing devices to tie down each vehicle.

*Transloading* means the transfer of a hazardous material by any person from one bulk packaging to another bulk packaging, from a bulk packaging to a non-bulk packaging, or from a non-bulk packaging to a bulk packaging for the purpose of continuing the movement of the hazardous material in commerce.

*Transport vehicle* means a cargo-carrying vehicle such as an automobile, van, tractor, truck, semitrailer, tank car or rail car used for the transportation of cargo by any mode. Each cargo-carrying body (trailer, rail car, etc.) is a separate transport vehicle.

*Transportation* or *transport* means the movement of property and loading, unloading, or storage incidental to that movement.

*UFC* means Uniform Freight Classification.

*UN* means United Nations.

*UN cylinder* means a transportable pressure receptacle with a water capacity not exceeding 150 L that has been marked and certified as conforming to the applicable requirements in part 178 of this subchapter.

*UN portable tank* means an intermodal tank having a capacity of more than 450 liters (118.9 gallons). It includes a shell fitted with service equipment and structural equipment, including stabilizing members external to the shell and skids, mountings or accessories to facilitate mechanical handling. A UN portable tank must be capable of being filled and discharged without the removal of its structural equipment and must be capable of being lifted when full. Cargo tanks, rail tank car tanks, non-metallic tanks, non-specification tanks, bulk bins, and IBCs and packagings made to cylinder specifications are not UN portable tanks.

*UN pressure receptacle* means a UN cylinder or tube.

*UN Recommendations* means the UN Recommendations on the Transport of Dangerous Goods (IBR, see § 171.7).

*UN standard packaging* means a packaging conforming to standards in the UN Recommendations (IBR, see § 171.7).

*UN tube* means a seamless transportable pressure receptacle with a water capacity exceeding 150 L but not more than 3,000 L that has been marked and certified as conforming to the requirements in part 178 of this subchapter.

*Undeclared hazardous material* means a hazardous material that is: (1) Subject to any of the hazard communication requirements in subparts C (Shipping Papers), D (Marking), E (Labeling), and F (Placarding) of Part 172 of this subchapter, or an alternative marking requirement in Part 173 of this subchapter (such as §§ 173.4(a)(10) and 173.6(c)); and (2) offered for transportation in commerce without any visible indication to the person accepting the hazardous material for transportation that a hazardous material is present, on either an accompanying shipping document, or the outside of a transport vehicle, freight container, or package.

*Unintentional release* means the escape of a hazardous material from a package on an occasion not anticipated or planned. This includes releases resulting from collision, package failures, human error, criminal activity, negligence, improper packing, or unusual conditions such as the operation of pressure relief devices as a result of over-pressurization, overfill or fire exposure. It does not include releases, such as venting of packages, where allowed, and the operational discharge of contents from packages.

*Unit load device* means any type of freight container, aircraft container, aircraft pallet with a net, or aircraft pallet with a net over an igloo.

*United States* means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, the Virgin Islands, American Samoa, Guam, or any other territory or possession of the United States designated by the Secretary.

*Unloading incidental to movement* means removing a packaged or containerized hazardous material from a transport vehicle, aircraft, or vessel, or for a bulk packaging, emptying a hazardous material from the bulk packaging after the hazardous material has been delivered to the consignee when performed by carrier personnel or in the presence of carrier personnel or, in the case of a private motor carrier, while the driver of the motor vehicle from which the hazardous material is being unloaded immediately after movement is completed is present during the unloading operation. (Emptying a hazardous material from a bulk packaging while the packaging is on board a vessel is subject to separate regulations as delegated by Department of Homeland Security Delegation No. 0170.1 at 2(103).) *Unloading incidental to movement* includes transloading.

*Vessel* includes every description of watercraft, used or capable of being used as a means of transportation on the water.

*Viscous liquid* means a liquid material which has a measured viscosity in excess of 2500 centistokes at 25 °C. (77 °F.) when determined in accordance with the procedures specified in ASTM Method D 445-72 "Kinematic Viscosity of Transparent and Opaque Liquids (and the Calculation of Dynamic Viscosity)" or ASTM Method D 1200-70 "Viscosity of Paints, Varnishes, and Lacquers by Ford Viscosity Cup."

*Volatility* refers to the relative rate of evaporation of materials to assume the vapor state.

*Water reactive material.* See § 173.124(c) of this subchapter.

*Water resistant* means having a degree of resistance to permeability by and damage caused by water in liquid form.

*Wooden barrel* means a packaging made of natural wood, of round cross-section, having convex walls, consisting of staves and heads and fitted with hoops.

*Working pressure* for purposes of UN pressure receptacles, means the settled pressure of a compressed gas at a reference temperature of 15 °C (59 °F).

*W.T.* means watertight.

[Amdt. 171-32, 41 FR 15994, Apr. 15, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 171.8, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 171.9 Rules of construction.

(a) In this subchapter, unless the context requires otherwise:

(1) Words imparting the singular include the plural;

(2) Words imparting the plural include the singular; and

(3) Words imparting the masculine gender include the feminine;

(b) In this subchapter, the word: (1) "Shall" is used in an imperative sense;

(2) "Must" is used in an imperative sense;

(3) "Should" is used in a recommendatory sense;

(4) "May" is used in a permissive sense to state authority or permission to do the act described, and the words "no person may \* \* \*" or "a person may not \* \* \*" means that no person is required, authorized, or permitted to do the act described; and

(5) "Includes" is used as a word of inclusion not limitation.

[Amdt. 171-32, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 171-32A, 41 FR 40630, Sept. 20, 1976; Amdt. 171-121, 58 FR 51528, Oct. 1, 1993]

#### § 171.10 Units of measure.

(a) *General.* To ensure compatibility with international transportation standards, most units of measure in this subchapter are expressed using the International System of Units ("SI" or metric). Where SI units appear, they are the regulatory standard. U.S. standard or customary units, which appear in parentheses following the SI units, are for information only and are not intended to be the regulatory standard.

(b) Abbreviations for SI units of measure generally used throughout this subchapter are as shown in paragraph (c) of this section. Customary units shown throughout this subchapter are generally not abbreviated.

(c) *Conversion values.* (1) Conversion values are provided in the following table and are based on values provided in ASTM E 380, "Standard for Metric Practice".

(2) If an exact conversion is needed, the following conversion table should be used.

TABLE OF CONVERSION FACTORS FOR SI UNITS

| Measurement           | SI to U.S. standard                 | U.S. standard to SI     |
|-----------------------|-------------------------------------|-------------------------|
| Activity .....        | 1 TBq=27 Ci .....                   | 1 Ci=0.037 TBq          |
| Length .....          | 1 cm=0.3937008 in .....             | 1 in=2.540000 cm        |
|                       | 1 m=3.280840 ft .....               | 1 ft=0.3048000 m        |
| Thickness .....       | 1 mm=0.03937008 in .....            | 1 in=25.40000 mm        |
| Mass (weight) .....   | 1 kg=2.204622 lb .....              | 1 lb=0.4535924 kg       |
|                       | 1 g=0.03527397 oz .....             | 1 oz=28.34952 g         |
| Pressure .....        | 1 kPa=0.1450377 psi .....           | 1 psi=6.894757 kPa      |
|                       | 1 Bar=100 kPa=14.504 psi .....      | 1 psi=0.06895 Bar       |
|                       | 1 kPa=7.5 mm Hg .....               |                         |
| Radiation level ..... | 1 Sv/hr=100 rem/hr .....            | 1 rem/hr=0.01 Sv/hr     |
| Volume (liquid) ..... | 1 L=0.2641720 gal .....             | 1 gal=3.785412 L        |
|                       | 1 mL=0.03381402 oz .....            | 1 oz=29.57353 mL        |
|                       | 1 m³=35.31466 ft³ .....             | 1 ft³=0.02831685 m³     |
| Density .....         | 1 kg/m³=0.06242797 lb/ft³ .....     | 1 lb/ft³=16.01846 kg/m³ |
| Force .....           | 1 Newton = 0.2248 Pound-force ..... | 1 Pound-force=4.483 N   |

Abbreviation for units of measure are as follows:

Unit of measure and abbreviation:

(SI): millimeter, mm; centimeter, cm; meter, m; gram, g; kilogram, kg; kilopascal, kPa; liter, L; milliliter, mL; cubic meter, m³; Terabecquerel, TBq; Gigabecquerel, GBq; millisievert, mSv; Newton, N;  
(U.S.): inch, in; foot, ft; ounce, oz; pound, lb; psig, psi; gallon, gal; cubic feet, ft³; Curie, Ci; millicurie, mCi; millirem, mrem.

[Amdt. 171–111, 56 FR 66159, Dec. 20, 1991, as amended by Amdt. 171–136, 60 FR 49108, Sept. 21, 1995; Amdt. 171–135, 60 FR 50302, Sept. 28, 1995; 66 FR 33335, June 21, 2001; 66 FR 45378, Aug. 28, 2001; 68 FR 75740, Dec. 31, 2003]

### § 171.11 [Reserved]

### § 171.12 North American Shipments.

(a) *Requirements for the use of the Transport Canada TDG Regulations.* (1) A hazardous material transported from Canada to the United States, from the United States to Canada, or transiting the United States to Canada or a foreign destination may be offered for transportation or transported by motor carrier and rail in accordance with the Transport Canada TDG Regulations (IBR, see § 171.7) as authorized in § 171.22, provided the requirements in §§ 171.22 and 171.23, as applicable, and this section are met. In addition, a cargo tank motor vehicle, portable tank or rail tank car authorized by the Transport Canada TDG Regulations may be used for transportation to, from, or within the United States provided the cargo tank motor vehicle, portable tank or rail tank car conforms to the applicable requirements of this section. Except as otherwise provided in this subpart, the requirements in parts 172, 173, and 178 of this subchapter do not apply for a material transported in accordance with the Transport Canada TDG Regulations if all other re-

quirements of this subpart and the TDG Regulations are met.

(2) *General packaging requirements.* When the provisions of this subchapter require a DOT specification or UN standard packaging to be used for transporting a hazardous material, a packaging authorized by the Transport Canada TDG Regulations may be used, subject to the limitations of this part, and only if it is equivalent to the corresponding DOT specification or UN packaging (see § 173.24(d)(2) of this subchapter) authorized by this subchapter.

(3) *Bulk packagings.* A portable tank, cargo tank motor vehicle or rail tank car equivalent to a corresponding DOT specification and conforming to and authorized by the Transport Canada TDG Regulations may be used provided—

(i) An equivalent type of packaging is authorized for the hazardous material according to the § 172.101 table of this subchapter;

(ii) The portable tank, cargo tank motor vehicle or rail tank car conforms to the requirements of the applicable part 173 bulk packaging section specified in the § 172.101 table for the material to be transported;

(iii) The portable tank, cargo tank motor vehicle or rail tank car conforms to the requirements of all assigned bulk packaging special provisions (B codes, and T and TP codes) in § 172.102 of this subchapter; and

(iv) The bulk packaging conforms to all applicable requirements of §§ 173.31, 173.32, 173.33 and 173.35 of this subchapter, and parts 177 and 180 of this subchapter. The periodic retests and inspections required by §§ 173.31, 173.32 and 173.33 of this subchapter may be performed in accordance with part 180 of this subchapter or in accordance with the requirements of the TDG Regulations provided that the intervals prescribed in part 180 of this subchapter are met.

(v) Rail tank cars must conform to the requirements of Canadian General Standards Board standard 43.147 (IBR, see § 171.7).

(4) *Cylinders.* When the provisions of this subchapter require that a DOT specification or a UN pressure receptacle must be used for a hazardous material, a packaging authorized by the Transport Canada TDG Regulations may be used only if it corresponds to the DOT specification or UN standard authorized by this subchapter. Unless otherwise excepted in this subchapter, a cylinder (including a UN pressure receptacle) may not be transported unless—

(i) The packaging is a UN pressure receptacle marked with the letters “CAN” for Canada as a country of manufacture or a country of approval or is a cylinder that was manufactured, inspected and tested in accordance with a DOT specification or a UN standard prescribed in part 178 of this subchapter, except that cylinders not conforming to these requirements must meet the requirements in § 171.23. Each cylinder must conform to the applicable requirements in part 173 of this subchapter for the hazardous material involved.

(ii) The packaging is a Canadian Transport Commission (CTC) specification cylinder manufactured, originally marked and approved in accordance with the CTC regulations and in full conformance with the Transport Canada TDG Regulations.

(A) The CTC specification corresponds with a DOT specification and the cylinder markings are the same as those specified in this subchapter except that they were originally marked with the letters “CTC” in place of “DOT”;

(B) The cylinder has been requalified under a program authorized by the Transport Canada TDG Regulations or requalified in accordance with the requirements in § 180.205 within the prescribed requalification period provided for the corresponding DOT specification;

(C) When the regulations authorize a cylinder for a specific hazardous material with a specification marking prefix of “DOT”, a cylinder marked “CTC” which otherwise bears the same markings that would be required of the specified “DOT” cylinder may be used; and

(D) Transport of the cylinder and the material it contains is in all other respects in conformance with the requirements of this subchapter (e.g. valve protection, filling requirements, operational requirements, etc.).

(5) *Class 1 (explosive) materials.* When transporting Class 1 (explosive) material, rail and motor carriers must comply with 49 CFR 1572.9 and 1572.11 to the extent the requirements apply.

(6) *Primary lithium batteries and cells.* Packages containing primary lithium batteries and cells that meet the exception in § 172.102, Special Provision 188 or 189 of this subchapter must be marked “PRIMARY LITHIUM BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT” or “LITHIUM METAL BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT.” The provisions of this paragraph do not apply to packages that contain 5 kg (11 pounds) net weight or less of primary lithium batteries cells that are contained in or packed with equipment.

(b) *Shipments to or from Mexico.* Unless otherwise excepted, hazardous materials shipments from Mexico to the United States or from the United States to Mexico must conform to all applicable requirements of this subchapter. When a hazardous material

## § 171.12a

## 49 CFR Ch. I (10–1–08 Edition)

that is a material poisonous by inhalation (see § 171.8) is transported by highway or rail from Mexico to the United States, or from the United States to Mexico, the following requirements apply:

(1) The shipping description must include the words “Toxic Inhalation Hazard” or “Poison-Inhalation Hazard” or “Inhalation Hazard”, as required in § 172.203(m) of this subchapter.

(2) The material must be packaged in accordance with requirements of this subchapter.

(3) The package must be marked in accordance with § 172.313 of this subchapter.

(4) Except as provided in paragraph (e)(5) of this section, the package must be labeled or placarded POISON GAS or POISON INHALATION HAZARD, as appropriate, in accordance with subparts E and F of this subchapter.

(5) A label or placard that conforms to the UN Recommendations (IBR, see § 171.7) specifications for a “Division 2.3” or “Division 6.1” label or placard may be substituted for the POISON GAS or POISON INHALATION HAZARD label or placard required by §§ 172.400(a) and 172.504(e) of this subchapter on a package transported in a closed transport vehicle or freight container. The transport vehicle or freight container must be marked with identification numbers for the material, regardless of the total quantity contained in the transport vehicle or freight container, in the manner specified in § 172.313(c) of this subchapter and placarded as required by subpart F of this subchapter.

[Amdt. 171–111, 55 FR 52472, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 171.12, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 171.12a [Reserved]

### § 171.14 Transitional provisions for implementing certain requirements.

*General.* The purpose of the provisions of this section is to provide an orderly transition to certain new requirements so as to minimize any burdens associated with them.

(a) *Previously filled packages*—(1) *Packages filled prior to October 1, 1991.* Notwithstanding the marking and labeling provisions of subparts D and E, respectively, of part 172, and the packaging provisions of part 173 and subpart B of part 172 of this subchapter, a package may be offered for transportation and transported prior to October 1, 2001, if it—

(i) Conforms to the old requirements of this subchapter in effect on September 30, 1991;

(ii) Was filled with a hazardous material prior to October 1, 1991;

(iii) Is marked “Inhalation Hazard” if appropriate, in accordance with § 172.313 of this subchapter or Special Provision 13, as assigned in the § 172.101 table; and

(iv) Is not emptied and refilled on or after October 1, 1991.

(2) *Non-bulk packages filled prior to October 1, 1996.* Notwithstanding the packaging provisions of subpart B of part 172 and the packaging provisions of part 173 of this subchapter with respect to UN standard packagings, a non-bulk package other than a cylinder may be offered for transportation and transported domestically prior to October 1, 1999, if it—

(i) Conforms to the requirements of this subchapter in effect on September 30, 1996;

(ii) Was filled with a hazardous material prior to October 1, 1996; and

(iii) Is not emptied and refilled on or after October 1, 1996.

(b) [Reserved]

(c) *Non-specification fiber drums.* A non-specification fiber drum with a removable head is authorized for a liquid hazardous material in Packing Group III that is not poisonous by inhalation for which the packaging was authorized under the requirements of part 172 or part 173 of this subchapter in effect on September 30, 1991. This authorization expires on the date on which funds are authorized to be appropriated to carry out chapter 51 of title 49, United States Code (related to transportation of hazardous materials), for fiscal years beginning after September 30, 1997. Information concerning this funding authorization date may be obtained by contacting the Office of the Associate Administrator.

(d) A final rule published in the FEDERAL REGISTER on December 29, 2006, effective January 1, 2007, resulted in revisions to this subchapter. During the transition period, until January 1, 2008, as provided in paragraph (d)(1) of this section, a person may elect to comply with either the applicable requirements of this subchapter in effect on December 31, 2006, or the requirements published in the December 29, 2006 final rule.

(1) *Transition dates.* The effective date of the final rule published on December 29, 2006 is January 1, 2007. A delayed compliance date of January 1, 2008, is authorized. Unless otherwise specified, on and after January 1, 2008, all applicable regulatory requirements adopted in the final rule in effect on January 1, 2007, must be met.

(2) *Intermixing old and new requirements.* Marking, labeling, placarding, and shipping paper descriptions must conform to either the old requirements of this subchapter in effect on December 31, 2006, or the new requirements of this subchapter in the final rule without intermixing communication elements, except that intermixing is permitted during the applicable transition period for packaging, hazard communication and handling provisions, as follows:

(i) If either shipping names or identification numbers are identical, a shipping paper may display the old shipping description even if the package is marked and labeled under the new shipping description;

(ii) If either shipping names or identification numbers are identical, a shipping paper may display the new shipping description; and

(iii) Either old or new placards may be used regardless of whether old or new shipping descriptions, labels, and package markings are used.

(3) [Reserved]

(4) Until January 1, 2010, a hazardous material may be transported in an IM, IMO, or DOT Specification 51 portable tank in accordance with the T Codes (Special Provisions) assigned to a hazardous material in Column (7) of the § 172.101 Table in effect on September 30, 2001.

(5) Proper shipping names that included the word “inhibited” prior to

the June 21, 2001 final rule in effect on October 1, 2001 are authorized on packagings and shipping papers in place of the word “stabilized” until October 1, 2007. Proper shipping names that included the word “compressed” prior to the final rule published on July 31, 2003 and effective on October 1, 2003 may continue to be shown on packagings and shipping papers until October 1, 2007.

(6) Section 172.202(a)(7) requires the number and types of packages to be indicated on shipping papers. Until October 1, 2007, a person may elect to comply with the requirements for the number and type of packages in effect on September 30, 2003.

(e) The shipping description sequences in effect on December 31, 2006, may be used until January 1, 2013.

(f) Except for transportation by highway, a Division 5.2 label and a Division 5.2 placard conforming to the specifications in §§ 172.427 and 172.552, respectively, of this subchapter in effect on December 31, 2006, may be used until January 1, 2011. For transportation by highway, a Division 5.2 placard conforming to the specifications in § 172.552 of this subchapter in effect on December 31, 2006 may be used until January 1, 2014.

(g) The Class 3 and Division 6.1 classification criteria and packing group assignments in effect on December 31, 2006, may be used until January 1, 2012.

(h) The proper shipping name “Gasohol gasoline mixed with ethyl alcohol, with not more than 20 percent alcohol” in effect on January 28, 2008, may continue to be used until October 1, 2010.

[Amdt. 171–131, 59 FR 67406, Dec. 29, 1994]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 171.14, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.



### Subpart B—Incident Reporting, Notification, BOE Approvals and Authorization

#### § 171.15 Immediate notice of certain hazardous materials incidents.

(a) *General.* As soon as practical but no later than 12 hours after the occurrence of any incident described in paragraph (b) of this section, each person in physical possession of the hazardous material must provide notice by telephone to the National Response Center (NRC) on 800-424-8802 (toll free) or 202-267-2675 (toll call). Notice involving an infectious substance (etiologic agent) may be given to the Director, Centers for Disease Control and Prevention, U.S. Public Health Service, Atlanta, GA, 800-232-0124 (toll free), in place of notice to the NRC. Each notice must include the following information:

- (1) Name of reporter;
- (2) Name and address of person represented by reporter;
- (3) Phone number where reporter can be contacted;
- (4) Date, time, and location of incident;
- (5) The extent of injury, if any;
- (6) Class or division, proper shipping name, and quantity of hazardous materials involved, if such information is available; and
- (7) Type of incident and nature of hazardous material involvement and whether a continuing danger to life exists at the scene.

(b) *Reportable incident.* A telephone report is required whenever any of the following occurs during the course of transportation in commerce (including loading, unloading, and temporary storage):

- (1) As a direct result of a hazardous material—
  - (i) A person is killed;
  - (ii) A person receives an injury requiring admittance to a hospital;
  - (iii) The general public is evacuated for one hour or more;
  - (iv) A major transportation artery or facility is closed or shut down for one hour or more; or
  - (v) The operational flight pattern or routine of an aircraft is altered;
- (2) Fire, breakage, spillage, or suspected radioactive contamination oc-

curs involving a radioactive material (see also § 176.48 of this subchapter);

(3) Fire, breakage, spillage, or suspected contamination occurs involving an infectious substance other than a regulated medical waste;

(4) A release of a marine pollutant occurs in a quantity exceeding 450 L (119 gallons) for a liquid or 400 kg (882 pounds) for a solid; or

(5) A situation exists of such a nature (*e.g.*, a continuing danger to life exists at the scene of the incident) that, in the judgment of the person in possession of the hazardous material, it should be reported to the NRC even though it does not meet the criteria of paragraph (b) (1), (2), (3) or (4) of this section.

(c) *Written report.* Each person making a report under this section must also make the report required by § 171.16 of this subpart.

NOTE TO § 171.15: Under 40 CFR 302.6, EPA requires persons in charge of facilities (including transport vehicles, vessels, and aircraft) to report any release of a hazardous substance in a quantity equal to or greater than its reportable quantity, as soon as that person has knowledge of the release, to DOT's National Response Center at (toll free) 800-424-8802 or (toll) 202-267-2675.

[68 FR 67759, Dec. 3, 2003, as amended at 72 FR 55684, Oct. 1, 2007]

#### § 171.16 Detailed hazardous materials incident reports.

(a) *General.* Each person in physical possession of a hazardous material at the time that any of the following incidents occurs during transportation (including loading, unloading, and temporary storage) must submit a Hazardous Materials Incident Report on DOT Form F 5800.1 (01/2004) within 30 days of discovery of the incident:

- (1) Any of the circumstances set forth in § 171.15(b);
- (2) An unintentional release of a hazardous material or the discharge of any quantity of hazardous waste;
- (3) A specification cargo tank with a capacity of 1,000 gallons or greater containing any hazardous material suffers structural damage to the lading retention system or damage that requires repair to a system intended to protect the lading retention system, even if

there is no release of hazardous material; or

(4) An undeclared hazardous material is discovered.

(b) *Providing and retaining copies of the report.* Each person reporting under this section must—

(1) Submit a written Hazardous Materials Incident Report to the Information Systems Manager, PHH-63, Pipeline and Hazardous Materials Safety Administration, Department of Transportation, Washington, DC 20590-0001, or an electronic Hazardous Material Incident Report to the Information System Manager, DHM-63, Research and Special Programs Administration, Department of Transportation, Washington, DC 20590-0001 at <http://hazmat.dot.gov>;

(2) For an incident involving transportation by aircraft, submit a written or electronic copy of the Hazardous Materials Incident Report to the FAA Security Field Office nearest the location of the incident; and

(3) Retain a written or electronic copy of the Hazardous Materials Incident Report for a period of two years at the reporting person's principal place of business. If the written or electronic Hazardous Materials Incident Report is maintained at other than the reporting person's principal place of business, the report must be made available at the reporting person's principal place of business within 24 hours of a request for the report by an authorized representative or special agent of the Department of Transportation.

(c) *Updating the incident report.* A Hazardous Materials Incident Report must be updated within one year of the date of occurrence of the incident whenever:

(1) A death results from injury caused by a hazardous material;

(2) There was a misidentification of the hazardous material or package information on a prior incident report;

(3) Damage, loss or related cost that was not known when the initial incident report was filed becomes known; or

(4) Damage, loss, or related cost changes by \$25,000 or more, or 10% of the prior total estimate, whichever is greater.

(d) *Exceptions.* Unless a telephone report is required under the provisions of § 171.15 of this part, the requirements of paragraphs (a), (b), and (c) of this section do not apply to the following incidents:

(1) A release of a minimal amount of material from—

(i) A vent, for materials for which venting is authorized;

(ii) The routine operation of a seal, pump, compressor, or valve; or

(iii) Connection or disconnection of loading or unloading lines, provided that the release does not result in property damage.

(2) An unintentional release of hazardous material when:

(i) The material is properly classed as—

(A) ORM-D; or

(B) a Packing Group III material in Class or Division 3, 4, 5, 6.1, 8, or 9;

(ii) Each package has a capacity of less than 20 liters (5.2 gallons) for liquids or less than 30 kg (66 pounds) for solids;

(iii) The total aggregate release is less than 20 liters (5.2 gallons) for liquids or less than 30 kg (66 pounds) for solids; and

(iv) The material is not—

(A) Offered for transportation or transported by aircraft,

(B) A hazardous waste, or

(C) An undeclared hazardous material.

(3) An undeclared hazardous material discovered in an air passenger's checked or carry-on baggage during the airport screening process. (For discrepancy reporting by carriers, see § 175.31 of this subchapter.)

[68 FR 67759, Dec. 3, 2003; 69 FR 30119, May 26, 2004, as amended at 70 FR 56091, Sept. 23, 2005]

#### §§ 171.17–171.18 [Reserved]

#### § 171.19 Approvals or authorizations issued by the Bureau of Explosives.

Effective December 31, 1998, approvals or authorizations issued by the Bureau of Explosives (BOE), other than those issued under part 179 of this subchapter, are no longer valid.

[63 FR 37459, July 10, 1998]

## § 171.20

### § 171.20 Submission of Examination Reports.

(a) When it is required in this subchapter that the issuance of an approval by the Associate Administrator be based on an examination by the Bureau of Explosives (or any other test facility recognized by PHMSA), it is the responsibility of the applicant to submit the results of the examination to the Associate Administrator.

(b) Applications for approval submitted under paragraph (a) of this section, must be submitted to the Associate Administrator for Hazardous Materials Safety, Pipeline and Hazardous Materials Safety Administration, Washington, DC 20590-0001.

(c) Any applicant for an approval aggrieved by an action taken by the Associate Administrator, under this subpart may file an appeal with the Administrator, PHMSA within 30 days of service of notification of a denial.

[Amdt. 171-54, 45 FR 32692, May 19, 1980, as amended by Amdt. 171-66, 47 FR 43064, Sept. 30, 1982; Amdt. 171-109, 55 FR 39978, Oct. 1, 1990; Amdt. 171-111, 56 FR 66162, Dec. 20, 1991; 66 FR 45378, Aug. 28, 2001]

### § 171.21 Assistance in investigations and special studies.

(a) A shipper, carrier, package owner, package manufacturer or certifier, repair facility, or person reporting an incident under the provisions of § 171.16 must:

(1) Make all records and information pertaining to the incident available to an authorized representative or special agent of the Department of Transportation upon request; and

(2) Give an authorized representative or special agent of the Department of Transportation reasonable assistance in the investigation of the incident.

(b) If an authorized representative or special agent of the Department of Transportation makes an inquiry of a person required to complete an incident report in connection with a study of incidents, the person shall:

(1) Respond to the inquiry within 30 days after its receipt or within such other time as the inquiry may specify; and

## 49 CFR Ch. I (10-1-08 Edition)

(2) Provide true and complete answers to any questions included in the inquiry.

[68 FR 67760, Dec. 3, 2003]

### Subpart C—Authorization and Requirements for the Use of International Transport Standards and Regulations

SOURCE: 72 FR 25172, May 3, 2007, unless otherwise noted.

### § 171.22 Authorization and conditions for the use of international standards and regulations.

(a) *Authorized international standards and regulations.* This subpart authorizes, with certain conditions and limitations, the offering for transportation and the transportation in commerce of hazardous materials to, from, or within the United States in accordance with the International Civil Aviation Organization's Technical Instructions for the Safe Transport of Dangerous Goods by Air (ICAO Technical Instructions), the International Maritime Dangerous Goods Code (IMDG Code), Transport Canada's Transportation of Dangerous Goods Regulations (Transport Canada TDG Regulations), and the International Atomic Energy Agency Regulations for the Safe Transport of Radioactive Material (IAEA Regulations) (IBR, see § 171.7).

(b) *Limitations on the use of international standards and regulations.* A hazardous material that is offered for transportation or transported in accordance with the international standards and regulations authorized in paragraph (a) of this section—

(1) Is subject to the requirements of the applicable international standard or regulation and must be offered for transportation or transported in conformance with the applicable standard or regulation; and

(2) Must conform to all applicable requirements of this subpart.

(c) *Materials excepted from regulation under international standards and regulations.* A material designated as a hazardous material under this subchapter, but excepted from or not subject to the international transport standards and regulations authorized in paragraph (a)

of this section (e.g., paragraph 1.16 of the Transport Canada TDG Regulations excepts from regulation quantities of hazardous materials less than or equal to 500 kg gross transported by rail) must be transported in accordance with all applicable requirements of this subchapter.

(d) *Materials not regulated under this subchapter.* Materials not designated as hazardous materials under this subchapter but regulated by an international transport standard or regulation authorized in paragraph (a) of this section may be offered for transportation and transported in the United States in full compliance (i.e., packaged, marked, labeled, classed, described, stowed, segregated, secured) with the applicable international transport standard or regulation.

(e) *Forbidden materials.* No person may offer for transportation or transport a hazardous material that is a forbidden material or package as designated in—

(1) Section 173.21 of this subchapter;

(2) Column (3) of the § 172.101 Table of this subchapter;

(3) Column (9A) of the § 172.101 Table of this subchapter when offered for transportation or transported on passenger aircraft or passenger railcar; or

(4) Column (9B) of the § 172.101 Table of this subchapter when offered for transportation or transported by cargo aircraft.

(f) *Complete information and certification.* (1) Except for shipments into the United States from Canada conforming to § 171.12, each person importing a hazardous material into the United States must provide the forwarding agent at the place of entry into the United States timely and complete written information as to the requirements of this subchapter applicable to the particular shipment.

(2) After May 4, 2009, the shipper, directly or through the forwarding agent at the place of entry, must provide the initial U.S. carrier with the shipper's certification required by § 172.204 of this subchapter, unless the shipment is otherwise excepted from the certification requirement. Except for shipments for which the certification requirement does not apply, a carrier may not accept a hazardous material

for transportation unless provided a shipper's certification.

(3) All shipping paper information and package markings required in accordance with this subchapter must be in English. The use of shipping papers and a package marked with both English and a language other than English, in order to dually comply with this subchapter and the regulations of a foreign entity, is permitted under this subchapter.

(4) Each person who provides for transportation or receives for transportation (see §§ 174.24, 175.30, 176.24 and 177.817 of this subchapter) a shipping paper must retain a copy of the shipping paper or an electronic image thereof that is accessible at or through its principal place of business in accordance with § 172.201(e) of this part.

(g) *Additional requirements for the use of international standards and regulations.* All shipments offered for transportation or transported in the United States in accordance with this subpart must conform to the following requirements of this subchapter, as applicable:

(1) The emergency response information requirements in subpart G of part 172 of this subchapter;

(2) The training requirements in subpart H of part 172 of this subchapter, including function-specific training in the use of the international transport standards and regulations authorized in paragraph (a) of this section, as applicable;

(3) The security requirements in subpart I of part 172 of this subchapter;

(4) The incident reporting requirements in §§ 171.15 and 171.16 of this part for incidents occurring within the jurisdiction of the United States including on board vessels in the navigable waters of the United States and aboard aircraft of United States registry anywhere in air commerce;

(5) For export shipments, the general packaging requirements in §§ 173.24 and 173.24a of this subchapter;

(6) For export shipments, the requirements for the reuse, reconditioning, and remanufacture of packagings in § 173.28 of this subchapter; and

(7) The registration requirements in subpart G of part 107 of this chapter.

[72 FR 25172, May 3, 2007, as amended at 72 FR 55091 Sept. 28, 2007]

**§ 171.23 Requirements for specific materials and packagings transported under the ICAO Technical Instructions, IMDG Code, Transport Canada TDG Regulations, or the IAEA Regulations.**

All shipments offered for transportation or transported in the United States under the ICAO Technical Instructions, IMDG Code, Transport Canada TDG Regulations, or the IAEA Regulations (IBR, see § 171.7) must conform to the requirements of this section, as applicable.

(a) *Conditions and requirements for cylinders*—(1) Except as provided in this paragraph, a filled cylinder (pressure receptacle) manufactured to other than a DOT specification or a UN standard in accordance with part 178 of this subchapter, or a DOT exemption or special permit cylinder or a cylinder used as a fire extinguisher in conformance with § 173.309(a) of this subchapter, may not be transported to, from, or within the United States.

(2) Cylinders (including UN pressure receptacles) transported to, from, or within the United States must conform to the applicable requirements of this subchapter. Unless otherwise excepted in this subchapter, a cylinder must not be transported unless—

(i) The cylinder is manufactured, inspected and tested in accordance with a DOT specification or a UN standard prescribed in part 178 of this subchapter, except that cylinders not conforming to these requirements must meet the requirements in paragraphs (a)(3), (a)(4) or (a)(5) of this section;

(ii) The cylinder is equipped with a pressure relief device in accordance with § 173.301(f) of this subchapter and conforms to the applicable requirements in part 173 of this subchapter for the hazardous material involved;

(iii) The openings on an aluminum cylinder in oxygen service conform to the requirements of this paragraph, except when the cylinder is used for aircraft parts or used aboard an aircraft in accordance with the applicable airworthiness requirements and operating regulations. An aluminum DOT specification cylinder must have an opening configured with straight (parallel) threads. A UN pressure receptacle may have straight (parallel) or tapered

threads provided the UN pressure receptacle is marked with the thread type, e.g. “17E, 25E, 18P, or 25P” and fitted with the properly marked valve; and

(iv) A UN pressure receptacle is marked with “USA” as a country of approval in conformance with §§ 178.69 and 178.70 of this subchapter.

(3) Importation of cylinders for discharge within a single port area: A cylinder manufactured to other than a DOT specification or UN standard in accordance with part 178 of this subchapter and certified as being in conformance with the transportation regulations of another country may be authorized, upon written request to and approval by the Associate Administrator, for transportation within a single port area, provided—

(i) The cylinder is transported in a closed freight container;

(ii) The cylinder is certified by the importer to provide a level of safety at least equivalent to that required by the regulations in this subchapter for a comparable DOT specification or UN cylinder; and

(iii) The cylinder is not refilled for export unless in compliance with paragraph (a)(4) of this section.

(4) Filling of cylinders for export or for use on board a vessel: A cylinder not manufactured, inspected, tested and marked in accordance with part 178 of this subchapter, or a cylinder manufactured to other than a UN standard, DOT specification, exemption or special permit, may be filled with a gas in the United States and offered for transportation and transported for export or alternatively, for use on board a vessel, if the following conditions are met:

(i) The cylinder has been requalified and marked with the month and year of requalification in accordance with subpart C of part 180 of this subchapter, or has been requalified as authorized by the Associate Administrator;

(ii) In addition to other requirements of this subchapter, the maximum filling density, service pressure, and pressure relief device for each cylinder conform to the requirements of this part for the gas involved; and

(iii) The bill of lading or other shipping paper identifies the cylinder and includes the following certification:

“This cylinder has (These cylinders have) been qualified, as required, and filled in accordance with the DOT requirements for export.”

(5) Cylinders not equipped with pressure relief devices: A DOT specification or a UN cylinder manufactured, inspected, tested and marked in accordance with part 178 of this subchapter and otherwise conforms to the requirements of part 173 for the gas involved, except that the cylinder is not equipped with a pressure relief device may be filled with a gas and offered for transportation and transported for export if the following conditions are met:

(i) Each DOT specification cylinder or UN pressure receptacle must be plainly and durably marked “For Export Only”;

(ii) The shipping paper must carry the following certification: “This cylinder has (These cylinders have) been retested and refilled in accordance with the DOT requirements for export.”; and

(iii) The emergency response information provided with the shipment and available from the emergency response telephone contact person must indicate that the pressure receptacles are not fitted with pressure relief devices and provide appropriate guidance for exposure to fire.

(b) *Conditions and requirements specific to certain materials*—(1) *Aerosols*. Except for a limited quantity of a compressed gas in a container of not more than 4 fluid ounces capacity meeting the requirements in §173.306(a)(1) of this subchapter, the proper shipping name “Aerosol,” UN1950, may be used only for a non-refillable receptacle containing a gas compressed, liquefied, or dissolved under pressure the sole purpose of which is to expel a nonpoisonous (other than Division 6.1, Packing Group III material) liquid, paste, or powder and fitted with a self-closing release device (see §171.8). In addition, an aerosol must be in a metal packaging when the packaging exceeds 7.22 cubic inches.

(2) *Air bag inflator, air bag module and seat-belt pretensioner*. For each approved air bag inflator, air bag module and seat-belt pretensioner, the shipping paper description must conform to the

requirements in §173.166(c) of this subchapter.

(i) The EX number or product code must be included in association with the basic shipping description. When a product code is used, it must be traceable to the specific EX number assigned to the inflator, module or seat-belt pretensioner by the Associate Administrator. The EX number or product code is not required to be marked on the outside package.

(ii) The proper shipping name “Articles, pyrotechnic *for technical purposes*, UN0431” must be used for all air bag inflators, air bag modules, and seat-belt pretensioners meeting the criteria for a Division 1.4G material.

(3) *Chemical oxygen generators*. Chemical oxygen generators must be approved, classed, described, packaged, and transported in accordance with the requirements of this subchapter.

(4) *Class 1 (explosive) materials*. Prior to being transported, Class 1 (explosive) materials must be approved by the Associate Administrator in accordance with §173.56 of this subchapter. Each package containing a Class 1 (explosive) material must conform to the marking requirements in §172.320 of this subchapter.

(5) *Hazardous substances*. A material meeting the definition of a hazardous substance as defined in §171.8, must conform to the shipping paper requirements in §172.203(c) of this subchapter and the marking requirements in §172.324 of this subchapter:

(i) The proper shipping name must identify the hazardous substance by name, or the name of the substance must be entered in parentheses in association with the basic description and marked on the package in association with the proper shipping name. If the hazardous substance meets the definition for a hazardous waste, the waste code (for example, D001), may be used to identify the hazardous substance;

(ii) The shipping paper and the package markings must identify at least two hazardous substances with the lowest reportable quantities (RQs) when the material contains two or more hazardous substances; and

(iii) The letters “RQ” must be entered on the shipping paper either before or after the basic description, and

marked on the package in association with the proper shipping name for each hazardous substance listed.

(6) *Hazardous wastes.* A material meeting the definition of a hazardous waste (see § 171.8) must conform to the following:

(i) The shipping paper and the package markings must include the word “Waste” immediately preceding the proper shipping name;

(ii) The shipping paper must be retained by the shipper and by each carrier for three years after the material is accepted by the initial carrier (see § 172.205(e)(5)); and

(iii) A hazardous waste manifest must be completed in accordance with § 172.205 of this subchapter.

(7) *Marine pollutants.* Except for marine pollutants (see § 171.8) transported in accordance with the IMDG Code, marine pollutants transported in bulk packages must meet the shipping paper requirements in § 172.203(l) of this subchapter and the package marking requirements in § 172.322 of this subchapter.

(8) *Organic peroxides.* Organic peroxides not identified by technical name in the Organic Peroxide Table in § 173.225(b) of this subchapter must be approved by the Associate Administrator in accordance with § 173.128(d) of this subchapter.

(9) *Poisonous materials, Division 6.1.* Division 6.1 hazardous materials transported as limited quantities are not excepted from labeling (see § 173.153(b)).

(10) *Poisonous by inhalation materials.* A material poisonous by inhalation (see § 171.8) must conform to the following requirements:

(i) The words “Poison-Inhalation Hazard” or “Toxic-Inhalation Hazard” and the words “Zone A,” “Zone B,” “Zone C,” or “Zone D” for gases, or “Zone A” or “Zone B” for liquids, as appropriate, must be entered on the shipping paper immediately following the basic shipping description. The word “Poison” or “Toxic” or the phrase “Poison-Inhalation Hazard” or “Toxic-Inhalation Hazard” need not be repeated if it otherwise appears in the shipping description;

(ii) The material must be packaged in accordance with the requirements of this subchapter;

(iii) The package must be marked in accordance with § 172.313 of this subchapter; and

(iv) Except as provided in subparagraph (B) of this paragraph (b)(10)(iv) and for a package containing anhydrous ammonia prepared in accordance with the Transport Canada TDG Regulations, the package must be labeled or placarded with POISON INHALATION HAZARD or POISON GAS, as appropriate, in accordance with Subparts E and F of part 172 of this subchapter.

(A) For a package transported in accordance with the IMDG Code in a closed transport vehicle or freight container, a label or placard conforming to the IMDG Code specifications for a “Class 2.3” or “Class 6.1” label or placard may be substituted for the POISON GAS or POISON INHALATION HAZARD label or placard, as appropriate. The transport vehicle or freight container must be marked with the identification numbers for the hazardous material, regardless of the total quantity contained in the transport vehicle or freight container, in the manner specified in § 172.313(c) of this subchapter and placarded as required by subpart F of part 172 of this subchapter.

(B) For a package transported in accordance with the Transport Canada TDG Regulations in a closed transport vehicle or freight container, a label or placard conforming to the TDG Regulations specifications for a “Class 2.3” or “Class 6.1” label or placard may be substituted for the POISON GAS or POISON INHALATION HAZARD label or placard, as appropriate. The transport vehicle or freight container must be marked with the identification numbers for the hazardous material, regardless of the total quantity contained in the transport vehicle or freight container, in the manner specified in § 172.313(c) of this subchapter and placarded as required by subpart F of part 172 of this subchapter. While in transportation in the United States, the transport vehicle or freight container may also be placarded in accordance with the appropriate Transport Canada TDG Regulations in addition to being placarded with the POISON GAS or POISON INHALATION HAZARD placards.

(11) *Class 7 (radioactive) materials.* (i) Highway route controlled quantities (see § 173.403 of this subchapter) must be shipped in accordance with §§ 172.203(d)(4) and (d)(10); 172.507, and 173.22(c) of this subchapter;

(ii) For fissile materials and Type B, Type B(U), and Type B(M) packagings, the competent authority certification and any necessary revalidation must be obtained from the appropriate competent authorities as specified in §§ 173.471, 173.472, and 173.473 of this subchapter, and all requirements of the certificates and revalidations must be met;

(iii) Type A package contents are limited in accordance with § 173.431 of this subchapter;

(iv) The country of origin for the shipment must have adopted the edition of TS-R-1 of the IAEA Regulations referenced in § 171.7;

(v) The shipment must conform to the requirements of § 173.448, when applicable;

(vi) The definition for “radioactive material” in § 173.403 of this subchapter must be applied to radioactive materials transported under the provisions of this subpart;

(vii) Except for limited quantities, the shipment must conform to the requirements of § 172.204(c)(4) of this subchapter; and

(viii) Excepted packages of radioactive material, instruments or articles, or articles containing natural uranium or thorium must conform to the requirements of §§ 173.421, 173.424, or 173.426 of this subchapter, as appropriate.

(12) *Self-reactive materials.* Self-reactive materials not identified by technical name in the Self-reactive Materials Table in § 173.224(b) of this subchapter must be approved by the Associate Administrator in accordance with § 173.124(a)(2)(iii) of this subchapter.

[72 FR 25172, May 3, 2007, as amended at 72 FR 55684, Oct. 1, 2007; 73 FR 57004, Oct. 1, 2008]

**§ 171.24 Additional requirements for the use of the ICAO Technical Instructions.**

(a) A hazardous material that is offered for transportation or transported within the United States by aircraft, and by motor vehicle or rail either be-

fore or after being transported by aircraft in accordance with the ICAO Technical Instructions (IBR, see § 171.7), as authorized in paragraph (a) of § 171.22, must conform to the requirements in § 171.22, as applicable, and this section.

(b) Any person who offers for transportation or transports a hazardous material in accordance with the ICAO Technical Instructions must comply with the following additional conditions and requirements:

(1) All applicable requirements in parts 171 and 175 of this subchapter (also see 14 CFR 121.135, 121.401, 121.433a, 135.323, 135.327 and 135.333);

(2) The quantity limits prescribed in the ICAO Technical Instructions for transportation by passenger-carrying or cargo aircraft, as applicable;

(3) The conditions or requirements of a United States variation, when specified in the ICAO Technical Instructions.

(c) *Highway transportation.* For transportation by highway prior to or after transportation by aircraft, a shipment must conform to the applicable requirements of part 177 of this subchapter, and the motor vehicle must be placarded in accordance with subpart F of part 172.

(d) *Conditions and requirements specific to certain materials.* Hazardous materials offered for transportation or transported in accordance with the ICAO Technical Instructions must conform to the following specific conditions and requirements, as applicable:

(1) *Batteries—(i) Nonspillable wet electric storage batteries.* Nonspillable wet electric storage batteries are not subject to the requirements of this subchapter provided—

(A) The battery meets the conditions specified in Special Provision 67 of the ICAO Technical Instructions;

(B) The battery, its outer packaging, and any overpack are plainly and durably marked “NONSPILLABLE” or “NONSPILLABLE BATTERY”; and

(C) The batteries or battery assemblies are offered for transportation or transported in a manner that prevents short circuiting or forced discharge, including, but not limited to, protection of exposed terminals.



(ii) *Primary lithium batteries and cells.* Primary lithium batteries and cells are forbidden for transportation aboard passenger-carrying aircraft. Equipment containing or packed with primary lithium batteries or cells are forbidden for transport aboard passenger-carrying aircraft except as provided in § 172.102, Special Provision A101 of this subchapter. When transported aboard cargo-only aircraft, packages containing primary lithium batteries and cells transported in accordance with Special Provision A45 of the ICAO Technical Instructions must be marked “PRIMARY LITHIUM BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT” or “LITHIUM METAL BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT.” This marking is not required on packages that contain 5 kg (11 pounds) net weight or less of primary lithium batteries or cells that are contained in or packed with equipment.

(iii) *Prototype lithium batteries and cells.* Prototype lithium batteries and cells are forbidden for transport aboard passenger aircraft and must be approved by the Associate Administrator prior to transportation aboard cargo aircraft, in accordance with the requirements of Special Provision A55 in § 172.102 of this subchapter.

(2) A package containing Oxygen, compressed, or any of the following oxidizing gases must be packaged as required by Parts 173 and 178 of this subchapter: carbon dioxide and oxygen mixtures, compressed; compressed gas, oxidizing, n.o.s.; liquefied gas, oxidizing, n.o.s.; nitrogen trifluoride; and nitrous oxide.

[72 FR 25172, May 3, 2007, as amended at 72 FR 44847, Aug. 9, 2007; 72 FR 55097, Sept. 28, 2007]

**§ 171.25 Additional requirements for the use of the IMDG Code.**

(a) A hazardous material may be offered for transportation or transported to, from or within the United States by vessel, and by motor carrier and rail in accordance with the IMDG Code (IBR, see § 171.7), as authorized in § 171.22, provided all or part of the movement is by vessel. Such shipments must conform

to the requirements in § 171.22, as applicable, and this section.

(b) Any person who offers for transportation or transports a hazardous material in accordance with the IMDG Code must conform to the following additional conditions and requirements:

(1) Unless otherwise excepted, a shipment must conform to the requirements in part 176 of this subchapter. For transportation by rail or highway prior to or subsequent to transportation by vessel, a shipment must conform to the applicable requirements of parts 174 and 177 respectively, of this subchapter, and the motor vehicle or rail car must be placarded in accordance with subpart F of part 172 of this subchapter. When a hazardous material regulated by this subchapter for transportation by highway is transported by motor vehicle on a public highway or by rail under the provisions of subpart C of part 171, the segregation requirements of Part 7, Chapter 7.2 of the IMDG Code are authorized.

(2) For transportation by vessel, the stowage and segregation requirements in Part 7 of the IMDG Code may be substituted for the stowage and segregation requirements in part 176 of this subchapter.

(3) Packages containing primary lithium batteries and cells that are transported in accordance with Special Provision 188 of the IMDG Code must be marked “PRIMARY LITHIUM BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT” or “LITHIUM METAL BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT.” This marking is not required on packages that contain 5 kg (11 pounds) net weight or less of primary lithium batteries and cells that are contained in or packed with equipment.

(c) *Conditions and requirements for bulk packagings.* Except for IBCs and UN portable tanks used for the transportation of liquids or solids, bulk packagings must conform to the requirements of this subchapter. Additionally, the following requirements apply:

(1) UN portable tanks must conform to the requirements in Special Provisions TP37, TP38, TP44 and TP45 when

applicable, and any applicable bulk special provisions assigned to the hazardous material in the Hazardous Materials Table in §172.101 of this subchapter;

(2) IMO Type 5 portable tanks must conform to DOT Specification 51 or UN portable tank requirements, unless specifically authorized in this subchapter or approved by the Associate Administrator;

(3) Except as specified in this subpart, for a material poisonous (toxic) by inhalation, the T Codes specified in Column 13 of the Dangerous Goods List in the IMDG Code may be applied to the transportation of those materials in IM, IMO and DOT Specification 51 portable tanks, when these portable tanks are authorized in accordance with the requirements of this subchapter; and

(4) No person may offer an IM or UN portable tank containing liquid hazardous materials of Class 3, PG I or II, or PG III with a flash point less than 100 °F (38 °C); Division 5.1, PG I or II; or Division 6.1, PG I or II, for unloading while it remains on a transport vehicle with the motive power unit attached, unless it conforms to the requirements in §177.834(o) of this subchapter.

(d) *Use of IMDG Code in port areas.* (1) Except for Division 1.1, 1.2, and Class 7 materials, a hazardous material being imported into or exported from the United States or passing through the United States in the course of being shipped between locations outside the United States may be offered and accepted for transportation and transported by motor vehicle within a single port area, including contiguous harbors, when packaged, marked, classed, labeled, stowed and segregated in accordance with the IMDG Code, offered and accepted in accordance with the requirements of subparts C and F of part 172 of this subchapter pertaining to shipping papers and placarding, and otherwise conforms to the applicable requirements of part 176 of this subchapter.

(2) The requirement in §172.201(d) of this subchapter for an emergency telephone number does not apply to shipments made in accordance with the IMDG Code if the hazardous material is not offloaded from the vessel, or is

offloaded between ocean vessels at a U.S. port facility without being transported by public highway.

[72 FR 25172, May 3, 2007, as amended at 72 FR 44847, Aug. 9, 2007; 73 FR 57004, Oct. 1, 2008]

#### **§171.26 Additional requirements for the use of the IAEA Regulations.**

A Class 7 (radioactive) material being imported into or exported from the United States or passing through the United States in the course of being shipped between places outside the United States may be offered for transportation or transported in accordance with the IAEA Regulations (IBR, see §171.7) as authorized in paragraph (a) of §171.22, provided the requirements in §171.22, as applicable, are met.

### **PART 172—HAZARDOUS MATERIALS TABLE, SPECIAL PROVISIONS, HAZARDOUS MATERIALS COMMUNICATIONS, EMERGENCY RESPONSE INFORMATION, TRAINING REQUIREMENTS, AND SECURITY PLANS**

#### **Subpart A—General**

Sec.

172.1 Purpose and scope.

172.3 Applicability.

#### **Subpart B—Table of Hazardous Materials and Special Provisions**

172.101 Purpose and use of hazardous materials table.

172.102 Special provisions.

#### **Subpart C—Shipping Papers**

172.200 Applicability.

172.201 Preparation and retention of shipping papers.

172.202 Description of hazardous material on shipping papers.

172.203 Additional description requirements.

172.204 Shipper's certification.

172.205 Hazardous waste manifest.

#### **Subpart D—Marking**

172.300 Applicability.

172.301 General marking requirements for non-bulk packagings.

172.302 General marking requirements for bulk packagings.

172.303 Prohibited marking.

172.304 Marking requirements.

172.306 [Reserved]

**Pt. 172****49 CFR Ch. I (10–1–08 Edition)**

- 172.308 Authorized abbreviations.
- 172.310 Class 7 (radioactive) materials.
- 172.312 Liquid hazardous materials in non-bulk packagings.
- 172.313 Poisonous hazardous materials.
- 172.315 Packages containing limited quantities.
- 172.316 Packagings containing materials classed as ORM-D.
- 172.317 KEEP AWAY FROM HEAT handling mark.
- 172.320 Explosive hazardous materials.
- 172.322 Marine pollutants.
- 172.323 Infectious substances.
- 172.324 Hazardous substances in non-bulk packagings.
- 172.325 Elevated temperature materials.
- 172.326 Portable tanks.
- 172.328 Cargo tanks.
- 172.330 Tank cars and multi-unit tank car tanks.
- 172.331 Bulk packagings other than portable tanks, cargo tanks, tank cars and multi-unit tank car tanks.
- 172.332 Identification number markings.
- 172.334 Identification numbers; prohibited display.
- 172.336 Identification numbers; special provisions.
- 172.338 Replacement of identification numbers.

**Subpart E—Labeling**

- 172.400 General labeling requirements.
- 172.400a Exceptions from labeling.
- 172.401 Prohibited labeling.
- 172.402 Additional labeling requirements.
- 172.403 Class 7 (radioactive) material.
- 172.404 Labels for mixed and consolidated packaging.
- 172.405 Authorized label modifications.
- 172.406 Placement of labels.
- 172.407 Label specifications.
- 172.411 EXPLOSIVE 1.1, 1.2, 1.3, 1.4, 1.5 and 1.6 labels, and EXPLOSIVE Subsidiary label.
- 172.415 NON-FLAMMABLE GAS label.
- 172.416 POISON GAS label.
- 172.417 FLAMMABLE GAS label.
- 172.419 FLAMMABLE LIQUID label.
- 172.420 FLAMMABLE SOLID label.
- 172.422 SPONTANEOUSLY COMBUSTIBLE label.
- 172.423 DANGEROUS WHEN WET label.
- 172.426 OXIDIZER label.
- 172.427 ORGANIC PEROXIDE label.
- 172.429 POISON INHALATION HAZARD label.
- 172.430 POISON label.
- 172.431 [Reserved]
- 172.432 INFECTIOUS SUBSTANCE label.
- 172.436 RADIOACTIVE WHITE-I label.
- 172.438 RADIOACTIVE YELLOW-II label.
- 172.440 RADIOACTIVE YELLOW-III label.
- 172.441 FISSILE label.
- 172.442 CORROSIVE label.

- 172.444 [Reserved]
- 172.446 CLASS 9 label.
- 172.448 CARGO AIRCRAFT ONLY label.
- 172.450 EMPTY label.

**Subpart F—Placarding**

- 172.500 Applicability of placarding requirements.
- 172.502 Prohibited and permissive placarding.
- 172.503 Identification number display on placards.
- 172.504 General placarding requirements.
- 172.505 Placarding for subsidiary hazards.
- 172.506 Providing and affixing placards: Highway.
- 172.507 Special placarding provisions: Highway.
- 172.508 Placarding and affixing placarding: Rail.
- 172.510 Special placarding provisions: Rail.
- 172.512 Freight containers and aircraft unit load devices.
- 172.514 Bulk packagings.
- 172.516 Visibility and display of placards.
- 172.519 General specifications for placards.
- 172.521 DANGEROUS placard.
- 172.522 EXPLOSIVES 1.1, EXPLOSIVES 1.2 and EXPLOSIVES 1.3 placards.
- 172.523 EXPLOSIVES 1.4 placard.
- 172.524 EXPLOSIVES 1.5 placard.
- 172.525 EXPLOSIVES 1.6 placard.
- 172.526 [Reserved]
- 172.527 Background requirements for certain placards.
- 172.528 NON-FLAMMABLE GAS placard.
- 172.530 OXYGEN placard.
- 172.532 FLAMMABLE GAS placard.
- 172.536 [Reserved]
- 172.540 POISON GAS placard.
- 172.542 FLAMMABLE placard.
- 172.544 COMBUSTIBLE placard.
- 172.546 FLAMMABLE SOLID placard.
- 172.547 SPONTANEOUSLY COMBUSTIBLE placard.
- 172.548 DANGEROUS WHEN WET placard.
- 172.550 OXIDIZER placard.
- 172.552 ORGANIC PEROXIDE placard.
- 172.553 [Reserved]
- 172.554 POISON placard.
- 172.555 POISON INHALATION HAZARD placard.
- 172.556 RADIOACTIVE placard.
- 172.558 CORROSIVE placard.
- 172.560 CLASS 9 placard.

**Subpart G—Emergency Response Information**

- 172.600 Applicability and general requirements.
- 172.602 Emergency response information.
- 172.604 Emergency response telephone number.
- 172.606 Carrier information contact.

**Subpart H—Training**

- 172.700 Purpose and scope.
- 172.701 Federal-State relationship.
- 172.702 Applicability and responsibility for training and testing.
- 172.704 Training requirements.

**Subpart I—Safety and Security Plans**

- 172.800 Purpose and applicability.
- 172.802 Components of a security plan.
- 172.804 Relationship to other Federal requirements.
- 172.820 Additional planning requirements for transportation by rail.
- 172.822 Limitation on actions by states, local governments, and Indian tribes.

APPENDIX A TO PART 172—OFFICE OF HAZARDOUS MATERIALS TRANSPORTATION COLOR TOLERANCE CHARTS AND TABLES

APPENDIX B TO PART 172—TREFOIL SYMBOL

APPENDIX C TO PART 172—DIMENSIONAL SPECIFICATIONS FOR RECOMMENDED PLACARD HOLDER

APPENDIX D TO PART 172—RAIL RISK ANALYSIS FACTORS

AUTHORITY: 49 U.S.C. 5101–5128, 44701; 49 CFR 1.53.

SOURCE: Amdt. 172–29, 41 FR 15996, Apr. 15, 1976, unless otherwise noted.

**Subpart A—General****§ 172.1 Purpose and scope.**

This part lists and classifies those materials which the Department has designated as hazardous materials for purposes of transportation and prescribes the requirements for shipping papers, package marking, labeling, and transport vehicle placarding applicable to the shipment and transportation of those hazardous materials.

[Amdt. 172–29, 41 FR 15997, Apr. 15, 1976, as amended by 66 FR 45379, Aug. 28, 2001]

**§ 172.3 Applicability.**

(a) This part applies to—

- (1) Each person who offers a hazardous material for transportation, and
- (2) Each carrier by air, highway, rail, or water who transports a hazardous material.

(b) When a person, other than one of those provided for in paragraph (a) of this section, performs a packaging labeling or marking function required by

this part, that person shall perform the function in accordance with this part.

[Amdt. 172–29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172–32, 41 FR 38179, Sept. 9, 1976]

**Subpart B—Table of Hazardous Materials and Special Provisions****§ 172.101 Purpose and use of hazardous materials table.**

(a) The Hazardous Materials Table (Table) in this section designates the materials listed therein as hazardous materials for the purpose of transportation of those materials. For each listed material, the Table identifies the hazard class or specifies that the material is forbidden in transportation, and gives the proper shipping name or directs the user to the preferred proper shipping name. In addition, the Table specifies or references requirements in this subchapter pertaining to labeling, packaging, quantity limits aboard aircraft and stowage of hazardous materials aboard vessels.

(b) *Column 1: Symbols.* Column 1 of the Table contains six symbols (“+”, “A”, “D”, “G”, “I” and “W”) as follows:

(1) The plus (+) sign fixes the proper shipping name, hazard class and packing group for that entry without regard to whether the material meets the definition of that class, packing group or any other hazard class definition. When the plus sign is assigned to a proper shipping name in Column (1) of the § 172.101 Table, it means that the material is known to pose a risk to humans. When a plus sign is assigned to mixtures or solutions containing a material where the hazard to humans is significantly different from that of the pure material or where no hazard to humans is posed, the material may be described using an alternative shipping name that represents the hazards posed by the material. An appropriate alternate proper shipping name and hazard class may be authorized by the Associate Administrator.

(2) The letter “A” denotes a material that is subject to the requirements of this subchapter only when offered or intended for transportation by aircraft, unless the material is a hazardous substance or a hazardous waste. A shipping description entry preceded by an

“A” may be used to describe a material for other modes of transportation provided all applicable requirements for the entry are met.

(3) The letter “D” identifies proper shipping names which are appropriate for describing materials for domestic transportation but may be inappropriate for international transportation under the provisions of international regulations (e.g., IMO, ICAO). An alternate proper shipping name may be selected when either domestic or international transportation is involved.

(4) The letter “G” identifies proper shipping names for which one or more technical names of the hazardous material must be entered in parentheses, in association with the basic description. (See § 172.203(k).)

(5) The letter “I” identifies proper shipping names which are appropriate for describing materials in international transportation. An alternate proper shipping name may be selected when only domestic transportation is involved.

(6) The letter “W” denotes a material that is subject to the requirements of this subchapter only when offered or intended for transportation by vessel, unless the material is a hazardous substance or a hazardous waste. A shipping description entry preceded by a “W” may be used to describe a material for other modes of transportation provided all applicable requirements for the entry are met.

(c) *Column 2: Hazardous materials descriptions and proper shipping names.* Column 2 lists the hazardous materials descriptions and proper shipping names of materials designated as hazardous materials. Modification of a proper shipping name may otherwise be required or authorized by this section. Proper shipping names are limited to those shown in Roman type (not italics).

(1) Proper shipping names may be used in the singular or plural and in either capital or lower case letters. Words may be alternatively spelled in the same manner as they appear in the ICAO Technical Instructions or the IMDG Code. For example “aluminum” may be spelled “aluminium” and “sulphur” may be spelled “sulfur”. However, the word “inflammable” may not

be used in place of the word “flammable”.

(2) Punctuation marks and words in italics are not part of the proper shipping name, but may be used in addition to the proper shipping name. The word “or” in italics indicates that terms in the sequence may be used as the proper shipping name, as appropriate.

(3) The word “poison” or “poisonous” may be used interchangeably with the word “toxic” when only domestic transportation is involved. The abbreviation “n.o.i.” or “n.o.i.b.n.” may be used interchangeably with “n.o.s.”.

(4) Except for hazardous wastes, when qualifying words are used as part of the proper shipping name, their sequence in the package markings and shipping paper description is optional. However, the entry in the Table reflects the preferred sequence.

(5) When one entry references another entry by use of the word “see”, if both names are in Roman type, either name may be used as the proper shipping name (e.g., Ethyl alcohol, *see* Ethanol).

(6) When a proper shipping name includes a concentration range as part of the shipping description, the actual concentration, if it is within the range stated, may be used in place of the concentration range. For example, an aqueous solution of hydrogen peroxide containing 30 percent peroxide may be described as “Hydrogen peroxide, aqueous solution with *not less than 20 percent but not more than 40 percent hydrogen peroxide*” or “Hydrogen peroxide, aqueous solution with *30 percent hydrogen peroxide*”.

(7) Use of the prefix “mono” is optional in any shipping name, when appropriate. Thus, Iodine monochloride may be used interchangeably with Iodine chloride. In “Glycerol alpha-monochlorohydrin” the term “mono” is considered a prefix to the term “chlorohydrin” and may be deleted.

(8) Use of the word “liquid” or “solid”. The word “liquid” or “solid” may be added to a proper shipping name when a hazardous material specifically listed by name may, due to differing physical states, be a liquid or solid. When the packaging specified in Column 8 is inappropriate for the physical state of the material, the table

provided in paragraph (i)(4) of this section should be used to determine the appropriate packaging section.

(9) *Hazardous wastes.* If the word “waste” is not included in the hazardous material description in Column 2 of the Table, the proper shipping name for a hazardous waste (as defined in § 171.8 of this subchapter), shall include the word “Waste” preceding the proper shipping name of the material. For example: Waste acetone.

(10) *Mixtures and solutions.* (i) A mixture or solution not identified specifically by name, comprised of a hazardous material identified in the Table by technical name and non-hazardous material, shall be described using the proper shipping name of the hazardous material and the qualifying word “mixture” or “solution”, as appropriate, unless—

(A) Except as provided in § 172.101(i)(4) the packaging specified in Column 8 is inappropriate to the physical state of the material;

(B) The shipping description indicates that the proper shipping name applies only to the pure or technically pure hazardous material;

(C) The hazard class, packing group, or subsidiary hazard of the mixture or solution is different from that specified for the entry;

(D) There is a significant change in the measures to be taken in emergencies;

(E) The material is identified by special provision in Column 7 of the § 172.101 Table as a material poisonous by inhalation; however, it no longer meets the definition of poisonous by inhalation or it falls within a different hazard zone than that specified in the special provision; or

(F) The material can be appropriately described by a shipping name that describes its intended application, such as “Coating solution”, “Extracts, flavoring” or “Compound, cleaning liquid”.

(ii) If one or more of the conditions specified in paragraph (c)(10)(i) of this section is satisfied, then a proper shipping name shall be selected as prescribed in paragraph (c)(12)(ii) of this section.

(iii) A mixture or solution not identified in the Table specifically by name,

comprised of two or more hazardous materials in the same hazard class, shall be described using an appropriate shipping description (e.g., “Flammable liquid, n.o.s.”). The name that most appropriately describes the material shall be used; e.g., an alcohol not listed by its technical name in the Table shall be described as “Alcohol, n.o.s.” rather than “Flammable liquid, n.o.s.”. Some mixtures may be more appropriately described according to their application, such as “Coating solution” or “Extracts, flavoring liquid” rather than by an n.o.s. entry. Under the provisions of subparts C and D of this part, the technical names of at least two components most predominately contributing to the hazards of the mixture or solution may be required in association with the proper shipping name.

(11) Except for a material subject to or prohibited by § 173.21, 173.54, 173.56(d), 173.56(e), 173.224(c) or 173.225(b) of this subchapter, a material that is considered to be a hazardous waste or a sample of a material for which the hazard class is uncertain and must be determined by testing may be assigned a tentative proper shipping name, hazard class, identification number and packing group, if applicable, based on the shipper’s tentative determination according to:

(i) Defining criteria in this subchapter;

(ii) The hazard precedence prescribed in § 173.2a of this subchapter;

(iii) The shipper’s knowledge of the material;

(iv) In addition to paragraphs (c)(11)(i) through (iii) of this section, for a sample of a material other than a waste, the following must be met:

(A) Except when the word “Sample” already appears in the proper shipping name, the word “Sample” must appear as part of the proper shipping name or in association with the basic description on the shipping paper.

(B) When the proper shipping description for a sample is assigned a “G” in Column (1) of the § 172.101 Table, and the primary constituent(s) for which the tentative classification is based are not known, the provisions requiring a technical name for the constituent(s) do not apply; and

(C) A sample must be transported in a combination packaging that conforms to the requirements of this subchapter that are applicable to the tentative packing group assigned, and may not exceed a net mass of 2.5 kg (5.5 pounds) per package.

NOTE TO PARAGRAPH (c)(11): For the transportation of samples of self-reactive materials, organic peroxides, explosives or lighters, see §§ 173.224(c)(3), 173.225(c)(2), 173.56(d) or 173.308(b)(2) of this subchapter, respectively.

(12) Except when the proper shipping name in the Table is preceded by a plus (+)—

(i) If it is specifically determined that a material meets the definition of a hazard class, packing group or hazard zone, other than the class, packing group or hazard zone shown in association with the proper shipping name, or does not meet the defining criteria for a subsidiary hazard shown in Column 6 of the Table, the material shall be described by an appropriate proper shipping name listed in association with the correct hazard class, packing group, hazard zone, or subsidiary hazard for the material.

(ii) *Generic or n.o.s. descriptions.* If an appropriate technical name is not shown in the Table, selection of a proper shipping name shall be made from the generic or n.o.s. descriptions corresponding to the specific hazard class, packing group, hazard zone, or subsidiary hazard, if any, for the material. The name that most appropriately describes the material shall be used; e.g., an alcohol not listed by its technical name in the Table shall be described as “Alcohol, n.o.s.” rather than “Flammable liquid, n.o.s.”. Some mixtures may be more appropriately described according to their application, such as “Coating solution” or “Extracts, flavoring, liquid”, rather than by an n.o.s. entry, such as “Flammable liquid, n.o.s.” It should be noted, however, that an n.o.s. description as a proper shipping name may not provide sufficient information for shipping papers and package markings. Under the provisions of subparts C and D of this part, the technical name of one or more constituents which makes the product a hazardous material may be required in

association with the proper shipping name.

(iii) *Multiple hazard materials.* If a material meets the definition of more than one hazard class, and is not identified in the Table specifically by name (e.g., acetyl chloride), the hazard class of the material shall be determined by using the precedence specified in § 173.2a of this subchapter, and an appropriate shipping description (e.g., “Flammable liquid, corrosive n.o.s.”) shall be selected as described in paragraph (c)(12)(ii) of this section.

(iv) If it is specifically determined that a material is not a forbidden material and does not meet the definition of any hazard class, the material is not a hazardous material.

(13) *Self-reactive materials and organic peroxides.* A generic proper shipping name for a self-reactive material or an organic peroxide, as listed in Column 2 of the Table, must be selected based on the material’s technical name and concentration, in accordance with the provisions of §§ 173.224 or 173.225 of this subchapter, respectively.

(14) A proper shipping name that describes all isomers of a material may be used to identify any isomer of that material if the isomer meets criteria for the same hazard class or division, subsidiary risk(s) and packing group, unless the isomer is specifically identified in the Table.

(15) Unless a hydrate is specifically listed in the Table, a proper shipping name for the equivalent anhydrous substance may be used, if the hydrate meets the same hazard class or division, subsidiary risk(s) and packing group.

(16) Unless it is already included in the proper shipping name in the § 172.101 Table, the qualifying words “liquid” or “solid” may be added in association with the proper shipping name when a hazardous material specifically listed by name in the § 172.101 Table may, due to the differing physical states of the various isomers of the material, be either a liquid or a solid (for example “Dinitrotoluenes, liquid” and “Dinitrotoluenes, solid”). Use of the words “liquid” or “solid” is subject to the limitations specified for the use of the words “mixture” or “solution” in paragraph (c)(10) of this section. The

qualifying word “molten” may be added in association with the proper shipping name when a hazardous material, which is a solid in accordance with the definition in §171.8 of this subchapter, is offered for transportation in the molten state (for example, “Alkylphenols, solid, n.o.s., molten”).

(d) *Column 3: Hazard class or Division.* Column 3 contains a designation of the hazard class or division corresponding to each proper shipping name, or the word “Forbidden”.

(1) A material for which the entry in this column is “Forbidden” may not be offered for transportation or transported. This prohibition does not apply if the material is diluted, stabilized or incorporated in a device and it is classed in accordance with the definitions of hazardous materials contained in part 173 of this subchapter.

(2) When a reevaluation of test data or new data indicates a need to modify the “Forbidden” designation or the hazard class or packing group specified for a material specifically identified in the Table, this data should be submitted to the Associate Administrator.

(3) A basic description of each hazard class and the section reference for class definitions appear in §173.2 of this subchapter.

(4) Each reference to a Class 3 material is modified to read “Combustible liquid” when that material is reclassified in accordance with §173.150(e) or (f) of this subchapter or has a flash point above 60 °C (140 °F) but below 93 °C (200 °F).

(e) *Column 4: Identification number.* Column 4 lists the identification number assigned to each proper shipping name. Those preceded by the letters “UN” are associated with proper shipping names considered appropriate for international transportation as well as domestic transportation. Those preceded by the letters “NA” are associated with proper shipping names not recognized for international transportation, except to and from Canada. Identification numbers in the “NA9000” series are associated with proper shipping names not appropriately covered by international hazardous materials (dangerous goods) transportation standards, or not appropriately addressed by international transpor-

tation standards for emergency response information purposes, except for transportation between the United States and Canada.

(f) *Column 5: Packing group.* Column 5 specifies one or more packing groups assigned to a material corresponding to the proper shipping name and hazard class for that material. Class 2, Class 7, Division 6.2 (other than regulated medical wastes), and ORM-D materials, do not have packing groups. Packing Groups I, II and III indicate the degree of danger presented by the material is either great, medium or minor, respectively. If more than one packing group is indicated for an entry, the packing group for the hazardous material is determined using the criteria for assignment of packing groups specified in subpart D of part 173. When a reevaluation of test data or new data indicates a need to modify the specified packing group(s), the data should be submitted to the Associate Administrator. Each reference in this column to a material which is a hazardous waste or a hazardous substance, and whose proper shipping name is preceded in Column 1 of the Table by the letter “A” or “W”, is modified to read “III” on those occasions when the material is offered for transportation or transported by a mode in which its transportation is not otherwise subject to requirements of this subchapter.

(g) *Column 6: Labels.* Column 6 specifies codes which represent the hazard warning labels required for a package filled with a material conforming to the associated hazard class and proper shipping name, unless the package is otherwise excepted from labeling by a provision in subpart E of this part, or part 173 of this subchapter. The first code is indicative of the primary hazard of the material. Additional label codes are indicative of subsidiary hazards. Provisions in §172.402 may require that a label other than that specified in Column 6 be affixed to the package in addition to that specified in Column 6. No label is required for a material classed as a combustible liquid or for a Class 3 material that is reclassified as a combustible liquid. For “Empty” label



requirements, see § 173.428 of this subchapter. The codes contained in Column 6 are defined according to the following table:

| LABEL SUBSTITUTION TABLE                                       |                            |
|----------------------------------------------------------------|----------------------------|
| Label code                                                     | Label name                 |
| 1                                                              | Explosive                  |
| 1.1 <sup>1</sup>                                               | Explosive 1.1 <sup>1</sup> |
| 1.2 <sup>1</sup>                                               | Explosive 1.2 <sup>1</sup> |
| 1.3 <sup>1</sup>                                               | Explosive 1.3 <sup>1</sup> |
| 1.4 <sup>1</sup>                                               | Explosive 1.4 <sup>1</sup> |
| 1.5 <sup>1</sup>                                               | Explosive 1.5 <sup>1</sup> |
| 1.6 <sup>1</sup>                                               | Explosive 1.6 <sup>1</sup> |
| 2.1                                                            | Flammable Gas              |
| 2.2                                                            | Non-Flammable Gas          |
| 2.3                                                            | Poison Gas                 |
| 3                                                              | Flammable Liquid           |
| 4.1                                                            | Flammable Solid            |
| 4.2                                                            | Spontaneously Combustible  |
| 4.3                                                            | Dangerous When Wet         |
| 5.1                                                            | Oxidizer                   |
| 5.2                                                            | Organic Peroxide           |
| 6.1 (inhalation hazard, Zone A or B).                          | Poison Inhalation Hazard   |
| 6.1 (other than inhalation hazard, Zone A or B) <sup>2</sup> . | Poison                     |
| 6.2                                                            | Infectious substance       |
| 7                                                              | Radioactive                |
| 8                                                              | Corrosive                  |
| 9                                                              | Class 9                    |

<sup>1</sup>Refers to the appropriate compatibility group letter.

<sup>2</sup>The packing group for a material is indicated in column 5 of the table.

(h) *Column 7: Special provisions.* Column 7 specifies codes for special provisions applicable to hazardous materials. When Column 7 refers to a special provision for a hazardous material, the meaning and requirements of that special provision are as set forth in § 172.102 of this subpart.

(i) *Column 8: Packaging authorizations.* Columns 8A, 8B and 8C specify the applicable sections for exceptions, non-bulk packaging requirements and bulk packaging requirements, respectively, in part 173 of this subchapter. Columns 8A, 8B and 8C are completed in a manner which indicates that “§173.” precedes the designated numerical entry. For example, the entry “202” in Column 8B associated with the proper shipping name “Gasoline” indicates that for this material conformance to non-bulk packaging requirements prescribed in § 173.202 of this subchapter is required. When packaging requirements are specified, they are in addition to the standard requirements for all packagings prescribed in § 173.24 of this subchapter and any other applicable requirements in subparts A and B of part 173 of this subchapter.

(1) Exceptions. Column 8A contains exceptions from some of the requirements of this subchapter. The referenced exceptions are in addition to those specified in subpart A of part 173 and elsewhere in this subchapter. A “None” in this column means no packaging exceptions are authorized, except as may be provided by special provisions in Column 7.

(2) Non-bulk packaging. Column 8B references the section in part 173 of this subchapter which prescribes packaging requirements for non-bulk packagings. A “None” in this column means non-bulk packagings are not authorized, except as may be provided by special provisions in Column 7. Each reference in this column to a material which is a hazardous waste or a hazardous substance, and whose proper shipping name is preceded in Column 1 of the Table by the letter “A” or “W”, is modified to include “§173.203” or “§173.213”, as appropriate for liquids and solids, respectively, on those occasions when the material is offered for transportation or transported by a mode in which its transportation is not otherwise subject to the requirements of this subchapter.

(3) *Bulk packaging.* Column (8C) specifies the section in part 173 of this subchapter that prescribes packaging requirements for bulk packagings, subject to the limitations, requirements, and additional authorizations of Columns (7) and (8B). A “None” in Column (8C) means bulk packagings are not authorized, except as may be provided by special provisions in Column (7) and in packaging authorizations Column (8B). Additional authorizations and limitations for use of UN portable tanks are set forth in Column 7. For each reference in this column to a material that is a hazardous waste or a hazardous substance, and whose proper shipping name is preceded in Column 1 of the Table by the letter “A” or “W” and that is offered for transportation or transported by a mode in which its transportation is not otherwise subject to the requirements of this subchapter:

(4) For a hazardous material which is specifically named in the Table and whose packaging sections specify packagings not applicable to the form of the material (e.g., packaging specified is

for solid material and the material is being offered for transportation in a liquid form) the following table should be used to determine the appropriate packaging section:

| Packaging section reference for solid materials | Corresponding packaging section for liquid materials |
|-------------------------------------------------|------------------------------------------------------|
| § 173.187 .....                                 | § 173.181                                            |
| § 173.211 .....                                 | § 173.201                                            |
| § 173.212 .....                                 | § 173.202                                            |
| § 173.213 .....                                 | § 173.203                                            |
| § 173.240 .....                                 | § 173.241                                            |
| § 173.242 .....                                 | § 173.243                                            |

(5) *Cylinders.* For cylinders, both non-bulk and bulk packaging authorizations are set forth in Column (8B). Notwithstanding a designation of “None” in Column (8C), a bulk cylinder may be used when specified through the section reference in Column (8B).

(j) *Column 9: Quantity limitations.* Columns 9A and 9B specify the maximum quantities that may be offered for transportation in one package by passenger-carrying aircraft or passenger-carrying rail car (Column 9A) or by cargo aircraft only (Column 9B), subject to the following:

(1) “Forbidden” means the material may not be offered for transportation or transported in the applicable mode of transport.

(2) The quantity limitation is “net” except where otherwise specified, such as for “Consumer commodity” which specifies “30 kg gross.”

(3) When articles or devices are specifically listed by name, the net quantity limitation applies to the entire article or device (less packaging and packaging materials) rather than only to its hazardous components.

(4) A package offered or intended for transportation by aircraft and which is filled with a material forbidden on passenger-carrying aircraft but permitted on cargo aircraft only, or which exceeds the maximum net quantity authorized on passenger-carrying aircraft, shall be labelled with the CARGO AIRCRAFT ONLY label specified in § 172.448 of this part.

(5) The total net quantity of hazardous material for an outer non-bulk packaging that contains more than one hazardous material may not exceed the lowest permitted maximum net quantity per package as shown in Column

9A or 9B, as appropriate. If one material is a liquid and one is a solid, the maximum net quantity must be calculated in kilograms. See § 173.24a(c)(1)(iv).

(k) *Column 10: Vessel stowage requirements.* Column 10A [Vessel stowage] specifies the authorized stowage locations on board cargo and passenger vessels. Column 10B [Other provisions] specifies codes for stowage requirements for specific hazardous materials. The meaning of each code in Column 10B is set forth in § 176.84 of this subchapter. Section 176.63 of this subchapter sets forth the physical requirements for each of the authorized locations listed in Column 10A. (For bulk transportation by vessel, see 46 CFR parts 30 to 40, 70, 98, 148, 151, 153 and 154.) The authorized stowage locations specified in Column 10A are defined as follows:

(1) Stowage category “A” means the material may be stowed “on deck” or “under deck” on a cargo vessel and on a passenger vessel.

(2) Stowage category “B” means—

(i) The material may be stowed “on deck” or “under deck” on a cargo vessel and on a passenger vessel carrying a number of passengers limited to not more than the larger of 25 passengers, or one passenger per each 3 m of overall vessel length; and

(ii) “On deck only” on passenger vessels in which the number of passengers specified in paragraph (k)(2)(i) of this section is exceeded.

(3) Stowage category “C” means the material must be stowed “on deck only” on a cargo vessel and on a passenger vessel.

(4) Stowage category “D” means the material must be stowed “on deck only” on a cargo vessel and on a passenger vessel carrying a number of passengers limited to not more than the larger of 25 passengers or one passenger per each 3 m of overall vessel length, but the material is prohibited on passenger vessels in which the limiting number of passengers is exceeded.

(5) Stowage category “E” means the material may be stowed “on deck” or “under deck” on a cargo vessel and on a passenger vessel carrying a number of passengers limited to not more than

the larger of 25 passengers, or one passenger per each 3 m of overall vessel length, but is prohibited from carriage on passenger vessels in which the limiting number of passengers is exceeded.

(6) Stowage category “01” means the material may be stowed “on deck” or “under deck” on a cargo vessel (up to 12 passengers) and on a passenger vessel.

(7) Stowage category “02” means the material may be stowed “on deck” or “under deck” on a cargo vessel (up to 12 passengers) and “on deck” in closed cargo transport units or “under deck” in closed cargo transport units on a passenger vessel.

(8) Stowage category “03” means the material may be stowed “on deck” or “under deck” on a cargo vessel (up to 12 passengers) and “on deck” in closed cargo transport units on a passenger vessel.

(9) Stowage category “04” means the material may be stowed “on deck” or “under deck” on a cargo vessel (up to 12 passengers) but the material is prohibited on a passenger vessel.

(10) Stowage category “05” means the material may be stowed “on deck” in closed cargo transport units or “under deck” on a cargo vessel (up to 12 passengers) and on a passenger vessel.

(11) Stowage category “06” means the material may be stowed “on deck” in closed cargo transport units or “under deck” on a cargo vessel (up to 12 passengers) and “on deck” in closed cargo transport units or “under deck” in closed cargo transport units on a passenger vessel.

(12) Stowage category “07” means the material may be stowed “on deck” in closed cargo transport units or “under deck” on a cargo vessel (up to 12 passengers) and “on deck” only in closed cargo transport units on a passenger vessel.

(13) Stowage category “08” means the material may be stowed “on deck” in closed cargo transport units or “under deck” on a cargo vessel (up to 12 passengers) but the material is prohibited on a passenger vessel.

(14) Stowage category “09” means the material may be stowed “on deck only” in closed cargo transport units or “under deck” in closed cargo trans-

port units on a cargo vessel (up to 12 passengers) and on a passenger vessel.

(15) Stowage category “10” means the material may be stowed “on deck” in closed cargo transport units or “under deck” in closed cargo transport units on a cargo vessel (up to 12 passengers) and “on deck” only in closed cargo transport units on a passenger vessel.

(16) Stowage category “11” means the material may be stowed “on deck” in closed cargo transport units or “under deck” in magazine stowage type “c” on a cargo vessel (up to 12 passengers) and “on deck” only in closed cargo transport units on a passenger vessel.

(17) Stowage category “12” means the material may be stowed “on deck” in closed cargo transport units or “under deck” in magazine stowage type “c” on a cargo vessel (up to 12 passengers) but the material is prohibited on a passenger vessel.

(18) Stowage category “13” means the material may be stowed “on deck” in closed cargo transport units or “under deck” in magazine stowage type “A” on a cargo vessel (up to 12 passengers) and “on deck” only in closed cargo transport units on a passenger vessel.

(19) Stowage category “14” means the material may be stowed “on deck” in closed cargo transport units on a cargo vessel (up to 12 passengers) but the material is prohibited on a passenger vessel.

(20) Stowage category “15” means the material may be stowed “on deck” in closed cargo transport units or “under deck” in closed cargo transport units on a cargo vessel (up to 12 passengers) but the material is prohibited on a passenger vessel.

(1) *Changes to the Table.* (1) Unless specifically stated otherwise in a rule document published in the FEDERAL REGISTER amending the Table—

(i) Such a change does not apply to the shipment of any package filled prior to the effective date of the amendment; and

(ii) Stocks of preprinted shipping papers and package markings may be continued in use, in the manner previously authorized, until depleted or for a one-year period, subsequent to the effective date of the amendment, whichever is less.

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 172.101**

(2) Except as otherwise provided in this section, any alteration of a shipping description or associated entry which is listed in the §172.101 Table must receive prior written approval from the Associate Administrator.

(3) The proper shipping name of a hazardous material changed in the May

6, 1997 final rule, in effect on October 1, 1997, only by the addition or omission of the word “compressed,” “inhibited,” “liquefied” or “solution” may continue to be used to comply with package marking requirements, until January 1, 2003.

§ 172.101 HAZARDOUS MATERIALS TABLE

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                               | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)                           | (8)                   |           |       | (9)                                             |                       | (10)             |                |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|------------------------------------------------------------|-----------------------|-----------|-------|-------------------------------------------------|-----------------------|------------------|----------------|
|          |                                                                                                                                                                           |                            |                            |     |             |                                                            | Packaging (§ 173.***) |           |       | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                |
|          |                                                                                                                                                                           |                            |                            |     |             |                                                            | Excep- tions          | Non- bulk | Bulk  | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other          |
| (1)      | (2)                                                                                                                                                                       | (3)                        | (4)                        | (5) | (6)         | (7)                                                        | (8A)                  | (8B)      | (8C)  | (9A)                                            | (9B)                  | (10A)            | (10B)          |
| A        | <i>Accellerene, see p-Nitrosodimethylaniline.</i>                                                                                                                         | .....                      |                            |     | .....       |                                                            | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....          |
|          | <i>Accumulators, electric, see Batteries, wet etc.</i>                                                                                                                    | .....                      |                            |     | .....       |                                                            | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....          |
|          | <i>Accumulators, pressurized, pneumatic or hydraulic (containing non-flammable gas), see Articles pressurized, pneumatic or hydraulic (containing non-flammable gas).</i> | .....                      |                            |     | .....       |                                                            | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....          |
|          | Acetal .....                                                                                                                                                              | 3                          | UN1088                     | II  | 3           | IB2, T4, TP1                                               | 150                   | 202       | 242   | 5 L                                             | 60 L                  | E                | .....          |
|          | Acetaldehyde .....                                                                                                                                                        | 3                          | UN1089                     | I   | 3           | A3, B16, T11, TP2, TP7                                     | None                  | 201       | 243   | Forbidden                                       | 30 L                  | E                | .....          |
|          | Acetaldehyde ammonia .....                                                                                                                                                | 9                          | UN1841                     | III | 9           | IB8, IP3, IP7, T1, TP33                                    | 155                   | 204       | 240   | 200 kg                                          | 200 kg                | A                | 34             |
|          | Acetaldehyde oxime .....                                                                                                                                                  | 3                          | UN2332                     | III | 3           | B1, IB3, T4, TP1                                           | 150                   | 203       | 242   | 60 L                                            | 220 L                 | A                | .....          |
|          | Acetic acid, glacial or Acetic acid solution, with more than 80 percent acid, by mass.                                                                                    | 8                          | UN2789                     | II  | 8, 3        | A3, A6, A7, A10, B2, IB2, T7, TP2                          | 154                   | 202       | 243   | 1 L                                             | 30 L                  | A                | .....          |
|          | Acetic acid solution, not less than 50 percent but not more than 80 percent acid, by mass.                                                                                | 8                          | UN2790                     | II  | 8           | A3, A6, A7, A10, B2, IB2, T7, TP2                          | 154                   | 202       | 242   | 1 L                                             | 30 L                  | A                | .....          |
|          | Acetic acid solution, with more than 10 percent and less than 50 percent acid, by mass.                                                                                   | 8                          | UN2790                     | III | 8           | IB3, T4, TP1                                               | 154                   | 203       | 242   | 5 L                                             | 60 L                  | A                | .....          |
|          | Acetic anhydride .....                                                                                                                                                    | 8                          | UN1715                     | II  | 8, 3        | A3, A6, A7, A10, B2, IB2, T7, TP2                          | 154                   | 202       | 243   | 1 L                                             | 30 L                  | A                | 40             |
|          | Acetone .....                                                                                                                                                             | 3                          | UN1090                     | II  | 3           | IB2, T4, TP1                                               | 150                   | 202       | 242   | 5 L                                             | 60 L                  | B                | .....          |
|          | Acetone cyanohydrin, stabilized                                                                                                                                           | 6.1                        | UN1541                     | I   | 6.1         | 2, B9, B14, B32, B76, B77, N34, T20, TP2, TP13, TP38, TP45 | None                  | 227       | 244   | Forbidden                                       | Forbidden             | D                | 25, 40, 52, 53 |
|          | Acetone oils .....                                                                                                                                                        | 3                          | UN1091                     | II  | 3           | IB2, T4, TP1, TP8                                          | 150                   | 202       | 242   | 5 L                                             | 60 L                  | B                | .....          |
|          | Acetonitrile .....                                                                                                                                                        | 3                          | UN1648                     | II  | 3           | IB2, T7, TP2                                               | 150                   | 202       | 242   | 5 L                                             | 60 L                  | B                | 40             |
|          | <i>Acetyl acetone peroxide with more than 9 percent by mass active oxygen.</i>                                                                                            | Forbidden                  |                            |     | .....       |                                                            | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....          |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                        |           |        |       |        |                                                                 |       |       |       |           |           |   |            |
|--------------------------------------------------------------------------------------------------------|-----------|--------|-------|--------|-----------------------------------------------------------------|-------|-------|-------|-----------|-----------|---|------------|
| Acetyl benzoyl peroxide, solid, or with more than 40 percent in solution.                              | Forbidden |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acetyl bromide .....                                                                                   | 8         | UN1716 | II    | 8      | B2, IB2, T8, TP2, TP12                                          | 154   | 202   | 242   | 1 L       | 30 L      | C | 40         |
| Acetyl chloride .....                                                                                  | 3         | UN1717 | II    | 3, 8   | A3, A6, A7, IB1, N34, T8, TP2, TP12                             | 150   | 202   | 243   | 1 L       | 5 L       | B | 40         |
| Acetyl cyclohexanesulfonyl peroxide, with more than 82 percent wetted with less than 12 percent water. | Forbidden |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acetyl iodide .....                                                                                    | 8         | UN1898 | II    | 8      | B2, IB2, T7, TP2, TP13                                          | 154   | 202   | 242   | 1 L       | 30 L      | C | 40         |
| Acetyl methyl carbinol .....                                                                           | 3         | UN2621 | III   | 3      | B1, IB3, T2, TP1                                                | 150   | 203   | 242   | 60 L      | 220 L     | A | .....      |
| Acetyl peroxide, solid, or with more than 25 percent in solution.                                      | Forbidden |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acetylene, dissolved .....                                                                             | 2.1       | UN1001 | ..... | 2.1    | N86, N88                                                        | None  | 303   | None  | Forbidden | 15 kg     | D | 25, 40, 57 |
| Acetylene (liquefied) .....                                                                            | Forbidden |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acetylene silver nitrate .....                                                                         | Forbidden |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acetylene, solvent free .....                                                                          | Forbidden |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acetylene tetrabromide, see Tetrabromoethane.                                                          | .....     |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acid butyl phosphate, see Butyl acid phosphate.                                                        | .....     |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acid, sludge, see Sludge acid ...                                                                      | .....     |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Acridine .....                                                                                         | 6.1       | UN2713 | III   | 6.1    | IB8, IP3, T1, TP33                                              | 153   | 213   | 240   | 100 kg    | 200 kg    | A | .....      |
| Acrolein dimer, stabilized .....                                                                       | 3         | UN2607 | III   | 3      | B1, IB3, T2, TP1                                                | 150   | 203   | 242   | 60 L      | 220 L     | A | 40         |
| Acrolein, stabilized .....                                                                             | 6.1       | UN1092 | I     | 6.1, 3 | 1, B9, B14, B30, B42, B72, B77, T22, TP2, TP7, TP13, TP38, TP44 | None  | 226   | 244   | Forbidden | Forbidden | D | 40         |
| Acrylamide, solid .....                                                                                | 6.1       | UN2074 | III   | 6.1    | IB8, IP3, T1, TP33                                              | 153   | 213   | 240   | 100 kg    | 200 kg    | A | 12         |
| Acrylamide solution .....                                                                              | 6.1       | UN3426 | III   | 6.1    | IB3, T4, TP1                                                    | 153   | 203   | 241   | 60 L      | 220 L     | A | 12         |
| Acrylic acid, stabilized .....                                                                         | 8         | UN2218 | II    | 8, 3   | B2, IB2, T7, TP2                                                | 154   | 202   | 243   | 1 L       | 30 L      | C | 25, 40     |
| Acrylonitrile, stabilized .....                                                                        | 3         | UN1093 | I     | 3, 6.1 | B9, T14, TP2, TP13                                              | None  | 201   | 243   | Forbidden | 30 L      | E | 40         |
| Actuating cartridge, explosive, see Cartridges, power device.                                          | .....     |        |       | .....  |                                                                 | ..... | ..... | ..... | .....     | .....     |   | .....      |
| Adhesives, containing a flammable liquid.                                                              | 3         | UN1133 | I     | 3      | B42, T11, TP1, TP8, TP27                                        | 150   | 201   | 243   | 1 L       | 30 L      | B | .....      |
|                                                                                                        | .....     |        | II    | 3      | 149, B52, IB2, T4, TP1, TP8                                     | 150   | 173   | 242   | 5 L       | 60 L      | B | .....      |
|                                                                                                        | .....     |        | III   | 3      | B1, B52, IB3, T2, TP1                                           | 150   | 173   | 242   | 60 L      | 220 L     | A | .....      |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |              |
|----------|----------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------------|
|          |                                                                                                                            |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |              |
|          |                                                                                                                            |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other        |
| (1)      | (2)                                                                                                                        | (3)                        | (4)                        | (5)   | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)        |
| I        | Adiponitrile .....                                                                                                         | 6.1                        | UN2205                     | III   | 6.1 ....    | IB3, T3, TP1                     | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | .....        |
|          | Aerosols, <i>corrosive, Packing Group II or III, (each not exceeding 1 L capacity).</i>                                    | 2.2                        | UN1950                     | ..... | 2.2, 8      | A34                              | 306 .....             | None .... | None .... | 75 kg                                           | 150 kg                | A                | 48, 87, 126  |
|          | Aerosols, <i>flammable, (each not exceeding 1 L capacity).</i>                                                             | 2.1                        | UN1950                     | ..... | 2.1 ....    | N82                              | 306 .....             | None .... | None .... | 75 kg                                           | 150 kg                | A                | 48, 87, 126  |
|          | Aerosols, <i>flammable, n.o.s. (engine starting fluid) (each not exceeding 1 L capacity).</i>                              | 2.1                        | UN1950                     | ..... | 2.1 ....    | N82                              | 306 .....             | 304 ..... | None .... | Forbidden                                       | 150 kg                | A                | 48, 87, 126  |
|          | Aerosols, <i>non-flammable, (each not exceeding 1 L capacity).</i>                                                         | 2.2                        | UN1950                     | ..... | 2.2 ....    | .....                            | 306 .....             | None .... | None .... | 75 kg                                           | 150 kg                | A                | 48, 87, 126. |
|          | Aerosols, <i>poison, (each not exceeding 1 L capacity).</i>                                                                | 2.2                        | UN1950                     | ..... | 2.2, 6.1    | .....                            | 306 .....             | None .... | None .... | Forbidden                                       | Forbidden             | A                | 48, 87, 126  |
|          | Air bag inflators, or Air bag modules, or Seat-belt pretensioners..                                                        | 1.4G                       | UN0503                     | II    | 1.4G ..     | 161                              | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 02               | .....        |
|          | Air bag inflators, or Air bag modules, or Seat-belt pretensioners..                                                        | 9                          | UN3268                     | III   | 9 .....     | 160                              | 166 .....             | 166 ..... | 166 ..... | 25 kg                                           | 100 kg                | A                | .....        |
|          | Air, compressed .....                                                                                                      | 2.2                        | UN1002                     | ..... | 2.2 ....    | 78                               | 306, 307.             | 302 ..... | 302 ..... | 75 kg                                           | 150 kg                | A                | .....        |
|          | Air, refrigerated liquid, (cryo- genic liquid).                                                                            | 2.2                        | UN1003                     | ..... | 2.2, 5.1    | T75, TP5, TP22                   | 320 .....             | 316 ..... | 318, 319. | Forbidden                                       | Forbidden             | D                | 51           |
|          | Air, refrigerated liquid, (cryo- genic liquid) non-pressurized.                                                            | 2.2                        | UN1003                     | ..... | 2.2, 5.1    | T75, TP5, TP22                   | 320 .....             | 316 ..... | 318, 319. | Forbidden                                       | Forbidden             | D                | 51           |
|          | Aircraft engines (including tur- bines), see Engines, internal combustion.                                                 | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |
|          | Aircraft evacuation slides, see Life saving appliances etc.                                                                | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |
|          | Aircraft hydraulic power unit fuel tank (containing a mixture of anhydrous hydrazine and monomethyl hydrazine) (M86 fuel). | 3                          | UN3165                     | I     | 3, 6.1, 8.  | .....                            | None ....             | 172 ..... | None .... | Forbidden                                       | 42 L                  | E                | .....        |
|          | Aircraft survival kits, see Life saving appliances etc.                                                                    | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                         |     |        |     |           |                                          |           |           |           |           |        |    |        |
|---|-------------------------------------------------------------------------|-----|--------|-----|-----------|------------------------------------------|-----------|-----------|-----------|-----------|--------|----|--------|
| G | Alcoholates solution, n.o.s., <i>in alcohol.</i>                        | 3   | UN3274 | II  | 3, 8 .... | IB2                                      | 150 ..... | 202 ..... | 243 ..... | 1 L       | 5 L    | B  | .....  |
|   | Alcoholic beverages .....                                               | 3   | UN3065 | II  | 3 .....   | 24, 149, B1, IB2, T4, TP1                | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L   | A  | .....  |
|   | .....                                                                   |     |        | III | 3 .....   | 24, B1, IB3, N11, T2, TP1                | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L  | A  | .....  |
|   | Alcohols, n.o.s. ....                                                   | 3   | UN1987 | I   | 3 .....   | 172, T11, TP1, TP8, TP27                 | None .... | 201 ..... | 243 ..... | 1 L       | 30 L   | E  | .....  |
|   | .....                                                                   |     |        | II  | 3 .....   | 172, IB2, T7, TP1, TP8, TP28             | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L   | B  | .....  |
|   | .....                                                                   |     |        | III | 3 .....   | 172, B1, IB3, T4, TP1, TP29              | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L  | A. | .....  |
| G | Alcohols, flammable, toxic n.o.s.                                       | 3   | UN1986 | I   | 3, 6.1    | T14, TP2, TP13, TP27                     | None .... | 201 ..... | 243 ..... | Forbidden | 30 L   | E  | 40     |
|   | .....                                                                   |     |        | II  | 3, 6.1    | IB2, T11, TP2, TP27                      | 150 ..... | 202 ..... | 243 ..... | 1 L       | 60 L   | B  | 40     |
|   | .....                                                                   |     |        | III | 3, 6.1    | B1, IB3, T7, TP1, TP28                   | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L  | A  | .....  |
|   | Aldehydes, n.o.s. ....                                                  | 3   | UN1989 | I   | 3 .....   | T11, TP1, TP27                           | None .... | 201 ..... | 243 ..... | 1 L       | 30 L   | E  | .....  |
|   | .....                                                                   |     |        | II  | 3 .....   | IB2, T7, TP1, TP8, TP28                  | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L   | B  | .....  |
|   | .....                                                                   |     |        | III | 3 .....   | B1, IB3, T4, TP1, TP29                   | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L  | A  | .....  |
| G | Aldehydes, flammable, toxic, n.o.s..                                    | 3   | UN1988 | I   | 3, 6.1    | T14, TP2, TP13, TP27                     | None .... | 201 ..... | 243 ..... | Forbidden | 30 L   | E  | 40     |
|   | .....                                                                   |     |        | II  | 3, 6.1    | IB2, T11, TP2, TP27                      | 150 ..... | 202 ..... | 243 ..... | 1 L       | 60 L   | B  | 40     |
|   | .....                                                                   |     |        | III | 3, 6.1    | B1, IB3, T7, TP1, TP28                   | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L  | A  | .....  |
|   | Aldol .....                                                             | 6.1 | UN2839 | II  | 6.1 ....  | IB2, T7, TP2                             | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L   | A  | 12     |
| G | Alkali metal alcoholates, self-heating, corrosive, n.o.s..              | 4.2 | UN3206 | II  | 4.2, 8    | 64, A7, IB5, IP2, T3, TP33               | None .... | 212 ..... | 242 ..... | 15 kg     | 50 kg  | B  | .....  |
|   | .....                                                                   |     |        | III | 4.2, 8    | 64, A7, IB8, IP3, T1, TP33               | None .... | 213 ..... | 242 ..... | 25 kg     | 100 kg | B  | .....  |
|   | Alkali metal alloys, liquid, n.o.s.                                     | 4.3 | UN1421 | I   | 4.3 ....  | A2, A3, A7, B48, N34                     | None .... | 201 ..... | 244 ..... | Forbidden | 1 L    | D  | 52     |
|   | Alkali metal amalgam, liquid .....                                      | 4.3 | UN1389 | I   | 4.3 ....  | A2, A3, A7, N34                          | None .... | 201 ..... | 244 ..... | Forbidden | 1 L    | D  | 40, 52 |
|   | Alkali metal amalgam, solid .....                                       | 4.3 | UN3401 | I   | 4.3 ....  | IB4, IP1, N40, T9, TP7, TP33             | None .... | 211 ..... | 242 ..... | Forbidden | 15 kg  | D  | 52     |
|   | Alkali metal amides .....                                               | 4.3 | UN1390 | II  | 4.3 ....  | A6, A7, A8, A19, A20, IB7, IP2, T3, TP33 | 151 ..... | 212 ..... | 241 ..... | 15 kg     | 50 kg  | E  | 40, 52 |
|   | Alkali metal dispersions, or Alkaline earth metal dispersions.          | 4.3 | UN1391 | I   | 4.3 ....  | A2, A3, A7                               | None .... | 201 ..... | 244 ..... | Forbidden | 1 L    | D  | 52     |
|   | Alkaline corrosive liquids, n.o.s., see Caustic alkali liquids, n.o.s.. |     |        |     | .....     | .....                                    | .....     | .....     | .....     | .....     | .....  |    | .....  |
| G | Alkaline earth metal alcoholates, n.o.s..                               | 4.2 | UN3205 | II  | 4.2 ....  | 65, A7, IB6, IP2, T3, TP33               | None .... | 212 ..... | 241 ..... | 15 kg     | 50 kg  | B  | .....  |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                           | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|-----------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                                                       |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                                                       |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| (1)      | (2)                                                                                                                   | (3)                        | (4)                        | (5) | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)  |
|          | .....                                                                                                                 | .....                      |                            | III | 4.2 .....   | 65, A7, IB8, IP3, T1, TP33       | None ....             | 213 ..... | 241 ..... | 25 kg                                           | 100 kg                | B                | .....  |
|          | Alkaline earth metal alloys, n.o.s..                                                                                  | 4.3                        | UN1393                     | II  | 4.3 .....   | A19, IB7, IP2, T3, TP33          | 151 .....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                 | E                | 52     |
|          | Alkaline earth metal amalgams, liquid.                                                                                | 4.3                        | UN1392                     | I   | 4.3 .....   | A19, N34, N40                    | None ....             | 201 ..... | 244 ..... | Forbidden                                       | 1 L                   | E                | 40, 52 |
|          | Alkaline earth metal amalgams, solid.                                                                                 | 4.3                        | UN3402                     | I   | 4.3 .....   | A19, N34, N40, T9, TP7, TP33     | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg                 | D                | 52     |
| G        | Alkaloids, liquid, n.o.s., or Alka-<br>loid salts, liquid, n.o.s..                                                    | 6.1                        | UN3140                     | I   | 6.1 .....   | A4, T14, TP2, TP27               | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | A                | .....  |
|          | .....                                                                                                                 | .....                      |                            | II  | 6.1 .....   | IB2, T11, TP2, TP27              | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | .....  |
|          | .....                                                                                                                 | .....                      |                            | III | 6.1 .....   | IB3, T7, TP1, TP28               | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | .....  |
| G        | Alkaloids, solid, n.o.s. or Alka-<br>loid salts, solid, n.o.s. poi-<br>sonous.                                        | 6.1                        | UN1544                     | I   | 6.1 .....   | IB7, IP1, T6, TP33               | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                 | A                |        |
|          | .....                                                                                                                 | .....                      |                            | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                |        |
|          | .....                                                                                                                 | .....                      |                            | III | 6.1 .....   | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                |        |
|          | Alkyl sulfonic acids, liquid or<br>Aryl sulfonic acids, liquid with<br>more than 5 percent free sul-<br>furic acid.   | 8                          | UN2584                     | II  | 8 .....     | B2, IB2, T8, TP2, TP12, TP13     | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | B                | .....  |
|          | Alkyl sulfonic acids, liquid or<br>Aryl sulfonic acids, liquid with<br>not more than 5 percent free<br>sulfuric acid. | 8                          | UN2586                     | III | 8 .....     | IB3, T4, TP1                     | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | B                | .....  |
|          | Alkyl sulfonic acids, solid or Aryl<br>sulfonic acids, solid, with<br>more than 5 percent free sul-<br>furic acid.    | 8                          | UN2583                     | II  | 8 .....     | IB8, IP2, IP4, T3, TP33          | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                 | A                | .....  |
|          | Alkyl sulfonic acids, solid or Aryl<br>sulfonic acids, solid with not<br>more than 5 percent free sul-<br>furic acid. | 8                          | UN2585                     | III | 8 .....     | IB8, IP3, T1, TP33               | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | .....  |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|                                                             |     |        |              |                                                       |      |     |     |           |           |   |     |
|-------------------------------------------------------------|-----|--------|--------------|-------------------------------------------------------|------|-----|-----|-----------|-----------|---|-----|
| Alkylphenols, liquid, n.o.s. (including C2-C12 homologues). | 8   | UN3145 | I 8          | A6, T14, TP2                                          | None | 201 | 243 | 0.5 L     | 2.5 L     | B |     |
| .....                                                       |     |        | II 8         | IB2, T11, TP2, TP27                                   | 154  | 202 | 242 | 1 L       | 30 L      | B |     |
| .....                                                       |     |        | III 8        | IB3, T7, TP1, TP28                                    | 154  | 203 | 241 | 5 L       | 60 L      | A |     |
| Alkylphenols, solid, n.o.s. (including C2-C12 homologues).  | 8   | UN2430 | I 8          | IB7, IP1, T6, TP33                                    | None | 211 | 242 | 1 kg      | 25 kg     | B |     |
| .....                                                       |     |        | II 8         | IB8, IP2, IP4, T3, TP33                               | 154  | 212 | 240 | 15 kg     | 50 kg     | B |     |
| .....                                                       |     |        | III 8        | IB8, IP3, T1, TP33                                    | 154  | 213 | 240 | 25 kg     | 100 kg    | A |     |
| Alkylsulfuric acids                                         | 8   | UN2571 | II 8         | B2, IB2, T8, TP2, TP12, TP13, TP28                    | 154  | 202 | 242 | 1 L       | 30 L      | C | 14  |
| Allethrin, see Pesticides, liquid, toxic, n.o.s..           |     |        |              |                                                       |      |     |     |           |           |   |     |
| Allyl acetate                                               | 3   | UN2333 | II 3, 6.1    | IB2, T7, TP1, TP13                                    | 150  | 202 | 243 | 1 L       | 60 L      | E | 40  |
| Allyl alcohol                                               | 6.1 | UN1098 | I 6.1, 3     | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None | 227 | 244 | Forbidden | Forbidden | D | 40  |
| Allyl bromide                                               | 3   | UN1099 | I 3, 6.1     | T14, TP2, TP13                                        | None | 201 | 243 | Forbidden | 30 L      | B | 40  |
| Allyl chloride                                              | 3   | UN1100 | I 3, 6.1     | T14, TP2, TP13                                        | None | 201 | 243 | Forbidden | 30 L      | E | 40  |
| Allyl chlorocarbonate, see Allyl chloroformate.             |     |        |              |                                                       |      |     |     |           |           |   |     |
| Allyl chloroformate                                         | 6.1 | UN1722 | I 6.1, 3, 8. | 2, B9, B14, B32, B74, N41, T20, TP2, TP13, TP38, TP45 | None | 227 | 244 | Forbidden | Forbidden | D | 40  |
| Allyl ethyl ether                                           | 3   | UN2335 | II 3, 6.1    | IB2, T7, TP1, TP13                                    | 150  | 202 | 243 | 1 L       | 60 L      | E | 40  |
| Allyl formate                                               | 3   | UN2336 | I 3, 6.1     | T14, TP2, TP13                                        | None | 201 | 243 | Forbidden | 30 L      | E | 40  |
| Allyl glycidyl ether                                        | 3   | UN2219 | III 3        | B1, IB3, T2, TP1                                      | 150  | 203 | 242 | 60 L      | 220 L     | A |     |
| Allyl iodide                                                | 3   | UN1723 | II 3, 8      | A3, A6, IB1, N34, T7, TP2, TP13                       | 150  | 202 | 243 | 1 L       | 5 L       | B | 40  |
| Allyl isothiocyanate, stabilized                            | 6.1 | UN1545 | II 6.1, 3    | A3, A7, IB2, T7, TP2                                  | None | 202 | 243 | Forbidden | 60 L      | D | 40  |
| Allylamine                                                  | 6.1 | UN2334 | I 6.1, 3     | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45      | None | 227 | 244 | Forbidden | Forbidden | D | 40  |
| Allyltrichlorosilane, stabilized                            | 8   | UN1724 | II 8, 3      | A7, B2, B6, IB2, N34, T7, TP2, TP13                   | None | 202 | 243 | Forbidden | 30 L      | C | 40  |
| Aluminum alkyl halides, liquid                              | 4.2 | UN3052 | I 4.2, 4.3.  | 173, B9, B11, T21, TP2, TP7                           | None | 181 | 244 | Forbidden | Forbidden | D | 134 |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes | Special provi-sions (§ 172.102) | (8)                   |           |           | (9)                                             |                      | (10)            |                         |
|----------|-------------------------------------------------------------|---------------------------|--------------------------|-------|-------------|---------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|-------------------------|
|          |                                                             |                           |                          |       |             |                                 | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |                         |
|          |                                                             |                           |                          |       |             |                                 | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other                   |
| (1)      | (2)                                                         | (3)                       | (4)                      | (5)   | (6)         | (7)                             | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                 | (10A)           | (10B)                   |
| D        | Aluminum alkyl halides, solid .....                         | 4.2                       | UN3461                   | I     | 4.2, 4.3    | 173, T21, TP7, TP33             | None ....             | 181 ..... | 244 ..... | Forbidden                                       | Forbidden            | D               | 134                     |
|          | Aluminum alkyl hydrides .....                               | 4.2                       | UN3076                   | I     | 4.2, 4.3    | 173, B9, B11, T21, TP2, TP7     | None ....             | 181 ..... | 244 ..... | Forbidden                                       | Forbidden            | D               | .....                   |
|          | Aluminum alkyls .....                                       | 4.2                       | UN3051                   | I     | 4.2, 4.3    | 173, B9, B11, T21, TP2, TP7     | None ....             | 181 ..... | 244 ..... | Forbidden                                       | Forbidden            | D               | .....                   |
|          | Aluminum borohydride or Alu-minum borohydride in devices.   | 4.2                       | UN2870                   | I     | 4.2, 4.3    | B11, T21, TP7, TP33             | None ....             | 181 ..... | 244 ..... | Forbidden                                       | Forbidden            | D               | .....                   |
|          | Aluminum bromide, anhydrous ..                              | 8                         | UN1725                   | II    | 8 .....     | IB8, IP2, IP4, T3, TP33         | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                | A               | 40                      |
|          | Aluminum bromide, solution .....                            | 8                         | UN2580                   | III   | 8 .....     | IB3, T4, TP1                    | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                 | A               | .....                   |
|          | Aluminum carbide .....                                      | 4.3                       | UN1394                   | II    | 4.3 .....   | A20, IB7, IP2, N41, T3, TP33    | 151 .....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                | A               | 52                      |
|          | Aluminum chloride, anhydrous ..                             | 8                         | UN1726                   | II    | 8 .....     | IB8, IP2, IP4, T3, TP33         | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                | A               | 40                      |
|          | Aluminum chloride, solution .....                           | 8                         | UN2581                   | III   | 8 .....     | IB3, T4, TP1                    | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                 | A               | .....                   |
|          | Aluminum dross, wet or hot .....                            | Forbidden                 | .....                    | ..... | .....       | .....                           | .....                 | .....     | .....     | .....                                           | .....                | .....           | .....                   |
|          | Aluminum ferrosilicon powder ....                           | 4.3                       | UN1395                   | II    | 4.3, 6.1    | A19, IB5, IP2, T3, TP33         | 151 .....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                | A               | 39, 40, 52, 53, 85, 103 |
|          | .....                                                       | .....                     | .....                    | III   | 4.3, 6.1    | A19, A20, IB4                   | 151 .....             | 213 ..... | 241 ..... | 25 kg                                           | 100 kg               | A               | 39, 40, 52, 53, 85, 103 |
|          | Aluminum hydride .....                                      | 4.3                       | UN2463                   | I     | 4.3 .....   | A19, N40                        | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg                | E               | .....                   |
|          | Aluminum, molten .....                                      | 9                         | NA9260                   | III   | 9 .....     | IB3, T1, TP3                    | None ....             | None .... | 247 ..... | Forbidden                                       | Forbidden            | D               | .....                   |
|          | Aluminum nitrate .....                                      | 5.1                       | UN1438                   | III   | 5.1 .....   | A1, A29, IB8, IP3, T1, TP33     | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | .....                   |
|          | Aluminum phosphate solution, see Corrosive liquids, etc.    | .....                     | .....                    | ..... | .....       | .....                           | .....                 | .....     | .....     | .....                                           | .....                | .....           | .....                   |
|          | Aluminum phosphide .....                                    | 4.3                       | UN1397                   | I     | 4.3, 6.1    | A8, A19, N40                    | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg                | E               | 40, 52, 85              |
|          | Aluminum phosphide pesticides                               | 6.1                       | UN3048                   | I     | 6.1 .....   | A8, IB7, IP1, T6, TP33          | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg                | E               | 40, 85                  |
|          | Aluminum powder, coated .....                               | 4.1                       | UN1309                   | II    | 4.1 .....   | IB8, IP2, IP4, T3, TP33         | 151 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                | A               | 13, 39, 52, 53, 74, 101 |
|          | .....                                                       | .....                     | .....                    | III   | 4.1 .....   | IB8, IP3, T1, TP33              | 151 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | 13, 39, 52, 53, 74, 101 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                          |       |        |       |       |       |                                        |       |       |       |       |       |       |       |        |       |                               |
|---|----------------------------------------------------------------------------------------------------------|-------|--------|-------|-------|-------|----------------------------------------|-------|-------|-------|-------|-------|-------|-------|--------|-------|-------------------------------|
|   | Aluminum powder, uncoated .....                                                                          | 4.3   | UN1396 | II    | 4.3   | ..... | A19, A20, IB7,<br>IP2, T3, TP33        | 151   | ..... | 212   | ..... | 242   | ..... | 15 kg | 50 kg  | A     | 39, 52,<br>53                 |
|   | .....                                                                                                    | ..... | .....  | III   | 4.3   | ..... | A19, A20, IB8,<br>IP4, T1, TP33        | 151   | ..... | 213   | ..... | 241   | ..... | 25 kg | 100 kg | A     | 39, 52,<br>53                 |
|   | Aluminum resinate .....                                                                                  | 4.1   | UN2715 | III   | 4.1   | ..... | IB6, T1, TP33                          | 151   | ..... | 213   | ..... | 240   | ..... | 25 kg | 100 kg | A     | .....                         |
|   | Aluminum silicon powder,<br>uncoated.                                                                    | 4.3   | UN1398 | III   | 4.3   | ..... | A1, A19, IB8,<br>IP4, T1, TP33         | 151   | ..... | 213   | ..... | 241   | ..... | 25 kg | 100 kg | A     | 39, 40,<br>52, 53,<br>85, 103 |
|   | Aluminum smelting by-products<br>or Aluminum remelting by-<br>products.                                  | 4.3   | UN3170 | II    | 4.3   | ..... | 128, B115, IB7,<br>IP2, T3, TP33       | None  | ....  | 212   | ..... | 242   | ..... | 15 kg | 50 kg  | B     | 85, 103                       |
|   | .....                                                                                                    | ..... | .....  | III   | 4.3   | ..... | 128, B115, IB8,<br>IP4, T1, TP33       | None  | ....  | 213   | ..... | 241   | ..... | 25 kg | 100 kg | B     | 85, 103                       |
|   | Amatols, see Explosives, blast-<br>ing, type B.                                                          | ..... | .....  | ..... | ..... | ..... | .....                                  | ..... | ..... | ..... | ..... | ..... | ..... | ..... | .....  | ..... | .....                         |
| G | Amines, flammable, corrosive,<br>n.o.s. or Polyamines, flam-<br>mable, corrosive, n.o.s.                 | 3     | UN2733 | I     | 3, 8  | ....  | T14, TP1, TP27                         | None  | ....  | 201   | ..... | 243   | ..... | 0.5 L | 2.5 L  | D     | 40, 52.                       |
|   | Amines, liquid, corrosive, flam-<br>mable n.o.s. or Polyamines,<br>liquid corrosive, flammable<br>n.o.s. | 8     | UN2734 | I     | 8, 3  | ..... | A3, A6, N34,<br>T14, TP2, TP27         | None  | ....  | 201   | ..... | 243   | ..... | 0.5L  | 2.5L   | A     | 52                            |
|   | .....                                                                                                    | ..... | .....  | II    | 3, 8  | ....  | IB2, T11, TP1,<br>TP27                 | 150   | ..... | 202   | ..... | 243   | ..... | 1 L   | 5 L    | B     | 40, 52.                       |
|   | .....                                                                                                    | ..... | .....  | III   | 3, 8  | ....  | B1, IB3, T7, TP1,<br>TP28              | 150   | ..... | 203   | ..... | 242   | ..... | 5 L   | 60 L   | A     | 40, 52.                       |
|   | .....                                                                                                    | ..... | .....  | II    | 8, 3  | ....  | IB2, T11, TP2,<br>TP27                 | None  | ....  | 202   | ..... | 243   | ..... | 1 L   | 30 L   | A     | 52                            |
| G | Amines, liquid, corrosive, n.o.s.,<br>or Polyamines, liquid, corro-<br>sive, n.o.s..                     | 8     | UN2735 | I     | 8     | ..... | A3, A6, B10,<br>N34, T14, TP2,<br>TP27 | None  | ....  | 201   | ..... | 243   | ..... | 0.5 L | 2.5 L  | A     | 52                            |
|   | .....                                                                                                    | ..... | .....  | II    | 8     | ..... | B2, IB2, T11,<br>TP1, TP27             | 154   | ..... | 202   | ..... | 242   | ..... | 1 L   | 30 L   | A     | 52                            |
|   | .....                                                                                                    | ..... | .....  | III   | 8     | ..... | IB3, T7, TP1,<br>TP28                  | 154   | ..... | 203   | ..... | 241   | ..... | 5 L   | 60 L   | A     | 52                            |
| G | Amines, solid, corrosive, n.o.s.,<br>or Polyamines, solid, corro-<br>sive n.o.s..                        | 8     | UN3259 | I     | 8     | ..... | IB7, IP1, T6,<br>TP33                  | None  | ....  | 211   | ..... | 242   | ..... | 1 kg  | 25 kg  | A     | 52                            |
|   | .....                                                                                                    | ..... | .....  | II    | 8     | ..... | IB8, IP2, IP4, T3,<br>TP33             | 154   | ..... | 212   | ..... | 240   | ..... | 15 kg | 50 kg  | A     | 52                            |
|   | .....                                                                                                    | ..... | .....  | III   | 8     | ..... | IB8, IP3, T1,<br>TP33                  | 154   | ..... | 213   | ..... | 240   | ..... | 25 kg | 100 kg | A     | 52                            |
|   | 2-Amino-4-chlorophenol .....                                                                             | 6.1   | UN2673 | II    | 6.1   | ..... | IB8, IP2, IP4, T3,<br>TP33             | 153   | ..... | 212   | ..... | 242   | ..... | 25 kg | 100 kg | A     | .....                         |
|   | 2-Amino-5-diethylaminopentane                                                                            | 6.1   | UN2946 | III   | 6.1   | ..... | IB3, T4, TP1                           | 153   | ..... | 203   | ..... | 241   | ..... | 60 L  | 220 L  | A     | .....                         |
|   | 2-Amino-4,6-Dinitrophenol,<br>wetted with not less than 20<br>percent water by mass.                     | 4.1   | UN3317 | I     | 4.1   | ..... | 23, A8, A19,<br>A20, N41               | None  | ....  | 211   | ..... | None  | ....  | 1 kg  | 15 kg  | E     | 28, 36                        |
|   | 2-(2-Aminoethoxy) ethanol .....                                                                          | 8     | UN3055 | III   | 8     | ..... | IB3, T4, TP1                           | 154   | ..... | 203   | ..... | 241   | ..... | 5 L   | 60 L   | A     | .....                         |
|   | N-Aminoethylpiperazine .....                                                                             | 8     | UN2815 | III   | 8     | ..... | IB3, T4, TP1                           | 154   | ..... | 203   | ..... | 241   | ..... | 5 L   | 60 L   | A     | 12                            |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                 | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |             |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------------|
|          |                                                                                                                                                             |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |             |
|          |                                                                                                                                                             |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other       |
| (1)      | (2)                                                                                                                                                         | (3)                        | (4)                        | (5)   | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)       |
| +        | Aminophenols (o-; m-; p-) .....                                                                                                                             | 6.1                        | UN2512                     | III   | 6.1 ....    | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | .....       |
|          | <i>Aminopropyl</i> diethanolamine, see Amines, etc. ....                                                                                                    |                            |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>n</i> -Aminopropylmorpholine, see Amines, etc. ....                                                                                                      |                            |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | Aminopyridines (o-; m-; p-) .....                                                                                                                           | 6.1                        | UN2671                     | II    | 6.1 ....    | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | B                | 12, 40, 52, |
| I        | Ammonia, anhydrous .....                                                                                                                                    | 2.3                        | UN1005                     | ..... | 2.3, 8      | 4, N87, T50                      | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 52, 57  |
| D        | Ammonia, anhydrous .....                                                                                                                                    | 2.2                        | UN1005                     | ..... | 2.2 ....    | 13, T50                          | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 52, 57  |
| I        | Ammonia solution, <i>relative density less than 0.880 at 15 degrees C in water, with more than 50 percent ammonia.</i>                                      | 2.3                        | UN3318                     | ..... | 2.3, 8      | 4, N87, T50                      | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 52, 57  |
| D        | Ammonia solution, <i>relative density less than 0.880 at 15 degrees C in water, with more than 50 percent ammonia.</i>                                      | 2.2                        | UN3318                     | ..... | 2.2 ....    | 13, T50                          | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 52, 57  |
|          | Ammonia solutions, <i>relative density less than 0.880 at 15 degrees C in water, with more than 35 percent but not more than 50 percent ammonia.</i>        | 2.2                        | UN2073                     | ..... | 2.2 ....    | N87                              | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg                | E                | 40, 52, 57  |
|          | Ammonia solution, <i>relative density between 0.880 and 0.957 at 15 degrees C in water, with more than 10 percent but not more than 35 percent ammonia.</i> | 8                          | UN2672                     | III   | 8 .....     | IB3, IP8, T7, TP1                | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | 40, 52, 85  |
|          | Ammonium arsenate .....                                                                                                                                     | 6.1                        | UN1546                     | II    | 6.1 ....    | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | 53          |
|          | Ammonium azide .....                                                                                                                                        | Forbidden                  |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | Ammonium bifluoride, solid, see Ammonium hydrogen difluoride, solid.                                                                                        |                            |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|     |                                                                                                                         |                        |        |        |        |                               |                         |       |       |           |           |       |                     |
|-----|-------------------------------------------------------------------------------------------------------------------------|------------------------|--------|--------|--------|-------------------------------|-------------------------|-------|-------|-----------|-----------|-------|---------------------|
| D   | Ammonium bifluoride solution, see Ammonium hydrogen difluoride, solution.                                               | .....                  |        |        | .....  |                               | .....                   | ..... | ..... | .....     | .....     | ..... | .....               |
|     | Ammonium bromate .....                                                                                                  | Forbidden<br>Forbidden |        |        | .....  |                               | .....                   | ..... | ..... | .....     | .....     | ..... | .....               |
|     | Ammonium chlorate .....                                                                                                 |                        |        |        | .....  |                               | .....                   | ..... | ..... | .....     | .....     | ..... | .....               |
|     | Ammonium dichromate .....                                                                                               | 5.1                    | UN1439 | II     | 5.1    | IB8, IP2, IP4, T3, TP33       | 152                     | 212   | 242   | 5 kg      | 25 kg     | A     | 52                  |
|     | Ammonium dinitro-o-cresolate, solid.                                                                                    | 6.1                    | UN1843 | II     | 6.1    | IB8, IP2, IP4, T3, TP33       | 153                     | 212   | 242   | 25 kg     | 100 kg    | B     | 36, 65, 66, 77      |
|     | Ammonium dinitro-o-cresolate solution.                                                                                  | 6.1                    | UN3424 | II     | 6.1    | IB2, T7, TP2                  | 153                     | 202   | 243   | 5 L       | 60 L      | B     | 36, 66, 78, 91      |
|     | .....                                                                                                                   | .....                  |        | III    | 6.1    | IB2, T7, TP2                  | 153                     | 203   | 241   | 60 L      | 220 L     | A     | 36, 66, 78, 91      |
|     | Ammonium fluoride .....                                                                                                 | 6.1                    | UN2505 | III    | 6.1    | IB8, IP3, T1, TP33            | 153                     | 213   | 240   | 100 kg    | 200 kg    | A     | 52                  |
|     | Ammonium fluorosilicate .....                                                                                           | 6.1                    | UN2854 | III    | 6.1    | IB8, IP3, T1, TP33            | 153                     | 213   | 240   | 100 kg    | 200 kg    | A     | 52                  |
|     | Ammonium fulminate .....                                                                                                | Forbidden              |        |        | .....  |                               | .....                   | ..... | ..... | .....     | .....     | ..... | .....               |
|     | Ammonium hydrogen sulfate .....                                                                                         |                        | 8      | UN2506 | II     | 8                             | IB8, IP2, IP4, T3, TP33 | 154   | 212   | 240       | 15 kg     | 50 kg | A                   |
|     | Ammonium hydrogendifluoride, solid.                                                                                     | 8                      | UN1727 | II     | 8      | IB8, IP2, IP4, N34, T3, TP33  | 154                     | 212   | 240   | 15 kg     | 50 kg     | A     | 25, 40, 52          |
|     | Ammonium hydrogendifluoride, solution.                                                                                  | 8                      | UN2817 | II     | 8, 6.1 | IB2, N34, T8, TP2, TP12, TP13 | 154                     | 202   | 243   | 1 L       | 30 L      | B     | 40                  |
|     | .....                                                                                                                   | .....                  |        | III    | 8, 6.1 | IB3, N3, T4, TP1, TP12, TP13  | 154                     | 203   | 241   | 5 L       | 60 L      | B     | 40, 95              |
| A W | Ammonium hydrosulfide, solution, see Ammonium sulfide solution.                                                         | .....                  |        |        | .....  |                               | .....                   | ..... | ..... | .....     | .....     | ..... | .....               |
|     | Ammonium hydroxide, see Ammonia solutions, etc.                                                                         | .....                  |        |        | .....  |                               | .....                   | ..... | ..... | .....     | .....     | ..... | .....               |
|     | Ammonium metavanadate .....                                                                                             | 6.1                    | UN2859 | II     | 6.1    | IB8, IP2, IP4, T3, TP33       | 153                     | 212   | 242   | 25 kg     | 100 kg    | A     | 44, 89, 100, 141    |
|     | Ammonium nitrate based fertilizer.                                                                                      | 5.1                    | UN2067 | III    | 5.1    | 52, 150, IB8, IP3, T1, TP33   | 152                     | 213   | 240   | 25 kg     | 100 kg    | B     | 48, 59, 60, 66, 117 |
| D   | Ammonium nitrate based fertilizer.                                                                                      | 9                      | UN2071 | III    | 9      | 132, IB8, IP3                 | 155                     | 213   | 240   | 200 kg    | 200 kg    | A     | .....               |
|     | Ammonium nitrate emulsion or Ammonium nitrate suspension or Ammonium nitrate gel, intermediate for blasting explosives. | 5.1                    | UN3375 | II     | 5.1    | 147, 163                      | None                    | 214   | 214   | Forbidden | Forbidden | D     | 48, 59, 60, 66, 124 |
|     | Ammonium nitrate-fuel oil mixture containing only prilled ammonium nitrate and fuel oil.                                | 1.5D                   | NA0331 | II     | 1.5D   | ..                            | None                    | 62    | None  | Forbidden | Forbidden | 10    | 19E                 |
|     | Ammonium nitrate, liquid (hot concentrated solution).                                                                   | 5.1                    | UN2426 | .....  | 5.1    | B5, T7                        | None                    | None  | 243   | Forbidden | Forbidden | D     | 59, 60              |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102) | (8)                   |           |           | (9)                                             |                      | (10)            |                  |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|---------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|------------------|
|          |                                                                                                                                                                            |                           |                          |     |             |                                 | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |                  |
|          |                                                                                                                                                                            |                           |                          |     |             |                                 | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other            |
| (1)      | (2)                                                                                                                                                                        | (3)                       | (4)                      | (5) | (6)         | (7)                             | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                 | (10A)           | (10B)            |
|          | Ammonium nitrate, with more than 0.2 percent combustible substances, including any organic substance calculated as carbon, to the exclusion of any other added substance.  | 1.1D                      | UN0222                   | II  | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | 19E              |
|          | Ammonium nitrate, with not more than 0.2% total combustible material, including any organic substance, calculated as carbon to the exclusion of any other added substance. | 5.1                       | UN1942                   | III | 5.1 .....   | A1, A29, IB8, IP3, T1, TP33     | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | 48, 59, 60, 116  |
|          | Ammonium nitrite .....                                                                                                                                                     | Forbidden                 |                          |     | .....       |                                 | .....                 | .....     | .....     | .....                                           | .....                |                 | .....            |
|          | Ammonium perchlorate .....                                                                                                                                                 | 1.1D                      | UN0402                   | II  | 1.1D ..     | 107                             | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | 19E              |
|          | Ammonium perchlorate .....                                                                                                                                                 | 5.1                       | UN1442                   | II  | 5.1 .....   | 107, A9, IB6, IP2, T3, TP33     | 152 .....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg                | E               | 58, 69           |
|          | Ammonium permanganate .....                                                                                                                                                | Forbidden                 |                          |     | .....       |                                 | .....                 | .....     | .....     | .....                                           | .....                |                 | .....            |
|          | Ammonium persulfate .....                                                                                                                                                  | 5.1                       | UN1444                   | III | 5.1 .....   | A1, A29, IB8, IP3, T1, TP33     | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | .....            |
|          | Ammonium picrate, dry or wetted with less than 10 percent water, by mass.                                                                                                  | 1.1D                      | UN0004                   | II  | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | 5E, 19E          |
|          | Ammonium picrate, wetted with not less than 10 percent water, by mass.                                                                                                     | 4.1                       | UN1310                   | I   | 4.1 .....   | 23, A2, N41                     | None ....             | 211 ..... | None .... | 0.5 kg                                          | 0.5 kg               | D               | 28, 36           |
|          | Ammonium polysulfide, solution                                                                                                                                             | 8                         | UN2818                   | II  | 8, 6.1      | IB2, T7, TP2, TP13              | 154 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 12, 40, 52       |
|          | .....                                                                                                                                                                      |                           |                          | III | 8, 6.1      | IB3, T4, TP1, TP13              | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                 | B               | 12, 40, 52       |
|          | Ammonium polyvanadate .....                                                                                                                                                | 6.1                       | UN2861                   | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33         | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | A               | 44, 89, 100, 141 |
|          | Ammonium silicofluoride, see Ammonium fluorosilicate.                                                                                                                      |                           |                          |     | .....       |                                 | .....                 | .....     | .....     | .....                                           | .....                |                 | .....            |
|          | Ammonium sulfide solution .....                                                                                                                                            | 8                         | UN2683                   | II  | 8, 6.1, 3.  | IB1, T7, TP2, TP13              | 154 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 12, 22, 52, 100  |
|          | Ammunition, blank, see Cartridges for weapons, blank.                                                                                                                      |                           |                          |     | .....       |                                 | .....                 | .....     | .....     | .....                                           | .....                |                 | .....            |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|                                                                                                                                                                                    |       |        |       |          |       |       |       |       |       |           |           |       |                            |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-------|----------|-------|-------|-------|-------|-------|-----------|-----------|-------|----------------------------|
| Ammunition, illuminating <i>with or without burster, expelling charge or propelling charge.</i>                                                                                    | 1.2G  | UN0171 | II    | 1.2G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 03    | .....                      |
| Ammunition, illuminating <i>with or without burster, expelling charge or propelling charge.</i>                                                                                    | 1.3G  | UN0254 | II    | 1.3G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 03    | .....                      |
| Ammunition, illuminating <i>with or without burster, expelling charge or propelling charge.</i>                                                                                    | 1.4G  | UN0297 | II    | 1.4G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | 75 kg     | 02    | .....                      |
| Ammunition, incendiary <i>liquid or gel, with burster, expelling charge or propelling charge.</i>                                                                                  | 1.3J  | UN0247 | II    | 1.3J ... | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 04    | 23E                        |
| Ammunition, incendiary (water-activated contrivances) <i>with burster, expelling charge or propelling charge, see Contrivances, water-activated, etc..</i>                         | ..... | .....  | ..... | .....    | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....                      |
| Ammunition, incendiary, white phosphorus, <i>with burster, expelling charge or propelling charge.</i>                                                                              | 1.2H  | UN0243 | II    | 1.2H ..  | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 08    | 8E,<br>14E,<br>15E,<br>17E |
| Ammunition, incendiary, white phosphorus, <i>with burster, expelling charge or propelling charge.</i>                                                                              | 1.3H  | UN0244 | II    | 1.3H ..  | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 08    | 8E,<br>14E,<br>15E,<br>17E |
| Ammunition, incendiary <i>with or without burster, expelling charge, or propelling charge.</i>                                                                                     | 1.2G  | UN0009 | II    | 1.2G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 03    | .....                      |
| Ammunition, incendiary <i>with or without burster, expelling charge, or propelling charge.</i>                                                                                     | 1.3G  | UN0010 | II    | 1.3G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 03    | .....                      |
| Ammunition, incendiary <i>with or without burster, expelling charge or propelling charge.</i>                                                                                      | 1.4G  | UN0300 | II    | 1.4G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | 75 kg     | 02    | .....                      |
| Ammunition, practice .....                                                                                                                                                         | 1.4G  | UN0362 | II    | 1.4G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | 75 kg     | 02    | .....                      |
| Ammunition, practice .....                                                                                                                                                         | 1.3G  | UN0488 | II    | 1.3G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | Forbidden | 03    | .....                      |
| Ammunition, proof .....                                                                                                                                                            | 1.4G  | UN0363 | II    | 1.4G ..  | ..... | 62    | ..... | None  | ....  | Forbidden | 75 kg     | 02    | .....                      |
| Ammunition, rocket, <i>see Warheads, rocket etc.</i>                                                                                                                               | ..... | .....  | ..... | .....    | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....                      |
| Ammunition, SA (small arms), <i>see Cartridges for weapons, etc.</i>                                                                                                               | ..... | .....  | ..... | .....    | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....                      |
| Ammunition, smoke (water-activated contrivances), white phosphorus, <i>with burster, expelling charge or propelling charge, see Contrivances, water-activated, etc. (UN 0248).</i> | ..... | .....  | ..... | .....    | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....                      |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                                                  | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes   | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |                       |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|---------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-----------------------|
|          |                                                                                                                                                                                                              |                            |                            |     |               |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                       |
|          |                                                                                                                                                                                                              |                            |                            |     |               |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                 |
| (1)      | (2)                                                                                                                                                                                                          | (3)                        | (4)                        | (5) | (6)           | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)                 |
|          | <i>Ammunition, smoke (water-acti- vated contrivances), without white phosphorus or phosphides, with burster, ex- pelling charge or propelling charge, see Contrivances, water-activated, etc. (UN 0249).</i> | .....                      |                            |     | .....         |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                 |
|          | <i>Ammunition smoke, white phos- phorus with burster,expelling charge, or propelling charge.</i>                                                                                                             | 1.2H                       | UN0245                     | II  | 1.2H ..       |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | 8E, 14E, 15E, 17E     |
|          | <i>Ammunition, smoke, white phos- phorus with burster, expelling charge, or propelling charge.</i>                                                                                                           | 1.3H                       | UN0246                     | II  | 1.3H ..       |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | 8E, 14E, 15E, 17E     |
|          | <i>Ammunition, smoke with or with- out burster, expelling charge or propelling charge.</i>                                                                                                                   | 1.2G                       | UN0015                     | II  | 1.2G ..       |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             |                  | 8E, 17E, 20E          |
|          | <i>Ammunition, smoke with or with- out burster, expelling charge or propelling charge.</i>                                                                                                                   | 1.3G                       | UN0016                     | II  | 1.3G ..       |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             |                  | 8E, 17E, 20E          |
|          | <i>Ammunition, smoke with or with- out burster, expelling charge or propelling charge.</i>                                                                                                                   | 1.4G                       | UN0303                     | II  | 1.4G ..       |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | 75 kg                 |                  | 7E, 8E, 14E, 15E, 17E |
|          | <i>Ammunition, sporting, see Car- tridges for weapons, etc. (UN 0012; UN 0328; UN 0339).</i>                                                                                                                 | .....                      |                            |     | .....         |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                 |
|          | <i>Ammunition, tear-producing, non-explosive, without burster or expelling charge, non-fuzed.</i>                                                                                                            | 6.1                        | UN2017                     | II  | 6.1, 8        |                                  | None ....             | 212 ..... | None .... | Forbidden                                       | 50 kg                 | E                | 13, 40                |
|          | <i>Ammunition, tear-producing with burster, expelling charge or propelling charge.</i>                                                                                                                       | 1.2G                       | UN0018                     | II  | 1.2G, 8, 6.1. |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             |                  | 8E, 17E, 20E          |
|          | <i>Ammunition, tear-producing with burster, expelling charge or propelling charge.</i>                                                                                                                       | 1.3G                       | UN0019                     | II  | 1.3G, 8, 6.1. |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             |                  | 8E, 17E, 20E          |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                                                                |       |        |     |               |                                     |       |       |       |       |      |           |           |        |                               |
|---|------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-----|---------------|-------------------------------------|-------|-------|-------|-------|------|-----------|-----------|--------|-------------------------------|
|   | Ammunition, tear-producing with burster, expelling charge or propelling charge.                                                                | 1.4G  | UN0301 | II  | 1.4G, 8, 6.1. |                                     | ..... | 62    | ..... | None  | .... | Forbidden | 75 kg     |        | 7E, 8E, 14E, 15E, 17E, 13, 40 |
|   | Ammunition, toxic, non-explosive, without burster or expelling charge, non-fuzed.                                                              | 6.1   | UN2016 | II  | 6.1           | .....                               | None  | ....  | 212   | ..... | None | ....      | Forbidden | 100 kg | E                             |
|   | Ammunition, toxic (water-activated contrivances), with burster, expelling charge or propelling charge, see Contrivances, water-activated, etc. | ..... |        |     | .....         |                                     | ..... |       |       |       |      | .....     | .....     |        | .....                         |
| G | Ammunition, toxic with burster, expelling charge, or propelling charge.                                                                        | 1.2K  | UN0020 | II  | 1.2K, 6.1.    |                                     | ..... | 62    | ..... | None  | .... | Forbidden | Forbidden | 08     | 8E, 14E, 15E, 17E             |
| G | Ammunition, toxic with burster, expelling charge, or propelling charge.                                                                        | 1.3K  | UN0021 | II  | 1.3K, 6.1.    |                                     | ..... | 62    | ..... | None  | .... | Forbidden | Forbidden | 08     | 8E, 14E, 15E, 17E             |
|   | Amyl acetates                                                                                                                                  | 3     | UN1104 | III | 3             | B1, IB3, T2, TP1                    | 150   | ..... | 203   | ..... | 242  | .....     | 60 L      | 220 L  | A                             |
|   | Amyl acid phosphate                                                                                                                            | 8     | UN2819 | III | 8             | IB3, T4, TP1                        | 154   | ..... | 203   | ..... | 241  | .....     | 5 L       | 60 L   | A                             |
|   | Amyl butyrates                                                                                                                                 | 3     | UN2620 | III | 3             | B1, IB3, T2, TP1                    | 150   | ..... | 203   | ..... | 242  | .....     | 60 L      | 220 L  | A                             |
|   | Amyl chlorides                                                                                                                                 | 3     | UN1107 | II  | 3             | IB2, T4, TP1                        | 150   | ..... | 202   | ..... | 242  | .....     | 5 L       | 60 L   | B                             |
|   | Amyl formates                                                                                                                                  | 3     | UN1109 | III | 3             | B1, IB3, T2, TP1                    | 150   | ..... | 203   | ..... | 242  | .....     | 60 L      | 220 L  | A                             |
|   | Amyl mercaptans                                                                                                                                | 3     | UN1111 | II  | 3             | A3, A6, IB2, T4, TP1                | None  | ....  | 202   | ..... | 242  | .....     | 5 L       | 60 L   | B                             |
|   | n-Amyl methyl ketone                                                                                                                           | 3     | UN1110 | III | 3             | B1, IB3, T2, TP1                    | 150   | ..... | 203   | ..... | 242  | .....     | 60 L      | 220 L  | A                             |
|   | Amyl nitrate                                                                                                                                   | 3     | UN1112 | III | 3             | B1, IB3, T2, TP1                    | 150   | ..... | 203   | ..... | 242  | .....     | 60 L      | 220 L  | A                             |
|   | Amyl nitrites                                                                                                                                  | 3     | UN1113 | II  | 3             | IB2, T4, TP1                        | 150   | ..... | 202   | ..... | 242  | .....     | 5 L       | 60 L   | E                             |
|   | Amylamines                                                                                                                                     | 3     | UN1106 | II  | 3, 8          | IB2, T7, TP1                        | 150   | ..... | 202   | ..... | 243  | .....     | 1 L       | 5 L    | B                             |
|   |                                                                                                                                                | ..... |        | III | 3, 8          | B1, IB3, T4, TP1                    | 150   | ..... | 203   | ..... | 242  | .....     | 5 L       | 60 L   | A                             |
|   | Amyltrimethylsilane                                                                                                                            | 8     | UN1728 | II  | 8             | A7, B2, B6, IB2, N34, T7, TP2, TP13 | None  | ....  | 202   | ..... | 242  | .....     | Forbidden | 30 L   | C                             |
|   | Anhydrous ammonia, see Ammonia, anhydrous.                                                                                                     | ..... |        |     | .....         |                                     | ..... |       |       |       |      | .....     | .....     |        | .....                         |
|   | Anhydrous hydrofluoric acid, see Hydrogen fluoride, anhydrous.                                                                                 | ..... |        |     | .....         |                                     | ..... |       |       |       |      | .....     | .....     |        | .....                         |
| + | Aniline                                                                                                                                        | 6.1   | UN1547 | II  | 6.1           | IB2, T7, TP2                        | 153   | ..... | 202   | ..... | 243  | .....     | 5 L       | 60 L   | A                             |
|   | Aniline hydrochloride                                                                                                                          | 6.1   | UN1548 | III | 6.1           | IB8, IP3, T1, TP33                  | 153   | ..... | 213   | ..... | 240  | .....     | 100 kg    | 200 kg | A                             |
|   | Aniline oil, see Aniline                                                                                                                       | ..... |        |     | .....         |                                     | ..... |       |       |       |      | .....     | .....     |        | .....                         |
|   | Anisidines                                                                                                                                     | 6.1   | UN2431 | III | 6.1           | IB3, T4, TP1                        | 153   | ..... | 203   | ..... | 241  | .....     | 60 L      | 220 L  | A                             |
|   | Anisole                                                                                                                                        | 3     | UN2222 | III | 3             | B1, IB3, T2, TP1                    | 150   | ..... | 203   | ..... | 242  | .....     | 60 L      | 220 L  | A                             |
|   | Anisoyl chloride                                                                                                                               | 8     | UN1729 | II  | 8             | B2, B4, IB8, IP2, IP4, T3, TP33     | 154   | ..... | 212   | ..... | 240  | .....     | 15 kg     | 50 kg  | A                             |
|   | Anti-freeze, liquid, see Flammable liquids, n.o.s..                                                                                            | ..... |        |     | .....         |                                     | ..... |       |       |       |      | .....     | .....     |        | .....                         |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                  | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)       | (8)                   |           |           | (9)                                             |                       | (10)             |                  |
|----------|------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|------------------|
|          |                                                                              |                            |                            |     |             |                                        | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                  |
|          |                                                                              |                            |                            |     |             |                                        | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other            |
| (1)      | (2)                                                                          | (3)                        | (4)                        | (5) | (6)         | (7)                                    | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)            |
|          | <i>Antimonous chloride, see Anti- mony trichloride.</i>                      |                            |                            |     |             |                                        |                       |           |           |                                                 |                       |                  |                  |
|          | Antimony compounds, inorganic, liquid, n.o.s..                               | 6.1                        | UN3141                     | III | 6.1         | 35, IB3, T7, TP1, TP28                 | 153                   | 203       | 241       | 60 L                                            | 220 L                 | A                |                  |
|          | Antimony compounds, inorganic, solid, n.o.s..                                | 6.1                        | UN1549                     | III | 6.1         | 35, IB8, IP3, T1, TP33                 | 153                   | 213       | 240       | 100 kg                                          | 200 kg                | A                |                  |
|          | Antimony lactate                                                             | 6.1                        | UN1550                     | III | 6.1         | IB8, IP3, T1, TP33                     | 153                   | 213       | 240       | 100 kg                                          | 200 kg                | A                |                  |
|          | Antimony pentachloride, liquid ...                                           | 8                          | UN1730                     | II  | 8           | B2, IB2, T7, TP2                       | None                  | 202       | 242       | 1 L                                             | 30 L                  | C                | 40               |
|          | Antimony pentachloride, solu- tions.                                         | 8                          | UN1731                     | II  | 8           | B2, IB2, T7, TP2                       | 154                   | 202       | 242       | 1 L                                             | 30 L                  | C                | 40               |
|          |                                                                              |                            |                            | III | 8           | IB3, T4, TP1                           | 154                   | 203       | 241       | 5 L                                             | 60 L                  | C                | 40               |
|          | Antimony pentafluoride                                                       | 8                          | UN1732                     | II  | 8, 6.1      | A3, A6, A7, A10, IB2, N3, N36, T7, TP2 | None                  | 202       | 243       | Forbidden                                       | 30 L                  | D                | 44, 89, 100, 141 |
|          | Antimony potassium tartrate                                                  | 6.1                        | UN1551                     | III | 6.1         | IB8, IP3, T1, TP33                     | 153                   | 213       | 240       | 100 kg                                          | 200 kg                | A                |                  |
|          | Antimony powder                                                              | 6.1                        | UN2871                     | III | 6.1         | IB8, IP3, T1, TP33                     | 153                   | 213       | 240       | 100 kg                                          | 200 kg                | A                |                  |
|          | <i>Antimony sulfide and a chlorate, mixtures of.</i>                         | Forbidden                  |                            |     |             |                                        |                       |           |           |                                                 |                       |                  |                  |
|          | <i>Antimony sulfide, solid, see Anti- mony compounds, inorganic, n.o.s..</i> |                            |                            |     |             |                                        |                       |           |           |                                                 |                       |                  |                  |
|          | Antimony trichloride, liquid                                                 | 8                          | UN1733                     | II  | 8           | B2, IB2                                | 154                   | 202       | 242       | 1 L                                             | 30 L                  | C                | 40               |
|          | Antimony trichloride, solid                                                  | 8                          | UN1733                     | II  | 8           | IB8, IP2, IP4, T3, TP33                | 154                   | 212       | 240       | 15 kg                                           | 50 kg                 | A                | 40.              |
|          | <i>Aqua ammonia, see Ammonia solution, etc.</i>                              |                            |                            |     |             |                                        |                       |           |           |                                                 |                       |                  |                  |
|          | Argon, compressed                                                            | 2.2                        | UN1006                     |     | 2.2         |                                        | 306                   | 302       | 314, 315. | 75 kg                                           | 150 kg                | A                |                  |
|          | Argon, refrigerated liquid ( <i>cryo- genic liquid</i> ).                    | 2.2                        | UN1951                     |     | 2.2         | T75, TP5                               | 320                   | 316       | 318       | 50 kg                                           | 500 kg                | B                |                  |
|          | Arsenic                                                                      | 6.1                        | UN1558                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33                | 153                   | 212       | 242       | 25 kg                                           | 100 kg                | A                |                  |
|          | Arsenic acid, liquid                                                         | 6.1                        | UN1553                     | I   | 6.1         | T20, TP2, TP7, TP13                    | None                  | 201       | 243       | 1 L                                             | 30 L                  | B                | 46               |
|          | Arsenic acid, solid                                                          | 6.1                        | UN1554                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33                | 153                   | 212       | 242       | 25 kg                                           | 100 kg                | A                |                  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                                                  |           |        |     |        |                                                  |      |     |     |           |           |   |         |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-----|--------|--------------------------------------------------|------|-----|-----|-----------|-----------|---|---------|
| Arsenic bromide .....                                                                                                                                            | 6.1       | UN1555 | II  | 6.1    | IB8, IP2, IP4, T3, TP33                          | 153  | 212 | 242 | 25 kg     | 100 kg    | A | 12, 40  |
| <i>Arsenic chloride, see Arsenic trichloride.</i>                                                                                                                |           |        |     |        |                                                  |      |     |     |           |           |   |         |
| Arsenic compounds, liquid, n.o.s. inorganic, including arsenates, n.o.s.; arsenites, n.o.s.; arsenic sulfides, n.o.s.; and organic compounds of arsenic, n.o.s.. | 6.1       | UN1556 | I   | 6.1    | T14, TP2, TP13, TP27                             | None | 201 | 243 | 1 L       | 30 L      | B | 40, 137 |
|                                                                                                                                                                  |           |        | II  | 6.1    | IB2, T11, TP2, TP13, TP27                        | 153  | 202 | 243 | 5 L       | 60 L      | B | 40, 137 |
|                                                                                                                                                                  |           |        | III | 6.1    | IB3, T7, TP2, TP28                               | 153  | 203 | 241 | 60 L      | 220 L     | B | 40, 137 |
| Arsenic compounds, solid, n.o.s. inorganic, including arsenates, n.o.s.; arsenites, n.o.s.; arsenic sulfides, n.o.s.; and organic compounds of arsenic, n.o.s..  | 6.1       | UN1557 | I   | 6.1    | IB7, IP1, T6, TP33                               | None | 211 | 242 | 5 kg      | 50 kg     | A | 137     |
|                                                                                                                                                                  |           |        | II  | 6.1    | IB8, IP2, IP4, T3, TP33                          | 153  | 212 | 242 | 25 kg     | 100 kg    | A | 137     |
|                                                                                                                                                                  |           |        | III | 6.1    | IB8, IP3, T1, TP33                               | 153  | 213 | 240 | 100 kg    | 200 kg    | A | 137     |
| Arsenic pentoxide .....                                                                                                                                          | 6.1       | UN1559 | II  | 6.1    | IB8, IP2, IP4, T3, TP33                          | 153  | 212 | 242 | 25 kg     | 100 kg    | A |         |
| <i>Arsenic sulfide and a chlorate, mixtures of.</i>                                                                                                              | Forbidden |        |     |        |                                                  |      |     |     |           |           |   |         |
| Arsenic trichloride .....                                                                                                                                        | 6.1       | UN1560 | I   | 6.1    | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45 | None | 227 | 244 | Forbidden | Forbidden | B | 40      |
| Arsenic trioxide .....                                                                                                                                           | 6.1       | UN1561 | II  | 6.1    | IB8, IP2, IP4, T3, TP33                          | 153  | 212 | 242 | 25 kg     | 100 kg    | A |         |
| <i>Arsenic, white, solid, see Arsenic trioxide.</i>                                                                                                              |           |        |     |        |                                                  |      |     |     |           |           |   |         |
| Arsenical dust .....                                                                                                                                             | 6.1       | UN1562 | II  | 6.1    | IB8, IP2, IP4, T3, TP33                          | 153  | 212 | 242 | 25 kg     | 100 kg    | A |         |
| Arsenical pesticides, liquid, flammable, toxic, flash point less than 23 degrees C.                                                                              | 3         | UN2760 | I   | 3, 6.1 | T14, TP2, TP13, TP27                             | None | 201 | 243 | Forbidden | 30 L      | B | 40      |
|                                                                                                                                                                  |           |        | II  | 3, 6.1 | IB2, T11, TP2, TP13, TP27                        | 150  | 202 | 243 | 1 L       | 60 L      | B | 40      |
| Arsenical pesticides, liquid, toxic                                                                                                                              | 6.1       | UN2994 | I   | 6.1    | T14, TP2, TP13, TP27                             | None | 201 | 243 | 1 L       | 30 L      | B | 40      |
|                                                                                                                                                                  |           |        | II  | 6.1    | IB2, T11, TP2, TP13, TP27                        | 153  | 202 | 243 | 5 L       | 60 L      | B | 40      |
|                                                                                                                                                                  |           |        | III | 6.1    | IB3, T7, TP2, TP28                               | 153  | 203 | 241 | 60 L      | 220 L     | A | 40      |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                    | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |                    |
|----------|------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------------------|
|          |                                                                                                |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                    |
|          |                                                                                                |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other              |
| (1)      | (2)                                                                                            | (3)                        | (4)                        | (5)   | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)              |
|          | Arsenical pesticides, liquid, toxic, flammable, <i>flash point not less than 23 degrees C.</i> | 6.1                        | UN2993                     | I     | 6.1, 3      | T14, TP2, TP13, TP27             | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40                 |
|          | .....                                                                                          | .....                      | .....                      | II    | 6.1, 3      | IB2, T11, TP2, TP13, TP27        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | 40                 |
|          | .....                                                                                          | .....                      | .....                      | III   | 6.1, 3      | B1, IB3, T7, TP2, TP28           | 153 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | 40                 |
|          | Arsenical pesticides, solid, toxic                                                             | 6.1                        | UN2759                     | I     | 6.1 ....    | IB7, IP1, T6, TP33               | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                 | A                | 40                 |
|          | .....                                                                                          | .....                      | .....                      | II    | 6.1 ....    | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | 40                 |
|          | .....                                                                                          | .....                      | .....                      | III   | 6.1 ....    | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | 40                 |
|          | <i>Arsenious acid, solid, see Ar- senic trioxide.</i>                                          | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....              |
|          | <i>Arsenious and mercuric iodide solution, see Arsenic com- pounds, liquid, n.o.s..</i>        | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....              |
|          | Arsine .....                                                                                   | 2.3                        | UN2188                     | ..... | 2.3, 2.1.   | 1                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40                 |
|          | Articles, explosive, extremely in- sensitive or Articles, EEI.                                 | 1.6N                       | UN0486                     | II    | 1.6N ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               |                    |
| G        | Articles, explosive, n.o.s .....                                                               | 1.4S                       | UN0349                     | II    | 1.4S ...    | .....                            | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               |                    |
| G        | Articles, explosive, n.o.s .....                                                               | 1.4B                       | UN0350                     | II    | 1.4B ...    | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 06               |                    |
| G        | Articles, explosive, n.o.s .....                                                               | 1.4C                       | UN0351                     | II    | 1.4C ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               |                    |
| G        | Articles, explosive, n.o.s .....                                                               | 1.4D                       | UN0352                     | II    | 1.4D ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               |                    |
| G        | Articles, explosive, n.o.s .....                                                               | 1.4G                       | UN0353                     | II    | 1.4G ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               |                    |
| G        | Articles, explosive, n.o.s .....                                                               | 1.1L                       | UN0354                     | II    | 1.1L ...    | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | 8E, 14E, 15E, 17E. |
| G        | Articles, explosive, n.o.s .....                                                               | 1.2L                       | UN0355                     | II    | 1.2L ...    | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | 8E, 14E, 15E, 17E. |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|     |                                                                                                                                                |           |        |       |          |                       |              |           |           |           |           |                             |        |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|----------|-----------------------|--------------|-----------|-----------|-----------|-----------|-----------------------------|--------|
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.3L      | UN0356 | II    | 1.3L ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 08        | 8E,<br>14E,<br>15E,<br>17E. |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.1C      | UN0462 | II    | 1.1C ..  | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.1D      | UN0463 | II    | 1.1D ..  | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.1E      | UN0464 | II    | 1.1E ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.1F      | UN0465 | II    | 1.1F ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 08        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.2C      | UN0466 | II    | 1.2C ..  | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.2D      | UN0467 | II    | 1.2D ..  | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07.       |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.2E      | UN0468 | II    | 1.2E ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.2F      | UN0469 | II    | 1.2F ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 08        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.3C      | UN0470 | II    | 1.3C ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.4E      | UN0471 | II    | 1.4E ... | None ....             | 62 .....     | None .... | Forbidden | 75 kg     | 06        |                             |        |
| G   | Articles, explosive, n.o.s .....                                                                                                               | 1.4F      | UN0472 | II    | 1.4F ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 08        |                             |        |
|     | Articles, pressurized pneumatic<br>or hydraulic containing non-<br>flammable gas.                                                              | 2.2       | UN3164 | ..... | 2.2 .... | 306 .....             | 302,<br>304. | None .... | No limit  | No limit  | A         | .....                       |        |
|     | Articles, pyrophoric .....                                                                                                                     | 1.2L      | UN0380 | II    | 1.2L ... | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 08        | 8E,<br>14E,<br>15E,<br>17E  |        |
|     | Articles, pyrotechnic for tech-<br>nical purposes.                                                                                             | 1.1G      | UN0428 | II    | 1.1G ..  | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        | .....                       |        |
|     | Articles, pyrotechnic for tech-<br>nical purposes.                                                                                             | 1.2G      | UN0429 | II    | 1.2G ..  | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        | .....                       |        |
|     | Articles, pyrotechnic for tech-<br>nical purposes.                                                                                             | 1.3G      | UN0430 | II    | 1.3G ..  | None ....             | 62 .....     | None .... | Forbidden | Forbidden | 07        | .....                       |        |
|     | Articles, pyrotechnic for tech-<br>nical purposes.                                                                                             | 1.4G      | UN0431 | II    | 1.4G ..  | None ....             | 62 .....     | None .... | Forbidden | 75 kg     | 06        | .....                       |        |
|     | Articles, pyrotechnic for tech-<br>nical purposes.                                                                                             | 1.4S      | UN0432 | II    | 1.4S ... | None ....             | 62 .....     | None .... | 25 kg     | 100 kg    | 05        | .....                       |        |
| D   | Asbestos .....                                                                                                                                 | 9         | NA2212 | III   | 9 .....  | 156, IB8, IP2,<br>IP4 | 155 .....    | 216 ..... | 240 ..... | 200 kg    | 200 kg    | A                           | 34, 40 |
|     | Ascaridole (organic peroxide) ....                                                                                                             | Forbidden |        |       |          |                       |              |           |           |           |           |                             |        |
| D   | Asphalt, at or above its flash<br>point.                                                                                                       | 3         | NA1999 | III   | 3 .....  | IB3, T1, TP3          | 150 .....    | 203 ..... | 247 ..... | Forbidden | Forbidden | D                           | .....  |
| D   | Asphalt, cut back, see Tars, liq-<br>uid, etc.                                                                                                 | .....     |        |       |          |                       |              |           |           |           |           |                             |        |
|     | Automobile, motorcycle, tractor,<br>other self-propelled vehicle,<br>engine, or other mechanical<br>apparatus, see Vehicles or<br>Battery etc. | .....     |        |       |          |                       |              |           |           |           |           |                             |        |
| A G | Aviation regulated liquid, n.o.s. ...                                                                                                          | 9         | UN3334 | ..... | 9 .....  | A35                   | 155 .....    | 204 ..... | .....     | No limit  | No limit  | A                           | .....  |
| A G | Aviation regulated solid, n.o.s. ...                                                                                                           | 9         | UN3335 | ..... | 9 .....  | A35                   | 155 .....    | 204 ..... | .....     | No limit  | No limit  | A                           | .....  |
|     | Azaurolic acid (salt of) (dry) .....                                                                                                           | Forbidden |        |       |          |                       |              |           |           |           |           |                             |        |
|     | Azido guanidine picrate (dry) .....                                                                                                            | Forbidden |        |       |          |                       |              |           |           |           |           |                             |        |
|     | 5-Azido-1-hydroxy tetrazole .....                                                                                                              | Forbidden |        |       |          |                       |              |           |           |           |           |                             |        |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                    | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)     | (8)                   |           |       | (9)                                             |                       | (10)             |                    |
|----------|------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|--------------------------------------|-----------------------|-----------|-------|-------------------------------------------------|-----------------------|------------------|--------------------|
|          |                                                                                                |                            |                            |     |             |                                      | Packaging (§ 173.***) |           |       | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                    |
|          |                                                                                                |                            |                            |     |             |                                      | Excep- tions          | Non- bulk | Bulk  | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other              |
| (1)      | (2)                                                                                            | (3)                        | (4)                        | (5) | (6)         | (7)                                  | (8A)                  | (8B)      | (8C)  | (9A)                                            | (9B)                  | (10A)            | (10B)              |
|          | <i>Azido hydroxy tetrazole (mer- cury and silver salts).</i>                                   | Forbidden                  |                            |     | .....       |                                      | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....              |
|          | <i>3-Azido-1,2-Propylene glycol dinitrate.</i>                                                 | Forbidden                  |                            |     | .....       |                                      | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....              |
|          | <i>Azidodithiocarbonic acid</i> .....                                                          | Forbidden                  |                            |     | .....       |                                      | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....              |
|          | <i>Azidoethyl nitrate</i> .....                                                                | Forbidden                  |                            |     | .....       |                                      | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....              |
|          | <i>1-Aziridinylphosphine oxide- (tris), see Tris-(1-aziridinyl) phosphine oxide, solution.</i> | .....                      |                            |     | .....       |                                      | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....              |
|          | <i>Azodicarbonamide</i> .....                                                                  | 4.1                        | UN3242                     | II  | 4.1         | 38, IB8, T3, TP33                    | 151                   | 212       | 240   | Forbidden                                       | Forbidden             | D                | 12, 52, 53, 74     |
|          | <i>Azotetrazole (dry)</i> .....                                                                | Forbidden                  |                            |     | .....       |                                      | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....              |
|          | <i>Barium</i> .....                                                                            | 4.3                        | UN1400                     | II  | 4.3         | A19, IB7, IP2, T3, TP33              | 151                   | 212       | 241   | 15 kg                                           | 50 kg                 | E                | 52                 |
|          | <i>Barium alloys, pyrophoric</i> .....                                                         | 4.2                        | UN1854                     | I   | 4.2         | T21, TP7, TP33                       | None                  | 181       | None  | Forbidden                                       | Forbidden             | D                | .....              |
|          | <i>Barium azide, dry or wetted with less than 50 percent water, by mass.</i>                   | 1.1A                       | UN0224                     | II  | 1.1A, 6.1.  | 111, 117                             | None                  | 62        | None  | Forbidden                                       | Forbidden             | 12               | .....              |
|          | <i>Barium azide, wetted with not less than 50 percent water, by mass.</i>                      | 4.1                        | UN1571                     | I   | 4.1, 6.1.   | 162, A2                              | None                  | 182       | None  | Forbidden                                       | 0.5 kg                | D                | 28                 |
|          | <i>Barium bromate</i> .....                                                                    | 5.1                        | UN2719                     | II  | 5.1, 6.1.   | IB8, IP2, IP4, T3, TP33              | 152                   | 212       | 242   | 5 kg                                            | 25 kg                 | A                | 56, 58             |
|          | <i>Barium chlorate, solid</i> .....                                                            | 5.1                        | UN1445                     | II  | 5.1, 6.1.   | A9, IB6, IP2, N34, T3, TP33          | 152                   | 212       | 242   | 5 kg                                            | 25 kg                 | A                | 56, 58             |
|          | <i>Barium chlorate, solution</i> .....                                                         | 5.1                        | UN3405                     | II  | 5.1, 6.1.   | A9, IB2, N34, T4, TP1                | 152                   | 202       | 243   | 1 L                                             | 5 L                   | A                | 56, 58, 133        |
|          | .....                                                                                          | .....                      |                            | III | 5.1, 6.1.   | A9, IB2, N34, T4, TP1                | 152                   | 203       | 242   | 2.5 L                                           | 30 L                  | A                | 56, 58, 133        |
|          | <i>Barium compounds, n.o.s.</i> .....                                                          | 6.1                        | UN1564                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33              | 153                   | 212       | 242   | 25 kg                                           | 100 kg                | A                | .....              |
|          | .....                                                                                          | .....                      |                            | III | 6.1         | IB8, IP3, T1, TP33                   | 153                   | 213       | 240   | 100 kg                                          | 200 kg                | A                | .....              |
|          | <i>Barium cyanide</i> .....                                                                    | 6.1                        | UN1565                     | I   | 6.1         | IB7, IP1, N74, N75, T6, TP33         | None                  | 211       | 242   | 5 kg                                            | 50 kg                 | A                | 40, 52             |
|          | <i>Barium hypochlorite with more than 22 percent available chlorine.</i>                       | 5.1                        | UN2741                     | II  | 5.1, 6.1.   | A7, A9, IB8, IP2, IP4, N34, T3, TP33 | 152                   | 212       | None  | 5 kg                                            | 25 kg                 | B                | 4, 52, 56, 58, 106 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                                                                        |           |        |       |          |                                              |       |       |       |             |              |          |                |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|----------|----------------------------------------------|-------|-------|-------|-------------|--------------|----------|----------------|
| Barium nitrate .....                                                                                                                                                                   | 5.1       | UN1446 | II    | 5.1, 6.1 | IB8, IP2, IP4, T3, TP33                      | 152   | 212   | 242   | 5 kg        | 25 kg        | A        | .....          |
| Barium oxide .....                                                                                                                                                                     | 6.1       | UN1884 | III   | 6.1      | IB8, IP3, T1, TP33                           | 153   | 213   | 240   | 100 kg      | 200 kg       | A        | .....          |
| Barium perchlorate, solid .....                                                                                                                                                        | 5.1       | UN1447 | II    | 5.1, 6.1 | IB6, IP2, T3, TP33                           | 152   | 212   | 242   | 5 kg        | 25 kg        | A        | 56, 58         |
| Barium perchlorate, solution .....                                                                                                                                                     | 5.1       | UN3406 | II    | 5.1, 6.1 | IB2, T4, TP1                                 | 152   | 202   | 243   | 1 L         | 5 L          | A        | 56, 58, 133    |
| .....                                                                                                                                                                                  | .....     | .....  | III   | 5.1, 6.1 | IB2, T4, TP1                                 | 152   | 203   | 242   | 2.5 L       | 30 L         | A        | 56, 58, 133    |
| Barium permanganate .....                                                                                                                                                              | 5.1       | UN1448 | II    | 5.1, 6.1 | IB6, IP2, T3, TP33                           | 152   | 212   | 242   | 5 kg        | 25 kg        | D        | 56, 58, 138    |
| Barium peroxide .....                                                                                                                                                                  | 5.1       | UN1449 | II    | 5.1, 6.1 | A9, IB6, IP2, T3, TP33                       | 152   | 212   | 242   | 5 kg        | 25 kg        | A        | 13, 52, 56, 75 |
| <i>Barium selenate, see Selenates or Selenites.</i>                                                                                                                                    | .....     | .....  | ..... | .....    | .....                                        | ..... | ..... | ..... | .....       | .....        | .....    | .....          |
| <i>Barium selenite, see Selenates or Selenites.</i>                                                                                                                                    | .....     | .....  | ..... | .....    | .....                                        | ..... | ..... | ..... | .....       | .....        | .....    | .....          |
| Batteries, containing sodium .....                                                                                                                                                     | 4.3       | UN3292 | II    | 4.3      | .....                                        | 189   | 189   | 189   | Forbidden   | No limit     | A        | .....          |
| Batteries, dry, containing potassium hydroxide solid, <i>electric storage.</i>                                                                                                         | 8         | UN3028 | III   | 8        | .....                                        | None  | 213   | None  | 25 kg gross | 230 kg gross | A        | 52.            |
| Batteries, wet, filled with acid, <i>electric storage.</i>                                                                                                                             | 8         | UN2794 | III   | 8        | .....                                        | 159   | 159   | 159   | 30 kg gross | No limit     | A        | .....          |
| Batteries, wet, filled with alkali, <i>electric storage.</i>                                                                                                                           | 8         | UN2795 | III   | 8        | .....                                        | 159   | 159   | 159   | 30 kg gross | No limit     | A        | 52.            |
| Batteries, wet, non-spillable, <i>electric storage.</i>                                                                                                                                | 8         | UN2800 | III   | 8        | .....                                        | 159   | 159   | 159   | No Limit    | No Limit     | A        | .....          |
| Batteries, dry, <i>not subject to the requirements of this subchapter.</i>                                                                                                             | .....     | .....  | ..... | .....    | 130                                          | ..... | ..... | ..... | .....       | .....        | .....    | .....          |
| Battery fluid, acid .....                                                                                                                                                              | 8         | UN2796 | II    | 8        | A3, A7, B2, B15, IB2, N6, N34, T8, TP2, TP12 | 154   | 202   | 242   | 1 L         | 30 L         | B        | .....          |
| Battery fluid, alkali .....                                                                                                                                                            | 8         | UN2797 | II    | 8        | B2, IB2, N6, T7, TP2, TP28                   | 154   | 202   | 242   | 1 L         | 30 L         | A        | 29             |
| <i>Battery lithium type, see Lithium batteries etc.</i>                                                                                                                                | .....     | .....  | ..... | .....    | .....                                        | ..... | ..... | ..... | .....       | .....        | .....    | .....          |
| Battery-powered vehicle or Battery-powered equipment.                                                                                                                                  | 9         | UN3171 | ..... | 9        | .....                                        | 134   | 220   | 220   | None        | No limit     | No limit | .....          |
| <i>Battery, wet, filled with acid or alkali with vehicle or mechanical equipment containing an internal combustion engine, see Vehicle, etc. or Engines, internal combustion, etc.</i> | .....     | .....  | ..... | .....    | .....                                        | ..... | ..... | ..... | .....       | .....        | .....    | .....          |
| + Benzaldehyde .....                                                                                                                                                                   | 9         | UN1990 | III   | 9        | IB3, T2, TP1                                 | 155   | 203   | 241   | 100 L       | 220 L        | A        | .....          |
| Benzene .....                                                                                                                                                                          | 3         | UN1114 | II    | 3        | IB2, T4, TP1                                 | 150   | 202   | 242   | 5 L         | 60 L         | B        | 40             |
| Benzene diazonium chloride (dry).                                                                                                                                                      | Forbidden | .....  | ..... | .....    | .....                                        | ..... | ..... | ..... | .....       | .....        | .....    | .....          |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                     | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102)                          | (8)                   |          |       | (9)                                             |                      | (10)            |         |
|----------|---------------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|----------------------------------------------------------|-----------------------|----------|-------|-------------------------------------------------|----------------------|-----------------|---------|
|          |                                                                                 |                           |                          |     |             |                                                          | Packaging (§ 173.***) |          |       | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |         |
|          |                                                                                 |                           |                          |     |             |                                                          | Excep-tions           | Non-bulk | Bulk  | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other   |
| (1)      | (2)                                                                             | (3)                       | (4)                      | (5) | (6)         | (7)                                                      | (8A)                  | (8B)     | (8C)  | (9A)                                            | (9B)                 | (10A)           | (10B)   |
|          | <i>Benzene diazonium nitrate (dry)</i>                                          | Forbidden                 |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzene phosphorus dichloride, see Phenyl phosphorus di-chloride.</i>        | .....                     |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzene phosphorus thiodichloride, see Phenyl phosphorus thiodichloride.</i> | .....                     |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzene sulfonyl chloride</i> .....                                          | 8                         | UN2225                   | III | 8           | IB3, T4, TP1                                             | 154                   | 203      | 241   | 5 L                                             | 60 L                 | A               | 40      |
|          | <i>Benzene triozonide</i> .....                                                 | Forbidden                 |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzenethiol, see Phenyl mercaptan.</i>                                      | .....                     |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzidine</i> .....                                                          | 6.1                       | UN1885                   | II  | 6.1         | IB8, IP2, IP4, T3, TP33                                  | 153                   | 212      | 242   | 25 kg                                           | 100 kg               | A               | .....   |
|          | <i>Benzol, see Benzene</i> .....                                                | .....                     |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzonitrile</i> .....                                                       | 6.1                       | UN2224                   | II  | 6.1         | IB2, T7, TP2                                             | 153                   | 202      | 243   | 5 L                                             | 60 L                 | A               | 40, 52  |
|          | <i>Benzoquinone</i> .....                                                       | 6.1                       | UN2587                   | II  | 6.1         | IB8, IP2, IP4, T3, TP33                                  | 153                   | 212      | 242   | 25 kg                                           | 100 kg               | A               | .....   |
|          | <i>Benzotrichloride</i> .....                                                   | 8                         | UN2226                   | II  | 8           | B2, IB2, T7, TP2                                         | 154                   | 202      | 242   | 1 L                                             | 30 L                 | A               | 40      |
|          | <i>Benzotrifluoride</i> .....                                                   | 3                         | UN2338                   | II  | 3           | IB2, T4, TP1                                             | 150                   | 202      | 242   | 5 L                                             | 60 L                 | B               | 40      |
|          | <i>Benzoxidiazoles (dry)</i> .....                                              | Forbidden                 |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzoyl azide</i> .....                                                      | Forbidden                 |                          |     | .....       |                                                          | .....                 | .....    | ..... | .....                                           | .....                |                 | .....   |
|          | <i>Benzoyl chloride</i> .....                                                   | 8                         | UN1736                   | II  | 8           | B2, IB2, T8, TP2, TP12, TP13                             | 154                   | 202      | 242   | 1 L                                             | 30 L                 | C               | 40      |
|          | <i>Benzyl bromide</i> .....                                                     | 6.1                       | UN1737                   | II  | 6.1, 8      | A3, A7, IB2, N33, N34, T8, TP2, TP12, TP13               | None                  | 202      | 243   | 1 L                                             | 30 L                 | D               | 13, 40. |
|          | <i>Benzyl chloride</i> .....                                                    | 6.1                       | UN1738                   | II  | 6.1, 8      | A3, A7, B70, IB2, N33, N42, T8, TP2, TP12, TP13          | None                  | 202      | 243   | 1 L                                             | 30 L                 | D               | 13, 40. |
|          | <i>Benzyl chloride unstabilized</i> .....                                       | 6.1                       | UN1738                   | II  | 6.1, 8      | A3, A7, B8, B11, IB2, N33, N34, N43, T8, TP2, TP12, TP13 | 153                   | 202      | 243   | 1 L                                             | 30 L                 | D               | 13, 40  |
|          | <i>Benzyl chloroformate</i> .....                                               | 8                         | UN1739                   | I   | 8           | A3, A6, B4, N41, T10, TP2, TP12, TP13                    | None                  | 201      | 243   | Forbidden                                       | 2.5 L                | D               | 40      |
|          | <i>Benzyl iodide</i> .....                                                      | 6.1                       | UN2653                   | II  | 6.1         | IB2, T7, TP2                                             | 153                   | 202      | 243   | 5 L                                             | 60 L                 | B               | 12, 40  |
|          | <i>Benzyl dimethylamine</i> .....                                               | 8                         | UN2619                   | II  | 8, 3        | B2, IB2, T7, TP2                                         | 154                   | 202      | 243   | 1 L                                             | 30 L                 | A               | 40, 48  |
|          | <i>Benzylidene chloride</i> .....                                               | 6.1                       | UN1886                   | II  | 6.1         | IB2, T7, TP2                                             | 153                   | 202      | 243   | 5 L                                             | 60 L                 | D               | 40      |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                         |           |        |       |        |                           |       |       |       |             |             |       |        |
|---------------------------------------------------------------------------------------------------------|-----------|--------|-------|--------|---------------------------|-------|-------|-------|-------------|-------------|-------|--------|
| Beryllium compounds, n.o.s. ....                                                                        | 6.1       | UN1566 | II    | 6.1    | IB8, IP2, IP4, T3, TP33   | 153   | 212   | 242   | 25 kg       | 100 kg      | A     | .....  |
| .....                                                                                                   | .....     | .....  | III   | 6.1    | IB8, IP3, T1, TP33        | 153   | 213   | 240   | 100 kg      | 200 kg      | A     | .....  |
| Beryllium nitrate .....                                                                                 | 5.1       | UN2464 | II    | 5.1,   | IB8, IP2, IP4, T3, TP33   | 152   | 212   | 242   | 5 kg        | 25 kg       | A     | .....  |
| Beryllium, powder .....                                                                                 | 6.1       | UN1567 | II    | 6.1,   | IB8, IP2, IP4, T3, TP33   | 153   | 212   | 242   | 15 kg       | 50 kg       | A     | .....  |
| Bicyclo [2,2,1] hepta-2,5-diene, stabilized or 2,5-Norbornadiene, stabilized.                           | 3         | UN2251 | II    | 4.1,   | IB2, T7, TP2              | 150   | 202   | 242   | 5 L         | 60 L        | D     | .....  |
| Biological substance, Category B.                                                                       | 6.2       | UN3373 | ..... | .....  | A82                       | 134   | 199   | None  | 4 L or 4 kg | 4 L or 4 kg | A     | 40     |
| Biphenyl triozone .....                                                                                 | Forbidden | .....  | ..... | .....  | .....                     | ..... | ..... | ..... | .....       | .....       | E     | .....  |
| Bipyridilium pesticides, liquid, flammable, toxic, flash point less than 23 degrees C.                  | 3         | UN2782 | I     | 3, 6.1 | T14, TP2, TP13, TP27      | None  | 201   | 243   | Forbidden   | 30 L        | E     | .....  |
| .....                                                                                                   | .....     | .....  | II    | 3, 6.1 | IB2, T11, TP2, TP13, TP27 | 150   | 202   | 243   | 1 L         | 60 L        | B     | 40     |
| Bipyridilium pesticides, liquid, toxic.                                                                 | 6.1       | UN3016 | I     | 6.1    | T14, TP2, TP13, TP27      | None  | 201   | 243   | 1 L         | 30 L        | B     | 40     |
| .....                                                                                                   | .....     | .....  | II    | 6.1    | IB2, T11, TP2, TP13, TP27 | 153   | 202   | 243   | 5 L         | 60 L        | B     | 40     |
| .....                                                                                                   | .....     | .....  | III   | 6.1    | IB3, T7, TP2, TP28        | 153   | 203   | 241   | 60 L        | 220 L       | A     | 40     |
| Bipyridilium pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C.              | 6.1       | UN3015 | I     | 6.1, 3 | T14, TP2, TP13, TP27      | None  | 201   | 243   | 1 L         | 30 L        | B     | 21, 40 |
| .....                                                                                                   | .....     | .....  | II    | 6.1, 3 | IB2, T11, TP2, TP13, TP27 | 153   | 202   | 243   | 5 L         | 60 L        | B     | 21, 40 |
| .....                                                                                                   | .....     | .....  | III   | 6.1, 3 | B1, IB3, T7, TP2, TP28    | 153   | 203   | 242   | 60 L        | 220 L       | A     | 21, 40 |
| Bipyridilium pesticides, solid, toxic.                                                                  | 6.1       | UN2781 | I     | 6.1    | IB7, IP1, T6, TP33        | None  | 211   | 242   | 5 kg        | 50 kg       | A     | 40     |
| .....                                                                                                   | .....     | .....  | II    | 6.1    | IB8, IP2, IP4, T3, TP33   | 153   | 212   | 242   | 25 kg       | 100 kg      | A     | 40     |
| .....                                                                                                   | .....     | .....  | III   | 6.1    | IB8, IP3, T1, TP33        | 153   | 213   | 240   | 100 kg      | 200 kg      | A     | 40     |
| Bis (Aminopropyl) piperazine, see Corrosive liquid, n.o.s..                                             | .....     | .....  | ..... | .....  | .....                     | ..... | ..... | ..... | .....       | .....       | ..... | .....  |
| Bisulfate, aqueous solution .....                                                                       | 8         | UN2837 | II    | 8      | A7, B2, IB2, N34, T7, TP2 | 154   | 202   | 242   | 1 L         | 30 L        | A     | .....  |
| .....                                                                                                   | .....     | .....  | III   | 8      | A7, IB3, N34, T4, TP1     | 154   | 203   | 241   | 5 L         | 60 L        | A     | .....  |
| Bisulfites, aqueous solutions, n.o.s..                                                                  | 8         | UN2693 | III   | 8      | IB3, T7, TP1, TP28        | 154   | 203   | 241   | 5 L         | 60 L        | A     | 40, 52 |
| Black powder, compressed or Gunpowder, compressed or Black powder, in pellets or Gunpowder, in pellets. | 1.1D      | UN0028 | II    | 1.1D   | .....                     | None  | 62    | None  | Forbidden   | Forbidden   | 10    | .....  |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                     | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|---------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                 |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                 |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| (1)      | (2)                                                                             | (3)                        | (4)                        | (5)   | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)  |
| D        | Black powder or Gunpowder, granular or as a meal.                               | 1.1D                       | UN0027                     | II    | 1.1D ..     | 70                               | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | .....  |
|          | Black powder for small arms .....                                               | 4.1                        | NA0027                     | I     | 4.1 .....   |                                  | None ....             | 170 ..... | None .... | Forbidden                                       | Forbidden             | E                | .....  |
|          | Blasting agent, n.o.s., see Ex- plosives, blasting etc.                         | .....                      | .....                      | ..... | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....  |
|          | Blasting cap assemblies, see Detonator assemblies, non- electric, for blasting. | .....                      | .....                      | ..... | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....  |
|          | Blasting caps, electric, see Det- onators, electric for blasting.               | .....                      | .....                      | ..... | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....  |
| I        | Blasting caps, non-electric, see Detonators, non-electric, for blasting.        | .....                      | .....                      | ..... | .....       | 156, IB8, IP2, IP4, T3, TP33     | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....  |
|          | Bleaching powder, see Calcium hypochlorite mixtures, etc.                       | .....                      | .....                      | ..... | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....  |
|          | Blue asbestos (Crocidolite) or Brown asbestos (amosite, mysorite).              | 9                          | UN2212                     | II    | 9 .....     |                                  | 155 .....             | 216 ..... | 240 ..... | Forbidden                                       | Forbidden             | A                | 34, 40 |
|          | Bombs, photo-flash .....                                                        | 1.1F                       | UN0037                     | II    | 1.1F ...    |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | .....  |
|          | Bombs, photo-flash .....                                                        | 1.1D                       | UN0038                     | II    | 1.1D ..     |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....  |
|          | Bombs, photo-flash .....                                                        | 1.2G                       | UN0039                     | II    | 1.2G ..     |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....  |
|          | Bombs, photo-flash .....                                                        | 1.3G                       | UN0299                     | II    | 1.3G ..     |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....  |
|          | Bombs, smoke, non-explosive, with corrosive liquid, without initiating device.  | 8                          | UN2028                     | II    | 8 .....     |                                  | None ....             | 160 ..... | None .... | Forbidden                                       | 50 kg                 | E                | 40     |
|          | Bombs, with bursting charge .....                                               | 1.1F                       | UN0033                     | II    | 1.1F ...    |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | .....  |
|          | Bombs, with bursting charge .....                                               | 1.1D                       | UN0034                     | II    | 1.1D ..     |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....  |
|          | Bombs, with bursting charge .....                                               | 1.2D                       | UN0035                     | II    | 1.2D ..     |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....  |
|          | Bombs, with bursting charge .....                                               | 1.2F                       | UN0291                     | II    | 1.2F ...    |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | .....  |
|          | Bombs with flammable liquid, with bursting charge.                              | 1.1J                       | UN0399                     | II    | 1.1J ...    |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 04               | 23E    |
|          | Bombs with flammable liquid, with bursting charge.                              | 1.2J                       | UN0400                     | II    | 1.2J ...    |                                  | .....                 | 62 .....  | None .... | Forbidden                                       | Forbidden             | 04               | 23E    |
|          | Boosters with detonator .....                                                   | 1.1B                       | UN0225                     | II    | 1.1B ...    |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 11               | .....  |
|          | Boosters with detonator .....                                                   | 1.2B                       | UN0268                     | II    | 1.2B ...    |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....  |
|          | Boosters, without detonator .....                                               | 1.1D                       | UN0042                     | II    | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....  |
|          | Boosters, without detonator .....                                               | 1.2D                       | UN0283                     | II    | 1.2D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                 |           |        |       |              |                                                             |           |           |           |           |           |   |                        |
|---|-----------------------------------------------------------------|-----------|--------|-------|--------------|-------------------------------------------------------------|-----------|-----------|-----------|-----------|-----------|---|------------------------|
|   | Borate and chlorate mixtures, see Chlorate and borate mixtures. |           |        |       |              |                                                             |           |           |           |           |           |   |                        |
|   | Borneol .....                                                   | 4.1       | UN1312 | III   | 4.1 .....    | A1, IB8, IP3, T1, TP33                                      | None .... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A | .....                  |
| + | Boron tribromide .....                                          | 8         | UN2692 | I     | 8, 6.1       | 2, B9, B14, B32, B74, N34, T20, TP2, TP12, TP13, TP38, TP45 | None .... | 227 ..... | 244 ..... | Forbidden | Forbidden | C | 12                     |
|   | Boron trichloride .....                                         | 2.3       | UN1741 | ..... | 2.3, 8       | 3, B9, B14                                                  | None .... | 304 ..... | 314 ..... | Forbidden | Forbidden | D | 25, 40                 |
|   | Boron trifluoride .....                                         | 2.3       | UN1008 | ..... | 2.3 .....    | 2, B9, B14                                                  | None .... | 302 ..... | 314, 315. | Forbidden | Forbidden | D | 40                     |
|   | Boron trifluoride acetic acid complex, liquid.                  | 8         | UN1742 | II    | 8 .....      | B2, B6, IB2, T8, TP2, TP12                                  | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | A | .....                  |
|   | Boron trifluoride acetic acid complex, solid.                   | 8         | UN3419 | II    | 8 .....      | B2, B6, IB8, IP2, IP4, T3, TP33                             | 154 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | A | .....                  |
|   | Boron trifluoride diethyl etherate                              | 8         | UN2604 | I     | 8, 3 .....   | A3, A19, T10, TP2                                           | None .... | 201 ..... | 243 ..... | 0.5 L     | 2.5 L     | D | 40                     |
|   | Boron trifluoride dihydrate .....                               | 8         | UN2851 | II    | 8 .....      | IB2, T7, TP2                                                | 154 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | B | 12, 40,                |
|   | Boron trifluoride dimethyl etherate.                            | 4.3       | UN2965 | I     | 4.3, 8, 3.   | A19, T10, TP2, TP7                                          | None .... | 201 ..... | 243 ..... | Forbidden | 1 L       | D | 21, 28, 40, 49, 100    |
|   | Boron trifluoride propionic acid complex, liquid.               | 8         | UN1743 | II    | 8 .....      | B2, IB2, T8, TP2, TP12                                      | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | A | .....                  |
|   | Boron trifluoride propionic acid complex, solid.                | 8         | UN3420 | II    | 8 .....      | B2, IB8, IP2, IP4, T3, TP33                                 | 154 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | A | .....                  |
|   | Box toe gum, see Nitrocellulose etc.                            | .....     |        |       | .....        |                                                             |           |           |           |           |           |   | .....                  |
|   | Bromates, inorganic, aqueous solution, n.o.s..                  | 5.1       | UN3213 | II    | 5.1 .....    | IB2, T4, TP1                                                | 152 ..... | 202 ..... | 242 ..... | 1 L       | 5 L       | B | 56, 58, 133            |
|   | .....                                                           | .....     |        | III   | 5.1 .....    | IB2, T4, TP1                                                | 152 ..... | 203 ..... | 241 ..... | 2.5 L     | 30 L      | B | 56, 58, 133            |
|   | Bromates, inorganic, n.o.s. ....                                | 5.1       | UN1450 | II    | 5.1 .....    | IB8, IP2, IP4, T3, TP33                                     | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A | 56, 58                 |
| + | Bromine .....                                                   | 8         | UN1744 | I     | 8, 6.1       | 1, B9, B64, B85, N34, N43, T22, TP2, TP10, TP12, TP13       | None .... | 226 ..... | 249 ..... | Forbidden | Forbidden | D | 12, 40, 66, 74, 89, 90 |
|   | Bromine azide .....                                             | Forbidden |        |       |              |                                                             |           |           |           |           |           |   |                        |
|   | Bromine chloride .....                                          | 2.3       | UN2901 | ..... | 2.3, 8, 5.1. | 2, B9, B14, N86                                             | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D | 40, 89, 90             |
| + | Bromine pentafluoride .....                                     | 5.1       | UN1745 | I     | 5.1, 6.1, 8. | 1, B9, B14, B30, B72, T22, TP2, TP12, TP13, TP38, TP44      | None .... | 228 ..... | 244 ..... | Forbidden | Forbidden | D | 25, 40, 66, 90         |
| + | Bromine solutions .....                                         | 8         | UN1744 | I     | 8, 6.1       | 1, B9, B64, B85, N34, N43, T22, TP2, TP10, TP12, TP13       | None .... | 226 ..... | 249 ..... | Forbidden | Forbidden | D | 12, 40, 66, 74, 89, 90 |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes  | Special provi- sions (§ 172.102)                       | (8)                   |           |           | (9)                                             |                       | (10)             |                        |
|----------|-------------------------------------------------------------|----------------------------|----------------------------|-----|--------------|--------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|------------------------|
|          |                                                             |                            |                            |     |              |                                                        | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                        |
|          |                                                             |                            |                            |     |              |                                                        | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                  |
| +        | Bromine solutions .....                                     | 8                          | UN1744                     | I   | 8, 6.1       | 2, B9, B64, B85, N34, N43, T22, TP2, TP10, TP12, TP13  | None ....             | 227 ..... | 249 ..... | Forbidden                                       | Forbidden             | D                | 12, 40, 66, 74, 89, 90 |
| +        | Bromine trifluoride .....                                   | 5.1                        | UN1746                     | I   | 5.1, 6.1, 8. | 2, B9, B14, B32, B74, T22, TP2, TP12, TP13, TP38, TP45 | None ....             | 228 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 25, 40, 66, 90         |
|          | 4-Bromo-1,2-dinitrobenzene .....                            | Forbidden                  |                            |     |              |                                                        |                       |           |           |                                                 |                       |                  |                        |
|          | 4-Bromo-1,2-dinitrobenzene (un- stable at 59 degrees C).    | Forbidden                  |                            |     |              |                                                        |                       |           |           |                                                 |                       |                  |                        |
|          | 1-Bromo-3-chloropropane .....                               | 6.1                        | UN2688                     | III | 6.1 .....    | IB3, T4, TP1                                           | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                |                        |
|          | 1-Bromo-3-methylbutane .....                                | 3                          | UN2341                     | III | 3 .....      | B1, IB3, T2, TP1                                       | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                |                        |
|          | 1-Bromo-3-nitrobenzene (unsta- ble at 56 degrees C).        | Forbidden                  |                            |     |              |                                                        |                       |           |           |                                                 |                       |                  |                        |
|          | 2-Bromo-2-nitropropane-1,3-diol                             | 4.1                        | UN3241                     | III | 4.1 .....    | 46, IB8, IP3                                           | 151 .....             | 213 ..... | None .... | 25 kg                                           | 50 kg                 | C                | 12, 25, 40             |
|          | Bromoacetic acid, solid .....                               | 8                          | UN3425                     | II  | 8 .....      | A7, IB8, IP2, IP4, N34, T3, TP33                       | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                 | A                |                        |
|          | Bromoacetic acid solution .....                             | 8                          | UN1938                     | II  | 8 .....      | A7, B2, IB2, T7, TP2                                   | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | A                | 40                     |
|          |                                                             |                            |                            | III | 8 .....      | B2, IB3, T7, TP2                                       | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | 40                     |
| +        | Bromoacetone .....                                          | 6.1                        | UN1569                     | II  | 6.1, 3       | 2, T20, TP2, TP13                                      | None ....             | 193 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40                     |
|          | Bromoacetyl bromide .....                                   | 8                          | UN2513                     | II  | 8 .....      | B2, IB2, T8, TP2, TP12                                 | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | C                | 40, 53                 |
|          | Bromobenzene .....                                          | 3                          | UN2514                     | III | 3 .....      | B1, IB3, T2, TP1                                       | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                |                        |
|          | Bromobenzyl cyanides, liquid ....                           | 6.1                        | UN1694                     | I   | 6.1 .....    | T14, TP2, TP13                                         | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 30 L                  | D                | 12, 40, 52             |
|          | Bromobenzyl cyanides, solid ....                            | 6.1                        | UN3449                     | I   | 6.1 .....    | T6, TP33                                               | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                 | D                | 12, 40, 52             |
|          | 1-Bromobutane .....                                         | 3                          | UN1126                     | II  | 3 .....      | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | 40                     |
|          | 2-Bromobutane .....                                         | 3                          | UN2339                     | II  | 3 .....      | B1, IB2, T4, TP1                                       | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | 40                     |
|          | Bromochloromethane .....                                    | 6.1                        | UN1887                     | III | 6.1 .....    | IB3, T4, TP1                                           | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                |                        |
|          | 2-Bromoethyl ethyl ether .....                              | 3                          | UN2340                     | II  | 3 .....      | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | 40                     |
|          | Bromoform .....                                             | 6.1                        | UN2515                     | III | 6.1 .....    | IB3, T4, TP1                                           | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | 12, 40                 |
|          | Bromomethylpropanes .....                                   | 3                          | UN2342                     | II  | 3 .....      | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                |                        |
|          | 2-Bromopentane .....                                        | 3                          | UN2343                     | II  | 3 .....      | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                |                        |
|          | Bromopropanes .....                                         | 3                          | UN2344                     | II  | 3 .....      | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | 40                     |
|          |                                                             |                            |                            | III | 3 .....      | IB3, T2, TP1                                           | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                |                        |
|          | 3-Bromopropyne .....                                        | 3                          | UN2345                     | II  | 3 .....      | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | D                | 40                     |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                  |           |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
|----------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-----|------------|-------|--------------------------------------------------------|------|-------|-----|-------|-----------|-----------|-----------|-----------|----|-----------------------------|
| Bromosilane .....                                                                                                                | Forbidden |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| Bromotoluene-alpha, see Benzyl bromide.                                                                                          |           |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| Bromotrifluoroethylene .....                                                                                                     | 2.1       | UN2419 |     | 2.1        | ..... |                                                        | None | ....  | 304 | ..... | 314, 315. | Forbidden | 150 kg    | B         |    | 40                          |
| Bromotrifluoromethane or Refrigerant gas, R 13B1..                                                                               | 2.2       | UN1009 |     | 2.2        | ..... | T50                                                    | 306  | ..... | 304 | ..... | 314, 315. | 75 kg     | 150 kg    | A         |    | .....                       |
| Brucine .....                                                                                                                    | 6.1       | UN1570 | I   | 6.1        | ..... | IB7, IP1, T6, TP33                                     | None | ....  | 211 | ..... | 242       | .....     | 5 kg      | 50 kg     | A  | .....                       |
| Bursters, explosive .....                                                                                                        | 1.1D      | UN0043 | II  | 1.1D       | ..    |                                                        | None | ....  | 62  | ..... | None      | .....     | Forbidden | Forbidden | 07 | .....                       |
| Butadienes, stabilized or Butadienes and Hydrocarbon mixture, stabilized containing more than 40% butadienes.                    | 2.1       | UN1010 |     | 2.1        | ..... | T50                                                    | 306  | ..... | 304 | ..... | 314, 315. | Forbidden | 150 kg    | B         |    | 40                          |
| Butane see also Petroleum gases, liquefied.                                                                                      | 2.1       | UN1011 |     | 2.1        | ..... | 19, T50                                                | 306  | ..... | 304 | ..... | 314, 315. | Forbidden | 150 kg    | E         |    | 40                          |
| Butane, butane mixtures and mixtures having similar properties in cartridges each not exceeding 500 grams, see Receptacles, etc. |           |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| Butanedione .....                                                                                                                | 3         | UN2346 | II  | 3          | ..... | IB2, T4, TP1                                           | 150  | ..... | 202 | ..... | 242       | .....     | 5 L       | 60 L      | B  | .....                       |
| 1,2,4-Butanetriol trinitrate .....                                                                                               | Forbidden |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| Butanols .....                                                                                                                   | 3         | UN1120 | II  | 3          | ..... | IB2, T4, TP1, TP29                                     | 150  | ..... | 202 | ..... | 242       | .....     | 5 L       | 60 L      | B  | .....                       |
| tert-Butoxycarbonyl azide .....                                                                                                  | Forbidden |        | III | 3          | ..... | B1, IB3, T2, TP1                                       | 150  | ..... | 203 | ..... | 242       | .....     | 60 L      | 220 L     | A  | .....                       |
| Butyl acetates .....                                                                                                             | 3         | UN1123 | II  | 3          | ..... | IB2, T4, TP1                                           | 150  | ..... | 202 | ..... | 242       | .....     | 5 L       | 60 L      | B  | .....                       |
| Butyl acid phosphate .....                                                                                                       | 8         | UN1718 | III | 3          | ..... | B1, IB3, T2, TP1                                       | 150  | ..... | 203 | ..... | 242       | .....     | 60 L      | 220 L     | A  | .....                       |
| Butyl acrylates, stabilized .....                                                                                                | 3         | UN2348 | III | 8          | ..... | IB3, T4, TP1                                           | 154  | ..... | 203 | ..... | 241       | .....     | 5 L       | 60 L      | A  | .....                       |
| Butyl alcohols, see Butanols .....                                                                                               |           |        | III | 3          | ..... | B1, IB3, T2, TP1                                       | 150  | ..... | 203 | ..... | 242       | .....     | 60 L      | 220 L     | A  | .....                       |
| Butyl benzenes .....                                                                                                             | 3         | UN2709 | III | 3          | ..... | B1, IB3, T2, TP1                                       | 150  | ..... | 203 | ..... | 242       | .....     | 60 L      | 220 L     | A  | .....                       |
| n-Butyl bromide, see 1-Bromobutane.                                                                                              |           |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| n-Butyl chloride, see Chlorobutanes.                                                                                             |           |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| D sec-Butyl chloroformate .....                                                                                                  | 6.1       | NA2742 | I   | 6.1, 3, 8. |       | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None | ....  | 227 | ..... | 244       | .....     | Forbidden | Forbidden | A  | 12, 13, 22, 25, 40, 48, 100 |
| n-Butyl chloroformate .....                                                                                                      | 6.1       | UN2743 | I   | 6.1, 8, 3. |       | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45       | None | ....  | 227 | ..... | 244       | .....     | Forbidden | Forbidden | A  | 12, 13, 21, 25, 40, 100     |
| Butyl ethers, see Dibutyl ethers                                                                                                 |           |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| Butyl ethyl ether, see Ethyl butyl ether.                                                                                        |           |        |     |            |       |                                                        |      |       |     |       |           |           |           |           |    |                             |
| n-Butyl formate .....                                                                                                            | 3         | UN1128 | II  | 3          | ..... | IB2, T4, TP1                                           | 150  | ..... | 202 | ..... | 242       | .....     | 5 L       | 60 L      | B  | .....                       |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                   | Hazard class or Division | Identification Numbers | PG  | Label Codes | Special provisions (§ 172.102)                        | (8)                   |           |           | (9)                                             |                     | (10)           |                 |
|----------|------------------------------------------------------------------------------|--------------------------|------------------------|-----|-------------|-------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|---------------------|----------------|-----------------|
|          |                                                                              |                          |                        |     |             |                                                       | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |                 |
|          |                                                                              |                          |                        |     |             |                                                       | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Location       | Other           |
|          | <i>tert</i> -Butyl hydroperoxide, with more than 90 percent with water.      | Forbidden                |                        |     |             |                                                       |                       |           |           |                                                 |                     |                |                 |
|          | <i>tert</i> -Butyl hypochlorite .....                                        | 4.2                      | UN3255                 | I   | 4.2, 8      |                                                       | None ....             | 211 ..... | 243 ..... | Forbidden                                       | Forbidden           | D              |                 |
|          | N- <i>n</i> -Butyl imidazole .....                                           | 6.1                      | UN2690                 | II  | 6.1 .....   | IB2, T7, TP2                                          | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                | A              |                 |
|          | <i>tert</i> -Butyl isocyanate .....                                          | 6.1                      | UN2484                 | I   | 6.1, 3      | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44      | None ....             | 226 ..... | 244 ..... | Forbidden                                       | Forbidden           | D              | 40              |
|          | <i>n</i> -Butyl isocyanate .....                                             | 6.1                      | UN2485                 | I   | 6.1, 3      | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden           | D              | 40              |
|          | Butyl mercaptans .....                                                       | 3                        | UN2347                 | II  | 3 .....     | A3, A6, IB2, T4, TP1                                  | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | D              | 52, 95          |
|          | <i>n</i> -Butyl methacrylate, stabilized                                     | 3                        | UN2227                 | III | 3 .....     | B1, IB3, T2, TP1                                      | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L               | A              |                 |
|          | Butyl methyl ether .....                                                     | 3                        | UN2350                 | II  | 3 .....     | IB2, T4, TP1                                          | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              |                 |
|          | Butyl nitrites .....                                                         | 3                        | UN2351                 | I   | 3 .....     | T11, TP1, TP8, TP27                                   | 150 .....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                | E              | 40              |
|          | .....                                                                        |                          |                        | II  | 3 .....     | IB2, T4, TP1                                          | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              | 40              |
|          | .....                                                                        |                          |                        | III | 3 .....     | B1, IB3, T2, TP1                                      | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L               | A              | 40              |
|          | <i>tert</i> -Butyl peroxyacetate, with more than 76 percent in solution.     | Forbidden                |                        |     |             |                                                       |                       |           |           |                                                 |                     |                |                 |
|          | <i>n</i> -Butyl peroxydicarbonate, with more than 52 percent in solution.    | Forbidden                |                        |     |             |                                                       |                       |           |           |                                                 |                     |                |                 |
|          | <i>tert</i> -Butyl peroxyisobutyrate, with more than 77 percent in solution. | Forbidden                |                        |     |             |                                                       |                       |           |           |                                                 |                     |                |                 |
|          | Butyl phosphoric acid, see Butyl acid phosphate.                             |                          |                        |     |             |                                                       |                       |           |           |                                                 |                     |                |                 |
|          | Butyl propionates .....                                                      | 3                        | UN1914                 | III | 3 .....     | B1, IB3, T2, TP1                                      | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L               | A              |                 |
|          | 5- <i>tert</i> -Butyl-2,4,6-trinitro- <i>m</i> -xylene or Musk xylene.       | 4.1                      | UN2956                 | III | 4.1 .....   | 159                                                   | None ....             | 223 ..... | None .... | Forbidden                                       | Forbidden           | D              | 12, 25, 48, 127 |
|          | Butyl vinyl ether, stabilized .....                                          | 3                        | UN2352                 | II  | 3 .....     | IB2, T4, TP1                                          | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              | 40              |
|          | <i>n</i> -Butylamine .....                                                   | 3                        | UN1125                 | II  | 3, 8 .....  | IB2, T7, TP1                                          | 150 .....             | 202 ..... | 242 ..... | 1 L                                             | 5 L                 | B              | 40              |
|          | N-Butylaniline .....                                                         | 6.1                      | UN2738                 | II  | 6.1 .....   | IB2, T7, TP2                                          | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                | A              | 74              |
|          | <i>tert</i> -Butylcyclohexylchloroformate.                                   | 6.1                      | UN2747                 | III | 6.1 .....   | IB3, T4, TP1                                          | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L               | A              | 12, 13, 25      |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|                                                                               |       |        |       |        |       |                                                |       |       |       |       |           |           |        |       |                      |
|-------------------------------------------------------------------------------|-------|--------|-------|--------|-------|------------------------------------------------|-------|-------|-------|-------|-----------|-----------|--------|-------|----------------------|
| Butylene <i>see also</i> Petroleum gases, liquefied.                          | 2.1   | UN1012 | ..... | 2.1    | ..... | 19, T50                                        | 306   | ..... | 304   | ..... | 314, 315. | Forbidden | 150 kg | E     | 40                   |
| 1,2-Butylene oxide, stabilized                                                | 3     | UN3022 | II    | 3      | ..... | IB2, T4, TP1                                   | 150   | ..... | 202   | ..... | 242       | 5 L       | 60 L   | B     | 27, 49               |
| Butyltoluenes                                                                 | 6.1   | UN2667 | III   | 6.1    | ..... | IB3, T4, TP1                                   | 153   | ..... | 203   | ..... | 241       | 60 L      | 220 L  | A     | .....                |
| Butyltrichlorosilane                                                          | 8     | UN1747 | II    | 8, 3   | ..... | A7, B2, B6, IB2, N34, T7, TP2, TP13            | None  | ..... | 202   | ..... | 243       | Forbidden | 30 L   | C     | 40                   |
| 1,4-Butynediol                                                                | 6.1   | UN2716 | III   | 6.1    | ..... | A1, IB8, IP3, T1, TP33                         | None  | ..... | 213   | ..... | 240       | 100 kg    | 200 kg | A     | 52, 53, 70, 139, 140 |
| Butyraldehyde                                                                 | 3     | UN1129 | II    | 3      | ..... | IB2, T4, TP1                                   | 150   | ..... | 202   | ..... | 242       | 5 L       | 60 L   | B     | .....                |
| Butyraldoxime                                                                 | 3     | UN2840 | III   | 3      | ..... | B1, IB3, T2, TP1                               | 150   | ..... | 203   | ..... | 242       | 60 L      | 220 L  | A     | .....                |
| Butyric acid                                                                  | 8     | UN2820 | III   | 8      | ..... | IB3, T4, TP1                                   | 154   | ..... | 203   | ..... | 241       | 5 L       | 60 L   | A     | 12                   |
| Butyric anhydride                                                             | 8     | UN2739 | III   | 8      | ..... | IB3, T4, TP1                                   | 154   | ..... | 203   | ..... | 241       | 5 L       | 60 L   | A     | .....                |
| Butyronitrile                                                                 | 3     | UN2411 | II    | 3, 6.1 | ..... | IB2, T7, TP1, TP13                             | 150   | ..... | 202   | ..... | 243       | 1 L       | 60 L   | E     | 40                   |
| Butyryl chloride                                                              | 3     | UN2353 | II    | 3, 8   | ..... | IB2, T8, TP2, TP12, TP13                       | 150   | ..... | 202   | ..... | 243       | 1 L       | 5 L    | C     | 40                   |
| Cacodylic acid                                                                | 6.1   | UN1572 | II    | 6.1    | ..... | IB8, IP2, IP4, T3, TP33                        | 153   | ..... | 212   | ..... | 242       | 25 kg     | 100 kg | E     | 52                   |
| Cadmium compounds                                                             | 6.1   | UN2570 | I     | 6.1    | ..... | IB7, IP1, T6, TP33                             | None  | ..... | 211   | ..... | 242       | 5 kg      | 50 kg  | A     | .....                |
| .....                                                                         | ..... | .....  | II    | 6.1    | ..... | IB8, IP2, IP4, T3, TP33                        | 153   | ..... | 212   | ..... | 242       | 25 kg     | 100 kg | A     | .....                |
| .....                                                                         | ..... | .....  | III   | 6.1    | ..... | IB8, IP3, T1, TP33                             | 153   | ..... | 213   | ..... | 240       | 100 kg    | 200 kg | A     | .....                |
| Caesium hydroxide                                                             | 8     | UN2682 | II    | 8      | ..... | IB8, IP2, IP4, T3, TP33                        | 154   | ..... | 212   | ..... | 240       | 15 kg     | 50 kg  | A     | 29, 52               |
| Caesium hydroxide solution                                                    | 8     | UN2681 | II    | 8      | ..... | B2, IB2, T7, TP2                               | 154   | ..... | 202   | ..... | 242       | 1 L       | 30 L   | A     | 29, 52               |
| Calcium                                                                       | 4.3   | UN1401 | III   | 8      | ..... | IB3, T4, TP1                                   | 154   | ..... | 203   | ..... | 241       | 5 L       | 60 L   | A     | 29, 52               |
| Calcium arsenate                                                              | 6.1   | UN1573 | II    | 4.3    | ..... | IB7, IP2, T3, TP33                             | 151   | ..... | 212   | ..... | 241       | 15 kg     | 50kg   | E     | 52                   |
| Calcium arsenate and calcium arsenite, mixtures, solid.                       | 6.1   | UN1574 | II    | 6.1    | ..... | IB8, IP2, IP4, T3, TP33                        | 153   | ..... | 212   | ..... | 242       | 25 kg     | 100 kg | A     | .....                |
| <i>Calcium bisulfite solution, see</i> Bisulfites, aqueous solutions, n.o.s., | ..... | .....  | ..... | .....  | ..... | .....                                          | ..... | ..... | ..... | ..... | .....     | .....     | .....  | ..... | .....                |
| Calcium carbide                                                               | 4.3   | UN1402 | I     | 4.3    | ..... | A1, A8, B55, B59, IB4, IP1, N34, T9, TP7, TP33 | None  | ..... | 211   | ..... | 242       | Forbidden | 15 kg  | B     | 52                   |
| .....                                                                         | ..... | .....  | II    | 4.3    | ..... | A1, A8, B55, B59, IB7, IP2, N34, T3, TP33      | 151   | ..... | 212   | ..... | 241       | 15 kg     | 50 kg  | B     | 52                   |
| Calcium chlorate                                                              | 5.1   | UN1452 | II    | 5.1    | ..... | A9, IB8, IP2, IP4, N34, T3, TP33               | 152   | ..... | 212   | ..... | 242       | 5 kg      | 25 kg  | A     | 56, 58               |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                     | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)               | (8)                   |           |       | (9)                                             |                       | (10)             |                                |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|------------------------------------------------|-----------------------|-----------|-------|-------------------------------------------------|-----------------------|------------------|--------------------------------|
|          |                                                                                                                                                 |                            |                            |       |             |                                                | Packaging (§ 173.***) |           |       | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                                |
|          |                                                                                                                                                 |                            |                            |       |             |                                                | Excep- tions          | Non- bulk | Bulk  | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                          |
| A        | Calcium chlorate aqueous solu- tion.                                                                                                            | 5.1                        | UN2429                     | II    | 5.1         | A2, IB2, N41, T4, TP1                          | 152                   | 202       | 242   | 1 L                                             | 5 L                   | B                | 56, 58, 133                    |
|          | .....                                                                                                                                           | .....                      | .....                      | III   | 5.1         | A2, IB2, N41, T4, TP1                          | 152                   | 203       | 241   | 2.5 L                                           | 30 L                  | B                | 56, 68, 133                    |
|          | Calcium chlorite .....                                                                                                                          | 5.1                        | UN1453                     | II    | 5.1         | A9, IB8, IP2, IP4, N34, T3, TP33               | 152                   | 212       | 242   | 5 kg                                            | 25 kg                 | A                | 56, 58                         |
|          | Calcium cyanamide with more than 0.1 percent of calcium carbide.                                                                                | 4.3                        | UN1403                     | III   | 4.3         | A1, A19, IB8, IP4, T1, TP33                    | 151                   | 213       | 241   | 25 kg                                           | 100 kg                | A                | 52                             |
|          | Calcium cyanide .....                                                                                                                           | 6.1                        | UN1575                     | I     | 6.1         | IB7, IP1, N79, N80, T6, TP33                   | None                  | 211       | 242   | 5 kg                                            | 50 kg                 | A                | 40, 52                         |
|          | Calcium dithionite or Calcium hydrosulfite.                                                                                                     | 4.2                        | UN1923                     | II    | 4.2         | A19, A20, IB6, IP2, T3, TP33                   | None                  | 212       | 241   | 15 kg                                           | 50 kg                 | E                | 13                             |
|          | Calcium hydride .....                                                                                                                           | 4.3                        | UN1404                     | I     | 4.3         | A19, N40                                       | None                  | 211       | 242   | Forbidden                                       | 15 kg                 | E                | 52                             |
|          | Calcium hydrosulfite, see Cal- cium dithionite.                                                                                                 | .....                      | .....                      | ..... | .....       | .....                                          | .....                 | .....     | ..... | .....                                           | .....                 | .....            | .....                          |
|          | Calcium hypochlorite, dry or Calcium hypochlorite mixtures dry with more than 39 percent available chlorine (8.8 percent available oxygen).     | 5.1                        | UN1748                     | II    | 5.1         | 165, 166, A7, A9, IB8, IP2, IP4, IP13, N34, W9 | 152                   | 212       | None  | 5 kg                                            | 25 kg                 | D                | 4, 25, 48, 52, 56, 58, 69, 142 |
|          | .....                                                                                                                                           | .....                      | .....                      | III   | 5.1         | 165, 171, A7, A9, IB8, IP4, IP13, N34, W9      | 152                   | 213       | 240   | 25 kg                                           | 100 kg                | D                | 4, 25, 48, 52, 56, 58, 69, 142 |
|          | Calcium hypochlorite, hydrated or Calcium hypochlorite, hy- drated mixtures, with not less than 5.5 percent but not more than 16 percent water. | 5.1                        | UN2880                     | II    | 5.1         | 165, IB8, IP2, IP4, IP13, W9                   | 152                   | 212       | 240   | 5 kg                                            | 25 kg                 | D                | 4, 25, 48, 52, 56, 58, 69, 142 |
|          | Calcium hypochlorite mixtures, dry, with more than 10 per- cent but not more than 39 percent available chlorine.                                | 5.1                        | UN2208                     | III   | 5.1         | 165, A1, A29, IB8, IP3, IP13, N34, W9          | 152                   | 213       | 240   | 25 kg                                           | 100 kg                | D                | 4, 25, 48, 52, 56, 58, 69, 142 |
|          | Calcium manganese silicon .....                                                                                                                 | 4.3                        | UN2844                     | III   | 4.3         | A1, A19, IB8, IP2, IP4, T1, TP33               | 151                   | 213       | 241   | 25 kg                                           | 100 kg                | A                | 52, 85, 103                    |
|          | Calcium nitrate .....                                                                                                                           | 5.1                        | UN1454                     | III   | 5.1         | 34, IB8, IP3, T1, TP33                         | 152                   | 213       | 240   | 25 kg                                           | 100 kg                | A                | .....                          |
|          | Calcium oxide .....                                                                                                                             | 8                          | UN1910                     | III   | 8           | IB8, IP3, T1, TP33                             | 154                   | 213       | 240   | 25 kg                                           | 100 kg                | A                | .....                          |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                         |       |        |       |                |                             |           |           |           |           |           |       |                |
|-----------------------------------------------------------------------------------------|-------|--------|-------|----------------|-----------------------------|-----------|-----------|-----------|-----------|-----------|-------|----------------|
| Calcium perchlorate .....                                                               | 5.1   | UN1455 | II    | 5.1 .....      | IB6, IP2, T3, TP33          | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A     | 56, 58         |
| Calcium permanganate .....                                                              | 5.1   | UN1456 | II    | 5.1 .....      | IB6, IP2, T3, TP33          | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | D     | 56, 58, 138    |
| Calcium peroxide .....                                                                  | 5.1   | UN1457 | II    | 5.1 .....      | IB6, IP2, T3, TP33          | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A     | 13, 52, 56, 75 |
| Calcium phosphide .....                                                                 | 4.3   | UN1360 | I     | 4.3, 6.1 ..... | A8, A19, N40                | None .... | 211 ..... | 242 ..... | Forbidden | 15 kg     | E     | 40, 52, 85     |
| Calcium, pyrophoric or Calcium alloys, pyrophoric.                                      | 4.2   | UN1855 | I     | 4.2 .....      |                             | None .... | 187 ..... | None .... | Forbidden | Forbidden | D     | .....          |
| Calcium resinate .....                                                                  | 4.1   | UN1313 | III   | 4.1 .....      | A1, A19, IB6, T1, TP33      | None .... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | .....          |
| Calcium resinate, fused .....                                                           | 4.1   | UN1314 | III   | 4.1 .....      | A1, A19, IB4, T1, TP33      | None .... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | .....          |
| Calcium selenate, see Selenates or Selenites.                                           | ..... | .....  | ..... | .....          | .....                       | .....     | .....     | .....     | .....     | .....     | ..... | .....          |
| Calcium silicide .....                                                                  | 4.3   | UN1405 | II    | 4.3 .....      | A19, IB7, IP2, T3, TP33     | 151 ..... | 212 ..... | 241 ..... | 15 kg     | 50 kg     | B     | 52, 85, 103    |
| .....                                                                                   | ..... | .....  | III   | 4.3 .....      | A1, A19, IB8, IP4, T1, TP33 | 151 ..... | 213 ..... | 241 ..... | 25 kg     | 100 kg    | B     | 52, 85, 103    |
| Camphor oil .....                                                                       | 3     | UN1130 | III   | 3 .....        | B1, IB3, T2, TP1            | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A     | .....          |
| Camphor, synthetic .....                                                                | 4.1   | UN2717 | III   | 4.1 .....      | A1, IB8, IP3, T1, TP33      | None .... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | .....          |
| Cannon primers, see Primers, tubular.                                                   | ..... | .....  | ..... | .....          | .....                       | .....     | .....     | .....     | .....     | .....     | ..... | .....          |
| Caproic acid .....                                                                      | 8     | UN2829 | III   | 8 .....        | IB3, T4, TP1                | 154 ..... | 203 ..... | 241 ..... | 5 L       | 60 L      | A     | .....          |
| Caps, blasting, see Detonators, etc.                                                    | ..... | .....  | ..... | .....          | .....                       | .....     | .....     | .....     | .....     | .....     | ..... | .....          |
| Carbamate pesticides, liquid, flammable, toxic, flash point less than 23 degrees C.     | 3     | UN2758 | I     | 3, 6.1 .....   | T14, TP2, TP13, TP27        | None .... | 201 ..... | 243 ..... | Forbidden | 30 L      | B     | 40             |
| .....                                                                                   | ..... | .....  | II    | 3, 6.1 .....   | IB2, T11, TP2, TP13, TP27   | 150 ..... | 202 ..... | 243 ..... | 1 L       | 60 L      | B     | 40             |
| Carbamate pesticides, liquid, toxic.                                                    | 6.1   | UN2992 | I     | 6.1 .....      | T14, TP2, TP13, TP27        | None .... | 201 ..... | 243 ..... | 1 L       | 30 L      | B     | 40             |
| .....                                                                                   | ..... | .....  | II    | 6.1 .....      | IB2, T11, TP2, TP13, TP27   | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B     | 40             |
| .....                                                                                   | ..... | .....  | III   | 6.1 .....      | IB3, T7, TP2, TP28          | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A     | 40             |
| Carbamate pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C. | 6.1   | UN2991 | I     | 6.1, 3 .....   | T14, TP2, TP13, TP27        | None .... | 201 ..... | 243 ..... | 1 L       | 30 L      | B     | 40             |
| .....                                                                                   | ..... | .....  | II    | 6.1, 3 .....   | IB2, T11, TP2, TP13, TP27   | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B     | 40             |
| .....                                                                                   | ..... | .....  | III   | 6.1, 3 .....   | B1, IB3, T7, TP2, TP28      | 153 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A     | 40             |
| Carbamate pesticides, solid, toxic.                                                     | 6.1   | UN2757 | I     | 6.1 .....      | IB7, IP1, T6, TP33          | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | A     | 40             |
| .....                                                                                   | ..... | .....  | II    | 6.1 .....      | IB8, IP2, IP4, T3, TP33     | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A     | 40             |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                     | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |                | (9)                                             |                       | (10)             |             |
|----------|---------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|----------------|-------------------------------------------------|-----------------------|------------------|-------------|
|          |                                                                                 |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |                | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |             |
|          |                                                                                 |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk           | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other       |
|          | .....                                                                           | .....                      |                            | III | 6.1         | IB8, IP3, T1, TP33               | 153                   | 213       | 240            | 100 kg                                          | 200 kg                | A                | 40          |
|          | <i>Carbolic acid, see</i> Phenol, solid or Phenol, molten.                      |                            |                            |     |             |                                  |                       |           |                |                                                 |                       |                  |             |
|          | <i>Carbolic acid solutions, see</i> Phenol solutions.                           |                            |                            |     |             |                                  |                       |           |                |                                                 |                       |                  |             |
| I        | Carbon, activated .....                                                         | 4.2                        | UN1362                     | III | 4.2         | IB8, IP3, T1, TP33               | None                  | 213       | 241            | 0.5 kg                                          | 0.5 kg                | A                | 12          |
| I        | Carbon, <i>animal or vegetable ori- gin.</i>                                    | 4.2                        | UN1361                     | II  | 4.2         | IB6, T3, TP33                    | None                  | 212       | 242            | Forbidden                                       | Forbidden             | A                | 12          |
|          | .....                                                                           |                            |                            | III | 4.2         | IB8, IP3, T1, TP33               | None                  | 213       | 241            | Forbidden                                       | Forbidden             | A                | 12          |
|          | <i>Carbon bisulfide, see</i> Carbon di- sulfide.                                |                            |                            |     |             |                                  |                       |           |                |                                                 |                       |                  |             |
|          | Carbon dioxide .....                                                            | 2.2                        | UN1013                     |     | 2.2         |                                  | 306                   | 302, 304. | 302, 314, 315. | 75 kg                                           | 150 kg                | A                |             |
|          | Carbon dioxide, refrigerated liq- uid.                                          | 2.2                        | UN2187                     |     | 2.2         | T75, TP5                         | 306                   | 304       | 314, 315.      | 50 kg                                           | 500 kg                | B                |             |
| A W      | Carbon dioxide, solid or Dry ice                                                | 9                          | UN1845                     | III | None        |                                  | 217                   | 217       | 240            | 200 kg                                          | 200 kg                | C                | 40          |
|          | Carbon disulfide .....                                                          | 3                          | UN1131                     | I   | 3, 6.1      | B16, T14, TP2, TP7, TP13         | None                  | 201       | 243            | Forbidden                                       | Forbidden             | D                | 18, 40, 115 |
|          | Carbon monoxide, compressed                                                     | 2.3                        | UN1016                     |     | 2.3, 2.1.   | 4                                | None                  | 302       | 314, 315.      | Forbidden                                       | 25 kg                 | D                | 40          |
| D        | Carbon monoxide, refrigerated liquid ( <i>cryogenic liquid</i> ).               | 2.3                        | NA9202                     |     | 2.3, 2.1.   | 4, T75, TP5                      | None                  | 316       | 318            | Forbidden                                       | Forbidden             | D                |             |
|          | Carbon tetrabromide .....                                                       | 6.1                        | UN2516                     | III | 6.1         | IB8, IP3, T1, TP33               | 153                   | 213       | 240            | 100 kg                                          | 200 kg                | A                | 25          |
|          | Carbon tetrachloride .....                                                      | 6.1                        | UN1846                     | II  | 6.1         | IB2, N36, T7, TP2                | 153                   | 202       | 243            | 5 L                                             | 60 L                  | A                | 40          |
|          | <i>Carbonyl chloride, see</i> Phos- gene.                                       |                            |                            |     |             |                                  |                       |           |                |                                                 |                       |                  |             |
|          | Carbonyl fluoride .....                                                         | 2.3                        | UN2417                     |     | 2.3, 8      | 2                                | None                  | 302       | None           | Forbidden                                       | Forbidden             | D                | 40          |
|          | Carbonyl sulfide .....                                                          | 2.3                        | UN2204                     |     | 2.3, 2.1.   | 3, B14                           | None                  | 304       | 314, 315.      | Forbidden                                       | Forbidden             | D                | 40          |
|          | <i>Cartridge cases, empty primed, see</i> Cases, cartridge, empty, with primer. |                            |                            |     |             |                                  |                       |           |                |                                                 |                       |                  |             |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                          |       |        |    |          |           |          |           |           |           |       |  |  |  |
|------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|----|----------|-----------|----------|-----------|-----------|-----------|-------|--|--|--|
| Cartridges, actuating, for aircraft ejector seat catapult, fire extinguisher, canopy removal or apparatus, see Cartridges, power device. | ..... |        |    | .....    |           |          |           |           |           |       |  |  |  |
| Cartridges, explosive, see Charges, demolition.                                                                                          | ..... |        |    | .....    |           |          |           |           |           |       |  |  |  |
| Cartridges, flash .....                                                                                                                  | 1.1G  | UN0049 | II | 1.1G ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 07    |  |  |  |
| Cartridges, flash .....                                                                                                                  | 1.3G  | UN0050 | II | 1.3G ..  | None .... | 62 ..... | None .... | Forbidden | 75 kg     | 07    |  |  |  |
| Cartridges for weapons, blank ...                                                                                                        | 1.1C  | UN0326 | II | 1.1C ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 07    |  |  |  |
| Cartridges for weapons, blank ...                                                                                                        | 1.2C  | UN0413 | II | 1.2C ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 07    |  |  |  |
| Cartridges for weapons, blank or Cartridges, small arms, blank.                                                                          | 1.4S  | UN0014 | II | None     | 63 .....  | 62 ..... | None .... | 25 kg     | 100 kg    | 05    |  |  |  |
| Cartridges for weapons, blank or Cartridges, small arms, blank.                                                                          | 1.3C  | UN0327 | II | 1.3C ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 07    |  |  |  |
| Cartridges for weapons, blank or Cartridges, small arms, blank.                                                                          | 1.4C  | UN0338 | II | 1.4C ..  | None .... | 62 ..... | None .... | Forbidden | 75 kg     | 06    |  |  |  |
| Cartridges for weapons, inert projectile.                                                                                                | 1.2C  | UN0328 | II | 1.2C ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 03    |  |  |  |
| Cartridges for weapons, inert projectile or Cartridges, small arms.                                                                      | 1.4S  | UN0012 | II | None     | 63 .....  | 62 ..... | None .... | 25 kg     | 100 kg    | 05    |  |  |  |
| Cartridges for weapons, inert projectile or Cartridges, small arms.                                                                      | 1.4C  | UN0339 | II | 1.4C ..  | None .... | 62 ..... | None .... | Forbidden | 75 kg     | 06    |  |  |  |
| Cartridges for weapons, inert projectile or Cartridges, small arms.                                                                      | 1.3C  | UN0417 | II | 1.3C ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 06    |  |  |  |
| Cartridges for weapons, with bursting charge.                                                                                            | 1.1F  | UN0005 | II | 1.1F ... | None .... | 62 ..... | None .... | Forbidden | Forbidden | 08    |  |  |  |
| Cartridges for weapons, with bursting charge.                                                                                            | 1.1E  | UN0006 | II | 1.1E ... | None .... | 62 ..... | None .... | Forbidden | Forbidden | 03    |  |  |  |
| Cartridges for weapons, with bursting charge.                                                                                            | 1.2F  | UN0007 | II | 1.2F ... | None .... | 62 ..... | None .... | Forbidden | Forbidden | 08    |  |  |  |
| Cartridges for weapons, with bursting charge.                                                                                            | 1.2E  | UN0321 | II | 1.2E ... | None .... | 62 ..... | None .... | Forbidden | Forbidden | 03    |  |  |  |
| Cartridges for weapons, with bursting charge.                                                                                            | 1.4F  | UN0348 | II | 1.4F ... | None .... | 62 ..... | None .... | Forbidden | Forbidden | 08    |  |  |  |
| Cartridges for weapons, with bursting charge.                                                                                            | 1.4E  | UN0412 | II | 1.4E ... | None .... | 62 ..... | None .... | Forbidden | 75 kg     | 02    |  |  |  |
| Cartridges, oil well .....                                                                                                               | 1.3C  | UN0277 | II | 1.3C ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 07    |  |  |  |
| Cartridges, oil well .....                                                                                                               | 1.4C  | UN0278 | II | 1.4C ..  | None .... | 62 ..... | None .... | Forbidden | 75 kg     | 06    |  |  |  |
| Cartridges, power device .....                                                                                                           | 1.3C  | UN0275 | II | 1.3C ..  | None .... | 62 ..... | None .... | Forbidden | 75 kg     | 07    |  |  |  |
| Cartridges, power device .....                                                                                                           | 1.4C  | UN0276 | II | 1.4C ..  | None .... | 62 ..... | None .... | Forbidden | 75 kg     | 06    |  |  |  |
| Cartridges, power device .....                                                                                                           | 1.4S  | UN0323 | II | 1.4S ... | 63 .....  | 62 ..... | None .... | 25 kg     | 100 kg    | 05    |  |  |  |
| Cartridges, power device .....                                                                                                           | 1.2C  | UN0381 | II | 1.2C ..  | None .... | 62 ..... | None .... | Forbidden | Forbidden | 07    |  |  |  |
| Cartridges, safety, blank, see Cartridges for weapons, blank (UN 0014).                                                                  | ..... |        |    | .....    | .....     | .....    | .....     | .....     | .....     | ..... |  |  |  |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                               | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                                                                           |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                                                                           |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
|          | <i>Cartridges, safety, see</i> Cartridges for weapons, inert projectile, or Cartridges, small arms or Cartridges, power device (UN 0323). |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |        |
|          | Cartridges, signal .....                                                                                                                  | 1.3G                       | UN0054                     | II  | 1.3G ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 07               | .....  |
|          | Cartridges, signal .....                                                                                                                  | 1.4G                       | UN0312                     | II  | 1.4G ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....  |
|          | Cartridges, signal .....                                                                                                                  | 1.4S                       | UN0405                     | II  | 1.4S ...    |                                  | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               | .....  |
| D        | Cartridges, small arms .....                                                                                                              | ORM-D                      |                            |     | None        |                                  | 63 .....              | None .... | None .... | 30 kg gross                                     | 30 kg gross           | A                | .....  |
| D        | Cartridges power device ( <i>used to project fastening devices</i> ).                                                                     | ORM-D                      |                            |     | None        |                                  | 63 .....              | None .... | None .... | 30 kg gross                                     | 30 kg gross           | A                | .....  |
|          | <i>Cartridges, sporting, see</i> Cartridges for weapons, inert projectile, or Cartridges, small arms.                                     |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |        |
|          | <i>Cartridges, starter, jet engine, see</i> Cartridges, power device.                                                                     |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |        |
|          | Cases, cartridge, empty with primer.                                                                                                      | 1.4S                       | UN0055                     | II  | 1.4S ...    | 50                               | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               | .....  |
|          | Cases, cartridges, empty with primer.                                                                                                     | 1.4C                       | UN0379                     | II  | 1.4C ..     | 50                               | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....  |
|          | Cases, combustible, empty, without primer.                                                                                                | 1.4C                       | UN0446                     | II  | 1.4C ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....  |
|          | Cases, combustible, empty, without primer.                                                                                                | 1.3C                       | UN0447                     | II  | 1.3C ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....  |
|          | <i>Casinghead gasoline see</i> Gasoline.                                                                                                  |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |        |
| A W      | Castor beans or Castor meal or Castor pomace or Castor flake.                                                                             | 9                          | UN2969                     | II  | None        | IB8, IP2, IP4, T3, TP33          | 155 .....             | 204 ..... | 240 ..... | No limit                                        | No limit              | E                | 34, 40 |
| G        | Caustic alkali liquids, n.o.s. ....                                                                                                       | 8                          | UN1719                     | II  | 8 .....     | B2, IB2, T11, TP2, TP27          | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | A                | 29, 52 |
|          | .....                                                                                                                                     |                            |                            | III | 8 .....     | IB3, T7, TP1, TP28               | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | 29, 52 |
|          | <i>Caustic potash, see</i> Potassium hydroxide etc.                                                                                       |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |        |
|          | <i>Caustic soda, (etc.) see</i> Sodium hydroxide etc.                                                                                     |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |        |
|          | Cells, containing sodium .....                                                                                                            | 4.3                        | UN3292                     | II  | 4.3 ....    |                                  | 189 .....             | 189 ..... | 189 ..... | 25 kg gross                                     | No limit              | A                | .....  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                             |       |        |       |           |                             |           |           |           |           |           |       |        |
|---|---------------------------------------------------------------------------------------------|-------|--------|-------|-----------|-----------------------------|-----------|-----------|-----------|-----------|-----------|-------|--------|
| D | Celluloid, <i>in block, rods, rolls, sheets, tubes, etc., except scrap.</i>                 | 4.1   | UN2000 | III   | 4.1 ..... |                             | None .... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | .....  |
|   | Celluloid, scrap .....                                                                      | 4.2   | UN2002 | III   | 4.2 ..... | IB8, IP3                    | None .... | 213 ..... | 241 ..... | Forbidden | Forbidden | D     | .....  |
|   | Cement, <i>see</i> Adhesives containing flammable liquid.                                   | ..... | .....  | ..... | .....     | .....                       | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
|   | Cerium, <i>slabs, ingots, or rods</i> ...                                                   | 4.1   | UN1333 | II    | 4.1 ..... | IB8, IP2, IP4, N34          | None .... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | A     | 74, 91 |
|   | Cerium, <i>turnings or gritty powder.</i>                                                   | 4.3   | UN3078 | II    | 4.3 ..... | A1, IB7, IP2, T3, TP33      | 151 ..... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | E     | 52     |
|   | Cesium or Caesium .....                                                                     | 4.3   | UN1407 | I     | 4.3 ..... | A7, A19, IB4, IP1, N34, N40 | None .... | 211 ..... | 242 ..... | Forbidden | 15 kg     | D     | 52     |
|   | Cesium nitrate or Caesium nitrate.                                                          | 5.1   | UN1451 | III   | 5.1 ..... | A1, A29, IB8, IP3, T1, TP33 | 152 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | .....  |
|   | Charcoal <i>briquettes, shell, screenings, wood, etc.</i>                                   | 4.2   | NA1361 | III   | 4.2 ..... | IB8, T1, TP33               | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | 12     |
|   | Charges, <i>bursting, plastics bonded.</i>                                                  | 1.1D  | UN0457 | II    | 1.1D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>bursting, plastics bonded.</i>                                                  | 1.2D  | UN0458 | II    | 1.2D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>bursting, plastics bonded.</i>                                                  | 1.4D  | UN0459 | II    | 1.4D ..   |                             | None .... | 62 .....  | None .... | Forbidden | 75 kg     | 06    | .....  |
|   | Charges, <i>bursting, plastics bonded.</i>                                                  | 1.4S  | UN0460 | II    | 1.4S ...  |                             | None .... | 62 .....  | None .... | 25 kg     | 100 kg    | 05    | .....  |
|   | Charges, <i>demolition</i> .....                                                            | 1.1D  | UN0048 | II    | 1.1D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 03    | .....  |
|   | Charges, <i>depth</i> .....                                                                 | 1.1D  | UN0056 | II    | 1.1D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 03    | .....  |
|   | Charges, <i>expelling, explosive, for fire extinguishers, see Cartridges, power device.</i> | ..... | .....  | ..... | .....     | .....                       | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
|   | Charges, <i>explosive, commercial without detonator.</i>                                    | 1.1D  | UN0442 | II    | 1.1D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>explosive, commercial without detonator.</i>                                    | 1.2D  | UN0443 | II    | 1.2D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>explosive, commercial without detonator.</i>                                    | 1.4D  | UN0444 | II    | 1.4D ..   |                             | None .... | 62 .....  | None .... | Forbidden | 75 kg     | 06    | .....  |
|   | Charges, <i>explosive, commercial without detonator.</i>                                    | 1.4S  | UN0445 | II    | 1.4S ...  |                             | None .... | 62 .....  | None .... | 25 kg     | 100 kg    | 05    | .....  |
|   | Charges, <i>propelling</i> .....                                                            | 1.1C  | UN0271 | II    | 1.1C ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>propelling</i> .....                                                            | 1.3C  | UN0272 | II    | 1.3C ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>propelling</i> .....                                                            | 1.2C  | UN0415 | II    | 1.2C ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>propelling</i> .....                                                            | 1.4C  | UN0491 | II    | 1.4C ..   |                             | None .... | 62 .....  | None .... | Forbidden | 75 kg     | 06    | .....  |
|   | Charges, <i>propelling, for cannon</i>                                                      | 1.3C  | UN0242 | II    | 1.3C ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | .....  |
|   | Charges, <i>propelling, for cannon</i>                                                      | 1.1C  | UN0279 | II    | 1.1C ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | .....  |
|   | Charges, <i>propelling, for cannon</i>                                                      | 1.2C  | UN0414 | II    | 1.2C ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | .....  |
|   | Charges, <i>shaped, flexible, linear</i>                                                    | 1.4D  | UN0237 | II    | 1.4D ..   |                             | None .... | 62 .....  | None .... | Forbidden | 75 kg     | 06    | .....  |
|   | Charges, <i>shaped, flexible, linear</i>                                                    | 1.1D  | UN0288 | II    | 1.1D ..   | .....                       | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>shaped, without detonator.</i>                                                  | 1.1D  | UN0059 | II    | 1.1D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |
|   | Charges, <i>shaped, without detonator.</i>                                                  | 1.2D  | UN0439 | II    | 1.2D ..   |                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 07    | .....  |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                       | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |             |
|----------|-----------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------------|
|          |                                                                                   |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |             |
|          |                                                                                   |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other       |
| D        | Charges, shaped, <i>without deto- nator</i> .                                     | 1.4D                       | UN0440                     | II    | 1.4D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....       |
|          | Charges, shaped, <i>without deto- nator</i> .                                     | 1.4S                       | UN0441                     | II    | 1.4S ...    |                                  | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               | .....       |
|          | Charges, supplementary explo- sive.                                               | 1.1D                       | UN0060                     | II    | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | .....       |
|          | Chemical kit .....                                                                | 8                          | NA1760                     | II    | 8 .....     |                                  | 154 .....             | 161 ..... | None .... | 1 L                                             | 30 L                  | B                | 40          |
|          | Chemical kits .....                                                               | 9                          | UN3316                     | ..... | 9 .....     | 15                               | 161 .....             | 161 ..... | None .... | 10 kg                                           | 10 kg                 | A                | .....       |
|          | Chloral, anhydrous, stabilized ....                                               | 6.1                        | UN2075                     | II    | 6.1 .....   | IB2, T7, TP2                     | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | D                | 40          |
|          | Chlorate and borate mixtures ....                                                 | 5.1                        | UN1458                     | II    | 5.1 .....   | A9, IB8, IP2, IP4, N34, T3, TP33 | 152 .....             | 212 ..... | 240 ..... | 5 kg                                            | 25 kg                 | A                | 56, 58      |
|          | .....                                                                             | .....                      | .....                      | III   | 5.1 .....   | A9, IB8, IP3, N34, T1, TP33      | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | 56, 58      |
|          | Chlorate and magnesium chlo- ride mixture solid.                                  | 5.1                        | UN1459                     | II    | 5.1 .....   | A9, IB8, IP2, IP4, N34, T3, TP33 | 152 .....             | 212 ..... | 240 ..... | 5 kg                                            | 25 kg                 | A                | 56, 58      |
|          | .....                                                                             | .....                      | .....                      | III   | 5.1 .....   | A9, IB8, IP3, N34, T1, TP33      | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | 56, 58      |
|          | Chlorate and magnesium chlo- ride mixture solution.                               | 5.1                        | UN3407                     | II    | 5.1 .....   | A9, IB2, N34, T4, TP1            | 152 .....             | 202 ..... | 242 ..... | 1 L                                             | 5 L                   | A                | 56, 58, 133 |
|          | .....                                                                             | .....                      | .....                      | III   | 5.1 .....   | A9, IB2, N34, T4, TP1            | 152 .....             | 203 ..... | 241 ..... | 2.5 L                                           | 30 L                  | A                | 56, 58, 133 |
|          | <i>Chlorate of potash, see Potas- sium chlorate.</i>                              | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....       |
|          | <i>Chlorate of soda, see Sodium chlorate.</i>                                     | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....       |
|          | Chlorates, inorganic, aqueous solution, n.o.s..                                   | 5.1                        | UN3210                     | II    | 5.1 .....   | IB2, T4, TP1                     | 152 .....             | 202 ..... | 242 ..... | 1 L                                             | 5 L                   | B                | 56, 58, 133 |
|          | .....                                                                             | .....                      | .....                      | III   | 5.1 .....   | IB2, T4, TP1                     | 152 .....             | 203 ..... | 241 ..... | 2.5 L                                           | 30 L                  | B                | 56, 58, 133 |
|          | Chlorates, inorganic, n.o.s. ....                                                 | 5.1                        | UN1461                     | II    | 5.1 .....   | A9, IB6, IP2, N34, T3, TP33      | 152 .....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg                 | A                | 56, 58      |
|          | Chloric acid aqueous solution, <i>with not more than 10 percent chloric acid.</i> | 5.1                        | UN2626                     | II    | 5.1 .....   | IB2, T4, TP1                     | None ....             | 229 ..... | None .... | Forbidden                                       | Forbidden             | D                | 56, 58      |
|          | <i>Chloride of phosphorus, see Phosphorus trichloride.</i>                        | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....       |
|          | <i>Chloride of sulfur, see Sulfur chloride.</i>                                   | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....       |
|          | <i>Chlorinated lime, see Calcium hypochlorite mixtures, etc.</i>                  | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....       |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                              |           |        |       |              |                                                                 |           |           |           |           |           |   |                            |
|---|--------------------------------------------------------------|-----------|--------|-------|--------------|-----------------------------------------------------------------|-----------|-----------|-----------|-----------|-----------|---|----------------------------|
| D | Chlorine .....                                               | 2.3       | UN1017 | ..... | 2.3, 8       | 2, B9, B14, N86, T50, TP19                                      | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D | 40, 51, 55, 62, 68, 89, 90 |
|   | Chlorine azide .....                                         | Forbidden |        |       | .....        |                                                                 | .....     | .....     | .....     | .....     | .....     |   | .....                      |
|   | Chlorine dioxide, hydrate, frozen                            | 5.1       | NA9191 | II    | 5.1, 6.1.    |                                                                 | None .... | 229 ..... | None .... | Forbidden | Forbidden | E | .....                      |
|   | Chlorine dioxide (not hydrate) ...                           | Forbidden |        |       | .....        |                                                                 | .....     | .....     | .....     | .....     | .....     |   | .....                      |
|   | Chlorine pentafluoride .....                                 | 2.3       | UN2548 | ..... | 2.3, 5.1, 8. | 1, B7, B9, B14, N86                                             | None .... | 304 ..... | 314 ..... | Forbidden | Forbidden | D | 40, 89, 90                 |
|   | Chlorine trifluoride .....                                   | 2.3       | UN1749 | ..... | 2.3, 5.1, 8. | 2, B7, B9, B14, N86                                             | None .... | 304 ..... | 314 ..... | Forbidden | Forbidden | D | 40, 89, 90                 |
|   | Chlorite solution .....                                      | 8         | UN1908 | II    | 8            | A3, A6, A7, B2, IB2, N34, T7, TP2, TP24                         | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | B | 26, 44, 89, 100, 141       |
|   | .....                                                        |           |        | III   | 8            | A3, A6, A7, B2, IB3, N34, T4, TP2, TP24                         | 154 ..... | 203 ..... | 241 ..... | 5 L       | 60 L      | B | 26, 44, 89, 100, 141       |
|   | Chlorites, inorganic, n.o.s. ....                            | 5.1       | UN1462 | II    | 5.1          | A7, IB6, IP2, N34, T3, TP33                                     | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A | 56, 58                     |
|   | 1-Chloro-1,1-difluoroethane or Refrigerant gas R 142b.       | 2.1       | UN2517 | ..... | 2.1          | T50                                                             | 306 ..... | 304 ..... | 314, 315. | Forbidden | 150 kg    | B | 40                         |
|   | 3-Chloro-4-methylphenyl isocyanate, liquid.                  | 6.1       | UN2236 | II    | 6.1          | IB2                                                             | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B | 40                         |
|   | 3-Chloro-4-methylphenyl isocyanate, solid.                   | 6.1       | UN3428 | II    | 6.1          | IB8, IP2, IP4, T3, TP33                                         | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | B | 40                         |
|   | 1-Chloro-1,2,2,2-tetrafluoroethane or Refrigerant gas R 124. | 2.2       | UN1021 | ..... | 2.2          | T50                                                             | 306 ..... | 304 ..... | 314, 315. | 75 kg     | 150 kg    | A | .....                      |
|   | 4-Chloro-o-toluidine hydrochloride, solid.                   | 6.1       | UN1579 | III   | 6.1          | IB8, IP3, T1, TP33                                              | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A | .....                      |
|   | 4-Chloro-o-toluidine hydrochloride, solution.                | 6.1       | UN3410 | III   | 6.1          | IB3, T4, TP1                                                    | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A | .....                      |
|   | 1-Chloro-2,2,2-trifluoroethane or Refrigerant gas R 133a.    | 2.2       | UN1983 | ..... | 2.2          | T50                                                             | 306 ..... | 304 ..... | 314, 315. | 75 kg     | 150 kg    | A | .....                      |
|   | Chloroacetic acid, molten .....                              | 6.1       | UN3250 | II    | 6.1, 8       | IB1, T7, TP3, TP28                                              | None .... | 202 ..... | 243 ..... | Forbidden | Forbidden | C | 40                         |
|   | Chloroacetic acid, solid .....                               | 6.1       | UN1751 | II    | 6.1, 8       | A3, A7, IB8, IP4, N34, T3, TP33                                 | 153 ..... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | A | 40                         |
|   | Chloroacetic acid, solution .....                            | 6.1       | UN1750 | II    | 6.1, 8       | A7, IB2, N34, T7, TP2                                           | 153 ..... | 202 ..... | 243 ..... | 1 L       | 30 L      | C | 40                         |
|   | Chloroacetone, stabilized .....                              | 6.1       | UN1695 | I     | 6.1, 3, 8.   | 2, B9, B14, B32, B74, N12, N32, N34, T20, TP2, TP13, TP38, TP45 | None .... | 227 ..... | 244 ..... | Forbidden | Forbidden | D | 21, 40, 100                |
|   |                                                              |           |        |       |              |                                                                 |           |           |           |           |           |   |                            |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                                                                                                        | Hazard class or Division | Identification Numbers | PG  | Label Codes | Special provisions (§ 172.102)                                          | (8)                   |          |           | (9)                                             |                     | (10)           |            |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|------------------------|-----|-------------|-------------------------------------------------------------------------|-----------------------|----------|-----------|-------------------------------------------------|---------------------|----------------|------------|
|          |                                                                                                                                                                   |                          |                        |     |             |                                                                         | Packaging (§ 173.***) |          |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |            |
|          |                                                                                                                                                                   |                          |                        |     |             |                                                                         | Excep-tions           | Non-bulk | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Location       | Other      |
| +        | <i>Chloroacetone (unstabilized)</i> .....                                                                                                                         | Forbidden                |                        |     |             |                                                                         |                       |          |           |                                                 |                     |                |            |
|          | Chloroacetonitrile .....                                                                                                                                          | 6.1                      | UN2668                 | II  | 6.1, 3      | 2, B9, B14, B32, B74, IB9, T20, TP2, TP38, TP45                         | None                  | 227      | 244       | Forbidden                                       | Forbidden           | A              | 12, 40, 52 |
|          | Chloroacetophenone, liquid, (CN).                                                                                                                                 | 6.1                      | UN3416                 | II  | 6.1         | A3, IB2, N12, N32, N33, T7, TP2, TP13                                   | None                  | 202      | 243       | Forbidden                                       | 60 L                | D              | 12, 40     |
|          | Chloroacetophenone, solid, (CN)                                                                                                                                   | 6.1                      | UN1697                 | II  | 6.1         | A3, IB8, IP2, IP4, N12, N32, N33, N34, T3, TP2, TP13, TP33              | None                  | 212      | None      | Forbidden                                       | 100 kg              | D              | 12, 40     |
|          | Chloroacetyl chloride .....                                                                                                                                       | 6.1                      | UN1752                 | I   | 6.1, 8      | 2, B3, B8, B9, B14, B32, B74, B77, N34, N43, T20, TP2, TP13, TP38, TP45 | None                  | 227      | 244       | Forbidden                                       | Forbidden           | D              | 40         |
|          | Chloroanilines, liquid .....                                                                                                                                      | 6.1                      | UN2019                 | II  | 6.1         | IB2, T7, TP2                                                            | 153                   | 202      | 243       | 5 L                                             | 60 L                | A              | 52         |
|          | Chloroanilines, solid .....                                                                                                                                       | 6.1                      | UN2018                 | II  | 6.1         | IB8, IP2, IP4, T3, TP33                                                 | 153                   | 212      | 242       | 25 kg                                           | 100 kg              | A              |            |
|          | Chloroanisidines .....                                                                                                                                            | 6.1                      | UN2233                 | III | 6.1         | IB8, IP3, T1, TP33                                                      | 153                   | 213      | 240       | 100 kg                                          | 200 kg              | A              |            |
|          | Chlorobenzene .....                                                                                                                                               | 3                        | UN1134                 | III | 3           | B1, IB3, T2, TP1                                                        | 150                   | 203      | 242       | 60 L                                            | 220 L               | A              |            |
|          | <i>Chlorobenzol, see Chlorobenzene.</i>                                                                                                                           |                          |                        |     |             |                                                                         |                       |          |           |                                                 |                     |                |            |
|          | Chlorobenzotrifluorides .....                                                                                                                                     | 3                        | UN2234                 | III | 3           | B1, IB3, T2, TP1                                                        | 150                   | 203      | 242       | 60 L                                            | 220 L               | A              | 40         |
|          | Chlorobenzyl chlorides, liquid ....                                                                                                                               | 6.1                      | UN2235                 | III | 6.1         | IB3, T4, TP1                                                            | 153                   | 203      | 241       | 60 L                                            | 220 L               | A              |            |
|          | Chlorobenzyl chlorides, solid .....                                                                                                                               | 6.1                      | UN3427                 | III | 6.1         | IB8, IP3, T1, TP33                                                      | 153                   | 213      | 240       | 100 kg                                          | 200 kg              | A              |            |
|          | Chlorobutanes .....                                                                                                                                               | 3                        | UN1127                 | II  | 3           | IB2, T4, TP1                                                            | 150                   | 202      | 242       | 5 L                                             | 60 L                | B              |            |
|          | Chlorocresols solution .....                                                                                                                                      | 6.1                      | UN2669                 | II  | 6.1         | IB2, T7, TP2                                                            | 153                   | 202      | 243       | 5 L                                             | 60 L                | A              | 12         |
|          |                                                                                                                                                                   |                          |                        | III | 6.1         | IB3, T7, TP2                                                            | 153                   | 203      | 241       | 60 L                                            | 220 L               | A              | 12         |
|          | Chlorocresols, solid .....                                                                                                                                        | 6.1                      | UN3437                 | II  | 6.1         | IB8, IP2, IP4, T3, TP33                                                 | 153                   | 212      | 242       | 25 kg                                           | 100 kg              | A              | 12         |
|          | Chlorodifluorobromomethane or Refrigerant gas R 12B1.                                                                                                             | 2.2                      | UN1974                 |     | 2.2         | T50                                                                     | 306                   | 304      | 314, 315. | 75 kg                                           | 150 kg              | A              |            |
|          | Chlorodifluoromethane and chloropentafluoroethane mixture or Refrigerant gas R 502 with fixed boiling point, with approximately 49 percent chlorodifluoromethane. | 2.2                      | UN1973                 |     | 2.2         | T50                                                                     | 306                   | 304      | 314, 315. | 75 kg                                           | 150 kg              | A              |            |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                         |     |        |       |            |                                                           |      |       |     |       |           |           |           |   |                         |
|---|---------------------------------------------------------|-----|--------|-------|------------|-----------------------------------------------------------|------|-------|-----|-------|-----------|-----------|-----------|---|-------------------------|
|   | Chlorodifluoromethane or Refrigerant gas R 22.          | 2.2 | UN1018 | ..... | 2.2        | T50                                                       | 306  | ..... | 304 | ..... | 314, 315. | 75 kg     | 150 kg    | A | .....                   |
| + | Chlorodinitrobenzenes, liquid. ....                     | 6.1 | UN1577 | II    | 6.1        | IB2, T7, TP2                                              | 153  | ..... | 202 | ..... | 243       | 5 L       | 60 L      | B | 91                      |
| + | Chlorodinitrobenzenes, solid .....                      | 6.1 | UN3441 | II    | 6.1        | IB8, IP2, IP4, T3, TP33                                   | 153  | ..... | 212 | ..... | 242       | 25 kg     | 100 kg    | A | 91                      |
|   | 2-Chloroethanal .....                                   | 6.1 | UN2232 | I     | 6.1        | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45          | None | ....  | 227 | ..... | 244       | Forbidden | Forbidden | D | 40                      |
|   | Chloroform .....                                        | 6.1 | UN1888 | III   | 6.1        | IB3, N36, T7, TP2                                         | 153  | ..... | 203 | ..... | 241       | 60 L      | 220 L     | A | 40                      |
| G | Chloroformates, toxic, corrosive, flammable, n.o.s..    | 6.1 | UN2742 | II    | 6.1, 8, 3. | 5, IB1, T7, TP2                                           | 153  | ..... | 202 | ..... | 243       | 1 L       | 30 L      | A | 12, 13, 21, 25, 40, 100 |
| G | Chloroformates, toxic, corrosive, n.o.s..               | 6.1 | UN3277 | II    | 6.1, 8     | IB2, T8, TP2, TP13, TP28                                  | 153  | ..... | 202 | ..... | 243       | 1 L       | 30 L      | A | 12, 13, 25, 40          |
|   | Chloromethyl chloroformate .....                        | 6.1 | UN2745 | II    | 6.1, 8     | IB2, T7, TP2, TP13                                        | 153  | ..... | 202 | ..... | 243       | 1 L       | 30 L      | A | 12, 13, 21, 25, 40, 100 |
|   | Chloromethyl ethyl ether .....                          | 3   | UN2354 | II    | 3, 6.1     | IB2, T7, TP1, TP13                                        | 150  | ..... | 202 | ..... | 243       | 1 L       | 60 L      | E | 40                      |
|   | Chloronitroanilines .....                               | 6.1 | UN2237 | III   | 6.1        | IB8, IP3, T1, TP33                                        | 153  | ..... | 213 | ..... | 240       | 100 kg    | 200 kg    | A | .....                   |
| + | Chloronitrobenzene, liquid <i>ortho</i>                 | 6.1 | UN3409 | II    | 6.1        | IB2, T7, TP2                                              | 153  | ..... | 202 | ..... | 243       | 5 L       | 60 L      | A | .....                   |
| + | Chloronitrobenzenes, solid <i>meta</i> or <i>para</i> . | 6.1 | UN1578 | II    | 6.1        | IB8, IP2, IP4, T3, TP33                                   | 153  | ..... | 212 | ..... | 242       | 25 kg     | 100 kg    | A | .....                   |
|   | Chloronitrotoluenes, liquid .....                       | 6.1 | UN2433 | III   | 6.1        | IB3, T4, TP1                                              | 153  | ..... | 203 | ..... | 241       | 60 L      | 220 L     | A | 44, 89, 100, 141        |
|   | Chloronitrotoluenes, solid .....                        | 6.1 | UN3457 | III   | 6.1        | IB8, IP3, T1, TP33                                        | 153  | ..... | 213 | ..... | 240       | 25 kg     | 200 kg    | A | .....                   |
|   | Chloropentafluoroethane or Refrigerant gas R 115.       | 2.2 | UN1020 | ..... | 2.2        | T50                                                       | 306  | ..... | 304 | ..... | 314, 315. | 75 kg     | 150 kg    | A | .....                   |
|   | Chlorophenolates, liquid or Phenolates, liquid.         | 8   | UN2904 | III   | 8          | IB3                                                       | 154  | ..... | 203 | ..... | 241       | 5 L       | 60 L      | A | .....                   |
|   | Chlorophenolates, solid or Phenolates, solid.           | 8   | UN2905 | III   | 8          | IB8, IP3, T1, TP33                                        | 154  | ..... | 213 | ..... | 240       | 25 kg     | 100 kg    | A | .....                   |
|   | Chlorophenols, liquid .....                             | 6.1 | UN2021 | III   | 6.1        | IB3, T4, TP1                                              | 153  | ..... | 203 | ..... | 241       | 60 L      | 220 L     | A | .....                   |
|   | Chlorophenols, solid .....                              | 6.1 | UN2020 | III   | 6.1        | IB8, IP3, T1, TP1, TP33                                   | 153  | ..... | 213 | ..... | 240       | 100 kg    | 200 kg    | A | .....                   |
|   | Chlorophenyltrichlorosilane .....                       | 8   | UN1753 | II    | 8          | A7, B2, B6, IB2, N34, T7, TP2                             | None | ....  | 202 | ..... | 242       | Forbidden | 30 L      | C | 40                      |
| + | Chloropicrin .....                                      | 6.1 | UN1580 | I     | 6.1        | 2, B7, B9, B14, B32, B46, B74, T20, TP2, TP13, TP38, TP45 | None | ....  | 227 | ..... | 244       | Forbidden | Forbidden | D | 40                      |
|   | Chloropicrin and methyl bromide mixtures.               | 2.3 | UN1581 | ..... | 2.3        | 2, B9, B14, N86, T50                                      | None | ....  | 193 | ..... | 314, 315. | Forbidden | Forbidden | D | 25, 40                  |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                   | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)                       | (8)                   |           |          | (9)                                             |                       | (10)             |                     |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|--------------------------------------------------------|-----------------------|-----------|----------|-------------------------------------------------|-----------------------|------------------|---------------------|
|          |                                                                                                                                                               |                            |                            |     |             |                                                        | Packaging (§ 173.***) |           |          | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                     |
|          |                                                                                                                                                               |                            |                            |     |             |                                                        | Excep- tions          | Non- bulk | Bulk     | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other               |
| (1)      | (2)                                                                                                                                                           | (3)                        | (4)                        | (5) | (6)         | (7)                                                    | (8A)                  | (8B)      | (8C)     | (9A)                                            | (9B)                  | (10A)            | (10B)               |
| D        | <i>Chloropicrin mixture, flammable (pressure not exceeding 14.7 psia at 115 degrees F flash point below 100 degrees F) see Toxic liquids, flammable, etc.</i> | .....                      |                            |     | .....       |                                                        | .....                 | .....     | .....    | .....                                           | .....                 |                  | .....               |
|          | Chloropicrin mixtures, n.o.s. ....                                                                                                                            | 6.1                        | UN1583                     | I   | 6.1 ....    | 5                                                      | None ....             | 201 ....  | 243 .... | Forbidden                                       | Forbidden             | C                | 40                  |
|          | .....                                                                                                                                                         | .....                      | .....                      | II  | 6.1 ....    | IB2                                                    | 153 ....              | 202 ....  | 243 .... | Forbidden                                       | Forbidden             | C                | 40                  |
|          | .....                                                                                                                                                         | .....                      | .....                      | III | 6.1 ....    | IB3                                                    | 153 ....              | 203 ....  | 241 .... | Forbidden                                       | Forbidden             | C                | 40                  |
|          | Chloropivaloyl chloride .....                                                                                                                                 | 6.1                        | NA9263                     | I   | 6.1, 8      | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None ....             | 227 ....  | 244 .... | Forbidden                                       | Forbidden             | B                | 40                  |
|          | Chloroplatinic acid, solid .....                                                                                                                              | 8                          | UN2507                     | III | 8 .....     | IB8, IP3, T1, TP33                                     | 154 ....              | 213 ....  | 240 .... | 25 kg                                           | 100 kg                | A                | .....               |
|          | Chloroprene, stabilized .....                                                                                                                                 | 3                          | UN1991                     | I   | 3, 6.1      | B57, T14, TP2, TP13                                    | None ....             | 201 ....  | 243 .... | Forbidden                                       | 30 L                  | D                | 40                  |
|          | <i>Chloroprene, uninhibited</i> .....                                                                                                                         | Forbidden                  |                            |     | .....       |                                                        | .....                 | .....     | .....    | .....                                           | .....                 |                  | .....               |
|          | 1-Chloropropane .....                                                                                                                                         | 3                          | UN1278                     | II  | 3 .....     | IB2, IP8, N34, T7, TP2                                 | None ....             | 202 ....  | 242 .... | Forbidden                                       | 60 L                  | E                | .....               |
|          | 2-Chloropropane .....                                                                                                                                         | 3                          | UN2356                     | I   | 3 .....     | N36, T11, TP2, TP13                                    | 150 ....              | 201 ....  | 243 .... | 1 L                                             | 30 L                  | E                | .....               |
|          | 3-Chloropropanol-1 .....                                                                                                                                      | 6.1                        | UN2849                     | III | 6.1 ....    | IB3, T4, TP1                                           | 153 ....              | 203 ....  | 241 .... | 60 L                                            | 220 L                 | A                | .....               |
|          | 2-Chloropropene .....                                                                                                                                         | 3                          | UN2456                     | I   | 3 .....     | A3, N36, T11, TP2                                      | 150 ....              | 201 ....  | 243 .... | 1 L                                             | 30 L                  | E                | .....               |
|          | 2-Chloropropionic acid .....                                                                                                                                  | 8                          | UN2511                     | III | 8 .....     | IB3, T4, TP2                                           | 154 ....              | 203 ....  | 241 .... | 5 L                                             | 60 L                  | A                | 8                   |
|          | 2-Chloropyridine .....                                                                                                                                        | 6.1                        | UN2822                     | II  | 6.1 ....    | IB2, T7, TP2                                           | 153 ....              | 202 ....  | 243 .... | 5 L                                             | 60 L                  | A                | 40                  |
|          | Chlorosilanes, corrosive, n.o.s. ...                                                                                                                          | 8                          | UN2987                     | II  | 8 .....     | B2, IB2, T14, TP2, TP27                                | None ....             | 202 ....  | 242 .... | 1 L                                             | 30 L                  | C                | 40.                 |
|          | Chlorosilanes, flammable, corro- sive, n.o.s.                                                                                                                 | 3                          | UN2985                     | II  | 3, 8 ....   | IB1, T11, TP2, TP13, TP27                              | None ....             | 201 ....  | 243 .... | 1 L                                             | 5 L                   | B                | 40.                 |
|          | Chlorosilanes, toxic, corrosive, n.o.s.                                                                                                                       | 6.1                        | UN3361                     | II  | 6.1, 8      | IB1, T11, TP2, TP13                                    | None ....             | 202 ....  | 243 .... | 1 L                                             | 30 L                  | C                | 40.                 |
|          | Chlorosilanes, toxic, corrosive, flammable, n.o.s.                                                                                                            | 6.1                        | UN3362                     | II  | 6.1, 3, 8.  | IB1, T11, TP2, TP13                                    | None ....             | 202 ....  | 243 .... | 1 L                                             | 30 L                  | C                | 40, 125.            |
|          | Chlorosilanes, water-reactive, flammable, corrosive, n.o.s..                                                                                                  | 4.3                        | UN2988                     | I   | 4.3, 3, 8.  | A2, T10, TP2, TP7, TP13                                | None ....             | 201 ....  | 244 .... | Forbidden                                       | 1 L                   | D                | 21, 28, 40, 49, 100 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                                                               |           |        |       |              |                                                       |      |      |           |           |           |           |                      |    |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|--------------|-------------------------------------------------------|------|------|-----------|-----------|-----------|-----------|----------------------|----|
| + | Chlorosulfonic acid ( <i>with or without sulfur trioxide</i> ).                                                                               | 8         | UN1754 | I     | 8, 6.1       | 2, B9, B10, B14, B32, B74, T20, TP2, TP12, TP38, TP45 | None | 227  | 244       | Forbidden | Forbidden | C         | 40                   |    |
|   | Chlorotoluenes .....                                                                                                                          | 3         | UN2238 | III   | 3            | B1, IB3, T2, TP1                                      | 150  | 203  | 242       | 60 L      | 220 L     | A         | .....                |    |
|   | Chlorotoluidines, liquid .....                                                                                                                | 6.1       | UN3429 | III   | 6.1          | IB3, T4, TP1                                          | 153  | 203  | 241       | 60 L      | 220 L     | A         | .....                |    |
|   | Chlorotoluidines, solid .....                                                                                                                 | 6.1       | UN2239 | III   | 6.1          | IB8, IP3, T1, TP33                                    | 153  | 213  | 240       | 100 kg    | 200 kg    | A         | .....                |    |
|   | Chlorotrifluoromethane and trifluoromethane azeotropic mixture or Refrigerant gas R 503 with approximately 60 percent chlorotrifluoromethane. | 2.2       | UN2599 | ..... | 2.2          |                                                       | 306  | 304  | 314, 315. | 75 kg     | 150 kg    | A         | .....                |    |
|   | Chlorotrifluoromethane or Refrigerant gas R 13.                                                                                               | 2.2       | UN1022 | ..... | 2.2          |                                                       | 306  | 304  | 314, 315. | 75 kg     | 150 kg    | A         | .....                |    |
|   | Chromic acid solution .....                                                                                                                   | 8         | UN1755 | II    | 8            | B2, IB2, T8, TP2, TP12                                | 154  | 202  | 242       | 1 L       | 30 L      | C         | 40, 44, 89, 100, 141 |    |
|   | .....                                                                                                                                         |           |        | III   | 8            | IB3, T4, TP1, TP12                                    | 154  | 203  | 241       | 5 L       | 60 L      | C         | 40, 44, 89, 100, 141 |    |
|   | Chromic anhydride, see Chromium trioxide, anhydrous.                                                                                          |           |        |       |              |                                                       |      |      |           |           |           |           | .....                |    |
|   | Chromic fluoride, solid .....                                                                                                                 | 8         | UN1756 | II    | 8            | IB8, IP2, IP4, T3, TP33                               | 154  | 212  | 240       | 15 kg     | 50 kg     | A         | 52                   |    |
|   | Chromic fluoride, solution .....                                                                                                              | 8         | UN1757 | II    | 8            | B2, IB2, T7, TP2                                      | 154  | 202  | 242       | 1 L       | 30 L      | A         | .....                |    |
|   | Chromium nitrate .....                                                                                                                        | 5.1       | UN2720 | III   | 8            | IB3, T4, TP1                                          | 154  | 203  | 241       | 5 L       | 60 L      | A         | .....                |    |
|   | .....                                                                                                                                         |           |        | III   | 5.1          | A1, A29, IB8, IP3, T1, TP33                           | 152  | 213  | 240       | 25 kg     | 100 kg    | A         | .....                |    |
|   | Chromium oxychloride .....                                                                                                                    | 8         | UN1758 | I     | 8            | A3, A6, A7, B10, N34, T10, TP2, TP12                  | None | 201  | 243       | 0.5 L     | 2.5 L     | C         | 40, 66, 74, 89, 90   |    |
|   | Chromium trioxide, anhydrous ...                                                                                                              | 5.1       | UN1463 | II    | 5.1, 6.1, 8. | IB8, IP4, T3, TP33                                    | None | 212  | 242       | 5 kg      | 25 kg     | A         |                      |    |
|   | Chromosulfuric acid .....                                                                                                                     | 8         | UN2240 | I     | 8            | A3, A6, A7, B4, B6, N34, T10, TP2, TP12, TP13         | None | 201  | 243       | 0.5 L     | 2.5 L     | B         | 40, 66, 74, 89, 90   |    |
|   | Chromyl chloride, see Chromium oxychloride.                                                                                                   |           |        |       |              |                                                       |      |      |           |           |           |           | .....                |    |
|   | Cigar and cigarette lighters, charged with fuel, see Lighters or Lighter refills containing flammable gas..                                   |           |        |       |              |                                                       |      |      |           |           |           |           | .....                |    |
|   | Coal briquettes, hot .....                                                                                                                    | Forbidden |        |       |              |                                                       |      |      |           |           |           |           | .....                |    |
|   | Coal gas, compressed .....                                                                                                                    | 2.3       | UN1023 | ..... | 2.3, 2.1.    |                                                       | 3    | None | 302       | 314, 315. | Forbidden | Forbidden | D                    | 40 |
|   | Coal tar distillates, flammable ....                                                                                                          | 3         | UN1136 | II    | 3            | IB2, T4, TP1                                          | 150  | 202  | 242       | 5 L       | 60 L      | B         | .....                |    |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                        | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                                                                    |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                                                                    |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
| (1)      | (2)                                                                                                                                                                | (3)                        | (4)                        | (5) | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B) |
|          | .....                                                                                                                                                              | .....                      |                            | III | 3 .....     | B1, IB3, T4, TP1, TP29           | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | <i>Coal tar dye, corrosive, liquid, n.o.s., see Dyes, liquid or solid, n.o.s. or Dye intermedi- ates, liquid or solid, corrosive, n.o.s..</i>                      | .....                      |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>Coating solution (includes sur- face treatments or coatings used for industrial or other purposes such as vehicle un- dercoating, drum or barrel lin- ing).</i> | 3                          | UN1139                     | I   | 3 .....     | T11, TP1, TP8, TP27              | 150 .....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | E                | ..... |
|          | .....                                                                                                                                                              | .....                      |                            | II  | 3 .....     | 149, IB2, T4, TP1, TP8           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |
|          | .....                                                                                                                                                              | .....                      |                            | III | 3 .....     | B1, IB3, T2, TP1                 | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Cobalt naphthenates, powder ....                                                                                                                                   | 4.1                        | UN2001                     | III | 4.1 .....   | A19, IB8, IP3, T1, TP33          | 151 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | ..... |
|          | Cobalt resinate, precipitated .....                                                                                                                                | 4.1                        | UN1318                     | III | 4.1 .....   | A1, A19, IB6, T1, TP33           | 151 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | ..... |
|          | <i>Coke, hot</i> .....                                                                                                                                             | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>Collodion, see Nitrocellulose etc</i>                                                                                                                           | .....                      |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| D G      | Combustible liquid, n.o.s. ....                                                                                                                                    | Comb liq                   | NA1993                     | III | None        | IB3, T1, T4, TP1                 | 150 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | ..... |
| G        | Components, explosive train, n.o.s.                                                                                                                                | 1.2B                       | UN0382                     | II  | 1.2B ...    | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 11               | ..... |
| G        | Components, explosive train, n.o.s.                                                                                                                                | 1.4B                       | UN0383                     | II  | 1.4B ...    | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | ..... |
| G        | Components, explosive train, n.o.s.                                                                                                                                | 1.4S                       | UN0384                     | II  | 1.4S ...    | .....                            | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               | ..... |
| G        | Components, explosive train, n.o.s.                                                                                                                                | 1.1B                       | UN0461                     | II  | 1.1B ...    | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 11               | ..... |
| D G      | <i>Composition B, see Hexolite, etc</i>                                                                                                                            | .....                      |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | Compounds, cleaning liquid .....                                                                                                                                   | 8                          | NA1760                     | I   | 8 .....     | A7, B10, T14, TP2, TP27          | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                 | B                | 40    |
|          | .....                                                                                                                                                              | .....                      |                            | II  | 8 .....     | B2, IB2, N37, T11, TP2, TP27     | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | B                | 40    |
|          | .....                                                                                                                                                              | .....                      |                            | III | 8 .....     | IB3, N37, T7, TP1, TP28          | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | 40    |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|     |                                                                                      |     |        |       |              |                              |           |           |           |           |           |           |          |
|-----|--------------------------------------------------------------------------------------|-----|--------|-------|--------------|------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|----------|
| D G | Compounds, cleaning liquid .....                                                     | 3   | NA1993 | I     | 3 .....      | T11, TP1                     | 150 ..... | 201 ..... | 243 ..... | 1 L       | 30 L      | E         | .....    |
|     | .....                                                                                |     |        | II    | 3 .....      | IB2, T7, TP1, TP8, TP28      | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B         | .....    |
|     | .....                                                                                |     |        | III   | 3 .....      | B1, B52, IB3, T4, TP1, TP29  | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A         | .....    |
| D G | Compounds, tree killing, liquid or Compounds, weed killing, liquid.                  | 8   | NA1760 | I     | 8 .....      | A7, B10, T14, TP2, TP27      | None .... | 201 ..... | 243 ..... | 0.5 L     | 2.5 L     | B         | 40       |
|     | .....                                                                                |     |        | II    | 8 .....      | B2, IB2, N37, T11, TP2, TP27 | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | B         | 40       |
|     | .....                                                                                |     |        | III   | 8 .....      | IB3, N37, T7, TP1, TP28      | 154 ..... | 203 ..... | 241 ..... | 5 L       | 60 L      | A         | 40       |
| D G | Compounds, tree killing, liquid or Compounds, weed killing, liquid.                  | 3   | NA1993 | I     | 3 .....      | T11, TP1                     | 150 ..... | 201 ..... | 243 ..... | 1 L       | 30 L      | E         | .....    |
|     | .....                                                                                |     |        | II    | 3 .....      | IB2, T7, TP1, TP8, TP28      | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B         | .....    |
|     | .....                                                                                |     |        | III   | 3 .....      | B1, B52, IB3, T4, TP1, TP29  | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A         | .....    |
| D G | Compounds, tree killing, liquid or Compounds, weed killing, liquid.                  | 6.1 | NA2810 | I     | 6.1 ....     | T14, TP2, TP13, TP27         | None .... | 201 ..... | 243 ..... | 1 L       | 30 L      | B         | 40       |
|     | .....                                                                                |     |        | II    | 6.1 ....     | IB2, T11, TP2, TP27          | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B         | 40       |
|     | .....                                                                                |     |        | III   | 6.1 ....     | IB3, T7, TP1, TP28           | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A         | 40       |
| G   | Compressed gas, flammable, n.o.s..                                                   | 2.1 | UN1954 | ..... | 2.1 ....     |                              | 306 ..... | 302, 305. | 314, 315. | Forbidden | 150 kg    | D         | 40       |
| G   | Compressed gas, n.o.s .....                                                          | 2.2 | UN1956 | ..... | 2.2 ....     |                              | 77        | 306, 307. | 302, 305. | 75 kg     | 150 kg    | A.        |          |
| G   | Compressed gas, oxidizing, n.o.s..                                                   | 2.2 | UN3156 | ..... | 2.2, 5.1.    | A14                          | 306 ..... | 302 ..... | 314, 315. | 75 kg     | 150 kg    | D         | .....    |
| G I | Compressed gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone A.</i>            | 2.3 | UN3304 | ..... | 2.3, 8       |                              | 1         | None .... | 192 ..... | 245 ..... | Forbidden | Forbidden | D 40     |
| G I | Compressed gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone B.</i>            | 2.3 | UN3304 | ..... | 2.3, 8       | 2, B9, B14                   | None .... | 302, 305. | 314, 315. | Forbidden | Forbidden | D         | 40       |
| G I | Compressed gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone C.</i>            | 2.3 | UN3304 | ..... | 2.3, 8       | 3, B14                       | None .... | 302, 305. | 314, 315. | Forbidden | Forbidden | D         | 40       |
| G I | Compressed gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone D.</i>            | 2.3 | UN3304 | ..... | 2.3, 8       | 4                            | None .... | 302, 305. | 314, 315. | Forbidden | Forbidden | D         | 40       |
| G I | Compressed gas, toxic, flammable, corrosive, n.o.s. <i>Inhalation Hazard Zone A.</i> | 2.3 | UN3305 | ..... | 2.3, 2.1, 8. |                              | 1         | None .... | 192 ..... | 245 ..... | Forbidden | Forbidden | D 17, 40 |
| G I | Compressed gas, toxic, flammable, corrosive, n.o.s. <i>Inhalation Hazard Zone B.</i> | 2.3 | UN3305 | ..... | 2.3, 2.1, 8. | 2, B9, B14                   | None .... | 302, 305. | 314, 315. | Forbidden | Forbidden | D         | 17, 40   |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                              | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes  | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |            |
|----------|------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|--------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|------------|
|          |                                                                                          |                            |                            |       |              |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |            |
|          |                                                                                          |                            |                            |       |              |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other      |
| (1)      | (2)                                                                                      | (3)                        | (4)                        | (5)   | (6)          | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)      |
| G I      | Compressed gas, toxic, flam- mable, corrosive, n.o.s. <i>Inha- lation Hazard Zone C.</i> | 2.3                        | UN3305                     | ..... | 2.3, 2.1, 8. | 3, B14                           | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 17, 40     |
| G I      | Compressed gas, toxic, flam- mable, corrosive, n.o.s. <i>Inha- lation Hazard Zone D.</i> | 2.3                        | UN3305                     | ..... | 2.3, 2.1, 8. | 4                                | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 17, 40     |
| G        | Compressed gas, toxic, flam- mable, n.o.s. <i>Inhalation haz- ard Zone A.</i>            | 2.3                        | UN1953                     | ..... | 2.3, 2.1.    | 1                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40         |
| G        | Compressed gas, toxic, flam- mable, n.o.s. <i>Inhalation haz- ard Zone B.</i>            | 2.3                        | UN1953                     | ..... | 2.3, 2.1.    | 2, B9, B14                       | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40         |
| G        | Compressed gas, toxic, flam- mable, n.o.s. <i>Inhalation Haz- ard Zone C.</i>            | 2.3                        | UN1953                     | ..... | 2.3, 2.1.    | 3, B14                           | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40         |
| G        | Compressed gas, toxic, flam- mable, n.o.s. <i>Inhalation Haz- ard Zone D.</i>            | 2.3                        | UN1953                     | ..... | 2.3, 2.1.    | 4                                | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40         |
| G        | Compressed gas, toxic, n.o.s. <i>Inhalation Hazard Zone A.</i>                           | 2.3                        | UN1955                     | ..... | 2.3 .....    | 1                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40         |
| G        | Compressed gas, toxic, n.o.s. <i>Inhalation Hazard Zone B.</i>                           | 2.3                        | UN1955                     | ..... | 2.3 .....    | 2, B9, B14                       | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40         |
| G        | Compressed gas, toxic, n.o.s. <i>Inhalation Hazard Zone C.</i>                           | 2.3                        | UN1955                     | ..... | 2.3 .....    | 3, B14                           | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40         |
| G        | Compressed gas, toxic, n.o.s. <i>Inhalation Hazard Zone D.</i>                           | 2.3                        | UN1955                     | ..... | 2.3 .....    | 4                                | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40         |
| G I      | Compressed gas, toxic, oxidizing, corrosive, n.o.s. <i>In- halation Hazard Zone A.</i>   | 2.3                        | UN3306                     | ..... | 2.3, 5.1, 8. | 1                                | None ....             | 192 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 40, 89, 90 |
| G I      | Compressed gas, toxic, oxi- dizing, corrosive, n.o.s. <i>Inha- lation Hazard Zone B.</i> | 2.3                        | UN3306                     | ..... | 2.3, 5.1, 8. | 2, B9, B14                       | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 89, 90 |
| G I      | Compressed gas, toxic, oxi- dizing, corrosive, n.o.s. <i>Inha- lation Hazard Zone C.</i> | 2.3                        | UN3306                     | ..... | 2.3, 5.1, 8. | 3, B14                           | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 89, 90 |
| G I      | Compressed gas, toxic, oxi- dizing, corrosive, n.o.s. <i>Inha- lation Hazard Zone D.</i> | 2.3                        | UN3306                     | ..... | 2.3, 5.1, 8. | 4                                | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 89, 90 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                   |           |        |       |           |                           |                     |                    |           |             |             |    |                   |
|---|---------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|---------------------------|---------------------|--------------------|-----------|-------------|-------------|----|-------------------|
| G | Compressed gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone A.</i>                         | 2.3       | UN3303 | ..... | 2.3, 5.1. | 1                         | None ....           | 192 .....          | 245 ..... | Forbidden   | Forbidden   | D  | 40                |
| G | Compressed gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone B.</i>                         | 2.3       | UN3303 | ..... | 2.3, 5.1. | 2, B9, B14                | None ....           | 302, 305.          | 314, 315. | Forbidden   | Forbidden   | D  | 40                |
| G | Compressed gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone C.</i>                         | 2.3       | UN3303 | ..... | 2.3, 5.1. | 3, B14                    | None ....           | 302, 305.          | 314, 315. | Forbidden   | Forbidden   | D  | 40                |
| G | Compressed gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone D.</i>                         | 2.3       | UN3303 | ..... | 2.3, 5.1. | 4                         | None ....           | 302, 305.          | 314, 315. | Forbidden   | Forbidden   | D  | 40                |
| D | Consumer commodity .....                                                                          | ORM-D     |        | ..... | None      |                           | 156, 306. None .... | 156, 306. 62 ..... | None .... | 30 kg gross | 30 kg gross | A  | .....             |
| G | Contrivances, water-activated, with burster, expelling charge or propelling charge.               | 1.2L      | UN0248 | II    | 1.2L ...  |                           | None ....           | 62 .....           | None .... | Forbidden   | Forbidden   | 08 | 8E, 14E, 15E, 17E |
| G | Contrivances, water-activated, with burster, expelling charge or propelling charge.               | 1.3L      | UN0249 | II    | 1.3L ...  |                           | None ....           | 62 .....           | None .... | Forbidden   | Forbidden   | 08 | 8E, 14E, 15E, 17E |
|   | Copper acetoarsenite .....                                                                        | 6.1       | UN1585 | II    | 6.1 ..... | IB8, IP2, IP4, T3, TP33   | 153 .....           | 212 .....          | 242 ..... | 25 kg       | 100 kg      | A  | .....             |
|   | Copper acetylide .....                                                                            | Forbidden |        |       | .....     |                           |                     |                    |           |             |             |    | .....             |
|   | Copper amine azide .....                                                                          | Forbidden |        |       | .....     |                           |                     |                    |           |             |             |    | .....             |
|   | Copper arsenite .....                                                                             | 6.1       | UN1586 | II    | 6.1 ..... | IB8, IP2, IP4, T3, TP33   | 153 .....           | 212 .....          | 242 ..... | 25 kg       | 100 kg      | A  | .....             |
|   | Copper based pesticides, liquid, flammable, toxic, <i>flash point less than 23 degrees C.</i>     | 3         | UN2776 | I     | 3, 6.1    | T14, TP2, TP13, TP27      | None ....           | 201 .....          | 243 ..... | Forbidden   | 30 L        | B  | 40                |
|   | .....                                                                                             |           |        | II    | 3, 6.1    | IB2, T11, TP2, TP13, TP27 | 150 .....           | 202 .....          | 243 ..... | 1 L         | 60 L        | B  | 40                |
|   | Copper based pesticides, liquid, toxic.                                                           | 6.1       | UN3010 | I     | 6.1 ..... | T14, TP2, TP13, TP27      | None ....           | 201 .....          | 243 ..... | 1 L         | 30 L        | B  | 40                |
|   | .....                                                                                             |           |        | II    | 6.1 ..... | IB2, T11, TP2, TP13, TP27 | 153 .....           | 202 .....          | 243 ..... | 5 L         | 60 L        | B  | 40                |
|   | .....                                                                                             |           |        | III   | 6.1 ..... | IB3, T7, TP2, TP28        | 153 .....           | 203 .....          | 241 ..... | 60 L        | 220 L       | A  | 40                |
|   | Copper based pesticides, liquid, toxic, flammable, <i>flash point not less than 23 degrees C.</i> | 6.1       | UN3009 | I     | 6.1, 3    | T14, TP2, TP13, TP27      | None ....           | 201 .....          | 243 ..... | 1 L         | 30 L        | B  | 40                |
|   | .....                                                                                             |           |        | II    | 6.1, 3    | IB2, T11, TP2, TP13, TP27 | 153 .....           | 202 .....          | 243 ..... | 5 L         | 60 L        | B  | 40                |
|   | .....                                                                                             |           |        | III   | 6.1, 3    | B1, IB3, T7, TP2, TP28    | 153 .....           | 203 .....          | 242 ..... | 60 L        | 220 L       | A  | 40                |
|   | Copper based pesticides, solid, toxic.                                                            | 6.1       | UN2775 | I     | 6.1 ..... | IB7, IP1, T6, TP33        | None ....           | 211 .....          | 242 ..... | 5 kg        | 50 kg       | A  | 40                |
|   | .....                                                                                             |           |        | II    | 6.1 ..... | IB8, IP2, IP4, T3, TP33   | 153 .....           | 212 .....          | 242 ..... | 25 kg       | 100 kg      | A  | 40                |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                          | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |                 |
|----------|--------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-----------------|
|          |                                                                                      |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                 |
|          |                                                                                      |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other           |
| (1)      | (2)                                                                                  | (3)                        | (4)                        | (5)   | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)           |
| A W      | .....                                                                                | .....                      | .....                      | III   | 6.1 .....   | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | 40              |
|          | Copper chlorate .....                                                                | 5.1                        | UN2721                     | II    | 5.1 .....   | A1, IB8, IP2, IP4, T3, TP33      | 152 .....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg                 | A                | 56, 58          |
|          | Copper chloride .....                                                                | 8                          | UN2802                     | III   | 8 .....     | IB8, IP3, T1, TP33               | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | .....           |
|          | Copper cyanide .....                                                                 | 6.1                        | UN1587                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33          | 153 .....             | 204 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | 52              |
|          | <i>Copper selenate, see Selenates or Selenites.</i>                                  | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....           |
|          | <i>Copper selenite, see Selenates or Selenites.</i>                                  | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....           |
|          | <i>Copper tetramine nitrate</i> .....                                                | Forbidden                  | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....           |
|          | Copra .....                                                                          | 4.2                        | UN1363                     | III   | 4.2 .....   | IB8, IP3, IP7                    | None ....             | 213 ..... | 241 ..... | Forbidden                                       | Forbidden             | A                | 13, 19, 48, 119 |
|          | Cord, detonating, <i>flexible</i> .....                                              | 1.1D                       | UN0065                     | II    | 1.1D ..     | 102                              | 63(a) ....            | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....           |
|          | Cord, detonating, <i>flexible</i> .....                                              | 1.4D                       | UN0289                     | II    | 1.4D ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....           |
|          | Cord detonating or Fuse deto- nating <i>metal clad</i> .                             | 1.2D                       | UN0102                     | II    | 1.2D ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....           |
|          | Cord, detonating or Fuse, deto- nating <i>metal clad</i> .                           | 1.1D                       | UN0290                     | II    | 1.1D ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....           |
|          | Cord, detonating, mild effect or Fuse, detonating, mild effect <i>metal clad</i> .   | 1.4D                       | UN0104                     | II    | 1.4D ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....           |
|          | Cord, igniter .....                                                                  | 1.4G                       | UN0066                     | II    | 1.4G ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....           |
|          | <i>Cordeau detonant fuse, see Cord, detonating, etc; Cord, detonating, flexible.</i> | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....           |
| G        | <i>Cordite, see Powder, smokeless</i>                                                | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....           |
| G        | Corrosive, liquid, acidic, inor- ganic, n.o.s.                                       | 8                          | UN3264                     | I     | 8 .....     | A6, B10, T14, TP2, TP27          | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                 | B                | 40.             |
|          | .....                                                                                | .....                      | .....                      | II    | 8 .....     | B2, IB2, T11, TP2, TP27          | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | B                | 40.             |
|          | .....                                                                                | .....                      | .....                      | III   | 8 .....     | IB3, T7, TP1, TP28               | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | 40.             |
| G        | Corrosive liquid, acidic, organic, n.o.s..                                           | 8                          | UN3265                     | I     | 8 .....     | A6, B10, T14, TP2, TP27          | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                 | B                | 40              |
|          | .....                                                                                | .....                      | .....                      | II    | 8 .....     | B2, IB2, T11, TP2, TP27          | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | B                | 40              |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                             |   |        |            |                                   |      |     |     |           |        |   |        |
|---|---------------------------------------------|---|--------|------------|-----------------------------------|------|-----|-----|-----------|--------|---|--------|
| G | Corrosive liquid, basic, inorganic, n.o.s.. | 8 | UN3266 | III 8      | IB3, T7, TP1, TP28                | 154  | 203 | 241 | 5 L       | 60 L   | A | 40     |
|   |                                             |   |        | I 8        | A6, T14, TP2, TP27                | None | 201 | 243 | 0.5 L     | 2.5 L  | B | 40, 52 |
|   |                                             |   |        | II 8       | B2, IB2, T11, TP2, TP27           | 154  | 202 | 242 | 1 L       | 30 L   | B | 40, 52 |
| G | Corrosive liquid, basic, organic, n.o.s..   | 8 | UN3267 | III 8      | IB3, T7, TP1, TP28                | 154  | 203 | 241 | 5 L       | 60 L   | A | 40, 52 |
|   |                                             |   |        | I 8        | A6, B10, T14, TP2, TP27           | None | 201 | 243 | 0.5 L     | 2.5 L  | B | 40, 52 |
|   |                                             |   |        | II 8       | B2, IB2, T11, TP2, TP27           | 154  | 202 | 242 | 1 L       | 30 L   | B | 40, 52 |
| G | Corrosive liquid, self-heating, n.o.s..     | 8 | UN3301 | III 8      | IB3, T7, TP1, TP28                | 154  | 203 | 241 | 5 L       | 60 L   | A | 40, 52 |
|   |                                             |   |        | I 8, 4.2   | A6, B10                           | None | 201 | 243 | 0.5 L     | 2.5 L  | D | .....  |
|   |                                             |   |        | II 8, 4.2  | B2, IB1                           | 154  | 202 | 242 | 1 L       | 30 L   | D | .....  |
| G | Corrosive liquids, flammable, n.o.s..       | 8 | UN2920 | I 8, 3     | A6, B10, T14, TP2, TP27           | None | 201 | 243 | 0.5 L     | 2.5 L  | C | 25, 40 |
|   |                                             |   |        | II 8, 3    | B2, IB2, T11, TP2, TP27           | None | 202 | 243 | 1 L       | 30 L   | C | 25, 40 |
|   |                                             |   |        | I 8        | A6, A7, B10, T14, TP2, TP27       | None | 201 | 243 | 0.5 L     | 2.5 L  | B | 40     |
| G | Corrosive liquids, n.o.s. ....              | 8 | UN1760 | II 8       | B2, IB2, T11, TP2, TP27           | 154  | 202 | 242 | 1 L       | 30 L   | B | 40     |
|   |                                             |   |        | III 8      | IB3, T7, TP1, TP28                | 154  | 203 | 241 | 5 L       | 60 L   | A | 40     |
|   |                                             |   |        | I 8, 5.1   | A6, A7                            | None | 201 | 243 | Forbidden | 2.5 L  | C | 89     |
| G | Corrosive liquids, oxidizing, n.o.s..       | 8 | UN3093 | II 8, 5.1  | A6, A7, IB2                       | None | 202 | 243 | 1 L       | 30 L   | C | 89     |
|   |                                             |   |        | I 8, 6.1   | A6, A7, B10, T14, TP2, TP13, TP27 | None | 201 | 243 | 0.5 L     | 2.5 L  | B | 40     |
|   |                                             |   |        | II 8, 6.1  | B3, IB2, T7, TP2                  | 154  | 202 | 243 | 1 L       | 30 L   | B | 40     |
| G | Corrosive liquids, water-reactive, n.o.s..  | 8 | UN3094 | III 8, 6.1 | IB3, T7, TP1, TP28                | 154  | 203 | 241 | 5 L       | 60 L   | B | 40     |
|   |                                             |   |        | I 8, 4.3   | A6, A7                            | None | 201 | 243 | Forbidden | 1 L    | E | .....  |
|   |                                             |   |        | II 8, 4.3  | A6, A7                            | None | 202 | 243 | 1 L       | 5 L    | E | .....  |
| G | Corrosive solid, acidic, inorganic, n.o.s.. | 8 | UN3260 | I 8        | IB7, IP1, T6, TP33                | None | 211 | 242 | 1 kg      | 25 kg  | B | .....  |
|   |                                             |   |        | II 8       | IB8, IP2, IP4, T3, TP33           | 154  | 212 | 240 | 15 kg     | 50 kg  | B | .....  |
|   |                                             |   |        | III 8      | IB8, IP3, T1, TP33                | 154  | 213 | 240 | 25 kg     | 100 kg | A | .....  |
| G | Corrosive solid, acidic, organic, n.o.s..   | 8 | UN3261 | I 8        | IB7, IP1, T6, TP33                | None | 211 | 242 | 1 kg      | 25 kg  | B | .....  |
|   |                                             |   |        | II 8       | IB8, IP2, IP4, T3, TP33           | 154  | 212 | 240 | 15 kg     | 50 kg  | B | .....  |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |      | (9)                                             |                       | (10)             |        |
|----------|-------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                             |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |      | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                             |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| (1)      | (2)                                                         | (3)                        | (4)                        | (5) | (6)         | (7)                              | (8A)                  | (8B)      | (8C) | (9A)                                            | (9B)                  | (10A)            | (10B)  |
| G        | Corrosive solid, basic, inorganic, n.o.s..                  | 8                          | UN3262                     | III | 8           | IB8, IP3, T1, TP33               | 154                   | 213       | 240  | 25 kg                                           | 100 kg                | A                | .....  |
|          |                                                             |                            |                            | I   | 8           | IB7, IP1, T6, TP33               | None                  | 211       | 242  | 1 kg                                            | 25 kg                 | B                | 52     |
|          |                                                             |                            |                            | II  | 8           | IB8, IP2, IP4, T3, TP33          | 154                   | 212       | 240  | 15 kg                                           | 50 kg                 | B                | 52     |
| G        | Corrosive solid, basic, organic, n.o.s..                    | 8                          | UN3263                     | III | 8           | IB8, IP3, T1, TP33               | 154                   | 213       | 240  | 25 kg                                           | 100 kg                | A                | 52     |
|          |                                                             |                            |                            | I   | 8           | IB7, IP1, T6, TP33               | None                  | 211       | 242  | 1 kg                                            | 25 kg                 | B                | 52     |
|          |                                                             |                            |                            | II  | 8           | IB8, IP2, IP4, T3, TP33          | 154                   | 212       | 240  | 15 kg                                           | 50 kg                 | B                | 52     |
| G        | Corrosive solids, flammable, n.o.s..                        | 8                          | UN2921                     | III | 8           | IB8, IP3, T1, TP33               | 154                   | 213       | 240  | 25 kg                                           | 100 kg                | A                | 52     |
|          |                                                             |                            |                            | I   | 8, 4.1      | IB6, T6, TP33                    | None                  | 211       | 242  | 1 kg                                            | 25 kg                 | B                | 12, 25 |
| G        | Corrosive solids, n.o.s. ....                               | 8                          | UN1759                     | II  | 8, 4.1      | IB8, IP2, IP4, T3, TP33          | None                  | 212       | 242  | 15 kg                                           | 50 kg                 | B                | 12, 25 |
|          |                                                             |                            |                            | I   | 8           | IB7, IP1, T6, TP33               | None                  | 211       | 242  | 1 kg                                            | 25 kg                 | B                | .....  |
| G        | Corrosive solids, oxidizing, n.o.s..                        | 8                          | UN3084                     | II  | 8           | 128, IB8, IP2, IP4, T3, TP33     | 154                   | 212       | 240  | 15 kg                                           | 50 kg                 | A                | .....  |
|          |                                                             |                            |                            | III | 8           | 128, IB8, IP3, T1, TP33          | 154                   | 213       | 240  | 25 kg                                           | 100 kg                | A                | .....  |
| G        | Corrosive solids, self-heating, n.o.s..                     | 8                          | UN3095                     | I   | 8, 5.1      | T6, TP33                         | None                  | 211       | 242  | 1 kg                                            | 25 kg                 | C                | .....  |
|          |                                                             |                            |                            | II  | 8, 5.1      | IB6, IP2, T3, TP33               | None                  | 212       | 242  | 15 kg                                           | 50 kg                 | C                | .....  |
| G        | Corrosive solids, toxic, n.o.s. ....                        | 8                          | UN2923                     | I   | 8, 4.2      | T6, TP33                         | None                  | 211       | 243  | 1 kg                                            | 25 kg                 | C                | .....  |
|          |                                                             |                            |                            | II  | 8, 4.2      | IB6, IP2, T3, TP33               | None                  | 212       | 242  | 15 kg                                           | 50 kg                 | C                | .....  |
| G        | Corrosive solids, water-reactive, n.o.s..                   | 8                          | UN3096                     | I   | 8, 6.1      | IB7, T6, TP33                    | None                  | 211       | 242  | 1 kg                                            | 25 kg                 | B                | 40     |
|          |                                                             |                            |                            | II  | 8, 6.1      | IB8, IP2, IP4, T3, TP33          | 154                   | 212       | 240  | 15 kg                                           | 50 kg                 | B                | 40     |
| G        | Corrosive solids, water-reactive, n.o.s..                   | 8                          | UN3096                     | III | 8, 6.1      | IB8, IP3, T1, TP33               | 154                   | 213       | 240  | 25 kg                                           | 100 kg                | B                | 40, 95 |
|          |                                                             |                            |                            | I   | 8, 4.3      | IB4, IP1, T6, TP33               | None                  | 211       | 243  | 1 kg                                            | 25 kg                 | D                | .....  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|     |                                                                                                        |       |        |       |           |                                                            |           |           |           |           |           |    |       |
|-----|--------------------------------------------------------------------------------------------------------|-------|--------|-------|-----------|------------------------------------------------------------|-----------|-----------|-----------|-----------|-----------|----|-------|
| D W | .....                                                                                                  | ..... | .....  | II    | 8, 4.3    | IB6, IP2, T3, TP33                                         | None .... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | D  | ..... |
|     | Cotton .....                                                                                           | 9     | NA1365 | ..... | 9 .....   | 137, IB8, IP2, IP4, W41                                    | None .... | None .... | None .... | No limit  | No limit  | A  | ..... |
| A W | Cotton waste, oily .....                                                                               | 4.2   | UN1364 | III   | 4.2 ..... | IB8, IP3, IP7                                              | None .... | 213 ..... | None .... | Forbidden | Forbidden | A  | 54    |
|     | Cotton, wet .....                                                                                      | 4.2   | UN1365 | III   | 4.2 ..... | IB8, IP3, IP7                                              | None .... | 204 ..... | 241 ..... | Forbidden | Forbidden | A  | ..... |
| A I | Coumarin derivative pesticides, liquid, flammable, toxic, flash point less than 23 degrees C. ....     | 3     | UN3024 | I     | 3, 6.1    | T14, TP2, TP13, TP27                                       | None .... | 201 ..... | 243 ..... | Forbidden | 30 L      | B  | 40    |
|     | .....                                                                                                  | ..... | .....  | II    | 3, 6.1    | IB2, T11, TP2, TP13, TP27                                  | 150 ..... | 202 ..... | 243 ..... | 1 L       | 60 L      | B  | 40    |
| W   | Coumarin derivative pesticides, liquid, toxic. ....                                                    | 6.1   | UN3026 | I     | 6.1 ..... | T14, TP2, TP13, TP27                                       | None .... | 201 ..... | 243 ..... | 1 L       | 30 L      | B  | 40    |
|     | .....                                                                                                  | ..... | .....  | II    | 6.1 ..... | IB2, T11, TP2, TP27                                        | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B  | 40    |
|     | .....                                                                                                  | ..... | .....  | III   | 6.1 ..... | IB3, T7, TP1, TP28                                         | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A  | 40    |
|     | Coumarin derivative pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C. .... | 6.1   | UN3025 | I     | 6.1, 3    | T14, TP2, TP13, TP27                                       | None .... | 201 ..... | 243 ..... | 1 L       | 30 L      | B  | 40    |
|     | .....                                                                                                  | ..... | .....  | II    | 6.1, 3    | IB2, T11, TP2, TP13, TP27                                  | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B  | 40    |
|     | .....                                                                                                  | ..... | .....  | III   | 6.1, 3    | B1, IB3, T7, TP1, TP28                                     | 153 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | 40    |
|     | Coumarin derivative pesticides, solid, toxic. ....                                                     | 6.1   | UN3027 | I     | 6.1 ..... | IB7, IP1, T6, TP33                                         | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | A  | 40    |
|     | .....                                                                                                  | ..... | .....  | II    | 6.1 ..... | IB8, IP2, IP4, T3, TP33                                    | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A  | 40    |
|     | .....                                                                                                  | ..... | .....  | III   | 6.1 ..... | IB8, IP3, T1, TP33                                         | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A  | 40    |
|     | Cresols, liquid .....                                                                                  | 6.1   | UN2076 | II    | 6.1, 8    | IB2, IP2, IP4, T7, TP2                                     | 153 ..... | 202 ..... | 243 ..... | 1 L       | 30 L      | B  | ..... |
|     | Cresols, solid .....                                                                                   | 6.1   | UN3455 | II    | 6.1, 8    | IB8, IP2, IP4, T3, TP33                                    | 153 ..... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | B  | ..... |
|     | Cresylic acid .....                                                                                    | 6.1   | UN2022 | II    | 6.1, 8    | IB2, T7, TP2, TP13                                         | 153 ..... | 202 ..... | 243 ..... | 1 L       | 30 L      | B  | ..... |
|     | Crotonaldehyde or Crotonaldehyde, stabilized. ....                                                     | 6.1   | UN1143 | I     | 6.1, 3    | 2, 175, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None .... | 227 ..... | 244 ..... | Forbidden | Forbidden | B  | 40    |
|     | Crotonic acid, liquid .....                                                                            | 8     | UN3472 | III   | 8 .....   | IB8, T1                                                    | 154 ..... | 203 ..... | 241 ..... | 5 L       | 60 L      | A  | 12.   |
|     | Crotonic acid, solid .....                                                                             | 8     | UN2823 | III   | 8 .....   | IB8, IP3, T1, TP33                                         | 154 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A  | 12.   |
|     | Crotonylene .....                                                                                      | 3     | UN1144 | I     | 3 .....   | T11, TP2                                                   | 150 ..... | 201 ..... | 243 ..... | 1 L       | 30 L      | E  | ..... |
|     | Cupriethylenediamine solution ...                                                                      | 8     | UN1761 | II    | 8, 6.1    | IB2, T7, TP2                                               | 154 ..... | 202 ..... | 243 ..... | 1 L       | 30 L      | A  | ..... |
|     | .....                                                                                                  | ..... | .....  | III   | 8, 6.1    | IB3, T7, TP1, TP28                                         | 154 ..... | 203 ..... | 242 ..... | 5 L       | 60 L      | A  | 95    |
|     | Cutters, cable, explosive .....                                                                        | 1.4S  | UN0070 | II    | 1.4S ...  |                                                            | None .... | 62 .....  | None .... | 25 kg     | 100 kg    | 05 | ..... |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                      | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)  | (8)                   |           |           | (9)                                             |                       | (10)             |                         |
|----------|----------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|-----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------------------------|
|          |                                                                                  |                            |                            |     |             |                                   | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                         |
|          |                                                                                  |                            |                            |     |             |                                   | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                   |
| (1)      | (2)                                                                              | (3)                        | (4)                        | (5) | (6)         | (7)                               | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)                   |
|          | <i>Cyanide or cyanide mixtures, dry, see Cyanides, inorganic, solid, n.o.s..</i> |                            |                            |     |             |                                   |                       |           |           |                                                 |                       |                  |                         |
|          | Cyanide solutions, n.o.s. ....                                                   | 6.1                        | UN1935                     | I   | 6.1         | B37, T14, TP2, TP13, TP27         | None                  | 201       | 243       | 1 L                                             | 30 L                  | B                | 40, 52                  |
|          |                                                                                  |                            |                            | II  | 6.1         | IB2, T11, TP2, TP13, TP27         | 153                   | 202       | 243       | 5 L                                             | 60 L                  | A                | 40, 52                  |
|          |                                                                                  |                            |                            | III | 6.1         | IB3, T7, TP2, TP13, TP28          | 153                   | 203       | 241       | 60 L                                            | 220 L                 | A                | 40, 52                  |
|          | Cyanides, inorganic, solid, n.o.s. ....                                          | 6.1                        | UN1588                     | I   | 6.1         | IB7, IP1, N74, N75, T6, TP33      | None                  | 211       | 242       | 5 kg                                            | 50 kg                 | A                | 52                      |
|          |                                                                                  |                            |                            | II  | 6.1         | IB8, IP2, IP4, N74, N75, T3, TP33 | 153                   | 212       | 242       | 25 kg                                           | 100 kg                | A                | 52                      |
|          |                                                                                  |                            |                            | III | 6.1         | IB8, IP3, N74, N75, T1, TP33      | 153                   | 213       | 240       | 100 kg                                          | 200 kg                | A                | 52                      |
|          | Cyanogen .....                                                                   | 2.3                        | UN1026                     |     | 2.3, 2.1.   | 2                                 | None                  | 304       | 245       | Forbidden                                       | Forbidden             | D                | 40                      |
|          | Cyanogen bromide .....                                                           | 6.1                        | UN1889                     | I   | 6.1, 8      | A6, A8, T6, TP33                  | None                  | 211       | 242       | 1 kg                                            | 15 kg                 | D                | 40                      |
|          | Cyanogen chloride, stabilized ....                                               | 2.3                        | UN1589                     |     | 2.3, 8      | 1                                 | None                  | 192       | 245       | Forbidden                                       | Forbidden             | D                | 40                      |
|          | Cyanuric chloride .....                                                          | 8                          | UN2670                     | II  | 8           | IB8, IP2, IP4, T3, TP33           | None                  | 212       | 240       | 15 kg                                           | 50 kg                 | A                | 12, 40                  |
|          | <i>Cyanuric triazide</i> .....                                                   | Forbidden                  |                            |     |             |                                   |                       |           |           |                                                 |                       |                  |                         |
|          | Cyclobutane .....                                                                | 2.1                        | UN2601                     |     | 2.1         |                                   | 306                   | 304       | 314, 315. | Forbidden                                       | 150 kg                | B                | 40                      |
|          | Cyclobutyl chloroformate .....                                                   | 6.1                        | UN2744                     | II  | 6.1, 8, 3.  | IB1, T7, TP2, TP13                | 153                   | 202       | 243       | 1 L                                             | 30 L                  | A                | 12, 13, 21, 25, 40, 100 |
|          | 1,5,9-Cyclododecatriene .....                                                    | 6.1                        | UN2518                     | III | 6.1         | IB3, T4, TP1                      | 153                   | 203       | 241       | 60 L                                            | 220 L                 | A                | 40                      |
|          | Cycloheptane .....                                                               | 3                          | UN2241                     | II  | 3           | IB2, T4, TP1                      | 150                   | 202       | 242       | 5 L                                             | 60 L                  | B                | 40                      |
|          | Cycloheptatriene .....                                                           | 3                          | UN2603                     | II  | 3, 6.1      | IB2, T7, TP1, TP13                | 150                   | 202       | 243       | 1 L                                             | 60 L                  | E                | 40                      |
|          | Cycloheptene .....                                                               | 3                          | UN2242                     | II  | 3           | B1, IB2, T4, TP1                  | 150                   | 202       | 242       | 5 L                                             | 60 L                  | B                |                         |
|          | Cyclohexane .....                                                                | 3                          | UN1145                     | II  | 3           | IB2, T4, TP1                      | 150                   | 202       | 242       | 5 L                                             | 60 L                  | E                |                         |
|          | Cyclohexanone .....                                                              | 3                          | UN1915                     | III | 3           | B1, IB3, T2, TP1                  | 150                   | 203       | 242       | 60 L                                            | 220 L                 | A                |                         |
|          | Cyclohexene .....                                                                | 3                          | UN2256                     | II  | 3           | IB2, T4, TP1                      | 150                   | 202       | 242       | 5 L                                             | 60 L                  | E                |                         |
|          | Cyclohexenytrichlorosilane .....                                                 | 8                          | UN1762                     | II  | 8           | A7, B2, IB2, N34, T7, TP2, TP13   | None                  | 202       | 242       | Forbidden                                       | 30 L                  | C                | 40                      |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                             |           |        |       |           |                                                       |           |           |           |           |           |    |        |
|---------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|-------------------------------------------------------|-----------|-----------|-----------|-----------|-----------|----|--------|
| Cyclohexyl acetate .....                                                                                                                    | 3         | UN2243 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....  |
| Cyclohexyl isocyanate .....                                                                                                                 | 6.1       | UN2488 | I     | 6.1, 3    | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None .... | 227 ..... | 244 ..... | Forbidden | Forbidden | D  | 40     |
| Cyclohexyl mercaptan .....                                                                                                                  | 3         | UN3054 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | 40, 95 |
| Cyclohexylamine .....                                                                                                                       | 8         | UN2357 | II    | 8, 3 .... | IB2, T7, TP2                                          | None .... | 202 ..... | 243 ..... | 1 L       | 30 L      | A  | 40     |
| Cyclohexyltrichlorosilane .....                                                                                                             | 8         | UN1763 | II    | 8 .....   | A7, B2, IB2, N34, T7, TP2, TP13                       | None .... | 202 ..... | 242 ..... | Forbidden | 30 L      | C  | 40     |
| Cyclonite and cyclotetramethylenetetranitramine mixtures, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized etc. .... |           |        |       |           |                                                       |           |           |           |           |           |    |        |
| Cyclonite and HMX mixtures, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized etc. ....                               |           |        |       |           |                                                       |           |           |           |           |           |    |        |
| Cyclonite and octogen mixtures, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized etc. ....                           |           |        |       |           |                                                       |           |           |           |           |           |    |        |
| Cyclonite, see Cyclotrimethylenetrinitramine, etc. ....                                                                                     |           |        |       |           |                                                       |           |           |           |           |           |    |        |
| Cyclooctadiene phosphines, see 9-Phosphabicyclononanes. ....                                                                                |           |        |       |           |                                                       |           |           |           |           |           |    |        |
| Cyclooctadienes .....                                                                                                                       | 3         | UN2520 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....  |
| Cyclooctatetraene .....                                                                                                                     | 3         | UN2358 | II    | 3 .....   | IB2, T4, TP1                                          | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B  | .....  |
| Cyclopentane .....                                                                                                                          | 3         | UN1146 | II    | 3 .....   | IB2, T7, TP1                                          | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | E  | .....  |
| Cyclopentane, methyl, see Methylcyclopentane. ....                                                                                          |           |        |       |           |                                                       |           |           |           |           |           |    |        |
| Cyclopentanol .....                                                                                                                         | 3         | UN2244 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....  |
| Cyclopentanone .....                                                                                                                        | 3         | UN2245 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....  |
| Cyclopentene .....                                                                                                                          | 3         | UN2246 | II    | 3 .....   | IB2, IP8, T7, TP2                                     | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | E  | .....  |
| Cyclopropane .....                                                                                                                          | 2.1       | UN1027 | ..... | 2.1 ..... | T50                                                   | 306 ..... | 304 ..... | 314, 315. | Forbidden | 150 kg    | E  | 40     |
| Cyclotetramethylene tetranitramine (dry or unphlegmatized) (HMX). ....                                                                      | Forbidden |        |       |           |                                                       |           |           |           |           |           |    |        |
| Cyclotetramethylenetetranitramine, desensitized or Octogen, desensitized or HMX, desensitized. ....                                         | 1.1D      | UN0484 | II    | 1.1D ..   |                                                       | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | .....  |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                                                            |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                                                            |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
| (1)      | (2)                                                                                                                                                        | (3)                        | (4)                        | (5)   | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B) |
|          | Cyclotetramethylenetetranitramine, wetted or HMX, wetted or Octogen, wetted with not less than 15 percent water, by mass.                                  | 1.1D                       | UN0226                     | II    | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | ..... |
|          | Cyclotrimethylenenitramine and octogen, mixtures, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized, etc.                            | .....                      |                            | ..... | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  |       |
|          | Cyclotrimethylenetrinitramine and cyclotetramethylenetetranitramine mixtures, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized etc. | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | Cyclotrimethylenetrinitramine and HMX mixtures, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized etc.                               | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | Cyclotrimethylenetrinitramine, desensitized or Cyclonite, desensitized or Hexogen, desensitized or RDX, desensitized.                                      | 1.1D                       | UN0483                     | II    | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | ..... |
|          | Cyclotrimethylenetrinitramine, wetted or Cyclonite, wetted or Hexogen, wetted or RDX, wetted with not less than 15 percent water by mass.                  | 1.1D                       | UN0072                     | II    | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | ..... |
|          | Cymenes .....                                                                                                                                              | 3                          | UN2046                     | III   | 3 .....     | B1, IB3, T2, TP1                 | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Dangerous Goods in Machinery or Dangerous Goods in Apparatus.                                                                                              | 9                          | UN3363                     | ..... | .....       | 136, A105                        | None ....             | 222 ..... | None .... | See A105                                        | See A105              | A.               |       |
|          | Decaborane .....                                                                                                                                           | 4.1                        | UN1868                     | II    | 4.1, 6.1.   | A19, A20, IB6, IP2, T3, TP33     | None ....             | 212 ..... | None .... | Forbidden                                       | 50 kg                 | A                | 74    |
|          | Decahydronaphthalene .....                                                                                                                                 | 3                          | UN1147                     | III   | 3 .....     | B1, IB3, T2, TP1                 | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                           |           |        |       |           |                  |                  |           |            |           |           |    |        |
|---|-----------------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|------------------|------------------|-----------|------------|-----------|-----------|----|--------|
|   | n-Decane .....                                                                                            | 3         | UN2247 | III   | 3 .....   | B1, IB3, T2, TP1 | 150 .....        | 203 ..... | 242 .....  | 60 L      | 220 L     | A  | .....  |
|   | Deflagrating metal salts of aromatic nitroderivatives, n.o.s..                                            | 1.3C      | UN0132 | II    | 1.3C ..   |                  | None .....       | 62 .....  | None ..... | Forbidden | Forbidden | 10 | 5E     |
|   | <i>Delay electric igniter, see Igniters.</i>                                                              | .....     |        |       | .....     |                  | .....            | .....     | .....      | .....     | .....     |    | .....  |
| D | Denatured alcohol .....                                                                                   | 3         | NA1987 | II    | 3 .....   | 172, T8          | 150 .....        | 202 ..... | 242 .....  | 5 L       | 60 L      | B  |        |
|   | <i>Depth charges, see Charges, depth.</i>                                                                 | .....     |        | III   | 3 .....   | 172, B1, T7      | 150 .....        | 203 ..... | 242 .....  | 60 L      | 220 L     | A  |        |
| G | Desensitized explosive, liquid, n.o.s..                                                                   | 3         | UN3379 | I     | 3 .....   | 164              | None ....        | 201 ..... | None ....  | Forbidden | Forbidden | D  | 36     |
| G | Desensitized explosive, solid, n.o.s..                                                                    | 4.1       | UN3380 | I     | 4.1 ..... | 164              | None ....        | 211 ..... | None ....  | Forbidden | Forbidden | D  | 28, 36 |
|   | <i>Detonating relays, see Detonators, etc.</i>                                                            | .....     |        |       | .....     |                  | .....            | .....     | .....      | .....     | .....     |    | .....  |
|   | Detonator assemblies, non-electric for blasting.                                                          | 1.1B      | UN0360 | II    | 1.1B ...  |                  | None ....        | 62 .....  | None ....  | Forbidden | Forbidden | 11 | .....  |
|   | Detonator assemblies, non-electric, for blasting.                                                         | 1.4B      | UN0361 | II    | 1.4B ...  | 103              | 63(f),<br>63(g). | 62 .....  | None ....  | Forbidden | 75 kg     | 06 | .....  |
|   | Detonator, assemblies, non-electric for blasting.                                                         | 1.4S      | UN0500 | II    | 1.4S ...  |                  | 63(f),<br>63(g). | 62 .....  | None ....  | 25 kg     | 100 kg    | 05 | .....  |
|   | Detonators, electric, for blasting                                                                        | 1.1B      | UN0030 | II    | 1.1B ...  |                  | 63(f),<br>63(g). | 62 .....  | None ....  | Forbidden | Forbidden | 11 | .....  |
|   | Detonators, electric, for blasting                                                                        | 1.4B      | UN0255 | II    | 1.4B ...  | 103              | 63(f),<br>63(g). | 62 .....  | None ....  | Forbidden | 75 kg     | 06 | .....  |
|   | Detonators, electric for blasting                                                                         | 1.4S      | UN0456 | II    | 1.4S ...  |                  | 63(f),<br>63(g). | 62 .....  | None ....  | 25 kg     | 100 kg    | 05 | .....  |
|   | Detonators for ammunition .....                                                                           | 1.1B      | UN0073 | II    | 1.1B ...  |                  | None ....        | 62 .....  | None ....  | Forbidden | Forbidden | 11 | .....  |
|   | Detonators for ammunition .....                                                                           | 1.2B      | UN0364 | II    | 1.2B ...  |                  | None ....        | 62 .....  | None ....  | Forbidden | Forbidden | 11 | .....  |
|   | Detonators for ammunition .....                                                                           | 1.4B      | UN0365 | II    | 1.4B ...  | 103              | None ....        | 62 .....  | None ....  | Forbidden | 75 kg     | 06 | .....  |
|   | Detonators for ammunition .....                                                                           | 1.4S      | UN0366 | II    | 1.4S ...  |                  | None ....        | 62 .....  | None ....  | 25 kg     | 100 kg    | 05 | .....  |
|   | Detonators, non-electric, for blasting.                                                                   | 1.1B      | UN0029 | II    | 1.1B ...  |                  | None ....        | 62 .....  | None ....  | Forbidden | Forbidden | 11 | .....  |
|   | Detonators, non-electric, for blasting.                                                                   | 1.4B      | UN0267 | II    | 1.4B ...  | 103              | 63(f),<br>63(g). | 62 .....  | None ....  | Forbidden | 75 kg     | 06 | .....  |
|   | Detonators, non-electric, for blasting.                                                                   | 1.4S      | UN0455 | II    | 1.4S ...  | .....            | 63(f),<br>63(g). | 62 .....  | None ....  | 25 kg     | 100 kg    | 05 | .....  |
|   | Deuterium, compressed .....                                                                               | 2.1       | UN1957 | ..... | 2.1 ..... | N89              | 306 .....        | 302 ..... | None ....  | Forbidden | 150 kg    | E  | 40     |
|   | Devices, small, hydrocarbon gas powered or Hydrocarbon gas refills for small devices with release device. | 2.1       | UN3150 | ..... | 2.1 ..... |                  | 306 .....        | 304 ..... | None ....  | 1 kg      | 15 kg     | B  | 40     |
|   | Di-n-amylamine .....                                                                                      | 3         | UN2841 | III   | 3, 6.1    | B1, IB3, T4, TP1 | 150 .....        | 203 ..... | 242 .....  | 60 L      | 220 L     | A  | .....  |
|   | <i>Di-n-butyl peroxydicarbonate, with more than 52 percent in solution.</i>                               | Forbidden |        |       | .....     |                  | .....            | .....     | .....      | .....     | .....     |    | .....  |
|   | Di-n-butylamine .....                                                                                     | 8         | UN2248 | II    | 8, 3 .... | IB2, T7, TP2     | None ....        | 202 ..... | 243 .....  | 1 L       | 30 L      | A  | .....  |
|   | <i>2,2-Di-(tert-butylperoxy) butane, with more than 55 percent in solution.</i>                           | Forbidden |        |       | .....     |                  | .....            | .....     | .....      | .....     | .....     |    | .....  |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                                                                                          | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |             |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------------|
|          |                                                                                                                                                                                                                                                      |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |             |
|          |                                                                                                                                                                                                                                                      |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other       |
| (1)      | (2)                                                                                                                                                                                                                                                  | (3)                        | (4)                        | (5) | (6)         | (7)                              | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)       |
|          | <i>Di-(tert-butylperoxy) phthalate, with more than 55 percent in solution.</i>                                                                                                                                                                       | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>2,2-Di-(4,4-di-tert-butylperoxycyclohexyl) propane, with more than 42 percent with inert solid.</i>                                                                                                                                               | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Di-2,4-dichlorobenzoyl peroxide, with more than 75 percent with water.</i>                                                                                                                                                                        | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>1,2-Di-(dimethylamino)ethane ....</i>                                                                                                                                                                                                             | 3                          | UN2372                     | II  | 3 .....     | IB2, T4, TP1                     | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....       |
|          | <i>Di-2-ethylhexyl phosphoric acid, see Diisooctyl acid phosphate.</i>                                                                                                                                                                               | .....                      |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Di-(1-hydroxytetrazole) (dry) .....</i>                                                                                                                                                                                                           | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Di-(1-naphthoyl) peroxide .....</i>                                                                                                                                                                                                               | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>a,a'-Di-(nitroxy) methylether .....</i>                                                                                                                                                                                                           | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Di-(beta-nitroxyethyl) ammonium nitrate.</i>                                                                                                                                                                                                      | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Diacetone alcohol .....</i>                                                                                                                                                                                                                       | 3                          | UN1148                     | II  | 3 .....     | IB2, T4, TP1                     | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....       |
|          | .....                                                                                                                                                                                                                                                | .....                      |                            | III | 3 .....     | B1, IB3, T2, TP1                 | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....       |
|          | <i>Diacetone alcohol peroxides, with more than 57 percent in solution with more than 9 percent hydrogen peroxide, less than 26 percent diacetone alcohol and less than 9 percent water; total active oxygen content more than 9 percent by mass.</i> | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Diacetyl, see Butanedione .....</i>                                                                                                                                                                                                               | .....                      |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Diacetyl peroxide, solid, or with more than 25 percent in solu- tion.</i>                                                                                                                                                                         | Forbidden                  |                            |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....       |
|          | <i>Diallylamine .....</i>                                                                                                                                                                                                                            | 3                          | UN2359                     | II  | 3, 6.1, 8.  | IB2, T7, TP1                     | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | 21, 40, 100 |
|          | <i>Diallylether .....</i>                                                                                                                                                                                                                            | 3                          | UN2360                     | II  | 3, 6.1      | IB2, N12, T7, TP1, TP13          | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 60 L                  | E                | 40          |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                          |           |        |       |            |                                                        |           |           |           |           |           |    |            |
|---|----------------------------------------------------------------------------------------------------------|-----------|--------|-------|------------|--------------------------------------------------------|-----------|-----------|-----------|-----------|-----------|----|------------|
|   | 4,4'-Diaminodiphenyl methane ..                                                                          | 6.1       | UN2651 | III   | 6.1 .....  | IB8, IP3, T1, TP33                                     | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A  | .....      |
|   | <i>p</i> -Diazidobenzene .....                                                                           | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | 1,2-Diazoethane .....                                                                                    | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | 1,1'-Diazoaminonaphthalene .....                                                                         | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Diazoaminotetrazole (dry) .....                                                                          | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Diazodinitrophenol (dry) .....                                                                           | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Diazodinitrophenol, wetted with not less than 40 percent water or mixture of alcohol and water, by mass. | 1.1A      | UN0074 | II    | 1.1A ...   | 111, 117                                               | None .... | 62 .....  | None .... | Forbidden | Forbidden | 12 | .....      |
|   | Diazodiphenylmethane .....                                                                               | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Diazonium nitrates (dry) .....                                                                           | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Diazonium perchlorates (dry) .....                                                                       | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | 1,3-Diazopropane .....                                                                                   | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Dibenzyl peroxydicarbonate, with more than 87 percent with water.                                        | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Dibenzylchlorosilane .....                                                                               | 8         | UN2434 | II    | 8 .....    | B2, IB2, T7, TP2, TP13                                 | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | C  | 40         |
|   | Diborane .....                                                                                           | 2.3       | UN1911 | ..... | 2.3, 2.1.  | 1, N89                                                 | None .... | 302 ..... | None .... | Forbidden | Forbidden | D  | 40, 57     |
| D | Diborane mixtures .....                                                                                  | 2.1       | NA1911 | ..... | 2.1 .....  | 5                                                      | None .... | 302 ..... | 245 ..... | Forbidden | Forbidden | D  | 40, 57     |
|   | Dibromoacetylene .....                                                                                   | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | 1,2-Dibromobutan-3-one .....                                                                             | 6.1       | UN2648 | II    | 6.1 .....  | IB2                                                    | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B  | 40         |
|   | Dibromochloropropane .....                                                                               | 6.1       | UN2872 | II    | 6.1 .....  | IB2, T7, TP2                                           | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | A  | .....      |
|   | .....                                                                                                    | .....     | .....  | III   | 6.1 .....  | IB3, T4, TP1                                           | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A  | .....      |
| A | Dibromodifluoromethane, R12B2                                                                            | 9         | UN1941 | III   | None ..... | T11, TP2                                               | 155 ..... | 203 ..... | 241 ..... | 100 L     | 220 L     | A  | 25         |
|   | 1,2-Dibromoethane, see Ethylene dibromide.                                                               | .....     |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | Dibromomethane .....                                                                                     | 6.1       | UN2664 | III   | 6.1 .....  | IB3, T4, TP1                                           | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A  | .....      |
|   | Dibutyl ethers .....                                                                                     | 3         | UN1149 | III   | 3 .....    | B1, IB3, T2, TP1                                       | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....      |
|   | Dibutylaminoethanol .....                                                                                | 6.1       | UN2873 | III   | 6.1 .....  | IB3, T4, TP1                                           | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A  | .....      |
|   | <i>N,N'</i> -Dichlorazodicarbonamidine (salts of) (dry).                                                 | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |
|   | 1,1-Dichloro-1-nitroethane .....                                                                         | 6.1       | UN2650 | II    | 6.1 .....  | IB2, T7, TP2                                           | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | A  | 12, 40, 74 |
| D | 3,5-Dichloro-2,4,6-trifluoropyridine.                                                                    | 6.1       | NA9264 | I     | 6.1 .....  | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None .... | 227 ..... | 244 ..... | Forbidden | Forbidden | A  | 40         |
|   | Dichloroacetic acid .....                                                                                | 8         | UN1764 | II    | 8 .....    | A3, A6, A7, B2, IB2, N34, T8, TP2, TP12                | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | A  | .....      |
|   | 1,3-Dichloroacetone .....                                                                                | 6.1       | UN2649 | II    | 6.1 .....  | IB8, IP2, IP4, T3, TP33                                | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | B  | 12, 40     |
|   | Dichloroacetyl chloride .....                                                                            | 8         | UN1765 | II    | 8 .....    | A3, A6, A7, B2, B6, IB2, N34, T7, TP2                  | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | D  | 40         |
|   | Dichloroacetylene .....                                                                                  | Forbidden |        |       | .....      |                                                        | .....     | .....     | .....     | .....     | .....     |    | .....      |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                   | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)    | (8)                   |           |           | (9)                                             |                       | (10)             |            |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|-------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|------------|
|          |                                                                                                                                               |                            |                            |       |             |                                     | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |            |
|          |                                                                                                                                               |                            |                            |       |             |                                     | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other      |
| (1)      | (2)                                                                                                                                           | (3)                        | (4)                        | (5)   | (6)         | (7)                                 | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)      |
| +        | Dichloroanilines, liquid .....                                                                                                                | 6.1                        | UN1590                     | II    | 6.1 .....   | IB2, T7, TP2                        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | 40         |
|          | Dichloroanilines, solid .....                                                                                                                 | 6.1                        | UN3442                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33             | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | 40         |
| +        | o-Dichlorobenzene .....                                                                                                                       | 6.1                        | UN1591                     | III   | 6.1 .....   | IB3, T4, TP1                        | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | .....      |
|          | 2,2'-Dichlorodiethyl ether .....                                                                                                              | 6.1                        | UN1916                     | II    | 6.1, 3      | IB2, N33, N34, T7, TP2 T50          | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | .....      |
|          | Dichlorodifluoromethane and difluoroethane azeotropic mixture or Refrigerant gas R 500 with approximately 74 percent dichlorodifluoromethane. | 2.2                        | UN2602                     | ..... | 2.2 .....   | T50                                 | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | A                | .....      |
|          | Dichlorodifluoromethane or Refrigerant gas R 12.                                                                                              | 2.2                        | UN1028                     | ..... | 2.2 .....   | T50                                 | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | A                | .....      |
|          | Dichlorodimethyl ether, symmetrical.                                                                                                          | 6.1                        | UN2249                     | I     | 6.1, 3      |                                     | None .....            | 201 ..... | 243 ..... | Forbidden                                       | Forbidden             |                  | 40         |
|          | 1,1-Dichloroethane .....                                                                                                                      | 3                          | UN2362                     | II    | 3 .....     | IB2, T4, TP1                        | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | 40         |
|          | 1,2-Dichloroethane, see Ethylene dichloride.                                                                                                  | .....                      | .....                      | ..... | .....       |                                     | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....      |
|          | Dichloroethyl sulfide .....                                                                                                                   | Forbidden                  | .....                      | ..... | .....       |                                     | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....      |
|          | 1,2-Dichloroethylene .....                                                                                                                    | 3                          | UN1150                     | II    | 3 .....     | IB2, T7, TP2                        | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | Dichlorofluoromethane or Refrigerant gas R21.                                                                                                 | 2.2                        | UN1029                     | ..... | 2.2 .....   | T50                                 | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | A                | .....      |
|          | Dichloroisocyanuric acid, dry or Dichloroisocyanuric acid salts.                                                                              | 5.1                        | UN2465                     | II    | 5.1 .....   | 28, IB8, IP4, T3, TP33              | 152 .....             | 212 ..... | 240 ..... | 5 kg                                            | 25 kg                 | A                | 13         |
|          | Dichloroisopropyl ether .....                                                                                                                 | 6.1                        | UN2490                     | II    | 6.1 .....   | IB2, T7, TP2                        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | Dichloromethane .....                                                                                                                         | 6.1                        | UN1593                     | III   | 6.1 .....   | IB3, IP8, N36, T7, TP2              | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | .....      |
|          | Dichloropentanes .....                                                                                                                        | 3                          | UN1152                     | III   | 3 .....     | B1, IB3, T2, TP1                    | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....      |
|          | Dichlorophenyl isocyanates .....                                                                                                              | 6.1                        | UN2250                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33             | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | B                | 25, 40, 48 |
|          | Dichlorophenyltrichlorosilane .....                                                                                                           | 8                          | UN1766                     | II    | 8 .....     | A7, B2, B6, IB2, N34, T7, TP2, TP13 | None .....            | 202 ..... | 242 ..... | Forbidden                                       | 30 L                  | C                | 40         |
|          | 1,2-Dichloropropane .....                                                                                                                     | 3                          | UN1279                     | II    | 3 .....     | IB2, N36, T4, TP1                   | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | 1,3-Dichloropropanol-2 .....                                                                                                                  | 6.1                        | UN2750                     | II    | 6.1 .....   | IB2, T7, TP2                        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | 12, 40     |
|          | Dichloropropene and propylene dichloride mixture, see 1,2-Dichloropropane.                                                                    | .....                      | .....                      | ..... | .....       |                                     | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....      |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                     |           |        |       |       |       |                                 |       |       |       |       |       |       |           |           |       |        |
|---------------------------------------------------------------------|-----------|--------|-------|-------|-------|---------------------------------|-------|-------|-------|-------|-------|-------|-----------|-----------|-------|--------|
| Dichloropropenes .....                                              | 3         | UN2047 | II    | 3     | ..... | IB2, T4, TP1                    | 150   | ..... | 202   | ..... | 242   | ..... | 5 L       | 60 L      | B     | .....  |
| .....                                                               | .....     | .....  | III   | 3     | ..... | B1, IB3, T2, TP1                | 150   | ..... | 203   | ..... | 242   | ..... | 60 L      | 220 L     | A     | .....  |
| Dichlorosilane .....                                                | 2.3       | UN2189 | ..... | 2.3,  | ..... | 2, B9, B14                      | None  | ....  | 304   | ..... | 314,  | ..... | Forbidden | Forbidden | D     | 17, 40 |
| .....                                                               | .....     | .....  | ..... | 2.1,  | ..... | .....                           | ..... | ..... | ..... | ..... | 315.  | ..... | .....     | .....     | ..... | .....  |
| .....                                                               | .....     | .....  | ..... | 8.    | ..... | .....                           | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| 1,2-Dichloro-1,1,2,2-tetrafluoroethane or Refrigerant gas R 114.    | 2.2       | UN1958 | ..... | 2.2   | ..... | T50                             | 306   | ..... | 304   | ..... | 314,  | ..... | 75 kg     | 150 kg    | A     | .....  |
| .....                                                               | .....     | .....  | ..... | ..... | ..... | .....                           | ..... | ..... | ..... | ..... | 315.  | ..... | .....     | .....     | ..... | .....  |
| Dichlorovinylchloroarsine .....                                     | Forbidden | .....  | ..... | ..... | ..... | .....                           | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Dicycloheptadiene, see Bicyclo [2,2,1] hepta-2,5-diene, stabilized. | .....     | .....  | ..... | ..... | ..... | .....                           | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Dicyclohexylamine .....                                             | 8         | UN2565 | III   | 8     | ..... | IB3, T4, TP1                    | 154   | ..... | 203   | ..... | 241   | ..... | 5 L       | 60 L      | A     | .....  |
| Dicyclohexylammonium nitrite ...                                    | 4.1       | UN2687 | III   | 4.1   | ..... | IB8, IP3, T1, TP33              | 151   | ..... | 213   | ..... | 240   | ..... | 25 kg     | 100 kg    | A     | 48     |
| Dicyclopentadiene .....                                             | 3         | UN2048 | III   | 3     | ..... | B1, IB3, T2, TP1                | 150   | ..... | 203   | ..... | 242   | ..... | 60 L      | 220 L     | A     | .....  |
| Didymium nitrate .....                                              | 5.1       | UN1465 | III   | 5.1   | ..... | A1, IB8, IP3, T1, TP33          | 152   | ..... | 213   | ..... | 240   | ..... | 25 kg     | 100 kg    | A     | .....  |
| D Diesel fuel .....                                                 | 3         | NA1993 | III   | None  | ..... | 144, B1, IB3, T4, TP1, TP29     | 150   | ..... | 203   | ..... | 242   | ..... | 60 L      | 220 L     | A     | .....  |
| I Diesel fuel .....                                                 | 3         | UN1202 | III   | 3     | ..... | 144, B1, IB3, T2, TP1           | 150   | ..... | 203   | ..... | 242   | ..... | 60 L      | 220 L     | A     | .....  |
| Diethanol nitrosamine dinitrate (dry).                              | Forbidden | .....  | ..... | ..... | ..... | .....                           | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Diethoxymethane .....                                               | 3         | UN2373 | II    | 3     | ..... | IB2, T4, TP1                    | 150   | ..... | 202   | ..... | 242   | ..... | 5 L       | 60 L      | E     | .....  |
| 3,3-Diethoxypropene .....                                           | 3         | UN2374 | II    | 3     | ..... | IB2, T4, TP1                    | 150   | ..... | 202   | ..... | 242   | ..... | 5 L       | 60 L      | B     | .....  |
| Diethyl carbonate .....                                             | 3         | UN2366 | III   | 3     | ..... | B1, IB3, T2, TP1                | 150   | ..... | 203   | ..... | 242   | ..... | 60 L      | 220 L     | A     | .....  |
| Diethyl cellosolve, see Ethylene glycol diethyl ether.              | .....     | .....  | ..... | ..... | ..... | .....                           | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Diethyl ether or Ethyl ether .....                                  | 3         | UN1155 | I     | 3     | ..... | T11, TP2                        | 150   | ..... | 201   | ..... | 243   | ..... | 1 L       | 30 L      | E     | 40     |
| Diethyl ketone .....                                                | 3         | UN1156 | II    | 3     | ..... | IB2, T4, TP1                    | 150   | ..... | 202   | ..... | 242   | ..... | 5 L       | 60 L      | B     | .....  |
| Diethyl peroxydicarbonate, with more than 27 percent in solution.   | Forbidden | .....  | ..... | ..... | ..... | .....                           | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Diethyl sulfate .....                                               | 6.1       | UN1594 | II    | 6.1   | ..... | IB2, T7, TP2                    | 153   | ..... | 202   | ..... | 243   | ..... | 5 L       | 60 L      | C     | .....  |
| Diethyl sulfide .....                                               | 3         | UN2375 | II    | 3     | ..... | IB2, T7, TP1, TP13              | None  | ....  | 202   | ..... | 243   | ..... | 5 L       | 60 L      | E     | .....  |
| Diethylamine .....                                                  | 3         | UN1154 | II    | 3, 8  | ....  | A3, IB2, N34, T7, TP1           | 150   | ..... | 202   | ..... | 243   | ..... | 1 L       | 5 L       | E     | 40     |
| 2-Diethylaminoethanol .....                                         | 8         | UN2686 | II    | 8, 3  | ....  | B2, IB2, T7, TP2                | None  | ....  | 202   | ..... | 243   | ..... | 1 L       | 30 L      | A     | .....  |
| 3-Diethylamino-propylamine. ....                                    | 3         | UN2684 | III   | 3, 8  | ....  | B1, IB3, T4, TP1                | 150   | ..... | 203   | ..... | 242   | ..... | 5 L       | 60 L      | A     | .....  |
| N, N-Diethylaniline .....                                           | 6.1       | UN2432 | III   | 6.1   | ..... | IB3, T4, TP1                    | 153   | ..... | 203   | ..... | 241   | ..... | 60 L      | 220 L     | A     | .....  |
| Diethylbenzene .....                                                | 3         | UN2049 | III   | 3     | ..... | B1, IB3, T2, TP1                | 150   | ..... | 203   | ..... | 242   | ..... | 60 L      | 220 L     | A     | .....  |
| Diethyldichlorosilane .....                                         | 8         | UN1767 | II    | 8, 3  | ....  | A7, B6, IB2, N34, T7, TP2, TP13 | None  | ....  | 202   | ..... | 243   | ..... | Forbidden | 30 L      | C     | 40     |
| Diethylene glycol dinitrate .....                                   | Forbidden | .....  | ..... | ..... | ..... | .....                           | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     | ..... | .....  |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                   | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)        | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|-------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|-----------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                                                               |                            |                            |       |             |                                         | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                                                               |                            |                            |       |             |                                         | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| (1)      | (2)                                                                                                                           | (3)                        | (4)                        | (5)   | (6)         | (7)                                     | (8A)                  | (8B)      | (8C)      | (9A)                                            | (9B)                  | (10A)            | (10B)  |
|          | Diethyleneglycol dinitrate, de- sensitized with not less than 25 percent non-volatile water- insoluble phlegmatizer, by mass. | 1.1D                       | UN0075                     | II    | 1.1D ..     |                                         | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 13               | 21E    |
|          | Diethylenetriamine .....                                                                                                      | 8                          | UN2079                     | II    | 8 .....     | B2, IB2, T7, TP2                        | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | A                | 40, 52 |
|          | N,N-Diethylethylenediamine .....                                                                                              | 8                          | UN2685                     | II    | 8, 3 ....   | IB2, T7, TP2                            | None ....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                  | A                | .....  |
|          | Diethylgold bromide .....                                                                                                     | Forbidden                  |                            |       |             |                                         |                       |           |           |                                                 |                       |                  |        |
|          | Diethylthiophosphoryl chloride ...                                                                                            | 8                          | UN2751                     | II    | 8 .....     | B2, IB2, T7, TP2                        | None ....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                 | D                | 12, 40 |
|          | Diethylzinc .....                                                                                                             | 4.2                        | UN1366                     | I     | 4.2, 4.3.   | 173, B11, T21, TP2, TP7                 | None ....             | 181 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 18     |
|          | Difluorochloroethanes, see 1- Chloro-1,1-difluoroethanes.                                                                     |                            |                            |       |             |                                         |                       |           |           |                                                 |                       |                  |        |
|          | 1,1-Difluoroethane or Refrig- erant gas R 152a.                                                                               | 2.1                        | UN1030                     | ..... | 2.1 .....   | T50                                     | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg                | B                | 40     |
|          | 1,1-Difluoroethylene or Refrig- erant gas R 1132a.                                                                            | 2.1                        | UN1959                     | ..... | 2.1 .....   |                                         | 306 .....             | 304 ..... | None .... | Forbidden                                       | 150 kg                | E                | 40     |
|          | Difluoromethane or Refrigerant gas R 32.                                                                                      | 2.1                        | UN3252                     | ..... | 2.1 .....   | T50                                     | 306 .....             | 302 ..... | 314, 315. | Forbidden                                       | 150 kg                | D                | 40     |
|          | Difluorophosphoric acid, anhy- drous.                                                                                         | 8                          | UN1768                     | II    | 8 .....     | A6, A7, B2, IB2, N5, N34, T8, TP2, TP12 | None ....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | A                | 40     |
|          | 2,3-Dihydropyran .....                                                                                                        | 3                          | UN2376                     | II    | 3 .....     | IB2, T4, TP1                            | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....  |
|          | 1,8-Dihydroxy-2,4,5,7- tetranitroanthraquinone (chrysamminic acid).                                                           | Forbidden                  |                            |       |             |                                         |                       |           |           |                                                 |                       |                  |        |
|          | Diiodoacetylene .....                                                                                                         | Forbidden                  |                            |       |             |                                         |                       |           |           |                                                 |                       |                  |        |
|          | Diisobutyl ketone .....                                                                                                       | 3                          | UN1157                     | III   | 3 .....     | B1, IB3, T2, TP1                        | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....  |
|          | Diisobutylamine .....                                                                                                         | 3                          | UN2361                     | III   | 3, 8 ....   | B1, IB3, T4, TP1                        | 150 .....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                  | A                | .....  |
|          | Diisobutylene, isomeric com- pounds.                                                                                          | 3                          | UN2050                     | II    | 3 .....     | IB2, T4, TP1                            | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....  |
|          | Diisooctyl acid phosphate .....                                                                                               | 8                          | UN1902                     | III   | 8 .....     | IB3, T4, TP1                            | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | .....  |
|          | Diisopropyl ether .....                                                                                                       | 3                          | UN1159                     | II    | 3 .....     | IB2, T4, TP1                            | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | E                | 40     |
|          | Diisopropylamine .....                                                                                                        | 3                          | UN1158                     | II    | 3, 8 ....   | IB2, T7, TP1                            | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | .....  |
|          | Diisopropylbenzene hydroperoxide, with more than 72 percent in solution.                                                      | Forbidden                  |                            |       |             |                                         |                       |           |           |                                                 |                       |                  |        |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                              |           |        |       |        |                                                       |      |     |           |           |           |   |             |
|------------------------------------------------------------------------------|-----------|--------|-------|--------|-------------------------------------------------------|------|-----|-----------|-----------|-----------|---|-------------|
| Diketene, stabilized .....                                                   | 6.1       | UN2521 | I     | 6.1, 3 | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45      | None | 227 | 244       | Forbidden | Forbidden | D | 26, 27, 40  |
| 1,2-Dimethoxyethane .....                                                    | 3         | UN2252 | II    | 3      | IB2, T4, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | B | .....       |
| 1,1-Dimethoxyethane .....                                                    | 3         | UN2377 | II    | 3      | IB2, T7, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | B | .....       |
| Dimethyl carbonate .....                                                     | 3         | UN1161 | II    | 3      | IB2, T4, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | B | .....       |
| Dimethyl chlorothiophosphate, see Dimethyl thiophosphoryl chloride.          | Forbidden |        |       |        |                                                       |      |     |           |           |           |   | .....       |
| 2,5-Dimethyl-2,5-dihydroperoxy hexane, with more than 82 percent with water. | Forbidden |        |       |        |                                                       |      |     |           |           |           |   | .....       |
| Dimethyl disulfide .....                                                     | 3         | UN2381 | II    | 3      | IB2, T4, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | B | 40          |
| Dimethyl ether .....                                                         | 2.1       | UN1033 | ..... | 2.1    | T50                                                   | 306  | 304 | 314, 315. | Forbidden | 150 kg    | B | 40          |
| Dimethyl-N-propylamine .....                                                 | 3         | UN2266 | II    | 3, 8   | IB2, T7, TP2, TP13                                    | 150  | 202 | 243       | 1 L       | 5 L       | B | 40          |
| Dimethyl sulfate .....                                                       | 6.1       | UN1595 | I     | 6.1, 8 | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None | 227 | 244       | Forbidden | Forbidden | D | 40          |
| Dimethyl sulfide .....                                                       | 3         | UN1164 | II    | 3      | IB2, IP8, T7, TP2                                     | 150  | 202 | 242       | 5 L       | 60 L      | E | 40          |
| Dimethyl thiophosphoryl chloride                                             | 6.1       | UN2267 | II    | 6.1, 8 | IB2, T7, TP2                                          | 153  | 202 | 243       | 1 L       | 30 L      | B | 25          |
| Dimethylamine, anhydrous .....                                               | 2.1       | UN1032 | ..... | 2.1    | N87, T50                                              | None | 304 | 314, 315. | Forbidden | 150 kg    | D | 40          |
| Dimethylamine solution .....                                                 | 3         | UN1160 | II    | 3, 8   | IB2, T7, TP1                                          | 150  | 202 | 243       | 1 L       | 5 L       | B | 52.         |
| 2-Dimethylaminoacetonitrile .....                                            | 3         | UN2378 | II    | 3, 6.1 | IB2, T7, TP1                                          | 150  | 202 | 243       | 1 L       | 60 L      | A | 40, 52      |
| 2-Dimethylaminoethanol .....                                                 | 8         | UN2051 | II    | 8, 3   | B2, IB2, T7, TP2                                      | 154  | 202 | 243       | 1 L       | 30 L      | A | .....       |
| 2-Dimethylaminoethyl acrylate ...                                            | 6.1       | UN3302 | II    | 6.1    | IB2, T7, TP2                                          | 153  | 202 | 243       | 5 L       | 60 L      | D | 25          |
| 2-Dimethylaminoethyl methacrylate.                                           | 6.1       | UN2522 | II    | 6.1    | IB2, T7, TP2                                          | 153  | 202 | 243       | 5 L       | 60 L      | B | 40          |
| N,N-Dimethylaniline .....                                                    | 6.1       | UN2253 | II    | 6.1    | IB1, T7, TP2                                          | 153  | 202 | 243       | 5 L       | 60 L      | A | .....       |
| 2,3-Dimethylbutane .....                                                     | 3         | UN2457 | II    | 3      | IB2, T7, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | E | .....       |
| 1, 3-Dimethylbutylamine .....                                                | 3         | UN2379 | II    | 3, 8   | IB2, T7, TP1                                          | 150  | 202 | 243       | 1 L       | 5 L       | B | 52.         |
| Dimethylcarbamoyl chloride .....                                             | 8         | UN2262 | II    | 8      | B2, IB2, T7, TP2                                      | 154  | 202 | 242       | 1 L       | 30 L      | A | 40          |
| Dimethylcyclohexanes .....                                                   | 3         | UN2263 | II    | 3      | IB2, T4, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | B | .....       |
| N,N-Dimethylcyclohexylamine ...                                              | 8         | UN2264 | II    | 8, 3   | B2, IB2, T7, TP2                                      | 154  | 202 | 243       | 1 L       | 30 L      | A | 40          |
| Dimethyldichlorosilane .....                                                 | 3         | UN1162 | II    | 3, 8   | B77, IB2, T7, TP2, TP13                               | None | 202 | 243       | Forbidden | Forbidden | B | 40          |
| Dimethyldiethoxysilane .....                                                 | 3         | UN2380 | II    | 3      | IB2, T4, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | B | .....       |
| Dimethyldioxanes .....                                                       | 3         | UN2707 | II    | 3      | IB2, T4, TP1                                          | 150  | 202 | 242       | 5 L       | 60 L      | B | .....       |
| .....                                                                        | .....     | .....  | III   | 3      | B1, IB3, T2, TP1                                      | 150  | 203 | 242       | 60 L      | 220 L     | A | .....       |
| N,N-Dimethylformamide .....                                                  | 3         | UN2265 | III   | 3      | B1, IB3, T2, TP2                                      | 150  | 203 | 242       | 60 L      | 220 L     | A | .....       |
| Dimethylhexane dihydroperoxide (dry).                                        | Forbidden |        |       |        |                                                       |      |     |           |           |           |   | .....       |
| Dimethylhydrazine, symmetrical                                               | 6.1       | UN2382 | I     | 6.1, 3 | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None | 227 | 244       | Forbidden | Forbidden | D | 40, 52, 74. |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                  | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes        | Special provi- sions (§ 172.102)                              | (8)                   |           |              | (9)                                             |                       | (10)             |                            |
|----------|------------------------------------------------------------------------------|----------------------------|----------------------------|-------|--------------------|---------------------------------------------------------------|-----------------------|-----------|--------------|-------------------------------------------------|-----------------------|------------------|----------------------------|
|          |                                                                              |                            |                            |       |                    |                                                               | Packaging (§ 173.***) |           |              | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                            |
|          |                                                                              |                            |                            |       |                    |                                                               | Excep- tions          | Non- bulk | Bulk         | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                      |
| (1)      | (2)                                                                          | (3)                        | (4)                        | (5)   | (6)                | (7)                                                           | (8A)                  | (8B)      | (8C)         | (9A)                                            | (9B)                  | (10A)            | (10B)                      |
|          | Dimethylhydrazine, unsymmet-<br>rical.                                       | 6.1                        | UN1163                     | I     | 6.1, 3,<br>8.      | 2, B7, B9, B14,<br>B32, B74, T20,<br>TP2, TP13,<br>TP38, TP45 | None ....             | 227 ..... | 244 .....    | Forbidden                                       | Forbidden             | D                | 21, 38,<br>40, 52,<br>100. |
|          | 2,2-Dimethylpropane .....                                                    | 2.1                        | UN2044                     | ..... | 2.1 .....          |                                                               | 306 .....             | 304 ..... | 314,<br>315. | Forbidden                                       | 150 kg                | E                | 40                         |
|          | Dimethylzinc .....                                                           | 4.2                        | UN1370                     | I     | 4.2,<br>4.3.       | 173, B11, B16,<br>T21, TP2, TP7                               | None ....             | 181 ..... | 244 .....    | Forbidden                                       | Forbidden             | D                | 18                         |
|          | Dinitro-o-cresol .....                                                       | 6.1                        | UN1598                     | II    | 6.1 .....          | IB8, IP2, IP4, T3,<br>TP33                                    | 153 .....             | 212 ..... | 242 .....    | 25 kg                                           | 100 kg                | A                | .....                      |
|          | 1,3-Dinitro-5,5-dimethyl<br>hydantoin.                                       | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | Dinitro-7,8-dimethylglycoluril<br>(dry).                                     | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | 1,3-Dinitro-4,5-dinitrosobenzene                                             | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | 1,4-Dinitro-1,1,4,4-<br>tetramethylolbutanetetranitrate<br>(dry).            | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | 2,4-Dinitro-1,3,5-<br>trimethylbenzene.                                      | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | Dinitroanilines .....                                                        | 6.1                        | UN1596                     | II    | 6.1 .....          | IB8, IP2, IP4, T3,<br>TP33                                    | 153 .....             | 212 ..... | 242 .....    | 25 kg                                           | 100 kg                | A                | 91                         |
|          | Dinitrobenzenes, liquid .....                                                | 6.1                        | UN1597                     | II    | 6.1 .....          | 11, IB2, T7, TP2                                              | 153 .....             | 202 ..... | 243 .....    | 5 L                                             | 60 L                  | A                | 91                         |
|          | .....                                                                        | .....                      | .....                      | III   | 6.1 .....          | 11, IB3, T7, TP2                                              | 153 .....             | 203 ..... | 241 .....    | 60 L                                            | 220 L                 | A                | 91                         |
|          | Dinitrobenzenes, solid .....                                                 | 6.1                        | UN3443                     | II    | 6.1 .....          | IB8, IP2, IP4, T3,<br>TP33                                    | 153 .....             | 212 ..... | 242 .....    | 25 kg                                           | 100 kg                | A                | 91                         |
|          | Dinitrochlorobenzene, see<br>Chlorodinitrobenzene.                           | .....                      |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | 1,2-Dinitroethane .....                                                      | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | 1,1-Dinitroethane (dry) .....                                                | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | Dinitrogen tetroxide .....                                                   | 2.3                        | UN1067                     | ..... | 2.3,<br>5.1,<br>8. | 1, B7, B14, B45,<br>B46, B61, B66,<br>B67, B77, T50,<br>TP21  | None ....             | 336 ..... | 314 .....    | Forbidden                                       | Forbidden             | D                | 40, 89,<br>90              |
|          | Dinitroglycoluril or Dingu .....                                             | 1.1D                       | UN0489                     | II    | 1.1D ..            |                                                               | None ....             | 62 .....  | None ....    | Forbidden                                       | Forbidden             | 10               | .....                      |
|          | Dinitromethane .....                                                         | Forbidden                  |                            |       | .....              |                                                               | .....                 | .....     | .....        | .....                                           | .....                 |                  | .....                      |
|          | Dinitrophenol, dry or wetted with<br>less than 15 percent water, by<br>mass. | 1.1D                       | UN0076                     | II    | 1.1D,<br>6.1.      |                                                               | None ....             | 62 .....  | None ....    | Forbidden                                       | Forbidden             | 10               | 5E                         |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|                                                                                          |           |        |               |                                              |           |           |           |           |           |       |        |
|------------------------------------------------------------------------------------------|-----------|--------|---------------|----------------------------------------------|-----------|-----------|-----------|-----------|-----------|-------|--------|
| Dinitrophenol solutions .....                                                            | 6.1       | UN1599 | II 6.1 .....  | IB2, T7, TP2                                 | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | A     | 36     |
| .....                                                                                    | .....     | .....  | III 6.1 ..... | IB3, T4, TP1                                 | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A     | 36     |
| Dinitrophenol, wetted with not less than 15 percent water, by mass.                      | 4.1       | UN1320 | I 4.1, 6.1.   | 23, A8, A19, A20, N41                        | None .... | 211 ..... | None .... | 1 kg      | 15 kg     | E     | 28, 36 |
| Dinitrophenolates alkali metals, dry or wetted with less than 15 percent water, by mass. | 1.3C      | UN0077 | II 1.3C, 6.1. |                                              | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | 5E     |
| Dinitrophenolates, wetted with not less than 15 percent water, by mass.                  | 4.1       | UN1321 | I 4.1, 6.1.   | 23, A8, A19, A20, N41                        | None .... | 211 ..... | None .... | 1 kg      | 15 kg     | E     | 28, 36 |
| Dinitropropylene glycol .....                                                            | Forbidden |        | .....         |                                              | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| Dinitroresorcinol, dry or wetted with less than 15 percent water, by mass.               | 1.1D      | UN0078 | II 1.1D ..    |                                              | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | 5E     |
| 2,4-Dinitroresorcinol (heavy metal salts of) (dry).                                      | Forbidden |        | .....         |                                              | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| 4,6-Dinitroresorcinol (heavy metal salts of) (dry).                                      | Forbidden |        | .....         |                                              | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| Dinitroresorcinol, wetted with not less than 15 percent water, by mass.                  | 4.1       | UN1322 | I 4.1 .....   | 23, A8, A19, A20, N41                        | None .... | 211 ..... | None .... | 1 kg      | 15 kg     | E     | 28, 36 |
| 3,5-Dinitrosalicylic acid (lead salt) (dry).                                             | Forbidden |        | .....         |                                              | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| Dinitrosobenzene .....                                                                   | 1.3C      | UN0406 | II 1.3C ..    |                                              | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | .....  |
| Dinitrosobenzylamidine and salts of (dry).                                               | Forbidden |        | .....         |                                              | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| 2,2-Dinitrostilbene .....                                                                | Forbidden |        | .....         |                                              | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| Dinitrotoluenes, liquid .....                                                            | 6.1       | UN2038 | II 6.1 .....  | IB2, T7, TP2                                 | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | A     | .....  |
| Dinitrotoluenes, molten .....                                                            | 6.1       | UN1600 | II 6.1 .....  | T7, TP3                                      | None .... | 202 ..... | 243 ..... | Forbidden | Forbidden | C     | .....  |
| Dinitrotoluenes, solid .....                                                             | 6.1       | UN3454 | II 6.1 .....  | IB8, IP2, IP4, T3, TP33                      | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A     | .....  |
| 1,9-Dinitroxy pentamethylene-2,4, 6,8-tetramine (dry).                                   | Forbidden |        | .....         |                                              | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| Dioxane .....                                                                            | 3         | UN1165 | II 3 .....    | IB2, T4, TP1                                 | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B     | .....  |
| Dioxolane .....                                                                          | 3         | UN1166 | II 3 .....    | IB2, T4, TP1                                 | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B     | 40     |
| Dipentene .....                                                                          | 3         | UN2052 | III 3 .....   | B1, IB3, T2, TP1                             | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A     | .....  |
| Diphenylamine chloroarsine .....                                                         | 6.1       | UN1698 | I 6.1 .....   | T6, TP33                                     | None .... | 201 ..... | None .... | Forbidden | Forbidden | D     | 40     |
| Diphenylchloroarsine, liquid .....                                                       | 6.1       | UN1699 | I 6.1 .....   | A8, B14, B32, N33, N34, T14, TP2, TP13, TP27 | None .... | 201 ..... | 243 ..... | Forbidden | 30 L      | D     | 40     |
| Diphenylchloroarsine, solid .....                                                        | 6.1       | UN3450 | I 6.1 .....   | IB7, IP1, T6, TP33                           | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | D     | 40     |
| Diphenyldichlorosilane .....                                                             | 8         | UN1769 | II 8 .....    | A7, B2, IB2, N34, T7, TP2, TP13              | None .... | 202 ..... | 242 ..... | Forbidden | 30 L      | C     | 40     |
| Diphenylmethyl bromide .....                                                             | 8         | UN1770 | II 8 .....    | IB8, IP2, IP4, T3, TP33                      | 154 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | D     | 40     |
| Dipicryl sulfide, dry or wetted with less than 10 percent water, by mass.                | 1.1D      | UN0401 | II 1.1D ..    |                                              | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | .....  |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                      | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes | Special provi-sions (§ 172.102)     | (8)                   |           |           | (9)                                             |                      | (10)            |       |
|----------|----------------------------------------------------------------------------------|---------------------------|--------------------------|-------|-------------|-------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                                                  |                           |                          |       |             |                                     | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                                                  |                           |                          |       |             |                                     | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
|          | Dipicryl sulfide, <i>dry or wetted with less than 10 percent water, by mass.</i> | 1.1D                      | UN0401                   | II    | 1.1D ..     |                                     | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | ..... |
|          | Dipicryl sulfide, <i>wetted with not less than 10 percent water, by mass.</i>    | 4.1                       | UN2852                   | I     | 4.1 .....   | 162, A2, N41, N84                   | None ....             | 211 ..... | None .... | Forbidden                                       | 0.5 kg               | D               | 28    |
|          | Dipicrylamine, <i>see</i> Hexanitrodiphenylamine.                                | .....                     | .....                    | ..... | .....       | .....                               | .....                 | .....     | .....     | .....                                           | .....                | .....           | ..... |
|          | Dipropionyl peroxide, <i>with more than 28 percent in solution.</i>              | Forbidden                 | .....                    | ..... | .....       | .....                               | .....                 | .....     | .....     | .....                                           | .....                | .....           | ..... |
|          | Di-n-propyl ether .....                                                          | 3                         | UN2384                   | II    | 3 .....     | IB2, T4, TP1                        | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                 | B               | ..... |
|          | Dipropyl ketone .....                                                            | 3                         | UN2710                   | III   | 3 .....     | B1, IB3, T2, TP1                    | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                | A               | ..... |
|          | Dipropylamine .....                                                              | 3                         | UN2383                   | II    | 3, 8 ....   | IB2, T7, TP1                        | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                  | B               | ..... |
| G        | Disinfectant, liquid, corrosive, n.o.s..                                         | 8                         | UN1903                   | I     | 8 .....     | A6, A7, B10, T14, TP2, TP27         | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                | B               | ..... |
| G        | Disinfectants, liquid, corrosive n.o.s..                                         | 8                         | UN1903                   | II    | 8 .....     | B2, IB2, T7, TP2                    | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                 | B               | ..... |
|          | .....                                                                            | .....                     | .....                    | III   | 8 .....     | IB3, T4, TP1                        | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                 | A               | ..... |
| G        | Disinfectants, liquid, toxic, n.o.s.                                             | 6.1                       | UN3142                   | I     | 6.1 ....    | A4, T14, TP2, TP27                  | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | A               | 40    |
|          | .....                                                                            | .....                     | .....                    | II    | 6.1 ....    | IB2, T11, TP2, TP27                 | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | A               | 40    |
|          | .....                                                                            | .....                     | .....                    | III   | 6.1 ....    | IB3, T7, TP1, TP28                  | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               | 40    |
| G        | Disinfectants, solid, toxic, n.o.s.                                              | 6.1                       | UN1601                   | I     | 6.1 ....    | IB7, IP1, T6, TP33                  | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                | A               | 40    |
|          | .....                                                                            | .....                     | .....                    | II    | 6.1 ....    | IB8, IP2, IP4, T3, TP33             | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | A               | 40    |
|          | .....                                                                            | .....                     | .....                    | III   | 6.1 ....    | IB8, IP3, T1, TP33                  | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg               | A               | 40    |
|          | Disodium trioxosilicate .....                                                    | 8                         | UN3253                   | III   | 8 .....     | IB8, IP3, T1, TP33                  | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | 52.   |
| G        | Dispersant gases, n.o.s. <i>see</i> Refrigerant gases, n.o.s..                   | .....                     | .....                    | ..... | .....       | .....                               | .....                 | .....     | .....     | .....                                           | .....                | .....           | ..... |
|          | Divinyl ether, stabilized .....                                                  | 3                         | UN1167                   | I     | 3 .....     | A7, T11, TP2                        | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | E               | 40    |
|          | Dodecyltrichlorosilane .....                                                     | 8                         | UN1771                   | II    | 8 .....     | A7, B2, B6, IB2, N34, T7, TP2, TP13 | None ....             | 202 ..... | 242 ..... | Forbidden                                       | 30 L                 | C               | 40    |
|          | Dry ice, <i>see</i> Carbon dioxide, solid.                                       | .....                     | .....                    | ..... | .....       | .....                               | .....                 | .....     | .....     | .....                                           | .....                | .....           | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                                                 |     |        |       |     |       |                             |             |       |      |       |     |       |           |           |   |       |
|---|---------------------------------------------------------------------------------------------------------------------------------|-----|--------|-------|-----|-------|-----------------------------|-------------|-------|------|-------|-----|-------|-----------|-----------|---|-------|
| G | Dyes, liquid, corrosive, n.o.s. or Dye intermediates, liquid, corrosive, n.o.s..                                                | 8   | UN2801 | I     | 8   | ..... | 11, A6, B10, T14, TP2, TP27 | None        | ....  | 201  | ..... | 243 | ..... | 0.5 L     | 2.5 L     | A | ..... |
|   | .....                                                                                                                           |     |        | II    | 8   | ..... | 11, B2, IB2, T11, TP2, TP27 | 154         | ..... | 202  | ..... | 242 | ..... | 1 L       | 30 L      | A | ..... |
|   | .....                                                                                                                           |     |        | III   | 8   | ..... | 11, IB3, T7, TP1, TP28      | 154         | ..... | 203  | ..... | 241 | ..... | 5 L       | 60 L      | A | ..... |
| G | Dyes, liquid, toxic, n.o.s. or Dye intermediates, liquid, toxic, n.o.s..                                                        | 6.1 | UN1602 | I     | 6.1 | ..... |                             | None        | ....  | 201  | ..... | 243 | ..... | 1 L       | 30 L      | A | ..... |
|   | .....                                                                                                                           |     |        | II    | 6.1 | ..... | IB2                         | 153         | ..... | 202  | ..... | 243 | ..... | 5 L       | 60 L      | A | ..... |
|   | .....                                                                                                                           |     |        | III   | 6.1 | ..... | IB3                         | 153         | ..... | 203  | ..... | 241 | ..... | 60 L      | 220 L     | A | ..... |
| G | Dyes, solid, corrosive, n.o.s. or Dye intermediates, solid, corrosive, n.o.s..                                                  | 8   | UN3147 | I     | 8   | ..... | IB7, IP1, T6, TP33          | None        | ....  | 211  | ..... | 242 | ..... | 1 kg      | 25 kg     | A | ..... |
|   | .....                                                                                                                           |     |        | II    | 8   | ..... | IB8, IP2, IP4, T3, TP33     | 154         | ..... | 212  | ..... | 240 | ..... | 15 kg     | 50 kg     | A | ..... |
|   | .....                                                                                                                           |     |        | III   | 8   | ..... | IB8, IP3, T1, TP33          | 154         | ..... | 213  | ..... | 240 | ..... | 25 kg     | 100 kg    | A | ..... |
| G | Dyes, solid, toxic, n.o.s. or Dye intermediates, solid, toxic, n.o.s..                                                          | 6.1 | UN3143 | I     | 6.1 | ..... | A5, IB7, IP1, T6, TP33      | None        | ....  | 211  | ..... | 242 | ..... | 5 kg      | 50 kg     | A | ..... |
|   | .....                                                                                                                           |     |        | II    | 6.1 | ..... | IB8, IP2, IP4, T3, TP33     | 153         | ..... | 212  | ..... | 242 | ..... | 25 kg     | 100 kg    | A | ..... |
|   | .....                                                                                                                           |     |        | III   | 6.1 | ..... | IB8, IP3, T1, TP33          | 153         | ..... | 213  | ..... | 240 | ..... | 100 kg    | 200 kg    | A | ..... |
|   | Dynamite, see Explosive, blasting, type A.                                                                                      |     |        |       |     |       |                             |             |       |      |       |     |       |           |           |   |       |
|   | Electrolyte (acid or alkali) for batteries, see Battery fluid, acid or Battery fluid, alkali.                                   |     |        |       |     |       |                             |             |       |      |       |     |       |           |           |   |       |
|   | Elevated temperature liquid, flammable, n.o.s., with flash point above 37.8 C, at or above its flash point.                     | 3   | UN3256 | III   | 3   | ..... | IB1, T3, TP3, TP29          | None        | ....  | None | ....  | 247 | ..... | Forbidden | Forbidden | A | ..... |
|   | Elevated temperature liquid, n.o.s., at or above 100 C and below its flash point (including molten metals, molten salts, etc.). | 9   | UN3257 | III   | 9   | ..... | IB1, T3, TP3, TP29          | None        | ....  | None | ....  | 247 | ..... | Forbidden | Forbidden | A | 85    |
|   | Elevated temperature solid, n.o.s., at or above 240 C, see § 173.247(h)(4).                                                     | 9   | UN3258 | III   | 9   | ..... |                             | 247(h) (4). |       | None | ....  | 247 | ..... | Forbidden | Forbidden | A | 85    |
|   | Engines, internal combustion, flammable gas powered.                                                                            | 9   | UN3166 | ..... | 9   | ..... | 135                         | 220         | ..... | 220  | ..... | 220 | ..... | Forbidden | No limit  | A | ..... |
|   | Engines, internal combustion, flammable liquid powered.                                                                         | 9   | UN3166 | ..... | 9   | ..... | 135                         | 220         | ..... | 220  | ..... | 220 | ..... | No limit  | No limit  | A | ..... |
| G | Environmentally hazardous substances, liquid, n.o.s..                                                                           | 9   | UN3082 | III   | 9   | ..... | 8, 146, IB3, T4, TP1, TP29  | 155         | ..... | 203  | ..... | 241 | ..... | No limit  | No limit  | A | ..... |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                 | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)     | (8)                   |            |           | (9)                                             |                       | (10)             |       |
|----------|-----------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|--------------------------------------|-----------------------|------------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                             |                            |                            |       |             |                                      | Packaging (§ 173.***) |            |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                             |                            |                            |       |             |                                      | Excep- tions          | Non- bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
| G        | Environmentally hazardous sub- stances, solid, n.o.s..                                                                      | 9                          | UN3077                     | III   | 9 .....     | 8, 146, B54, IB8, IP3, N20, T1, TP33 | 155 .....             | 213 .....  | 240 ..... | No limit                                        | No limit              | A                | ..... |
|          | Epibromohydrin .....                                                                                                        | 6.1                        | UN2558                     | I     | 6.1, 3      | T14, TP2, TP13                       | None .....            | 201 .....  | 243 ..... | Forbidden                                       | Forbidden             | D                | 40    |
|          | + Epichlorohydrin .....                                                                                                     | 6.1                        | UN2023                     | II    | 6.1, 3      | IB2, T7, TP2, TP13                   | 153 .....             | 202 .....  | 243 ..... | 5 L                                             | 60 L                  | A                | 40    |
|          | 1,2-Epoxy-3-ethoxypropane .....                                                                                             | 3                          | UN2752                     | III   | 3 .....     | B1, IB3, T2, TP1                     | 150 .....             | 203 .....  | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Esters, n.o.s. ....                                                                                                         | 3                          | UN3272                     | II    | 3 .....     | IB2, T7, TP1, TP8, TP28              | 150 .....             | 202 .....  | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |
| D        | .....                                                                                                                       | .....                      | .....                      | III   | 3 .....     | B1, IB3, T4, TP1, TP29               | 150 .....             | 203 .....  | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | <i>Etching acid, liquid, n.o.s., see Hydrofluoric acid, etc.</i>                                                            | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....      | .....     | .....                                           | .....                 | .....            | ..... |
|          | Ethane .....                                                                                                                | 2.1                        | UN1035                     | ..... | 2.1 .....   | .....                                | 306 .....             | 304 .....  | 302 ..... | Forbidden                                       | 150 kg                | E                | 40    |
|          | Ethane-Propane mixture, refrigerated liquid.                                                                                | 2.1                        | NA1961                     | ..... | 2.1 .....   | T75, TP5                             | None .....            | 316 .....  | 314, 315. | Forbidden                                       | Forbidden             | D                | 40    |
|          | Ethane, refrigerated liquid .....                                                                                           | 2.1                        | UN1961                     | ..... | 2.1 .....   | T75, TP5                             | None .....            | None ..... | 315 ..... | Forbidden                                       | Forbidden             | D                | 40    |
|          | <i>Ethanol amine dinitrate</i> .....                                                                                        | Forbidden                  | .....                      | ..... | .....       | .....                                | .....                 | .....      | .....     | .....                                           | .....                 | .....            | ..... |
|          | Ethanol and gasoline mixture or Ethanol and motor spirit mixture or Ethanol and petrol mixture, with more than 10% ethanol. | 3                          | UN3475                     | II    | 3 .....     | 144, 177, IB2, T4, TP1               | 150 .....             | 202 .....  | 242 ..... | 5 L                                             | 60 L                  | E                | ..... |
|          | Ethanol or Ethyl alcohol or Ethanol solutions or Ethyl alcohol solutions.                                                   | 3                          | UN1170                     | II    | 3 .....     | 24, IB2, T4, TP1                     | 150 .....             | 202 .....  | 242 ..... | 5 L                                             | 60 L                  | A                | ..... |
|          | .....                                                                                                                       | .....                      | .....                      | III   | 3 .....     | 24, B1, IB3, T2, TP1                 | 150 .....             | 203 .....  | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Ethanolamine or Ethanolamine solutions.                                                                                     | 8                          | UN2491                     | III   | 8 .....     | IB3, T4, TP1                         | 154 .....             | 203 .....  | 241 ..... | 5 L                                             | 60 L                  | A                | 52.   |
|          | <i>Ether, see Diethyl ether</i> .....                                                                                       | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....      | .....     | .....                                           | .....                 | .....            | ..... |
|          | Ethers, n.o.s. ....                                                                                                         | 3                          | UN3271                     | II    | 3 .....     | IB2, T7, TP1, TP8, TP28              | 150 .....             | 202 .....  | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |
|          | .....                                                                                                                       | .....                      | .....                      | III   | 3 .....     | B1, IB3, T4, TP1, TP29               | 150 .....             | 203 .....  | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Ethyl acetate .....                                                                                                         | 3                          | UN1173                     | II    | 3 .....     | IB2, T4, TP1                         | 150 .....             | 202 .....  | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |
|          | Ethyl acrylate, stabilized .....                                                                                            | 3                          | UN1917                     | II    | 3 .....     | IB2, T4, TP1, TP13                   | 150 .....             | 202 .....  | 242 ..... | 5 L                                             | 60 L                  | B                | 40    |
|          | Ethyl alcohol, see Ethanol .....                                                                                            | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....      | .....     | .....                                           | .....                 | .....            | ..... |
|          | <i>Ethyl aldehyde, see Acetaldehyde.</i>                                                                                    | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....      | .....     | .....                                           | .....                 | .....            | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                              |           |        |       |            |       |                                                        |       |       |       |       |           |       |           |           |       |             |
|----------------------------------------------|-----------|--------|-------|------------|-------|--------------------------------------------------------|-------|-------|-------|-------|-----------|-------|-----------|-----------|-------|-------------|
| Ethyl amyl ketone .....                      | 3         | UN2271 | III   | 3          | ..... | B1, IB3, T2, TP1                                       | 150   | ..... | 203   | ..... | 242       | ..... | 60 L      | 220 L     | A     | .....       |
| N-Ethylbenzyltoluidines, solid ....          | 6.1       | UN3460 | III   | 6.1        | ..... | IB8, IP3, T1, TP33                                     | 153   | ..... | 213   | ..... | 240       | ..... | 100 kg    | 200 kg    | A     | .....       |
| N-Ethyl-N-benzylaniline .....                | 6.1       | UN2274 | III   | 6.1        | ..... | IB3, T4, TP1                                           | 153   | ..... | 203   | ..... | 241       | ..... | 60 L      | 220 L     | A     | .....       |
| Ethyl borate .....                           | 3         | UN1176 | II    | 3          | ..... | IB2, T4, TP1                                           | 150   | ..... | 202   | ..... | 242       | ..... | 5 L       | 60 L      | B     | .....       |
| Ethyl bromide .....                          | 6.1       | UN1891 | II    | 6.1        | ..... | IB2, IP8, T7, TP2, TP13                                | 153   | ..... | 202   | ..... | 243       | ..... | 5 L       | 60 L      | B     | 40, 85      |
| Ethyl bromoacetate .....                     | 6.1       | UN1603 | II    | 6.1, 3     | ..... | IB2, T7, TP2                                           | None  | ....  | 202   | ..... | 243       | ..... | Forbidden | Forbidden | D     | 40          |
| Ethyl butyl ether .....                      | 3         | UN1179 | II    | 3          | ..... | B1, IB2, T4, TP1                                       | 150   | ..... | 202   | ..... | 242       | ..... | 5 L       | 60 L      | B     | .....       |
| Ethyl butyrate .....                         | 3         | UN1180 | III   | 3          | ..... | B1, IB3, T2, TP1                                       | 150   | ..... | 203   | ..... | 242       | ..... | 60 L      | 220 L     | A     | .....       |
| Ethyl chloride .....                         | 2.1       | UN1037 | ..... | 2.1        | ..... | B77, N86, T50                                          | None  | ....  | 322   | ..... | 314, 315. | ..... | Forbidden | 150 kg    | B     | 40          |
| Ethyl chloroacetate .....                    | 6.1       | UN1181 | II    | 6.1, 3     | ..... | IB2, T7, TP2                                           | 153   | ..... | 202   | ..... | 243       | ..... | 5 L       | 60 L      | A     | .....       |
| Ethyl chloroformate .....                    | 6.1       | UN1182 | I     | 6.1, 3, 8. | ..... | 2, B9, B14, B32, B74, N34, T20, TP2, TP13, TP38, TP45  | None  | ....  | 227   | ..... | 244       | ..... | Forbidden | Forbidden | D     | 21, 40, 100 |
| Ethyl 2-chloropropionate .....               | 3         | UN2935 | III   | 3          | ..... | B1, IB3, T2, TP1                                       | 150   | ..... | 203   | ..... | 242       | ..... | 60 L      | 220 L     | A     | .....       |
| Ethyl chlorothioformate .....                | 8         | UN2826 | II    | 8, 6.1, 3. | ..... | 2, B9, B14, B32, B74, T20, TP2, TP38, TP45             | None  | ....  | 227   | ..... | 244       | ..... | Forbidden | Forbidden | A     | 40          |
| Ethyl crotonate .....                        | 3         | UN1862 | II    | 3          | ..... | IB2, T4, TP2                                           | 150   | ..... | 202   | ..... | 242       | ..... | 5 L       | 60 L      | B     | .....       |
| Ethyl ether, <i>see</i> Diethyl ether ....   | .....     | .....  | ..... | .....      | ..... | .....                                                  | ..... | ..... | ..... | ..... | .....     | ..... | .....     | .....     | ..... | .....       |
| Ethyl fluoride or Refrigerant gas R161.      | 2.1       | UN2453 | ..... | 2.1        | ..... | .....                                                  | 306   | ..... | 304   | ..... | 314, 315. | ..... | Forbidden | 150 kg    | E     | 40          |
| Ethyl formate .....                          | 3         | UN1190 | II    | 3          | ..... | IB2, T4, TP1                                           | 150   | ..... | 202   | ..... | 242       | ..... | 5 L       | 60 L      | E     | .....       |
| Ethyl hydroperoxide .....                    | Forbidden | .....  | ..... | .....      | ..... | .....                                                  | ..... | ..... | ..... | ..... | .....     | ..... | .....     | .....     | ..... | .....       |
| Ethyl isobutyrate .....                      | 3         | UN2385 | II    | 3          | ..... | IB2, T4, TP1                                           | 150   | ..... | 202   | ..... | 242       | ..... | 5 L       | 60 L      | B     | .....       |
| Ethyl isocyanate .....                       | 3         | UN2481 | I     | 3, 6.1     | ..... | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44       | None  | ....  | 226   | ..... | 244       | ..... | Forbidden | Forbidden | D     | 40, 52      |
| Ethyl lactate .....                          | 3         | UN1192 | III   | 3          | ..... | B1, IB3, T2, TP1                                       | 150   | ..... | 203   | ..... | 242       | ..... | 60 L      | 220 L     | A     | .....       |
| Ethyl mercaptan .....                        | 3         | UN2363 | I     | 3          | ..... | A6, T11, TP2, TP13                                     | None  | ....  | 201   | ..... | 243       | ..... | Forbidden | 30 L      | E     | 95, 102     |
| Ethyl methacrylate, stabilized ....          | 3         | UN2277 | II    | 3          | ..... | IB2, T4, TP1                                           | 150   | ..... | 202   | ..... | 242       | ..... | 5 L       | 60 L      | B     | .....       |
| Ethyl methyl ether .....                     | 2.1       | UN1039 | ..... | 2.1        | ..... | .....                                                  | None  | ....  | 201   | ..... | 314, 315. | ..... | Forbidden | 150 kg    | B     | 40          |
| Ethyl methyl ketone or Methyl ethyl ketone.  | 3         | UN1193 | II    | 3          | ..... | IB2, T4, TP1                                           | 150   | ..... | 202   | ..... | 242       | ..... | 5 L       | 60 L      | B     | .....       |
| Ethyl nitrite solutions .....                | 3         | UN1194 | I     | 3, 6.1     | ..... | .....                                                  | None  | ....  | 201   | ..... | None      | ....  | Forbidden | Forbidden | E     | 40, 105     |
| Ethyl orthoformate .....                     | 3         | UN2524 | III   | 3          | ..... | B1, IB3, T2, TP1                                       | 150   | ..... | 203   | ..... | 242       | ..... | 60 L      | 220 L     | A     | .....       |
| Ethyl oxalate .....                          | 6.1       | UN2525 | III   | 6.1        | ..... | IB3, T4, TP1                                           | 153   | ..... | 203   | ..... | 241       | ..... | 60 L      | 220 L     | A     | .....       |
| Ethyl perchlorate .....                      | Forbidden | .....  | ..... | .....      | ..... | .....                                                  | ..... | ..... | ..... | ..... | .....     | ..... | .....     | .....     | ..... | .....       |
| Ethyl phosphonothioic dichloride, anhydrous. | 6.1       | NA2927 | I     | 6.1, 8     | ..... | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None  | ....  | 227   | ..... | 244       | ..... | Forbidden | Forbidden | D     | 40          |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                            | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)                       | (8)                   |           |           | (9)                                             |                       | (10)             |                     |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|--------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|---------------------|
|          |                                                                                                                                                                                        |                            |                            |       |             |                                                        | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                     |
|          |                                                                                                                                                                                        |                            |                            |       |             |                                                        | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other               |
| D        | Ethyl phosphonous dichloride, anhydrous <i>pyrophoric liquid</i> .                                                                                                                     | 6.1                        | NA2845                     | I     | 6.1, 4.2.   | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 18                  |
| D        | Ethyl phosphorodichloridate .....                                                                                                                                                      | 6.1                        | NA2927                     | I     | 6.1, 8      | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 40                  |
|          | Ethyl propionate .....                                                                                                                                                                 | 3                          | UN1195                     | II    | 3 .....     | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....               |
|          | Ethyl propyl ether .....                                                                                                                                                               | 3                          | UN2615                     | II    | 3 .....     | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | E                | .....               |
|          | <i>Ethyl silicate, see Tetraethyl sili- cate.</i>                                                                                                                                      |                            |                            |       |             |                                                        |                       |           |           |                                                 |                       |                  |                     |
|          | Ethylacetylene, stabilized .....                                                                                                                                                       | 2.1                        | UN2452                     | ..... | 2.1 ....    | N88                                                    | None ....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg                | B                | 40                  |
|          | Ethylamine .....                                                                                                                                                                       | 2.1                        | UN1036                     | ..... | 2.1 ....    | B77, N87, T50                                          | None ....             | 321 ..... | 314, 315. | Forbidden                                       | 150 kg                | D                | 40                  |
|          | Ethylamine, aqueous solution with not less than 50 percent but not more than 70 percent ethylamine.                                                                                    | 3                          | UN2270                     | II    | 3, 8 ....   | IB2, T7, TP1                                           | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | 40, 52.             |
|          | N-Ethylaniline .....                                                                                                                                                                   | 6.1                        | UN2272                     | III   | 6.1 ....    | IB3, T4, TP1                                           | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | 52, 74              |
|          | 2-Ethylaniline .....                                                                                                                                                                   | 6.1                        | UN2273                     | III   | 6.1 ....    | IB3, T4, TP1                                           | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | 52, 74              |
|          | Ethylbenzene .....                                                                                                                                                                     | 3                          | UN1175                     | II    | 3 .....     | IB2, T4, TP1                                           | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....               |
|          | N-Ethylbenzyltoluidines liquid ....                                                                                                                                                    | 6.1                        | UN2753                     | III   | 6.1 ....    | IB3, T7, TP1                                           | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | .....               |
|          | 2-Ethylbutanol .....                                                                                                                                                                   | 3                          | UN2275                     | III   | 3 .....     | B1, IB3, T2, TP1                                       | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....               |
|          | 2-Ethylbutyl acetate .....                                                                                                                                                             | 3                          | UN1177                     | III   | 3 .....     | B1, IB3, T2, TP1                                       | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....               |
|          | 2-Ethylbutyraldehyde .....                                                                                                                                                             | 3                          | UN1178                     | II    | 3 .....     | B1, IB2, T4, TP1                                       | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....               |
|          | Ethyldichloroarsine .....                                                                                                                                                              | 6.1                        | UN1892                     | I     | 6.1 ....    | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45       | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 40                  |
|          | Ethyldichlorosilane .....                                                                                                                                                              | 4.3                        | UN1183                     | I     | 4.3, 8, 3.  | A2, A3, A7, N34, T10, TP2, TP7, TP13                   | None ....             | 201 ..... | 244 ..... | Forbidden                                       | 1 L                   | D                | 21, 28, 40, 49, 100 |
|          | Ethylene, acetylene and propylene in mixture, refrigerated liquid with at least 71.5 percent ethylene with not more than 22.5 percent acetylene and not more than 6 percent propylene. | 2.1                        | UN3138                     | ..... | 2.1 ....    | T75, TP5                                               | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40, 57              |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                    |           |        |       |           |                                                       |           |           |           |           |           |   |       |
|--------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|-------------------------------------------------------|-----------|-----------|-----------|-----------|-----------|---|-------|
| Ethylene chlorohydrin .....                                                                                        | 6.1       | UN1135 | I     | 6.1, 3    | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45      | None .... | 227 ..... | 244 ..... | Forbidden | Forbidden | D | 40    |
| Ethylene .....                                                                                                     | 2.1       | UN1962 | ..... | 2.1 ..... |                                                       | 306 ..... | 304 ..... | 302 ..... | Forbidden | 150 kg    | E | 40    |
| Ethylene diamine diperchlorate                                                                                     | Forbidden |        |       |           |                                                       |           |           |           |           |           |   |       |
| Ethylene dibromide .....                                                                                           | 6.1       | UN1605 | I     | 6.1 ..... | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None .... | 227 ..... | 244 ..... | Forbidden | Forbidden | D | 40    |
| Ethylene dibromide and methyl bromide liquid mixtures, see Methyl bromide and ethylene dibromide, liquid mixtures. |           |        |       |           |                                                       |           |           |           |           |           |   |       |
| Ethylene dichloride .....                                                                                          | 3         | UN1184 | II    | 3, 6.1    | IB2, N36, T7, TP1                                     | 150 ..... | 202 ..... | 243 ..... | 1 L       | 60 L      | B | 40    |
| Ethylene glycol diethyl ether .....                                                                                | 3         | UN1153 | II    | 3 .....   | IB2, T4, TP1                                          | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | A | ..... |
| Ethylene glycol dinitrate .....                                                                                    | Forbidden |        | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A | ..... |
| Ethylene glycol monoethyl ether                                                                                    | 3         | UN1171 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A | ..... |
| Ethylene glycol monoethyl ether acetate.                                                                           | 3         | UN1172 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A | ..... |
| Ethylene glycol monomethyl ether.                                                                                  | 3         | UN1188 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A | ..... |
| Ethylene glycol monomethyl ether acetate.                                                                          | 3         | UN1189 | III   | 3 .....   | B1, IB3, T2, TP1                                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A | ..... |
| Ethylene oxide and carbon dioxide mixture with more than 87 percent ethylene oxide.                                | 2.3       | UN3300 | ..... | 2.3, 2.1. | 4                                                     | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D | 40    |
| Ethylene oxide and carbon dioxide mixtures with more than 9 percent but not more than 87 percent ethylene oxide.   | 2.1       | UN1041 | ..... | 2.1 ..... | T50                                                   | 306 ..... | 304 ..... | 314, 315. | Forbidden | 25 kg     | B | 40    |
| Ethylene oxide and carbon dioxide mixtures with not more than 9 percent ethylene oxide.                            | 2.2       | UN1952 | ..... | 2.2 ..... |                                                       | 306 ..... | 304 ..... | 314, 315. | 75 kg     | 150 kg    | A | ..... |
| Ethylene oxide and chlorotetrafluoroethane mixture with not more than 8.8 percent ethylene oxide.                  | 2.2       | UN3297 | ..... | 2.2 ..... | T50                                                   | 306 ..... | 304 ..... | 314, 315. | 75 kg     | 150 kg    | A | ..... |
| Ethylene oxide and dichlorodifluoromethane mixture, with not more than 12.5 percent ethylene oxide.                | 2.2       | UN3070 | ..... | 2.2 ..... | T50                                                   | 306 ..... | 304 ..... | 314, 315. | 75 kg     | 150 kg    | A | ..... |
| Ethylene oxide and pentafluoroethane mixture with not more than 7.9 percent ethylene oxide.                        | 2.2       | UN3298 | ..... | 2.2 ..... | T50                                                   | 306 ..... | 304 ..... | 314, 315. | 75 kg     | 150 kg    | A | ..... |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                             | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)                                | (8)                   |           |           | (9)                                             |                       | (10)             |                         |
|----------|---------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|-----------------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------------------------|
|          |                                                                                                         |                            |                            |       |             |                                                                 | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                         |
|          |                                                                                                         |                            |                            |       |             |                                                                 | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                   |
|          | Ethylene oxide and propylene oxide mixtures, with not more than 30 percent ethylene oxide.              | 3                          | UN2983                     | I     | 3, 6.1      | 5, A11, N4, N34, T14, TP2, TP7, TP13                            | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 30 L                  | E                | 40                      |
|          | Ethylene oxide and tetrafluoroethane mixture with not more than 5.6 percent ethylene oxide.             | 2.2                        | UN3299                     | ..... | 2.2 ....    | T50                                                             | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | A                | .....                   |
|          | Ethylene oxide or Ethylene oxide with nitrogen up to a total pressure of 1MPa (10 bar) at 50 degrees C. | 2.3                        | UN1040                     | ..... | 2.3, 2.1.   | 4, A59, T50, TP20                                               | None ....             | 323 ..... | 323 ..... | Forbidden                                       | Forbidden             | D                | 40                      |
|          | Ethylene, refrigerated liquid (cryogenic liquid).                                                       | 2.1                        | UN1038                     | ..... | 2.1 ....    | T75, TP5                                                        | None ....             | 316 ..... | 318, 319. | Forbidden                                       | Forbidden             | D                | 40                      |
|          | Ethylenediamine .....                                                                                   | 8                          | UN1604                     | II    | 8, 3 ....   | IB2, T7, TP2                                                    | 154 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                  | A                | 40, 52.                 |
|          | Ethyleneimine, stabilized .....                                                                         | 6.1                        | UN1185                     | I     | 6.1, 3      | 1, B9, B14, B30, B72, B77, N25, N32, T22, TP2, TP13, TP38, TP44 | None ....             | 226 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 40                      |
|          | <i>Ethylhexaldehyde, see Octyl aldehydes etc.</i>                                                       | .....                      | .....                      | ..... | .....       | .....                                                           | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....                   |
|          | 2-Ethylhexyl chloroformate .....                                                                        | 6.1                        | UN2748                     | II    | 6.1, 8      | IB2, T7, TP2, TP13                                              | 153 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                  | A                | 12, 13, 21, 25, 40, 100 |
|          | 2-Ethylhexylamine .....                                                                                 | 3                          | UN2276                     | III   | 3, 8 ....   | B1, IB3, T4, TP1                                                | 150 .....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                  | A                | 40                      |
|          | Ethylphenyldichlorosilane .....                                                                         | 8                          | UN2435                     | II    | 8 .....     | A7, B2, IB2, N34, T7, TP2, TP13                                 | None ....             | 202 ..... | 242 ..... | Forbidden                                       | 30 L                  | C                | .....                   |
|          | 1-Ethylpiperidine .....                                                                                 | 3                          | UN2386                     | II    | 3, 8 ....   | IB2, T7, TP1                                                    | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | 52.                     |
|          | N-Ethyltoluidines .....                                                                                 | 6.1                        | UN2754                     | II    | 6.1 ....    | IB2, T7, TP2                                                    | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | .....                   |
|          | Ethyltrichlorosilane .....                                                                              | 3                          | UN1196                     | II    | 3, 8 ....   | A7, IB1, N34, T7, TP2, TP13                                     | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | 40.                     |
|          | <i>Etiologic agent, see Infectious substances, etc.</i>                                                 | .....                      | .....                      | ..... | .....       | .....                                                           | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....                   |
|          | <i>Explosive articles, see Articles, explosive, n.o.s. etc.</i>                                         | .....                      | .....                      | ..... | .....       | .....                                                           | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....                   |
|          | Explosive, blasting, type A .....                                                                       | 1.1D                       | UN0081                     | II    | 1.1D ..     | .....                                                           | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | 19E, 21E                |
|          | Explosive, blasting, type B .....                                                                       | 1.1D                       | UN0082                     | II    | 1.1D ..     | .....                                                           | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | 19E                     |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                       |           |        |     |           |                                      |           |           |           |           |           |    |                         |
|---------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-----|-----------|--------------------------------------|-----------|-----------|-----------|-----------|-----------|----|-------------------------|
| Explosive, blasting, type B or Agent blasting, Type B.                                                                                | 1.5D      | UN0331 | II  | 1.5D ..   | 105,106                              | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | 19E                     |
| Explosive, blasting, type C .....                                                                                                     | 1.1D      | UN0083 | II  | 1.1D ..   | 123                                  | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | 22E                     |
| Explosive, blasting, type D .....                                                                                                     | 1.1D      | UN0084 | II  | 1.1D ..   |                                      | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | .....                   |
| Explosive, blasting, type E .....                                                                                                     | 1.1D      | UN0241 | II  | 1.1D ..   | .....                                | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | 19E                     |
| Explosive, blasting, type E or Agent blasting, Type E.                                                                                | 1.5D      | UN0332 | II  | 1.5D ..   | 105, 106                             | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | 19E                     |
| <i>Explosive, forbidden. See § 173.54.</i>                                                                                            | Forbidden |        |     | .....     |                                      | .....     | .....     | .....     | .....     | .....     |    | .....                   |
| <i>Explosive substances, see Substances, explosive, n.o.s. etc.</i>                                                                   | .....     |        |     | .....     |                                      | .....     | .....     | .....     | .....     | .....     |    | .....                   |
| <i>Explosives, slurry, see Explosive, blasting, type E.</i>                                                                           | .....     |        |     | .....     |                                      | .....     | .....     | .....     | .....     | .....     |    | .....                   |
| <i>Explosives, water gels, see Explosive, blasting, type E.</i>                                                                       | .....     |        |     | .....     |                                      | .....     | .....     | .....     | .....     | .....     |    | .....                   |
| Extracts, aromatic, liquid .....                                                                                                      | 3         | UN1169 | II  | 3 .....   | 149, IB2, T4, TP1, TP8               | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B  | .....                   |
| .....                                                                                                                                 | .....     |        | III | 3 .....   | B1, IB3, T2, TP1                     | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....                   |
| Extracts, flavoring, liquid .....                                                                                                     | 3         | UN1197 | II  | 3 .....   | 149, IB2, T4, TP1, TP8               | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B  | .....                   |
| .....                                                                                                                                 | .....     |        | III | 3 .....   | B1, IB3, T2, TP1                     | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....                   |
| <i>Fabric with animal or vegetable oil, see Fibers or fabrics, etc.</i>                                                               | .....     |        |     | .....     |                                      | .....     | .....     | .....     | .....     | .....     |    | .....                   |
| Ferric arsenate .....                                                                                                                 | 6.1       | UN1606 | II  | 6.1 ..... | IB8, IP2, IP4, T3, TP33              | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A  | .....                   |
| Ferric arsenite .....                                                                                                                 | 6.1       | UN1607 | II  | 6.1 ..... | IB8, IP2, IP4, T3, TP33              | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A  | .....                   |
| Ferric chloride, anhydrous .....                                                                                                      | 8         | UN1773 | III | 8 .....   | IB8, IP3, T1, TP33                   | 154 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A  | .....                   |
| Ferric chloride, solution .....                                                                                                       | 8         | UN2582 | III | 8 .....   | B15, IB3, T4, TP1                    | 154 ..... | 203 ..... | 241 ..... | 5 L       | 60 L      | A  | .....                   |
| Ferric nitrate .....                                                                                                                  | 5.1       | UN1466 | III | 5.1 ..... | A1, A29, IB8, IP3, T1, TP33          | 152 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A  | .....                   |
| Ferrocerium .....                                                                                                                     | 4.1       | UN1323 | II  | 4.1 ..... | 59, A19, IB8, IP2, IP4, T3, TP33     | 151 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | A  | .....                   |
| Ferrosilicon with 30 percent or more but less than 90 percent silicon.                                                                | 4.3       | UN1408 | III | 4.3, 6.1. | A1, A19, B6, IB8, IP4, IP7, T1, TP33 | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A  | 13, 40, 52, 53, 85, 103 |
| Ferrous arsenate .....                                                                                                                | 6.1       | UN1608 | II  | 6.1 ..... | IB8, IP2, IP4, T3, TP33              | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A  | .....                   |
| D Ferrous chloride, solid .....                                                                                                       | 8         | NA1759 | II  | 8 .....   | IB8, IP2, IP4, T3, TP33              | 154 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | A  | .....                   |
| D Ferrous chloride, solution .....                                                                                                    | 8         | NA1760 | II  | 8 .....   | B3, IB2, T11, TP2, TP27              | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | B  | 40                      |
| Ferrous metal borings or Ferrous metal shavings or Ferrous metal turnings or Ferrous metal cuttings in a form liable to self-heating. | 4.2       | UN2793 | III | 4.2 ..... | A1, A19, IB8, IP3, IP7               | None .... | 213 ..... | 241 ..... | 25 kg     | 100 kg    | A  | .....                   |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols              | Hazardous materials descrip-tions and proper shipping names                                        | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)      | (8)                   |           |           | (9)                                             |                       | (10)             |              |
|-----------------------|----------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|---------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------------|
|                       |                                                                                                    |                            |                            |       |             |                                       | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |              |
|                       |                                                                                                    |                            |                            |       |             |                                       | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other        |
| A I<br>W<br>IW<br>A W | Fertilizer ammoniating solution with free ammonia.                                                 | 2.2                        | UN1043                     | ..... | 2.2 ....    | N87                                   | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg                | E                | 40           |
|                       | Fibers, animal or Fibers, vegetable burnt, wet or damp.                                            | 4.2                        | UN1372                     | III   | 4.2 ....    | .....                                 | 151 .....             | 213 ..... | 240 ..... | Forbidden                                       | Forbidden             | A                | .....        |
|                       | Fibers, vegetable, dry .....                                                                       | 4.1                        | UN3360                     | III   | 4.1 ....    | 137                                   | 151 .....             | 213 ..... | 240 ..... | No Limit                                        | No Limit              | A                | .....        |
|                       | Fibers or Fabrics, animal or vegetable or Synthetic, n.o.s. with animal or vegetable oil.          | 4.2                        | UN1373                     | III   | 4.2 ....    | 137, IB8, IP3, T1, TP33               | None ....             | 213 ..... | 241 ..... | Forbidden                                       | Forbidden             | A                | .....        |
|                       | Fibers or Fabrics impregnated with weakly nitrated nitrocellulose, n.o.s..                         | 4.1                        | UN1353                     | III   | 4.1 ....    | A1, IB8, IP3                          | None ....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | D                | .....        |
| W                     | Films, nitrocellulose base, from which gelatine has been removed; film scrap, see Celluloid scrap. | .....                      | .....                      | ..... | .....       | .....                                 | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |
|                       | Films, nitrocellulose base, gelatine coated (except scrap).                                        | 4.1                        | UN1324                     | III   | 4.1 ....    | .....                                 | None ....             | 183 ..... | None .... | 25 kg                                           | 100 kg                | D                | 28           |
|                       | Fire extinguisher charges, corrosive liquid.                                                       | 8                          | UN1774                     | II    | 8 .....     | N41                                   | 154 .....             | 202 ..... | None .... | 1 L                                             | 30 L                  | A                | .....        |
|                       | Fire extinguisher charges, expelling, explosive, see Cartridges, power device.                     | .....                      | .....                      | ..... | .....       | .....                                 | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |
|                       | Fire extinguishers containing compressed or liquefied gas.                                         | 2.2                        | UN1044                     | ..... | 2.2 ....    | 18, 110                               | 309 .....             | 309 ..... | None .... | 75 kg                                           | 150 kg                | A                | .....        |
|                       | Firelighters, solid with flammable liquid.                                                         | 4.1                        | UN2623                     | III   | 4.1 ....    | A1, A19                               | None ....             | 213 ..... | None .... | 25 kg                                           | 100 kg                | A                | 52           |
|                       | Fireworks .....                                                                                    | 1.1G                       | UN0333                     | II    | 1.1G ..     | 108                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....        |
|                       | Fireworks .....                                                                                    | 1.2G                       | UN0334                     | II    | 1.2G ..     | 108                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....        |
|                       | Fireworks .....                                                                                    | 1.3G                       | UN0335                     | II    | 1.3G ..     | 108                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....        |
|                       | Fireworks .....                                                                                    | 1.4G                       | UN0336                     | II    | 1.4G ..     | 108                                   | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....        |
| W                     | Fireworks .....                                                                                    | 1.4S                       | UN0337                     | II    | 1.4S ...    | 108                                   | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               | .....        |
|                       | First aid kits .....                                                                               | 9                          | UN3316                     | ..... | 9 .....     | 15                                    | 161 .....             | 161 ..... | None .... | 10 kg                                           | 10 kg                 | A                | .....        |
|                       | Fish meal, stabilized or Fish scrap, stabilized.                                                   | 9                          | UN2216                     | III   | None        | 155, IB8, IP3, T1, TP33               | 155 .....             | 218 ..... | 218 ..... | No limit                                        | No limit              | B                | 88, 122, 128 |
|                       | Fish meal, unstablized or Fish scrap, unstablized.                                                 | 4.2                        | UN1374                     | II    | 4.2 ....    | 155, A1, A19, IB8, IP2, IP4, T3, TP33 | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                 | B                | 18, 128      |
|                       | Flammable compressed gas, see Compressed or Liquefied gas, flammable, etc.                         | .....                      | .....                      | ..... | .....       | .....                                 | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |
|                       | .....                                                                                              | .....                      | .....                      | ..... | .....       | .....                                 | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |
|                       | .....                                                                                              | .....                      | .....                      | ..... | .....       | .....                                 | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....        |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                                                     |     |        |     |               |                                |           |           |           |           |           |   |                |  |
|---|-------------------------------------------------------------------------------------------------------------------------------------|-----|--------|-----|---------------|--------------------------------|-----------|-----------|-----------|-----------|-----------|---|----------------|--|
|   | Flammable compressed gas<br>(small receptacles not fitted<br>with a dispersion device, not<br>refillable), see Receptacles,<br>etc. |     |        |     |               |                                |           |           |           |           |           |   |                |  |
|   | Flammable gas in lighters, see<br>Lighters or lighter refills, ciga-<br>rettes, containing flammable<br>gas.                        |     |        |     |               |                                |           |           |           |           |           |   |                |  |
| G | Flammable liquid, toxic, corro-<br>sive, n.o.s..                                                                                    | 3   | UN3286 | I   | 3, 6.1,<br>8. | T14, TP2, TP13,<br>TP27        | None .... | 201 ..... | 243 ..... | Forbidden | 2.5 L     | E | 21, 40,<br>100 |  |
|   |                                                                                                                                     |     |        | II  | 3, 6.1,<br>8. | IB2, T11, TP2,<br>TP13, TP27   | 150 ..... | 202 ..... | 243 ..... | 1 L       | 5 L       | B | 21, 40,<br>100 |  |
| G | Flammable liquids, corrosive,<br>n.o.s..                                                                                            | 3   | UN2924 | I   | 3, 8 ....     | T14, TP2                       | None .... | 201 ..... | 243 ..... | 0.5 L     | 2.5 L     | E | 40             |  |
|   |                                                                                                                                     |     |        | II  | 3, 8 ....     | IB2, T11, TP2,<br>TP27         | 150 ..... | 202 ..... | 243 ..... | 1 L       | 5 L       | B | 40             |  |
|   |                                                                                                                                     |     |        | III | 3, 8 ....     | B1, IB3, T7, TP1,<br>TP28      | 150 ..... | 203 ..... | 242 ..... | 5 L       | 60 L      | A | 40             |  |
| G | Flammable liquids, n.o.s. ....                                                                                                      | 3   | UN1993 | I   | 3 .....       | T11, TP1, TP27                 | 150 ..... | 201 ..... | 243 ..... | 1 L       | 30 L      | E | .....          |  |
|   |                                                                                                                                     |     |        | II  | 3 .....       | IB2, T7, TP1,<br>TP8, TP28     | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B | .....          |  |
|   |                                                                                                                                     |     |        | III | 3 .....       | B1, B52, IB3, T4,<br>TP1, TP29 | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A | .....          |  |
| G | Flammable liquids, toxic, n.o.s.                                                                                                    | 3   | UN1992 | I   | 3, 6.1        | T14, TP2, TP13,<br>TP27        | None .... | 201 ..... | 243 ..... | Forbidden | 30 L      | E | 40             |  |
|   |                                                                                                                                     |     |        | II  | 3, 6.1        | IB2, T7, TP2,<br>TP13          | 150 ..... | 202 ..... | 243 ..... | 1 L       | 60 L      | B | 40             |  |
|   |                                                                                                                                     |     |        | III | 3, 6.1        | B1, IB3, T7, TP1,<br>TP28      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A | .....          |  |
| G | Flammable solid, corrosive, inor-<br>ganic, n.o.s..                                                                                 | 4.1 | UN3180 | II  | 4.1, 8        | A1, IB6, IP2, T3,<br>TP33      | 151 ..... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | D | 40             |  |
|   |                                                                                                                                     |     |        | III | 4.1, 8        | A1, IB6, T1,<br>TP33           | 151 ..... | 213 ..... | 242 ..... | 25 kg     | 100 kg    | D | 40             |  |
| G | Flammable solid, inorganic,<br>n.o.s..                                                                                              | 4.1 | UN3178 | II  | 4.1 ....      | A1, IB8, IP2, IP4,<br>T3, TP33 | 151 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | B | .....          |  |
|   |                                                                                                                                     |     |        | III | 4.1 ....      | A1, IB8, IP3, T1,<br>TP33      | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | B | .....          |  |
| G | Flammable solid, organic, mol-<br>ten, n.o.s..                                                                                      | 4.1 | UN3176 | II  | 4.1 ....      | IB1, T3, TP3,<br>TP26          | 151 ..... | 212 ..... | 240 ..... | Forbidden | Forbidden | C | .....          |  |
|   |                                                                                                                                     |     |        | III | 4.1 ....      | IB1, T1, TP3,<br>TP26          | 151 ..... | 213 ..... | 240 ..... | Forbidden | Forbidden | C | .....          |  |
| G | Flammable solid, oxidizing,<br>n.o.s..                                                                                              | 4.1 | UN3097 | II  | 4.1,<br>5.1.  | 131                            | None .... | 214 ..... | 214 ..... | Forbidden | Forbidden | E | 40             |  |
|   |                                                                                                                                     |     |        | III | 4.1,<br>5.1.  | 131, T1, TP33                  | None .... | 214 ..... | 214 ..... | Forbidden | Forbidden | D | 40             |  |
| G | Flammable solid, toxic, inor-<br>ganic, n.o.s..                                                                                     | 4.1 | UN3179 | II  | 4.1,<br>6.1.  | A1, IB6, IP2, T3,<br>TP33      | 151 ..... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | B | 40             |  |
|   |                                                                                                                                     |     |        | III | 4.1,<br>6.1.  | A1, IB6, T1,<br>TP33           | 151 ..... | 213 ..... | 242 ..... | 25 kg     | 100 kg    | B | 40             |  |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names             | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes  | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |            |
|----------|-------------------------------------------------------------------------|----------------------------|----------------------------|-------|--------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|------------|
|          |                                                                         |                            |                            |       |              |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |            |
|          |                                                                         |                            |                            |       |              |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other      |
| G        | Flammable solids, corrosive, or- ganic, n.o.s..                         | 4.1                        | UN2925                     | II    | 4.1, 8       | A1, IB6, IP2, T3, TP33           | None ....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                 | D                | 40         |
|          | .....                                                                   | .....                      | .....                      | III   | 4.1, 8       | A1, IB6, T1, TP33                | 151 .....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg                | D                | 40         |
| G        | Flammable solids, organic, n.o.s..                                      | 4.1                        | UN1325                     | II    | 4.1 .....    | A1, IB8, IP2, IP4, T3, TP33      | 151 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                 | B                | .....      |
|          | .....                                                                   | .....                      | .....                      | III   | 4.1 .....    | A1, IB8, IP3, T1, TP33           | 151 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | B                | .....      |
| G        | Flammable solids, toxic, organic, n.o.s..                               | 4.1                        | UN2926                     | II    | 4.1, 6.1.    | A1, IB6, IP2, T3, TP33           | 151 .....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                 | B                | 40         |
|          | .....                                                                   | .....                      | .....                      | III   | 4.1, 6.1.    | A1, IB6, T1, TP33                | 151 .....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg                | B                | 40         |
|          | Flares, aerial .....                                                    | 1.3G                       | UN0093                     | II    | 1.3G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 07               | .....      |
|          | Flares, aerial .....                                                    | 1.4G                       | UN0403                     | II    | 1.4G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....      |
|          | Flares, aerial .....                                                    | 1.4S                       | UN0404                     | II    | 1.4S ..      |                                  | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               | .....      |
|          | Flares, aerial .....                                                    | 1.1G                       | UN0420                     | II    | 1.1G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....      |
|          | Flares, aerial .....                                                    | 1.2G                       | UN0421                     | II    | 1.2G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....      |
|          | <i>Flares, airplane, see</i> Flares, aer- ial.                          | .....                      | .....                      | ..... | .....        |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | <i>Flares, signal, see</i> Cartridges, signal.                          | .....                      | .....                      | ..... | .....        |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | Flares, surface .....                                                   | 1.3G                       | UN0092                     | II    | 1.3G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 07               | .....      |
|          | Flares, surface .....                                                   | 1.1G                       | UN0418                     | II    | 1.1G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....      |
|          | Flares, surface .....                                                   | 1.2G                       | UN0419                     | II    | 1.2G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....      |
|          | <i>Flares, water-activated, see</i> Contrivances, water-activated, etc. | .....                      | .....                      | ..... | .....        |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | Flash powder .....                                                      | 1.1G                       | UN0094                     | II    | 1.1G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 15               | .....      |
|          | Flash powder .....                                                      | 1.3G                       | UN0305                     | II    | 1.3G ..      |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 15               | .....      |
|          | <i>Flue dusts, poisonous, see</i> Ar- senical dust.                     | .....                      | .....                      | ..... | .....        |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | <i>Fluoric acid, see</i> Hydrofluoric acid, etc.                        | .....                      | .....                      | ..... | .....        |                                  | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | Fluorine, compressed .....                                              | 2.3                        | UN1045                     | ..... | 2.3, 5.1, 8. | 1, N86                           | None ....             | 302 ..... | None .... | Forbidden                                       | Forbidden             | D                | 40, 89, 90 |
|          | Fluoroacetic acid .....                                                 | 6.1                        | UN2642                     | I     | 6.1 .....    | IB7, IP1, T6, TP33               | None ....             | 211 ..... | 242 ..... | 1 kg                                            | 15 kg                 | E                | .....      |
|          | Fluoroanilines .....                                                    | 6.1                        | UN2941                     | III   | 6.1 .....    | IB3, T4, TP1                     | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | .....      |
|          | Fluorobenzene .....                                                     | 3                          | UN2387                     | II    | 3 .....      | IB2, T4, TP1                     | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                              |           |        |     |      |       |                                                            |      |       |     |       |      |       |           |           |    |       |
|------------------------------------------------------------------------------|-----------|--------|-----|------|-------|------------------------------------------------------------|------|-------|-----|-------|------|-------|-----------|-----------|----|-------|
| Fluoroboric acid .....                                                       | 8         | UN1775 | II  | 8    | ..... | A6, A7, B2, B15,<br>IB2, N3, N34,<br>T7, TP2               | 154  | ..... | 202 | ..... | 242  | ..... | 1 L       | 30 L      | A  | ..... |
| Fluorophosphoric acid anhy-<br>drous.                                        | 8         | UN1776 | II  | 8    | ..... | A6, A7, B2, IB2,<br>N3, N34, T8,<br>TP2, TP12              | None | ....  | 202 | ..... | 242  | ..... | 1 L       | 30 L      | A  | ..... |
| Fluorosilicates, n.o.s. ....                                                 | 6.1       | UN2856 | III | 6.1  | ....  | IB8, IP3, T1,<br>TP33                                      | 153  | ..... | 213 | ..... | 240  | ..... | 100 kg    | 200 kg    | A  | 52    |
| Fluorosilicic acid .....                                                     | 8         | UN1778 | II  | 8    | ..... | A6, A7, B2, B15,<br>IB2, N3, N34,<br>T8, TP2, TP12         | None | ....  | 202 | ..... | 242  | ..... | 1 L       | 30 L      | A  | ..... |
| Fluorosulfonic acid .....                                                    | 8         | UN1777 | I   | 8    | ..... | A3, A6, A7, A10,<br>B6, B10, N3,<br>N36, T10, TP2,<br>TP12 | None | ....  | 201 | ..... | 243  | ..... | 0.5 L     | 2.5 L     | D  | 40    |
| Fluorotoluenes .....                                                         | 3         | UN2388 | II  | 3    | ..... | IB2, T4, TP1                                               | 150  | ..... | 202 | ..... | 242  | ..... | 5 L       | 60 L      | B  | 40    |
| <i>Forbidden materials. See<br/>§ 173.21.</i>                                | Forbidden |        |     |      |       |                                                            |      |       |     |       |      |       |           |           |    |       |
| Formaldehyde, solutions, flam-<br>mable.                                     | 3         | UN1198 | III | 3, 8 | ....  | B1, IB3, T4, TP1                                           | 150  | ..... | 203 | ..... | 242  | ..... | 5 L       | 60 L      | A  | 40    |
| Formaldehyde, solutions, with<br>not less than 25 percent form-<br>aldehyde. | 8         | UN2209 | III | 8    | ..... | IB3, T4, TP1                                               | 154  | ..... | 203 | ..... | 241  | ..... | 5 L       | 60 L      | A  | ..... |
| <i>Formalin, see Formaldehyde,<br/>solutions.</i>                            |           |        |     |      |       |                                                            |      |       |     |       |      |       |           |           |    |       |
| Formic acid with not less than<br>10% but not more than 85%<br>acid by mass. | 8         | UN3412 | II  | 8    | ..... | IB2, T7, TP2                                               | 154  | ..... | 202 | ..... | 242  | ..... | 1 L       | 30 L      | A  | 40.   |
| Formic acid with not less than<br>5% but less than 10% acid by<br>mass.      | 8         | UN3412 | III | 8    | ..... | IB3, T4, TP1                                               | 154  | ..... | 203 | ..... | 241  | ..... | 5 L       | 60 L      | A  | 40    |
| Formic acid with more than 85%<br>acid by mass.                              | 8         | UN1779 | II  | 8, 3 | ....  | B2, B28, IB2, T7,<br>TP2                                   | 154  | ..... | 202 | ..... | 242  | ..... | 1 L       | 30 L      | A  | 40.   |
| Fracturing devices, explosive,<br>without detonators for oil wells.          | 1.1D      | UN0099 | II  | 1.1D | ..    |                                                            | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 07 | ..... |
| Fuel, aviation, turbine engine ....                                          | 3         | UN1863 | I   | 3    | ..... | 144, T11, TP1,<br>TP8, TP28                                | 150  | ..... | 201 | ..... | 243  | ..... | 1 L       | 30 L      | E  | ..... |
| .....                                                                        |           |        | II  | 3    | ..... | 144, IB2, T4,<br>TP1, TP8                                  | 150  | ..... | 202 | ..... | 242  | ..... | 5 L       | 60 L      | B  | ..... |
| .....                                                                        |           |        | III | 3    | ..... | 144, B1, IB3, T2,<br>TP1                                   | 150  | ..... | 203 | ..... | 242  | ..... | 60 L      | 220 L     | A  | ..... |
| Fuel cell cartridges containing<br>flammable liquids.                        | 3         | UN3473 | II  | 3    | ..... | .....                                                      | 150  | ..... | 230 | ..... | None | ....  | 5 L       | 60 L      | A  |       |
| D Fuel oil (No. 1, 2, 4, 5, or 6) .....                                      | 3         | NA1993 | III | 3    | ..... | 144, B1, IB3, T4,<br>TP1, TP29                             | 150  | ..... | 203 | ..... | 242  | ..... | 60 L      | 220 L     | A  | ..... |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                   | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |       | (9)                                             |                       | (10)             |        |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                                                                                                               |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |       | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                                                                                                               |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk  | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
|          | <i>Fuel system components (in- cluding fuel control units (FCU), carburetors, fuel lines, fuel pumps) see Dangerous Goods in Apparatus or Dan- gerous Goods in Machinery.</i> | .....                      |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fulminate of mercury (dry) .....</i>                                                                                                                                       | Forbidden                  |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fulminate of mercury, wet, see Mercury fulminate, etc.</i>                                                                                                                 | .....                      |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fulminating gold .....</i>                                                                                                                                                 | Forbidden                  |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fulminating mercury .....</i>                                                                                                                                              | Forbidden                  |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fulminating platinum .....</i>                                                                                                                                             | Forbidden                  |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fulminating silver .....</i>                                                                                                                                               | Forbidden                  |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fulminic acid .....</i>                                                                                                                                                    | Forbidden                  |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fumaryl chloride .....</i>                                                                                                                                                 | 8                          | UN1780                     | II  | 8           | B2, IB2, T7, TP2                 | 154                   | 202       | 242   | 1 L                                             | 30 L                  | C                | 8, 40  |
|          | <i>Fumigated lading, see §§ 172.302(g), 173.9 and 176.76(h).</i>                                                                                                              | .....                      |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fumigated transport vehicle or freight container see § 173.9.</i>                                                                                                          | .....                      |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Furaldehydes .....</i>                                                                                                                                                     | 6.1                        | UN1199                     | II  | 6.1, 3      | IB2, T7, TP2                     | 153                   | 202       | 243   | 5 L                                             | 60 L                  | A                | .....  |
|          | <i>Furan .....</i>                                                                                                                                                            | 3                          | UN2389                     | I   | 3           | T12, TP2, TP13                   | None                  | 201       | 243   | 1 L                                             | 30 L                  | E                | 40     |
|          | <i>Furfuryl alcohol .....</i>                                                                                                                                                 | 6.1                        | UN2874                     | III | 6.1         | IB3, T4, TP1                     | 153                   | 203       | 241   | 60 L                                            | 220 L                 | A                | 52, 74 |
|          | <i>Furfurylamine .....</i>                                                                                                                                                    | 3                          | UN2526                     | III | 3, 8        | B1, IB3, T4, TP1                 | 150                   | 203       | 242   | 5 L                                             | 60 L                  | A                | 40     |
|          | <i>Fuse, detonating, metal clad, see Cord, detonating, metal clad.</i>                                                                                                        | .....                      |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fuse, detonating, mild effect, metal clad, see Cord, deto- nating, mild effect, metal clad.</i>                                                                            | .....                      |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |
|          | <i>Fuse, igniter tubular metal clad</i>                                                                                                                                       | 1.4G                       | UN0103                     | II  | 1.4G        |                                  | None                  | 62        | None  | Forbidden                                       | 75 kg                 | 06               | .....  |
|          | <i>Fuse, non-detonating instanta- neous or quickmatch.</i>                                                                                                                    | 1.3G                       | UN0101                     | II  | 1.3G        |                                  | None                  | 62        | None  | Forbidden                                       | Forbidden             | 07               | .....  |
|          | <i>Fuse, safety .....</i>                                                                                                                                                     | 1.4S                       | UN0105                     | II  | 1.4S        |                                  | None                  | 62        | None  | 25 kg                                           | 100 kg                | 05               | .....  |
| D        | <i>Fusee (railway or highway) .....</i>                                                                                                                                       | 4.1                        | NA1325                     | II  | 4.1         |                                  | None                  | 184       | None  | 15 kg                                           | 50 kg                 | B                | .....  |
|          | <i>Fusel oil .....</i>                                                                                                                                                        | 3                          | UN1201                     | II  | 3           | IB2, T4, TP1                     | 150                   | 202       | 242   | 5 L                                             | 60 L                  | B                | .....  |
|          | .....                                                                                                                                                                         | .....                      |                            | III | 3           | B1, IB3, T2, TP1                 | 150                   | 203       | 242   | 60 L                                            | 220 L                 | A                | .....  |
|          | <i>Fuses, tracer, see Tracers for ammunition.</i>                                                                                                                             | .....                      |                            |     |             |                                  | .....                 | .....     | ..... | .....                                           | .....                 |                  | .....  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                    |           |        |     |           |                       |      |           |      |           |           |    |    |
|--------------------------------------------------------------------------------------------------------------------|-----------|--------|-----|-----------|-----------------------|------|-----------|------|-----------|-----------|----|----|
| Fuzes, combination, percussion and time, see Fuzes, detonating (UN0257, UN0367); Fuzes, igniting (UN0317, UN0368). |           |        |     |           |                       |      |           |      |           |           |    |    |
| Fuzes, detonating                                                                                                  | 1.1B      | UN0106 | II  | 1.1B ..   |                       | None | 62        | None | Forbidden | Forbidden | 11 |    |
| Fuzes, detonating                                                                                                  | 1.2B      | UN0107 |     | 1.2B ..   |                       | None | 62        | None | Forbidden | Forbidden | 11 |    |
| Fuzes, detonating                                                                                                  | 1.4B      | UN0257 | II  | 1.4B ..   | 116                   | None | 62        | None | Forbidden | 75 kg     | 06 |    |
| Fuzes, detonating                                                                                                  | 1.4S      | UN0367 |     | 1.4S ..   | 116                   | None | 62        | None | 25 kg     | 100 kg    | 05 |    |
| Fuzes, detonating, with protective features.                                                                       | 1.1D      | UN0408 | II  | 1.1D ..   |                       | None | 62        | None | Forbidden | Forbidden | 07 |    |
| Fuzes, detonating, with protective features.                                                                       | 1.2D      | UN0409 | II  | 1.2D ..   |                       | None | 62        | None | Forbidden | Forbidden | 07 |    |
| Fuzes, detonating, with protective features.                                                                       | 1.4D      | UN0410 | II  | 1.4D ..   | 116                   | None | 62        | None | Forbidden | 75 kg     | 06 |    |
| Fuzes, igniting                                                                                                    | 1.3G      | UN0316 | II  | 1.3G ..   |                       | None | 62        | None | Forbidden | Forbidden | 07 |    |
| Fuzes, igniting                                                                                                    | 1.4G      | UN0317 | II  | 1.4G ..   |                       | None | 62        | None | Forbidden | 75 kg     | 06 |    |
| Fuzes, igniting                                                                                                    | 1.4S      | UN0368 | II  | 1.4S ..   |                       | None | 62        | None | 25 kg     | 100 kg    | 05 |    |
| Galactsan trinitrate                                                                                               | Forbidden |        |     |           |                       |      |           |      |           |           |    |    |
| Gallium                                                                                                            | 8         | UN2803 | III | 8 .....   | T1, TP33              | None | 162       | 240  | 20 kg     | 20 kg     | B  | 48 |
| Gas cartridges, (flammable) without a release device, non-refillable.                                              | 2.1       | UN2037 |     | 2.1 ..... |                       | 306  | 304       | None | 1 kg      | 15 kg     | B  | 40 |
| D Gas identification set                                                                                           | 2.3       | NA9035 |     | 2.3 ..... | 6                     | None | 194       | None | Forbidden | Forbidden | D  |    |
| Gas oil                                                                                                            | 3         | UN1202 | III | 3 .....   | 144, B1, IB3, T2, TP1 | 150  | 203       | 242  | 60 L      | 220 L     | A  |    |
| G Gas, refrigerated liquid, flammable, n.o.s. (cryogenic liquid).                                                  | 2.1       | UN3312 |     | 2.1 ..... | T75, TP5              | None | 316       | 318  | Forbidden | Forbidden | D  | 40 |
| G Gas, refrigerated liquid, n.o.s. (cryogenic liquid).                                                             | 2.2       | UN3158 |     | 2.2 ..... | T75, TP5              | 320  | 316       | 318  | 50 kg     | 500 kg    | D  |    |
| G Gas, refrigerated liquid, oxidizing, n.o.s. (cryogenic liquid).                                                  | 2.2       | UN3311 |     | 2.2, 5.1. | T75, TP5, TP22        | 320  | 316       | 318  | Forbidden | Forbidden | D  |    |
| Gas sample, non-pressurized, flammable, n.o.s., not refrigerated liquid.                                           | 2.1       | UN3167 |     | 2.1 ..... |                       | 306  | 302, 304. | None | 1 L       | 5 L       | D  |    |
| Gas sample, non-pressurized, toxic, flammable, n.o.s., not refrigerated liquid.                                    | 2.3       | UN3168 |     | 2.3, 2.1. | 6                     | 306  | 302       | None | Forbidden | 1 L       | D  |    |
| Gas sample, non-pressurized, toxic, n.o.s., not refrigerated liquid.                                               | 2.3       | UN3169 |     | 2.3 ..... | 6                     | 306  | 302, 304. | None | Forbidden | 1 L       | D  |    |
| D Gasohol gasoline mixed with ethyl alcohol, with not more than 10% alcohol.                                       | 3         | NA1203 | II  | 3 .....   | 144                   | 150  | 202       | 242  | 5 L       | 60 L      | E  |    |
| Gasoline includes gasoline mixed with ethyl alcohol, with not more than 10% alcohol.                               | 3         | UN1203 | II  | 3 .....   | 144, B1, B33, T8      | 150  | 202       | 242  | 5 L       | 60 L      | E  |    |
| Gasoline, casinghead, see Gasoline.                                                                                |           |        |     |           |                       |      |           |      |           |           |    |    |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                                    | Hazard class or Division | Identification Numbers | PG    | Label Codes | Special provisions (§ 172.102) | (8)                   |          |       | (9)                                             |                     | (10)           |       |
|----------|-----------------------------------------------------------------------------------------------|--------------------------|------------------------|-------|-------------|--------------------------------|-----------------------|----------|-------|-------------------------------------------------|---------------------|----------------|-------|
|          |                                                                                               |                          |                        |       |             |                                | Packaging (§ 173.***) |          |       | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |       |
|          |                                                                                               |                          |                        |       |             |                                | Excep-tions           | Non-bulk | Bulk  | Passenger aircraft/rail                         | Cargo aircraft only | Loca-tion      | Other |
|          | <i>Gelatine, blasting, see Explosive, blasting, type A.</i>                                   | .....                    | .....                  | ..... | .....       |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | <i>Gelatine dynamites, see Explosive, blasting, type A.</i>                                   | .....                    | .....                  | ..... | .....       |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | Germane .....                                                                                 | 2.3                      | UN2192                 | ..... | 2.3, 2.1.   | 2                              | None                  | 302      | 245   | Forbidden                                       | Forbidden           | D              | 40    |
|          | <i>Glycerol-1,3-dinitrate</i> .....                                                           | Forbidden                |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | <i>Glycerol gluconate trinitrate</i> .....                                                    | Forbidden                |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | <i>Glycerol lactate trinitrate</i> .....                                                      | Forbidden                |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | Glycerol alpha-monochlorohydrin.                                                              | 6.1                      | UN2689                 | III   | 6.1         | IB3, T4, TP1                   | 153                   | 203      | 241   | 60 L                                            | 220 L               | A              | ..... |
|          | <i>Glyceryl trinitrate, see Nitroglycerin, etc.</i>                                           | .....                    |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | Glycidaldehyde .....                                                                          | 3                        | UN2622                 | II    | 3, 6.1      | IB2, IP8, T7, TP1              | 150                   | 202      | 243   | 1 L                                             | 60 L                | A              | 40    |
|          | Grenades, hand or rifle, with bursting charge.                                                | 1.1D                     | UN0284                 | II    | 1.1D        |                                | .....                 | 62       | None  | Forbidden                                       | Forbidden           | 07             | ..... |
|          | Grenades, hand or rifle, with bursting charge.                                                | 1.2D                     | UN0285                 | II    | 1.2D        |                                | .....                 | 62       | None  | Forbidden                                       | Forbidden           | 07             | ..... |
|          | Grenades, hand or rifle, with bursting charge.                                                | 1.1F                     | UN0292                 | II    | 1.1F        |                                | .....                 | 62       | None  | Forbidden                                       | Forbidden           | 08             | ..... |
|          | Grenades, hand or rifle, with bursting charge.                                                | 1.2F                     | UN0293                 | II    | 1.2F        |                                | .....                 | 62       | None  | Forbidden                                       | Forbidden           | 08             | ..... |
|          | Grenades, illuminating, see Ammunition, illuminating, etc.                                    | .....                    |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | Grenades, practice, hand or rifle                                                             | 1.4S                     | UN0110                 | II    | 1.4S        |                                | .....                 | 62       | None  | 25 kg                                           | 100 kg              | 05             | ..... |
|          | Grenades, practice, hand or rifle                                                             | 1.3G                     | UN0318                 | II    | 1.3G        |                                | .....                 | 62       | None  | Forbidden                                       | Forbidden           | 07             | ..... |
|          | Grenades, practice, hand or rifle                                                             | 1.2G                     | UN0372                 | II    | 1.2G        |                                | .....                 | 62       | None  | Forbidden                                       | Forbidden           | 07             | ..... |
|          | Grenades practice Hand or rifle                                                               | 1.4G                     | UN0452                 | II    | 1.4G        |                                | .....                 | 62       | None  | Forbidden                                       | 75 kg               | 06             | ..... |
|          | Grenades, smoke, see Ammunition, smoke, etc.                                                  | .....                    |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | Guanidine nitrate .....                                                                       | 5.1                      | UN1467                 | III   | 5.1         | A1, IB8, IP3, T1, TP33         | 152                   | 213      | 240   | 25 kg                                           | 100 kg              | A              | 73    |
|          | <i>Guanyl nitrosaminoguanylidene hydrazine (dry).</i>                                         | Forbidden                |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |
|          | Guanyl nitrosaminoguanylidene hydrazine, wetted with not less than 30 percent water, by mass. | 1.1A                     | UN0113                 | II    | 1.1A        | 111, 117                       | None                  | 62       | None  | Forbidden                                       | Forbidden           | 12             | ..... |
|          | <i>Guanyl nitrosaminoguanyltetrazene (dry).</i>                                               | Forbidden                |                        |       |             |                                | .....                 | .....    | ..... | .....                                           | .....               | .....          | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|     |                                                                                                                                                                                                                                     |       |        |       |          |                                       |           |           |           |           |           |       |        |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-------|----------|---------------------------------------|-----------|-----------|-----------|-----------|-----------|-------|--------|
|     | Guanyl nitrosaminoguanilyltetrazene, wetted or Tetrazene, wetted with not less than 30 percent water or mixture of alcohol and water, by mass.                                                                                      | 1.1A  | UN0114 | II    | 1.1A ... | 111, 117                              | None .... | 62 .....  | None .... | Forbidden | Forbidden | 12    | .....  |
|     | Gunpowder, compressed or Gunpowder in pellets, see Black powder (UN 0028).                                                                                                                                                          | ..... | .....  | ..... | .....    | .....                                 | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
|     | Gunpowder, granular or as a meal, see Black powder (UN 0027).                                                                                                                                                                       | ..... | .....  | ..... | .....    | .....                                 | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
|     | Hafnium powder, dry .....                                                                                                                                                                                                           | 4.2   | UN2545 | I     | 4.2 .... |                                       | None .... | 211 ..... | 242 ..... | Forbidden | Forbidden | D     | .....  |
|     | .....                                                                                                                                                                                                                               | ..... | .....  | II    | 4.2 .... | A19, A20, IB6, IP2, N34, T3, TP33     | None .... | 212 ..... | 241 ..... | 15 kg     | 50 kg     | D     | .....  |
|     | .....                                                                                                                                                                                                                               | ..... | .....  | III   | 4.2 .... | IB8, IP3, T1, TP33                    | None .... | 213 ..... | 241 ..... | 25 kg     | 100 kg    | D     | .....  |
|     | Hafnium powder, wetted with not less than 25 percent water (a visible excess of water must be present) (a) mechanically produced, particle size less than 53 microns; (b) chemically produced, particle size less than 840 microns. | 4.1   | UN1326 | II    | 4.1 .... | A6, A19, A20, IB6, IP2, N34, T3, TP33 | None .... | 212 ..... | 241 ..... | 15 kg     | 50 kg     | E     | 74     |
|     | Hand signal device, see Signal devices, hand.                                                                                                                                                                                       | ..... | .....  | ..... | .....    | .....                                 | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
|     | Hazardous substances, liquid or solid, n.o.s., see Environmentally hazardous substances, etc.                                                                                                                                       | ..... | .....  | ..... | .....    | .....                                 | .....     | .....     | .....     | .....     | .....     | ..... | .....  |
| D G | Hazardous waste, liquid, n.o.s. ...                                                                                                                                                                                                 | 9     | NA3082 | III   | 9 .....  | IB3, T2, TP1                          | 155 ..... | 203 ..... | 241 ..... | No limit  | No limit  | A     | .....  |
| D G | Hazardous waste, solid, n.o.s. ...                                                                                                                                                                                                  | 9     | NA3077 | III   | 9 .....  | B54, IB8, IP2, T1, TP33               | 155 ..... | 213 ..... | 240 ..... | No limit  | No limit  | A     | .....  |
|     | Heating oil, light .....                                                                                                                                                                                                            | 3     | UN1202 | III   | 3 .....  | B1, IB3, T2, TP1                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A     | .....  |
|     | Helium, compressed .....                                                                                                                                                                                                            | 2.2   | UN1046 | ..... | 2.2 .... |                                       | 306 ..... | 302 ..... | 302, 314. | 75 kg     | 150 kg    | A     | 85     |
|     | Helium, refrigerated liquid (cryogenic liquid).                                                                                                                                                                                     | 2.2   | UN1963 | ..... | 2.2 .... | T75, TP5                              | 320 ..... | 316 ..... | 318 ..... | 50 kg     | 500 kg    | B     | .....  |
|     | Heptafluoropropane or Refrigerant gas R 227.                                                                                                                                                                                        | 2.2   | UN3296 | ..... | 2.2 .... | T50                                   | 306 ..... | 304 ..... | 314, 315. | 75 kg     | 150 kg    | A     | .....  |
|     | n-Heptaldehyde .....                                                                                                                                                                                                                | 3     | UN3056 | III   | 3 .....  | B1, IB3, T2, TP1                      | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A     | .....  |
|     | Heptanes .....                                                                                                                                                                                                                      | 3     | UN1206 | II    | 3 .....  | IB2, T4, TP1                          | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B     | .....  |
|     | n-Heptene .....                                                                                                                                                                                                                     | 3     | UN2278 | II    | 3 .....  | IB2, T4, TP1                          | 150 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B     | .....  |
|     | Hexachloroacetone .....                                                                                                                                                                                                             | 6.1   | UN2661 | III   | 6.1 .... | IB3, T4, TP1                          | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | B     | 12, 40 |
|     | Hexachlorobenzene .....                                                                                                                                                                                                             | 6.1   | UN2729 | III   | 6.1 .... | B3, IB8, IP3, T1, TP33                | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A     | .....  |
|     | Hexachlorobutadiene .....                                                                                                                                                                                                           | 6.1   | UN2279 | III   | 6.1 .... | IB3, T4, TP1                          | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A     | .....  |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes | Special provi-sions (§ 172.102)                       | (8)                   |           |           | (9)                                             |                      | (10)            |        |
|----------|-------------------------------------------------------------|---------------------------|--------------------------|-------|-------------|-------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|--------|
|          |                                                             |                           |                          |       |             |                                                       | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |        |
|          |                                                             |                           |                          |       |             |                                                       | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other  |
|          | Hexachlorocyclopentadiene .....                             | 6.1                       | UN2646                   | I     | 6.1 .....   | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden            | D               | 40     |
|          | Hexachlorophene .....                                       | 6.1                       | UN2875                   | III   | 6.1 .....   | IB8, IP3, T1, TP33                                    | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg               | A               | .....  |
|          | Hexadecyltrichlorosilane .....                              | 8                         | UN1781                   | II    | 8 .....     | A7, B2, B6, IB2, N34, T7, TP2                         | None ....             | 202 ..... | 242 ..... | Forbidden                                       | 30 L                 | C               | 40     |
|          | Hexadienes .....                                            | 3                         | UN2458                   | II    | 3 .....     | IB2, T4, TP1                                          | None ....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                 | B               | .....  |
|          | Hexaethyl tetraphosphate and compressed gas mixtures.       | 2.3                       | UN1612                   | ..... | 2.3 .....   | 3                                                     | None ....             | 334 ..... | None .... | Forbidden                                       | Forbidden            | D               | 40     |
|          | Hexaethyl tetraphosphate, <i>liquid</i>                     | 6.1                       | UN1611                   | II    | 6.1 .....   | IB2, N76, T7, TP2                                     | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | E               | 40     |
|          | Hexaethyl tetraphosphate, <i>solid</i>                      | 6.1                       | UN1611                   | II    | 6.1 .....   | IB8, IP2, IP4, N76                                    | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | E               | 40     |
|          | Hexafluoroacetone .....                                     | 2.3                       | UN2420                   | ..... | 2.3, 8      | 2, B9, B14                                            | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden            | D               | 40     |
|          | Hexafluoroacetone hydrate, liq-uid.                         | 6.1                       | UN2552                   | II    | 6.1 .....   | IB2, T7, TP2                                          | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | B               | 40     |
|          | Hexafluoroacetone hydrate, solid.                           | 6.1                       | UN3436                   | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                               | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | B               | 40     |
|          | Hexafluoroethane, or Refrigerant gas R 116.                 | 2.2                       | UN2193                   | ..... | 2.2 .....   |                                                       | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg               | A               | .....  |
|          | Hexafluorophosphoric acid .....                             | 8                         | UN1782                   | II    | 8 .....     | A6, A7, B2, IB2, N3, N34, T8, TP2, TP12               | None ....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                 | A               | .....  |
|          | Hexafluoropropylene com-pressed or Refrigerant gas R 1216.  | 2.2                       | UN1858                   | ..... | 2.2 .....   | T50                                                   | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg               | A               | .....  |
|          | Hexaldehyde .....                                           | 3                         | UN1207                   | III   | 3 .....     | B1, IB3, T2, TP1                                      | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                | A               | .....  |
|          | Hexamethylene diisocyanate .....                            | 6.1                       | UN2281                   | II    | 6.1 .....   | IB2, T7, TP2, TP13                                    | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | C               | 13, 40 |
|          | <i>Hexamethylene triperoxide diamine (dry).</i>             | Forbidden                 |                          |       | .....       |                                                       | .....                 | .....     | .....     | .....                                           | .....                |                 |        |
|          | Hexamethylenediamine, solid ....                            | 8                         | UN2280                   | III   | 8 .....     | IB8, IP3, T1, TP33                                    | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | 12     |
|          | Hexamethylenediamine solution .....                         | 8                         | UN1783                   | II    | 8 .....     | IB2, T7, TP2                                          | None ....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                 | A               | .....  |
|          | .....                                                       |                           |                          | III   | 8 .....     | IB3, T4, TP1                                          | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                 | A               | .....  |
|          | Hexamethyleneimine .....                                    | 3                         | UN2493                   | II    | 3, 8 ....   | IB2, T7, TP1                                          | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                  | B               | 40     |
|          | Hexamethylenetetramine .....                                | 4.1                       | UN1328                   | III   | 4.1 .....   | A1, IB8, IP3, T1, TP33                                | 151 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | .....  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

[illegible]

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                    | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)           | (8)                   |           |      | (9)                                             |                       | (10)             |                  |
|----------|--------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|--------------------------------------------|-----------------------|-----------|------|-------------------------------------------------|-----------------------|------------------|------------------|
|          |                                                                                |                            |                            |     |             |                                            | Packaging (§ 173.***) |           |      | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                  |
|          |                                                                                |                            |                            |     |             |                                            | Excep- tions          | Non- bulk | Bulk | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other            |
|          | HMX, <i>see</i> Cyclotetramethylenete trinitramine, <i>etc.</i>                |                            |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          | Hydrazine, anhydrous                                                           | 8                          | UN2029                     | I   | 8, 3, 6.1.  | A3, A6, A7, A10, B7, B16, B53 IB3, T4, TP1 | None                  | 201       | 243  | Forbidden                                       | 2.5 L                 | D                | 40, 52, 125, 52. |
|          | Hydrazine, aqueous solution, with not more than 37 percent hydrazine, by mass. | 6.1                        | UN3293                     | III | 6.1         |                                            | 153                   | 203       | 241  | 60 L                                            | 220 L                 | A                |                  |
|          | Hydrazine aqueous solution, with more than 37% hydra- zine, by mass.           | 8                          | UN2030                     | I   | 8, 6.1      | B16, B53, T10, TP2, TP13                   | None                  | 201       | 243  | Forbidden                                       | 2.5 L                 | D                | 40, 52           |
|          |                                                                                |                            |                            | II  | 8, 6.1      | B16, B53, IB2, T7, TP2, TP13               | None                  | 202       | 243  | Forbidden                                       | 30 L                  | D                | 40, 52           |
|          |                                                                                |                            |                            | III | 8, 6.1      | B16, B53, IB3, T4, TP1                     | 154                   | 203       | 241  | 5 L                                             | 60 L                  | D                | 40, 52           |
|          | Hydrazine azide                                                                | Forbidden                  |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          | Hydrazine chlorate                                                             | Forbidden                  |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          | Hydrazine dicarbonic acid diazide.                                             | Forbidden                  |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          |                                                                                |                            |                            | II  | 8, 6.1      | B16, B53, IB2, T7, TP2, TP13               | None                  | 202       | 243  | Forbidden                                       | 30 L                  | D                | 40               |
|          |                                                                                |                            |                            | III | 8, 6.1      | B16, B53, IB3, T4, TP1                     | 154                   | 203       | 241  | 5 L                                             | 60 L                  | D                | 40               |
|          | Hydrazine perchlorate                                                          | Forbidden                  |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          | Hydrazine selenate                                                             | Forbidden                  |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          | Hydriodic acid, anhydrous, <i>see</i> Hydrogen iodide, anhydrous.              |                            |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          | Hydriodic acid                                                                 | 8                          | UN1787                     | II  | 8           | A3, A6, B2, IB2, N41, T7, TP2              | 154                   | 202       | 242  | 1 L                                             | 30 L                  | C                |                  |
|          |                                                                                |                            |                            | III | 8           | IB3, T4, TP1                               | 154                   | 203       | 241  | 5 L                                             | 60 L                  | C                | 8                |
|          | Hydrobromic acid, anhydrous, <i>see</i> Hydrogen bromide, anhy- drous.         |                            |                            |     |             |                                            |                       |           |      |                                                 |                       |                  |                  |
|          | Hydrobromic acid, with more than 49 percent hydrobromic acid.                  | 8                          | UN1788                     | II  | 8           | B2, B15, IB2, N41, T7, TP2                 | 154                   | 202       | 242  | Forbidden                                       | Forbidden             | C                |                  |
|          |                                                                                |                            |                            | III | 8           | IB3, T4, TP1                               | 154                   | 203       | 241  | Forbidden                                       | Forbidden             | C                | 8                |
|          | Hydrobromic acid, with not more than 49 percent hydrobromic acid.              | 8                          | UN1788                     | II  | 8           | A3, A6, B2, B15, IB2, N41, T7, TP2         | 154                   | 202       | 242  | 1 L                                             | 30 L                  | C                |                  |
|          |                                                                                |                            |                            | III | 8           | A3, IB3, T4, TP1                           | 154                   | 203       | 241  | 5 L                                             | 60 L                  | C                | 8                |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                            |           |        |       |        |       |                                                     |       |       |       |       |           |           |           |           |       |        |
|----------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|--------|-------|-----------------------------------------------------|-------|-------|-------|-------|-----------|-----------|-----------|-----------|-------|--------|
| Hydrocarbon gas mixture, compressed, n.o.s..                                                                               | 2.1       | UN1964 | ..... | 2.1    | ..... |                                                     | 306   | ..... | 302   | ..... | 314, 315. | Forbidden | 150 kg    | E         | 40    |        |
| Hydrocarbon gas mixture, liquefied, n.o.s..                                                                                | 2.1       | UN1965 | ..... | 2.1    | ..... | T50                                                 | 306   | ..... | 304   | ..... | 314, 315. | Forbidden | 150 kg    | E         | 40    |        |
| Hydrocarbons, liquid, n.o.s. ....                                                                                          | 3         | UN3295 | I     | 3      | ..... | 144, T11, TP1, TP8, TP28                            | 150   | ..... | 201   | ..... | 243       | .....     | 1 L       | 30 L      | E     | .....  |
| .....                                                                                                                      | .....     | .....  | II    | 3      | ..... | 144, IB2, T7, TP1, TP8, TP28                        | 150   | ..... | 202   | ..... | 242       | .....     | 5 L       | 60 L      | B     | .....  |
| .....                                                                                                                      | .....     | .....  | III   | 3      | ..... | 144, B1, IB3, T4, TP1, TP29                         | 150   | ..... | 203   | ..... | 242       | .....     | 60 L      | 220 L     | A     | .....  |
| Hydrochloric acid, anhydrous, see Hydrogen chloride, anhydrous.                                                            | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrochloric acid .....                                                                                                    | 8         | UN1789 | II    | 8      | ..... | A3, A6, B3, B15, IB2, N41, T8, TP2, TP12            | 154   | ..... | 202   | ..... | 242       | .....     | 1 L       | 30 L      | C     | .....  |
| .....                                                                                                                      | .....     | .....  | III   | 8      | ..... | A3, IB3, T4, TP1, TP12                              | 154   | ..... | 203   | ..... | 241       | .....     | 5 L       | 60 L      | C     | 8      |
| Hydrocyanic acid, anhydrous, see Hydrogen cyanide etc.                                                                     | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrocyanic acid, aqueous solutions or Hydrogen cyanide, aqueous solutions with not more than 20 percent hydrogen cyanide. | 6.1       | UN1613 | I     | 6.1    | ..... | 2, B61, B65, B77, B82, T20, TP2, TP13               | None  | ....  | 195   | ..... | 244       | .....     | Forbidden | Forbidden | D     | 40     |
| Hydrocyanic acid, aqueous solutions with less than 5 percent hydrogen cyanide.                                             | 6.1       | NA1613 | II    | 6.1    | ..... | IB1, T14, TP2, TP13, TP27                           | None  | ....  | 195   | ..... | 243       | .....     | Forbidden | 5 L       | D     | 40     |
| Hydrocyanic acid, liquefied, see Hydrogen cyanide, etc.                                                                    | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrocyanic acid (prussic), unstabilized.                                                                                  | Forbidden | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrofluoric acid and Sulfuric acid mixtures.                                                                              | 8         | UN1786 | I     | 8, 6.1 | ..... | A6, A7, B15, B23, N5, N34, T10, TP2, TP12, TP13     | None  | ....  | 201   | ..... | 243       | .....     | Forbidden | 2.5 L     | D     | 40     |
| .....                                                                                                                      | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrofluoric acid, anhydrous, see Hydrogen fluoride, anhydrous.                                                            | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrofluoric acid, with more than 60 percent strength.                                                                     | 8         | UN1790 | I     | 8, 6.1 | ..... | A6, A7, B4, B15, B23, N5, N34, T10, TP2, TP12, TP13 | None  | ....  | 201   | ..... | 243       | .....     | 0.5 L     | 2.5 L     | D     | 12, 40 |
| .....                                                                                                                      | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrofluoric acid, with not more than 60 percent strength.                                                                 | 8         | UN1790 | II    | 8, 6.1 | ..... | A6, A7, B15, IB2, N5, N34, T8, TP2, TP12            | 154   | ..... | 202   | ..... | 243       | .....     | 1 L       | 30 L      | D     | 12, 40 |
| .....                                                                                                                      | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrofluoroboric acid, see Fluoroboric acid.                                                                               | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |
| Hydrofluorosilicic acid, see Fluorosilicic acid.                                                                           | .....     | .....  | ..... | .....  | ..... | .....                                               | ..... | ..... | ..... | ..... | .....     | .....     | .....     | .....     | ..... | .....  |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                                            | Hazard class or Division | Identification Numbers | PG    | Label Codes | Special provisions (§ 172.102)                   | (8)                   |           |                | (9)                                             |                     | (10)           |             |
|----------|-------------------------------------------------------------------------------------------------------|--------------------------|------------------------|-------|-------------|--------------------------------------------------|-----------------------|-----------|----------------|-------------------------------------------------|---------------------|----------------|-------------|
|          |                                                                                                       |                          |                        |       |             |                                                  | Packaging (§ 173.***) |           |                | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |             |
|          |                                                                                                       |                          |                        |       |             |                                                  | Excep-tions           | Non-bulk  | Bulk           | Passenger aircraft/rail                         | Cargo aircraft only | Location       | Other       |
|          | Hydrogen and Methane mixtures, compressed.                                                            | 2.1                      | UN2034                 | ..... | 2.1 .....   | N89                                              | 306 .....             | 302 ..... | 302, 314, 315. | Forbidden                                       | 150 kg              | E              | 40, 57      |
|          | Hydrogen bromide, anhydrous ..                                                                        | 2.3                      | UN1048                 | ..... | 2.3, 8      | 3, B14, N86, N89                                 | None ....             | 304 ..... | 314, 315.      | Forbidden                                       | Forbidden           | D              | 40          |
|          | Hydrogen chloride, anhydrous ...                                                                      | 2.3                      | UN1050                 | ..... | 2.3, 8      | 3, N86, N89                                      | None ....             | 304 ..... | None ....      | Forbidden                                       | Forbidden           | D              | 40          |
|          | Hydrogen chloride, refrigerated liquid.                                                               | 2.3                      | UN2186                 | ..... | 2.3, 8      | 3, B6                                            | None ....             | None .... | 314, 315.      | Forbidden                                       | Forbidden           | B              | 40          |
|          | Hydrogen, compressed .....                                                                            | 2.1                      | UN1049                 |       | 2.1 .....   | N89                                              | 306 .....             | 302 ..... | 302, 314.      | Forbidden                                       | 150 kg              | E              | 40, 57      |
|          | Hydrogen cyanide, solution in alcohol with not more than 45 percent hydrogen cyanide.                 | 6.1                      | UN3294                 | I     | 6.1, 3      | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45 | None ....             | 227 ..... | 244 .....      | Forbidden                                       | Forbidden           | D              | 40          |
|          | Hydrogen cyanide, stabilized with less than 3 percent water.                                          | 6.1                      | UN1051                 | I     | 6.1, 3      | 1, B35, B61, B65, B77, B82                       | None ....             | 195 ..... | 244 .....      | Forbidden                                       | Forbidden           | D              | 40          |
|          | Hydrogen cyanide, stabilized, with less than 3 percent water and absorbed in a porous inert material. | 6.1                      | UN1614                 | I     | 6.1 .....   | 5                                                | None ....             | 195 ..... | None ....      | Forbidden                                       | Forbidden           | D              | 25, 40      |
|          | Hydrogen fluoride, anhydrous ....                                                                     | 8                        | UN1052                 | I     | 8, 6.1      | 3, B7, B46, B71, B77, N86, T10, TP2              | None ....             | 163 ..... | 243 .....      | Forbidden                                       | Forbidden           | D              | 40          |
|          | Hydrogen in a metal hydride storage system.                                                           | 2.1                      | UN3468                 | ..... | 2.1 .....   | 167                                              | None ....             | 214 ..... | None ....      | Forbidden                                       | 100 kg gross        | D              |             |
|          | Hydrogen iodide, anhydrous .....                                                                      | 2.3                      | UN2197                 | ..... | 2.3 .....   | 3, B14, N86, N89                                 | None ....             | 304 ..... | 314, 315.      | Forbidden                                       | Forbidden           | D              | 40          |
|          | Hydrogen iodide solution, see Hydriodic acid.                                                         | .....                    |                        |       | .....       | .....                                            | .....                 | .....     | .....          | .....                                           | .....               |                |             |
|          | Hydrogendifluoride, solid, n.o.s                                                                      | 8                        | UN1740                 | III   | 8 .....     | IB8, IP3, N3, N34, T1, TP33                      | 154 .....             | 213 ..... | 240 .....      | 25 kg                                           | 100 kg              | A              | 25, 40, 52. |
|          |                                                                                                       |                          |                        | II    | 8 .....     | IB8, IP2, IP4, N3, N34, T3, TP33                 | None ....             | 212 ..... | 240 .....      | 15 kg                                           | 50 kg               | A              | 25, 40, 52  |
|          |                                                                                                       |                          |                        | III   | 8 .....     | IB8, IP3, N3, N34, T1, TP33                      | 154 .....             | 213 ..... | 240 .....      | 25 kg                                           | 100 kg              | A              | 25, 40, 52  |
|          | Hydrogendifluoride solution, n.o.s.                                                                   | 8                        | UN3471                 | II    | 8, 6.1      | IB2, T7, TP2                                     | 154 .....             | 202 ..... | 242 .....      | 1 L                                             | 30 L                | A              | 25, 40, 52. |
|          |                                                                                                       |                          |                        | III   | 8, 6.1      | IB3, T4, TP1                                     | 154 .....             | 203 ..... | 241 .....      | 5 L                                             | 60 L                | A              | 25, 40, 52. |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                              |           |        |       |           |                                                                 |           |           |           |           |           |   |                                     |
|----------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|-----------------------------------------------------------------|-----------|-----------|-----------|-----------|-----------|---|-------------------------------------|
| Hydrogen peroxide and peroxy-acetic acid mixtures, stabilized with acids, water, and not more than 5 percent peroxy-acetic acid.             | 5.1       | UN3149 | II    | 5.1, 8    | 145, A2, A3, A6, B53, IB2, IP5, T7, TP2, TP6, TP24              | None .... | 202 ..... | 243 ..... | 1 L       | 5 L       | D | 25, 66, 75.                         |
| Hydrogen, peroxide, aqueous solutions with more than 40 percent but not more than 60 percent hydrogen peroxide (stabilized as necessary).    | 5.1       | UN2014 | II    | 5.1, 8    | 12, A60, B53, B80, B81, B85, IB2, IP5, T7, TP2, TP6, TP24, TP37 | None .... | 202 ..... | 243 ..... | Forbidden | Forbidden | D | 25, 66, 75                          |
| Hydrogen peroxide, aqueous solutions with not less than 20 percent but not more than 40 percent hydrogen peroxide (stabilized as necessary). | 5.1       | UN2014 | II    | 5.1, 8    | A2, A3, A6, B53, IB2, IP5, T7, TP2, TP6, TP24, TP37             | None .... | 202 ..... | 243 ..... | 1 L       | 5 L       | D | 25, 66, 75.                         |
| Hydrogen, peroxide, aqueous solutions with not less than 8 percent but less than 20 percent hydrogen peroxide (stabilized as necessary).     | 5.1       | UN2984 | III   | 5.1 ..... | A1, IB2, IP5, T4, TP1, TP6, TP24, TP37                          | 152 ..... | 203 ..... | 241 ..... | 2.5 L     | 30 L      | B | 25, 66, 75                          |
| Hydrogen peroxide, stabilized or Hydrogen peroxide aqueous solutions, stabilized with more than 60 percent hydrogen peroxide.                | 5.1       | UN2015 | I     | 5.1, 8    | 12, B53, B80, B81, B85, T9, TP2, TP6, TP24, TP37                | None .... | 201 ..... | 243 ..... | Forbidden | Forbidden | D | 25, 66, 75.                         |
| Hydrogen, refrigerated liquid (cryogenic liquid).                                                                                            | 2.1       | UN1966 | ..... | 2.1 ..... | T75, TP5                                                        | None .... | 316 ..... | 318, 319. | Forbidden | Forbidden | D | 40                                  |
| Hydrogen selenide, anhydrous ..                                                                                                              | 2.3       | UN2202 | ..... | 2.3, 2.1. | 1                                                               | None .... | 192 ..... | 245 ..... | Forbidden | Forbidden | D | 40                                  |
| Hydrogen sulfate, see Sulfuric acid.                                                                                                         | .....     |        |       | .....     |                                                                 | .....     | .....     | .....     | .....     | .....     |   | .....                               |
| Hydrogen sulfide .....                                                                                                                       | 2.3       | UN1053 |       | 2.3, 2.1. | 2, B9, B14, N89                                                 | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D | 40                                  |
| Hydrosilicofluoric acid, see Fluorosilicic acid.                                                                                             | .....     |        |       | .....     |                                                                 | .....     | .....     | .....     | .....     | .....     |   | .....                               |
| Hydroxylamine iodide .....                                                                                                                   | Forbidden |        |       | .....     |                                                                 | .....     | .....     | .....     | .....     | .....     |   | .....                               |
| Hydroxylamine sulfate .....                                                                                                                  | 8         | UN2865 | III   | 8 .....   | IB8, IP3, T1, TP33                                              | 154 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A | .....                               |
| Hypochlorite solutions .....                                                                                                                 | 8         | UN1791 | II    | 8 .....   | A7, B2, B15, IB2, IP5, N34, T7, TP2, TP24                       | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | B | 26.                                 |
| Hypochlorites, inorganic, n.o.s. ..                                                                                                          | 5.1       | UN3212 | II    | 5.1 ..... | A9, IB8, IP2, IP4, T3, TP33                                     | 152 ..... | 212 ..... | 240 ..... | 5 kg      | 25 kg     | D | 4, 48, 52, 56, 58, 69, 106, 116 118 |
| Hyponitrous acid .....                                                                                                                       | Forbidden |        |       | .....     |                                                                 | .....     | .....     | .....     | .....     | .....     |   | .....                               |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                  | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |                    |
|----------|------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------------------|
|          |                                                                              |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                    |
|          |                                                                              |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other              |
|          | <i>Igniter fuse, metal clad, see Fuse, igniter, tubular, metal clad.</i>     |                            |                            |       |             |                                  |                       |           |           |                                                 |                       |                  |                    |
|          | Igniters .....                                                               | 1.1G                       | UN0121                     | II    | 1.1G ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....              |
|          | Igniters .....                                                               | 1.2G                       | UN0314                     | II    | 1.2G ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....              |
|          | Igniters .....                                                               | 1.3G                       | UN0315                     | II    | 1.3G ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 07               | .....              |
|          | Igniters .....                                                               | 1.4G                       | UN0325                     | II    | 1.4G ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....              |
|          | Igniters .....                                                               | 1.4S                       | UN0454                     | II    | 1.4S ...    |                                  | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg                | 05               | .....              |
|          | 3,3'-Iminodipropylamine .....                                                | 8                          | UN2269                     | III   | 8 .....     | IB3, T4, TP2                     | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | .....              |
| G        | Infectious substances, affecting animals only.                               | 6.2                        | UN2900                     | ..... | 6.2 .....   | A82                              | 134 .....             | 196 ..... | None .... | 50 mL or 50 g                                   | 4 L or 4 kg           | B                | 40                 |
| G        | Infectious substances, affecting humans.                                     | 6.2                        | UN 2814                    | ..... | 6.2 .....   | A82                              | 134 .....             | 196 ..... | None .... | 50 mL or 50 g                                   | 4 L or 4 kg           | B                | 40                 |
|          | <i>Inflammable, see Flammable</i> .....                                      |                            |                            |       |             |                                  |                       |           |           |                                                 |                       |                  |                    |
|          | <i>Initiating explosives (dry)</i> .....                                     | Forbidden                  |                            |       |             |                                  |                       |           |           |                                                 |                       |                  |                    |
|          | <i>Inositol hexanitrate (dry)</i> .....                                      | Forbidden                  |                            |       |             |                                  |                       |           |           |                                                 |                       |                  |                    |
| G        | Insecticide gases, n.o.s. ....                                               | 2.2                        | UN1968                     | ..... | 2.2 .....   |                                  | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | A                | .....              |
| G        | Insecticide gases, flammable, n.o.s..                                        | 2.1                        | UN3354                     | ..... | 2.1 .....   | T50                              | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg                | D                | 40                 |
| G        | Insecticide gases, toxic, flammable, n.o.s. <i>Inhalation hazard Zone A.</i> | 2.3                        | UN3355                     | ..... | 2.3, 2.1.   | 1                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40                 |
| G        | Insecticide gases, toxic, flammable, n.o.s. <i>Inhalation hazard Zone B.</i> | 2.3                        | UN3355                     | ..... | 2.3, 2.1.   | 2, B9, B14                       | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | 40                 |
| G        | Insecticide gases, toxic, flammable, n.o.s. <i>Inhalation hazard Zone C.</i> | 2.3                        | UN3355                     | ..... | 2.3, 2.1.   | 3, B14                           | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | .....              |
| G        | Insecticide gases, toxic, flammable, n.o.s. <i>Inhalation hazard Zone D.</i> | 2.3                        | UN3355                     | ..... | 2.3, 2.1.   | 4                                | None ....             | 302, 305. | 314, 315. | Forbidden                                       | Forbidden             | D                | .....              |
| G        | Insecticide gases, toxic, n.o.s. ...                                         | 2.3                        | UN1967                     | ..... | 2.3 .....   | 3                                | None ....             | 193, 334. | 245 ..... | Forbidden                                       | Forbidden             | D                | 40                 |
|          | <i>Inulin trinitrate (dry)</i> .....                                         | Forbidden                  |                            |       |             |                                  |                       |           |           |                                                 |                       |                  |                    |
|          | <i>Iodine azide (dry)</i> .....                                              | Forbidden                  |                            |       |             |                                  |                       |           |           |                                                 |                       |                  |                    |
|          | Iodine monochloride .....                                                    | 8                          | UN1792                     | II    | 8 .....     | B6, IB8, IP2, IP4, N41, T7, TP2  | None ....             | 212 ..... | 240 ..... | Forbidden                                       | 50 kg                 | D                | 40, 66, 74, 89, 90 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                               |           |        |       |              |                                                        |      |     |           |           |           |   |                             |
|-------------------------------------------------------------------------------|-----------|--------|-------|--------------|--------------------------------------------------------|------|-----|-----------|-----------|-----------|---|-----------------------------|
| Iodine pentafluoride .....                                                    | 5.1       | UN2495 | I     | 5.1, 6.1, 8. |                                                        | None | 205 | 243       | Forbidden | Forbidden | D | 25, 40, 52, 66, 90          |
| 2-Iodobutane .....                                                            | 3         | UN2390 | II    | 3            | IB2, T4, TP1                                           | 150  | 202 | 242       | 5 L       | 60 L      | B | .....                       |
| Iodomethylpropanes .....                                                      | 3         | UN2391 | II    | 3            | IB2, T4, TP1                                           | 150  | 202 | 242       | 5 L       | 60 L      | B | .....                       |
| Iodopropanes .....                                                            | 3         | UN2392 | III   | 3            | B1, IB3, T2, TP1                                       | 150  | 203 | 242       | 60 L      | 220 L     | A | .....                       |
| Iodoxy compounds (dry) .....                                                  | Forbidden |        |       |              |                                                        |      |     |           |           |           |   | .....                       |
| Iridium nitratopentamine iridium nitrate.                                     | Forbidden |        |       |              |                                                        |      |     |           |           |           |   | .....                       |
| Iron chloride, see Ferric chloride.                                           |           |        |       |              |                                                        |      |     |           |           |           |   | .....                       |
| Iron oxide, spent, or Iron sponge, spent obtained from coal gas purification. | 4.2       | UN1376 | III   | 4.2          | B18, IB8, IP3, T1, TP33                                | None | 213 | 240       | Forbidden | Forbidden | E | .....                       |
| Iron pentacarbonyl .....                                                      | 6.1       | UN1994 | I     | 6.1, 3       | 1, B9, B14, B30, B72, B77, T22, TP2, TP13, TP38, TP44  | None | 226 | 244       | Forbidden | Forbidden | D | 40                          |
| Iron sesquichloride, see Ferric chloride.                                     |           |        |       |              |                                                        |      |     |           |           |           |   | .....                       |
| Irritating material, see Tear gas substances, etc.                            |           |        |       |              |                                                        |      |     |           |           |           |   | .....                       |
| Isobutane see also Petroleum gases, liquefied.                                | 2.1       | UN1969 | ..... | 2.1          | 19, T50                                                | 306  | 304 | 314, 315. | Forbidden | 150 kg    | E | 40                          |
| Isobutanol or Isobutyl alcohol ....                                           | 3         | UN1212 | III   | 3            | B1, IB3, T2, TP1                                       | 150  | 203 | 242       | 60 L      | 220 L     | A | .....                       |
| Isobutyl acetate .....                                                        | 3         | UN1213 | II    | 3            | IB2, T4, TP1                                           | 150  | 202 | 242       | 5 L       | 60 L      | B | .....                       |
| Isobutyl acrylate, stabilized .....                                           | 3         | UN2527 | III   | 3            | B1, IB3, T2, TP1                                       | 150  | 203 | 242       | 60 L      | 220 L     | A | .....                       |
| Isobutyl alcohol, see Isobutanol                                              |           |        |       |              |                                                        |      |     |           |           |           |   | .....                       |
| Isobutyl aldehyde, see Isobutyraldehyde.                                      |           |        |       |              |                                                        |      |     |           |           |           |   | .....                       |
| D Isobutyl chloroformate .....                                                | 6.1       | NA2742 | I     | 6.1, 3, 8.   | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None | 227 | 244       | Forbidden | Forbidden | A | 12, 13, 22, 25, 40, 48, 100 |
| Isobutyl formate .....                                                        | 3         | UN2393 | II    | 3            | IB2, T4, TP1                                           | 150  | 202 | 242       | 5 L       | 60 L      | B | .....                       |
| Isobutyl isobutyrate .....                                                    | 3         | UN2528 | III   | 3            | B1, IB3, T2, TP1                                       | 150  | 203 | 242       | 60 L      | 220 L     | A | .....                       |
| + Isobutyl isocyanate .....                                                   | 3         | UN2486 | I     | 3, 6.1       | 1, B9, B14, B30, B72, T22, TP2, TP13, TP27             | None | 226 | 244       | Forbidden | Forbidden | D | 40                          |
| Isobutyl methacrylate, stabilized                                             | 3         | UN2283 | III   | 3            | B1, IB3, T2, TP1                                       | 150  | 203 | 242       | 60 L      | 220 L     | A | .....                       |
| Isobutyl propionate .....                                                     | 3         | UN2394 | III   | 3            | B1, IB3, T2, TP1                                       | 150  | 203 | 242       | 60 L      | 220 L     | B | .....                       |
| Isobutylamine .....                                                           | 3         | UN1214 | II    | 3, 8         | IB2, T7, TP1                                           | 150  | 202 | 243       | 1 L       | 5 L       | B | 40                          |
| Isobutylene see also Petroleum gases, liquefied.                              | 2.1       | UN1055 | ..... | 2.1          | 19, T50                                                | 306  | 304 | 314, 315. | Forbidden | 150 kg    | E | 40                          |
| Isobutyraldehyde or Isobutyl aldehyde.                                        | 3         | UN2045 | II    | 3            | IB2, T4, TP1                                           | 150  | 202 | 242       | 5 L       | 60 L      | E | 40                          |
| Isobutyric acid .....                                                         | 3         | UN2529 | III   | 3, 8         | B1, IB3, T4, TP1                                       | 150  | 203 | 242       | 5 L       | 60 L      | A | .....                       |
| Isobutyronitrile .....                                                        | 3         | UN2284 | II    | 3, 6.1       | IB2, T7, TP2, TP13                                     | 150  | 202 | 243       | 1 L       | 60 L      | E | 40                          |
| Isobutyryl chloride .....                                                     | 3         | UN2395 | II    | 3, 8         | IB1, T7, TP2                                           | 150  | 202 | 243       | 1 L       | 5 L       | C | 40                          |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                                                        | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)     | (8)                   |           |           | (9)                                             |                       | (10)             |            |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|--------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|------------|
|          |                                                                                                                                                                                                                    |                            |                            |       |             |                                      | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |            |
|          |                                                                                                                                                                                                                    |                            |                            |       |             |                                      | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other      |
| G        | Isocyanates, flammable, toxic, n.o.s. or Isocyanate solutions, flammable, toxic, n.o.s. <i>flash point less than 23 degrees C.</i>                                                                                 | 3                          | UN2478                     | II    | 3, 6.1      | 5, A3, A7, IB2, T11, TP2, TP13, TP27 | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 60 L                  | D                | 40         |
|          | .....                                                                                                                                                                                                              | .....                      | .....                      | III   | 3, 6.1      | 5, A3, A7, IB3, T7, TP1, TP13, TP28  | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....      |
| G        | Isocyanates, toxic, flammable, n.o.s. or Isocyanate solutions, toxic, flammable, n.o.s., <i>flash point not less than 23 degrees C but not more than 61 de- grees C and boiling point less than 300 degrees C.</i> | 6.1                        | UN3080                     | II    | 6.1, 3      | IB2, T11, TP2, TP13, TP27            | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | 25, 40, 48 |
| G        | Isocyanates, toxic, n.o.s. or Isocyanate solutions, toxic, n.o.s., <i>flash point more than 61 degrees C and boiling point less than 300 degrees C.</i>                                                            | 6.1                        | UN2206                     | II    | 6.1 .....   | IB2, T11, TP2, TP13, TP27            | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | E                | 25, 40, 48 |
|          | .....                                                                                                                                                                                                              | .....                      | .....                      | III   | 6.1 .....   | IB3, T7, TP1, TP13, TP28             | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | E                | 25, 40, 48 |
|          | Isocyanatobenzotrifluorides .....                                                                                                                                                                                  | 6.1                        | UN2285                     | II    | 6.1, 3      | 5, IB2, T7, TP2                      | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | D                | 25, 40, 48 |
|          | Isoheptenes .....                                                                                                                                                                                                  | 3                          | UN2287                     | II    | 3 .....     | IB2, T4, TP1                         | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | Isohexenes .....                                                                                                                                                                                                   | 3                          | UN2288                     | II    | 3 .....     | IB2, IP8, T11, TP1                   | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | E                | .....      |
|          | <i>Isooctane</i> , see Octanes .....                                                                                                                                                                               | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | Isooctenes .....                                                                                                                                                                                                   | 3                          | UN1216                     | II    | 3 .....     | IB2, T4, TP1                         | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | <i>Isopentane</i> , see Pentane .....                                                                                                                                                                              | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | <i>Isopentanoic acid</i> , see Corrosive liquids, n.o.s. ....                                                                                                                                                      | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....      |
|          | Isopentenenes .....                                                                                                                                                                                                | 3                          | UN2371                     | I     | 3 .....     | T11, TP2                             | 150 .....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | E                | .....      |
|          | Isophorone diisocyanate .....                                                                                                                                                                                      | 6.1                        | UN2290                     | III   | 6.1 .....   | IB3, T4, TP2                         | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | B                | 40         |
|          | Isophoronediamine .....                                                                                                                                                                                            | 8                          | UN2289                     | III   | 8 .....     | IB3, T4, TP1                         | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | .....      |
|          | Isoprene, stabilized .....                                                                                                                                                                                         | 3                          | UN1218                     | I     | 3 .....     | T11, TP2                             | 150 .....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | E                | .....      |
|          | Isopropanol or Isopropyl alcohol .....                                                                                                                                                                             | 3                          | UN1219                     | II    | 3 .....     | IB2, T4, TP1                         | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | Isopropenyl acetate .....                                                                                                                                                                                          | 3                          | UN2403                     | II    | 3 .....     | IB2, T4, TP1                         | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | Isopropenylbenzene .....                                                                                                                                                                                           | 3                          | UN2303                     | III   | 3 .....     | B1, IB3, T2, TP1                     | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....      |
|          | Isopropyl acetate .....                                                                                                                                                                                            | 3                          | UN1220                     | II    | 3 .....     | IB2, T4, TP1                         | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....      |
|          | Isopropyl acid phosphate .....                                                                                                                                                                                     | 8                          | UN1793                     | III   | 8 .....     | IB2, T4, TP1                         | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | .....      |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

[illegible]

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                          | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |       | (9)                                             |                       | (10)             |       |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                                                      |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |       | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                                                      |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk  | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
| G        | Kerosene .....                                                                                                                                       | 3                          | UN1223                     | III   | 3           | 144, B1, IB3, T2, TP2            | 150                   | 203       | 242   | 60 L                                            | 220 L                 | A                | ..... |
|          | Ketones, liquid, n.o.s. ....                                                                                                                         | 3                          | UN1224                     | I     | 3           | T11, TP1, TP8, TP27              | None                  | 201       | 243   | 1 L                                             | 30 L                  | E                | ..... |
|          | .....                                                                                                                                                | .....                      | .....                      | II    | 3           | IB2, T7, TP1, TP8, TP28          | 150                   | 202       | 242   | 5 L                                             | 60 L                  | B                | ..... |
|          | .....                                                                                                                                                | .....                      | .....                      | III   | 3           | B1, IB3, T4, TP1, TP29           | 150                   | 203       | 242   | 60 L                                            | 220 L                 | A                | ..... |
|          | Krypton, compressed .....                                                                                                                            | 2.2                        | UN1056                     | ..... | 2.2         | .....                            | 306                   | 302       | None  | 75 kg                                           | 150 kg                | A                | ..... |
|          | Krypton, refrigerated liquid (cryogenic liquid) .....                                                                                                | 2.2                        | UN1970                     | ..... | 2.2         | T75, TP5                         | 320                   | None      | None  | 50 kg                                           | 500 kg                | B                | ..... |
|          | Lacquer base or lacquer chips, nitrocellulose, dry, see Nitrocellulose, etc. (UN 2557) .....                                                         | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | ..... | .....                                           | .....                 | .....            | ..... |
|          | Lacquer base or lacquer chips, plastic, wet with alcohol or solvent, see Nitrocellulose (UN2059, UN2555, UN2556, UN2557) or Paint etc.(UN1263) ..... | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | ..... | .....                                           | .....                 | .....            | ..... |
|          | Lead acetate .....                                                                                                                                   | 6.1                        | UN1616                     | III   | 6.1         | IB8, IP3, T1, TP33               | 153                   | 213       | 240   | 100 kg                                          | 200 kg                | A                | ..... |
|          | Lead arsenates .....                                                                                                                                 | 6.1                        | UN1617                     | II    | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242   | 25 kg                                           | 100 kg                | A                | ..... |
|          | Lead arsenites .....                                                                                                                                 | 6.1                        | UN1618                     | II    | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242   | 25 kg                                           | 100 kg                | A                | ..... |
|          | Lead azide (dry) .....                                                                                                                               | Forbidden                  | .....                      | ..... | .....       | .....                            | .....                 | .....     | ..... | .....                                           | .....                 | .....            | ..... |
|          | Lead azide, wetted with not less than 20 percent water or mixture of alcohol and water, by mass. ....                                                | 1.1A                       | UN0129                     | II    | 1.1A        | 111, 117                         | None                  | 62        | None  | Forbidden                                       | Forbidden             | 12               | ..... |
|          | Lead compounds, soluble, n.o.s. ....                                                                                                                 | 6.1                        | UN2291                     | III   | 6.1         | 138, IB8, IP3, T1, TP33          | 153                   | 213       | 240   | 100 kg                                          | 200 kg                | A                | ..... |
|          | Lead cyanide .....                                                                                                                                   | 6.1                        | UN1620                     | II    | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242   | 25 kg                                           | 100 kg                | A                | 52    |
|          | Lead dioxide .....                                                                                                                                   | 5.1                        | UN1872                     | III   | 5.1         | A1, IB8, IP3, T1, TP33           | 152                   | 213       | 240   | 25 kg                                           | 100 kg                | A                | ..... |
|          | Lead dross, see Lead sulfate, with more than 3 percent free acid. ....                                                                               | .....                      | .....                      | ..... | .....       | .....                            | .....                 | .....     | ..... | .....                                           | .....                 | .....            | ..... |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|                                                                                                                                          |           |        |     |          |                         |           |           |           |           |           |    |        |
|------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-----|----------|-------------------------|-----------|-----------|-----------|-----------|-----------|----|--------|
| Lead nitrate .....                                                                                                                       | 5.1       | UN1469 | II  | 5.1, 6.1 | IB8, IP2, IP4, T3, TP33 | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A  | .....  |
| Lead nitroresorcinate (dry) .....                                                                                                        | Forbidden |        |     |          |                         |           |           |           |           |           |    |        |
| Lead perchlorate, solid .....                                                                                                            | 5.1       | UN1470 | II  | 5.1, 6.1 | IB6, IP2, T3, TP33      | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A  | 56, 58 |
| Lead perchlorate, solution .....                                                                                                         | 5.1       | UN3408 | II  | 5.1, 6.1 | IB2, T4, TP1            | 152 ..... | 202 ..... | 243 ..... | 1 L       | 5 L       | A  | 56, 58 |
|                                                                                                                                          |           |        | III | 5.1, 6.1 | IB2, T4, TP1            | 152 ..... | 203 ..... | 242 ..... | 2.5 L     | 30 L      | A  | 56, 58 |
| Lead peroxide, see Lead dioxide .....                                                                                                    |           |        |     |          |                         |           |           |           |           |           |    |        |
| Lead phosphite, dibasic .....                                                                                                            | 4.1       | UN2989 | II  | 4.1      | IB8, IP2, IP4, T3, TP33 | None      | 212 ..... | 240 ..... | 15 kg     | 50 kg     | B  | 34.    |
|                                                                                                                                          |           |        | III | 4.1      | IB8, IP3, T1, TP33      | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | B  | 34.    |
| Lead picrate (dry) .....                                                                                                                 | Forbidden |        |     |          |                         |           |           |           |           |           |    |        |
| Lead styphnate (dry) .....                                                                                                               | Forbidden |        |     |          |                         |           |           |           |           |           |    |        |
| Lead styphnate, wetted or Lead trinitroresorcinate, wetted with not less than 20 percent water or mixture of alcohol and water, by mass. | 1.1A      | UN0130 | II  | 1.1A     | 111, 117                | None      | 62 .....  | None      | Forbidden | Forbidden | 12 | .....  |
| Lead sulfate with more than 3 percent free acid.                                                                                         | 8         | UN1794 | II  | 8        | IB8, IP2, IP4, T3, TP33 | 154 ..... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | A  | .....  |
| Lead trinitroresorcinate, see Lead styphnate, etc.                                                                                       |           |        |     |          |                         |           |           |           |           |           |    |        |
| Life-saving appliances, not self inflating containing dangerous goods as equipment.                                                      | 9         | UN3072 |     | None     |                         | None      | 219 ..... | None      | No limit  | No limit  | A  | .....  |
| Life-saving appliances, self inflating.                                                                                                  | 9         | UN2990 |     | None     |                         | None      | 219 ..... | None      | No limit  | No limit  | A  | .....  |
| Lighters containing flammable gas.                                                                                                       | 2.1       | UN1057 |     | 2.1      | 168                     | 21,308    | 21,308    | None      | 1 kg      | 15 kg     | B  | 40     |
| Lighters, new or empty, purged of all residual fuel and vapors.                                                                          |           |        |     |          | 168                     |           |           |           |           |           |    |        |
| Lighters, non-pressurized, containing flammable liquid.                                                                                  | 3         | NA1057 | II  | 3        | 168                     | 21        | None      | None      | Forbidden | Forbidden | B  | 40     |
| Lighter refills containing flammable gas not exceeding 4 fluid ounces (7.22 cubic inches) and 65 grams of flammable gas.                 | 2.1       | UN1057 |     | 2.1      | 169                     | 306       | 306       | None      | 1 kg      | 15 kg     | B  | 40     |
| Lighter replacement cartridges containing liquefied petroleum gases see Lighter refills containing flammable gas. Etc.                   |           |        |     |          |                         |           |           |           |           |           |    |        |
| Lighters, fuse .....                                                                                                                     | 1.4S      | UN0131 | II  | 1.4S     |                         | None      | 62 .....  | None      | 25 kg     | 100 kg    | 05 | .....  |
| Lime, unslaked, see Calcium oxide.                                                                                                       |           |        |     |          |                         |           |           |           |           |           |    |        |
| Liquefied gas, flammable, n.o.s.                                                                                                         | 2.1       | UN3161 |     | 2.1      | T50                     | 306       | 304       | 314, 315. | Forbidden | 150 kg    | D  | 40     |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                         | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes  | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|-------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|--------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                     |                            |                            |       |              |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                     |                            |                            |       |              |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| G        | Liquefied gas, n.o.s. ....                                                          | 2.2                        | UN3163                     | ..... | 2.2 ....     | T50                              | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | A                | .....  |
| G        | Liquefied gas, oxidizing, n.o.s. ..                                                 | 2.2                        | UN3157                     | ..... | 2.2, 5.1.    | A14                              | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | D                | .....  |
| G I      | Liquefied gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone A.</i>            | 2.3                        | UN3308                     | ..... | 2.3, 8       | 1                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40     |
| G I      | Liquefied gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone B.</i>            | 2.3                        | UN3308                     | ..... | 2.3, 8       | 2, B9, B14                       | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40     |
| G I      | Liquefied gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone C.</i>            | 2.3                        | UN3308                     | ..... | 2.3, 8       | 3, B14                           | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40     |
| G I      | Liquefied gas, toxic, corrosive, n.o.s. <i>Inhalation Hazard Zone D.</i>            | 2.3                        | UN3308                     | ..... | 2.3, 8       | 4                                | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40     |
| G I      | Liquefied gas, toxic, flammable, corrosive, n.o.s. <i>Inhalation Hazard Zone A.</i> | 2.3                        | UN3309                     | ..... | 2.3, 2.1, 8. | 1                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 17, 40 |
| G I      | Liquefied gas toxic, flammable, corrosive, n.o.s. <i>Inhalation Hazard Zone B.</i>  | 2.3                        | UN3309                     | ..... | 2.3, 2.1, 8. | 2, B9, B14                       | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 17, 40 |
| G I      | Liquefied gas, toxic, flammable, corrosive, n.o.s. <i>Inhalation Hazard Zone C.</i> | 2.3                        | UN3309                     | ..... | 2.3, 2.1, 8. | 3, B14                           | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 17, 40 |
| G I      | Liquefied gas, toxic, flammable, corrosive, n.o.s. <i>Inhalation Hazard Zone D.</i> | 2.3                        | UN3309                     | ..... | 2.3, 2.1, 8. | 4                                | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 17, 40 |
| G        | Liquefied gas, toxic, flammable, n.o.s. <i>Inhalation Hazard Zone A.</i>            | 2.3                        | UN3160                     | ..... | 2.3, 2.1.    | 1                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40     |
| G        | Liquefied gas, toxic, flammable, n.o.s. <i>Inhalation Hazard Zone B.</i>            | 2.3                        | UN3160                     | ..... | 2.3, 2.1.    | 2, B9, B14                       | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40     |
| G        | Liquefied gas, toxic, flammable, n.o.s. <i>Inhalation Hazard Zone C.</i>            | 2.3                        | UN3160                     | ..... | 2.3, 2.1.    | 3, B14                           | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40     |
| G        | Liquefied gas, toxic, flammable, n.o.s. <i>Inhalation Hazard Zone D.</i>            | 2.3                        | UN3160                     | ..... | 2.3, 2.1.    | 4                                | None ....             | 304 ..... | 314, 315. | Forbidden                                       | Forbidden             | D                | 40     |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|     |                                                                                     |       |        |       |              |                         |           |           |           |           |           |       |            |
|-----|-------------------------------------------------------------------------------------|-------|--------|-------|--------------|-------------------------|-----------|-----------|-----------|-----------|-----------|-------|------------|
| G   | Liquefied gas, toxic, n.o.s. <i>Inhalation Hazard Zone A.</i>                       | 2.3   | UN3162 | ..... | 2.3 .....    | 1                       | None .... | 192 ..... | 245 ..... | Forbidden | Forbidden | D     | 40         |
| G   | Liquefied gas, toxic, n.o.s. <i>Inhalation Hazard Zone B.</i>                       | 2.3   | UN3162 | ..... | 2.3 .....    | 2, B9, B14              | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40         |
| G   | Liquefied gas, toxic, n.o.s. <i>Inhalation Hazard Zone C.</i>                       | 2.3   | UN3162 | ..... | 2.3 .....    | 3, B14                  | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40         |
| G   | Liquefied gas, toxic, n.o.s. <i>Inhalation Hazard Zone D.</i>                       | 2.3   | UN3162 | ..... | 2.3 .....    | 4                       | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40         |
| G I | Liquefied gas, toxic, oxidizing, corrosive, n.o.s. <i>Inhalation Hazard Zone A.</i> | 2.3   | UN3310 | ..... | 2.3, 5.1, 8. | 1                       | None .... | 192 ..... | 245 ..... | Forbidden | Forbidden | D     | 40, 89, 90 |
| G I | Liquefied gas, toxic, oxidizing, corrosive, n.o.s. <i>Inhalation Hazard Zone B.</i> | 2.3   | UN3310 | ..... | 2.3, 5.1, 8. | 2, B9, B14              | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40, 89, 90 |
| G I | Liquefied gas, toxic, oxidizing, corrosive, n.o.s. <i>Inhalation Hazard Zone C.</i> | 2.3   | UN3310 | ..... | 2.3, 5.1, 8. | 3, B14                  | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40, 89, 90 |
| G I | Liquefied gas, toxic, oxidizing, corrosive, n.o.s. <i>Inhalation Hazard Zone D.</i> | 2.3   | UN3310 | ..... | 2.3, 5.1, 8. | 4                       | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40, 89, 90 |
| G   | Liquefied gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone A.</i>            | 2.3   | UN3307 | ..... | 2.3, 5.1.    | 1                       | None .... | 192 ..... | 245 ..... | Forbidden | Forbidden | D     | 40         |
| G   | Liquefied gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone B.</i>            | 2.3   | UN3307 | ..... | 2.3, 5.1.    | 2, B9, B14              | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40         |
| G   | Liquefied gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone C.</i>            | 2.3   | UN3307 | ..... | 2.3, 5.1.    | 3, B14                  | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40         |
| G   | Liquefied gas, toxic, oxidizing, n.o.s. <i>Inhalation Hazard Zone D.</i>            | 2.3   | UN3307 | ..... | 2.3, 5.1.    | 4                       | None .... | 304 ..... | 314, 315. | Forbidden | Forbidden | D     | 40         |
|     | Liquefied gases, <i>non-flammable charged with nitrogen, carbon dioxide or air.</i> | 2.2   | UN1058 | ..... | 2.2 .....    |                         | 306 ..... | 304 ..... | None .... | 75 kg     | 150 kg    | A     | .....      |
|     | <i>Liquefied hydrocarbon gas, see Hydrocarbon gas mixture, liquefied, n.o.s..</i>   | ..... |        | ..... | .....        |                         | .....     | .....     | .....     | .....     | .....     | ..... | .....      |
|     | <i>Liquefied natural gas, see Methane, etc. (UN 1972).</i>                          | ..... |        | ..... | .....        |                         | .....     | .....     | .....     | .....     | .....     | ..... | .....      |
|     | <i>Liquefied petroleum gas see Petroleum gases, liquefied.</i>                      | ..... |        | ..... | .....        |                         | .....     | .....     | .....     | .....     | .....     | ..... | .....      |
|     | Lithium .....                                                                       | 4.3   | UN1415 | I     | 4.3 .....    | A7, A19, IB4, IP1, N45  | None .... | 211 ..... | 244 ..... | Forbidden | 15 kg     | E     | 52         |
|     | <i>Lithium acetylide ethylene-diamine complex, see Water reactive solid etc.</i>    | ..... |        | ..... | .....        |                         | .....     | .....     | .....     | .....     | .....     | ..... | .....      |
|     | Lithium alkyls, liquid .....                                                        | 4.2   | UN2445 | I     | 4.2, 4.3.    | 173, B11, T21, TP2, TP7 | None .... | 181 ..... | 244 ..... | Forbidden | Forbidden | D     | .....      |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                                                                                                                                   | Hazard class or Division | Identification Numbers | PG    | Label Codes | Special provisions (§ 172.102)          | (8)                   |           |           | (9)                                             |                     | (10)           |                                 |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|------------------------|-------|-------------|-----------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|---------------------|----------------|---------------------------------|
|          |                                                                                                                                                                                              |                          |                        |       |             |                                         | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |                                 |
|          |                                                                                                                                                                                              |                          |                        |       |             |                                         | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Loca-tion      | Other                           |
|          | Lithium alkyls, solid .....                                                                                                                                                                  | 4.2                      | UN3433                 | I     | 4.2, 4.3.   | 173, B11, T21, TP7, TP33                | None ....             | 181 ..... | 244 ..... | Forbidden                                       | Forbidden           | D              | .....                           |
|          | Lithium aluminum hydride .....                                                                                                                                                               | 4.3                      | UN1410                 | I     | 4.3 .....   | A19                                     | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg               | E              | 52                              |
|          | Lithium aluminum hydride, ethereal.                                                                                                                                                          | 4.3                      | UN1411                 | I     | 4.3, 3      | A2, A3, A11, N34                        | None ....             | 201 ..... | 244 ..... | Forbidden                                       | 1 L                 | D              | 40                              |
|          | Lithium batteries, contained in equipment.                                                                                                                                                   | 9                        | UN3091                 | II    | 9 .....     | 29, 188, 189, 190, A54, A55, A101, A104 | 185 .....             | 185 ..... | None .... | See A101, A104.                                 | 35 kg               | A              | .....                           |
|          | Lithium batteries packed with equipment.                                                                                                                                                     | 9                        | UN3091                 | II    | 9 .....     | 29, 188, 189, 190, A54, A55, A101, A103 | 185 .....             | 185 ..... | None .... | See A101, A103.                                 | 35 kg gross         | A              | .....                           |
|          | Lithium battery .....                                                                                                                                                                        | 9                        | UN3090                 | II    | 9 .....     | 29, 188, 189, 190, A54, A55, A100.      | 185 .....             | 185 ..... | None .... | See A100                                        | 35 kg gross         | A              | .....                           |
|          | Lithium borohydride .....                                                                                                                                                                    | 4.3                      | UN1413                 | I     | 4.3 .....   | A19, N40                                | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg               | E              | 52                              |
|          | Lithium ferrosilicon .....                                                                                                                                                                   | 4.3                      | UN2830                 | II    | 4.3 .....   | A19, IB7, IP2, T3, TP33                 | 151 .....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg               | E              | 40, 85, 103                     |
|          | Lithium hydride .....                                                                                                                                                                        | 4.3                      | UN1414                 | I     | 4.3 .....   | A19, N40                                | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg               | E              | 52                              |
|          | Lithium hydride, fused solid .....                                                                                                                                                           | 4.3                      | UN2805                 | II    | 4.3 .....   | A8, A19, A20, IB4, T3, TP33             | 151 .....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg               | E              | 52                              |
|          | Lithium hydroxide .....                                                                                                                                                                      | 8                        | UN2680                 | II    | 8 .....     | IB8, IP2, IP4, T3, TP33                 | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg               | A              | 52.                             |
|          | Lithium hydroxide, solution .....                                                                                                                                                            | 8                        | UN2679                 | II    | 8 .....     | B2, IB2, T7, TP2                        | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                | A              | 29, 52.                         |
|          |                                                                                                                                                                                              |                          |                        | III   | 8 .....     | IB3, T4, TP2                            | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                | A              | 29, 52, 96.                     |
|          | Lithium hypochlorite, dry with more than 39% available chlorine (8.8% available oxygen) or Lithium hypochlorite mixtures, dry with more than 39% available chlorine (8.8% available oxygen). | 5.1                      | UN1471                 | II    | 5.1 .....   | A9, IB8, IP2, IP4, N34                  | 152 .....             | 212 ..... | 240 ..... | 5 kg                                            | 25 kg               | A              | 4, 48, 52, 56, 58, 69, 106, 116 |
|          | Lithium in cartridges, see Lithium.                                                                                                                                                          | .....                    | .....                  | ..... | .....       | .....                                   | .....                 | .....     | .....     | .....                                           | .....               | .....          | .....                           |
|          | Lithium nitrate .....                                                                                                                                                                        | 5.1                      | UN2722                 | III   | 5.1 .....   | A1, IB8, IP3, T1, TP33                  | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg              | A              | .....                           |
|          | Lithium nitride .....                                                                                                                                                                        | 4.3                      | UN2806                 | I     | 4.3 .....   | A19, IB4, IP1, N40                      | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg               | E              | .....                           |
|          | Lithium peroxide .....                                                                                                                                                                       | 5.1                      | UN1472                 | II    | 5.1 .....   | A9, IB6, IP2, N34, T3, TP33             | 152 .....             | 212 ..... | None .... | 5 kg                                            | 25 kg               | A              | 13, 52, 66, 75                  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                 |           |        |       |              |                                 |           |           |           |           |           |       |                           |
|-----------------------------------------------------------------------------------------------------------------|-----------|--------|-------|--------------|---------------------------------|-----------|-----------|-----------|-----------|-----------|-------|---------------------------|
| Lithium silicon .....                                                                                           | 4.3       | UN1417 | II    | 4.3 .....    | A19, A20, IB7,<br>IP2, T3, TP33 | 151 ..... | 212 ..... | 241 ..... | 15 kg     | 50 kg     | A     | 85, 103                   |
| LNG, see Methane etc. (UN 1972).                                                                                | .....     | .....  | ..... | .....        | .....                           | .....     | .....     | .....     | .....     | .....     | ..... | .....                     |
| London purple .....                                                                                             | 6.1       | UN1621 | II    | 6.1 .....    | IB8, IP2, IP4, T3,<br>TP33      | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A     | .....                     |
| LPG, see Petroleum gases, liq-<br>uefied.                                                                       | .....     | .....  | ..... | .....        | .....                           | .....     | .....     | .....     | .....     | .....     | ..... | .....                     |
| Lye, see Sodium hydroxide, so-<br>lutions.                                                                      | .....     | .....  | ..... | .....        | .....                           | .....     | .....     | .....     | .....     | .....     | ..... | .....                     |
| Magnesium alkyls .....                                                                                          | 4.2       | UN3053 | I     | 4.2,<br>4.3. | B11, T21, TP2,<br>TP7           | None .... | 181 ..... | 244 ..... | Forbidden | Forbidden | D     | 18                        |
| Magnesium aluminum<br>phosphide.                                                                                | 4.3       | UN1419 | I     | 4.3,<br>6.1. | A19, N34, N40                   | None .... | 211 ..... | 242 ..... | Forbidden | 15 kg     | E     | 40, 52,<br>85             |
| + Magnesium arsenate .....                                                                                      | 6.1       | UN1622 | II    | 6.1 .....    | IB8, IP2, IP4, T3,<br>TP33      | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A     | .....                     |
| Magnesium bisulfite solution,<br>see Bisulfites, aqueous solu-<br>tions, n.o.s..                                | .....     | .....  | ..... | .....        | .....                           | .....     | .....     | .....     | .....     | .....     | ..... | .....                     |
| Magnesium bromate .....                                                                                         | 5.1       | UN1473 | II    | 5.1 .....    | A1, IB8, IP4, T3,<br>TP33       | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A     | 56, 58                    |
| Magnesium chlorate .....                                                                                        | 5.1       | UN2723 | II    | 5.1 .....    | IB8, IP2, IP4, T3,<br>TP33      | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A     | 56, 58                    |
| Magnesium diamide .....                                                                                         | 4.2       | UN2004 | II    | 4.2 .....    | A8, A19, A20,<br>IB6, T3, TP33  | None .... | 212 ..... | 241 ..... | 15 kg     | 50 kg     | C     | .....                     |
| Magnesium diphenyl .....                                                                                        | 4.2       | UN2005 | I     | 4.2 .....    | 173, T21, TP7,<br>TP33          | None .... | 187 ..... | 244 ..... | Forbidden | Forbidden | C     | .....                     |
| Magnesium dross, wet or hot ....                                                                                | Forbidden | .....  | ..... | .....        | .....                           | .....     | .....     | .....     | .....     | .....     | ..... | .....                     |
| Magnesium fluorosilicate .....                                                                                  | 6.1       | UN2853 | III   | 6.1 .....    | IB8, IP3, T1,<br>TP33           | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A     | 52                        |
| Magnesium granules, coated,<br>particle size not less than 149<br>microns.                                      | 4.3       | UN2950 | III   | 4.3 .....    | A1, A19, IB8,<br>IP4, T1, TP33  | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | 52                        |
| Magnesium hydride .....                                                                                         | 4.3       | UN2010 | I     | 4.3 .....    | A19, N40                        | None .... | 211 ..... | 242 ..... | Forbidden | 15 kg     | E     | 52                        |
| Magnesium or Magnesium al-<br>loys with more than 50 per-<br>cent magnesium in pellets,<br>turnings or ribbons. | 4.1       | UN1869 | III   | 4.1 .....    | A1, IB8, IP3, T1,<br>TP33       | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | 39, 52,<br>53, 74,<br>101 |
| Magnesium nitrate .....                                                                                         | 5.1       | UN1474 | III   | 5.1 .....    | A1, IB8, IP3, T1,<br>TP33       | 152 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | .....                     |
| Magnesium perchlorate .....                                                                                     | 5.1       | UN1475 | II    | 5.1 .....    | IB6, IP2, T3,<br>TP33           | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A     | 56, 58                    |
| Magnesium peroxide .....                                                                                        | 5.1       | UN1476 | II    | 5.1 .....    | IB6, IP2, T3,<br>TP33           | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A     | 13, 52,<br>66, 75         |
| Magnesium phosphide .....                                                                                       | 4.3       | UN2011 | I     | 4.3,<br>6.1. | A19, N40                        | None .... | 211 ..... | None .... | Forbidden | 15 kg     | E     | 40, 52,<br>85             |
| Magnesium, powder or Magne-<br>sium alloys, powder.                                                             | 4.3       | UN1418 | I     | 4.3,<br>4.2. | A19, B56                        | None .... | 211 ..... | 244 ..... | Forbidden | 15 kg     | A     | 39, 52                    |
| .....                                                                                                           | .....     | .....  | II    | 4.3,<br>4.2. | A19, B56, IB5,<br>IP2, T3, TP33 | None .... | 212 ..... | 241 ..... | 15 kg     | 50 kg     | A     | 39, 52                    |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                                                                          | Hazard class or Division | Identification Numbers | PG  | Label Codes | Special provisions (§ 172.102)  | (8)                   |           |           | (9)                                             |                     | (10)           |         |
|----------|-------------------------------------------------------------------------------------------------------------------------------------|--------------------------|------------------------|-----|-------------|---------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|---------------------|----------------|---------|
|          |                                                                                                                                     |                          |                        |     |             |                                 | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |         |
|          |                                                                                                                                     |                          |                        |     |             |                                 | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Location       | Other   |
|          | .....                                                                                                                               | .....                    |                        | III | 4.3, 4.2.   | A19, B56, IB8, IP4, T1, TP33    | None ....             | 213 ..... | 241 ..... | 25 kg                                           | 100 kg              | A              | 39, 52  |
|          | <i>Magnesium scrap, see Magnesium, etc. (UN 1869).</i>                                                                              |                          |                        |     |             |                                 |                       |           |           |                                                 |                     |                |         |
|          | Magnesium silicide .....                                                                                                            | 4.3                      | UN2624                 | II  | 4.3 .....   | A19, A20, IB7, IP2, T3, TP33    | 151 .....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg               | B              | 85, 103 |
|          | <i>Magnetized material, see § 173.21.</i>                                                                                           |                          |                        |     |             |                                 |                       |           |           |                                                 |                     |                |         |
|          | Maleic anhydride .....                                                                                                              | 8                        | UN2215                 | III | 8 .....     | IB8, IP3, T1, TP33              | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg              | A              |         |
|          | Maleic anhydride, molten .....                                                                                                      | 8                        | UN2215                 | III | 8 .....     | T4, TP3                         | None ....             | 213 ..... | 240 ..... | Forbidden                                       | Forbidden           | A              |         |
|          | Malononitrile .....                                                                                                                 | 6.1                      | UN2647                 | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33         | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg              | A              | 12      |
|          | <i>Mancozeb (manganese ethylenebisdithiocarbamate complex with zinc) see Maneb.</i>                                                 |                          |                        |     |             |                                 |                       |           |           |                                                 |                     |                |         |
|          | Maneb or Maneb preparations with not less than 60 percent maneb.                                                                    | 4.2                      | UN2210                 | III | 4.2, 4.3.   | 57, A1, A19, IB6, T1, TP33      | None ....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg              | A              | 34      |
|          | Maneb stabilized or Maneb preparations, stabilized against self-heating.                                                            | 4.3                      | UN2968                 | III | 4.3 .....   | 54, A1, A19, IB8, IP4, T1, TP33 | 151 .....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg              | B              | 34, 52  |
|          | Manganese nitrate .....                                                                                                             | 5.1                      | UN2724                 | III | 5.1 .....   | A1, IB8, IP3, T1, TP33          | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg              | A              |         |
|          | Manganese resinate .....                                                                                                            | 4.1                      | UN1330                 | III | 4.1 .....   | A1, IB6, T1, TP33               | 151 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg              | A              |         |
|          | <i>Mannitan tetranitrate</i> .....                                                                                                  | Forbidden                |                        |     |             |                                 |                       |           |           |                                                 |                     |                |         |
|          | <i>Mannitol hexanitrate (dry)</i> .....                                                                                             | Forbidden                |                        |     |             |                                 |                       |           |           |                                                 |                     |                |         |
|          | Mannitol hexanitrate, wetted or Nitromannite, wetted with not less than 40 percent water, or mixture of alcohol and water, by mass. | 1.1D                     | UN0133                 | II  | 1.1D ..     | 121                             | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden           | 10             |         |
|          | <i>Marine pollutants, liquid or solid, n.o.s., see Environmentally hazardous substances, liquid or solid, n.o.s..</i>               |                          |                        |     |             |                                 |                       |           |           |                                                 |                     |                |         |
|          | <i>Matches, block, see Matches, 'strike anywhere'.</i>                                                                              |                          |                        |     |             |                                 |                       |           |           |                                                 |                     |                |         |
|          | Matches, fusee .....                                                                                                                | 4.1                      | UN2254                 | III | 4.1 .....   |                                 | 186 .....             | 186 ..... | None .... | Forbidden                                       | Forbidden           | A              |         |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                               |           |        |            |                               |      |      |           |           |        |           |
|-----------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|------------|-------------------------------|------|------|-----------|-----------|--------|-----------|
| Matches, safety ( <i>book, card or strike on box</i> )                                                                                        | 4.1       | UN1944 | III 4.1    | 186                           | 186  | None | 25 kg     | 100 kg    | A      |           |
| Matches, strike anywhere                                                                                                                      | 4.1       | UN1331 | III 4.1    | 186                           | 186  | None | Forbidden | Forbidden | B      |           |
| Matches, wax, Vesta                                                                                                                           | 4.1       | UN1945 | III 4.1    | 186                           | 186  | None | 25 kg     | 100 kg    | B      |           |
| <i>Matting acid, see Sulfuric acid</i>                                                                                                        |           |        |            |                               |      |      |           |           |        |           |
| Medicine, liquid, flammable, toxic, n.o.s.                                                                                                    | 3         | UN3248 | II 3, 6.1  | 36, IB2                       | 150  | 202  | None      | 1 L       | 5 L    | B 40      |
| Medicine, liquid, toxic, n.o.s.                                                                                                               | 6.1       | UN1851 | III 3, 6.1 | 36, IB3                       | 150  | 203  | None      | 5 L       | 5 L    | A         |
| Medicine, solid, toxic, n.o.s.                                                                                                                | 6.1       | UN3249 | II 6.1     | 36                            | 153  | 202  | 243       | 5 L       | 5 L    | C 40      |
|                                                                                                                                               |           |        | III 6.1    | 36                            | 153  | 203  | 241       | 5 L       | 5 L    | C 40      |
|                                                                                                                                               |           |        | II 6.1     | 36, T3, TP33                  | 153  | 212  | None      | 5 kg      | 5 kg   | C 40      |
|                                                                                                                                               |           |        | III 6.1    | 36, T1, TP33                  | 153  | 213  | None      | 5 kg      | 5 kg   | C 40      |
| <i>Mentetrahydrophthalic anhydride, see Corrosive liquids, n.o.s.</i>                                                                         |           |        |            |                               |      |      |           |           |        |           |
| Mercaptans, liquid, flammable, n.o.s. or Mercaptan mixture, liquid, flammable, n.o.s.                                                         | 3         | UN3336 | I 3        | T11, TP2                      | 150  | 201  | 243       | 1 L       | 30 L   | E 95      |
|                                                                                                                                               |           |        | II 3       | IB2, T7, TP1, TP8, TP28       | 150  | 202  | 242       | 5 L       | 60 L   | B 95      |
|                                                                                                                                               |           |        | III 3      | B1, B52, IB3, T4, TP1, TP29   | 150  | 203  | 241       | 60 L      | 220 L  | B 95      |
| Mercaptans, liquid, flammable, toxic, n.o.s. or Mercaptan mixtures, liquid, flammable, toxic, n.o.s.                                          | 3         | UN1228 | II 3, 6.1  | IB2, T11, TP2, TP27           | None | 202  | 243       | Forbidden | 60 L   | B 40, 95  |
|                                                                                                                                               |           |        | III 3, 6.1 | A6, B1, IB3, T7, TP1, TP28    | 150  | 203  | 242       | 5 L       | 220 L  | A 40, 95  |
| Mercaptans, liquid, toxic, flammable, n.o.s. or Mercaptan mixtures, liquid, toxic, flammable, n.o.s., flash point not less than 23 degrees C. | 6.1       | UN3071 | II 6.1, 3  | A6, IB2, T11, TP2, TP13, TP27 | 153  | 202  | 243       | 5 L       | 60 L   | C 40, 121 |
| 5-Mercaptotetrazol-1-acetic acid                                                                                                              | 1.4C      | UN0448 | II 1.4C    |                               | None | 62   | None      | Forbidden | 75 kg  | 09        |
| Mercuric arsenate                                                                                                                             | 6.1       | UN1623 | II 6.1     | IB8, IP2, IP4, T3, TP33       | 153  | 212  | 242       | 25 kg     | 100 kg | A         |
| Mercuric chloride                                                                                                                             | 6.1       | UN1624 | II 6.1     | IB8, IP2, IP4, T3, TP33       | 153  | 212  | 242       | 25 kg     | 100 kg | A         |
| <i>Mercuric compounds, see Mercury compounds, etc.</i>                                                                                        |           |        |            |                               |      |      |           |           |        |           |
| Mercuric nitrate                                                                                                                              | 6.1       | UN1625 | II 6.1     | IB8, IP2, IP4, N73, T3, TP33  | 153  | 212  | 242       | 25 kg     | 100 kg | A         |
| + Mercuric potassium cyanide                                                                                                                  | 6.1       | UN1626 | I 6.1      | IB7, IP1, N74, N75, T6, TP33  | None | 211  | 242       | 5 kg      | 50 kg  | A 52      |
| <i>Mercuric sulfocyanate, see Mercury thiocyanate.</i>                                                                                        |           |        |            |                               |      |      |           |           |        |           |
| <i>Mercuriol, see Mercury nucleate</i>                                                                                                        |           |        |            |                               |      |      |           |           |        |           |
| <i>Mercurous azide</i>                                                                                                                        | Forbidden |        |            |                               |      |      |           |           |        |           |
| <i>Mercurous compounds, see Mercury compounds, etc.</i>                                                                                       |           |        |            |                               |      |      |           |           |        |           |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                      | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |      | (9)                                             |                       | (10)             |        |
|----------|--------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                                  |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |      | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                                  |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| A W      | Mercurous nitrate .....                                                                          | 6.1                        | UN1627                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242  | 25 kg                                           | 100 kg                | A                | .....  |
|          | Mercury .....                                                                                    | 8                          | UN2809                     | III | 8           |                                  | 164                   | 164       | 240  | 35 kg                                           | 35 kg                 | B                | 40, 97 |
|          | Mercury acetate .....                                                                            | 6.1                        | UN1629                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242  | 25 kg                                           | 100 kg                | A                | .....  |
|          | Mercury acetylide .....                                                                          | Forbidden                  |                            |     |             |                                  |                       |           |      |                                                 |                       |                  | .....  |
|          | Mercury ammonium chloride .....                                                                  | 6.1                        | UN1630                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242  | 25 kg                                           | 100 kg                | A                | .....  |
|          | Mercury based pesticides, liquid, flammable, toxic, flash point less than 23 degrees C. ....     | 3                          | UN2778                     | I   | 3, 6.1      | T14, TP2, TP13, TP27             | None                  | 201       | 243  | Forbidden                                       | 30 L                  | B                | 40     |
|          | .....                                                                                            |                            |                            | II  | 3, 6.1      | IB2, T11, TP2, TP13, TP27        | 150                   | 202       | 243  | 1 L                                             | 60 L                  | B                | 40     |
|          | Mercury based pesticides, liquid, toxic. ....                                                    | 6.1                        | UN3012                     | I   | 6.1         | T14, TP2, TP13, TP27             | None                  | 201       | 243  | 1 L                                             | 30 L                  | B                | 40     |
|          | .....                                                                                            |                            |                            | II  | 6.1         | IB2, T11, TP2, TP13, TP27        | 153                   | 202       | 243  | 5 L                                             | 60 L                  | B                | 40     |
|          | .....                                                                                            |                            |                            | III | 6.1         | IB3, T7, TP2, TP28               | 153                   | 203       | 241  | 60 L                                            | 220 L                 | A                | 40     |
|          | Mercury based pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C. .... | 6.1                        | UN3011                     | I   | 6.1, 3      | T14, TP2, TP13, TP27             | None                  | 201       | 243  | 1 L                                             | 30 L                  | B                | 40     |
|          | .....                                                                                            |                            |                            | II  | 6.1, 3      | IB2, T11, TP2, TP13, TP27        | 153                   | 202       | 243  | 5 L                                             | 60 L                  | B                | 40     |
|          | .....                                                                                            |                            |                            | III | 6.1, 3      | IB3, T7, TP2, TP28               | 153                   | 203       | 242  | 60 L                                            | 220 L                 | A                | 40     |
|          | Mercury based pesticides, solid, toxic. ....                                                     | 6.1                        | UN2777                     | I   | 6.1         | IB7, IP1, T6, TP33               | None                  | 211       | 242  | 5 kg                                            | 50 kg                 | A                | 40     |
|          | .....                                                                                            |                            |                            | II  | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242  | 25 kg                                           | 100 kg                | A                | 40     |
|          | .....                                                                                            |                            |                            | III | 6.1         | IB8, IP3, T1, TP33               | 153                   | 213       | 240  | 100 kg                                          | 200 kg                | A                | 40     |
|          | Mercury benzoate .....                                                                           | 6.1                        | UN1631                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242  | 25 kg                                           | 100 kg                | A                | .....  |
|          | Mercury bromides .....                                                                           | 6.1                        | UN1634                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33          | 153                   | 212       | 242  | 25 kg                                           | 100 kg                | A                | .....  |
|          | Mercury compounds, liquid, n.o.s.. ....                                                          | 6.1                        | UN2024                     | I   | 6.1         |                                  | None                  | 201       | 243  | 1 L                                             | 30 L                  | B                | 40     |
|          | .....                                                                                            |                            |                            | II  | 6.1         | IB2                              | 153                   | 202       | 243  | 5 L                                             | 60 L                  | B                | 40     |
|          | .....                                                                                            |                            |                            | III | 6.1         | IB3                              | 153                   | 203       | 241  | 60 L                                            | 220 L                 | B                | 40     |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                          |           |        |         |                                   |       |       |       |           |           |       |        |
|---|----------------------------------------------------------------------------------------------------------|-----------|--------|---------|-----------------------------------|-------|-------|-------|-----------|-----------|-------|--------|
| A | Mercury compounds, solid, n.o.s..                                                                        | 6.1       | UN2025 | I 6.1   | IB7, IP1, T6, TP33                | None  | 211   | 242   | 5 kg      | 50 kg     | A     | .....  |
|   | .....                                                                                                    | .....     | .....  | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | .....                                                                                                    | .....     | .....  | III 6.1 | IB8, IP3, T1, TP33                | 153   | 213   | 240   | 100 kg    | 200 kg    | A     | .....  |
|   | Mercury contained in manufactured articles.                                                              | 8         | UN2809 | III 8   | .....                             | None  | 164   | None  | No limit  | No limit  | B     | 40, 97 |
|   | Mercury cyanide                                                                                          | 6.1       | UN1636 | II 6.1  | IB8, IP2, IP4, N74, N75, T3, TP33 | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | 52     |
|   | Mercury fulminate, wetted with not less than 20 percent water, or mixture of alcohol and water, by mass. | 1.1A      | UN0135 | II 1.1A | 111, 117                          | None  | 62    | None  | Forbidden | Forbidden | 12    | .....  |
|   | Mercury gluconate                                                                                        | 6.1       | UN1637 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mercury iodide                                                                                           | 6.1       | UN1638 | II 6.1  | IB2, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mercury iodide aquabasic ammonobasic (iodide of Millon's base).                                          | Forbidden | .....  | .....   | .....                             | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
|   | Mercury nitride                                                                                          | Forbidden | .....  | .....   | .....                             | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
|   | Mercury nucleate                                                                                         | 6.1       | UN1639 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mercury oleate                                                                                           | 6.1       | UN1640 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mercury oxide                                                                                            | 6.1       | UN1641 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mercury oxycyanide                                                                                       | Forbidden | .....  | .....   | .....                             | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| + | Mercury oxycyanide, desensitized.                                                                        | 6.1       | UN1642 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | 52, 91 |
|   | Mercury potassium iodide                                                                                 | 6.1       | UN1643 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mercury salicylate                                                                                       | 6.1       | UN1644 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mercury sulfates                                                                                         | 6.1       | UN1645 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
| G | Mercury thiocyanate                                                                                      | 6.1       | UN1646 | II 6.1  | IB8, IP2, IP4, T3, TP33           | 153   | 212   | 242   | 25 kg     | 100 kg    | A     | .....  |
|   | Mesityl oxide                                                                                            | 3         | UN1229 | III 3   | B1, IB3, T2, TP1                  | 150   | 203   | 242   | 60 L      | 220 L     | A     | .....  |
|   | Metal carbonyls, liquid, n.o.s. ....                                                                     | 6.1       | UN3281 | I 6.1   | 5, T14, TP2, TP13, TP27           | None  | 201   | 243   | 1 L       | 30 L      | B     | 40     |
| G | .....                                                                                                    | .....     | .....  | II 6.1  | IB2, T11, TP2, TP27               | 153   | 202   | 243   | 5 L       | 60 L      | B     | 40     |
|   | .....                                                                                                    | .....     | .....  | III 6.1 | IB3, T7, TP1, TP28                | 153   | 203   | 241   | 60 L      | 220 L     | A     | 40     |
|   | Metal carbonyls, solid, n.o.s. ....                                                                      | 6.1       | UN3466 | I 6.1   | IB7, IP1, T6, TP33                | None  | 211   | 242   | 5 kg      | 50 kg     | D     | 40     |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102) | (8)                   |          |      | (9)                                             |                      | (10)            |       |
|----------|-------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|---------------------------------|-----------------------|----------|------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                             |                           |                          |     |             |                                 | Packaging (§ 173.***) |          |      | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                             |                           |                          |     |             |                                 | Excep-tions           | Non-bulk | Bulk | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
|          |                                                             |                           |                          | II  | 6.1         | IB8, IP2, IP4, T3, TP33         | 153                   | 212      | 242  | 25 kg                                           | 100 kg               | B               | 40    |
|          |                                                             |                           |                          | III | 6.1         | IB8, IP3, T1, TP33              | 153                   | 213      | 240  | 100 kg                                          | 200 kg               | B               | 40    |
|          | Metal catalyst, dry                                         | 4.2                       | UN2881                   | I   | 4.2         | N34, T21, TP7, TP33             | None                  | 187      | None | Forbidden                                       | Forbidden            | C               |       |
|          |                                                             |                           |                          | II  | 4.2         | IB6, IP2, N34, T3, TP33         | None                  | 187      | 242  | Forbidden                                       | 50 kg                | C               |       |
|          |                                                             |                           |                          | III | 4.2         | IB8, IP3, N34, T1, TP33         | None                  | 187      | 241  | 25 kg                                           | 100 kg               | C               |       |
|          | Metal catalyst, wetted with a visible excess of liquid.     | 4.2                       | UN1378                   | II  | 4.2         | A2, A8, IB1, N34, T3, TP33      | None                  | 212      | None | Forbidden                                       | 50 kg                | C               |       |
|          | Metal hydrides, flammable, n.o.s..                          | 4.1                       | UN3182                   | II  | 4.1         | A1, IB4, T3, TP33               | 151                   | 212      | 240  | 15 kg                                           | 50 kg                | E               |       |
|          |                                                             |                           |                          | III | 4.1         | A1, IB4, T1, TP33               | 151                   | 213      | 240  | 25 kg                                           | 100 kg               | E               |       |
|          | Metal hydrides, water reactive, n.o.s..                     | 4.3                       | UN1409                   | I   | 4.3         | A19, N34, N40                   | None                  | 211      | 242  | Forbidden                                       | 15 kg                | D               | 52    |
|          |                                                             |                           |                          | II  | 4.3         | A19, IB4, N34, N40, T3, TP33    | 151                   | 212      | 242  | 15 kg                                           | 50 kg                | D               | 52    |
|          | Metal powder, self-heating, n.o.s..                         | 4.2                       | UN3189                   | II  | 4.2         | IB6, IP2, T3, TP33              | None                  | 212      | 241  | 15 kg                                           | 50 kg                | C               |       |
|          |                                                             |                           |                          | III | 4.2         | IB8, IP3, T1, TP33              | None                  | 213      | 241  | 25 kg                                           | 100 kg               | C               |       |
|          | Metal powders, flammable, n.o.s..                           | 4.1                       | UN3089                   | II  | 4.1         | IB8, IP2, IP4, T3, TP33         | 151                   | 212      | 240  | 15 kg                                           | 50 kg                | B               |       |
|          | Metal salts of methyl nitramine (dry).                      | Forbidden                 |                          | III | 4.1         | IB6, T1, TP33                   | 151                   | 213      | 240  | 25 kg                                           | 100 kg               | B               |       |
| G        | Metal salts of organic compounds, flammable, n.o.s..        | 4.1                       | UN3181                   | II  | 4.1         | A1, IB8, IP2, IP4, T3, TP33     | 151                   | 212      | 240  | 15 kg                                           | 50 kg                | B               | 40    |
|          |                                                             |                           |                          | III | 4.1         | A1, IB8, IP3, T1, TP33          | 151                   | 213      | 240  | 25 kg                                           | 100 kg               | B               | 40    |
|          | Metaldehyde                                                 | 4.1                       | UN1332                   | III | 4.1         | A1, IB8, IP3, T1, TP33          | 151                   | 213      | 240  | 25 kg                                           | 100 kg               | A               |       |
| G        | Metallic substance, water-reactive, n.o.s..                 | 4.3                       | UN3208                   | I   | 4.3         | A7, IB4                         | None                  | 211      | 242  | Forbidden                                       | 15 kg                | E               | 40    |
|          |                                                             |                           |                          | II  | 4.3         | A7, IB7, IP2, T3, TP33          | 151                   | 212      | 242  | 15 kg                                           | 50 kg                | E               | 40    |
|          |                                                             |                           |                          | III | 4.3         | A7, IB8, IP4, T1, TP33          | 151                   | 213      | 241  | 25 kg                                           | 100 kg               | E               | 40    |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|     |                                                                                                                                     |           |        |       |           |                                                        |       |       |           |           |           |       |            |
|-----|-------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|--------------------------------------------------------|-------|-------|-----------|-----------|-----------|-------|------------|
| G   | Metallic substance, water-reactive, self-heating, n.o.s.                                                                            | 4.3       | UN3209 | I     | 4.3, 4.2. | A7                                                     | None  | 211   | 242       | Forbidden | 15 kg     | E     | 40         |
|     | .....                                                                                                                               | .....     | .....  | II    | 4.3, 4.2. | A7, IB5, IP2, T3, TP33                                 | None  | 212   | 242       | 15 kg     | 50 kg     | E     | 40         |
|     | .....                                                                                                                               | .....     | .....  | III   | 4.3, 4.2. | A7, IB8, IP4, T1, TP33                                 | None  | 213   | 242       | 25 kg     | 100 kg    | E     | 40         |
|     | Methacrylaldehyde, stabilized                                                                                                       | 3         | UN2396 | II    | 3, 6.1    | 45, IB2, T7, TP1, TP13                                 | 150   | 202   | 243       | 1 L       | 60 L      | E     | 40         |
|     | Methacrylic acid, stabilized                                                                                                        | 8         | UN2531 | II    | 8         | IB2, T7, TP1, TP18, TP30                               | 154   | 202   | 242       | 1 L       | 30 L      | C     | 40         |
| +   | Methacrylonitrile, stabilized                                                                                                       | 3         | UN3079 | I     | 3, 6.1    | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45       | None  | 227   | 244       | Forbidden | Forbidden | D     | 12, 40, 48 |
|     | Methallyl alcohol                                                                                                                   | 3         | UN2614 | III   | 3         | B1, IB3, T2, TP1                                       | 150   | 203   | 242       | 60 L      | 220 L     | A     | .....      |
|     | Methane and hydrogen, mixtures, see Hydrogen and methane, mixtures, etc.                                                            | .....     | .....  | ..... | .....     | .....                                                  | ..... | ..... | .....     | .....     | .....     | ..... | .....      |
|     | Methane, compressed or Natural gas, compressed (with high methane content).                                                         | 2.1       | UN1971 | ..... | 2.1       | .....                                                  | 306   | 302   | 302       | Forbidden | 150 kg    | E     | 40         |
|     | Methane, refrigerated liquid (cryogenic liquid) or Natural gas, refrigerated liquid (cryogenic liquid), with high methane content). | 2.1       | UN1972 | ..... | 2.1       | T75, TP5                                               | None  | None  | 318       | Forbidden | Forbidden | D     | 40         |
|     | Methanesulfonyl chloride                                                                                                            | 6.1       | UN3246 | I     | 6.1, 8    | 2, B9, B14, B32, B74, T20, TP2, TP12, TP13, TP38, TP45 | None  | 227   | 244       | Forbidden | Forbidden | D     | 40         |
| + I | Methanol                                                                                                                            | 3         | UN1230 | II    | 3, 6.1    | IB2, T7, TP2                                           | 150   | 202   | 242       | 1 L       | 60 L      | B     | 40         |
| D   | Methanol                                                                                                                            | 3         | UN1230 | II    | 3         | IB2, T7, TP2                                           | 150   | 202   | 242       | 1 L       | 60 L      | B     | 40         |
|     | Methazoic acid                                                                                                                      | Forbidden | .....  | ..... | .....     | .....                                                  | ..... | ..... | .....     | .....     | .....     | ..... | .....      |
|     | 4-Methoxy-4-methylpentan-2-one.                                                                                                     | 3         | UN2293 | III   | 3         | B1, IB3, T2, TP1                                       | 150   | 203   | 242       | 60 L      | 220 L     | A     | .....      |
|     | 1-Methoxy-2-propanol                                                                                                                | 3         | UN3092 | III   | 3         | B1, IB3, T2, TP1                                       | 150   | 203   | 242       | 60 L      | 220 L     | A     | .....      |
| +   | Methoxymethyl isocyanate                                                                                                            | 3         | UN2605 | I     | 3, 6.1    | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44       | None  | 226   | 244       | Forbidden | Forbidden | D     | 40         |
|     | Methyl acetate                                                                                                                      | 3         | UN1231 | II    | 3         | IB2, T4, TP1                                           | 150   | 202   | 242       | 5 L       | 60 L      | B     | .....      |
|     | Methyl acetylene and propadiene mixtures, stabilized.                                                                               | 2.1       | UN1060 | ..... | 2.1       | N88, T50                                               | 306   | 304   | 314, 315. | Forbidden | 150 kg    | B     | 40         |
|     | Methyl acrylate, stabilized                                                                                                         | 3         | UN1919 | II    | 3         | IB2, T4, TP1, TP13                                     | 150   | 202   | 242       | 5 L       | 60 L      | B     | .....      |
|     | Methyl alcohol, see Methanol                                                                                                        | .....     | .....  | ..... | .....     | .....                                                  | ..... | ..... | .....     | .....     | .....     | ..... | .....      |
|     | Methyl allyl chloride                                                                                                               | 3         | UN2554 | II    | 3         | IB2, T4, TP1, TP13                                     | 150   | 202   | 242       | 5 L       | 60 L      | E     | .....      |
|     | Methyl amyl ketone, see Amyl methyl ketone.                                                                                         | .....     | .....  | ..... | .....     | .....                                                  | ..... | ..... | .....     | .....     | .....     | ..... | .....      |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                          | Hazard class or Di-vision | Identifica-tion Num-bers | PG | Label Codes | Special provi-sions (§ 172.102)                       | (8)                   |          |           | (9)                                             |                      | (10)            |             |
|----------|--------------------------------------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|----|-------------|-------------------------------------------------------|-----------------------|----------|-----------|-------------------------------------------------|----------------------|-----------------|-------------|
|          |                                                                                                                                      |                           |                          |    |             |                                                       | Packaging (§ 173.***) |          |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |             |
|          |                                                                                                                                      |                           |                          |    |             |                                                       | Excep-tions           | Non-bulk | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other       |
|          | Methyl bromide .....                                                                                                                 | 2.3                       | UN1062                   |    | 2.3         | 3, B14, N86, T50                                      | None                  | 193      | 314, 315. | Forbidden                                       | Forbidden            | D               | 40          |
|          | <i>Methyl bromide and chloropicrin mixtures with more than 2 percent chloropicrin, see Chloropicrin and methyl bromide mixtures.</i> |                           |                          |    |             |                                                       |                       |          |           |                                                 |                      |                 |             |
|          | <i>Methyl bromide and chloropicrin mixtures with not more than 2 percent chloropicrin, see Methyl bromide.</i>                       |                           |                          |    |             |                                                       |                       |          |           |                                                 |                      |                 |             |
|          | Methyl bromide and ethylene dibromide mixtures, liquid.                                                                              | 6.1                       | UN1647                   | I  | 6.1         | 2, B9, B14, B32, B74, N65, T20, TP2, TP13, TP38, TP44 | None                  | 227      | 244       | Forbidden                                       | Forbidden            | C               | 40          |
|          | Methyl bromoacetate .....                                                                                                            | 6.1                       | UN2643                   | II | 6.1         | IB2, T7, TP2                                          | 153                   | 202      | 243       | 5 L                                             | 60 L                 | D               | 40          |
|          | 2-Methylbutanal .....                                                                                                                | 3                         | UN3371                   | II | 3           | IB2, T4, TP1                                          | 150                   | 202      | 242       | 5 L                                             | 60 L                 | B               |             |
|          | 2-Methyl-1-butene .....                                                                                                              | 3                         | UN2459                   | I  | 3           | T11, TP2                                              | None                  | 201      | 243       | 1 L                                             | 30 L                 | E               |             |
|          | 2-Methyl-2-butene .....                                                                                                              | 3                         | UN2460                   | II | 3           | IB2, IP8, T7, TP1                                     | None                  | 202      | 242       | 5 L                                             | 60 L                 | E               |             |
|          | 3-Methyl-1-butene .....                                                                                                              | 3                         | UN2561                   | I  | 3           | T11, TP2                                              | None                  | 201      | 243       | 1 L                                             | 30 L                 | E               |             |
|          | Methyl tert-butyl ether .....                                                                                                        | 3                         | UN2398                   | II | 3           | IB2, T7, TP1                                          | 150                   | 202      | 242       | 5 L                                             | 60 L                 | E               |             |
|          | Methyl butyrate .....                                                                                                                | 3                         | UN1237                   | II | 3           | IB2, T4, TP1                                          | 150                   | 202      | 242       | 5 L                                             | 60 L                 | B               |             |
|          | Methyl chloride or Refrigerant gas R 40.                                                                                             | 2.1                       | UN1063                   |    | 2.1         | N86, T50                                              | 306                   | 304      | 314, 315. | 5 kg                                            | 100 kg               | D               | 40          |
|          | <i>Methyl chloride and chloropicrin mixtures, see Chloropicrin and methyl chloride mixtures.</i>                                     |                           |                          |    |             |                                                       |                       |          |           |                                                 |                      |                 |             |
|          | Methyl chloride and methylene chloride mixtures.                                                                                     | 2.1                       | UN1912                   |    | 2.1         | N86, T50                                              | 306                   | 304      | 314, 315. | Forbidden                                       | 150 kg               | D               | 40          |
|          | Methyl chloroacetate .....                                                                                                           | 6.1                       | UN2295                   | I  | 6.1, 3      | T14, TP2, TP13                                        | None                  | 201      | 243       | 1 L                                             | 30 L                 | D               |             |
|          | <i>Methyl chlorocarbonate, see Methyl chloroformate.</i>                                                                             |                           |                          |    |             |                                                       |                       |          |           |                                                 |                      |                 |             |
|          | <i>Methyl chloroform, see 1,1,1-Tri-chloroethane.</i>                                                                                |                           |                          |    |             |                                                       |                       |          |           |                                                 |                      |                 |             |
|          | Methyl chloroformate .....                                                                                                           | 6.1                       | UN1238                   | I  | 6.1, 3, 8.  | 1, B9, B14, B30, B72, N34, T22, TP2, TP13, TP38, TP44 | None                  | 226      | 244       | Forbidden                                       | Forbidden            | D               | 21, 40, 100 |
|          | Methyl chloromethyl ether .....                                                                                                      | 6.1                       | UN1239                   | I  | 6.1, 3      | 1, B9, B14, B30, B72, T22, TP2, TP38, TP44            | None                  | 226      | 244       | Forbidden                                       | Forbidden            | D               | 40          |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                     |           |        |       |           |       |                                                  |      |       |     |       |           |       |           |           |   |         |
|-----------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|-------|--------------------------------------------------|------|-------|-----|-------|-----------|-------|-----------|-----------|---|---------|
| Methyl 2-chloropropionate .....                                                                     | 3         | UN2933 | III   | 3         | ..... | B1, IB3, T2, TP1                                 | 150  | ..... | 203 | ..... | 242       | ..... | 60 L      | 220 L     | A | .....   |
| Methyl dichloroacetate .....                                                                        | 6.1       | UN2299 | III   | 6.1       | ..... | IB3, T4, TP1                                     | 153  | ..... | 203 | ..... | 241       | ..... | 60 L      | 220 L     | A | .....   |
| <i>Methyl ethyl ether, see Ethyl methyl ether.</i>                                                  | .....     |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |
| <i>Methyl ethyl ketone, see Ethyl methyl ketone.</i>                                                | .....     |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |
| <i>Methyl ethyl ketone peroxide, in solution with more than 9 percent by mass active oxygen.</i>    | Forbidden |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |
| 2-Methyl-5-ethylpyridine .....                                                                      | 6.1       | UN2300 | III   | 6.1       | ..... | IB3, T4, TP1                                     | 153  | ..... | 203 | ..... | 241       | ..... | 60 L      | 220 L     | A | .....   |
| Methyl fluoride, or Refrigerant gas R 41.                                                           | 2.1       | UN2454 | ..... | 2.1       | ..... |                                                  | 306  | ..... | 304 | ..... | 314, 315. | ..... | Forbidden | 150 kg    | E | 40      |
| Methyl formate .....                                                                                | 3         | UN1243 | I     | 3         | ..... | T11, TP2                                         | 150  | ..... | 201 | ..... | 243       | ..... | 1 L       | 30 L      | E | .....   |
| 2-Methyl-2-heptanethiol .....                                                                       | 6.1       | UN3023 | I     | 6.1, 3    | ..... | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45 | None | ..... | 227 | ..... | 244       | ..... | Forbidden | Forbidden | D | 40, 102 |
| Methyl iodide .....                                                                                 | 6.1       | UN2644 | I     | 6.1       | ..... | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45 | None | ..... | 227 | ..... | 244       | ..... | Forbidden | Forbidden | A | 12, 40  |
| Methyl isobutyl carbinol .....                                                                      | 3         | UN2053 | III   | 3         | ..... | B1, IB3, T2, TP1                                 | 150  | ..... | 203 | ..... | 242       | ..... | 60 L      | 220 L     | A | .....   |
| Methyl isobutyl ketone .....                                                                        | 3         | UN1245 | II    | 3         | ..... | IB2, T4, TP1                                     | 150  | ..... | 202 | ..... | 242       | ..... | 5 L       | 60 L      | B | .....   |
| <i>Methyl isobutyl ketone peroxide, in solution with more than 9 percent by mass active oxygen.</i> | Forbidden |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |
| Methyl isocyanate .....                                                                             | 6.1       | UN2480 | I     | 6.1, 3    | ..... | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44 | None | ..... | 226 | ..... | 244       | ..... | Forbidden | Forbidden | D | 40, 52  |
| Methyl isopropenyl ketone, stabilized.                                                              | 3         | UN1246 | II    | 3         | ..... | IB2, T4, TP1                                     | 150  | ..... | 202 | ..... | 242       | ..... | 5 L       | 60 L      | B | .....   |
| Methyl isothiocyanate .....                                                                         | 6.1       | UN2477 | I     | 6.1, 3    | ..... | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45 | None | ..... | 227 | ..... | 244       | ..... | Forbidden | Forbidden | A | .....   |
| Methyl isovalerate .....                                                                            | 3         | UN2400 | II    | 3         | ..... | IB2, T4, TP1                                     | 150  | ..... | 202 | ..... | 242       | ..... | 5 L       | 60 L      | B | .....   |
| Methyl magnesium bromide, in ethyl ether.                                                           | 4.3       | UN1928 | I     | 4.3, 3    | ..... |                                                  | None | ..... | 201 | ..... | 243       | ..... | Forbidden | 1 L       | D | .....   |
| Methyl mercaptan .....                                                                              | 2.3       | UN1064 | ..... | 2.3, 2.1. | ..... | 3, B7, B9, B14, N89, T50                         | None | ..... | 304 | ..... | 314, 315. | ..... | Forbidden | Forbidden | D | 40      |
| <i>Methyl mercaptopropionaldehyde, see 4-Thiapentanal.</i>                                          | .....     |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |
| Methyl methacrylate monomer, stabilized.                                                            | 3         | UN1247 | II    | 3         | ..... | IB2, T4, TP1                                     | 150  | ..... | 202 | ..... | 242       | ..... | 5 L       | 60 L      | B | 40      |
| Methyl nitramine (dry) .....                                                                        | Forbidden |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |
| Methyl nitrate .....                                                                                | Forbidden |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |
| Methyl nitrite .....                                                                                | Forbidden |        |       |           | ..... |                                                  |      |       |     |       |           |       |           |           |   | .....   |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                         | Hazard class or Division | Identification Numbers | PG  | Label Codes | Special provisions (§ 172.102)                                   | (8)                   |           |           | (9)                                             |                     | (10)           |          |
|----------|------------------------------------------------------------------------------------|--------------------------|------------------------|-----|-------------|------------------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|---------------------|----------------|----------|
|          |                                                                                    |                          |                        |     |             |                                                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |          |
|          |                                                                                    |                          |                        |     |             |                                                                  | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Loca-tion      | Other    |
|          | <i>Methyl norbornene dicarboxylic anhydride, see Corrosive liquids, n.o.s..</i>    |                          |                        |     |             |                                                                  |                       |           |           |                                                 |                     |                |          |
|          | Methyl orthosilicate .....                                                         | 6.1                      | UN2606                 | I   | 6.1, 3      | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45                 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden           | E              | 40       |
| D        | Methyl phosphonic dichloride ....                                                  | 6.1                      | NA9206                 | I   | 6.1, 8      | 2, B9, B14, B32, B74, N34, N43, T20, TP4, TP12, TP13, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden           | C              |          |
|          | <i>Methyl phosphonothioic dichloride, anhydrous, see Corrosive liquid, n.o.s..</i> |                          |                        |     |             |                                                                  |                       |           |           |                                                 |                     |                |          |
| D        | Methyl phosphonous dichloride, pyrophoric liquid.                                  | 6.1                      | NA2845                 | I   | 6.1, 4.2.   | 2, B9, B14, B16, B32, B74, T20, TP4, TP12, TP13, TP38, TP45      | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden           | D              | 18       |
|          | <i>Methyl picric acid (heavy metal salts of).</i>                                  | Forbidden                |                        |     |             |                                                                  |                       |           |           |                                                 |                     |                |          |
|          | Methyl propionate .....                                                            | 3                        | UN1248                 | II  | 3 .....     | IB2, T4, TP1                                                     | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              |          |
|          | Methyl propyl ether .....                                                          | 3                        | UN2612                 | II  | 3 .....     | IB2, IP8, T7, TP2                                                | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | E              | 40       |
|          | Methyl propyl ketone .....                                                         | 3                        | UN1249                 | II  | 3 .....     | IB2, T4, TP1                                                     | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              |          |
|          | <i>Methyl sulfate, see Dimethyl sulfate.</i>                                       |                          |                        |     |             |                                                                  |                       |           |           |                                                 |                     |                |          |
|          | <i>Methyl sulfide, see Dimethyl sulfide.</i>                                       |                          |                        |     |             |                                                                  |                       |           |           |                                                 |                     |                |          |
|          | Methyl trichloroacetate .....                                                      | 6.1                      | UN2533                 | III | 6.1 .....   | IB3, T4, TP1                                                     | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L               | A              |          |
|          | <i>Methyl trimethylol methane trinitrate.</i>                                      | Forbidden                |                        |     |             |                                                                  |                       |           |           |                                                 |                     |                |          |
|          | Methyl vinyl ketone, stabilized ...                                                | 6.1                      | UN1251                 | I   | 6.1, 3, 8.  | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44                 | None ....             | 226 ..... | 244 ..... | Forbidden                                       | Forbidden           | B              | 40       |
|          | Methylal .....                                                                     | 3                        | UN1234                 | II  | 3 .....     | IB2, IP8, T7, TP2                                                | None ....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | E              |          |
|          | Methylamine, anhydrous .....                                                       | 2.1                      | UN1061                 |     | 2.1 .....   | N87, T50                                                         | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg              | B              | 40       |
|          | Methylamine, aqueous solution                                                      | 3                        | UN1235                 | II  | 3, 8 ....   | B1, IB2, T7, TP1                                                 | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                 | E              | 52, 135. |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                |           |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
|------------------------------------------------|-----------|--------|-----|------------|----------------------------------------------------------------|------|-----|-----------|-----------|-----------|---|--|--|--|--|--|--|------------------------|
| Methylamine dinitramine and dry salts thereof. | Forbidden |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| Methylamine nitroform .....                    | Forbidden |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| Methylamine perchlorate (dry) ...              | Forbidden |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| Methylamyl acetate .....                       | 3         | UN1233 | III | 3          | B1, IB3, T2, TP1                                               | 150  | 203 | 242       | 60 L      | 220 L     | A |  |  |  |  |  |  |                        |
| N-Methylaniline .....                          | 6.1       | UN2294 | III | 6.1        | IB3, T4, TP1                                                   | 153  | 203 | 241       | 60 L      | 220 L     | A |  |  |  |  |  |  |                        |
| alpha-Methylbenzyl alcohol, liq- uid.          | 6.1       | UN2937 | III | 6.1        | IB3, T4, TP1                                                   | 153  | 203 | 241       | 60 L      | 220 L     | A |  |  |  |  |  |  |                        |
| alpha-Methylbenzyl alcohol, solid.             | 6.1       | UN3438 | III | 6.1        | IB8, IP3, T1, TP33                                             | 153  | 213 | 240       | 100 kg    | 200 kg    | A |  |  |  |  |  |  |                        |
| 3-Methylbutan-2-one .....                      | 3         | UN2397 | II  | 3          | IB2, T4, TP1                                                   | 150  | 202 | 242       | 5 L       | 60 L      | B |  |  |  |  |  |  |                        |
| N-Methylbutylamine .....                       | 3         | UN2945 | II  | 3, 8       | IB2, T7, TP1                                                   | 150  | 202 | 243       | 1 L       | 5 L       | B |  |  |  |  |  |  | 40                     |
| Methylchlorosilane .....                       | 2.3       | UN2534 |     | 2.3,       | 2, B9, B14, N34                                                | None | 226 | 314, 315. | Forbidden | Forbidden | D |  |  |  |  |  |  | 17, 40                 |
|                                                |           |        |     | 2.1, 8.    |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| Methylcyclohexane .....                        | 3         | UN2296 | II  | 3          | B1, IB2, T4, TP1                                               | 150  | 202 | 242       | 5 L       | 60 L      | B |  |  |  |  |  |  |                        |
| Methylcyclohexanols, flammable                 | 3         | UN2617 | III | 3          | B1, IB3, T2, TP1                                               | 150  | 203 | 242       | 60 L      | 220 L     | A |  |  |  |  |  |  |                        |
| Methylcyclohexanone .....                      | 3         | UN2297 | III | 3          | B1, IB3, T2, TP1                                               | 150  | 203 | 242       | 60 L      | 220 L     | A |  |  |  |  |  |  |                        |
| Methylcyclopentane .....                       | 3         | UN2298 | II  | 3          | IB2, T4, TP1                                                   | 150  | 202 | 242       | 5 L       | 60 L      | B |  |  |  |  |  |  |                        |
| D Methylchloroarsine .....                     | 6.1       | NA1556 | I   | 6.1        | 2, T20, TP4, TP12, TP13, TP38, TP45                            | None | 192 | None      | Forbidden | Forbidden | D |  |  |  |  |  |  | 40                     |
| Methylchlorosilane .....                       | 4.3       | UN1242 | I   | 4.3, 8, 3. | A2, A3, A7, B6, B77, N34, T10, TP2, TP7, TP13                  | None | 201 | 243       | Forbidden | 1 L       | D |  |  |  |  |  |  | 21, 28, 40, 49, 100    |
| Methylene chloride, see Dichloromethane.       |           |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| Methylene glycol dinitrate .....               | Forbidden |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| 2-Methylfuran .....                            | 3         | UN2301 | II  | 3          | IB2, T4, TP1                                                   | 150  | 202 | 242       | 5 L       | 60 L      | E |  |  |  |  |  |  |                        |
| a-Methylglucoside tetranitrate ....            | Forbidden |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| a-Methylglycerol trinitrate .....              | Forbidden |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| 5-Methylhexan-2-one .....                      | 3         | UN2302 | III | 3          | B1, IB3, T2, TP1                                               | 150  | 203 | 242       | 60 L      | 220 L     | A |  |  |  |  |  |  |                        |
| Methylhydrazine .....                          | 6.1       | UN1244 | I   | 6.1, 3, 8. | 1, B7, B9, B14, B30, B72, B77, N34, T22, TP2, TP13, TP38, TP44 | None | 226 | 244       | Forbidden | Forbidden | D |  |  |  |  |  |  | 21, 40, 49, 52 and 100 |
| 4-Methylmorpholine or n-methylmorpholine.      | 3         | UN2535 | II  | 3, 8       | B6, IB2, T7, TP1                                               | 150  | 202 | 243       | 1 L       | 5 L       | B |  |  |  |  |  |  | 40                     |
| Methylpentadienes .....                        | 3         | UN2461 | II  | 3          | IB2, T4, TP1                                                   | 150  | 202 | 242       | 5 L       | 60 L      | E |  |  |  |  |  |  |                        |
| 2-Methylpentan-2-ol .....                      | 3         | UN2560 | III | 3          | B1, IB3, T2, TP1                                               | 150  | 203 | 242       | 60 L      | 220 L     | A |  |  |  |  |  |  |                        |
| Methylpentanes, see Hexanes ..                 |           |        |     |            |                                                                |      |     |           |           |           |   |  |  |  |  |  |  |                        |
| Methylphenyldichlorosilane .....               | 8         | UN2437 | II  | 8          | IB2, T7, TP2, TP13                                             | None | 202 | 242       | 1 L       | 30 L      | C |  |  |  |  |  |  | 40.                    |
| 1-Methylpiperidine .....                       | 3         | UN2399 | II  | 3, 8       | IB2, T7, TP1                                                   | 150  | 202 | 243       | 1 L       | 5 L       | B |  |  |  |  |  |  | 52.                    |
| Methyltetrahydrofuran .....                    | 3         | UN2536 | II  | 3          | IB2, T4, TP1                                                   | 150  | 202 | 242       | 5 L       | 60 L      | B |  |  |  |  |  |  |                        |
| Methyltrichlorosilane .....                    | 3         | UN1250 | I   | 3, 8       | A7, B6, B77, N34, T11, TP2, TP13                               | None | 201 | 243       | Forbidden | 2.5 L     | B |  |  |  |  |  |  | 40                     |
| alpha-Methylvaleraldehyde .....                | 3         | UN2367 | II  | 3          | B1, IB2, T4, TP1                                               | 150  | 202 | 242       | 5 L       | 60 L      | B |  |  |  |  |  |  |                        |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                      | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102)  | (8)                   |           |           | (9)                                             |                      | (10)            |         |
|----------|----------------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|---------|
|          |                                                                                  |                           |                          |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |         |
|          |                                                                                  |                           |                          |     |             |                                  | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other   |
|          | <i>Mine rescue equipment con-taining carbon dioxide, see Carbon dioxide.</i>     | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | <i>Mines with bursting charge</i> .....                                          | 1.1F                      | UN0136                   | II  | 1.1F ...    |                                  | .....                 | 62 .....  | None ...  | Forbidden                                       | Forbidden            | 08              | .....   |
|          | <i>Mines with bursting charge</i> .....                                          | 1.1D                      | UN0137                   | II  | 1.1D ..     |                                  | .....                 | 62 .....  | None ...  | Forbidden                                       | Forbidden            | 03              | .....   |
|          | <i>Mines with bursting charge</i> .....                                          | 1.2D                      | UN0138                   | II  | 1.2D ..     |                                  | .....                 | 62 .....  | None ...  | Forbidden                                       | Forbidden            | 03              | .....   |
|          | <i>Mines with bursting charge</i> .....                                          | 1.2F                      | UN0294                   | II  | 1.2F ...    |                                  | .....                 | 62 .....  | None ...  | Forbidden                                       | Forbidden            | 08              | .....   |
|          | <i>Mixed acid, see Nitrating acid, mixtures etc.</i>                             | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | <i>Mobility aids, see Battery powered equipment or Battery powered vehicle'.</i> | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
| D        | Model rocket motor .....                                                         | 1.4C                      | NA0276                   | II  | 1.4C ..     | 51                               | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                | 06              | .....   |
| D        | Model rocket motor .....                                                         | 1.4S                      | NA0323                   | II  | 1.4S ...    | 51                               | None ....             | 62 .....  | None .... | 25 kg                                           | 100 kg               | 05              | .....   |
|          | Molybdenum pentachloride .....                                                   | 8                         | UN2508                   | III | 8 .....     | IB8, IP3, T1, TP33               | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | C               | 40      |
|          | <i>Monochloroacetone (unstabilized).</i>                                         | Forbidden                 |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | <i>Monochloroethylene, see Vinyl chloride, stabilized.</i>                       | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | <i>Monoethanolamine, see Ethanolamine, solutions.</i>                            | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | <i>Monoethylamine, see Ethylamine.</i>                                           | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | Morpholine .....                                                                 | 8                         | UN2054                   | I   | 8, 3 ....   | A6, T10, TP2                     | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                | A               | .....   |
|          | <i>Morpholine, aqueous, mixture, see Corrosive liquids, n.o.s..</i>              | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | Motor fuel anti-knock compounds see Motor fuel anti-knock mixtures.              | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
| +        | Motor fuel anti-knock mixtures ...                                               | 6.1                       | UN1649                   | I   | 6.1 .....   | 14, 151, B9, B90, T14, TP2, TP13 | None ....             | 201 ..... | 244 ..... | Forbidden                                       | 30 L                 | D               | 25, 40. |
|          | Motor spirit, see Gasoline .....                                                 | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | <i>Muriatic acid, see Hydrochloric acid.</i>                                     | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | Musk xylene, see 5-tert-Butyl-2,4,6-trinitro-m-xylene.                           | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |
|          | <i>Naphtha see Petroleum distillates n.o.s..</i>                                 | .....                     |                          |     | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                |                 | .....   |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                  |           |        |     |        |                                   |      |     |      |           |           |   |        |
|----------------------------------------------------------------------------------|-----------|--------|-----|--------|-----------------------------------|------|-----|------|-----------|-----------|---|--------|
| Naphthalene, crude or Naphthalene, refined.                                      | 4.1       | UN1334 | III | 4.1    | A1, IB8, IP3, T1, TP33            | 151  | 213 | 240  | 25 kg     | 100 kg    | A |        |
| Naphthalene diozonide                                                            | Forbidden |        |     |        |                                   |      |     |      |           |           |   |        |
| beta-Naphthylamine, solid                                                        | 6.1       | UN1650 | II  | 6.1    | IB8, IP2, IP4, T3, TP33           | 153  | 212 | 242  | 25 kg     | 100 kg    | A |        |
| beta-Naphthylamine solution                                                      | 6.1       | UN3411 | II  | 6.1    | IB2, T7, TP2                      | 153  | 202 | 243  | 5 L       | 60 L      | A |        |
| alpha-Naphthylamine                                                              | 6.1       | UN2077 | III | 6.1    | IB2, T7, TP2                      | 153  | 203 | 241  | 60 L      | 220 L     | A |        |
| Naphthalene, molten                                                              | 4.1       | UN2304 | III | 6.1    | IB8, IP3, T1, TP33                | 153  | 213 | 240  | 100 kg    | 200 kg    | A |        |
| Naphthylamineperchlorate                                                         | Forbidden |        |     |        |                                   |      |     |      |           |           |   |        |
| Naphthylthiourea                                                                 | 6.1       | UN1651 | II  | 4.1    | IB1, T1, TP3                      | 151  | 213 | 241  | Forbidden | Forbidden | C |        |
| Naphthylurea                                                                     | 6.1       | UN1652 | II  | 6.1    | IB8, IP2, IP4, T3, TP33           | 153  | 212 | 242  | 25 kg     | 100 kg    | A |        |
| Natural gases (with high methane content), see Methane, etc. (UN 1971, UN 1972). |           |        |     |        |                                   |      |     |      |           |           |   |        |
| Neohexane, see Hexanes                                                           |           |        |     |        |                                   |      |     |      |           |           |   |        |
| Neon, compressed                                                                 | 2.2       | UN1065 |     | 2.2    |                                   | 306  | 302 | 302  | 75 kg     | 150 kg    | A |        |
| Neon, refrigerated liquid (cryogenic liquid).                                    | 2.2       | UN1913 |     | 2.2    | T75, TP5                          | 320  | 316 | None | 50 kg     | 500 kg    | B |        |
| New explosive or explosive device, see §§ 173.51 and 173.56.                     |           |        |     |        |                                   |      |     |      |           |           |   |        |
| Nickel carbonyl                                                                  | 6.1       | UN1259 | I   | 6.1, 3 | 1                                 | None | 198 | None | Forbidden | Forbidden | D | 18, 40 |
| Nickel cyanide                                                                   | 6.1       | UN1653 | II  | 6.1    | IB8, IP2, IP4, N74, N75, T3, TP33 | 153  | 212 | 242  | 25 kg     | 100 kg    | A | 52     |
| Nickel nitrate                                                                   | 5.1       | UN2725 | III | 5.1    | A1, IB8, IP3, T1, TP33            | 152  | 213 | 240  | 25 kg     | 100 kg    | A |        |
| Nickel nitrite                                                                   | 5.1       | UN2726 | III | 5.1    | A1, IB8, IP3, T1, TP33            | 152  | 213 | 240  | 25 kg     | 100 kg    | A | 56, 58 |
| Nickel picrate                                                                   | Forbidden |        |     |        |                                   |      |     |      |           |           |   |        |
| Nicotine                                                                         | 6.1       | UN1654 | II  | 6.1    | IB2                               | 153  | 202 | 243  | 5 L       | 60 L      | A |        |
| Nicotine compounds, liquid, n.o.s. or Nicotine preparations, liquid, n.o.s..     | 6.1       | UN3144 | I   | 6.1    | A4                                | None | 201 | 243  | 1 L       | 30 L      | B | 40     |
|                                                                                  |           |        | II  | 6.1    | IB2, T11, TP2, TP27               | 153  | 202 | 243  | 5 L       | 60 L      | B | 40     |
|                                                                                  |           |        | III | 6.1    | IB3, T7, TP1, TP28                | 153  | 203 | 241  | 60 L      | 220 L     | B | 40     |
| Nicotine compounds, solid, n.o.s. or Nicotine preparations, solid, n.o.s..       | 6.1       | UN1655 | I   | 6.1    | IB7, IP1, T6, TP33                | None | 211 | 242  | 5 kg      | 50 kg     | B |        |
|                                                                                  |           |        | II  | 6.1    | IB8, IP2, IP4, T3, TP33           | 153  | 212 | 242  | 25 kg     | 100 kg    | A |        |
|                                                                                  |           |        | III | 6.1    | IB8, IP3, T1, TP33                | 153  | 213 | 240  | 100 kg    | 200 kg    | A |        |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names               | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102) | (8)                   |          |      | (9)                                             |                      | (10)            |             |
|----------|---------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|---------------------------------|-----------------------|----------|------|-------------------------------------------------|----------------------|-----------------|-------------|
|          |                                                                           |                           |                          |     |             |                                 | Packaging (§ 173.***) |          |      | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |             |
|          |                                                                           |                           |                          |     |             |                                 | Excep-tions           | Non-bulk | Bulk | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other       |
|          | Nicotine hydrochloride liquid or solution.                                | 6.1                       | UN1656                   | II  | 6.1         | IB2                             | 153                   | 202      | 243  | 5 L                                             | 60 L                 | A               | .....       |
|          | Nicotine hydrochloride, solid                                             | 6.1                       | UN3444                   | III | 6.1         | IB3                             | 153                   | 203      | 241  | 60 L                                            | 220 L                | A               | .....       |
|          | Nicotine salicylate                                                       | 6.1                       | UN1657                   | II  | 6.1         | IB8, IP2, IP4, T3, TP33         | 153                   | 212      | 242  | 25 kg                                           | 100 kg               | A               | .....       |
|          | Nicotine sulfate solution                                                 | 6.1                       | UN1658                   | II  | 6.1         | IB8, IP2, IP4, T3, TP33         | 153                   | 212      | 242  | 25 kg                                           | 100 kg               | A               | .....       |
|          | Nicotine sulphate, solid                                                  | 6.1                       | UN3445                   | III | 6.1         | IB2, T7, TP2                    | 153                   | 202      | 243  | 5 L                                             | 60 L                 | A               | .....       |
|          | Nicotine tartrate                                                         | 6.1                       | UN1659                   | II  | 6.1         | IB3, T7, TP2                    | 153                   | 203      | 241  | 60 L                                            | 220 L                | A               | .....       |
|          | Nitrated paper (unstable)                                                 | Forbidden                 |                          | II  | 6.1         | IB8, IP2, IP4, T3, TP33         | 153                   | 212      | 242  | 25 kg                                           | 100 kg               | A               | .....       |
|          | Nitrates, inorganic, aqueous solution, n.o.s..                            | 5.1                       | UN3218                   | III | 5.1         | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 25 kg                                           | 100 kg               | A               | .....       |
|          | Nitrates, inorganic, n.o.s.                                               | 5.1                       | UN1477                   | II  | 5.1         | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58, 133 |
|          | Nitrates of diazonium compounds.                                          | Forbidden                 |                          | III | 5.1         | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58, 133 |
|          | Nitrating acid mixtures, spent with more than 50 percent nitric acid.     | 8                         | UN1826                   | I   | 8, 5.1      | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitrating acid mixtures spent with not more than 50 percent nitric acid.  | 8                         | UN1826                   | II  | 8           | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitrating acid mixtures with more than 50 percent nitric acid.            | 8                         | UN1796                   | I   | 8, 5.1      | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitrating acid mixtures with not more than 50 percent nitric acid.        | 8                         | UN1796                   | II  | 8           | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitric acid other than red fuming, with more than 70 percent nitric acid. | 8                         | UN2031                   | I   | 8, 5.1      | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitrating acid mixtures, spent with more than 50 percent nitric acid.     | 8                         | UN1826                   | I   | 8, 5.1      | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitrating acid mixtures spent with not more than 50 percent nitric acid.  | 8                         | UN1826                   | II  | 8           | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitrating acid mixtures with more than 50 percent nitric acid.            | 8                         | UN1796                   | I   | 8, 5.1      | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitrating acid mixtures with not more than 50 percent nitric acid.        | 8                         | UN1796                   | II  | 8           | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |
|          | Nitric acid other than red fuming, with more than 70 percent nitric acid. | 8                         | UN2031                   | I   | 8, 5.1      | IB8, IP2, IP4, T3, TP33         | 152                   | 212      | 240  | 5 kg                                            | 25 kg                | A               | 56, 58      |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                      |           |        |       |              |       |                                                   |      |       |     |       |      |       |           |           |   |                          |
|---|------------------------------------------------------------------------------------------------------|-----------|--------|-------|--------------|-------|---------------------------------------------------|------|-------|-----|-------|------|-------|-----------|-----------|---|--------------------------|
|   | Nitric acid <i>other than red fuming with not more than 20 percent nitric acid.</i>                  | 8         | UN2031 | II    | 8            | ..... | A6, B2, B47, B53, IB2, T8, TP2, TP12              | None | ....  | 158 | ..... | 242  | ..... | 1 L       | 30 L      | D |                          |
|   | Nitric acid <i>other than red fuming, with not more than 70 percent nitric acid.</i>                 | 8         | UN2031 | II    | 8            | ..... | A6, B2, B47, B53, IB2, T8, TP2, TP12              | None | ....  | 158 | ..... | 242  | ..... | Forbidden | 30 L      | D | 44, 66, 89, 90, 110, 111 |
| + | Nitric acid, red fuming .....                                                                        | 8         | UN2032 | I     | 8, 5.1, 6.1. |       | 2, B9, B32, B74, T20, TP2, TP12, TP13, TP38, TP45 | None | ....  | 227 | ..... | 244  | ..... | Forbidden | Forbidden | D | 40, 66, 74, 89, 90       |
|   | Nitric oxide, compressed .....                                                                       | 2.3       | UN1660 | ..... | 2.3, 5.1, 8. |       | 1, B37, B46, B50, B60, B77                        | None | ....  | 337 | ..... | None | ....  | Forbidden | Forbidden | D | 40, 89, 90               |
|   | Nitric oxide and dinitrogen tetroxide mixtures <i>or</i> Nitric oxide and nitrogen dioxide mixtures. | 2.3       | UN1975 | ..... | 2.3, 5.1, 8. |       | 1, B7, B9, B14, B45, B46, B61, B66, B67, B77      | None | ....  | 337 | ..... | None | ....  | Forbidden | Forbidden | D | 40, 89, 90               |
| G | Nitriles, flammable, toxic, n.o.s.                                                                   | 3         | UN3273 | I     | 3, 6.1       |       | T14, TP2, TP13, TP27                              | None | ....  | 201 | ..... | 243  | ..... | Forbidden | 30 L      | E | 40, 52                   |
|   | .....                                                                                                |           |        | II    | 3, 6.1       |       | IB2, T11, TP2, TP13, TP27                         | 150  | ..... | 202 | ..... | 243  | ..... | 1 L       | 60 L      | B | 40, 52                   |
| G | Nitriles, toxic, flammable, n.o.s.                                                                   | 6.1       | UN3275 | I     | 6.1, 3       |       | 5, T14, TP2, TP13, TP27                           | None | ....  | 201 | ..... | 243  | ..... | 1 L       | 30 L      | B | 40, 52                   |
|   | .....                                                                                                |           |        | II    | 6.1, 3       |       | IB2, T11, TP2, TP13, TP27                         | 153  | ..... | 202 | ..... | 243  | ..... | 5 L       | 60 L      | B | 40, 52                   |
| G | Nitriles, toxic, liquid, n.o.s. ....                                                                 | 6.1       | UN3276 | I     | 6.1          | ..... | 5, T14, TP2, TP13, TP27                           | None | ....  | 201 | ..... | 243  | ..... | 1 L       | 30 L      | B | 52                       |
|   |                                                                                                      |           |        | II    | 6.1          | ..... | IB2, T11, TP2, TP27                               | 153  | ..... | 202 | ..... | 243  | ..... | 5 L       | 60 L      | B | 52                       |
|   |                                                                                                      |           |        | III   | 6.1          | ..... | IB3, T7, TP1, TP28                                | 153  | ..... | 203 | ..... | 241  | ..... | 60 L      | 220 L     | A | 52                       |
| G | Nitriles, toxic, solid, n.o.s. ....                                                                  | 6.1       | UN3439 | I     | 6.1          | ..... | IB7, IP1, T6, TP33                                | None | ....  | 211 | ..... | 242  | ..... | 5 kg      | 50 kg     | D | 52                       |
|   |                                                                                                      |           |        | II    | 6.1          | ..... | IB8, IP2, IP4, T3, TP33                           | 153  | ..... | 212 | ..... | 242  | ..... | 25 kg     | 100 kg    | B | 52                       |
|   |                                                                                                      |           |        | III   | 6.1          | ..... | IB8, IP3, T1, TP33                                | 153  | ..... | 213 | ..... | 240  | ..... | 100 kg    | 200 kg    | A | 52                       |
|   | Nitrites, inorganic, aqueous solution, n.o.s..                                                       | 5.1       | UN3219 | II    | 5.1          | ..... | IB1, T4, TP1                                      | 152  | ..... | 202 | ..... | 242  | ..... | 1 L       | 5 L       | B | 46, 56, 58, 133          |
|   | .....                                                                                                |           |        | III   | 5.1          | ..... | IB2, T4, TP1                                      | 152  | ..... | 203 | ..... | 241  | ..... | 2.5 L     | 30 L      | B | 46, 56, 58, 133          |
|   | Nitrites, inorganic, n.o.s. ....                                                                     | 5.1       | UN2627 | II    | 5.1          | ..... | 33, IB8, IP4, T3, TP33                            | 152  | ..... | 212 | ..... | None | ....  | 5 kg      | 25 kg     | A | 46, 56, 58, 133          |
|   | 3-Nitro-4-chlorobenzotrifluoride ..                                                                  | 6.1       | UN2307 | II    | 6.1          | ..... | IB2, T7, TP2                                      | 153  | ..... | 202 | ..... | 243  | ..... | 5 L       | 60 L      | A | 40                       |
|   | 6-Nitro-4-diazotoluene-3-sulfonic acid (dry).                                                        | Forbidden |        |       |              | ..... |                                                   |      |       |     |       |      |       |           |           |   |                          |
|   | Nitro isobutane triol trinitrate .....                                                               | Forbidden |        |       |              | ..... |                                                   |      |       |     |       |      |       |           |           |   |                          |
|   | N-Nitro-N-methylglycolamide nitrate.                                                                 | Forbidden |        |       |              | ..... |                                                   |      |       |     |       |      |       |           |           |   |                          |
|   | 2-Nitro-2-methylpropanol nitrate                                                                     | Forbidden |        |       |              | ..... |                                                   |      |       |     |       |      |       |           |           |   |                          |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                   | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                                               |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                                               |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
| +        | Nitro urea .....                                                                                                                              | 1.1D                       | UN0147                     | II  | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | ..... |
|          | <i>N-Nitroaniline</i> .....                                                                                                                   | Forbidden                  |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |       |
|          | Nitroanilines ( <i>o</i> -; <i>m</i> -; <i>p</i> -) .....                                                                                     | 6.1                        | UN1661                     | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | ..... |
|          | Nitroanisole, liquid .....                                                                                                                    | 6.1                        | UN2730                     | III | 6.1 .....   | IB3, T4, TP1                     | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Nitroanisoles, solid .....                                                                                                                    | 6.1                        | UN3458                     | III | 6.1 .....   | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | ..... |
| +        | Nitrobenzene .....                                                                                                                            | 6.1                        | UN1662                     | II  | 6.1 .....   | IB2, T7, TP2                     | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | 40    |
|          | <i>m</i> -Nitrobenzene diazonium per- chlorate.                                                                                               | Forbidden                  |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |       |
|          | Nitrobenzenesulfonic acid .....                                                                                                               | 8                          | UN2305                     | II  | 8 .....     | B2, B4, IB8, IP2, IP4, T3, TP33  | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | A                | ..... |
|          | <i>Nitrobenzol</i> , see Nitrobenzene ..                                                                                                      |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |       |
|          | 5-Nitrobenzotriazol .....                                                                                                                     | 1.1D                       | UN0385                     | II  | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | ..... |
|          | Nitrobenzotrifluorides, liquid .....                                                                                                          | 6.1                        | UN2306                     | II  | 6.1 .....   | IB2, T7, TP2                     | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | 40    |
|          | Nitrobenzotrifluorides, solid .....                                                                                                           | 6.1                        | UN3431                     | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | 40    |
|          | Nitrobromobenzenes, liquid .....                                                                                                              | 6.1                        | UN2732                     | III | 6.1 .....   | IB3, T4, TP1                     | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Nitrobromobenzenes, solid .....                                                                                                               | 6.1                        | UN3459                     | III | 6.1 .....   | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | ..... |
|          | Nitrocellulose, <i>dry or wetted with less than 25 percent water (or alcohol)</i> , by mass.                                                  | 1.1D                       | UN0340                     | II  | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 13               | 27E   |
|          | Nitrocellulose, <i>with not more than 12.6 percent, by dry mass mixture with or without plasticizer, with or without pigment</i> .            | 4.1                        | UN2557                     | II  | 4.1 .....   | 44                               | 151 .....             | 212 ..... | None .... | 1 kg                                            | 15 kg                 | D                | 28    |
|          | Nitrocellulose membrane filters, <i>with not more than 12.6% ni- trogen, by dry mass</i> .                                                    | 4.1                        | UN3270                     | II  | 4.1 .....   | 43, A1                           | 151 .....             | 212 ..... | 240 ..... | 1 kg                                            | 15 kg                 | D                | ..... |
|          | Nitrocellulose, <i>plasticized with not less than 18 percent plas- ticizing substance, by mass</i> .                                          | 1.3C                       | UN0343                     | II  | 1.3C ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | ..... |
|          | Nitrocellulose, <i>solution, flam- mable with not more than 12.6 percent nitrogen, by mass, and not more than 55 percent nitrocellulose</i> . | 3                          | UN2059                     | I   | 3 .....     | T11, TP1, TP8, TP27              | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | E                | ..... |
|          | .....                                                                                                                                         |                            |                            | II  | 3 .....     | IB2, T4, TP1, TP8                | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                              |           |        |                    |                    |           |           |           |           |           |    |            |
|----------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|--------------------|--------------------|-----------|-----------|-----------|-----------|-----------|----|------------|
| Nitrocellulose, <i>unmodified or plasticized with less than 18 percent plasticizing substance, by mass.</i>                                  | 1.1D      | UN0341 | III 3 .....        | B1, IB3, T2, TP1   | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....      |
|                                                                                                                                              |           |        | II 1.1D ..         |                    | None .... | 62 .....  | None .... | Forbidden | Forbidden | 13 | 27E        |
| Nitrocellulose, <i>wetted with not less than 25 percent alcohol, by mass.</i>                                                                | 1.3C      | UN0342 | II 1.3C ..         |                    | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | .....      |
| Nitrocellulose with alcohol with <i>not less than 25 percent alcohol by mass, and with not more than 12.6 percent nitrogen, by dry mass.</i> | 4.1       | UN2556 | II 4.1 .....       |                    | 151 ..... | 212 ..... | None .... | 1 kg      | 15 kg     | D  | 28         |
| Nitrocellulose with water with <i>not less than 25 percent water, by mass.</i>                                                               | 4.1       | UN2555 | II 4.1 .....       |                    | 151 ..... | 212 ..... | None .... | 15 kg     | 50 kg     | E  | 28         |
| Nitrochlorobenzene, <i>see</i> Chloronitrobenzenes etc.                                                                                      |           |        |                    |                    |           |           |           |           |           |    |            |
| Nitrocresols, liquid .....                                                                                                                   | 6.1       | UN3434 | III 6.1 .....      | IB3, T4, TP1       | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A  | .....      |
| Nitrocresols, solid .....                                                                                                                    | 6.1       | UN2446 | III 6.1 .....      | IB8, IP3, T1, TP33 | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A  | .....      |
| Nitroethane .....                                                                                                                            | 3         | UN2842 | III 3 .....        | B1, IB3, T2, TP1   | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A  | .....      |
| Nitroethyl nitrate .....                                                                                                                     | Forbidden |        |                    |                    |           |           |           |           |           |    |            |
| Nitroethylene polymer .....                                                                                                                  | Forbidden |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen, compressed .....                                                                                                                   | 2.2       | UN1066 | ..... 2.2 .....    |                    | 306, 307. | 302 ..... | 314, 315. | 75 kg     | 150 kg    | A  | .....      |
| Nitrogen dioxide, <i>see</i> Dinitrogen tetroxide.                                                                                           |           |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen fertilizer solution, <i>see</i> Fertilizer ammoniating solution etc.                                                                |           |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen peroxide, <i>see</i> Dinitrogen tetroxide.                                                                                          |           |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen, refrigerated liquid <i>cryogenic liquid.</i>                                                                                       | 2.2       | UN1977 | ..... 2.2 .....    | T75, TP5           | 320 ..... | 316 ..... | 318 ..... | 50 kg     | 500 kg    | D  | .....      |
| Nitrogen tetroxide and nitric oxide mixtures, <i>see</i> Nitric oxide and nitrogen tetroxide mixtures.                                       |           |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen tetroxide, <i>see</i> Dinitrogen tetroxide.                                                                                         |           |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen trichloride .....                                                                                                                   | Forbidden |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen trifluoride .....                                                                                                                   | 2.2       | UN2451 | ..... 2.2, 5.1.    |                    | None .... | 302 ..... | None .... | 75 kg     | 150 kg    | D  | 40         |
| Nitrogen triiodide .....                                                                                                                     | Forbidden |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen triiodide monoamine ....                                                                                                            | Forbidden |        |                    |                    |           |           |           |           |           |    |            |
| Nitrogen trioxide .....                                                                                                                      | 2.3       | UN2421 | ..... 2.3, 5.1, 8. | 1                  | None .... | 336 ..... | 245 ..... | Forbidden | Forbidden | D  | 40, 89, 90 |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                             | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)   | (8)                   |           |           | (9)                                             |                       | (10)             |                    |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------------------|
|          |                                                                                                                                         |                            |                            |       |             |                                    | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                    |
|          |                                                                                                                                         |                            |                            |       |             |                                    | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other              |
|          | Nitroglycerin, desensitized <i>with not less than 40 percent non-volatile water insoluble phlegmatizer, by mass.</i>                    | 1.1D                       | UN0143                     | II    | 1.1D, 6.1.  | 125                                | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 13               | 21E                |
|          | Nitroglycerin, liquid, not desensitized.                                                                                                | Forbidden                  |                            |       | .....       |                                    | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....              |
|          | Nitroglycerin mixture, desensitized, liquid, flammable, n.o.s. <i>with not more than 30 percent nitroglycerin, by mass.</i>             | 3                          | UN3343                     | ..... | 3 .....     | 129                                | None ....             | 214 ..... | None .... | Forbidden                                       | Forbidden             | D                | .....              |
|          | Nitroglycerin mixture, desensitized, liquid, n.o.s. <i>with not more than 30% nitroglycerin, by mass.</i>                               | 3                          | UN3357                     | II    | 3 .....     | 142                                | None ....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | E                | .....              |
|          | Nitroglycerin mixture, desensitized, solid, n.o.s. <i>with more than 2 percent but not more than 10 percent nitroglycerin, by mass.</i> | 4.1                        | UN3319                     | II    | 4.1 .....   | 118                                | None ....             | None .... | None .... | Forbidden                                       | 0.5 kg                | E                | .....              |
|          | Nitroglycerin, solution in alcohol, <i>with more than 1 percent but not more than 5 percent nitroglycerin.</i>                          | 3                          | UN3064                     | II    | 3 .....     | N8                                 | None ....             | 202 ..... | None .... | Forbidden                                       | 5 L                   | E                | .....              |
|          | Nitroglycerin, solution in alcohol, <i>with more than 1 percent but not more than 10 percent nitroglycerin.</i>                         | 1.1D                       | UN0144                     | II    | 1.1D ..     |                                    | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | 21E                |
|          | Nitroglycerin solution in alcohol <i>with not more than 1 percent nitroglycerin.</i>                                                    | 3                          | UN1204                     | II    | 3 .....     | IB2, N34                           | 150 .....             | 202 ..... | None .... | 5 L                                             | 60 L                  | B                | .....              |
|          | Nitroguanidine nitrate .....                                                                                                            | Forbidden                  |                            |       | .....       |                                    | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....              |
|          | Nitroguanidine or Picrite, dry or wetted <i>with less than 20 percent water, by mass.</i>                                               | 1.1D                       | UN0282                     | II    | 1.1D ..     |                                    | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | .....              |
|          | Nitroguanidine, wetted or Picrite, wetted <i>with not less than 20 percent water, by mass.</i>                                          | 4.1                        | UN1336                     | I     | 4.1 .....   | 23, A8, A19, A20, N41              | None ....             | 211 ..... | None .... | 1 kg                                            | 15 kg                 | E                | 28                 |
|          | 1-Nitrohydantoin .....                                                                                                                  | Forbidden                  |                            |       | .....       |                                    | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....              |
|          | Nitrohydrochloric acid .....                                                                                                            | 8                          | UN1798                     | I     | 8 .....     | A3, B10, N41, T10, TP2, TP12, TP13 | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 2.5 L                 | D                | 40, 66, 74, 89, 90 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                |           |        |     |           |                                         |      |     |           |           |           |    |                    |
|------------------------------------------------------------------------------------------------|-----------|--------|-----|-----------|-----------------------------------------|------|-----|-----------|-----------|-----------|----|--------------------|
| Nitromannite (dry) .....                                                                       | Forbidden |        |     |           |                                         |      |     |           |           |           |    |                    |
| Nitromannite, wetted, see Mannitol hexanitrate, etc. ....                                      |           |        |     |           |                                         |      |     |           |           |           |    |                    |
| Nitromethane .....                                                                             | 3         | UN1261 | II  | 3         |                                         | 150  | 202 | None      | Forbidden | 60 L      | A  |                    |
| Nitromuriatic acid, see Nitrohydrochloric acid. ....                                           |           |        |     |           |                                         |      |     |           |           |           |    |                    |
| Nitronaphthalene .....                                                                         | 4.1       | UN2538 | III | 4.1       | A1, IB8, IP3, T1, TP33                  | 151  | 213 | 240       | 25 kg     | 100 kg    | A  |                    |
| Nitrophenols (o-; m-; p-) .....                                                                | 6.1       | UN1663 | III | 6.1       | IB8, IP3, T1, TP33                      | 153  | 213 | 240       | 100 kg    | 200 kg    | A  |                    |
| m-Nitrophenyldinitro methane ....                                                              | Forbidden |        |     |           |                                         |      |     |           |           |           |    |                    |
| Nitropropanes .....                                                                            | 3         | UN2608 | III | 3         | B1, IB3, T2, TP1                        | 150  | 203 | 242       | 60 L      | 220 L     | A  |                    |
| p-Nitrosodimethylaniline .....                                                                 | 4.2       | UN1369 | II  | 4.2       | A19, A20, IB6, IP2, N34, T3, TP33       | None | 212 | 241       | 15 kg     | 50 kg     | D  | 34                 |
| Nitrostarch, dry or wetted with less than 20 percent water, by mass. ....                      | 1.1D      | UN0146 | II  | 1.1D      |                                         | None | 62  | None      | Forbidden | Forbidden | 10 |                    |
| Nitrostarch, wetted with not less than 20 percent water, by mass. ....                         | 4.1       | UN1337 | I   | 4.1       | 23, A8, A19, A20, N41                   | None | 211 | None      | 1 kg      | 15 kg     | D  | 28                 |
| Nitrosugars (dry) .....                                                                        | Forbidden |        |     |           |                                         |      |     |           |           |           |    |                    |
| Nitrosyl chloride .....                                                                        | 2.3       | UN1069 |     | 2.3, 8    | 3, B14                                  | None | 304 | 314, 315. | Forbidden | Forbidden | D  | 40                 |
| Nitrosylsulfuric acid, liquid .....                                                            | 8         | UN2308 | II  | 8         | A3, A6, A7, B2, IB2, N34, T8, TP2, TP12 | 154  | 202 | 242       | 1 L       | 30 L      | D  | 40, 66, 74, 89, 90 |
| Nitrosylsulphuric acid, solid .....                                                            | 8         | UN3456 | II  | 8         | IB8, IP2, IP4, T3, TP33                 | 154  | 212 | 240       | 15 kg     | 50 kg     | D  | 40, 66, 74, 89, 90 |
| Nitrotoluenes, liquid .....                                                                    | 6.1       | UN1664 | II  | 6.1       | IB2, T7, TP2                            | 153  | 202 | 243       | 5 L       | 60 L      | A  |                    |
| Nitrotoluenes, solid .....                                                                     | 6.1       | UN3446 | II  | 6.1       | IB8, IP2, IP4, T3, TP33                 | 153  | 212 | 242       | 25 kg     | 100 kg    | A  |                    |
| Nitrotoluidines (mono) .....                                                                   | 6.1       | UN2660 | III | 6.1       | IB8, IP3, T1, TP33                      | 153  | 213 | 240       | 100 kg    | 200 kg    | A  |                    |
| Nitrotriazolone or NTO .....                                                                   | 1.1D      | UN0490 | II  | 1.1D      |                                         | None | 62  | None      | Forbidden | Forbidden | 10 |                    |
| Nitrous oxide and carbon dioxide mixtures, see Carbon dioxide and nitrous oxide mixtures. .... |           |        |     |           |                                         |      |     |           |           |           |    |                    |
| Nitrous oxide .....                                                                            | 2.2       | UN1070 |     | 2.2, 5.1. | A14                                     | 306  | 304 | 314, 315. | 75 kg     | 150 kg    | A  | 40                 |
| Nitrous oxide, refrigerated liquid .....                                                       | 2.2       | UN2201 |     | 2.2, 5.1. | B6, T75, TP5, TP22                      | None | 304 | 314, 315. | Forbidden | Forbidden | B  | 40                 |
| Nitroxylenes, liquid .....                                                                     | 6.1       | UN1665 | II  | 6.1       | IB2, T7, TP2                            | 153  | 202 | 243       | 5 L       | 60 L      | A  |                    |
| Nitroxylenes, solid .....                                                                      | 6.1       | UN3447 | II  | 6.1       | IB8, IP2, IP4, T3, TP33                 | 153  | 212 | 242       | 25 kg     | 100 kg    | A  |                    |
| Nitroxylol, see Nitroxylenes .....                                                             |           |        |     |           |                                         |      |     |           |           |           |    |                    |
| Nonanes .....                                                                                  | 3         | UN1920 | III | 3         | B1, IB3, T2, TP1                        | 150  | 203 | 242       | 60 L      | 220 L     | A  |                    |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                           | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)    | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|---------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|-------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                       |                            |                            |     |             |                                     | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                       |                            |                            |     |             |                                     | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
|          | <i>Non-flammable gas, n.o.s., see Compressed gas, etc. or Liq- uiefied gas, etc.</i>  |                            |                            |     |             |                                     |                       |           |           |                                                 |                       |                  |       |
|          | <i>Nonliquefied gases, see Com- pressed gases, etc.</i>                               |                            |                            |     |             |                                     |                       |           |           |                                                 |                       |                  |       |
|          | <i>Nonliquefied hydrocarbon gas, see Hydrocarbon gas mixture, compressed, n.o.s..</i> |                            |                            |     |             |                                     |                       |           |           |                                                 |                       |                  |       |
|          | Nonyltrichlorosilane .....                                                            | 8                          | UN1799                     | II  | 8           | A7, B2, B6, IB2, N34, T7, TP2, TP13 | None                  | 202       | 242       | Forbidden                                       | 30 L                  | C                | 40    |
|          | <i>Nordhausen acid, see Sulfuric acid, fuming etc.</i>                                |                            |                            |     |             |                                     |                       |           |           |                                                 |                       |                  |       |
|          | <i>2,5-Norbornadiene, stabilized, see Bicyclo 2,2,1 hepta-2,5- diene, stabilized.</i> |                            |                            |     |             |                                     |                       |           |           |                                                 |                       |                  |       |
|          | Octadecyltrichlorosilane .....                                                        | 8                          | UN1800                     | II  | 8           | A7, B2, B6, IB2, N34, T7, TP2, TP13 | None                  | 202       | 242       | Forbidden                                       | 30 L                  | C                | 40    |
|          | Octadiene .....                                                                       | 3                          | UN2309                     | II  | 3           | B1, IB2, T4, TP1                    | 150                   | 202       | 242       | 5 L                                             | 60 L                  | B                |       |
|          | <i>1,7-Octadine-3,5-diyne-1,8- dimethoxy-9-octadecynoic acid.</i>                     | Forbidden                  |                            |     |             |                                     |                       |           |           |                                                 |                       |                  |       |
|          | Octafluorobut-2-ene or Refrig- erant gas R 1318.                                      | 2.2                        | UN2422                     |     | 2.2         |                                     | None                  | 304       | 314, 315. | 75 kg                                           | 150 kg                | A                |       |
|          | Octafluorocyclobutane, or Re- frigerant gas RC 318.                                   | 2.2                        | UN1976                     |     | 2.2         | T50                                 | None                  | 304       | 314, 315. | 75 kg                                           | 150 kg                | A                |       |
|          | Octafluoropropane or Refrigerant gas R 218.                                           | 2.2                        | UN2424                     |     | 2.2         | T50                                 | None                  | 304       | 314, 315. | 75 kg                                           | 150 kg                | A                |       |
|          | Octanes .....                                                                         | 3                          | UN1262                     | II  | 3           | IB2, T4, TP1                        | 150                   | 202       | 242       | 5 L                                             | 60 L                  | B                |       |
|          | Octogen, etc., see Cyclotetramethylene tetranitramine, etc..                          |                            |                            |     |             |                                     |                       |           |           |                                                 |                       |                  |       |
|          | Octolite or Octol, dry or wetted with less than 15 percent water, by mass.            | 1.1D                       | UN0266                     | II  | 1.1D        |                                     | None                  | 62        | None      | Forbidden                                       | Forbidden             | 10               |       |
|          | Octonal .....                                                                         | 1.1D                       | UN0496                     |     | 1.1D        |                                     | None                  | 62        | None      | Forbidden                                       | Forbidden             | 10               |       |
|          | Octyl aldehydes .....                                                                 | 3                          | UN1191                     | III | 3           | B1, IB3, T2, TP1                    | 150                   | 203       | 242       | 60 L                                            | 220 L                 | A                |       |
|          | Octyltrichlorosilane .....                                                            | 8                          | UN1801                     | II  | 8           | A7, B2, B6, IB2, N34, T7, TP2, TP13 | None                  | 202       | 242       | Forbidden                                       | 30 L                  | C                | 40    |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                          |           |        |       |              |      |           |           |              |           |           |   |                   |
|---|----------------------------------------------------------|-----------|--------|-------|--------------|------|-----------|-----------|--------------|-----------|-----------|---|-------------------|
|   | Oil gas, compressed .....                                | 2.3       | UN1071 | ..... | 2.3,<br>2.1. | 6    | None .... | 304 ..... | 314,<br>315. | Forbidden | 25 kg     | D | 40                |
|   | <i>Oleum, see Sulfuric acid, fuming</i>                  | .....     |        | ..... | .....        |      | .....     | .....     | .....        | .....     | .....     |   | .....             |
|   | <i>Organic peroxide type A, liquid or solid.</i>         | Forbidden |        | ..... | .....        |      | .....     | .....     | .....        | .....     | .....     |   | .....             |
| G | Organic peroxide type B, liquid                          | 5.2       | UN3101 | II    | 5.2, 1       | 53   | 152 ..... | 225 ..... | None ....    | Forbidden | Forbidden | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type B, liquid, temperature controlled. | 5.2       | UN3111 | II    | 5.2, 1       | 53   | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type B, solid ..                        | 5.2       | UN3102 | II    | 5.2, 1       | 53   | 152 ..... | 225 ..... | None ....    | Forbidden | Forbidden | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type B, solid, temperature controlled.  | 5.2       | UN3112 | II    | 5.2, 1       | 53   | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type C, liquid                          | 5.2       | UN3103 | II    | 5.2 .....    |      | 152 ..... | 225 ..... | None ....    | 5 L       | 10 L      | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type C, liquid, temperature controlled. | 5.2       | UN3113 | II    | 5.2 .....    |      | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type C, solid ..                        | 5.2       | UN3104 | II    | 5.2 .....    |      | 152 ..... | 225 ..... | None ....    | 5 kg      | 10 kg     | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type C, solid, temperature controlled.  | 5.2       | UN3114 | II    | 5.2 .....    |      | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type D, liquid                          | 5.2       | UN3105 | II    | 5.2 .....    |      | 152 ..... | 225 ..... | None ....    | 5 L       | 10 L      | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type D, liquid, temperature controlled. | 5.2       | UN3115 | II    | 5.2 .....    |      | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type D, solid ..                        | 5.2       | UN3106 | II    | 5.2 .....    |      | 152 ..... | 225 ..... | None ....    | 5 kg      | 10 kg     | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type D, solid, temperature controlled.  | 5.2       | UN3116 | II    | 5.2 .....    |      | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type E, liquid                          | 5.2       | UN3107 | II    | 5.2 .....    |      | 152 ..... | 225 ..... | None ....    | 10 L      | 25 L      | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type E, liquid, temperature controlled. | 5.2       | UN3117 | II    | 5.2 .....    |      | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type E, solid ..                        | 5.2       | UN3108 | II    | 5.2 .....    |      | 152 ..... | 225 ..... | None ....    | 10 kg     | 25 kg     | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type E, solid, temperature controlled.  | 5.2       | UN3118 | II    | 5.2 .....    |      | None .... | 225 ..... | None ....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type F, liquid ..                       | 5.2       | UN3109 | II    | 5.2 .....    | IP5  | 152 ..... | 225 ..... | 225 .....    | 10 L      | 25 L      | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type F, liquid, temperature controlled. | 5.2       | UN3119 | II    | 5.2 .....    | IP5  | None .... | 225 ..... | 225 .....    | Forbidden | Forbidden | D | 2, 40,<br>52, 53  |
| G | Organic peroxide type F, solid ...                       | 5.2       | UN3110 | II    | 5.2 .....    | TP33 | 152 ..... | 225 ..... | 225 .....    | 10 kg     | 25 kg     | D | 12, 40,<br>52, 53 |
| G | Organic peroxide type F, solid, temperature controlled.  | 5.2       | UN3120 | II    | 5.2 .....    | TP33 | None .... | 225 ..... | 225 .....    | Forbidden | Forbidden | D | 2, 52,<br>53      |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                                        | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes | Special provi-sions (§ 172.102) | (8)                   |           |           | (9)                                             |                      | (10)            |       |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|-------|-------------|---------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                                                                                                                                                                    |                           |                          |       |             |                                 | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                                                                                                                                                                    |                           |                          |       |             |                                 | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
| D        | Organic phosphate, mixed with compressed gas or Organic phosphate compound, mixed with compressed gas or Organic phosphorus compound, mixed with compressed gas. Organic pigments, self-heating .. | 2.3                       | NA1955                   | ..... | 2.3         | 3                               | None ....             | 334 ..... | None .... | Forbidden                                       | Forbidden            | D               | 40    |
|          | .....                                                                                                                                                                                              | 4.2                       | UN3313                   | II    | 4.2         | IB8, IP2, IP4, T3, TP33         | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                | C               | ..... |
|          | .....                                                                                                                                                                                              |                           |                          | III   | 4.2         | IB8, IP3, T1, TP33              | None ....             | 213 ..... | 241 ..... | 25 kg                                           | 100 kg               | C               | ..... |
| G        | Organoarsenic compound, liquid, n.o.s..                                                                                                                                                            | 6.1                       | UN3280                   | I     | 6.1         | 5, T14, TP2, TP13, TP27         | None ....             | 201 ..... | 242 ..... | 1 L                                             | 30 L                 | B               |       |
|          | .....                                                                                                                                                                                              |                           |                          | II    | 6.1         | IB2, T11, TP2, TP27             | 153 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                 | B               |       |
|          | .....                                                                                                                                                                                              |                           |                          | III   | 6.1         | IB3, T7, TP1, TP28              | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               |       |
| G        | Organoarsenic compound, solid, n.o.s..                                                                                                                                                             | 6.1                       | UN3465                   | I     | 6.1         | IB7, IP1, T6, TP33              | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                | B               | ..... |
|          | .....                                                                                                                                                                                              |                           |                          | II    | 6.1         | IB8, IP2, IP4, T3, TP33         | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | B               | ..... |
|          | .....                                                                                                                                                                                              |                           |                          | III   | 6.1         | IB8, IP3, T1, TP33              | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg               | A               | ..... |
|          | Organochlorine pesticides liquid, flammable, toxic, flash point less than 23 degrees C.                                                                                                            | 3                         | UN2762                   | I     | 3, 6.1      | T14, TP2, TP13, TP27            | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 30 L                 | B               | 40    |
|          | .....                                                                                                                                                                                              |                           |                          | II    | 3, 6.1      | IB2, T11, TP2, TP13, TP27       | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 60 L                 | B               | 40    |
|          | Organochlorine pesticides, liquid, toxic.                                                                                                                                                          | 6.1                       | UN2996                   | I     | 6.1         | T14, TP2, TP13, TP27            | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 40    |
|          | .....                                                                                                                                                                                              |                           |                          | II    | 6.1         | IB2, T11, TP2, TP13, TP27       | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | B               | 40    |
|          | .....                                                                                                                                                                                              |                           |                          | III   | 6.1         | IB3, T7, TP2, TP28              | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               | 40    |
|          | Organochlorine pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C.                                                                                                       | 6.1                       | UN2995                   | I     | 6.1, 3      | T14, TP2, TP13, TP27            | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 40    |
|          | .....                                                                                                                                                                                              |                           |                          | II    | 6.1, 3      | IB2, T11, TP2, TP13, TP27       | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | B               | 40    |
|          | .....                                                                                                                                                                                              |                           |                          | III   | 6.1, 3      | B1, IB3, T7, TP2, TP28          | 153 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                | A               | 40    |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                               |       |        |                    |                         |           |           |           |           |           |   |        |
|---|---------------------------------------------------------------|-------|--------|--------------------|-------------------------|-----------|-----------|-----------|-----------|-----------|---|--------|
|   | Organochlorine pesticides, solid, toxic.                      | 6.1   | UN2761 | I 6.1 .....        | IB7, IP1, T6, TP33      | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | A | 40     |
|   | .....                                                         | ..... |        | II 6.1 .....       | IB8, IP2, IP4, T3, TP33 | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A | 40     |
|   | .....                                                         | ..... |        | III 6.1 .....      | IB8, IP3, T1, TP33      | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A | 40     |
| G | Organometallic compound, toxic, liquid, n.o.s..               | 6.1   | UN3282 | I 6.1 .....        | T14, TP2, TP13, TP27    | None .... | 201 ..... | 242 ..... | 1 L       | 30 L      | B | .....  |
|   | .....                                                         | ..... |        | II 6.1 .....       | IB2, T11, TP2, TP27     | 153 ..... | 202 ..... | 242 ..... | 5 L       | 60 L      | B | .....  |
|   | .....                                                         | ..... |        | III 6.1 .....      | IB3, T7, TP1, TP28      | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A |        |
| G | Organometallic compound, toxic, solid, n.o.s..                | 6.1   | UN3467 | I 6.1 .....        | IB7, IP1, T6, TP33      | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | B | .....  |
|   | .....                                                         | ..... |        | II 6.1 .....       | IB8, IP2, IP4, T3, TP33 | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | B | .....  |
|   | .....                                                         | ..... |        | III 6.1 .....      | IB8, IP3, T1, TP33      | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A | .....  |
| G | Organometallic substance, liquid, pyrophoric.                 | 4.2   | UN3392 | I 4.2 .....        | B11, T21, TP2, TP7      | None .... | 181 ..... | 244 ..... | Forbidden | Forbidden | D | 143    |
| G | Organometallic substance, liquid, pyrophoric, water-reactive. | 4.2   | UN3394 | I 4.2, 4.3 .....   | B11, T21, TP2, TP7      | None .... | 181 ..... | 244 ..... | Forbidden | Forbidden | D | .....  |
| G | Organometallic substance, liquid, water-reactive.             | 4.3   | UN3398 | I 4.3 .....        | T13, TP2, TP7           | None .... | 201 ..... | 244 ..... | Forbidden | 1 L       | E | 40, 52 |
|   |                                                               |       |        | II 4.3 .....       | IB1, T7, TP2, TP7       | None .... | 202 ..... | 243 ..... | 1 L       | 5 L       | E | 40, 52 |
|   |                                                               |       |        | III 4.3 .....      | IB2, T7, TP2, TP7       | None .... | 203 ..... | 242 ..... | 5 L       | 60 L      | E | 40, 52 |
| G | Organometallic substance, liquid, water-reactive, flammable.  | 4.3   | UN3399 | I 4.3, 3 .....     | T13, TP2, TP7           | None .... | 201 ..... | 244 ..... | Forbidden | 1 L       | E | 40, 52 |
|   |                                                               |       |        | II 4.3, 3 .....    | IB1, IP2, T7, TP2, TP7  | None .... | 202 ..... | 243 ..... | 1 L       | 5 L       | E | 40, 52 |
|   |                                                               |       |        | III 4.3, 3 .....   | IB2, IP4, T7, TP2, TP7  | None .... | 203 ..... | 242 ..... | 5 L       | 60 L      | E | 40, 52 |
| G | Organometallic substance, solid, pyrophoric.                  | 4.2   | UN3391 | I 4.2 .....        | T21, TP7, TP33          | None .... | 187 ..... | 244 ..... | Forbidden | Forbidden | D |        |
| G | Organometallic substance, solid, pyrophoric, water-reactive.  | 4.2   | UN3393 | I 4.2, 4.3 .....   | B11, T21, TP7, TP33     | None .... | 187 ..... | 244 ..... | Forbidden | Forbidden | D | 52.    |
| G | Organometallic substance, solid, self-heating.                | 4.2   | UN3400 | II 4.2 .....       | IB6, T3, TP33           | None .... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | C | .....  |
|   | .....                                                         | ..... |        | III 4.2 .....      | IB8, T1, TP33           | None .... | 203 ..... | 242 ..... | 25 kg     | 100 kg    | C | .....  |
|   | Organometallic substance, solid, water-reactive.              | 4.3   | UN3395 | I 4.3 .....        | N40, T9, TP7, TP33      | None .... | 211 ..... | 242 ..... | Forbidden | Forbidden | E | 40, 52 |
| G | Organometallic substance, solid, water-reactive, flammable.   | 4.3   | UN3396 | I 4.3, 4.1 .....   | N40, T9, TP7, TP33      | None .... | 211 ..... | 242 ..... | Forbidden | Forbidden | E | 40, 52 |
|   | .....                                                         | ..... |        | II 4.3, 4.1 .....  | IB4, T3, TP33           | 151 ..... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | E | 40, 52 |
|   | .....                                                         | ..... |        | III 4.3, 4.1 ..... | IB6, T1, TP33           | 151 ..... | 213 ..... | 241 ..... | 25 kg     | 100 kg    | E | 40, 52 |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                    | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                                |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                                |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| G        | Organometallic substance, solid, water-reactive, self-heating.                                 | 4.3                        | UN3397                     | I   | 4.3,        | N40, T9, TP7, TP33               | None ....             | 211 ..... | 242 ..... | Forbidden                                       | Forbidden             | E                | 40, 52 |
|          |                                                                                                |                            |                            | II  | 4.3,        | IB4, T3, TP33                    | None ....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                 | E                | 40, 52 |
|          |                                                                                                |                            |                            | III | 4.3,        | IB6, T1, TP33                    | None ....             | 213 ..... | 241 ..... | 25 kg                                           | 100 kg                | E                | 40, 52 |
|          | Organophosphorus compound, toxic, flammable, n.o.s..                                           | 6.1                        | UN3279                     | I   | 6.1, 3      | 5, T14, TP2, TP13, TP27          | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40     |
|          |                                                                                                |                            |                            | II  | 6.1, 3      | IB2, T11, TP2, TP13, TP27        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | 40     |
|          |                                                                                                |                            |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |        |
| G        | Organophosphorus compound, toxic, liquid, n.o.s..                                              | 6.1                        | UN3278                     | I   | 6.1 .....   | 5, T14, TP2, TP13, TP27          | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | .....  |
|          |                                                                                                |                            |                            | II  | 6.1 .....   | IB2, T11, TP2, TP27              | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | .....  |
|          |                                                                                                |                            |                            | III | 6.1 .....   | IB3, T7, TP1, TP28               | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | .....  |
| G        | Organophosphorus compound, toxic, solid, n.o.s..                                               | 6.1                        | UN3464                     | I   | 6.1 .....   | IB7, IP1, T6, TP33               | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                 | B                | .....  |
|          |                                                                                                |                            |                            | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | B                | .....  |
|          |                                                                                                |                            |                            | III | 6.1 .....   | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | .....  |
|          | Organophosphorus pesticides, liquid, flammable, toxic, flash point less than 23 degrees C.     | 3                          | UN2784                     | I   | 3, 6.1      | T14, TP2, TP13, TP27             | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 30 L                  | B                | 40     |
|          |                                                                                                |                            |                            | II  | 3, 6.1      | IB2, T11, TP2, TP13, TP27        | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 60 L                  | B                | 40     |
|          | Organophosphorus pesticides, liquid, toxic.                                                    | 6.1                        | UN3018                     | I   | 6.1 .....   | N76, T14, TP2, TP13, TP27        | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40     |
|          |                                                                                                |                            |                            | II  | 6.1 .....   | IB2, N76, T11, TP2, TP13, TP27   | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | 40     |
|          |                                                                                                |                            |                            | III | 6.1 .....   | IB3, N76, T7, TP2, TP28          | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | 40     |
|          | Organophosphorus pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C. | 6.1                        | UN3017                     | I   | 6.1, 3      | N76, T14, TP2, TP13, TP27        | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40     |
|          |                                                                                                |                            |                            | II  | 6.1, 3      | IB2, N76, T11, TP2, TP13, TP27   | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | 40     |
|          |                                                                                                |                            |                            | III | 6.1, 3      | B1, IB3, N76, T7, TP2, TP28      | 153 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | 40     |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                         |       |        |            |                                         |       |       |       |           |        |       |       |
|-----------------------------------------------------------------------------------------|-------|--------|------------|-----------------------------------------|-------|-------|-------|-----------|--------|-------|-------|
| Organophosphorus pesticides, solid, toxic.                                              | 6.1   | UN2783 | I 6.1      | IB7, IP1, N77, T6, TP33                 | None  | 211   | 242   | 5 kg      | 50 kg  | A     | 40    |
| .....                                                                                   | ..... | .....  | II 6.1     | IB8, IP2, IP4, N77, T3, TP33            | 153   | 212   | 242   | 25 kg     | 100 kg | A     | 40    |
| .....                                                                                   | ..... | .....  | III 6.1    | IB8, IP3, N77, T1, TP33                 | 153   | 213   | 240   | 100 kg    | 200 kg | A     | 40    |
| Organotin compounds, liquid, n.o.s..                                                    | 6.1   | UN2788 | I 6.1      | A3, N33, N34, T14, TP2, TP13, TP27      | None  | 201   | 243   | 1 L       | 30 L   | B     | 40    |
| .....                                                                                   | ..... | .....  | II 6.1     | A3, IB2, N33, N34, T11, TP2, TP13, TP27 | 153   | 202   | 243   | 5 L       | 60 L   | A     | 40    |
| .....                                                                                   | ..... | .....  | III 6.1    | IB3, T7, TP2, TP28                      | 153   | 203   | 241   | 60 L      | 220 L  | A     | 40    |
| Organotin compounds, solid, n.o.s..                                                     | 6.1   | UN3146 | I 6.1      | A5, IB7, IP1, T6, TP33                  | None  | 211   | 242   | 5 kg      | 50 kg  | B     | 40    |
| .....                                                                                   | ..... | .....  | II 6.1     | IB8, IP2, IP4, T3, TP33                 | 153   | 212   | 242   | 25 kg     | 100 kg | A     | 40    |
| .....                                                                                   | ..... | .....  | III 6.1    | IB8, IP3, T1, TP33                      | 153   | 213   | 240   | 100 kg    | 200 kg | A     | 40    |
| Organotin pesticides, liquid, flammable, toxic, flash point less than 23 degrees C.     | 3     | UN2787 | I 3, 6.1   | T14, TP2, TP13, TP27                    | None  | 201   | 243   | Forbidden | 30 L   | B     | 40    |
| .....                                                                                   | ..... | .....  | II 3, 6.1  | IB2, T11, TP2, TP13, TP27               | 150   | 202   | 243   | 1 L       | 60 L   | B     | 40    |
| Organotin pesticides, liquid, toxic.                                                    | 6.1   | UN3020 | I 6.1      | T14, TP2, TP13, TP27                    | None  | 201   | 243   | 1 L       | 30 L   | B     | 40    |
| .....                                                                                   | ..... | .....  | II 6.1     | IB2, T11, TP2, TP13, TP27               | 153   | 202   | 243   | 5 L       | 60 L   | B     | 40    |
| .....                                                                                   | ..... | .....  | III 6.1    | IB3, T7, TP2, TP28                      | 153   | 203   | 241   | 60 L      | 220 L  | A     | 40    |
| Organotin pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C. | 6.1   | UN3019 | I 6.1, 3   | T14, TP2, TP13, TP27                    | None  | 201   | 243   | 1 L       | 30 L   | B     | 40    |
| .....                                                                                   | ..... | .....  | II 6.1, 3  | IB2, T11, TP2, TP13, TP27               | 153   | 202   | 243   | 5 L       | 60 L   | B     | 40    |
| .....                                                                                   | ..... | .....  | III 6.1, 3 | B1, IB3, T7, TP2, TP28                  | 153   | 203   | 242   | 60 L      | 220 L  | A     | 40    |
| Organotin pesticides, solid, toxic                                                      | 6.1   | UN2786 | I 6.1      | IB7, IP1, T6, TP33                      | None  | 211   | 242   | 5 kg      | 50 kg  | A     | 40    |
| .....                                                                                   | ..... | .....  | II 6.1     | IB8, IP2, IP4, T3, TP33                 | 153   | 212   | 242   | 25 kg     | 100 kg | A     | 40    |
| .....                                                                                   | ..... | .....  | III 6.1    | IB8, IP3, T1, TP33                      | 153   | 213   | 240   | 100 kg    | 200 kg | A     | 40    |
| .....                                                                                   | ..... | .....  | .....      | .....                                   | ..... | ..... | ..... | .....     | .....  | ..... | ..... |
| Orthonitroaniline, Nitroanilines etc.                                                   | see   | .....  | .....      | .....                                   | ..... | ..... | ..... | .....     | .....  | ..... | ..... |
| Osmium tetroxide                                                                        | 6.1   | UN2471 | I 6.1      | A8, IB7, IP1, N33, N34, T6, TP33        | None  | 211   | 242   | 5 kg      | 50 kg  | B     | 40    |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |                      |
|----------|-------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|----------------------|
|          |                                                             |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                      |
|          |                                                             |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                |
| D G      | Other regulated substances, liq- uid, n.o.s..               | 9                          | NA3082                     | III | 9 .....     | IB3, T2, TP1                     | 155 .....             | 203 ..... | 241 ..... | No limit                                        | No limit              | A                | .....                |
| D G      | Other regulated substances, solid, n.o.s..                  | 9                          | NA3077                     | III | 9 .....     | B54, IB8, IP2, T1, TP33 A6       | 155 .....             | 213 ..... | 240 ..... | No limit                                        | No limit              | A                | .....                |
| G        | Oxidizing liquid, corrosive, n.o.s.                         | 5.1                        | UN3098                     | I   | 5.1, 8      |                                  | None ....             | 201 ..... | 244 ..... | Forbidden                                       | 2.5 L                 | D                | 13, 56, 58, 106, 138 |
|          | .....                                                       |                            |                            | II  | 5.1, 8      | IB1                              | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | 34, 56, 58, 106, 138 |
|          | .....                                                       |                            |                            | III | 5.1, 8      | IB2                              | 152 .....             | 203 ..... | 242 ..... | 2.5 L                                           | 30 L                  | B                | 34, 56, 58, 106, 138 |
| G        | Oxidizing liquid, n.o.s. ....                               | 5.1                        | UN3139                     | I   | 5.1 ....    | 127, A2, A6                      | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 2.5 L                 | D                | 56, 58, 106, 138     |
|          | .....                                                       |                            |                            | II  | 5.1 ....    | 127, A2, IB2                     | 152 .....             | 202 ..... | 242 ..... | 1 L                                             | 5 L                   | B                | 56, 58, 106, 138     |
|          | .....                                                       |                            |                            | III | 5.1 ....    | 127, A2, IB2                     | 152 .....             | 203 ..... | 241 ..... | 2.5 L                                           | 30 L                  | B                | 56, 58, 106, 138     |
| G        | Oxidizing liquid, toxic, n.o.s. ....                        | 5.1                        | UN3099                     | I   | 5.1, 6.1.   | A6                               | None ....             | 201 ..... | 244 ..... | Forbidden                                       | 2.5 L                 | D                | 56, 58, 106, 138     |
|          | .....                                                       |                            |                            | II  | 5.1, 6.1.   | IB1                              | 152 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | 56, 58, 95, 106, 138 |
|          | .....                                                       |                            |                            | III | 5.1, 6.1.   | IB2                              | 152 .....             | 203 ..... | 242 ..... | 2.5 L                                           | 30 L                  | B                | 56, 58, 95, 106, 138 |
| G        | Oxidizing solid, corrosive, n.o.s.                          | 5.1                        | UN3085                     | I   | 5.1, 8      |                                  | None ....             | 211 ..... | 242 ..... | 1 kg                                            | 15 kg                 | D                | 13, 56, 58, 106, 138 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                                                                                         |       |        |       |              |                         |           |           |           |           |             |   |                          |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-------|--------------|-------------------------|-----------|-----------|-----------|-----------|-------------|---|--------------------------|
|   | .....                                                                                                                                                                   | ..... |        | II    | 5.1, 8       | IB6, IP2, T3, TP33      | None .... | 212 ..... | 242 ..... | 5 kg      | 25 kg       | B | 13, 34, 56, 58, 106, 138 |
|   | .....                                                                                                                                                                   | ..... |        | III   | 5.1, 8       | IB8, IP3, T1, TP33      | 152 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg      | B | 13, 34, 56, 58, 106, 138 |
| G | Oxidizing solid, flammable, n.o.s..                                                                                                                                     | 5.1   | UN3137 | I     | 5.1, 4.1.    |                         | None .... | 214 ..... | 214 ..... | Forbidden | Forbidden   |   | .....                    |
| G | Oxidizing solid, n.o.s. ....                                                                                                                                            | 5.1   | UN1479 | I     | 5.1 .....    | IB5, IP1                | None .... | 211 ..... | 242 ..... | 1 kg      | 15 kg       | D | 56, 58, 106, 138         |
|   | .....                                                                                                                                                                   | ..... |        | II    | 5.1 .....    | IB8, IP2, IP4, T3, TP33 | 152 ..... | 212 ..... | 240 ..... | 5 kg      | 25 kg       | B | 56, 58, 106, 138         |
|   | .....                                                                                                                                                                   | ..... |        | III   | 5.1 .....    | IB8, IP3, T1, TP33      | 152 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg      | B | 56, 58, 106, 138         |
| G | Oxidizing solid, self-heating, n.o.s..                                                                                                                                  | 5.1   | UN3100 | I     | 5.1, 4.2.    |                         | None .... | 214 ..... | 214 ..... | Forbidden | Forbidden   |   | .....                    |
|   | .....                                                                                                                                                                   | ..... |        | II    | 5.1, 4.2.    |                         | None .... | 214 ..... | 214 ..... | Forbidden | Forbidden   |   | .....                    |
| G | Oxidizing solid, toxic, n.o.s. ....                                                                                                                                     | 5.1   | UN3087 | I     | 5.1, 6.1.    |                         | None .... | 211 ..... | 242 ..... | 1 kg      | 15 kg       | D | 56, 58, 106, 138         |
|   | .....                                                                                                                                                                   | ..... |        | II    | 5.1, 6.1.    | IB6, IP2, T3, TP33      | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg       | B | 56, 58, 95, 106, 138     |
|   | .....                                                                                                                                                                   | ..... |        | III   | 5.1, 6.1.    | IB8, IP3, T1, TP33      | 152 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg      | B | 56, 58, 95, 106, 138     |
| G | Oxidizing solid, water-reactive, n.o.s..                                                                                                                                | 5.1   | UN3121 | ..... | 5.1, 4.3.    |                         | None .... | 214 ..... | 214 ..... | Forbidden | Forbidden   |   | .....                    |
|   | <i>Oxygen and carbon dioxide mixtures, see Carbon dioxide and oxygen mixtures.</i>                                                                                      | ..... | .....  | ..... | .....        |                         | .....     | .....     | .....     | .....     | .....       |   | .....                    |
|   | Oxygen, compressed .....                                                                                                                                                | 2.2   | UN1072 | ..... | 2.2, 5.1.    | A14                     | 306 ..... | 302 ..... | 314, 315. | 75 kg     | 150 kg      | A | .....                    |
|   | Oxygen difluoride, compressed                                                                                                                                           | 2.3   | UN2190 | ..... | 2.3, 5.1, 8. | 1, N86                  | None .... | 304 ..... | None .... | Forbidden | Forbidden   | D | 13, 40, 89, 90           |
|   | Oxygen generator, chemical ( <i>including when contained in associated equipment, e.g., passenger service units (PSUs), portable breathing equipment (PBE), etc.</i> ). | 5.1   | UN3356 | II    | 5.1 .....    | .....                   | None .... | 168 ..... | None .... | Forbidden | 25 kg gross | D | 56, 58, 69, 106          |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                             | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)  | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|-----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                                         |                            |                            |       |             |                                   | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                                         |                            |                            |       |             |                                   | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
| +        | Oxygen generator, chemical, spent.                                                                                                      | 9                          | NA3356                     | III   | 9 .....     | 61                                | None ....             | 213 ..... | None .... | Forbidden                                       | Forbidden             | A                | ..... |
|          | Oxygen, mixtures with rare gases, see Rare gases and oxygen mixtures.                                                                   | .....                      | .....                      | ..... | .....       | .....                             | .....                 | .....     | .....     | .....                                           | .....                 | .....            | ..... |
|          | Oxygen, refrigerated liquid (cryogenic liquid).                                                                                         | 2.2                        | UN1073                     | ..... | 2.2, 5.1    | T75, TP5, TP22                    | 320 .....             | 316 ..... | 318 ..... | Forbidden                                       | Forbidden             | D                | ..... |
|          | Paint including paint, lacquer, enamel, stain, shellac solutions, varnish, polish, liquid filler and liquid lacquer base.               | 3                          | UN1263                     | I     | 3 .....     | T11, TP1, TP8, TP27               | 150 .....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | E                | ..... |
|          |                                                                                                                                         |                            |                            | II    | 3 .....     | 149, B52, IB2, T4, TP1, TP8, TP28 | 150 .....             | 173 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |
|          |                                                                                                                                         |                            |                            | III   | 3 .....     | B1, B52, IB3, T2, TP1, TP29       | 150 .....             | 173 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Paint or Paint related material ...                                                                                                     | 8                          | UN3066                     | II    | 8 .....     | B2, IB2, T7, TP2, TP28            | 154 .....             | 173 ..... | 242 ..... | 1 L                                             | 30 L                  | A                | ..... |
|          |                                                                                                                                         |                            |                            | III   | 8 .....     | B52, IB3, T4, TP1, TP29           | 154 .....             | 173 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | ..... |
|          | Paint related material including paint thinning, drying, removing, or reducing compound.                                                | 3                          | UN1263                     | I     | 3 .....     | T11, TP1, TP8, TP27               | 150 .....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | E                | ..... |
|          |                                                                                                                                         |                            |                            | II    | 3 .....     | 149, B52, IB2, T4, TP1, TP8, TP28 | 150 .....             | 173 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |
|          |                                                                                                                                         |                            |                            | III   | 3 .....     | B1, B52, IB3, T2, TP1, TP29       | 150 .....             | 173 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | ..... |
|          | Paint, corrosive, flammable (including paint, lacquer, enamel, stain, shellac, varnish, polish, liquid filler and liquid lacquer base). | 8                          | UN3470                     | II    | 8, 3 ....   | IB2, T7, TP2, TP8, TP28           | 154 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40.   |
|          | Paint related material corrosive, flammable (including paint thinning or reducing compound).                                            | 8                          | UN3470                     | II    | 8, 3 ....   | IB2, T7, TP2, TP8, TP28           | 154 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40.   |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|               |                                                                                                                                                                                                                                                                                      |           |        |       |           |                         |           |           |           |           |           |       |       |
|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|-------------------------|-----------|-----------|-----------|-----------|-----------|-------|-------|
| D<br>A W<br>+ | Paint, flammable, corrosive ( <i>including paint, lacquer, enamel, stain, shellac, varnish, polish, liquid filler and liquid lacquer base</i> ).                                                                                                                                     | 3         | UN3469 | I     | 3, 8 .... | T11, TP2, TP27          | None .... | 201 ..... | 243 ..... | 0.5 L     | 2.5 L     | E     | 40.   |
|               |                                                                                                                                                                                                                                                                                      |           |        | II    | 3, 8 .... | IB2, T7, TP2, TP8, TP28 | 150 ..... | 202 ..... | 243 ..... | 1 L       | 5 L       | B     | 40.   |
|               |                                                                                                                                                                                                                                                                                      |           |        | III   | 3, 8 .... | IB3, T4, TP1, TP29      | 150 ..... | 203 ..... | 242 ..... | 5 L       | 60 L      | A     | 40.   |
|               | Paper, unsaturated oil treated incompletely dried ( <i>including carbon paper</i> ).                                                                                                                                                                                                 | 4.2       | UN1379 | III   | 4.2 ....  | IB8, IP3                | None .... | 213 ..... | 241 ..... | Forbidden | Forbidden | A     | ..... |
|               | Paraformaldehyde .....                                                                                                                                                                                                                                                               | 4.1       | UN2213 | III   | 4.1 ....  | A1, IB8, IP3, T1, TP33  | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A     | ..... |
|               | Paraldehyde .....                                                                                                                                                                                                                                                                    | 3         | UN1264 | III   | 3 .....   | B1, IB3, T2, TP1        | 150 ..... | 203 ..... | 242 ..... | 60 L      | 220 L     | A     | ..... |
|               | <i>Paranitroaniline, solid, see Nitroanilines etc.</i>                                                                                                                                                                                                                               | .....     | .....  | ..... | .....     | .....                   | .....     | .....     | .....     | .....     | .....     | ..... | ..... |
|               | Parathion and compressed gas mixture.                                                                                                                                                                                                                                                | 2.3       | NA1967 | ..... | 2.3 ....  | 3                       | None .... | 334 ..... | 245 ..... | Forbidden | Forbidden | E     | 40    |
|               | <i>Paris green, solid, see Copper acetoarsenite.</i>                                                                                                                                                                                                                                 | .....     | .....  | ..... | .....     | .....                   | .....     | .....     | .....     | .....     | .....     | ..... | ..... |
|               | PCB, <i>see</i> Polychlorinated biphenyls.                                                                                                                                                                                                                                           | .....     | .....  | ..... | .....     | .....                   | .....     | .....     | .....     | .....     | .....     | ..... | ..... |
|               | Pentaborane .....                                                                                                                                                                                                                                                                    | 4.2       | UN1380 | I     | 4.2, 6.1. | 1                       | None .... | 205 ..... | 245 ..... | Forbidden | Forbidden | D     | ..... |
|               | Pentachloroethane .....                                                                                                                                                                                                                                                              | 6.1       | UN1669 | II    | 6.1 ..... | IB2, T7, TP2            | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | A     | 40    |
|               | Pentachlorophenol .....                                                                                                                                                                                                                                                              | 6.1       | UN3155 | II    | 6.1 ..... | IB8, IP2, IP4, T3, TP33 | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A     | ..... |
|               | <i>Pentaerythrite tetranitrate (dry) ..</i>                                                                                                                                                                                                                                          | Forbidden | .....  | ..... | .....     | .....                   | .....     | .....     | .....     | .....     | .....     | ..... | ..... |
|               | Pentaerythrite tetranitrate mixture, desensitized, solid, n.o.s. with more than 10 percent but not more than 20 percent PETN, by mass.                                                                                                                                               | 4.1       | UN3344 | II    | 4.1 ....  | 118, N85                | None .... | 214 ..... | None .... | Forbidden | Forbidden | E     | ..... |
|               | Pentaerythrite tetranitrate or Pentaerythritol tetranitrate or PETN, with not less than 7 percent wax by mass.                                                                                                                                                                       | 1.1D      | UN0411 | II    | 1.1D ..   |                         | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | ..... |
|               | Pentaerythrite tetranitrate, wetted or Pentaerythritol tetranitrate, wetted, or PETN, wetted with not less than 25 percent water, by mass, or Pentaerythrite tetranitrate, or Pentaerythritol tetranitrate or PETN, desensitized with not less than 15 percent phlegmatizer by mass. | 1.1D      | UN0150 | II    | 1.1D ..   | 121                     | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10    | ..... |
|               | Pentaerythritol tetranitrate, <i>see</i> Pentaerythrite tetranitrate, <i>etc.</i>                                                                                                                                                                                                    | .....     | .....  | ..... | .....     | .....                   | .....     | .....     | .....     | .....     | .....     | ..... | ..... |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                           | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes | Special provi-sions (§ 172.102)                       | (8)                   |           |            | (9)                                             |                      | (10)            |                 |
|----------|---------------------------------------------------------------------------------------|---------------------------|--------------------------|-------|-------------|-------------------------------------------------------|-----------------------|-----------|------------|-------------------------------------------------|----------------------|-----------------|-----------------|
|          |                                                                                       |                           |                          |       |             |                                                       | Packaging (§ 173.***) |           |            | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |                 |
|          |                                                                                       |                           |                          |       |             |                                                       | Excep-tions           | Non-bulk  | Bulk       | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other           |
|          | Pentafluoroethane or Refrigerant gas R 125.                                           | 2.2                       | UN3220                   | ..... | 2.2 .....   | T50                                                   | 306 .....             | 304 ..... | 314, 315.  | 75 kg                                           | 150 kg               | A               | .....           |
|          | Pentamethylheptane .....                                                              | 3                         | UN2286                   | III   | 3 .....     | B1, IB3, T2, TP1                                      | 150 .....             | 203 ..... | 242 .....  | 60 L                                            | 220 L                | A               | .....           |
|          | Pentane-2,4-dione .....                                                               | 3                         | UN2310                   | III   | 3, 6.1      | B1, IB3, T4, TP1                                      | 150 .....             | 203 ..... | 242 .....  | 60 L                                            | 220 L                | A               | .....           |
|          | Pentanes .....                                                                        | 3                         | UN1265                   | I     | 3 .....     | T11, TP2                                              | 150 .....             | 201 ..... | 243 .....  | 1 L                                             | 30 L                 | E               | .....           |
|          | .....                                                                                 |                           |                          | II    | 3 .....     | IB2, IP8, T4, TP1                                     | 150 .....             | 202 ..... | 242 .....  | 5 L                                             | 60 L                 | E               | .....           |
|          | Pentanitroaniline (dry) .....                                                         | Forbidden                 |                          |       |             |                                                       |                       |           |            |                                                 |                      |                 |                 |
|          | Pentanols .....                                                                       | 3                         | UN1105                   | II    | 3 .....     | IB2, T4, TP1, TP29                                    | 150 .....             | 202 ..... | 242 .....  | 5 L                                             | 60 L                 | B               | .....           |
|          | .....                                                                                 |                           |                          | III   | 3 .....     | B1, B3, IB3, T2, TP1                                  | 150 .....             | 203 ..... | 242 .....  | 60 L                                            | 220 L                | A               | .....           |
|          | 1-Pentene (n-amylene) .....                                                           | 3                         | UN1108                   | I     | 3 .....     | T11, TP2                                              | 150 .....             | 201 ..... | 243 .....  | 1 L                                             | 30 L                 | E               | .....           |
|          | 1-Pentol .....                                                                        | 8                         | UN2705                   | II    | 8 .....     | B2, IB2, T7, TP2                                      | 154 .....             | 202 ..... | 242 .....  | 1 L                                             | 30 L                 | B               | 26, 27          |
|          | Pentolite, dry or wetted with less than 15 percent water, by mass.                    | 1.1D                      | UN0151                   | II    | 1.1D ..     |                                                       | None .....            | 62 .....  | None ..... | Forbidden                                       | Forbidden            | 10              | .....           |
|          | Pepper spray, see Aerosols, etc. or Self-defense spray, non-pressurized.              |                           |                          |       |             |                                                       |                       |           |            |                                                 |                      |                 |                 |
|          | Perchlorates, inorganic, aqueous solution, n.o.s..                                    | 5.1                       | UN3211                   | II    | 5.1 .....   | IB2, T4, TP1                                          | 152 .....             | 202 ..... | 242 .....  | 1 L                                             | 5 L                  | B               | 56, 58, 133     |
|          | .....                                                                                 |                           |                          | III   | 5.1 .....   | IB2, T4, TP1                                          | 152 .....             | 202 ..... | 241 .....  | 2.5 L                                           | 30 L                 | B               | 56, 58, 69, 133 |
|          | Perchlorates, inorganic, n.o.s. ...                                                   | 5.1                       | UN1481                   | II    | 5.1 .....   | IB6, IP2, T3, TP33                                    | 152 .....             | 212 ..... | 242 .....  | 5 kg                                            | 25 kg                | A               | 56, 58          |
|          | .....                                                                                 |                           |                          | III   | 5.1 .....   | IB8, IP3, T1, TP33                                    | 152 .....             | 213 ..... | 240 .....  | 25 kg                                           | 100 kg               | A               | 56, 58          |
|          | Perchloric acid, with more than 72 percent acid by mass.                              | Forbidden                 |                          |       |             |                                                       |                       |           |            |                                                 |                      |                 |                 |
|          | Perchloric acid with more than 50 percent but not more than 72 percent acid, by mass. | 5.1                       | UN1873                   | I     | 5.1, 8      | A2, A3, N41, T10, TP1, TP12                           | None .....            | 201 ..... | 243 .....  | Forbidden                                       | 2.5 L                | D               | 66              |
|          | Perchloric acid with not more than 50 percent acid by mass.                           | 8                         | UN1802                   | II    | 8, 5.1      | IB2, N41, T7, TP2                                     | None .....            | 202 ..... | 243 .....  | Forbidden                                       | 30 L                 | C               | 66              |
|          | Perchloroethylene, see Tetrachloroethylene.                                           |                           |                          |       |             |                                                       |                       |           |            |                                                 |                      |                 |                 |
|          | Perchloromethyl mercaptan .....                                                       | 6.1                       | UN1670                   | I     | 6.1 .....   | 2, B9, B14, B32, B74, N34, T20, TP2, TP13, TP38, TP45 | None .....            | 227 ..... | 244 .....  | Forbidden                                       | Forbidden            | D               | 40              |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|   |                                                                                                                                         |           |        |       |              |                                        |           |                      |              |           |           |   |                        |
|---|-----------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|--------------|----------------------------------------|-----------|----------------------|--------------|-----------|-----------|---|------------------------|
|   | Perchloryl fluoride .....                                                                                                               | 2.3       | UN3083 | ..... | 2.3,<br>5.1. | 2, B9, B14                             | None .... | 302 .....            | 314,<br>315. | Forbidden | Forbidden | D | 40                     |
|   | <i>Percussion caps, see</i> Primers,<br>cap type. ....                                                                                  |           |        |       | .....        |                                        |           |                      |              |           |           |   |                        |
|   | <i>Perfluoro-2-butene, see</i><br>Octafluorobut-2-ene. ....                                                                             |           |        |       | .....        |                                        |           |                      |              |           |           |   |                        |
|   | Perfluoro(ethyl vinyl ether) .....                                                                                                      | 2.1       | UN3154 | ..... | 2.1 .....    |                                        | 306 ..... | 302,<br>304,<br>305. | 314,<br>315. | Forbidden | 150 kg    | E | 40                     |
|   | Perfluoro(methyl vinyl ether) .....                                                                                                     | 2.1       | UN3153 | ..... | 2.1 .....    | T50                                    | 306 ..... | 302,<br>304,<br>305. | 314,<br>315. | Forbidden | 150 kg    | E | 40                     |
|   | Perfumery products <i>with flam-</i><br><i>mable solvents.</i> .....                                                                    | 3         | UN1266 | II    | 3 .....      | 149, IB2, T4,<br>TP1, TP8              | 150 ..... | 202 .....            | 242 .....    | 15 L      | 60 L      | B | .....                  |
|   | Permanganates, inorganic,<br>aqueous solution, n.o.s.. .....                                                                            | 5.1       | UN3214 | II    | 5.1 .....    | B1, IB3, T2, TP1<br>26, IB2, T4, TP1   | 150 ..... | 203 .....            | 242 .....    | 60 L      | 220 L     | A | .....                  |
|   | Permanganates, inorganic,<br>n.o.s.. .....                                                                                              | 5.1       | UN1482 | II    | 5.1 .....    | 26, A30, IB6,<br>IP2, T3, TP33         | 152 ..... | 212 .....            | 242 .....    | 5 kg      | 25 kg     | D | 56, 58,<br>133,<br>138 |
|   | .....                                                                                                                                   |           |        | III   | 5.1 .....    | 26, A30, IB8,<br>IP3, T1, TP33         | 152 ..... | 213 .....            | 240 .....    | 25 kg     | 100 kg    | D | 56, 58,<br>138         |
|   | Peroxides, inorganic, n.o.s. ....                                                                                                       | 5.1       | UN1483 | II    | 5.1 .....    | A7, A20, IB6,<br>IP2, N34, T3,<br>TP33 | None .... | 212 .....            | 242 .....    | 5 kg      | 25 kg     | A | 13, 52,<br>66, 75      |
|   | .....                                                                                                                                   |           |        | III   | 5.1 .....    | A7, A20, IB8,<br>IP3, N34, T1,<br>TP33 | 152 ..... | 213 .....            | 240 .....    | 25 kg     | 100 kg    | A | 13, 52,<br>66, 75      |
|   | <i>Peroxyacetic acid, with more</i><br><i>than 43 percent and with</i><br><i>more than 6 percent hydrogen</i><br><i>peroxide.</i> ..... | Forbidden |        |       | .....        |                                        |           |                      |              |           |           |   |                        |
|   | Persulfates, inorganic, aqueous<br>solution, n.o.s.. .....                                                                              | 5.1       | UN3216 | III   | 5.1 .....    | IB2, T4, TP1,<br>TP29                  | 152 ..... | 203 .....            | 241 .....    | 2.5 L     | 30 L      | A | 56, 133                |
|   | Persulfates, inorganic, n.o.s. ....                                                                                                     | 5.1       | UN3215 | III   | 5.1 .....    | IB8, IP3, T1,<br>TP33                  | 152 ..... | 213 .....            | 240 .....    | 25 kg     | 100 kg    | A | 56, 58                 |
| G | Pesticides, liquid, flammable,<br>toxic, <i>flash point less than 23</i><br><i>degrees C.</i> .....                                     | 3         | UN3021 | I     | 3, 6.1       | B5, T14, TP2,<br>TP13, TP27            | None .... | 201 .....            | 243 .....    | Forbidden | 30 L      | B | .....                  |
|   | .....                                                                                                                                   |           |        | II    | 3, 6.1       | IB2, T11, TP2,<br>TP13, TP27           | 150 ..... | 202 .....            | 243 .....    | 1 L       | 60 L      | B | .....                  |
| G | Pesticides, liquid, toxic, flam-<br>mable, n.o.s. <i>flash point not</i><br><i>less than 23 degrees C.</i> .....                        | 6.1       | UN2903 | I     | 6.1, 3       | T14, TP2, TP13,<br>TP27                | None .... | 201 .....            | 243 .....    | 1 L       | 30 L      | B | 40                     |
|   | .....                                                                                                                                   |           |        | II    | 6.1, 3       | IB2, T11, TP2,<br>TP13, TP27           | 153 ..... | 202 .....            | 243 .....    | 5 L       | 60 L      | B | 40                     |
|   | .....                                                                                                                                   |           |        | III   | 6.1, 3       | B1, IB3, T7, TP2                       | 153 ..... | 203 .....            | 242 .....    | 60 L      | 220 L     | A | 40                     |
| G | Pesticides, liquid, toxic, n.o.s. ....                                                                                                  | 6.1       | UN2902 | I     | 6.1 .....    | T14, TP2, TP13,<br>TP27                | None .... | 201 .....            | 243 .....    | 1 L       | 30 L      | B | 40                     |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names  | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes | Special provi-sions (§ 172.102) | (8)                   |          |           | (9)                                             |                      | (10)            |       |
|----------|--------------------------------------------------------------|---------------------------|--------------------------|-------|-------------|---------------------------------|-----------------------|----------|-----------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                              |                           |                          |       |             |                                 | Packaging (§ 173.***) |          |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                              |                           |                          |       |             |                                 | Excep-tions           | Non-bulk | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
| G        | .....                                                        | .....                     | .....                    | II    | 6.1         | IB2, T11, TP2, TP13, TP27       | 153                   | 202      | 243       | 5 L                                             | 60 L                 | B               | 40    |
|          | .....                                                        | .....                     | .....                    | III   | 6.1         | IB3, T7, TP2, TP28              | 153                   | 203      | 241       | 60 L                                            | 220 L                | A               | 40    |
|          | Pesticides, solid, toxic, n.o.s. ....                        | 6.1                       | UN2588                   | I     | 6.1         | IB7, T6, TP33                   | None                  | 211      | 242       | 5 kg                                            | 50 kg                | A               | 40    |
|          | .....                                                        | .....                     | .....                    | II    | 6.1         | IB8, IP2, IP4, T3, TP33         | 153                   | 212      | 242       | 25 kg                                           | 100 kg               | A               | 40    |
|          | .....                                                        | .....                     | .....                    | III   | 6.1         | IB8, IP3, T1, TP33              | 153                   | 213      | 240       | 100 kg                                          | 200 kg               | A               | 40    |
| D        | PETN, see Pentaerythrite tetranitrate.                       | .....                     | .....                    | ..... | .....       | .....                           | .....                 | .....    | .....     | .....                                           | .....                | .....           | ..... |
|          | PETN/TNT, see Pentolite, etc ...                             | .....                     | .....                    | ..... | .....       | .....                           | .....                 | .....    | .....     | .....                                           | .....                | .....           | ..... |
|          | Petrol, see Gasoline .....                                   | .....                     | .....                    | ..... | .....       | .....                           | .....                 | .....    | .....     | .....                                           | .....                | .....           | ..... |
|          | Petroleum crude oil .....                                    | 3                         | UN1267                   | I     | 3           | 144, T11, TP1, TP8              | 150                   | 201      | 243       | 1 L                                             | 30 L                 | E               | ..... |
|          | .....                                                        | .....                     | .....                    | II    | 3           | 144, IB2, T4, TP1, TP8          | 150                   | 202      | 242       | 5 L                                             | 60 L                 | B               | ..... |
|          | .....                                                        | .....                     | .....                    | III   | 3           | 144, B1, IB3, T2, TP1           | 150                   | 203      | 242       | 60 L                                            | 220 L                | A               | ..... |
|          | Petroleum distillates, n.o.s. or Petroleum products, n.o.s.. | 3                         | UN1268                   | I     | 3           | 144, T11, TP1, TP8              | 150                   | 201      | 243       | 1 L                                             | 30 L                 | E               | ..... |
|          | .....                                                        | .....                     | .....                    | II    | 3           | 144, IB2, T7, TP1, TP8, TP28    | 150                   | 202      | 242       | 5 L                                             | 60 L                 | B               | ..... |
|          | .....                                                        | .....                     | .....                    | III   | 3           | 144, B1, IB3, T4, TP1, TP29     | 150                   | 203      | 242       | 60 L                                            | 220 L                | A               | ..... |
|          | Petroleum gases, liquefied or Liquefied petroleum gas.       | 2.1                       | UN1075                   | ..... | 2.1         | T50                             | 306                   | 304      | 314, 315. | Forbidden                                       | 150 kg               | E               | 40    |
|          | Petroleum oil .....                                          | 3                         | NA1270                   | I     | 3           | 144, T11, TP1                   | None                  | 201      | 243       | 1 L                                             | 30 L                 | E               | ..... |
| +        | .....                                                        | .....                     | .....                    | II    | 3           | 144, IB2, T7, TP1, TP8, TP28    | 150                   | 202      | 242       | 5 L                                             | 60 L                 | B               | ..... |
|          | .....                                                        | .....                     | .....                    | III   | 3           | 144, B1, IB3, T4, TP1, TP29     | 150                   | 203      | 242       | 60 L                                            | 220 L                | A               | ..... |
|          | Phenacyl bromide .....                                       | 6.1                       | UN2645                   | II    | 6.1         | IB8, IP2, IP4, T3, TP33         | 153                   | 212      | 242       | 25 kg                                           | 100 kg               | B               | 40    |
|          | Phenetidines .....                                           | 6.1                       | UN2311                   | III   | 6.1         | IB3, T4, TP1                    | 153                   | 203      | 241       | 60 L                                            | 220 L                | A               | ..... |
|          | Phenol, molten .....                                         | 6.1                       | UN2312                   | II    | 6.1         | B14, T7, TP3                    | None                  | 202      | 243       | Forbidden                                       | Forbidden            | B               | 40    |
|          | Phenol, solid .....                                          | 6.1                       | UN1671                   | II    | 6.1         | IB8, IP2, IP4, N78, T3, TP33    | 153                   | 212      | 242       | 25 kg                                           | 100 kg               | A               | ..... |
|          | Phenol solutions .....                                       | 6.1                       | UN2821                   | II    | 6.1         | IB2, T7, TP2                    | 153                   | 202      | 243       | 5 L                                             | 60 L                 | A               | ..... |
|          | .....                                                        | .....                     | .....                    | III   | 6.1         | IB3, T4, TP1                    | 153                   | 203      | 241       | 60 L                                            | 220 L                | A               | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                   |       |        |     |        |                                                                 |      |     |     |           |           |   |                         |
|-------------------------------------------------------------------------------------------------------------------|-------|--------|-----|--------|-----------------------------------------------------------------|------|-----|-----|-----------|-----------|---|-------------------------|
| Phenolsulfonic acid, liquid .....                                                                                 | 8     | UN1803 | II  | 8      | B2, IB2, N41, T7, TP2                                           | 154  | 202 | 242 | 1 L       | 30 L      | C | 14                      |
| Phenoxyacetic acid derivative pesticide, liquid, flammable, toxic <i>flash point less than 23 degrees C.</i>      | 3     | UN3346 | I   | 3, 6.1 | T14, TP2, TP13, TP27                                            | None | 201 | 243 | Forbidden | 30 L      | B | 40                      |
| .....                                                                                                             | ..... | .....  | II  | 3, 6.1 | IB2, T11, TP2, TP13, TP27                                       | 150  | 202 | 243 | 1 L       | 60 L      | B | 40                      |
| Phenoxyacetic acid derivative pesticide, liquid, toxic.                                                           | 6.1   | UN3348 | I   | 6.1    | T14, TP2, TP13, TP27                                            | None | 201 | 243 | 1 L       | 30 L      | B | 40                      |
| .....                                                                                                             | ..... | .....  | II  | 6.1    | IB2, T11, TP2, TP27                                             | 153  | 202 | 243 | 5 L       | 60 L      | B | 40                      |
| .....                                                                                                             | ..... | .....  | III | 6.1    | IB3, T7, TP2, TP28                                              | 153  | 203 | 241 | 60 L      | 220 L     | A | 40                      |
| Phenoxyacetic acid derivative pesticide, liquid, toxic, flammable, <i>flash point not less than 23 degrees C.</i> | 6.1   | UN3347 | I   | 6.1, 3 | T14, TP2, TP13, TP27                                            | None | 201 | 243 | 1 L       | 30 L      | B | 40                      |
| .....                                                                                                             | ..... | .....  | II  | 6.1, 3 | IB2, T11, TP2, TP13, TP27                                       | 153  | 202 | 243 | 5 L       | 60 L      | B | 40                      |
| .....                                                                                                             | ..... | .....  | III | 6.1, 3 | IB3, T7, TP2, TP28                                              | 153  | 203 | 241 | 60 L      | 220 L     | A | 40                      |
| Phenoxyacetic acid derivative pesticide, solid, toxic.                                                            | 6.1   | UN3345 | I   | 6.1    | IB7, IP1, T6, TP33                                              | None | 211 | 242 | 5 kg      | 50 kg     | A | 40                      |
| .....                                                                                                             | ..... | .....  | II  | 6.1    | IB8, IP2, IP4, T3, TP33                                         | 153  | 212 | 242 | 25 kg     | 100 kg    | A | 40                      |
| .....                                                                                                             | ..... | .....  | III | 6.1    | IB8, IP3, T1, TP33                                              | 153  | 213 | 240 | 100 kg    | 200 kg    | A | 40                      |
| Phenyl chloroformate .....                                                                                        | 6.1   | UN2746 | II  | 6.1, 8 | IB2, T7, TP2, TP13                                              | 153  | 202 | 243 | 1 L       | 30 L      | A | 12, 13, 21, 25, 40, 100 |
| Phenyl isocyanate .....                                                                                           | 6.1   | UN2487 | I   | 6.1, 3 | 2, B9, B14, B32, B74, B77, N33, N34, T20, TP2, TP13, TP38, TP45 | None | 227 | 244 | Forbidden | Forbidden | D | 40                      |
| Phenyl mercaptan .....                                                                                            | 6.1   | UN2337 | I   | 6.1, 3 | 2, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45           | None | 227 | 244 | Forbidden | Forbidden | B | 40, 52                  |
| Phenyl phosphorus dichloride ....                                                                                 | 8     | UN2798 | II  | 8      | B2, B15, IB2, T7, TP2                                           | 154  | 202 | 242 | Forbidden | 30 L      | B | 40                      |
| Phenyl phosphorus thiodichloride.                                                                                 | 8     | UN2799 | II  | 8      | B2, B15, IB2, T7, TP2                                           | 154  | 202 | 242 | Forbidden | 30 L      | B | 40                      |
| Phenyl urea pesticides, liquid, toxic.                                                                            | 6.1   | UN3002 | I   | 6.1    | T14, TP2 TP27                                                   | None | 201 | 243 | 1 L       | 30 L      | B | 40                      |
| .....                                                                                                             | ..... | .....  | II  | 6.1    | T7, TP2                                                         | None | 202 | 243 | 5 L       | 60 L      | B | 40                      |
| Phenylacetonitrile, liquid .....                                                                                  | 6.1   | UN2470 | III | 6.1    | T4, TP1                                                         | 153  | 203 | 241 | 60 L      | 220 L     | A | 40                      |
| Phenylacetyl chloride .....                                                                                       | 8     | UN2577 | III | 6.1    | IB3, T4, TP1                                                    | 153  | 203 | 241 | 60 L      | 220 L     | A | 52                      |
| .....                                                                                                             | ..... | .....  | II  | 8      | B2, IB2, T7, TP2                                                | 154  | 202 | 242 | 1 L       | 30 L      | C | 40                      |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                       | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)                 | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|-----------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|--------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                   |                            |                            |       |             |                                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                   |                            |                            |       |             |                                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
|          | Phenylcarbylamine chloride .....                                                  | 6.1                        | UN1672                     | I     | 6.1 .....   | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 40    |
|          | <i>m</i> -Phenylene diaminedipерchlorate (dry).                                   | Forbidden                  |                            |       |             |                                                  |                       |           |           |                                                 |                       |                  |       |
| +        | Phenylenediamines (o-; m-; p-)                                                    | 6.1                        | UN1673                     | III   | 6.1 .....   | IB8, IP3, T1, TP33                               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                |       |
|          | Phenylhydrazine .....                                                             | 6.1                        | UN2572                     | II    | 6.1 .....   | IB2, T7, TP2                                     | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | 40    |
|          | Phenylmercuric acetate .....                                                      | 6.1                        | UN1674                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                |       |
|          | Phenylmercuric compounds, n.o.s..                                                 | 6.1                        | UN2026                     | I     | 6.1 .....   | IB7, IP1, T6, TP33                               | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                 | A                |       |
|          |                                                                                   |                            |                            | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                |       |
|          |                                                                                   |                            |                            | III   | 6.1 .....   | IB8, IP3, T1, TP33                               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                |       |
|          | Phenylmercuric hydroxide .....                                                    | 6.1                        | UN1894                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                |       |
|          | Phenylmercuric nitrate .....                                                      | 6.1                        | UN1895                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                |       |
|          | Phenyltrichlorosilane .....                                                       | 8                          | UN1804                     | II    | 8 .....     | A7, B6, IB2, N34, T7, TP2                        | None ....             | 202 ..... | 242 ..... | Forbidden                                       | 30 L                  | C                | 40    |
|          | Phosgene .....                                                                    | 2.3                        | UN1076                     | ..... | 2.3, 8      | 1, B7, B46                                       | None ....             | 192 ..... | 314 ..... | Forbidden                                       | Forbidden             | D                | 40    |
|          | 9-Phosphabicyclononanes or Cyclooctadiene phosphines.                             | 4.2                        | UN2940                     | II    | 4.2 .....   | A19, IB6, IP2, T3, TP33                          | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                 | A                |       |
|          | Phosphine .....                                                                   | 2.3                        | UN2199                     | ..... | 2.3, 2.1.   | 1                                                | None ....             | 192 ..... | 245 ..... | Forbidden                                       | Forbidden             | D                | 40    |
|          | Phosphoric acid solution .....                                                    | 8                          | UN1805                     | III   | 8 .....     | A7, IB3, N34, T4, TP1                            | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                |       |
|          | Phosphoric acid, solid .....                                                      | 8                          | UN3453                     | III   | 8 .....     | IB8, IP3, T1, TP33                               | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                |       |
|          | Phosphoric acid triethyleneimine, see Tris-(1-aziridyl)phosphine oxide, solution. |                            |                            |       |             |                                                  |                       |           |           |                                                 |                       |                  |       |
|          | Phosphoric anhydride, see Phosphorus pentoxide.                                   |                            |                            |       |             |                                                  |                       |           |           |                                                 |                       |                  |       |
|          | Phosphorous acid .....                                                            | 8                          | UN2834                     | III   | 8 .....     | IB8, IP3, T1, TP33                               | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | 48    |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                        |     |        |       |           |                                                                 |      |           |           |           |           |   |                      |
|------------------------------------------------------------------------|-----|--------|-------|-----------|-----------------------------------------------------------------|------|-----------|-----------|-----------|-----------|---|----------------------|
| Phosphorus, amorphous .....                                            | 4.1 | UN1338 | III   | 4.1       | A1, A19, B1, B9, B26, IB8, IP3, T1, TP33                        | None | 213       | 243       | 25 kg     | 100 kg    | A | 74                   |
| <i>Phosphorus bromide, see Phosphorus tribromide.</i>                  |     |        |       |           |                                                                 |      |           |           |           |           |   |                      |
| <i>Phosphorus chloride, see Phosphorus trichloride.</i>                |     |        |       |           |                                                                 |      |           |           |           |           |   |                      |
| Phosphorus heptasulfide, <i>free from yellow or white phosphorus.</i>  | 4.1 | UN1339 | II    | 4.1       | A20, IB4, N34, T3, TP33                                         | None | 212       | 240       | 15 kg     | 50 kg     | B | 74                   |
| Phosphorus oxybromide .....                                            | 8   | UN1939 | II    | 8         | B8, IB8, IP2, IP4, N41, N43, T3, TP33                           | None | 212       | 240       | Forbidden | 50 kg     | C | 12, 40               |
| Phosphorus oxybromide, molten                                          | 8   | UN2576 | II    | 8         | B2, B8, IB1, N41, N43, T7, TP3, TP13                            | None | 202       | 242       | Forbidden | Forbidden | C | 40                   |
| + Phosphorus oxychloride .....                                         | 8   | UN1810 | II    | 8, 6.1    | 2, B9, B14, B32, B74, B77, N34, T20, TP2, TP38, TP45            | None | 227       | 244       | Forbidden | Forbidden | C | 40                   |
| Phosphorus pentabromide .....                                          | 8   | UN2691 | II    | 8         | A7, IB8, IP2, IP4, N34, T3, TP33                                | 154  | 212       | 240       | Forbidden | 50 kg     | B | 12, 40, 53, 55       |
| Phosphorus pentachloride .....                                         | 8   | UN1806 | II    | 8         | A7, IB8, IP2, IP4, N34, T3, TP33                                | None | 212       | 240       | Forbidden | 50 kg     | C | 40, 44, 89, 100, 141 |
| Phosphorus Pentafluoride .....                                         | 2.3 | UN2198 | ..... | 2.3, 8    | 2, B9, B14                                                      | None | 302, 304. | 314, 315. | Forbidden | Forbidden | D | 40                   |
| Phosphorus pentasulfide, <i>free from yellow or white phosphorus.</i>  | 4.3 | UN1340 | II    | 4.3, 4.1. | A20, B59, IB4, T3, TP33                                         | 151  | 212       | 242       | 15 kg     | 50 kg     | B | 74                   |
| Phosphorus pentoxide .....                                             | 8   | UN1807 | II    | 8         | A7, IB8, IP2, IP4, N34, T3, TP33                                | 154  | 212       | 240       | 15 kg     | 50 kg     | A | .....                |
| Phosphorus sesquisulfide, <i>free from yellow or white phosphorus.</i> | 4.1 | UN1341 | II    | 4.1       | A20, IB4, N34, T3, TP33                                         | None | 212       | 240       | 15 kg     | 50 kg     | B | 74                   |
| Phosphorus tribromide .....                                            | 8   | UN1808 | II    | 8         | A3, A6, A7, B2, B25, IB2, N34, N43, T7, TP2                     | None | 202       | 242       | Forbidden | 30 L      | C | 40                   |
| Phosphorus trichloride .....                                           | 6.1 | UN1809 | I     | 6.1, 8    | 2, B9, B14, B15, B32, B74, B77, N34, T20, TP2, TP13, TP38, TP45 | None | 227       | 244       | Forbidden | Forbidden | C | 40                   |
| Phosphorus trioxide .....                                              | 8   | UN2578 | III   | 8         | IB8, IP3, T1, TP33                                              | 154  | 213       | 240       | 25 kg     | 100 kg    | A | 12                   |
| Phosphorus trisulfide, <i>free from yellow or white phosphorus.</i>    | 4.1 | UN1343 | II    | 4.1       | A20, IB4, N34, T3, TP33                                         | None | 212       | 240       | 15 kg     | 50 kg     | B | 74                   |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                                 | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)  | (8)                   |           |           | (9)                                             |                       | (10)             |                      |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|-----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|----------------------|
|          |                                                                                                                                                                                             |                            |                            |     |             |                                   | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                      |
|          |                                                                                                                                                                                             |                            |                            |     |             |                                   | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other                |
|          | Phosphorus, white dry or Phos- phorus, white, under water or Phosphorus white, in solution or Phosphorus, yellow dry or Phosphorus, yellow, under water or Phosphorus, yellow, in solution. | 4.2                        | UN1381                     | I   | 4.2, 6.1.   | B9, B26, N34, T9, TP3, TP31       | None ....             | 188 ..... | 243 ..... | Forbidden                                       | Forbidden             | E                | .....                |
|          | Phosphorus white, molten .....                                                                                                                                                              | 4.2                        | UN2447                     | I   | 4.2, 6.1.   | B9, B26, N34, T21, TP3, TP7, TP26 | None ....             | 188 ..... | 243 ..... | Forbidden                                       | Forbidden             | D                | .....                |
|          | <i>Phosphorus (white or red) and a chlorate, mixtures of.</i>                                                                                                                               | Forbidden                  |                            |     | .....       |                                   | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                |
|          | <i>Phosphoryl chloride, see Phos- phorus oxychloride.</i>                                                                                                                                   |                            |                            |     | .....       |                                   | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                |
|          | Phthalic anhydride with more than .05 percent maleic anhy- dride.                                                                                                                           | 8                          | UN2214                     | III | 8 .....     | IB8, IP3, T1, TP33                | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | .....                |
|          | Picolines .....                                                                                                                                                                             | 3                          | UN2313                     | III | 3 .....     | B1, IB3, T4, TP1                  | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | 40                   |
|          | Picric acid, see Trinitrophenol, etc.                                                                                                                                                       |                            |                            |     | .....       |                                   | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                |
|          | Picrite, see Nitroguanidine, etc ..                                                                                                                                                         |                            |                            |     | .....       |                                   | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                |
|          | Picryl chloride, see Trinitrochlorobenzene.                                                                                                                                                 |                            |                            |     | .....       |                                   | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                |
|          | Pine oil .....                                                                                                                                                                              | 3                          | UN1272                     | III | 3 .....     | B1, IB3, T2, TP1                  | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....                |
|          | alpha-Pinene .....                                                                                                                                                                          | 3                          | UN2368                     | III | 3 .....     | B1, IB3, T2, TP1                  | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....                |
|          | Piperazine .....                                                                                                                                                                            | 8                          | UN2579                     | III | 8 .....     | IB8, IP3, T1, TP33                | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | 12, 52               |
|          | Piperidine .....                                                                                                                                                                            | 8                          | UN2401                     | I   | 8, 3 ....   | A10, T10, TP2                     | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                 | B                | 52                   |
|          | <i>Pivaloyl chloride, see Trimethylacetyl chloride.</i>                                                                                                                                     |                            |                            |     | .....       |                                   | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                |
|          | Plastic molding compound in dough, sheet or extruded rope form evolving flammable vapor.                                                                                                    | 9                          | UN3314                     | III | 9 .....     | 32, IB8, IP3, IP7                 | 155 .....             | 221 ..... | 221 ..... | 100 kg                                          | 200 kg                | E                | 19, 21, 25, 87, 144. |
|          | <i>Plastic solvent, n.o.s., see Flam- mable liquids, n.o.s..</i>                                                                                                                            |                            |                            |     | .....       |                                   | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....                |
|          | Plastics, nitrocellulose-based, self-heating, n.o.s..                                                                                                                                       | 4.2                        | UN2006                     | III | 4.2 ....    |                                   | None ....             | 213 ..... | None .... | Forbidden                                       | Forbidden             | C                | .....                |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                   |           |        |       |       |       |                                                     |       |       |       |       |       |       |           |        |   |                         |
|---------------------------------------------------------------------------------------------------|-----------|--------|-------|-------|-------|-----------------------------------------------------|-------|-------|-------|-------|-------|-------|-----------|--------|---|-------------------------|
| Poisonous gases, n.o.s., see Compressed or liquefied gases, flammable or toxic, n.o.s..           | .....     |        |       | ..... |       | .....                                               | ..... | ..... | ..... | ..... |       | ..... |           |        |   |                         |
| Polyalkylamines, n.o.s., see Amines, etc.                                                         | .....     |        |       | ..... |       | .....                                               | ..... | ..... | ..... | ..... |       | ..... |           |        |   |                         |
| Polyamines, flammable, corrosive, n.o.s. see Amines, flammable, corrosive, n.o.s.                 |           |        |       |       |       |                                                     |       |       |       |       |       |       |           |        |   |                         |
| Polyamines, liquid, corrosive, n.o.s. see Amines, liquid, corrosive, n.o.s.                       |           |        |       |       |       |                                                     |       |       |       |       |       |       |           |        |   |                         |
| Polyamines, liquid, corrosive, flammable, n.o.s. see Amines, liquid, corrosive, flammable, n.o.s. |           |        |       |       |       |                                                     |       |       |       |       |       |       |           |        |   |                         |
| Polychlorinated biphenyls, liquid                                                                 | 9         | UN2315 | II    | 9     | ..... | 9, 81, 140, IB3, T4, TP1                            | 155   | ..... | 202   | ..... | 241   | ..... | 100 L     | 220 L  | A | 95                      |
| Polychlorinated biphenyls, solid                                                                  | 9         | UN3432 | II    | 9     | ..... | 9, 81, 140, IB8, T3, TP33                           | 155   | ..... | 212   | ..... | 240   | ..... | 100 kg    | 200 kg | A | 95                      |
| Polyester resin kit                                                                               | 3         | UN3269 | ..... | 3     | ..... | 40, 149                                             | 152   | ..... | 225   | ..... | None  | ..... | 5 kg      | 5 kg   | B | .....                   |
| Polyhalogenated biphenyls, liquid or Polyhalogenated terphenyls liquid.                           | 9         | UN3151 | II    | 9     | ..... | IB2                                                 | 155   | ..... | 204   | ..... | 241   | ..... | 100 L     | 220 L  | A | 95                      |
| Polyhalogenated biphenyls, solid or Polyhalogenated terphenyls, solid.                            | 9         | UN3152 | II    | 9     | ..... | IB8, IP2, IP4, T3, TP33                             | 155   | ..... | 204   | ..... | 241   | ..... | 100 kg    | 200 kg | A | 95                      |
| Polymeric beads expandable, evolving flammable vapor.                                             | 9         | UN2211 | III   | 9     | ..... | 32, IB8, IP3, IP7, T1, TP33                         | 155   | ..... | 221   | ..... | 221   | ..... | 100 kg    | 200 kg | E | 19, 21, 25, 87, 144, 52 |
| Potassium                                                                                         | 4.3       | UN2257 | I     | 4.3   | ..... | A7, A19, A20, B27, IB4, IP1, N6, N34, T9, TP7, TP33 | None  | ..... | 211   | ..... | 244   | ..... | Forbidden | 15 kg  | D |                         |
| Potassium arsenate                                                                                | 6.1       | UN1677 | II    | 6.1   | ..... | IB8, IP2, IP4, T3, TP33                             | 153   | ..... | 212   | ..... | 242   | ..... | 25 kg     | 100 kg | A | .....                   |
| Potassium arsenite                                                                                | 6.1       | UN1678 | II    | 6.1   | ..... | IB8, IP2, IP4, T3, TP33                             | 153   | ..... | 212   | ..... | 242   | ..... | 25 kg     | 100 kg | A | .....                   |
| Potassium bisulfite solution, see Bisulfites, aqueous solutions, n.o.s..                          | .....     |        |       | ..... |       |                                                     | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....  |   | .....                   |
| Potassium borohydride                                                                             | 4.3       | UN1870 | I     | 4.3   | ..... | A19, N40                                            | None  | ..... | 211   | ..... | 242   | ..... | Forbidden | 15 kg  | E | 52                      |
| Potassium bromate                                                                                 | 5.1       | UN1484 | II    | 5.1   | ..... | IB8, IP4, T3, TP33                                  | 152   | ..... | 212   | ..... | 242   | ..... | 5 kg      | 25 kg  | A | 56, 58                  |
| Potassium carbonyl                                                                                | Forbidden |        |       | ..... |       |                                                     | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....  |   | .....                   |
| Potassium chlorate                                                                                | 5.1       | UN1485 | II    | 5.1   | ..... | A9, IB8, IP4, N34, T3, TP33                         | 152   | ..... | 212   | ..... | 242   | ..... | 5 kg      | 25 kg  | A | 56, 58                  |
| Potassium chlorate, aqueous solution.                                                             | 5.1       | UN2427 | II    | 5.1   | ..... | A2, IB2, T4, TP1                                    | 152   | ..... | 202   | ..... | 241   | ..... | 1 L       | 5 L    | B | 56, 58, 133             |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                             | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)              | (8)                   |           |      | (9)                                             |                       | (10)             |                 |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|-----------------------------------------------|-----------------------|-----------|------|-------------------------------------------------|-----------------------|------------------|-----------------|
|          |                                                                                                                                                         |                            |                            |     |             |                                               | Packaging (§ 173.***) |           |      | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                 |
|          |                                                                                                                                                         |                            |                            |     |             |                                               | Excep- tions          | Non- bulk | Bulk | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other           |
|          | .....                                                                                                                                                   | .....                      |                            | III | 5.1         | A2, IB2, T4, TP1                              | 152                   | 203       | 241  | 2.5 L                                           | 30 L                  | B                | 56, 58, 69, 133 |
|          | <i>Potassium chlorate mixed with mineral oil, see Explosive, blasting, type C.</i>                                                                      |                            |                            |     |             |                                               |                       |           |      |                                                 |                       |                  |                 |
|          | Potassium cuprocyanide .....                                                                                                                            | 6.1                        | UN1679                     | II  | 6.1         | IB8, IP2, IP4, T3, TP33                       | 153                   | 212       | 242  | 25 kg                                           | 100 kg                | A                | 52              |
|          | Potassium cyanide, solid .....                                                                                                                          | 6.1                        | UN1680                     | I   | 6.1         | B69, B77, IB7, IP1, N74, N75, T6, TP33        | None                  | 211       | 242  | 5 kg                                            | 50 kg                 | B                | 52              |
|          | Potassium cyanide solution .....                                                                                                                        | 6.1                        | UN3413                     | I   | 6.1         | B69, B77, N74, N75, T14, TP2, TP13            | None                  | 201       | 243  | 1 L                                             | 30 L                  | B                | 52              |
|          | .....                                                                                                                                                   |                            |                            | II  | 6.1         | B69, B77, IB2, N74, N75, T11, TP2, TP13, TP27 | 153                   | 202       | 243  | 5 L                                             | 60 L                  | B                | 52              |
|          | .....                                                                                                                                                   |                            |                            | III | 6.1         | B69, B77, IB3, N74, N75, T7, TP2, TP13, TP28  | 153                   | 203       | 241  | 60 L                                            | 220 L                 | A                | 52              |
|          | <i>Potassium dichloro isocyanurate or Potassium dichloro-s-triazinetriane, see Dichloroisocyanuric acid, dry or Dichloroisocyanuric acid salts etc.</i> |                            |                            |     |             |                                               |                       |           |      |                                                 |                       |                  |                 |
|          | Potassium dithionite or Potas- sium hydrosulfite.                                                                                                       | 4.2                        | UN1929                     | II  | 4.2         | A8, A19, A20, IB6, IP2, T3, TP33              | None                  | 212       | 241  | 15 kg                                           | 50 kg                 | E                | 13              |
|          | Potassium fluoride, solid .....                                                                                                                         | 6.1                        | UN1812                     | III | 6.1         | IB8, IP3, T1, TP33                            | 153                   | 213       | 240  | 100 kg                                          | 200 kg                | A                | 52              |
|          | Potassium fluoride solution .....                                                                                                                       | 6.1                        | UN3422                     | III | 6.1         | IB3, T4, TP1                                  | 153                   | 203       | 241  | 60 L                                            | 220 L                 | A                | 52              |
|          | Potassium fluoroacetate .....                                                                                                                           | 6.1                        | UN2628                     | I   | 6.1         | IB7, IP1, T6, TP33                            | None                  | 211       | 242  | 5 kg                                            | 50 kg                 | E                | .....           |
|          | Potassium fluorosilicate .....                                                                                                                          | 6.1                        | UN2655                     | III | 6.1         | IB8, IP3, T1, TP33                            | 153                   | 213       | 240  | 100 kg                                          | 200 kg                | A                | 52              |
|          | <i>Potassium hydrate, see Potas- sium hydroxide, solid.</i>                                                                                             |                            |                            |     |             |                                               |                       |           |      |                                                 |                       |                  |                 |
|          | <i>Potassium hydrogen fluoride, see Potassium hydrogen difluoride.</i>                                                                                  |                            |                            |     |             |                                               |                       |           |      |                                                 |                       |                  |                 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                     |       |        |     |          |                                        |       |       |       |           |        |       |                |
|---------------------------------------------------------------------|-------|--------|-----|----------|----------------------------------------|-------|-------|-------|-----------|--------|-------|----------------|
| Potassium hydrogen fluoride solution, see Corrosive liquid, n.o.s.. | ..... |        |     | .....    | .....                                  | ..... | ..... | ..... | .....     | .....  | ..... | .....          |
| Potassium hydrogen sulfate .....                                    | 8     | UN2509 | II  | 8        | A7, IB8, IP2, IP4, N34, T3, TP33       | 154   | 212   | 240   | 15 kg     | 50 kg  | A     | .....          |
| Potassium hydrogendifluoride solid.                                 | 8     | UN1811 | II  | 8, 6.1   | IB8, IP2, IP4, N3, N34, T3, TP33       | 154   | 212   | 240   | 15 kg     | 50 kg  | A     | 25, 40, 52     |
| Potassium hydrogendifluoride solution.                              | 8     | UN3421 | II  | 8, 6.1   | IB2, N3, N34, T7, TP2                  | 154   | 202   | 243   | 1 L       | 30 L   | A     | 25, 40, 52     |
| .....                                                               | ..... |        | III | 8, 6.1   | IB3, N3, N34, T4, TP1                  | 154   | 203   | 241   | 5 L       | 60 L   | A     | 40, 52         |
| Potassium hydrosulfite, see Potassium dithionite.                   | ..... |        |     | .....    | .....                                  | ..... | ..... | ..... | .....     | .....  |       | .....          |
| Potassium hydroxide, liquid, see Potassium hydroxide solution.      | ..... |        |     | .....    | .....                                  | ..... | ..... | ..... | .....     | .....  |       | .....          |
| Potassium hydroxide, solid .....                                    | 8     | UN1813 | II  | 8        | IB8, IP2, IP4, T3, TP33                | 154   | 212   | 240   | 15 kg     | 50 kg  | A     | 52.            |
| Potassium hydroxide, solution ...                                   | 8     | UN1814 | II  | 8        | B2, IB2, T7, TP2                       | 154   | 202   | 242   | 1 L       | 30 L   | A     | 52.            |
| .....                                                               | ..... |        | III | 8        | IB3, T4, TP1                           | 154   | 203   | 241   | 5 L       | 60 L   | A     | 52.            |
| Potassium hypochlorite, solution, see Hypochlorite solutions, etc.  | ..... |        |     | .....    | .....                                  | ..... | ..... | ..... | .....     | .....  |       | .....          |
| Potassium, metal alloys, liquid ..                                  | 4.3   | UN1420 | I   | 4.3      | A7, A19, A20, B27                      | None  | 201   | 244   | Forbidden | 1 L    | E     | 40, 52         |
| Potassium, metal alloys, solid ...                                  | 4.3   | UN3403 | I   | 4.3      | A19, A20, B27, IB4, IP1, T9, TP7, TP33 | None  | 211   | 244   | Forbidden | 15 kg  | D     | .....          |
| Potassium metavanadate .....                                        | 6.1   | UN2864 | II  | 6.1      | IB8, IP2, IP4, T3, TP33                | 153   | 212   | 242   | 25 kg     | 100 kg | A     | .....          |
| Potassium monoxide .....                                            | 8     | UN2033 | II  | 8        | IB8, IP2, IP4, T3, TP33                | 154   | 212   | 240   | 15 kg     | 50 kg  | A     | 29, 52.        |
| Potassium nitrate .....                                             | 5.1   | UN1486 | III | 5.1      | A1, A29, IB8, IP3, T1, TP33            | 152   | 213   | 240   | 25 kg     | 100 kg | A     | .....          |
| Potassium nitrate and sodium nitrite mixtures.                      | 5.1   | UN1487 | II  | 5.1      | B78, IB8, IP4, T3, TP33                | 152   | 212   | 240   | 5 kg      | 25 kg  | A     | 56, 58         |
| Potassium nitrite .....                                             | 5.1   | UN1488 | II  | 5.1      | IB8, IP4, T3, TP33                     | 152   | 212   | 242   | 5 kg      | 25 kg  | A     | 56, 58         |
| Potassium perchlorate .....                                         | 5.1   | UN1489 | II  | 5.1      | IB6, IP2, T3, TP33                     | 152   | 212   | 242   | 5 kg      | 25 kg  | A     | 56, 58         |
| Potassium permanganate .....                                        | 5.1   | UN1490 | II  | 5.1      | IB8, IP4, T3, TP33                     | 152   | 212   | 240   | 5 kg      | 25 kg  | D     | 56, 58, 138    |
| Potassium peroxide .....                                            | 5.1   | UN1491 | I   | 5.1      | A20, IB6, IP1, N34                     | None  | 211   | None  | Forbidden | 15 kg  | B     | 13, 52, 66, 75 |
| Potassium persulfate .....                                          | 5.1   | UN1492 | III | 5.1      | A1, A29, IB8, IP3, T1, TP33            | 152   | 213   | 240   | 25 kg     | 100 kg | A     | 56, 58         |
| Potassium phosphide .....                                           | 4.3   | UN2012 | I   | 4.3, 6.1 | A19, N40                               | None  | 211   | None  | Forbidden | 15 kg  | E     | 40, 52, 85     |
| Potassium selenate, see Selenates or Selenites.                     | ..... |        |     | .....    | .....                                  | ..... | ..... | ..... | .....     | .....  |       | .....          |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                             | Hazard class or Di- vision | Identifica- tion Num- bers | PG | Label Codes | Special provi- sions (§ 172.102)           | (8)                   |           |      | (9)                                             |                       | (10)             |                |
|----------|---------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|----|-------------|--------------------------------------------|-----------------------|-----------|------|-------------------------------------------------|-----------------------|------------------|----------------|
|          |                                                                                                         |                            |                            |    |             |                                            | Packaging (§ 173.***) |           |      | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |                |
|          |                                                                                                         |                            |                            |    |             |                                            | Excep- tions          | Non- bulk | Bulk | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other          |
|          | <i>Potassium selenite, see Selenates or Selenites.</i>                                                  |                            |                            |    |             |                                            |                       |           |      |                                                 |                       |                  |                |
|          | Potassium sodium alloys, liquid                                                                         | 4.3                        | UN1422                     | I  | 4.3         | A7, A19, B27, N34, N40, T9, TP3, TP7, TP31 | None                  | 201       | 244  | Forbidden                                       | 1 L                   | E                | 40, 52         |
|          | Potassium sodium alloys, solid ..                                                                       | 4.3                        | UN3404                     | I  | 4.3         | A19, B27, N34, N40, T9, TP7, TP33          | None                  | 211       | 244  | Forbidden                                       | 15 kg                 | D                | 52             |
|          | Potassium sulfide, anhydrous or Potassium sulfide with less than 30 percent water of crys- tallization. | 4.2                        | UN1382                     | II | 4.2         | A19, A20, B16, IB6, IP2, N34, T3, TP33     | None                  | 212       | 241  | 15 kg                                           | 50 kg                 | A                | 52             |
|          | Potassium sulfide, hydrated with not less than 30 percent water of crystallization.                     | 8                          | UN1847                     | II | 8           | IB8, IP2, IP4, T3, TP33                    | 154                   | 212       | 240  | 15 kg                                           | 50 kg                 | A                | 52             |
|          | Potassium superoxide .....                                                                              | 5.1                        | UN2466                     | I  | 5.1         | A20, IB6, IP1                              | None                  | 211       | None | Forbidden                                       | 15 kg                 | B                | 13, 52, 66, 75 |
|          | Powder cake, wetted or Powder paste, wetted with not less than 17 percent alcohol by mass.              | 1.1C                       | UN0433                     | II | 1.1C        |                                            | None                  | 62        | None | Forbidden                                       | Forbidden             | 10               |                |
|          | Powder cake, wetted or Powder paste, wetted with not less than 25 percent water, by mass.               | 1.3C                       | UN0159                     | II | 1.3C        |                                            | None                  | 62        | None | Forbidden                                       | Forbidden             | 10               |                |
|          | Powder paste, see Powder cake, etc.                                                                     |                            |                            |    |             |                                            |                       |           |      |                                                 |                       |                  |                |
|          | Powder, smokeless .....                                                                                 | 1.1C                       | UN0160                     | II | 1.1C        |                                            | None                  | 62        | None | Forbidden                                       | Forbidden             |                  | 26E            |
|          | Powder, smokeless .....                                                                                 | 1.3C                       | UN0161                     | II | 1.3C        |                                            | None                  | 62        | None | Forbidden                                       | Forbidden             |                  | 26E            |
|          | Power device, explosive, see Cartridges, power device.                                                  |                            |                            |    |             |                                            |                       |           |      |                                                 |                       |                  |                |
|          | Primers, cap type .....                                                                                 | 1.4S                       | UN0044                     | II | None        |                                            | None                  | 62        | None | 25 kg                                           | 100 kg                | 05               |                |
|          | Primers, cap type .....                                                                                 | 1.1B                       | UN0377                     | II | 1.1B        |                                            | None                  | 62        | None | Forbidden                                       | Forbidden             | 11               |                |
|          | Primers, cap type .....                                                                                 | 1.4B                       | UN0378                     | II | 1.4B        |                                            | None                  | 62        | None | Forbidden                                       | 75 kg                 | 06               |                |
|          | Primers, small arms, see Prim- ers, cap type.                                                           |                            |                            |    |             |                                            |                       |           |      |                                                 |                       |                  |                |
|          | Primers, tubular .....                                                                                  | 1.3G                       | UN0319                     | II | 1.3G        |                                            | None                  | 62        | None | Forbidden                                       | Forbidden             | 07               |                |
|          | Primers, tubular .....                                                                                  | 1.4G                       | UN0320                     | II | 1.4G        |                                            | None                  | 62        | None | Forbidden                                       | 75 kg                 | 06               |                |
|          | Primers, tubular .....                                                                                  | 1.4S                       | UN0376                     | II | None        |                                            | None                  | 62        | None | 25 kg                                           | 100 kg                | 05               |                |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                                                          |       |        |       |       |       |                           |       |       |       |       |              |           |           |           |       |         |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-------|-------|-------|---------------------------|-------|-------|-------|-------|--------------|-----------|-----------|-----------|-------|---------|
| Printing ink, <i>flammable</i> or Print-<br>ing ink related material ( <i>in-<br/>cluding printing ink thinning or<br/>reducing compound</i> ), <i>flam-<br/>mable</i> . | 3     | UN1210 | I     | 3     | ..... | T11, TP1, TP8             | 150   | ..... | 173   | ..... | 243          | .....     | 1 L       | 30 L      | E     | .....   |
| .....                                                                                                                                                                    | ..... | .....  | II    | 3     | ..... | 149, IB2, T4,<br>TP1, TP8 | 150   | ..... | 173   | ..... | 242          | .....     | 5 L       | 60 L      | B     | .....   |
| .....                                                                                                                                                                    | ..... | .....  | III   | 3     | ..... | B1, IB3, T2, TP1          | 150   | ..... | 173   | ..... | 242          | .....     | 60 L      | 220 L     | A     | .....   |
| .....                                                                                                                                                                    | ..... | .....  | ..... | ..... | ..... | .....                     | ..... | ..... | ..... | ..... | .....        | .....     | .....     | .....     | ..... | .....   |
| <i>Projectiles, illuminating, see Am-<br/>munition, illuminating, etc.</i>                                                                                               | ..... | .....  | ..... | ..... | ..... | .....                     | ..... | ..... | ..... | ..... | .....        | .....     | .....     | .....     | ..... | .....   |
| Projectiles, <i>inert with tracer</i> .....                                                                                                                              | 1.4S  | UN0345 | II    | 1.4S  | ...   | .....                     | ..... | 62    | ..... | None  | ...          | 25 kg     | 100 kg    | 01        | ..... | .....   |
| Projectiles, <i>inert, with tracer</i> .....                                                                                                                             | 1.3G  | UN0424 | II    | 1.3G  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 03        | ..... | .....   |
| Projectiles, <i>inert, with tracer</i> .....                                                                                                                             | 1.4G  | UN0425 | II    | 1.4G  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | 75 kg     | 02        | ..... | .....   |
| Projectiles, <i>with burster or ex-<br/>pelling charge</i> .                                                                                                             | 1.2D  | UN0346 | II    | 1.2D  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 03        | ..... | .....   |
| Projectiles, <i>with burster or ex-<br/>pelling charge</i> .                                                                                                             | 1.4D  | UN0347 | II    | 1.4D  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | 75 kg     | 02        | ..... | .....   |
| Projectiles, <i>with burster or ex-<br/>pelling charge</i> .                                                                                                             | 1.2F  | UN0426 | II    | 1.2F  | ...   | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 08        | ..... | .....   |
| Projectiles, <i>with burster or ex-<br/>pelling charge</i> .                                                                                                             | 1.4F  | UN0427 | II    | 1.4F  | ...   | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 08        | ..... | .....   |
| Projectiles, <i>with burster or ex-<br/>pelling charge</i> .                                                                                                             | 1.2G  | UN0434 | II    | 1.2G  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 03        | ..... | .....   |
| Projectiles, <i>with burster or ex-<br/>pelling charge</i> .                                                                                                             | 1.4G  | UN0435 | II    | 1.4G  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | 75 kg     | 02        | ..... | .....   |
| Projectiles, <i>with bursting charge</i>                                                                                                                                 | 1.1F  | UN0167 | II    | 1.1F  | ...   | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 08        | ..... | .....   |
| Projectiles, <i>with bursting charge</i>                                                                                                                                 | 1.1D  | UN0168 | II    | 1.1D  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 03        | ..... | .....   |
| Projectiles, <i>with bursting charge</i>                                                                                                                                 | 1.2D  | UN0169 | II    | 1.2D  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 03        | ..... | .....   |
| Projectiles, <i>with bursting charge</i>                                                                                                                                 | 1.2F  | UN0324 | II    | 1.2F  | ...   | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | Forbidden | 08        | ..... | .....   |
| Projectiles, <i>with bursting charge</i>                                                                                                                                 | 1.4D  | UN0344 | II    | 1.4D  | ..    | .....                     | ..... | 62    | ..... | None  | ...          | Forbidden | 75 kg     | 02        | ..... | .....   |
| Propadiene, stabilized .....                                                                                                                                             | 2.1   | UN2200 | ..... | 2.1   | ....  | .....                     | None  | ..... | 304   | ..... | 314,<br>315. | Forbidden | 150 kg    | B         | 40    | .....   |
| .....                                                                                                                                                                    | ..... | .....  | ..... | ..... | ..... | .....                     | ..... | ..... | ..... | ..... | .....        | .....     | .....     | .....     | ..... | .....   |
| <i>Propadiene mixed with methyl<br/>acetylene, see Methyl<br/>acetylene and propadiene<br/>mixtures, stabilized.</i>                                                     | ..... | .....  | ..... | ..... | ..... | .....                     | ..... | ..... | ..... | ..... | .....        | .....     | .....     | .....     | ..... | .....   |
| Propane <i>see also</i> Petroleum<br>gases, liquefied.                                                                                                                   | 2.1   | UN1978 | ..... | 2.1   | ....  | 19, T50                   | 306   | ..... | 304   | ..... | 314,<br>315. | Forbidden | 150 kg    | E         | 40    | .....   |
| Propanethiols .....                                                                                                                                                      | 3     | UN2402 | II    | 3     | ..... | A6, IB2, T4, TP1,<br>TP13 | 150   | ..... | 202   | ..... | 242          | .....     | 5 L       | 60 L      | E     | 95, 102 |
| n-Propanol or Propyl alcohol,<br>normal.                                                                                                                                 | 3     | UN1274 | II    | 3     | ..... | B1, IB2, T4, TP1          | 150   | ..... | 202   | ..... | 242          | .....     | 5 L       | 60 L      | B     | .....   |
| .....                                                                                                                                                                    | ..... | .....  | III   | 3     | ..... | B1, IB3, T2, TP1          | 150   | ..... | 203   | ..... | 242          | .....     | 60 L      | 220 L     | A     | .....   |
| Propellant, liquid .....                                                                                                                                                 | 1.3C  | UN0495 | II    | 1.3C  | ..    | 37                        | None  | ..... | 62    | ..... | None         | ...       | Forbidden | Forbidden | 10    | .....   |
| Propellant, liquid .....                                                                                                                                                 | 1.1C  | UN0497 | II    | 1.1C  | ..    | 37                        | None  | ..... | 62    | ..... | None         | ...       | Forbidden | Forbidden | 10    | .....   |
| Propellant, solid .....                                                                                                                                                  | 1.1C  | UN0498 | II    | 1.1C  | ..    | .....                     | None  | ..... | 62    | ..... | None         | ...       | Forbidden | Forbidden | 26E   | .....   |
| Propellant, solid .....                                                                                                                                                  | 1.3C  | UN0499 | II    | 1.3C  | ..    | .....                     | None  | ..... | 62    | ..... | None         | ...       | Forbidden | Forbidden | 26E   | .....   |
| Propellant, solid .....                                                                                                                                                  | 1.4C  | UN0501 | ..... | 1.4C  | ..    | .....                     | None  | ..... | 62    | ..... | None         | ...       | Forbidden | Forbidden | A     | 24E     |
| Propionaldehyde .....                                                                                                                                                    | 3     | UN1275 | II    | 3     | ..... | IB2, T7, TP1              | 150   | ..... | 202   | ..... | 242          | .....     | 5 L       | 60 L      | E     | .....   |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names            | Hazard class or Division | Identification Numbers | PG    | Label Codes | Special provisions (§ 172.102)                             | (8)                   |           |           | (9)                                             |                     | (10)           |                 |
|----------|-----------------------------------------------------------------------|--------------------------|------------------------|-------|-------------|------------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|---------------------|----------------|-----------------|
|          |                                                                       |                          |                        |       |             |                                                            | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |                 |
|          |                                                                       |                          |                        |       |             |                                                            | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Loca-tion      | Other           |
|          | Propionic acid with not less than 90% acid by mass.                   | 8                        | UN3463                 | II    | 8, 3 ....   | IB2, T7, TP2                                               | 154 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                | A.             |                 |
|          | Propionic acid with not less than 10% and less than 90% acid by mass. | 8                        | UN1848                 | III   | 8 .....     | IB3, T4, TP1                                               | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                | A.             |                 |
|          | Propionic anhydride .....                                             | 8                        | UN2496                 | III   | 8 .....     | IB3, T4, TP1                                               | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                | A              | .....           |
|          | Propionitrile .....                                                   | 3                        | UN2404                 | II    | 3, 6.1      | IB2, T7, TP1, TP13                                         | None ....             | 202 ..... | 243 ..... | Forbidden                                       | 60 L                | E              | 40              |
|          | Propionyl chloride .....                                              | 3                        | UN1815                 | II    | 3, 8 ....   | IB1, T7, TP1                                               | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                 | B              | 40              |
|          | n-Propyl acetate .....                                                | 3                        | UN1276                 | II    | 3 .....     | IB2, T4, TP1                                               | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              | .....           |
|          | Propyl alcohol, see Propanol .....                                    |                          |                        |       |             |                                                            |                       |           |           |                                                 |                     |                |                 |
|          | n-Propyl benzene .....                                                | 3                        | UN2364                 | III   | 3 .....     | B1, IB3, T2, TP1                                           | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L               | A              | .....           |
|          | n-Propyl chloroformate .....                                          | 6.1                      | UN2740                 | I     | 6.1, 3, 8.  | 2, B9, B14, B32, B74, B77, N34, T20, TP2, TP13, TP38, TP44 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden           | B              | 21, 40, 100     |
|          | Propyl chloride see 1-Chloropropane.                                  |                          |                        |       |             |                                                            |                       |           |           |                                                 |                     |                |                 |
|          | Propyl formates .....                                                 | 3                        | UN1281                 | II    | 3 .....     | IB2, T4, TP1                                               | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              | .....           |
|          | n-Propyl isocyanate .....                                             | 6.1                      | UN2482                 | I     | 6.1, 3      | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44           | None ....             | 226 ..... | 244 ..... | Forbidden                                       | Forbidden           | D              | 40              |
|          | Propyl mercaptan, see Propanethiols.                                  |                          |                        |       |             |                                                            |                       |           |           |                                                 |                     |                |                 |
|          | n-Propyl nitrate .....                                                | 3                        | UN1865                 | II    | 3 .....     | IB9                                                        | 150 .....             | 202 ..... | None .... | 5 L                                             | 60 L                | D              | 44, 89, 90, 100 |
|          | Propylamine .....                                                     | 3                        | UN1277                 | II    | 3, 8 ....   | A7, IB2, N34, T7, TP1                                      | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                 | E              | 40              |
|          | Propylene see also Petroleum gases, liquefied.                        | 2.1                      | UN1077                 | ..... | 2.1 ....    | 19, T50                                                    | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg              | E              | 40              |
|          | Propylene chlorohydrin .....                                          | 6.1                      | UN2611                 | II    | 6.1, 3      | IB2, T7, TP2, TP13                                         | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                | A              | 12, 40, 48      |
|          | Propylene oxide .....                                                 | 3                        | UN1280                 | I     | 3 .....     | A3, N34, T11, TP2, TP7                                     | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                | E              | 40              |
|          | Propylene tetramer .....                                              | 3                        | UN2850                 | III   | 3 .....     | B1, IB3, T2, TP1                                           | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L               | A              | .....           |
|          | 1,2-Propylenediamine .....                                            | 8                        | UN2258                 | II    | 8, 3 ....   | A3, A6, IB2, N34, T7, TP2                                  | None ....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                | A              | 40              |
|          | Propyleneimine, stabilized .....                                      | 3                        | UN1921                 | I     | 3, 6.1      | A3, N34, T14, TP2, TP13                                    | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                | B              | 40              |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                         |           |        |     |           |                                     |           |           |           |           |           |   |         |
|-----------------------------------------------------------------------------------------|-----------|--------|-----|-----------|-------------------------------------|-----------|-----------|-----------|-----------|-----------|---|---------|
| Propyltrichlorosilane .....                                                             | 8         | UN1816 | II  | 8, 3 .... | A7, B2, B6, IB2, N34, T7, TP2, TP13 | None .... | 202 ..... | 243 ..... | Forbidden | 30 L      | C | 40      |
| <i>Prussic acid, see Hydrogen cyanide.</i>                                              |           |        |     |           |                                     |           |           |           |           |           |   |         |
| Pyrethroid pesticide, liquid, flammable, toxic, flash point less than 23 degrees C.     | 3         | UN3350 | I   | 3, 6.1    | T14, TP2, TP13, TP27                | None .... | 201 ..... | 243 ..... | Forbidden | 30 L      | B | 40      |
|                                                                                         |           |        | II  | 3, 6.1    | IB2, T11, TP2, TP13, TP27           | 150 ..... | 202 ..... | 243 ..... | 1 L       | 60 L      | B | 40      |
| Pyrethroid pesticide, liquid toxic                                                      | 6.1       | UN3352 | I   | 6.1 ..... | T14, TP2, TP13, TP27                | None .... | 211 ..... | 242 ..... | 1 L       | 30 L      | A | 40      |
|                                                                                         |           |        | II  | 6.1 ..... | IB2, T11, TP2, TP27                 | 153 ..... | 212 ..... | 242 ..... | 5 L       | 60 L      | A | 40      |
|                                                                                         |           |        | III | 6.1 ..... | IB3, T7, TP2, TP28                  | 153 ..... | 213 ..... | 240 ..... | 60 L      | 220 L     | A | 40      |
| Pyrethroid pesticide, liquid, toxic, flammable, flash point not less than 23 degrees C. | 6.1       | UN3351 | I   | 6.1, 3    | T14, TP2, TP13, TP27                | None .... | 201 ..... | 243 ..... | 1 L       | 30 L      | B | 40      |
|                                                                                         |           |        | II  | 6.1, 3    | IB2, T11, TP2, TP13, TP27           | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B | 40      |
|                                                                                         |           |        | III | 6.1, 3    | IB3, T7, TP2, TP28                  | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | B | 40      |
| Pyrethroid pesticide, solid, toxic                                                      | 6.1       | UN3349 | I   | 6.1 ..... | IB7, IP1, T6, TP33                  | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | A | 40      |
|                                                                                         |           |        | II  | 6.1 ..... | IB8, IP2, IP4, T3, TP33             | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A | 40      |
|                                                                                         |           |        | III | 6.1 ..... | IB8, IP3, T1, TP33                  | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A | 40      |
| Pyridine .....                                                                          | 3         | UN1282 | II  | 3 .....   | IB2, T4, TP2                        | None .... | 202 ..... | 242 ..... | 5 L       | 60 L      | B | 21, 100 |
| Pyridine perchlorate .....                                                              | Forbidden |        |     |           |                                     |           |           |           |           |           |   |         |
| G Pyrophoric liquid, inorganic, n.o.s..                                                 | 4.2       | UN3194 | I   | 4.2 ..... |                                     | None .... | 181 ..... | 244 ..... | Forbidden | Forbidden | D | 18      |
| G Pyrophoric liquids, organic, n.o.s..                                                  | 4.2       | UN2845 | I   | 4.2 ..... | B11, T22, TP2, TP7                  | None .... | 181 ..... | 244 ..... | Forbidden | Forbidden | D | 18      |
| G Pyrophoric metals, n.o.s., or Pyrophoric alloys, n.o.s..                              | 4.2       | UN1383 | I   | 4.2 ..... | B11, T21, TP7, TP33                 | None .... | 187 ..... | 242 ..... | Forbidden | Forbidden | D |         |
| G Pyrophoric solid, inorganic, n.o.s..                                                  | 4.2       | UN3200 | I   | 4.2 ..... | T21, TP7, TP33                      | None .... | 187 ..... | 242 ..... | Forbidden | Forbidden | D |         |
| G Pyrophoric solids, organic, n.o.s.                                                    | 4.2       | UN2846 | I   | 4.2 ..... |                                     | None .... | 187 ..... | 242 ..... | Forbidden | Forbidden | D |         |
| Pyrosulfuryl chloride .....                                                             | 8         | UN1817 | II  | 8 .....   | B2, IB2, T8, TP2, TP12              | 154 ..... | 202 ..... | 242 ..... | 1 L       | 30 L      | C | 40      |
| <i>Pyroxylin solution or solvent, see Nitrocellulose.</i>                               |           |        |     |           |                                     |           |           |           |           |           |   |         |
| Pyrrolidine .....                                                                       | 3         | UN1922 | II  | 3, 8 .... | IB2, T7, TP1                        | 150 ..... | 202 ..... | 243 ..... | 1 L       | 5 L       | B | 40, 52  |
| Quebrachitol pentanitrate .....                                                         | Forbidden |        |     |           |                                     |           |           |           |           |           |   |         |
| Quicklime, see Calcium oxide ...                                                        |           |        |     |           |                                     |           |           |           |           |           |   |         |
| Quinoline .....                                                                         | 6.1       | UN2656 | III | 6.1 ..... | IB3, T4, TP1                        | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A | 12      |
| R 12, see Dichlorodifluoromethane.                                                      |           |        |     |           |                                     |           |           |           |           |           |   |         |

## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                 | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|-----------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                             |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                             |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
| R        | 12B1, see Chlorodifluorobromomethane.                                                                                       | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 13, see Chlorotrifluoromethane.                                                                                             | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 13B1, see Bromotrifluoromethane.                                                                                            | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 14, see Tetrafluoromethane ...                                                                                              | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 21, see Dichlorofluoromethane.                                                                                              | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 22, see Chlorodifluoromethane.                                                                                              | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 114, see Dichlorotetrafluoroethane.                                                                                         | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 115, see Chloropentafluoroethane.                                                                                           | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 116, see Hexafluoroethane ....                                                                                              | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 124, see Chlorotetrafluoroethane.                                                                                           | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 133a, see Chlorotrifluoroethane.                                                                                            | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 152a, see Difluoroethane .....                                                                                              | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 500, see Dichlorodifluoro- methane and difluorethane, etc.                                                                  | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 502, see Chlorodifluoromethane and chloropentafluoroethane mixture, etc.                                                    | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
| R        | 503, see Chlorotrifluoromethane and trifluoromethane, etc.                                                                  | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | Radioactive material, excepted package-articles manufac- tured from natural uranium or depleted uranium or natural thorium. | 7                          | UN2909                     | ..... | None        |                                  | 422, 426.             | 422, 426. | 422, 426. | .....                                           | .....                 | A                | ..... |
|          | Radioactive material, excepted package-empty packaging.                                                                     | 7                          | UN2908                     | ..... | Empty       |                                  | 422, 428.             | 422, 428. | 422, 428. | .....                                           | .....                 | A                | ..... |
|          | Radioactive material, excepted package-instruments or arti- cles.                                                           | 7                          | UN2911                     | ..... | None        |                                  | 422, 424.             | 422, 424. | .....     | .....                                           | .....                 | A                | ..... |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|                                                                                                               |     |        |       |         |                  |                |                |                |           |           |   |              |
|---------------------------------------------------------------------------------------------------------------|-----|--------|-------|---------|------------------|----------------|----------------|----------------|-----------|-----------|---|--------------|
| Radioactive material, excepted package-limited quantity of material.                                          | 7   | UN2910 | ..... | None    |                  | 421, 422.      | 421, 422.      | 421, 422.      | .....     | .....     | A | .....        |
| Radioactive material, low specific activity (LSA-I) <i>non fissile or fissile-excepted</i> .                  | 7   | UN2912 | ..... | 7       | A56, T5, TP4, W7 | 421, 422, 428. | 427            | 427            | .....     | .....     | A | 95, 129      |
| Radioactive material, low specific activity (LSA-II) <i>non fissile or fissile-excepted</i> .                 | 7   | UN3321 | ..... | 7       | A56, T5, TP4, W7 | 421, 422, 428. | 427            | 427            | .....     | .....     | A | 95, 129      |
| Radioactive material, low specific activity (LSA-III) <i>non fissile or fissile excepted</i> .                | 7   | UN3322 | ..... | 7       | A56, T5, TP4, W7 | 421, 422, 428. | 427            | 427            | .....     | .....     | A | 95, 129      |
| Radioactive material, surface contaminated objects (SCO-I or SCO-II) <i>non fissile or fissile-excepted</i> . | 7   | UN2913 | ..... | 7       | A56              | 421, 422, 428. | 427            | 427            | .....     | .....     | A | 95           |
| Radioactive material, transported under special arrangement, <i>non fissile or fissile excepted</i> .         | 7   | UN2919 | ..... | 7       | A56, 139         | .....          | .....          | .....          | .....     | .....     | A | 95, 105      |
| Radioactive material, transported under special arrangement, fissile.                                         | 7   | UN3331 | ..... | 7       | A56, 139         | .....          | .....          | .....          | .....     | .....     | A | 95, 105      |
| Radioactive material, Type A package, fissile <i>non-special form</i> .                                       | 7   | UN3327 | ..... | 7       | A56, W7, W8      | 453            | 417            | 417            | .....     | .....     | A | 95, 105, 131 |
| Radioactive material, Type A package <i>non-special form, non fissile or fissile-excepted</i> .               | 7   | UN2915 | ..... | 7       | A56, W7, W8      | None           | 415, 418, 419. | 415, 418, 419. | .....     | .....     | A | 95, 130      |
| Radioactive material, Type A package, special form <i>non fissile or fissile-excepted</i> .                   | 7   | UN3332 | ..... | 7       | A56, W7, W8      | .....          | 415, 476.      | 415, 476.      | .....     | .....     | A | 95           |
| Radioactive material, Type A package, special form, fissile.                                                  | 7   | UN3333 | ..... | 7       | A56, W7, W8      | 453            | 417, 476.      | 417, 476.      | .....     | .....     | A | 95, 105      |
| Radioactive material, Type B(M) package, fissile.                                                             | 7   | UN3329 | ..... | 7       | A56              | 453            | 417            | 417            | .....     | .....     | A | 95, 105      |
| Radioactive material, Type B(M) package <i>non fissile or fissile-excepted</i> .                              | 7   | UN2917 | ..... | 7       | A56              | .....          | 416            | 416            | .....     | .....     | A | 95, 105      |
| Radioactive material, Type B(U) package, fissile.                                                             | 7   | UN3328 | ..... | 7       | A56              | 453            | 417            | 417            | .....     | .....     | A | 95, 105      |
| Radioactive material, Type B(U) package <i>non fissile or fissile-excepted</i> .                              | 7   | UN2916 | ..... | 7       | A56              | .....          | 416            | 416            | .....     | .....     | A | 95, 105      |
| Radioactive material, uranium hexafluoride <i>non fissile or fissile-excepted</i> .                           | 7   | UN2978 | ..... | 7, 8    |                  | 423            | 420, 427.      | 420, 427.      | .....     | .....     | A | 95, 132      |
| Radioactive material, uranium hexafluoride, fissile.                                                          | 7   | UN2977 | ..... | 7, 8    | .....            | 453            | 417, 420.      | 417, 420.      | .....     | .....     | A | 95, 132      |
| A W Rags, oily                                                                                                | 4.2 | UN1856 | ..... | III 4.2 |                  | 151            | 213            | 240            | Forbidden | Forbidden | A | .....        |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                               | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                                                                           |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                                                                           |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
|          | <i>Railway torpedo, see Signals, railway track, explosive.</i>                                                                                                            | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>RC 318, see Octafluorocyclobutane.</i>                                                                                                                                 | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>RDX and cyclotetramethylenetetranitra- mine, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized.</i>                                              | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>RDX and HMX mixtures, wetted with not less than 15 percent water by mass or RDX and HMX mixtures, desensitized with not less than 10 percent phlegmatizer by mass.</i> | 1.1D                       | UN0391                     | II    | 1.1D ..     |                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | ..... |
|          | <i>RDX and Octogen mixtures, wetted or desensitized see RDX and HMX mixtures, wetted or desensitized etc.</i>                                                             | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>RDX, see Cyclotrimethylene trinitramine, etc.</i>                                                                                                                      | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>Receptacles, small, containing agas (gas cartridges) non- flammable, without release device, not refillable and not exceeding 1 L capacity.</i>                        | 2.2                        | UN2037                     | ..... | 2.2, 5.1.   | A14                              | 306 .....             | 304 ..... | None .... | 1 kg                                            | 15 kg                 | B                | 40    |
|          | <i>Receptacles, small, containing gas (gas cartridges) flam- mable, without release device, not refillable and not exceed- ing 1 L capacity.</i>                          | 2.1                        | UN2037                     | ..... | 2.1 .....   |                                  | 306 .....             | 304 ..... | None .... | 1 kg                                            | 15 kg                 | B                | 40    |
|          | <i>Receptacles, small, containing gas (gas cartridges) non-flam- mable, without release device, not refillable and not exceed- ing 1 L capacity.</i>                      | 2.2                        | UN2037                     | ..... | 2.2 .....   |                                  | 306 .....             | 304 ..... | None .... | 1 kg                                            | 15 kg                 | B                | 40    |
|          | <i>Red phosphorus, see Phos- phorus, amorphous.</i>                                                                                                                       | .....                      |                            |       | .....       |                                  | .....                 | .....     | .....     | .....                                           | .....                 |                  | ..... |
|          | <i>Refrigerant gas R 404A</i>                                                                                                                                             | 2.2                        | UN3337                     | ..... | 2.2 .....   | T50                              | 306 .....             | 304 ..... | 314, 315. | 75 kg                                           | 150 kg                | A                | ..... |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|   |                                                                                                                 |      |        |       |      |       |                                |              |       |     |       |              |           |           |    |                    |
|---|-----------------------------------------------------------------------------------------------------------------|------|--------|-------|------|-------|--------------------------------|--------------|-------|-----|-------|--------------|-----------|-----------|----|--------------------|
|   | Refrigerant gas R 407A .....                                                                                    | 2.2  | UN3338 | ..... | 2.2  | ..... | T50                            | 306          | ..... | 304 | ..... | 314,<br>315. | 75 kg     | 150 kg    | A  | .....              |
|   | Refrigerant gas R 407B .....                                                                                    | 2.2  | UN3339 | ..... | 2.2  | ..... | T50                            | 306          | ..... | 304 | ..... | 314,<br>315. | 75 kg     | 150 kg    | A  | .....              |
|   | Refrigerant gas R 407C .....                                                                                    | 2.2  | UN3340 | ..... | 2.2  | ..... | T50                            | 306          | ..... | 304 | ..... | 314,<br>315. | 75 kg     | 150 kg    | A  | .....              |
| G | Refrigerant gases, n.o.s. ....                                                                                  | 2.2  | UN1078 | ..... | 2.2  | ..... | T50                            | 306          | ..... | 304 | ..... | 314,<br>315. | 75 kg     | 150 kg    | A  | .....              |
| D | Refrigerant gases, n.o.s. or Dis-<br>persant gases, n.o.s..                                                     | 2.1  | NA1954 | ..... | 2.1  | ..... | T50                            | 306          | ..... | 304 | ..... | 314,<br>315. | Forbidden | 150 kg    | D  | 40                 |
|   | Refrigerating machines, con-<br>taining flammable, non-toxic,<br>liquefied gas.                                 | 2.1  | UN3358 | ..... | 2.1  | ..... | .....                          | 306,<br>307. | ..... | 306 | ..... | 306          | Forbidden | Forbidden | D  | 40                 |
|   | Refrigerating machines, con-<br>taining non-flammable, non-<br>toxic gases, or ammonia solu-<br>tions (UN2672). | 2.2  | UN2857 | ..... | 2.2  | ..... | A53                            | 306,<br>307. | ..... | 306 | ..... | 306,<br>307. | 450 kg    | 450 kg    | A  | .....              |
|   | Regulated medical waste, n.o.s.<br>or Clinical waste, unspecified,<br>n.o.s. or (BIO) Medical waste,<br>n.o.s.  | 6.2  | UN3291 | II    | 6.2  | ..... | A13                            | 134          | ..... | 197 | ..... | 197          | No limit  | No limit  | B  | 40.                |
|   | Release devices, explosive .....                                                                                | 1.4S | UN0173 | II    | 1.4S | ...   |                                | None         | ...   | 62  | ..... | None         | 25 kg     | 100 kg    | 05 | .....              |
|   | Resin solution, flammable .....                                                                                 | 3    | UN1866 | I     | 3    | ..... | B52, T11, TP1,<br>TP8, TP28    | 150          | ..... | 201 | ..... | 243          | 1 L       | 30 L      | E  | .....              |
|   | .....                                                                                                           |      |        | II    | 3    | ..... | 149, B52, IB2,<br>T4, TP1, TP8 | 150          | ..... | 173 | ..... | 242          | 5 L       | 60 L      | B  | .....              |
|   | .....                                                                                                           |      |        | III   | 3    | ..... | B1, B52, IB3, T2,<br>TP1       | 150          | ..... | 173 | ..... | 242          | 60 L      | 220 L     | A  | .....              |
|   | Resorcinol .....                                                                                                | 6.1  | UN2876 | III   | 6.1  | ..... | IB8, IP3, T1,<br>TP33          | 153          | ..... | 213 | ..... | 240          | 100 kg    | 200 kg    | A  | .....              |
|   | Rifle grenade, see Grenades,<br>hand or rifle, etc.                                                             |      |        |       |      | ..... |                                |              |       |     |       |              |           |           |    | .....              |
|   | Rifle powder, see Powder,<br>smokeless (UN 0160).                                                               |      |        |       |      | ..... |                                |              |       |     |       |              |           |           |    | .....              |
|   | Rivets, explosive .....                                                                                         | 1.4S | UN0174 | II    | 1.4S | ...   |                                | None         | ...   | 62  | ..... | None         | 25 kg     | 100 kg    | 05 | .....              |
|   | Road asphalt or tar liquid, see<br>Tars, liquid, etc.                                                           |      |        |       |      | ..... |                                |              |       |     |       |              |           |           |    | .....              |
|   | Rocket motors .....                                                                                             | 1.3C | UN0186 | II    | 1.3C | ..    | 109                            | None         | ...   | 62  | ..... | None         | Forbidden | 220 kg    | 03 | .....              |
|   | Rocket motors .....                                                                                             | 1.1C | UN0280 | II    | 1.1C | ..    | 109                            | None         | ...   | 62  | ..... | None         | Forbidden | Forbidden | 03 | .....              |
|   | Rocket motors .....                                                                                             | 1.2C | UN0281 | II    | 1.2C | ..    | 109                            | None         | ...   | 62  | ..... | None         | Forbidden | Forbidden | 03 | .....              |
|   | Rocket motors, liquid fueled .....                                                                              | 1.2J | UN0395 | II    | 1.2J | ...   | 109                            | None         | ...   | 62  | ..... | None         | Forbidden | Forbidden | 04 | 23E                |
|   | Rocket motors, liquid fueled .....                                                                              | 1.3J | UN0396 | II    | 1.3J | ...   | 109                            | None         | ...   | 62  | ..... | None         | Forbidden | Forbidden | 04 | 23E                |
|   | Rocket motors with hypergolic<br>liquids with or without an ex-<br>pelling charge.                              | 1.3L | UN0250 | II    | 1.3L | ...   | 109                            | None         | ...   | 62  | ..... | None         | Forbidden | Forbidden | 08 | 8E,<br>14E,<br>15E |
|   | Rocket motors with hypergolic<br>liquids with or without an ex-<br>pelling charge.                              | 1.2L | UN0322 | II    | 1.2L | ...   | 109                            | None         | ...   | 62  | ..... | None         | Forbidden | Forbidden | 08 | 8E,<br>14E,<br>15E |
|   | Rockets, line-throwing .....                                                                                    | 1.2G | UN0238 | II    | 1.2G | ..    |                                | None         | ...   | 62  | ..... | None         | Forbidden | Forbidden | 07 | .....              |
|   | Rockets, line-throwing .....                                                                                    | 1.3G | UN0240 | II    | 1.3G | ..    |                                | None         | ...   | 62  | ..... | None         | Forbidden | 75 kg     | 07 | .....              |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                              | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)     | (8)                   |           |           | (9)                                             |                       | (10)             |         |
|----------|--------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|--------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|---------|
|          |                                                                                                                          |                            |                            |       |             |                                      | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |         |
|          |                                                                                                                          |                            |                            |       |             |                                      | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other   |
|          | Rockets, line-throwing .....                                                                                             | 1.4G                       | UN0453                     | II    | 1.4G ..     |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 06               | .....   |
|          | Rockets, liquid fueled <i>with burst- ing charge</i> .                                                                   | 1.1J                       | UN0397                     | II    | 1.1J ...    |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 04               | 23E     |
|          | Rockets, liquid fueled <i>with burst- ing charge</i> .                                                                   | 1.2J                       | UN0398                     | II    | 1.2J ...    |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 04               | 23E     |
|          | Rockets, <i>with bursting charge</i> ...                                                                                 | 1.1F                       | UN0180                     | II    | 1.1F ...    |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | .....   |
|          | Rockets, <i>with bursting charge</i> ...                                                                                 | 1.1E                       | UN0181                     | II    | 1.1E ...    |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....   |
|          | Rockets, <i>with bursting charge</i> ...                                                                                 | 1.2E                       | UN0182                     | II    | 1.2E ...    |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....   |
|          | Rockets, <i>with bursting charge</i> ...                                                                                 | 1.2F                       | UN0295                     | II    | 1.2F ...    |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 08               | .....   |
|          | Rockets, <i>with expelling charge</i> ..                                                                                 | 1.2C                       | UN0436                     | II    | 1.2C ..     |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....   |
|          | Rockets, <i>with expelling charge</i> ..                                                                                 | 1.3C                       | UN0437                     | II    | 1.3C ..     |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....   |
|          | Rockets, <i>with expelling charge</i> ..                                                                                 | 1.4C                       | UN0438                     | II    | 1.4C ..     |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 02               | .....   |
|          | Rockets, <i>with inert head</i> .....                                                                                    | 1.3C                       | UN0183                     | II    | 1.3C ..     |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 03               | .....   |
|          | Rockets, <i>with inert head</i> .....                                                                                    | 1.2C                       | UN0502                     | ..... | 1.2C ..     |                                      | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | B                | 1E, 5E  |
|          | Rosin oil .....                                                                                                          | 3                          | UN1286                     | II    | 3 .....     | IB2, T4, TP1                         | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....   |
|          | .....                                                                                                                    | .....                      | .....                      | III   | 3 .....     | B1, IB3, T2, TP1                     | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....   |
|          | Rubber solution .....                                                                                                    | 3                          | UN1287                     | II    | 3 .....     | 149, IB2, T4, TP1, TP8               | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....   |
|          | .....                                                                                                                    | .....                      | .....                      | III   | .....       | B1, IB3, T2, TP1                     | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....   |
|          | Rubber scrap or shoddy, <i>pow- dered or granulated, not ex- ceeding 840 microns and rub- ber contend exceeding 45%.</i> | 4.1                        | UN1345                     | II    | 4.1 .....   | IB8, IP2, IP4, T3, TP33              | 151 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                 | A                | .....   |
|          | Rubidium .....                                                                                                           | 4.3                        | UN1423                     | I     | 4.3 .....   | 22, A7, A19, IB4, IP1, N34, N40, N45 | None ....             | 211 ..... | 242 ..... | Forbidden                                       | 15 kg                 | D                | 52      |
|          | Rubidium hydroxide .....                                                                                                 | 8                          | UN2678                     | II    | 8 .....     | IB8, IP2, IP4, T3, TP33              | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                 | A                | 29, 52. |
|          | Rubidium hydroxide solution .....                                                                                        | 8                          | UN2677                     | II    | 8 .....     | B2, IB2, T7, TP2                     | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                  | A                | 29, 52. |
|          | .....                                                                                                                    | .....                      | .....                      | III   | 8 .....     | IB3, T4, TP1                         | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | 29, 52. |
|          | Safety fuse, see Fuse, safety ....                                                                                       | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
| G        | Samples, explosive, <i>other than initiating explosives.</i>                                                             | .....                      | UN0190                     | II    | .....       | 113                                  | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 14               | .....   |
|          | Sand acid, see Fluorosilicic acid .....                                                                                  | .....                      | .....                      | ..... | .....       | .....                                | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|     |                                                                                                                                                                                                                                         |           |        |       |           |                                       |           |           |           |           |           |   |       |
|-----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-------|-----------|---------------------------------------|-----------|-----------|-----------|-----------|-----------|---|-------|
|     | Seed cake, containing vegetable oil solvent extractions and expelled seeds, with not more than 10 percent of oil and when the amount of moisture is higher than 11 percent, with not more than 20 percent of oil and moisture combined. | 4.2       | UN1386 | III   | None      | IB8, IP3, IP7, N7                     | None .... | 213 ..... | 241 ..... | Forbidden | Forbidden | A | 13    |
| I   | Seed cake with more than 1.5 percent oil and not more than 11 percent moisture.                                                                                                                                                         | 4.2       | UN1386 | III   | None      | IB8, IP3, IP7, N7                     | None .... | 213 ..... | 241 ..... | Forbidden | Forbidden | E | 13    |
| I   | Seed cake with not more than 1.5 percent oil and not more than 11 percent moisture.                                                                                                                                                     | 4.2       | UN2217 | III   | None      | IB8, IP3, IP7, N7                     | None .... | 213 ..... | 241 ..... | Forbidden | Forbidden | A | 13    |
|     | Selenates or Selenites .....                                                                                                                                                                                                            | 6.1       | UN2630 | I     | 6.1 ..... | IB7, IP1, T6, TP33                    | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | E | ..... |
|     | Selenic acid .....                                                                                                                                                                                                                      | 8         | UN1905 | I     | 8 .....   | IB7, IP1, N34, T6, TP33               | None .... | 211 ..... | 242 ..... | Forbidden | 25 kg     | A | ..... |
|     | Selenium compound, liquid, n.o.s.                                                                                                                                                                                                       | 6.1       | UN3440 | I     | 6.1 ..... | T14, TP2, TP27                        | None .... | 201 ..... | 243 ..... | 1L        | 30L       | B | ..... |
|     |                                                                                                                                                                                                                                         |           |        | II    | 6.1 ..... | IIB2, T11, TP2, TP27                  | 153 ..... | 202 ..... | 243 ..... | 5 L       | 60 L      | B | ..... |
|     |                                                                                                                                                                                                                                         |           |        | III   | 6.1 ..... | IB3, T7, TP1, TP28                    | 153 ..... | 203 ..... | 241 ..... | 60 L      | 220 L     | A | ..... |
|     | Selenium compound, solid, n.o.s..                                                                                                                                                                                                       | 6.1       | UN3283 | I     | 6.1 ..... | IB7, IP1, T6, TP33                    | None .... | 211 ..... | 242 ..... | 5 kg      | 50 kg     | B | ..... |
|     |                                                                                                                                                                                                                                         |           |        | II    | 6.1 ..... | IB8, IP2, IP4, T3, TP33               | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | B | ..... |
|     |                                                                                                                                                                                                                                         |           |        | III   | 6.1 ..... | IB8, IP3, T1, TP33                    | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A | ..... |
|     | Selenium disulfide .....                                                                                                                                                                                                                | 6.1       | UN2657 | II    | 6.1 ..... | IB8, IP2, IP4, T3, TP33               | 153 ..... | 212 ..... | 242 ..... | 25 kg     | 100 kg    | A | ..... |
|     | Selenium hexafluoride .....                                                                                                                                                                                                             | 2.3       | UN2194 | ..... | 2.3, 8    | 1                                     | None .... | 302 ..... | None .... | Forbidden | Forbidden | D | 40    |
|     | Selenium nitride .....                                                                                                                                                                                                                  | Forbidden |        |       |           |                                       |           |           |           |           |           |   |       |
|     | Selenium oxychloride .....                                                                                                                                                                                                              | 8         | UN2879 | I     | 8, 6.1    | A3, A6, A7, N34, T10, TP2, TP12, TP13 | None .... | 201 ..... | 243 ..... | 0.5 L     | 2.5 L     | E | 40    |
|     | Self-defense spray, aerosol, see Aerosols, etc.                                                                                                                                                                                         | .....     |        |       |           |                                       |           |           |           |           |           |   |       |
| + A | Self-defense spray, non-pressurized.                                                                                                                                                                                                    | 9         | NA3334 | III   | 9 .....   | A37                                   | 155 ..... | 203 ..... | None .... | No limit  | No limit  | A | ..... |
| D   |                                                                                                                                                                                                                                         |           |        |       |           |                                       |           |           |           |           |           |   |       |
| G   | Self-heating liquid, corrosive, inorganic, n.o.s..                                                                                                                                                                                      | 4.2       | UN3188 | II    | 4.2, 8    | IB2                                   | None .... | 202 ..... | 243 ..... | 1 L       | 5 L       | C | ..... |
|     |                                                                                                                                                                                                                                         |           |        | III   | 4.2, 8    | IB2                                   | None .... | 203 ..... | 241 ..... | 5 L       | 60 L      | C | ..... |
| G   | Self-heating liquid, corrosive, organic, n.o.s..                                                                                                                                                                                        | 4.2       | UN3185 | II    | 4.2, 8    | IB2                                   | None .... | 202 ..... | 243 ..... | 1 L       | 5 L       | C | ..... |
|     |                                                                                                                                                                                                                                         |           |        | III   | 4.2, 8    | IB2                                   | None .... | 203 ..... | 241 ..... | 5 L       | 60 L      | C | ..... |
| G   | Self-heating liquid, inorganic, n.o.s..                                                                                                                                                                                                 | 4.2       | UN3186 | II    | 4.2 ..... | IB2                                   | None .... | 202 ..... | 242 ..... | 1 L       | 5 L       | C | ..... |
|     |                                                                                                                                                                                                                                         |           |        | III   | 4.2 ..... | IB2                                   | None .... | 203 ..... | 241 ..... | 5 L       | 60 L      | C | ..... |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names    | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|----------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                |                            |                            |       |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                |                            |                            |       |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| G        | Self-heating liquid, organic, n.o.s..                          | 4.2                        | UN3183                     | II    | 4.2 .....   | IB2                              | None ....             | 202 ..... | 242 ..... | 1 L                                             | 5 L                   | C                | .....  |
| G        | Self-heating liquid, toxic, inor- ganic, n.o.s..               | 4.2                        | UN3187                     | III   | 4.2 .....   | IB2                              | None ....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | C                | .....  |
|          |                                                                |                            |                            | II    | 4.2, 6.1.   | IB2                              | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | C                | .....  |
| G        | Self-heating liquid, toxic, or- ganic, n.o.s..                 | 4.2                        | UN3184                     | III   | 4.2, 6.1.   | IB2                              | None ....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | C                | .....  |
|          |                                                                |                            |                            | II    | 4.2, 6.1.   | IB2                              | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | C                | .....  |
| G        | Self-heating solid, corrosive, in- organic, n.o.s..            | 4.2                        | UN3192                     | III   | 4.2, 6.1.   | IB2                              | None ....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | C                | .....  |
|          |                                                                |                            |                            | II    | 4.2, 8      | IB5, IP2, T3, TP33               | None ....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                 | C                | .....  |
| G        | Self-heating, solid, corrosive, or- ganic, n.o.s..             | 4.2                        | UN3126                     | III   | 4.2, 8      | IB8, IP3, T1, TP33               | None ....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg                | C                | .....  |
|          |                                                                |                            |                            | II    | 4.2, 8      | IB5, IP2, T3, TP33               | None ....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                 | C                | .....  |
| G        | Self-heating solid, inorganic, n.o.s..                         | 4.2                        | UN3190                     | III   | 4.2, 8      | IB8, IP3, T1, TP33               | None ....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg                | C                | .....  |
|          |                                                                |                            |                            | II    | 4.2 .....   | IB6, IP2, T3, TP33               | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                 | C                | .....  |
| G        | Self-heating, solid, organic, n.o.s..                          | 4.2                        | UN3088                     | III   | 4.2 .....   | IB8, IP3, T1, TP33               | None ....             | 213 ..... | 241 ..... | 25 kg                                           | 100 kg                | C                | .....  |
|          |                                                                |                            |                            | II    | 4.2 .....   | IB6, IP2, T3, TP33               | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                 | C                | .....  |
| G        | Self-heating, solid, oxidizing, n.o.s..                        | 4.2                        | UN3127                     | ..... | 4.2, 5.1.   | None ....                        | 214 .....             | 214 ..... | Forbidden | Forbidden                                       |                       |                  | .....  |
| G        | Self-heating solid, toxic, inor- ganic, n.o.s..                | 4.2                        | UN3191                     | II    | 4.2, 6.1.   | IB5, IP2, T3, TP33               | None ....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                 | C                | .....  |
|          |                                                                |                            |                            | III   | 4.2, 6.1.   | IB8, IP3, T1, TP33               | None ....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg                | C                | .....  |
| G        | Self-heating, solid, toxic, or- ganic, n.o.s..                 | 4.2                        | UN3128                     | II    | 4.2, 6.1.   | IB5, IP2, T3, TP33               | None ....             | 212 ..... | 242 ..... | 15 kg                                           | 50 kg                 | C                | .....  |
|          |                                                                |                            |                            | III   | 4.2, 6.1.   | IB8, IP3, T1, TP33               | None ....             | 213 ..... | 242 ..... | 25 kg                                           | 100 kg                | C                | .....  |
|          | <i>Self-propelled vehicle, see En- gines or Batteries etc.</i> |                            |                            |       |             |                                  |                       |           |           |                                                 |                       |                  |        |
| G        | Self-reactive liquid type B .....                              | 4.1                        | UN3221                     | II    | 4.1 .....   | 53                               | None ....             | 224 ..... | None .... | Forbidden                                       | Forbidden             | D                | 52, 53 |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                         |      |        |       |      |       |                     |       |       |       |       |       |       |           |           |    |           |
|---|-----------------------------------------------------------------------------------------|------|--------|-------|------|-------|---------------------|-------|-------|-------|-------|-------|-------|-----------|-----------|----|-----------|
| G | Self-reactive liquid type B, temperature controlled.                                    | 4.1  | UN3231 | II    | 4.1  | ..... | 53                  | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive liquid type C .....                                                       | 4.1  | UN3223 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 5 L       | 10 L      | D  | 52, 53    |
| G | Self-reactive liquid type C, temperature controlled.                                    | 4.1  | UN3233 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive liquid type D .....                                                       | 4.1  | UN3225 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 5 L       | 10 L      | D  | 52, 53    |
| G | Self-reactive liquid type D, temperature controlled.                                    | 4.1  | UN3235 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive liquid type E .....                                                       | 4.1  | UN3227 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 10 L      | 25 L      | D  | 52, 53    |
| G | Self-reactive liquid type E, temperature controlled.                                    | 4.1  | UN3237 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive liquid type F .....                                                       | 4.1  | UN3229 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 10 L      | 25 L      | D  | 52, 53    |
| G | Self-reactive liquid type F, temperature controlled.                                    | 4.1  | UN3239 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive solid type B .....                                                        | 4.1  | UN3222 | II    | 4.1  | ..... | 53                  | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 52, 53    |
| G | Self-reactive solid type B, temperature controlled.                                     | 4.1  | UN3232 | II    | 4.1  | ..... | 53                  | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive solid type C .....                                                        | 4.1  | UN3224 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 5 kg      | 10 kg     | D  | 52, 53    |
| G | Self-reactive solid type C, temperature controlled.                                     | 4.1  | UN3234 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive solid type D .....                                                        | 4.1  | UN3226 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 5 kg      | 10 kg     | D  | 52, 53    |
| G | Self-reactive solid type D, temperature controlled.                                     | 4.1  | UN3236 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive solid type E .....                                                        | 4.1  | UN3228 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 10 kg     | 25 kg     | D  | 52, 53    |
| G | Self-reactive solid type E, temperature controlled.                                     | 4.1  | UN3238 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
| G | Self-reactive solid type F .....                                                        | 4.1  | UN3230 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | 10 kg     | 25 kg     | D  | 52, 53    |
| G | Self-reactive solid type F, temperature controlled.                                     | 4.1  | UN3240 | II    | 4.1  | ..... |                     | None  | ....  | 224   | ..... | None  | ....  | Forbidden | Forbidden | D  | 2, 52, 53 |
|   | Shale oil .....                                                                         | 3    | UN1288 | I     | 3    | ..... | T11, TP1, TP8, TP27 | None  | ....  | 201   | ..... | 243   | ..... | 1 L       | 30 L      | B  | .....     |
|   | .....                                                                                   |      |        | II    | 3    | ..... | IB2, T4, TP1, TP8   | 150   | ..... | 202   | ..... | 242   | ..... | 5 L       | 60 L      | B  | .....     |
|   | .....                                                                                   |      |        | III   | 3    | ..... | B1, IB3, T2, TP1    | 150   | ..... | 203   | ..... | 242   | ..... | 60 L      | 220 L     | A  | .....     |
|   | .....                                                                                   |      |        |       |      |       |                     | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     |    | .....     |
|   | <i>Shaped charges, see Charges, shaped, etc.</i>                                        |      |        |       |      |       |                     |       |       |       |       |       |       |           |           |    |           |
|   | Signal devices, hand .....                                                              | 1.4G | UN0191 | II    | 1.4G | ..    |                     | None  | ....  | 62    | ..... | None  | ....  | Forbidden | 75 kg     | 06 | .....     |
|   | Signal devices, hand .....                                                              | 1.4S | UN0373 | II    | 1.4S | ...   |                     | None  | ....  | 62    | ..... | None  | ....  | 25 kg     | 100 kg    | 05 | .....     |
|   | Signals, distress, <i>ship</i> .....                                                    | 1.1G | UN0194 | II    | 1.1G | ..    |                     | None  | ....  | 62    | ..... | None  | ....  | Forbidden | Forbidden | 07 | .....     |
|   | Signals, distress, <i>ship</i> .....                                                    | 1.3G | UN0195 | II    | 1.3G | ..    |                     | None  | ....  | 62    | ..... | None  | ....  | Forbidden | 75 kg     | 07 | .....     |
|   | <i>Signals, highway, see</i> Signal devices, hand.                                      |      |        |       |      |       |                     | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     |    | .....     |
|   | Signals, railway track, explosive                                                       | 1.1G | UN0192 | II    | 1.1G | ..    |                     | None  | ....  | 62    | ..... | None  | ....  | Forbidden | Forbidden | 07 | .....     |
|   | Signals, railway track, explosive                                                       | 1.4S | UN0193 | II    | 1.4S | ...   |                     | None  | ....  | 62    | ..... | None  | ....  | 25 kg     | 100 kg    | 05 | .....     |
|   | Signals, railway track, explosive                                                       | 1.3G | UN0492 | ..... | 1.3G | ..    |                     | None  | ....  | 62    | ..... | None  | ....  | Forbidden | Forbidden | 07 | .....     |
|   | Signals, railway track, explosive                                                       | 1.4G | UN0493 | ..... | 1.4G | ..    |                     | None  | ....  | 62    | ..... | None  | ....  | Forbidden | 75 kg     | 06 | .....     |
|   | <i>Signals, ship distress, water-activated, see</i> Contrivances, water-activated, etc. |      |        |       |      |       |                     | ..... | ..... | ..... | ..... | ..... | ..... | .....     | .....     |    | .....     |
|   | Signals, smoke .....                                                                    | 1.1G | UN0196 | II    | 1.1G | ..    |                     | None  | ....  | 62    | ..... | None  | ....  | Forbidden | Forbidden | 07 | .....     |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names               | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102)           | (8)                   |           |           | (9)                                             |                      | (10)            |             |
|----------|---------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|-------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|-------------|
|          |                                                                           |                           |                          |     |             |                                           | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |             |
|          |                                                                           |                           |                          |     |             |                                           | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other       |
|          | Signals, smoke .....                                                      | 1.4G                      | UN0197                   | II  | 1.4G ..     |                                           | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                | 06              | .....       |
|          | Signals, smoke .....                                                      | 1.2G                      | UN0313                   | II  | 1.2G ..     |                                           | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 07              | .....       |
|          | Signals, smoke .....                                                      | 1.3G                      | UN0487                   | II  | 1.3G ..     |                                           | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 07              | .....       |
|          | Silane .....                                                              | 2.1                       | UN2203                   |     | 2.1 .....   |                                           | None ....             | 302 ..... | None .... | Forbidden                                       | Forbidden            | E               | 40, 57, 104 |
|          | <i>Silicofluoric acid, see Fluorosilicic acid.</i> .....                  |                           |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | <i>Silicon chloride, see Silicon tetrachloride.</i> .....                 |                           |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | Silicon powder, amorphous .....                                           | 4.1                       | UN1346                   | III | 4.1 .....   | A1, IB8, IP3, T1, TP33                    | None ....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | 74          |
|          | Silicon tetrachloride .....                                               | 8                         | UN1818                   | II  | 8 .....     | A3, A6, B2, B6, IB2, T7, TP2, TP7         | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                 | C               | 40          |
|          | Silicon tetrafluoride .....                                               | 2.3                       | UN1859                   |     | 2.3, 8      | 2                                         | None ....             | 302 ..... | None .... | Forbidden                                       | Forbidden            | D               | 40          |
|          | <i>Silver acetylide (dry)</i> .....                                       | Forbidden                 |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | Silver arsenite .....                                                     | 6.1                       | UN1683                   | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33                   | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | A               | .....       |
|          | <i>Silver azide (dry)</i> .....                                           | Forbidden                 |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | <i>Silver chlorite (dry)</i> .....                                        | Forbidden                 |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | Silver cyanide .....                                                      | 6.1                       | UN1684                   | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33                   | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | A               | 40, 52      |
|          | <i>Silver fulminate (dry)</i> .....                                       | Forbidden                 |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | Silver nitrate .....                                                      | 5.1                       | UN1493                   | II  | 5.1 .....   | IB8, IP4, T3, TP33                        | 152 .....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg                | A               | .....       |
|          | <i>Silver oxalate (dry)</i> .....                                         | Forbidden                 |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | <i>Silver picrate (dry)</i> .....                                         | Forbidden                 |                          |     |             |                                           |                       |           |           |                                                 |                      |                 |             |
|          | Silver picrate, wetted with not less than 30 percent water, by mass. .... | 4.1                       | UN1347                   | I   | 4.1 .....   | 23                                        | None ....             | 211 ..... | None .... | Forbidden                                       | Forbidden            | D               | 28, 36      |
|          | Sludge, acid .....                                                        | 8                         | UN1906                   | II  | 8 .....     | A3, A7, B2, IB2, N34, T8, TP2, TP12, TP28 | None ....             | 202 ..... | 242 ..... | Forbidden                                       | 30 L                 | C               | 14          |
| D        | Smokeless powder for small arms (100 pounds or less). ....                | 4.1                       | NA3178                   | I   | 4.1 .....   | 16                                        | None ....             | 171 ..... | None .... | Forbidden                                       | 7.3 kg               | A               | .....       |
|          | Soda lime with more than 4 percent sodium hydroxide. ....                 | 8                         | UN1907                   | III | 8 .....     | IB8, IP3, T1, TP33                        | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | 52.         |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|   |                                                                                                                                                           |     |        |     |     |                                                                    |      |     |     |           |        |   |             |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|-----|-----|--------------------------------------------------------------------|------|-----|-----|-----------|--------|---|-------------|
| A | Sodium .....                                                                                                                                              | 4.3 | UN1428 | I   | 4.3 | A7, A8, A19, A20, B9, B48, B68, IB4, IP1, N34, T9, TP7, TP33, TP46 | None | 211 | 244 | Forbidden | 15 kg  | D | 52          |
|   | Sodium aluminate, solid .....                                                                                                                             | 8   | UN2812 | III | 8   | IB8, IP3, T1, TP33                                                 | 154  | 213 | 240 | 25 kg     | 100 kg | A |             |
|   | Sodium aluminate, solution .....                                                                                                                          | 8   | UN1819 | II  | 8   | B2, IB2, T7, TP2                                                   | 154  | 202 | 242 | 1 L       | 30 L   | A | 52.         |
|   | Sodium aluminum hydride .....                                                                                                                             | 4.3 | UN2835 | III | 8   | IB3, T4, TP1                                                       | 154  | 203 | 241 | 5 L       | 60 L   | A | 52.         |
|   | Sodium ammonium vanadate ....                                                                                                                             | 6.1 | UN2863 | II  | 4.3 | A8, A19, A20, IB4, T3, TP33                                        | 151  | 212 | 242 | Forbidden | 50 kg  | E | 52          |
|   | Sodium arsanilate .....                                                                                                                                   | 6.1 | UN2863 | II  | 6.1 | IB8, IP2, IP4, T3, TP33                                            | 153  | 212 | 242 | 25 kg     | 100 kg | A | .....       |
|   | Sodium arsanilate .....                                                                                                                                   | 6.1 | UN2473 | III | 6.1 | IB8, IP3, T1, TP33                                                 | 153  | 213 | 240 | 100 kg    | 200 kg | A | .....       |
|   | Sodium arsenate .....                                                                                                                                     | 6.1 | UN1685 | II  | 6.1 | IB8, IP2, IP4, T3, TP33                                            | 153  | 212 | 242 | 25 kg     | 100 kg | A | .....       |
|   | Sodium arsenite, aqueous solutions.                                                                                                                       | 6.1 | UN1686 | II  | 6.1 | IB2, T7, TP2                                                       | 153  | 202 | 243 | 5 L       | 60 L   | A | .....       |
|   | .....                                                                                                                                                     |     |        | III | 6.1 | IB3, T4, TP2                                                       | 153  | 203 | 241 | 60 L      | 220 L  | A | .....       |
|   | Sodium arsenite, solid .....                                                                                                                              | 6.1 | UN2027 | II  | 6.1 | IB8, IP2, IP4, T3, TP33                                            | 153  | 212 | 242 | 25 kg     | 100 kg | A | .....       |
|   | Sodium azide .....                                                                                                                                        | 6.1 | UN1687 | II  | 6.1 | IB8, IP2, IP4                                                      | 153  | 212 | 242 | 25 kg     | 100 kg | A | 36, 52, 91  |
|   | Sodium biftuoride, see Sodium hydrogendifluoride.                                                                                                         |     |        |     |     |                                                                    |      |     |     |           |        |   | .....       |
|   | Sodium bisulfite, solution, see Bisulfites, aqueous solutions, n.o.s..                                                                                    |     |        |     |     |                                                                    |      |     |     |           |        |   | .....       |
|   | Sodium borohydride .....                                                                                                                                  | 4.3 | UN1426 | I   | 4.3 | N40                                                                | None | 211 | 242 | Forbidden | 15 kg  | E | 52          |
|   | Sodium borohydride and sodium hydroxide solution, with not more than 12 percent sodium borohydride and not more than 40 percent sodium hydroxide by mass. | 8   | UN3320 | II  | 8   | B2, IB2, N34, T7, TP2                                              | 154  | 202 | 242 | 1 L       | 30 L   | A | 52          |
|   | .....                                                                                                                                                     |     |        | III | 8   | B2, IB3, N34, T4, TP2                                              | 154  | 203 | 241 | 5 L       | 60 L   | A | 52          |
|   | Sodium bromate .....                                                                                                                                      | 5.1 | UN1494 | II  | 5.1 | IB8, IP4, T3, TP33                                                 | 152  | 212 | 242 | 5 kg      | 25 kg  | A | 56, 58      |
|   | Sodium cacodylate .....                                                                                                                                   | 6.1 | UN1688 | II  | 6.1 | IB8, IP2, IP4, T3, TP33                                            | 153  | 212 | 242 | 25 kg     | 100 kg | A | 52          |
|   | Sodium carbonate peroxyhydrate.                                                                                                                           | 5.1 | UN3378 | II  | 5.1 | IB8, IP2, IP4, T3, TP33                                            | 152  | 212 | 240 | 5 kg      | 25 kg  | A | 13, 48, 75  |
|   | .....                                                                                                                                                     |     |        | III | 5.1 | IB8, IP3, T1, TP33                                                 | 152  | 213 | 240 | 25 kg     | 100 kg | A | 13, 48, 75  |
|   | Sodium chlorate .....                                                                                                                                     | 5.1 | UN1495 | II  | 5.1 | A9, IB8, IP4, N34, T3, TP33                                        | 152  | 212 | 240 | 5 kg      | 25 kg  | A | 56, 58      |
|   | Sodium chlorate, aqueous solution.                                                                                                                        | 5.1 | UN2428 | II  | 5.1 | A2, IB2, T4, TP1                                                   | 152  | 202 | 241 | 1 L       | 5 L    | B | 56, 58, 133 |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                                                | Hazard class or Division | Identification Numbers | PG  | Label Codes | Special provisions (§ 172.102)                | (8)                   |           |           | (9)                                             |                     | (10)           |                 |
|----------|-----------------------------------------------------------------------------------------------------------|--------------------------|------------------------|-----|-------------|-----------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|---------------------|----------------|-----------------|
|          |                                                                                                           |                          |                        |     |             |                                               | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |                 |
|          |                                                                                                           |                          |                        |     |             |                                               | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Location       | Other           |
|          | .....                                                                                                     | .....                    |                        | III | 5.1 .....   | A2, IB2, T4, TP1                              | 152 .....             | 203 ..... | 241 ..... | 2.5 L                                           | 30 L                | B              | 56, 58, 69, 133 |
|          | <i>Sodium chlorate mixed with dinitrotoluene, see Explosive blasting, type C.</i>                         | .....                    |                        |     | .....       |                                               | .....                 | .....     | .....     | .....                                           | .....               |                | .....           |
|          | Sodium chlorite .....                                                                                     | 5.1                      | UN1496                 | II  | 5.1 .....   | A9, IB8, IP2, IP4, N34, T3, TP33              | None ....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg               | A              | 56, 58          |
|          | Sodium chloroacetate .....                                                                                | 6.1                      | UN2659                 | III | 6.1 .....   | IB8, IP3, T1, TP33                            | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg              | A              | .....           |
|          | Sodium cuprocyanide, solid .....                                                                          | 6.1                      | UN2316                 | I   | 6.1 .....   | IB7, IP1, T6, TP33                            | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg               | A              | 52              |
|          | Sodium cuprocyanide, solution ..                                                                          | 6.1                      | UN2317                 | I   | 6.1 .....   | T14, TP2, TP13                                | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                | B              | 40, 52          |
|          | Sodium cyanide, solid .....                                                                               | 6.1                      | UN1689                 | I   | 6.1 .....   | B69, B77, IB7, N74, N75, T6, TP33             | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg               | B              | 52              |
|          | Sodium cyanide solution .....                                                                             | 6.1                      | UN3414                 | I   | 6.1 .....   | B69, B77, N74, N75, T14, TP2, TP13            | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                | B              | 52              |
|          | .....                                                                                                     | .....                    |                        | II  | 6.1 .....   | B69, B77, IB2, N74, N75, T11, TP2, TP13, TP27 | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                | B              | 52              |
|          | .....                                                                                                     | .....                    |                        | III | 6.1 .....   | B69, B77, IB3, N74, N75, T7, TP2, TP13, TP28  | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L               | A              | 52              |
|          | <i>Sodium dichloroisocyanurate or Sodium dichloro-s-triazinetriene, see Dichloroisocyanuric acid etc.</i> | .....                    |                        |     | .....       |                                               | .....                 | .....     | .....     | .....                                           | .....               |                | .....           |
|          | Sodium dinitro-o-cresolate, dry or wetted with less than 15 percent water, by mass.                       | 1.3C                     | UN0234                 | II  | 1.3C ..     |                                               | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden           | 10             | 5E              |
|          | Sodium dinitro-o-cresolate, wetted with not less than 10% water, by mass.                                 | 4.1                      | UN3369                 | I   | 4.1 .....   | 162, A8, A19, N41, N84                        | None ....             | 211 ..... | None .... | 0.5 kg                                          | 0.5 kg              | E              | 36              |
|          | Sodium dinitro-o-cresolate, wetted with not less than 15 percent water, by mass.                          | 4.1                      | UN1348                 | I   | 4.1, 6.1    | 23, A8, A19, A20, N41                         | None ....             | 211 ..... | None .... | 1 kg                                            | 15 kg               | E              | 28, 36          |
|          | Sodium dithionite or Sodium hydrosulfite.                                                                 | 4.2                      | UN1384                 | II  | 4.2 .....   | A19, A20, IB6, IP2, T3, TP33                  | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg               | E              | 13              |
|          | Sodium fluoride, solid .....                                                                              | 6.1                      | UN1690                 | III | 6.1 .....   | IB8, IP3, T1, TP33                            | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg              | A              | 52              |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                             |     |        |     |          |                                  |      |     |     |           |        |   |                |
|-----------------------------------------------------------------------------|-----|--------|-----|----------|----------------------------------|------|-----|-----|-----------|--------|---|----------------|
| Sodium fluoride solution .....                                              | 6.1 | UN3415 | III | 6.1      | IB3, T4, TP1                     | 153  | 203 | 241 | 60 L      | 220 L  | A | 52             |
| Sodium fluoroacetate .....                                                  | 6.1 | UN2629 | I   | 6.1      | IB7, IP1, T6, TP33               | None | 211 | 242 | 5 kg      | 50 kg  | E | .....          |
| Sodium fluorosilicate .....                                                 | 6.1 | UN2674 | III | 6.1      | IB8, IP3, T1, TP33               | 153  | 213 | 240 | 100 kg    | 200 kg | A | 52             |
| <i>Sodium hydrate, see Sodium hydroxide, solid.</i>                         |     |        |     |          |                                  |      |     |     |           |        |   | .....          |
| Sodium hydride .....                                                        | 4.3 | UN1427 | I   | 4.3      | A19, N40                         | None | 211 | 242 | Forbidden | 15 kg  | E | 52             |
| Sodium hydrogendifluoride .....                                             | 8   | UN2439 | II  | 8        | IB8, IP2, IP4, N3, N34, T3, TP33 | 154  | 212 | 240 | 15 kg     | 50 kg  | A | 12, 25, 40, 52 |
| Sodium hydrosulfide, with less than 25 percent water of crystallization.    | 4.2 | UN2318 | II  | 4.2      | A7, A19, A20, IB6, IP2, T3, TP33 | None | 212 | 241 | 15 kg     | 50 kg  | A | 52.            |
| Sodium hydrosulfide with not less than 25 percent water of crystallization. | 8   | UN2949 | II  | 8        | A7, IB8, IP2, IP4, T7, TP2       | 154  | 212 | 240 | 15 kg     | 50 kg  | A | 52             |
| <i>Sodium hydrosulfite, see Sodium dithionite.</i>                          |     |        |     |          |                                  |      |     |     |           |        |   | .....          |
| Sodium hydroxide, solid .....                                               | 8   | UN1823 | II  | 8        | IB8, IP2, IP4, T3, TP33          | 154  | 212 | 240 | 15 kg     | 50 kg  | A | 52.            |
| Sodium hydroxide solution .....                                             | 8   | UN1824 | II  | 8        | B2, IB2, N34, T7, TP2            | 154  | 202 | 242 | 1 L       | 30 L   | A | 52.            |
|                                                                             |     |        | III | 8        | IB3, N34, T4, TP1                | 154  | 203 | 241 | 5 L       | 60 L   | A | 52.            |
| <i>Sodium hypochlorite, solution, see Hypochlorite solutions etc.</i>       |     |        |     |          |                                  |      |     |     |           |        |   | .....          |
| <i>Sodium metal, liquid alloy, see Alkali metal alloys, liquid, n.o.s..</i> |     |        |     |          |                                  |      |     |     |           |        |   | .....          |
| Sodium methylate .....                                                      | 4.2 | UN1431 | II  | 4.2, 8   | A7, A19, IB5, IP2, T3, TP33      | None | 212 | 242 | 15 kg     | 50 kg  | B | .....          |
| Sodium methylate solutions in alcohol.                                      | 3   | UN1289 | II  | 3, 8     | IB2, T7, TP1, TP8                | 150  | 202 | 243 | 1 L       | 5 L    | B | .....          |
|                                                                             |     |        | III | 3, 8     | B1, IB3, T4, TP1                 | 150  | 203 | 242 | 5 L       | 60 L   | A | .....          |
| Sodium monoxide .....                                                       | 8   | UN1825 | II  | 8        | IB8, IP2, IP4, T3, TP33          | 154  | 212 | 240 | 15 kg     | 50 kg  | A | 52.            |
| Sodium nitrate .....                                                        | 5.1 | UN1498 | III | 5.1      | A1, A29, IB8, IP3, T1, TP33      | 152  | 213 | 240 | 25 kg     | 100 kg | A | .....          |
| Sodium nitrate and potassium nitrate mixtures.                              | 5.1 | UN1499 | III | 5.1      | A1, A29, IB8, IP3, T1, TP33      | 152  | 213 | 240 | 25 kg     | 100 kg | A | .....          |
| Sodium nitrite .....                                                        | 5.1 | UN1500 | III | 5.1, 6.1 | A1, A29, IB8, IP3, T1, TP33      | 152  | 213 | 240 | 25 kg     | 100 kg | A | 56, 58         |
| Sodium pentachlorophenate .....                                             | 6.1 | UN2567 | II  | 6.1      | IB8, IP2, IP4, T3, TP33          | 153  | 212 | 242 | 25 kg     | 100 kg | A | .....          |
| Sodium perborate monohydrate                                                | 5.1 | UN3377 | III | 5.1      | IB8, IP3, T1, TP33               | 152  | 213 | 240 | 25 kg     | 100 kg | A | 13, 48, 75     |
| Sodium perchlorate .....                                                    | 5.1 | UN1502 | II  | 5.1      | IB6, IP2, T3, TP33               | 152  | 212 | 242 | 5 kg      | 25 kg  | A | 56, 58         |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                             | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes       | Special provi-sions (§ 172.102)   | (8)                   |           |           | (9)                                             |                      | (10)            |                |
|----------|---------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------------|-----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|----------------|
|          |                                                                                                         |                           |                          |     |                   |                                   | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |                |
|          |                                                                                                         |                           |                          |     |                   |                                   | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other          |
|          | Sodium permanganate .....                                                                               | 5.1                       | UN1503                   | II  | 5.1 .....         | IB6, IP2, T3, TP33                | 152 .....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg                | D               | 56, 58, 138    |
|          | Sodium peroxide .....                                                                                   | 5.1                       | UN1504                   | I   | 5.1 .....         | A20, IB5, IP1, N34                | None ....             | 211 ..... | None .... | Forbidden                                       | 15 kg                | B               | 13, 52, 66, 75 |
|          | Sodium peroxoborate, anhy-drous.                                                                        | 5.1                       | UN3247                   | II  | 5.1 .....         | IB8, IP4, T3, TP33                | 152 .....             | 212 ..... | 240 ..... | 5 kg                                            | 25 kg                | A               | 13, 25         |
|          | Sodium persulfate .....                                                                                 | 5.1                       | UN1505                   | III | 5.1 .....         | A1, IB8, IP3, T1, TP33            | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg               | A               | 56, 58         |
|          | Sodium phosphide .....                                                                                  | 4.3                       | UN1432                   | I   | 4.3, 6.1, 1.3C .. | A19, N40                          | None ....             | 211 ..... | None .... | Forbidden                                       | 15 kg                | E               | 40, 52, 85     |
|          | Sodium picramate, <i>dry or wetted with less than 20 percent water, by mass.</i>                        | 1.3C                      | UN0235                   | II  | 1.3C ..           |                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | 5E             |
|          | Sodium picramate, <i>wetted with not less than 20 percent water, by mass.</i>                           | 4.1                       | UN1349                   | I   | 4.1 .....         | 23, A8, A19, N41                  | None ....             | 211 ..... | None .... | Forbidden                                       | 15 kg                | E               | 28, 36         |
|          | Sodium picryl peroxide .....                                                                            | Forbidden                 |                          |     |                   |                                   |                       |           |           |                                                 |                      |                 |                |
|          | Sodium potassium alloys, <i>see</i> Potassium sodium alloys.                                            |                           |                          |     |                   |                                   |                       |           |           |                                                 |                      |                 |                |
|          | Sodium selenate, <i>see</i> Selenates or Selenites.                                                     |                           |                          |     |                   |                                   |                       |           |           |                                                 |                      |                 |                |
|          | Sodium sulfide, anhydrous or Sodium sulfide <i>with less than 30 percent water of crys-tallization.</i> | 4.2                       | UN1385                   | II  | 4.2 .....         | A19, A20, IB6, IP2, N34, T3, TP33 | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                | A               | 52             |
|          | Sodium sulfide, <i>hydrated with not less than 30 percent water.</i>                                    | 8                         | UN1849                   | II  | 8 .....           | IB8, IP2, IP4, T3, TP33           | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                | A               | 52.            |
|          | Sodium superoxide .....                                                                                 | 5.1                       | UN2547                   | I   | 5.1 .....         | A20, IB6, IP1, N34                | None ....             | 211 ..... | None .... | Forbidden                                       | 15 kg                | E               | 13, 52, 66, 75 |
|          | Sodium tetranitride .....                                                                               | Forbidden                 |                          |     |                   |                                   |                       |           |           |                                                 |                      |                 |                |
| G        | Solids containing corrosive liq-uid, n.o.s..                                                            | 8                         | UN3244                   | II  | 8 .....           | 49, IB5, T3, TP33                 | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                | B               | 40             |
| G        | Solids containing flammable liq-uid, n.o.s..                                                            | 4.1                       | UN3175                   | II  | 4.1 .....         | 47, IB6, IP2, T3, TP33            | 151 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                | B               |                |
| G        | Solids containing toxic liquid, n.o.s..                                                                 | 6.1                       | UN3243                   | II  | 6.1 .....         | 48, IB2, T2, TP33                 | 153 .....             | 212 ..... | 240 ..... | 25 kg                                           | 100 kg               | B               | 40             |
|          | Sounding devices, explosive ....                                                                        | 1.2F                      | UN0204                   | II  | 1.2F ...          |                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 08              |                |
|          | Sounding devices, explosive ....                                                                        | 1.1F                      | UN0296                   | II  | 1.1F ...          |                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 08              |                |
|          | Sounding devices, explosive ....                                                                        | 1.1D                      | UN0374                   | II  | 1.1D ..           |                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 07              |                |
|          | Sounding devices, explosive ....                                                                        | 1.2D                      | UN0375                   | II  | 1.2D ..           |                                   | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 07              |                |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

|   |                                                        |      |        |     |           |                                      |      |     |      |           |           |    |                    |
|---|--------------------------------------------------------|------|--------|-----|-----------|--------------------------------------|------|-----|------|-----------|-----------|----|--------------------|
|   | <i>Spirits of salt, see Hydrochloric acid.</i>         |      |        |     |           |                                      |      |     |      |           |           |    |                    |
|   | <i>Squibs, see Igniters etc</i>                        |      |        |     |           |                                      |      |     |      |           |           |    |                    |
|   | Stannic chloride, anhydrous                            | 8    | UN1827 | II  | 8         | B2, IB2, T7, TP2                     | 154  | 202 | 242  | 1 L       | 30 L      | C  |                    |
|   | Stannic chloride pentahydrate                          | 8    | UN2440 | III | 8         | IB8, IP3, T1, TP33                   | 154  | 213 | 240  | 25 kg     | 100 kg    | A  |                    |
|   | Stannic phosphide                                      | 4.3  | UN1433 | I   | 4.3, 6.1. | A19, N40                             | None | 211 | 242  | Forbidden | 15 kg     | E  | 40, 52, 85         |
|   | <i>Steel swarf, see Ferrous metal borings, etc.</i>    |      |        |     |           |                                      |      |     |      |           |           |    |                    |
|   | Stibine                                                | 2.3  | UN2676 |     | 2.3, 2.1. | 1                                    | None | 304 | None | Forbidden | Forbidden | D  | 40                 |
|   | <i>Storage batteries, wet, see Batteries, wet etc.</i> |      |        |     |           |                                      |      |     |      |           |           |    |                    |
|   | Strontium arsenite                                     | 6.1  | UN1691 | II  | 6.1       | IB8, IP2, IP4, T3, TP33              | 153  | 212 | 242  | 25 kg     | 100 kg    | A  |                    |
|   | Strontium chlorate                                     | 5.1  | UN1506 | II  | 5.1       | A1, A9, IB8, IP2, IP4, N34, T3, TP33 | 152  | 212 | 242  | 5 kg      | 25 kg     | A  | 56, 58             |
|   | Strontium nitrate                                      | 5.1  | UN1507 | III | 5.1       | A1, A29, IB8, IP3, T1, TP33          | 152  | 213 | 240  | 25 kg     | 100 kg    | A  |                    |
|   | Strontium perchlorate                                  | 5.1  | UN1508 | II  | 5.1       | IB6, IP2, T3, TP33                   | 152  | 212 | 242  | 5 kg      | 25 kg     | A  | 56, 58             |
|   | Strontium peroxide                                     | 5.1  | UN1509 | II  | 5.1       | IB6, IP2, T3, TP33                   | 152  | 212 | 242  | 5 kg      | 25 kg     | A  | 13, 52, 66, 75     |
|   | Strontium phosphide                                    | 4.3  | UN2013 | I   | 4.3, 6.1. | A19, N40                             | None | 211 | None | Forbidden | 15 kg     | E  | 40, 52, 85         |
|   | Strychnine or Strychnine salts                         | 6.1  | UN1692 | I   | 6.1       | IB7, IP1, T6, TP33                   | None | 211 | 242  | 5 kg      | 50 kg     | A  | 40                 |
|   | <i>Styphnic acid, see Trinitroresorcinol, etc.</i>     |      |        |     |           |                                      |      |     |      |           |           |    |                    |
| G | Styrene monomer, stabilized                            | 3    | UN2055 | III | 3         | B1, IB3, T2, TP1                     | 150  | 203 | 242  | 60 L      | 220 L     | A  |                    |
|   | Substances, explosive, n.o.s                           | 1.1L | UN0357 | II  | 1.1L      |                                      | None | 62  | None | Forbidden | Forbidden |    | 8E, 14E, 15E, 17E. |
| G | Substances, explosive, n.o.s                           | 1.2L | UN0358 | II  | 1.2L      |                                      | None | 62  | None | Forbidden | Forbidden |    | 8E, 14E, 15E, 17E. |
| G | Substances, explosive, n.o.s                           | 1.3L | UN0359 | II  | 1.3L      |                                      | None | 62  | None | Forbidden | Forbidden |    | 8E, 14E, 15E, 17E. |
| G | Substances, explosive, n.o.s                           | 1.1A | UN0473 | II  | 1.1A      | 111                                  | None | 62  | None | Forbidden | Forbidden | 12 |                    |
| G | Substances, explosive, n.o.s                           | 1.1C | UN0474 | II  | 1.1C      |                                      | None | 62  | None | Forbidden | Forbidden | 10 |                    |
| G | Substances, explosive, n.o.s                           | 1.1D | UN0475 | II  | 1.1D      |                                      | None | 62  | None | Forbidden | Forbidden | 10 |                    |
| G | Substances, explosive, n.o.s                           | 1.1G | UN0476 | II  | 1.1G      |                                      | None | 62  | None | Forbidden | Forbidden | 08 |                    |
| G | Substances, explosive, n.o.s                           | 1.3C | UN0477 | II  | 1.3C      |                                      | None | 62  | None | Forbidden | Forbidden | 10 |                    |
| G | Substances, explosive, n.o.s                           | 1.3G | UN0478 | II  | 1.3G      |                                      | None | 62  | None | Forbidden | Forbidden | 10 |                    |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                               | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102) | (8)                   |           |           | (9)                                             |                       | (10)             |         |
|----------|-----------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|---------|
|          |                                                                                                           |                            |                            |     |             |                                  | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |         |
|          |                                                                                                           |                            |                            |     |             |                                  | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other   |
| G        | Substances, explosive, n.o.s. ....                                                                        | 1.4C                       | UN0479                     | II  | 1.4C ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 09               |         |
| G        | Substances, explosive, n.o.s. ....                                                                        | 1.4D                       | UN0480                     | II  | 1.4D ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 09               |         |
| G        | Substances, explosive, n.o.s. ....                                                                        | 1.4S                       | UN0481                     | II  | 1.4S ...    | .....                            | None ....             | 62 .....  | None .... | 25 kg                                           | 75 kg                 | 05               |         |
| G        | Substances, explosive, n.o.s. ....                                                                        | 1.4G                       | UN0485                     | II  | 1.4G ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                 | 08               |         |
| G        | Substances, explosive, very in- sensitive, n.o.s. or Sub- stances,EVI, n.o.s.                             | 1.5D                       | UN0482                     | II  | 1.5D ..     | .....                            | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               |         |
|          | Substituted nitrophenol pes- ticides, liquid, flammable, toxic, flash point less than 23 degrees C.       | 3                          | UN2780                     | I   | 3, 6.1      | T14, TP2, TP13, TP27             | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 30 L                  | B                | 40      |
|          | .....                                                                                                     |                            |                            | II  | 3, 6.1      | IB2, T11, TP2, TP13, TP27        | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 60 L                  | B                | 40      |
|          | Substituted nitrophenol pes- ticides, liquid, toxic.                                                      | 6.1                        | UN3014                     | I   | 6.1 .....   | T14, TP2, TP13, TP27             | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40      |
|          | .....                                                                                                     |                            |                            | II  | 6.1 .....   | IB2, T11, TP2, TP13, TP27        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | 40      |
|          | .....                                                                                                     |                            |                            | III | 6.1 .....   | IB3, T7, TP2, TP28               | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                | 40      |
|          | Substituted nitrophenol pes- ticides, liquid, toxic, flam- mable, flash point not less than 23 degrees C. | 6.1                        | UN3013                     | I   | 6.1, 3      | T14, TP2, TP13, TP27             | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                  | B                | 40      |
|          | .....                                                                                                     |                            |                            | II  | 6.1, 3      | IB2, T11, TP2, TP13, TP27        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | B                | 40      |
|          | .....                                                                                                     |                            |                            | III | 6.1, 3      | B1, IB3, T7, TP2, TP28           | 153 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | 40      |
|          | Substituted nitrophenol pes- ticides, solid, toxic.                                                       | 6.1                        | UN2779                     | I   | 6.1 .....   | IB7, IP1, T6, TP33               | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                 | A                | 40      |
|          | .....                                                                                                     |                            |                            | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33          | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | 40      |
|          | .....                                                                                                     |                            |                            | III | 6.1 .....   | IB8, IP3, T1, TP33               | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | 40      |
|          | Sucrose octanitrate (dry) .....                                                                           | Forbidden                  |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |         |
|          | Sulfamic acid .....                                                                                       | 8                          | UN2967                     | III | 8 .....     | IB8, IP3, T1, TP33               | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                |         |
| D        | Sulfur .....                                                                                              | 9                          | NA1350                     | III | 9 .....     | 30, IB8, IP2                     | None ....             | None .... | 240 ..... | No Limit                                        | No Limit              | A                | 19, 74  |
| I        | Sulfur .....                                                                                              | 4.1                        | UN1350                     | III | 4.1 .....   | 30, IB8, IP3, T1, TP33           | None ....             | None .... | 240 ..... | 25 kg                                           | 100 kg                | A                | 19, 74. |
|          | Sulfur and chlorate, loose mix- tures of.                                                                 | Forbidden                  |                            |     |             |                                  |                       |           |           |                                                 |                       |                  |         |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                       |     |        |     |        |                                                                                   |      |     |           |           |           |   |        |
|---|---------------------------------------------------------------------------------------|-----|--------|-----|--------|-----------------------------------------------------------------------------------|------|-----|-----------|-----------|-----------|---|--------|
|   | Sulfur chlorides .....                                                                | 8   | UN1828 | I   | 8      | 5, A3, A7, A10, B10, B77, N34, T20, TP2, TP12                                     | None | 201 | 243       | Forbidden | 2.5 L     | C | 40     |
|   | <i>Sulfur dichloride, see Sulfur chlorides.</i>                                       |     |        |     |        |                                                                                   |      |     |           |           |           |   |        |
|   | Sulfur dioxide .....                                                                  | 2.3 | UN1079 |     | 2.3, 8 | 3, B14, T50, TP19                                                                 | None | 304 | 314, 315. | Forbidden | Forbidden | D | 40     |
|   | <i>Sulfur dioxide solution, see Sulfurous acid.</i>                                   |     |        |     |        |                                                                                   |      |     |           |           |           |   |        |
|   | Sulfur hexafluoride .....                                                             | 2.2 | UN1080 |     | 2.2    |                                                                                   | 306  | 304 | 314, 315. | 75 kg     | 150 kg    | A |        |
| D | Sulfur, molten .....                                                                  | 9   | NA2448 | III | 9      | 30, IB3, T1, TP3                                                                  | None | 213 | 247       | Forbidden | Forbidden | C | 61     |
| I | Sulfur, molten .....                                                                  | 4.1 | UN2448 | III | 4.1    | 30, IB1, T1, TP3                                                                  | None | 213 | 247       | Forbidden | Forbidden | C | 74     |
|   | Sulfur tetrafluoride .....                                                            | 2.3 | UN2418 |     | 2.3, 8 | 1                                                                                 | None | 302 | 245       | Forbidden | Forbidden | D | 40, 52 |
| + | Sulfur trioxide, stabilized .....                                                     | 8   | UN1829 | I   | 8, 6.1 | 2, B9, B14, B32, B49, B74, B77, N34, T20, TP4, TP12, TP13, TP25, TP26, TP38, TP45 | None | 227 | 244       | Forbidden | Forbidden | A | 40     |
|   | <i>Sulfuretted hydrogen, see Hydrogen sulfide.</i>                                    |     |        |     |        |                                                                                   |      |     |           |           |           |   |        |
|   | Sulfuric acid, fuming with less than 30 percent free sulfur trioxide.                 | 8   | UN1831 | I   | 8      | A3, A7, B84, N34, T20, TP2, TP12, TP13                                            | None | 201 | 243       | Forbidden | 2.5 L     | C | 14, 40 |
|   | Sulfuric acid, fuming with 30 percent or more free sulfur trioxide.                   | 8   | UN1831 | I   | 8, 6.1 | 2, B9, B14, B32, B74, B77, B84, N34, T20, TP2, TP12, TP13                         | None | 227 | 244       | Forbidden | Forbidden | C | 14, 40 |
|   | Sulfuric acid, spent .....                                                            | 8   | UN1832 | II  | 8      | A3, A7, B2, B83, B84, IB2, N34, T8, TP2, TP12                                     | None | 202 | 242       | Forbidden | 30 L      | C | 14     |
|   | Sulfuric acid with more than 51 percent acid.                                         | 8   | UN1830 | II  | 8      | A3, A7, B3, B83, B84, IB2, N34, T8, TP2, TP12                                     | 154  | 202 | 242       | 1 L       | 30 L      | C | 14     |
|   | Sulfuric acid with not more than 51% acid.                                            | 8   | UN2796 | II  | 8      | A3, A7, B2, B15, IB2, N6, N34, T8, TP2, TP12                                      | 154  | 202 | 242       | 1 L       | 30 L      | B |        |
|   | Sulfuric and hydrofluoric acid mixtures, see Hydrofluoric and sulfuric acid mixtures. |     |        |     |        |                                                                                   |      |     |           |           |           |   |        |
|   | <i>Sulfuric anhydride, see Sulfur trioxide, stabilized.</i>                           |     |        |     |        |                                                                                   |      |     |           |           |           |   |        |
|   | Sulfurous acid .....                                                                  | 8   | UN1833 | II  | 8      | B3, IB2, T7, TP2                                                                  | 154  | 202 | 242       | 1 L       | 30 L      | B | 40     |
| + | Sulfuryl chloride .....                                                               | 8   | UN1834 | I   | 8, 6.1 | 1, B6, B9, B10, B14, B30, B74, B77, N34, T22, TP2, TP12, TP38, TP44               | None | 226 | 244       | Forbidden | Forbidden | C | 40     |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                   | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes    | Special provi-sions (§ 172.102) | (8)                   |           |                     | (9)                                             |                      | (10)            |       |
|----------|---------------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|-------|----------------|---------------------------------|-----------------------|-----------|---------------------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                                                                               |                           |                          |       |                |                                 | Packaging (§ 173.***) |           |                     | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                                                                               |                           |                          |       |                |                                 | Excep-tions           | Non-bulk  | Bulk                | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
|          | Sulfuryl fluoride .....                                                                                       | 2.3                       | UN2191                   | ..... | 2.3 .....      | 4                               | None ....             | 304 ..... | 314, 315, 242 ..... | Forbidden                                       | Forbidden            | D               | 40    |
|          | Tars, liquid <i>including road asphalt and oils, bitumen and cut backs.</i> .....                             | 3                         | UN1999                   | II    | 3 .....        | 149, B13, IB2, T3, TP3, TP29    | 150 .....             | 202 ..... | 242 .....           | 5 L                                             | 60 L                 | B               | ..... |
|          | .....                                                                                                         | .....                     | .....                    | III   | 3 .....        | B1, B13, IB3, T1, TP3           | 150 .....             | 203 ..... | 242 .....           | 60 L                                            | 220 L                | A               | ..... |
|          | Tear gas candles .....                                                                                        | 6.1                       | UN1700                   | II    | 6.1, 4.1. .... |                                 | None ....             | 340 ..... | None ....           | Forbidden                                       | 50 kg                | D               | 40    |
|          | <i>Tear gas cartridges, see Ammu-nition, tear-producing, etc.</i> .....                                       | .....                     | .....                    | ..... | .....          |                                 | .....                 | .....     | .....               | .....                                           | .....                | .....           | ..... |
| D        | Tear gas devices <i>with more than 2 percent tear gas sub-stances, by mass.</i> .....                         | 6.1                       | NA1693                   | I     | 6.1 ....       |                                 | None ....             | 340 ..... | None ....           | Forbidden                                       | Forbidden            | D               | 40    |
|          | <i>Tear gas devices, with not more than 2 percent tear gas sub-stances, by mass, see Aerosols, etc.</i> ..... | .....                     | .....                    | II    | 6.1 ....       |                                 | None ....             | 340 ..... | None ....           | Forbidden                                       | Forbidden            | D               | 40    |
|          | <i>Tear gas grenades, see Tear gas candles.</i> .....                                                         | .....                     | .....                    | ..... | .....          |                                 | .....                 | .....     | .....               | .....                                           | .....                | .....           | ..... |
| G        | Tear gas substances, liquid, n.o.s., .....                                                                    | 6.1                       | UN1693                   | I     | 6.1 ....       |                                 | None ....             | 201 ..... | None ....           | Forbidden                                       | Forbidden            | D               | 40    |
|          | .....                                                                                                         | .....                     | .....                    | II    | 6.1 ....       | IB2                             | None ....             | 202 ..... | None ....           | Forbidden                                       | 5 L                  | D               | 40    |
| G        | Tear gas substance, solid, n.o.s. ....                                                                        | 6.1                       | UN3448                   | I     | 6.1 ....       | T6, TP33                        | None ....             | 211 ..... | 242 .....           | Forbidden                                       | Forbidden            | D               | 40    |
|          | .....                                                                                                         | .....                     | .....                    | II    | 6.1 ....       | IB8, IP2, IP4, T3, TP33         | None ....             | 212 ..... | 242 .....           | Forbidden                                       | 25 kg                | D               | 40    |
|          | Tellurium compound, n.o.s. ....                                                                               | 6.1                       | UN3284                   | I     | 6.1 ....       | IB7, IP1, T6, TP33              | None ....             | 211 ..... | 242 .....           | 5 kg                                            | 50 kg                | B               | ..... |
|          | .....                                                                                                         | .....                     | .....                    | II    | 6.1 ....       | IB8, IP2, IP4, T3, TP33         | 153 .....             | 212 ..... | 242 .....           | 25 kg                                           | 100 kg               | B               | ..... |
|          | .....                                                                                                         | .....                     | .....                    | III   | 6.1 ....       | IB8, IP3, T1, TP33              | 153 .....             | 213 ..... | 240 .....           | 100 kg                                          | 200 kg               | A               | ..... |
|          | Tellurium hexafluoride .....                                                                                  | 2.3                       | UN2195                   | ..... | 2.3, 8         | 1                               | None ....             | 302 ..... | None ....           | Forbidden                                       | Forbidden            | D               | 40    |
|          | Terpene hydrocarbons, n.o.s. ....                                                                             | 3                         | UN2319                   | III   | 3 .....        | B1, IB3, T4, TP1, TP29          | 150 .....             | 203 ..... | 242 .....           | 60 L                                            | 220 L                | A               | ..... |
|          | Terpinolene .....                                                                                             | 3                         | UN2541                   | III   | 3 .....        | B1, IB3, T2, TP1                | 150 .....             | 203 ..... | 242 .....           | 60 L                                            | 220 L                | A               | ..... |
|          | <i>Tetraazido benzene quinone</i> ....                                                                        | Forbidden                 | .....                    | ..... | .....          |                                 | .....                 | .....     | .....               | .....                                           | .....                | .....           | ..... |
|          | Tetrabromoethane .....                                                                                        | 6.1                       | UN2504                   | III   | 6.1 ....       | IB3, T4, TP1                    | 153 .....             | 203 ..... | 241 .....           | 60 L                                            | 220 L                | A               | ..... |
|          | 1,1,2,2-Tetrachloroethane .....                                                                               | 6.1                       | UN1702                   | II    | 6.1 ....       | IB2, N36, T7, TP2               | 153 .....             | 202 ..... | 243 .....           | 5 L                                             | 60 L                 | A               | 40    |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                |           |        |       |           |                                                  |            |           |            |           |           |    |        |
|--------------------------------------------------------------------------------|-----------|--------|-------|-----------|--------------------------------------------------|------------|-----------|------------|-----------|-----------|----|--------|
| Tetrachloroethylene .....                                                      | 6.1       | UN1897 | III   | 6.1 ..... | IB3, N36, T4, TP1                                | 153 .....  | 203 ..... | 241 .....  | 60 L      | 220 L     | A  | 40     |
| Tetraethyl dithiopyrophosphate ..                                              | 6.1       | UN1704 | II    | 6.1 ..... | IB2, T7, TP2                                     | 153 .....  | 212 ..... | 242 .....  | 25 kg     | 100 kg    | D  | 40     |
| Tetraethyl silicate .....                                                      | 3         | UN1292 | III   | 3 .....   | B1, IB3, T2, TP1                                 | 150 .....  | 203 ..... | 242 .....  | 60 L      | 220 L     | A  | .....  |
| <i>Tetraethylammonium perchlorate (dry).</i>                                   | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| Tetraethylenepentamine .....                                                   | 8         | UN2320 | III   | 8 .....   | IB3, T4, TP1                                     | 154 .....  | 203 ..... | 241 .....  | 5 L       | 60 L      | A  | 52.    |
| 1,1,1,2-Tetrafluoroethane or Refrigerant gas R 134a.                           | 2.2       | UN3159 | ..... | 2.2 ..... | T50                                              | 306 .....  | 304 ..... | 314, 315.  | 75 kg     | 150 kg    | A  | .....  |
| Tetrafluoroethylene, stabilized ...                                            | 2.1       | UN1081 | ..... | 2.1 ..... |                                                  | 306 .....  | 304 ..... | None ..... | Forbidden | 150 kg    | E  | 40     |
| Tetrafluoromethane or Refrigerant gas R 14.                                    | 2.2       | UN1982 | ..... | 2.2 ..... |                                                  | None ..... | 302 ..... | None ..... | 75 kg     | 150 kg    | A  | .....  |
| 1,2,3,6-Tetrahydrobenzaldehyde                                                 | 3         | UN2498 | III   | 3 .....   | B1, IB3, T2, TP1                                 | 150 .....  | 203 ..... | 242 .....  | 60 L      | 220 L     | A  | .....  |
| Tetrahydrofuran .....                                                          | 3         | UN2056 | II    | 3 .....   | IB2, T4, TP1                                     | None ..... | 202 ..... | 242 .....  | 5 L       | 60 L      | B  | .....  |
| Tetrahydrofurfurylamine .....                                                  | 3         | UN2943 | III   | 3 .....   | B1, IB3, T2, TP1                                 | 150 .....  | 203 ..... | 242 .....  | 60 L      | 220 L     | A  | .....  |
| Tetrahydrophthalic anhydrides with more than 0.05 percent of maleic anhydride. | 8         | UN2698 | III   | 8 .....   | IB8, IP3, T1, TP33                               | 154 .....  | 213 ..... | 240 .....  | 25 kg     | 100 kg    | A  | .....  |
| 1,2,3,6-Tetrahydropyridine .....                                               | 3         | UN2410 | II    | 3 .....   | IB2, T4, TP1                                     | 150 .....  | 202 ..... | 242 .....  | 5 L       | 60 L      | B  | .....  |
| Tetrahydrothiophene .....                                                      | 3         | UN2412 | II    | 3 .....   | IB2, T4, TP1                                     | 150 .....  | 202 ..... | 242 .....  | 5 L       | 60 L      | B  | .....  |
| Tetramethylammonium hydroxide, solid.                                          | 8         | UN3423 | II    | 8 .....   | B2, IB8, IP2, IP4, T3, TP33                      | 154 .....  | 213 ..... | 240 .....  | 15 kg     | 50 kg     | A  | 52     |
| Tetramethylammonium hydroxide solution.                                        | 8         | UN1835 | II    | 8 .....   | B2, IB2, T7, TP2                                 | 154 .....  | 202 ..... | 242 .....  | 1 L       | 30 L      | A  | 52     |
| <i>Tetramethylene diperoxide dicarbamide.</i>                                  | Forbidden |        | III   | 8 .....   | B2, IB3, T7, TP2                                 | 154 .....  | 203 ..... | 241 .....  | 5 L       | 60 L      | A  | 52     |
| Tetramethylsilane .....                                                        | 3         | UN2749 | I     | 3 .....   | A7, T14, TP2                                     | None ..... | 201 ..... | 243 .....  | Forbidden | 30 L      | D  | .....  |
| <i>Tetranitro diglycerin</i> .....                                             | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| Tetranitroaniline .....                                                        | 1.1D      | UN0207 | II    | 1.1D ..   |                                                  | None ..... | 62 .....  | None ..... | Forbidden | Forbidden | 10 |        |
| Tetranitromethane .....                                                        | 5.1       | UN1510 | I     | 5.1, 6.1. | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP44 | None ..... | 227 ..... | None ..... | Forbidden | Forbidden | D  | 40, 66 |
| <i>2,3,4,6-Tetranitrophenol</i> .....                                          | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| <i>2,3,4,6-Tetranitrophenyl methyl nitramine.</i>                              | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| <i>2,3,4,6-Tetranitrophenylnitramine.</i>                                      | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| <i>Tetranitroresorcinol (dry)</i> .....                                        | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| <i>2,3,5,6-Tetranitroso-1,4-dinitrobenzene.</i>                                | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| <i>2,3,5,6-Tetranitroso nitrobenzene (dry).</i>                                | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| Tetrapropylorthotitanate .....                                                 | 3         | UN2413 | III   | 3 .....   | B1, IB3, T4, TP1                                 | 150 .....  | 203 ..... | 242 .....  | 60 L      | 220 L     | A  | .....  |
| Tetrazene, see Guanyl nitrosaminoguanyltetrazene.                              | .....     |        |       |           |                                                  |            |           |            |           |           |    |        |
| <i>Tetrazine (dry)</i> .....                                                   | Forbidden |        |       |           |                                                  |            |           |            |           |           |    |        |
| Tetrazol-1-acetic acid .....                                                   | 1.4C      | UN0407 | II    | 1.4C ..   |                                                  | None ..... | 62 .....  | None ..... | Forbidden | 75 kg     | 09 |        |
| 1H-Tetrazole .....                                                             | 1.1D      | UN0504 | ..... | 1.1D ..   |                                                  | None ..... | 62 .....  | None ..... | Forbidden | Forbidden | B  | 1E, 5E |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names                                              | Hazard class or Division | Identification Numbers | PG  | Label Codes | Special provisions (§ 172.102) | (8)                   |          |      | (9)                                             |                     | (10)           |        |
|----------|---------------------------------------------------------------------------------------------------------|--------------------------|------------------------|-----|-------------|--------------------------------|-----------------------|----------|------|-------------------------------------------------|---------------------|----------------|--------|
|          |                                                                                                         |                          |                        |     |             |                                | Packaging (§ 173.***) |          |      | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |        |
|          |                                                                                                         |                          |                        |     |             |                                | Excep-tions           | Non-bulk | Bulk | Passenger aircraft/rail                         | Cargo aircraft only | Loca-tion      | Other  |
| A I<br>W | <i>Tetrazolyl azide (dry)</i> .....                                                                     | Forbidden                |                        |     |             |                                |                       |          |      |                                                 |                     |                |        |
|          | Tetryl, <i>see</i> .....                                                                                |                          |                        |     |             |                                |                       |          |      |                                                 |                     |                |        |
|          | Trinitrophenylmethylnitramine.                                                                          |                          |                        |     |             |                                |                       |          |      |                                                 |                     |                |        |
|          | Textile waste, wet .....                                                                                | 4.2                      | UN1857                 | III | 4.2         |                                | 151                   | 213      | 240  | Forbidden                                       | Forbidden           | A              |        |
|          | Thallium chlorate .....                                                                                 | 5.1                      | UN2573                 | II  | 5.1,        | IB6, IP2, T3, TP33             | 152                   | 212      | 242  | 5 kg                                            | 25 kg               | A              | 56, 58 |
|          | Thallium compounds, n.o.s. ....                                                                         | 6.1                      | UN1707                 | II  | 6.1         | IB8, IP2, IP4, T3, TP33        | 153                   | 212      | 242  | 25 kg                                           | 100 kg              | A              |        |
|          | Thallium nitrate .....                                                                                  | 6.1                      | UN2727                 | II  | 6.1,        | IB6, IP2, T3, TP33             | 153                   | 212      | 242  | 5 kg                                            | 25 kg               | A              |        |
|          | 4-Thiapentanal .....                                                                                    | 6.1                      | UN2785                 | III | 6.1         | IB3, T4, TP1                   | 153                   | 203      | 241  | 60 L                                            | 220 L               | D              | 25, 49 |
|          | Thioacetic acid .....                                                                                   | 3                        | UN2436                 | II  | 3           | IB2, T4, TP1                   | 150                   | 202      | 242  | 5 L                                             | 60 L                | B              |        |
|          | Thiocarbamate pesticide, liquid, flammable, toxic, <i>flash point less than 23 degrees C.</i> .....     | 3                        | UN2772                 | I   | 3, 6.1      | T14, TP2, TP13, TP27           | None                  | 201      | 243  | Forbidden                                       | 30 L                | B              | 40     |
|          | .....                                                                                                   |                          |                        | II  | 3, 6.1      | IB2, T11, TP13, TP27           | 150                   | 202      | 243  | 1 L                                             | 60 L                | B              | 40     |
|          | Thiocarbamate pesticide, liquid, toxic, flammable, <i>flash point not less than 23 degrees C.</i> ..... | 6.1                      | UN3005                 | I   | 6.1, 3      | T14, TP2, TP13                 | None                  | 201      | 243  | 1 L                                             | 30 L                | B              | 40     |
|          | .....                                                                                                   |                          |                        | II  | 6.1, 3      | IB2, T11, TP2, TP13, TP27      | 153                   | 202      | 243  | 5 L                                             | 60 L                | B              | 40     |
|          | .....                                                                                                   |                          |                        | III | 6.1, 3      | IB3, T7, TP2, TP28             | 153                   | 203      | 242  | 60 L                                            | 220 L               | A              | 40     |
|          | Thiocarbamate pesticide, liquid, toxic. ....                                                            | 6.1                      | UN3006                 | I   | 6.1         | T14, TP2, TP13                 | None                  | 201      | 243  | 1 L                                             | 30 L                | B              | 40     |
|          | .....                                                                                                   |                          |                        | II  | 6.1         | IB2, T11, TP2, TP13, TP27      | 153                   | 202      | 243  | 5 L                                             | 60 L                | B              | 40     |
|          | .....                                                                                                   |                          |                        | III | 6.1         | IB3, T7, TP2, TP28             | 153                   | 203      | 241  | 60 L                                            | 220 L               | A              | 40     |
|          | Thiocarbamate pesticides, solid, toxic. ....                                                            | 6.1                      | UN2771                 | I   | 6.1         | IB7, IP1, T6, TP33             | None                  | 211      | 242  | 5 kg                                            | 50 kg               | A              | 40     |
|          | .....                                                                                                   |                          |                        | II  | 6.1         | IB8, IP2, IP4, T3, TP33        | 153                   | 212      | 242  | 25 kg                                           | 100 kg              | A              | 40     |
|          | .....                                                                                                   |                          |                        | III | 6.1         | IB8, IP3, T1, TP33             | 153                   | 213      | 240  | 100 kg                                          | 200 kg              | A              | 40     |
|          | <i>Thiocarbonylchloride,</i> <i>see</i> .....                                                           |                          |                        |     |             |                                |                       |          |      |                                                 |                     |                |        |
|          | Thiophosgene. ....                                                                                      |                          |                        |     |             |                                |                       |          |      |                                                 |                     |                |        |
|          | Thioglycol .....                                                                                        | 6.1                      | UN2966                 | II  | 6.1         | IB2, T7, TP2                   | 153                   | 202      | 243  | 5 L                                             | 60 L                | A              |        |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                                                                                                                                      |       |        |       |       |                                                      |       |       |       |           |           |       |        |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-------|-------|------------------------------------------------------|-------|-------|-------|-----------|-----------|-------|--------|
| Thioglycolic acid .....                                                                                                                                                                                                              | 8     | UN1940 | II    | 8     | A7, B2, IB2, N34, T7, TP2                            | 154   | 202   | 242   | 1 L       | 30 L      | A     | .....  |
| Thiolactic acid .....                                                                                                                                                                                                                | 6.1   | UN2936 | II    | 6.1   | IB2, T7, TP2                                         | 153   | 202   | 243   | 5 L       | 60 L      | A     | .....  |
| Thionyl chloride .....                                                                                                                                                                                                               | 8     | UN1836 | I     | 8     | B6, B10, N34, T10, TP2, TP12, TP13                   | None  | 201   | 243   | Forbidden | Forbidden | C     | 40     |
| Thiophene .....                                                                                                                                                                                                                      | 3     | UN2414 | II    | 3     | IB2, T4, TP1                                         | 150   | 202   | 242   | 5 L       | 60 L      | B     | 40     |
| + Thiophosgene .....                                                                                                                                                                                                                 | 6.1   | UN2474 | II    | 6.1   | 2, B9, B14, B32, B74, N33, N34, T20, TP2, TP38, TP45 | None  | 227   | 244   | Forbidden | Forbidden | B     | 40, 52 |
| Thiophosphoryl chloride .....                                                                                                                                                                                                        | 8     | UN1837 | II    | 8     | A3, A7, B2, B8, B25, IB2, N34, T7, TP2               | None  | 202   | 242   | Forbidden | 30 L      | C     | 40     |
| Thiourea dioxide .....                                                                                                                                                                                                               | 4.2   | UN3341 | II    | 4.2   | IB6, IP2, T3, TP33                                   | None  | 212   | 241   | 15 kg     | 50 kg     | D     | .....  |
| .....                                                                                                                                                                                                                                | ..... | .....  | III   | 4.2   | IB8, IP3, T1, TP33                                   | None  | 213   | 241   | 25 kg     | 100 kg    | D     | .....  |
| <i>Tin chloride, fuming, see Stannic chloride, anhydrous.</i>                                                                                                                                                                        | ..... | .....  | ..... | ..... | .....                                                | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| <i>Tin perchloride or Tin tetrachloride, see Stannic chloride, anhydrous.</i>                                                                                                                                                        | ..... | .....  | ..... | ..... | .....                                                | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Tinctures, medicinal .....                                                                                                                                                                                                           | 3     | UN1293 | II    | 3     | IB2, T4, TP1, TP8                                    | 150   | 202   | 242   | 5 L       | 60 L      | B     | .....  |
| .....                                                                                                                                                                                                                                | ..... | .....  | III   | 3     | B1, IB3, T2, TP1                                     | 150   | 203   | 242   | 60 L      | 220 L     | A     | .....  |
| <i>Tinning flux, see Zinc chloride ...</i>                                                                                                                                                                                           | ..... | .....  | ..... | ..... | .....                                                | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Tires and tire assemblies, see Air, compressed or Nitrogen, compressed.                                                                                                                                                              | ..... | .....  | ..... | ..... | .....                                                | ..... | ..... | ..... | .....     | .....     | ..... | .....  |
| Titanium disulphide .....                                                                                                                                                                                                            | 4.2   | UN3174 | III   | 4.2   | IB8, IP3, T1, TP33                                   | None  | 213   | 241   | 25 kg     | 100 kg    | A     | .....  |
| Titanium hydride .....                                                                                                                                                                                                               | 4.1   | UN1871 | II    | 4.1   | A19, A20, IB4, N34, T3, TP33                         | None  | 212   | 241   | 15 kg     | 50 kg     | E     | .....  |
| Titanium powder, dry .....                                                                                                                                                                                                           | 4.2   | UN2546 | I     | 4.2   | A19, A20, IB6, IP2, N5, N34, T3, TP33                | None  | 211   | 242   | Forbidden | Forbidden | D     | .....  |
| .....                                                                                                                                                                                                                                | ..... | .....  | II    | 4.2   | IB8, IP3, T1, TP33                                   | None  | 212   | 241   | 15 kg     | 50 kg     | D     | .....  |
| .....                                                                                                                                                                                                                                | ..... | .....  | III   | 4.2   | IB8, IP3, T1, TP33                                   | None  | 213   | 241   | 25 kg     | 100 kg    | D     | .....  |
| Titanium powder, wetted with not less than 25 percent water (a visible excess of water must be present) (a) mechanically produced, particle size less than 53 microns; (b) chemically produced, particle size less than 840 microns. | 4.1   | UN1352 | II    | 4.1   | A19, A20, IB6, IP2, N34, T3, TP33                    | None  | 212   | 240   | 15 kg     | 50 kg     | E     | 74     |
| Titanium sponge granules or Titanium sponge powders.                                                                                                                                                                                 | 4.1   | UN2878 | III   | 4.1   | A1, IB8, IP3, T1, TP33                               | None  | 213   | 240   | 25 kg     | 100 kg    | D     | 74     |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                             | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)                          | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|-----------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                                                                                                         |                            |                            |     |             |                                                           | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                                                                                                         |                            |                            |     |             |                                                           | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
| +        | Titanium tetrachloride .....                                                                                                                                            | 8                          | UN1838                     | II  | 8, 6.1      | 2, B7, B9, B14, B32, B74, B77, T20, TP2, TP13, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden             | C                | 40     |
|          | Titanium trichloride mixtures .....                                                                                                                                     | 8                          | UN2869                     | II  | 8 .....     | A7, IB8, IP2, IP4, N34, T3, TP33                          | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                 | A                | 40     |
|          | .....                                                                                                                                                                   |                            |                            | III | 8 .....     | A7, IB8, IP3, N34, T1, TP33                               | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | 40     |
|          | Titanium trichloride, pyrophoric or Titanium trichloride mixtures, pyrophoric.                                                                                          | 4.2                        | UN2441                     | I   | 4.2, 8      | N34                                                       | None ....             | 181 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 40     |
|          | TNT mixed with aluminum, see Tritonal.                                                                                                                                  |                            |                            |     |             |                                                           |                       |           |           |                                                 |                       |                  |        |
|          | TNT, see Trinitrotoluene, etc .....                                                                                                                                     |                            |                            |     |             |                                                           |                       |           |           |                                                 |                       |                  |        |
|          | Toluene .....                                                                                                                                                           | 3                          | UN1294                     | II  | 3 .....     | IB2, T4, TP1                                              | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                |        |
|          | Toluene diisocyanate .....                                                                                                                                              | 6.1                        | UN2078                     | II  | 6.1 .....   | IB2, T7, TP2, TP13                                        | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | D                | 25, 40 |
|          | Toluene sulfonic acid, see Alkyl, or Aryl sulfonic acid etc.                                                                                                            |                            |                            |     |             |                                                           |                       |           |           |                                                 |                       |                  |        |
|          | Toluidines, liquid .....                                                                                                                                                | 6.1                        | UN1708                     | II  | 6.1 .....   | IB2, T7, TP2                                              | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                |        |
| +        | Toluidines, solid .....                                                                                                                                                 | 6.1                        | UN3451                     | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33                                   | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                |        |
|          | 2,4-Toluylenediamine, solid or 2,4-Toluenediamine, solid.                                                                                                               | 6.1                        | UN1709                     | III | 6.1 .....   | IB8, IP3, T1, TP33                                        | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                |        |
|          | 2,4-Toluylenediamine solution or 2,4-Toluenediamine solution.                                                                                                           | 6.1                        | UN3418                     | III | 6.1 .....   | IB3, T4, TP1                                              | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | A                |        |
|          | Torpedoes, liquid fueled, with inert head.                                                                                                                              | 1.3J                       | UN0450                     | II  | 1.3J ...    |                                                           |                       | 62 .....  | None ...  | Forbidden                                       | Forbidden             | 04               | 23E    |
|          | Torpedoes, liquid fueled, with or without bursting charge.                                                                                                              | 1.1J                       | UN0449                     | II  | 1.1J ...    |                                                           |                       | 62 .....  | None ...  | Forbidden                                       | Forbidden             | 04               | 23E    |
|          | Torpedoes with bursting charge                                                                                                                                          | 1.1E                       | UN0329                     | II  | 1.1E ...    |                                                           |                       | 62 .....  | None ...  | Forbidden                                       | Forbidden             | 03               |        |
|          | Torpedoes with bursting charge                                                                                                                                          | 1.1F                       | UN0330                     | II  | 1.1F ...    |                                                           |                       | 62 .....  | None ...  | Forbidden                                       | Forbidden             | 08               |        |
|          | Torpedoes with bursting charge                                                                                                                                          | 1.1D                       | UN0451                     | II  | 1.1D ..     |                                                           |                       | 62 .....  | None ...  | Forbidden                                       | Forbidden             | 03               |        |
|          | G Toxic by inhalation liquid, n.o.s. with an inhalation toxicity lower than or equal to 200 ml/ m3 and saturated vapor concentration greater than or equal to 500 LC50. | 6.1                        | UN3381                     | I   | 6.1 .....   | 1, B9, B14, B30, B72, T22, TP2, TP13, TP27, TP38, TP44    | None ....             | 226 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 40     |
|          |                                                                                                                                                                         |                            |                            |     |             |                                                           |                       |           |           |                                                 |                       |                  |        |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                                                                                                                                                      |     |        |   |           |       |                                                        |      |      |     |       |     |       |           |           |   |    |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|---|-----------|-------|--------------------------------------------------------|------|------|-----|-------|-----|-------|-----------|-----------|---|----|
| G | Toxic by inhalation liquid, n.o.s. with an inhalation toxicity lower than or equal to 1000ml/m3 and saturated vapor concentration greater than or equal to 10 LC50.                  | 6.1 | UN3382 | I | 6.1       | ..... | 2, B9, B14, B32, B74, T20, TP2, TP13, TP27, TP38, TP45 | None | .... | 227 | ..... | 244 | ..... | Forbidden | Forbidden | D | 40 |
| G | Toxic by inhalation liquid, flammable, n.o.s. with an inhalation toxicity lower than or equal to 200 ml/m3 and saturated vapor concentration greater than or equal to 500 LC50.      | 6.1 | UN3383 | I | 6.1, 3    |       | 1, B9, B14, B30, B72, T22, TP2, TP13, TP27, TP38, TP44 | None | .... | 226 | ..... | 244 | ..... | Forbidden | Forbidden | D | 40 |
| G | Toxic by inhalation liquid, flammable, n.o.s. with an inhalation toxicity lower than or equal to 1000 ml/m3 and saturated vapor concentration greater than or equal to 10 LC50.      | 6.1 | UN3384 | I | 6.1, 3    |       | 2, B9, B14, B32, B74, T20, TP2, TP13, TP27, TP38, TP45 | None | .... | 227 | ..... | 244 | ..... | Forbidden | Forbidden | D | 40 |
| G | Toxic by inhalation liquid, water-reactive, n.o.s. with an inhalation toxicity lower than or equal to 200 ml/m3 and saturated vapor concentration greater than or equal to 500 LC50. | 6.1 | UN3385 | I | 6.1, 4.3. |       | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44       | None | .... | 226 | ..... | 244 | ..... | Forbidden | Forbidden | D | 40 |
| G | Toxic by inhalation liquid, water-reactive, n.o.s. with an inhalation toxicity lower than or equal to 1000 ml/m3 and saturated vapor concentration greater than or equal to 10 LC50. | 6.1 | UN3386 | I | 6.1, 4.3. |       | 2, B9, B14, B32, B74, T20, TP2, TP13, TP38, TP44       | None | .... | 227 | ..... | 244 | ..... | Forbidden | Forbidden | D | 40 |
| G | Toxic by inhalation liquid, oxidizing, n.o.s. with an inhalation toxicity lower than or equal to 200 ml/m3 and saturated vapor concentration greater than or equal to 500 LC50.      | 6.1 | UN3387 | I | 6.1, 5.1. |       | 1, B9, B14, B30, B72, T22, TP2, TP13, TP38, TP44       | None | .... | 226 | ..... | 244 | ..... | Forbidden | Forbidden | D | 40 |
| G | Toxic by inhalation liquid, oxidizing, n.o.s. with an inhalation toxicity lower than or equal to 1000 ml/m3 and saturated vapor concentration greater than or equal to 10 LC50.      | 6.1 | UN3388 | I | 6.1, 5.1. |       | 2, B9, B14, B32, T20, TP2, TP13, TP38, TP44            | None | .... | 227 | ..... | 244 | ..... | Forbidden | Forbidden | D | 40 |



§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                             | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102)                        | (8)                   |           |           | (9)                                             |                      | (10)            |       |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|--------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                                                                                                                                                         |                           |                          |     |             |                                                        | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                                                                                                                                                         |                           |                          |     |             |                                                        | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
| G        | Toxic by inhalation liquid, corro-sive, n.o.s. <i>with an inhalation toxicity lower than or equal to 200 ml/m3 and saturated vapor concentration greater than or equal to 500 LC50.</i> | 6.1                       | UN3389                   | I   | 6.1, 8      | 1, B9, B14, B30, B72, T22, TP2, TP13, TP27, TP38, TP44 | None ....             | 226 ..... | 244 ..... | Forbidden                                       | Forbidden            | D               | 40    |
| G        | Toxic by inhalation liquid, corro-sive, n.o.s. <i>with an inhalation toxicity lower than or equal to 1000 ml/m3 and saturated vapor concentration greater than or equal to 10 LC50.</i> | 6.1                       | UN3390                   | I   | 6.1, 8      | 2, B9, B14, B32, B74, T20, TP2, TP13, TP27, TP38, TP45 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden            | D               | 40    |
| G        | Toxic liquid, corrosive, inorganic, n.o.s..                                                                                                                                             | 6.1                       | UN3289                   | I   | 6.1, 8      | T14, TP2, TP13, TP27                                   | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                | A               | ..... |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | II  | 6.1, 8      | IB2, T11, TP2, TP27                                    | 153 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                 | A               | ..... |
| G        | Toxic liquid, inorganic, n.o.s. ....                                                                                                                                                    | 6.1                       | UN3287                   | I   | 6.1 ....    | T14, TP2, TP13, TP27                                   | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | A               | ..... |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | II  | 6.1 ....    | IB2, T11, TP2, TP27                                    | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | A               | ..... |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | III | 6.1 ....    | IB3, T7, TP1, TP28                                     | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               | ..... |
| G        | Toxic liquids, corrosive, organic, n.o.s..                                                                                                                                              | 6.1                       | UN2927                   | I   | 6.1, 8      | T14, TP2, TP13, TP27                                   | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                | B               | 40    |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | II  | 6.1, 8      | IB2, T11, TP2, TP27                                    | 153 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 40    |
| G        | Toxic liquids, flammable, or-ganic, n.o.s..                                                                                                                                             | 6.1                       | UN2929                   | I   | 6.1, 3      | T14, TP2, TP13, TP27                                   | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 40    |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | II  | 6.1, 3      | IB2, T11, TP2, TP13, TP27                              | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | B               | 40    |
| G        | Toxic, liquids, organic, n.o.s. ....                                                                                                                                                    | 6.1                       | UN2810                   | I   | 6.1 ....    | T14, TP2, TP13, TP27                                   | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 40    |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | II  | 6.1 ....    | IB2, T11, TP2, TP13, TP27                              | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | B               | 40    |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | III | 6.1 ....    | IB3, T7, TP1, TP28                                     | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               | 40    |
| G        | Toxic liquids, oxidizing, n.o.s. ....                                                                                                                                                   | 6.1                       | UN3122                   | I   | 6.1, 5.1.   | A4                                                     | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 2.5 L                | C               | ..... |
|          | .....                                                                                                                                                                                   | .....                     | .....                    | II  | 6.1, 5.1.   | IB2                                                    | 153 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                  | C               | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                        |      |        |     |           |                             |      |       |     |       |      |       |           |           |    |       |
|---|--------------------------------------------------------|------|--------|-----|-----------|-----------------------------|------|-------|-----|-------|------|-------|-----------|-----------|----|-------|
| G | Toxic liquids, water-reactive, n.o.s..                 | 6.1  | UN3123 | I   | 6.1, 4.3. | A4                          | None | ....  | 201 | ..... | 243  | ..... | Forbidden | 1 L       | E  | 40    |
|   |                                                        |      |        | II  | 6.1, 4.3. | IB2                         | None | ....  | 202 | ..... | 243  | ..... | 1 L       | 5 L       | E  | 40    |
| G | Toxic solid, corrosive, inorganic, n.o.s..             | 6.1  | UN3290 | I   | 6.1, 8    | IB7, T6, TP33               | None | ....  | 211 | ..... | 242  | ..... | 1 kg      | 25 kg     | A  | ..... |
|   |                                                        |      |        | II  | 6.1, 8    | IB6, IP2, T3, TP33          | 153  | ..... | 212 | ..... | 242  | ..... | 15 kg     | 50 kg     | A  | ..... |
| G | Toxic solid, inorganic, n.o.s. ....                    | 6.1  | UN3288 | I   | 6.1       | IB7, T6, TP33               | None | ....  | 211 | ..... | 242  | ..... | 5 kg      | 50 kg     | A  | ..... |
|   |                                                        |      |        | II  | 6.1       | IB8, IP2, IP4, T3, TP33     | 153  | ..... | 212 | ..... | 242  | ..... | 25 kg     | 100 kg    | A  | ..... |
|   |                                                        |      |        | III | 6.1       | IB8, IP3, T1, TP33          | 153  | ..... | 213 | ..... | 240  | ..... | 100 kg    | 200 kg    | A  | ..... |
| G | Toxic solids, corrosive, organic, n.o.s..              | 6.1  | UN2928 | I   | 6.1, 8    | IB7, T6, TP33               | None | ....  | 211 | ..... | 242  | ..... | 1 kg      | 25 kg     | B  | 40    |
|   |                                                        |      |        | II  | 6.1, 8    | IB6, IP2, T3, TP33          | 153  | ..... | 212 | ..... | 242  | ..... | 15 kg     | 50 kg     | B  | 40    |
| G | Toxic solids, flammable, organic, n.o.s..              | 6.1  | UN2930 | I   | 6.1, 4.1. | IB6, T6, TP33               | None | ....  | 211 | ..... | 242  | ..... | 1 kg      | 15 kg     | B  | ..... |
|   |                                                        |      |        | II  | 6.1, 4.1. | IB8, IP2, IP4, T3, TP33     | 153  | ..... | 212 | ..... | 242  | ..... | 15 kg     | 50 kg     | B  | ..... |
| G | Toxic solids, organic, n.o.s. ....                     | 6.1  | UN2811 | I   | 6.1       | IB7, T6, TP33               | None | ....  | 211 | ..... | 242  | ..... | 5 kg      | 50 kg     | B  | ..... |
|   |                                                        |      |        | II  | 6.1       | IB8, IP2, IP4, T3, TP33     | 153  | ..... | 212 | ..... | 242  | ..... | 25 kg     | 100 kg    | B  | ..... |
|   |                                                        |      |        | III | 6.1       | IB8, IP3, T1, TP33          | 153  | ..... | 213 | ..... | 240  | ..... | 100 kg    | 200 kg    | A  | ..... |
| G | Toxic solids, oxidizing, n.o.s. ....                   | 6.1  | UN3086 | I   | 6.1, 5.1. | T6, TP33                    | None | ....  | 211 | ..... | 242  | ..... | 1 kg      | 15 kg     | C  | ..... |
|   |                                                        |      |        | II  | 6.1, 5.1. | IB6, IP2, T3, TP33          | 153  | ..... | 212 | ..... | 242  | ..... | 15 kg     | 50 kg     | C  | ..... |
| G | Toxic solids, self-heating, n.o.s.                     | 6.1  | UN3124 | I   | 6.1, 4.2. | A5, T6, TP33                | None | ....  | 211 | ..... | 242  | ..... | 5 kg      | 15 kg     | D  | 40    |
|   |                                                        |      |        | II  | 6.1, 4.2. | IB6, IP2, T3, TP33          | None | ....  | 212 | ..... | 242  | ..... | 15 kg     | 50 kg     | D  | 40    |
| G | Toxic solids, water-reactive, n.o.s..                  | 6.1  | UN3125 | I   | 6.1, 4.3. | A5, T6, TP33                | None | ....  | 211 | ..... | 242  | ..... | 5 kg      | 15 kg     | D  | 40    |
|   |                                                        |      |        | II  | 6.1, 4.3. | IB6, IP2, T3, TP33          | 153  | ..... | 212 | ..... | 242  | ..... | 15 kg     | 50 kg     | D  | 40    |
| G | Toxins, extracted from living sources, liquid, n.o.s.. | 6.1  | UN3172 | I   | 6.1       | 141                         | None | ....  | 201 | ..... | 243  | ..... | 1 L       | 30 L      | B  | 40    |
|   |                                                        |      |        | II  | 6.1       | 141, IB2                    | None | ....  | 202 | ..... | 243  | ..... | 5 L       | 60 L      | B  | 40    |
|   |                                                        |      |        | III | 6.1       | 141, IB3                    | 153  | ..... | 203 | ..... | 241  | ..... | 60 L      | 220 L     | B  | 40    |
| G | Toxins, extracted from living sources, solid, n.o.s..  | 6.1  | UN3462 | I   | 6.1       | 141, IB7, IP1, T6, TP33     | None | ....  | 211 | ..... | 243  | ..... | 5 kg      | 50 kg     | B  | ..... |
|   |                                                        |      |        | II  | 6.1       | 141, IB8, IP2, IP4, T3 TP33 | None | ....  | 212 | ..... | 243  | ..... | 25 kg     | 100 kg    | B  | ..... |
|   |                                                        |      |        | III | 6.1       | 141, IB8, IP3, T1 TP33      | 153  | ..... | 213 | ..... | 241  | ..... | 100 kg    | 200 kg    | A  | ..... |
| D | Toy Caps .....                                         | 1.4S | NA0337 | II  | 1.4S      | ..                          | None | ....  | 62  | ..... | None | ....  | 25 kg     | 100 kg    | 05 | ..... |
|   | Tracers for ammunition .....                           | 1.3G | UN0212 | II  | 1.3G      | ..                          | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 07 | ..... |

Pipeline and Hazardous Materials Safety Admin., DOT

\$ 172.101

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                       | Hazard class or Di-vision | Identifica-tion Num-bers | PG  | Label Codes | Special provi-sions (§ 172.102)   | (8)                   |           |           | (9)                                             |                      | (10)            |       |
|----------|-------------------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|-----|-------------|-----------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                                                                                   |                           |                          |     |             |                                   | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                                                                                   |                           |                          |     |             |                                   | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
|          | Tracers for ammunition .....                                                                                      | 1.4G                      | UN0306                   | II  | 1.4G ..     |                                   | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg                | 06              | ..... |
|          | Tractors, see Vehicle, etc .....                                                                                  | Forbidden                 |                          |     |             |                                   | .....                 | .....     | .....     | .....                                           | .....                |                 | ..... |
|          | Tri-(b-nitroxyethyl) ammonium nitrate.                                                                            |                           |                          |     |             |                                   | .....                 | .....     | .....     | .....                                           | .....                |                 | ..... |
|          | Triallyl borate .....                                                                                             | 6.1                       | UN2609                   | III | 6.1 .....   | IB3                               | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               | 13    |
|          | Triallylamine .....                                                                                               | 3                         | UN2610                   | III | 3, 8 ....   | B1, IB3, T4, TP1                  | None ....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                 | A               | 40    |
|          | Triazine pesticides, liquid, flammable, toxic, flash point less than 23 degrees C.                                | 3                         | UN2764                   | I   | 3, 6.1      | T14, TP2, TP13, TP27              | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 30 L                 | B               | 40    |
|          | .....                                                                                                             |                           |                          | II  | 3, 6.1      | IB2, T11, TP2, TP13, TP27         | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 60 L                 | B               | 40    |
|          | Triazine pesticides, liquid, toxic                                                                                | 6.1                       | UN2998                   | I   | 6.1 .....   | T14, TP2, TP13, TP27              | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 40    |
|          | .....                                                                                                             |                           |                          | II  | 6.1 .....   | IB2, T11, TP2, TP13, TP27         | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | B               | 40    |
|          | .....                                                                                                             |                           |                          | III | 6.1 .....   | IB3, T7, TP2, TP28                | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               | 40    |
|          | Triazine pesticides, liquid, toxic, flammable, flash point not less than 23 degrees C.                            | 6.1                       | UN2997                   | I   | 6.1, 3      | T14, TP2, TP13, TP27              | None ....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                 | B               | 40    |
|          | .....                                                                                                             |                           |                          | II  | 6.1, 3      | IB2, T11, TP2, TP13, TP27         | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | B               | 40    |
|          | .....                                                                                                             |                           |                          | III | 6.1, 3      | IB3, T7, TP2, TP28                | 153 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                | A               | 40    |
|          | Triazine pesticides, solid, toxic ..                                                                              | 6.1                       | UN2763                   | I   | 6.1 .....   | IB7, IP1, T6, TP33                | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                | A               | 40    |
|          | .....                                                                                                             |                           |                          | II  | 6.1 .....   | IB8, IP2, IP4, T3, TP33           | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg               | A               | 40    |
|          | .....                                                                                                             |                           |                          | III | 6.1 .....   | IB8, IP3, T1, TP33                | 153 .....             | 213 ..... | 240 ..... | 100 kg                                          | 200 kg               | A               | 40    |
|          | Tributylamine .....                                                                                               | 6.1                       | UN2542                   | II  | 6.1 .....   | IB2, T7, TP2                      | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | A               | ..... |
|          | Tributylphosphane .....                                                                                           | 4.2                       | UN3254                   | I   | 4.2 .....   | T21, TP7, TP33                    | None ....             | 211 ..... | 242 ..... | Forbidden                                       | Forbidden            | D               | 136   |
|          | Trichloro-s-triazinetrione dry, with more than 39 percent available chlorine, see Trichloroisocyanuric acid, dry. |                           |                          |     |             |                                   | .....                 | .....     | .....     | .....                                           | .....                |                 | ..... |
|          | Trichloroacetic acid .....                                                                                        | 8                         | UN1839                   | II  | 8 .....     | A7, IB8, IP2, IP4, N34, T3, TP33  | 154 .....             | 212 ..... | 240 ..... | 15 kg                                           | 50 kg                | A               | ..... |
|          | Trichloroacetic acid, solution .....                                                                              | 8                         | UN2564                   | II  | 8 .....     | A3, A6, A7, B2, IB2, N34, T7, TP2 | 154 .....             | 202 ..... | 242 ..... | 1 L                                             | 30 L                 | B               | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|   |                                                            |            |       |           |       |                                                        |      |       |      |       |           |       |           |           |   |                     |
|---|------------------------------------------------------------|------------|-------|-----------|-------|--------------------------------------------------------|------|-------|------|-------|-----------|-------|-----------|-----------|---|---------------------|
|   | .....                                                      | .....      | III   | 8         | ..... | A3, A6, A7, IB3, N34, T4, TP1                          | 154  | ..... | 203  | ..... | 241       | ..... | 5 L       | 60 L      | B | 8                   |
| + | Trichloroacetyl chloride                                   | 8 UN2442   | II    | 8, 6.1    | ..... | 2, B9, B14, B32, B74, N34, T20, TP2, TP38, TP45        | None | ....  | 227  | ..... | 244       | ..... | Forbidden | Forbidden | D | 40                  |
|   | Trichlorobenzenes, liquid                                  | 6.1 UN2321 | III   | 6.1       | ..... | IB3, T4, TP1                                           | 153  | ..... | 203  | ..... | 241       | ..... | 60 L      | 220 L     | A | .....               |
|   | Trichlorobutene                                            | 6.1 UN2322 | II    | 6.1       | ..... | IB2, T7, TP2                                           | 153  | ..... | 202  | ..... | 243       | ..... | 5 L       | 60 L      | A | 25, 40              |
|   | 1,1,1-Trichloroethane                                      | 6.1 UN2831 | III   | 6.1       | ..... | IB3, N36, T4, TP1                                      | 153  | ..... | 203  | ..... | 241       | ..... | 60 L      | 220 L     | A | 40                  |
|   | Trichloroethylene                                          | 6.1 UN1710 | III   | 6.1       | ..... | IB3, N36, T4, TP1                                      | 153  | ..... | 203  | ..... | 241       | ..... | 60 L      | 220 L     | A | 40                  |
|   | Trichloroisocyanuric acid, dry                             | 5.1 UN2468 | II    | 5.1       | ..... | IB8, IP4, T3, TP33                                     | 152  | ..... | 212  | ..... | 240       | ..... | 5 kg      | 25 kg     | A | 13                  |
|   | Trichloromethyl perchlorate                                | Forbidden  |       |           |       |                                                        |      |       |      |       |           |       |           |           |   |                     |
|   | Trichlorosilane                                            | 4.3 UN1295 | I     | 4.3, 3, 8 | ..... | N34, T14, TP2, TP7, TP13                               | None | ....  | 201  | ..... | 244       | ..... | Forbidden | Forbidden | D | 21, 28, 40, 49, 100 |
|   | Tricresyl phosphate with more than 3 percent ortho isomer. | 6.1 UN2574 | II    | 6.1       | ..... | A3, IB2, N33, N34, T7, TP2                             | 153  | ..... | 202  | ..... | 243       | ..... | 5 L       | 60 L      | A | .....               |
|   | Triethyl phosphite                                         | 3 UN2323   | III   | 3         | ..... | B1, IB3, T2, TP1                                       | 150  | ..... | 203  | ..... | 242       | ..... | 60 L      | 220 L     | A | .....               |
|   | Triethylamine                                              | 3 UN1296   | II    | 3, 8      | ..... | IB2, T7, TP1                                           | 150  | ..... | 202  | ..... | 243       | ..... | 1 L       | 5 L       | B | 40                  |
|   | Triethylenetetramine                                       | 8 UN2259   | II    | 8         | ..... | B2, IB2, T7, TP2                                       | 154  | ..... | 202  | ..... | 242       | ..... | 1 L       | 30 L      | B | 40, 52              |
|   | Trifluoroacetic acid                                       | 8 UN2699   | I     | 8         | ..... | A3, A6, A7, B4, N3, N34, N36, T10, TP2, TP12           | None | ....  | 201  | ..... | 243       | ..... | 0.5 L     | 2.5 L     | B | 12, 40              |
|   | Trifluoroacetyl chloride                                   | 2.3 UN3057 | ..... | 2.3, 8    | ..... | 2, B7, B9, B14, T50, TP21                              | None | ....  | 304  | ..... | 314, 315. | ..... | Forbidden | Forbidden | D | 40                  |
|   | Trifluorochloroethylene, stabilized.                       | 2.3 UN1082 | ..... | 2.3, 2.1. | ..... | 3, B14, T50                                            | None | ....  | 304  | ..... | 314, 315. | ..... | Forbidden | Forbidden | D | 40                  |
|   | Trifluoromethane or Refrigerant gas R 23.                  | 2.2 UN1984 | ..... | 2.2       | ..... |                                                        | 306  | ..... | 304  | ..... | 314, 315. | ..... | 75 kg     | 150 kg    | A | .....               |
|   | Trifluoromethane, refrigerated liquid.                     | 2.2 UN3136 | ..... | 2.2       | ..... | T75, TP5                                               | 306  | ..... | None | ....  | 314, 315. | ..... | 50 kg     | 500 kg    | D | .....               |
|   | 1,1,1-Trifluoroethane or Refrigerant gas, R 143a.          | 2.1 UN2035 | ..... | 2.1       | ..... | T50                                                    | 306  | ..... | 304  | ..... | 314, 315. | ..... | Forbidden | 150 kg    | B | 40                  |
|   | 2-Trifluoromethylaniline                                   | 6.1 UN2942 | III   | 6.1       | ..... | IB3                                                    | 153  | ..... | 203  | ..... | 241       | ..... | 60 L      | 220 L     | A | .....               |
|   | 3-Trifluoromethylaniline                                   | 6.1 UN2948 | II    | 6.1       | ..... | IB2, T7, TP2                                           | 153  | ..... | 202  | ..... | 243       | ..... | 5 L       | 60 L      | A | 40                  |
|   | Triformoxime trinitrate                                    | Forbidden  |       |           |       |                                                        |      |       |      |       |           |       |           |           |   |                     |
|   | Triisobutylene                                             | 3 UN2324   | III   | 3         | ..... | B1, IB3, T4, TP1                                       | 150  | ..... | 203  | ..... | 242       | ..... | 60 L      | 220 L     | A | .....               |
|   | Triisopropyl borate                                        | 3 UN2616   | II    | 3         | ..... | IB2, T4, TP1                                           | 150  | ..... | 202  | ..... | 242       | ..... | 5 L       | 60 L      | A | .....               |
|   | .....                                                      | .....      | III   | 3         | ..... | B1, IB3, T2, TP1                                       | 150  | ..... | 203  | ..... | 242       | ..... | 60 L      | 220 L     | A | .....               |
| D | Trimethoxysilane                                           | 6.1 NA9269 | I     | 6.1, 3    | ..... | 2, B9, B14, B32, B74, T20, TP4, TP12, TP13, TP38, TP45 | None | ....  | 227  | ..... | 244       | ..... | Forbidden | Forbidden | E | 40                  |
|   | Trimethyl borate                                           | 3 UN2416   | II    | 3         | ..... | IB2, T7, TP1                                           | 150  | ..... | 202  | ..... | 242       | ..... | 5 L       | 60 L      | B | .....               |
|   | Trimethyl phosphite                                        | 3 UN2329   | III   | 3         | ..... | B1, IB3, T2, TP1                                       | 150  | ..... | 203  | ..... | 242       | ..... | 60 L      | 220 L     | A | .....               |
|   | 1,3,5-Trimethyl-2,4,6-trinitrobenzene.                     | Forbidden  |       |           |       |                                                        |      |       |      |       |           |       |           |           |   |                     |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                               | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)                                   | (8)                   |           |           | (9)                                             |                       | (10)             |         |
|----------|-------------------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|--------------------------------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|---------|
|          |                                                                                           |                            |                            |       |             |                                                                    | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |         |
|          |                                                                                           |                            |                            |       |             |                                                                    | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other   |
|          | Trimethylacetyl chloride .....                                                            | 6.1                        | UN2438                     | I     | 6.1, 8, 3.  | 2, B3, B9, B14, B32, B74, N34, T20, TP2, TP13, TP38, TP45 N87, T50 | None ....             | 227 ..... | 244 ..... | Forbidden                                       | Forbidden             | D                | 25, 40  |
|          | Trimethylamine, anhydrous .....                                                           | 2.1                        | UN1083                     | ..... | 2.1 ....    | N87, T50                                                           | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg                | B                | 40      |
|          | Trimethylamine, aqueous solu- tions with not more than 50 percent trimethylamine by mass. | 3                          | UN1297                     | I     | 3, 8 ....   | T11, TP1                                                           | None ....             | 201 ..... | 243 ..... | 0.5 L                                           | 2.5 L                 | D                | 40, 135 |
|          | .....                                                                                     | .....                      | .....                      | II    | 3, 8 ....   | B1, IB2, T7, TP1                                                   | 150 .....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | B                | 40, 41  |
|          | .....                                                                                     | .....                      | .....                      | III   | 3, 8 ....   | B1, IB3, T7, TP1                                                   | 150 .....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                  | A                | 40, 41  |
|          | 1,3,5-Trimethylbenzene .....                                                              | 3                          | UN2325                     | III   | 3 .....     | B1, IB3, T2, TP1                                                   | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....   |
|          | Trimethylchloro-silane .....                                                              | 3                          | UN1298                     | II    | 3, 8 ....   | A3, A7, B77, IB2, N34, T7, TP2, TP13                               | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                   | E                | 40.     |
|          | Trimethylcyclohexylamine .....                                                            | 8                          | UN2326                     | III   | 8 .....     | IB3, T4, TP1                                                       | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | .....   |
|          | Trimethylene glycol diperchlorate.                                                        | Forbidden                  | .....                      | ..... | .....       | .....                                                              | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
|          | Trimethylhexamethylene diisocyanate.                                                      | 6.1                        | UN2328                     | III   | 6.1 ....    | IB3, T4, TP2, TP13                                                 | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                 | B                | .....   |
|          | Trimethylhexamethylenediamin- es.                                                         | 8                          | UN2327                     | III   | 8 .....     | IB3, T4, TP1                                                       | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | .....   |
|          | Trimethylol nitromethane trinitrate.                                                      | Forbidden                  | .....                      | ..... | .....       | .....                                                              | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
|          | Trinitro-meta-cresol .....                                                                | 1.1D                       | UN0216                     | II    | 1.1D ..     | .....                                                              | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | 5E      |
|          | 2,4,6-Trinitro-1,3-diazobenzene                                                           | Forbidden                  | .....                      | ..... | .....       | .....                                                              | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
|          | 2,4,6-Trinitro-1,3,5-triazido ben- zene (dry).                                            | Forbidden                  | .....                      | ..... | .....       | .....                                                              | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
|          | Trinitroacetic acid .....                                                                 | Forbidden                  | .....                      | ..... | .....       | .....                                                              | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
|          | Trinitroacetone nitrile .....                                                             | Forbidden                  | .....                      | ..... | .....       | .....                                                              | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
|          | Trinitroamine cobalt .....                                                                | Forbidden                  | .....                      | ..... | .....       | .....                                                              | .....                 | .....     | .....     | .....                                           | .....                 | .....            | .....   |
|          | Trinitroaniline or Picramide .....                                                        | 1.1D                       | UN0153                     | II    | 1.1D ..     | .....                                                              | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | .....   |
|          | Trinitroanisole .....                                                                     | 1.1D                       | UN0213                     | II    | 1.1D ..     | .....                                                              | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | .....   |
|          | Trinitrobenzene, wetted, with not less than 10% water, by mass.                           | 4.1                        | UN3367                     | I     | 4.1 ....    | 162, A8, A19, N41, N84                                             | None ....             | 211 ..... | None .... | 0.5 kg                                          | 0.5 kg                | E                | 36      |
|          | Trinitrobenzene, dry or wetted with less than 30 percent water, by mass.                  | 1.1D                       | UN0214                     | II    | 1.1D ..     | .....                                                              | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden             | 10               | .....   |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                               |           |        |    |      |       |                        |      |       |     |       |      |       |           |           |    |        |
|-------------------------------------------------------------------------------------------------------------------------------|-----------|--------|----|------|-------|------------------------|------|-------|-----|-------|------|-------|-----------|-----------|----|--------|
| Trinitrobenzene, wetted with not less than 30 percent water, by mass.                                                         | 4.1       | UN1354 | I  | 4.1  | ..... | 23, A2, A8, A19, N41   | None | ....  | 211 | ..... | None | ....  | 0.5 kg    | 0.5 kg    | E  | 28     |
| Trinitrobenzenesulfonic acid .....                                                                                            | 1.1D      | UN0386 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | 5E     |
| Trinitrobenzoic acid, dry or wetted with less than 30 percent water, by mass.                                                 | 1.1D      | UN0215 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | .....  |
| Trinitrobenzoic acid, wetted with not less than 10% water by mass.                                                            | 4.1       | UN3368 | I  | 4.1  | ..... | 162, A8, A19, N41, N84 | None | ....  | 211 | ..... | None | ....  | 0.5 kg    | 0.5 kg    | E  | 36     |
| Trinitrobenzoic acid, wetted with not less than 30 percent water, by mass.                                                    | 4.1       | UN1355 | I  | 4.1  | ..... | 23, A2, A8, A19, N41   | None | ....  | 211 | ..... | None | ....  | 0.5 kg    | 0.5 kg    | E  | 28     |
| Trinitrochlorobenzene or Picryl chloride.                                                                                     | 1.1D      | UN0155 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | .....  |
| Trinitrochlorobenzene (picryl chloride), wetted, with not less than 10% water by mass.                                        | 4.1       | UN3365 | I  | 4.1  | ..... | 162, A8, A19, N41, N84 | None | ....  | 211 | ..... | None | ....  | 0.5 kg    | 0.5 kg    | E  | 36     |
| Trinitroethanol .....                                                                                                         | Forbidden |        |    |      | ..... |                        |      | ..... |     | ..... |      | ..... |           |           |    | .....  |
| Trinitroethylnitrate .....                                                                                                    | Forbidden |        |    |      | ..... |                        |      | ..... |     | ..... |      | ..... |           |           |    | .....  |
| Trinitrofluorenone .....                                                                                                      | 1.1D      | UN0387 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | .....  |
| Trinitromethane .....                                                                                                         | Forbidden |        |    |      | ..... |                        |      | ..... |     | ..... |      | ..... |           |           |    | .....  |
| 1,3,5-Trinitronaphthalene .....                                                                                               | Forbidden |        |    |      | ..... |                        |      | ..... |     | ..... |      | ..... |           |           |    | .....  |
| Trinitronaphthalene .....                                                                                                     | 1.1D      | UN0217 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | .....  |
| Trinitrophenetole .....                                                                                                       | 1.1D      | UN0218 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | .....  |
| Trinitrophenol (picric acid), wetted, with not less than 10 percent water by mass.                                            | 4.1       | UN3364 | I  | 4.1  | ..... | 162, A8, A19, N41, N84 | None | ....  | 211 | ..... | None | ....  | 0.5 kg    | 0.5 kg    | E  | 36     |
| Trinitrophenol or Picric acid, dry or wetted with less than 30 percent water, by mass.                                        | 1.1D      | UN0154 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | 5E     |
| Trinitrophenol, wetted with not less than 30 percent water, by mass.                                                          | 4.1       | UN1344 | I  | 4.1  | ..... | 23, A8, A19, N41       | None | ....  | 211 | ..... | None | ....  | 1 kg      | 15 kg     | E  | 28, 36 |
| 2,4,6-Trinitrophenyl guanidine (dry).                                                                                         | Forbidden |        |    |      | ..... |                        |      | ..... |     | ..... |      | ..... |           |           |    | .....  |
| 2,4,6-Trinitrophenyl nitramine ....                                                                                           | Forbidden |        |    |      | ..... |                        |      | ..... |     | ..... |      | ..... |           |           |    | .....  |
| 2,4,6-Trinitrophenyl trimethylol methyl nitramine trinitrate (dry).                                                           | Forbidden |        |    |      | ..... |                        |      | ..... |     | ..... |      | ..... |           |           |    | .....  |
| Trinitrophenylmethyl nitramine or Tetryl.                                                                                     | 1.1D      | UN0208 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | .....  |
| Trinitroresorcinol or Styphnic acid, dry or wetted with less than 20 percent water, or mixture of alcohol and water, by mass. | 1.1D      | UN0219 | II | 1.1D | ..    |                        | None | ....  | 62  | ..... | None | ....  | Forbidden | Forbidden | 10 | 5E     |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                               | Hazard class or Di-vision | Identifica-tion Num-bers | PG    | Label Codes | Special provi-sions (§ 172.102) | (8)                   |           |           | (9)                                             |                      | (10)            |       |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|--------------------------|-------|-------------|---------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|----------------------|-----------------|-------|
|          |                                                                                                                                                                           |                           |                          |       |             |                                 | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                      | Vessel stow-age |       |
|          |                                                                                                                                                                           |                           |                          |       |             |                                 | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo air-craft only | Loca-tion       | Other |
|          | Trinitroresorcinol, wetted or Styphnic acid, wetted with not less than 20 percent water, or mixture of alcohol and water by mass.                                         | 1.1D                      | UN0394                   | II    | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | 5E    |
|          | 2,4,6-Trinitroso-3-methyl nitraminoanisole.                                                                                                                               | Forbidden                 |                          |       | .....       |                                 | .....                 | .....     | .....     | .....                                           | .....                |                 | ..... |
|          | Trinitrotetramine cobalt nitrate ...                                                                                                                                      | Forbidden                 |                          |       | .....       |                                 | .....                 | .....     | .....     | .....                                           | .....                |                 | ..... |
|          | Trinitrotoluene and Trinitrobenzene mixtures or TNT and trinitrobenzene mixtures or TNT and hexanitrostilbene mixtures or Trinitrotoluene and hexanitrostilbene mixtures. | 1.1D                      | UN0388                   | II    | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | ..... |
|          | Trinitrotoluene mixtures containing Trinitrobenzene and Hexanitrostilbene or TNT mixtures containing trinitrobenzene and hexanitrostilbene.                               | 1.1D                      | UN0389                   | II    | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | ..... |
|          | Trinitrotoluene or TNT, dry or wetted with less than 30 percent water, by mass.                                                                                           | 1.1D                      | UN0209                   | II    | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | ..... |
|          | Trinitrotoluene (TNT), wetted, with not less than 10 percent water by mass.                                                                                               | 4.1                       | UN3366                   | I     | 4.1 .....   | 162, A8, A19, N41, N84          | None ....             | 211 ..... | None .... | 0.5 kg                                          | 0.5 kg               | E               | 36    |
|          | Trinitrotoluene, wetted with not less than 30 percent water, by mass.                                                                                                     | 4.1                       | UN1356                   | I     | 4.1 .....   | 23, A2, A8, A19, N41            | None ....             | 211 ..... | None .... | 0.5 kg                                          | 0.5 kg               | E               | 28    |
|          | Tripropylamine .....                                                                                                                                                      | 3                         | UN2260                   | III   | 3, 8 ....   | B1, IB3, T4, TP1                | 150 .....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                 | A               | 40    |
|          | Tripropylene .....                                                                                                                                                        | 3                         | UN2057                   | II    | 3 .....     | IB2, T4, TP1                    | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                 | B               | ..... |
|          | .....                                                                                                                                                                     |                           |                          | III   | 3 .....     | B1, IB3, T2, TP1                | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                | A               | ..... |
|          | Tris-(1-aziridinyl)phosphine oxide, solution.                                                                                                                             | 6.1                       | UN2501                   | II    | 6.1 .....   | IB2, T7, TP2                    | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                 | A               | ..... |
|          | .....                                                                                                                                                                     |                           |                          | III   | 6.1 .....   | IB3, T4, TP1                    | 153 .....             | 203 ..... | 241 ..... | 60 L                                            | 220 L                | A               | ..... |
|          | Tris, bis-bifluoroamino diethoxy propane (TVOPA).                                                                                                                         | Forbidden                 |                          |       | .....       |                                 | .....                 | .....     | .....     | .....                                           | .....                |                 | ..... |
|          | Tritonal .....                                                                                                                                                            | 1.1D                      | UN0390                   | II    | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden            | 10              | ..... |
|          | Tungsten hexafluoride .....                                                                                                                                               | 2.3                       | UN2196                   | ..... | 2.3, 8      | 2, N86                          | None ....             | 338 ..... | None .... | Forbidden                                       | Forbidden            | D               | 40    |
|          | Turpentine .....                                                                                                                                                          | 3                         | UN1299                   | III   | 3 .....     | B1, IB3, T2, TP1                | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                | A               | ..... |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                       |       |        |       |         |                                        |       |       |           |           |           |       |        |
|-----------------------------------------------------------------------|-------|--------|-------|---------|----------------------------------------|-------|-------|-----------|-----------|-----------|-------|--------|
| Turpentine substitute .....                                           | 3     | UN1300 | I     | 3       | T11, TP1, TP8, TP27                    | None  | 201   | 243       | 1 L       | 30 L      | B     | .....  |
| .....                                                                 | ..... | .....  | II    | 3       | IB2, T4, TP1                           | 150   | 202   | 242       | 5 L       | 60 L      | B     | .....  |
| .....                                                                 | ..... | .....  | III   | 3       | B1, IB3, T2, TP1                       | 150   | 203   | 242       | 60 L      | 220 L     | A     | .....  |
| Undecane .....                                                        | 3     | UN2330 | III   | 3       | B1, IB3, T2, TP1                       | 150   | 203   | 242       | 60 L      | 220 L     | A     | .....  |
| Urea hydrogen peroxide .....                                          | 5.1   | UN1511 | III   | 5.1, 8  | A1, A7, A29, IB8, IP3, T1, TP33        | 152   | 213   | 240       | 25 kg     | 100 kg    | A     | 13     |
| Urea nitrate, dry or wetted with less than 20 percent water, by mass. | 1.1D  | UN0220 | II    | 1.1D .. | 119                                    | None  | 62    | None      | Forbidden | Forbidden | 10    | .....  |
| Urea nitrate, wetted, with not less than 10 percent water by mass.    | 4.1   | UN3370 | I     | 4.1     | 162, A8, A19, N41, N84                 | None  | 211   | None      | 0.5 kg    | 0.5 kg    | E     | 36     |
| Urea nitrate, wetted with not less than 20 percent water, by mass.    | 4.1   | UN1357 | I     | 4.1     | 23, 39, A8, A19, N41                   | None  | 211   | None      | 1 kg      | 15 kg     | E     | 28, 36 |
| Urea peroxide, see Urea hydrogen peroxide.                            | ..... | .....  | ..... | .....   | .....                                  | ..... | ..... | .....     | .....     | .....     | ..... | .....  |
| Valeraldehyde .....                                                   | 3     | UN2058 | II    | 3       | IB2, T4, TP1                           | 150   | 202   | 242       | 5 L       | 60 L      | B     | .....  |
| Valeric acid, see Corrosive liquids, n.o.s.                           | ..... | .....  | ..... | .....   | .....                                  | ..... | ..... | .....     | .....     | .....     | ..... | .....  |
| Valeryl chloride .....                                                | 8     | UN2502 | II    | 8, 3    | A3, A6, A7, B2, IB2, N34, T7, TP2      | 154   | 202   | 243       | 1 L       | 30 L      | C     | 40     |
| Vanadium compound, n.o.s. ....                                        | 6.1   | UN3285 | I     | 6.1     | IB7, IP1, T6, TP33                     | None  | 211   | 242       | 5 kg      | 50 kg     | B     | .....  |
| .....                                                                 | ..... | .....  | II    | 6.1     | IB8, IP2, IP4, T3, TP33                | 153   | 212   | 242       | 25 kg     | 100 kg    | B     | .....  |
| .....                                                                 | ..... | .....  | III   | 6.1     | IB8, IP3, T1, TP33                     | 153   | 213   | 240       | 100 kg    | 200 kg    | A     | .....  |
| Vanadium oxytrichloride .....                                         | 8     | UN2443 | II    | 8       | A3, A6, A7, B2, B16, IB2, N34, T7, TP2 | 154   | 202   | 242       | Forbidden | 30 L      | C     | 40     |
| Vanadium pentoxide, non-fused form.                                   | 6.1   | UN2862 | III   | 6.1     | IB8, IP3, T1, TP33                     | 153   | 213   | 240       | 100 kg    | 200 kg    | A     | 40     |
| Vanadium tetrachloride .....                                          | 8     | UN2444 | I     | 8       | A3, A6, A7, B4, N34, T10, TP2          | None  | 201   | 243       | Forbidden | 2.5 L     | C     | 40     |
| Vanadium trichloride .....                                            | 8     | UN2475 | III   | 8       | IB8, IP3, T1, TP33                     | 154   | 213   | 240       | 25 kg     | 100 kg    | A     | 40     |
| Vanadyl sulfate .....                                                 | 6.1   | UN2931 | II    | 6.1     | IB8, IP2, IP4, T3, TP33                | 153   | 212   | 242       | 25 kg     | 100 kg    | A     | .....  |
| Vehicle, flammable gas powered                                        | 9     | UN3166 | ..... | 9       | 135, 157                               | 220   | 220   | 220       | Forbidden | No limit  | A     | .....  |
| Vehicle, flammable liquid powered.                                    | 9     | UN3166 | ..... | 9       | 135, 157                               | 220   | 220   | 220       | No limit  | No limit  | A     | .....  |
| Very signal cartridge, see Cartridges, signal.                        | ..... | .....  | ..... | .....   | .....                                  | ..... | ..... | .....     | .....     | .....     | ..... | .....  |
| Vinyl acetate, stabilized .....                                       | 3     | UN1301 | II    | 3       | IB2, T4, TP1                           | 150   | 202   | 242       | 5 L       | 60 L      | B     | .....  |
| Vinyl bromide, stabilized .....                                       | 2.1   | UN1085 | ..... | 2.1     | N86, T50                               | 306   | 304   | 314, 315. | Forbidden | 150 kg    | B     | 40     |
| Vinyl butyrate, stabilized .....                                      | 3     | UN2838 | II    | 3       | IB2, T4, TP1                           | 150   | 202   | 242       | 5 L       | 60 L      | B     | .....  |



## § 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descriptions and proper shipping names | Hazard class or Division | Identification Numbers | PG    | Label Codes | Special provisions (§ 172.102)  | (8)                   |           |           | (9)                                             |                     | (10)           |             |
|----------|------------------------------------------------------------|--------------------------|------------------------|-------|-------------|---------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|---------------------|----------------|-------------|
|          |                                                            |                          |                        |       |             |                                 | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                     | Vessel stowage |             |
|          |                                                            |                          |                        |       |             |                                 | Excep-tions           | Non-bulk  | Bulk      | Passenger aircraft/rail                         | Cargo aircraft only | Loca-tion      | Other       |
|          | Vinyl chloride, stabilized .....                           | 2.1                      | UN1086                 | ..... | 2.1 .....   | 21, B44, N86, T50               | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg              | B              | 40          |
|          | Vinyl chloroacetate .....                                  | 6.1                      | UN2589                 | II    | 6.1, 3      | IB2, T7, TP2                    | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                | A              | .....       |
|          | Vinyl ethyl ether, stabilized .....                        | 3                        | UN1302                 | I     | 3 .....     | A3, T11, TP2                    | None .....            | 201 ..... | 243 ..... | 1 L                                             | 30 L                | D              | .....       |
|          | Vinyl fluoride, stabilized .....                           | 2.1                      | UN1860                 | ..... | 2.1 .....   | N86                             | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg              | E              | 40          |
|          | Vinyl isobutyl ether, stabilized ...                       | 3                        | UN1304                 | II    | 3 .....     | IB2, T4, TP1                    | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                | B              | .....       |
|          | Vinyl methyl ether, stabilized .....                       | 2.1                      | UN1087                 | ..... | 2.1 .....   | B44, T50                        | 306 .....             | 304 ..... | 314, 315. | Forbidden                                       | 150 kg              | B              | 40          |
|          | Vinyl nitrate polymer .....                                | Forbidden                |                        |       |             |                                 |                       |           |           |                                                 |                     |                |             |
|          | Vinylidene chloride, stabilized ....                       | 3                        | UN1303                 | I     | 3 .....     | T12, TP2, TP7                   | 150 .....             | 201 ..... | 243 ..... | 1 L                                             | 30 L                | E              | 40          |
|          | Vinylpyridines, stabilized .....                           | 6.1                      | UN3073                 | II    | 6.1, 3, 8.  | IB1, T7, TP2, TP13              | 153 .....             | 202 ..... | 243 ..... | 1 L                                             | 30 L                | B              | 21, 40, 52. |
|          | Vinyltoluenes, stabilized .....                            | 3                        | UN2618                 | III   | 3 .....     | B1, IB3, T2, TP1                | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L               | A              | .....       |
|          | Vinyltrichlorosilane, stabilized ....                      | 3                        | UN1305                 | I     | 3, 8 .....  | A3, A7, B6, N34, T11, TP2, TP13 | None .....            | 201 ..... | 243 ..... | Forbidden                                       | 2.5 L               | B              | 40          |
|          | Warheads, rocket with burster or expelling charge.         | 1.4D                     | UN0370                 | II    | 1.4D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | 75 kg               | 02             | .....       |
|          | Warheads, rocket with burster or expelling charge.         | 1.4F                     | UN0371                 | II    | 1.4F ...    |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden           | 08             | .....       |
|          | Warheads, rocket with bursting charge.                     | 1.1D                     | UN0286                 | II    | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden           | 03             | .....       |
|          | Warheads, rocket with bursting charge.                     | 1.2D                     | UN0287                 | II    | 1.2D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden           | 03             | .....       |
|          | Warheads, rocket with bursting charge.                     | 1.1F                     | UN0369                 | II    | 1.1F ...    |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden           | 08             | .....       |
|          | Warheads, torpedo with bursting charge.                    | 1.1D                     | UN0221                 | II    | 1.1D ..     |                                 | None ....             | 62 .....  | None .... | Forbidden                                       | Forbidden           | 03             | .....       |
| G        | Water-reactive liquid, corrosive, n.o.s..                  | 4.3                      | UN3129                 | I     | 4.3, 8      |                                 | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 1 L                 | D              | .....       |
|          | .....                                                      |                          |                        | II    | 4.3, 8      | IB1                             | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                 | E              | 85          |
|          | .....                                                      |                          |                        | III   | 4.3, 8      | IB2                             | None ....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                | E              | .....       |
| G        | Water-reactive liquid, n.o.s. ....                         | 4.3                      | UN3148                 | I     | 4.3 .....   |                                 | None ....             | 201 ..... | 244 ..... | Forbidden                                       | 1 L                 | E              | 40          |
|          | .....                                                      |                          |                        | II    | 4.3 .....   | IB1                             | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                 | E              | 40          |
|          | .....                                                      |                          |                        | III   | 4.3 .....   | IB2                             | None ....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                | E              | 40          |
| G        | Water-reactive liquid, toxic, n.o.s..                      | 4.3                      | UN3130                 | I     | 4.3, 6.1.   | A4                              | None ....             | 201 ..... | 243 ..... | Forbidden                                       | 1 L                 | D              | .....       |
|          | .....                                                      |                          |                        | II    | 4.3, 6.1.   | IB1                             | None ....             | 202 ..... | 243 ..... | 1 L                                             | 5 L                 | E              | 85          |
|          | .....                                                      |                          |                        | III   | 4.3, 6.1.   | IB2                             | None ....             | 203 ..... | 242 ..... | 5 L                                             | 60 L                | E              | 85          |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|          |                                                                             |       |        |     |           |                              |      |     |     |           |           |   |        |
|----------|-----------------------------------------------------------------------------|-------|--------|-----|-----------|------------------------------|------|-----|-----|-----------|-----------|---|--------|
| G        | Water-reactive solid, corrosive, n.o.s..                                    | 4.3   | UN3131 | I   | 4.3, 8    | IB4, IP1, N40                | None | 211 | 242 | Forbidden | 15 kg     | D | .....  |
|          | .....                                                                       | ..... | .....  | II  | 4.3, 8    | IB6, IP2, T3, TP33           | 151  | 212 | 242 | 15 kg     | 50 kg     | E | 85     |
|          | .....                                                                       | ..... | .....  | III | 4.3, 8    | IB8, IP4, T1, TP33           | 151  | 213 | 241 | 25 kg     | 100 kg    | E | 85     |
|          | Water-reactive solid, flammable, n.o.s..                                    | 4.3   | UN3132 | I   | 4.3, 4.1. | IB4, N40                     | None | 211 | 242 | Forbidden | 15 kg     | D | .....  |
|          | .....                                                                       | ..... | .....  | II  | 4.3, 4.1. | IB4, T3, TP33                | 151  | 212 | 242 | 15 kg     | 50 kg     | E | .....  |
|          | .....                                                                       | ..... | .....  | III | 4.3, 4.1. | IB6, T1, TP33                | 151  | 213 | 241 | 25 kg     | 100 kg    | E | .....  |
|          | Water-reactive solid, n.o.s. ....                                           | 4.3   | UN2813 | I   | 4.3       | IB4, N40                     | None | 211 | 242 | Forbidden | 15 kg     | E | 40     |
|          | .....                                                                       | ..... | .....  | II  | 4.3       | IB7, IP2, T3, TP33           | 151  | 212 | 242 | 15 kg     | 50 kg     | E | 40     |
|          | .....                                                                       | ..... | .....  | III | 4.3       | IB8, IP4, T1, TP33           | 151  | 213 | 241 | 25 kg     | 100 kg    | E | 40     |
|          | Water-reactive, solid, oxidizing, n.o.s..                                   | 4.3   | UN3133 | II  | 4.3, 5.1. |                              | None | 214 | 214 | Forbidden | Forbidden | E | 40     |
| G        | .....                                                                       | ..... | .....  | III | 4.3, 5.1. |                              | None | 214 | 214 | Forbidden | Forbidden | E | 40     |
|          | Water-reactive solid, self-heating, n.o.s..                                 | 4.3   | UN3135 | I   | 4.3, 4.2. | N40                          | None | 211 | 242 | Forbidden | 15 kg     | E | .....  |
|          | .....                                                                       | ..... | .....  | II  | 4.3, 4.2. | IB5, IP2, T3, TP33           | None | 212 | 242 | 15 kg     | 50 kg     | E | .....  |
|          | .....                                                                       | ..... | .....  | III | 4.3, 4.2. | IB8, IP4, T1, TP33           | None | 213 | 241 | 25 kg     | 100 kg    | E | .....  |
|          | Water-reactive solid, toxic, n.o.s.                                         | 4.3   | UN3134 | I   | 4.3, 6.1. | A8, IB4, IP1, N40            | None | 211 | 242 | Forbidden | 15 kg     | D | .....  |
|          | .....                                                                       | ..... | .....  | II  | 4.3, 6.1. | IB5, IP2, T3, TP33           | 151  | 212 | 242 | 15 kg     | 50 kg     | E | 85     |
|          | .....                                                                       | ..... | .....  | III | 4.3, 6.1. | IB8, IP4, T1, TP33           | 151  | 213 | 241 | 25 kg     | 100 kg    | E | 85     |
|          | .....                                                                       | ..... | .....  |     | .....     |                              |      |     |     |           |           |   | .....  |
|          | .....                                                                       | ..... | .....  |     | .....     |                              |      |     |     |           |           |   | .....  |
|          | .....                                                                       | ..... | .....  |     | .....     |                              |      |     |     |           |           |   | .....  |
| I        | White asbestos ( <i>chrysotile, actinolite, anthophyllite, tremolite</i> ). | 9     | UN2590 | III | 9         | 156, IB8, IP2, IP3, T1, TP33 | 155  | 216 | 240 | 200 kg    | 200 kg    | A | 34, 40 |
|          | Wood preservatives, liquid                                                  | 3     | UN1306 | II  | 3         | 149, IB2, T4, TP1, TP8       | 150  | 202 | 242 | 5 L       | 60 L      | B | .....  |
|          | .....                                                                       | ..... | .....  | III | 3         | B1, IB3, T2, TP1             | 150  | 203 | 242 | 60 L      | 220 L     | A | 40     |
|          | Wool waste, wet                                                             | 4.2   | UN1387 | III | 4.2       |                              | 151  | 213 | 240 | Forbidden | Forbidden | A | .....  |
|          | Xanthates                                                                   | 4.2   | UN3342 | II  | 4.2       | IB6, IP2, T3, TP33           | None | 212 | 241 | 15 kg     | 50 kg     | D | 40     |
|          | .....                                                                       | ..... | .....  | III | 4.2       | IB8, IP3, T1, TP33           | None | 213 | 241 | 25 kg     | 100 kg    | D | 40     |
|          | .....                                                                       | ..... | .....  |     |           |                              |      |     |     |           |           |   |        |
|          | .....                                                                       | ..... | .....  |     |           |                              |      |     |     |           |           |   |        |
|          | .....                                                                       | ..... | .....  |     |           |                              |      |     |     |           |           |   |        |
|          | .....                                                                       | ..... | .....  |     |           |                              |      |     |     |           |           |   |        |
| A I<br>W | .....                                                                       | ..... | .....  |     |           |                              |      |     |     |           |           |   |        |
|          | .....                                                                       | ..... | .....  |     |           |                              |      |     |     |           |           |   |        |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                      | Hazard class or Di- vision | Identifica- tion Num- bers | PG    | Label Codes | Special provi- sions (§ 172.102)         | (8)                   |           |           | (9)                                             |                       | (10)             |        |
|----------|----------------------------------------------------------------------------------|----------------------------|----------------------------|-------|-------------|------------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|--------|
|          |                                                                                  |                            |                            |       |             |                                          | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |        |
|          |                                                                                  |                            |                            |       |             |                                          | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other  |
|          | Xenon .....                                                                      | 2.2                        | UN2036                     | ..... | 2.2 .....   |                                          | 306 .....             | 302 ..... | None .... | 75 kg                                           | 150 kg                | A                | .....  |
|          | Xenon, refrigerated liquid ( <i>cryo- genic liquids</i> ). .....                 | 2.2                        | UN2591                     | ..... | 2.2 .....   | T75, TP5                                 | 320 .....             | None .... | None .... | 50 kg                                           | 500 kg                | B                | .....  |
|          | Xylenes .....                                                                    | 3                          | UN1307                     | II    | 3 .....     | IB2, T4, TP1                             | 150 .....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | .....  |
|          | .....                                                                            |                            |                            | III   | 3 .....     | B1, IB3, T2, TP1                         | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | A                | .....  |
|          | Xylenols, solid .....                                                            | 6.1                        | UN2261                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                  | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | .....  |
|          | Xylenols, liquid .....                                                           | 6.1                        | UN3430                     | II    | 6.1 .....   | IB2, T7, TP2                             | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | .....  |
|          | Xylidines, liquid .....                                                          | 6.1                        | UN1711                     | II    | 6.1 .....   | IB2, T7, TP2                             | 153 .....             | 202 ..... | 243 ..... | 5 L                                             | 60 L                  | A                | .....  |
|          | Xylidines, solid .....                                                           | 6.1                        | UN3452                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                  | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | .....  |
|          | Xylyl bromide, liquid .....                                                      | 6.1                        | UN1701                     | II    | 6.1 .....   | A3, A6, A7, IB2, N33, T7, TP2, TP13      | None ....             | 340 ..... | None .... | Forbidden                                       | 60 L                  | D                | 40     |
|          | Xylyl bromide, solid .....                                                       | 6.1                        | UN3417                     | II    | 6.1 .....   | A3, A6, A7, IB8, IP2, IP4, N33, T3, TP33 | None ....             | 340 ..... | None .... | 25 kg                                           | 100 kg                | B                | 40     |
|          | <i>p</i> -Xylyl diazide .....                                                    | Forbidden                  |                            |       | .....       |                                          | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....  |
|          | Zinc ammonium nitrite .....                                                      | 5.1                        | UN1512                     | II    | 5.1 .....   | IB8, IP4, T3, TP33                       | None ....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg                 | E                | .....  |
|          | Zinc arsenate or Zinc arsenite or Zinc arsenate and zinc arsenite mixtures. .... | 6.1                        | UN1712                     | II    | 6.1 .....   | IB8, IP2, IP4, T3, TP33                  | 153 .....             | 212 ..... | 242 ..... | 25 kg                                           | 100 kg                | A                | .....  |
|          | Zinc ashes .....                                                                 | 4.3                        | UN1435                     | III   | 4.3 .....   | A1, A19, IB8, IP4, T1, TP33              | 151 .....             | 213 ..... | 241 ..... | 25 kg                                           | 100 kg                | A                | .....  |
|          | <i>Zinc bisulfite solution, see Bisulfites, aqueous solutions, n.o.s..</i> ..... |                            |                            |       | .....       |                                          | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....  |
|          | Zinc bromate .....                                                               | 5.1                        | UN2469                     | III   | 5.1 .....   | A1, A29, IB8, IP3, T1, TP33              | 152 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | 56, 58 |
|          | Zinc chlorate .....                                                              | 5.1                        | UN1513                     | II    | 5.1 .....   | A9, IB8, IP2, IP4, N34, T3, TP33         | 152 .....             | 212 ..... | 242 ..... | 5 kg                                            | 25 kg                 | A                | 56, 58 |
|          | Zinc chloride, anhydrous .....                                                   | 8                          | UN2331                     | III   | 8 .....     | IB8, IP3, T1, TP33                       | None ....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | .....  |
|          | Zinc chloride, solution .....                                                    | 8                          | UN1840                     | III   | 8 .....     | IB3, T4, TP1                             | 154 .....             | 203 ..... | 241 ..... | 5 L                                             | 60 L                  | A                | .....  |
|          | Zinc cyanide .....                                                               | 6.1                        | UN1713                     | I     | 6.1 .....   | IB7, IP1, T6, TP33                       | None ....             | 211 ..... | 242 ..... | 5 kg                                            | 50 kg                 | A                | 52     |
|          | Zinc dithionite or Zinc hydro- sulfite. ....                                     | 9                          | UN1931                     | III   | None        | IB8, IP3, T1, TP33                       | 155 .....             | 204 ..... | 240 ..... | 100 kg                                          | 200 kg                | A                | 49     |
|          | <i>Zinc ethyl, see Diethylzinc</i> .....                                         |                            |                            |       | .....       |                                          | .....                 | .....     | .....     | .....                                           | .....                 |                  | .....  |

§ 172.101

49 CFR Ch. I (10-1-08 Edition)

|                                                                                                                       |       |        |     |           |                                       |           |           |           |           |           |    |                |
|-----------------------------------------------------------------------------------------------------------------------|-------|--------|-----|-----------|---------------------------------------|-----------|-----------|-----------|-----------|-----------|----|----------------|
| Zinc fluorosilicate .....                                                                                             | 6.1   | UN2855 | III | 6.1 ..... | IB8, IP3, T1, TP33                    | 153 ..... | 213 ..... | 240 ..... | 100 kg    | 200 kg    | A  | 52             |
| Zinc hydrosulfite, see Zinc dithionite.                                                                               | ..... |        |     | .....     |                                       | .....     | .....     | .....     | .....     | .....     |    | .....          |
| Zinc muriate solution, see Zinc chloride, solution.                                                                   | ..... |        |     | .....     |                                       | .....     | .....     | .....     | .....     | .....     |    | .....          |
| Zinc nitrate .....                                                                                                    | 5.1   | UN1514 | II  | 5.1 ..... | IB8, IP4, T3, TP33                    | 152 ..... | 212 ..... | 240 ..... | 5 kg      | 25 kg     | A  | .....          |
| Zinc permanganate .....                                                                                               | 5.1   | UN1515 | II  | 5.1 ..... | IB6, IP2, T3, TP33                    | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | D  | 56, 58, 138    |
| Zinc peroxide .....                                                                                                   | 5.1   | UN1516 | II  | 5.1 ..... | IB6, IP2, T3, TP33                    | 152 ..... | 212 ..... | 242 ..... | 5 kg      | 25 kg     | A  | 13, 52, 66, 75 |
| Zinc phosphide .....                                                                                                  | 4.3   | UN1714 | I   | 4.3, 6.1. | A19, N40                              | None .... | 211 ..... | None .... | Forbidden | 15 kg     | E  | 40, 52, 85     |
| Zinc powder or Zinc dust .....                                                                                        | 4.3   | UN1436 | I   | 4.3, 4.2. | A19, IB4, IP1, N40                    | None .... | 211 ..... | 242 ..... | Forbidden | 15 kg     | A  | 52, 53         |
| .....                                                                                                                 | ..... |        | II  | 4.3, 4.2. | A19, IB7, IP2, T3, TP33               | None .... | 212 ..... | 242 ..... | 15 kg     | 50 kg     | A  | 52, 53         |
| .....                                                                                                                 | ..... |        | III | 4.3, 4.2. | IB8, IP4, T1, TP33                    | None .... | 213 ..... | 242 ..... | 25 kg     | 100 kg    | A  | 52, 53         |
| Zinc resinate .....                                                                                                   | 4.1   | UN2714 | III | 4.1 ..... | A1, IB6, T1, TP33                     | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A  | .....          |
| Zinc selenate, see Selenates or Selenites.                                                                            | ..... |        |     | .....     |                                       | .....     | .....     | .....     | .....     | .....     |    | .....          |
| Zinc selenite, see Selenates or Selenites.                                                                            | ..... |        |     | .....     |                                       | .....     | .....     | .....     | .....     | .....     |    | .....          |
| Zinc silicofluoride, see Zinc fluorosilicate.                                                                         | ..... |        |     | .....     |                                       | .....     | .....     | .....     | .....     | .....     |    | .....          |
| Zirconium, dry, coiled wire, finished metal sheets, strip (thinner than 254 microns but not thinner than 18 microns). | 4.1   | UN2858 | III | 4.1 ..... | A1                                    | 151 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A  | .....          |
| Zirconium, dry, finished sheets, strip or coiled wire.                                                                | 4.2   | UN2009 | III | 4.2 ..... | A1, A19                               | None .... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | D  | .....          |
| Zirconium hydride .....                                                                                               | 4.1   | UN1437 | II  | 4.1 ..... | A19, A20, IB4, N34, T3, TP33          | None .... | 212 ..... | 240 ..... | 15 kg     | 50 kg     | E  | .....          |
| Zirconium nitrate .....                                                                                               | 5.1   | UN2728 | III | 5.1 ..... | A1, A29, IB8, IP3, T1, TP33           | 152 ..... | 213 ..... | 240 ..... | 25 kg     | 100 kg    | A  | .....          |
| Zirconium picramate, dry or wetted with less than 20 percent water, by mass.                                          | 1.3C  | UN0236 | II  | 1.3C ..   |                                       | None .... | 62 .....  | None .... | Forbidden | Forbidden | 10 | 5E             |
| Zirconium picramate, wetted with not less than 20 percent water, by mass.                                             | 4.1   | UN1517 | I   | 4.1 ..... | 23, N41                               | None .... | 211 ..... | None .... | 1 kg      | 15 kg     | D  | 28, 36         |
| Zirconium powder, dry .....                                                                                           | 4.2   | UN2008 | I   | 4.2 ..... | T21, TP7, TP33                        | None .... | 211 ..... | 242 ..... | Forbidden | Forbidden | D  | .....          |
| .....                                                                                                                 | ..... |        | II  | 4.2 ..... | A19, A20, IB6, IP2, N5, N34, T3, TP33 | None .... | 212 ..... | 241 ..... | 15 kg     | 50 kg     | D  | .....          |
| .....                                                                                                                 | ..... |        | III | 4.2 ..... | IB8, IP3, T1, TP33                    | None .... | 213 ..... | 241 ..... | 25 kg     | 100 kg    | D  | .....          |

§ 172.101 HAZARDOUS MATERIALS TABLE—Continued

| Sym-bols | Hazardous materials descrip-tions and proper shipping names                                                                                                                                                                                    | Hazard class or Di- vision | Identifica- tion Num- bers | PG  | Label Codes | Special provi- sions (§ 172.102)     | (8)                   |           |           | (9)                                             |                       | (10)             |       |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------|-----|-------------|--------------------------------------|-----------------------|-----------|-----------|-------------------------------------------------|-----------------------|------------------|-------|
|          |                                                                                                                                                                                                                                                |                            |                            |     |             |                                      | Packaging (§ 173.***) |           |           | Quantity limitations (see §§ 173.27 and 175.75) |                       | Vessel stow- age |       |
|          |                                                                                                                                                                                                                                                |                            |                            |     |             |                                      | Excep- tions          | Non- bulk | Bulk      | Passenger aircraft/rail                         | Cargo air- craft only | Loca- tion       | Other |
|          | Zirconium powder, wetted <i>with not less than 25 percent water (a visible excess of water must be present) (a) mechani- cally produced, particle size less than 53 microns; (b) chemically produced, particle size less than 840 microns.</i> | 4.1                        | UN1358                     | II  | 4.1 .....   | A19, A20, IB6, IP2, N34, T3, TP33    | None ....             | 212 ..... | 241 ..... | 15 kg                                           | 50 kg                 | E                | 74    |
|          | Zirconium scrap .....                                                                                                                                                                                                                          | 4.2                        | UN1932                     | III | 4.2 .....   | IB8, IP3, N34, T1, TP33              | None ....             | 213 ..... | 240 ..... | Forbidden                                       | Forbidden             | D                | ..... |
|          | Zirconium suspended in a liquid .....                                                                                                                                                                                                          | 3                          | UN1308                     | I   | 3 .....     | IB2<br>B1, IB2<br>IB8, IP3, T1, TP33 | None ....             | 201 ..... | 243 ..... | Forbidden                                       | Forbidden             | B                | ..... |
|          | .....                                                                                                                                                                                                                                          |                            |                            | II  | 3 .....     |                                      | None ....             | 202 ..... | 242 ..... | 5 L                                             | 60 L                  | B                | ..... |
|          | .....                                                                                                                                                                                                                                          |                            |                            | III | 3 .....     |                                      | 150 .....             | 203 ..... | 242 ..... | 60 L                                            | 220 L                 | B                | ..... |
|          | Zirconium tetrachloride .....                                                                                                                                                                                                                  | 8                          | UN2503                     | III | 8 .....     |                                      | 154 .....             | 213 ..... | 240 ..... | 25 kg                                           | 100 kg                | A                | ..... |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

## APPENDIX A TO § 172.101—LIST OF HAZARDOUS SUBSTANCES AND REPORTABLE QUANTITIES

1. This appendix lists materials and their corresponding reportable quantities (RQ's) that are listed or designated as "hazardous substances" under section 101(14) of the Comprehensive Environmental Response, Compensation, and Liability Act, 42 U.S.C. 9601(14) (CERCLA; 42 U.S.C. 9601 *et seq.*). This listing fulfills the requirement of CERCLA, 42 U.S.C. 9656(a), that all "hazardous substances," as defined in 42 U.S.C. 9601(14), be listed and regulated as hazardous materials under 49 U.S.C. 5101–5127. That definition includes substances listed under sections 311(b)(2)(A) and 307(a) of the Federal Water Pollution Control Act, 33 U.S.C. 1321(b)(2)(A) and 1317(a), section 3001 of the Solid Waste Disposal Act, 42 U.S.C. 6921, and section 112 of the Clean Air Act, 42 U.S.C. 7412. In addition, this list contains materials that the Administrator of the Environmental Protection Agency has determined to be hazardous substances in accordance with section 102 of CERCLA, 42 U.S.C. 9602. It should be noted that 42 U.S.C. 9656(b) provides that common and contract carriers may be held liable under laws other than CERCLA for the release of a hazardous substance as defined in that Act, during transportation that commenced before the effective date of the listing and regulating of that substance as a hazardous material under 49 U.S.C. 5101–5127.

2. This appendix is divided into two TABLES which are entitled "TABLE 1—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES" and "TABLE 2—RADIONUCLIDES." A material listed in this appendix is regulated as a hazardous material and a hazardous substance under this subchapter if it meets the definition of a hazardous substance in § 171.8 of this subchapter.

3. The procedure for selecting a proper shipping name for a hazardous substance is set forth in § 172.101(c).

4. Column 1 of TABLE 1, entitled "Hazardous substance", contains the names of those elements and compounds that are hazardous substances. Following the listing of elements and compounds is a listing of waste streams. These waste streams appear on the list in numerical sequence and are referenced by the appropriate "D", "F", or "K" numbers. Column 2 of TABLE 1, entitled "Reportable quantity (RQ)", contains the report-

able quantity (RQ), in pounds and kilograms, for each hazardous substance listed in Column 1 of TABLE 1.

5. A series of notes is used throughout TABLE 1 and TABLE 2 to provide additional information concerning certain hazardous substances. These notes are explained at the end of each TABLE.

6. TABLE 2 lists radionuclides that are hazardous substances and their corresponding RQ's. The RQ's in table 2 for radionuclides are expressed in units of curies and terabecquerels, whereas those in table 1 are expressed in units of pounds and kilograms. If a material is listed in both table 1 and table 2, the lower RQ shall apply. Radionuclides are listed in alphabetical order. The RQ's for radionuclides are given in the radiological unit of measure of curie, abbreviated "Ci", followed, in parentheses, by an equivalent unit measured in terabecquerels, abbreviated "TBq".

7. For mixtures of radionuclides, the following requirements shall be used in determining if a package contains an RQ of a hazardous substance: (i) if the identity and quantity (in curies or terabecquerels) of each radionuclide in a mixture or solution is known, the ratio between the quantity per package (in curies or terabecquerels) and the RQ for the radionuclide must be determined for each radionuclide. A package contains an RQ of a hazardous substance when the sum of the ratios for the radionuclides in the mixture or solution is equal to or greater than one; (ii) if the identity of each radionuclide in a mixture or solution is known but the quantity per package (in curies or terabecquerels) of one or more of the radionuclides is unknown, an RQ of a hazardous substance is present in a package when the total quantity (in curies or terabecquerels) of the mixture or solution is equal to or greater than the lowest RQ of any individual radionuclide in the mixture or solution; and (iii) if the identity of one or more radionuclides in a mixture or solution is unknown (or if the identity of a radionuclide by itself is unknown), an RQ of a hazardous substance is present when the total quantity (in curies or terabecquerels) in a package is equal to or greater than either one curie or the lowest RQ of any known individual radionuclide in the mixture or solution, whichever is lower.

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES

| Hazardous substance         | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|-----------------------------|---------------------------------------------------|
| A2213 .....                 | 5000 (2270)                                       |
| Acenaphthene .....          | 100 (45.4)                                        |
| Acenaphthylene .....        | 5000 (2270)                                       |
| Acetaldehyde .....          | 1000 (454)                                        |
| Acetaldehyde, chloro- ..... | 1000 (454)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                       | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|-----------------------------------------------------------|---------------------------------------------------|
| Acetaldehyde, trichloro- .....                            | 5000 (2270)                                       |
| Acetamide .....                                           | 100 (45.4)                                        |
| Acetamide, N-(aminothioxomethyl)- .....                   | 1000 (454)                                        |
| Acetamide, N-(4-ethoxyphenyl)- .....                      | 100 (45.4)                                        |
| Acetamide, N-9H-fluoren-2-yl- .....                       | 1 (0.454)                                         |
| Acetamide, 2-fluoro- .....                                | 100 (45.4)                                        |
| Acetic acid .....                                         | 5000 (2270)                                       |
| Acetic acid, (2,4-dichlorophenoxy)-, salts & esters ..... | 100 (45.4)                                        |
| Acetic acid, ethyl ester .....                            | 5000 (2270)                                       |
| Acetic acid, fluoro-, sodium salt .....                   | 10 (4.54)                                         |
| Acetic acid, lead(2+) salt .....                          | 10 (4.54)                                         |
| Acetic acid, thallium(1+) salt .....                      | 100 (45.4)                                        |
| Acetic acid, (2,4,5-trichlorophenoxy)- .....              | 1000 (454)                                        |
| Acetic anhydride .....                                    | 5000 (2270)                                       |
| Acetone .....                                             | 5000 (2270)                                       |
| Acetone cyanohydrin .....                                 | 10 (4.54)                                         |
| Acetonitrile .....                                        | 5000 (2270)                                       |
| Acetophenone .....                                        | 5000 (2270)                                       |
| 2-Acetylaminofluorene .....                               | 1 (0.454)                                         |
| Acetyl bromide .....                                      | 5000 (2270)                                       |
| Acetyl chloride .....                                     | 5000 (2270)                                       |
| 1-Acetyl-2-thiourea .....                                 | 1000 (454)                                        |
| Acrolein .....                                            | 1 (0.454)                                         |
| Acrylamide .....                                          | 5000 (2270)                                       |
| Acrylic acid .....                                        | 5000 (2270)                                       |
| Acrylonitrile .....                                       | 100 (45.4)                                        |
| Adipic acid .....                                         | 5000 (2270)                                       |
| Aldicarb .....                                            | 1 (0.454)                                         |
| Aldicarb sulfone .....                                    | 100 (45.4)                                        |
| Aldrin .....                                              | 1 (0.454)                                         |
| Allyl alcohol .....                                       | 100 (45.4)                                        |
| Allyl chloride .....                                      | 1000 (454)                                        |
| Aluminum phosphide .....                                  | 100 (45.4)                                        |
| Aluminum sulfate .....                                    | 5000 (2270)                                       |
| 4-Aminobiphenyl .....                                     | 1 (0.454)                                         |
| 5-(Aminomethyl)-3-isoxazolol .....                        | 1000 (454)                                        |
| 4-Aminopyridine .....                                     | 1000 (454)                                        |
| Amitrole .....                                            | 10 (4.54)                                         |
| Ammonia .....                                             | 100 (45.4)                                        |
| Ammonium acetate .....                                    | 5000 (2270)                                       |
| Ammonium benzoate .....                                   | 5000 (2270)                                       |
| Ammonium bicarbonate .....                                | 5000 (2270)                                       |
| Ammonium bichromate .....                                 | 10 (4.54)                                         |
| Ammonium bifluoride .....                                 | 100 (45.4)                                        |
| Ammonium bisulfite .....                                  | 5000 (2270)                                       |
| Ammonium carbamate .....                                  | 5000 (2270)                                       |
| Ammonium carbonate .....                                  | 5000 (2270)                                       |
| Ammonium chloride .....                                   | 5000 (2270)                                       |
| Ammonium chromate .....                                   | 10 (4.54)                                         |
| Ammonium citrate, dibasic .....                           | 5000 (2270)                                       |
| Ammonium dichromate® .....                                | 10 (4.54)                                         |
| Ammonium fluoroborate .....                               | 5000 (2270)                                       |
| Ammonium fluoride .....                                   | 100 (45.4)                                        |
| Ammonium hydroxide .....                                  | 1000 (454)                                        |
| Ammonium oxalate .....                                    | 5000 (2270)                                       |
| Ammonium picrate .....                                    | 10 (4.54)                                         |
| Ammonium silicofluoride .....                             | 1000 (454)                                        |
| Ammonium sulfamate .....                                  | 5000 (2270)                                       |
| Ammonium sulfide .....                                    | 100 (45.4)                                        |
| Ammonium sulfite .....                                    | 5000 (2270)                                       |
| Ammonium tartrate .....                                   | 5000 (2270)                                       |
| Ammonium thiocyanate .....                                | 5000 (2270)                                       |
| Ammonium vanadate .....                                   | 1000 (454)                                        |
| Amyl acetate .....                                        | 5000 (2270)                                       |
| iso-Amyl acetate.                                         |                                                   |
| sec-Amyl acetate.                                         |                                                   |
| tert-Amyl acetate.                                        |                                                   |
| Aniline .....                                             | 5000 (2270)                                       |
| o-Anisidine .....                                         | 100 (45.4)                                        |
| Anthracene .....                                          | 5000 (2270)                                       |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                                                                                                  | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Antimony cent: .....                                                                                                                                                                 | 5000 (2270)                                       |
| Antimony pentachloride .....                                                                                                                                                         | 1000 (454)                                        |
| Antimony potassium tartrate .....                                                                                                                                                    | 100 (45.4)                                        |
| Antimony tribromide .....                                                                                                                                                            | 1000 (454)                                        |
| Antimony trichloride .....                                                                                                                                                           | 1000 (454)                                        |
| Antimony trifluoride .....                                                                                                                                                           | 1000 (454)                                        |
| Antimony trioxide .....                                                                                                                                                              | 1000 (454)                                        |
| Argentate(1-), bis(cyano-C)-, potassium .....                                                                                                                                        | 1 (0.454)                                         |
| Aroclor 1016 .....                                                                                                                                                                   | 1 (0.454)                                         |
| Aroclor 1221 .....                                                                                                                                                                   | 1 (0.454)                                         |
| Aroclor 1232 .....                                                                                                                                                                   | 1 (0.454)                                         |
| Aroclor 1242 .....                                                                                                                                                                   | 1 (0.454)                                         |
| Aroclor 1248 .....                                                                                                                                                                   | 1 (0.454)                                         |
| Aroclor 1254 .....                                                                                                                                                                   | 1 (0.454)                                         |
| Aroclor 1260 .....                                                                                                                                                                   | 1 (0.454)                                         |
| Aroclors .....                                                                                                                                                                       | 1 (0.454)                                         |
| Arsenic cent: .....                                                                                                                                                                  | 1 (0.454)                                         |
| Arsenic acid H <sub>3</sub> AsO <sub>4</sub> .....                                                                                                                                   | 1 (0.454)                                         |
| Arsenic disulfide .....                                                                                                                                                              | 1 (0.454)                                         |
| Arsenic oxide As <sub>2</sub> O <sub>3</sub> .....                                                                                                                                   | 1 (0.454)                                         |
| Arsenic oxide As <sub>2</sub> O <sub>5</sub> .....                                                                                                                                   | 1 (0.454)                                         |
| Arsenic pentoxide .....                                                                                                                                                              | 1 (0.454)                                         |
| Arsenic trichloride .....                                                                                                                                                            | 1 (0.454)                                         |
| Arsenic trioxide .....                                                                                                                                                               | 1 (0.454)                                         |
| Arsenic trisulfide .....                                                                                                                                                             | 1 (0.454)                                         |
| Arsine, diethyl- .....                                                                                                                                                               | 1 (0.454)                                         |
| Arsinic acid, dimethyl- .....                                                                                                                                                        | 1 (0.454)                                         |
| Arsonous dichloride, phenyl- .....                                                                                                                                                   | 1 (0.454)                                         |
| Asbestos cent, cent: .....                                                                                                                                                           | 1 (0.454)                                         |
| Auramine .....                                                                                                                                                                       | 100 (45.4)                                        |
| Azaserine .....                                                                                                                                                                      | 1 (0.454)                                         |
| Aziridine .....                                                                                                                                                                      | 1 (0.454)                                         |
| Aziridine, 2-methyl- .....                                                                                                                                                           | 1 (0.454)                                         |
| Azirino[2,3':3,4]pyrrolo[1,2-a]indole-4,7-dione, 6-amino-8-[[[(aminocarbonyl)oxy]methyl]-1,1a,2,8,8a,8b-hexahydro-8a-methoxy-5-methyl-, [1aS-(1aalpha,8beta,8aalpha, 8balph)]- ..... | 10 (4.54)                                         |
| Barban .....                                                                                                                                                                         | 10 (4.54)                                         |
| Barium cyanide .....                                                                                                                                                                 | 10 (4.54)                                         |
| Bendiocarb .....                                                                                                                                                                     | 100 (45.4)                                        |
| Bendiocarb phenol .....                                                                                                                                                              | 1000 (454)                                        |
| Benomyl .....                                                                                                                                                                        | 10 (4.54)                                         |
| Benz[j]aceanthrylene, 1,2-dihydro-3-methyl- .....                                                                                                                                    | 10 (4.54)                                         |
| Benz[c]acridine .....                                                                                                                                                                | 100 (45.4)                                        |
| Benzal chloride .....                                                                                                                                                                | 5000 (2270)                                       |
| Benzamide, 3,5-dichloro-N-(1,1-dimethyl-2-propynyl)- .....                                                                                                                           | 5000 (2270)                                       |
| Benz[a]anthracene .....                                                                                                                                                              | 10 (4.54)                                         |
| 1,2-Benzanthracene .....                                                                                                                                                             | 10 (4.54)                                         |
| Benz[a]anthracene, 7,12-dimethyl- .....                                                                                                                                              | 1 (0.454)                                         |
| Benzenamine .....                                                                                                                                                                    | 5000 (2270)                                       |
| Benzenamine, 4,4'-carbonimidoylbis (N,N dimethyl- .....                                                                                                                              | 100 (45.4)                                        |
| Benzenamine, 4-chloro- .....                                                                                                                                                         | 1000 (454)                                        |
| Benzenamine, 4-chloro-2-methyl-, hydrochloride .....                                                                                                                                 | 100 (45.4)                                        |
| Benzenamine, N,N-dimethyl-4-(phenylazo)- .....                                                                                                                                       | 10 (4.54)                                         |
| Benzenamine, 2-methyl- .....                                                                                                                                                         | 100 (45.4)                                        |
| Benzenamine, 4-methyl- .....                                                                                                                                                         | 100 (45.4)                                        |
| Benzenamine, 4,4'-methylenebis[2-chloro- .....                                                                                                                                       | 10 (4.54)                                         |
| Benzenamine, 2-methyl-, hydrochloride .....                                                                                                                                          | 100 (45.4)                                        |
| Benzenamine, 2-methyl-5-nitro- .....                                                                                                                                                 | 100 (45.4)                                        |
| Benzenamine, 4-nitro- .....                                                                                                                                                          | 5000 (2270)                                       |
| Benzene .....                                                                                                                                                                        | 10 (4.54)                                         |
| Benzenecetic acid, 4-chloro- $\alpha$ -(4-chlorophenyl)- $\alpha$ -hydroxy-, ethyl ester .....                                                                                       | 10 (4.54)                                         |
| Benzene, 1-bromo-4-phenoxy- .....                                                                                                                                                    | 100 (45.4)                                        |
| Benzenebutanoic acid, 4-[bis(2-chloroethyl)amino]- .....                                                                                                                             | 10 (4.54)                                         |
| Benzene, chloro- .....                                                                                                                                                               | 100 (45.4)                                        |
| Benzene, (chloromethyl)- .....                                                                                                                                                       | 100 (45.4)                                        |
| Benzenediamine, ar-methyl- .....                                                                                                                                                     | 10 (4.54)                                         |
| 1,2-Benzenedicarboxylic acid, bis(2-ethylhexyl) ester .....                                                                                                                          | 100 (45.4)                                        |
| 1,2-Benzenedicarboxylic acid, dibutyl ester .....                                                                                                                                    | 10 (4.54)                                         |
| 1,2-Benzenedicarboxylic acid, diethyl ester .....                                                                                                                                    | 1000 (454)                                        |
| 1,2-Benzenedicarboxylic acid, dimethyl ester .....                                                                                                                                   | 5000 (2270)                                       |
| 1,2-Benzenedicarboxylic acid, dioctyl ester .....                                                                                                                                    | 5000 (2270)                                       |



TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                                                                    | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|--------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Benzene, 1,2-dichloro- .....                                                                                                                           | 100 (45.4)                                        |
| Benzene, 1,3-dichloro- .....                                                                                                                           | 100 (45.4)                                        |
| Benzene, 1,4-dichloro- .....                                                                                                                           | 100 (45.4)                                        |
| Benzene, 1,1'-(2,2-dichloroethylidene) bis[4-chloro- .....                                                                                             | 1 (0.454)                                         |
| Benzene, (dichloromethyl)- .....                                                                                                                       | 5000 (2270)                                       |
| Benzene, 1,3-diisocyanatomethyl- .....                                                                                                                 | 100 (45.4)                                        |
| Benzene, dimethyl- .....                                                                                                                               | 100 (45.4)                                        |
| 1,3-Benzenediol .....                                                                                                                                  | 5000 (2270)                                       |
| 1,2-Benzenediol,4-[1-hydroxy-2-(methylamino) ethyl]- .....                                                                                             | 1000 (454)                                        |
| Benzeneethanamine, alpha,alpha-dimethyl- .....                                                                                                         | 5000 (2270)                                       |
| Benzene, hexachloro- .....                                                                                                                             | 10 (4.54)                                         |
| Benzene, hexahydro- .....                                                                                                                              | 1000 (454)                                        |
| Benzene, methyl- .....                                                                                                                                 | 1000 (454)                                        |
| Benzene, 1-methyl-2,4-dinitro- .....                                                                                                                   | 10 (4.54)                                         |
| Benzene, 2-methyl-1,3-dinitro- .....                                                                                                                   | 100 (45.4)                                        |
| Benzene, (1-methylethyl)- .....                                                                                                                        | 5000 (2270)                                       |
| Benzene, nitro- .....                                                                                                                                  | 1000 (454)                                        |
| Benzene, pentachloro- .....                                                                                                                            | 10 (4.54)                                         |
| Benzene, pentachloronitro- .....                                                                                                                       | 100 (45.4)                                        |
| Benzenesulfonic acid chloride .....                                                                                                                    | 100 (45.4)                                        |
| Benzenesulfonyl chloride .....                                                                                                                         | 100 (45.4)                                        |
| Benzene,1,2,4,5-tetrachloro- .....                                                                                                                     | 5000 (2270)                                       |
| Benzenethiol .....                                                                                                                                     | 100 (45.4)                                        |
| Benzene,1,1'-(2,2,2-trichloroethylidene) bis[4-chloro- .....                                                                                           | 1 (0.454)                                         |
| Benzene,1,1'-(2,2,2-trichloroethylidene) bis[4-methoxy- .....                                                                                          | 1 (0.454)                                         |
| Benzene, (trichloromethyl)- .....                                                                                                                      | 10 (4.54)                                         |
| Benzene, 1,3,5-trinitro- .....                                                                                                                         | 10 (4.54)                                         |
| Benzidine .....                                                                                                                                        | 1 (0.454)                                         |
| 1,2-Benzisothiazol-3(2H)-one, 1,1-dioxide, & salts .....                                                                                               | 100 (45.4)                                        |
| Benzo[a]anthracene .....                                                                                                                               | 10 (4.54)                                         |
| 1,3-Benzodioxole, 5-(1-propenyl)-1 .....                                                                                                               | 100 (45.4)                                        |
| 1,3-Benzodioxole, 5-(2-propenyl)- .....                                                                                                                | 100 (45.4)                                        |
| 1,3-Benzodioxole, 5-propyl- .....                                                                                                                      | 10 (4.54)                                         |
| 1,3-Benzodioxol-4-ol, 2,2-dimethyl- .....                                                                                                              | 1000 (454)                                        |
| 1,3-Benzodioxol-4-ol, 2,2-dimethyl-, methyl carbamate .....                                                                                            | 100 (45.4)                                        |
| Benzo[b]fluoranthene .....                                                                                                                             | 1 (0.454)                                         |
| Benzo[k]fluoranthene .....                                                                                                                             | 5000 (2270)                                       |
| 7-Benzofuranol, 2,3-dihydro-2,2-dimethyl- .....                                                                                                        | 10 (4.54)                                         |
| 7-Benzofuranol, 2,3-dihydro-2,2-dimethyl-, methylcarbamate .....                                                                                       | 10 (4.54)                                         |
| Benzoic acid .....                                                                                                                                     | 5000 (2270)                                       |
| Benzoic acid, 2-hydroxy-, compd. with (3aS-cis)-1,2,3,3a,8,8a-hexahydro-1,3a,8-trimethylpyrrolo [2,3-b]indol-5-yl<br>methylcarbamate ester (1:1) ..... | 100 (45.4)                                        |
| Benzonitrile .....                                                                                                                                     | 5000 (2270)                                       |
| Benzo[rs]pentaphene .....                                                                                                                              | 10 (4.54)                                         |
| Benzo[ghi]perylene .....                                                                                                                               | 5000 (2270)                                       |
| 2H-1-Benzopyran-2-one, 4-hydroxy-3-(3-oxo-1-phenylbutyl)-, & salts .....                                                                               | 100 (45.4)                                        |
| Benzo[a]pyrene .....                                                                                                                                   | 1 (0.454)                                         |
| 3,4-Benzopyrene .....                                                                                                                                  | 1 (0.454)                                         |
| p-Benzoquinone .....                                                                                                                                   | 10 (4.54)                                         |
| Benzotrichloride .....                                                                                                                                 | 10 (4.54)                                         |
| Benzoyl chloride .....                                                                                                                                 | 1000 (454)                                        |
| Benzyl chloride .....                                                                                                                                  | 100 (45.4)                                        |
| Beryllium <sup>cent</sup> ; .....                                                                                                                      | 10 (4.54)                                         |
| Beryllium chloride .....                                                                                                                               | 1 (0.454)                                         |
| Beryllium fluoride .....                                                                                                                               | 1 (0.454)                                         |
| Beryllium nitrate .....                                                                                                                                | 1 (0.454)                                         |
| Beryllium powder <sup>cent</sup> ; .....                                                                                                               | 10 (4.54)                                         |
| alpha-BHC .....                                                                                                                                        | 10 (4.54)                                         |
| beta-BHC .....                                                                                                                                         | 1 (0.454)                                         |
| delta-BHC .....                                                                                                                                        | 1 (0.454)                                         |
| gamma-BHC .....                                                                                                                                        | 1 (0.454)                                         |
| 2,2'-Bioxirane .....                                                                                                                                   | 10 (4.54)                                         |
| Biphenyl .....                                                                                                                                         | 100 (45.4)                                        |
| [1,1'-Biphenyl]-4,4'-diamine .....                                                                                                                     | 1 (0.454)                                         |
| [1,1'-Biphenyl]-4,4'-diamine,3,3'-dichloro- .....                                                                                                      | 1 (0.454)                                         |
| [1,1'-Biphenyl]-4,4'-diamine,3,3'-dimethoxy- .....                                                                                                     | 100 (45.4)                                        |
| [1,1'-Biphenyl]-4,4'-diamine,3,3'-dimethyl- .....                                                                                                      | 10 (4.54)                                         |
| Bis(2-chloroethoxy) methane .....                                                                                                                      | 1000 (454)                                        |
| Bis(2-chloroethyl) ether .....                                                                                                                         | 10 (4.54)                                         |
| Bis(chloromethyl) ether .....                                                                                                                          | 10 (4.54)                                         |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                                                                                                       | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Bis(2-ethylhexyl) phthalate .....                                                                                                                                                         | 100 (45.4)                                        |
| Bromoacetone .....                                                                                                                                                                        | 1000 (454)                                        |
| Bromoform .....                                                                                                                                                                           | 100 (45.4)                                        |
| Bromomethane .....                                                                                                                                                                        | 1000 (454)                                        |
| 4-Bromophenyl phenyl ether .....                                                                                                                                                          | 100 (45.4)                                        |
| Brucine .....                                                                                                                                                                             | 100 (45.4)                                        |
| 1,3-Butadiene .....                                                                                                                                                                       | 10 (4.54)                                         |
| 1,3-Butadiene, 1,1,2,3,4,4-hexachloro- .....                                                                                                                                              | 1 (0.454)                                         |
| 1-Butanamine, N-butyl-N-nitroso- .....                                                                                                                                                    | 10 (4.54)                                         |
| 1-Butanol .....                                                                                                                                                                           | 5000 (2270)                                       |
| 2-Butanone .....                                                                                                                                                                          | 5000 (2270)                                       |
| 2-Butanone, 3,3-dimethyl-1(methylthio)-, O [(methylamino) carbonyl] oxime .....                                                                                                           | 100 (45.4)                                        |
| 2-Butanone peroxide .....                                                                                                                                                                 | 10 (4.54)                                         |
| 2-Butenal .....                                                                                                                                                                           | 100 (45.4)                                        |
| 2-Butene, 1,4-dichloro- .....                                                                                                                                                             | 1 (0.454)                                         |
| 2-Butenoic acid, 2-methyl-, 7-[[[2,3-dihydroxy-2-(1-methoxyethyl)-3-methyl-1-oxobutoxy] methyl]-2,3,5,7a-tetrahydro-1H-pyrrolizin-1-yl ester, [1S-[1alpha(Z), 7(2S*,3R*),7aalpha]-] ..... | 10 (4.54)                                         |
| Butyl acetate .....                                                                                                                                                                       | 5000 (2270)                                       |
| iso-Butyl acetate.                                                                                                                                                                        |                                                   |
| sec-Butyl acetate.                                                                                                                                                                        |                                                   |
| tert-Butyl acetate.                                                                                                                                                                       |                                                   |
| n-Butyl alcohol .....                                                                                                                                                                     | 5000 (2270)                                       |
| Butylamine .....                                                                                                                                                                          | 1000 (454)                                        |
| iso-Butylamine.                                                                                                                                                                           |                                                   |
| sec-Butylamine.                                                                                                                                                                           |                                                   |
| tert-Butylamine.                                                                                                                                                                          |                                                   |
| Butyl benzyl phthalate .....                                                                                                                                                              | 100 (45.4)                                        |
| n-Butyl phthalate .....                                                                                                                                                                   | 10 (4.54)                                         |
| Butyric acid .....                                                                                                                                                                        | 5000 (2270)                                       |
| iso-Butyric acid.                                                                                                                                                                         |                                                   |
| Cacodylic acid .....                                                                                                                                                                      | 1 (0.454)                                         |
| Cadmium cent. ....                                                                                                                                                                        | 10 (4.54)                                         |
| Cadmium acetate .....                                                                                                                                                                     | 10 (4.54)                                         |
| Cadmium bromide .....                                                                                                                                                                     | 10 (4.54)                                         |
| Cadmium chloride .....                                                                                                                                                                    | 10 (4.54)                                         |
| Calcium arsenate .....                                                                                                                                                                    | 1 (0.454)                                         |
| Calcium arsenite .....                                                                                                                                                                    | 1 (0.454)                                         |
| Calcium carbide .....                                                                                                                                                                     | 10 (4.54)                                         |
| Calcium chromate .....                                                                                                                                                                    | 10 (4.54)                                         |
| Calcium cyanamide .....                                                                                                                                                                   | 1000 (454)                                        |
| Calcium cyanide Ca(CN) <sub>2</sub> .....                                                                                                                                                 | 10 (4.54)                                         |
| Calcium dodecylbenzenesulfonate .....                                                                                                                                                     | 1000 (454)                                        |
| Calcium hypochlorite .....                                                                                                                                                                | 10 (4.54)                                         |
| Captan .....                                                                                                                                                                              | 10 (4.54)                                         |
| Carbamic acid, 1H-benzimidazol-2-yl, methyl ester .....                                                                                                                                   | 10 (4.54)                                         |
| Carbamic acid, [1-[(butylamino)carbonyl]-1H-benzimidazol-2-yl]-, methyl ester .....                                                                                                       | 10 (4.54)                                         |
| Carbamic acid, (3-chlorophenyl)-, 4-chloro-2-butenyl ester .....                                                                                                                          | 10 (4.54)                                         |
| Carbamic acid, [(dibutylamino)-thio]methyl-, 2,3-dihydro-2,2-dimethyl-7-benzofuranyl ester .....                                                                                          | 1000 (454)                                        |
| Carbamic acid, dimethyl-, 1-[(dimethyl-amino)carbonyl]-5-methyl-1H-pyrazol-3-yl ester .....                                                                                               | 1 (0.454)                                         |
| Carbamic acid, dimethyl-, 3-methyl-1-(1-methylethyl)-1H-pyrazol-5-yl ester .....                                                                                                          | 100 (45.4)                                        |
| Carbamic acid, ethyl ester .....                                                                                                                                                          | 100 (45.4)                                        |
| Carbamic acid, methyl-, 3-methylphenyl ester .....                                                                                                                                        | 1000 (454)                                        |
| Carbamic acid, methylnitroso-, ethyl ester .....                                                                                                                                          | 1 (0.454)                                         |
| Carbamic acid, [1,2-phenylenebis(iminocarbonothioyl)] bis-, dimethyl ester .....                                                                                                          | 10 (4.54)                                         |
| Carbamic acid, phenyl-, 1-methylethyl ester .....                                                                                                                                         | 1000 (454)                                        |
| Carbamic chloride, dimethyl- .....                                                                                                                                                        | 1 (0.454)                                         |
| Carbamodithioic acid, 1,2-ethanediylbis-, salts & esters .....                                                                                                                            | 5000 (2270)                                       |
| Carbamothioic acid, bis(1-methylethyl)-, S-(2,3-dichloro-2-propenyl) ester .....                                                                                                          | 100 (45.4)                                        |
| Carbamothioic acid, bis(1-methylethyl)-, S-(2,3,3-trichloro-2-propenyl) ester .....                                                                                                       | 100 (45.4)                                        |
| Carbamothioic acid, dipropyl-, S-(phenylmethyl) ester .....                                                                                                                               | 5000 (2270)                                       |
| Carbaryl .....                                                                                                                                                                            | 100 (45.4)                                        |
| Carbendazim .....                                                                                                                                                                         | 10 (4.54)                                         |
| Carbofuran .....                                                                                                                                                                          | 10 (4.54)                                         |
| Carbofuran phenol .....                                                                                                                                                                   | 10 (4.54)                                         |
| Carbon disulfide .....                                                                                                                                                                    | 100 (45.4)                                        |
| Carbonic acid, dithallium(1+) salt .....                                                                                                                                                  | 100 (45.4)                                        |
| Carbonic dichloride .....                                                                                                                                                                 | 10 (4.54)                                         |
| Carbonic difluoride .....                                                                                                                                                                 | 1000 (454)                                        |
| Carbonochloridic acid, methyl ester .....                                                                                                                                                 | 1000 (454)                                        |
| Carbon oxyfluoride .....                                                                                                                                                                  | 1000 (454)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                               | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|-------------------------------------------------------------------|---------------------------------------------------|
| Carbon tetrachloride .....                                        | 10 (4.54)                                         |
| Carbonyl sulfide .....                                            | 100 (45.4)                                        |
| Carbosulfan .....                                                 | 1000 (454)                                        |
| Catechol .....                                                    | 100 (45.4)                                        |
| Chloral .....                                                     | 5000 (2270)                                       |
| Chloramben .....                                                  | 100 (45.4)                                        |
| Chlorambucil .....                                                | 10 (4.54)                                         |
| Chlordane .....                                                   | 1 (0.454)                                         |
| Chlordane, alpha & gamma isomers .....                            | 1 (0.454)                                         |
| CHLORDANE (TECHNICAL MIXTURE AND METABOLITES) .....               | 1 (0.454)                                         |
| Chlorinated camphene .....                                        | 1 (0.454)                                         |
| Chlorine .....                                                    | 10 (4.54)                                         |
| Chloromaphazine .....                                             | 100 (45.4)                                        |
| Chloroacetaldehyde .....                                          | 1000 (454)                                        |
| Chloroacetic acid .....                                           | 100 (45.4)                                        |
| 2-Chloroacetophenone .....                                        | 100 (45.4)                                        |
| p-Chloroaniline .....                                             | 1000 (454)                                        |
| Chlorobenzene .....                                               | 100 (45.4)                                        |
| Chlorobenzilate .....                                             | 10 (4.54)                                         |
| p-Chloro-m-cresol .....                                           | 5000 (2270)                                       |
| Chlorodibromomethane .....                                        | 100 (45.4)                                        |
| 1-Chloro-2,3-epoxypropane .....                                   | 100 (45.4)                                        |
| Chloroethane .....                                                | 100 (45.4)                                        |
| 2-Chloroethyl vinyl ether .....                                   | 1000 (454)                                        |
| Chloroform .....                                                  | 10 (4.54)                                         |
| Chloromethane .....                                               | 100 (45.4)                                        |
| Chloromethyl methyl ether .....                                   | 10 (4.54)                                         |
| beta-Chloronaphthalene .....                                      | 5000 (2270)                                       |
| 2-Chloronaphthalene .....                                         | 5000 (2270)                                       |
| 2-Chlorophenol .....                                              | 100 (45.4)                                        |
| o-Chlorophenol .....                                              | 100 (45.4)                                        |
| 4-Chlorophenyl phenyl ether .....                                 | 5000 (2270)                                       |
| 1-(o-Chlorophenyl)thiourea .....                                  | 100 (45.4)                                        |
| Chloroprene .....                                                 | 100 (45.4)                                        |
| 3-Chloropropionitrile .....                                       | 1000 (454)                                        |
| Chlorosulfonic acid .....                                         | 1000 (454)                                        |
| 4-Chloro-o-toluidine, hydrochloride .....                         | 100 (45.4)                                        |
| Chlorpyrifos .....                                                | 1 (0.454)                                         |
| Chromic acetate .....                                             | 1000 (454)                                        |
| Chromic acid .....                                                | 10 (4.54)                                         |
| Chromic acid H <sub>2</sub> CrO <sub>4</sub> , calcium salt ..... | 10 (4.54)                                         |
| Chromic sulfate .....                                             | 1000 (454)                                        |
| Chromium cent. ....                                               | 5000 (2270)                                       |
| Chromous chloride .....                                           | 1000 (454)                                        |
| Chrysene .....                                                    | 100 (45.4)                                        |
| Cobaltous bromide .....                                           | 1000 (454)                                        |
| Cobaltous formate .....                                           | 1000 (454)                                        |
| Cobaltous sulfamate .....                                         | 1000 (454)                                        |
| Coke Oven Emissions .....                                         | 1 (0.454)                                         |
| Copper cent. ....                                                 | 5000 (2270)                                       |
| Copper chloride ® .....                                           | 10 (4.54)                                         |
| Copper cyanide Cu(CN) .....                                       | 10 (4.54)                                         |
| Coumaphos .....                                                   | 10 (4.54)                                         |
| Creosote .....                                                    | 1 (0.454)                                         |
| Cresol (cresylic acid) .....                                      | 100 (45.4)                                        |
| m-Cresol .....                                                    | 100 (45.4)                                        |
| o-Cresol .....                                                    | 100 (45.4)                                        |
| p-Cresol .....                                                    | 100 (45.4)                                        |
| Cresols (isomers and mixture) .....                               | 100 (45.4)                                        |
| Cresylic acid (isomers and mixture) .....                         | 100 (45.4)                                        |
| Crotonaldehyde .....                                              | 100 (45.4)                                        |
| Cumene .....                                                      | 5000 (2270)                                       |
| m-Cumenyl methylcarbamate .....                                   | 10 (4.54)                                         |
| Cupric acetate .....                                              | 100 (45.4)                                        |
| Cupric acetoarsenite .....                                        | 1 (0.454)                                         |
| Cupric chloride .....                                             | 10 (4.54)                                         |
| Cupric nitrate .....                                              | 100 (45.4)                                        |
| Cupric oxalate .....                                              | 100 (45.4)                                        |
| Cupric sulfate .....                                              | 10 (4.54)                                         |
| Cupric sulfate, ammoniated .....                                  | 100 (45.4)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                                 | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|---------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Cupric tartrate                                                                                                     | 100 (45.4)                                        |
| Cyanides (soluble salts and complexes) not otherwise specified                                                      | 10 (4.54)                                         |
| Cyanogen                                                                                                            | 100 (45.4)                                        |
| Cyanogen bromide (CN)Br                                                                                             | 1000 (454)                                        |
| Cyanogen chloride (CN)Cl                                                                                            | 10 (4.54)                                         |
| 2,5-Cyclohexadiene-1,4-dione                                                                                        | 10 (4.54)                                         |
| Cyclohexane                                                                                                         | 1000 (454)                                        |
| Cyclohexane, 1,2,3,4,5,6-hexachloro-, (1 $\alpha$ , 2 $\alpha$ , 3 $\beta$ -, 4 $\alpha$ , 5 $\alpha$ , 6 $\beta$ ) | 1 (0.454)                                         |
| Cyclohexanone                                                                                                       | 5000 (2270)                                       |
| 2-Cyclohexyl-4,6-dinitrophenol                                                                                      | 100 (45.4)                                        |
| 1,3-Cyclopentadiene, 1,2,3,4,5,5-hexachloro-                                                                        | 10 (4.54)                                         |
| Cyclophosphamide                                                                                                    | 10 (4.54)                                         |
| 2,4-D Acid                                                                                                          | 100 (45.4)                                        |
| 2,4-D Ester                                                                                                         | 100 (45.4)                                        |
| 2,4-D, salts and esters                                                                                             | 100 (45.4)                                        |
| Daunomycin                                                                                                          | 10 (4.54)                                         |
| DDD                                                                                                                 | 1 (0.454)                                         |
| 4,4'-DDD                                                                                                            | 1 (0.454)                                         |
| DDE (72-55-9) #                                                                                                     | 1 (0.454)                                         |
| DDE (3547-04-4) #                                                                                                   | 5000 (2270)                                       |
| 4,4'-DDE                                                                                                            | 1 (0.454)                                         |
| DDT                                                                                                                 | 1 (0.454)                                         |
| 4,4'-DDT                                                                                                            | 1 (0.454)                                         |
| DEHP                                                                                                                | 100 (45.4)                                        |
| Diallate                                                                                                            | 100 (45.4)                                        |
| Diazinon                                                                                                            | 1 (0.454)                                         |
| Diazomethane                                                                                                        | 100 (45.4)                                        |
| Dibenz[a,h]anthracene                                                                                               | 1 (0.454)                                         |
| 1,2,5,6-Dibenzanthracene                                                                                            | 1 (0.454)                                         |
| Dibenzo[a,h]anthracene                                                                                              | 1 (0.454)                                         |
| Dibenzofuran                                                                                                        | 100 (45.4)                                        |
| Dibenzo[a,i]pyrene                                                                                                  | 10 (4.54)                                         |
| 1,2-Dibromo-3-chloropropane                                                                                         | 1 (0.454)                                         |
| Dibromoethane                                                                                                       | 1 (0.454)                                         |
| Dibutyl phthalate                                                                                                   | 10 (4.54)                                         |
| Di-n-butyl phthalate                                                                                                | 10 (4.54)                                         |
| Dicamba                                                                                                             | 1000 (454)                                        |
| Dichlobenil                                                                                                         | 100 (45.4)                                        |
| Dichlone                                                                                                            | 1 (0.454)                                         |
| Dichlorobenzene                                                                                                     | 100 (45.4)                                        |
| 1,2-Dichlorobenzene                                                                                                 | 100 (45.4)                                        |
| 1,3-Dichlorobenzene                                                                                                 | 100 (45.4)                                        |
| 1,4-Dichlorobenzene                                                                                                 | 100 (45.4)                                        |
| m-Dichlorobenzene                                                                                                   | 100 (45.4)                                        |
| o-Dichlorobenzene                                                                                                   | 100 (45.4)                                        |
| p-Dichlorobenzene                                                                                                   | 100 (45.4)                                        |
| 3,3'-Dichlorobenzidine                                                                                              | 1 (0.454)                                         |
| Dichlorobromomethane                                                                                                | 5000 (2270)                                       |
| 1,4-Dichloro-2-butene                                                                                               | 1 (0.454)                                         |
| Dichlorodifluoromethane                                                                                             | 5000 (2270)                                       |
| 1,1-Dichloroethane                                                                                                  | 1000 (454)                                        |
| 1,2-Dichloroethane                                                                                                  | 100 (45.4)                                        |
| 1,1-Dichloroethylene                                                                                                | 100 (45.4)                                        |
| 1,2-Dichloroethylene                                                                                                | 1000 (454)                                        |
| Dichloroethyl ether                                                                                                 | 10 (4.54)                                         |
| Dichloroisopropyl ether                                                                                             | 1000 (454)                                        |
| Dichloromethane                                                                                                     | 1000 (454)                                        |
| Dichloromethoxyethane                                                                                               | 1000 (454)                                        |
| Dichloromethyl ether                                                                                                | 10 (4.54)                                         |
| 2,4-Dichlorophenol                                                                                                  | 100 (45.4)                                        |
| 2,6-Dichlorophenol                                                                                                  | 100 (45.4)                                        |
| Dichlorophenylarsine                                                                                                | 1 (0.454)                                         |
| Dichloropropane                                                                                                     | 1000 (454)                                        |
| 1,1-Dichloropropane.                                                                                                |                                                   |
| 1,3-Dichloropropane.                                                                                                |                                                   |
| 1,2-Dichloropropane                                                                                                 | 1000 (454)                                        |
| Dichloropropane-Dichloropropene (mixture)                                                                           | 100 (45.4)                                        |
| Dichloropropene                                                                                                     | 100 (45.4)                                        |
| 2,3-Dichloropropene.                                                                                                |                                                   |
| 1,3-Dichloropropene                                                                                                 | 100 (45.4)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                                                                                                  | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| 2,2-Dichloropropionic acid .....                                                                                                                                                     | 5000 (2270)                                       |
| Dichlorvos .....                                                                                                                                                                     | 10 (4.54)                                         |
| Dicofol .....                                                                                                                                                                        | 10 (4.54)                                         |
| Dieldrin .....                                                                                                                                                                       | 1 (0.454)                                         |
| 1,2:3,4-Diepoxybutane .....                                                                                                                                                          | 10 (4.54)                                         |
| Diethanolamine .....                                                                                                                                                                 | 100 (45.4)                                        |
| Diethylamine .....                                                                                                                                                                   | 100 (45.4)                                        |
| N,N-Diethylaniline .....                                                                                                                                                             | 1000 (454)                                        |
| Diethylarsine .....                                                                                                                                                                  | 1 (0.454)                                         |
| Diethylene glycol, dicarbamate .....                                                                                                                                                 | 5000 (2270)                                       |
| 1,4-Diethyleneoxide .....                                                                                                                                                            | 100 (45.4)                                        |
| Diethylhexyl phthalate .....                                                                                                                                                         | 100 (45.4)                                        |
| N,N'-Diethylhydrazine .....                                                                                                                                                          | 10 (4.54)                                         |
| O,O-Diethyl S-methyl dithiophosphate .....                                                                                                                                           | 5000 (2270)                                       |
| Diethyl-p-nitrophenyl phosphate .....                                                                                                                                                | 100 (45.4)                                        |
| Diethyl phthalate .....                                                                                                                                                              | 1000 (454)                                        |
| O,O-Diethyl O-pyrazinyl phosphorothioate .....                                                                                                                                       | 100 (45.4)                                        |
| Diethylstilbestrol .....                                                                                                                                                             | 1 (0.454)                                         |
| Diethyl sulfate .....                                                                                                                                                                | 10 (4.54)                                         |
| Dihydrosafrole .....                                                                                                                                                                 | 10 (4.54)                                         |
| Diisopropylfluorophosphate (DFP) .....                                                                                                                                               | 100 (45.4)                                        |
| 1,4:5,8-Dimethanonaphthalene, 1,2,3,4,10,10-hexachloro-1,4,4a,5,8,8a-hexahydro-, (1alpha, 4alpha, 4abeta, 5alpha, 8alpha, 8abeta)- .....                                             | 1 (0.454)                                         |
| 1,4:5,8-Dimethanonaphthalene, 1,2,3,4,10,10-hexachloro-1,4,4a,5,8,8a-hexahydro-, (1alpha, 4alpha, 4abeta, 5beta, 8beta, 8abeta)-1 (0.454) .....                                      |                                                   |
| 2,7:3,6-Dimethanonaphth[2,3-b]oxirene,3,4,5,6,9,9-hexachloro-1a,2,2a,3,6,6a,7,7a-octahydro-, (1aalpha, 2beta, 2aalpha, 3beta, 6beta, 6aalpha, 7beta, 7aalpha)- .....                 | 1 (0.454)                                         |
| 2,7:3,6-Dimethanonaphth[2, 3-b]oxirene,3,4,5,6,9,9-hexachloro-1a,2,2a,3,6,6a,7,7a-octahydro-, (1aalpha, 2beta, 2abeta, 3alpha, 6alpha, 6abeta, 7beta, 7aalpha)-, & metabolites ..... | 1 (0.454)                                         |
| Dimethoate .....                                                                                                                                                                     | 10 (4.54)                                         |
| 3,3'-Dimethoxybenzidine .....                                                                                                                                                        | 100 (45.4)                                        |
| Dimethylamine .....                                                                                                                                                                  | 1000 (454)                                        |
| Dimethyl aminoazobenzene .....                                                                                                                                                       | 10 (4.54)                                         |
| p-Dimethylaminoazobenzene .....                                                                                                                                                      | 10 (4.54)                                         |
| N,N-Dimethylaniline .....                                                                                                                                                            | 100 (45.4)                                        |
| 7,12-Dimethylbenz[a]anthracene .....                                                                                                                                                 | 1 (0.454)                                         |
| 3,3'-Dimethylbenzidine .....                                                                                                                                                         | 10 (4.54)                                         |
| alpha,alpha-Dimethylbenzylhydroperoxide .....                                                                                                                                        | 10 (4.54)                                         |
| Dimethylcarbamoyl chloride .....                                                                                                                                                     | 1 (0.454)                                         |
| Dimethylformamide .....                                                                                                                                                              | 100 (45.4)                                        |
| 1,1-Dimethylhydrazine .....                                                                                                                                                          | 10 (4.54)                                         |
| 1,2-Dimethylhydrazine .....                                                                                                                                                          | 1 (0.454)                                         |
| Dimethylhydrazine, unsymmetrical® .....                                                                                                                                              | 10 (4.54)                                         |
| alpha,alpha-Dimethylphenethylamine .....                                                                                                                                             | 5000 (2270)                                       |
| 2,4-Dimethylphenol .....                                                                                                                                                             | 100 (45.4)                                        |
| Dimethyl phthalate .....                                                                                                                                                             | 5000 (2270)                                       |
| Dimethyl sulfate .....                                                                                                                                                               | 100 (45.4)                                        |
| Dimetilan .....                                                                                                                                                                      | 1 (0.454)                                         |
| Dinitrobenzene (mixed) .....                                                                                                                                                         | 100 (45.4)                                        |
| m-Dinitrobenzene.                                                                                                                                                                    |                                                   |
| o-Dinitrobenzene.                                                                                                                                                                    |                                                   |
| p-Dinitrobenzene.                                                                                                                                                                    |                                                   |
| 4,6-Dinitro-o-cresol, and salts .....                                                                                                                                                | 10 (4.54)                                         |
| Dinitrogen tetroxide® .....                                                                                                                                                          | 10 (4.54)                                         |
| Dinitrophenol .....                                                                                                                                                                  | 10 (4.54)                                         |
| 2,5-Dinitrophenol.                                                                                                                                                                   |                                                   |
| 2,6-Dinitrophenol.                                                                                                                                                                   |                                                   |
| 2,4-Dinitrophenol .....                                                                                                                                                              | 10 (4.54)                                         |
| Dinitrotoluene .....                                                                                                                                                                 | 10 (4.54)                                         |
| 3,4-Dinitrotoluene.                                                                                                                                                                  |                                                   |
| 2,4-Dinitrotoluene .....                                                                                                                                                             | 10 (4.54)                                         |
| 2,6-Dinitrotoluene .....                                                                                                                                                             | 100 (45.4)                                        |
| Dinoseb .....                                                                                                                                                                        | 1000 (454)                                        |
| Di-n-octyl phthalate .....                                                                                                                                                           | 5000 (2270)                                       |
| 1,4-Dioxane .....                                                                                                                                                                    | 100 (45.4)                                        |
| 1,2-Diphenylhydrazine .....                                                                                                                                                          | 10 (4.54)                                         |
| Diphosphoramidate, octamethyl- .....                                                                                                                                                 | 100 (45.4)                                        |
| Diphosphoric acid, tetraethyl ester .....                                                                                                                                            | 10 (4.54)                                         |
| Dipropylamine .....                                                                                                                                                                  | 5000 (2270)                                       |
| Di-n-propylnitrosamine .....                                                                                                                                                         | 10 (4.54)                                         |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                  | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Diquat .....                                                                                         | 1000 (454)                                        |
| Disulfoton .....                                                                                     | 1 (0.454)                                         |
| Dithiobiuret .....                                                                                   | 100 (45.4)                                        |
| 1,3-Dithiolane-2-carboxaldehyde, 2,4-dimethyl-, O-[(methylamino)-carbonyl]oxime .....                | 100 (45.4)                                        |
| Diuron .....                                                                                         | 100 (45.4)                                        |
| Dodecylbenzenesulfonic acid .....                                                                    | 1000 (454)                                        |
| Endosulfan .....                                                                                     | 1 (0.454)                                         |
| alpha-Endosulfan .....                                                                               | 1 (0.454)                                         |
| beta-Endosulfan .....                                                                                | 1 (0.454)                                         |
| Endosulfan sulfate .....                                                                             | 1 (0.454)                                         |
| Endothall .....                                                                                      | 1000 (454)                                        |
| Endrin .....                                                                                         | 1 (0.454)                                         |
| Endrin aldehyde .....                                                                                | 1 (0.454)                                         |
| Endrin, & metabolites .....                                                                          | 1 (0.454)                                         |
| Epichlorohydrin .....                                                                                | 100 (45.4)                                        |
| Epinephrine .....                                                                                    | 1000 (454)                                        |
| 1,2-Epoxybutane .....                                                                                | 100 (45.4)                                        |
| Ethanal .....                                                                                        | 1000 (454)                                        |
| Ethanamine, N,N-diethyl- .....                                                                       | 5000 (2270)                                       |
| Ethanamine, N-ethyl-N-nitroso- .....                                                                 | 1 (0.454)                                         |
| 1,2-Ethanediamine, N,N-dimethyl-N'-2-pyridinyl-N'-(2-thienylmethyl)- .....                           | 5000 (2270)                                       |
| Ethane, 1,2-dibromo- .....                                                                           | 1 (0.454)                                         |
| Ethane, 1,1-dichloro- .....                                                                          | 1000 (454)                                        |
| Ethane, 1,2-dichloro- .....                                                                          | 100 (45.4)                                        |
| Ethanedinitrile .....                                                                                | 100 (45.4)                                        |
| Ethane, hexachloro- .....                                                                            | 100 (45.4)                                        |
| Ethane, 1,1'-[methylenebis(oxy)]bis[2-chloro- .....                                                  | 1000 (454)                                        |
| Ethane, 1,1'-oxybis- .....                                                                           | 100 (45.4)                                        |
| Ethane, 1,1'-oxybis[2-chloro- .....                                                                  | 10 (4.54)                                         |
| Ethane, pentachloro- .....                                                                           | 10 (4.54)                                         |
| Ethane, 1,1,1,2-tetrachloro- .....                                                                   | 100 (45.4)                                        |
| Ethane, 1,1,2,2-tetrachloro- .....                                                                   | 100 (45.4)                                        |
| Ethanethioamide .....                                                                                | 10 (4.54)                                         |
| Ethane, 1,1,1-trichloro- .....                                                                       | 1000 (454)                                        |
| Ethane, 1,1,2-trichloro- .....                                                                       | 100 (45.4)                                        |
| Ethanimidothioic acid, 2-(dimethylamino)-N-hydroxy-2-oxo-, methyl ester .....                        | 5000 (2270)                                       |
| Ethanimidothioic acid, 2-(dimethylamino)-N-[[[(methylamino) carbonyl]oxy]-2-oxo-, methyl ester ..... | 100 (45.4)                                        |
| Ethanimidothioic acid, N-[[[(methylamino) carbonyl]oxy]-, methyl ester .....                         | 100 (45.4)                                        |
| Ethanimidothioic acid, N,N'[thiobis[(methylimino)carbonyloxy]] bis-, dimethyl ester .....            | 100 (45.4)                                        |
| Ethanol, 2-ethoxy- .....                                                                             | 1000 (454)                                        |
| Ethanol, 2,2'-(nitrosoimino)bis- .....                                                               | 1 (0.454)                                         |
| Ethanol, 2,2'-oxybis-, dicarbamate .....                                                             | 5000 (2270)                                       |
| Ethanone, 1-phenyl- .....                                                                            | 5000 (2270)                                       |
| Ethene, chloro- .....                                                                                | 1 (0.454)                                         |
| Ethene, (2-chloroethoxy)- .....                                                                      | 1000 (454)                                        |
| Ethene, 1,1-dichloro- .....                                                                          | 100 (45.4)                                        |
| Ethene, 1,2-dichloro-(E) .....                                                                       | 1000 (454)                                        |
| Ethene, tetrachloro- .....                                                                           | 100 (45.4)                                        |
| Ethene, trichloro- .....                                                                             | 100 (45.4)                                        |
| Ethion .....                                                                                         | 10 (4.54)                                         |
| Ethyl acetate .....                                                                                  | 5000 (2270)                                       |
| Ethyl acrylate .....                                                                                 | 1000 (454)                                        |
| Ethylbenzene .....                                                                                   | 1000 (454)                                        |
| Ethyl carbamate .....                                                                                | 100 (45.4)                                        |
| Ethyl chloride .....                                                                                 | 100 (45.4)                                        |
| Ethyl cyanide .....                                                                                  | 10 (4.54)                                         |
| Ethylenedisithiocarbamic acid, salts & esters .....                                                  | 5000 (2270)                                       |
| Ethylenediamine .....                                                                                | 5000 (2270)                                       |
| Ethylenediamine-tetraacetic acid (EDTA) .....                                                        | 5000 (2270)                                       |
| Ethylene dibromide .....                                                                             | 1 (0.454)                                         |
| Ethylene dichloride .....                                                                            | 100 (45.4)                                        |
| Ethylene glycol .....                                                                                | 5000 (2270)                                       |
| Ethylene glycol monoethyl ether .....                                                                | 1000 (454)                                        |
| Ethylene oxide .....                                                                                 | 10 (4.54)                                         |
| Ethylenethiourea .....                                                                               | 10 (4.54)                                         |
| Ethylenimine .....                                                                                   | 1 (0.454)                                         |
| Ethyl ether .....                                                                                    | 100 (45.4)                                        |
| Ethylidene dichloride .....                                                                          | 1000 (454)                                        |
| Ethyl methacrylate .....                                                                             | 1000 (454)                                        |
| Ethyl methanesulfonate .....                                                                         | 1 (0.454)                                         |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                           | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|---------------------------------------------------------------|---------------------------------------------------|
| Ethyl methyl ketone @                                         | 5000 (2270)                                       |
| Famphur                                                       | 1000 (454)                                        |
| Ferric ammonium citrate                                       | 1000 (454)                                        |
| Ferric ammonium oxalate                                       | 1000 (454)                                        |
| Ferric chloride                                               | 1000 (454)                                        |
| Ferric fluoride                                               | 100 (45.4)                                        |
| Ferric nitrate                                                | 1000 (454)                                        |
| Ferric sulfate                                                | 1000 (454)                                        |
| Ferrous ammonium sulfate                                      | 1000 (454)                                        |
| Ferrous chloride                                              | 100 (45.4)                                        |
| Ferrous sulfate                                               | 1000 (454)                                        |
| Fluoranthene                                                  | 100 (45.4)                                        |
| Fluorene                                                      | 5000 (2270)                                       |
| Fluorine                                                      | 10 (4.54)                                         |
| Fluoroacetamide                                               | 100 (45.4)                                        |
| Fluoroacetic acid, sodium salt                                | 10 (4.54)                                         |
| Formaldehyde                                                  | 100 (45.4)                                        |
| Formetanate hydrochloride                                     | 100 (45.4)                                        |
| Formic acid                                                   | 5000 (2270)                                       |
| Formparanate                                                  | 100 (45.4)                                        |
| Fulminic acid, mercury(2+)salt                                | 10 (4.54)                                         |
| Fumaric acid                                                  | 5000 (2270)                                       |
| Furan                                                         | 100 (45.4)                                        |
| 2-Furancarboxyaldehyde                                        | 5000 (2270)                                       |
| 2,5-Furandione                                                | 5000 (2270)                                       |
| Furan, tetrahydro-                                            | 1000 (454)                                        |
| Furfural                                                      | 5000 (2270)                                       |
| Furfuran                                                      | 100 (45.4)                                        |
| Glucopyranose, 2-deoxy-2-(3-methyl-3-nitrosoureido)-, D-      | 1 (0.454)                                         |
| D-Glucose, 2-deoxy-2-[[[(methylnitrosoamino)-carbonyl]amino]- | 1 (0.454)                                         |
| Glycidylaldehyde                                              | 10 (4.54)                                         |
| Guanidine, N-methyl-N'-nitro-N-nitroso-                       | 10 (4.54)                                         |
| Guthion                                                       | 1 (0.454)                                         |
| Heptachlor                                                    | 1 (0.454)                                         |
| Heptachlor epoxide                                            | 1 (0.454)                                         |
| Hexachlorobenzene                                             | 10 (4.54)                                         |
| Hexachlorobutadiene                                           | 1 (0.454)                                         |
| Hexachlorocyclopentadiene                                     | 10 (4.54)                                         |
| Hexachloroethane                                              | 100 (45.4)                                        |
| Hexachlorophene                                               | 100 (45.4)                                        |
| Hexachloropropene                                             | 1000 (454)                                        |
| Hexaethyl tetraphosphate                                      | 100 (45.4)                                        |
| Hexamethylene-1,6-diisocyanate                                | 100 (45.4)                                        |
| Hexamethylphosphoramide                                       | 1 (0.454)                                         |
| Hexane                                                        | 5000 (2270)                                       |
| Hexone                                                        | 5000 (2270)                                       |
| Hydrazine                                                     | 1 (0.454)                                         |
| Hydrazinecarbothioamide                                       | 100 (45.4)                                        |
| Hydrazine, 1,2-diethyl-                                       | 10 (4.54)                                         |
| Hydrazine, 1,1-dimethyl-                                      | 10 (4.54)                                         |
| Hydrazine, 1,2-dimethyl-                                      | 1 (0.454)                                         |
| Hydrazine, 1,2-diphenyl-                                      | 10 (4.54)                                         |
| Hydrazine, methyl-                                            | 10 (4.54)                                         |
| Hydrochloric acid                                             | 5000 (2270)                                       |
| Hydrocyanic acid                                              | 10 (4.54)                                         |
| Hydrofluoric acid                                             | 100 (45.4)                                        |
| Hydrogen chloride                                             | 5000 (2270)                                       |
| Hydrogen cyanide                                              | 10 (4.54)                                         |
| Hydrogen fluoride                                             | 100 (45.4)                                        |
| Hydrogen phosphide                                            | 100 (45.4)                                        |
| Hydrogen sulfide H2S                                          | 100 (45.4)                                        |
| Hydroperoxide, 1-methyl-1-phenylethyl-                        | 10 (4.54)                                         |
| Hydroquinone                                                  | 100 (45.4)                                        |
| 2-Imidazolidinethione                                         | 10 (4.54)                                         |
| Indeno(1,2,3-cd)pyrene                                        | 100 (45.4)                                        |
| Iodomethane                                                   | 100 (45.4)                                        |
| 1,3-Isobenzofurandione                                        | 5000 (2270)                                       |
| Isobutyl alcohol                                              | 5000 (2270)                                       |
| Isodrin                                                       | 1 (0.454)                                         |
| Isolan                                                        | 100 (45.4)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                  | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Isophorone .....                                                                                     | 5000 (2270)                                       |
| Isoprene .....                                                                                       | 100 (45.4)                                        |
| Isopropanolamine dodecylbenzenesulfonate .....                                                       | 1000 (454)                                        |
| 3-Isopropylphenyl N-methylcarbamate .....                                                            | 10 (4.54)                                         |
| Isosafrole .....                                                                                     | 100 (45.4)                                        |
| 3(2H)-Isoxazalone, 5-(aminomethyl)- .....                                                            | 1000 (454)                                        |
| Kepone .....                                                                                         | 1 (0.454)                                         |
| Lasiocarpine .....                                                                                   | 10 (4.54)                                         |
| Lead <sup>cent</sup> .....                                                                           | 10 (4.54)                                         |
| Lead acetate .....                                                                                   | 10 (4.54)                                         |
| Lead arsenate .....                                                                                  | 1 (0.454)                                         |
| Lead, bis(acetato-O)tetrahydroxytri- .....                                                           | 10 (4.54)                                         |
| Lead chloride .....                                                                                  | 10 (4.54)                                         |
| Lead fluoborate .....                                                                                | 10 (4.54)                                         |
| Lead fluoride .....                                                                                  | 10 (4.54)                                         |
| Lead iodide .....                                                                                    | 10 (4.54)                                         |
| Lead nitrate .....                                                                                   | 10 (4.54)                                         |
| Lead phosphate .....                                                                                 | 10 (4.54)                                         |
| Lead stearate .....                                                                                  | 10 (4.54)                                         |
| Lead subacetate .....                                                                                | 10 (4.54)                                         |
| Lead sulfate .....                                                                                   | 10 (4.54)                                         |
| Lead sulfide .....                                                                                   | 10 (4.54)                                         |
| Lead thiocyanate .....                                                                               | 10 (4.54)                                         |
| Lindane .....                                                                                        | 1 (0.454)                                         |
| Lindane (all isomers) .....                                                                          | 1 (0.454)                                         |
| Lithium chromate .....                                                                               | 10 (4.54)                                         |
| Malathion .....                                                                                      | 100 (45.4)                                        |
| Maleic acid .....                                                                                    | 5000 (2270)                                       |
| Maleic anhydride .....                                                                               | 5000 (2270)                                       |
| Maleic hydrazide .....                                                                               | 5000 (2270)                                       |
| Malononitrile .....                                                                                  | 1000 (454)                                        |
| Manganese, bis(dimethylcarbamodithioato-S,S')- .....                                                 | 10 (4.54)                                         |
| Manganese dimethyldithiocarbamate .....                                                              | 10 (4.54)                                         |
| MDI .....                                                                                            | 5000 (2270)                                       |
| MEK .....                                                                                            | 5000 (2270)                                       |
| Melphalan .....                                                                                      | 1 (0.454)                                         |
| Mercaptodimethur .....                                                                               | 10 (4.54)                                         |
| Mercuric cyanide .....                                                                               | 1 (0.454)                                         |
| Mercuric nitrate .....                                                                               | 10 (4.54)                                         |
| Mercuric sulfate .....                                                                               | 10 (4.54)                                         |
| Mercuric thiocyanate .....                                                                           | 10 (4.54)                                         |
| Mercurous nitrate .....                                                                              | 10 (4.54)                                         |
| Mercury .....                                                                                        | 1 (0.454)                                         |
| Mercury, (acetato-O)phenyl- .....                                                                    | 100 (45.4)                                        |
| Mercury fulminate .....                                                                              | 10 (4.54)                                         |
| Methacrylonitrile .....                                                                              | 1000 (454)                                        |
| Methanamine, N-methyl- .....                                                                         | 1000 (454)                                        |
| Methanamine, N-methyl-N-nitroso- .....                                                               | 10 (4.54)                                         |
| Methane, bromo- .....                                                                                | 1000 (454)                                        |
| Methane, chloro- .....                                                                               | 100 (45.4)                                        |
| Methane, chloromethoxy- .....                                                                        | 10 (4.54)                                         |
| Methane, dibromo- .....                                                                              | 1000 (454)                                        |
| Methane, dichloro- .....                                                                             | 1000 (454)                                        |
| Methane, dichlorodifluoro- .....                                                                     | 5000 (2270)                                       |
| Methane, iodo- .....                                                                                 | 100 (45.4)                                        |
| Methane, isocyanato- .....                                                                           | 10 (4.54)                                         |
| Methane, oxybis(chloro- .....                                                                        | 10 (4.54)                                         |
| Methanesulfonyl chloride, trichloro- .....                                                           | 100 (45.4)                                        |
| Methanesulfonic acid, ethyl ester .....                                                              | 1 (0.454)                                         |
| Methane, tetrachloro- .....                                                                          | 10 (4.54)                                         |
| Methane, tetranitro- .....                                                                           | 10 (4.54)                                         |
| Methanethiol .....                                                                                   | 100 (45.4)                                        |
| Methane, tribromo- .....                                                                             | 100 (45.4)                                        |
| Methane, trichloro- .....                                                                            | 10 (4.54)                                         |
| Methane, trichlorofluoro- .....                                                                      | 5000 (2270)                                       |
| Methanimidamide, N,N-dimethyl-N'-[3-[(methylamino) carbonyl] oxy] .....                              |                                                   |
| phenyl]-, monohydrochloride .....                                                                    | 100 (45.4)                                        |
| Methanimidamide, N,N-dimethyl-N'-[2-methyl-4-[(methylamino)carbonyl] oxy]phenyl]- .....              | 100 (45.4)                                        |
| 6,9-Methano-2,4,3-benzodioxathiepin,6,7,8,9,10,10-hexachloro-1,5,5a,6,9,9a-hexahydro-, 3-oxide ..... | 1 (0.454)                                         |
| 4,7-Methano-1H-indene, 1,4,5,6,7,8,8-heptachloro-3a,4,7,7a-tetrahydro- .....                         | 1 (0.454)                                         |



TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                                                                     | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|---------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| 4,7-Methano-1H-indene, 1,2,4,5,6,7,8,8-octachloro-2,3,3a,4,7,7a-hexahydro-                                                                              | 1 (0.454)                                         |
| Methanol                                                                                                                                                | 5000 (2270)                                       |
| Methapyrilene                                                                                                                                           | 5000 (2270)                                       |
| 1,3,4-Metheno-2H-cyclobuta[cd]pentalen-2-one, 1,1a,3,3a,4,5,5,5a,5b,6-decachlorooctahydro-                                                              | 1 (0.454)                                         |
| Methiocarb                                                                                                                                              | 10 (4.54)                                         |
| Methomyl                                                                                                                                                | 100 (45.4)                                        |
| Methoxychlor                                                                                                                                            | 1 (0.454)                                         |
| Methyl alcohol                                                                                                                                          | 5000 (2270)                                       |
| Methylamine ®                                                                                                                                           | 100 (45.4)                                        |
| 2-Methyl aziridine                                                                                                                                      | 1 (0.454)                                         |
| Methyl bromide                                                                                                                                          | 1000 (454)                                        |
| 1-Methylbutadiene                                                                                                                                       | 100 (45.4)                                        |
| Methyl chloride                                                                                                                                         | 100 (45.4)                                        |
| Methyl chlorocarbonate                                                                                                                                  | 1000 (454)                                        |
| Methyl chloroform                                                                                                                                       | 1000 (454)                                        |
| Methyl chloroformate ®                                                                                                                                  | 1000 (454)                                        |
| Methyl chloromethyl ether ®                                                                                                                             | 10 (4.54)                                         |
| 3-Methylcholanthrene                                                                                                                                    | 10 (4.54)                                         |
| 4,4'-Methylenebis(2-chloroaniline)                                                                                                                      | 10 (4.54)                                         |
| Methylene bromide                                                                                                                                       | 1000 (454)                                        |
| Methylene chloride                                                                                                                                      | 1000 (454)                                        |
| 4,4'-Methylenedianiline                                                                                                                                 | 10 (4.54)                                         |
| Methylene diphenyl diisocyanate                                                                                                                         | 5000 (2270)                                       |
| Methyl ethyl ketone                                                                                                                                     | 5000 (2270)                                       |
| Methyl ethyl ketone peroxide                                                                                                                            | 10 (4.54)                                         |
| Methyl hydrazine                                                                                                                                        | 10 (4.54)                                         |
| Methyl iodide                                                                                                                                           | 100 (45.4)                                        |
| Methyl isobutyl ketone                                                                                                                                  | 5000 (2270)                                       |
| Methyl isocyanate                                                                                                                                       | 10 (4.54)                                         |
| 2-Methylacetonitrile                                                                                                                                    | 10 (4.54)                                         |
| Methyl mercaptan                                                                                                                                        | 100 (45.4)                                        |
| Methyl methacrylate                                                                                                                                     | 1000 (454)                                        |
| Methyl parathion                                                                                                                                        | 100 (45.4)                                        |
| 4-Methyl-2-pentanone                                                                                                                                    | 5000 (2270)                                       |
| Methyl tert-butyl ether                                                                                                                                 | 1000 (454)                                        |
| Methylthiouracil                                                                                                                                        | 10 (4.54)                                         |
| Metolcarb                                                                                                                                               | 1000 (454)                                        |
| Mevinphos                                                                                                                                               | 10 (4.54)                                         |
| Mexacarbate                                                                                                                                             | 1000 (454)                                        |
| Mitomycin C                                                                                                                                             | 10 (4.54)                                         |
| MNNG                                                                                                                                                    | 10 (4.54)                                         |
| Monoethylamine                                                                                                                                          | 100 (45.4)                                        |
| Monomethylamine                                                                                                                                         | 100 (45.4)                                        |
| Naled                                                                                                                                                   | 10 (4.54)                                         |
| 5,12-Naphthacenedione, 8-acetyl-10-[(3-amino-2,3,6-trideoxy-alpha-L-lyxo-hexopyranosyl)oxy]-7,8,9,10-tetrahydro-6,8,11-trihydroxy-1-methoxy-, (8S-cis)- | 10 (4.54)                                         |
| 1-Naphthalenamine                                                                                                                                       | 100 (45.4)                                        |
| 2-Naphthalenamine                                                                                                                                       | 10 (4.54)                                         |
| Naphthalenamine, N,N'-bis(2-chloroethyl)-                                                                                                               | 100 (45.4)                                        |
| Naphthalene                                                                                                                                             | 100 (45.4)                                        |
| Naphthalene, 2-chloro-                                                                                                                                  | 5000 (2270)                                       |
| 1,4-Naphthalenedione                                                                                                                                    | 5000 (2270)                                       |
| 2,7-Naphthalenedisulfonic acid, 3,3'-[(3,3'-dimethyl-(1,1'-biphenyl)-4,4'-diyl)-bis(azo)]bis(5-amino-4-hydroxy)-tetrasodium salt                        | 10 (4.54)                                         |
| 1-Naphthalenol, methylcarbamate                                                                                                                         | 100 (45.4)                                        |
| Naphthenic acid                                                                                                                                         | 100 (45.4)                                        |
| 1,4-Naphthoquinone                                                                                                                                      | 5000 (2270)                                       |
| alpha-Naphthylamine                                                                                                                                     | 100 (45.4)                                        |
| beta-Naphthylamine                                                                                                                                      | 10 (4.54)                                         |
| alpha-Naphthylthiourea                                                                                                                                  | 100 (45.4)                                        |
| Nickel cent                                                                                                                                             | 100 (45.4)                                        |
| Nickel ammonium sulfate                                                                                                                                 | 100 (45.4)                                        |
| Nickel carbonyl Ni(CO)4, (T-4)-                                                                                                                         | 10 (4.54)                                         |
| Nickel chloride                                                                                                                                         | 100 (45.4)                                        |
| Nickel cyanide Ni(CN)2                                                                                                                                  | 10 (4.54)                                         |
| Nickel hydroxide                                                                                                                                        | 10 (4.54)                                         |
| Nickel nitrate                                                                                                                                          | 100 (45.4)                                        |
| Nickel sulfate                                                                                                                                          | 100 (45.4)                                        |
| Nicotine, & salts                                                                                                                                       | 100 (45.4)                                        |
| Nitric acid                                                                                                                                             | 1000 (454)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                 | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|-------------------------------------------------------------------------------------|---------------------------------------------------|
| Nitric acid, thallium (1+) salt .....                                               | 100 (45.4)                                        |
| Nitric oxide .....                                                                  | 10 (4.54)                                         |
| p-Nitroaniline .....                                                                | 5000 (2270)                                       |
| Nitrobenzene .....                                                                  | 1000 (454)                                        |
| 4-Nitrobiphenyl .....                                                               | 10 (4.54)                                         |
| Nitrogen dioxide .....                                                              | 10 (4.54)                                         |
| Nitrogen oxide NO .....                                                             | 10 (4.54)                                         |
| Nitrogen oxide NO <sub>2</sub> .....                                                | 10 (4.54)                                         |
| Nitroglycerine .....                                                                | 10 (4.54)                                         |
| Nitrophenol (mixed) .....                                                           | 100 (45.4)                                        |
| m-Nitrophenol.                                                                      |                                                   |
| o-Nitrophenol .....                                                                 | 100 (45.4)                                        |
| p-Nitrophenol .....                                                                 | 100 (45.4)                                        |
| 2-Nitrophenol .....                                                                 | 100 (45.4)                                        |
| 4-Nitrophenol .....                                                                 | 100 (45.4)                                        |
| 2-Nitropropane .....                                                                | 10 (4.54)                                         |
| N-Nitrosodi-n-butylamine .....                                                      | 10 (4.54)                                         |
| N-Nitrosodiethanolamine .....                                                       | 1 (0.454)                                         |
| N-Nitrosodimethylamine .....                                                        | 1 (0.454)                                         |
| N-Nitrosodiphenylamine .....                                                        | 10 (4.54)                                         |
| N-Nitrosodiphenylamine .....                                                        | 100 (45.4)                                        |
| N-Nitroso-N-ethylurea .....                                                         | 1 (0.454)                                         |
| N-Nitroso-N-methylurea .....                                                        | 1 (0.454)                                         |
| N-Nitroso-N-methylurethane .....                                                    | 1 (0.454)                                         |
| N-Nitrosomethylvinylamine .....                                                     | 10 (4.54)                                         |
| N-Nitrosomorpholine .....                                                           | 1 (0.454)                                         |
| N-Nitrosopiperidine .....                                                           | 10 (4.54)                                         |
| N-Nitrosopyrrolidine .....                                                          | 1 (0.454)                                         |
| Nitrotoluene .....                                                                  | 1000 (454)                                        |
| m-Nitrotoluene.                                                                     |                                                   |
| o-Nitrotoluene.                                                                     |                                                   |
| p-Nitrotoluene.                                                                     |                                                   |
| 5-Nitro-o-toluidine .....                                                           | 100 (45.4)                                        |
| Octamethylpyrophosphoramide .....                                                   | 100 (45.4)                                        |
| Osmium oxide OsO <sub>4</sub> , (T-4) .....                                         | 1000 (454)                                        |
| Osmium tetroxide .....                                                              | 1000 (454)                                        |
| 7-Oxabicyclo[2.2.1]heptane-2,3-dicarboxylic acid .....                              | 1000 (454)                                        |
| Oxamyl .....                                                                        | 100 (45.4)                                        |
| 1,2-Oxathiolane, 2,2-dioxide .....                                                  | 10 (4.54)                                         |
| 2H-1,3,2-Oxazaphosphorin-2-amine, N,N-bis(2-chloroethyl) tetrahydro-, 2-oxide ..... | 10 (4.54)                                         |
| Oxirane .....                                                                       | 10 (4.54)                                         |
| Oxiranecarboxyaldehyde .....                                                        | 10 (4.54)                                         |
| Oxirane, (chloromethyl)- .....                                                      | 100 (45.4)                                        |
| Paraformaldehyde .....                                                              | 1000 (454)                                        |
| Paraldehyde .....                                                                   | 1000 (454)                                        |
| Parathion .....                                                                     | 10 (4.54)                                         |
| PCBs .....                                                                          | 1 (0.454)                                         |
| PCNB .....                                                                          | 100 (45.4)                                        |
| Pentachlorobenzene .....                                                            | 10 (4.54)                                         |
| Pentachloroethane .....                                                             | 10 (4.54)                                         |
| Pentachloronitrobenzene .....                                                       | 100 (45.4)                                        |
| Pentachlorophenol .....                                                             | 10 (4.54)                                         |
| 1,3-Pentadiene .....                                                                | 100 (45.4)                                        |
| Perchloroethylene .....                                                             | 100 (45.4)                                        |
| Perchloromethyl mercaptan® .....                                                    | 100 (45.4)                                        |
| Phenacetin .....                                                                    | 100 (45.4)                                        |
| Phenanthrene .....                                                                  | 5000 (2270)                                       |
| Phenol .....                                                                        | 1000 (454)                                        |
| Phenol, 2-chloro- .....                                                             | 100 (45.4)                                        |
| Phenol, 4-chloro-3-methyl- .....                                                    | 5000 (2270)                                       |
| Phenol, 2-cyclohexyl-4,6-dinitro- .....                                             | 100 (45.4)                                        |
| Phenol, 2,4-dichloro- .....                                                         | 100 (45.4)                                        |
| Phenol, 2,6-dichloro- .....                                                         | 100 (45.4)                                        |
| Phenol, 4,4'-(1,2-diethyl-1,2-ethenediyl)bis-, (E) .....                            | 1 (0.454)                                         |
| Phenol, 2,4-dimethyl- .....                                                         | 100 (45.4)                                        |
| Phenol, 4-(dimethylamino)-3,5-dimethyl-, methylcarbamate (ester) .....              | 1000 (454)                                        |
| Phenol, (3,5-dimethyl-4-(methylthio)-, methylcarbamate .....                        | 10 (4.54)                                         |
| Phenol, 2,4-dinitro- .....                                                          | 10 (4.54)                                         |
| Phenol, methyl- .....                                                               | 100 (45.4)                                        |
| Phenol, 2-methyl-4,6-dinitro-, & salts .....                                        | 10 (4.54)                                         |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                   | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|---------------------------------------------------------------------------------------|---------------------------------------------------|
| Phenol, 2,2'-methylenebis[3,4,6-trichloro- .....                                      | 100 (45.4)                                        |
| Phenol, 2-(1-methylethoxy)-, methylcarbamate .....                                    | 100 (45.4)                                        |
| Phenol, 3-(1-methylethyl)-, methyl carbamate .....                                    | 10 (4.54)                                         |
| Phenol, 3-methyl-5-(1-methylethyl)-, methyl carbamate .....                           | 1000 (454)                                        |
| Phenol, 2-(1-methylpropyl)-4,6-dinitro- .....                                         | 1000 (454)                                        |
| Phenol, 4-nitro- .....                                                                | 100 (45.4)                                        |
| Phenol, pentachloro- .....                                                            | 10 (4.54)                                         |
| Phenol, 2,3,4,6-tetrachloro- .....                                                    | 10 (4.54)                                         |
| Phenol, 2,4,5-trichloro- .....                                                        | 10 (4.54)                                         |
| Phenol, 2,4,6-trichloro- .....                                                        | 10 (4.54)                                         |
| Phenol, 2,4,6-trinitro-, ammonium salt .....                                          | 10 (4.54)                                         |
| L-Phenylalanine, 4-[bis(2-chloroethyl)amino]- .....                                   | 1 (0.454)                                         |
| p-Phenylenediamine .....                                                              | 5000 (2270)                                       |
| Phenyl mercaptan® .....                                                               | 100 (45.4)                                        |
| Phenylmercury acetate .....                                                           | 100 (45.4)                                        |
| Phenylthiourea .....                                                                  | 100 (45.4)                                        |
| Phorate .....                                                                         | 10 (4.54)                                         |
| Phosgene .....                                                                        | 10 (4.54)                                         |
| Phosphine .....                                                                       | 100 (45.4)                                        |
| Phosphoric acid .....                                                                 | 5000 (2270)                                       |
| Phosphoric acid, diethyl 4-nitrophenyl ester .....                                    | 100 (45.4)                                        |
| Phosphoric acid, lead(2+) salt (2:3) .....                                            | 10 (4.54)                                         |
| Phosphorodithioic acid, O,O-diethyl S-[2-(ethylthio)ethyl] ester .....                | 1 (0.454)                                         |
| Phosphorodithioic acid, O,O-diethyl S-[(ethylthio)methyl] ester .....                 | 10 (4.54)                                         |
| Phosphorodithioic acid, O,O-diethyl S-methyl ester .....                              | 5000 (2270)                                       |
| Phosphorodithioic acid, O,O-dimethyl S-[2-(methylamino)-2-oxoethyl] ester .....       | 10 (4.54)                                         |
| Phosphorofluoridic acid, bis(1-methylethyl) ester .....                               | 100 (45.4)                                        |
| Phosphorothioic acid, O,O-diethyl O-(4-nitrophenyl) ester .....                       | 10 (4.54)                                         |
| Phosphorothioic acid, O,O-diethyl O-pyrazinyl ester .....                             | 100 (45.4)                                        |
| Phosphorothioic acid, O-[4-[(dimethylamino) sulfonyl]phenyl] O,O-dimethyl ester ..... | 1000 (454)                                        |
| Phosphorothioic acid, O,O-dimethyl O-(4-nitrophenyl) ester .....                      | 100 (45.4)                                        |
| Phosphorus .....                                                                      | 1 (0.454)                                         |
| Phosphorus oxychloride .....                                                          | 1000 (454)                                        |
| Phosphorus pentasulfide .....                                                         | 100 (45.4)                                        |
| Phosphorus sulfide .....                                                              | 100 (45.4)                                        |
| Phosphorus trichloride .....                                                          | 1000 (454)                                        |
| Phthalic anhydride .....                                                              | 5000 (2270)                                       |
| Physostigmine .....                                                                   | 100 (45.4)                                        |
| Physostigmine salicylate .....                                                        | 100 (45.4)                                        |
| 2-Picoline .....                                                                      | 5000 (2270)                                       |
| Piperidine, 1-nitroso- .....                                                          | 10 (4.54)                                         |
| Plumbane, tetraethyl- .....                                                           | 10 (4.54)                                         |
| POLYCHLORINATED BIPHENYLS .....                                                       | 1 (0.454)                                         |
| Potassium arsenate .....                                                              | 1 (0.454)                                         |
| Potassium arsenite .....                                                              | 1 (0.454)                                         |
| Potassium bichromate .....                                                            | 10 (4.54)                                         |
| Potassium chromate .....                                                              | 10 (4.54)                                         |
| Potassium cyanide K(CN) .....                                                         | 10 (4.54)                                         |
| Potassium hydroxide .....                                                             | 1000 (454)                                        |
| Potassium permanganate .....                                                          | 100 (45.4)                                        |
| Potassium silver cyanide .....                                                        | 1 (0.454)                                         |
| Promecarb .....                                                                       | 1000 (454)                                        |
| Pronamide .....                                                                       | 5000 (2270)                                       |
| Propanal, 2-methyl-2-(methylsulfonyl)-, O-[(methylamino)carbonyl] oxime .....         | 100 (45.4)                                        |
| Propanal, 2-methyl-2-(methylthio)-, O-[(methylamino)carbonyl] oxime .....             | 1 (0.454)                                         |
| 1-Propanamine .....                                                                   | 5000 (2270)                                       |
| 1-Propanamine, N-propyl- .....                                                        | 5000 (2270)                                       |
| 1-Propanamine, N-nitroso-N-propyl- .....                                              | 10 (4.54)                                         |
| Propane, 1,2-dibromo-3-chloro- .....                                                  | 1 (0.454)                                         |
| Propane, 1,2-dichloro- .....                                                          | 1000 (454)                                        |
| Propanedinitrile .....                                                                | 1000 (454)                                        |
| Propanenitrile .....                                                                  | 10 (4.54)                                         |
| Propanenitrile, 3-chloro- .....                                                       | 1000 (454)                                        |
| Propanenitrile, 2-hydroxy-2-methyl- .....                                             | 10 (4.54)                                         |
| Propane, 2-nitro- .....                                                               | 10 (4.54)                                         |
| Propane, 2,2'-oxybis[2-chloro- .....                                                  | 1000 (454)                                        |
| 1,3-Propane sultone .....                                                             | 10 (4.54)                                         |
| 1,2,3-Propanetriol, trinitrate .....                                                  | 10 (4.54)                                         |
| Propanoic acid, 2-(2,4,5-trichlorophenoxy)- .....                                     | 100 (45.4)                                        |
| 1-Propanol, 2,3-dibromo-, phosphate (3:1) .....                                       | 10 (4.54)                                         |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                            | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|----------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| 1-Propanol, 2-methyl- .....                                                                                    | 5000 (2270)                                       |
| 2-Propanone .....                                                                                              | 5000 (2270)                                       |
| 2-Propanone, 1-bromo- .....                                                                                    | 1000 (454)                                        |
| Propargite .....                                                                                               | 10 (4.54)                                         |
| Propargyl alcohol .....                                                                                        | 1000 (454)                                        |
| 2-Propenal .....                                                                                               | 1 (0.454)                                         |
| 2-Propenamide .....                                                                                            | 5000 (2270)                                       |
| 1-Propene, 1,3-dichloro- .....                                                                                 | 100 (45.4)                                        |
| 1-Propene, 1,1,2,3,3,3-hexachloro- .....                                                                       | 1000 (454)                                        |
| 2-Propenenitrile .....                                                                                         | 100 (45.4)                                        |
| 2-Propenenitrile, 2-methyl- .....                                                                              | 1000 (454)                                        |
| 2-Propenoic acid .....                                                                                         | 5000 (2270)                                       |
| 2-Propenoic acid, ethyl ester .....                                                                            | 1000 (454)                                        |
| 2-Propenoic acid, 2-methyl-, ethyl ester .....                                                                 | 1000 (454)                                        |
| 2-Propenoic acid, 2-methyl-, methyl ester .....                                                                | 1000 (454)                                        |
| 2-Propen-1-ol .....                                                                                            | 100 (45.4)                                        |
| Propham .....                                                                                                  | 1000 (454)                                        |
| beta-Propiolactone .....                                                                                       | 10 (4.54)                                         |
| Propionaldehyde .....                                                                                          | 1000 (454)                                        |
| Propionic acid .....                                                                                           | 5000 (2270)                                       |
| Propionic anhydride .....                                                                                      | 5000 (2270)                                       |
| Propoxur (Baygon) .....                                                                                        | 100 (45.4)                                        |
| n-Propylamine .....                                                                                            | 5000 (2270)                                       |
| Propylene dichloride .....                                                                                     | 1000 (454)                                        |
| Propylene oxide .....                                                                                          | 100 (45.4)                                        |
| 1,2-Propylenimine .....                                                                                        | 1 (0.454)                                         |
| 2-Propyn-1-ol .....                                                                                            | 1000 (454)                                        |
| Prosulfocarb .....                                                                                             | 5000 (2270)                                       |
| Pyrene .....                                                                                                   | 5000 (2270)                                       |
| Pyrethrins .....                                                                                               | 1 (0.454)                                         |
| 3,6-Pyridazinedione, 1,2-dihydro- .....                                                                        | 5000 (2270)                                       |
| 4-Pyridinamine .....                                                                                           | 1000 (454)                                        |
| Pyridine .....                                                                                                 | 1000 (454)                                        |
| Pyridine, 2-methyl- .....                                                                                      | 5000 (2270)                                       |
| Pyridine, 3-(1-methyl-2-pyrrolidinyl)-, (S)-, & salts .....                                                    | 100 (45.4)                                        |
| 2,4-(1H,3H)-Pyrimidinedione, 5-[bis(2-chloroethyl)amino]- .....                                                | 10 (4.54)                                         |
| 4(1H)-Pyrimidinone, 2,3-dihydro-6-methyl-2-thioxo- .....                                                       | 10 (4.54)                                         |
| Pyrrolidine, 1-nitroso- .....                                                                                  | 1 (0.454)                                         |
| Pyrrolo[2,3-b] indol-5-ol,1,2,3,3a,8,8a-hexahydro-1,3a,8-trimethyl-, methylcarbamate (ester), (3aS-cis)- ..... | 100 (45.4)                                        |
| Quinoline .....                                                                                                | 5000 (2270)                                       |
| Quinone .....                                                                                                  | 10 (4.54)                                         |
| Quintobenzene .....                                                                                            | 100 (45.4)                                        |
| RADIONUCLIDES .....                                                                                            | See Table 2                                       |
| Reserpine .....                                                                                                | 5000 (2270)                                       |
| Resorcinol .....                                                                                               | 5000 (2270)                                       |
| Saccharin & salts .....                                                                                        | 100 (45.4)                                        |
| Safrole .....                                                                                                  | 100 (45.4)                                        |
| Selenious acid .....                                                                                           | 10 (4.54)                                         |
| Selenious acid, dithallium (1+) salt .....                                                                     | 1000 (454)                                        |
| Selenium cent; .....                                                                                           | 100 (45.4)                                        |
| Selenium dioxide .....                                                                                         | 10 (4.54)                                         |
| Selenium oxide .....                                                                                           | 10 (4.54)                                         |
| Selenium sulfide SeS2 .....                                                                                    | 10 (4.54)                                         |
| Selenourea .....                                                                                               | 1000 (454)                                        |
| L-Serine, diazoacetate (ester) .....                                                                           | 1 (0.454)                                         |
| Silver cent; .....                                                                                             | 1000 (454)                                        |
| Silver cyanide Ag(CN) .....                                                                                    | 1 (0.454)                                         |
| Silver nitrate .....                                                                                           | 1 (0.454)                                         |
| Silvex (2,4,5-TP) .....                                                                                        | 100 (45.4)                                        |
| Sodium .....                                                                                                   | 10 (4.54)                                         |
| Sodium arsenate .....                                                                                          | 1 (0.454)                                         |
| Sodium arsenite .....                                                                                          | 1 (0.454)                                         |
| Sodium azide .....                                                                                             | 1000 (454)                                        |
| Sodium bichromate .....                                                                                        | 10 (4.54)                                         |
| Sodium bifluoride .....                                                                                        | 100 (45.4)                                        |
| Sodium bisulfite .....                                                                                         | 5000 (2270)                                       |
| Sodium chromate .....                                                                                          | 10 (4.54)                                         |
| Sodium cyanide Na(CN) .....                                                                                    | 10 (4.54)                                         |
| Sodium dodecylbenzenesulfonate .....                                                                           | 1000 (454)                                        |
| Sodium fluoride .....                                                                                          | 1000 (454)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                    | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|--------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Sodium hydrosulfide .....                                                                              | 5000 (2270)                                       |
| Sodium hydroxide .....                                                                                 | 1000 (454)                                        |
| Sodium hypochlorite .....                                                                              | 100 (45.4)                                        |
| Sodium methylate .....                                                                                 | 1000 (454)                                        |
| Sodium nitrite .....                                                                                   | 100 (45.4)                                        |
| Sodium phosphate, dibasic .....                                                                        | 5000 (2270)                                       |
| Sodium phosphate, tribasic .....                                                                       | 5000 (2270)                                       |
| Sodium selenite .....                                                                                  | 100 (45.4)                                        |
| Streptozotocin .....                                                                                   | 1 (0.454)                                         |
| Strontium chromate .....                                                                               | 10 (4.54)                                         |
| Strychnidin-10-one, & salts .....                                                                      | 10 (4.54)                                         |
| Strychnidin-10-one, 2,3-dimethoxy- .....                                                               | 100 (45.4)                                        |
| Strychnine, & salts .....                                                                              | 10 (4.54)                                         |
| Styrene .....                                                                                          | 1000 (454)                                        |
| Styrene oxide .....                                                                                    | 100 (45.4)                                        |
| Sulfur chlorides @ .....                                                                               | 1000 (454)                                        |
| Sulfuric acid .....                                                                                    | 1000 (454)                                        |
| Sulfuric acid, dimethyl ester .....                                                                    | 100 (45.4)                                        |
| Sulfuric acid, dithallium (1+) salt .....                                                              | 100 (45.4)                                        |
| Sulfur monochloride .....                                                                              | 1000 (454)                                        |
| Sulfur phosphide .....                                                                                 | 100 (45.4)                                        |
| 2,4,5-T .....                                                                                          | 1000 (454)                                        |
| 2,4,5-T acid .....                                                                                     | 1000 (454)                                        |
| 2,4,5-T amines .....                                                                                   | 5000 (2270)                                       |
| 2,4,5-T esters .....                                                                                   | 1000 (454)                                        |
| 2,4,5-T salts .....                                                                                    | 1000 (454)                                        |
| TCDD .....                                                                                             | 1 (0.454)                                         |
| TDE .....                                                                                              | 1 (0.454)                                         |
| 1,2,4,5-Tetrachlorobenzene .....                                                                       | 5000 (2270)                                       |
| 2,3,7,8-Tetrachlorodibenzo-p-dioxin .....                                                              | 1 (0.454)                                         |
| 1,1,1,2-Tetrachloroethane .....                                                                        | 100 (45.4)                                        |
| 1,1,2,2-Tetrachloroethane .....                                                                        | 100 (45.4)                                        |
| Tetrachloroethylene .....                                                                              | 100 (45.4)                                        |
| 2,3,4,6-Tetrachlorophenol .....                                                                        | 10 (4.54)                                         |
| Tetraethyl pyrophosphate .....                                                                         | 10 (4.54)                                         |
| Tetraethyl lead .....                                                                                  | 10 (4.54)                                         |
| Tetraethyldithiopyrophosphate .....                                                                    | 100 (45.4)                                        |
| Tetrahydrofuran .....                                                                                  | 1000 (454)                                        |
| Tetranitromethane .....                                                                                | 10 (4.54)                                         |
| Tetraphosphoric acid, hexaethyl ester .....                                                            | 100 (45.4)                                        |
| Thallic oxide .....                                                                                    | 100 (45.4)                                        |
| Thallium cent. ....                                                                                    | 1000 (454)                                        |
| Thallium (I) acetate .....                                                                             | 100 (45.4)                                        |
| Thallium (I) carbonate .....                                                                           | 100 (45.4)                                        |
| Thallium chloride TlCl .....                                                                           | 100 (45.4)                                        |
| Thallium (I) nitrate .....                                                                             | 100 (45.4)                                        |
| Thallium oxide Tl <sub>2</sub> O <sub>3</sub> .....                                                    | 100 (45.4)                                        |
| Thallium (I) selenite .....                                                                            | 1000 (454)                                        |
| Thallium (I) sulfate .....                                                                             | 100 (45.4)                                        |
| Thioacetamide .....                                                                                    | 10 (4.54)                                         |
| Thiodicarb .....                                                                                       | 100 (45.4)                                        |
| Thiodiphosphoric acid, tetraethyl ester .....                                                          | 100 (45.4)                                        |
| Thiofanox .....                                                                                        | 100 (45.4)                                        |
| Thioimidodicarbonic diamide [(H <sub>2</sub> N)C(S)] <sub>2</sub> NH .....                             | 100 (45.4)                                        |
| Thiomethanol .....                                                                                     | 100 (45.4)                                        |
| Thioperoxydicarbonic diamide [(H <sub>2</sub> N)C(S)] <sub>2</sub> S <sub>2</sub> , tetramethyl- ..... | 10 (4.54)                                         |
| Thiophanate-methyl .....                                                                               | 10 (4.54)                                         |
| Thiophenol .....                                                                                       | 100 (45.4)                                        |
| Thiosemicarbazide .....                                                                                | 100 (45.4)                                        |
| Thiourea .....                                                                                         | 10 (4.54)                                         |
| Thiourea, (2-chlorophenyl)- .....                                                                      | 100 (45.4)                                        |
| Thiourea, 1-naphthalenyl- .....                                                                        | 100 (45.4)                                        |
| Thiourea, phenyl- .....                                                                                | 100 (45.4)                                        |
| Thiram .....                                                                                           | 10 (4.54)                                         |
| Tirpate .....                                                                                          | 100 (45.4)                                        |
| Titanium tetrachloride .....                                                                           | 1000 (454)                                        |
| Toluene .....                                                                                          | 1000 (454)                                        |
| Toluenediamine .....                                                                                   | 10 (4.54)                                         |
| 2,4-Toluene diamine .....                                                                              | 10 (4.54)                                         |
| Toluene diisocyanate .....                                                                             | 100 (45.4)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                 | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|---------------------------------------------------------------------|---------------------------------------------------|
| 2,4-Toluene diisocyanate .....                                      | 100 (45.4)                                        |
| o-Toluidine .....                                                   | 100 (45.4)                                        |
| p-Toluidine .....                                                   | 100 (45.4)                                        |
| o-Toluidine hydrochloride .....                                     | 100 (45.4)                                        |
| Toxaphene .....                                                     | 1 (0.454)                                         |
| 2,4,5-TP acid .....                                                 | 100 (45.4)                                        |
| 2,4,5-TP esters .....                                               | 100 (45.4)                                        |
| Triallate .....                                                     | 100 (45.4)                                        |
| 1H-1,2,4-Triazol-3-amine .....                                      | 10 (4.54)                                         |
| Trichlorfon .....                                                   | 100 (45.4)                                        |
| 1,2,4-Trichlorobenzene .....                                        | 100 (45.4)                                        |
| 1,1,1-Trichloroethane .....                                         | 1000 (454)                                        |
| 1,1,2-Trichloroethane .....                                         | 100 (45.4)                                        |
| Trichloroethylene .....                                             | 100 (45.4)                                        |
| Trichloromethanesulfonyl chloride .....                             | 100 (45.4)                                        |
| Trichloromonofluoromethane .....                                    | 5000 (2270)                                       |
| Trichlorophenol .....                                               | 10 (4.54)                                         |
| 2,3,4-Trichlorophenol .....                                         |                                                   |
| 2,3,5-Trichlorophenol .....                                         |                                                   |
| 2,3,6-Trichlorophenol .....                                         |                                                   |
| 3,4,5-Trichlorophenol .....                                         |                                                   |
| 2,4,5-Trichlorophenol .....                                         | 10 (4.54)                                         |
| 2,4,6-Trichlorophenol .....                                         | 10 (4.54)                                         |
| Triethanolamine dodecylbenzenesulfonate .....                       | 1000 (454)                                        |
| Triethylamine .....                                                 | 5000 (2270)                                       |
| Trifluralin .....                                                   | 10 (4.54)                                         |
| Trimethylamine .....                                                | 100 (45.4)                                        |
| 2,2,4-Trimethylpentane .....                                        | 1000 (454)                                        |
| 1,3,5-Trinitrobenzene .....                                         | 10 (4.54)                                         |
| 1,3,5-Trioxane, 2,4,6-trimethyl- .....                              | 1000 (454)                                        |
| Tris(2,3-dibromopropyl) phosphate .....                             | 10 (4.54)                                         |
| Trypan blue .....                                                   | 10 (4.54)                                         |
| D002 Unlisted Hazardous Wastes Characteristic of Corrosivity .....  | 100 (45.4)                                        |
| D001 Unlisted Hazardous Wastes Characteristic of Ignitability ..... | 100 (45.4)                                        |
| D003 Unlisted Hazardous Wastes Characteristic of Reactivity .....   | 100 (45.4)                                        |
| D004–D043 Unlisted Hazardous Wastes Characteristic of Toxicity:     |                                                   |
| Arsenic (D004) .....                                                | 1 (0.454)                                         |
| Barium (D005) .....                                                 | 1000 (454)                                        |
| Benzene (D018) .....                                                | 10 (4.54)                                         |
| Cadmium (D006) .....                                                | 10 (4.54)                                         |
| Carbon tetrachloride (D019) .....                                   | 10 (4.54)                                         |
| Chlordane (D020) .....                                              | 1 (0.454)                                         |
| Chlorobenzene (D021) .....                                          | 100 (45.4)                                        |
| Chloroform (D022) .....                                             | 10 (4.54)                                         |
| Chromium (D007) .....                                               | 10 (4.54)                                         |
| o-Cresol (D023) .....                                               | 100 (45.4)                                        |
| m-Cresol (D024) .....                                               | 100 (45.4)                                        |
| p-Cresol (D025) .....                                               | 100 (45.4)                                        |
| Cresol (D026) .....                                                 | 100 (45.4)                                        |
| 2,4-D (D016) .....                                                  | 100 (45.4)                                        |
| 1,4-Dichlorobenzene (D027) .....                                    | 100 (45.4)                                        |
| 1,2-Dichloroethane (D028) .....                                     | 100 (45.4)                                        |
| 1,1-Dichloroethylene (D029) .....                                   | 100 (45.4)                                        |
| 2,4-Dinitrotoluene (D030) .....                                     | 10 (4.54)                                         |
| Endrin (D012) .....                                                 | 1 (0.454)                                         |
| Heptachlor (and epoxide) (D031) .....                               | 1 (0.454)                                         |
| Hexachlorobenzene (D032) .....                                      | 10 (4.54)                                         |
| Hexachlorobutadiene (D033) .....                                    | 1 (0.454)                                         |
| Hexachloroethane (D034) .....                                       | 100 (45.4)                                        |
| Lead (D008) .....                                                   | 10 (4.54)                                         |
| Lindane (D013) .....                                                | 1 (0.454)                                         |
| Mercury (D009) .....                                                | 1 (0.454)                                         |
| Methoxychlor (D014) .....                                           | 1 (0.454)                                         |
| Methyl ethyl ketone (D035) .....                                    | 5000 (2270)                                       |
| Nitrobenzene (D036) .....                                           | 1000 (454)                                        |
| Pentachlorophenol (D037) .....                                      | 10 (4.54)                                         |
| Pyridine (D038) .....                                               | 1000 (454)                                        |
| Selenium (D010) .....                                               | 10 (4.54)                                         |
| Silver (D011) .....                                                 | 1 (0.454)                                         |
| Tetrachloroethylene (D039) .....                                    | 100 (45.4)                                        |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                                                                                                                       | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|-------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|
| Toxaphene (D015) .....                                                                                                                    | 1 (0.454)                                         |
| Trichloroethylene (D040) .....                                                                                                            | 100 (45.4)                                        |
| 2,4,5-Trichlorophenol (D041) .....                                                                                                        | 10 (4.54)                                         |
| 2,4,6-Trichlorophenol (D042) .....                                                                                                        | 10 (4.54)                                         |
| 2,4,5-TP (D017) .....                                                                                                                     | 100 (45.4)                                        |
| Vinyl chloride (D043) .....                                                                                                               | 1 (0.454)                                         |
| Uracil mustard .....                                                                                                                      | 10 (4.54)                                         |
| Uranyl acetate .....                                                                                                                      | 100 (45.4)                                        |
| Uranyl nitrate .....                                                                                                                      | 100 (45.4)                                        |
| Urea, N-ethyl-N-nitroso- .....                                                                                                            | 1 (0.454)                                         |
| Urea, N-methyl-N-nitroso- .....                                                                                                           | 1 (0.454)                                         |
| Urethane .....                                                                                                                            | 100 (45.4)                                        |
| Vanadic acid, ammonium salt .....                                                                                                         | 1000 (454)                                        |
| Vanadium oxide V <sub>2</sub> O <sub>5</sub> .....                                                                                        | 1000 (454)                                        |
| Vanadium pentoxide .....                                                                                                                  | 1000 (454)                                        |
| Vanadyl sulfate .....                                                                                                                     | 1000 (454)                                        |
| Vinyl acetate .....                                                                                                                       | 5000 (2270)                                       |
| Vinyl acetate monomer .....                                                                                                               | 5000 (2270)                                       |
| Vinylamine, N-methyl-N-nitroso- .....                                                                                                     | 10 (4.54)                                         |
| Vinyl bromide .....                                                                                                                       | 100 (45.4)                                        |
| Vinyl chloride .....                                                                                                                      | 1 (0.454)                                         |
| Vinylidene chloride .....                                                                                                                 | 100 (45.4)                                        |
| Warfarin, & salts .....                                                                                                                   | 100 (45.4)                                        |
| Xylene .....                                                                                                                              | 100 (45.4)                                        |
| m-Xylene .....                                                                                                                            | 1000 (454)                                        |
| o-Xylene .....                                                                                                                            | 1000 (454)                                        |
| p-Xylene .....                                                                                                                            | 100 (45.4)                                        |
| Xylene (mixed) .....                                                                                                                      | 100 (45.4)                                        |
| Xylenes (isomers and mixture) .....                                                                                                       | 100 (45.4)                                        |
| Xylenol .....                                                                                                                             | 1000 (454)                                        |
| Yohimban-16-carboxylic acid,11,17-dimethoxy-18-[(3,4,5-trimethoxybenzoyl)oxy]-, methyl ester (3beta,16beta,17alpha,18beta, 20alpha) ..... | 5000 (2270)                                       |
| Zinc cent .....                                                                                                                           | 1000 (454)                                        |
| Zinc acetate .....                                                                                                                        | 1000 (454)                                        |
| Zinc ammonium chloride .....                                                                                                              | 1000 (454)                                        |
| Zinc, bis(dimethylcarbamoithioato-S,S')- .....                                                                                            | 10 (4.54)                                         |
| Zinc borate .....                                                                                                                         | 1000 (454)                                        |
| Zinc bromide .....                                                                                                                        | 1000 (454)                                        |
| Zinc carbonate .....                                                                                                                      | 1000 (454)                                        |
| Zinc chloride .....                                                                                                                       | 1000 (454)                                        |
| Zinc cyanide Zn(CN) <sub>2</sub> .....                                                                                                    | 10 (4.54)                                         |
| Zinc fluoride .....                                                                                                                       | 1000 (454)                                        |
| Zinc formate .....                                                                                                                        | 1000 (454)                                        |
| Zinc hydrosulfite .....                                                                                                                   | 1000 (454)                                        |
| Zinc nitrate .....                                                                                                                        | 1000 (454)                                        |
| Zinc phenolsulfonate .....                                                                                                                | 5000 (2270)                                       |
| Zinc phosphide Zn <sub>3</sub> P <sub>2</sub> .....                                                                                       | 100 (45.4)                                        |
| Zinc silicofluoride .....                                                                                                                 | 5000 (2270)                                       |
| Zinc sulfate .....                                                                                                                        | 1000 (454)                                        |
| Ziram .....                                                                                                                               | 10 (4.54)                                         |
| Zirconium nitrate .....                                                                                                                   | 5000 (2270)                                       |
| Zirconium potassium fluoride .....                                                                                                        | 1000 (454)                                        |
| Zirconium sulfate .....                                                                                                                   | 5000 (2270)                                       |
| Zirconium tetrachloride .....                                                                                                             | 5000 (2270)                                       |
| F001 .....                                                                                                                                | 10 (4.54)                                         |
| (a) Tetrachloroethylene .....                                                                                                             | 100 (45.4)                                        |
| (b) Trichloroethylene .....                                                                                                               | 100 (45.4)                                        |
| (c) Methylene chloride .....                                                                                                              | 1000 (454)                                        |
| (d) 1,1,1-Trichloroethane .....                                                                                                           | 1000 (454)                                        |
| (e) Carbon tetrachloride .....                                                                                                            | 10 (4.54)                                         |
| (f) Chlorinated fluorocarbons .....                                                                                                       | 5000 (2270)                                       |
| F002 .....                                                                                                                                | 10 (4.54)                                         |
| (a) Tetrachloroethylene .....                                                                                                             | 100 (45.4)                                        |
| (b) Methylene chloride .....                                                                                                              | 1000 (454)                                        |
| (c) Trichloroethylene .....                                                                                                               | 100 (45.4)                                        |
| (d) 1,1,1-Trichloroethane .....                                                                                                           | 1000 (454)                                        |
| (e) Chlorobenzene .....                                                                                                                   | 100 (45.4)                                        |
| (f) 1,1,2-Trichloro-1,2,2-trifluoroethane .....                                                                                           | 5000 (2270)                                       |
| (g) o-Dichlorobenzene .....                                                                                                               | 100 (45.4)                                        |
| (h) Trichlorofluoromethane .....                                                                                                          | 5000 (2270)                                       |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance                  | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|--------------------------------------|---------------------------------------------------|
| F003 (i) 1,1,2-Trichloroethane ..... | 100 (45.4)                                        |
| .....                                | 100 (45.4)                                        |
| (a) Xylene .....                     | 1000 (454)                                        |
| (b) Acetone .....                    | 5000 (2270)                                       |
| (c) Ethyl acetate .....              | 5000 (2270)                                       |
| (d) Ethylbenzene .....               | 1000 (454)                                        |
| (e) Ethyl ether .....                | 100 (45.4)                                        |
| (f) Methyl isobutyl ketone .....     | 5000 (2270)                                       |
| (g) n-Butyl alcohol .....            | 5000 (2270)                                       |
| (h) Cyclohexanone .....              | 5000 (2270)                                       |
| (i) Methanol .....                   | 5000 (2270)                                       |
| F004 .....                           | 100 (45.4)                                        |
| (a) Cresols/Cresylic acid .....      | 100 (45.4)                                        |
| (b) Nitrobenzene .....               | 1000 (454)                                        |
| F005 .....                           | 100 (45.4)                                        |
| (a) Toluene .....                    | 1000 (454)                                        |
| (b) Methyl ethyl ketone .....        | 5000 (2270)                                       |
| (c) Carbon disulfide .....           | 100 (45.4)                                        |
| (d) Isobutanol .....                 | 5000 (2270)                                       |
| (e) Pyridine .....                   | 1000 (454)                                        |
| F006 .....                           | 10 (4.54)                                         |
| F007 .....                           | 10 (4.54)                                         |
| F008 .....                           | 10 (4.54)                                         |
| F009 .....                           | 10 (4.54)                                         |
| F010 .....                           | 10 (4.54)                                         |
| F011 .....                           | 10 (4.54)                                         |
| F012 .....                           | 10 (4.54)                                         |
| F019 .....                           | 10 (4.54)                                         |
| F020 .....                           | 1 (0.454)                                         |
| F021 .....                           | 1 (0.454)                                         |
| F022 .....                           | 1 (0.454)                                         |
| F023 .....                           | 1 (0.454)                                         |
| F024 .....                           | 1 (0.454)                                         |
| F025 .....                           | 1 (0.454)                                         |
| F026 .....                           | 1 (0.454)                                         |
| F027 .....                           | 1 (0.454)                                         |
| F028 .....                           | 1 (0.454)                                         |
| F032 .....                           | 1 (0.454)                                         |
| F034 .....                           | 1 (0.454)                                         |
| F035 .....                           | 1 (0.454)                                         |
| F037 .....                           | 1 (0.454)                                         |
| F038 .....                           | 1 (0.454)                                         |
| F039 .....                           | 1 (0.454)                                         |
| K001 .....                           | 1 (0.454)                                         |
| K002 .....                           | 10 (4.54)                                         |
| K003 .....                           | 10 (4.54)                                         |
| K004 .....                           | 10 (4.54)                                         |
| K005 .....                           | 10 (4.54)                                         |
| K006 .....                           | 10 (4.54)                                         |
| K007 .....                           | 10 (4.54)                                         |
| K008 .....                           | 10 (4.54)                                         |
| K009 .....                           | 10 (4.54)                                         |
| K010 .....                           | 10 (4.54)                                         |
| K011 .....                           | 10 (4.54)                                         |
| K013 .....                           | 10 (4.54)                                         |
| K014 .....                           | 5000 (2270)                                       |
| K015 .....                           | 10 (4.54)                                         |
| K016 .....                           | 1 (0.454)                                         |
| K017 .....                           | 10 (4.54)                                         |
| K018 .....                           | 1 (0.454)                                         |
| K019 .....                           | 1 (0.454)                                         |
| K020 .....                           | 1 (0.454)                                         |
| K021 .....                           | 10 (4.54)                                         |
| K022 .....                           | 1 (0.454)                                         |
| K023 .....                           | 5000 (2270)                                       |
| K024 .....                           | 5000 (2270)                                       |
| K025 .....                           | 10 (4.54)                                         |
| K026 .....                           | 1000 (454)                                        |
| K027 .....                           | 10 (4.54)                                         |
| K028 .....                           | 1 (0.454)                                         |



TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|---------------------|---------------------------------------------------|
| K029 .....          | 1 (0.454)                                         |
| K030 .....          | 1 (0.454)                                         |
| K031 .....          | 1 (0.454)                                         |
| K032 .....          | 10 (4.54)                                         |
| K033 .....          | 10 (4.54)                                         |
| K034 .....          | 10 (4.54)                                         |
| K035 .....          | 1 (0.454)                                         |
| K036 .....          | 1 (0.454)                                         |
| K037 .....          | 1 (0.454)                                         |
| K038 .....          | 10 (4.54)                                         |
| K039 .....          | 10 (4.54)                                         |
| K040 .....          | 10 (4.54)                                         |
| K041 .....          | 1 (0.454)                                         |
| K042 .....          | 10 (4.54)                                         |
| K043 .....          | 10 (4.54)                                         |
| K044 .....          | 10 (4.54)                                         |
| K045 .....          | 10 (4.54)                                         |
| K046 .....          | 10 (4.54)                                         |
| K047 .....          | 10 (4.54)                                         |
| K048 .....          | 10 (4.54)                                         |
| K049 .....          | 10 (4.54)                                         |
| K050 .....          | 10 (4.54)                                         |
| K051 .....          | 10 (4.54)                                         |
| K052 .....          | 10 (4.54)                                         |
| K060 .....          | 1 (0.454)                                         |
| K061 .....          | 10 (4.54)                                         |
| K062 .....          | 10 (4.54)                                         |
| K064 .....          | 10 (4.54)                                         |
| K065 .....          | 10 (4.54)                                         |
| K066 .....          | 10 (4.54)                                         |
| K069 .....          | 10 (4.54)                                         |
| K071 .....          | 1 (0.454)                                         |
| K073 .....          | 10 (4.54)                                         |
| K083 .....          | 100 (45.4)                                        |
| K084 .....          | 1 (0.454)                                         |
| K085 .....          | 10 (4.54)                                         |
| K086 .....          | 10 (4.54)                                         |
| K087 .....          | 100 (45.4)                                        |
| K088 .....          | 10 (4.54)                                         |
| K090 .....          | 10 (4.54)                                         |
| K091 .....          | 10 (4.54)                                         |
| K093 .....          | 5000 (2270)                                       |
| K094 .....          | 5000 (2270)                                       |
| K095 .....          | 100 (45.4)                                        |
| K096 .....          | 100 (45.4)                                        |
| K097 .....          | 1 (0.454)                                         |
| K098 .....          | 1 (0.454)                                         |
| K099 .....          | 10 (4.54)                                         |
| K100 .....          | 10 (4.54)                                         |
| K101 .....          | 1 (0.454)                                         |
| K102 .....          | 1 (0.454)                                         |
| K103 .....          | 100 (45.4)                                        |
| K104 .....          | 10 (4.54)                                         |
| K105 .....          | 10 (4.54)                                         |
| K106 .....          | 1 (0.454)                                         |
| K107 .....          | 10 (4.54)                                         |
| K108 .....          | 10 (4.54)                                         |
| K109 .....          | 10 (4.54)                                         |
| K110 .....          | 10 (4.54)                                         |
| K111 .....          | 10 (4.54)                                         |
| K112 .....          | 10 (4.54)                                         |
| K113 .....          | 10 (4.54)                                         |
| K114 .....          | 10 (4.54)                                         |
| K115 .....          | 10 (4.54)                                         |
| K116 .....          | 10 (4.54)                                         |
| K117 .....          | 1 (0.454)                                         |
| K118 .....          | 1 (0.454)                                         |
| K123 .....          | 10 (4.54)                                         |
| K124 .....          | 10 (4.54)                                         |
| K125 .....          | 10 (4.54)                                         |

TABLE 1 TO APPENDIX A—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES—Continued

| Hazardous substance | Reportable quantity (RQ)<br>pounds<br>(kilograms) |
|---------------------|---------------------------------------------------|
| K126 .....          | 10 (4.54)                                         |
| K131 .....          | 100 (45.4)                                        |
| K132 .....          | 1000 (454)                                        |
| K136 .....          | 1 (0.454)                                         |
| K141 .....          | 1 (0.454)                                         |
| K142 .....          | 1 (0.454)                                         |
| K143 .....          | 1 (0.454)                                         |
| K144 .....          | 1 (0.454)                                         |
| K145 .....          | 1 (0.454)                                         |
| K147 .....          | 1 (0.454)                                         |
| K148 .....          | 1 (0.454)                                         |
| K149 .....          | 10 (4.54)                                         |
| K150 .....          | 10 (4.54)                                         |
| K151 .....          | 10 (4.54)                                         |
| K156 .....          | 10 (4.54)                                         |
| K157 .....          | 10 (4.54)                                         |
| K158 .....          | 10 (4.54)                                         |
| K159 .....          | 10 (4.54)                                         |
| K161 .....          | 1 (0.454)                                         |
| K169 .....          | 10 (4.54)                                         |
| K170 .....          | 1 (0.454)                                         |
| K171 .....          | 1 (0.454)                                         |
| K172 .....          | 1 (0.454)                                         |
| K174 .....          | 1 (0.454)                                         |
| K175 .....          | 1 (0.454)                                         |
| K176 .....          | 1 (0.454)                                         |
| K177 .....          | 5000 (2270)                                       |
| K178 .....          | 1000 (454)                                        |
| K181 .....          | 1 (0.454)                                         |

cent; The RQ for these hazardous substances is limited to those pieces of the metal having a diameter smaller than 100 micrometers (0.004 inches).

cent; cent; The RQ for asbestos is limited to friable forms only.

® Indicates that the name was added by PHMSA because (1) the name is a synonym for a specific hazardous substance and (2) the name appears in the Hazardous Materials Table as a proper shipping name.

\* To provide consistency with EPA regulations, two entries with different CAS numbers are provided. Refer to the EPA Table 302.4—List of Hazardous Substances and Reportable Quantities for an explanation of the two entries.

LIST OF HAZARDOUS SUBSTANCES AND REPORTABLE QUANTITIES

TABLE 2 TO APPENDIX A—RADIONUCLIDES

| (1)—Radionuclide     | (2)—Atomic Number | (3)—Reportable Quantity (RQ)<br>Ci (TBq) |
|----------------------|-------------------|------------------------------------------|
| Actinium-224 .....   | 89                | 100 (3.7)                                |
| Actinium-225 .....   | 89                | 1 (.037)                                 |
| Actinium-226 .....   | 89                | 10 (.37)                                 |
| Actinium-227 .....   | 89                | 0.001 (.00037)                           |
| Actinium-228 .....   | 89                | 10 (.37)                                 |
| Aluminum-26 .....    | 13                | 10 (.37)                                 |
| Americium-237 .....  | 95                | 1000 (37)                                |
| Americium-238 .....  | 95                | 100 (3.7)                                |
| Americium-239 .....  | 95                | 100 (3.7)                                |
| Americium-240 .....  | 95                | 10 (.37)                                 |
| Americium-241 .....  | 95                | 0.01 (.00037)                            |
| Americium-242 .....  | 95                | 100 (3.7)                                |
| Americium-242m ..... | 95                | 0.01 (.00037)                            |
| Americium-243 .....  | 95                | 0.01 (.00037)                            |
| Americium-244 .....  | 95                | 10 (.37)                                 |
| Americium-244m ..... | 95                | 1000 (37)                                |
| Americium-245 .....  | 95                | 1000 (37)                                |
| Americium-246 .....  | 95                | 1000 (37)                                |
| Americium-246m ..... | 95                | 1000 (37)                                |
| Antimony-115 .....   | 51                | 1000 (37)                                |
| Antimony-116 .....   | 51                | 1000 (37)                                |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—Continued

| (1)—Radionuclide              | (2)—Atomic Number | (3)—Reportable Quantity (RQ)<br>Ci (TBq) |
|-------------------------------|-------------------|------------------------------------------|
| Antimony-116m .....           | 51                | 100 (3.7)                                |
| Antimony-117 .....            | 51                | 1000 (37)                                |
| Antimony-118m .....           | 51                | 10 (.37)                                 |
| Antimony-119 .....            | 51                | 1000 (37)                                |
| Antimony-120 (16 min) .....   | 51                | 1000 (37)                                |
| Antimony-120 (5.76 day) ..... | 51                | 10 (.37)                                 |
| Antimony-122 .....            | 51                | 10 (.37)                                 |
| Antimony-124 .....            | 51                | 10 (.37)                                 |
| Antimony-124m .....           | 51                | 1000 (37)                                |
| Antimony-125 .....            | 51                | 10 (.37)                                 |
| Antimony-126 .....            | 51                | 10 (.37)                                 |
| Antimony-126m .....           | 51                | 1000 (37)                                |
| Antimony-127 .....            | 51                | 10 (.37)                                 |
| Antimony-128 (10.4 min) ..... | 51                | 1000 (37)                                |
| Antimony-128 (9.01 hr) .....  | 51                | 10 (.37)                                 |
| Antimony-129 .....            | 51                | 100 (3.7)                                |
| Antimony-130 .....            | 51                | 100 (3.7)                                |
| Antimony-131 .....            | 51                | 1000 (37)                                |
| Argon-39 .....                | 18                | 1000 (37)                                |
| Argon-41 .....                | 18                | 10 (.37)                                 |
| Arsenic-69 .....              | 33                | 1000 (37)                                |
| Arsenic-70 .....              | 33                | 100 (3.7)                                |
| Arsenic-71 .....              | 33                | 100 (3.7)                                |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|------------------|-------------------------------|---------------------------------------------|
| Arsenic-72       | 33                            | 10 (.37)                                    |
| Arsenic-73       | 33                            | 100 (3.7)                                   |
| Arsenic-74       | 33                            | 10 (.37)                                    |
| Arsenic-76       | 33                            | 100 (3.7)                                   |
| Arsenic-77       | 33                            | 1000 (37)                                   |
| Arsenic-78       | 33                            | 100 (3.7)                                   |
| Astatine-207     | 85                            | 100 (3.7)                                   |
| Astatine-211     | 85                            | 100 (3.7)                                   |
| Barium-126       | 56                            | 1000 (37)                                   |
| Barium-128       | 56                            | 10 (.37)                                    |
| Barium-131       | 56                            | 10 (.37)                                    |
| Barium-131m      | 56                            | 1000 (37)                                   |
| Barium-133       | 56                            | 10 (.37)                                    |
| Barium-133m      | 56                            | 100 (3.7)                                   |
| Barium-135m      | 56                            | 1000 (37)                                   |
| Barium-139       | 56                            | 1000 (37)                                   |
| Barium-140       | 56                            | 10 (.37)                                    |
| Barium-141       | 56                            | 1000 (37)                                   |
| Barium-142       | 56                            | 1000 (37)                                   |
| Berkelium-245    | 97                            | 100 (3.7)                                   |
| Berkelium-246    | 97                            | 10 (.37)                                    |
| Berkelium-247    | 97                            | 0.01 (.00037)                               |
| Berkelium-249    | 97                            | 1 (.037)                                    |
| Berkelium-250    | 97                            | 100 (3.7)                                   |
| Beryllium-10     | 4                             | 1 (.037)                                    |
| Beryllium-7      | 4                             | 100 (3.7)                                   |
| Bismuth-200      | 83                            | 100 (3.7)                                   |
| Bismuth-201      | 83                            | 100 (3.7)                                   |
| Bismuth-202      | 83                            | 1000 (37)                                   |
| Bismuth-203      | 83                            | 10 (.37)                                    |
| Bismuth-205      | 83                            | 10 (.37)                                    |
| Bismuth-206      | 83                            | 10 (.37)                                    |
| Bismuth-207      | 83                            | 10 (.37)                                    |
| Bismuth-210      | 83                            | 10 (.37)                                    |
| Bismuth-210m     | 83                            | 0.1 (.0037)                                 |
| Bismuth-212      | 83                            | 100 (3.7)                                   |
| Bismuth-213      | 83                            | 100 (3.7)                                   |
| Bismuth-214      | 83                            | 100 (3.7)                                   |
| Bromine-74       | 35                            | 100 (3.7)                                   |
| Bromine-74m      | 35                            | 100 (3.7)                                   |
| Bromine-75       | 35                            | 100 (3.7)                                   |
| Bromine-76       | 35                            | 10 (.37)                                    |
| Bromine-77       | 35                            | 100 (3.7)                                   |
| Bromine-80       | 35                            | 1000 (37)                                   |
| Bromine-80m      | 35                            | 1000 (37)                                   |
| Bromine-82       | 35                            | 10 (.37)                                    |
| Bromine-83       | 35                            | 1000 (37)                                   |
| Bromine-84       | 35                            | 100 (3.7)                                   |
| Cadmium-104      | 48                            | 1000 (37)                                   |
| Cadmium-107      | 48                            | 1000 (37)                                   |
| Cadmium-109      | 48                            | 1 (.037)                                    |
| Cadmium-113      | 48                            | 0.1 (.0037)                                 |
| Cadmium-113m     | 48                            | 0.1 (.0037)                                 |
| Cadmium-115      | 48                            | 100 (3.7)                                   |
| Cadmium-115m     | 48                            | 10 (.37)                                    |
| Cadmium-117      | 48                            | 100 (3.7)                                   |
| Cadmium-117m     | 48                            | 10 (.37)                                    |
| Calcium-41       | 20                            | 10 (.37)                                    |
| Calcium-45       | 20                            | 10 (.37)                                    |
| Calcium-47       | 20                            | 10 (.37)                                    |
| Californium-244  | 98                            | 1000 (37)                                   |
| Californium-246  | 98                            | 10 (.37)                                    |
| Californium-248  | 98                            | 0.1 (.0037)                                 |
| Californium-249  | 98                            | 0.01 (.00037)                               |
| Californium-250  | 98                            | 0.01 (.00037)                               |
| Californium-251  | 98                            | 0.01 (.00037)                               |
| Californium-252  | 98                            | 0.1 (.0037)                                 |
| Californium-253  | 98                            | 10 (.37)                                    |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|------------------|-------------------------------|---------------------------------------------|
| Californium-254  | 98                            | 0.1 (.0037)                                 |
| Carbon-11        | 6                             | 1000 (37)                                   |
| Carbon-14        | 6                             | 10 (.37)                                    |
| Cerium-134       | 58                            | 10 (.37)                                    |
| Cerium-135       | 58                            | 10 (.37)                                    |
| Cerium-137       | 58                            | 1000 (37)                                   |
| Cerium-137m      | 58                            | 100 (3.7)                                   |
| Cerium-139       | 58                            | 100 (3.7)                                   |
| Cerium-141       | 58                            | 10 (.37)                                    |
| Cerium-143       | 58                            | 100 (3.7)                                   |
| Cerium-144       | 58                            | 1 (.037)                                    |
| Cesium-125       | 55                            | 1000 (37)                                   |
| Cesium-127       | 55                            | 100 (3.7)                                   |
| Cesium-129       | 55                            | 100 (3.7)                                   |
| Cesium-130       | 55                            | 1000 (37)                                   |
| Cesium-131       | 55                            | 1000 (37)                                   |
| Cesium-132       | 55                            | 10 (.37)                                    |
| Cesium-134       | 55                            | 1 (.037)                                    |
| Cesium-134m      | 55                            | 1000 (37)                                   |
| Cesium-135       | 55                            | 10 (.37)                                    |
| Cesium-135m      | 55                            | 100 (3.7)                                   |
| Cesium-136       | 55                            | 10 (.37)                                    |
| Cesium-137       | 55                            | 1 (.037)                                    |
| Cesium-138       | 55                            | 100 (3.7)                                   |
| Chlorine-36      | 17                            | 10 (.37)                                    |
| Chlorine-38      | 17                            | 100 (3.7)                                   |
| Chlorine-39      | 17                            | 100 (3.7)                                   |
| Chromium-48      | 24                            | 100 (3.7)                                   |
| Chromium-49      | 24                            | 1000 (37)                                   |
| Chromium-51      | 24                            | 1000 (37)                                   |
| Cobalt-55        | 27                            | 10 (.37)                                    |
| Cobalt-56        | 27                            | 10 (.37)                                    |
| Cobalt-57        | 27                            | 100 (3.7)                                   |
| Cobalt-58        | 27                            | 10 (.37)                                    |
| Cobalt-58m       | 27                            | 1000 (37)                                   |
| Cobalt-60        | 27                            | 10 (.37)                                    |
| Cobalt-60m       | 27                            | 1000 (37)                                   |
| Cobalt-61        | 27                            | 1000 (37)                                   |
| Cobalt-62m       | 27                            | 1000 (37)                                   |
| Copper-60        | 29                            | 100 (3.7)                                   |
| Copper-61        | 29                            | 100 (3.7)                                   |
| Copper-64        | 29                            | 1000 (37)                                   |
| Copper-67        | 29                            | 100 (3.7)                                   |
| Curium-238       | 96                            | 1000 (37)                                   |
| Curium-240       | 96                            | 1 (.037)                                    |
| Curium-241       | 96                            | 10 (.37)                                    |
| Curium-242       | 96                            | 1 (.037)                                    |
| Curium-243       | 96                            | 0.01 (.00037)                               |
| Curium-244       | 96                            | 0.01 (.00037)                               |
| Curium-245       | 96                            | 0.01 (.00037)                               |
| Curium-246       | 96                            | 0.01 (.00037)                               |
| Curium-247       | 96                            | 0.01 (.00037)                               |
| Curium-248       | 96                            | 0.001 (.000037)                             |
| Curium-249       | 96                            | 1000 (37)                                   |
| Dysprosium-155   | 66                            | 100 (3.7)                                   |
| Dysprosium-157   | 66                            | 100 (3.7)                                   |
| Dysprosium-159   | 66                            | 100 (3.7)                                   |
| Dysprosium-165   | 66                            | 1000 (37)                                   |
| Dysprosium-166   | 66                            | 10 (.37)                                    |
| Einsteinium-250  | 99                            | 10 (.37)                                    |
| Einsteinium-251  | 99                            | 1000 (37)                                   |
| Einsteinium-253  | 99                            | 10 (.37)                                    |
| Einsteinium-254  | 99                            | 0.1 (.0037)                                 |
| Einsteinium-254m | 99                            | 1 (.037)                                    |
| Erbium-161       | 68                            | 100 (3.7)                                   |
| Erbium-165       | 68                            | 1000 (37)                                   |
| Erbium-169       | 68                            | 100 (3.7)                                   |
| Erbium-171       | 68                            | 100 (3.7)                                   |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide             | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|------------------------------|-------------------------------|---------------------------------------------|
| Erbium-172 .....             | 68                            | 10 (.37)                                    |
| Europium-145 .....           | 63                            | 10 (.37)                                    |
| Europium-146 .....           | 63                            | 10 (.37)                                    |
| Europium-147 .....           | 63                            | 10 (.37)                                    |
| Europium-148 .....           | 63                            | 10 (.37)                                    |
| Europium-149 .....           | 63                            | 100 (3.7)                                   |
| Europium-150 (12.6 hr) ..... | 63                            | 1000 (37)                                   |
| Europium-150 (34.2 yr) ..... | 63                            | 10 (.37)                                    |
| Europium-152 .....           | 63                            | 10 (.37)                                    |
| Europium-152m .....          | 63                            | 100 (3.7)                                   |
| Europium-154 .....           | 63                            | 10 (.37)                                    |
| Europium-155 .....           | 63                            | 10 (.37)                                    |
| Europium-156 .....           | 63                            | 10 (.37)                                    |
| Europium-157 .....           | 63                            | 10 (.37)                                    |
| Europium-158 .....           | 63                            | 1000 (37)                                   |
| Fermium-252 .....            | 100                           | 10 (.37)                                    |
| Fermium-253 .....            | 100                           | 10 (.37)                                    |
| Fermium-254 .....            | 100                           | 100 (3.7)                                   |
| Fermium-255 .....            | 100                           | 100 (3.7)                                   |
| Fermium-257 .....            | 100                           | 1 (.037)                                    |
| Fluorine-18 .....            | 9                             | 1000 (37)                                   |
| Francium-222 .....           | 87                            | 100 (3.7)                                   |
| Francium-223 .....           | 87                            | 100 (3.7)                                   |
| Gadolinium-145 .....         | 64                            | 100 (3.7)                                   |
| Gadolinium-146 .....         | 64                            | 10 (.37)                                    |
| Gadolinium-147 .....         | 64                            | 10 (.37)                                    |
| Gadolinium-148 .....         | 64                            | 0.001 (.000037)                             |
| Gadolinium-149 .....         | 64                            | 100 (3.7)                                   |
| Gadolinium-151 .....         | 64                            | 100 (3.7)                                   |
| Gadolinium-152 .....         | 64                            | 0.001 (.000037)                             |
| Gadolinium-153 .....         | 64                            | 10 (.37)                                    |
| Gadolinium-159 .....         | 64                            | 1000 (37)                                   |
| Gallium-65 .....             | 31                            | 1000 (37)                                   |
| Gallium-66 .....             | 31                            | 10 (.37)                                    |
| Gallium-67 .....             | 31                            | 100 (3.7)                                   |
| Gallium-68 .....             | 31                            | 1000 (37)                                   |
| Gallium-70 .....             | 31                            | 1000 (37)                                   |
| Gallium-72 .....             | 31                            | 10 (.37)                                    |
| Gallium-73 .....             | 31                            | 100 (3.7)                                   |
| Germanium-66 .....           | 32                            | 100 (3.7)                                   |
| Germanium-67 .....           | 32                            | 1000 (37)                                   |
| Germanium-68 .....           | 32                            | 10 (.37)                                    |
| Germanium-69 .....           | 32                            | 10 (.37)                                    |
| Germanium-71 .....           | 32                            | 1000 (37)                                   |
| Germanium-75 .....           | 32                            | 1000 (37)                                   |
| Germanium-77 .....           | 32                            | 10 (.37)                                    |
| Germanium-78 .....           | 32                            | 1000 (37)                                   |
| Gold-193 .....               | 79                            | 100 (3.7)                                   |
| Gold-194 .....               | 79                            | 10 (.37)                                    |
| Gold-195 .....               | 79                            | 100 (3.7)                                   |
| Gold-198 .....               | 79                            | 100 (3.7)                                   |
| Gold-198m .....              | 79                            | 10 (.37)                                    |
| Gold-199 .....               | 79                            | 100 (3.7)                                   |
| Gold-200 .....               | 79                            | 1000 (37)                                   |
| Gold-200m .....              | 79                            | 10 (.37)                                    |
| Gold-201 .....               | 79                            | 1000 (37)                                   |
| Hafnium-170 .....            | 72                            | 100 (3.7)                                   |
| Hafnium-172 .....            | 72                            | 1 (.037)                                    |
| Hafnium-173 .....            | 72                            | 100 (3.7)                                   |
| Hafnium-175 .....            | 72                            | 100 (3.7)                                   |
| Hafnium-177m .....           | 72                            | 1000 (37)                                   |
| Hafnium-178m .....           | 72                            | 0.1 (.0037)                                 |
| Hafnium-179m .....           | 72                            | 100 (3.7)                                   |
| Hafnium-180m .....           | 72                            | 100 (3.7)                                   |
| Hafnium-181 .....            | 72                            | 10 (.37)                                    |
| Hafnium-182 .....            | 72                            | 0.1 (.0037)                                 |
| Hafnium-182m .....           | 72                            | 100 (3.7)                                   |
| Hafnium-183 .....            | 72                            | 100 (3.7)                                   |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide            | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|-----------------------------|-------------------------------|---------------------------------------------|
| Hafnium-184 .....           | 72                            | 100 (3.7)                                   |
| Holmium-155 .....           | 67                            | 1000 (37)                                   |
| Holmium-157 .....           | 67                            | 1000 (37)                                   |
| Holmium-159 .....           | 67                            | 1000 (37)                                   |
| Holmium-161 .....           | 67                            | 1000 (37)                                   |
| Holmium-162 .....           | 67                            | 1000 (37)                                   |
| Holmium-162m .....          | 67                            | 1000 (37)                                   |
| Holmium-164 .....           | 67                            | 1000 (37)                                   |
| Holmium-164m .....          | 67                            | 1000 (37)                                   |
| Holmium-166 .....           | 67                            | 100 (3.7)                                   |
| Holmium-166m .....          | 67                            | 1 (.037)                                    |
| Holmium-167 .....           | 67                            | 100 (3.7)                                   |
| Hydrogen-3 .....            | 1                             | 100 (3.7)                                   |
| Indium-109 .....            | 49                            | 100 (3.7)                                   |
| Indium-110 (4.9 hr) .....   | 49                            | 10 (.37)                                    |
| Indium-110 (69.1 min) ..... | 49                            | 100 (3.7)                                   |
| Indium-111 .....            | 49                            | 100 (3.7)                                   |
| Indium-112 .....            | 49                            | 1000 (37)                                   |
| Indium-113m .....           | 49                            | 1000 (37)                                   |
| Indium-114m .....           | 49                            | 10 (.37)                                    |
| Indium-115 .....            | 49                            | 0.1 (.0037)                                 |
| Indium-115m .....           | 49                            | 100 (3.7)                                   |
| Indium-116m .....           | 49                            | 100 (3.7)                                   |
| Indium-117 .....            | 49                            | 1000 (37)                                   |
| Indium-117m .....           | 49                            | 100 (3.7)                                   |
| Indium-119m .....           | 49                            | 1000 (37)                                   |
| Iodine-120 .....            | 53                            | 10 (.37)                                    |
| Iodine-120m .....           | 53                            | 100 (3.7)                                   |
| Iodine-121 .....            | 53                            | 100 (3.7)                                   |
| Iodine-123 .....            | 53                            | 10 (.37)                                    |
| Iodine-124 .....            | 53                            | 0.1 (.0037)                                 |
| Iodine-125 .....            | 53                            | 0.01 (.00037)                               |
| Iodine-126 .....            | 53                            | 0.01 (.00037)                               |
| Iodine-128 .....            | 53                            | 1000 (37)                                   |
| Iodine-129 .....            | 53                            | 0.001 (.000037)                             |
| Iodine-130 .....            | 53                            | 1 (.037)                                    |
| Iodine-131 .....            | 53                            | 0.01 (.00037)                               |
| Iodine-132 .....            | 53                            | 10 (.37)                                    |
| Iodine-132m .....           | 53                            | 10 (.37)                                    |
| Iodine-133 .....            | 53                            | 0.1 (.0037)                                 |
| Iodine-134 .....            | 53                            | 100 (3.7)                                   |
| Iodine-135 .....            | 53                            | 10 (.37)                                    |
| Iridium-182 .....           | 77                            | 1000 (37)                                   |
| Iridium-184 .....           | 77                            | 100 (3.7)                                   |
| Iridium-185 .....           | 77                            | 100 (3.7)                                   |
| Iridium-186 .....           | 77                            | 10 (.37)                                    |
| Iridium-187 .....           | 77                            | 100 (3.7)                                   |
| Iridium-188 .....           | 77                            | 10 (.37)                                    |
| Iridium-189 .....           | 77                            | 100 (3.7)                                   |
| Iridium-190 .....           | 77                            | 10 (.37)                                    |
| Iridium-190m .....          | 77                            | 1000 (37)                                   |
| Iridium-192 .....           | 77                            | 10 (.37)                                    |
| Iridium-192m .....          | 77                            | 100 (3.7)                                   |
| Iridium-194 .....           | 77                            | 100 (3.7)                                   |
| Iridium-194m .....          | 77                            | 10 (.37)                                    |
| Iridium-195 .....           | 77                            | 1000 (37)                                   |
| Iridium-195m .....          | 77                            | 100 (3.7)                                   |
| Iron-52 .....               | 26                            | 100 (3.7)                                   |
| Iron-55 .....               | 26                            | 100 (3.7)                                   |
| Iron-59 .....               | 26                            | 10 (.37)                                    |
| Iron-60 .....               | 26                            | 0.1 (.0037)                                 |
| Krypton-74 .....            | 36                            | 10 (.37)                                    |
| Krypton-76 .....            | 36                            | 10 (.37)                                    |
| Krypton-77 .....            | 36                            | 10 (.37)                                    |
| Krypton-79 .....            | 36                            | 100 (3.7)                                   |
| Krypton-81 .....            | 36                            | 1000 (37)                                   |
| Krypton-83m .....           | 36                            | 1000 (37)                                   |
| Krypton-85 .....            | 36                            | 1000 (37)                                   |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|------------------|-------------------------------|---------------------------------------------|
| Krypton-85m      | 36                            | 100 (3.7)                                   |
| Krypton-87       | 36                            | 10 (.37)                                    |
| Krypton-88       | 36                            | 10 (.37)                                    |
| Lanthanum-131    | 57                            | 1000 (37)                                   |
| Lanthanum-132    | 57                            | 100 (3.7)                                   |
| Lanthanum-135    | 57                            | 1000 (37)                                   |
| Lanthanum-137    | 57                            | 10 (.37)                                    |
| Lanthanum-138    | 57                            | 1 (.037)                                    |
| Lanthanum-140    | 57                            | 10 (.37)                                    |
| Lanthanum-141    | 57                            | 1000 (37)                                   |
| Lanthanum-142    | 57                            | 100 (3.7)                                   |
| Lanthanum-143    | 57                            | 1000 (37)                                   |
| Lead-195m        | 82                            | 1000 (37)                                   |
| Lead-198         | 82                            | 100 (3.7)                                   |
| Lead-199         | 82                            | 100 (3.7)                                   |
| Lead-200         | 82                            | 100 (3.7)                                   |
| Lead-201         | 82                            | 100 (3.7)                                   |
| Lead-202         | 82                            | 1 (.037)                                    |
| Lead-202m        | 82                            | 10 (.37)                                    |
| Lead-203         | 82                            | 100 (3.7)                                   |
| Lead-205         | 82                            | 100 (3.7)                                   |
| Lead-209         | 82                            | 1000 (37)                                   |
| Lead-210         | 82                            | 0.01 (.00037)                               |
| Lead-211         | 82                            | 100 (3.7)                                   |
| Lead-212         | 82                            | 10 (.37)                                    |
| Lead-214         | 82                            | 100 (3.7)                                   |
| Lutetium-169     | 71                            | 10 (.37)                                    |
| Lutetium-170     | 71                            | 10 (.37)                                    |
| Lutetium-171     | 71                            | 10 (.37)                                    |
| Lutetium-172     | 71                            | 10 (.37)                                    |
| Lutetium-173     | 71                            | 100 (3.7)                                   |
| Lutetium-174     | 71                            | 10 (.37)                                    |
| Lutetium-174m    | 71                            | 10 (.37)                                    |
| Lutetium-176     | 71                            | 1 (.037)                                    |
| Lutetium-176m    | 71                            | 1000 (37)                                   |
| Lutetium-177     | 71                            | 100 (3.7)                                   |
| Lutetium-177m    | 71                            | 10 (.37)                                    |
| Lutetium-178     | 71                            | 1000 (37)                                   |
| Lutetium-178m    | 71                            | 1000 (37)                                   |
| Lutetium-179     | 71                            | 1000 (37)                                   |
| Magnesium-28     | 12                            | 10 (.37)                                    |
| Manganese-51     | 25                            | 1000 (37)                                   |
| Manganese-52     | 25                            | 10 (.37)                                    |
| Manganese-52m    | 25                            | 1000 (37)                                   |
| Manganese-53     | 25                            | 1000 (37)                                   |
| Manganese-54     | 25                            | 10 (.37)                                    |
| Manganese-56     | 25                            | 100 (3.7)                                   |
| Mendelevium-257  | 101                           | 100 (3.7)                                   |
| Mendelevium-258  | 101                           | 1 (.037)                                    |
| Mercury-193      | 80                            | 100 (3.7)                                   |
| Mercury-193m     | 80                            | 10 (.37)                                    |
| Mercury-194      | 80                            | 0.1 (.0037)                                 |
| Mercury-195      | 80                            | 100 (3.7)                                   |
| Mercury-195m     | 80                            | 100 (3.7)                                   |
| Mercury-197      | 80                            | 1000 (37)                                   |
| Mercury-197m     | 80                            | 1000 (37)                                   |
| Mercury-199m     | 80                            | 1000 (37)                                   |
| Mercury-203      | 80                            | 10 (.37)                                    |
| Molybdenum-101   | 42                            | 1000 (37)                                   |
| Molybdenum-90    | 42                            | 100 (3.7)                                   |
| Molybdenum-93    | 42                            | 100 (3.7)                                   |
| Molybdenum-93m   | 42                            | 10 (.37)                                    |
| Molybdenum-99    | 42                            | 100 (3.7)                                   |
| Neodymium-136    | 60                            | 1000 (37)                                   |
| Neodymium-138    | 60                            | 1000 (37)                                   |
| Neodymium-139    | 60                            | 1000 (37)                                   |
| Neodymium-139m   | 60                            | 100 (3.7)                                   |
| Neodymium-141    | 60                            | 1000 (37)                                   |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide           | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|----------------------------|-------------------------------|---------------------------------------------|
| Neodymium-147              | 60                            | 10 (.37)                                    |
| Neodymium-149              | 60                            | 100 (3.7)                                   |
| Neodymium-151              | 60                            | 1000 (37)                                   |
| Neptunium-232              | 93                            | 1000 (37)                                   |
| Neptunium-233              | 93                            | 1000 (37)                                   |
| Neptunium-234              | 93                            | 10 (.37)                                    |
| Neptunium-235              | 93                            | 1000 (37)                                   |
| Neptunium-236 (1.2 E 5 yr) | 93                            | 0.1 (.0037)                                 |
| Neptunium-236 (22.5 hr)    | 93                            | 100 (3.7)                                   |
| Neptunium-237              | 93                            | 0.01 (.00037)                               |
| Neptunium-238              | 93                            | 10 (.37)                                    |
| Neptunium-239              | 93                            | 100 (3.7)                                   |
| Neptunium-240              | 93                            | 100 (3.7)                                   |
| Nickel-56                  | 28                            | 10 (.37)                                    |
| Nickel-57                  | 28                            | 10 (.37)                                    |
| Nickel-59                  | 28                            | 100 (3.7)                                   |
| Nickel-63                  | 28                            | 100 (3.7)                                   |
| Nickel-65                  | 28                            | 100 (3.7)                                   |
| Nickel-66                  | 28                            | 10 (.37)                                    |
| Niobium-88                 | 41                            | 100 (3.7)                                   |
| Niobium-89 (122 min)       | 41                            | 100 (3.7)                                   |
| Niobium-89 (66 min)        | 41                            | 100 (3.7)                                   |
| Niobium-90                 | 41                            | 10 (.37)                                    |
| Niobium-93m                | 41                            | 100 (3.7)                                   |
| Niobium-94                 | 41                            | 10 (.37)                                    |
| Niobium-95                 | 41                            | 10 (.37)                                    |
| Niobium-95m                | 41                            | 100 (3.7)                                   |
| Niobium-96                 | 41                            | 10 (.37)                                    |
| Niobium-97                 | 41                            | 100 (3.7)                                   |
| Niobium-98                 | 41                            | 1000 (37)                                   |
| Osmium-180                 | 76                            | 1000 (37)                                   |
| Osmium-181                 | 76                            | 100 (3.7)                                   |
| Osmium-182                 | 76                            | 100 (3.7)                                   |
| Osmium-185                 | 76                            | 10 (.37)                                    |
| Osmium-189m                | 76                            | 1000 (37)                                   |
| Osmium-191                 | 76                            | 100 (3.7)                                   |
| Osmium-191m                | 76                            | 1000 (37)                                   |
| Osmium-193                 | 76                            | 100 (3.7)                                   |
| Osmium-194                 | 76                            | 1 (.037)                                    |
| Palladium-100              | 46                            | 100 (3.7)                                   |
| Palladium-101              | 46                            | 100 (3.7)                                   |
| Palladium-103              | 46                            | 100 (3.7)                                   |
| Palladium-107              | 46                            | 100 (3.7)                                   |
| Palladium-109              | 46                            | 1000 (37)                                   |
| Phosphorus-32              | 15                            | 0.1 (.0037)                                 |
| Phosphorus-33              | 15                            | 1 (.037)                                    |
| Platinum-186               | 78                            | 100 (3.7)                                   |
| Platinum-188               | 78                            | 100 (3.7)                                   |
| Platinum-189               | 78                            | 100 (3.7)                                   |
| Platinum-191               | 78                            | 100 (3.7)                                   |
| Platinum-193               | 78                            | 1000 (37)                                   |
| Platinum-193m              | 78                            | 100 (3.7)                                   |
| Platinum-195m              | 78                            | 100 (3.7)                                   |
| Platinum-197               | 78                            | 1000 (37)                                   |
| Platinum-197m              | 78                            | 1000 (37)                                   |
| Platinum-199               | 78                            | 1000 (37)                                   |
| Platinum-200               | 78                            | 100 (3.7)                                   |
| Plutonium-234              | 94                            | 1000 (37)                                   |
| Plutonium-235              | 94                            | 1000 (37)                                   |
| Plutonium-236              | 94                            | 0.1 (.0037)                                 |
| Plutonium-237              | 94                            | 1000 (37)                                   |
| Plutonium-238              | 94                            | 0.01 (.00037)                               |
| Plutonium-239              | 94                            | 0.01 (.00037)                               |
| Plutonium-240              | 94                            | 0.01 (.00037)                               |
| Plutonium-241              | 94                            | 1 (.037)                                    |
| Plutonium-242              | 94                            | 0.01 (.00037)                               |
| Plutonium-243              | 94                            | 1000 (37)                                   |
| Plutonium-244              | 94                            | 0.01 (.00037)                               |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide            | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|-----------------------------|-------------------------------|---------------------------------------------|
| Plutonium-245 .....         | 94                            | 100 (3.7)                                   |
| Polonium-203 .....          | 84                            | 100 (3.7)                                   |
| Polonium-205 .....          | 84                            | 100 (3.7)                                   |
| Polonium-207 .....          | 84                            | 10 (.37)                                    |
| Polonium-210 .....          | 84                            | 0.01 (.00037)                               |
| Potassium-40 .....          | 19                            | 1 (.037)                                    |
| Potassium-42 .....          | 19                            | 100 (3.7)                                   |
| Potassium-43 .....          | 19                            | 10 (.37)                                    |
| Potassium-44 .....          | 19                            | 100 (3.7)                                   |
| Potassium-45 .....          | 19                            | 1000 (37)                                   |
| Praseodymium-136 .....      | 59                            | 1000 (37)                                   |
| Praseodymium-137 .....      | 59                            | 1000 (37)                                   |
| Praseodymium-138m .....     | 59                            | 100 (3.7)                                   |
| Praseodymium-139 .....      | 59                            | 1000 (37)                                   |
| Praseodymium-142 .....      | 59                            | 100 (3.7)                                   |
| Praseodymium-142m .....     | 59                            | 1000 (37)                                   |
| Praseodymium-143 .....      | 59                            | 10 (.37)                                    |
| Praseodymium-144 .....      | 59                            | 1000 (37)                                   |
| Praseodymium-145 .....      | 59                            | 1000 (37)                                   |
| Praseodymium-147 .....      | 59                            | 1000 (37)                                   |
| Promethium-141 .....        | 61                            | 1000 (37)                                   |
| Promethium-143 .....        | 61                            | 100 (3.7)                                   |
| Promethium-144 .....        | 61                            | 10 (.37)                                    |
| Promethium-145 .....        | 61                            | 100 (3.7)                                   |
| Promethium-146 .....        | 61                            | 10 (.37)                                    |
| Promethium-147 .....        | 61                            | 10 (.37)                                    |
| Promethium-148 .....        | 61                            | 10 (.37)                                    |
| Promethium-148m .....       | 61                            | 10 (.37)                                    |
| Promethium-149 .....        | 61                            | 100 (3.7)                                   |
| Promethium-150 .....        | 61                            | 100 (3.7)                                   |
| Promethium-151 .....        | 61                            | 100 (3.7)                                   |
| Protactinium-227 .....      | 91                            | 100 (3.7)                                   |
| Protactinium-228 .....      | 91                            | 10 (.37)                                    |
| Protactinium-230 .....      | 91                            | 10 (.37)                                    |
| Protactinium-231 .....      | 91                            | 0.01 (.00037)                               |
| Protactinium-232 .....      | 91                            | 10 (.37)                                    |
| Protactinium-233 .....      | 91                            | 100 (3.7)                                   |
| Protactinium-234 .....      | 91                            | 10 (.37)                                    |
| RADIONUCLIDES \$† .....     |                               | 1 (.037)                                    |
| Radium-223 .....            | 88                            | 1 (.037)                                    |
| Radium-224 .....            | 88                            | 10 (.37)                                    |
| Radium-225 .....            | 88                            | 1 (.037)                                    |
| Radium-226 ** .....         | 88                            | 0.1 (.0037)                                 |
| Radium-227 .....            | 88                            | 1000 (37)                                   |
| Radium-228 .....            | 88                            | 0.1 (.0037)                                 |
| Radon-220 .....             | 86                            | 0.1 (.0037)                                 |
| Radon-222 .....             | 86                            | 0.1 (.0037)                                 |
| Rhenium-177 .....           | 75                            | 1000 (37)                                   |
| Rhenium-178 .....           | 75                            | 1000 (37)                                   |
| Rhenium-181 .....           | 75                            | 100 (3.7)                                   |
| Rhenium-182 (12.7 hr) ..... | 75                            | 10 (.37)                                    |
| Rhenium-182 (64.0 hr) ..... | 75                            | 10 (.37)                                    |
| Rhenium-184 .....           | 75                            | 10 (.37)                                    |
| Rhenium-184m .....          | 75                            | 10 (.37)                                    |
| Rhenium-186 .....           | 75                            | 100 (3.7)                                   |
| Rhenium-186m .....          | 75                            | 10 (.37)                                    |
| Rhenium-187 .....           | 75                            | 1000 (37)                                   |
| Rhenium-188 .....           | 75                            | 1000 (37)                                   |
| Rhenium-188m .....          | 75                            | 1000 (37)                                   |
| Rhenium-189 .....           | 75                            | 1000 (37)                                   |
| Rhodium-100 .....           | 45                            | 10 (.37)                                    |
| Rhodium-101 .....           | 45                            | 10 (.37)                                    |
| Rhodium-101m .....          | 45                            | 100 (3.7)                                   |
| Rhodium-102 .....           | 45                            | 10 (.37)                                    |
| Rhodium-102m .....          | 45                            | 10 (.37)                                    |
| Rhodium-103m .....          | 45                            | 1000 (37)                                   |
| Rhodium-105 .....           | 45                            | 100 (3.7)                                   |
| Rhodium-106m .....          | 45                            | 10 (.37)                                    |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide    | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|---------------------|-------------------------------|---------------------------------------------|
| Rhodium-107 .....   | 45                            | 1000 (37)                                   |
| Rhodium-99 .....    | 45                            | 10 (.37)                                    |
| Rhodium-99m .....   | 45                            | 100 (3.7)                                   |
| Rubidium-79 .....   | 37                            | 1000 (37)                                   |
| Rubidium-81 .....   | 37                            | 100 (3.7)                                   |
| Rubidium-81m .....  | 37                            | 1000 (37)                                   |
| Rubidium-82m .....  | 37                            | 10 (.37)                                    |
| Rubidium-83 .....   | 37                            | 10 (.37)                                    |
| Rubidium-84 .....   | 37                            | 10 (.37)                                    |
| Rubidium-86 .....   | 37                            | 10 (.37)                                    |
| Rubidium-87 .....   | 37                            | 10 (.37)                                    |
| Rubidium-88 .....   | 37                            | 1000 (37)                                   |
| Rubidium-89 .....   | 37                            | 1000 (37)                                   |
| Ruthenium-103 ..... | 44                            | 10 (.37)                                    |
| Ruthenium-105 ..... | 44                            | 100 (3.7)                                   |
| Ruthenium-106 ..... | 44                            | 1 (.037)                                    |
| Ruthenium-94 .....  | 44                            | 1000 (37)                                   |
| Ruthenium-97 .....  | 44                            | 100 (3.7)                                   |
| Samarium-141 .....  | 62                            | 1000 (37)                                   |
| Samarium-141m ..... | 62                            | 1000 (37)                                   |
| Samarium-142 .....  | 62                            | 1000 (37)                                   |
| Samarium-145 .....  | 62                            | 100 (3.7)                                   |
| Samarium-146 .....  | 62                            | 0.01 (.00037)                               |
| Samarium-147 .....  | 62                            | 0.01 (.00037)                               |
| Samarium-151 .....  | 62                            | 10 (.37)                                    |
| Samarium-153 .....  | 62                            | 100 (3.7)                                   |
| Samarium-155 .....  | 62                            | 1000 (37)                                   |
| Samarium-156 .....  | 62                            | 100 (3.7)                                   |
| Scandium-43 .....   | 21                            | 1000 (37)                                   |
| Scandium-44 .....   | 21                            | 100 (3.7)                                   |
| Scandium-44m .....  | 21                            | 10 (.37)                                    |
| Scandium-46 .....   | 21                            | 10 (.37)                                    |
| Scandium-47 .....   | 21                            | 100 (3.7)                                   |
| Scandium-48 .....   | 21                            | 10 (.37)                                    |
| Scandium-49 .....   | 21                            | 1000 (37)                                   |
| Selenium-70 .....   | 34                            | 1000 (37)                                   |
| Selenium-73 .....   | 34                            | 10 (.37)                                    |
| Selenium-73m .....  | 34                            | 100 (3.7)                                   |
| Selenium-75 .....   | 34                            | 10 (.37)                                    |
| Selenium-79 .....   | 34                            | 10 (.37)                                    |
| Selenium-81 .....   | 34                            | 1000 (37)                                   |
| Selenium-81m .....  | 34                            | 1000 (37)                                   |
| Selenium-83 .....   | 34                            | 1000 (37)                                   |
| Silicon-31 .....    | 14                            | 1000 (37)                                   |
| Silicon-32 .....    | 14                            | 1 (.037)                                    |
| Silver-102 .....    | 47                            | 100 (3.7)                                   |
| Silver-103 .....    | 47                            | 1000 (37)                                   |
| Silver-104 .....    | 47                            | 1000 (37)                                   |
| Silver-104m .....   | 47                            | 1000 (37)                                   |
| Silver-105 .....    | 47                            | 10 (.37)                                    |
| Silver-106 .....    | 47                            | 1000 (37)                                   |
| Silver-106m .....   | 47                            | 10 (.37)                                    |
| Silver-108m .....   | 47                            | 10 (.37)                                    |
| Silver-110m .....   | 47                            | 10 (.37)                                    |
| Silver-111 .....    | 47                            | 10 (.37)                                    |
| Silver-112 .....    | 47                            | 100 (3.7)                                   |
| Silver-115 .....    | 47                            | 1000 (37)                                   |
| Sodium-22 .....     | 11                            | 10 (.37)                                    |
| Sodium-24 .....     | 11                            | 10 (.37)                                    |
| Strontium-80 .....  | 38                            | 100 (3.7)                                   |
| Strontium-81 .....  | 38                            | 1000 (37)                                   |
| Strontium-83 .....  | 38                            | 100 (3.7)                                   |
| Strontium-85 .....  | 38                            | 10 (.37)                                    |
| Strontium-85m ..... | 38                            | 1000 (37)                                   |
| Strontium-87m ..... | 38                            | 100 (3.7)                                   |
| Strontium-89 .....  | 38                            | 10 (.37)                                    |
| Strontium-90 .....  | 38                            | 0.1 (.0037)                                 |
| Strontium-91 .....  | 38                            | 10 (.37)                                    |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide             | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|------------------------------|-------------------------------|---------------------------------------------|
| Strontium-92 .....           | 38                            | 100 (3.7)                                   |
| Sulfur-35 .....              | 16                            | 1 (.037)                                    |
| Tantalum-172 .....           | 73                            | 100 (3.7)                                   |
| Tantalum-173 .....           | 73                            | 100 (3.7)                                   |
| Tantalum-174 .....           | 73                            | 100 (3.7)                                   |
| Tantalum-175 .....           | 73                            | 100 (3.7)                                   |
| Tantalum-176 .....           | 73                            | 10 (.37)                                    |
| Tantalum-177 .....           | 73                            | 1000 (37)                                   |
| Tantalum-178 .....           | 73                            | 1000 (37)                                   |
| Tantalum-179 .....           | 73                            | 1000 (37)                                   |
| Tantalum-180 .....           | 73                            | 100 (3.7)                                   |
| Tantalum-180m .....          | 73                            | 1000 (37)                                   |
| Tantalum-182 .....           | 73                            | 10 (.37)                                    |
| Tantalum-182m .....          | 73                            | 1000 (37)                                   |
| Tantalum-183 .....           | 73                            | 100 (3.7)                                   |
| Tantalum-184 .....           | 73                            | 10 (.37)                                    |
| Tantalum-185 .....           | 73                            | 1000 (37)                                   |
| Tantalum-186 .....           | 73                            | 1000 (37)                                   |
| Technetium-101 .....         | 43                            | 1000 (37)                                   |
| Technetium-104 .....         | 43                            | 1000 (37)                                   |
| Technetium-93 .....          | 43                            | 100 (3.7)                                   |
| Technetium-93m .....         | 43                            | 1000 (37)                                   |
| Technetium-94 .....          | 43                            | 10 (.37)                                    |
| Technetium-94m .....         | 43                            | 100 (3.7)                                   |
| Technetium-96 .....          | 43                            | 10 (.37)                                    |
| Technetium-96m .....         | 43                            | 1000 (37)                                   |
| Technetium-97 .....          | 43                            | 100 (3.7)                                   |
| Technetium-97m .....         | 43                            | 100 (3.7)                                   |
| Technetium-98 .....          | 43                            | 10 (.37)                                    |
| Technetium-99 .....          | 43                            | 10 (.37)                                    |
| Technetium-99m .....         | 43                            | 100 (3.7)                                   |
| Tellurium-116 .....          | 52                            | 1000 (37)                                   |
| Tellurium-121 .....          | 52                            | 10 (.37)                                    |
| Tellurium-121m .....         | 52                            | 10 (.37)                                    |
| Tellurium-123 .....          | 52                            | 10 (.37)                                    |
| Tellurium-123m .....         | 52                            | 10 (.37)                                    |
| Tellurium-125m .....         | 52                            | 10 (.37)                                    |
| Tellurium-127 .....          | 52                            | 1000 (37)                                   |
| Tellurium-127m .....         | 52                            | 10 (.37)                                    |
| Tellurium-129 .....          | 52                            | 1000 (37)                                   |
| Tellurium-129m .....         | 52                            | 10 (.37)                                    |
| Tellurium-131 .....          | 52                            | 1000 (37)                                   |
| Tellurium-131m .....         | 52                            | 10 (.37)                                    |
| Tellurium-132 .....          | 52                            | 10 (.37)                                    |
| Tellurium-133 .....          | 52                            | 1000 (37)                                   |
| Tellurium-133m .....         | 52                            | 1000 (37)                                   |
| Tellurium-134 .....          | 52                            | 1000 (37)                                   |
| Terbium-147 .....            | 65                            | 100 (3.7)                                   |
| Terbium-149 .....            | 65                            | 100 (3.7)                                   |
| Terbium-150 .....            | 65                            | 100 (3.7)                                   |
| Terbium-151 .....            | 65                            | 10 (.37)                                    |
| Terbium-153 .....            | 65                            | 100 (3.7)                                   |
| Terbium-154 .....            | 65                            | 10 (.37)                                    |
| Terbium-155 .....            | 65                            | 100 (3.7)                                   |
| Terbium-156 .....            | 65                            | 10 (.37)                                    |
| Terbium-156m (24.4 hr) ..... | 65                            | 1000 (37)                                   |
| Terbium-156m (5.0 hr) .....  | 65                            | 1000 (37)                                   |
| Terbium-157 .....            | 65                            | 100 (3.7)                                   |
| Terbium-158 .....            | 65                            | 10 (.37)                                    |
| Terbium-160 .....            | 65                            | 10 (.37)                                    |
| Terbium-161 .....            | 65                            | 100 (3.7)                                   |
| Thallium-194 .....           | 81                            | 1000 (37)                                   |
| Thallium-194m .....          | 81                            | 100 (3.7)                                   |
| Thallium-195 .....           | 81                            | 100 (3.7)                                   |
| Thallium-197 .....           | 81                            | 100 (3.7)                                   |
| Thallium-198 .....           | 81                            | 10 (.37)                                    |
| Thallium-198m .....          | 81                            | 100 (3.7)                                   |
| Thallium-199 .....           | 81                            | 100 (3.7)                                   |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide                           | (2)—<br>Atomic<br>Num-<br>ber | (3)—Reportable<br>Quantity (RQ)<br>Ci (TBq) |
|--------------------------------------------|-------------------------------|---------------------------------------------|
| Thallium-200 .....                         | 81                            | 10 (.37)                                    |
| Thallium-201 .....                         | 81                            | 1000 (37)                                   |
| Thallium-202 .....                         | 81                            | 10 (.37)                                    |
| Thallium-204 .....                         | 81                            | 10 (.37)                                    |
| Thorium (Irradiated) .....                 | 90                            | ***                                         |
| Thorium (Natural) .....                    | 90                            | **                                          |
| Thorium-226 .....                          | 90                            | 100 (3.7)                                   |
| Thorium-227 .....                          | 90                            | 1 (.037)                                    |
| Thorium-228 .....                          | 90                            | 0.01 (.00037)                               |
| Thorium-229 .....                          | 90                            | 0.001 (.00037)                              |
| Thorium-230 .....                          | 90                            | 0.01 (.00037)                               |
| Thorium-231 .....                          | 90                            | 100 (3.7)                                   |
| Thorium-232 ** .....                       | 90                            | 0.001 (.00037)                              |
| Thorium-234 .....                          | 90                            | 100 (3.7)                                   |
| Thulium-162 .....                          | 69                            | 1000 (37)                                   |
| Thulium-166 .....                          | 69                            | 10 (.37)                                    |
| Thulium-167 .....                          | 69                            | 100 (3.7)                                   |
| Thulium-170 .....                          | 69                            | 10 (.37)                                    |
| Thulium-171 .....                          | 69                            | 100 (3.7)                                   |
| Thulium-172 .....                          | 69                            | 100 (3.7)                                   |
| Thulium-173 .....                          | 69                            | 100 (3.7)                                   |
| Thulium-175 .....                          | 69                            | 1000 (37)                                   |
| Tin-110 .....                              | 50                            | 100 (3.7)                                   |
| Tin-111 .....                              | 50                            | 1000 (37)                                   |
| Tin-113 .....                              | 50                            | 10 (.37)                                    |
| Tin-117m .....                             | 50                            | 100 (3.7)                                   |
| Tin-119m .....                             | 50                            | 10 (.37)                                    |
| Tin-121 .....                              | 50                            | 1000 (37)                                   |
| Tin-121m .....                             | 50                            | 10 (.37)                                    |
| Tin-123 .....                              | 50                            | 10 (.37)                                    |
| Tin-123m .....                             | 50                            | 1000 (37)                                   |
| Tin-125 .....                              | 50                            | 10 (.37)                                    |
| Tin-126 .....                              | 50                            | 1 (.037)                                    |
| Tin-127 .....                              | 50                            | 100 (3.7)                                   |
| Tin-128 .....                              | 50                            | 1000 (37)                                   |
| Titanium-44 .....                          | 22                            | 1 (.037)                                    |
| Titanium-45 .....                          | 22                            | 1000 (37)                                   |
| Tungsten-176 .....                         | 74                            | 1000 (37)                                   |
| Tungsten-177 .....                         | 74                            | 100 (3.7)                                   |
| Tungsten-178 .....                         | 74                            | 100 (3.7)                                   |
| Tungsten-179 .....                         | 74                            | 1000 (37)                                   |
| Tungsten-181 .....                         | 74                            | 100 (3.7)                                   |
| Tungsten-185 .....                         | 74                            | 10 (.37)                                    |
| Tungsten-187 .....                         | 74                            | 100 (3.7)                                   |
| Tungsten-188 .....                         | 74                            | 10 (.37)                                    |
| Uranium (Depleted) .....                   | 92                            | ***                                         |
| Uranium (Irradiated) .....                 | 92                            | ***                                         |
| Uranium (Natural) .....                    | 92                            | **                                          |
| Uranium Enriched 20% or great-<br>er ..... | 92                            | ***                                         |
| Uranium Enriched less than<br>20% .....    | 92                            | ***                                         |
| Uranium-230 .....                          | 92                            | 1 (.037)                                    |
| Uranium-231 .....                          | 92                            | 1000 (37)                                   |
| Uranium-232 .....                          | 92                            | 0.01 (.00037)                               |
| Uranium-233 .....                          | 92                            | 0.1 (.0037)                                 |
| Uranium-234 ** .....                       | 92                            | 0.1 (.0037)                                 |
| Uranium-235 ** .....                       | 92                            | 0.1 (.0037)                                 |
| Uranium-236 .....                          | 92                            | 0.1 (.0037)                                 |
| Uranium-237 .....                          | 92                            | 100 (3.7)                                   |
| Uranium-238 ** .....                       | 92                            | 0.1 (.0037)                                 |
| Uranium-239 .....                          | 92                            | 1000 (37)                                   |
| Uranium-240 .....                          | 92                            | 1000 (37)                                   |
| Vanadium-47 .....                          | 23                            | 1000 (37)                                   |
| Vanadium-48 .....                          | 23                            | 10 (.37)                                    |
| Vanadium-49 .....                          | 23                            | 1000 (37)                                   |
| Xenon-120 .....                            | 54                            | 100 (3.7)                                   |
| Xenon-121 .....                            | 54                            | 10 (.37)                                    |

TABLE 2 TO APPENDIX A—RADIONUCLIDES—  
Continued

| (1)—Radionuclide    | (2)—Atomic Number | (3)—Reportable Quantity (RQ) Ci (TBq) |
|---------------------|-------------------|---------------------------------------|
| Xenon-122 .....     | 54                | 100 (3.7)                             |
| Xenon-123 .....     | 54                | 10 (.37)                              |
| Xenon-125 .....     | 54                | 100 (3.7)                             |
| Xenon-127 .....     | 54                | 100 (3.7)                             |
| Xenon-129m .....    | 54                | 1000 (37)                             |
| Xenon-131m .....    | 54                | 1000 (37)                             |
| Xenon-133 .....     | 54                | 1000 (37)                             |
| Xenon-133m .....    | 54                | 1000 (37)                             |
| Xenon-135 .....     | 54                | 100 (3.7)                             |
| Xenon-135m .....    | 54                | 10 (.37)                              |
| Xenon-138 .....     | 54                | 10 (.37)                              |
| Ytterbium-162 ..... | 70                | 1000 (37)                             |
| Ytterbium-166 ..... | 70                | 10 (.37)                              |
| Ytterbium-167 ..... | 70                | 1000 (37)                             |
| Ytterbium-169 ..... | 70                | 10 (.37)                              |
| Ytterbium-175 ..... | 70                | 100 (3.7)                             |
| Ytterbium-177 ..... | 70                | 1000 (37)                             |
| Ytterbium-178 ..... | 70                | 1000 (37)                             |
| Yttrium-86 .....    | 39                | 10 (.37)                              |
| Yttrium-86m .....   | 39                | 1000 (37)                             |
| Yttrium-87 .....    | 39                | 10 (.37)                              |
| Yttrium-88 .....    | 39                | 10 (.37)                              |
| Yttrium-90 .....    | 39                | 10 (.37)                              |
| Yttrium-90m .....   | 39                | 100 (3.7)                             |
| Yttrium-91 .....    | 39                | 10 (.37)                              |
| Yttrium-91m .....   | 39                | 1000 (37)                             |
| Yttrium-92 .....    | 39                | 100 (3.7)                             |
| Yttrium-93 .....    | 39                | 100 (3.7)                             |
| Yttrium-94 .....    | 39                | 1000 (37)                             |
| Yttrium-95 .....    | 39                | 1000 (37)                             |
| Zinc-62 .....       | 30                | 100 (3.7)                             |
| Zinc-63 .....       | 30                | 1000 (37)                             |
| Zinc-65 .....       | 30                | 10 (.37)                              |
| Zinc-69 .....       | 30                | 1000 (37)                             |
| Zinc-69m .....      | 30                | 100 (3.7)                             |
| Zinc-71m .....      | 30                | 100 (3.7)                             |
| Zinc-72 .....       | 30                | 100 (3.7)                             |
| Zirconium-86 .....  | 40                | 100 (3.7)                             |
| Zirconium-88 .....  | 40                | 10 (.37)                              |
| Zirconium-89 .....  | 40                | 100 (3.7)                             |
| Zirconium-93 .....  | 40                | 1 (.037)                              |
| Zirconium-95 .....  | 40                | 10 (.37)                              |
| Zirconium-97 .....  | 40                | 10 (.37)                              |

\$The RQs for all radionuclides apply to chemical compounds containing the radionuclides and elemental forms regardless of the diameter of pieces of solid material.

†The RQ of one curie applies to all radionuclides not otherwise listed. Whenever the RQs in TABLE 1—HAZARDOUS SUBSTANCES OTHER THAN RADIONUCLIDES and this table conflict, the lowest RQ shall apply. For example, uranyl acetate and uranyl nitrate have RQs shown in TABLE 1 of 100 pounds, equivalent to about one-tenth the RQ level for uranium-238 in this table.

\*\*The method to determine the RQs for mixtures or solutions of radionuclides can be found in paragraph 7 of the note preceding TABLE 1 of this appendix. RQs for the following four common radionuclide mixtures are provided: radium-226 in secular equilibrium with its daughters (0.053 curie); natural uranium (0.1 curie); natural uranium in secular equilibrium with its daughters (0.052 curie); and natural thorium in secular equilibrium with its daughters (0.011 curie).

\*\*\*Indicates that the name was added by PHMSA because it appears in the list of radionuclides in 49 CFR 173.435. The reportable quantity (RQ), if not specifically listed elsewhere in this appendix, shall be determined in accordance with the procedures in paragraph 7 of this appendix.

APPENDIX B TO § 172.101—LIST OF MARINE  
POLLUTANTS

1. See § 171.4 of this subchapter for applicability to marine pollutants. This appendix lists potential marine pollutants as defined in § 171.8 of this subchapter.

2. Marine pollutants listed in this appendix are not necessarily listed by name in the § 172.101 Table. If a marine pollutant not listed by name or by synonym in the § 172.101 Table meets the definition of any hazard Class 1 through 8, then you must determine the class and division of the material in accordance with § 173.2a of this subchapter. You must also select the most appropriate hazardous material description and proper shipping name. If a marine pollutant not listed by name or by synonym in the § 172.101 Table does not meet the definition of any Class 1 through 8, then you must offer it for transportation under the most appropriate of the following two Class 9 entries: “Environmentally hazardous substances, liquid, n.o.s.,” UN3082, or “Environmentally hazardous substances, solid, n.o.s.” UN3077.

3. This appendix contains two columns. The first column, entitled “S.M.P.” (for severe marine pollutants), identifies whether a material is a severe marine pollutant. If the letters “PP” appear in this column for a material, the material is a severe marine pollutant, otherwise it is not. The second column, entitled “Marine Pollutant”, lists the marine pollutants.

4. If a material is not listed in this appendix and meets the criteria for a marine pollutant as provided in Chapter 2.10 of the IMDG Code, “Guidelines for the Identification of Harmful Substances in Packaged Form” (incorporated by reference; see § 171.7 of this subchapter), the material may be transported as a marine pollutant in accordance with the applicable requirements of this subchapter.

5. If a material listed in this appendix does not meet the criteria for a marine pollutant as provided in Chapter 2.10 of the IMDG Code, “Guidelines for the Identification of Harmful Substances in Packaged Form” (incorporated by reference; see § 171.7 of this subchapter), it may be excepted from the requirements of this subchapter as a marine pollutant if that exception is approved by the Associate Administrator.

## LIST OF MARINE POLLUTANTS

| S.M.P.<br>(1) | Marine pollutant<br>(2)                  |
|---------------|------------------------------------------|
|               | Acetone cyanohydrin, stabilized          |
|               | Acetylene tetrabromide                   |
|               | Acetylene tetrachloride                  |
|               | Acraldehyde, inhibited                   |
|               | Acrolein, inhibited                      |
|               | Acrolein, stabilized                     |
|               | Acrylic aldehyde, inhibited              |
|               | Alcohol C-12 - C-16 poly(1-6) ethoxylate |



§ 172.101

LIST OF MARINE POLLUTANTS—Continued

| S.M.P.<br>(1) | Marine pollutant<br>(2)                                                                                             |
|---------------|---------------------------------------------------------------------------------------------------------------------|
| PP            | Alcohol C-6 - C-17 (secondary)poly(3-6) ethoxylate                                                                  |
|               | Aldicarb                                                                                                            |
|               | Aldrin                                                                                                              |
|               | Alkyl (c12-c14) dimethylamine                                                                                       |
|               | Alkyl (c7-c9) nitrates                                                                                              |
|               | Alkybenzenesulphonates, branched and straight chain (excluding C11–C13 straight chain or branched chain homologues) |
|               | Allyl bromide                                                                                                       |
|               | ortho-Aminoanisole                                                                                                  |
|               | Aminocarb                                                                                                           |
|               | Ammonium dinitro-o-cresolate                                                                                        |
|               | n-Amylbenzene                                                                                                       |
| PP            | Azinphos-ethyl                                                                                                      |
| PP            | Azinphos-methyl                                                                                                     |
|               | Barium cyanide                                                                                                      |
|               | Bendiocarb                                                                                                          |
|               | Benomyl                                                                                                             |
|               | Benquinox                                                                                                           |
|               | Benzyl chlorocarbonate                                                                                              |
|               | Benzyl chloroformate                                                                                                |
| PP            | Binapacryl                                                                                                          |
|               | N,N-Bis (2-hydroxyethyl) oleamide (LOA)                                                                             |
| PP            | Brodifacoum                                                                                                         |
|               | Bromine cyanide                                                                                                     |
|               | Bromoacetone                                                                                                        |
|               | Bromoallylene                                                                                                       |
|               | Bromobenzene                                                                                                        |
|               | ortho-Bromobenzyl cyanide                                                                                           |
|               | Bromocycane                                                                                                         |
|               | Bromoform                                                                                                           |
| PP            | Bromophos-ethyl                                                                                                     |
|               | 3-Bromopropene                                                                                                      |
|               | Bromoxynil                                                                                                          |
|               | Butanedione                                                                                                         |
|               | 2-Butenal, stabilized                                                                                               |
|               | Butyl benzyl phthalate                                                                                              |
|               | N-tert-butyl-N-cyclopropyl-6-methylthio-1,3,5-triazine-2,4-diamine                                                  |
|               | 2,4-Di-tert-butylphenol                                                                                             |
| PP            | 2, 6-Di-tert-Butylphenol                                                                                            |
|               | para-tertiary-butyltoluene                                                                                          |
| PP            | Cadmium compounds                                                                                                   |
|               | Cadmium sulphide                                                                                                    |
|               | Calcium arsenate                                                                                                    |
|               | Calcium arsenate and calcium arsenite, mixtures, solid                                                              |
| PP            | Calcium cyanide                                                                                                     |
|               | Camphochlor                                                                                                         |
|               | Carbaryl                                                                                                            |
|               | Carbendazim                                                                                                         |
|               | Carbofuran                                                                                                          |
|               | Carbon tetrabromide                                                                                                 |
| PP            | Carbon tetrachloride                                                                                                |
|               | Carbophenothion                                                                                                     |
| PP            | Cartap hydrochloride                                                                                                |
|               | Chlordane                                                                                                           |
|               | Chlorfenvinphos                                                                                                     |
| PP            | Chlorinated paraffins (C-10 - C-13)                                                                                 |
| PP            | Chlorinated paraffins (C14–C17), with more than 1% shorter chain length                                             |
|               | Chlorine                                                                                                            |
|               | Chlorine cyanide, inhibited                                                                                         |
|               | Chlormephos                                                                                                         |
|               | Chloroacetone, stabilized                                                                                           |
|               | 1-Chloro-2,3-Epoxypropane                                                                                           |
|               | 2-Chloro-6-nitrotoluene                                                                                             |
|               | 4-Chloro-2-nitrotoluene                                                                                             |
|               | Chloro-ortho-nitrotoluene                                                                                           |
|               | 2-Chloro-5-trifluoromethylnitrobenzene                                                                              |
|               | para-Chlorobenzyl chloride, liquid or solid                                                                         |

49 CFR Ch. I (10–1–08 Edition)

LIST OF MARINE POLLUTANTS—Continued

| S.M.P.<br>(1) | Marine pollutant<br>(2)                |
|---------------|----------------------------------------|
|               | Chlorodinitrobenzenes, liquid or solid |
|               | 1-Chloroheptane                        |
|               | 1-Chlorohexane                         |
|               | Chloronitroanilines                    |
|               | Chloronitrotoluenes, liquid            |
|               | Chloronitrotoluenes, solid             |
|               | 1-Chlorooctane                         |
| PP            | Chlorophenolates, liquid               |
| PP            | Chlorophenolates, solid                |
|               | Chlorophenyltrichlorosilane            |
|               | Chloropicrin                           |
|               | alpha-Chloropropylene                  |
|               | Chlorotoluenes (meta-;para-)           |
| PP            | Chlorpyrifos                           |
| PP            | Chlorthiophos                          |
|               | Cocculus                               |
|               | Coconitrile                            |
|               | Copper acetoarsenite                   |
|               | Copper arsenite                        |
|               | Copper chloride                        |
| PP            | Copper chloride solution               |
| PP            | Copper cyanide                         |
| PP            | Copper metal powder                    |
| PP            | Copper sulphate, anhydrous, hydrates   |
|               | Coumachlor                             |
| PP            | Coumaphos                              |
|               | Cresyl diphenyl phosphate              |
|               | Crotonaldehyde, stabilized             |
|               | Crotonic aldehyde, stabilized          |
|               | Crotoxyphos                            |
|               | Cupric arsenite                        |
| PP            | Cupric chloride                        |
| PP            | Cupric cyanide                         |
| PP            | Cupric sulfate                         |
|               | Cupriethylenediamine solution          |
| PP            | Cuprous chloride                       |
|               | Cyanide mixtures                       |
|               | Cyanide solutions                      |
|               | Cyanides, inorganic, n.o.s.            |
|               | Cyanogen bromide                       |
|               | Cyanogen chloride, inhibited           |
|               | Cyanogen chloride, stabilized          |
|               | Cyanophos                              |
| PP            | 1,5,9-Cyclododecatriene                |
| PP            | Cyhexatin                              |
| PP            | Cyrenes (o-;m-;p-)                     |
| PP            | Cypermethrin                           |
|               | Decyl acrylate                         |
| PP            | DDT                                    |
|               | Decyloxytetrahydrothiophene dioxide    |
|               | DEF                                    |
|               | Desmedipham                            |
|               | Di-allate                              |
|               | Di-n-Butyl phthalate                   |
| PP            | Dialifos                               |
|               | 4,4'-Diaminodiphenylmethane            |
| PP            | Diazinon                               |
|               | 1,3-Dibromobenzene                     |
| PP            | Dichlofenthion                         |
|               | Dichloroanilines                       |
|               | 1,3-Dichlorobenzene                    |
|               | 1,4-Dichlorobenzene                    |
|               | Dichlorobenzene (meta-; para-)         |
|               | 2,2-Dichlorodiethyl ether              |
|               | Dichlorodimethyl ether, symmetrical    |
|               | Di-(2-chloroethyl) ether               |
|               | 1,1-Dichloroethylene, inhibited        |
|               | 1,6-Dichlorohexane                     |
|               | Dichlorophenyltrichlorosilane          |
|               | Dichlorvos                             |
| PP            | Diclofop-methyl                        |

| LIST OF MARINE POLLUTANTS—Continued |                                                                                                 | LIST OF MARINE POLLUTANTS—Continued |                                                                                                                |
|-------------------------------------|-------------------------------------------------------------------------------------------------|-------------------------------------|----------------------------------------------------------------------------------------------------------------|
| S.M.P.<br>(1)                       | Marine pollutant<br>(2)                                                                         | S.M.P.<br>(1)                       | Marine pollutant<br>(2)                                                                                        |
| PP                                  | Dicrotophos                                                                                     |                                     | Ferric arsenite                                                                                                |
|                                     | Dieldrin                                                                                        |                                     | Ferrous arsenate                                                                                               |
|                                     | Diisopropylbenzenes                                                                             | PP                                  | Fonofos                                                                                                        |
|                                     | Diisopropylnaphthalenes, mixed isomers                                                          |                                     | Formetanate                                                                                                    |
| PP                                  | Dimethoate                                                                                      | PP                                  | Furathiocarb (ISO)                                                                                             |
| PP                                  | N,N-Dimethyldodecylamine                                                                        | PP                                  | gamma-BHC                                                                                                      |
|                                     | Dimethylhydrazine, symmetrical                                                                  |                                     | Gasoline, leaded                                                                                               |
|                                     | Dimethylhydrazine, unsymmetrical                                                                | PP                                  | Heptachlor                                                                                                     |
|                                     | Dinitro-o-cresol, <i>solid</i>                                                                  |                                     | Heptenophos                                                                                                    |
|                                     | Dinitro-o-cresol, <i>solution</i>                                                               |                                     | n-Heptaldehyde                                                                                                 |
|                                     | Dinitrochlorobenzenes, liquid or solid                                                          |                                     | n-Heptylbenzene                                                                                                |
|                                     | Dinitrophenol, <i>dry or wetted with less than 15 per cent water, by mass</i>                   |                                     | normal-Heptyl chloride                                                                                         |
|                                     | Dinitrophenol solutions                                                                         | PP                                  | Hexachlorobutadiene                                                                                            |
|                                     | Dinitrophenol, wetted with not less than 15 per cent water, by mass                             | PP                                  | 1,3-Hexachlorobutadiene                                                                                        |
|                                     | Dinitrophenolates <i>alkali metals, dry or wetted with less than 15 per cent water, by mass</i> |                                     | Hexaethyl tetraphosphate <i>liquid</i>                                                                         |
|                                     | Dinitrophenolates, wetted with not less than 15 per cent water, by mass                         |                                     | Hexaethyl tetraphosphate, <i>solid</i>                                                                         |
|                                     | Dinobuton                                                                                       |                                     | normal-Hexyl chloride                                                                                          |
|                                     | Dinoseb                                                                                         |                                     | n-Hexylbenzene                                                                                                 |
|                                     | Dinoseb acetate                                                                                 |                                     | Hydrocyanic acid, anhydrous, stabilized, containing less than 3% water                                         |
|                                     | Dioxacarb                                                                                       |                                     | Hydrocyanic acid, anhydrous, stabilized, containing less than 3% water and absorbed in a porous inert material |
|                                     | Dioxathion                                                                                      |                                     | Hydrocyanic acid, aqueous solutions <i>not more than 20% hydrocyanic acid</i>                                  |
|                                     | Dipentene                                                                                       |                                     | Hydrogen cyanide solution in alcohol, <i>with not more than 45% hydrogen cyanide</i>                           |
|                                     | Diphacinone                                                                                     |                                     | Hydrogen cyanide, stabilized <i>with less than 3% water</i>                                                    |
|                                     | Diphenyl                                                                                        |                                     | Hydrogen cyanide, stabilized <i>with less than 3% water and absorbed in a porous inert material</i>            |
| PP                                  | Diphenylamine chloroarsine                                                                      |                                     | Hydroxydimethylbenzenes, liquid or solid                                                                       |
| PP                                  | Diphenylchloroarsine, solid or liquid                                                           |                                     | Ioxynil                                                                                                        |
|                                     | Disulfoton                                                                                      |                                     | Isobenzan                                                                                                      |
|                                     | 1,4-Di-tert-butylbenzene                                                                        |                                     | Isobutyl butyrate                                                                                              |
|                                     | DNOC                                                                                            |                                     | Isobutylbenzene                                                                                                |
|                                     | DNOC (pesticide)                                                                                |                                     | Isodecyl acrylate                                                                                              |
|                                     | Dodecyl diphenyl oxide disulphonate                                                             |                                     | Isodecyl diphenyl phosphate                                                                                    |
| PP                                  | Dodecyl hydroxypropyl sulfide                                                                   |                                     | Isofenphos                                                                                                     |
|                                     | 1-Dodecylamine                                                                                  |                                     | Isooctyl nitrate                                                                                               |
| PP                                  | Dodecylphenol                                                                                   |                                     | Isoprocarb                                                                                                     |
|                                     | Drazoxolon                                                                                      |                                     | Isopropenylbenzene                                                                                             |
|                                     | Edifenphos                                                                                      |                                     | Isotetramethylbenzene                                                                                          |
| PP                                  | Endosulfan                                                                                      |                                     | Isoxathion                                                                                                     |
| PP                                  | Endrin                                                                                          |                                     | Lead acetate                                                                                                   |
|                                     | Epibromohydrin                                                                                  |                                     | Lead arsenates                                                                                                 |
|                                     | Epichlorohydrin                                                                                 | PP                                  | Lead arsenites                                                                                                 |
| PP                                  | EPN                                                                                             |                                     | Lead compounds, soluble, n.o.s.                                                                                |
| PP                                  | Esfenvalerate                                                                                   |                                     | Lead cyanide                                                                                                   |
| PP                                  | Ethion                                                                                          |                                     | Lead nitrate                                                                                                   |
|                                     | Ethoprophos                                                                                     |                                     | Lead perchlorate, solid or solution                                                                            |
|                                     | Ethyl fluid                                                                                     |                                     | Lead tetraethyl                                                                                                |
|                                     | Ethyl mercaptan                                                                                 |                                     | Lead tetramethyl                                                                                               |
|                                     | 2-Ethylhexyl nitrate                                                                            |                                     | Lindane                                                                                                        |
|                                     | 5-Ethyl-2-picoline                                                                              |                                     | Linuron                                                                                                        |
|                                     | Ethyl propenoate, inhibited                                                                     |                                     | London Purple                                                                                                  |
|                                     | 2-Ethyl-3-propylacrolein                                                                        |                                     | Magnesium arsenate                                                                                             |
|                                     | Ethyl tetraphosphate                                                                            | PP                                  | Malathion                                                                                                      |
|                                     | Ethylchloroarsine                                                                               |                                     | Mancozeb (ISO)                                                                                                 |
|                                     | Ethylene dibromide and methyl bromide mixtures, liquid                                          |                                     | Maneb                                                                                                          |
|                                     | 2-Ethylhexaldehyde                                                                              |                                     | Maneb preparations <i>with not less than 60% maneb</i>                                                         |
| PP                                  | Fenamiphos                                                                                      |                                     | Maneb preparation, stabilized against self-heating                                                             |
| PP                                  | Fenbutatin oxide                                                                                |                                     | Maneb stabilized or Maneb preparations, stabilized <i>against self-heating</i>                                 |
| PP                                  | Fenchlorazole-ethyl                                                                             |                                     | Manganese ethylene-1,2-bis dithiocarbamate                                                                     |
| PP                                  | Fenitrothion                                                                                    |                                     | Manganese ethylene-1,2-bis-dithiocarbamate, stabilized against self-heating                                    |
| PP                                  | Fenoxapro-P-ethyl                                                                               |                                     | Mecarbam                                                                                                       |
| PP                                  | Fenpropathrin                                                                                   |                                     | Mephosfolan                                                                                                    |
|                                     | Fensulfothion                                                                                   |                                     | Mercaptodimethur                                                                                               |
| PP                                  | Fenthion                                                                                        |                                     | Mercuric acetate                                                                                               |
| PP                                  | Fentin acetate                                                                                  |                                     |                                                                                                                |
| PP                                  | Fentin hydroxide                                                                                |                                     |                                                                                                                |
|                                     | Ferric arsenate                                                                                 | PP                                  |                                                                                                                |

§ 172.101

49 CFR Ch. I (10–1–08 Edition)

LIST OF MARINE POLLUTANTS—Continued

| S.M.P.<br>(1) | Marine pollutant<br>(2)                                |
|---------------|--------------------------------------------------------|
| PP            | Mercuric ammonium chloride                             |
| PP            | Mercuric arsenate                                      |
| PP            | Mercuric benzoate                                      |
| PP            | Mercuric bisulphate                                    |
| PP            | Mercuric bromide                                       |
| PP            | Mercuric chloride                                      |
| PP            | Mercuric cyanide                                       |
| PP            | Mercuric gluconate                                     |
|               | Mercuric iodide                                        |
| PP            | Mercuric nitrate                                       |
| PP            | Mercuric oleate                                        |
| PP            | Mercuric oxide                                         |
| PP            | Mercuric oxycyanide, desensitized                      |
| PP            | Mercuric potassium cyanide                             |
| PP            | Mercuric Sulphate                                      |
| PP            | Mercuric thiocyanate                                   |
| PP            | Mercuriol                                              |
| PP            | Mercurous acetate                                      |
| PP            | Mercurous bisulphate                                   |
| PP            | Mercurous bromide                                      |
| PP            | Mercurous chloride                                     |
| PP            | Mercurous nitrate                                      |
| PP            | Mercurous salicylate                                   |
| PP            | Mercurous sulphate                                     |
| PP            | Mercury acetates                                       |
| PP            | Mercury ammonium chloride                              |
| PP            | Mercury based pesticide, liquid, flammable, toxic      |
| PP            | Mercury based pesticides, liquid, toxic, flammable     |
| PP            | Mercury based pesticides, liquid, toxic                |
| PP            | Mercury based pesticides, solid, toxic                 |
| PP            | Mercury benzoate                                       |
| PP            | Mercury bichloride                                     |
| PP            | Mercury bisulphates                                    |
| PP            | Mercury bromides                                       |
| PP            | Mercury compounds, liquid, n.o.s.                      |
| PP            | Mercury compounds, solid, n.o.s.                       |
| PP            | Mercury cyanide                                        |
| PP            | Mercury gluconate                                      |
| PP            | Mercury (I) (mercurous) compounds (pesticides)         |
| PP            | Mercury (II) (mercuric) compounds (pesticides)         |
|               | Mercury iodide                                         |
| PP            | Mercury nucleate                                       |
| PP            | Mercury oleate                                         |
| PP            | Mercury oxide                                          |
| PP            | Mercury oxycyanide, desensitized                       |
| PP            | Mercury potassium cyanide                              |
| PP            | Mercury potassium iodide                               |
| PP            | Mercury salicylate                                     |
| PP            | Mercury sulfates                                       |
| PP            | Mercury thiocyanate                                    |
|               | Metam-sodium                                           |
|               | Methamidophos                                          |
|               | Methanethiol                                           |
|               | Methidathion                                           |
|               | Methomyl                                               |
|               | ortho-Methoxyaniline                                   |
|               | Methyl bromide and ethylene dibromide mixtures, liquid |
|               | Methyl mercaptan                                       |
|               | 3-Methylacrolein, stabilized                           |
|               | Methylchlorobenzenes                                   |
|               | Methylnitrophenols                                     |
|               | 3-Methylpyridine                                       |
|               | Methyltrithion                                         |
|               | Methylvinylbenzenes, inhibited                         |
| PP            | Mevinphos                                              |
|               | Mexacarbate                                            |
|               | Mirex                                                  |
|               | Monocrotophos                                          |
|               | Motor fuel anti-knock mixtures                         |
|               | Motor fuel anti-knock mixtures or compounds            |

LIST OF MARINE POLLUTANTS—Continued

| S.M.P.<br>(1) | Marine pollutant<br>(2)                                                                         |
|---------------|-------------------------------------------------------------------------------------------------|
|               | Nabam                                                                                           |
|               | Naled                                                                                           |
| PP            | Nickel carbonyl                                                                                 |
| PP            | Nickel cyanide                                                                                  |
| PP            | Nickel tetracarbonyl                                                                            |
|               | 3-Nitro-4-chlorobenzotrifluoride                                                                |
|               | Nitrobenzene                                                                                    |
|               | Nitrobenzotrifluorides, liquid or solid                                                         |
|               | Nonylphenol                                                                                     |
|               | normal-Octaldehyde                                                                              |
|               | Oleylamine                                                                                      |
| PP            | Organotin compounds, liquid, n.o.s.                                                             |
| PP            | Organotin compounds (pesticides)                                                                |
| PP            | Organotin compounds, solid, n.o.s.                                                              |
| PP            | Organotin pesticides, liquid, flammable, toxic, n.o.s.,<br><i>flash point less than 23deg C</i> |
| PP            | Organotin pesticides, liquid, toxic, flammable, n.o.s.                                          |
| PP            | Organotin pesticides, liquid, toxic, n.o.s.                                                     |
| PP            | Organotin pesticides, solid, toxic, n.o.s.                                                      |
|               | Orthoarsenic acid                                                                               |
| PP            | Osmium tetroxide                                                                                |
|               | Oxamyl                                                                                          |
|               | Oxydisulfoton                                                                                   |
|               | Paraoxon                                                                                        |
| PP            | Parathion                                                                                       |
| PP            | Parathion-methyl                                                                                |
| PP            | PCBs.                                                                                           |
|               | Pentachloroethane                                                                               |
| PP            | Pentachlorophenol                                                                               |
|               | Pentalin                                                                                        |
|               | n-Pentylbenzene                                                                                 |
|               | Perchloroethylene                                                                               |
|               | Perchloromethylmercaptan                                                                        |
|               | Petrol, leaded                                                                                  |
| PP            | Phenarsazine chloride                                                                           |
|               | d-Phenothrin                                                                                    |
| PP            | Phenthoate                                                                                      |
|               | 1-Phenylbutane                                                                                  |
|               | 2-Phenylbutane                                                                                  |
|               | Phenylcyclohexane                                                                               |
| PP            | Phenylmercuric acetate                                                                          |
| PP            | Phenylmercuric compounds, n.o.s.                                                                |
| PP            | Phenylmercuric hydroxide                                                                        |
| PP            | Phenylmercuric nitrate                                                                          |
|               | 2-Phenylpropene                                                                                 |
| PP            | Phorate                                                                                         |
| PP            | Phosalone                                                                                       |
|               | Phosmet                                                                                         |
| PP            | Phosphamidon                                                                                    |
| PP            | Phosphorus, white, molten                                                                       |
| PP            | Phosphorus, white or yellow dry or under water or in<br>solution                                |
| PP            | Phosphorus white, or yellow, molten                                                             |
| PP            | Phosphorus, yellow, molten                                                                      |
|               | Pindone (and salts of)                                                                          |
|               | Pirimicarb                                                                                      |
| PP            | Pirimiphos-ethyl                                                                                |
| PP            | Polychlorinated biphenyls                                                                       |
| PP            | Polyhalogenated biphenyls, liquid or Terphenyls liquid                                          |
|               | Polyhalogenated biphenyls, solid or Terphenyls,<br>solid                                        |
| PP            | Potassium cuprocyanide                                                                          |
|               | Potassium cyanide, solid                                                                        |
|               | Potassium cyanide, solution                                                                     |
| PP            | Potassium cyanocuprate (I)                                                                      |
| PP            | Potassium cyanomercurate                                                                        |
| PP            | Potassium mercuric iodide                                                                       |
|               | Promecarb                                                                                       |
|               | Propachlor                                                                                      |
|               | Propaphos                                                                                       |

LIST OF MARINE POLLUTANTS—Continued

| S.M.P.<br>(1) | Marine pollutant<br>(2)                                                                     |
|---------------|---------------------------------------------------------------------------------------------|
|               | Propenal, inhibited                                                                         |
|               | Propoxur                                                                                    |
|               | Prothoate                                                                                   |
|               | Prussic acid, anhydrous, stabilized                                                         |
|               | Prussic acid, anhydrous, stabilized, absorbed in a porous inert material                    |
| PP            | Pyrazophos                                                                                  |
|               | Quinalphos                                                                                  |
| PP            | Quizalofop                                                                                  |
| PP            | Quizalofop-p-ethyl                                                                          |
|               | Rotenone                                                                                    |
|               | Salithion                                                                                   |
| PP            | Silafluofen                                                                                 |
|               | Silver arsenite                                                                             |
|               | Silver cyanide                                                                              |
|               | Silver orthoarsenite                                                                        |
| PP            | Sodium copper cyanide, solid                                                                |
| PP            | Sodium copper cyanide solution                                                              |
| PP            | Sodium cuprocyanide, solid                                                                  |
| PP            | Sodium cuprocyanide, solution                                                               |
|               | Sodium cyanide, solid                                                                       |
|               | Sodium cyanide, solution                                                                    |
|               | Sodium dinitro-o-cresolate, <i>dry or wetted with less than 15 per cent water, by mass</i>  |
|               | Sodium dinitro-ortho-cresolate, <i>wetted with not less than 15 per cent water, by mass</i> |
| PP            | Sodium pentachlorophenate                                                                   |
|               | Strychnine or Strychnine salts                                                              |
|               | Sulfotep                                                                                    |
| PP            | Sulprophos                                                                                  |
|               | Tallow nitrile                                                                              |
|               | Temephos                                                                                    |
|               | TEPP                                                                                        |
| PP            | Terbufos                                                                                    |
|               | Tetrabromoethane                                                                            |
|               | Tetrabromomethane                                                                           |
|               | 1,1,2,2-Tetrachloroethane                                                                   |
|               | Tetrachloroethylene                                                                         |
|               | Tetrachloromethane                                                                          |
|               | Tetraethyl dithiopyrophosphate                                                              |
| PP            | Tetraethyl lead, liquid                                                                     |
|               | Tetramethrin                                                                                |
|               | Tetramethyllead                                                                             |
|               | Thallium chlorate                                                                           |
|               | Thallium compounds, n.o.s.                                                                  |
|               | Thallium compounds (pesticides)                                                             |
|               | Thallium nitrate                                                                            |
|               | Thallium sulfate                                                                            |
|               | Thallos chlorate                                                                            |
|               | Thiocarbonyl tetrachloride                                                                  |
| PP            | Triaryl phosphates, isopropylated                                                           |
|               | Triaryl phosphates, n.o.s.                                                                  |
|               | Triazophos                                                                                  |
|               | Tribromomethane                                                                             |
| PP            | Tributyltin compounds                                                                       |
|               | Trichlorfon                                                                                 |
| PP            | 1,2,3-Trichlorobenzene                                                                      |
|               | Trichlorobenzenes, liquid                                                                   |
|               | Trichlorobutene                                                                             |
|               | Trichlorobutylene                                                                           |
|               | Trichloromethane sulphuryl chloride                                                         |
|               | Trichloromethyl sulphochloride                                                              |
|               | Trichloronat                                                                                |
|               | Tricresyl phosphate (less than 1% ortho-isomer)                                             |
| PP            | Tricresyl phosphate, not less than 1% ortho-isomer but not more than 3% orthoisomer         |
| PP            | Tricresyl phosphate with more than 3 per cent ortho isomer                                  |
|               | Triethylbenzene                                                                             |
|               | Triisopropylated phenyl phosphates                                                          |
|               | Trimethylene dichloride                                                                     |

LIST OF MARINE POLLUTANTS—Continued

| S.M.P.<br>(1) | Marine pollutant<br>(2)                                                                                     |
|---------------|-------------------------------------------------------------------------------------------------------------|
| PP            | Triphenylphosphate                                                                                          |
|               | Triphenyl phosphate/tert-butylated triphenyl phosphates mixtures containing 5% to 10% triphenyl phosphates  |
| PP            | Triphenyl phosphate/tert-butylated triphenyl phosphates mixtures containing 10% to 48% triphenyl phosphates |
| PP            | Triphenyltin compounds                                                                                      |
|               | Tritolyl phosphate (less than 1% ortho-isomer)                                                              |
| PP            | Tritolyl phosphate (not less than 1% ortho-isomer)                                                          |
|               | Trixylenyl phosphate                                                                                        |
|               | Vinylidene chloride, stabilized                                                                             |
|               | Warfarin (and salts of)                                                                                     |
| PP            | White phosphorus, dry                                                                                       |
| PP            | White phosphorus, wet                                                                                       |
|               | White spirit, low (15-20%) aromatic                                                                         |
| PP            | Yellow phosphorus, dry                                                                                      |
| PP            | Yellow phosphorus, wet                                                                                      |
|               | Zinc bromide                                                                                                |
|               | Zinc cyanide                                                                                                |

[Amdt. 172–173, 55 FR 52474, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 172.101, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

EDITORIAL NOTE: At 70 FR 34388, June 14, 2005, § 172.101 was amended; however, two amendments could not be incorporated due to inaccurate amendatory instruction.

**§ 172.102 Special provisions.**

(a) *General.* When column 7 of the § 172.101 table refers to a special provision for a hazardous material, the meaning and requirements of that provision are as set forth in this section. When a special provision specifies packaging or packaging requirements—

(1) The special provision is in addition to the standard requirements for all packagings prescribed in § 173.24 of this subchapter and any other applicable packaging requirements in subparts A and B of part 173 of this subchapter; and

(2) To the extent a special provision imposes limitations or additional requirements on the packaging provisions set forth in column 8 of the § 172.101 table, packagings must conform to the requirements of the special provision.

(b) *Description of codes for special provisions.* Special provisions contain packaging provisions, prohibitions, exceptions from requirements for particular quantities or forms of materials

and requirements or prohibitions applicable to specific modes of transportation, as follows:

(1) A code consisting only of numbers (for example, “11”) is multi-modal in application and may apply to bulk and non-bulk packagings.

(2) A code containing the letter “A” refers to a special provision which applies only to transportation by aircraft.

(3) A code containing the letter “B” refers to a special provision that applies only to bulk packaging requirements. Unless otherwise provided in this subchapter, these special provisions do not apply to UN, IM Specification portable tanks or IBCs.

(4) A code containing the letters “IB” or “IP” refers to a special provision that applies only to transportation in IBCs.

(5) A code containing the letter “N” refers to a special provision which applies only to non-bulk packaging requirements.

(6) A code containing the letter “R” refers to a special provision which applies only to transportation by rail.

(7) A code containing the letter “T” refers to a special provision which applies only to transportation in UN or IM Specification portable tanks.

(8) A code containing the letters “TP” refers to a portable tank special provision for UN or IM Specification portable tanks that is in addition to those provided by the portable tank instructions or the requirements in part 178 of this subchapter.

(9) A code containing the letter “W” refers to a special provision that applies only to transportation by water.

(c) *Tables of special provisions.* The following tables list, and set forth the requirements of, the special provisions referred to in column 7 of the § 172.101 table.

(1) *Numeric provisions.* These provisions are multi-modal and apply to bulk and non-bulk packagings:

*Code/Special Provisions*

1 This material is poisonous by inhalation (see § 171.8 of this subchapter) in Hazard Zone A (see § 173.116(a) or § 173.133(a) of this subchapter), and must be described as an inhalation hazard under the provisions of this subchapter.

2 This material is poisonous by inhalation (see § 171.8 of this subchapter) in Hazard Zone B (see § 173.116(a) or § 173.133(a) of this subchapter), and must be described as an inhalation hazard under the provisions of this subchapter.

3 This material is poisonous by inhalation (see § 171.8 of this subchapter) in Hazard Zone C (see § 173.116(a) of this subchapter), and must be described as an inhalation hazard under the provisions of this subchapter.

4 This material is poisonous by inhalation (see § 171.8 of this subchapter) in Hazard Zone D (see § 173.116(a) of this subchapter), and must be described as an inhalation hazard under the provisions of this subchapter.

5 If this material meets the definition for a material poisonous by inhalation (see § 171.8 of this subchapter), a shipping name must be selected which identifies the inhalation hazard, in Division 2.3 or Division 6.1, as appropriate.

6 This material is poisonous-by-inhalation and must be described as an inhalation hazard under the provisions of this subchapter.

8 A hazardous substance that is not a hazardous waste may be shipped under the shipping description “Other regulated substances, liquid or solid, n.o.s.”, as appropriate. In addition, for solid materials, special provision B54 applies.

9 Packaging for certain PCBs for disposal and storage is prescribed by EPA in 40 CFR 761.60 and 761.65.

11 The hazardous material must be packaged as either a liquid or a solid, as appropriate, depending on its physical form at 55 °C (131 °F) at atmospheric pressure.

12 In concentrations greater than 40 percent, this material has strong oxidizing properties and is capable of starting fires in contact with combustible materials. If appropriate, a package containing this material must conform to the additional labeling requirements of § 172.402 of this subchapter.

13 The words “Inhalation Hazard” shall be entered on each shipping paper in association with the shipping description, shall be marked on each non-bulk package in association with the proper shipping name and identification number, and shall be marked on two opposing sides of each bulk package. Size of marking on bulk package must conform to § 172.302(b) of this subchapter. The requirements of §§ 172.203(m) and 172.505 of this subchapter do not apply.

14 Motor fuel antiknock mixtures are:  
a. Mixtures of one or more organic lead mixtures (such as tetraethyl lead, triethylmethyl lead, diethyldimethyl lead, ethyltrimethyl lead, and tetramethyl lead) with one or more halogen compounds (such as ethylene

- dibromide and ethylene dichloride), hydrocarbon solvents or other equally efficient stabilizers; or
- b. tetraethyl lead.
- 15 This entry applies to "Chemical kits" and "First aid kits" containing one or more compatible items of hazardous materials in boxes, cases, etc. that, for example, are used for medical, analytical, diagnostic, testing, or repair purposes. For transportation by aircraft, materials forbidden for transportation by passenger aircraft or cargo aircraft may not be included in the kits. Chemical kits and first aid kits are excepted from the specification packaging requirements of this subchapter when packaged in combination packagings. Chemical kits and first aid kits are also excepted from the labeling and placarding requirements of this subchapter, except when offered for transportation or transported by air. Chemical and first aid kits may be transported in accordance with the consumer commodity and ORM exceptions in § 173.156, provided they meet all required conditions. Kits that are carried on board transport vehicles for first aid or operating purposes are not subject to the requirements of this subchapter.
- 16 This description applies to smokeless powder and other solid propellants that are used as powder for small arms and have been classed as Division 1.3 and 4.1 in accordance with § 173.56 of this subchapter.
- 18 This description is authorized only for fire extinguishers listed in § 173.309(b) of this subchapter meeting the following conditions:
- Each fire extinguisher may only have extinguishing contents that are nonflammable, non-poisonous, non-corrosive and commercially free from corroding components.
  - Each fire extinguisher must be charged with a nonflammable, non-poisonous, dry gas that has a dew-point at or below minus 46.7 °C (minus 52 °F) at 101 kPa (1 atmosphere) and is free of corroding components, to not more than the service pressure of the cylinder.
  - A fire extinguisher may not contain more than 30% carbon dioxide by volume or any other corrosive extinguishing agent.
  - Each fire extinguisher must be protected externally by suitable corrosion-resisting coating.
- 19 For domestic transportation only, the identification number "UN1075" may be used in place of the identification number specified in column (4) of the § 172.101 table. The identification number used must be consistent on package markings, shipping papers and emergency response information.
- 21 This material must be stabilized by appropriate means (e.g., addition of chemical inhibitor, purging to remove oxygen) to prevent dangerous polymerization (see § 173.21(f) of this subchapter).
- 22 If the hazardous material is in dispersion in organic liquid, the organic liquid must have a flash point above 50 °C (122 °F).
- 23 This material may be transported under the provisions of Division 4.1 only if it is so packed that the percentage of diluent will not fall below that stated in the shipping description at any time during transport. Quantities of not more than 500 g per package with not less than 10 percent water by mass may also be classed in Division 4.1, provided a negative test result is obtained when tested in accordance with test series 6(c) of the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter).
- 24 Alcoholic beverages containing more than 70 percent alcohol by volume must be transported as materials in Packing Group II. Alcoholic beverages containing more than 24 percent but not more than 70 percent alcohol by volume must be transported as materials in Packing Group III.
- 26 This entry does not include ammonium permanganate, the transport of which is prohibited except when approved by the Associate Administrator.
- 28 The dihydrated sodium salt of dichloroisocyanuric acid is not subject to the requirements of this subchapter.
- 29 For transportation by motor vehicle, rail car or vessel, production runs (exceptions for prototypes can be found in § 173.185(e)) of not more than 100 lithium cells or batteries are excepted from the testing requirements of § 173.185(a)(1) if—
- For a lithium metal cell or battery, the lithium content is not more than 1.0 g per cell and the aggregate lithium content is not more than 2.0 g per battery, and, for a lithium-ion cell or battery, the equivalent lithium content is not more than 1.5 g per cell and the aggregate equivalent lithium content is not more than 8 g per battery;
  - The cells and batteries are transported in an outer packaging that is a metal, plastic or plywood drum or metal, plastic or wooden box that meets the criteria for Packing Group I packagings; and
  - Each cell and battery is individually packed in an inner packaging inside an outer packaging and is surrounded by cushioning material that is non-combustible, and non-conductive.
- 30 Sulfur is not subject to the requirements of this subchapter if transported in a non-bulk packaging or if formed to a specific shape (for example, prills, granules, pellets, pastilles, or flakes). A bulk packaging containing sulfur is not subject to the placarding requirements of subpart F of this part, if it is marked with the appropriate identification number as required by subpart D of this part. Molten sulfur must

- be marked as required by § 172.325 of this subchapter.
- 31 Materials which have undergone sufficient heat treatment to render them non-hazardous are not subject to the requirements of this subchapter.
- 32 Polymeric beads and molding compounds may be made from polystyrene, poly(methyl methacrylate) or other polymeric material.
- 33 Ammonium nitrites and mixtures of an inorganic nitrite with an ammonium salt are prohibited.
- 34 The commercial grade of calcium nitrate fertilizer, when consisting mainly of a double salt (calcium nitrate and ammonium nitrate) containing not more than 10 percent ammonium nitrate and at least 12 percent water of crystallization, is not subject to the requirements of this subchapter.
- 35 Antimony sulphides and oxides which do not contain more than 0.5 percent of arsenic calculated on the total mass do not meet the definition of Division 6.1.
- 36 The maximum net quantity per package is 5 L (1 gallon) or 5 kg (11 pounds).
- 37 Unless it can be demonstrated by testing that the sensitivity of the substance in its frozen state is no greater than in its liquid state, the substance must remain liquid during normal transport conditions. It must not freeze at temperatures above  $-15^{\circ}\text{C}$  ( $5^{\circ}\text{F}$ ).
- 38 If this material shows a violent effect in laboratory tests involving heating under confinement, the labeling requirements of Special Provision 53 apply, and the material must be packaged in accordance with packing method OP6 in § 173.225 of this subchapter. If the SADT of the technically pure substance is higher than  $75^{\circ}\text{C}$ , the technically pure substance and formulations derived from it are not self-reactive materials and, if not meeting any other hazard class, are not subject to the requirements of this subchapter.
- 39 This substance may be carried under provisions other than those of Class 1 only if it is so packed that the percentage of water will not fall below that stated at any time during transport. When phlegmatized with water and inorganic inert material, the content of urea nitrate must not exceed 75 percent by mass and the mixture should not be capable of being detonated by test 1(a)(i) or test 1(a)(ii) in the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter).
- 40 Polyester resin kits consist of two components: a base material (Class 3, Packing Group II or III) and an activator (organic peroxide), each separately packed in an inner packaging. The organic peroxide must be type D, E, or F, not requiring temperature control, and be limited to a quantity of 125 mL (4.22 ounces) per inner packaging if liquid, and 500 g (1 pound) if solid.
- The components may be placed in the same outer packaging provided they will not interact dangerously in the event of leakage. Packing group will be II or III, according to the criteria for Class 3, applied to the base material.
- 43 The membrane filters, including paper separators and coating or backing materials, that are present in transport, must not be able to propagate a detonation as tested by one of the tests described in the UN Manual of Tests and Criteria, Part I, Test series 1(a) (IBR, see § 171.7 of this subchapter). On the basis of the results of suitable burning rate tests, and taking into account the standard tests in the UN Manual of Tests and Criteria, Part III, subsection 33.2.1 (IBR, see § 171.7 of this subchapter), nitrocellulose membrane filters in the form in which they are to be transported that do not meet the criteria for a Division 4.1 material are not subject to the requirements of this subchapter. Packagings must be so constructed that explosion is not possible by reason of increased internal pressure. Nitrocellulose membrane filters covered by this entry, each with a mass not exceeding 0.5 g, are not subject to the requirements of this subchapter when contained individually in an article or a sealed packet.
- 44 The formulation must be prepared so that it remains homogenous and does not separate during transport. Formulations with low nitrocellulose contents and neither showing dangerous properties when tested for their ability to detonate, deflagrate or explode when heated under defined confinement by the appropriate test methods and criteria in the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter), nor classed as a Division 4.1 (flammable solid) when tested in accordance with the procedures specified in § 173.124 of this subchapter (chips, if necessary, crushed and sieved to a particle size of less than 1.25 mm), are not subject to the requirements of this subchapter.
- 45 Temperature should be maintained between  $18^{\circ}\text{C}$  ( $64.4^{\circ}\text{F}$ ) and  $40^{\circ}\text{C}$  ( $104^{\circ}\text{F}$ ). Tanks containing solidified methacrylic acid must not be reheated during transport.
- 46 This material must be packed in accordance with packing method OP6 (see § 173.225 of this subchapter). During transport, it must be protected from direct sunshine and stored (or kept) in a cool and well-ventilated place, away from all sources of heat.
- 47 Mixtures of solids that are not subject to this subchapter and flammable liquids may be transported under this entry without first applying the classification criteria of Division 4.1, provided there is no free liquid visible at the time the material is loaded or at the time the packaging or transport

- unit is closed. Except when the liquids are fully absorbed in solid material contained in sealed bags, each packaging must correspond to a design type that has passed a leakproofness test at the Packing Group II level. Small inner packagings consisting of sealed packets and articles containing less than 10 mL of a Class 3 liquid in Packing Group II or III absorbed onto a solid material are not subject to this subchapter provided there is no free liquid in the packet or article.
- 48 Mixtures of solids which are not subject to this subchapter and toxic liquids may be transported under this entry without first applying the classification criteria of Division 6.1, provided there is no free liquid visible at the time the material is loaded or at the time the packaging or transport unit is closed. Each packaging must correspond to a design type that has passed a leakproofness test at the Packing Group II level. This entry may not be used for solids containing a Packing Group I liquid.
- 49 Mixtures of solids which are not subject to this subchapter and corrosive liquids may be transported under this entry without first applying the classification criteria of Class 8, provided there is no free liquid visible at the time the material is loaded or at the time the packaging or transport unit is closed. Each packaging must correspond to a design type that has passed a leakproofness test at the Packing Group II level.
- 50 Cases, cartridge, empty with primer which are made of metallic or plastic casings and meeting the classification criteria of Division 1.4 are not regulated for domestic transportation.
- 51 This description applies to items previously described as "Toy propellant devices, Class C" and includes reloadable kits. Model rocket motors containing 30 grams or less propellant are classed as Division 1.4S and items containing more than 30 grams of propellant but not more than 62.5 grams of propellant are classed as Division 1.4C.
- 52 This entry may only be used for substances that do not exhibit explosive properties of Class 1 (explosive) when tested in accordance with Test Series 1 and 2 of Class 1 (explosive) in the UN Manual of Tests and Criteria, Part I (incorporated by reference; see § 171.7 of this subchapter).
- 53 Packages of these materials must bear the subsidiary risk label, "EXPLOSIVE", and the subsidiary hazard class/division must be entered in parentheses immediately following the primary hazard class in the shipping description, unless otherwise provided in this subchapter or through an approval issued by the Associate Administrator, or the competent authority of the country of origin. A copy of the approval shall accompany the shipping papers.
- 54 Maneb or maneb preparations not meeting the definition of Division 4.3 or any other hazard class are not subject to the requirements of this subchapter when transported by motor vehicle, rail car, or aircraft.
- 55 This device must be approved in accordance with § 173.56 of this subchapter by the Associate Administrator.
- 56 A means to interrupt and prevent detonation of the detonator from initiating the detonating cord must be installed between each electric detonator and the detonating cord ends of the jet perforating guns before the charged jet perforating guns are offered for transportation.
- 57 Maneb or Maneb preparations stabilized against self-heating need not be classified in Division 4.2 when it can be demonstrated by testing that a volume of 1 m<sup>3</sup> of substance does not self-ignite and that the temperature at the center of the sample does not exceed 200 °C, when the sample is maintained at a temperature of not less than 75 °C ± 2 °C for a period of 24 hours, in accordance with procedures set forth for testing self-heating materials in the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter).
- 58 Aqueous solutions of Division 5.1 inorganic solid nitrate substances are considered as not meeting the criteria of Division 5.1 if the concentration of the substances in solution at the minimum temperature encountered in transport is not greater than 80% of the saturation limit.
- 59 Ferrocium, stabilized against corrosion, with a minimum iron content of 10 percent is not subject to the requirements of this subchapter.
- 61 A chemical oxygen generator is spent if its means of ignition and all or a part of its chemical contents have been expended.
- 64 The group of alkali metals includes lithium, sodium, potassium, rubidium, and caesium.
- 65 The group of alkaline earth metals includes magnesium, calcium, strontium, and barium.
- 66 Formulations of these substances containing not less than 30 percent non-volatile, non-flammable phlegmatizer are not subject to this subchapter.
- 70 Black powder that has been classed in accordance with the requirements of § 173.56 of this subchapter may be reclassified and offered for domestic transportation as a Division 4.1 material if it is offered for transportation and transported in accordance with the limitations and packaging requirements of § 173.170 of this subchapter.
- 74 During transport, this material must be protected from direct sunshine and stored or kept in a cool and well-ventilated place, away from all sources of heat.



- 77 Mixtures containing not more than 23.5% oxygen by volume may be transported under this entry when no other oxidizing gases are present. A Division 5.1 subsidiary risk label is not required if this special provision applies.
- 78 This entry may not be used to describe compressed air which contains more than 23.5 percent oxygen. An oxidizer label is not required for any oxygen concentration of 23.5 percent or less.
- 79 This entry may not be used for mixtures that meet the definition for oxidizing gas.
- 81 Polychlorinated biphenyl items, as defined in 40 CFR 761.3, for which specification packagings are impractical, may be packaged in non-specification packagings meeting the general packaging requirements of subparts A and B of part 173 of this subchapter. Alternatively, the item itself may be used as a packaging if it meets the general packaging requirements of subparts A and B of part 173 of this subchapter.
- 102 The ends of the detonating cord must be tied fast so that the explosive cannot escape. The articles may be transported as in Division 1.4 Compatibility Group D (1.4D) if all of the conditions specified in § 173.63(a) of this subchapter are met.
- 103 Detonators which will not mass detonate and undergo only limited propagation in the shipping package may be assigned to 1.4B classification code. Mass detonate means that more than 90 percent of the devices tested in a package explode practically simultaneously. Limited propagation means that if one detonator near the center of a shipping package is exploded, the aggregate weight of explosives, excluding ignition and delay charges, in this and all additional detonators in the outside packaging that explode may not exceed 25 grams.
- 105 The word “Agents” may be used instead of “Explosives” when approved by the Associate Administrator.
- 106 The recognized name of the particular explosive may be specified in addition to the type.
- 107 The classification of the substance is expected to vary especially with the particle size and packaging but the border lines have not been experimentally determined; appropriate classifications should be verified following the test procedures in §§ 173.57 and 173.58 of this subchapter.
- 108 Fireworks must be so constructed and packaged that loose pyrotechnic composition will not be present in packages during transportation.
- 109 Rocket motors must be nonpropulsive in transportation unless approved in accordance with § 173.56 of this subchapter. A rocket motor to be considered “nonpropulsive” must be capable of unrestrained burning and must not appreciably move in any direction when ignited by any means.
- 110 Fire extinguishers transported under UN1044 may include installed actuating cartridges (cartridges, power device of Division 1.4C or 1.4S), without changing the classification of Division 2.2, provided the aggregate quantity of deflagrating (propellant) explosives does not exceed 3.2 grams per extinguishing unit.
- 111 Explosive substances of Division 1.1 Compatibility Group A (1.1A) are forbidden for transportation if dry or not desensitized, unless incorporated in a device.
- 113 The sample must be given a tentative approval by an agency or laboratory in accordance with § 173.56 of this subchapter.
- 114 Jet perforating guns, charged, oil well, without detonator may be reclassified to Division 1.4 Compatibility Group D (1.4D) if the following conditions are met:
  - a. The total weight of the explosive contents of the shaped charges assembled in the guns does not exceed 90.5 kg (200 pounds) per vehicle; and
  - b. The guns are packaged in accordance with Packing Method US 1 as specified in § 173.62 of this subchapter.
- 115 Boosters with detonator, detonator assemblies and boosters with detonators in which the total explosive charge per unit does not exceed 25 g, and which will not mass detonate and undergo only limited propagation in the shipping package may be assigned to 1.4B classification code. Mass detonate means more than 90 percent of the devices tested in a package explode practically simultaneously. Limited propagation means that if one booster near the center of the package is exploded, the aggregate weight of explosives, excluding ignition and delay charges, in this and all additional boosters in the outside packaging that explode may not exceed 25 g.
- 116 Fuzes, detonating may be classed in Division 1.4 if the fuzes do not contain more than 25 g of explosive per fuze and are made and packaged so that they will not cause functioning of other fuzes, explosives or other explosive devices if one of the fuzes detonates in a shipping packaging or in adjacent packages.
- 117 If shipment of the explosive substance is to take place at a time that freezing weather is anticipated, the water contained in the explosive substance must be mixed with denatured alcohol so that freezing will not occur.
- 118 This substance may not be transported under the provisions of Division 4.1 unless specifically authorized by the Associate Administrator.
- 119 This substance, when in quantities of not more than 11.5 kg (25.3 pounds), with not less than 10 percent water, by mass, also may be classed as Division 4.1, provided a negative test result is obtained

- when tested in accordance with test series 6(c) of the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter).
- 120 The phlegmatized substance must be significantly less sensitive than dry PETN.
- 121 This substance, when containing less alcohol, water or phlegmatizer than specified, may not be transported unless approved by the Associate Administrator.
- 123 Any explosives, blasting, type C containing chlorates must be segregated from explosives containing ammonium nitrate or other ammonium salts.
- 125 Lactose or glucose or similar materials may be used as a phlegmatizer provided that the substance contains not less than 90%, by mass, of phlegmatizer. These mixtures may be classified in Division 4.1 when tested in accordance with test series 6(c) of the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter) and approved by the Associate Administrator. Testing must be conducted on at least three packages as prepared for transport. Mixtures containing at least 98%, by mass, of phlegmatizer are not subject to the requirements of this subchapter. Packages containing mixtures with not less than 90% by mass, of phlegmatizer need not bear a POISON subsidiary risk label.
- 127 Mixtures containing oxidizing and organic materials transported under this entry may not meet the definition and criteria of a Class 1 material. (See §173.50 of this subchapter.)
- 128 Regardless of the provisions of §172.101(c)(12), aluminum smelting by-products and aluminum remelting by-products described under this entry, meeting the definition of Class 8, Packing Group II and III may be classed as a Division 4.3 material and transported under this entry. The presence of a Class 8 hazard must be communicated as required by this Part for subsidiary hazards.
- 129 These materials may not be classified and transported unless authorized by the Associate Administrator on the basis of results from Series 2 Test and a Series 6(c) Test from the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter) on packages as prepared for transport. The packing group assignment and packaging must be approved by the Associate Administrator for Hazardous Materials Safety on the basis of the criteria in §173.21 of this subchapter and the package type used for the Series 6(c) test.
- 130 For other than a dry battery specifically covered by another entry in the §172.101 Table, "Batteries, dry" are not subject to the requirements of this subchapter when they are securely packaged and offered for transportation in a manner that prevents the dangerous evolution of heat (for example, by the effective insulation of exposed terminals) and protects against short circuits.
- 131 This material may not be offered for transportation unless approved by the Associate Administrator.
- 132 This entry may only be used for uniform, ammonium nitrate based fertilizer mixtures, containing nitrogen, phosphate or potash, meeting the following criteria: (1) Contains not more than 70% ammonium nitrate and not more than 0.4% total combustible, organic material calculated as carbon or (2) Contains not more than 45% ammonium nitrate and unrestricted combustible material.
- 134 This entry only applies to vehicles, machinery and equipment powered by wet batteries, sodium batteries, or lithium batteries that are transported with these batteries installed. Examples of such items are electrically-powered cars, lawn mowers, wheelchairs, and other mobility aids. Self-propelled vehicles that also contain an internal combustion engine must be consigned under the entry "Vehicle, flammable gas powered" or "Vehicle, flammable liquid powered", as appropriate. Except as provided in Special Provision A101, vehicles, machinery and equipment powered by primary lithium batteries that are transported with these batteries installed are forbidden aboard passenger-carrying aircraft.
- 135 The entries "Vehicle, flammable gas powered" or "Vehicle, flammable liquid powered," as appropriate, must be used when internal combustion engines are installed in a vehicle. These entries include hybrid electric vehicles powered by both an internal combustion engine and batteries.
- 136 This entry only applies to machinery and apparatus containing hazardous materials as in integral element of the machinery or apparatus. It may not be used to describe machinery or apparatus for which a proper shipping name exists in the §172.101 Table. Except when approved by the Associate Administrator, machinery or apparatus may only contain hazardous materials for which exceptions are referenced in Column (8) of the §172.101 Table and are provided in part 173, subpart D, of this subchapter. Hazardous materials shipped under this entry are excepted from the labeling requirements of this subchapter unless offered for transportation or transported by aircraft and are not subject to the placarding requirements of part 172, subpart F, of this subchapter. Orientation markings as described in §172.312 (a)(2) are required when liquid hazardous materials may escape due to incorrect orientation. The machinery or apparatus, if unpackaged, or the packaging in which it is contained shall be marked "Dangerous goods in machinery" or "Dangerous goods in apparatus", as appropriate, with the

## § 172.102

identification number UN3363. For transportation by aircraft, machinery or apparatus may not contain any material forbidden for transportation by passenger or cargo aircraft. The Associate Administrator may except from the requirements of this subchapter, equipment, machinery and apparatus provided:

- a. It is shown that it does not pose a significant risk in transportation;
- b. The quantities of hazardous materials do not exceed those specified in §173.4 of this subchapter; and
- c. The equipment, machinery or apparatus conforms with §173.222 of this subchapter.

137 Cotton, dry; flax, dry; and sisal, dry are not subject to the requirements of this subchapter when they are baled in accordance with ISO 8115, "Cotton Bales—Dimensions and Density" (IBR, see §171.7 of this subchapter) to a density of not less than 360 kg/m<sup>3</sup> (22.1 lb/ft<sup>3</sup>) for cotton, 400 kg/m<sup>3</sup> (24.97 lb/ft<sup>3</sup>) for flax and 620 kg/m<sup>3</sup> (38.71 lb/ft<sup>3</sup>) for sisal and transported in a freight container or closed transport vehicle.

138 Lead compounds which, when mixed in a ratio of 1:1000 with 0.07M (Molar concentration) hydrochloric acid and stirred for one hour at a temperature of 23 °C ±2 °C, exhibit a solubility of 5% or less are considered insoluble.

139 Use of the "special arrangement" proper shipping names for international shipments must be made under an IAEA Certificate of Competent Authority issued by the Associate Administrator in accordance with the requirements in §173.471, §173.472, or §173.473 of this subchapter. Use of these proper shipping names for domestic shipments may be made only under a DOT special permit, as defined in, and in accordance with the requirements of subpart B of part 107 of this subchapter.

140 This material is regulated only when it meets the defining criteria for a hazardous substance or a marine pollutant. In addition, the column 5 reference is modified to read "III" on those occasions when this material is offered for transportation or transported by highway or rail.

141 A toxin obtained from a plant, animal, or bacterial source containing an infectious substance, or a toxin contained in an infectious substance, must be classed as Division 6.2, described as an infectious substance, and assigned to UN 2814 or UN 2900, as appropriate.

142 These hazardous materials may not be classified and transported unless authorized by the Associate Administrator. The Associate Administrator will base the authorization on results from Series 2 tests and a Series 6(c) test from the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter) on packages as prepared

## 49 CFR Ch. I (10–1–08 Edition)

for transport in accordance with the requirements of this subchapter.

144 If transported as a residue in an underground storage tank (UST), as defined in 40 CFR 280.12, that has been cleaned and purged or rendered inert according to the American Petroleum Institute (API) Standard 1604 (IBR, see §171.7 of this subchapter), then the tank and this material are not subject to any other requirements of this subchapter. However, sediments remaining in the tank that meet the definition for a hazardous material are subject to the applicable regulations of this subchapter.

145 This entry applies to formulations that neither detonate in the cavitated state nor deflagrate in laboratory testing, show no effect when heated under confinement, exhibit no explosive power, and are thermally stable (self-accelerating decomposition temperature (SADT) at 60 °C (140 °F) or higher for a 50 kg (110.2 lbs.) package). Formulations not meeting these criteria must be transported under the provisions applicable to the appropriate entry in the Organic Peroxide Table in §173.225 of this subchapter.

146 This description may be used for a material that poses a hazard to the environment but does not meet the definition for a hazardous waste or a hazardous substance, as defined in §171.8 of this subchapter, or any hazard class, as defined in part 173 of this subchapter, if it is designated as environmentally hazardous by another Competent Authority. This provision may be used for both domestic and international shipments.

147 This entry applies to non-sensitized emulsions, suspensions, and gels consisting primarily of a mixture of ammonium nitrate and fuel, intended to produce a Type E blasting explosive only after further processing prior to use. The mixture for emulsions typically has the following composition: 60–85% ammonium nitrate; 5–30% water; 2–8% fuel; 0.5–4% emulsifier or thickening agent; 0–10% soluble flame suppressants; and trace additives. Other inorganic nitrate salts may replace part of the ammonium nitrate. The mixture for suspensions and gels typically has the following composition: 60–85% ammonium nitrate; 0–5% sodium or potassium perchlorate; 0–17% hexamine nitrate or monomethylamine nitrate; 5–30% water; 2–15% fuel; 0.5–4% thickening agent; 0–10% soluble flame suppressants; and trace additives. Other inorganic nitrate salts may replace part of the ammonium nitrate. These substances must satisfactorily pass Test Series 8 of the UN Manual of Tests and Criteria, Part I, Section 18 (IBR, see §171.7 of this subchapter), and may not be classified and transported unless approved by the Associate Administrator.

- 149 When transported as a limited quantity or a consumer commodity, the maximum net capacity specified in §173.150(b)(2) of this subchapter for inner packagings may be increased to 5 L (1.3 gallons).
- 150 This description may be used only for uniform mixtures of fertilizers containing ammonium nitrate as the main ingredient within the following composition limits:
- Not less than 90% ammonium nitrate with not more than 0.2% total combustible, organic material calculated as carbon, and with added matter, if any, that is inorganic and inert when in contact with ammonium nitrate; or
  - Less than 90% but more than 70% ammonium nitrate with other inorganic materials, or more than 80% but less than 90% ammonium nitrate mixed with calcium carbonate and/or dolomite, and not more than 0.4% total combustible, organic material calculated as carbon; or
  - Ammonium nitrate-based fertilizers containing mixtures of ammonium nitrate and ammonium sulphate with more than 45% but less than 70% ammonium nitrate, and not more than 0.4% total combustible, organic material calculated as carbon such that the sum of the percentage of compositions of ammonium nitrate and ammonium sulphate exceeds 70%.
- 151 If this material meets the definition of a flammable liquid in §173.120 of this subchapter, a FLAMMABLE LIQUID label is also required and the basic description on the shipping paper must indicate the Class 3 subsidiary hazard.
- 155 Fish meal or fish scrap may not be transported if the temperature at the time of loading either exceeds 35 °C (95 °F), or exceeds 5 °C (41 °F) above the ambient temperature, whichever is higher.
- 156 Asbestos that is immersed or fixed in a natural or artificial binder material, such as cement, plastic, asphalt, resins or mineral ore, or contained in manufactured products is not subject to the requirements of this subchapter.
- 157 This entry includes hybrid electric vehicles powered by both an internal combustion engine and wet, sodium or lithium batteries installed. Vehicles containing an internal combustion engine must be consigned under the entry "Vehicle, flammable gas powered" or "Vehicle, flammable liquid powered", as appropriate. Except as provided in Special Provision A101, vehicles powered by primary lithium batteries, that are transported with these batteries installed are forbidden aboard passenger-carrying aircraft.
- 159 This material must be protected from direct sunshine and kept in a cool, well-ventilated place away from sources of heat.
- 160 This entry applies to articles that are used as life-saving vehicle air bag inflators, air bag modules or seat-belt pretensioners containing Class 1 (explosive) materials or materials of other hazard classes. Air bag inflators and modules must be tested in accordance with Test series 6(c) of Part I of the UN Manual of Tests and Criteria (incorporated by reference; see §171.7 of this subchapter), with no explosion of the device, no fragmentation of device casing or pressure vessel, and no projection hazard or thermal effect that would significantly hinder fire-fighting or other emergency response efforts in the immediate vicinity. If the air bag inflator unit satisfactorily passes the series 6(c) test, it is not necessary to repeat the test on the air bag module.
- 161 For domestic transport, air bag inflators, air bag modules or seat belt pretensioners that meet the criteria for a Division 1.4G explosive must be transported using the description, "Articles, pyrotechnic for technical purposes," UN0431.
- 162 This material may be transported under the provisions of Division 4.1 only if it is packed so that at no time during transport will the percentage of diluent fall below the percentage that is stated in the shipping description.
- 163 Substances must satisfactorily pass Test Series 8 of the UN Manual of Tests and Criteria, Part I, Section 18 (IBR, see §171.7 of this subchapter).
- 164 Substances must not be transported under this entry unless approved by the Associate Administrator on the basis of the results of appropriate tests according to Part I of the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter). The material must be packaged so that the percentage of diluent does not fall below that stated in the approval at any time during transportation.
- 165 These substances are susceptible to exothermic decomposition at elevated temperatures. Decomposition can be initiated by heat, moisture or by impurities (e.g., powdered metals (iron, manganese, cobalt, magnesium)). During the course of transportation, these substances must be shaded from direct sunlight and all sources of heat and be placed in adequately ventilated areas.
- 166 When transported in non-friable tablet form, calcium hypochlorite, dry, may be transported as a Packing Group III material.
- 167 These storage systems shall always be considered as containing hydrogen.
- 168 For lighters containing a Division 2.1 gas (see §171.8 of this subchapter), representative samples of each new lighter design must be examined and successfully tested as specified in §173.308(b)(3). For criteria in determining what is a new lighter

design, *see* §173.308(b)(1). For transportation of new lighter design samples for examination and testing, *see* §173.308(b)(2). The examination and testing of each lighter design must be performed by a person authorized by the Associate Administrator under the provisions of subpart E of part 107 of this chapter, as specified in §173.308(a)(4). For continued use of approvals dated prior to January 1, 2012, *see* §173.308(b)(5).

For non-pressurized lighters containing a Class 3 (flammable liquid) material, its design, description, and packaging must be approved by the Associate Administrator prior to being offered for transportation or transported in commerce. In addition, a lighter design intended to contain a non-pressurized Class 3 material is excepted from the examination and testing criteria specified in §173.308(b)(3). An unused lighter or a lighter that is cleaned of residue and purged of vapors is not subject to the requirements of this subchapter.

169 This entry applies to lighter refills (*see* §171.8 of this subchapter) that contain a Division 2.1 (flammable) gas but do not contain an ignition device. Lighter refills offered for transportation under this entry may not exceed 4 fluid ounces capacity (7.22 cubic inches) or contain more than 65 grams of fuel. A lighter refill exceeding 4 fluid ounces capacity (7.22 cubic inches) or containing more than 65 grams of fuel must be classed as a Division 2.1 material, described with the proper shipping name appropriate for the material, and packaged in the packaging specified in part 173 of this subchapter for the flammable gas contained therein. In addition, a container exceeding 4 fluid ounces volumetric capacity (7.22 cubic inches) or containing more than 65 grams of fuel may not be connected or manifolded to a lighter or similar device and must also be described and packaged according to the fuel contained therein. For transportation by passenger-carrying aircraft, the net mass of lighter refills may not exceed 1 kg per package, and, for cargo-only aircraft, the net mass of lighter refills may not exceed 15 kg per package. *See* §173.306(h) of this subchapter.

170 Air must be eliminated from the vapor space by nitrogen or other means.

171 This entry may only be used when the material is transported in non-friable tablet form or for granular or powdered mixtures that have been shown to meet the PG III criteria in §173.127.

172 This entry includes alcohol mixtures containing up to 5% petroleum products.

173 An appropriate generic entry may be used for this material.

175 This substance must be stabilized when in concentrations of not more than 99%.

177 Ethanol and gasoline mixtures for use in spark-ignition engines (e.g., in auto-

mobiles, stationary engines and other engines) must be assigned to this entry regardless of variations in volatility.

188 *Small lithium cells and batteries.* Lithium cells or batteries, including cells or batteries packed with or contained in equipment, are not subject to any other requirements of this subchapter if they meet all of the following:

a. *Primary lithium batteries and cells.* (1) Primary lithium batteries and cells are forbidden for transport aboard passenger-carrying aircraft. The outside of each package that contains primary (nonrechargeable) lithium batteries or cells must be marked “PRIMARY LITHIUM BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT” or “LITHIUM METAL BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT” on a background of contrasting color. The letters in the marking must be:

(i) At least 12 mm (0.5 inch) in height on packages having a gross weight of more than 30 kg (66 pounds); or

(ii) At least 6 mm (0.25 inch) on packages having a gross weight of 30 kg (66 pounds) or less, except that smaller font may be used as necessary to fit package dimensions; and

(2) The provisions of paragraph (a)(1) do not apply to packages that contain 5 kg (11 pounds) net weight or less of primary lithium batteries or cells that are contained in or packed with equipment and the package contains no more than the number of lithium batteries or cells necessary to power the piece of equipment;

b. For a lithium metal or lithium alloy cell, the lithium content is not more than 1.0 g. For a lithium-ion cell, the equivalent lithium content is not more than 1.5 g;

c. For a lithium metal or lithium alloy battery, the aggregate lithium content is not more than 2.0 g. For a lithium-ion battery, the aggregate equivalent lithium content is not more than 8 g;

d. Effective October 1, 2009, the cell or battery must be of a type proven to meet the requirements of each test in the UN Manual of Tests and Criteria (IBR; *see* §171.7 of this subchapter);

e. Cells or batteries are separated so as to prevent short circuits and are packed in a strong outer packaging or are contained in equipment;

f. Effective October 1, 2008, except when contained in equipment, each package containing more than 24 lithium cells or 12 lithium batteries must be:

(1) Marked to indicate that it contains lithium batteries, and special procedures should be followed in the event that the package is damaged;

(2) Accompanied by a document indicating that the package contains lithium batteries and special procedures should be followed in the event that the package is damaged;

(3) Capable of withstanding a 1.2 meter drop test in any orientation without damage to cells or batteries contained in the package, without shifting of the contents that would allow short circuiting and without release of package contents; and

(4) Gross weight of the package may not exceed 30 kg (66 pounds). This requirement does not apply to lithium cells or batteries packed with equipment;

g. Electrical devices must conform to §173.21 of this subchapter; and

h. Lithium batteries or cells are not authorized aboard an aircraft in checked or carry-on luggage except as provided in §175.10.

189 *Medium lithium cells and batteries.* Effective October 1, 2008, when transported by motor vehicle or rail car, lithium cells or batteries, including cells or batteries packed with or contained in equipment, are not subject to any other requirements of this subchapter if they meet all of the following:

a. The lithium content anode of each cell, when fully charged, is not more than 5 grams.

b. The aggregate lithium content of the anode of each battery, when fully charged, is not more than 25 grams.

c. The cells or batteries are of a type proven to meet the requirements of each test in the UN Manual of Tests and Criteria (IBR; see §171.7 of this subchapter). A cell or battery and equipment containing a cell or battery that was first transported prior to January 1, 2006 and is of a type proven to meet the criteria of Class 9 by testing in accordance with the tests in the UN Manual of Tests and Criteria, Third Revised Edition, 1999, need not be retested.

d. Cells or batteries are separated so as to prevent short circuits and are packed in a strong outer packaging or are contained in equipment.

e. The outside of each package must be marked "LITHIUM BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD AIRCRAFT AND VESSEL" on a background of contrasting color, in letters:

(1) At least 12 mm (0.5 inch) in height on packages having a gross weight of more than 30 kg (66 pounds); or

(2) At least 6 mm (0.25 inch) on packages having a gross weight of 30 kg (66 pounds) or less, except that smaller font may be used as necessary to fit package dimensions.

f. Except when contained in equipment, each package containing more than 24 lithium cells or 12 lithium batteries must be:

(1) Marked to indicate that it contains lithium batteries, and that special procedures should be followed in the event that the package is damaged;

(2) Accompanied by a document indicating that the package contains lithium batteries and that special procedures should be fol-

lowed in the event that the package is damaged;

(3) Capable of withstanding a 1.2 meter drop test in any orientation without damage to cells or batteries contained in the package, without shifting of the contents that would allow short circuiting and without release of package contents; and

(4) Gross weight of the package may not exceed 30 kg (66 pounds). This requirement does not apply to lithium cells or batteries packed with equipment.

g. Electrical devices must conform to §173.21 of this subchapter.

190 Until the effective date of the standards set forth in Special Provision 189, medium lithium cells or batteries, including cells or batteries packed with or contained in equipment, are not subject to any other requirements of this subchapter if they meet all of the following:

a. *Primary lithium batteries and cells.* (1) Primary lithium batteries and cells are forbidden for transport aboard passenger-carrying aircraft. The outside of each package that contains primary (nonrechargeable) lithium batteries or cells must be marked "PRIMARY LITHIUM BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT" or "LITHIUM METAL BATTERIES—FORBIDDEN FOR TRANSPORT ABOARD PASSENGER AIRCRAFT" on a background of contrasting color. The letters in the marking must be:

(i) At least 12 mm (0.5 inch) in height on packages having a gross weight of more than 30 kg (66 pounds); or

(ii) At least 6 mm (0.25 inch) on packages having a gross weight of 30 kg (66 pounds) or less, except that smaller font may be used as necessary to fit package dimensions; and

(2) The provisions of paragraph (a)(1) do not apply to packages that contain 5 kg (11 pounds) net weight or less of primary lithium batteries or cells that are contained in or packed with equipment and the package contains no more than the number of lithium batteries or cells necessary to power the piece of equipment.

b. The lithium content of each cell, when fully charged, is not more than 5 grams.

c. The aggregate lithium content of each battery, when fully charged, is not more than 25 grams.

d. The cells or batteries are of a type proven to meet the requirements of each test in the UN Manual of Tests and Criteria (IBR; see §171.7 of this subchapter). A cell or battery and equipment containing a cell or battery that was first transported prior to January 1, 2006 and is of a type proven to meet the criteria of Class 9 by testing in accordance with the tests in the UN Manual of Tests and Criteria, Third Revised Edition, 1999, need not be retested.

e. Cells or batteries are separated so as to prevent short circuits and are packed in a

## § 172.102

strong outer packaging or are contained in equipment.

f. Electrical devices must conform to §173.21 of this subchapter.

(2) “A” codes. These provisions apply only to transportation by aircraft:

### *Code/Special Provisions*

- A1 Single packagings are not permitted on passenger aircraft.
- A2 Single packagings are not permitted on aircraft.
- A3 For combination packagings, if glass inner packagings (including ampoules) are used, they must be packed with absorbent material in tightly closed metal receptacles before packing in outer packagings.
- A4 Liquids having an inhalation toxicity of Packing Group I are not permitted on aircraft.
- A5 Solids having an inhalation toxicity of Packing Group I are not permitted on passenger aircraft and may not exceed a maximum net quantity per package of 15 kg (33 pounds) on cargo aircraft.
- A6 For combination packagings, if plastic inner packagings are used, they must be packed in tightly closed metal receptacles before packing in outer packagings.
- A7 Steel packagings must be corrosion-resistant or have protection against corrosion.
- A8 For combination packagings, if glass inner packagings (including ampoules) are used, they must be packed with cushioning material in tightly closed metal receptacles before packing in outer packagings.
- A9 For combination packagings, if plastic bags are used, they must be packed in tightly closed metal receptacles before packing in outer packagings.
- A10 When aluminum or aluminum alloy construction materials are used, they must be resistant to corrosion.
- A11 For combination packagings, when metal inner packagings are permitted, only specification cylinders constructed of metals which are compatible with the hazardous material may be used.
- A13 Bulk packagings are not authorized for transportation by aircraft.
- A14 This material is not authorized to be transported as a limited quantity or consumer commodity in accordance with §173.306 of this subchapter when transported aboard an aircraft.
- A19 Combination packagings consisting of outer fiber drums or plywood drums, with inner plastic packagings, are not authorized for transportation by aircraft.
- A20 Plastic bags as inner receptacles of combination packagings are not authorized for transportation by aircraft.
- A29 Combination packagings consisting of outer expanded plastic boxes with inner

## 49 CFR Ch. I (10–1–08 Edition)

plastic bags are not authorized for transportation by aircraft.

A30 Ammonium permanganate is not authorized for transportation on aircraft.

A34 Aerosols containing a corrosive liquid in Packing Group II charged with a gas are not permitted for transportation by aircraft.

A35 This includes any material which is not covered by any of the other classes but which has an anesthetic, narcotic, noxious or other similar properties such that, in the event of spillage or leakage on an aircraft, extreme annoyance or discomfort could be caused to crew members so as to prevent the correct performance of assigned duties.

A37 This entry applies only to a material meeting the definition in §171.8 of this subchapter for self-defense spray.

A53 Refrigerating machines and refrigerating machine components are not subject to the requirements of this subchapter when containing less than 12 kg (26.4 pounds) of a non-flammable gas or when containing 12 L (3 gallons) or less of ammonia solution (UN2672) (see §173.307 of this subchapter).

A54 Lithium batteries or lithium batteries contained or packed with equipment that exceed the maximum gross weight allowed by Column (9B) of the §172.101 Table may only be transported on cargo aircraft if approved by the Associate Administrator.

A55 Prototype lithium batteries and cells that are packed with not more than 24 cells or 12 batteries per packaging that have not completed the test requirements in Sub-section 38.3 of the UN Manual of Tests and Criteria (incorporated by reference; see §171.7 of this subchapter) may be transported by cargo aircraft if approved by the Associate Administrator and provided the following requirements are met:

- a. The cells and batteries must be transported in rigid outer packagings that conform to the requirements of Part 178 of this subchapter at the Packing Group I performance level; and
- b. Each cell and battery must be protected against short circuiting, must be surrounded by cushioning material that is non-combustible and non-conductive, and must be individually packed in an inner packaging that is placed inside an outer specification packaging.

A56 Radioactive material with a subsidiary hazard of Division 4.2, Packing Group I, must be transported in Type B packages when offered for transportation by aircraft. Radioactive material with a subsidiary hazard of Division 2.1 is forbidden from transport on passenger aircraft.

A59 Sterilization devices, when containing less than 30 mL per inner packaging with no more than 300 mL per outer packaging

may be transported in accordance with provisions in §173.4(a)(11)(i). In addition, after filling, each inner packaging must be determined to be leak-tight by placing the inner packaging in a hot water bath at a temperature and for a period of time sufficient to ensure an internal pressure equal to the vapor pressure of ethylene oxide at 55 °C is achieved. Any inner packaging showing evidence of leakage, distortion or other defect under this test may not be transported under the terms of this special provision. In addition to the packaging required in §173.4, inner packagings must be placed in a sealed plastic bag compatible with ethylene oxide and capable of containing the contents in the event of breakage or leakage of the inner packaging. Glass inner packagings must be placed within a protective shield capable of preventing the glass from puncturing the plastic bag in the event of damage to the packaging (e.g., crushing).

A60 Articles such as sterilization devices, UN2014, Hydrogen peroxide, aqueous solutions with more than 40 percent but not more than 60 percent hydrogen peroxide (stabilized as necessary), when containing less than 30 mL per inner packaging with not more than 150 mL per outer packaging, may be transported in accordance with the provisions in §173.4, irrespective of §173.4(a)(11)(i), provided such packagings were first subjected to comparative fire testing. Comparative fire testing must show no difference in burning rate between a package as prepared for transport (including the substance to be transported) and an identical package filled with water.

A82 The quantity limits in columns (9A) and (9B) do not apply to human or animal body parts, whole organs or whole bodies known to contain or suspected of containing an infectious substance.

A100 Primary (non-rechargeable) lithium batteries and cells are forbidden for transport aboard passenger carrying aircraft. Secondary (rechargeable) lithium batteries and cells are authorized aboard passenger carrying aircraft in packages that do not exceed a gross weight of 5 kg.

A101 A primary lithium battery or cell packed with or contained in equipment is forbidden for transport aboard a passenger carrying aircraft unless the equipment and the battery conform to the following provisions and the package contains no more than the number of lithium batteries or cells necessary to power the intended piece of equipment:

- (1) The lithium content of each cell, when fully charged, is not more than 5 grams.
- (2) The aggregate lithium content of the anode of each battery, when fully charged, is not more than 25 grams.
- (3) The net weight of lithium batteries does not exceed 5 kg (11 pounds).

A103 Equipment is authorized aboard passenger carrying aircraft if the gross weight of the inner package of secondary lithium batteries or cells packed with the equipment does not exceed 5 kg (11 pounds).

A104 The net weight of secondary lithium batteries or cells contained in equipment may not exceed 5 kg (11 pounds) in packages that are authorized aboard passenger carrying aircraft.

A105 The total net quantity of dangerous goods contained in one package, excluding magnetic material, must not exceed the following:

- a. 1 kg (2.2 pounds) in the case of solids;
- b. 0.5 L (0.1 gallons) in the case of liquids;
- c. 0.5 kg (1.1 pounds) in the case of Division 2.2 gases; or
- d. any combination thereof.

(3) “B” codes. These provisions apply only to bulk packagings. Except as otherwise provided in this subchapter, these special provisions do not apply to UN portable tanks or IBCs:

#### Code/Special Provisions

B1 If the material has a flash point at or above 38 °C (100 °F) and below 93 °C (200 °F), then the bulk packaging requirements of §173.241 of this subchapter are applicable. If the material has a flash point of less than 38 °C (100 °F), then the bulk packaging requirements of §173.242 of this subchapter are applicable.

B2 MC 300, MC 301, MC 302, MC 303, MC 305, and MC 306 and DOT 406 cargo tanks are not authorized.

B3 MC 300, MC 301, MC 302, MC 303, MC 305, and MC 306 and DOT 406 cargo tanks and DOT 57 portable tanks are not authorized.

B4 MC 300, MC 301, MC 302, MC 303, MC 305, and MC 306 and DOT 406 cargo tanks are not authorized.

B5 Only ammonium nitrate solutions with 35 percent or less water that will remain completely in solution under all conditions of transport at a maximum lading temperature of 116 °C (240 °F) are authorized for transport in the following bulk packagings: MC 307, MC 312, DOT 407 and DOT 412 cargo tanks with at least 172 kPa (25 psig) design pressure. The packaging shall be designed for a working temperature of at least 121 °C (250 °F). Only Specifications MC 304, MC 307 or DOT 407 cargo tank motor vehicles are authorized for transportation by vessel.

B6 Packagings shall be made of steel.

B7 Safety relief devices are not authorized on multi-unit tank car tanks. Openings for safety relief devices on multi-unit tank car tanks shall be plugged or blank flanged.

B8 Packagings shall be made of nickel, stainless steel, or steel with nickel, stainless steel, lead or other suitable corrosion resistant metallic lining.



## § 172.102

## 49 CFR Ch. I (10–1–08 Edition)

- B9 Bottom outlets are not authorized.
- B10 MC 300, MC 301, MC 302, MC 303, MC 305, and MC 306 and DOT 406 cargo tanks, and DOT 57 portable tanks are not authorized.
- B11 Tank car tanks must have a test pressure of at least 2,068.5 kPa (300 psig). Cargo and portable tanks must have a design pressure of at least 1,207 kPa (175 psig).
- B13 A nonspecification cargo tank motor vehicle authorized in §173.247 of this subchapter must be at least equivalent in design and in construction to a DOT 406 cargo tank or MC 306 cargo tank (if constructed before August 31, 1995), except as follows:
- Packagings equivalent to MC 306 cargo tanks are excepted from the certification, venting, and emergency flow requirements of the MC 306 specification.
  - Packagings equivalent to DOT 406 cargo tanks are excepted from §§178.345–7(d)(5), circumferential reinforcements; 178.345–10, pressure relief; 178.345–11, outlets; 178.345–14, marking, and 178.345–15, certification.
  - Packagings are excepted from the design stress limits at elevated temperatures, as described in Section VIII of the ASME Code (IBR, see §171.7 of this subchapter). However, the design stress limits may not exceed 25 percent of the stress for 0 temper at the maximum design temperature of the cargo tank, as specified in the Aluminum Association's "Aluminum Standards and Data" (IBR, see §171.7 of this subchapter).
- B14 Each bulk packaging, except a tank car or a multi-unit-tank car tank, must be insulated with an insulating material so that the overall thermal conductance at 15.5 °C (60 °F) is no more than 1.5333 kilojoules per hour per square meter per degree Celsius (0.075 Btu per hour per square foot per degree Fahrenheit) temperature differential. Insulating materials must not promote corrosion to steel when wet.
- B15 Packagings must be protected with non-metallic linings impervious to the lading or have a suitable corrosion allowance.
- B16 The lading must be completely covered with nitrogen, inert gas or other inert materials.
- B18 Open steel hoppers or bins are authorized.
- B23 Tanks must be made of steel that is rubber lined or unlined. Unlined tanks must be passivated before being placed in service. If unlined tanks are washed out with water, they must be repassivated prior to return to service. Lading in unlined tanks must be inhibited so that the corrosive effect on steel is not greater than that of hydrofluoric acid of 65 percent concentration.
- B25 Packagings must be made from monel or nickel or monel-lined or nickel-lined steel.
- B26 Tanks must be insulated. Insulation must be at least 100 mm (3.9 inches) except that the insulation thickness may be reduced to 51 mm (2 inches) over the exterior heater coils. Interior heating coils are not authorized. The packaging may not be loaded with a material outside of the packaging's design temperature range. In addition, the material also must be covered with an inert gas or the container must be filled with water to the tank's capacity. After unloading, the residual material also must be covered with an inert gas or the container must be filled with water to the tank's capacity.
- B27 Tanks must have a service pressure of 1,034 kPa (150 psig). Tank car tanks must have a test pressure rating of 1,379 kPa (200 psig). Lading must be blanketed at all times with a dry inert gas at a pressure not to exceed 103 kPa (15 psig).
- B28 Packagings must be made of stainless steel.
- B30 MC 312, MC 330, MC 331 and DOT 412 cargo tanks and DOT 51 portable tanks must be made of stainless steel, except that steel other than stainless steel may be used in accordance with the provisions of §173.24b(b) of this subchapter. Thickness of stainless steel for tank shell and heads for cargo tanks and portable tanks must be the greater of 7.62 mm (0.300 inch) or the thickness required for a tank with a design pressure at least equal to 1.5 times the vapor pressure of the lading at 46 °C (115 °F). In addition, MC 312 and DOT 412 cargo tank motor vehicles must:
- Be ASME Code (U) stamped for 100% radiography of all pressure-retaining welds;
  - Have accident damage protection which conforms with §178.345–8 of this subchapter;
  - Have a MAWP or design pressure of at least 87 psig; and
  - Have a bolted manway cover.
- B32 MC 312, MC 330, MC 331, DOT 412 cargo tanks and DOT 51 portable tanks must be made of stainless steel, except that steel other than stainless steel may be used in accordance with the provisions of §173.24b(b) of this subchapter. Thickness of stainless steel for tank shell and heads for cargo tanks and portable tanks must be the greater of 6.35 mm (0.250 inch) or the thickness required for a tank with a design pressure at least equal to 1.3 times the vapor pressure of the lading at 46 °C (115 °F). In addition, MC 312 and DOT 412 cargo tank motor vehicles must:
- Be ASME Code (U) stamped for 100% radiography of all pressure-retaining welds;
  - Have accident damage protection which conforms with §178.345–8 of this subchapter;
  - Have a MAWP or design pressure of at least 87 psig; and

d. Have a bolted manway cover.

B33 MC 300, MC 301, MC 302, MC 303, MC 305, MC 306, and DOT 406 cargo tanks equipped with a 1 psig normal vent used to transport gasoline must conform to Table I of this Special Provision. Based on the volatility class determined by using ASTM D 439 and the Reid vapor pressure (RVP) of the particular gasoline, the maximum lading pressure and maximum ambient temperature permitted during the loading of gasoline may not exceed that listed in Table I.

TABLE I—MAXIMUM AMBIENT TEMPERATURE—  
GASOLINE

| ASTM D439 volatility class | Maximum lading and ambient temperature (see note 1) |
|----------------------------|-----------------------------------------------------|
| A .....<br>(RVP≤9.0 psia)  | 131 °F                                              |
| B .....<br>(RVP≤10.0 psia) | 124 °F                                              |
| C .....<br>(RVP≤11.5 psia) | 116 °F                                              |
| D .....<br>(RVP≤13.5 psia) | 107 °F                                              |
| E .....<br>(RVP≤15.0 psia) | 100 °F                                              |

NOTE 1: Based on maximum lading pressure of 1 psig at top of cargo tank.

B35 Tank cars containing hydrogen cyanide may be alternatively marked “Hydrocyanic acid, liquefied” if otherwise conforming to marking requirements in subpart D of this part. Tank cars marked “HYDROCYANIC ACID” prior to October 1, 1991 do not need to be remarked.

B37 The amount of nitric oxide charged into any tank car tank may not exceed 1,379 kPa (200 psig) at 21 °C (70 °F).

B42 Tank cars must have a test pressure of 34.47 Bar (500 psig) or greater and conform to Class 105J. Each tank car must have a reclosing pressure relief device having a start-to-discharge pressure of 10.34 Bar (150 psig). The tank car specification may be marked to indicate a test pressure of 13.79 Bar (200 psig).

B44 All parts of valves and safety relief devices in contact with lading must be of a material which will not cause formation of acetylides.

B45 Each tank must have a reclosing combination pressure relief device equipped with stainless steel or platinum rupture discs approved by the AAR Tank Car Committee.

B46 The detachable protective housing for the loading and unloading valves of multi-unit tank car tanks must withstand tank test pressure and must be approved by the Associate Administrator.

B47 Each tank may have a reclosing pressure relief device having a start-to-discharge pressure setting of 310 kPa (45 psig).

B48 Portable tanks in sodium metal service may be visually inspected at least once every 5 years instead of being retested hydrostatically. Date of the visual inspection must be stenciled on the tank near the other required markings.

B49 Tanks equipped with interior heater coils are not authorized. Single unit tank car tanks must have a reclosing pressure relief device having a start-to-discharge pressure set at no more than 1551 kPa (225 psig).

B50 Each valve outlet of a multi-unit tank car tank must be sealed by a threaded solid plug or a threaded cap with inert luting or gasket material. Valves must be of stainless steel and the caps, plugs, and valve seats must be of a material that will not deteriorate as a result of contact with the lading.

B52 Notwithstanding the provisions of §173.24b of this subchapter, non-reclosing pressure relief devices are authorized on DOT 57 portable tanks.

B53 Packagings must be made of either aluminum or steel.

B54 Open-top, sift-proof rail cars are also authorized.

B55 Water-tight, sift-proof, closed-top, metal-covered hopper cars, equipped with a venting arrangement (including flame arrestors) approved by the Associate Administrator are also authorized.

B56 Water-tight, sift-proof, closed-top, metal-covered hopper cars are also authorized if the particle size of the hazardous material is not less than 149 microns.

B57 Class 115A tank car tanks used to transport chloroprene must be equipped with a non-reclosing pressure relief device of a diameter not less than 305 mm (12 inches) with a maximum rupture disc pressure of 310 kPa (45 psig).

B59 Water-tight, sift-proof, closed-top, metal-covered hopper cars are also authorized provided that the lading is covered with a nitrogen blanket.

B60 DOT Specification 106A500X multi-unit tank car tanks that are not equipped with a pressure relief device of any type are authorized. For the transportation of phosgene, the outage must be sufficient to prevent tanks from becoming liquid full at 55 °C (130 °F).

B61 Written procedures covering details of tank car appurtenances, dome fittings, safety devices, and marking, loading, handling, inspection, and testing practices must be approved by the Associate Administrator before any single unit tank car tank is offered for transportation.

B64 Each single unit tank car tank built after December 31, 1990 must be equipped with a tank head puncture resistance system that conforms to §179.16 of this subchapter.

- B65 Tank cars must have a test pressure of 34.47 Bar (500 psig) or greater and conform to Class 105A. Each tank car must have a pressure relief device having a start-to-discharge pressure of 15.51 Bar (225 psig). The tank car specification may be marked to indicate a test pressure of 20.68 Bar (300 psig).
- B66 Each tank must be equipped with gas tight valve protection caps. Outage must be sufficient to prevent tanks from becoming liquid full at 55 °C (130 °F). Specification 110A500W tanks must be stainless steel.
- B67 All valves and fittings must be protected by a securely attached cover made of metal not subject to deterioration by the lading, and all valve openings, except safety valve, must be fitted with screw plugs or caps to prevent leakage in the event of valve failure.
- B68 Sodium must be in a molten condition when loaded and allowed to solidify before shipment. Outage must be at least 5 percent at 98 °C (208 °F). Bulk packagings must have exterior heating coils fusion welded to the tank shell which have been properly stress relieved. The only tank car tanks authorized are Class DOT 105 tank cars having a test pressure of 2,069 kPa (300 psig) or greater.
- B69 Dry sodium cyanide or potassium cyanide may be shipped in the following sift-proof and weather-resistant packagings: metal covered hopper cars, covered motor vehicles, portable tanks, or non-specification bins.
- B70 If DOT 103ANW tank car tank is used: All cast metal in contact with the lading must have 96.7 percent nickel content; and the lading must be anhydrous and free from any impurities.
- B71 Tank cars must have a test pressure of 20.68 Bar (300 psig) or greater and conform to Class 105, 112, 114 or 120.
- B72 Tank cars must have a test pressure of 34.47 Bar (500 psig) or greater and conform to Class 105J, 106, or 110.
- B74 Tank cars must have a test pressure of 20.68 Bar (300 psig) or greater and conform to Class 105S, 106, 110, 112J, 114J or 120S.
- B76 Tank cars must have a test pressure of 20.68 Bar (300 psig) or greater and conform to Class 105S, 112J, 114J or 120S. Each tank car must have a reclosing pressure relief device having a start-to-discharge pressure of 10.34 Bar (150 psig). The tank car specification may be marked to indicate a test pressure of 13.79 Bar (200 psig).
- B77 Other packaging are authorized when approved by the Associate Administrator.
- B78 Tank cars must have a test pressure of 4.14 Bar (60 psig) or greater and conform to Class 103, 104, 105, 109, 111, 112, 114 or 120. Heater pipes must be of welded construction designed for a test pressure of 500 psig. A 25 mm (1 inch) woven lining of asbestos

or other approved material must be placed between the bolster slabbing and the bottom of the tank. If a tank car tank is equipped with a non-reclosing pressure relief device, the rupture disc must be perforated with a 3.2 mm (0.13 inch) diameter hole. If a tank car tank is equipped with a reclosing pressure relief valve, the tank must also be equipped with a vacuum relief valve.

- B80 Each cargo tank must have a minimum design pressure of 276 kPa (40 psig).
- B81 Venting and pressure relief devices for tank car tanks and cargo tanks must be approved by the Associate Administrator.
- B82 Cargo tanks and portable tanks are not authorized.
- B83 Bottom outlets are prohibited on tank car tanks transporting sulfuric acid in concentrations over 65.25 percent.
- B84 Packagings must be protected with non-metallic linings impervious to the lading or have a suitable corrosion allowance for sulfuric acid or spent sulfuric acid in concentration up to 65.25 percent.
- B85 Cargo tanks must be marked with the name of the lading in accordance with the requirements of § 172.302(b).
- B90 Steel tanks conforming or equivalent to ASME specifications which contain solid or semisolid residual motor fuel anti-knock mixture (including rust, scale, or other contaminants) may be shipped by rail freight or highway. The tank must have been designed and constructed to be capable of withstanding full vacuum. All openings must be closed with gasketed blank flanges or vapor tight threaded closures.
- B115 Rail cars, highway trailers, roll-on/roll-off bins, or other non-specification bulk packagings are authorized. Packagings must be sift-proof, prevent liquid water from reaching the hazardous material, and be provided with sufficient venting to preclude dangerous accumulation of flammable, corrosive, or toxic gaseous emissions such as methane, hydrogen, and ammonia. The material must be loaded dry.
- (4) *Table 1 and Table 2—IB Codes and IP Special IBC Packing Provisions.* These provisions apply only to transportation in IBCs. When no IBC code is assigned in the § 172.101 Table for a specific proper shipping name, or in § 173.225(e) for Type F organic peroxides, an IBC may not be used unless authorized by the Associate Administrator. The letter “Z” shown in the marking code for composite IBCs must be replaced with a capital code letter designation found in § 178.702(a)(2) of this subchapter to

specify the material used for the outer packaging. Tables 1 and 2 follow:

TABLE 1—IB CODES (IBC CODES)

| IBC Code  | Authorized IBCs                                                                                                                                                                                                                                                                                                                                                                                                  |
|-----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| IB1 ..... | <i>Authorized IBCs:</i> Metal (31A, 31B and 31N).<br><i>Additional Requirement:</i> Only liquids with a vapor pressure less than or equal to 110 kPa at 50 °C (1.1 bar at 122 °F), or 130 kPa at 55 °C (1.3 bar at 131 °F) are authorized.                                                                                                                                                                       |
| IB2 ..... | <i>Authorized IBCs:</i> Metal (31A, 31B and 31N); Rigid plastics (31H1 and 31H2); Composite (31HZ1).<br><i>Additional Requirement:</i> Only liquids with a vapor pressure less than or equal to 110 kPa at 50 °C (1.1 bar at 122 °F), or 130 kPa at 55 °C (1.3 bar at 131 °F) are authorized.                                                                                                                    |
| IB3 ..... | <i>Authorized IBCs:</i> Metal (31A, 31B and 31N); Rigid plastics (31H1 and 31H2); Composite (31HZ1 and 31HA2, 31HB2, 31HN2, 31HD2 and 31HH2).<br><i>Additional Requirement:</i> Only liquids with a vapor pressure less than or equal to 110 kPa at 50 °C (1.1 bar at 122 °F), or 130 kPa at 55 °C (1.3 bar at 131 °F) are authorized, except for UN2672 (also see Special Provision IP8 in Table 2 for UN2672). |
| IB4 ..... | <i>Authorized IBCs:</i> Metal (11A, 11B, 11N, 21A, 21B, 21N, 31A, 31B and 31N).                                                                                                                                                                                                                                                                                                                                  |
| IB5 ..... | <i>Authorized IBCs:</i> Metal (11A, 11B, 11N, 21A, 21B, 21N, 31A, 31B and 31N); Rigid plastics (11H1, 11H2, 21H1, 21H2, 31H1 and 31H2); Composite (11HZ1, 21HZ1 and 31HZ1).                                                                                                                                                                                                                                      |
| IB6 ..... | <i>Authorized IBCs:</i> Metal (11A, 11B, 11N, 21A, 21B, 21N, 31A, 31B and 31N); Rigid plastics (11H1, 11H2, 21H1, 21H2, 31H1 and 31H2); Composite (11HZ1, 11HZ2, 21HZ1, 21HZ2, 31HZ1 and 31HZ2).<br><i>Additional Requirement:</i> Composite IBCs 11HZ2 and 21HZ2 may not be used when the hazardous materials being transported may become liquid during transport.                                             |
| IB7 ..... | <i>Authorized IBCs:</i> Metal (11A, 11B, 11N, 21A, 21B, 21N, 31A, 31B and 31N); Rigid plastics (11H1, 11H2, 21H1, 21H2, 31H1 and 31H2); Composite (11HZ1, 11HZ2, 21HZ1, 21HZ2, 31HZ1 and 31HZ2); Wooden (11C, 11D and 11F).<br><i>Additional Requirement:</i> Liners of wooden IBCs must be sift-proof.                                                                                                          |
| IB8 ..... | <i>Authorized IBCs:</i> Metal (11A, 11B, 11N, 21A, 21B, 21N, 31A, 31B and 31N); Rigid plastics (11H1, 11H2, 21H1, 21H2, 31H1 and 31H2); Composite (11HZ1, 11HZ2, 21HZ1, 21HZ2, 31HZ1 and 31HZ2); Fiberboard (11G); Wooden (11C, 11D and 11F); Flexible (13H1, 13H2, 13H3, 13H4, 13H5, 13L1, 13L2, 13L3, 13L4, 13M1 or 13M2).                                                                                     |
| IB9 ..... | IBCs are only authorized if approved by the Associate Administrator.                                                                                                                                                                                                                                                                                                                                             |

TABLE 2—IP CODES

| IBC Code   | Authorized IBCs                                                                                                                                                                                                                                                                                                                                 |
|------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| IP1 .....  | IBCs must be packed in closed freight containers or a closed transport vehicle.                                                                                                                                                                                                                                                                 |
| IP2 .....  | When IBCs other than metal or rigid plastics IBCs are used, they must be offered for transportation in a closed freight container or a closed transport vehicle.                                                                                                                                                                                |
| IP3 .....  | Flexible IBCs must be sift-proof and water-resistant or must be fitted with a sift-proof and water-resistant liner.                                                                                                                                                                                                                             |
| IP4 .....  | Flexible, fiberboard or wooden IBCs must be sift-proof and water-resistant or be fitted with a sift-proof and water-resistant liner.                                                                                                                                                                                                            |
| IP5 .....  | IBCs must have a device to allow venting. The inlet to the venting device must be located in the vapor space of the IBC under maximum filling conditions.                                                                                                                                                                                       |
| IP6 .....  | Non-specification bulk bins are authorized.                                                                                                                                                                                                                                                                                                     |
| IP7 .....  | For UN identification numbers 1327, 1363, 1364, 1365, 1386, 1841, 2211, 2217, 2793 and 3314, IBCs are not required to meet the IBC performance tests specified in part 178, subpart N of this subchapter.                                                                                                                                       |
| IP8 .....  | Ammonia solutions may be transported in rigid or composite plastic IBCs (31H1, 31H2 and 31HZ1) that have successfully passed, without leakage or permanent deformation, the hydrostatic test specified in § 178.814 of this subchapter at a test pressure that is not less than 1.5 times the vapor pressure of the contents at 55 °C (131 °F). |
| IP13 ..... | Transportation by vessel in IBCs is prohibited.                                                                                                                                                                                                                                                                                                 |
| IP14 ..... | Air shall be eliminated from the vapor space by nitrogen or other means.                                                                                                                                                                                                                                                                        |
| IP20 ..... | Dry sodium cyanide or potassium cyanide is also permitted in siftproof, water-resistant, fiberboard IBCs when transported in closed freight containers or transport vehicles.                                                                                                                                                                   |

(5) “N” codes. These provisions apply only to non-bulk packagings:

*Code/Special Provisions*

N3 Glass inner packagings are permitted in combination or composite packagings only if the hazardous material is free from hydrofluoric acid.

N4 For combination or composite packagings, glass inner packagings, other than ampoules, are not permitted.

N5 Glass materials of construction are not authorized for any part of a packaging which is normally in contact with the hazardous material.

N6 Battery fluid packaged with electric storage batteries, wet or dry, must conform to the packaging provisions of § 173.159 (g) or (h) of this subchapter.

- N7 The hazard class or division number of the material must be marked on the package in accordance with § 172.302 of this subchapter. However, the hazard label corresponding to the hazard class or division may be substituted for the marking.
- N8 Nitroglycerin solution in alcohol may be transported under this entry only when the solution is packed in metal cans of not more than 1 L capacity each, overpacked in a wooden box containing not more than 5 L. Metal cans must be completely surrounded with absorbent cushioning material. Wooden boxes must be completely lined with a suitable material impervious to water and nitroglycerin.
- N11 This material is excepted for the specification packaging requirements of this subchapter if the material is packaged in strong, tight non-bulk packaging meeting the requirements of subparts A and B of part 173 of this subchapter.
- N12 Plastic packagings are not authorized.
- N20 A 5M1 multi-wall paper bag is authorized if transported in a closed transport vehicle.
- N25 Steel single packagings are not authorized.
- N32 Aluminum materials of construction are not authorized for single packagings.
- N33 Aluminum drums are not authorized.
- N34 Aluminum construction materials are not authorized for any part of a packaging which is normally in contact with the hazardous material.
- N36 Aluminum or aluminum alloy construction materials are permitted only for halogenated hydrocarbons that will not react with aluminum.
- N37 This material may be shipped in an integrally-lined fiber drum (1G) which meets the general packaging requirements of subpart B of part 173 of this subchapter, the requirements of part 178 of this subchapter at the packing group assigned for the material and to any other special provisions of column 7 of the § 172.101 table.
- N40 This material is not authorized in the following packagings:
- A combination packaging consisting of a 4G fiberboard box with inner receptacles of glass or earthenware;
  - A single packaging of a 4C2 sift-proof, natural wood box; or
  - A composite packaging 6PG2 (glass, porcelain or stoneware receptacles within a fiberboard box).
- N41 Metal construction materials are not authorized for any part of a packaging which is normally in contact with the hazardous material.
- N42 1A1 drums made of carbon steel with thickness of body and heads of not less than 1.3 mm (0.050 inch) and with a corrosion-resistant phenolic lining are authorized for stabilized benzyl chloride if tested and certified to the Packing Group I performance level at a specific gravity of not less than 1.8.
- N43 Metal drums are permitted as single packagings only if constructed of nickel or monel.
- N45 Copper cartridges are authorized as inner packagings if the hazardous material is not in dispersion.
- N65 Outage must be sufficient to prevent cylinders or spheres from becoming liquid full at 55 °C (130 °F). The vacant space (outage) may be charged with a nonflammable nonliquefied compressed gas if the pressure in the cylinder or sphere at 55 °C (130 °F) does not exceed 125 percent of the marked service pressure.
- N72 Packagings must be examined by the Bureau of Explosives and approved by the Associate Administrator.
- N73 Packagings consisting of outer wooden or fiberboard boxes with inner glass, metal or other strong containers; metal or fiber drums; kegs or barrels; or strong metal cans are authorized and need not conform to the requirements of part 178 of this subchapter.
- N74 Packages consisting of tightly closed inner containers of glass, earthenware, metal or polyethylene, capacity not over 0.5 kg (1.1 pounds) securely cushioned and packed in outer wooden barrels or wooden or fiberboard boxes, not over 15 kg (33 pounds) net weight, are authorized and need not conform to the requirements of part 178 of this subchapter.
- N75 Packages consisting of tightly closed inner packagings of glass, earthenware or metal, securely cushioned and packed in outer wooden barrels or wooden or fiberboard boxes, capacity not over 2.5 kg (5.5 pounds) net weight, are authorized and need not conform to the requirements of part 178 of this subchapter.
- N76 For materials of not more than 25 percent active ingredient by weight, packages consisting of inner metal packagings not greater than 250 mL (8 ounces) capacity each, packed in strong outer packagings together with sufficient absorbent material to completely absorb the liquid contents are authorized and need not conform to the requirements of part 178 of this subchapter.
- N77 For materials of not more than two percent active ingredients by weight, packagings need not conform to the requirements of part 178 of this subchapter, if liquid contents are absorbed in an inert material.
- N78 Packages consisting of inner glass, earthenware, or polyethylene or other non-fragile plastic bottles or jars not over 0.5 kg (1.1 pounds) capacity each, or metal cans not over five pounds capacity each, packed in outer wooden boxes, barrels or kegs, or fiberboard boxes are authorized and need not conform to the requirements

of part 178 of this subchapter. Net weight of contents in fiberboard boxes may not exceed 29 kg (64 pounds). Net weight of contents in wooden boxes, barrels or kegs may not exceed 45 kg (99 pounds).

N79 Packages consisting of tightly closed metal inner packagings not over 0.5 kg (1.1 pounds) capacity each, packed in outer wooden or fiberboard boxes, or wooden barrels, are authorized and need not conform to the requirements of part 178 of this subchapter. Net weight of contents may not exceed 15 kg (33 pounds).

N80 Packages consisting of one inner metal can, not over 2.5 kg (5.5 pounds) capacity, packed in an outer wooden or fiberboard box, or a wooden barrel, are authorized and need not conform to the requirements of part 178 of this subchapter.

N82 See §173.306 of this subchapter for classification criteria for flammable aerosols.

N83 This material may not be transported in quantities of more than 11.5 kg (25.4 lbs) per package.

N84 The maximum quantity per package is 500 g (1.1 lbs.).

N85 Packagings certified at the Packing Group I performance level may not be used.

N86 UN pressure receptacles made of aluminum alloy are not authorized.

N87 The use of copper valves on UN pressure receptacles is prohibited.

N88 Any metal part of a UN pressure receptacle in contact with the contents may not contain more than 65% copper, with a tolerance of 1%.

N89 When steel UN pressure receptacles are used, only those bearing the “H” mark are authorized.

(6) “R” codes. These provisions apply only to transportation by rail. [Reserved]

(7) “T” codes. (i) These provisions apply to the transportation of haz-

ardous materials in UN portable tanks. Portable tank instructions specify the requirements applicable to a portable tank when used for the transportation of a specific hazardous material. These requirements must be met in addition to the design and construction specifications in part 178 of this subchapter. Portable tank instructions T1 through T22 specify the applicable minimum test pressure, the minimum shell thickness (in reference steel), bottom opening requirements and pressure relief requirements. Liquefied compressed gases are assigned to portable tank instruction T50. Refrigerated liquefied gases that are authorized to be transported in portable tanks are specified in tank instruction T75.

(ii) The following table specifies the portable tank requirements applicable to “T” Codes T1 through T22. Column 1 specifies the “T” Code. Column 2 specifies the minimum test pressure, in bar (1 bar = 14.5 psig), at which the periodic hydrostatic testing required by §180.605 of this subchapter must be conducted. Column 3 specifies the section reference for minimum shell thickness or, alternatively, the minimum shell thickness value. Column 4 specifies the applicability of §178.275(g)(3) of this subchapter for the pressure relief devices. When the word “Normal” is indicated, §178.275(g)(3) of this subchapter does not apply. Column 5 references the applicable requirements for bottom openings in part 178 of this subchapter or references “Prohibited” which means bottom openings are prohibited. The table follows:

TABLE OF PORTABLE TANK T CODES T1–T22

[Portable tank codes T1–T22 apply to liquid and solid hazardous materials of Classes 3 through 9 which are transported in portable tanks.]

| Portable tank instruction<br>(1) | Minimum test pressure<br>(bar)<br>(2) | Minimum shell thickness<br>(in mm-reference steel)<br>(See §178.274(d))<br>(3) | Pressure-relief requirements<br>(See §178.275(g))<br>(4) | Bottom opening requirements<br>(See §178.275(d))<br>(5) |
|----------------------------------|---------------------------------------|--------------------------------------------------------------------------------|----------------------------------------------------------|---------------------------------------------------------|
| T1 .....                         | 1.5                                   | §178.274(d)(2)                                                                 | Normal .....                                             | §178.275(d)(2)                                          |
| T2 .....                         | 1.5                                   | §178.274(d)(2)                                                                 | Normal .....                                             | §178.275(d)(3)                                          |
| T3 .....                         | 2.65                                  | §178.274(d)(2)                                                                 | Normal .....                                             | §178.275(d)(2)                                          |
| T4 .....                         | 2.65                                  | §178.274(d)(2)                                                                 | Normal .....                                             | §178.275(d)(3)                                          |
| T5 .....                         | 2.65                                  | §178.274(d)(2)                                                                 | §178.275(g)(3) .....                                     | Prohibited                                              |
| T6 .....                         | 4                                     | §178.274(d)(2)                                                                 | Normal .....                                             | §178.275(d)(2)                                          |
| T7 .....                         | 4                                     | §178.274(d)(2)                                                                 | Normal .....                                             | §178.275(d)(3)                                          |
| T8 .....                         | 4                                     | §178.274(d)(2)                                                                 | Normal .....                                             | Prohibited                                              |
| T9 .....                         | 4                                     | 6 mm                                                                           | Normal .....                                             | Prohibited                                              |
| T10 .....                        | 4                                     | 6 mm                                                                           | §178.275(g)(3) .....                                     | Prohibited                                              |
| T11 .....                        | 6                                     | §178.274(d)(2)                                                                 | Normal .....                                             | §178.275(d)(3)                                          |
| T12 .....                        | 6                                     | §178.274(d)(2)                                                                 | §178.275(g)(3) .....                                     | §178.275(d)(3)                                          |
| T13 .....                        | 6                                     | 6 mm                                                                           | Normal .....                                             | Prohibited                                              |

TABLE OF PORTABLE TANK T CODES T1–T22—Continued

[Portable tank codes T1–T22 apply to liquid and solid hazardous materials of Classes 3 through 9 which are transported in portable tanks.]

| Portable tank instruction<br>(1) | Minimum test pressure<br>(bar)<br>(2) | Minimum shell thickness<br>(in mm-reference steel)<br>(See § 178.274(d))<br>(3) | Pressure-relief requirements<br>(See § 178.275(g))<br>(4) | Bottom opening requirements<br>(See § 178.275(d))<br>(5) |
|----------------------------------|---------------------------------------|---------------------------------------------------------------------------------|-----------------------------------------------------------|----------------------------------------------------------|
| T14 .....                        | 6                                     | 6 mm                                                                            | § 178.275(g)(3) .....                                     | Prohibited                                               |
| T15 .....                        | 10                                    | § 178.274(d)(2)                                                                 | Normal .....                                              | § 178.275(d)(3)                                          |
| T16 .....                        | 10                                    | § 178.274(d)(2)                                                                 | § 178.275(g)(3) .....                                     | § 178.275(d)(3)                                          |
| T17 .....                        | 10                                    | 6 mm                                                                            | Normal .....                                              | § 178.275(d)(3)                                          |
| T18 .....                        | 10                                    | 6 mm                                                                            | § 178.275(g)(3) .....                                     | § 178.275(d)(3)                                          |
| T19 .....                        | 10                                    | 6 mm                                                                            | § 178.275(g)(3) .....                                     | Prohibited                                               |
| T20 .....                        | 10                                    | 8 mm                                                                            | § 178.275(g)(3) .....                                     | Prohibited                                               |
| T21 .....                        | 10                                    | 10 mm                                                                           | Normal .....                                              | Prohibited                                               |
| T22 .....                        | 10                                    | 10 mm                                                                           | § 178.275(g)(3) .....                                     | Prohibited                                               |

(iii) *T50*. When portable tank instruction T50 is referenced in Column (7) of the § 172.101 Table, the applicable liquefied compressed gases are authorized to be transported in portable tanks in accordance with the requirements of § 173.313 of this subchapter.

(iv) *T75*. When portable tank instruction T75 is referenced in Column (7) of the § 172.101 Table, the applicable refrigerated liquefied gases are authorized to be transported in portable tanks in accordance with the requirements of § 178.277 of this subchapter.

(v) *UN and IM portable tank codes/special provisions*. When a specific portable tank instruction is specified by a “T” Code in Column (7) of the § 172.101 Table for a specific hazardous material, a specification portable tank conforming to an alternative tank instruction may be used if:

(A) The alternative portable tank has a higher or equivalent test pressure (for example, 4 bar when 2.65 bar is specified);

(B) The alternative portable tank has greater or equivalent wall thickness (for example, 10 mm when 6 mm is specified);

(C) The alternative portable tank has a pressure relief device as specified in the “T” Code. If a frangible disc is required in series with the reclosing pressure relief device for the specified portable tank, the alternative portable tank must be fitted with a frangible disc in series with the reclosing pressure relief device; and

(D) With regard to bottom openings—  
(1) When two effective means are specified, the alternative portable tank is fitted with bottom openings having

two or three effective means of closure or no bottom openings; or

(2) When three effective means are specified, the portable tank has no bottom openings or three effective means of closure; or

(3) When no bottom openings are authorized, the alternative portable tank must not have bottom openings.

(vi) Except when an organic peroxide is authorized under § 173.225(g), if a hazardous material is not assigned a portable tank “T” Code, the hazardous material may not be transported in a portable tank unless approved by the Associate Administrator.

(8) “*TP*” codes. (i) These provisions apply to the transportation of hazardous materials in IM and UN Specification portable tanks. Portable tank special provisions are assigned to certain hazardous materials to specify requirements that are in addition to those provided by the portable tank instructions or the requirements in part 178 of this subchapter. Portable tank special provisions are designated with the abbreviation TP (tank provision) and are assigned to specific hazardous materials in Column (7) of the § 172.101 Table.

(ii) The following is a list of the portable tank special provisions:

#### Code/Special Provisions

TP1 The maximum degree of filling must not exceed the degree of filling determined by the following:

$$\left( \text{Degree of filling} = \frac{97}{1 + \alpha(t_r - t_f)} \right).$$

Where:

$t_r$  is the maximum mean bulk temperature during transport, and  $t_f$  is the temperature in degrees celsius of the liquid during filling.

TP2 a. The maximum degree of filling must not exceed the degree of filling determined by the following:

$$\left( \text{Degree of filling} = \frac{95}{1 + \alpha(t_r - t_f)} \right).$$

Where:

$t_r$  is the maximum mean bulk temperature during transport,

$t_f$  is the temperature in degrees celsius of the liquid during filling, and

$\alpha$  is the mean coefficient of cubical expansion of the liquid between the mean temperature of the liquid during filling ( $t_f$ ) and the maximum mean bulk temperature during transportation ( $t_r$ ) both in degrees celsius.

b. For liquids transported under ambient conditions  $\alpha$  may be calculated using the formula:

$$\alpha = \frac{d_{15} - d_{50}}{35 d_{50}}$$

Where:

$d_{15}$  and  $d_{50}$  are the densities (in units of mass per unit volume) of the liquid at 15 °C (59 °F) and 50 °C (122 °F), respectively.

TP3 The maximum degree of filling (in %) for solids transported above their melting points and for elevated temperature liquids shall be determined by the following:

$$\left( \text{Degree of filling} = 95 \frac{d_r}{d_f} \right).$$

Where:  $d_f$  and  $d_r$  are the mean densities of the liquid at the mean temperature of the liquid during filling and the maximum mean bulk temperature during transport respectively.

TP4 The maximum degree of filling for portable tanks must not exceed 90%.

TP5 For a portable tank used for the transport of flammable refrigerated liquefied gases or refrigerated liquefied oxygen, the maximum rate at which the portable tank may be filled must not exceed the liquid flow capacity of the primary pressure relief system rated at a pressure not exceeding 120 percent of the portable tank's design pressure. For portable tanks used for the transport of refrigerated liquefied helium and refrigerated liquefied atmospheric gas (except oxygen), the maximum rate at which the tank is filled must not exceed the liquid flow capacity of the pressure relief device rated at 130 percent of the portable tank's design pressure. Except for a portable tank con-

taining refrigerated liquefied helium, a portable tank shall have an outage of at least two percent below the inlet of the pressure relief device or pressure control valve, under conditions of incipient opening, with the portable tank in a level attitude. No outage is required for helium.

TP6 The tank must be equipped with a pressure release device which prevent a tank from bursting under fire engulfment conditions (the conditions prescribed in CGA pamphlet S-1.2 (see §171.7 of this subchapter) or alternative conditions approved by the Associate Administrator may be used to consider the fire engulfment condition), taking into account the properties of the hazardous material to be transported.

TP7 The vapor space must be purged of air by nitrogen or other means.

TP8 A portable tank having a minimum test pressure of 1.5 bar (150 kPa) may be used when the flash point of the hazardous material transported is greater than 0 °C (32 °F).

TP9 A hazardous material assigned to special provision TP9 in Column (7) of the §172.101 Table may only be transported in a portable tank if approved by the Associate Administrator.

TP10 The portable tank must be fitted with a lead lining at least 5 mm (0.2 inches) thick. The lead lining must be tested annually to ensure that it is intact and functional. Another suitable lining material may be used if approved by the Associate Administrator.

TP12 This material is considered highly corrosive to steel.

TP13 Self-contained breathing apparatus must be provided when this hazardous material is transported by sea.

TP16 The portable tank must be protected against over and under pressurization which may be experienced during transportation. The means of protection must be approved by the approval agency designated to approve the portable tank in accordance with the procedures in part 107, subpart E, of this subchapter. The pressure relief device must be preceded by a frangible disk in accordance with the requirements in §178.275(g)(3) of this subchapter to prevent crystallization of the product in the pressure relief device.

TP17 Only inorganic non-combustible materials may be used for thermal insulation of the tank.

TP18 The temperature of this material must be maintained between 18 °C (64.4 °F) and 40 °C (104 °F) while in transportation. Portable tanks containing solidified methacrylic acid must not be reheated during transportation.

TP19 The calculated wall thickness must be increased by 3 mm at the time of construction. Wall thickness must be verified ultrasonically at intervals midway between periodic hydraulic tests (every 2.5 years).



The portable tank must not be used if the wall thickness is less than that prescribed by the applicable T code in Column (7) of the Table for this material.

TP20 This hazardous material must only be transported in insulated tanks under a nitrogen blanket.

TP21 The wall thickness must not be less than 8 mm. Portable tanks must be hydraulically tested and internally inspected at intervals not exceeding 2.5 years.

TP22 Lubricants for portable tank fittings (for example, gaskets, shut-off valves, flanges) must be oxygen compatible.

TP24 The portable tank may be fitted with a device to prevent the build up of excess pressure due to the slow decomposition of the hazardous material being transported. The device must be in the vapor space when the tank is filled under maximum filling conditions. This device must also prevent an unacceptable amount of leakage of liquid in the case of overturning.

TP25 Sulphur trioxide 99.95% pure and above may be transported in tanks without an inhibitor provided that it is maintained at a temperature equal to or above 32.5 °C (90.5 °F).

TP26 The heating device must be exterior to the shell. For UN 3176, this requirement only applies when the hazardous material reacts dangerously with water.

TP27 A portable tank having a minimum test pressure of 4 bar (400 kPa) may be used provided the calculated test pressure is 4 bar or less based on the MAWP of the hazardous material, as defined in §178.275 of this subchapter, where the test pressure is 1.5 times the MAWP.

TP28 A portable tank having a minimum test pressure of 2.65 bar (265 kPa) may be used provided the calculated test pressure is 2.65 bar or less based on the MAWP of the hazardous material, as defined in §178.275 of this subchapter, where the test pressure is 1.5 times the MAWP.

TP29 A portable tank having a minimum test pressure of 1.5 bar (150.0 kPa) may be used provided the calculated test pressure is 1.5 bar or less based on the MAWP of the hazardous materials, as defined in §178.275 of this subchapter, where the test pressure is 1.5 times the MAWP.

TP30 This hazardous material may only be transported in insulated tanks.

TP31 This hazardous material may only be transported in tanks in the solid state.

TP32 Portable tanks may be used subject to the following conditions:

a. Each portable tank constructed of metal must be fitted with a pressure-relief device consisting of a reclosing spring loaded type, a frangible disc or a fusible element. The set to discharge for the spring loaded pressure relief device and the burst pressure for the frangible disc, as applicable, must not be

greater than 2.65 bar for portable tanks with minimum test pressures greater than 4 bar;

b. The suitability for transport in tanks must be demonstrated using test 8(d) in Test Series 8 (see UN Manual of Tests and Criteria, Part 1, Sub-section 18.7) (IBR, see §171.7 of this subchapter) or an alternative means approved by the Associate Administrator.

TP33 The portable tank instruction assigned for this substance applies for granular and powdered solids and for solids which are filled and discharged at temperatures above their melting point which are cooled and transported as a solid mass. Solid substances transported or offered for transport above their melting point are authorized for transportation in portable tanks conforming to the provisions of portable tank instruction T4 for solid substances of packing group III or T7 for solid substances of packing group II, unless a tank with more stringent requirements for minimum shell thickness, maximum allowable working pressure, pressure-relief devices or bottom outlets are assigned in which case the more stringent tank instruction and special provisions shall apply. Filling limits must be in accordance with portable tank special provision TP3. Solids meeting the definition of an elevated temperature material must be transported in accordance with the applicable requirements of this subchapter.

TP37 IM portable tanks are only authorized for the shipment of hydrogen peroxide solutions in water containing 72% or less hydrogen peroxide by weight. Pressure relief devices shall be designed to prevent the entry of foreign matter, the leakage of liquid and the development of any dangerous excess pressure. In addition, the portable tank must be designed so that internal surfaces may be effectively cleaned and passivated. Each tank must be equipped with pressure relief devices conforming to the following requirements:

| Concentration of hydrogen peroxide solution | Total <sup>1</sup> |
|---------------------------------------------|--------------------|
| 52% or less .....                           | 11                 |
| Over 52%, but not greater than 60% .....    | 22                 |
| Over 60%, but not greater than 72% .....    | 32                 |

<sup>1</sup>Total venting capacity in standard cubic feet hour (S.C.F.H.) per pound of hydrogen peroxide solution.

TP38 Each portable tank must be insulated with an insulating material so that the overall thermal conductance at 15.5 °C (60 °F) is no more than 1.5333 kilojoules per hour per square meter per degree Celsius (0.075 Btu per hour per square foot per degree Fahrenheit) temperature differential. Insulating materials may not promote corrosion to steel when wet.

TP44 Each portable tank must be made of stainless steel, except that steel other than stainless steel may be used in accordance

with the provisions of § 173.24b(b) of this subchapter. Thickness of stainless steel for tank shell and heads must be the greater of 7.62 mm (0.300 inch) or the thickness required for a portable tank with a design pressure at least equal to 1.5 times the vapor pressure of the hazardous material at 46 °C (115 °F).

TP45 Each portable tank must be made of stainless steel, except that steel other than stainless steel may be used in accordance with the provisions of 173.24b(b) of this subchapter. Thickness of stainless steel for portable tank shells and heads must be the greater of 6.35 mm (0.250 inch) or the thickness required for a portable tank with a design pressure at least equal to 1.3 times the vapor pressure of the hazardous material at 46 °C (115 °F).

TP46 Portable tanks in sodium metal service are not required to be hydrostatically retested.

(9) “W” codes. These provisions apply only to transportation by water:

*Code/Special Provisions*

W7 Vessel stowage category for uranyl nitrate hexahydrate solution is “D” as defined in § 172.101(k)(4).

W8 Vessel stowage category for pyrophoric thorium metal or pyrophoric uranium metal is “D” as defined in § 172.101(k)(4).

W9 When offered for transportation by water, the following Specification packagings are not authorized unless approved by the Associate Administrator: woven plastic bags, plastic film bags, textile bags, paper bags, IBCs and bulk packagings.

W41 When offered for transportation by water, this material must be packaged in bales and be securely and tightly bound with rope, wire or similar means.

[Amdt. 172–123, 55 FR 52582, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 172.102, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

## Subpart C—Shipping Papers

### § 172.200 Applicability.

(a) *Description of hazardous materials required.* Except as otherwise provided in this subpart, each person who offers a hazardous material for transportation shall describe the hazardous material on the shipping paper in the manner required by this subpart.

(b) This subpart does not apply to any material, other than a hazardous substance, hazardous waste or marine pollutant, that is—

(1) Identified by the letter “A” in column 1 of the § 172.101 table, except when the material is offered or intended for transportation by air; or

(2) Identified by the letter “W” in column 1 of the § 172.101 table, except when the material is offered or intended for transportation by water; or

(3) An ORM-D, except when the material is offered or intended for transportation by air.

(4) Category B infectious substances prepared in accordance with § 173.199.

[Amdt. 172–29A, 41 FR 40677, Sept. 20, 1976, as amended by Amdt. 172–58, 45 FR 34697, May 22, 1980; Amdt. 172–74, 47 FR 43065, Sept. 30, 1982; Amdt. 172–112, 53 FR 17160, May 13, 1988; Amdt. 172–127, 57 FR 52938, Nov. 5, 1992; 71 FR 32258, June 2, 2006]

### § 172.201 Preparation and retention of shipping papers.

(a) *Contents.* When a description of hazardous material is required to be included on a shipping paper, that description must conform to the following requirements:

(1) When a hazardous material and a material not subject to the requirements of this subchapter are described on the same shipping paper, the hazardous material description entries required by § 172.202 and those additional entries that may be required by § 172.203:

(i) Must be entered first, or

(ii) Must be entered in a color that clearly contrasts with any description on the shipping paper of a material not subject to the requirements of this subchapter, except that a description on a reproduction of a shipping paper may be highlighted, rather than printed, in a contrasting color (the provisions of this paragraph apply only to the basic description required by § 172.202(a)(1), (2), (3), and (4)), or

(iii) Must be identified by the entry of an “X” placed before the basic shipping description required by § 172.202 in a column captioned “HM.” (The “X” may be replaced by “RQ,” if appropriate.)

(2) The required shipping description on a shipping paper and all copies thereof used for transportation purposes, must be legible and printed (manually or mechanically) in English.

## § 172.202

## 49 CFR Ch. I (10–1–08 Edition)

(3) Unless it is specifically authorized or required in this subchapter, the required shipping description may not contain any code or abbreviation.

(4) A shipping paper may contain additional information concerning the material provided the information is not inconsistent with the required description. Unless otherwise permitted or required by this subpart, additional information must be placed after the basic description required by § 172.202(a).

(b) [Reserved]

(c) *Continuation page.* A shipping paper may consist of more than one page, if each page is consecutively numbered and the first page bears a notation specifying the total number of pages included in the shipping paper. For example, “Page 1 of 4 pages.”

(d) *Emergency response telephone number.* Except as provided in § 172.604(c), a shipping paper must contain an emergency response telephone number, as prescribed in subpart G of this part.

(e) *Retention and Recordkeeping.* Each person who provides a shipping paper must retain a copy of the shipping paper required by § 172.200(a), or an electronic image thereof, that is accessible at or through its principal place of business and must make the shipping paper available, upon request, to an authorized official of a Federal, State, or local government agency at reasonable times and locations. For a hazardous waste, the shipping paper copy must be retained for three years after the material is accepted by the initial carrier. For all other hazardous materials, the shipping paper must be retained for two years after the material is accepted by the initial carrier. Each shipping paper copy must include the date of acceptance by the initial carrier, except that, for rail, vessel, or air shipments, the date on the shipment waybill, airbill, or bill of lading may be used in place of the date of acceptance by the initial carrier. A motor carrier (as defined in § 390.5 of subchapter B of chapter III of subtitle B) using a shipping paper without change for multiple shipments of one or more hazardous materials having the same shipping name and identification number may retain a single copy of the shipping paper, instead of a copy

for each shipment made, if the carrier also retains a record of each shipment made, to include shipping name, identification number, quantity transported, and date of shipment.

[Amdt. 172–29A, 41 FR 40677, Sept. 20, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 172.201, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 172.202 Description of hazardous material on shipping papers.

(a) The shipping description of a hazardous material on the shipping paper must include:

(1) The identification number prescribed for the material as shown in Column (4) of the § 172.101 table;

(2) The proper shipping name prescribed for the material in Column (2) of the § 172.101 table;

(3) The hazard class or division number prescribed for the material, as shown in Column (3) of the § 172.101 table. Except for combustible liquids, the subsidiary hazard class(es) or subsidiary division number(s) must be entered in parentheses immediately following the primary hazard class or division number. In addition—

(i) The words “Class” or “Division” may be included preceding the primary and subsidiary hazard class or division numbers.

(ii) The hazard class need not be included for the entry “Combustible liquid, n.o.s.”

(iii) For domestic shipments, primary and subsidiary hazard class or division names may be entered following the numerical hazard class or division, or following the basic description.

(4) The packing group in Roman numerals, as designated for the hazardous material in Column (5) of the § 172.101 table. Class 1 (explosives) materials, self-reactive substances, organic peroxides and entries that are not assigned a packing group are excepted from this requirement. The packing group may be preceded by the letters “PG” (for example, “PG II”); and

(5) Except for transportation by aircraft, the total quantity of hazardous materials covered by the description must be indicated (by mass or volume, or by activity for Class 7 materials)

and must include an indication of the applicable unit of measurement, for example, “200 kg” (440 pounds) or “50 L” (13 gallons). The following provisions also apply:

(i) For Class 1 materials, the quantity must be the net explosive mass. For an explosive that is an article, such as Cartridges, small arms, the net explosive mass may be expressed in terms of the net mass of either the article or the explosive materials contained in the article.

(ii) For hazardous materials in salvage packaging, an estimate of the total quantity is acceptable.

(iii) The following are excepted from the requirements of paragraph (a)(5) of this section:

(A) Bulk packages, provided some indication of the total quantity is shown, for example, “1 cargo tank” or “2 IBCs.”

(B) Cylinders, provided some indication of the total quantity is shown, for example, “10 cylinders.”

(C) Packages containing only residue.

(6) For transportation by aircraft, the total net mass per package, must be shown unless a gross mass is indicated in Columns (9A) or (9B) of the §172.101 table in which case the total gross mass per package must be shown; or, for Class 7 materials, the quantity of radioactive material must be shown by activity. The following provisions also apply:

(i) For empty uncleaned packaging, only the number and type of packaging must be shown;

(ii) For chemical kits and first aid kits, the total net mass of hazardous materials must be shown. Where the kits contain only liquids, or solids and liquids, the net mass of liquids within the kits is to be calculated on a 1 to 1 basis, i.e., 1 L (0.3 gallons) equals 1 kg (2.2 pounds);

(iii) For dangerous goods in machinery or apparatus, the individual total quantities or an estimate of the individual total quantities of dangerous goods in solid, liquid or gaseous state, contained in the article must be shown;

(iv) For dangerous goods transported in a salvage packaging, an estimate of the quantity of dangerous goods per package must be shown;

(v) For cylinders, total quantity may be indicated by the number of cylinders, for example, “10 cylinders;”

(vi) For items where “No Limit” is shown in Column (9A) or (9B) of the §172.101 table, the quantity shown should be the net mass or volume of the material, except for UN2800, UN2807, UN3072, UN3166 and UN3171 where the quantity should be the gross mass of the article; and

(7) The number and type of packages must be indicated. The type of packages must be indicated by description of the package (for example, “12 drums”). Indication of the packaging specification number (“1H1”) may be included in the description of the package (for example, “12 1H1 drums” or “12 drums (UN 1A1)”). Abbreviations may be used for indicating packaging types (for example, “cyl.” for “cylinder”) provided the abbreviations are commonly accepted and recognizable.

(b) Except as provided in this subpart, the basic description specified in paragraphs (a)(1), (2), (3) and (4) of this section must be shown in sequence with no additional information interspersed. For example, “UN2744, Cyclobutyl chloroformate, 6.1, (8, 3), PG II.”

(c) The total quantity of the material covered by one description must appear before or after, or both before and after, the description required and authorized by this subpart. The type of packaging and destination marks may be entered in any appropriate manner before or after the basic description. Abbreviations may be used to express units of measurement and types of packagings.

(d) Technical and chemical group names may be entered in parentheses between the proper shipping name and hazard class or following the basic description. An appropriate modifier, such as “contains” or “containing,” and/or the percentage of the technical constituent may also be used. For example: “Flammable liquids, n.o.s. (contains Xylene and Benzene), 3, UN 1993, II”.

(e) Except for those materials in the UN Recommendations, the ICAO Technical Instructions, or the IMDG Code (IBR, see §171.7 of this subchapter), a

## § 172.203

material that is not a hazardous material according to this subchapter may not be offered for transportation or transported when its description on a shipping paper includes a hazard class or an identification number specified in the § 172.101 Table.

[Amdt. 172–101, 45 FR 74665, Nov. 10, 1980, as amended by Amdt. 172–103, 51 FR 5970, Feb. 18, 1986; Amdt. 172–123, 55 FR 52589, Dec. 21, 1990; 56 FR 66252, Dec. 20, 1991; Amdt. 172–127, 57 FR 52938, Nov. 5, 1992; Amdt. 172–130, 58 FR 51531, Oct. 1, 1993; 66 FR 33425, June 21, 2001; 68 FR 45030, July 31, 2003; 68 FR 75741, Dec. 31, 2003; 69 FR 34611, June 22, 2004; 69 FR 54046, Sept. 7, 2004; 69 FR 76153, Dec. 20, 2004; 70 FR 34397, June 14, 2005; 71 FR 78626, Dec 29, 2006; 72 FR 55692, Oct. 1, 2007; 73 FR 57005, Oct. 1, 2008]

### § 172.203 Additional description requirements.

(a) *Special permits.* Except as provided in § 173.23 of this subchapter, each shipping paper issued in connection with a shipment made under a special permit must bear the notation “DOT-SP” followed by the special permit number assigned and located so that the notation is clearly associated with the description to which the special permit applies. Each shipping paper issued in connection with a shipment made under an exemption or special permit issued prior to October 1, 2007, may bear the notation “DOT-E” followed by the number assigned and so located that the notation is clearly associated with the description to which it applies.

(b) *Limited quantities.* The description for a material offered for transportation as “limited quantity,” as authorized by this subchapter, must include the words “Limited Quantity” or “Ltd Qty” following the basic description.

(c) *Hazardous substances.* (1) Except for Class 7 (radioactive) materials described in accordance with paragraph (d) of this section, if the proper shipping name for a material that is a hazardous substance does not identify the hazardous substance by name, the name of the hazardous substance must be entered in parentheses in association with the basic description. If the material contains two or more hazardous substances, at least two hazardous substances, including the two with the lowest reportable quantities

## 49 CFR Ch. I (10–1–08 Edition)

(RQs), must be identified. For a hazardous waste, the waste code (e.g., D001), if appropriate, may be used to identify the hazardous substance.

(2) The letters “RQ” must be entered on the shipping paper either before or after the basic description required by § 172.202 for each hazardous substance (see definition in § 171.8 of this subchapter). For example: “RQ, UN 1098, Allyl alcohol, 6.1, I, Toxic-inhalation hazard, Zone B”; or “UN 3077, Environmentally hazardous substances, solid, n.o.s., 9, III, RQ (Adipic acid)”.

(d) *Radioactive material.* The description for a shipment of a Class 7 (radioactive) material must include the following additional entries as appropriate:

(1) The name of each radionuclide in the Class 7 (radioactive) material that is listed in § 173.435 of this subchapter. For mixtures of radionuclides, the radionuclides required to be shown must be determined in accordance with § 173.433(g) of this subchapter. Abbreviations, e.g., “<sup>99</sup>Mo,” are authorized.

(2) A description of the physical and chemical form of the material, if the material is not in special form (generic chemical description is acceptable for chemical form).

(3) The activity contained in each package of the shipment in terms of the appropriate SI units (e.g., Becquerels (Bq), Terabecquerels (TBq), etc.). The activity may also be stated in appropriate customary units (Curies (Ci), milliCuries (mCi), microCuries (uCi), etc.) in parentheses following the SI units. Abbreviations are authorized. Except for plutonium-239 and plutonium-241, the weight in grams or kilograms of fissile radionuclides may be inserted instead of activity units. For plutonium-239 and plutonium-241, the weight in grams of fissile radionuclides may be inserted in addition to the activity units.

(4) The category of label applied to each package in the shipment. For example: “RADIOACTIVE WHITE-I.”

(5) The transport index assigned to each package in the shipment bearing RADIOACTIVE YELLOW-II or RADIOACTIVE YELLOW-III labels.

(6) For a package containing fissile Class 7 (radioactive) material:

(i) The words "Fissile Excepted" if the package is excepted pursuant to §173.453 of this subchapter; or otherwise

(ii) The criticality safety index for that package.

(7) For a package approved by the U.S. Department of Energy (DOE) or U.S. Nuclear Regulatory Commission (NRC), a notation of the package identification marking as prescribed in the applicable DOE or NRC approval (see §173.471 of the subchapter).

(8) For an export shipment or a shipment in a foreign made package, a notation of the package identification marking as prescribed in the applicable International Atomic Energy Agency (IAEA) Certificate of Competent Authority which has been issued for the package (see §173.473 of the subchapter).

(9) For a shipment required by this subchapter to be consigned as exclusive use:

(i) An indication that the shipment is consigned as exclusive use; or

(ii) If all the descriptions on the shipping paper are consigned as exclusive use, then the statement "Exclusive Use Shipment" may be entered only once on the shipping paper in a clearly visible location.

(10) For the shipment of a package containing a highway route controlled quantity of Class 7 (radioactive) materials (see §173.403 of this subchapter) the words "Highway route controlled quantity" or "HRCQ" must be entered in association with the basic description.

(e) *Empty packagings.* (1) The description on the shipping paper for a packaging containing the residue of a hazardous material may include the words "RESIDUE: Last Contained \* \* \*" in association with the basic description of the hazardous material last contained in the packaging.

(2) The description on the shipping paper for a tank car containing the residue of a hazardous material must include the phrase, "RESIDUE: LAST CONTAINED \* \* \*" before the basic description.

(f) *Transportation by air.* A statement indicating that the shipment is within the limitations prescribed for either passenger and cargo aircraft or cargo

aircraft only must be entered on the shipping paper.

(g) *Transportation by rail.* (1) A shipping paper prepared by a rail carrier for a rail car, freight container, transport vehicle or portable tank that contains hazardous materials must include the reporting mark and number when displayed on the rail car, freight container, transport vehicle or portable tank.

(2) The shipping paper for each DOT-113 tank car containing a Division 2.1 material or its residue must contain an appropriate notation, such as "DOT 113", and the statement "Do not hump or cut off car while in motion."

(3) When shipments of elevated temperature materials are transported under the exception permitted in §173.247(h)(3) of this subchapter, the shipping paper must contain an appropriate notation, such as "Maximum operating speed 15 mph."

(h) *Transportation by highway.* Following the basic description for a hazardous material in a Specification MC 330 or MC 331 cargo tank, there must be entered for—

(1) *Anhydrous ammonia.* (i) The words "0.2 PERCENT WATER" to indicate the suitability for shipping anhydrous ammonia in a cargo tank made of quenched and tempered steel as authorized by §173.315(a), Note 14 of this subchapter, or

(ii) The words "NOT FOR Q and T TANKS" when the anhydrous ammonia does not contain 0.2 percent or more water by weight.

(2) *Liquefied petroleum gas.* (i) The word "NONCORROSIVE" or "NONCOR" to indicate the suitability for shipping "Noncorrosive" liquefied petroleum gas in a cargo tank made of quenched and tempered steel as authorized by §173.315(a), Note 15 of this subchapter, or

(ii) The words "NOT FOR Q and T TANKS" for grades of liquefied petroleum gas other than "Noncorrosive".

(i) *Transportation by water.* Each shipment by water must have the following additional shipping paper entries:

(1) The name of the shipper.

(2) Minimum flash point if 60°C (140°F) or below (in °C closed cup (c.c.)) in association with the basic description.

(3) For a hazardous material consigned under an “n.o.s.” entry not included in the segregation groups listed in section 3.1.4 of the IMDG Code but belonging, in the opinion of the consignor, to one of these groups, the appropriate segregation group must be shown in association with the basic description (for example, IMDG Code segregation group—1 Acids). When no segregation group is applicable, there is no requirement to indicate that condition.

(j) [Reserved]

(k) *Technical names for “n.o.s.” and other generic descriptions.* Unless otherwise excepted, if a material is described on a shipping paper by one of the proper shipping names identified by the letter “G” in column (1) of the § 172.101 Table, the technical name of the hazardous material must be entered in parentheses in association with the basic description. For example “Corrosive liquid, n.o.s., (Octanoyl chloride), 8, UN 1760, II”, or “Corrosive liquid, n.o.s., 8, UN 1760, II (contains Octanoyl chloride)”. The word “contains” may be used in association with the technical name, if appropriate. For organic peroxides which may qualify for more than one generic listing depending on concentration, the technical name must include the actual concentration being shipped or the concentration range for the appropriate generic listing. For example, “Organic peroxide type B, solid, 5.2, UN 3102 (dibenzoyl peroxide, 52–100%)” or “Organic peroxide type E, solid, 5.2, UN 3108 (dibenzoyl peroxide, paste, <52%)”. Shipping descriptions for toxic materials that meet the criteria of Division 6.1, PG I or II (as specified in § 173.132(a) of this subchapter) or Division 2.3 (as specified in § 173.115(c) of this subchapter) and are identified by the letter “G” in column (1) of the § 172.101 Table, must have the technical name of the toxic constituent entered in parentheses in association with the basic description. A material classed as Division 6.2 and assigned identification number UN 2814 or UN 2900 that is suspected to contain an unknown Category A infectious substance must have the words “suspected Category A infectious substance” entered in parentheses in place of the technical name

as part of the proper shipping description. For additional technical name options, see the definition for “Technical name” in § 171.8. A technical name should not be marked on the outer package of a Division 6.2 material (see § 172.301(b)).

(1) If a hazardous material is a mixture or solution of two or more hazardous materials, the technical names of at least two components most predominately contributing to the hazards of the mixture or solution must be entered on the shipping paper as required by paragraph (k) of this section. For example, “Flammable liquid, corrosive, n.o.s., 3, UN 2924, II (contains Methanol, Potassium hydroxide)”.

(2) The provisions of this paragraph do not apply—

(i) To a material that is a hazardous waste and described using the proper shipping name “Hazardous waste, liquid or solid, n.o.s.”, classed as a miscellaneous Class 9, provided the EPA hazardous waste number is included on the shipping paper in association with the basic description, or provided the material is described in accordance with the provisions of § 172.203(c) of this part.

(ii) To a material for which the hazard class is to be determined by testing under the criteria in § 172.101(c)(11).

(iii) If the n.o.s. description for the material (other than a mixture of hazardous materials of different classes meeting the definitions of more than one hazard class) contains the name of the chemical element or group which is primarily responsible for the material being included in the hazard class indicated.

(iv) If the n.o.s. description for the material (which is a mixture of hazardous materials of different classes meeting the definition of more than one hazard class) contains the name of the chemical element or group responsible for the material meeting the definition of one of these classes. In such cases, only the technical name of the component that is not appropriately identified in the n.o.s. description shall be entered in parentheses.

(l) *Marine pollutants.* (1) If the proper shipping name for a material which is a marine pollutant does not identify by name the component which makes the

material a marine pollutant, the name of that component must appear in parentheses in association with the basic description. Where two or more components which make a material a marine pollutant are present, the names of at least two of the components most predominantly contributing to the marine pollutant designation must appear in parentheses in association with the basic description.

(2) The words "Marine Pollutant" shall be entered in association with the basic description for a material which is a marine pollutant.

(3) Except for transportation by vessel, marine pollutants subject to the provisions of 49 CFR 130.11 are excepted from the requirements of paragraph (l) of this section if a phrase indicating the material is an oil is placed in association with the basic description.

(4) Except when all or part of transportation is by vessel, marine pollutants in non-bulk packagings are not subject to the requirements of paragraphs (l)(1) and (l)(2) of this section (see § 171.4 of this subchapter).

(m) *Poisonous Materials*. Notwithstanding the hazard class to which a material is assigned, for materials that are poisonous by inhalation (see § 171.8 of this subchapter), the words "Poison-Inhalation Hazard" or "Toxic-Inhalation Hazard" and the words "Zone A", "Zone B", "Zone C", or "Zone D" for gases or "Zone A" or "Zone B" for liquids, as appropriate, shall be entered on the shipping paper immediately following the shipping description. The word "Poison" or "Toxic" need not be repeated if it otherwise appears in the shipping description.

(n) *Elevated temperature materials*. If a liquid material in a package meets the definition of an elevated temperature material in § 171.8 of this subchapter, and the fact that it is an elevated temperature material is not disclosed in the proper shipping name (for example, when the words "Molten" or "Elevated temperature" are part of the proper shipping name), the word "HOT" must immediately precede the proper shipping name of the material on the shipping paper.

(o) *Organic peroxides and self-reactive materials*. The description on a shipping paper for a Division 4.1 (self-reactive)

material or a Division 5.2 (organic peroxide) material must include the following additional information, as appropriate:

(1) If notification or competent authority approval is required, the shipping paper must contain a statement of approval of the classification and conditions of transport.

(2) For Division 4.1 (self-reactive) and Division 5.2 (organic peroxide) materials that require temperature control during transport, the control and emergency temperature must be included on the shipping paper.

(3) The word "SAMPLE" must be included in association with the basic description when a sample of a Division 4.1 (self-reactive) material (see § 173.224(c)(3) of this subchapter) or Division 5.2 (organic peroxide) material (see § 173.225(b)(2) of this subchapter) is offered for transportation.

[Amdt. 172-29A, 41 FR 40677, Sept. 20, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 172.203, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 172.204 Shipper's certification.

(a) *General*. Except as provided in paragraphs (b) and (c) of this section, each person who offers a hazardous material for transportation shall certify that the material is offered for transportation in accordance with this subchapter by printing (manually or mechanically) on the shipping paper containing the required shipping description the certification contained in paragraph (a)(1) of this section or the certification (declaration) containing the language contained in paragraph (a)(2) of this section.

(1) "This is to certify that the above-named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation according to the applicable regulations of the Department of Transportation."

NOTE: In line one of the certification the words "herein-named" may be substituted for the words "above-named".

(2) "I hereby declare that the contents of this consignment are fully and



accurately described above by the proper shipping name, and are classified, packaged, marked and labelled/placarded, and are in all respects in proper condition for transport according to applicable international and national governmental regulations.”

(b) *Exceptions.* (1) Except for a hazardous waste, no certification is required for a hazardous material offered for transportation by motor vehicle and transported:

(i) In a cargo tank supplied by the carrier, or

(ii) By the shipper as a private carrier except for a hazardous material that is to be reshipped or transferred from one carrier to another.

(2) No certification is required for the return of an empty tank car which previously contained a hazardous material and which has not been cleaned or purged.

(c) *Transportation by air—(1) General.* Certification containing the following language may be used in place of the certification required by paragraph (a) of this section:

I hereby certify that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packaged, marked and labeled, and in proper condition for carriage by air according to applicable national governmental regulations.

NOTE TO PARAGRAPH (c)(1): In the certification, the word “packed” may be used instead of the word “packaged” until October 1, 2010.

(2) *Certificate in duplicate.* Each person who offers a hazardous material to an aircraft operator for transportation by air shall provide two copies of the certification required in this section. (See § 175.30 of this subchapter.)

(3) *Additional certification requirements.* Effective October 1, 2006, each person who offers a hazardous material for transportation by air must add to the certification required in this section the following statement:

“I declare that all of the applicable air transport requirements have been met.”

(i) Each person who offers any package or overpack of hazardous materials for transport by air must ensure that:

(A) The articles or substances are not prohibited for transport by air (see the § 172.101 Table);

(B) The articles or substances are properly classed, marked and labeled and otherwise in a condition for transport as required by this subchapter;

(C) The articles or substances are packaged in accordance with all the applicable air transport requirements, including appropriate types of packaging that conform to the packing requirements and the “A” Special Provisions in § 172.102; inner packaging and maximum quantity per package limits; the compatibility requirements (see, for example, § 173.24 of this subchapter); and requirements for closure for both inner and outer packagings, absorbent materials, and pressure differential in § 173.27 of this subchapter. Other requirements may also apply. For example, single packagings may be prohibited, inner packaging may need to be packed in intermediate packagings, and certain materials may be required to be transported in packagings meeting a more stringent performance level.

(ii) [Reserved]

(4) *Radioactive material.* Each person who offers any radioactive material for transportation aboard a passenger-carrying aircraft shall sign (mechanically or manually) a printed certificate stating that the shipment contains radioactive material intended for use in, or incident to, research, or medical diagnosis or treatment.

(d) *Signature.* The certifications required by paragraph (a) or (c) of this section:

(1) Must be legibly signed by a principal, officer, partner, or employee of the shipper or his agent; and

(2) May be legibly signed manually, by typewriter, or by other mechanical means.

[Amdt. 172–29A, 41 FR 40677, Sept. 20, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 172.204, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 172.205 Hazardous waste manifest.

(a) No person may offer, transport, transfer, or deliver a hazardous waste (waste) unless an EPA Form 8700–22 and 8700–22A (when necessary) hazardous waste manifest (manifest) is prepared in accordance with 40 CFR

262.20 and is signed, carried, and given as required of that person by this section.

(b) The shipper (generator) shall prepare the manifest in accordance with 40 CFR part 262.

(c) The original copy of the manifest must be dated by, and bear the handwritten signature of, the person representing:

(1) The shipper (generator) of the waste at the time it is offered for transportation, and

(2) The initial carrier accepting the waste for transportation.

(d) A copy of the manifest must be dated by, and bear the handwritten signature of the person representing:

(1) Each subsequent carrier accepting the waste for transportation, at the time of acceptance, and

(2) The designated facility receiving the waste, upon receipt.

(e) A copy of the manifest bearing all required dates and signatures must be:

(1) Given to a person representing each carrier accepting the waste for transportation,

(2) Carried during transportation in the same manner as required by this subchapter for shipping papers,

(3) Given to a person representing the designated facility receiving the waste,

(4) Returned to the shipper (generator) by the carrier that transported the waste from the United States to a foreign destination with a notation of the date of departure from the United States, and

(5) Retained by the shipper (generator) and by the initial and each subsequent carrier for three years from the date the waste was accepted by the initial carrier. Each retained copy must bear all required signatures and dates up to and including those entered by the next person who received the waste.

(f) *Transportation by rail.* Notwithstanding the requirements of paragraphs (d) and (e) of this section, the following requirements apply:

(1) When accepting hazardous waste from a non-rail transporter, the initial rail transporter must:

(i) Sign and date the manifest acknowledging acceptance of the hazardous waste;

(ii) Return a signed copy of the manifest to the non-rail transporter;

(iii) Forward at least three copies of the manifest to:

(A) The next non-rail transporter, if any;

(B) The designated facility, if the shipment is delivered to that facility by rail; or

(C) The last rail transporter designated to handle the waste in the United States; and

(iv) Retain one copy of the manifest and rail shipping paper in accordance with 40 CFR 263.22.

(2) Rail transporters must ensure that a shipping paper containing all the information required on the manifest (excluding the EPA identification numbers, generator certification and signatures) and, for exports, an EPA Acknowledgment of Consent accompanies the hazardous waste at all times. Intermediate rail transporters are not required to sign either the manifest or shipping paper.

(3) When delivering hazardous waste to the designated facility, a rail transporter must:

(i) Obtain the date of delivery and handwritten signature of the owner or operator of the designated facility on the manifest or the shipping paper (if the manifest has not been received by the facility); and

(ii) Retain a copy of the manifest or signed shipping paper in accordance with 40 CFR 263.22.

(4) When delivering hazardous waste to a non-rail transporter, a rail transporter must:

(i) Obtain the date of delivery and the handwritten signature of the next non-rail transporter on the manifest; and

(ii) Retain a copy of the manifest in accordance with 40 CFR 263.22.

(5) Before accepting hazardous waste from a rail transporter, a non-rail transporter must sign and date the manifest and provide a copy to the rail transporter.

(g) The person delivering a hazardous waste to an initial rail carrier shall send a copy of the manifest, dated and signed by a representative of the rail carrier, to the person representing the designated facility.

## § 172.300

## 49 CFR Ch. I (10–1–08 Edition)

(h) A hazardous waste manifest required by 40 CFR part 262, containing all of the information required by this subpart, may be used as the shipping paper required by this subpart.

(i) The shipping description for a hazardous waste must be modified as required by § 172.101(c)(9).

[Amdt. 172–58, 45 FR 34698, May 22, 1980, as amended by Amdt. 172–90, 49 FR 10510, Mar. 20, 1984; 49 FR 11184, Mar. 26, 1984; Amdt. 172–248, 61 FR 28675, June 5, 1996; 70 FR 34075, June 13, 2005]

### Subpart D—Marking

#### § 172.300 Applicability.

(a) Each person who offers a hazardous material for transportation shall mark each package, freight container, and transport vehicle containing the hazardous material in the manner required by this subpart.

(b) When assigned the function by this subpart, each carrier that transports a hazardous material shall mark each package, freight container, and transport vehicle containing the hazardous material in the manner required by this subpart.

[Amdt. 172–101, 45 FR 74666, Nov. 10, 1980]

#### § 172.301 General marking requirements for non-bulk packagings.

(a) *Proper shipping name and identification number.* (1) Except as otherwise provided by this subchapter, each person who offers a hazardous material for transportation in a non-bulk packaging must mark the package with the proper shipping name and identification number (preceded by “UN” or “NA,” as appropriate) for the material as shown in the § 172.101 Table. Identification numbers are not required on packagings that contain only ORM-D materials or limited quantities, as defined in § 171.8 of this subchapter, except for limited quantities marked in accordance with the marking requirements in § 172.315.

(2) The proper shipping name for a hazardous waste (as defined in § 171.8 of this subchapter) is not required to include the word “waste” if the package bears the EPA marking prescribed by 40 CFR 262.32.

(3) *Large quantities of a single hazardous material in non-bulk packages.* A transport vehicle or freight container containing only a single hazardous material in non-bulk packages must be marked, on each side and each end as specified in the § 172.332 or § 172.336, with the identification number specified for the hazardous material in the § 172.101 Table, subject to the following provisions and limitations:

(i) Each package is marked with the same proper shipping name and identification number;

(ii) The aggregate gross weight of the hazardous material is 4,000 kg (8,820 pounds) or more;

(iii) All of the hazardous material is loaded at one loading facility;

(iv) The transport vehicle or freight container contains no other material, hazardous or otherwise; and

(v) The identification number marking requirement of this paragraph (a)(3) does not apply to Class 1, Class 7, or to non-bulk packagings for which identification numbers are not required.

(b) *Technical names.* In addition to the marking required by paragraph (a) of this section, each non-bulk packaging containing a hazardous material subject to the provisions of § 172.203(k) of this part, except for a Division 6.2 material, must be marked with the technical name in parentheses in association with the proper shipping name in accordance with the requirements and exceptions specified for display of technical descriptions on shipping papers in § 172.203(k) of this part. A technical name should not be marked on the outer package of a Division 6.2 material.

(c) *Special permit packagings.* Except as provided in § 173.23 of this subchapter, the outside of each package authorized by a special permit must be plainly and durably marked “DOT–SP” followed by the special permit number assigned. Packages authorized by an exemption issued prior to October 1, 2007, may be plainly and durably marked “DOT–E” in lieu of “DOT–SP” followed by the number assigned as specified in the most recent version of that exemption.

(d) *Consignee’s or consignor’s name and address.* Each person who offers for transportation a hazardous material in

a non-bulk package shall mark that package with the name and address of the consignor or consignee except when the package is—

(1) Transported by highway only and will not be transferred from one motor carrier to another; or

(2) Part of a carload lot, truckload lot or freight container load, and the entire contents of the rail car, truck or freight container are shipped from one consignor to one consignee.

(e) *Previously marked packagings.* A package which has been previously marked as required for the material it contains and on which the marking remains legible, need not be remarked. (For empty packagings, see §173.29 of this subchapter.)

(f) *NON-ODORIZED marking on cylinders containing LPG.* After September 30, 2006, no person may offer for transportation or transport a specification cylinder, except a Specification 2P or 2Q container or a Specification 39 cylinder, that contains an unodorized Liquefied petroleum gas (LPG) unless it is legibly marked NON-ODORIZED or NOT ODORIZED in letters not less than 6.3 mm (0.25 inches) in height near the marked proper shipping name required by paragraph (a) of this section.

[Amdt. 172–123, 55 FR 52590, Dec. 21, 1990, as amended by Amdt. 172–151, 62 FR 1227, Jan. 8, 1997; 62 FR 39404, July 22, 1997; 63 FR 16075, Apr. 1, 1998; 66 FR 45182, Aug. 28, 2001; 68 FR 45030, July 31, 2003; 69 FR 64471, Nov. 4, 2004; 70 FR 73164, Dec. 9, 2005; 71 FR 32258, June 2, 2006]

**§ 172.302 General marking requirements for bulk packagings.**

(a) *Identification numbers.* Except as otherwise provided in this subpart, no person may offer for transportation or transport a hazardous material in a bulk packaging unless the packaging is marked as required by §172.332 with the identification number specified for the material in the §172.101 table—

(1) On each side and each end, if the packaging has a capacity of 3,785 L (1,000 gallons) or more;

(2) On two opposing sides, if the packaging has a capacity of less than 3,785 L (1,000 gallons); or

(3) For cylinders permanently installed on a tube trailer motor vehicle,

on each side and each end of the motor vehicle.

(b) *Size of markings.* Except as otherwise provided, markings required by this subpart on bulk packagings must—

(1) Have a width of at least 6.0 mm (0.24 inch) and a height of at least 100 mm (3.9 inches) for rail cars;

(2) Have a width of at least 4.0 mm (0.16 inch) and a height of at least 25 mm (one inch) for portable tanks with capacities of less than 3,785 L (1,000 gallons) and IBCs; and

(3) Have a width of at least 6.0 mm (0.24 inch) and a height of at least 50 mm (2.0 inches) for cargo tanks and other bulk packagings.

(c) *Special permit packagings.* Except as provided in §173.23 of this subchapter, the outside of each package used under the terms of a special permit must be plainly and durably marked “DOT-SP” followed by the special permit number assigned. Packages authorized by an exemption issued prior to October 1, 2007 may be plainly and durably marked “DOT-E” in lieu of “DOT-SP” followed by the number assigned as specified in the most recent version of that exemption.

(d) Each bulk packaging marked with a proper shipping name, common name or identification number as required by this subpart must remain marked when it is emptied unless it is—

(1) Sufficiently cleaned of residue and purged of vapors to remove any potential hazard; or

(2) Refilled, with a material requiring different markings or no markings, to such an extent that any residue remaining in the packaging is no longer hazardous.

(e) Additional requirements for marking portable tanks, cargo tanks, tank cars, multi-unit tank car tanks, and other bulk packagings are prescribed in §§172.326, 172.328, 172.330, and 172.331, respectively, of this subpart.

(f) A bulk packaging marked prior to October 1, 1991, in conformance to the regulations of this subchapter in effect on September 30, 1991, need not be remarked if the key words of the proper shipping name are identical to those currently specified in the §172.101 table. For example, a tank car marked

## § 172.303

“NITRIC OXIDE” need not be remarked “NITRIC OXIDE, COMPRESSED”.

(g) A rail car, freight container, truck body or trailer in which the loading has been fumigated with any hazardous material, or is undergoing fumigation, must be marked as specified in § 173.9 of this subchapter.

[Amdt. 172–123, 55 FR 52591, Dec. 21, 1990, as amended at 56 FR 66254, Dec. 20, 1991; Amdt. 172–150, 61 FR 50624, Sept. 26, 1996; Amdt. 172–151, 62 FR 1228, Jan. 8, 1997; 62 FR 39398, July 22, 1997; 66 FR 45379, Aug. 28, 2001; 70 FR 73164, Dec. 9, 2005; 72 FR 55692, Oct. 1, 2007]

## § 172.303 Prohibited marking.

(a) No person may offer for transportation or transport a package which is marked with the proper shipping name, the identification number of a hazardous material or any other markings indicating that the material is hazardous (e.g., RQ, INHALATION HAZARD) unless the package contains the identified hazardous material or its residue.

(b) This section does not apply to—

(1) Transportation of a package in a transport vehicle or freight container if the package is not visible during transportation and is loaded by the shipper and unloaded by the shipper or consignee.

(2) Markings on a package which are securely covered in transportation.

(3) The marking of a shipping name on a package when the name describes a material not regulated under this subchapter.

[Amdt. 172–123, 55 FR 52591, Dec. 21, 1990, as amended at 56 FR 66254, Dec. 20, 1991; 72 FR 55692, Oct. 1, 2007]

## § 172.304 Marking requirements.

(a) The marking required in this subpart—

(1) Must be durable, in English and printed on or affixed to the surface of a package or on a label, tag, or sign.

(2) Must be displayed on a background of sharply contrasting color;

(3) Must be unobscured by labels or attachments; and

(4) Must be located away from any other marking (such as advertising) that could substantially reduce its effectiveness.

## 49 CFR Ch. I (10–1–08 Edition)

(b) [Reserved]

[Amdt. 172–29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172–29B, 41 FR 57067, Dec. 30, 1976]

## § 172.306 [Reserved]

## § 172.308 Authorized abbreviations.

(a) Abbreviations may not be used in a proper shipping name marking except as authorized in this section.

(b) The abbreviation “ORM” may be used in place of the words “Other Regulated Material.”

(c) Abbreviations which appear as authorized descriptions in column 2 of the § 172.101 table (e.g., “TNT” and “PCB”) are authorized.

[Amdt. 172–123, 55 FR 52591, Dec. 21, 1990, as amended by Amdt. 172–145, 60 FR 49110, Sept. 21, 1995]

## § 172.310 Class 7 (radioactive) materials.

In addition to any other markings required by this subpart, each package containing Class 7 (radioactive) materials must be marked as follows:

(a) Each package with a gross mass greater than 50 kg (110 lb) must have its gross mass including the unit of measurement (which may be abbreviated) marked on the outside of the package.

(b) Each industrial, Type A, Type B(U), or Type B(M) package must be legibly and durably marked on the outside of the packaging, in letters at least 13 mm (0.5 in) high, with the words “TYPE IP–1,” “TYPE IP–2,” “TYPE IP–3,” “TYPE A,” “TYPE B(U)” or “TYPE B(M),” as appropriate. A package which does not conform to Type IP–1, Type IP–2, Type IP–3, Type A, Type B(U) or Type B(M) requirements may not be so marked.

(c) Each package which conforms to an IP–1, IP–2, IP–3 or a Type A package design must be legibly and durably marked on the outside of the packaging with the international vehicle registration code of the country of origin of the design. The international vehicle registration code for packages designed by a United States company or agency is the symbol “USA.”

(d) Each package which conforms to a Type B(U) or Type B(M) package design must have the outside of the outermost receptacle, which is resistant to the effects of fire and water, plainly marked by embossing, stamping or other means resistant to the effects of fire and water with a radiation symbol that conforms to the requirements of Appendix B of this part.


(e) Each Type B(U), Type B(M) or fissile material package destined for export shipment must also be marked "USA" in conjunction with the specification marking, or other package certificate identification. (See §§ 173.471, 173.472, and 173.473 of this subchapter.)

[Docket No. RSPA-99-6283 (HM-230), 69 FR 3668, Jan. 26, 2004]

**§ 172.312 Liquid hazardous materials in non-bulk packagings.**

(a) Except as provided in this section, each non-bulk combination package having inner packagings containing liquid hazardous materials, single packaging fitted with vents, or open cryogenic receptacle intended for the transport of refrigerated liquefied gases must be:

- (1) Packed with closures upward, and
- (2) Legibly marked with package orientation markings that are similar to the illustration shown in this paragraph, on two opposite vertical sides of the package with the arrows pointing in the correct upright direction. The arrows must be either black or red on white or other suitable contrasting background and commensurate with the size of the package. Depicting a rectangular border around the arrows is optional.



**Package orientation**

(b) Arrows for purposes other than indicating proper package orientation may not be displayed on a package containing a liquid hazardous material.

(c) The requirements of paragraph (a) of this section do not apply to—

- (1) A non-bulk package with inner packagings which are cylinders.
- (2) Except when offered or intended for transportation by aircraft, packages containing flammable liquids in inner packagings of 1 L or less prepared in accordance with § 173.150 (b) or (c) of this subchapter.
- (3) When offered or intended for transportation by aircraft, packages containing flammable liquids in inner packagings of 120 mL (4 fluid oz.) or less prepared in accordance with § 173.150 (b) or (c) of this subchapter when packed with sufficient absorption material between the inner and outer packagings to completely absorb the liquid contents.
- (4) Liquids contained in manufactured articles (e.g., alcohol or mercury in thermometers) which are leak-tight in all orientations.
- (5) A non-bulk package with hermetically sealed inner packagings.
- (6) Packages containing liquid infectious substances in primary receptacles not exceeding 50 mL (1.7 oz.).

## § 172.313

(7) Class 7 radioactive material in Type A, IP-2, IP-3, Type B(U), or Type B(M) packages.

[Amdt. 172-123, 55 FR 52591, Dec. 21, 1990, as amended at 56 FR 66254, Dec. 20, 1991; 57 FR 45458, Oct. 1, 1992; 64 FR 51918, Sept. 27, 1999; 66 FR 45379, Aug. 28, 2001; 68 FR 45030, July 31, 2003; 71 FR 54395, Sept. 14, 2006; 71 FR 78627, Dec. 29, 2006]

### § 172.313 Poisonous hazardous materials.

In addition to any other markings required by this subpart:

(a) A material poisonous by inhalation (see § 171.8 of this subchapter) shall be marked "Inhalation Hazard" in association with the required labels or placards, as appropriate, and shipping name when required. The marking must be on two opposing sides of a bulk packaging. (See § 172.302(b) of this subpart for size of markings on bulk packages.) When the words "Inhalation Hazard" appear on the label, as prescribed in §§ 172.416 and 172.429, or placard, as prescribed in §§ 172.540 and 172.555, the "Inhalation Hazard" marking is not required on the package.

(b) Each non-bulk plastic outer packaging used as a single or composite packaging for materials meeting the definition of Division 6.1 (in § 173.132 of this subchapter) shall be permanently marked, by embossment or other durable means, with the word "POISON" in letters at least 6.3 mm (0.25 inch) in height. Additional text or symbols related to hazard warning may be included in the marking. The marking shall be located within 150 mm (6 inches) of the closure of the packaging.

(c) A transport vehicle or freight container containing a material poisonous by inhalation in non-bulk packages shall be marked, on each side and each end as specified in § 172.332 or § 172.336, with the identification number specified for the hazardous material in the § 172.101 table, subject to the following provisions and limitations:

(1) The material is in Hazard Zone A or B;

(2) The transport vehicle or freight container is loaded at one facility with 1,000 kg (2,205 pounds) or more aggregate gross weight of the material in non-bulk packages marked with the

## 49 CFR Ch. I (10-1-08 Edition)

same proper shipping name and identification number; and

(3) If the transport vehicle or freight container contains more than one material meeting the provisions of this paragraph (c), it shall be marked with the identification number for one material, determined as follows:

(i) For different materials in the same hazard zone, with the identification number of the material having the greatest aggregate gross weight; and

(ii) For different materials in both Hazard Zones A and B, with the identification number for the Hazard Zone A material.

(d) For a packaging containing a Division 6.1 PG III material, "PG III" may be marked adjacent to the POISON label. (See § 172.405(c).)

[Amdt. 172-123, 55 FR 52592, Dec. 21, 1990, as amended at 57 FR 46624, Oct. 9, 1992; Amdt. 172-151, 62 FR 1228, Jan. 8, 1997; 62 FR 39398, 39405, July 22, 1997; 63 FR 16075, Apr. 1, 1998; 64 FR 10776, Mar. 5, 1999]

### § 172.315 Packages containing limited quantities.

Except for transportation by aircraft or as otherwise provided in this subchapter, a package containing a limited quantity of hazardous materials is not required to be marked with the proper shipping name provided it is marked with the identification (ID) number, preceded by the letters "UN" or "NA," as applicable, for the entry as shown in the § 172.101 Table, and placed within a square-on-point border in accordance with the following:

(a) The ID number marking must be durable, legible and of such a size relative to the package as to be readily visible. The width of line forming the square-on-point must be at least 2 mm and the height of the ID number must be at least 6 mm. The marking must be applied on at least one side or one end of the outer packaging.

(b) When two or more hazardous materials with different ID numbers are contained in the package, the packaging must be marked with either individual square-on-points bearing a single ID number, or a single square-on-point large enough to include each applicable ID number.

(c) As applicable, the letters "RQ" must be marked in association with

the square-on-point border containing the identification (ID) number.

[68 FR 45030, July 31, 2003, as amended at 69 FR 76153, Dec. 20, 2004; 73 FR 4716, Jan. 28, 2008]

**§ 172.316 Packagings containing materials classed as ORM-D.**

(a) Each non-bulk packaging containing a material classed as ORM-D must be marked on at least one side or end with the ORM-D designation immediately following or below the proper shipping name of the material. The ORM designation must be placed within a rectangle that is approximately 6.3 mm (0.25 inches) larger on each side than the designation. The designation for ORM-D must be:

(1) ORM-D-AIR for an ORM-D that is prepared for air shipment and packaged in accordance with the provisions of § 173.27 of this subchapter.

(2) ORM-D for an ORM-D other than as described in paragraph (a)(1) of this section.

(b) When the ORM-D marking including the proper shipping name can not be affixed on the package surface, it may be on an attached tag.

(c) The marking ORM-D is the certification by the person offering the packaging for transportation that the material is properly described, classed, packaged, marked and labeled (when

appropriate) and in proper condition for transportation according to the applicable regulations of this subchapter. This form of certification does not preclude the requirement for a certificate on a shipping paper when required by subpart C of this part.

[Amdt. 172-29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172-123, 55 FR 52592, Dec. 21, 1990; 56 FR 66254, Dec. 20, 1991]

**§ 172.317 KEEP AWAY FROM HEAT handling mark.**


(a) *General.* For transportation by aircraft, each package containing self-reactive substances of Division 4.1 or organic peroxides of Division 5.2 must be marked with the KEEP AWAY FROM HEAT handling mark specified in this section.

(b) *Location and design.* The marking must be a rectangle measuring at least 105 mm (4.1 inches) in height by 74 mm (2.9 inches) in width. Markings with not less than half this dimension are permissible where the dimensions of the package can only bear a smaller mark.

(c) *KEEP AWAY FROM HEAT handling mark.* The KEEP AWAY FROM HEAT handling mark must conform to the following:

(1) Except for size, the KEEP AWAY FROM HEAT handling mark must appear as follows:





(2) The symbol, letters and border must be black and the background white, except for the starburst which must be red.

(3) The KEEP AWAY FROM HEAT handling marking required by paragraph (a) of this section must be durable, legible and displayed on a background of contrasting color.

[69 FR 76153, Dec. 20, 2004]

**§ 172.320 Explosive hazardous materials.**

(a) Except as otherwise provided in paragraphs (b), (c), (d) and (e) of this section, each package containing a Class 1 material must be marked with the EX-number for each substance, article or device contained therein.

(b) Except for fireworks approved in accordance with § 173.56(j) of this subchapter, a package of Class 1 materials may be marked, in lieu of the EX-number required by paragraph (a) of this section, with a national stock number issued by the Department of Defense or identifying information, such as a product code required by regulations for commercial explosives specified in 27 CFR part 555, if the national stock number or identifying information can be specifically associated with the EX-number assigned.

(c) When more than five different Class 1 materials are packed in the same package, the package may be marked with only five of the EX-numbers, national stock numbers, product codes, or combination thereof.

(d) The requirements of this section do not apply if the EX-number, product code or national stock number of each explosive item described under a proper shipping description is shown in association with the shipping description required by § 172.202(a) of this part. Product codes and national stock numbers must be traceable to the specific EX-number assigned by the Associate Administrator.

(e) The requirements of this section do not apply to the following Class 1 materials:

(1) Those being shipped to a testing agency in accordance with § 173.56(d) of this subchapter;

(2) Those being shipped in accordance with § 173.56(e) of this subchapter, for the purposes of developmental testing;

(3) Those which meet the requirements of § 173.56(h) of this subchapter and therefore are not subject to the approval process of § 173.56 of this subchapter;

(4) Until October 1, 1993, those which are shipped under § 171.19 of this subchapter; and

(5) Those that are transported in accordance with § 173.56(c)(2) of this subchapter and, therefore, are covered by a national security classification currently in effect.

[Amdt. 172-123, 56 FR 66254, Dec. 20, 1991, as amended by Amdt. 172-139, 59 FR 67487, Dec. 29, 1994; 66 FR 45379, Aug. 28, 2001]

#### § 172.322 Marine pollutants.

(a) For vessel transportation of each non-bulk packaging that contains a marine pollutant—

(1) If the proper shipping name for a material which is a marine pollutant does not identify by name the component which makes the material a marine pollutant, the name of that component must be marked on the package in parentheses in association with the marked proper shipping name. Where two or more components which make a material a marine pollutant are present, the names of at least two of the components most predominantly contributing to the marine pollutant designation must appear in parentheses in association with the marked proper shipping name; and

(2) The MARINE POLLUTANT mark shall be placed in association with the

hazard warning labels required by subpart E of this part or, in the absence of any labels, in association with the marked proper shipping name.

(b) A bulk packaging that contains a marine pollutant must—

(1) Be marked with the MARINE POLLUTANT mark on at least two opposing sides or two ends other than the bottom if the packaging has a capacity of less than 3,785 L (1,000 gallons). The mark must be visible from the direction it faces. The mark may be displayed in black lettering on a square-on-point configuration having the same outside dimensions as a placard; or

(2) Be marked on each end and each side with the MARINE POLLUTANT mark if the packaging has a capacity of 3,785 L (1,000 gallons) or more. The mark must be visible from the direction it faces. The mark may be displayed in black lettering on a square-on-point configuration having the same outside dimensions as a placard.

(c) A transport vehicle or freight container that contains a package subject to the marking requirements of paragraph (a) or (b) of this section must be marked with the MARINE POLLUTANT mark. The mark must appear on each side and each end of the transport vehicle or freight container, and must be visible from the direction it faces. This requirement may be met by the marking displayed on a freight container or portable tank loaded on a motor vehicle or rail car. This mark may be displayed in black lettering on a white square-on-point configuration having the same outside dimensions as a placard.

(d) The MARINE POLLUTANT mark is not required—

(1) On a combination package containing a severe marine pollutant (see appendix B to § 172.101), in inner packagings each of which contains:

(i) 0.5 L (17 ounces) or less net capacity for liquids; or

(ii) 500 g (17.6 ounces) or less net capacity for solids.

(2) On a combination packaging containing a marine pollutant, other than a severe marine pollutant, in inner packagings each of which contains:

(i) 5 L (1.3 gallons) or less net capacity for liquids; or

**§ 172.323**


**49 CFR Ch. I (10–1–08 Edition)**

(ii) 5 kg (11 pounds) or less net capacity for solids.

(3) Except for transportation by vessel, on a bulk packaging, freight container or transport vehicle that bears a label or placard specified in subparts E or F of this part.

(e) *MARINE POLLUTANT mark.* The MARINE POLLUTANT mark must conform to the following:

(1) Except for size, the MARINE POLLUTANT mark must appear as follows:



(2) The symbol, letters and border must be black and the background white, or the symbol, letters, border and background must be of contrasting color to the surface to which the mark is affixed. Each side of the mark must be—

(i) At least 100 mm (3.9 inches) for marks applied to:

(A) Non-bulk packagings, except in the case of packagings which, because of their size, can only bear smaller marks; or

(B) Bulk packagings with a capacity of less than 3785 L (1,000 gallons); or

(ii) At least 250 mm (9.8 inches) for marks applied to all other bulk packagings.

(f) *Exceptions.* See § 171.4(c).

[Amdt. 172–127, 57 FR 52938, Nov. 5, 1992, as amended by Amdt. 172–136, 59 FR 38064, July 26, 1994; Amdt. 172–145, 60 FR 49110, Sept. 21, 1995; 66 FR 45379, Aug. 28, 2001; 70 FR 56098, Sept. 23, 2005]

**§ 172.323 Infectious substances.**

(a) In addition to other requirements of this subpart, after September 30, 2003, a bulk packaging containing a regulated medical waste, as defined in § 173.134(a)(5) of this subchapter, must be marked with a BIOHAZARD marking conforming to 29 CFR 1910.1030(g)(1)(i)—

(1) On two opposing sides or two ends other than the bottom if the packaging has a capacity of less than 3,785 L (1,000 gallons). The BIOHAZARD marking must measure at least 152.4 mm (6

inches) on each side and must be visible from the direction it faces.

(2) On each end and each side if the packaging has a capacity of 3,785 L (1,000 gallons) or more. The BIOHAZARD marking must measure at least 152.4 mm (6 inches) on each side and must be visible from the direction it faces.

(b) For a bulk packaging contained in or on a transport vehicle or freight container, if the BIOHAZARD marking

on the bulk packaging is not visible, the transport vehicle or freight container must be marked as required by paragraph (a) of this section on each side and each end.

(c) The background color for the BIOHAZARD marking required by paragraph (a) of this section must be orange and the symbol and letters must be black. Except for size the BIOHAZARD marking must appear as follows:



## § 172.324

(d) The BIOHAZARD marking required by paragraph (a) of this section must be displayed on a background of contrasting color. It may be displayed on a plain white square-on-point configuration having the same outside dimensions as a placard, as specified in § 172.519(c) of this part.

[67 FR 53135, Aug. 14, 2002]

## § 172.324 Hazardous substances in non-bulk packagings.

For each non-bulk package that contains a hazardous substance—

(a) Except for packages of radioactive material labeled in accordance with § 172.403, if the proper shipping name of a material that is a hazardous substance does not identify the hazardous substance by name, or if the package contains a limited quantity marked in accordance with § 172.315, the name of the hazardous substance must be marked on the package, in parentheses, in association with the proper shipping name or the identification number as applicable. If the material contains two or more hazardous substances, at least two hazardous substances, including the two with the lowest reportable quantities (RQs), must be identified. For a hazardous waste, the waste code (e.g., D001), if appropriate, may be used to identify the hazardous substance.

(b) The letters “RQ” must be marked on the package in association with the proper shipping name or the identifica-

## 49 CFR Ch. I (10–1–08 Edition)

tion number displayed in accordance with § 172.315.

[73 FR 4716, Jan. 28, 2008]

## § 172.325 Elevated temperature materials.

(a) Except as provided in paragraph (b) of this section, a bulk packaging containing an elevated temperature material must be marked on two opposing sides with the word “HOT” in black or white Gothic lettering on a contrasting background. The marking must be displayed on the packaging itself or in black lettering on a plain white square-on-point configuration having the same outside dimensions as a placard. (See § 172.302(b) for size of markings on bulk packagings.)

(b) Bulk packagings containing molten aluminum or molten sulfur must be marked “MOLTEN ALUMINUM” or “MOLTEN SULFUR”, respectively, in the same manner as prescribed in paragraph (a) of this section.

(c) If the identification number is displayed on a white-square-on-point display configuration, as prescribed in § 172.336(b), the word “HOT” may be displayed in the upper corner of the same white-square-on-point display configuration. The word “HOT” must be in black letters having a height of at least 50 mm (2.0 inches). Except for size, these markings shall be as illustrated for an Elevated temperature material, liquid, n.o.s.:



[Amdt. 172-125, 58 FR 3348, Jan. 8, 1993, as amended by Amdt. 172-139, 59 FR 67487, Dec. 29, 1994]

**§ 172.326 Portable tanks.**

(a) *Shipping name.* No person may offer for transportation or transport a portable tank containing a hazardous material unless it is legibly marked on two opposing sides with the proper shipping name specified for the material in the § 172.101 table.

(b) *Owner's name.* The name of the owner or of the lessee, if applicable, must be displayed on a portable tank that contains a hazardous material.

(c) *Identification numbers.* (1) If the identification number markings required by § 172.302(a) are not visible, a transport vehicle or freight container used to transport a portable tank con-

taining a hazardous material must be marked on each side and each end as required by § 172.332 with the identification number specified for the material in the § 172.101 table.

(2) Each person who offers a portable tank containing a hazardous material to a motor carrier, for transportation in a transport vehicle or freight container, shall provide the motor carrier with the required identification numbers on placards, orange panels, or the white square-on-point configuration, as appropriate, for each side and each end of the transport vehicle or freight container from which identification numbers on the portable tank are not visible.

## § 172.328

## 49 CFR Ch. I (10–1–08 Edition)

(d) *NON-ODORIZED marking on portable tanks containing LPG.* After September 30, 2006, no person may offer for transportation or transport a portable tank containing liquefied petroleum gas (LPG) that is unodorized as authorized in § 173.315(b)(1) unless it is legibly marked NON-ODORIZED or NOT ODORIZED on two opposing sides near the marked proper shipping name required by paragraph (a) of this section, or near the placards.

[Amdt. 172–123, 55 FR 52592, Dec. 21, 1990, as amended at 56 FR 66255, Dec. 20, 1991; 69 FR 64471, Nov. 4, 2004]

### § 172.328 Cargo tanks.

(a) *Providing and affixing identification numbers.* Unless a cargo tank is already marked with the identification numbers required by this subpart, the identification numbers must be provided or affixed as follows:

(1) A person who offers a hazardous material to a motor carrier for transportation in a cargo tank shall provide the motor carrier the identification numbers on placards or shall affix orange panels containing the required identification numbers, prior to or at the time the material is offered for transportation.

(2) A person who offers a cargo tank containing a hazardous material for transportation shall affix the required identification numbers on panels or placards prior to or at the time the cargo tank is offered for transportation.

(3) For a cargo tank transported on or in a transport vehicle or freight container, if the identification number marking on the cargo tank required by § 172.302(a) would not normally be visible during transportation—

(i) The transport vehicle or freight container must be marked as required by § 172.332 on each side and each end with the identification number specified for the material in the § 172.101 table; and

(ii) When the cargo tank is permanently installed within an enclosed cargo body of the transport vehicle or freight container, the identification number marking required by § 172.302(a) need only be displayed on each side and end of a cargo tank that is visible when the cargo tank is accessed.

(b) *Required markings: Gases.* Except for certain nurse tanks which must be marked as specified in § 173.315(m) of this subchapter, each cargo tank transporting a Class 2 material subject to this subchapter must be marked, in lettering no less than 50 mm (2.0 inches), on each side and each end with—

(1) The proper shipping name specified for the gas in the § 172.101 table; or

(2) An appropriate common name for the material (e.g., “Refrigerant Gas”).

(c) *QT/NQT markings.* Each MC 330 and MC 331 cargo tank must be marked near the specification plate, in letters no less than 50 mm (2.0 inches) in height, with—

(1) “QT”, if the cargo tank is constructed of quenched and tempered steel; or

(2) “NQT”, if the cargo tank is constructed of other than quenched and tempered steel.

(d) After October 3, 2005, each on-vehicle manually-activated remote shut-off device for closure of the internal self-closing stop valve must be identified by marking “Emergency Shutoff” in letters at least 0.75 inches in height, in a color that contrasts with its background, and located in an area immediately adjacent to the means of closure.

(e) *NON-ODORIZED marking on cargo tanks containing LPG.* After September 30, 2006, no person may offer for transportation or transport a cargo tank containing liquefied petroleum gas (LPG) that is unodorized as authorized in § 173.315(b)(1) unless it is legibly marked NON-ODORIZED or NOT ODORIZED on two opposing sides near the marked proper shipping name as specified in paragraph (b)(1) of this section, or near the placards.

[Amdt. 172–123, 55 FR 52592, Dec. 21, 1990, as amended at 56 FR 66255, Dec. 20, 1991; Amdt. 172–151, 62 FR 1228, Jan. 8, 1997; 62 FR 39045, July 22, 1997; 68 FR 19277, Apr. 18, 2003; 69 FR 64471, Nov. 4, 2004]

### § 172.330 Tank cars and multi-unit tank car tanks.

(a) *Shipping name and identification number.* No person may offer for transportation or transport a hazardous material—

(1) In a tank car unless the following conditions are met:

(i) The tank car must be marked on each side and each end as required by § 172.302 with the identification number specified for the material in the § 172.101 table; and

(ii) A tank car containing any of the following materials must be marked on each side with the key words of the proper shipping name specified for the material in the § 172.101 table, or with a common name authorized for the material in this subchapter (e.g., “Refrigerant Gas”):

Acrolein, stabilized  
 Ammonia, anhydrous, liquefied  
 Ammonia solutions (more than 50% ammonia)  
 Bromine or Bromine solutions  
 Bromine chloride  
 Chloroprene, stabilized  
 Dispersant gas or Refrigerant gas (as defined in § 173.115 of this subchapter)  
 Division 2.1 materials  
 Division 2.2 materials (in Class DOT 107 tank cars only)  
 Division 2.3 materials  
 Formic acid  
 Hydrocyanic acid, aqueous solutions  
 Hydrofluoric acid, solution  
 Hydrogen cyanide, stabilized (less than 3% water)  
 Hydrogen fluoride, anhydrous  
 Hydrogen peroxide, aqueous solutions (greater than 20% hydrogen peroxide)  
 Hydrogen peroxide, stabilized  
 Hydrogen peroxide and peroxyacetic acid mixtures  
 Nitric acid (other than red fuming)  
 Phosphorus, amorphous  
 Phosphorus, white dry or Phosphorus, white, under water or Phosphorus white, in solution, or Phosphorus, yellow dry or Phosphorus, yellow, under water or Phosphorus, yellow, in solution  
 Phosphorus white, molten  
 Potassium nitrate and sodium nitrate mixtures  
 Potassium permanganate  
 Sulfur trioxide, stabilized  
 Sulfur trioxide, uninhibited

(2) In a multi-unit tank car tank, unless the tank is marked on two opposing sides, in letters and numerals no less than 50 mm (2.0 inches) high—

(i) With the proper shipping name specified for the material in the § 172.101 table or with a common name authorized for the material in this subchapter (e.g., “Refrigerant Gas”); and

(ii) With the identification number specified for the material in the § 172.101 table, unless marked in accordance with §§ 172.302(a) and 172.332 of this subpart.

(b) A motor vehicle or rail car used to transport a multi-unit tank car tank containing a hazardous material must be marked on each side and each end, as required by § 172.332, with the identification number specified for the material in the § 172.101 table.

(c) After September 30, 2006, no person may offer for transportation or transport a tank car or multi-unit tank car tank containing liquefied petroleum gas (LPG) that is unodorized unless it is legibly marked NON-ODORIZED or NOT ODORIZED on two opposing sides near the marked proper shipping name required by paragraphs (a)(1) and (a)(2) of this section, or near the placards. The NON-ODORIZED or NOT ODORIZED marking may appear on a tank car or multi-unit tank car tank used for both unodorized and odorized LPG.

[Amdt. 172–123, 55 FR 52593, Dec. 21, 1990, as amended at 56 FR 66255, Dec. 20, 1991; 57 FR 45458, Oct. 1, 1992; Amdt. 172–148, 61 FR 28676, June 5, 1996; Amdt. 172–148, 61 FR 50254, Sept. 25, 1996; 66 FR 33425, June 21, 2001; 69 FR 64471, Nov. 4, 2004]

§ 172.331 Bulk packagings other than portable tanks, cargo tanks, tank cars and multi-unit tank car tanks.

(a) Each person who offers a hazardous material to a motor carrier for transportation in a bulk packaging shall provide the motor carrier with the required identification numbers on placards or plain white square-on-point display configurations, as authorized, or shall affix orange panels containing the required identification numbers to the packaging prior to or at the time the material is offered for transportation, unless the packaging is already marked with the identification number as required by this subchapter.

(b) Each person who offers a bulk packaging containing a hazardous material for transportation shall affix to the packaging the required identification numbers on orange panels, square-on-point configurations or placards, as appropriate, prior to, or at the time the packaging is offered for transportation unless it is already marked with identification numbers as required by this subchapter.



(c) For a bulk packaging contained in or on a transport vehicle or freight container, if the identification number marking on the bulk packaging (e.g., an IBC) required by § 172.302(a) is not visible, the transport vehicle or freight container must be marked as required by § 172.332 on each side and each end with the identification number specified for the material in the § 172.101 table.

[Amdt. 172–123, 55 FR 52593, Dec. 21, 1994, as amended by Amdt. 172–151, 62 FR 1228, Jan. 8, 1997; 62 FR 39398, July 22, 1997]

**§ 172.332 Identification number markings.**

(a) *General.* When required by § 172.301, § 172.302, § 172.313, § 172.326, § 172.328, § 172.330, or § 172.331, identification number markings must be displayed on orange panels or placards as specified in this section, or on white square-on-point configurations as prescribed in § 172.336(b).

(b) *Orange panels.* Display of an identification number on an orange panel shall be in conformance with the following:

(1) The orange panel must be 160 mm (6.3 inches) high by 400 mm (15.7 inches) wide with a 15 mm (0.6 inches) black outer border. The identification number shall be displayed in 100 mm (3.9 inches) black Helvetica Medium numerals on the orange panel. Measurements may vary from those specified plus or minus 5 mm (0.2 inches).

(2) The orange panel may be made of any durable material prescribed for placards in § 172.519, and shall be of the orange color specified for labels or placards in appendix A to this part.

(3) The name and hazard class of a material may be shown in the upper left border of the orange panel in letters not more than 18 points (0.25 in.) high.

(4) Except for size and color, the orange panel and identification numbers shall be as illustrated for Liquefied petroleum gas:



(c) *Placards.* Display of an identification number on a hazard warning placard shall be in conformance with the following:

(1) The identification number shall be displayed across the center area of the placard in 88 mm (3.5 inches) black Alpine Gothic or Alternate Gothic No. 3 numerals on a white background 100 mm (3.9 inches) high and approximately 215 mm (8.5 inches) wide and may be outlined with a solid or dotted line border.

(2) The top of the 100 mm (3.9 inches) high white background shall be approximately 40 mm (1.6 inches) above the placard horizontal center line.

(3) An identification number may be displayed only on a placard corresponding to the primary hazard class of the hazardous material.

(4) For a COMBUSTIBLE placard used to display an identification number, the entire background below the white background for the identification number must be white during transportation by rail and may be white during transportation by highway.

(5) The name of the hazardous material and the hazard class may be shown in letters not more than 18 points high immediately within the upper border of the space on the placard bearing the identification number of the material.

(6) If an identification number is placed over the word(s) on a placard, the word(s) should be substantially covered to maximize the effectiveness of the identification number.

(d) Except for size and color, the display of an identification number on a placard shall be as illustrated for Acetone:



[Amdt. 172-101, 45 FR 74667, Nov. 10, 1980, as amended by Amdt. 172-81, 48 FR 28099, June 20, 1983; Amdt. 172-110, 52 FR 29527, Aug. 10, 1987; Amdt. 172-123, 55 FR 52593, Dec. 21, 1990; 56 FR 66255, Dec. 20, 1991; Amdt. 172-151, 62 FR 1228, Jan. 8, 1997; 65 FR 50459, Aug. 18, 2000; 68 FR 57632, Oct. 6, 2003]

**§ 172.334 Identification numbers; prohibited display.**

(a) No person may display an identification number on a RADIOACTIVE, EXPLOSIVES 1.1, 1.2, 1.3, 1.4, 1.5 or 1.6, DANGEROUS, or subsidiary hazard placard.

(b) No person may display an identification number on a placard, orange panel or white square-on-point display configuration unless—

(1) The identification number is specified for the material in § 172.101;

(2) The identification number is displayed on the placard, orange panel or white square-on-point configuration authorized by § 172.332 or § 172.336(b), as appropriate, and any placard used for display of the identification number corresponds to the hazard class of the material specified in § 172.504;

(3) Except as provided under § 172.336(c)(4) or (c)(5), the package, freight container, or transport vehicle on which the number is displayed contains the hazardous material associated with that identification number in § 172.101.

(c) Except as required by § 172.332(c)(4) for a combustible liquid, the identification number of a material may be displayed only on the placards required by the tables in § 172.504.

(d) Except as provided in § 172.336, a placard bearing an identification number may not be used to meet the requirements of subpart F of this part

unless it is the correct identification number for all hazardous materials of the same class in the transport vehicle or freight container on which it is displayed.

(e) Except as specified in § 172.338, an identification number may not be displayed on an orange panel on a cargo tank unless affixed to the cargo tank by the person offering the hazardous material for transportation in the cargo tank.

(f) If a placard is required by § 172.504, an identification number may not be displayed on an orange panel unless it is displayed in proximity to the placard.

(g) No person shall add any color, number, letter, symbol, or word other than as specified in this subchapter, to any identification number marking display which is required or authorized by this subchapter.

[Amdt. 172-101, 45 FR 74667, Nov. 10, 1980, as amended by Amdt. 172-104, 51 FR 23078, June 25, 1986; Amdt. 172-110, 52 FR 29528, Aug. 10, 1987; Amdt. 172-123, 55 FR 52593, Dec. 21, 1990; 56 FR 66255, Dec. 20, 1991; Amdt. 172-127, 59 FR 49133, Sept. 26, 1994]

**§ 172.336 Identification numbers; special provisions.**

(a) When not required or prohibited by this subpart, identification numbers may be displayed on a transport vehicle or a freight container in the manner prescribed by this subpart.

(b) Identification numbers, when required, must be displayed on either orange panels (see § 172.332(b)) or on a plain white square-on-point display configuration having the same outside dimensions as a placard. In addition, for materials in hazard classes for which placards are specified and identification number displays are required, but for which identification numbers may not be displayed on the placards authorized for the material (see § 172.334(a)), identification numbers must be displayed on orange panels or on the plain white square-on-point display configuration in association with the required placards. An identification number displayed on a white square-on-point display configuration is not considered to be a placard.

## § 172.338

## 49 CFR Ch. I (10–1–08 Edition)

(1) The 100 mm (3.9 inch) by 215 mm (8.5 inches) area containing the identification number shall be located as prescribed by § 172.332 (c)(1) and (c)(2) and may be outlined with a solid or dotted line border.

(2) [Reserved]

(c) Identification numbers are not required:

(1) On the ends of a portable tank, cargo tank or tank car having more than one compartment if hazardous materials having different identification numbers are being transported therein. In such a circumstance, the identification numbers on the sides of the tank shall be displayed in the same sequence as the compartments containing the materials they identify.

(2) On a cargo tank containing only gasoline, if the cargo tank is marked “Gasoline” on each side and rear in letters no less than 50 mm (2 inches) high, or is placarded in accordance with § 172.542(c).

(3) On a cargo tank containing only fuel oil, if the cargo tank is marked “Fuel Oil” on each side and rear in letters no less than 50 mm (2 inches) high, or is placarded in accordance with § 172.544(c).

(4) For each of the different liquid petroleum distillate fuels, including gasoline and gasohol, in a compartmented cargo tank or tank car, if the identification number is displayed for the distillate fuel having the lowest flash point. After October 1, 2010, if a compartmented cargo tank or tank car contains such fuels together with a gasoline and alcohol fuel blend containing more than ten percent ethanol, the identification number “3475” or “1987” must also be displayed as appropriate in addition to the identification number for the liquid petroleum distillate fuel having the lowest flash point.

(5) For each of the different liquid petroleum distillate fuels, including gasoline and gasohol transported in a cargo tank, if the identification number is displayed for the liquid petroleum distillate fuel having the lowest flash point.

(6) For each of the different liquid petroleum distillate fuels, including gasoline and gasohol, transported in a cargo tank, if the identification num-

ber is displayed for the liquid petroleum distillate fuel having the lowest flash point. After October 1, 2010, if a cargo tank is used to transport a gasoline and alcohol fuel blend containing more than ten percent ethanol, the identification number “3475” must also be displayed in addition to the identification number for the liquid petroleum distillate fuel having the lowest flash point.

(7) On nurse tanks meeting the provisions of § 173.315(m) of this subchapter.

[Amdt. 172–101, 45 FR 74667, Nov. 10, 1980, as amended by Amdt. 172–74, 47 FR 40365, Sept. 30, 1982; Amdt. 172–109, 52 FR 13038, Apr. 20, 1987; Amdt. 172–110, 52 FR 29528, Aug. 10, 1987; Amdt. 172–123, 55 FR 52593, Dec. 21, 1990; 56 FR 66255, Dec. 20, 1991; 65 FR 50459, Aug. 18, 2000; 73 FR 4716, Jan. 28, 2008]

### § 172.338 Replacement of identification numbers.

If more than one of the identification number markings on placards, orange panels, or white square-on-point display configurations that are required to be displayed are lost, damaged or destroyed during transportation, the carrier shall replace all the missing or damaged identification numbers as soon as practicable. However, in such a case, the numbers may be entered by hand on the appropriate placard, orange panel or white square-on-point display configuration providing the correct identification numbers are entered legibly using an indelible marking material. When entered by hand, the identification numbers must be located in the white display area specified in § 172.332. This section does not preclude required compliance with the placarding requirements of subpart F of this subchapter.

[Amdt. 172–110, 52 FR 29528, Aug. 10, 1987]

## Subpart E—Labeling

### § 172.400 General labeling requirements.

(a) Except as specified in § 172.400a, each person who offers for transportation or transports a hazardous material in any of the following packages or containment devices, shall label the package or containment device with labels specified for the material in the § 172.101 table and in this subpart:

- (1) A non-bulk package;
- (2) A bulk packaging, other than a cargo tank, portable tank, or tank car, with a volumetric capacity of less than 18 m<sup>3</sup> (640 cubic feet), unless placarded in accordance with subpart F of this part;
- (3) A portable tank of less than 3785 L (1000 gallons) capacity, unless placarded in accordance with subpart F of this part;
- (4) A DOT Specification 106 or 110 multi-unit tank car tank, unless placarded in accordance with subpart F of this part; and
- (5) An overpack, freight container or unit load device, of less than 18 m<sup>3</sup> (640 cubic feet), which contains a package for which labels are required, unless placarded or marked in accordance with § 172.512 of this part.
- (b) Labeling is required for a hazardous material which meets one or more hazard class definitions, in accordance with column 6 of the § 172.101 table and the following table:

| Hazard class or division                                                 | Label name                              | Label design or section reference |
|--------------------------------------------------------------------------|-----------------------------------------|-----------------------------------|
| 1.1 .....                                                                | EXPLOSIVES 1.1 .....                    | 172.411                           |
| 1.2 .....                                                                | EXPLOSIVES 1.2 .....                    | 172.411                           |
| 1.3 .....                                                                | EXPLOSIVES 1.3 .....                    | 172.411                           |
| 1.4 .....                                                                | EXPLOSIVES 1.4 .....                    | 172.411                           |
| 1.5 .....                                                                | EXPLOSIVES 1.5 .....                    | 172.411                           |
| 1.6 .....                                                                | EXPLOSIVES 1.6 .....                    | 172.411                           |
| 2.1 .....                                                                | FLAMMABLE GAS .....                     | 172.417                           |
| 2.2 .....                                                                | NONFLAMMABLE GAS .....                  | 172.415                           |
| 2.3 .....                                                                | POISON GAS .....                        | 172.416                           |
| 3 (flammable liquid) Combustible liquid .....                            | FLAMMABLE LIQUID (none) .....           | 172.419                           |
| 4.1 .....                                                                | FLAMMABLE SOLID .....                   | 172.420                           |
| 4.2 .....                                                                | SPONTANEOUSLY COMBUSTIBLE .....         | 172.422                           |
| 4.3 .....                                                                | DANGEROUS WHEN WET .....                | 172.423                           |
| 5.1 .....                                                                | OXIDIZER .....                          | 172.426                           |
| 5.2 .....                                                                | ORGANIC PEROXIDE .....                  | 172.427                           |
| 6.1 (material poisonous by inhalation (see § 171.8 of this subchapter)). | POISON INHALATION HAZARD .....          | 172.429                           |
| 6.1 (other than material poisonous by inhalation) .....                  | POISON .....                            | 172.430                           |
| 6.1 (inhalation hazard, Zone A or B) .....                               | POISON INHALATION HAZARD .....          | 172.429                           |
| 6.1 (other than inhalation hazard, Zone A or B) .....                    | POISON .....                            | 172.430                           |
| 6.2 .....                                                                | INFECTIOUS SUBSTANCE <sup>1</sup> ..... | 172.432                           |
| 7 (see § 172.403) .....                                                  | RADIOACTIVE WHITE-I .....               | 172.436                           |
| 7 .....                                                                  | RADIOACTIVE YELLOW-II .....             | 172.438                           |
| 7 .....                                                                  | RADIOACTIVE YELLOW-III .....            | 172.440                           |
| 7 (fissile radioactive material; see § 172.402) .....                    | FISSILE .....                           | 172.441                           |
| 7 (empty packages; see § 173.428 of this subchapter) ..                  | EMPTY .....                             | 172.450                           |
| 8 .....                                                                  | CORROSIVE .....                         | 172.442                           |
| 9 .....                                                                  | CLASS 9 .....                           | 172.446                           |

<sup>1</sup>The ETIOLOGIC AGENT label specified in regulations of the Department of Health and Human Services at 42 CFR 72.3 may apply to packages of infectious substances.

[Amdt. 172–123, 55 FR 52593, Dec. 21, 1990, as amended at 56 FR 66255, Dec. 20, 1991; Amdt. 172–151, 62 FR 1228, Jan. 8, 1997; 64 FR 10776, Mar. 5, 1999; 64 FR 51918, Sept. 27, 1999; 69 FR 3668, Jan. 26, 2004; 69 FR 64471, Nov. 4, 2004]

#### § 172.400a Exceptions from labeling.

(a) Notwithstanding the provisions of § 172.400, a label is not required on—

- (1) A Dewar flask meeting the requirements in § 173.320 of this subchapter or a cylinder containing a Division 2.1, 2.2, or 2.3 material that is—
- (i) Not overpacked; and
- (ii) Durably and legibly marked in accordance with CGA C–7, Appendix A (IBR; see § 171.7 of this subchapter).

(2) A package or unit of military explosives (including ammunition) shipped by or on behalf of the DOD when in—

- (i) Freight containerload, carload or truckload shipments, if loaded and unloaded by the shipper or DOD; or
- (ii) Unitized or palletized break-bulk shipments by cargo vessel under charter to DOD if at least one required label is displayed on each unitized or palletized load.

## § 172.401

## 49 CFR Ch. I (10–1–08 Edition)

(3) A package containing a hazardous material other than ammunition that is—

(i) Loaded and unloaded under the supervision of DOD personnel, and

(ii) Escorted by DOD personnel in a separate vehicle.

(4) A compressed gas cylinder permanently mounted in or on a transport vehicle.

(5) A freight container, aircraft unit load device or portable tank, which—

(i) Is placarded in accordance with subpart F of this part, or

(ii) Conforms to paragraph (a)(3) or (b)(3) of § 172.512.

(6) An overpack or unit load device in or on which labels representative of each hazardous material in the overpack or unit load device are visible.

(7) A package of low specific activity radioactive material and surface contaminated objects, when transported under § 173.427(a)(6)(vi) of this subchapter.

(b) Certain exceptions to labeling requirements are provided for small quantities and limited quantities in applicable sections in part 173 of this subchapter.

(c) Notwithstanding the provisions of § 172.402(a), a subsidiary hazard label is not required on a package containing a Class 8 (corrosive) material which has a subsidiary hazard of Division 6.1 (poisonous) if the toxicity of the material is based solely on the corrosive destruction of tissue rather than systemic poisoning.

(d) A package containing a material poisonous by inhalation (see § 171.8 of this subchapter) in a closed transport vehicle or freight container may be excepted from the POISON INHALATION HAZARD or POISON GAS label or placard, under the conditions set forth in § 171.23(b)(11) of this subchapter.

[Amdt. 172–123, 55 FR 52594, Dec. 21, 1990, as amended by Amdt. 172–132, 58 FR 50501, Sept. 27, 1993; 172–130, 58 FR 51531, Oct. 1, 1993; Amdt. 172–139, 59 FR 67490, Dec. 29, 1994; Amdt. 172–145, 60 FR 49110, Sept. 21, 1995; 63 FR 52849, Oct. 1, 1998; 64 FR 10776, Mar. 5, 1999; 65 FR 58626, Sept. 29, 2000; 66 FR 44255, Aug. 22, 2001; 68 FR 75742, Dec. 31, 2003; 69 FR 64472, Nov. 4, 2004; 72 FR 25176, May 3, 2007; 73 FR 4716, Jan. 28, 2008]

### § 172.401 Prohibited labeling.

(a) Except as otherwise provided in this section, no person may offer for transportation and no carrier may transport a package bearing a label specified in this subpart unless:

(1) The package contains a material that is a hazardous material, and

(2) The label represents a hazard of the hazardous material in the package.

(b) No person may offer for transportation and no carrier may transport a package bearing any marking or label which by its color, design, or shape could be confused with or conflict with a label prescribed by this part.

(c) The restrictions in paragraphs (a) and (b) of this section, do not apply to packages labeled in conformance with:

(1) The UN Recommendations (IBR, see § 171.7 of this subchapter);

(2) The IMDG Code (IBR, see § 171.7 of this subchapter);

(3) The ICAO Technical Instructions (IBR, see § 171.7 of this subchapter);

(4) The TDG Regulations (IBR, see § 171.7 of this subchapter).

(d) The provisions of paragraph (a) of this section do not apply to a packaging bearing a label if that packaging is:

(1) Unused or cleaned and purged of all residue;

(2) Transported in a transport vehicle or freight container in such a manner that the packaging is not visible during transportation; and

(3) Loaded by the shipper and unloaded by the shipper or consignee.

[Amdt. 172–9, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172–75, 47 FR 44471, Oct. 7, 1982; Amdt. 172–77, 47 FR 54822, Dec. 6, 1982; Amdt. 172–94, 49 FR 38134, Sept. 27, 1984; Amdt. 172–100, 50 FR 41521, Oct. 11, 1985; Amdt. 172–123, 55 FR 52594, Dec. 21, 1990; Amdt. 172–132, 58 FR 50501, Sept. 27, 1993; 66 FR 8647, Feb. 1, 2001; 66 FR 45379, Aug. 28, 2001; 68 FR 75741, 75742, Dec. 31, 2003]

### § 172.402 Additional labeling requirements.

(a) *Subsidiary hazard labels.* Each package containing a hazardous material—

(1) Shall be labeled with primary and subsidiary hazard labels as specified in column 6 of the § 172.101 table (unless excepted in paragraph (a)(2) of this section); and

(2) For other than Class 1 or Class 2 materials (for subsidiary labeling requirements for Class 1 or Class 2 materials see paragraph (e) or paragraphs (f) and (g), respectively, of this section), if not already labeled under paragraph (a)(1) of this section, shall be labeled with subsidiary hazard labels in accordance with the following table:

SUBSIDIARY HAZARD LABELS

| Subsidiary hazard level (packing group) | Subsidiary Hazard (Class or Division) |     |     |     |     |     |   |
|-----------------------------------------|---------------------------------------|-----|-----|-----|-----|-----|---|
|                                         | 3                                     | 4.1 | 4.2 | 4.3 | 5.1 | 6.1 | 8 |
| I .....                                 | X                                     | *** | *** | X   | X   | X   | X |
| II .....                                | X                                     | X   | X   | X   | X   | X   | X |
| III .....                               | *                                     | X   | X   | X   | X   | X   | X |

X—Required for all modes.

\*—Required for all modes, except for a material with a flash point at or above 38 °C (100 °F) transported by rail or highway.

\*\*—Reserved

\*\*\*—Impossible as subsidiary hazard.

(b) *Display of hazard class on labels.* The appropriate hazard class or division number must be displayed in the lower corner of a primary hazard label and a subsidiary hazard label. A subsidiary label meeting the specifications of this section which were in effect on September 30, 2001, such as, a label without the hazard class or division number displayed in the lower corner of the label) may continue to be used as a subsidiary label in domestic transportation by rail or highway until October 1, 2005, provided the color tolerances are maintained and are in accordance with the display requirements in this subchapter.

(c) *Cargo Aircraft Only label.* Each person who offers for transportation or transports by aircraft a package containing a hazardous material which is authorized on cargo aircraft only shall label the package with a CARGO AIRCRAFT ONLY label specified in § 172.448 of this subpart.

(d) *Class 7 (Radioactive) Materials.* Except as otherwise provided in this paragraph, each package containing a Class 7 material that also meets the definition of one or more additional hazard classes must be labeled as a Class 7 material as required by § 172.403 and for each additional hazard.

(1) For a package containing a Class 7 material that also meets the definition of one or more additional hazard classes, whether or not the material satisfies § 173.4(a)(1)(iv) of this sub-

chapter, a subsidiary label is not required on the package if the material conforms to the remaining criteria in § 173.4 of this subchapter.

(2) Each package or overpack containing fissile material, other than fissile-excepted material (see § 173.453 of this subchapter) must bear two FISSILE labels, affixed to opposite sides of the package or overpack, which conforms to the figure shown in § 172.441; such labels, where applicable, must be affixed adjacent to the labels for radioactive materials.

(e) *Class 1 (explosive) Materials.* In addition to the label specified in column 6 of the § 172.101 table, each package of Class 1 material that also meets the definition for:

(1) Division 6.1, Packing Groups I or II, shall be labeled POISON or POISON INHALATION HAZARD, as appropriate.

(2) Class 7, shall be labeled in accordance with § 172.403 of this subpart.

(f) *Division 2.2 materials.* In addition to the label specified in column 6 of the § 172.101 table, each package of Division 2.2 material that also meets the definition for an oxidizing gas (see § 171.8 of this subchapter) must be labeled OXIDIZER.

(g) *Division 2.3 materials.* In addition to the label specified in column 6 of the § 172.101 table, each package of Division 2.3 material that also meets the definition for:

(1) Division 2.1, must be labeled Flammable Gas;

(2) Division 5.1, must be labeled Oxidizer; and

(3) Class 8, must be labeled Corrosive.

[Amdt. 172–123, 55 FR 52594, Dec. 21, 1990, as amended at 56 FR 66255, Dec. 20, 1991; Amdt. 172–139, 59 FR 67490, Dec. 29, 1994; Amdt. 172–140, 60 FR 26805, May 18, 1995; Amdt. 172–149, 61 FR 27173, May 30, 1996; 62 FR 39405, July 22, 1997; 66 FR 33425, June 21, 2001; 69 FR 3668, Jan. 26, 2004]

#### § 172.403 Class 7 (radioactive) material.

(a) Unless excepted from labeling by §§ 173.421 through 173.427 of this subchapter, each package of radioactive material must be labeled as provided in this section.

(b) The proper label to affix to a package of Class 7 (radioactive) material is based on the radiation level at

the surface of the package and the transport index. The proper category of label must be determined in accordance with paragraph (c) of this section. The label to be applied must be the highest category required for any of the two determining conditions for the package. RADIOACTIVE WHITE-I is the lowest category and RADIO-

ACTIVE YELLOW-III is the highest. For example, a package with a transport index of 0.8 and a maximum surface radiation level of 0.6 millisievert (60 millirems) per hour must bear a RADIOACTIVE YELLOW-III label.

(c) Category of label to be applied to Class 7 (radioactive) materials packages:

| Transport index                        | Maximum radiation level at any point on the external surface                           | Label category <sup>1</sup>                                                                     |
|----------------------------------------|----------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------|
| 0 <sup>2</sup> .....                   | Less than or equal to 0.005 mSv/h (0.5 mrem/h).                                        | WHITE-I.                                                                                        |
| More than 0 but not more than 1 .....  | Greater than 0.005 mSv/h (0.5 mrem/h) but less than or equal to 0.5 mSv/h (50 mrem/h). | YELLOW-II.                                                                                      |
| More than 1 but not more than 10 ..... | Greater than 0.5 mSv/h (50 mrem/h) but less than or equal to 2 mSv/h (200 mrem/h).     | YELLOW-III.                                                                                     |
| More than 10 .....                     | Greater than 2 mSv/h (200 mrem/h) but less than or equal to 10 mSv/h (1,000 mrem/h).   | YELLOW-III (Must be shipped under exclusive use provisions; see 173.441(b) of this subchapter). |

<sup>1</sup> Any package containing a "highway route controlled quantity" (§ 173.403 of this subchapter) must be labelled as RADIOACTIVE YELLOW-III.

<sup>2</sup> If the measured TI is not greater than 0.05, the value may be considered to be zero.

(d) *EMPTY* label. See § 173.428(d) of this subchapter for EMPTY labeling requirements.

(e) *FISSILE* label. For packages required in § 172.402 to bear a FISSILE label, each such label must be completed with the criticality safety index (CSI) assigned in the NRC or DOE package design approval, or in the certificate of approval for special arrangement or the certificate of approval for the package design issued by the Competent Authority for import and export shipments. For overpacks and freight containers required in § 172.402 to bear a FISSILE label, the CSI on the label must be the sum of the CSIs for all of the packages contained in the overpack or freight container.

(f) Each package required by this section to be labeled with a RADIOACTIVE label must have two of these labels, affixed to opposite sides of the package. (See § 172.406(e)(3) for freight container label requirements).

(g) The following applicable items of information must be entered in the blank spaces on the RADIOACTIVE label by legible printing (manual or mechanical), using a durable weather resistant means of marking:

(1) *Contents*. Except for LSA-1 material, the names of the radionuclides as taken from the listing of radionuclides

in § 173.435 of this subchapter (symbols which conform to established radiation protection terminology are authorized, i.e., <sup>99</sup>Mo, <sup>60</sup>Co, etc.). For mixtures of radionuclides, with consideration of space available on the label, the radionuclides that must be shown must be determined in accordance with § 173.433(g) of this subchapter. For LSA-I material, the term "LSA-I" may be used in place of the names of the radionuclides.

(2) *Activity*. The activity in the package must be expressed in appropriate SI units (e.g., Becquerels (Bq), Terabecquerels (TBq), etc.). The activity may also be stated in appropriate customary units (Curies (Ci), milliCuries (mCi), microCuries (uCi), etc.) in parentheses following the SI units. Abbreviations are authorized. Except for plutonium-239 and plutonium-241, the weight in grams or kilograms of fissile radionuclides may be inserted instead of activity units. For plutonium-239 and plutonium-241, the weight in grams of fissile radionuclides may be inserted in addition to the activity units.

(3) *Transport index*. (see § 173.403 of this subchapter.)

(h) When one or more packages of Class 7 (radioactive) material are

placed within an overpack, the overpack must be labeled as prescribed in this section, except as follows:

(1) The “contents” entry on the label may state “mixed” in place of the names of the radionuclides unless each inside package contains the same radionuclide(s).

(2) The “activity” entry on the label must be determined by adding together the number of becquerels of the Class 7 (radioactive) materials packages contained therein.

(3) For an overpack, the transport index (TI) must be determined by adding together the transport indices of the Class 7 (radioactive) materials packages contained therein, except that for a rigid overpack, the transport index (TI) may alternatively be determined by direct measurement as prescribed in § 173.403 of this subchapter under the definition for “transport index,” taken by the person initially offering the packages contained within the overpack for shipment.

(4) The category of Class 7 label for the overpack must be determined from the table in § 172.403(c) using the TI derived according to paragraph (h)(3) of this section, and the maximum radiation level on the surface of the overpack.

(5) The category of the Class 7 label of the overpack, and not that of any of the packages contained therein, must be used in accordance with Table 1 of § 172.504(e) to determine when the transport vehicle must be placarded.

(6) For fissile material, the criticality safety index which must be entered on the overpack FISSILE label is the sum of the criticality safety indices of the individual packages in the overpack, as stated in the certificate of approval for the package design issued by the NRC or the U.S. Competent Authority.

[Amdt. 172–29, 41 FR 15996, Apr. 15, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 172.403, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 172.404 Labels for mixed and consolidated packaging.

(a) *Mixed packaging.* When hazardous materials having different hazard

classes are packed within the same packaging, or within the same outside container or overpack as described in § 173.25 and authorized by § 173.21 of this subchapter, the packaging, outside container or overpack must be labeled as required for each class of hazardous material contained therein.

(b) *Consolidated packaging.* When two or more packages containing compatible hazardous material (see § 173.21 of this subchapter) are placed within the same outside container or overpack, the outside container or overpack must be labeled as required for each class of hazardous material contained therein.

#### § 172.405 Authorized label modifications.

(a) For Classes 1, 2, 3, 4, 5, 6, and 8, text indicating a hazard (for example FLAMMABLE LIQUID) is not required on a primary or subsidiary label.

(b) For a package containing Oxygen, compressed, or Oxygen, refrigerated liquid, the OXIDIZER label specified in § 172.426 of this subpart, modified to display the word “OXYGEN” instead of “OXIDIZER”, and the class number “2” instead of “5.1”, may be used in place of the NON-FLAMMABLE GAS and OXIDIZER labels. Notwithstanding the provisions of paragraph (a) of this section, the word “OXYGEN” must appear on the label.

(c) For a package containing a Division 6.1, Packing Group III material, the POISON label specified in § 172.430 may be modified to display the text “PG III” instead of “POISON” or “TOXIC” below the mid line of the label. Also see § 172.313(d).

[Amdt. 172–123, 55 FR 52594, Dec. 21, 1990, as amended at 56 FR 66255, Dec. 20, 1991; 57 FR 45458, Oct. 1, 1992; 64 FR 10776, Mar. 5, 1999; 66 FR 33425, June 21, 2001]

#### § 172.406 Placement of labels.

(a) *General.* (1) Except as provided in paragraphs (b) and (e) of this section, each label required by this subpart must—

(i) Be printed on or affixed to a surface (other than the bottom) of the package or containment device containing the hazardous material; and



## § 172.407

## 49 CFR Ch. I (10–1–08 Edition)

(ii) Be located on the same surface of the package and near the proper shipping name marking, if the package dimensions are adequate.

(2) Except as provided in paragraph (e) of this section, duplicate labeling is not required on a package or containment device (such as to satisfy redundant labeling requirements).

(b) *Exceptions.* A label may be printed on or placed on a securely affixed tag, or may be affixed by other suitable means to:

(1) A package that contains no radioactive material and which has dimensions less than those of the required label;

(2) A cylinder; and

(3) A package which has such an irregular surface that a label cannot be satisfactorily affixed.

(c) *Placement of multiple labels.* When primary and subsidiary hazard labels are required, they must be displayed next to each other. Placement conforms to this requirement if labels are within 150 mm (6 inches) of one another.

(d) *Contrast with background.* Each label must be printed on or affixed to a background of contrasting color, or must have a dotted or solid line outer border.

(e) *Duplicate labeling.* Generally, only one of each different required label must be displayed on a package. However, duplicate labels must be displayed on at least two sides or two ends (other than the bottom) of—

(1) Each package or overpack having a volume of 1.8 m<sup>3</sup> (64 cubic feet) or more;

(2) Each non-bulk package containing a radioactive material;

(3) Each DOT 106 or 110 multi-unit tank car tank. Labels must be displayed on each end;

(4) Each portable tank of less than 3,785 L (1000 gallons) capacity;

(5) Each freight container or aircraft unit load device having a volume of 1.8 m<sup>3</sup> (64 cubic feet) or more, but less than 18 m<sup>3</sup> (640 cubic feet). One of each required label must be displayed on or near the closure; and

(6) An IBC having a volume of 1.8 m<sup>3</sup> (64 cubic feet) or more.

(f) *Visibility.* A label must be clearly visible and may not be obscured by markings or attachments.

[Amdt. 172–123, 55 FR 52594, Dec. 21, 1990, as amended at 56 FR 66255, Dec. 20, 1991; Amdt. 172–130, 58 FR 51531, Oct. 1, 1993; 73 FR 4716, Jan. 28, 2008]

### § 172.407 Label specifications.

(a) *Durability.* Each label, whether printed on or affixed to a package, must be durable and weather resistant. A label on a package must be able to withstand, without deterioration or a substantial change in color, a 30-day exposure to conditions incident to transportation that reasonably could be expected to be encountered by the labeled package.

(b) *Design.* (1) Except for size and color, the printing, inner border, and symbol on each label must be as shown in §§172.411 through 172.448 of this subpart, as appropriate.

(2) The dotted line border shown on each label is not part of the label specification, except when used as an alternative for the solid line outer border to meet the requirements of §172.406(d) of this subpart.

(c) *Size.* (1) Each diamond (square-on-point) label prescribed in this subpart must be at least 100 mm (3.9 inches) on each side with each side having a solid line inner border 5.0 to 6.3 mm (0.2 to 0.25 inches) from the edge.

(2) The CARGO AIRCRAFT ONLY label must be a rectangle measuring at least 110 mm (4.3 inches) in height by 120 mm (4.7 inches) in width. The word “DANGER” must be shown in letters measuring at least 12.7 mm (0.5 inches) in height.

(3) Except as otherwise provided in this subpart, the hazard class number, or division number, as appropriate, must be at least 6.3 mm (0.25 inches) and not greater than 12.7 mm (0.5 inches).

(4) When text indicating a hazard is displayed on a label, the label name must be shown in letters measuring at least 7.6 mm (0.3 inches) in height. For SPONTANEOUSLY COMBUSTIBLE or DANGEROUS WHEN WET labels, the words “Spontaneously” and “When Wet” must be shown in letters measuring at least 5.1 mm (0.2 inches) in height.

(5) The symbol on each label must be proportionate in size to that shown in the appropriate section of this subpart.

(d) *Color.* (1) The background color on each label must be as prescribed in §§ 172.411 through 172.448 of this subpart, as appropriate.

(2) The symbol, text, numbers, and border must be shown in black on a label except that—

(i) White may be used on a label with a one color background of green, red or blue.

(ii) White must be used for the text and class number for the CORROSIVE label.

(iii) White may be used for the symbol for the ORGANIC PEROXIDE label.

(3) Black and any color on a label must be able to withstand, without substantial change, a 72-hour fadeometer test (for a description of equipment designed for this purpose, see ASTM G 23-69 (1975) or ASTM G 26-70).

(4) (i) A color on a label, upon visual examination, must fall within the color tolerances—

(A) Displayed on color charts conforming to the technical specifications for charts set forth in table 1 or 2 in appendix A to this part; or

(B) For labels printed on packaging surfaces, specified in table 3 in appendix A to this part.

(ii) Color charts conforming to appendix A to this part are on display in Office of Hazardous Materials Safety, Office of Hazardous Materials Standards, Room 8422, Nassif Building, 400 Seventh Street, SW., Washington DC 20590-0001.

(5) The following color standards in the PANTONE® formula guide coated/uncoated (see § 171.7(b) of this subchapter) may be used to achieve the required colors on markings and hazard warning labels and placards:

- (i) For Red—Use PANTONE® 186 U
- (ii) For Orange—Use PANTONE® 151 U
- (iii) For Yellow—Use PANTONE® 109 U
- (iv) For Green—Use PANTONE® 335 U
- (v) For Blue—Use PANTONE® 285 U
- (vi) For Purple—Use PANTONE® 259 U

(6) Where specific colors from the PANTONE MATCHING SYSTEM® are applied as opaque coatings, such as paint, enamel, or plastic, or where labels are printed directly on the surface of a packaging, a spectrophotometer or other instrumentation must be used to ensure a proper match with the color standards in the PANTONE® formula guide coated/uncoated for colors prescribed in paragraph (d)(5) of this section. PANTONE® is the property of Pantone, Inc.

(7) The specified label color must extend to the edge of the label in the area designated on each label, except for the CORROSIVE, RADIOACTIVE YELLOW-II, and RADIOACTIVE YELLOW-III labels on which the color must extend only to the inner border.

(e) *Form identification.* A label may contain form identification information, including the name of its maker, provided that information is printed outside the solid line inner border in no larger than 10-point type.

(f) *Exceptions.* Except for materials poisonous by inhalation (See § 171.8 of this subchapter), a label conforming to specifications in the UN Recommendations may be used in place of a corresponding label that conforms to the requirements of this subpart.

(g) *Trefoil symbol.* The trefoil symbol on the RADIOACTIVE WHITE-I, RADIOACTIVE YELLOW-II, and RADIOACTIVE YELLOW-III labels must meet the appropriate specifications in appendix B of this part.

[Amdt. 172-123, 55 FR 52595, Dec. 21, 1990, as amended at 56 FR 66256, Dec. 20, 1991; Amdt. 172-143, 60 FR 50305, Sept. 28, 1995; 64 FR 10776, Mar. 5, 1999; 66 FR 8647, Feb. 1, 2001; 66 FR 44255, Aug. 22, 2001; 67 FR 61013, Sept. 27, 2002; 69 FR 64472, Nov. 4, 2004; 71 FR 78627, Dec. 29, 2006]

**§ 172.411 EXPLOSIVE 1.1, 1.2, 1.3, 1.4, 1.5 and 1.6 labels, and EXPLOSIVE Subsidiary label.**

(a) Except for size and color, the EXPLOSIVE 1.1, EXPLOSIVE 1.2 and EXPLOSIVE 1.3 labels must be as follows:

EXPLOSIVE 1.5:



(b) In addition to complying with §172.407, the background color on the EXPLOSIVE 1.1, EXPLOSIVE 1.2 and EXPLOSIVE 1.3 labels must be orange. The “\*\*” must be replaced with the appropriate division number and compatibility group letter. The compatibility group letter must be the same size as the division number and must be shown as a capitalized Roman letter.

EXPLOSIVE 1.6:

(c) Except for size and color, the EXPLOSIVE 1.4, EXPLOSIVE 1.5 and EXPLOSIVE 1.6 labels must be as follows:


EXPLOSIVE 1.4:



(d) In addition to complying with §172.407, the background color on the EXPLOSIVE 1.4, EXPLOSIVE 1.5 and EXPLOSIVE 1.6 label must be orange. The “\*” must be replaced with the appropriate compatibility group. The compatibility group letter must be shown as a capitalized Roman letter. Division numbers must measure at least 30 mm (1.2 inches) in height and at least 5 mm (0.2 inches) in width.

(e) An EXPLOSIVE subsidiary label is required for materials identified in Column (6) of the HMT as having an explosive subsidiary hazard. The division number or compatibility group letter may be displayed on the subsidiary

hazard label. Except for size and color, the EXPLOSIVE subsidiary label must be as follows:




(f) The EXPLOSIVE subsidiary label must comply with §172.407.

[Amdt. 172-123, 56 FR 66256, Dec. 20, 1991, as amended by Amdt. 172-139, 59 FR 67490, Dec. 29, 1994; 66 FR 33425, June 21, 2001; 68 FR 45031, July 31, 2003]

**§ 172.415 NON-FLAMMABLE GAS label.**

(a) Except for size and color, the NON-FLAMMABLE GAS label must be as follows:



(b) In addition to complying with §172.407, the background color on the

NON-FLAMMABLE GAS label must be green.

[Amdt. 172-123, 56 FR 66256, Dec. 20, 1991]

**§ 172.416 POISON GAS label.**

(a) Except for size and color, the POISON GAS label must be as follows:




(b) In addition to complying with §172.407, the background on the POISON GAS label and the symbol must be white. The background of the upper diamond must be black and the lower point of the upper diamond must be 14 mm (0.54 inches) above the horizontal center line.

[62 FR 39405, July 22, 1997]

**§ 172.417 FLAMMABLE GAS label.**

(a) Except for size and color, the FLAMMABLE GAS label must be as follows:



**§ 172.419**

(b) In addition to complying with §172.407, the background color on the FLAMMABLE GAS label must be red.

[Amdt. 172-123, 56 FR 66257, Dec. 20, 1991]

**§ 172.419 FLAMMABLE LIQUID label.**

(a) Except for size and color the FLAMMABLE LIQUID label must be as follows:




(b) In addition to complying with §172.407, the background color on the FLAMMABLE LIQUID label must be red.

[Amdt. 172-123, 56 FR 66257, Dec. 20, 1991]

**§ 172.420 FLAMMABLE SOLID label.**

(a) Except for size and color, the FLAMMABLE SOLID label must be as follows:



(b) In addition to complying with §172.407, the background on the FLAM-


**49 CFR Ch. I (10-1-08 Edition)**

MABLE SOLID label must be white with vertical red stripes equally spaced on each side of a red stripe placed in the center of the label. The red vertical stripes must be spaced so that, visually, they appear equal in width to the white spaces between them. The symbol (flame) and text (when used) must be overprinted. The text "FLAMMABLE SOLID" may be placed in a white rectangle.

[Amdt. 172-123, 56 FR 66257, Dec. 20, 1991]

**§ 172.422 SPONTANEOUSLY COMBUSTIBLE label.**

(a) Except for size and color, the SPONTANEOUSLY COMBUSTIBLE label must be as follows:



(b) In addition to complying with §172.407, the background color on the lower half of the SPONTANEOUSLY COMBUSTIBLE label must be red and the upper half must be white.

[Amdt. 172-123, 56 FR 66257, Dec. 20, 1991, as amended at 57 FR 45458, Oct. 1, 1992]

**§ 172.423 DANGEROUS WHEN WET label.**

(a) Except for size and color, the DANGEROUS WHEN WET label must be as follows:



(b) In addition to complying with §172.407, the background color on the DANGEROUS WHEN WET label must be blue.

[Amdt. 172–123, 56 FR 66257, Dec. 20, 1991]

**§ 172.426 OXIDIZER label.**

(a) Except for size and color, the OXIDIZER label must be as follows:




(b) In addition to complying with §172.407, the background color on the OXIDIZER label must be yellow.

[Amdt. 172–123, 56 FR 66257, Dec. 20, 1991]

**§ 172.427 ORGANIC PEROXIDE label.**

(a) Except for size and color, the ORGANIC PEROXIDE label must be as follows:



(b) In addition to complying with §172.407, the background on the ORGANIC PEROXIDE label must be red in the top half and yellow in the lower half.

[71 FR 78627, Dec. 29, 2006]

**§ 172.429 POISON INHALATION HAZARD label.**

(a) Except for size and color, the POISON INHALATION HAZARD label must be as follows:



(b) In addition to complying with §172.407, the background on the POISON INHALATION HAZARD label and the symbol must be white. The background of the upper diamond must be black and the lower point of the upper diamond must be 14 mm (0.54 inches) above the horizontal center line.

[62 FR 39406, July 22, 1997]

**§ 172.430 POISON label.**

(a) Except for size and color, the POISON label must be as follows:



(b) In addition to complying with §172.407, the background on the POISON label must be white. The word "TOXIC" may be used in lieu of the word "POISON".

[Amdt. 172-123, 56 FR 66258, Dec. 20, 1991, as amended by Amdt. 172-139, 59 FR 67490, Dec. 29, 1994]

**§ 172.431 [Reserved]**

**§ 172.432 INFECTIOUS SUBSTANCE label.**

(a) Except for size and color, the INFECTIOUS SUBSTANCE label must be as follows:





(b) In addition to complying with §172.407, the background on the INFECTIOUS SUBSTANCE label must be white.

[Amdt. 172–123, 56 FR 66258, Dec. 20, 1991, as amended at 67 FR 53136, Aug. 14, 2002]

**§ 172.436 RADIOACTIVE WHITE-I label.**

(a) Except for size and color, the RADIOACTIVE WHITE-I label must be as follows:



(b) In addition to complying with § 172.407, the background on the RADIOACTIVE WHITE-I label must be white. The printing and symbol must be black, except for the “I” which must be red.

[Amdt. 172–123, 56 FR 66259, Dec. 20, 1991]

**§ 172.438 RADIOACTIVE YELLOW-II label.**

(a) Except for size and color, the RADIOACTIVE YELLOW-II must be as follows:



(b) In addition to complying with § 172.407, the background color on the RADIOACTIVE YELLOW-II label must be yellow in the top half and white in the lower half. The printing and sym-

bol must be black, except for the “II” which must be red.

[Amdt. 172–123, 56 FR 66259, Dec. 20, 1991]

**§ 172.440 RADIOACTIVE YELLOW-III label.**

(a) Except for size and color, the RADIOACTIVE YELLOW-III label must be as follows:




(b) In addition to complying with § 172.407, the background color on the RADIOACTIVE YELLOW-III label must be yellow in the top half and white in the lower half. The printing and symbol must be black, except for the “III” which must be red.

[Amdt. 172–123, 56 FR 66259, Dec. 20, 1991]

**§ 172.441 FISSILE label.**

(a) Except for size and color, the FISSILE label must be as follows:




(b) In addition to complying with §172.407, the background color on the FISSILE label must be white.

[69 FR 3669, Jan. 26, 2004]

**§ 172.442 CORROSIVE label.**

(a) Except for size and color, the CORROSIVE label must be as follows:




(b) In addition to complying with § 172.407, the background on the CORROSIVE label must be white in the top half and black in the lower half.

[Amdt. 172-123, 56 FR 66259, Dec. 20, 1991]

**§ 172.444 [Reserved]**

**§ 172.446 CLASS 9 label.**

(a) Except for size and color, the “CLASS 9” (miscellaneous hazardous materials) label must be as follows:



(b) In addition to complying with § 172.407, the background on the CLASS 9 label must be white with seven black vertical stripes on the top half. The black vertical stripes must be spaced, so that, visually, they appear equal in width to the six white spaces between them. The lower half of the label must be white with the class number “9” underlined and centered at the bottom.

[Amdt. 172-123, 56 FR 66259, Dec. 20, 1991]

**§ 172.448 CARGO AIRCRAFT ONLY label.**

(a) Except for size and color, the CARGO AIRCRAFT ONLY label must be as follows:




(b) The CARGO AIRCRAFT ONLY label must be black on an orange background.

[Amdt. 172-123, 56 FR 66259, Dec. 20, 1991]

**§ 172.450 EMPTY label.**

(a) Each EMPTY label, except for size, must be as follows:



(1) Each side must be at least 6 inches (152 mm.) with each letter at least 1 inch (25.4 mm.) in height.

(2) The label must be white with black printing.

(b) [Reserved]

**Subpart F—Placarding**

**§ 172.500 Applicability of placarding requirements.**

(a) Each person who offers for transportation or transports any hazardous

## § 172.502

material subject to this subchapter shall comply with the applicable placarding requirements of this subpart.

(b) This subpart does not apply to—

(1) Infectious substances;

(2) Hazardous materials classed as ORM-D;

(3) Hazardous materials authorized by this subchapter to be offered for transportation as Limited Quantities when identified as such on shipping papers in accordance with § 172.203(b);

(4) Hazardous materials prepared in accordance with § 173.13 of this subchapter;

(5) Hazardous materials which are packaged as small quantities under the provisions of § 173.4 of this subchapter; and

(6) Combustible liquids in non-bulk packagings.

[Amdt. 172–123, 55 FR 52599, Dec. 21, 1990, as amended by Amdt. 172–149, 61 FR 27173, May 30, 1996]

### § 172.502 Prohibited and permissive placarding.

(a) *Prohibited placarding.* Except as provided in paragraph (b) of this section, no person may affix or display on a packaging, freight container, unit load device, motor vehicle or rail car—

(1) Any placard described in this subpart unless—

(i) The material being offered or transported is a hazardous material;

(ii) The placard represents a hazard of the hazardous material being offered or transported; and

(iii) Any placarding conforms to the requirements of this subpart.

(2) Any sign, advertisement, slogan (such as “Drive Safely”), or device that, by its color, design, shape or content, could be confused with any placard prescribed in this subpart.

(b) *Exceptions.* (1) The restrictions in paragraph (a) of this section do not apply to a bulk packaging, freight container, unit load device, transport vehicle or rail car which is placarded in conformance with TDG Regulations, the IMDG Code or the UN Recommendations (IBR, see § 171.7 of this subchapter).

(2) The restrictions of paragraph (a) of this section do not apply to the display of a BIOHAZARD marking, a

## 49 CFR Ch. I (10–1–08 Edition)

“HOT” marking, or an identification number on a white square-on-point configuration in accordance with §§ 172.323(c), 172.325(c), or 172.336(b) of this part, respectively.

(3) The restrictions in paragraph (a)(2) of this section do not apply until October 1, 2001 to a safety sign or safety slogan (e.g., “Drive Safely” or “Drive Carefully”), which was permanently marked on a transport vehicle, bulk packaging, or freight container on or before August 21, 1997.

(c) *Permissive placarding.* Placards may be displayed for a hazardous material, even when not required, if the placarding otherwise conforms to the requirements of this subpart.

[Amdt. 172–123, 55 FR 52599, Dec. 21, 1990, as amended at 56 FR 66259, Dec. 20, 1991; Amdt. 172–151, 62 FR 1230, Jan. 8, 1997; 62 FR 39389 and 39407, July 22, 1997; 66 FR 8647, Feb. 1, 2001; 66 FR 33426, June 21, 2001; 67 FR 53137, Aug. 14, 2002; 68 FR 75741, Dec. 31, 2003]

### § 172.503 Identification number display on placards.

For procedures and limitations pertaining to the display of identification numbers on placards, see § 172.334.

[Amdt. 172–58, 45 FR 34701, May 22, 1980]

### § 172.504 General placarding requirements.

(a) *General.* Except as otherwise provided in this subchapter, each bulk packaging, freight container, unit load device, transport vehicle or rail car containing any quantity of a hazardous material must be placarded on each side and each end with the type of placards specified in tables 1 and 2 of this section and in accordance with other placarding requirements of this subpart, including the specifications for the placards named in the tables and described in detail in §§ 172.519 through 172.560.

(b) *DANGEROUS placard.* A freight container, unit load device, transport vehicle, or rail car which contains non-bulk packages with two or more categories of hazardous materials that require different placards specified in table 2 of paragraph (e) of this section may be placarded with a DANGEROUS placard instead of the separate placarding specified for each of the materials in table 2 of paragraph (e) of

this section. However, when 1,000 kg (2,205 pounds) aggregate gross weight or more of one category of material is loaded therein at one loading facility on a freight container, unit load device, transport vehicle, or rail car, the placard specified in table 2 of paragraph (e) of this section for that category must be applied.

(c) *Exception for less than 454 kg (1,001 pounds).* Except for bulk packagings and hazardous materials subject to § 172.505, when hazardous materials covered by table 2 of this section are transported by highway or rail, placards are not required on—

(1) A transport vehicle or freight container which contains less than 454 kg (1001 pounds) aggregate gross weight of hazardous materials covered by table 2 of paragraph (e) of this section; or

(2) A rail car loaded with transport vehicles or freight containers, none of which is required to be placarded.

The exceptions provided in paragraph (c) of this section do not prohibit the display of placards in the manner prescribed in this subpart, if not otherwise prohibited (see § 172.502), on transport vehicles or freight containers which are not required to be placarded.

(d) *Exception for empty non-bulk packages.* Except for hazardous materials subject to § 172.505, a non-bulk packaging that contains only the residue of a hazardous material covered by Table 2 of paragraph (e) of this section need not be included in determining placarding requirements.

(e) *Placarding tables.* Placards are specified for hazardous materials in accordance with the following tables:

TABLE 1

| Category of material (Hazard class or division number and additional description, as appropriate) | Placard name                   | Placard design section reference (§) |
|---------------------------------------------------------------------------------------------------|--------------------------------|--------------------------------------|
| 1.1 .....                                                                                         | EXPLOSIVES 1.1 .....           | 172.522                              |
| 1.2 .....                                                                                         | EXPLOSIVES 1.2 .....           | 172.522                              |
| 1.3 .....                                                                                         | EXPLOSIVES 1.3 .....           | 172.522                              |
| 2.3 .....                                                                                         | POISON GAS .....               | 172.540                              |
| 4.3 .....                                                                                         | DANGEROUS WHEN WET .....       | 172.548                              |
| 5.2 (Organic peroxide, Type B, liquid or solid, temperature controlled).                          | ORGANIC PEROXIDE .....         | 172.552                              |
| 6.1 (material poisonous by inhalation (see § 171.8 of this subchapter)).                          | POISON INHALATION HAZARD ..... | 172.555                              |
| 7 (Radioactive Yellow III label only) .....                                                       | RADIOACTIVE <sup>1</sup> ..... | 172.556                              |

<sup>1</sup>RADIOACTIVE placard also required for exclusive use shipments of low specific activity material and surface contaminated objects transported in accordance with § 173.427(b)(4) and (5) or (c) of this subchapter.

TABLE 2

| Category of material (Hazard class or division number and additional description, as appropriate) | Placard name                        | Placard design section reference (§) |
|---------------------------------------------------------------------------------------------------|-------------------------------------|--------------------------------------|
| 1.4 .....                                                                                         | EXPLOSIVES 1.4 .....                | 172.523                              |
| 1.5 .....                                                                                         | EXPLOSIVES 1.5 .....                | 172.524                              |
| 1.6 .....                                                                                         | EXPLOSIVES 1.6 .....                | 172.525                              |
| 2.1 .....                                                                                         | FLAMMABLE GAS .....                 | 172.532                              |
| 2.2 .....                                                                                         | NON-FLAMMABLE GAS .....             | 172.528                              |
| 3 .....                                                                                           | FLAMMABLE .....                     | 172.542                              |
| Combustible liquid .....                                                                          | COMBUSTIBLE .....                   | 172.544                              |
| 4.1 .....                                                                                         | FLAMMABLE SOLID .....               | 172.546                              |
| 4.2 .....                                                                                         | SPONTANEOUSLY COMBUSTIBLE .....     | 172.547                              |
| 5.1 .....                                                                                         | OXIDIZER .....                      | 172.550                              |
| 5.2 (Other than organic peroxide, Type B, liquid or solid, temperature controlled).               | ORGANIC PEROXIDE .....              | 172.552                              |
| 6.1 (other than material poisonous by inhalation) .....                                           | POISON .....                        | 172.554                              |
| 6.2 .....                                                                                         | (None) .....                        | .....                                |
| 8 .....                                                                                           | CORROSIVE .....                     | 172.558                              |
| 9 .....                                                                                           | Class 9 (see § 172.504(f)(9)) ..... | 172.560                              |
| ORM-D .....                                                                                       | (None) .....                        | .....                                |

(f) *Additional placarding exceptions.* (1) When more than one division placard is required for Class 1 materials on a transport vehicle, rail car, freight container or unit load device, only the placard representing the lowest division number must be displayed.

(2) A FLAMMABLE placard may be used in place of a COMBUSTIBLE placard on—

(i) A cargo tank or portable tank.

(ii) A compartmented tank car which contains both flammable and combustible liquids.

(3) A NON-FLAMMABLE GAS placard is not required on a transport vehicle which contains non-flammable gas if the transport vehicle also contains flammable gas or oxygen and it is placarded with FLAMMABLE GAS or OXYGEN placards, as required.

(4) OXIDIZER placards are not required for Division 5.1 materials on freight containers, unit load devices, transport vehicles or rail cars which also contain Division 1.1 or 1.2 materials and which are placarded with EXPLOSIVES 1.1 or 1.2 placards, as required.

(5) For transportation by transport vehicle or rail car only, an OXIDIZER placard is not required for Division 5.1 materials on a transport vehicle, rail car or freight container which also contains Division 1.5 explosives and is placarded with EXPLOSIVES 1.5 placards, as required.

(6) The EXPLOSIVE 1.4 placard is not required for those Division 1.4 Compatibility Group S (1.4S) materials that are not required to be labeled 1.4S.

(7) For domestic transportation of oxygen, compressed or oxygen, refrigerated liquid, the OXYGEN placard in §172.530 of this subpart may be used in place of a NON-FLAMMABLE GAS placard.

(8) For domestic transportation, a POISON INHALATION HAZARD placard is not required on a transport vehicle or freight container that is already placarded with the POISON GAS placard.

(9) For Class 9, a CLASS 9 placard is not required for domestic transportation, including that portion of international transportation, defined in §171.8 of this subchapter, which occurs within the United States. However, a

bulk packaging must be marked with the appropriate identification number on a CLASS 9 placard, an orange panel, or a white square-on-point display configuration as required by subpart D of this part.

(10) For Division 6.1, PG III materials, a POISON placard may be modified to display the text “PG III” below the mid line of the placard.

(11) For domestic transportation, a POISON placard is not required on a transport vehicle or freight container required to display a POISON INHALATION HAZARD or POISON GAS placard.

(g) For shipments of Class 1 (explosive materials) by aircraft or vessel, the applicable compatibility group letter must be displayed on the placards, or labels when applicable, required by this section. When more than one compatibility group placard is required for Class 1 materials, only one placard is required to be displayed, as provided in paragraphs (g)(1) through (g)(4) of this section. For the purposes of paragraphs (g)(1) through (g)(4), there is a distinction between the phrases *explosive articles* and *explosive substances*. *Explosive article* means an article containing an explosive substance; examples include a detonator, flare, primer or fuse. *Explosive substance* means a substance contained in a packaging that is not contained in an article; examples include black powder and smokeless powder.

(1) Explosive articles of compatibility groups C, D or E may be placarded displaying compatibility group E.

(2) Explosive articles of compatibility groups C, D, or E, when transported with those in compatibility group N, may be placarded displaying compatibility group D.

(3) Explosive substances of compatibility groups C and D may be placarded displaying compatibility group D.

(4) Explosive articles of compatibility groups C, D, E or G, except for fireworks, may be placarded displaying compatibility group E.

[Amdt. 172–123, 55 FR 52600, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 172.504, see the List of CFR

Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 172.505 Placarding for subsidiary hazards.**

(a) Each transport vehicle, freight container, portable tank, unit load device, or rail car that contains a poisonous material subject to the "Poison Inhalation Hazard" shipping description of § 172.203(m) must be placarded with a POISON INHALATION HAZARD or POISON GAS placard, as appropriate, on each side and each end, in addition to any other placard required for that material in § 172.504. Duplication of the POISON INHALATION HAZARD or POISON GAS placard is not required.

(b) In addition to the RADIOACTIVE placard which may be required by § 172.504(e) of this subpart, each transport vehicle, portable tank or freight container that contains 454 kg (1001 pounds) or more gross weight of fissile or low specific activity uranium hexafluoride shall be placarded with a CORROSIVE placard on each side and each end.

(c) Each transport vehicle, portable tank, freight container or unit load device that contains a material which has a subsidiary hazard of being dangerous when wet, as defined in § 173.124 of this subchapter, shall be placarded with DANGEROUS WHEN WET placards, on each side and each end, in addition to the placards required by § 172.504.

(d) Hazardous materials that possess secondary hazards may exhibit subsidiary placards that correspond to the placards described in this part, even when not required by this part (see also § 172.519(b) (4) of this subpart).

[Amdt. 172-123, 55 FR 52601, Dec. 21, 1990, as amended at 56 FR 66260, Dec. 20, 1991; 57 FR 45460, Oct. 1, 1992; Amdt. 172-127, 59 FR 49133, Sept. 26, 1994; Amdt. 172-151, 62 FR 1231, Jan. 8, 1997; 62 FR 39398, July 22, 1997; 65 FR 58626, Sept. 29, 2000; 72 FR 55692, Oct. 1, 2007]

**§ 172.506 Providing and affixing placards: Highway.**

(a) Each person offering a motor carrier a hazardous material for transportation by highway shall provide to the motor carrier the required placards for the material being offered prior to or

at the same time the material is offered for transportation, unless the carrier's motor vehicle is already placarded for the material as required by this subpart.

(1) No motor carrier may transport a hazardous material in a motor vehicle, unless the placards required for the hazardous material are affixed thereto as required by this subpart.

(2) [Reserved]

(b) [Reserved]

[Amdt. 172-29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172-29A, 41 FR 40679, Sept. 20, 1976]

**§ 172.507 Special placarding provisions: Highway.**

(a) Each motor vehicle used to transport a package of highway route controlled quantity Class 7 (radioactive) materials (see § 173.403 of this subchapter) must have the required RADIOACTIVE warning placard placed on a square background as described in § 172.527.

(b) A nurse tank, meeting the provisions of § 173.315(m) of this subchapter, is not required to be placarded on an end containing valves, fittings, regulators or gauges when those appurtenances prevent the markings and placard from being properly placed and visible.

[Amdt. 172-103, 51 FR 5971, Feb. 18, 1986, as amended by Amdt. 172-143, 60 FR 50305, Sept. 28, 1995]

**§ 172.508 Placarding and affixing placards: Rail.**

(a) Each person offering a hazardous material for transportation by rail shall affix to the rail car containing the material, the placards specified by this subpart. Placards displayed on motor vehicles, transport containers, or portable tanks may be used to satisfy this requirement, if the placards otherwise conform to the provisions of this subpart.

(b) No rail carrier may accept a rail car containing a hazardous material for transportation unless the placards for the hazardous material are affixed thereto as required by this subpart.

[Amdt. 172-29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172-123, 55 FR 52601, Dec. 21, 1990]



## § 172.510

## 49 CFR Ch. I (10–1–08 Edition)

### § 172.510 Special placarding provisions: Rail.

(a) *White square background.* The following must have the specified placards placed on a white square background, as described in § 172.527:

(1) Division 1.1 and 1.2 (explosive) materials which require EXPLOSIVES 1.1 or EXPLOSIVES 1.2 placards affixed to the rail car;

(2) Materials classed in Division 2.3 Hazard Zone A or 6.1 Packing Group I Hazard Zone A which require POISON GAS or POISON placards affixed to the rail car, including tank cars containing only a residue of the material; and

(3) Class DOT 113 tank cars used to transport a Division 2.1 (flammable gas) material, including tank cars containing only a residue of the material.

(b) *Chemical ammunition.* Each rail car containing Division 1.1 or 1.2 (explosive) ammunition which also meets the definition of a material poisonous by inhalation (see § 171.8 of this subchapter) must be placarded EXPLOSIVES 1.1 or EXPLOSIVES 1.2 and POISON GAS or POISON INHALATION HAZARD.

[Amdt. 172–29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172–103, 51 FR 5971, Feb. 18, 1986; Amdt. 172–110, 52 FR 29528, Aug. 10, 1987; Amdt. 172–111, 52 FR 36671, Sept. 30, 1987; Amdt. 172–123, 55 FR 52601, Dec. 21, 1990; 56 FR 66260, Dec. 20, 1991; 57 FR 45460, Oct. 1, 1992; Amdt. 172–248, 61 FR 28676, June 5, 1996; Amdt. 172–151, 62 FR 1231, Jan. 8, 1997; 62 FR 39398, July 22, 1997]

### § 172.512 Freight containers and aircraft unit load devices.

(a) *Capacity of 640 cubic feet or more.* Each person who offers for transportation, and each person who loads and transports, a hazardous material in a freight container or aircraft unit load device having a capacity of 640 cubic feet or more shall affix to the freight container or aircraft unit load device the placards specified for the material in accordance with § 172.504. However:

(1) The placarding exception provided in § 172.504(c) applies to motor vehicles transporting freight containers and aircraft unit load devices,

(2) The placarding exception provided in § 172.504(c) applies to each freight container and aircraft unit load device being transported for delivery to a con-

signee immediately following an air or water shipment, and,

(3) Placarding is not required on a freight container or aircraft unit load device if it is only transported by air and is identified as containing a hazardous material in the manner provided in part 7, chapter 2, section 2.7, of the ICAO Technical Instructions (IBR, see § 171.7 of this subchapter).

(b) *Capacity less than 18 m<sup>3</sup> (640 cubic feet).* Each person who offers for transportation by air, and each person who loads and transports by air, a hazardous material in a freight container or aircraft unit load device having a capacity of less than 18 m<sup>3</sup> (640 cubic feet) shall affix one placard of the type specified by paragraph (a) of this section unless the freight container or aircraft unit load device:

(1) Is labeled in accordance with subpart E of this part, including § 172.406(e);

(2) Contains radioactive materials requiring the Radioactive Yellow III label and is placarded with one Radioactive placard and is labeled in accordance with subpart E of this part, including § 172.406(e); or,

(3) Is identified as containing a hazardous material in the manner provided in part 7, chapter 2, section 2.7, of the ICAO Technical Instructions. When hazardous materials are offered for transportation, not involving air transportation, in a freight container having a capacity of less than 640 cubic feet the freight container need not be placarded. However, if not placarded, it must be labeled in accordance with subpart E of this part.

(c) Notwithstanding paragraphs (a) and (b) of this section, packages containing hazardous materials, other than ORM-D, offered for transportation by air in freight containers are subject to the inspection requirements of § 175.30 of this chapter.

[Amdt. 172–29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172–29A, 41 FR 40680, Sept. 20, 1976; Amdt. 172–87, 48 FR 53712, Nov. 29, 1983; 48 FR 55469, Dec. 13, 1983; Amdt. 172–103, 51 FR 5971, Feb. 18, 1986; Amdt. 172–111, 52 FR 36671, Sept. 30, 1987; Amdt. 172–123, 55 FR 52601, Dec. 21, 1990; 66 FR 33426, June 21, 2001; 66 FR 45182, Aug. 28, 2001; 68 FR 75741, Dec. 31, 2003; 69 FR 54046, Sept. 7, 2004]

**§ 172.514 Bulk packagings.**

(a) Except as provided in paragraph (c) of this section, each person who offers for transportation a bulk packaging which contains a hazardous material, shall affix the placards specified for the material in §§ 172.504 and 172.505.

(b) Each bulk packaging that is required to be placarded when it contains a hazardous material, must remain placarded when it is emptied, unless it—

(1) Is sufficiently cleaned of residue and purged of vapors to remove any potential hazard;

(2) Is refilled, with a material requiring different placards or no placards, to such an extent that any residue remaining in the packaging is no longer hazardous; or

(3) Contains the residue of a hazardous substance in Class 9 in a quantity less than the reportable quantity, and conforms to § 173.29(b)(1) of this subchapter.

(c) Exceptions. The following packagings may be placarded on only two opposite sides or, alternatively, may be labeled instead of placarded in accordance with subpart E of this part:

(1) A portable tank having a capacity of less than 3,785 L (1000 gallons);

(2) A DOT 106 or 110 multi-unit tank car tank;

(3) A bulk packaging other than a portable tank, cargo tank, or tank car (e.g., a bulk bag or box) with a volumetric capacity of less than 18 m<sup>3</sup> (640 cubic feet); and

(4) An IBC.

[Amdt. 172–136, 59 FR 38064, July 26, 1994; Amdt. 172–148, 61 FR 50255, Sept. 25, 1996, as amended by 66 FR 45379, Aug. 28, 2001; 69 FR 64473, Nov. 4, 2004]

**§ 172.516 Visibility and display of placards.**

(a) Each placard on a motor vehicle and each placard on a rail car must be clearly visible from the direction it faces, except from the direction of another transport vehicle or rail car to which the motor vehicle or rail car is coupled. This requirement may be met by the placards displayed on the freight containers or portable tanks loaded on a motor vehicle or rail car.

(b) The required placarding of the front of a motor vehicle may be on the

front of a truck-tractor instead of or in addition to the placarding on the front of the cargo body to which a truck-tractor is attached.

(c) Each placard on a transport vehicle, bulk packaging, freight container or aircraft unit load device must—

(1) Be securely attached or affixed thereto or placed in a holder thereon. (See appendix C to this part.);

(2) Be located clear of appurtenances and devices such as ladders, pipes, doors, and tarpaulins;

(3) So far as practicable, be located so that dirt or water is not directed to it from the wheels of the transport vehicle;

(4) Be located away from any marking (such as advertising) that could substantially reduce its effectiveness, and in any case at least 3 inches (76.0 mm.) away from such marking;

(5) Have the words or identification number (when authorized) printed on it displayed horizontally, reading from left to right;

(6) Be maintained by the carrier in a condition so that the format, legibility, color, and visibility of the placard will not be substantially reduced due to damage, deterioration, or obscurement by dirt or other matter;

(7) Be affixed to a background of contrasting color, or must have a dotted or solid line outer border which contrasts with the background color.

(d) Recommended specifications for a placard holder are set forth in appendix C of this part. Except for a placard holder similar to that contained in appendix C to this part, the means used to attach a placard may not obscure any part of its surface other than the borders.

(e) A placard or placard holder may be hinged provided the required format, color, and legibility of the placard are maintained.

[Amdt. 172–29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172–101, 45 FR 74668, Nov. 10, 1980; Amdt. 172–123, 55 FR 52601, Dec. 21, 1990; 65 FR 50460, Aug. 18, 2000]

**§ 172.519 General specifications for placards.**

(a) *Strength and durability.* Placards must conform to the following:

(1) A placard may be made of any plastic, metal or other material capable of withstanding, without deterioration or a substantial reduction in effectiveness, a 30-day exposure to open weather conditions.

(2) A placard made of tagboard must be at least equal to that designated commercially as white tagboard. Tagboard must have a weight of at least 80 kg (176 pounds) per ream of 610 by 910 mm (24 by 36-inch) sheets, waterproofing materials included. In addition, each placard made of tagboard must be able to pass a 414 kPa (60 p.s.i.) Mullen test.

(3) Reflective or retroreflective materials may be used on a placard if the prescribed colors, strength and durability are maintained.

(b) *Design.* (1) Except as provided in § 172.332 of this part, each placard must be as described in this subpart, and except for size and color, the printing, inner border and symbol must be as shown in §§ 172.521 through 172.560 of this subpart, as appropriate.

(2) The dotted line border shown on each placard is not part of the placard specification. However, a dotted or solid line outer border may be used when needed to indicate the full size of a placard that is part of a larger format or is on a background of a non-contrasting color.

(3) For other than Class 7 or the DANGEROUS placard, text indicating a hazard (for example, “FLAMMABLE”) is not required. Text may be omitted from the OXYGEN placard only if the specific identification number is displayed on the placard.

(4) For a placard corresponding to the primary or subsidiary hazard class of a material, the hazard class or division number must be displayed in the lower corner of the placard. However, a permanently affixed subsidiary placard meeting the specifications of this section which were in effect on October 1, 2001, (such as, a placard without the hazard class or division number displayed in the lower corner of the placard) and which was installed prior to September 30, 2001, may continue to be used as a subsidiary placard in domestic transportation by rail or highway, provided the color tolerances are maintained and are in accordance with

the display requirements in this subchapter. Stocks of non-permanently affixed subsidiary placards in compliance with the requirements in effect on September 30, 2001, may continue to be used in domestic transportation by rail or highway until October 1, 2005, or until current stocks are depleted, whichever occurs first.

(c) *Size.* (1) Each placard prescribed in this subpart must measure at least 273 mm (10.8 inches) on each side and must have a solid line inner border approximately 12.7 mm (0.5 inches) from each edge.

(2) Except as otherwise provided in this subpart, the hazard class or division number, as appropriate, must be shown in numerals measuring at least 41 mm (1.6 inches) in height.

(3) Except as otherwise provided in this subpart, when text indicating a hazard is displayed on a placard, the printing must be in letters measuring at least 41 mm (1.6 inches) in height.

(d) *Color.* (1) The background color, symbol, text, numerals and inner border on a placard must be as specified in §§ 172.521 through 172.560 of this subpart, as appropriate.

(2) Black and any color on a placard must be able to withstand, without substantial change—

(i) A 72-hour fadeometer test (for a description of equipment designed for this purpose, see ASTM G 23–69 or ASTM G 26–70); and

(ii) A 30-day exposure to open weather.

(3) Upon visual examination, a color on a placard must fall within the color tolerances displayed on the appropriate Hazardous Materials Label and Placard Color Tolerance Chart (see § 172.407(d)(4)). As an alternative, the PANTONE® formula guide coated/uncoated as specified for colors in § 172.407(d)(5) may be used.

(4) The placard color must extend to the inner border and may extend to the edge of the placard in the area designated on each placard except the color on the CORROSIVE and RADIOACTIVE placards (black and yellow, respectively) must extend only to the inner border.

(e) *Form identification.* A placard may contain form identification information, including the name of its maker,

provided that information is printed outside of the solid line inner border in no larger than 10-point type.

(f) *Exceptions.* When hazardous materials are offered for transportation or transported under the provisions of subpart C of part 171 of this subchapter, a placard conforming to the specifications in the ICAO Technical Instructions, the IMDG Code, or the Transport Canada TDG Regulations (IBR, see §171.7 of this subchapter) may be used in place of a corresponding placard conforming to the requirements of this subpart. However, a bulk packaging, transport vehicle, or freight container containing a material poisonous by inhalation (see §171.8 of this subchapter) must be placarded in accordance with this subpart (see §171.23(b)(11) of this subchapter).

(g) *Trefoil symbol.* The trefoil symbol on the RADIOACTIVE placard must meet the appropriate specification in appendix B of this part.

[Amdt. 172-123, 55 FR 52601, Dec. 21, 1990, as amended at 56 FR 66260, Dec. 20, 1991; 57 FR 45460, Oct. 1, 1992; Amdt. 172-143, 60 FR 50305, Sept. 28, 1995; 65 FR 50460, Aug. 18, 2000; 66 FR 33426, June 21, 2001; 66 FR 44255, Aug. 22, 2001; 67 FR 15743, Apr. 3, 2002; 70 FR 34075, June 13, 2005; 69 FR 64473, Nov. 4, 2004; 72 FR 25176, May 3, 2007]

#### § 172.521 DANGEROUS placard.

(a) Except for size and color, the DANGEROUS placard must be as follows:



(b) In addition to meeting the requirements of §172.519, and appendix B to this part, the DANGEROUS placard

must have a red upper and lower triangle. The placard center area and ½-inch (12.7 mm.) border must be white. The inscription must be black with the ⅛-inch (3.2 mm.) border marker in the white area at each end of the inscription red.

[Amdt. 172-29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172-29A, 41 FR 40680, Sept. 20, 1976]

#### § 172.522 EXPLOSIVES 1.1, EXPLOSIVES 1.2 and EXPLOSIVES 1.3 placards.

(a) Except for size and color, the EXPLOSIVES 1.1, EXPLOSIVES 1.2 and EXPLOSIVES 1.3 placards must be as follows:



(b) In addition to complying with §172.519 of this subpart, the background color on the EXPLOSIVES 1.1, EXPLOSIVES 1.2, and EXPLOSIVES 1.3 placards must be orange. The “\*” shall be replaced with the appropriate division number and, when required, appropriate compatibility group letter. The symbol, text, numerals and inner border must be black.

[Amdt. 172-123, 55 FR 52602, Dec. 21, 1990, as amended at 56 FR 66260, Dec. 20, 1991]

#### § 172.523 EXPLOSIVES 1.4 placard.

(a) Except for size and color, the EXPLOSIVES 1.4 placard must be as follows:

§ 172.524



(b) In addition to complying with § 172.519 of this subpart, the background color on the EXPLOSIVES 1.4 placard must be orange. The “\*” shall be replaced, when required, with the appropriate compatibility group letter. The division numeral, 1.4, must measure at least 64 mm (2.5 inches) in height. The text, numerals and inner border must be black.

[Amdt. 172–123, 55 FR 52602, Dec. 21, 1990, as amended at 56 FR 66261, Dec. 20, 1991]

§ 172.524 EXPLOSIVES 1.5 placard.

(a) Except for size and color, the EXPLOSIVES 1.5 placard must be as follows:



(b) In addition to complying with the § 172.519 of this subpart, the background color on EXPLOSIVES 1.5 placard

49 CFR Ch. I (10–1–08 Edition)

must be orange. The “\*” shall be replaced, when required, with the appropriate compatibility group letter. The division numeral, 1.5, must measure at least 64 mm (2.5 inches) in height. The text, numerals and inner border must be black.

[Amdt. 172–123, 55 FR 52602, Dec. 21, 1990, as amended at 56 FR 66261, Dec. 20, 1991]

§ 172.525 EXPLOSIVES 1.6 placard.

(a) Except for size and color the EXPLOSIVES 1.6 placard must be as follows:




(b) In addition to complying with § 172.519 of this subpart, the background color on the EXPLOSIVES 1.6 placard must be orange. The “\*” shall be replaced, when required, with the appropriate compatibility group letter. The division numeral, 1.6, must measure at least 64 mm (2.5 inches) in height. The text, numerals and inner border must be black.

[Amdt. 172–123, 55 FR 52603, Dec. 21, 1990, as amended at 56 FR 66261, Dec. 20, 1991; Amdt. 172–130, 58 FR 51531, Oct. 1, 1993]

§ 172.526 [Reserved]

§ 172.527 Background requirements for certain placards.

(a) Except for size and color, the square background required by § 172.510(a) for certain placards on rail cars, and § 172.507 for placards on motor vehicles containing a package of highway route controlled quantity radioactive materials, must be as follows:



high. The symbol, text, class number and inner border must be white.

[Amdt. 172-123, 56 FR 66261, Dec. 20, 1991]

**§ 172.530 OXYGEN placard.**

(a) Except for size and color, the OXYGEN placard must be as follows:



(b) In addition to meeting the requirements of § 172.519 for minimum durability and strength, the square background must consist of a white square measuring 14¼ inches (362.0 mm.) on each side surrounded by a black border extending to 15¼ inches (387.0 mm.) on each side.

[Amdt. 172-29, 41 FR 15996, Apr. 15, 1976, as amended by Amdt. 172-64, 46 FR 5316, Jan. 19, 1981; Amdt. 172-78, 48 FR 10226, Mar. 10, 1983]

**§ 172.528 NON-FLAMMABLE GAS placard.**

(a) Except for size and color, the NON-FLAMMABLE GAS placard must be as follows:



(b) In addition to complying with § 172.519, the background color on the NON-FLAMMABLE GAS placard must be green. The letters in both words must be at least 38 mm (1.5 inches)

(b) In addition to complying with § 172.519 of this subpart, the background color on the OXYGEN placard must be yellow. The symbol, text, class number and inner border must be black.

[Amdt. 172-123, 56 FR 66262, Dec. 20, 1991]

**§ 172.532 FLAMMABLE GAS placard.**

(a) Except for size and color, the FLAMMABLE GAS placard must be as follows:



(b) In addition to complying with § 172.519, the background color on the

**§ 172.536**

FLAMMABLE GAS placard must be red. The symbol, text, class number and inner border must be white.

[Amdt. 172-123, 56 FR 66262, Dec. 20, 1991]

**§ 172.536 [Reserved]**

**§ 172.540 POISON GAS placard.**

(a) Except for size and color, the POISON GAS placard must be as follows:



(b) In addition to complying with § 172.519, the background on the POISON GAS placard and the symbol must be white. The background of the upper diamond must be black and the lower point of the upper diamond must be 65 mm (2 $\frac{5}{8}$  inches) above the horizontal center line. The text, class number, and inner border must be black.

[62 FR 39408, July 22, 1997]

**§ 172.542 FLAMMABLE placard.**

(a) Except for size and color, the FLAMMABLE placard must be as follows:

**49 CFR Ch. I (10-1-08 Edition)**



(b) In addition to complying with § 172.519, the background color on the FLAMMABLE placard must be red. The symbol, text, class number and inner border must be white.

(c) The word "GASOLINE" may be used in place of the word "FLAMMABLE" on a placard that is displayed on a cargo tank or a portable tank being used to transport gasoline by highway. The word "GASOLINE" must be shown in white.

[Amdt. 172-123, 56 FR 66262, Dec. 20, 1991]

**§ 172.544 COMBUSTIBLE placard.**

(a) Except for size and color, the COMBUSTIBLE placard must be as follows:



(b) In addition to complying with § 172.519, the background color on the COMBUSTIBLE placard must be red.

The symbol, text, class number and inner border must be white. On a COMBUSTIBLE placard with a white bottom as prescribed by §172.332(c)(4), the class number must be red or black.

(c) The words "FUEL OIL" may be used in place of the word "COMBUSTIBLE" on a placard that is displayed on a cargo tank or portable tank being used to transport by highway fuel oil that is not classed as a flammable liquid. The words "FUEL OIL" must be white.

[Amdt. 172-123, 56 FR 66262, Dec. 20, 1991]

**§ 172.546 FLAMMABLE SOLID placard.**

(a) Except for size and color, the FLAMMABLE SOLID placard must be as follows:



(b) In addition to complying with §172.519, the background on the FLAMMABLE SOLID placard must be white with seven vertical red stripes. The stripes must be equally spaced, with one red stripe placed in the center of the label. Each red stripe and each white space between two red stripes must be 25 mm (1.0 inches) wide. The letters in the word "SOLID" must be at least 38.1 mm (1.5 inches) high. The symbol, text, class number and inner border must be black.

[Amdt. 172-123, 56 FR 66263, Dec. 20, 1991]

**§ 172.547 SPONTANEOUSLY COMBUSTIBLE placard.**

(a) Except for size and color, the SPONTANEOUSLY COMBUSTIBLE placard must be as follows:



(b) In addition to complying with §172.519, the background color on the SPONTANEOUSLY COMBUSTIBLE placard must be red in the lower half and white in upper half. The letters in the word "SPONTANEOUSLY" must be at least 12 mm (0.5 inch) high. The symbol, text, class number and inner border must be black.

[Amdt. 172-123, 56 FR 66263, Dec. 20, 1991, as amended by Amdt. 172-139, 59 FR 67490, Dec. 29, 1994]

**§ 172.548 DANGEROUS WHEN WET placard.**

(a) Except for size and color, the DANGEROUS WHEN WET placard must be as follows:



(b) In addition to complying with §172.519, the background color on the DANGEROUS WHEN WET placard must be blue. The letters in the words



**§ 172.550**

“WHEN WET” must be at least 25 mm (1.0 inches) high. The symbol, text, class number and inner border must be white.

[Amdt. 172–123, 56 FR 66263, Dec. 20, 1991]

**§ 172.550 OXIDIZER placard.**

(a) Except for size and color, the OXIDIZER placard must be as follows:



**49 CFR Ch. I (10–1–08 Edition)**

(b) In addition to complying with § 172.519, the background color on the OXIDIZER placard must be yellow. The symbol, text, division number and inner border must be black.

[Amdt. 172–123, 56 FR 66263, Dec. 20, 1991]

**§ 172.552 ORGANIC PEROXIDE placard.**

(a) Except for size and color, the ORGANIC PEROXIDE placard must be as follows:



(b) In addition to complying with §172.519, the background on the ORGANIC PEROXIDE placard must be red in the top half and yellow in the lower half. The text, division number and inner border must be black; the symbol may be either black or white.

[71 FR 78628, Dec. 29, 2006]

**§ 172.553 [Reserved]**

**§ 172.554 POISON placard.**

(a) Except for size and color, the POISON placard must be as follows:



**§ 172.555**

(b) In addition to complying with §172.519, the background on the POISON placard must be white. The symbol, text, class number and inner border must be black. The word “TOXIC” may be used in lieu of the word “POISON”.

[Amdt. 172–123, 56 FR 66264, Dec. 20, 1991, as amended by Amdt. 172–139, 59 FR 67490, Dec. 29, 1994]

**§ 172.555 POISON INHALATION HAZARD placard.**

(a) Except for size and color, the POISON INHALATION HAZARD placard must be as follows:



**49 CFR Ch. I (10–1–08 Edition)**

(b) In addition to complying with §172.519, the background on the POISON INHALATION HAZARD placard and the symbol must be white. The background of the upper diamond must be black and the lower point of the upper diamond must be 65 mm (2<sup>5</sup>/<sub>16</sub> inches) above the horizontal center line. The text, class number, and inner border must be black.

[62 FR 39409, July 22, 1997]

**§ 172.556 RADIOACTIVE placard.**

(a) Except for size and color, the RADIOACTIVE placard must be as follows:



(b) In addition to complying with §172.519, the background color on the RADIOACTIVE placard must be white in the lower portion with a yellow triangle in the upper portion. The base of the yellow triangle must be 29 mm  $\pm$  5 mm (1.1 inches  $\pm$  0.2 inches) above the placard horizontal center line. The

symbol, text, class number and inner border must be black.

[Amdt. 172-123, 56 FR 66264, Dec. 20, 1991; Amdt. 172-130, 58 FR 51531, Oct. 1, 1993; 65 FR 58627, Sept. 29, 2000]

**§ 172.558 CORROSIVE placard.**

(a) Except for size and color, the CORROSIVE placard must be as follows:




(b) In addition to complying with §172.519, the background color on the CORROSIVE placard must be black in the lower portion with a white triangle in the upper portion. The base of the white triangle must be 38 mm  $\pm$  5 mm (1.5 inches  $\pm$  0.2 inches) above the placard horizontal center line. The text and class number must be white. The symbol and inner border must be black.

[Amdt. 172–123, 56 FR 66264, Dec. 20, 1991, as amended at 65 FR 58627, Sept. 29, 2000]

**§ 172.560 CLASS 9 placard.**

(a) Except for size and color the CLASS 9 (miscellaneous hazardous materials) placard must be as follows:



(b) In addition to conformance with § 172.519, the background on the CLASS 9 placard must be white with seven black vertical stripes on the top half extending from the top of the placard to one inch above the horizontal centerline. The black vertical stripes must be spaced so that, visually, they appear equal in width to the six white spaces between them. The space below the vertical lines must be white with the class number 9 underlined and centered at the bottom.

[Amdt. 172-123, 56 FR 66264, Dec. 20, 1991, as amended at 57 FR 45460, Oct. 1, 1992]

### Subpart G—Emergency Response Information

#### § 172.600 Applicability and general requirements.

(a) *Scope.* Except as provided in paragraph (d) of this section, this subpart prescribes requirements for providing and maintaining emergency response information during transportation and at facilities where hazardous materials are loaded for transportation, stored incidental to transportation or otherwise handled during any phase of transportation.

(b) *Applicability.* This subpart applies to persons who offer for transportation, accept for transportation, transfer or otherwise handle hazardous materials during transportation.

(c) *General requirements.* No person to whom this subpart applies may offer for transportation, accept for transportation, transfer, store or otherwise handle during transportation a hazardous material unless:

(1) Emergency response information conforming to this subpart is immediately available for use at all times the hazardous material is present; and

(2) Emergency response information, including the emergency response telephone number, required by this subpart is immediately available to any person who, as a representative of a Federal, State or local government agency, responds to an incident involving a hazardous material, or is conducting an investigation which involves a hazardous material.

(d) *Exceptions.* The requirements of this subpart do not apply to hazardous material which is excepted from the

shipping paper requirements of this subchapter or a material properly classified as an ORM-D.

[Amdt. 172-116, 54 FR 27145, June 27, 1989; 54 FR 28750, July 5, 1989, as amended at 55 FR 33712, Aug. 17, 1990; 172-127, 59 FR 49133, Sept. 26, 1994; Amdt. 172-149, 61 FR 27173, May 30, 1996]

#### § 172.602 Emergency response information.

(a) *Information required.* For purposes of this subpart, the term “emergency response information” means information that can be used in the mitigation of an incident involving hazardous materials and, as a minimum, must contain the following information:

(1) The basic description and technical name of the hazardous material as required by §§ 172.202 and 172.203(k), the ICAO Technical Instructions, the IMDG Code, or the TDG Regulations, as appropriate (IBR, see § 171.7 of this subchapter);

(2) Immediate hazards to health;

(3) Risks of fire or explosion;

(4) Immediate precautions to be taken in the event of an accident or incident;

(5) Immediate methods for handling fires;

(6) Initial methods for handling spills or leaks in the absence of fire; and

(7) Preliminary first aid measures.

(b) *Form of information.* The information required for a hazardous material by paragraph (a) of this section must be:

(1) Printed legibly in English;

(2) Available for use away from the package containing the hazardous material; and

(3) Presented—

(i) On a shipping paper;

(ii) In a document, other than a shipping paper, that includes both the basic description and technical name of the hazardous material as required by §§ 172.202 and 172.203(k), the ICAO Technical Instructions, the IMDG Code, or the TDG Regulations, as appropriate, and the emergency response information required by this subpart (e.g., a material safety data sheet); or

(iii) Related to the information on a shipping paper, a written notification to pilot-in-command, or a dangerous cargo manifest, in a separate document

## § 172.604

## 49 CFR Ch. I (10–1–08 Edition)

(e.g., an emergency response guidance document), in a manner that cross-references the description of the hazardous material on the shipping paper with the emergency response information contained in the document. Aboard aircraft, the ICAO “Emergency Response Guidance for Aircraft Incidents Involving Dangerous Goods” and, aboard vessels, the IMO “Emergency Procedures for Ships Carrying Dangerous Goods”, or equivalent documents, may be used to satisfy the requirements of this section for a separate document.

(c) *Maintenance of information.* Emergency response information shall be maintained as follows:

(1) *Carriers.* Each carrier who transports a hazardous material shall maintain the information specified in paragraph (a) of this section and § 172.606 of this part in the same manner as prescribed for shipping papers, except that the information must be maintained in the same manner aboard aircraft as the notification of pilot-in-command, and aboard vessels in the same manner as the dangerous cargo manifest. This information must be immediately accessible to train crew personnel, drivers of motor vehicles, flight crew members, and bridge personnel on vessels for use in the event of incidents involving hazardous materials.

(2) *Facility operators.* Each operator of a facility where a hazardous material is received, stored or handled during transportation, shall maintain the information required by paragraph (a) of this section whenever the hazardous material is present. This information must be in a location that is immediately accessible to facility personnel in the event of an incident involving the hazardous material.

[Amdt. 172–116, 54 FR 27146, June 27, 1989; 54 FR 28750, July 5, 1989, as amended by Amdt. 172–116, 55 FR 875, Jan. 10, 1990; Amdt. 172–151, 62 FR 1234, Jan. 8, 1997; 66 FR 45379, Aug. 28, 2001; 68 FR 75741, Dec. 31, 2003]

### § 172.604 Emergency response telephone number.

(a) A person who offers a hazardous material for transportation must provide an emergency response telephone number, including the area code or international access code, for use in

the event of an emergency involving the hazardous material. The telephone number must be—

(1) Monitored at all times the hazardous material is in transportation, including storage incidental to transportation;

(2) The telephone number of a person who is either knowledgeable of the hazardous material being shipped and has comprehensive emergency response and incident mitigation information for that material, or has immediate access to a person who possesses such knowledge and information. A telephone number that requires a call back (such as an answering service, answering machine, or beeper device) does not meet the requirements of paragraph (a) of this section; and

(3) Entered on a shipping paper, as follows:

(i) Immediately following the description of the hazardous material required by subpart C of this part; or

(ii) Entered once on the shipping paper in a clearly visible location. This provision may be used only if the telephone number applies to each hazardous material entered on the shipping paper, and if it is indicated that the telephone number is for emergency response information (for example: “EMERGENCY CONTACT: \* \* \*”).

(b) The telephone number required by paragraph (a) of this section must be the number of the person offering the hazardous material for transportation or the number of an agency or organization capable of, and accepting responsibility for, providing the detailed information concerning the hazardous material. A person offering a hazardous material for transportation who lists the telephone number of an agency or organization shall ensure that agency or organization has received current information on the material, as required by paragraph (a)(2) of this section before it is offered for transportation.

(c) The requirements of this section do not apply to—

(1) Hazardous materials that are offered for transportation under the provisions applicable to limited quantities; and

(2) Materials properly described under the following shipping names:

Battery powered equipment  
 Battery powered vehicle  
 Carbon dioxide, solid  
 Castor bean  
 Castor flake  
 Castor meal  
 Castor pomace  
 Consumer commodity  
 Dry ice  
 Engines, internal combustion  
 Fish meal, stabilized  
 Fish scrap, stabilized  
 Refrigerating machine  
 Vehicle, flammable gas powered  
 Vehicle, flammable liquid powered  
 Wheelchair, electric

[Amdt. 172-116, 54 FR 27145, June 27, 1989, as amended at 55 FR 33713, Aug. 17, 1990; Amdt. 172-127, 59 FR 49133, Sept. 26, 1994; Amdt. 172-149, 61 FR 27173, May 30, 1996; 65 FR 50460, Aug. 18, 2000; 65 FR 58628, Sept. 29, 2000; 66 FR 45182, Aug. 28, 2001; 69 FR 64473, Nov. 4, 2004]

#### § 172.606 Carrier information contact.

(a) Each carrier who transports or accepts for transportation a hazardous material for which a shipping paper is required shall instruct the operator of a motor vehicle, train, aircraft, or vessel to contact the carrier (e.g., by telephone or mobile radio) in the event of an incident involving the hazardous material.

(b) For transportation by highway, if a transport vehicle, (e.g., a semi-trailer or freight container-on-chassis) contains hazardous material for which a shipping paper is required and the vehicle is separated from its motive power and parked at a location other than a facility operated by the consignor or consignee or a facility (e.g., a carrier's terminal or a marine terminal) subject to the provisions of § 172.602(c)(2), the carrier shall—

(1) Mark the transport vehicle with the telephone number of the motor carrier on the front exterior near the brake hose and electrical connections or on a label, tag, or sign attached to the vehicle at the brake hose or electrical connection; or

(2) Have the shipping paper and emergency response information readily available on the transport vehicle.

(c) The requirements specified in paragraph (b) of this section do not apply to an unattended motor vehicle separated from its motive power when the motor vehicle is marked on an orange panel, a placard, or a plain white

square-on-point configuration with the identification number of each hazardous material loaded therein, and the marking or placard is visible on the outside of the motor vehicle.

[Amdt. 172-151, 62 FR 1234, Jan. 8, 1997, as amended at 62 FR 39398 and 39409, July 22, 1997; 63 FR 16076, Apr. 1, 1998]

### Subpart H—Training

SOURCE: Amdt. 172-126, 57 FR 20952, May 15, 1992, unless otherwise noted.

#### § 172.700 Purpose and scope.

(a) *Purpose.* This subpart prescribes requirements for training hazmat employees.

(b) *Scope.* Training as used in this subpart means a systematic program that ensures a hazmat employee has familiarity with the general provisions of this subchapter, is able to recognize and identify hazardous materials, has knowledge of specific requirements of this subchapter applicable to functions performed by the employee, and has knowledge of emergency response information, self-protection measures and accident prevention methods and procedures (see § 172.704).

(c) *Modal-specific training requirements.* Additional training requirements for the individual modes of transportation are prescribed in parts 174, 175, 176, and 177 of this subchapter.

#### § 172.701 Federal-State relationship.

This subpart and the parts referenced in § 172.700(c) prescribe minimum training requirements for the transportation of hazardous materials. For motor vehicle drivers, however, a State may impose more stringent training requirements only if those requirements—

(a) Do not conflict with the training requirements in this subpart and in part 177 of this subchapter; and

(b) Apply only to drivers domiciled in that State.

#### § 172.702 Applicability and responsibility for training and testing.

(a) A hazmat employer shall ensure that each of its hazmat employees is trained in accordance with the requirements prescribed in this subpart.



## § 172.704

## 49 CFR Ch. I (10–1–08 Edition)

(b) Except as provided in § 172.704(c)(1), a hazmat employee who performs any function subject to the requirements of this subchapter may not perform that function unless instructed in the requirements of this subchapter that apply to that function. It is the duty of each hazmat employer to comply with the applicable requirements of this subchapter and to thoroughly instruct each hazmat employee in relation thereto.

(c) Training may be provided by the hazmat employer or other public or private sources.

(d) A hazmat employer shall ensure that each of its hazmat employees is tested by appropriate means on the training subjects covered in § 172.704.

[Amdt. 172–126, 57 FR 20952, May 15, 1992; 57 FR 22182, May 27, 1992, as amended by Amdt. 172–149, 61 FR 27173, May 30, 1996]

### § 172.704 Training requirements.

(a) Hazmat employee training must include the following:

(1) *General awareness/familiarization training.* Each hazmat employee shall be provided general awareness/familiarization training designed to provide familiarity with the requirements of this subchapter, and to enable the employee to recognize and identify hazardous materials consistent with the hazard communication standards of this subchapter.

(2) *Function-specific training.* (i) Each hazmat employee must be provided function-specific training concerning requirements of this subchapter, or exemptions or special permits issued under subchapter A of this chapter, that are specifically applicable to the functions the employee performs.

(ii) As an alternative to function-specific training on the requirements of this subchapter, training relating to the requirements of the ICAO Technical Instructions and the IMDG Code may be provided to the extent such training addresses functions authorized by subpart C of part 171 of this subchapter.

(3) *Safety training.* Each hazmat employee shall receive safety training concerning—

(i) Emergency response information required by subpart G of part 172;

(ii) Measures to protect the employee from the hazards associated with hazardous materials to which they may be exposed in the work place, including specific measures the hazmat employer has implemented to protect employees from exposure; and

(iii) Methods and procedures for avoiding accidents, such as the proper procedures for handling packages containing hazardous materials.

(4) *Security awareness training.* No later than the date of the first scheduled recurrent training after March 25, 2003, and in no case later than March 24, 2006, each hazmat employee must receive training that provides an awareness of security risks associated with hazardous materials transportation and methods designed to enhance transportation security. This training must also include a component covering how to recognize and respond to possible security threats. After March 25, 2003, new hazmat employees must receive the security awareness training required by this paragraph within 90 days after employment.

(5) *In-depth security training.* By December 22, 2003, each hazmat employee of a person required to have a security plan in accordance with subpart I of this part must be trained concerning the security plan and its implementation. Security training must include company security objectives, specific security procedures, employee responsibilities, actions to take in the event of a security breach, and the organizational security structure.

(b) *OSHA, EPA, and other training.* Training conducted by employers to comply with the hazard communication programs required by the Occupational Safety and Health Administration of the Department of Labor (29 CFR 1910.120 or 1910.1200) or the Environmental Protection Agency (40 CFR 311.1), or training conducted by employers to comply with security training programs required by other Federal or international agencies, may be used to satisfy the training requirements in paragraph (a) of this section to the extent that such training addresses the training components specified in paragraph (a) of this section.

(c) *Initial and recurrent training*—(1) *Initial training.* A new hazmat employee, or a hazmat employee who changes job functions may perform those functions prior to the completion of training provided—

(i) The employee performs those functions under the direct supervision of a properly trained and knowledgeable hazmat employee; and

(ii) The training is completed within 90 days after employment or a change in job function.

(2) *Recurrent training.* A hazmat employee shall receive the training required by this subpart at least once every three years.

(3) *Relevant Training.* Relevant training received from a previous employer or other source may be used to satisfy the requirements of this subpart provided a current record of training is obtained from hazmat employees' previous employer.

(4) *Compliance.* Each hazmat employer is responsible for compliance with the requirements of this subchapter regardless of whether the training required by this subpart has been completed.

(d) *Recordkeeping.* A record of current training, inclusive of the preceding three years, in accordance with this section shall be created and retained by each hazmat employer for as long as that employee is employed by that employer as a hazmat employee and for 90 days thereafter. The record shall include:

(1) The hazmat employee's name;

(2) The most recent training completion date of the hazmat employee's training;

(3) A description, copy, or the location of the training materials used to meet the requirements in paragraph (a) of this section;

(4) The name and address of the person providing the training; and

(5) Certification that the hazmat employee has been trained and tested, as required by this subpart.

(e) *Limitations.* The following limitations apply:

(1) A hazmat employee who repairs, modifies, reconditions, or tests packagings, as qualified for use in the transportation of hazardous materials, and who does not perform any other

function subject to the requirements of this subchapter, is not subject to the training requirement of paragraph (a)(3) of this section.

(2) A railroad maintenance-of-way employee or railroad signalman, who does not perform any function subject to the requirements of this subchapter, is not subject to the training requirements of paragraphs (a)(2), (a)(4), or (a)(5) of this section. Initial training for a railroad maintenance-of-way employee or railroad signalman in accordance with this section must be completed by October 1, 2006.

[Amdt. 172–126, 57 FR 20952, May 15, 1992, as amended by Amdt. 172–126, 58 FR 5851, Jan. 22, 1993; Amdt. 172–145, 60 FR 49110, Sept. 21, 1995; Amdt. 172–149, 61 FR 27173, May 30, 1996; 65 FR 50460, Aug. 18, 2000; 68 FR 14521, Mar. 25, 2003; 70 FR 73164, Dec. 9, 2005; 73 FR 4716, Jan. 28, 2008; 73 FR 57005, Oct. 1, 2008]

### Subpart I—Safety and Security Plans

SOURCE: 68 FR 14521, Mar. 25, 2003, unless otherwise noted.

#### § 172.800 Purpose and applicability.

(a) *Purpose.* This subpart prescribes requirements for development and implementation of plans to address security risks related to the transportation of hazardous materials in commerce.

(b) *Applicability.* By September 25, 2003, each person who offers for transportation in commerce or transports in commerce one or more of the following hazardous materials must develop and adhere to a security plan for hazardous materials that conforms to the requirements of this subpart:

(1) A highway route-controlled quantity of a Class 7 (radioactive) material, as defined in §173.403 of this subchapter, in a motor vehicle, rail car, or freight container;

(2) More than 25 kg (55 pounds) of a Division 1.1, 1.2, or 1.3 (explosive) material in a motor vehicle, rail car, or freight container;

(3) More than one L (1.06 qt) per package of a material poisonous by inhalation, as defined in §171.8 of this subchapter, that meets the criteria for Hazard Zone A, as specified in §§173.116(a) or 173.133(a) of this subchapter;

(4) A shipment of a quantity of hazardous materials in a bulk packaging having a capacity equal to or greater than 13,248 L (3,500 gallons) for liquids or gases or more than 13.24 cubic meters (468 cubic feet) for solids;

(5) A shipment in other than a bulk packaging of 2,268 kg (5,000 pounds) gross weight or more of one class of hazardous materials for which placarding of a vehicle, rail car, or freight container is required for that class under the provisions of subpart F of this part;

(6) A select agent or toxin regulated by the Centers for Disease Control and Prevention under 42 CFR part 73 or, by April 1, 2007, a select agent or toxin regulated by the United States Department of Agriculture under 9 CFR part 121; or

(7) A quantity of hazardous material that requires placarding under the provisions of subpart F of this part.

(c) *Exceptions.* Transportation activities of a farmer, who generates less than \$500,000 annually in gross receipts from the sale of agricultural commodities or products, are not subject to this subpart if such activities are:

(1) Conducted by highway or rail;

(2) In direct support of their farming operations; and

(3) Conducted within a 150-mile radius of those operations.

[68 FR 14521, Mar. 25, 2003, as amended at 70 FR 73164, Dec. 9, 2005; 71 FR 32258, June 2, 2006]

**§ 172.802 Components of a security plan.**

(a) The security plan must include an assessment of possible transportation security risks for shipments of the hazardous materials listed in § 172.800 and appropriate measures to address the assessed risks. Specific measures put into place by the plan may vary commensurate with the level of threat at a particular time. At a minimum, a security plan must include the following elements:

(1) *Personnel security.* Measures to confirm information provided by job applicants hired for positions that involve access to and handling of the hazardous materials covered by the security plan. Such confirmation system must be consistent with applicable

Federal and State laws and requirements concerning employment practices and individual privacy.

(2) *Unauthorized access.* Measures to address the assessed risk that unauthorized persons may gain access to the hazardous materials covered by the security plan or transport conveyances being prepared for transportation of the hazardous materials covered by the security plan.

(3) *En route security.* Measures to address the assessed security risks of shipments of hazardous materials covered by the security plan en route from origin to destination, including shipments stored incidental to movement.

(b) The security plan must be in writing and must be retained for as long as it remains in effect. Copies of the security plan, or portions thereof, must be available to the employees who are responsible for implementing it, consistent with personnel security clearance or background investigation restrictions and a demonstrated need to know. The security plan must be revised and updated as necessary to reflect changing circumstances. When the security plan is updated or revised, all copies of the plan must be maintained as of the date of the most recent revision.

**§ 172.804 Relationship to other Federal requirements.**

To avoid unnecessary duplication of security requirements, security plans that conform to regulations, standards, protocols, or guidelines issued by other Federal agencies, international organizations, or industry organizations may be used to satisfy the requirements in this subpart, provided such security plans address the requirements specified in this subpart.

**§ 172.820 Additional planning requirements for transportation by rail.**

(a) *General.* Each rail carrier transporting in commerce one or more of the following materials is subject to the additional safety and security planning requirements of this section:

(1) More than 2,268 kg (5,000 lbs) in a single carload of a Division 1.1, 1.2 or 1.3 explosive;

(2) A bulk quantity of a material poisonous by inhalation, as defined in

§ 171.8 of this subchapter (including anhydrous ammonia); or

(3) A highway route-controlled quantity of a Class 7 (radioactive) material, as defined in § 173.403 of this subchapter.

(b) *Commodity data.* Not later than 90 days after the end of each calendar year, a rail carrier must compile commodity data for the previous calendar year for the materials listed in paragraph (a) of this section, except that for calendar year 2008, data may be compiled for the 6-month period beginning July 1, 2008. The following stipulations apply to data collected:

(1) Commodity data must be collected by route, a line segment or series of line segments as aggregated by the rail carrier. Within the rail carrier selected route, the commodity data must identify the geographic location of the route and the total number of shipments by UN identification number for the materials specified in paragraph (a) of this section.

(2) A carrier may compile commodity data, by UN number, for all Class 7 materials transported (instead of only highway route controlled quantities of Class 7 materials) and for all Division 6.1 materials transported (instead of only Division 6.1 poison inhalation hazard materials).

(c) *Rail transportation route analysis.* For each calendar year, a rail carrier must analyze the safety and security risks for the transportation route(s), identified in the commodity data collected as required by paragraph (b) of this section. The route analysis must be in writing and include the factors contained in Appendix D to this part, as applicable.

(1) The safety and security risks present must be analyzed for the route and railroad facilities along the route. For purposes of this section, railroad facilities are railroad property including, but not limited to, classification and switching yards, storage facilities, and non-private sidings. This term does not include an offeror's facility, private track, private siding, or consignee's facility.

(2) In performing the analysis required by this paragraph, the rail carrier must seek relevant information from state, local, and tribal officials,

as appropriate, regarding security risks to high-consequence targets along or in proximity to the route(s) utilized. If a rail carrier is unable to acquire relevant information from state, local, or tribal officials, then it must document that in its analysis. For purposes of this section, a high-consequence target means a property, natural resource, location, area, or other target designated by the Secretary of Homeland Security that is a viable terrorist target of national significance, the attack of which by railroad could result in catastrophic loss of life, significant damage to national security or defense capabilities, or national economic harm.

(d) *Alternative route analysis.* (1) For each calendar year, a rail carrier must identify practicable alternative routes over which it has authority to operate, if an alternative exists, as an alternative route for each of the transportation routes analyzed in accordance with paragraph (c) of this section. The carrier must perform a safety and security risk assessment of the alternative routes for comparison to the route analysis prescribed in paragraph (c) of this section. The alternative route analysis must be in writing and include the criteria in Appendix D of this part. When determining practicable alternative routes, the rail carrier must consider the use of interchange agreements with other rail carriers. The written alternative route analysis must also consider:

(i) Safety and security risks presented by use of the alternative route(s);

(ii) Comparison of the safety and security risks of the alternative(s) to the primary rail transportation route, including the risk of a catastrophic release from a shipment traveling along each route;

(iii) Any remediation or mitigation measures implemented on the primary or alternative route(s); and

(iv) Potential economic effects of using the alternative route(s), including but not limited to the economics of the commodity, route, and customer relationship.

(2) In performing the analysis required by this paragraph, the rail carrier should seek relevant information from state, local, and tribal officials,

as appropriate, regarding security risks to high-consequence targets along or in proximity to the alternative routes. If a rail carrier determines that it is not appropriate to seek such relevant information, then it must explain its reasoning for that determination in its analysis.

(e) *Route Selection.* A carrier must use the analysis performed as required by paragraphs (c) and (d) of this section to select the route to be used in moving the materials covered by paragraph (a) of this section. The carrier must consider any remediation measures implemented on a route. Using this process, the carrier must at least annually review and select the practicable route posing the least overall safety and security risk. The rail carrier must retain in writing all route review and selection decision documentation and restrict the distribution, disclosure, and availability of information contained in the route analysis to covered persons with a need-to-know, as described in parts 15 and 1520 of this title. This documentation should include, but is not limited to, comparative analyses, charts, graphics or rail system maps.

(f) *Completion of route analyses.* (1) The initial rail transportation route analysis, alternative route analysis, and route selection process required under paragraphs (c), (d), and (e) of this section must be completed by September 1, 2009. In subsequent years, the rail transportation route analysis, alternative route analysis, and route selection process required under paragraphs (c), (d), and (e) of this section must be completed no later than the end of the calendar year following the year to which the analyses apply. The initial analysis and route selection determinations required under paragraphs (c), (d), and (e) of this section must include a comprehensive review of the entire system. Subsequent analyses and route selection determinations required under paragraphs (c), (d), and (e) of this section must include a comprehensive, system-wide review of all operational changes, infrastructure modifications, traffic adjustments, changes in the nature of high-consequence targets located along, or in proximity to, the route, and any other changes affecting the safety or

security of the movements of the materials specified in paragraph (a) of this section that were implemented during the calendar year.

(2) A rail carrier need not perform a rail transportation route analysis, alternative route analysis, or route selection process for any hazardous material other than the materials specified in paragraph (a) of this section.

(g) *Storage, delays in transit, and notification.* With respect to the materials specified in paragraph (a) of this section, each rail carrier must ensure the safety and security plan it develops and implements under this subpart includes all of the following:

(1) A procedure under which the rail carrier must formally consult with offerors and consignees in order to develop measures for minimizing, to the extent practicable, the duration of any storage of the material incidental to movement (see §171.8 of this subchapter). Such measures should be implemented with mutual consent of all parties.

(2) Measures to prevent unauthorized access to the materials during storage or delays in transit.

(3) Measures to mitigate risk to population centers associated with in-transit storage.

(4) Measures to be taken in the event of an escalating threat level for materials stored in transit.

(5) Procedures for notifying the consignee in the event of a significant delay during transportation; such notification must be completed within 48 hours after the carrier has identified the delay and must include a revised delivery schedule. A significant delay is one that compromises the safety or security of the hazardous material or delays the shipment beyond its normal expected or planned shipping time. Notification should be made by a method acceptable to both the rail carrier and consignee.

(h) *Recordkeeping.* (1) Each rail carrier must maintain a copy of the information specified in paragraphs (b), (c), (d), (e), and (f) of this section (or an electronic image thereof) that is accessible at, or through, its principal place of business and must make the record available upon request, at a reasonable

time and location, to an authorized official of the Department of Transportation or the Department of Homeland Security. Records must be retained for a minimum of two years.

(2) Each rail carrier must restrict the distribution, disclosure, and availability of information collected or developed in accordance with paragraphs (c), (d), (e), and (f) of this section to covered persons with a need-to-know, as described in parts 15 and 1520 of this title.

(i) *Compliance and enforcement.* If the carrier's route selection documentation and underlying analyses are found to be deficient, the carrier may be required to revise the analyses or make changes in route selection. If DOT finds that a chosen route is not the safest and most secure practicable route available, the FRA Associate Administrator for Safety, in consultation with TSA, may require the use of an alternative route. Prior to making such a determination, FRA and TSA will consult with the Surface Transportation Board (STB) regarding whether the contemplated alternative route(s) would be economically practicable.

[73 FR 20771, April 16, 2008]

**§ 172.822 Limitation on actions by states, local governments, and Indian tribes.**

A law, order, or other directive of a state, political subdivision of a state, or an Indian tribe that designates, limits, or prohibits the use of a rail line

(other than a rail line owned by a state, political subdivision of a state, or an Indian tribe) for the transportation of hazardous materials, including, but not limited to, the materials specified in § 172.820(a), is preempted. 49 U.S.C. 5125, 20106.

[73 FR 20772, April 16, 2008]

**APPENDIX A TO PART 172—OFFICE OF HAZARDOUS MATERIALS TRANSPORTATION COLOR TOLERANCE CHARTS AND TABLES**

The following are Munsell notations and Commission Internationale de L'Eclairage (CIE) coordinates which describe the Office of Hazardous Materials Transportation Label and Placard Color Tolerance Charts in tables 1 and 2, and the CIE coordinates for the color tolerances specified in table 3. Central colors and tolerances described in table 2 approximate those described in table 1 while allowing for differences in production methods and materials used to manufacture labels and placards surfaced with printing inks. Primarily, the color charts based on table 1 are for label or placard colors applied as opaque coatings such as paint, enamel or plastic, whereas color charts based on table 2 are intended for use with labels and placards surfaced only with inks.

For labels printed directly on packaging surfaces, table 3 may be used, although compliance with either table 1 or table 2 is sufficient. However, if visual reference indicates that the colors of labels printed directly on package surfaces are outside the table 1 or 2 tolerances, a spectrophotometer or other instrumentation may be required to insure compliance with table 3.

**TABLE 1—SPECIFICATIONS FOR COLOR TOLERANCE CHARTS FOR USE WITH LABELS AND PLACARDS SURFACED WITH PAINT, LACQUER, ENAMEL, PLASTIC, OTHER OPAQUE COATINGS, OR INK<sup>1</sup>**

| Color                    | Munsell notations   | CIE data for source C |       |       |
|--------------------------|---------------------|-----------------------|-------|-------|
|                          |                     | Y                     | x     | y     |
| Red:                     |                     |                       |       |       |
| Central color .....      | 7.5R 4.0/14 .....   | 12.00                 | .5959 | .3269 |
| Orange .....             | 8.5R 4.0/14 .....   | 12.00                 | .6037 | .3389 |
| Purple and vivid .....   | 6.5R 4.0/14 .....   | 12.00                 | .5869 | .3184 |
| Grayish .....            | 7.5R 4.0/12 .....   | 12.00                 | .5603 | .3321 |
| Vivid .....              | 7.5R 4.0/16 .....   | 12.00                 | .6260 | .3192 |
| Light .....              | 7.5R 4.5/14 .....   | 15.57                 | .5775 | .3320 |
| Dark .....               | 7.5R 3.5/14 .....   | 09.00                 | .6226 | .3141 |
| Orange:                  |                     |                       |       |       |
| Central color .....      | 5.OYR 6.0/15 .....  | 30.05                 | .5510 | .4214 |
| Yellow and Grayish ..... | 6.25YR 6.0/15 ..... | 30.05                 | .5452 | .4329 |
| Red and vivid .....      | 3.75YR 6.0/15 ..... | 30.05                 | .5552 | .4091 |
| Grayish .....            | 5.OYR 6.0/13 .....  | 30.05                 | .5311 | .4154 |
| Vivid .....              | 5.OYR 6.0/16 .....  | 30.05                 | .5597 | .4239 |
| Light .....              | 5.OYR 6.5/15 .....  | 36.20                 | .5427 | .4206 |
| Dark .....               | 5.OYR 5.5/15 .....  | 24.58                 | .5606 | .4218 |
| Yellow:                  |                     |                       |       |       |
| Central color .....      | 5.OY 8.0/12 .....   | 59.10                 | .4562 | .4788 |

TABLE 1—SPECIFICATIONS FOR COLOR TOLERANCE CHARTS FOR USE WITH LABELS AND PLACARDS SURFACED WITH PAINT, LACQUER, ENAMEL, PLASTIC, OTHER OPAQUE COATINGS, OR INK<sup>1</sup>—Continued

| Color                        | Munsell notations   | CIE data for source C |       |       |
|------------------------------|---------------------|-----------------------|-------|-------|
|                              |                     | Y                     | x     | y     |
| Green .....                  | 6.5Y 8.0/12 .....   | 59.10                 | .4498 | .4865 |
| Orange and vivid .....       | 3.5Y 8.0/12 .....   | 59.10                 | .4632 | .4669 |
| Grayish .....                | 5.0Y 8.0/10 .....   | 59.10                 | .4376 | .4601 |
| Vivid .....                  | 5.0Y 8.0/14 .....   | 59.10                 | .4699 | .4920 |
| Light .....                  | 5.0Y 8.5/12 .....   | 68.40                 | .4508 | .4754 |
| Dark .....                   | 5.0Y 7.5/12 .....   | 50.68                 | .4620 | .4823 |
| Green:                       |                     |                       |       |       |
| Central color .....          | 7.5G 4.0/9 .....    | 12.00                 | .2111 | .4121 |
| Bluish .....                 | 0.5BG 4.0/9 .....   | 12.00                 | .1974 | .3809 |
| Green-yellow .....           | 5.0G 4.0/9 .....    | 12.00                 | .2237 | .4399 |
| Grayish A .....              | 7.5G 4.0/7 .....    | 12.00                 | .2350 | .3922 |
| Grayish B <sup>2</sup> ..... | 7.5G 4.0/6 .....    | 12.00                 | .2467 | .3822 |
| Vivid .....                  | 7.5G 4.0/11 .....   | 12.00                 | .1848 | .4319 |
| Light .....                  | 7.5G 4.5/9 .....    | 15.57                 | .2204 | .4060 |
| Dark .....                   | 7.5G 3.5/9 .....    | 09.00                 | .2027 | .4163 |
| Blue:                        |                     |                       |       |       |
| Central color .....          | 2.5PB 3.5/10 .....  | 09.00                 | .1691 | .1744 |
| Purple .....                 | 4.5PB 3.5/10 .....  | 09.00                 | .1796 | .1711 |
| Green and vivid .....        | 10.0B 3.5/10 .....  | 09.00                 | .1557 | .1815 |
| Grayish .....                | 2.5PB 3.5/8 .....   | 09.00                 | .1888 | .1964 |
| Vivid .....                  | 2.5PB 3.5/12 .....  | 09.00                 | .1516 | .1547 |
| Light .....                  | 2.5PB 4.0/10 .....  | 12.00                 | .1805 | .1888 |
| Dark .....                   | 2.5PB 3.0/10 .....  | 06.55                 | .1576 | .1600 |
| Purple:                      |                     |                       |       |       |
| Central color .....          | 10.0P 4.5/10 .....  | 15.57                 | .3307 | .2245 |
| Reddish purple .....         | 2.5RP 4.5/10 .....  | 15.57                 | .3584 | .2377 |
| Blue purple .....            | 7.5P 4.5/10 .....   | 15.57                 | .3068 | .2145 |
| Reddish gray .....           | 10.0P 4.5/8 .....   | 15.57                 | .3280 | .2391 |
| Gray <sup>2</sup> .....      | 10.0P 4.5/6.5 ..... | 15.57                 | .3254 | .2519 |
| Vivid .....                  | 10.0P 4.5/12 .....  | 15.57                 | .3333 | .2101 |
| Light .....                  | 10.0P 5.0/10 .....  | 19.77                 | .3308 | .2328 |
| Dark .....                   | 10.0P 4.0/10 .....  | 12.00                 | .3306 | .2162 |

<sup>1</sup> Maximum chroma is not limited.

<sup>2</sup> For the colors green and purple, the minimum saturation (chroma) limits for porcelain enamel on metal are lower than for most other surface coatings. Therefore, the minimum chroma limits of these two colors as displayed on the Charts for comparison to porcelain enamel on metal is low, as shown for green (grayish B) and purple (gray).

NOTE: CIE=Commission Internationale de L'Eclairage.

TABLE 2—SPECIFICATIONS FOR COLOR TOLERANCE CHARTS FOR USE WITH LABELS AND PLACARDS SURFACED WITH INK

| Color/series               | Munsell notation       | CIE data for source C |       |       |
|----------------------------|------------------------|-----------------------|-------|-------|
|                            |                        | Y                     | x     | y     |
| Red:                       |                        |                       |       |       |
| Central series:            |                        |                       |       |       |
| Central color .....        | 6.8R 4.47/12.8 .....   | 15.34                 | .5510 | .3286 |
| Grayish .....              | 7.2R 4.72/12.2 .....   | 17.37                 | .5368 | .3348 |
| Purple .....               | 6.4R 4.49/12.7 .....   | 15.52                 | .5442 | .3258 |
| Purple and vivid .....     | 6.1R 4.33/13.1 .....   | 14.25                 | .5529 | .3209 |
| Vivid .....                | 6.7R 4.29/13.2 .....   | 13.99                 | .5617 | .3253 |
| Orange .....               | 7.3R 4.47/12.8 .....   | 15.34                 | .5572 | .3331 |
| Orange and grayish .....   | 7.65R 4.70/12.4 .....  | 17.20                 | .5438 | .3382 |
| Light series:              |                        |                       |       |       |
| Light .....                | 7.0R 4.72/13.2 .....   | 17.32                 | .5511 | .3322 |
| Light and orange .....     | 7.4R 4.96/12.6 .....   | 19.38                 | .5365 | .3382 |
| Light and purple .....     | 6.6R 4.79/12.9 .....   | 17.94                 | .5397 | .3289 |
| Dark series:               |                        |                       |       |       |
| Dark A .....               | 6.7R 4.19/12.5 .....   | 13.30                 | .5566 | .3265 |
| Dark B .....               | 7.0R 4.25/12.35 .....  | 13.72                 | .5522 | .3294 |
| Dark and purple .....      | 7.5R 4.23/12.4 .....   | 13.58                 | .5577 | .3329 |
| Orange:                    |                        |                       |       |       |
| Central series:            |                        |                       |       |       |
| Central color .....        | 5.0YR 6.10/12.15 ..... | 31.27                 | .5193 | .4117 |
| Yellow and grayish A ..... | 5.8YR 6.22/11.7 .....  | 32.69                 | .5114 | .4155 |
| Yellow and grayish B ..... | 6.1YR 6.26/11.85 ..... | 33.20                 | .5109 | .4190 |
| Vivid .....                | 5.1YR 6.07/12.3 .....  | 30.86                 | .5226 | .4134 |

TABLE 2—SPECIFICATIONS FOR COLOR TOLERANCE CHARTS FOR USE WITH LABELS AND PLACARDS  
SURFACED WITH INK—Continued

| Color/series                 | Munsell notation       | CIE data for source C |       |       |
|------------------------------|------------------------|-----------------------|-------|-------|
|                              |                        | Y                     | x     | y     |
| Red and vivid A .....        | 3.9YR 5.87/12.75 ..... | 28.53                 | .5318 | .4038 |
| Red and vivid B .....        | 3.6YR 5.91/12.6 .....  | 29.05                 | .5291 | .4021 |
| Grayish .....                | 4.9YR 6.10/11.9 .....  | 31.22                 | .5170 | .4089 |
| Light series:                |                        |                       |       |       |
| Light and vivid A .....      | 5.8YR 6.78/12.7 .....  | 39.94                 | .5120 | .4177 |
| Light and yellow .....       | 6.0YR 6.80/12.8 .....  | 40.20                 | .5135 | .4198 |
| Light and vivid B .....      | 4.9YR 6.60/12.9 .....  | 37.47                 | .5216 | .4126 |
| Dark series:                 |                        |                       |       |       |
| Dark and yellow .....        | 5.8YR 5.98/11.0 .....  | 29.87                 | .5052 | .4132 |
| Dark A .....                 | 5.1YR 5.80/11.1 .....  | 27.80                 | .5127 | .4094 |
| Dark B .....                 | 5.0YR 5.80/11.0 .....  | 27.67                 | .5109 | .4068 |
| Yellow:                      |                        |                       |       |       |
| Central series:              |                        |                       |       |       |
| Central color .....          | 4.3Y 7.87/10.3 .....   | 56.81                 | .4445 | .4589 |
| Vivid A .....                | 4.5Y 7.82/10.8 .....   | 55.92                 | .4503 | .4658 |
| Vivid B .....                | 3.3Y 7.72/11.35 .....  | 54.24                 | .4612 | .4624 |
| Vivid and orange .....       | 3.2Y 7.72/10.8 .....   | 54.25                 | .4576 | .4572 |
| Grayish A .....              | 4.1Y 7.95/9.7 .....    | 58.18                 | .4380 | .4516 |
| Grayish B .....              | 5.1Y 8.06/9.05 .....   | 60.12                 | .4272 | .4508 |
| Green-yellow .....           | 5.2Y 7.97/9.9 .....    | 58.53                 | .4356 | .4605 |
| Light series:                |                        |                       |       |       |
| Light .....                  | 5.4Y 8.59/10.5 .....   | 70.19                 | .4351 | .4628 |
| Light and green-yellow ..... | 5.4Y 8.56/11.2 .....   | 69.59                 | .4414 | .4692 |
| Light and vivid .....        | 4.4Y 8.45/11.4 .....   | 67.42                 | .4490 | .4662 |
| Dark series:                 |                        |                       |       |       |
| Dark and green-yellow .....  | 4.4Y 7.57/9.7 .....    | 51.82                 | .4423 | .4562 |
| Dark and orange A .....      | 3.4Y 7.39/10.4 .....   | 48.86                 | .4584 | .4590 |
| Dark and orange B .....      | 3.5Y 7.41/10.0 .....   | 49.20                 | .4517 | .4544 |
| Green:                       |                        |                       |       |       |
| Central series:              |                        |                       |       |       |
| Central color .....          | 9.75G 4.26/7.75 .....  | 13.80                 | .2214 | .3791 |
| Grayish .....                | 10G 4.46/7.5 .....     | 15.25                 | .2263 | .3742 |
| Blue A .....                 | 1.4BG 4.20/7.4 .....   | 13.36                 | .2151 | .3625 |
| Blue B .....                 | 1.0BG 4.09/7.75 .....  | 12.60                 | .2109 | .3685 |
| Vivid .....                  | 8.4G 4.09/8.05 .....   | 12.59                 | .2183 | .3954 |
| Vivid green-yellow .....     | 7.0G 4.23/8.0 .....    | 13.54                 | .2292 | .4045 |
| Green-yellow .....           | 7.85G 4.46/7.7 .....   | 15.23                 | .2313 | .3914 |
| Light series:                |                        |                       |       |       |
| Light and vivid .....        | 9.5G 4.45/8.8 .....    | 15.21                 | .2141 | .3863 |
| Light and blue .....         | 0.2BG 4.31/8.8 .....   | 14.12                 | .2069 | .3814 |
| Light and green-yellow ..... | 8.3G 4.29/9.05 .....   | 14.01                 | .2119 | .4006 |
| Dark series:                 |                        |                       |       |       |
| Dark and green-yellow .....  | 7.1G 4.08/7.1 .....    | 12.55                 | .2354 | .3972 |
| Dark and grayish .....       | 9.5G 4.11/6.9 .....    | 12.70                 | .2282 | .3764 |
| Dark .....                   | 8.5G 3.97/7.2 .....    | 11.78                 | .2269 | .3874 |
| Blue:                        |                        |                       |       |       |
| Central series:              |                        |                       |       |       |
| Central color .....          | 3.5PB 3.94/9.7 .....   | 11.58                 | .1885 | .1911 |
| Green and grayish A .....    | 2.0PB 4.35/8.7 .....   | 14.41                 | .1962 | .2099 |
| Green and grayish B .....    | 1.7PB 4.22/9.0 .....   | 13.50                 | .1898 | .2053 |
| Vivid .....                  | 2.9PB 3.81/9.7 .....   | 10.78                 | .1814 | .1852 |
| Purple and vivid A .....     | 4.7PB 3.53/10.0 .....  | 9.15                  | .1817 | .1727 |
| Purple and vivid B .....     | 5.0PB 3.71/9.9 .....   | 10.20                 | .1888 | .1788 |
| Grayish .....                | 3.75PB 4.03/9.1 .....  | 12.17                 | .1943 | .1961 |
| Light series:                |                        |                       |       |       |
| Light and green A .....      | 1.7PB 4.32/9.2 .....   | 14.22                 | .1904 | .2056 |
| Light and green B .....      | 1.5PB 4.11/9.6 .....   | 12.72                 | .1815 | .1971 |
| Light and vivid .....        | 3.2PB 3.95/10.05 ..... | 11.70                 | .1831 | .1868 |
| Dark series:                 |                        |                       |       |       |
| Dark and grayish .....       | 3.9PB 4.01/8.7 .....   | 12.04                 | .1982 | .1992 |
| Dark and purple A .....      | 4.8PB 3.67/9.3 .....   | 9.95                  | .1918 | .1831 |
| Dark and purple B .....      | 5.2PB 3.80/9.05 .....  | 10.76                 | .1985 | .1885 |
| Purple:                      |                        |                       |       |       |
| Central series:              |                        |                       |       |       |
| Central color .....          | 9.5P 4.71/11.3 .....   | 17.25                 | .3274 | .2165 |
| Red .....                    | 1.0RP 5.31/10.8 .....  | 22.70                 | .3404 | .2354 |
| Red and vivid A .....        | 1.4RP 5.00/11.9 .....  | 19.78                 | .3500 | .2274 |
| Red and vivid B .....        | 0.2RP 4.39/12.5 .....  | 14.70                 | .3365 | .2059 |
| Vivid .....                  | 8.0P 4.04/12.0 .....   | 12.23                 | .3098 | .1916 |



TABLE 2—SPECIFICATIONS FOR COLOR TOLERANCE CHARTS FOR USE WITH LABELS AND PLACARDS SURFACED WITH INK—Continued

| Color/series           | Munsell notation       | CIE data for source C |       |       |
|------------------------|------------------------|-----------------------|-------|-------|
|                        |                        | Y                     | x     | y     |
| Blue .....             | 7.0P 4.39/10.8 .....   | 14.71                 | .3007 | .2037 |
| Grayish .....          | 8.8P 5.00/10.3 .....   | 19.73                 | .3191 | .2251 |
| Light series:          |                        |                       |       |       |
| Light and red A .....  | 0.85RP 5.56/11.1 ..... | 25.18                 | .3387 | .2356 |
| Light and red B .....  | 1.1RP 5.27/12.3 .....  | 22.27                 | .3460 | .2276 |
| Light and vivid .....  | 9.2P 4.94/11.95 .....  | 19.24                 | .3247 | .2163 |
| Dark series:           |                        |                       |       |       |
| Dark and grayish ..... | 9.6P 4.70/10.9 .....   | 17.19                 | .3283 | .2204 |
| Dark and vivid .....   | 8.4P 4.05/11.6 .....   | 12.35                 | .3144 | .1970 |
| Dark and blue .....    | 7.5P 4.32/10.5 .....   | 14.19                 | .3059 | .2078 |

TABLE 3—SPECIFICATION FOR COLORS FOR USE WITH LABELS PRINTED ON PACKAGINGS SURFACES

| CIE data for source C | Red  | Orange | Yellow | Green | Blue | Purple |
|-----------------------|------|--------|--------|-------|------|--------|
| x .....               | .424 | .460   | .417   | .228  | .200 | .377   |
| y .....               | .306 | .370   | .392   | .354  | .175 | .205   |
| x .....               | .571 | .543   | .490   | .310  | .255 | .377   |
| y .....               | .306 | .400   | .442   | .354  | .250 | .284   |
| x .....               | .424 | .445   | .390   | .228  | .177 | .342   |
| y .....               | .350 | .395   | .430   | .403  | .194 | .205   |
| x .....               | .571 | .504   | .440   | .310  | .230 | .342   |
| y .....               | .350 | .430   | .492   | .403  | .267 | .284   |
| Y (high) .....        | 23.0 | 41.6   | 72.6   | 20.6  | 15.9 | 21.2   |
| Y (low) .....         | 7.7  | 19.5   | 29.1   | 7.4   | 6.5  | 8.2    |


[Amdt. 172–50, 44 FR 9757, Feb. 15, 1979; Amdt. 172–50, 44 FR 10984, Feb. 26, 1979, as amended by Amdt. 172–50, 44 FR 22467, Apr. 16, 1979; 50 FR 45731, Nov. 1, 1985; Amdt. 172–127, 59 FR 49133, Sept. 26, 1994]

#### APPENDIX B TO PART 172—TREFOIL SYMBOL

1. Except as provided in paragraph 2 of this appendix, the trefoil symbol required for RADIOACTIVE labels and placards and required to be marked on certain packages of Class 7

materials must conform to the design and size requirements of this appendix.


2. RADIOACTIVE labels and placards that were printed prior to April 1, 1996, in conformance with the requirements of this subchapter in effect on March 30, 1996, may continue to be used.



1=Radius of Circle—  
Minimum dimensions  
4 mm (0.16 inch) for markings and labels  
12.5 mm (0.5 inch) for placards  
2=1½ Radii

3=5 radii for markings and labels  
4½ radii for placards.

[60 FR 50306, Sept. 28, 1995, as amended by  
172-143, 61 FR 20750, May 8, 1996]

APPENDIX C TO PART 172—DIMENSIONAL SPECIFICATIONS FOR RECOMMENDED  
PLACARD HOLDERAPPENDIX D TO PART 172—RAIL RISK  
ANALYSIS FACTORS

A. This appendix sets forth the minimum criteria that must be considered by rail carriers when performing the safety and security risk analyses required by §172.820. The risk analysis to be performed may be quantitative, qualitative, or a combination of both. In addition to clearly identifying the hazardous material(s) and route(s) being analyzed, the analysis must provide a thorough

description of the threats, identified vulnerabilities, and mitigation measures implemented to address identified vulnerabilities.

B. In evaluating the safety and security of hazardous materials transport, selection of the route for transportation is critical. For the purpose of rail transportation route analysis, as specified in §172.820(c) and (d), a route may include the point where the carrier takes possession of the material and all track and railroad facilities up to the point

where the material is relinquished to another entity. Railroad facilities are railroad property including, but not limited to, classification and switching yards, storage facilities, and non-private sidings; however, they do not include an offeror's facility, private track, private siding, or consignee's facility. Each rail carrier must use best efforts to communicate with its shippers, consignees, and interlining partners to ensure the safety and security of shipments during all stages of transportation.

C. Because of the varying operating environments and interconnected nature of the rail system, each carrier must select and document the analysis method/model used and identify the routes to be analyzed.

D. The safety and security risk analysis must consider current data and information as well as changes that may reasonably be anticipated to occur during the analysis year. Factors to be considered in the performance of this safety and security risk analysis include:

1. Volume of hazardous material transported;
2. Rail traffic density;
3. Trip length for route;
4. Presence and characteristics of railroad facilities;
5. Track type, class, and maintenance schedule;
6. Track grade and curvature;
7. Presence or absence of signals and train control systems along the route ("dark" versus signaled territory);
8. Presence or absence of wayside hazard detectors;
9. Number and types of grade crossings;
10. Single versus double track territory;
11. Frequency and location of track turn-outs;
12. Proximity to iconic targets;
13. Environmentally sensitive or significant areas;
14. Population density along the route;
15. Venues along the route (stations, events, places of congregation);
16. Emergency response capability along the route;
17. Areas of high consequence along the route, including high consequence targets as defined in §172.820(c);
18. Presence of passenger traffic along route (shared track);
19. Speed of train operations;
20. Proximity to en-route storage or repair facilities;
21. Known threats, including any non-public threat scenarios provided by the Department of Homeland Security or the Department of Transportation for carrier use in the development of the route assessment;
22. Measures in place to address apparent safety and security risks;
23. Availability of practicable alternative routes;

24. Past incidents;
25. Overall times in transit;
26. Training and skill level of crews; and
27. Impact on rail network traffic and congestion.

[73 FR 20772, April 16, 2008]

## **PART 173—SHIPPERS—GENERAL REQUIREMENTS FOR SHIPMENTS AND PACKAGINGS**

### **Subpart A—General**

#### **Sec.**

- 173.1 Purpose and scope.
- 173.2 Hazardous materials classes and index to hazard class definitions.
- 173.2a Classification of a material having more than one hazard.
- 173.3 Packaging and exceptions.
- 173.4 Small quantity exceptions.
- 173.5 Agricultural operations.
- 173.5a Oilfield service vehicles and mechanical displacement meter provers.
- 173.6 Materials of trade exceptions.
- 173.7 Government operations and materials.
- 173.8 Exceptions for non-specification packagings used in intrastate transportation.
- 173.9 Transport vehicles or freight containers containing lading which has been fumigated.
- 173.10 Tank car shipments.
- 173.12 Exceptions for shipment of waste materials.
- 173.13 Exceptions for Class 3, Divisions 4.1, 4.2, 4.3, 5.1, 6.1, and Classes 8 and 9 materials.

### **Subpart B—Preparation of Hazardous Materials for Transportation**

- 173.21 Forbidden materials and packages.
- 173.22 Shipper's responsibility.
- 173.22a Use of packagings authorized under special permits.
- 173.23 Previously authorized packaging.
- 173.24 General requirements for packagings and packages.
- 173.24a Additional general requirements for non-bulk packagings and packages.
- 173.24b Additional general requirements for bulk packagings.
- 173.25 Authorized packagings and over-packs.
- 173.26 Quantity limitations.
- 173.27 General requirements for transportation by aircraft.
- 173.28 Reuse, reconditioning and remanufacture of packagings.
- 173.29 Empty packagings.
- 173.30 Loading and unloading of transport vehicles.
- 173.31 Use of tank cars.
- 173.32 Requirements for the use of portable tanks.

**Pt. 173**

**49 CFR Ch. I (10–1–08 Edition)**

- 173.33 Hazardous materials in cargo tank motor vehicles.
- 173.34 [Reserved]
- 173.35 Hazardous materials in intermediate bulk containers (IBCs).
- 173.40 General packaging requirements for toxic materials packaged in cylinders.

**Subpart C—Definitions, Classification and Packaging for Class 1**

- 173.50 Class 1—Definitions.
- 173.51 Authorization to offer and transport explosives.
- 173.52 Classification codes and compatibility groups of explosives.
- 173.53 Provisions for using old classifications of explosives.
- 173.54 Forbidden explosives.
- 173.55 [Reserved]
- 173.56 New explosives—Definition and procedures for classification and approval.
- 173.57 Acceptance criteria for new explosives.
- 173.58 Assignment of class and division for new explosives.
- 173.59 Description of terms for explosives.
- 173.60 General packaging requirements for explosives.
- 173.61 Mixed packaging requirements.
- 173.62 Specific packaging requirements for explosives.
- 173.63 Packaging exceptions.

**Subpart D—Definitions, Classification, Packing Group Assignments and Exceptions for Hazardous Material Other Than Class 1 and Class 7**

- 173.115 Class 2, Divisions 2.1, 2.2, and 2.3—Definitions.
- 173.116 Class 2—Assignment of hazard zone.
- 173.117–173.119 [Reserved]
- 173.120 Class 3—Definitions.
- 173.121 Class 3—Assignment of packing group.
- 173.124 Class 4, Divisions 4.1, 4.2 and 4.3—Definitions.
- 173.125 Class 4—Assignment of packing group.
- 173.127 Class 5, Division 5.1—Definition and assignment of packing groups.
- 173.128 Class 5, Division 5.2—Definitions and types.
- 173.129 Class 5, Division 5.2—Assignment of packing group.
- 173.132 Class 6, Division 6.1—Definitions.
- 173.133 Assignment of packing group and hazard zones for Division 6.1 materials.
- 173.134 Class 6, Division 6.2—Definitions and exceptions.
- 173.136 Class 8—Definitions.
- 173.137 Class 8—Assignment of packing group.
- 173.140 Class 9—Definitions.
- 173.141 Class 9—Assignment of packing group.

- 173.144 Other Regulated Materials (ORM)—Definitions.
- 173.145 Other Regulated Materials—Assignment of packing group.
- 173.150 Exceptions for Class 3 (flammable and combustible liquids).
- 173.151 Exceptions for Class 4.
- 173.152 Exceptions for Division 5.1 (oxidizers) and Division 5.2 (organic peroxides).
- 173.153 Exceptions for Division 6.1 (poisonous materials).
- 173.154 Exceptions for Class 8 (corrosive materials).
- 173.155 Exceptions for Class 9 (miscellaneous hazardous materials).
- 173.156 Exceptions for ORM materials.

**Subpart E—Non-bulk Packaging for Hazardous Materials Other Than Class 1 and Class 7**

- 173.158 Nitric acid.
- 173.159 Batteries, wet.
- 173.160 Bombs, smoke, non-explosive (corrosive).
- 173.161 Chemical kits and first aid kits.
- 173.162 Gallium.
- 173.163 Hydrogen fluoride.
- 173.164 Mercury (metallic and articles containing mercury).
- 173.166 Air bag inflators, air bag modules and seat-belt pretensioners.
- 173.168 Chemical oxygen generators.
- 173.170 Black powder for small arms.
- 173.171 Smokeless powder for small arms.
- 173.172 Aircraft hydraulic power unit fuel tank.
- 173.173 Paint, paint-related material, adhesives and ink and resins.
- 173.174 Refrigerating machines.
- 173.181 Pyrophoric materials (liquids).
- 173.182 Barium azide—50 percent or more water wet.
- 173.183 Nitrocellulose base film.
- 173.184 Highway or rail fusee.
- 173.185 Lithium batteries and cells.
- 173.186 Matches.
- 173.187 Pyrophoric solids, metals or alloys, n.o.s.
- 173.188 White or yellow phosphorous.
- 173.189 Batteries containing sodium or cells containing sodium.
- 173.192 Packaging for certain toxic gases in Hazard Zone A.
- 173.193 Bromoacetone, methyl bromide, chloropicrin and methyl bromide or methyl chloride mixtures, etc.
- 173.194 Gas identification sets.
- 173.195 Hydrogen cyanide, anhydrous, stabilized (hydrocyanic acid, aqueous solution).
- 173.196 Category A infectious substances.
- 173.197 Regulated medical waste.
- 173.198 Nickel carbonyl.
- 173.199 Category B infectious substances.

- 173.201 Non-bulk packagings for liquid hazardous materials in Packing Group I.
- 173.202 Non-bulk packagings for liquid hazardous materials in Packing Group II.
- 173.203 Non-bulk packagings for liquid hazardous materials in Packing Group III.
- 173.204 Non-bulk, non-specification packagings for certain hazardous materials.
- 173.205 Specification cylinders for liquid hazardous materials.
- 173.211 Non-bulk packagings for solid hazardous materials in Packing Group I.
- 173.212 Non-bulk packagings for solid hazardous materials in Packing Group II.
- 173.213 Non-bulk packagings for solid hazardous materials in Packing Group III.
- 173.214 Packagings which require approval by the Associate Administrator.
- 173.216 Asbestos, blue, brown, or white.
- 173.217 Carbon dioxide, solid (dry ice).
- 173.218 Fish meal or fish scrap.
- 173.219 Life-saving appliances.
- 173.220 Internal combustion engines, self-propelled vehicles, mechanical equipment containing internal combustion engines, and battery powered vehicles or equipment.
- 173.221 Polymeric beads, expandable and plastic molding compound.
- 173.222 Dangerous good in machinery or apparatus.
- 173.223 Musk xylene.
- 173.224 Packaging and control and emergency temperatures for self-reactive materials.
- 173.225 Packaging requirements and other provisions for organic peroxides.
- 173.226 Materials poisonous by inhalation, Division 6.1, Packing Group I, Hazard Zone A.
- 173.227 Materials poisonous by inhalation, Division 6.1, Packing Group I, Hazard Zone B.
- 173.228 Bromine pentafluoride or bromine trifluoride.
- 173.229 Chloric acid solution or chlorine dioxide hydrate, frozen.
- 173.230 Fuel cell cartridges containing flammable liquids.

#### **Subpart F—Bulk Packaging for Hazardous Materials Other Than Class 1 and Class 7**

- 173.240 Bulk packaging for certain low hazard solid materials.
- 173.241 Bulk packagings for certain low hazard liquid and solid materials.
- 173.242 Bulk packagings for certain medium hazard liquids and solids, including solids with dual hazards.
- 173.243 Bulk packaging for certain high hazard liquids and dual hazard materials which pose a moderate hazard.
- 173.244 Bulk packaging for certain pyrophoric liquids (Division 4.2), dangerous when wet (Division 4.3) materials, and poisonous liquids with inhalation hazards (Division 6.1).
- 173.245 Bulk packaging for extremely hazardous materials such as poisonous gases (Division 2.3).
- 173.247 Bulk packaging for certain elevated temperature materials.
- 173.249 Bromine.

#### **Subpart G—Gases; Preparation and Packaging**

- 173.300 [Reserved]
- 173.301 General requirements for shipment of compressed gases and other hazardous materials in cylinders, UN pressure receptacles and spherical pressure vessels.
- 173.301a Additional general requirements for shipment of specification cylinders.
- 173.301b Additional general requirements for shipment of UN pressure receptacles.
- 173.302 Filling of cylinders with nonliquefied (permanent) compressed gases.
- 173.302a Additional requirements for shipment nonliquefied (permanent) compressed gases in specification cylinders.
- 173.302b Additional requirements for shipment of non-liquefied (permanent) compressed gases in UN pressure receptacles.
- 173.303 Charging of cylinders with compressed gas in solution (acetylene).
- 173.304 Filling of cylinders with liquefied compressed gases.
- 173.304a Additional requirements for shipment of liquefied compressed gases in specification cylinders.
- 173.304b Additional requirements for shipment of liquefied compressed gases in UN pressure receptacles.
- 173.305 Charging of cylinders with a mixture of compressed gas and other material.
- 173.306 Limited quantities of compressed gases.
- 173.307 Exceptions for compressed gases.
- 173.308 Cigarette lighter or other similar device charged with fuel.
- 173.309 Fire extinguishers.
- 173.312 Requirements for shipment of MEGCs.
- 173.313 UN Portable Tank Table for Liquefied Compressed Gases.
- 173.314 Compressed gases in tank cars and multi-unit tank cars.
- 173.315 Compressed gases in cargo tanks and portable tanks.
- 173.316 Cryogenic liquids in cylinders.
- 173.318 Cryogenic liquids in cargo tanks.
- 173.319 Cryogenic liquids in tank cars.
- 173.320 Cryogenic liquids; exceptions.
- 173.321 Ethylamine.
- 173.322 Ethyl chloride.
- 173.323 Ethylene oxide.
- 173.334 Organic phosphates mixed with compressed gas.
- 173.335 [Reserved]
- 173.336 Nitrogen dioxide, liquefied, or dinitrogen tetroxide, liquefied.

## § 173.1

- 173.337 Nitric oxide.
- 173.338 Tungsten hexafluoride.
- 173.340 Tear gas devices.

### Subpart H [Reserved]

#### Subpart I—Class 7 (Radioactive) Materials

- 173.401 Scope.
- 173.403 Definitions.
- 173.410 General design requirements.
- 173.411 Industrial packagings.
- 173.412 Additional design requirements for Type A packages.
- 173.413 Requirements for Type B packages.
- 173.415 Authorized Type A packages.
- 173.416 Authorized Type B packages.
- 173.417 Authorized fissile materials packages.
- 173.418 Authorized packages—pyrophoric Class 7 (radioactive) materials.
- 173.419 Authorized packages—oxidizing Class 7 (radioactive) materials.
- 173.420 Uranium hexafluoride (fissile, fissile excepted and non-fissile).
- 173.421 Excepted packages for limited quantities of Class 7 (radioactive) materials.
- 173.422 Additional requirements for excepted packages containing Class 7 (radioactive) materials.
- 173.423 Requirements for multiple hazard limited quantity Class 7 (radioactive) materials.
- 173.424 Excepted packages for radioactive instruments and articles.
- 173.425 Table of activity limits—excepted quantities and articles.
- 173.426 Excepted packages for articles containing natural uranium or thorium.
- 173.427 Transport requirements for low specific activity (LSA) Class 7 (radioactive) materials and surface contaminated objects (SCO).
- 173.428 Empty Class 7 (radioactive) materials packaging.
- 173.431 Activity limits for Type A and Type B packages.
- 173.433 Requirements for determining basic radionuclide values, and for the listing of radionuclides on shipping papers and labels.
- 173.434 Activity-mass relationships for uranium and natural thorium.
- 173.435 Table of  $A_1$  and  $A_2$  values for radionuclides.
- 173.436 Exempt material activity concentrations and exempt consignment activity limits for radionuclides.
- 173.441 Radiation level limitations and exclusive use provisions.
- 173.442 Thermal limitations.
- 173.443 Contamination control.
- 173.447 Storage incident to transportation—general requirements.
- 173.448 General transportation requirements.
- 173.453 Fissile materials—exceptions.

## 49 CFR Ch. I (10–1–08 Edition)

- 173.457 Transportation of fissile material packages—specific requirements.
- 173.459 Mixing of fissile material packages with non-fissile or fissile-excepted material packages.
- 173.461 Demonstration of compliance with tests.
- 173.462 Preparation of specimens for testing.
- 173.465 Type A packaging tests.
- 173.466 Additional tests for Type A packagings designed for liquids and gases.
- 173.467 Tests for demonstrating the ability of Type B and fissile materials packagings to withstand accident conditions in transportation.
- 173.468 Test for LSA-III material.
- 173.469 Tests for special form Class 7 (radioactive) materials.
- 173.471 Requirements for U.S. Nuclear Regulatory Commission approved packages.
- 173.472 Requirements for exporting DOT Specification Type B and fissile packagings.
- 173.473 Requirements for foreign-made packages.
- 173.474 Quality control for construction of packaging.
- 173.475 Quality control requirements prior to each shipment of Class 7 (radioactive) materials.
- 173.476 Approval of special form Class 7 (radioactive) materials.
- 173.477 Approval of packagings containing greater than 0.1 kg of non-fissile or fissile-excepted uranium hexafluoride.

### Subparts J–O [Reserved]

- APPENDIX A TO PART 173 [RESERVED]
- APPENDIX B TO PART 173—PROCEDURE FOR TESTING CHEMICAL COMPATIBILITY AND RATE OF PERMEATION IN PLASTIC PACKAGING AND RECEPTACLES
- APPENDIX C TO PART 173—PROCEDURE FOR BASE-LEVEL VIBRATION TESTING
- APPENDIX D TO PART 173—TEST METHODS FOR DYNAMITE (EXPLOSIVE, BLASTING, TYPE A)
- APPENDICES E–G TO PART 173 [RESERVED]
- APPENDIX H TO PART 173—METHOD OF TESTING FOR SUSTAINED COMBUSTIBILITY

AUTHORITY: 49 U.S.C. 5101–5128, 44701; 49 CFR 1.45, 1.53.

EDITORIAL NOTE: Nomenclature changes to part 173 appear at 70 FR 56098, Sept. 23, 2005.

### Subpart A—General

#### § 173.1 Purpose and scope.

- (a) This part includes:
  - (1) Definitions of hazardous materials for transportation purposes;

(2) Requirements to be observed in preparing hazardous materials for shipment by air, highway, rail, or water, or any combination thereof; and

(3) Inspection, testing, and retesting responsibilities for persons who retest, recondition, maintain, repair and rebuild containers used or intended for use in the transportation of hazardous materials.

(b) A shipment of hazardous materials that is not prepared in accordance with this subchapter may not be offered for transportation by air, highway, rail, or water. It is the responsibility of each hazmat employer subject to the requirements of this subchapter to ensure that each hazmat employee is trained in accordance with the requirements prescribed in this subchapter. It is the duty of each person who offers hazardous materials for transportation to instruct each of his officers, agents, and employees having any responsibility for preparing hazardous materials for shipment as to applicable regulations in this subchapter.

(c) In general, the Hazardous Materials Regulations (HMR) contained in this subchapter are based on the UN Recommendations and are consistent with international regulations issued

by the International Civil Aviation Organization (ICAO Technical Instructions) and the International Maritime Organization (IMDG Code). However, the HMR are not consistent in all respects with the UN Recommendations, the ICAO Technical Instructions or the IMDG Code, and compliance with the HMR will not guarantee acceptance by regulatory bodies outside of the United States.

[Amdt. 173-94, 41 FR 16062, Apr. 15, 1976, as amended by Amdt. 173-100, 41 FR 40476, Sept. 20, 1976; Amdt. 173-161, 48 FR 2655, Jan. 20, 1983; Amdt. 173-224, 55 FR 52606, Dec. 21, 1990; Amdt. 173-231, 57 FR 20953, May 15, 1992; 64 FR 10776, Mar. 5, 1999; 68 FR 61941, Oct. 30, 2003]

#### § 173.2 Hazardous materials classes and index to hazard class definitions.

The hazard class of a hazardous material is indicated either by its class (or division) number, its class name, or by the letters “ORM-D”. The following table lists class numbers, division numbers, class or division names and those sections of this subchapter which contain definitions for classifying hazardous materials, including forbidden materials.

| Class No. | Division No. (if any) | Name of class or division                           | 49 CFR reference for definitions |
|-----------|-----------------------|-----------------------------------------------------|----------------------------------|
| None      | .....                 | Forbidden materials .....                           | 173.21                           |
| None      | .....                 | Forbidden explosives .....                          | 173.54                           |
| 1         | 1.1                   | Explosives (with a mass explosion hazard) .....     | 173.50                           |
| 1         | 1.2                   | Explosives (with a projection hazard) .....         | 173.50                           |
| 1         | 1.3                   | Explosives (with predominately a fire hazard) ..... | 173.50                           |
| 1         | 1.4                   | Explosives (with no significant blast hazard) ..... | 173.50                           |
| 1         | 1.5                   | Very insensitive explosives; blasting agents .....  | 173.50                           |
| 1         | 1.6                   | Extremely insensitive detonating substances .....   | 173.50                           |
| 2         | 2.1                   | Flammable gas .....                                 | 173.115                          |
| 2         | 2.2                   | Non-flammable compressed gas .....                  | 173.115                          |
| 2         | 2.3                   | Poisonous gas .....                                 | 173.115                          |
| 3         | .....                 | Flammable and combustible liquid .....              | 173.120                          |
| 4         | 4.1                   | Flammable solid .....                               | 173.124                          |
| 4         | 4.2                   | Spontaneously combustible material .....            | 173.124                          |
| 4         | 4.3                   | Dangerous when wet material .....                   | 173.124                          |
| 5         | 5.1                   | Oxidizer .....                                      | 173.127                          |
| 5         | 5.2                   | Organic peroxide .....                              | 173.128                          |
| 6         | 6.1                   | Poisonous materials .....                           | 173.132                          |
| 6         | 6.2                   | Infectious substance (Etiologic agent) .....        | 173.134                          |
| 7         | .....                 | Radioactive material .....                          | 173.403                          |
| 8         | .....                 | Corrosive material .....                            | 173.136                          |
| 9         | .....                 | Miscellaneous hazardous material .....              | 173.140                          |
| None      | .....                 | Other regulated material: ORM-D .....               | 173.144                          |

[Amdt. 173-224, 55 FR 52606, Dec. 21, 1990, as amended at 57 FR 45460, Oct. 1, 1992; Amdt. 173-234, 58 FR 51531, Oct. 1, 1993]



**§ 173.2a Classification of a material having more than one hazard.**

(a) *Classification of a material having more than one hazard.* Except as provided in paragraph (c) of this section, a material not specifically listed in the § 172.101 table that meets the definition of more than one hazard class or division as defined in this part, shall be classed according to the highest applicable hazard class of the following hazard classes, which are listed in descending order of hazard:

(1) Class 7 (radioactive materials, other than limited quantities).

(2) Division 2.3 (poisonous gases).

(3) Division 2.1 (flammable gases).

(4) Division 2.2 (nonflammable gases).

(5) Division 6.1 (poisonous liquids), Packing Group I, poisonous-by-inhalation only.

(6) A material that meets the definition of a pyrophoric material in § 173.124(b)(1) of this subchapter (Division 4.2).

(7) A material that meets the definition of a self-reactive material in § 173.124(a)(2) of this subchapter (Division 4.1).

(8) Class 3 (flammable liquids), Class 8 (corrosive materials), Division 4.1 (flammable solids), Division 4.2 (spontaneously combustible materials), Division 4.3 (dangerous when wet materials), Division 5.1 (oxidizers) or Division 6.1 (poisonous liquids or solids other than Packing Group I, poisonous-by-inhalation). The hazard class and packing group for a material meeting more than one of these hazards shall be determined using the precedence table in paragraph (b) of this section.

(9) Combustible liquids.

(10) Class 9 (miscellaneous hazardous materials).

(b) *Precedence of hazard table for Classes 3 and 8 and Divisions 4.1, 4.2, 4.3, 5.1 and 6.1.* The following table ranks those materials that meet the definition of Classes 3 and 8 and Divisions 4.1, 4.2, 4.3, 5.1 and 6.1:

PRECEDENCE OF HAZARD TABLE  
[ Hazard class or division and packing group ]

|                            | 4.2   | 4.3   | 5.1<br>I <sup>1</sup> | 5.1<br>II <sup>1</sup> | 5.1<br>III <sup>1</sup> | 6.1, I<br>dermal | 6.1, I<br>oral | 6.1<br>II | 6.1<br>III     | 8, I<br>liquid | 8, I<br>solid | 8, II<br>liquid | 8, II<br>solid | 8, III<br>liquid | 8, III<br>solid |
|----------------------------|-------|-------|-----------------------|------------------------|-------------------------|------------------|----------------|-----------|----------------|----------------|---------------|-----------------|----------------|------------------|-----------------|
| 3 I <sup>2</sup> .....     | ..... | 4.3   | .....                 | .....                  | .....                   | 3                | 3              | 3         | 3              | 3              | (3)           | 3               | (3)            | 3                | (3)             |
| 3 II <sup>2</sup> .....    | ..... | 4.3   | .....                 | .....                  | .....                   | 3                | 3              | 3         | 3              | 8              | (3)           | 3               | (3)            | 3                | (3)             |
| 3 III <sup>2</sup> .....   | ..... | 4.3   | .....                 | .....                  | .....                   | 6.1              | 6.1            | 6.1       | 3 <sup>4</sup> | 8              | (3)           | 8               | (3)            | 3                | (3)             |
| 4.1 II <sup>2</sup> .....  | 4.2   | 4.3   | 5.1                   | 4.1                    | 4.1                     | 6.1              | 6.1            | 4.1       | 4.1            | (3)            | 8             | (3)             | 4.1            | (3)              | 4.1             |
| 4.1 III <sup>2</sup> ..... | 4.2   | 4.3   | 5.1                   | 4.1                    | 4.1                     | 6.1              | 6.1            | 6.1       | 4.1            | (3)            | 8             | (3)             | 8              | (3)              | 4.1             |
| 4.2 II .....               | ..... | 4.3   | 5.1                   | 4.2                    | 4.2                     | 6.1              | 6.1            | 4.2       | 4.2            | 8              | 8             | 4.2             | 4.2            | 4.2              | 4.2             |
| 4.2 III .....              | ..... | 4.3   | 5.1                   | 5.1                    | 4.2                     | 6.1              | 6.1            | 6.1       | 4.2            | 8              | 8             | 8               | 8              | 4.2              | 4.2             |
| 4.3 I .....                | ..... | ..... | 5.1                   | 4.3                    | 4.3                     | 6.1              | 4.3            | 4.3       | 4.3            | 4.3            | 4.3           | 4.3             | 4.3            | 4.3              | 4.3             |
| 4.3 II .....               | ..... | ..... | 5.1                   | 4.3                    | 4.3                     | 6.1              | 4.3            | 4.3       | 4.3            | 8              | 8             | 4.3             | 4.3            | 4.3              | 4.3             |
| 4.3 III .....              | ..... | ..... | 5.1                   | 5.1                    | 4.3                     | 6.1              | 6.1            | 6.1       | 4.3            | 8              | 8             | 8               | 8              | 4.3              | 4.3             |
| 5.1 I <sup>1</sup> .....   | ..... | ..... | .....                 | .....                  | .....                   | 5.1              | 5.1            | 5.1       | 5.1            | 5.1            | 5.1           | 5.1             | 5.1            | 5.1              | 5.1             |
| 5.1 II <sup>1</sup> .....  | ..... | ..... | .....                 | .....                  | .....                   | 6.1              | 5.1            | 5.1       | 5.1            | 8              | 8             | 5.1             | 5.1            | 5.1              | 5.1             |
| 5.1 III <sup>1</sup> ..... | ..... | ..... | .....                 | .....                  | .....                   | 6.1              | 6.1            | 6.1       | 5.1            | 8              | 8             | 8               | 8              | 5.1              | 5.1             |
| 6.1 I, Dermal .....        | ..... | ..... | .....                 | .....                  | .....                   | .....            | .....          | .....     | .....          | 8              | 6.1           | 6.1             | 6.1            | 6.1              | 6.1             |
| 6.1 I, Oral .....          | ..... | ..... | .....                 | .....                  | .....                   | .....            | .....          | .....     | .....          | 8              | 6.1           | 6.1             | 6.1            | 6.1              | 6.1             |
| 6.1 II, Inhalation .....   | ..... | ..... | .....                 | .....                  | .....                   | .....            | .....          | .....     | .....          | 8              | 6.1           | 6.1             | 6.1            | 6.1              | 6.1             |
| 6.1 II, Dermal .....       | ..... | ..... | .....                 | .....                  | .....                   | .....            | .....          | .....     | .....          | 8              | 6.1           | 8               | 6.1            | 6.1              | 6.1             |
| 6.1 II, Oral .....         | ..... | ..... | .....                 | .....                  | .....                   | .....            | .....          | .....     | .....          | 8              | 8             | 8               | 6.1            | 6.1              | 6.1             |
| 6.1 III .....              | ..... | ..... | .....                 | .....                  | .....                   | .....            | .....          | .....     | .....          | 8              | 8             | 8               | 8              | 8                | 8               |

<sup>1</sup> See § 173.127.

<sup>2</sup> Materials of Division 4.1 other than self-reactive substances and solid desensitized explosives, and materials of Class 3 other than liquid desensitized explosives.

<sup>3</sup> Denotes an impossible combination.

<sup>4</sup> For pesticides only, where a material has the hazards of Class 3, Packing Group III, and Division 6.1, Packing Group III, the primary hazard is Division 6.1, Packing Group III.

NOTE 1: The most stringent packing group assigned to a hazard of the material takes precedence over other packing groups; for example, a material meeting Class 3 PG II and Division 6.1 PG I (oral toxicity) is classified as Class 3 PG I.

NOTE 2: A material which meets the definition of Class 8 and has an inhalation toxicity by dusts and mists which meets criteria for Packing Group I specified in § 173.133(a)(1) must be classed as Division 6.1 if the oral or dermal toxicity meets criteria for Packing Group I or II. If the oral or dermal toxicity

meets criteria for Packing Group III or less, the material must be classed as Class 8.

(c) The following materials are not subject to the provisions of paragraph (a) of this section because of their unique properties:

(1) A Class 1 (explosive) material that meets any other hazard class or division as defined in this part shall be assigned a division in Class 1. Class 1 materials shall be classed and approved in accordance with § 173.56 of this part;

(2) A Division 5.2 (organic peroxide) material that meets the definition of any other hazard class or division as defined in this part, shall be classed as Division 5.2;

(3) A Division 6.2 (infectious substance) material that also meets the definition of another hazard class or division, other than Class 7, or that also is a limited quantity Class 7 material, shall be classed as Division 6.2;

(4) A material that meets the definition of a wetted explosive in § 173.124(a)(1) of this subchapter (Division 4.1). Wetted explosives are either specifically listed in the § 172.101 table or are approved by the Associate Administrator (see § 173.124(a)(1) of this subchapter); and

(5) A limited quantity of a Class 7 (radioactive) material that meets the definition for more than one hazard class or division shall be classed in accordance with § 173.423.

[Amdt. 173–224, 55 FR 52606, Dec. 21, 1990, as amended at 56 FR 66264, Dec. 20, 1991; Amdt. 173–241, 59 FR 67490, Dec. 29, 1994; Amdt. 173–247, 60 FR 48787, Sept. 20, 1995; Amdt. 173–244, 60 FR 50307, Sept. 28, 1995; 64 FR 10776, Mar. 5, 1999; 66 FR 33426, June 21, 2001; 66 FR 45182, 45379, Aug. 28, 2001; 68 FR 45032, July 31, 2003]

#### § 173.3 Packaging and exceptions.

(a) The packaging of hazardous materials for transportation by air, highway, rail, or water must be as specified in this part. Methods of manufacture, packing, and storage of hazardous materials, that affect safety in transportation, must be open to inspection by a duly authorized representative of the initial carrier or of the Department. Methods of manufacture and related functions necessary for completion of a DOT specification or U.N. standard packaging must be open to inspection by a representative of the Department.

(b) The regulations setting forth packaging requirements for a specific material apply to all modes of transportation unless otherwise stated, or unless exceptions from packaging requirements are authorized.

(c) *Salvage drums.* Packages of hazardous materials that are damaged, defective, or leaking; packages found to be not conforming to the requirements of this subchapter after having been placed in transportation; and, hazardous materials that have spilled or leaked may be placed in a metal or plastic removable head salvage drum that is compatible with the lading and shipped for repackaging or disposal under the following conditions:

(1) Except as provided in paragraph (c)(7) of this section, the drum must be a UN 1A2, 1B2, 1N2 or 1H2 tested and marked for Packing Group III or higher performance standards for liquids or solids and a leakproofness test of 20 kPa (3 psig). Alternatively, a drum manufactured and marked prior to October 1, 1993 as a salvage drum, in accordance with the provisions of this section in effect on September 30, 1991, is authorized. Capacity of the drum may not exceed 450 L (119 gallons).

(2) Each drum shall be provided when necessary with sufficient cushioning and absorption material to prevent excessive shifting of the damaged package and to eliminate the presence of any free liquid at the time the salvage drum is closed. All cushioning and absorbent material used in the drum must be compatible with the hazardous material.

(3) Each salvage packaging must be marked with the proper shipping name of the hazardous material inside the packaging and the name and address of the consignee. In addition, the packaging must be marked “SALVAGE” or “SALVAGE DRUM”.

(4) Each drum shall be labeled as prescribed for the respective material.

(5) The shipper shall prepare shipping papers in accordance with subpart C of part 172 of this subchapter.

(6) The overpack requirements of § 173.25 do not apply to drums used in accordance with this paragraph.

### § 173.3

### 49 CFR Ch. I (10–1–08 Edition)

(7) A salvage packaging marked “T” in accordance with applicable provisions in the UN Recommendations may be used.

(d) *Salvage cylinders.* Cylinders of hazardous materials that are damaged or leaking may be overpacked in a non-DOT specification full opening hinged head or fully removable head steel salvage cylinder under the following conditions:

(1) Only a cylinder containing a Division 2.1, 2.2, 2.3, 3, 6.1, or a Class 8 material may be overpacked in a salvage cylinder. A cylinder containing acetylene may not be overpacked in a salvage cylinder.

(2) Each salvage cylinder—

(i) Must be designed, constructed and marked in accordance with Section VIII, Division I of the ASME Code (IBR, see §171.7 of this subchapter) with a minimum design margin of 4 to 1. Salvage cylinders may not be equipped with a pressure relief device. Damaged cylinders must be securely positioned in the salvage cylinder to prevent excessive movement. The overpack requirements of §173.25 of this part do not apply to salvage cylinders used in accordance with this section.

(ii) Must have a maximum water capacity of 450 L (119 gallons).

(iii) Except for liquefied nitrous oxide and carbon dioxide, contents of the damaged or leaking cylinder must be limited in pressure and volume so that if totally discharged into the salvage cylinder, the pressure in the salvage cylinder will not exceed  $\frac{3}{4}$  of the MAWP at 55 °C (131 °F).

(iv) Must have gaskets, valves and fittings that are compatible with the hazardous materials contained within.

(3) Each salvage cylinder must be plainly and durably marked. Unless otherwise specified, the markings below must be in the same area on any portion of the upper end:

(i) The proper shipping name of the hazardous material contained inside the packaging;

(ii) The name and address of the consignee or consignor;

(iii) The name and address or registered symbol of the manufacturer; and

(iv) The words “SALVAGE CYLINDER” in letters at least 50 mm (2.0

inches) high on opposite sides near the middle of the cylinder; stamping on the sidewall is not authorized.

(4) Each salvage cylinder must be labeled for the hazardous material contained inside the packaging.

(5) The shipper must prepare shipping papers in accordance with subpart C of part 172 of this subchapter.

(6) Transportation is authorized by motor vehicle only.

(7) Each salvage cylinder must be cleaned and purged after each use.

(8) In addition to the training requirements of §§172.700 through 172.704 of this subchapter, a person who loads, unloads or transports a salvage cylinder must be trained in handling, loading and unloading the salvage cylinder.

(9) *Cylinder Requalification:* At least once every five years, each cylinder must be visually inspected (internally and externally) in accordance with CGA Pamphlet C-6 (IBR, see §171.7 of this subchapter) and pressure tested. A minimum test pressure of at least  $1\frac{1}{2}$  times MAWP must be maintained for at least 30 seconds. The cylinder must be examined under test pressure and removed from service if a leak or a defect is found.

(i) The retest and inspection must be performed by a person familiar with salvage cylinders and trained and experienced in the use of the inspection and testing equipment.

(ii) Each salvage cylinder that is successfully requalified must be durably and legibly marked with the word “Tested” followed by the requalification date (month/year), e.g., “Tested 9/04.” The marking must be in letters and numbers at least 12 mm (0.5 inches) high. The requalification marking may be placed on any portion of the upper end of the cylinder near the marking required in (d)(3) of this section or on a metal plate permanently secured to the cylinder. Stamping on the cylinder sidewall is not authorized.

(10) *Record retention:* The owner of each salvage cylinder or his authorized agent shall retain a record of the most recent visual inspection and pressure test until the salvage cylinder is requalified. The records must be made available to a DOT representative upon request.

(e) *Emergency transportation of DOT 3A480 or 3AA480 cylinders and DOT 106A500 multi-unit tank car tanks.* (1) A DOT 3A480 or DOT 3AA480 cylinder containing chlorine or sulphur dioxide that has developed a leak in a valve or fusible plug may be repaired temporarily by trained personnel using a Chlorine Institute Kit “A” (IBR, *see* § 171.7 of this subchapter). The repaired cylinder is authorized to be transported by private or contract carrier one time, one way, from the point of discovery to a proper facility for discharge and examination.

(2) A DOT 106A500 multi-unit tank car tank containing chlorine or sulphur dioxide that has developed a leak in the valve or fusible plug may be temporarily repaired by trained personnel using a Chlorine Institute Kit “B” (IBR, *see* § 171.7 of this subchapter). The repaired tank is authorized to be transported by private or contract carrier one time, one way, from the point of discovery to a proper facility for discharge and examination.

(3) Training for personnel making the repairs in paragraphs (d)(1) and (d)(2) of this section must include:

(i) Proper use of the devices and tools in the applicable kits;

(ii) Use of respiratory equipment and all other safety equipment; and

(iii) Knowledge of the properties of chlorine and sulphur dioxide.

(4) Packagings repaired with “A” or “B” kits must be properly blocked and braced to ensure the packagings are secured in the transport vehicle.

[Amdt. 173–224, 55 FR 52607, Dec. 21, 1990, as amended at 56 FR 66265, Dec. 20, 1991; Amdt. 173–234, 58 FR 51531, Oct. 1, 1993; Amdt. 173–261, 62 FR 24719, May 6, 1997; 66 FR 45380, Aug. 28, 2001; 68 FR 48569, Aug. 14, 2003; 69 FR 76154, Dec. 20, 2004; 70 FR 3307, Jan. 24, 2005; 68 FR 61941, Oct. 30, 2003; 70 FR 34397, June 14, 2005; 70 FR 56098, Sept. 23, 2005]

#### § 173.4 Small quantity exceptions.

(a) Small quantities of Class 3, Division 4.1, Division 4.2 (PG II and III), Division 4.3 (PG II and III), Division 5.1, Division 5.2, Division 6.1, Class 7, Class 8, and Class 9 materials that also meet the definition of one or more of these hazard classes, are not subject to any other requirements of this subchapter when—

(1) The maximum quantity of material per inner receptacle or article is limited to—

(i) Thirty (30) mL (1 ounce) for authorized liquids, other than Division 6.1, Packing Group I, Hazard Zone A or B materials;

(ii) Thirty (30) g (1 ounce) for authorized solid materials;

(iii) One (1) g (0.04 ounce) for authorized materials meeting the definition of a Division 6.1, Packing Group I, Hazard Zone A or B material; and

(iv) An activity level not exceeding that specified in §§ 173.421, 173.424, 173.425 or 173.426, as appropriate, for a package containing a Class 7 (radioactive) material.

(2) With the exception of temperature sensing devices, each inner receptacle:

(i) Is not liquid-full at 55 °C (131 °F), and

(ii) Is constructed of plastic having a minimum thickness of no less than 0.2 mm (0.008 inch), or earthenware, glass, or metal;

(3) Each inner receptacle with a removable closure has its closure held securely in place with wire, tape, or other positive means;

(4) Unless equivalent cushioning and absorbent material surrounds the inside packaging, each inner receptacle is securely packed in an inside packaging with cushioning and absorbent material that:

(i) Will not react chemically with the material, and

(ii) Is capable of absorbing the entire contents (if a liquid) of the receptacle;

(5) The inside packaging is securely packed in a strong outside packaging;

(6) The completed package, as demonstrated by prototype testing, is capable of sustaining—

(i) Each of the following free drops made from a height of 1.8 m (5.9 feet) directly onto a solid unyielding surface without breakage or leakage from any inner receptacle and without a substantial reduction in the effectiveness of the package:

(A) One drop flat on bottom;

(B) One drop flat on top;

(C) One drop flat on the long side;

(D) One drop flat on the short side; and

(E) One drop on a corner at the junction of three intersecting edges; and

#### § 173.4

#### 49 CFR Ch. I (10–1–08 Edition)

(ii) A compressive load as specified in § 178.606(c) of this subchapter.

NOTE TO PARAGRAPH (a)(6): Each of the tests in paragraph (a)(6) of this section may be performed on a different but identical package; *i.e.*, all tests need not be performed on the same package.

(7) Placement of the material in the package or packing different materials in the package does not result in a violation of § 173.21;

(8) The gross mass of the completed package does not exceed 29 kg (64 pounds);

(9) The package is not opened or otherwise altered until it is no longer in commerce; and

(10) The shipper certifies conformance with this section by marking the outside of the package with the statement “This package conforms to 49 CFR 173.4.”

(11) For transportation by aircraft:

(i) The hazardous material must be authorized to be carried aboard passenger-carrying aircraft;

(ii) The hazardous material is not authorized to be carried in checked or carry-on baggage.

(b) A package containing a Class 7 (radioactive) material also must conform to the requirements of § 173.421(a)(1) through (a)(5) or § 173.424(a) through (g), as appropriate.

(c) Packages which contain a Class 2, Division 4.2 (PG I), or Division 4.3 (PG I) material conforming to paragraphs (a)(1) through (a)(10) of this section may be offered for transportation or transported if specifically approved by the Associate Administrator.

(d) Lithium batteries and cells are not eligible for the exceptions provided in this section.

(e) Packing Group II and III materials in Class 3, Division 4.1, Division 4.2, Division 4.3, Division 5.1, Division 6.1, Class 8, and Class 9 do not meet the definition of a hazardous material in § 171.8 of this subchapter when packaged in accordance with this paragraph (e) and, therefore, are not subject to the requirements of this subchapter.

(1) The maximum quantity of material per inner receptacle or article is limited to—

(i) One (1) mL (0.03 ounce) for authorized liquids; and

(ii) One (1) g (0.04 ounce) for authorized solid materials;

(2) Each inner receptacle with a removable closure has its closure held securely in place with wire, tape, or other positive means;

(3) Unless equivalent cushioning and absorbent material surrounds the inside packaging, each inner receptacle is securely packed in an inside packaging with cushioning and absorbent material that:

(i) Will not react chemically with the material, and

(ii) Is capable of absorbing the entire contents (if a liquid) of the receptacle;

(4) The inside packaging is securely packed in a strong outside packaging;

(5) The completed package is capable of sustaining—

(i) Each of the following free drops made from a height of 1.8 m (5.9 feet) directly onto a solid unyielding surface without breakage or leakage from any inner receptacle and without a substantial reduction in the effectiveness of the package:

(A) One drop flat on bottom;

(B) One drop flat on top;

(C) One drop flat on the long side;

(D) One drop flat on the short side; and

(E) One drop on a corner at the junction of three intersecting edges; and

(ii) A compressive load as specified in § 178.606(c) of this subchapter. Each of the tests in this paragraph (e)(5) may be performed on a different but identical package; that is, all tests need not be performed on the same package.

(6) Placement of the material in the package or packing different materials in the package does not result in a violation of § 173.21;

(7) The aggregate quantity of hazardous material per package does not exceed 100 g (0.22 pounds) for solids or 100 mL (3.38 ounces) for liquids;

(8) The gross mass of the completed package does not exceed 29 kg (64 pounds);

(9) The package is not opened or otherwise altered until it is no longer in commerce; and

(10) For transportation by aircraft:

(i) The hazardous material is authorized to be carried aboard passenger-carrying aircraft in Column 9A of the § 172.101 Hazardous Materials Table;

(ii) The hazardous material may not be carried in checked or carry-on baggage.

[Amdt. 173-224, 55 FR 52608, Dec. 21, 1990, as amended at 56 FR 66265, Dec. 20, 1991; Amdt. 173-234, 58 FR 51531, Oct. 1, 1993; Amdt. 173-244, 60 FR 50307, Sept. 28, 1995; Amdt. 173-253, 61 FR 27173, May 30, 1996; 65 FR 50460, Aug. 18, 2000; 65 FR 58628, Sept. 29, 2000; 66 FR 33426, June 21, 2001; 66 FR 45183, 45379, 45381, Aug. 28, 2001; 67 FR 61013, Sept. 27, 2002; 69 FR 75216, Dec. 15, 2004; 70 FR 56098, Sept. 23, 2005; 71 FR 14602, Mar. 22, 2006; 73 FR 4716, Jan. 28, 2008]

#### § 173.5 Agricultural operations.

(a) For other than a Class 2 material, the transportation of an agricultural product over local roads between fields of the same farm is excepted from the requirements of this subchapter. A Class 2 material transported over local roads between fields of the same farm is excepted from subparts G and H of part 172 of this subchapter. In either instance, transportation of the hazardous material is subject to the following conditions:

(1) It is transported by a farmer who is an intrastate private motor carrier; and

(2) The movement of the agricultural product conforms to requirements of the State in which it is transported and is specifically authorized by a State statute or regulation in effect before October 1, 1998.

(b) The transportation of an agricultural product to or from a farm, within 150 miles of the farm, is excepted from the requirements in subparts G and H of part 172 of this subchapter and from the specific packaging requirements of this subchapter when:

(1) It is transported by a farmer who is an intrastate private motor carrier;

(2) The total amount of agricultural product being transported on a single motor vehicle does not exceed:

(i) 7,300 kg (16,094 lbs.) of ammonium nitrate fertilizer properly classed as Division 5.1, PG III, in a bulk packaging, or

(ii) 1900 L (502 gallons) for liquids or gases, or 2,300 kg (5,070 lbs.) for solids, of any other agricultural product;

(3) The movement and packaging of the agricultural product conform to the requirements of the State in which it is transported and are specifically

authorized by a State statute or regulation in effect before October 1, 1998; and

(4) Each person having any responsibility for transporting the agricultural product or preparing the agricultural product for shipment has been instructed in the applicable requirements of this subchapter.

(c) Formulated liquid agricultural products in specification packagings of 220 L (58 gallons) capacity, or less, with closures manifolded to a closed mixing system and equipped with positive dry disconnect devices may be transported by a private motor carrier between a final distribution point and an ultimate point of application or for loading aboard an airplane for aerial application.

(d) See §173.315(m) pertaining to nurse tanks of anhydrous ammonia.

(e) See §173.6 pertaining to materials of trade.

(f) See §172.800(b) pertaining to security plans.

[Amdt. 173-259, 62 FR 1215, Jan. 8, 1997, as amended by Amdt. 173-262, 62 FR 49566, Sept. 22, 1997; Amdt. 173-259, 63 FR 8142, Feb. 18, 1998; 65 FR 50460, Aug. 18, 2000; 70 FR 73165, Dec. 9, 2005; 73 FR 4717, Jan. 28, 2008]

#### § 173.5a Oilfield service vehicles and mechanical displacement meter provers.

(a) *Oilfield service vehicles.* Notwithstanding §173.29 of this subchapter, a cargo tank motor vehicle used in oilfield servicing operations is not subject to the specification requirements of this subchapter provided—

(1) The cargo tank and equipment contains only residual amounts (*i.e.*, it is emptied so far as practicable) of a flammable liquid alone or in combination with water,

(2) No flame producing device is operated during transportation, and

(3) The proper shipping name is preceded by “RESIDUE: LAST CONTAINED \* \* \*” on the shipping paper for each movement on a public highway.

(b) *Mechanical displacement meter provers.* (1) For purposes of this section, a mechanical displacement meter prover is a mechanical device, permanently mounted on a truck chassis or trailer

## § 173.6

## 49 CFR Ch. I (10–1–08 Edition)

and transported by motor vehicle, consisting of a pipe assembly that is used to calibrate the accuracy and performance of meters that measure the quantity of a product being pumped or transferred at facilities such as drilling locations, refineries, tank farms and loading racks.

(2) A mechanical displacement meter prover is excepted from the specification packaging requirements in part 178 of this subchapter provided it—

(i) Contains only the residue of a Class 3 or Division 2.1 material. For liquids, the meter prover must be drained to the maximum extent practicable and may not exceed 10% of its capacity; for gases, the meter prover must not exceed 25% of the marked pressure rating;

(ii) Has a water capacity of 3,785 L (1,000 gallons) or less;

(iii) Is designed and constructed in accordance with chapters II, III, IV, V and VI of the ASME Standard B31.4 (IBR, see § 171.7 of this subchapter);

(iv) Is marked with the maximum service pressure determined from the pipe component with the lowest pressure rating; and

(v) Is equipped with rear-end protection as prescribed in § 178.337–10(c) of this subchapter and with 49 CFR 393.86 of the Federal Motor Carrier Safety Regulations.

(3) The description on the shipping paper for a meter prover containing the residue of a hazardous material must include the phrase “RESIDUE: LAST CONTAINED \* \* \* ” before the basic description.

(4) *Periodic test and inspection.* (i) Each meter prover must be externally visually inspected once a year. The external visual inspection must include at a minimum: checking for leakage, defective fittings and welds, defective closures, significant dents and other defects or abnormalities which indicate a potential or actual weakness that could render the meter prover unsafe for transportation; and

(ii) Each meter prover must be pressure tested once every 5 years at not less than 75% of design pressure. The pressure must be held for a period of time sufficiently long to assure detection of leaks, but in no case less than 5 minutes.

(5) In addition to the training requirements in subpart H, the person who performs the visual inspection or pressure test and/or signs the inspection report must have the knowledge and ability to perform them as required by this section.

(6) A meter prover that fails the periodic test and inspection, must be rejected and removed from hazardous materials service unless the meter prover is adequately repaired, and thereafter, a successful test is conducted in accordance with the requirements of this section.

(7) Prior to any repair work, the meter prover must be emptied of any hazardous material. A meter prover containing flammable lading must be purged.

(8) Each meter prover successfully completing the external visual inspection and the pressure test must be marked with the test date (month/year), the type of test or inspection as follows:

(i) V for external visual inspection; and

(ii) P for pressure test.

The marking must be on the side of a tank or the largest piping component in letters 32 mm (1.25 inches) high on a contrasting background.

(9) The owner must retain a record of the most recent external visual inspection and pressure test until the next test or inspection of the same type successfully completed. The test or inspection report must include the following:

(i) Serial number or other meter prover identifier;

(ii) Type of test or inspection performed;

(iii) Test date (month/year);

(iv) Location of defects found, if any, and method used to repair each defect;

(v) Name and address of person performing the test or inspection;

(vi) Disposition statement, such as “Meter Prover returned to service” or “Meter Prover removed from service”.

[70 FR 3308, Jan. 24, 2005]

### § 173.6 Materials of trade exceptions.

When transported by motor vehicle in conformance with this section, a material of trade (see § 171.8 of this subchapter) is not subject to any other requirements of this subchapter besides

those set forth or referenced in this section.

(a) *Materials and amounts.* A material of trade is limited to the following:

(1) A Class 3, 8, 9, Division 4.1, 5.1, 5.2, 6.1, or ORM-D material contained in a packaging having a gross mass or capacity not over—

(i) 0.5 kg (1 pound) or 0.5 L (1 pint) for a Packing Group I material;

(ii) 30 kg (66 pounds) or 30 L (8 gallons) for a Packing Group II, Packing Group III, or ORM-D material;

(iii) 1500 L (400 gallons) for a diluted mixture, not to exceed 2 percent concentration, of a Class 9 material.

(2) A Division 2.1 or 2.2 material in a cylinder with a gross weight not over 100 kg (220 pounds), or a permanently mounted tank manufactured to the ASME Code of not more than 70 gallon water capacity for a non-liquefied Division 2.2 material with no subsidiary hazard.

(3) A Division 4.3 material in Packing Group II or III contained in a packaging having a gross capacity not exceeding 30 mL (1 ounce).

(4) A Division 6.2 material, other than a Category A infectious substance, contained in human or animal samples (including, but not limited to, secret, excreta, blood and its components, tissue and tissue fluids, and body parts) being transported for research, diagnosis, investigational activities, or disease treatment or prevention, or is a biological product or regulated medical waste. The material must be contained in a combination packaging. For liquids, the inner packaging must be leakproof, and the outer packaging must contain sufficient absorbent material to absorb the entire contents of the inner packaging. For sharps, the inner packaging (sharps container) must be constructed of a rigid material resistant to punctures and securely closed to prevent leaks or punctures, and the outer packaging must be securely closed to prevent leaks or punctures. For solids, liquids, and sharps, the outer packaging must be a strong, tight packaging securely closed and secured against shifting, including relative motion between packages, within the vehicle on which it is being transported.

(i) For other than a regulated medical waste, the amount of Division 6.2 material in a combination packaging must conform to the following limitations:

(A) One or more inner packagings, each of which may not contain more than 0.5 kg (1.1 lbs) or 0.5 L (17 ounces), and an outer packaging containing not more than 4 kg (8.8 lbs) or 4 L (1 gallon); or

(B) A single inner packaging containing not more than 16 kg (35.2 lbs) or 16 L (4.2 gallons) in a single outer packaging.

(ii) For a regulated medical waste, a combination packaging must consist of one or more inner packagings, each of which may not contain more than 4 kg (8.8 lbs) or 4 L (1 gallon), and an outer packaging containing not more than 16 kg (35.2 lbs) or 16 L (4.2 gallons).

(5) This section does not apply to a hazardous material that is self-reactive (see §173.124), poisonous by inhalation (see §173.133), or a hazardous waste.

(b) *Packaging.* (1) Packagings must be leak tight for liquids and gases, sift proof for solids, and be securely closed, secured against shifting, and protected against damage.

(2) Each material must be packaged in the manufacturer's original packaging, or a packaging of equal or greater strength and integrity.

(3) Outer packagings are not required for receptacles (e.g., cans and bottles) that are secured against shifting in cages, carts, bins, boxes or compartments.

(4) For gasoline, a packaging must be made of metal or plastic and conform to the requirements of this subchapter or to the requirements of the Occupational Safety and Health Administration of the Department of Labor contained in 29 CFR 1910.106(d)(2) or 1926.152(a)(1).

(5) A cylinder or other pressure vessel containing a Division 2.1 or 2.2 material must conform to packaging, qualification, maintenance, and use requirements of this subchapter, except that outer packagings are not required. Manifolding of cylinders is authorized provided all valves are tightly closed.

(c) *Hazard communication.* (1) A non-bulk packaging other than a cylinder (including a receptacle transported



without an outer packaging) must be marked with a common name or proper shipping name to identify the material it contains, including the letters “RQ” if it contains a reportable quantity of a hazardous substance.

(2) A bulk packaging containing a diluted mixture of a Class 9 material must be marked on two opposing sides with the four-digit identification number of the material. The identification number must be displayed on placards, orange panels or, alternatively, a white square-on-point configuration having the same outside dimensions as a placard (at least 273 mm (10.8 inches) on a side), in the manner specified in § 172.332 (b) and (c) of this subchapter.

(3) A DOT specification cylinder (except DOT specification 39) must be marked and labeled as prescribed in this subchapter. Each DOT-39 cylinder must display the markings specified in 178.65(i).

(4) The operator of a motor vehicle that contains a material of trade must be informed of the presence of the hazardous material (including whether the package contains a reportable quantity) and must be informed of the requirements of this section.

(d) *Aggregate gross weight.* Except for a material of trade authorized by paragraph (a)(1)(iii) of this section, the aggregate gross weight of all materials of trade on a motor vehicle may not exceed 200 kg (440 pounds).

(e) *Other exceptions.* A material of trade may be transported on a motor vehicle under the provisions of this section with other hazardous materials without affecting its eligibility for exceptions provided by this section.

[Amdt. 173–259, 62 FR 1216, Jan. 8, 1997, as amended by Amdt. 173–262, 62 FR 49566, Sept. 22, 1997; 62 FR 51560, Oct. 1, 1997; Amdt. 173–259, 63 FR 8142, Feb. 18, 1998; 63 FR 52849, Oct. 1, 1998; 66 FR 45381, Aug. 28, 2001; 67 FR 53137, Aug. 14, 2002; 68 FR 75742, Dec. 31, 2003; 68 FR 61941, Oct. 30, 2003; 71 FR 32258, June 2, 2006; 72 FR 55692, Oct. 1, 2007]

#### § 173.7 Government operations and materials.

(a) Hazardous materials offered for transportation by, for, or to the Department of Defense (DOD) of the U.S. Government, including commercial shipments pursuant to a DOD contract, must be packaged in accordance with

the regulations in this subchapter or in packagings of equal or greater strength and efficiency as certified by DOD in accordance with the procedures prescribed by “Packaging of Hazardous Material, DLAD 4145.41/AR 700–143/AFJI 24–210/NAVSUPINST 4030.55B/MCO 4030.40B (IBR, see § 171.7 of this subchapter).” Hazardous materials offered for transportation by DOD under this provision may be reshipped by any shipper to any consignee provided the original packaging has not been damaged or altered in any manner.

(1) Hazardous materials sold by the DOD in packagings that are not marked in accordance with the requirements of this subchapter may be shipped from DOD installations if the DOD certifies in writing that the packagings are equal to or greater in strength and efficiency than the packaging prescribed in this subchapter. The shipper shall obtain such a certification in duplicate for each shipment. He shall give one copy to the originating carrier and retain the other for no less than 1 year.

(2) [Reserved]

(b) Shipments of hazardous materials, made by or under the direction or supervision of the U.S. Department of Energy (DOE) or the Department of Defense (DOD), for the purpose of national security, and which are escorted by personnel specifically designated by or under the authority of those agencies, are not subject to the requirements of this subchapter. For transportation by a motor vehicle or a rail car, the escorts must be in a separate transport vehicle from the transport vehicle carrying the hazardous materials that are excepted by this paragraph. A document certifying that the shipment is for the purpose of national security must be in the possession of the person in charge of providing security during transportation.

(c) Shipments of explosive samples, not exceeding 1 g net weight, offered by and consigned to the Bureau of Alcohol, Tobacco and Firearms (ATF) of the Department of the Treasury are not otherwise subject to the regulations in parts 110–189 of this subchapter when placed in a specifically designed multi-unit assembly packed in a strong outside packaging. The packaging

must be of a type accepted by ATF as capable of precluding a propagation of any explosion outside the packaging. The second component from the outside of the packaging must be marked or tagged to indicate the presence of an explosive.

(d) Notwithstanding the requirements of §§173.416 and 173.417 of this subchapter, packagings made by or under the direction of the U.S. Department of Energy may be used for the transportation of Class 7 materials when evaluated, approved, and certified by the Department of Energy against packaging standards equivalent to those specified in 10 CFR part 71. Packages shipped in accordance with this paragraph shall be marked and otherwise prepared for shipment in a manner equivalent to that required by this subchapter for packagings approved by the Nuclear Regulatory Commission.

(e) Class 1 (explosive) materials owned by the Department of Defense and packaged prior to January 1, 1990, in accordance with the requirements of this subchapter in effect at that time, are excepted from the marking and labeling requirements of part 172 of this subchapter and the packaging and package marking requirements of part 178 of this subchapter, provided the packagings have maintained their integrity and the explosive material is declared as "government-owned goods packaged prior to January 1, 1990" on the shipping papers. In addition, packages of these materials owned by the Department of Defense that are marked and labeled in conformance with the requirements of the HMR that were in effect at the time they were originally marked and labeled are excepted from the current marking and labeling requirements.

(f) The requirements of this subchapter do not apply to shipments of hazardous materials carried aboard an aircraft that is not owned by a government or engaged in carrying persons or property for commercial purposes, but is under the exclusive direction and control of the government for a period of not less than 90 days as specified in a written contract or lease. An aircraft is under the exclusive direction and control of a government when the government exercises responsibility for:

(1) Approving crew members and determining they are qualified to operate the aircraft;

(2) Determining the airworthiness and directing maintenance of the aircraft; and

(3) Dispatching the aircraft, including the times of departure, airports to be used, and type and amount of cargo to be carried.

[29 FR 18671, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §173.7, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 173.8 Exceptions for non-specification packagings used in intrastate transportation.**

(a) *Non-specification bulk packagings.* Notwithstanding requirements for specification packagings in subpart F of this part and parts 178 and 180 of this subchapter, a non-specification bulk packaging may be used for transportation of a hazardous material by an intrastate motor carrier until July 1, 2000, in accordance with the provisions of paragraph (d) of this section.

(b) *Non-specification cargo tanks for petroleum products.* Notwithstanding requirements for specification packagings in subpart F of this part and parts 178 and 180 of this subchapter, a non-specification cargo tank motor vehicle having a capacity of less than 13,250 L (3,500 gallons) may be used by an intrastate motor carrier for transportation of a flammable liquid petroleum product in accordance with the provisions of paragraph (d) of this section.

(c) *Permanently secured non-bulk tanks for petroleum products.* Notwithstanding requirements for specification packagings in subpart F of this part 173 and parts 178 and 180 of this subchapter, a non-specification metal tank permanently secured to a transport vehicle and protected against leakage or damage in the event of a turnover, having a capacity of less than 450 L (119 gallons), may be used by an intrastate motor carrier for transportation of a flammable liquid petroleum product in accordance with the provisions of paragraph (d) of this section.

## § 173.9

## 49 CFR Ch. I (10–1–08 Edition)

(d) *Additional requirements.* A packaging used under the provisions of paragraphs (a), (b) or (c) of this section must—

(1) Be operated by an intrastate motor carrier and in use as a packaging for hazardous material before October 1, 1998;

(2) Be operated in conformance with the requirements of the State in which it is authorized;

(3) Be specifically authorized by a State statute or regulation in effect before October 1, 1998, for use as a packaging for the hazardous material being transported;

(4) Be offered for transportation and transported in conformance with all other applicable requirements of this subchapter;

(5) Not be used to transport a flammable cryogenic liquid, hazardous substance, hazardous waste, or a marine pollutant (except for gasoline); and

(6) On and after July 1, 2000, for a tank authorized under paragraph (b) or (c) of this section, conform to all requirements in part 180 (except for §180.405(g)) of this subchapter in the same manner as required for a DOT specification MC 306 cargo tank motor vehicle.

[Amdt. 173–259, 62 FR 1216, Jan. 8, 1997, as amended by Amdt. 172–262, 62 FR 49567, Sept. 22, 1997; Amdt. 173–259, 63 FR 8142, Feb. 18, 1998; 66 FR 45380, Aug. 28, 2001]

### **§ 173.9 Transport vehicles or freight containers containing lading which has been fumigated.**

(a) For the purpose of this section, not including 49 CFR part 387, a rail car, freight container, truck body, or trailer in which the lading has been fu-

migated with any material, or is undergoing fumigation, is a package containing a hazardous material.


(b) No person may offer for transportation or transport a rail car, freight container, truck body, or trailer in which the lading has been fumigated or treated with any material, or is undergoing fumigation, unless the FUMIGANT marking specified in paragraph (e) of this section is prominently displayed so that it can be seen by any person attempting to enter the interior of the transport vehicle or freight container. For domestic transportation, a hazard warning label authorized by EPA under 40 CFR part 156 may be used as an alternative to the FUMIGANT marking.

(c) No person may affix or display on a rail car, freight container, truck body, or trailer the FUMIGANT marking specified in paragraph (e) of this section, unless the lading has been fumigated or is undergoing fumigation.

(d) The FUMIGANT marking required by paragraph (b) of this section must remain on the rail car, freight container, truck body, or trailer until the rail car, freight container, truck body, or trailer has been completely ventilated either by opening the doors of the unit or by mechanical ventilation to ensure no harmful concentration of gas remains after fumigation has been completed.

(e) *FUMIGANT marking.* (1) The FUMIGANT marking must consist of red or black letters on a white background that is at least 30 cm (11.8 inches) wide and at least 25 cm (9.8 inches) high. Except for size and color, the FUMIGANT marking must be as follows:

# DANGER



**THIS UNIT IS UNDER FUMIGATION  
WITH \* \_\_\_\_\_ APPLIED ON**

**Date** \_\_\_\_\_

**Time** \_\_\_\_\_

**Ventilated on** \_\_\_\_\_

# DO NOT ENTER

(2) The “\*” shall be replaced with the technical name of the fumigant.

(f) A closed cargo transport unit that has been fumigated is not subject to any other provisions of this subchapter if it—

(1) Has been completely ventilated either by opening the doors of the unit or by mechanical ventilation after fumigation, and

(2) Displays the FUMIGANT marking, including the date of ventilation.

(g) For international shipments, transport documents should indicate the date of fumigation, type and amount of fumigant used, and instructions for disposal of any residual fumigant, including fumigation devices.

(h) Any person subject to the requirements of this section, solely due to the fumigated lading, must be informed of the requirements of this section and the safety precautions necessary to protect themselves and others in the event of an incident or accident involving the fumigated lading.

(i) Any person who offers for transportation or transports a rail car, freight container, truck body or trailer that is subject to this subchapter solely because of the hazardous materials designation specified in paragraph (a) of this section is not subject to any requirements of this subchapter other than those contained in this section.

[71 FR 78629, Dec. 29, 2006]

**§ 173.10 Tank car shipments.**

(a) Tank cars containing any 2.1 material (including a cryogenic liquid) or Class 3 material with a flash point below 38 °C (100 °F), except liquid road asphalt or tar, may not be offered for transportation unless originally consigned or subsequently reconsigned to parties having private-siding (see Note 1 of this section) or to parties using railroad siding facilities which have been equipped for piping the liquid from tank cars to permanent storage tanks of sufficient capacity to receive contents of car.

(b) A tank car containing any Class 2 material must not be offered for transportation unless the car is consigned for delivery (see paragraph (c) of this section) and unloading on a private track (see Note 1 of this section) except that where no private track is available, delivery and unloading on carrier tracks is permitted provided the following conditions are complied with:

(1) Any tank car of DOT-106A or 110A type (see §§179.300 and 179.301 of this subchapter) may be offered for transportation and the loaded unit tanks may be removed from car frame on carrier tracks, provided the shipper has obtained from the delivering carrier and filed with originating carrier, written permission (see Note 2 of this sec-

tion) for such removal. The consignee must furnish adequately safe mechanical hoist, obtained from the carrier if desirable, by which the tanks shall be lifted from the car and deposited directly upon vehicles furnished by the consignee for immediate removal from carrier property or tanks must be lifted by adequately safe mechanical hoist from car directly to vessels for further transportation.

(c) Any tank car of other than DOT-106A or 110A type (see §§179.300 and 179.301 of this subchapter), containing anhydrous ammonia, liquefied hydrocarbon or liquefied petroleum gas, and having interior pipes of liquid and gas discharge valves equipped with check valves, may be consigned for delivery and unloading on carrier tracks, if the lading is piped directly from the car to permanent storage tanks of sufficient capacity to receive the entire contents of the car. Such cars may also be consigned for storage on a private track or on a carrier track when designated by the carrier for such storage.

(d) For cars of the DOT-106A or 110A type (see §§179.300 and 179.301 of this subchapter), the tanks must be placed in position and attached to the car structure by the shipper.

(e) Class 3 materials with a flash point below 38 °C (100 °F) and Division 2.1 materials (including a cryogenic liquid) may not be loaded into tank cars on carrier property from tank trucks or drums.

NOTE 1: For this purpose, a private track is a track outside of carrier's right-of-way, yard, and terminals, and of which the carrier does not own either the rails, ties, roadbed or right-of-way; or a track or portion of a track which is devoted to the purpose of its user, either by lease or written agreement; in which case the lease or written agreement will be considered as equivalent to ownership.

NOTE 2: Carriers should give permission for the unloading of these containers on carrier tracks only where no private siding is available within reasonable trucking distance of final destination. The danger involved is the release of compressed gases due to accidental

damage to container in handling. The exposure to this danger decreases directly with the isolation of the unloading point.

[29 FR 18773, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and by Amdt. 173-162, 48 FR 10226, Mar. 10, 1983, and amended by Amdt. 173-180, 49 FR 42735, Oct. 24, 1984; Amdt. 173-207, 53 FR 38274, Sept. 29, 1988; Amdt. 173-224, 55 FR 52608, Dec. 21, 1990; 56 FR 66265, Dec. 20, 1991; Amdt. 173-234, 58 FR 51532, Oct. 1, 1993; 67 FR 61013, Sept. 27, 2002]

#### § 173.12 Exceptions for shipment of waste materials.

(a) *Open head drums.* If a hazardous material that is a hazardous waste is required by this subchapter to be shipped in a closed head drum (i.e., a drum with a 7.0 cm (3 inches) or less bung opening) and the hazardous waste contains solids or semisolids that make its placement in a closed head drum impracticable, an equivalent (except for closure) open head drum may be used for the hazardous waste.

(b) *Lab packs.* (1) Waste materials classed as Class or Division 3, 4.1, 4.2, 4.3, 5.1, 6.1, 8, or 9 are excepted from the specification packaging requirements of this subchapter for combination packagings if packaged in accordance with this paragraph and transported for disposal or recovery by highway, rail or cargo vessel only. In addition, a generic description from the § 172.101 table may be used in place of specific chemical names, when two or more chemically compatible waste materials in the same hazard class are packaged in the same outside packaging.

(2) Additional packaging requirements are as follows:

(i) The outer packaging must be a UN 1A2 or UN 1B2 metal drum, a UN 1D plywood drum, a UN 1G fiber drum or a UN 1H2 plastic drum tested and marked at least for the Packing Group III performance level for liquids or solids;

(ii) The inner packagings must be either glass, not exceeding 4 L (1 gallon) rated capacity, or metal or plastic, not exceeding 20 L (5.3 gallons) rated capacity;

(iii) Each outer packaging may contain only one class of hazardous material;

(iv) Inner packagings containing liquid must be surrounded by a chemically compatible absorbent material in

sufficient quantity to absorb the total liquid contents; and

(v) Gross weight of the complete package may not exceed 205 kg (452 lbs).

(3) *Prohibited materials.* The following materials may not be packaged or described under the provisions of this paragraph (b): a material poisonous by inhalation, a Division 6.1 Packing Group I material, a Division 4.2 Packing Group I material, chloric acid and oleum (fuming sulfuric acid).

(c) *Reuse of packagings.* A previously used packaging may be reused for the shipment of waste material transported for disposal or recovery, not subject to the reconditioning and reuse provisions contained in § 173.28 and part 178 of this subchapter, under the following conditions:

(1) Except as authorized by this paragraph, the waste must be packaged in accordance with this part and offered for transportation in accordance with the requirements of this subchapter.

(2) Transportation is performed by highway only.

(3) A package is not offered for transportation less than 24 hours after it is finally closed for transportation, and each package is inspected for leakage and is found to be free from leaks immediately prior to being offered for transportation.

(4) Each package is loaded by the shipper and unloaded by the consignee, unless the motor carrier is a private or contract carrier.

(5) The packaging may be used only once under this paragraph and may not be used again for shipment of hazardous materials except in accordance with § 173.28.

(d) *Technical names for n.o.s. descriptions.* The requirements for the inclusion of technical names for n.o.s. descriptions on shipping papers and package markings, §§ 172.203 and 172.301 of this subchapter, respectively, do not apply to packages prepared in accordance with paragraph (b) of this section, except that packages containing materials meeting the definition of a hazardous substance must be described as required in § 172.203 of this subchapter and marked as required in § 172.324 of this subchapter.

### § 173.13

### 49 CFR Ch. I (10–1–08 Edition)

(e) *Exceptions from segregation requirements.* (1) The provisions of §§ 174.81(c), 176.83(b) and 177.848(c) of this subchapter do not apply to waste cyanides or waste cyanide mixtures or solutions stored, loaded, or transported with acids in accordance with the following:

(i) The waste cyanides or waste cyanide mixtures or solutions must be packaged in lab packs in accordance with paragraph (b) of this section;

(ii) The acids must be packaged in lab packs in accordance with paragraph (b) of this section or in authorized single packagings not exceeding 208 L (55 gallons) capacity;

(iii) Waste cyanides or waste cyanide mixtures may not exceed 2 kg (4.4 pounds) per inner receptacle and may not exceed 10 kg (22 pounds) per outer packaging; waste cyanide solutions may not exceed 2 L (0.6 gallon) per inner receptacle and may not exceed 10 L (3.0 gallons) per outer packaging.

(iv) The waste cyanides or waste cyanide mixtures or solutions must be—

(A) Separated from the acids by a minimum horizontal distance of 1.2 m (4 feet); and

(B) Loaded at least 100 mm (4 inches) off the floor of the freight container, unit load device, transport vehicle or rail car.

(2) The provisions of §§ 174.81(d), 176.83(b) and 177.848(d) of this subchapter do not apply to waste Division 4.2 materials stored, loaded or transported with Class 8 liquids in accordance with the following:

(i) The waste Division 4.2 materials are packaged in lab packs in accordance with paragraph (b) of this section;

(ii) The Class 8 liquids are packaged in lab packs in accordance with paragraph (b) of this section or in authorized single packagings not exceeding 208 L (55 gallons) capacity;

(iii) The waste Division 4.2 materials may not exceed 2 kg (4.4 pounds) per inner receptacle and may not exceed 10 kg (22 pounds) per outer packaging;

(iv) The waste Division 4.2 materials must be separated from the Class 8 liquids by a minimum horizontal distance of 1.2 m (4 feet);

(v) The waste Division 4.2 materials and the Class 8 liquids are loaded at least 100 mm (4 inches) off the floor of

the freight container, unit load device, transport vehicle or rail car.

(f) *Household waste.* Household waste, as defined in § 171.8 of this subchapter, is not subject to the requirements of this subchapter.

[Amdt. 173–224, 55 FR 52609, Dec. 21, 1990, as amended at 56 FR 66265, Dec. 20, 1991; Amdt. 173–231, 57 FR 52939, Nov. 5, 1992; Amdt. 173–138, 59 FR 49133, Sept. 26, 1994; 65 FR 50460, Aug. 18, 2000; 65 FR 58629, Sept. 29, 2000; 68 FR 48569, Aug. 14, 2003; 70 FR 3309, Jan. 24, 2005; 73 FR 4717, Jan. 28, 2008]

### § 173.13 Exceptions for Class 3, Divisions 4.1, 4.2, 4.3, 5.1, 6.1, and Classes 8 and 9 materials.

(a) A Class 3, 8 or 9, or Division 4.1, 4.2, 4.3, 5.1, or 6.1 material is excepted from the labeling (except for the CARGO AIRCRAFT ONLY label), placarding and segregation requirements of this subchapter if prepared for transportation in accordance with the requirements of this section. A material that meets the definition of a material poisonous by inhalation may not be offered for transportation or transported under provisions of this section.

(b) A hazardous material conforming to the requirements of this section may be transported by motor vehicle and rail car. In addition, packages prepared in accordance with this section may be transported by aircraft under the following conditions:

(1) *Cargo-only aircraft.* Only hazardous materials permitted to be transported aboard either a passenger or cargo-only aircraft by column (9A) or (9B) of the Hazardous Materials Table in § 172.101 of this subchapter are authorized aboard cargo-only aircraft.

(2) *Passenger carrying aircraft.* Only hazardous materials permitted to be transported aboard a passenger aircraft by column (9A) of the Hazardous Materials Table in § 172.101 of this subchapter are authorized aboard passenger aircraft. The completed package, assembled as for transportation, must be successfully tested in accordance with part 178 of this subchapter at the Packing Group I level. A hazardous material which meets the definition of a Division 5.1 (oxidizer) at the Packing Group I level in accordance with § 173.127(b)(1)(i) of this subchapter may not be transported aboard a passenger aircraft.

(3) Packages offered for transportation aboard either passenger or cargo-only aircraft must meet the requirements for transportation by aircraft specified in §173.27 of this subchapter.

(c) A hazardous material permitted by paragraph (a) of this section must be packaged as follows:

(1) For liquids:

(i) The hazardous material must be placed in a tightly closed glass, plastic or metal inner packaging with a maximum capacity not exceeding 1.2 L. Sufficient outage must be provided such that the inner packaging will not become liquid full at 55 °C (130 °F). The net quantity (measured at 20 °C (68 °F)) of liquid in any inner packaging may not exceed 1 L. For transportation by aircraft, the net quantity in one package may not exceed the quantity specified in columns (9A) or (9B), as appropriate.

(ii) The inner packaging must be placed in a hermetically sealed barrier bag which is impervious to the lading, and then wrapped in a non-reactive absorbent material in sufficient quantity to completely absorb the contents of the inner packaging, and placed in a snugly fitting, metal can.

(iii) The metal can must be securely closed. For liquids that are in Division 4.2 or 4.3, the metal can must be hermetically sealed. For Division 4.2 materials in Packing Group I, the metal can must be tested in accordance with part 178 of this subchapter at the Packing Group I performance level.

(iv) The metal can must be placed in a fiberboard box that is placed in a hermetically sealed barrier bag which is impervious to the lading.

(v) The intermediate packaging must be placed inside a securely closed, outer packaging conforming to §173.201.

(vi) Not more than four intermediate packagings are permitted in an outer packaging.

(2) For solids:

(i) The hazardous material must be placed in a tightly closed glass, plastic or metal inner packaging. The net quantity of material in any inner packaging may not exceed 2.85kg (6.25 pounds). For transportation by aircraft, the net quantity in one package

may not exceed the quantity specified in columns (9A) or (9B), as appropriate.

(ii) The inner packaging must be placed in a hermetically sealed barrier bag which is impervious to the lading.

(iii) The barrier bag and its contents must be placed in a fiberboard box that is placed in a hermetically-sealed barrier bag which is impervious to the lading.

(iv) The intermediate packaging must be placed inside an outer packaging conforming to §173.211.

(v) Not more than four intermediate packagings are permitted in an outer packaging.

(d) The outside of the package must be marked, in association with the proper shipping name, with the statement: "This package conforms to 49 CFR 173.13."

[Amdt. 173-253, 61 FR 27173, May 30, 1996, as amended at 65 FR 50460, Aug. 18, 2000; 66 FR 45381, Aug. 28, 2001; 70 FR 3309, Jan. 24, 2005; 71 FR 54395, Sept. 14, 2006]

## Subpart B—Preparation of Hazardous Materials for Transportation

### § 173.21 Forbidden materials and packages.

Unless otherwise provided in this subchapter, the offering for transportation or transportation of the following is forbidden:

(a) Materials that are designated "Forbidden" in Column 3 of the §172.101 table.

(b) Forbidden explosives as defined in §173.54 of this part.

(c) Electrical devices which are likely to create sparks or generate a dangerous quantity of heat, unless packaged in a manner which precludes such an occurrence.

(d) For carriage by aircraft, any package which has a magnetic field of more than 0.00525 gauss measured at 4.5 m (15 feet) from any surface of the package.

(e) A material in the same packaging, freight container, or overpack with another material, the mixing of which is likely to cause a dangerous evolution of heat, or flammable or poisonous gases or vapors, or to produce corrosive materials.



# § 173.21

# 49 CFR Ch. I (10–1–08 Edition)

(f) A package containing a material which is likely to decompose with a self-accelerated decomposition temperature (SADT) of 50 °C (122 °F) or less, or polymerize at a temperature of 54 °C (130 °F) or less with an evolution of a dangerous quantity of heat or gas when decomposing or polymerizing, unless the material is stabilized or inhibited in a manner to preclude such evolution. The SADT may be determined by any of the test methods described in Part II of the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter).

(1) A package meeting the criteria of paragraph (f) of this section may be required to be shipped under controlled temperature conditions. The control temperature and emergency temperature for a package shall be as specified in the table in this paragraph based upon the SADT of the material. The control temperature is the temperature above which a package of the material may not be offered for transportation or transported. The emergency temperature is the temperature at which, due to imminent danger, emergency measures must be initiated.

§ 173.21 TABLE: METHOD OF DETERMINING CONTROL AND EMERGENCY TEMPERATURE.

| SADT <sup>1</sup>                      | Control temperatures      | Emergency temperature     |
|----------------------------------------|---------------------------|---------------------------|
| SADT ≤ 20 °C (68 °F).                  | 20 °C (36 °F) below SADT. | 10 °C (18 °F) below SADT. |
| 20 °C (68 °F) < SADT ≤ 35 °C (95 °F).  | 15 °C (27 °F) below SADT. | 10 °C (18 °F) below SADT. |
| 35 °C (95 °F) < SADT ≤ 50 °C (122 °F). | 10 °C (18 °F) below SADT. | 5 °C (9 °F) below SADT.   |
| 50 °C (122 °F) < SADT.                 | ( <sup>2</sup> )          | ( <sup>2</sup> )          |

<sup>1</sup> Self-accelerating decomposition temperature.

<sup>2</sup> Temperature control not required.

(2) For self-reactive materials listed in §173.224(b) table control and emergency temperatures, where required are shown in Columns 5 and 6, respectively. For organic peroxides listed in The Organic Peroxides Table in §173.225 control and emergency temperatures, where required, are shown in Columns 7a and 7b, respectively.

(3) Refrigeration may be used as a means of stabilization only when ap-

proved by the Associate Administrator. Approvals issued by the Bureau of Explosives are no longer valid (see §171.19 of this subchapter). Methods of stabilization approved by the Associate Administrator are as follows:

(i) For highway transportation:

(A) A material meeting the criteria of this paragraph (f) may be transported only in a transport vehicle, freight container, or motor vehicle equipped with a mechanical refrigeration unit, or loaded with a consumable refrigerant, capable of maintaining the inside temperature of the hazardous material at or below the control temperature required for the material during transportation.

(B) Each package containing a material meeting the criteria of this paragraph (f) must be loaded and maintained at or below the control temperature required for the material. The temperature of the material must be determined by appropriate means and entered on a written record at the time the packaging is loaded.

(C) The vehicle operator shall monitor the inside temperature of the transport vehicle, freight container, or motor vehicle and enter that temperature on a written record at the time the package is loaded and thereafter at intervals not exceeding two hours. Alternatively, a transport vehicle, freight container, or motor vehicle may be equipped with a visible or audible warning device that activates when the inside temperature of the transport vehicle, freight container, or motor vehicle exceeds the control temperature required for the material. The warning device must be readily visible or audible, as appropriate, from the vehicle operator's seat in the vehicle.

(D) The carrier shall advise the vehicle operator of the emergency temperature for the material, and provide the vehicle operator with written procedures that must be followed to assure maintenance of the control temperature inside the transport vehicle, freight container, or motor vehicle. The written procedures must include instructions for the vehicle operator on actions to take if the inside temperature exceeds the control temperature and approaches or reaches the emergency temperature for the material. In

addition, the written temperature-control procedures must identify enroute points where the consumable refrigerant may be procured, or where repairs to, or replacement of, the mechanical refrigeration unit may be accomplished.

(E) The vehicle operator shall maintain the written temperature-control procedures, and the written record of temperature measurements specified in paragraph (f)(3)(i)(C) of this section, if applicable, in the same manner as specified in § 177.817 of this subchapter for shipping papers.

(F) If the control temperature is maintained by use of a consumable refrigerant (e.g., dry ice or liquid nitrogen), the quantity of consumable refrigerant must be sufficient to maintain the control temperature for twice the average transit time under normal conditions of transportation.

(G) A material that has a control temperature of 40 °C (104 °F) or higher may be transported by common carrier. A material that has a control temperature below 40 °C (104 °F) must be transported by a private or contract carrier.

(ii) For transportation by vessel, shipments are authorized in accordance with the control temperature requirements in Chapter 7.7 of the IMDG Code (IBR, see § 171.7 of this subchapter).

(g) Packages which give off a flammable gas or vapor, released from a material not otherwise subject to this subchapter, likely to create a flammable mixture with air in a transport vehicle.

(h) Packages containing materials (other than those classed as explosive) which will detonate in a fire.

(1) For purposes of this paragraph, “detonate” means an explosion in which the shock wave travels through the material at a speed greater than the speed of sound.

(2) When tests are required to evaluate the performance of a package under the provisions of this paragraph, the testing must be done or approved by one of the agencies specified in § 173.56.

(i) Except for a package containing a lighter design sample that meets the requirements of § 173.308(b)(2), a package containing a lighter (see § 171.8 of this subchapter) containing a Division

2.1 material, of a design that has not been examined and successfully tested by an authorized person under the criteria specified in § 173.308(a)(4) or, a lighter design containing a Class 3 material, that has not been approved by the Associate Administrator.

(j) An organic peroxide of the “ketone peroxide” category which contains more than 9 percent available oxygen as calculated using the equation in § 173.128(a)(4)(ii). The category, ketone peroxide, includes, but is not limited to:

Acetyl acetone peroxide  
Cyclohexanone peroxide(s)  
Diacetone alcohol peroxides  
Methylcyclohexanone peroxide(s)  
Methyl ethyl ketone peroxide(s)  
Methyl isobutyl ketone peroxide(s)

(k) Notwithstanding any other provision of this subchapter, including subpart C of part 171 and 175.10(a)(2) of this subchapter, an oxygen generator (chemical) as cargo on a passenger-carrying aircraft. This prohibition does not apply to an oxygen generator for medical or personal use of a passenger that meets the requirements of § 175.10(a)(7) of this subchapter.

[Amdt. 173–224, 55 FR 52609, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 173.21, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 173.22 Shipper's responsibility.

(a) Except as otherwise provided in this part, a person may offer a hazardous material for transportation in a packaging or container required by this part only in accordance with the following:

(1) The person shall class and describe the hazardous material in accordance with parts 172 and 173 of this subchapter, and

(2) The person shall determine that the packaging or container is an authorized packaging, including part 173 requirements, and that it has been manufactured, assembled, and marked in accordance with:

(i) Section 173.7(a) and parts 173, 178, or 179 of this subchapter;

(ii) A specification of the Department in effect at the date of manufacture of the packaging or container;

## § 173.22a

## 49 CFR Ch. I (10–1–08 Edition)

(iii) National or international regulations based on the UN Recommendations (IBR, see §171.7 of this subchapter), as authorized in §173.24(d)(2);

(iv) An approval issued under this subchapter; or

(v) An exemption or special permit issued under subchapter A of this chapter.

(3) In making the determination under paragraph (a)(2) of this section, the person may accept:

(i) Except for the marking on the bottom of a metal or plastic drum with a capacity over 100 L which has been reconditioned, remanufactured or otherwise converted, the manufacturer's certification, specification, approval, or exemption or special permit marking (see §§178.2 and 179.1 of this subchapter); or

(ii) With respect to cargo tanks provided by a carrier, the manufacturer's identification plate or a written certification of specification or exemption or special permit provided by the carrier.

(4) For a DOT Specification or UN standard packaging subject to the requirements of part 178 of this subchapter, a person must perform all functions necessary to bring the package into compliance with parts 173 and 178 of this subchapter, as identified by the packaging manufacturer or subsequent distributor (for example, applying closures consistent with the manufacturer's closure instructions) in accordance with §178.2 of this subchapter.

(b) No person may offer a motor carrier any hazardous material specified in 49 CFR 385.403 unless that motor carrier holds a safety permit issued by the Federal Motor Carrier Safety Administration.

(c) Prior to each shipment of fissile radioactive materials, and Type B or highway route controlled quantity packages of radioactive materials (see §173.403), the shipper shall notify the consignee of the dates of shipment and expected arrival. The shipper shall also notify each consignee of any special loading/unloading instructions prior to his first shipment. For any shipment of irradiated reactor fuel, the shipper shall provide physical protection in compliance with a plan established under:

(1) Requirements prescribed by the U.S. Nuclear Regulatory Commission, or

(2) Equivalent requirements approved by the Associate Administrator.

[Amdt. 173–100, 42 FR 2689, Jan. 13, 1977]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §173.22, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 173.22a Use of packagings authorized under special permits.

(a) Except as provided in paragraph (b) of this section, no person may offer a hazardous material for transportation in a packaging the use of which is dependent upon an exemption or special permit issued under subpart B of part 107 of this title, unless that person is the holder of or a party to the exemption or special permit.

(b) If an exemption or special permit authorizes the use of a packaging for the transportation of a hazardous material by any person or class of persons other than or in addition to the holder of the exemption or special permit, that person or a member of that class of persons may use the packaging for the purposes authorized in the exemption or special permit subject to the terms specified therein. Copies of exemptions and special permits may be obtained by accessing the Hazardous Materials Safety Web site at [http://hazmat.dot.gov/specialpermits\\_index.htm](http://hazmat.dot.gov/specialpermits_index.htm) or by writing to the Associate Administrator for Hazardous Materials Safety, U.S. Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590–0001, Attention: Records Center.

(c) When an exemption or special permit issued to a person who offers a hazardous material contains requirements that apply to a carrier of the hazardous material, the offeror shall furnish a copy of the current exemption or special permit to the carrier before or at the time a shipment is tendered.

[70 FR 73165, Dec. 9, 2005, as amended at 72 FR 55692, Oct. 1, 2007]

**§ 173.23 Previously authorized packaging.**

(a) When the regulations specify a packaging with a specification marking prefix of “DOT,” a packaging marked prior to January 1, 1970, with the prefix of “ICC” may be used in its place if the packaging otherwise conforms to applicable specification requirements.

(b) [Reserved]

(c) After July 2, 1982, a seamless aluminum cylinder manufactured in conformance with and for use under DOT special permit (SP) or exemption (E) 6498, 7042, 8107, 8364 or 8422 may be continued in use if marked before or at the time of the next retest with either the specification identification “3AL” immediately above the special permit or exemption number, or the DOT mark (e.g., DOT 3AL 1800) in proximity to the special permit or exemption marking.

(d) Cylinders (spheres) manufactured and marked under DOT special permit (SP) or exemption (E) 6616 prior to January 1, 1983, may be continued in use if marked before or at the time of the next retest with the specification identification “4BA” near the special permit or exemption marking.

(e) After October 1, 1984, cylinders manufactured for use under special permit (SP) or exemption (E) 6668 or 8404 may be continued in use, and must be marked “DOT-4LXXXXYY” (XXX to be replaced by the service pressure, YY to be replaced by the letters “AL”, if applicable) in compliance with Specification 4L (§178.57 of this subchapter) on or before January 1, 1986. The “DOT-4LXXXXYY” must appear in proximity to other required special permit or exemption markings.

(f) An MC 331 cargo tank motor vehicle must conform to structural integrity requirements in §178.337-3 or to corresponding requirements in effect at the time of manufacture.

(g) A non-bulk packaging manufactured, tested, marked, and certified on or before September 30, 1996, in accordance with the applicable provisions of subparts L and M of part 178 of this subchapter in effect on September 30, 1995, may be used as authorized by this subchapter if the packaging conforms to all requirements applicable at the

time of manufacture. In addition, such a packaging may be reused as authorized by §173.28 without a nominal thickness marking, if it conforms to the minimum thickness criteria prescribed in §173.28(b)(4).

(h) An exemption packaging or shipping paper that is permanently marked “DOT-E” prior to October 1, 2007, may continue in use as long as the exemption or special permit remains valid, unless otherwise specified in the exemption or special permit.

[Amdt. 173-3, 33 FR 14921, Oct. 4, 1968]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §173.23, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 173.24 General requirements for packagings and packages.**

(a) Applicability. Except as otherwise provided in this subchapter, the provisions of this section apply to—

- (1) Bulk and non-bulk packagings;
- (2) New packagings and packagings which are reused; and
- (3) Specification and non-specification packagings.

(b) Each package used for the shipment of hazardous materials under this subchapter shall be designed, constructed, maintained, filled, its contents so limited, and closed, so that under conditions normally incident to transportation—

(1) Except as otherwise provided in this subchapter, there will be no identifiable (without the use of instruments) release of hazardous materials to the environment;

(2) The effectiveness of the package will not be substantially reduced; for example, impact resistance, strength, packaging compatibility, etc. must be maintained for the minimum and maximum temperatures, changes in humidity and pressure, and shocks, loadings and vibrations, normally encountered during transportation;

(3) There will be no mixture of gases or vapors in the package which could, through any credible spontaneous increase of heat or pressure, significantly reduce the effectiveness of the packaging;

(4) There will be no hazardous material residue adhering to the outside of the package during transport.

(c) Authorized packagings. A packaging is authorized for a hazardous material only if—

(1) The packaging is prescribed or permitted for the hazardous material in a packaging section specified for that material in Column 8 of the §172.101 table and conforms to applicable requirements in the special provisions of Column 7 of the §172.101 table and, for specification packagings (but not including UN standard packagings manufactured outside the United States), the specification requirements in parts 178 and 179 of this subchapter; or

(2) The packaging is permitted under, and conforms to, provisions contained in subparts B or C of part 171 of this subchapter or §§173.3, 173.4, 173.5, 173.5a, 173.6, 173.7, 173.8, 173.27, or §176.11 of this subchapter.

(d) *Specification packagings and UN standard packagings manufactured outside the U.S.*—(1) *Specification packagings.* A specification packaging, including a UN standard packaging manufactured in the United States, must conform in all details to the applicable specification or standard in part 178 or part 179 of this subchapter.

(2) UN standard packagings manufactured outside the United States. A UN standard packaging manufactured outside the United States, in accordance with national or international regulations based on the UN Recommendations (IBR, see §171.7 of this subchapter), may be imported and used and is considered to be an authorized packaging under the provisions of paragraph (c)(1) of this section, subject to the following conditions and limitations:

(i) The packaging fully conforms to applicable provisions in the UN Recommendations and the requirements of this subpart, including reuse provisions;

(ii) The packaging is capable of passing the prescribed tests in part 178 of this subchapter applicable to that standard; and

(iii) The competent authority of the country of manufacture provides recip-

rocal treatment for UN standard packagings manufactured in the U.S.

(e) Compatibility. (1) Even though certain packagings are specified in this part, it is, nevertheless, the responsibility of the person offering a hazardous material for transportation to ensure that such packagings are compatible with their lading. This particularly applies to corrosivity, permeability, softening, premature aging and embrittlement.

(2) Packaging materials and contents must be such that there will be no significant chemical or galvanic reaction between the materials and contents of the package.

(3) Plastic packagings and receptacles. (i) Plastic used in packagings and receptacles must be of a type compatible with the lading and may not be permeable to an extent that a hazardous condition is likely to occur during transportation, handling or refilling.

(ii) Each plastic packaging or receptacle which is used for liquid hazardous materials must be capable of withstanding without failure the procedure specified in appendix B of this part (“Procedure for Testing Chemical Compatibility and Rate of Permeation in Plastic Packagings and Receptacles”). The procedure specified in appendix B of this part must be performed on each plastic packaging or receptacle used for Packing Group I materials. The maximum rate of permeation of hazardous lading through or into the plastic packaging or receptacles may not exceed 0.5 percent for materials meeting the definition of a Division 6.1 material according to §173.132 and 2.0 percent for other hazardous materials, when subjected to a temperature no lower than—

(A) 18 °C (64 °F) for 180 days in accordance with Test Method 1 in appendix B of this part;

(B) 50 °C (122 °F) for 28 days in accordance with Test Method 2 in appendix B of this part; or

(C) 60 °C (140 °F) for 14 days in accordance with Test Method 3 in appendix B of this part.

(iii) Alternative procedures or rates of permeation are permitted if they yield a level of safety equivalent to or

greater than that provided by paragraph (e)(3)(ii) of this section and are specifically approved by the Associate Administrator.

(4) Mixed contents. Hazardous materials may not be packed or mixed together in the same outer packaging with other hazardous or nonhazardous materials if such materials are capable of reacting dangerously with each other and causing—

(i) Combustion or dangerous evolution of heat;

(ii) Evolution of flammable, poisonous, or asphyxiant gases; or

(iii) Formation of unstable or corrosive materials.

(5) Packagings used for solids, which may become liquid at temperatures likely to be encountered during transportation, must be capable of containing the hazardous material in the liquid state.

(f) Closures. (1) Closures on packagings shall be so designed and closed that under conditions (including the effects of temperature, pressure and vibration) normally incident to transportation—

(i) Except as provided in paragraph (g) of this section, there is no identifiable release of hazardous materials to the environment from the opening to which the closure is applied; and

(ii) The closure is leakproof and secured against loosening. For air transport, stoppers, corks or other such friction closures must be held in place by positive means.

(2) Except as otherwise provided in this subchapter, a closure (including gaskets or other closure components, if any) used on a specification packaging must conform to all applicable requirements of the specification and must be closed in accordance with information, as applicable, provided by the manufacturer's notification required by §178.2 of this subchapter.

(g) Venting. Venting of packagings, to reduce internal pressure which may develop by the evolution of gas from the contents, is permitted only when—

(1) Except for shipments of cryogenic liquids as specified in §173.320(c) and of carbon dioxide, solid (dry ice), transportation by aircraft is not involved;

(2) Except as otherwise provided in this subchapter, the evolved gases are

not poisonous, likely to create a flammable mixture with air or be an asphyxiant under normal conditions of transportation;

(3) The packaging is designed so as to preclude an unintentional release of hazardous materials from the receptacle;

(4) For bulk packagings, other than IBCs, venting is authorized for the specific hazardous material by a special provision in the §172.101 table or by the applicable bulk packaging specification in part 178 of this subchapter; and

(5) Intermediate bulk packagings (IBCs) may be vented when required to reduce internal pressure that may develop by the evolution of gas subject to the requirements of paragraphs (g)(1) through (g)(3) of this section. The IBC must be of a type that has successfully passed (with the vent in place) the applicable design qualification tests with no release of hazardous material.

(h) Outage and filling limits—(1) *General*. When filling packagings and receptacles for liquids, sufficient ullage (outage) must be left to ensure that neither leakage nor permanent distortion of the packaging or receptacle will occur as a result of an expansion of the liquid caused by temperatures likely to be encountered during transportation. Requirements for outage and filling limits for non-bulk and bulk packagings are specified in §§173.24a(d) and 173.24b(a), respectively.

(2) *Compressed gases and cryogenic liquids*. Filling limits for compressed gases and cryogenic liquids are specified in §§173.301 through 173.306 for cylinders and §§173.314 through 173.319 for bulk packagings.

(i) *Air transportation*. Except as provided in subpart C of part 171 of this subchapter, packages offered or intended for transportation by aircraft must conform to the general requirements for transportation by aircraft in §173.27.

[Amdt. 173–224, 55 FR 52610, Dec. 21, 1990, as amended by Amdt. 173–227, 56 FR 49989, Oct. 2, 1991; 56 FR 66265, Dec. 20, 1991; Amdt. 173–238, 59 FR 38064, July 26, 1994; Amdt. 173–241, 59 FR 67491, Dec. 29, 1994; Amdt. 173–242, 60 FR 26805, May 18, 1995; 66 FR 8647, Feb. 1, 2001; 66 FR 45379, 81, Aug. 28, 2001; 68 FR 45032, July 31, 2003; 68 FR 75742, Dec. 31, 2003; 69 FR 76154, Dec. 20, 2004; 72 FR 25176, May 3, 2007; 73 FR 4717, Jan. 28, 2008]

**§ 173.24a Additional general requirements for non-bulk packagings and packages.**

(a) *Packaging design.* Except as provided in § 172.312 of this subchapter:

(1) *Inner packaging closures.* A combination packaging containing liquid hazardous materials must be packed so that closures on inner packagings are upright.

(2) *Friction.* The nature and thickness of the outer packaging must be such that friction during transportation is not likely to generate an amount of heat sufficient to alter dangerously the chemical stability of the contents.

(3) *Securing and cushioning.* Inner packagings of combination packagings must be so packed, secured and cushioned to prevent their breakage or leakage and to control their shifting within the outer packaging under conditions normally incident to transportation. Cushioning material must not be capable of reacting dangerously with the contents of the inner packagings or having its protective properties significantly weakened in the event of leakage.

(4) *Metallic devices.* Nails, staples and other metallic devices shall not protrude into the interior of the outer packaging in such a manner as to be likely to damage inner packagings or receptacles.

(5) *Vibration.* Each non-bulk package must be capable of withstanding, without rupture or leakage, the vibration test procedure specified in § 178.608 of this subchapter.

(b) *Non-bulk packaging filling limits.* (1) A single or composite non-bulk packaging may be filled with a liquid hazardous material only when the specific gravity of the material does not exceed that marked on the packaging, or a specific gravity of 1.2 if not marked, except as follows:

(i) A Packing Group I packaging may be used for a Packing Group II material with a specific gravity not exceeding the greater of 1.8, or 1.5 times the specific gravity marked on the packaging, provided all the performance criteria can still be met with the higher specific gravity material;

(ii) A Packing Group I packaging may be used for a Packing Group III material with a specific gravity not ex-

ceeding the greater of 2.7, or 2.25 times the specific gravity marked on the packaging, provided all the performance criteria can still be met with the higher specific gravity material; and

(iii) A Packing Group II packaging may be used for a Packing Group III material with a specific gravity not exceeding the greater of 1.8, or 1.5 times the specific gravity marked on the packaging, provided all the performance criteria can still be met with the higher specific gravity material.

(2) Except as otherwise provided in this section, a non-bulk packaging may not be filled with a hazardous material to a gross mass greater than the maximum gross mass marked on the packaging.

(3) A single or composite non-bulk packaging which is tested and marked for liquid hazardous materials may be filled with a solid hazardous material to a gross mass, in kilograms, not exceeding the rated capacity of the packaging in liters, multiplied by the specific gravity marked on the packaging, or 1.2 if not marked. In addition:

(i) A single or composite non-bulk packaging which is tested and marked for Packing Group I liquid hazardous materials may be filled with a solid Packing Group II hazardous material to a gross mass, in kilograms, not exceeding the rated capacity of the packaging in liters, multiplied by 1.5, multiplied by the specific gravity marked on the packaging, or 1.2 if not marked.

(ii) A single or composite non-bulk packaging which is tested and marked for Packing Group I liquid hazardous materials may be filled with a solid Packing Group III hazardous material to a gross mass, in kilograms, not exceeding the rated capacity of the packaging in liters, multiplied by 2.25, multiplied by the specific gravity marked on the packaging, or 1.2 if not marked.

(iii) A single or composite non-bulk packaging which is tested and marked for Packing Group II liquid hazardous materials may be filled with a solid Packing Group III hazardous material to a gross mass, in kilograms, not exceeding the rated capacity of the packaging in liters, multiplied by 1.5, multiplied by the specific gravity marked on the packaging, or 1.2 if not marked.

(4) Packagings tested as prescribed in § 178.605 of this subchapter and marked with the hydrostatic test pressure as prescribed in § 178.503(a)(5) of this subchapter may be used for liquids only when the vapor pressure of the liquid conforms to one of the following:

(i) The vapor pressure must be such that the total pressure in the packaging (i.e., the vapor pressure of the liquid plus the partial pressure of air or other inert gases, less 100 kPa (15 psia)) at 55 °C (131 °F), determined on the basis of a maximum degree of filling in accordance with paragraph (d) of this section and a filling temperature of 15 °C (59 °F)), will not exceed two-thirds of the marked test pressure;

(ii) The vapor pressure at 50 °C (122 °F) must be less than four-sevenths of the sum of the marked test pressure plus 100 kPa (15 psia); or

(iii) The vapor pressure at 55 °C (131 °F) must be less than two-thirds of the sum of the marked test pressure plus 100 kPa (15 psia).

(5) No hazardous material may remain on the outside of a package after filling.

(c) *Mixed contents.* (1) An outer non-bulk packaging may contain more than one hazardous material only when—

(i) The inner and outer packagings used for each hazardous material conform to the relevant packaging sections of this part applicable to that hazardous material;

(ii) The package as prepared for shipment meets the performance tests prescribed in part 178 of this subchapter for the packing group indicating the highest order of hazard for the hazardous materials contained in the package;

(iii) Corrosive materials (except ORM-D) in bottles are further packed in securely closed inner receptacles before packing in outer packagings; and

(iv) For transportation by aircraft, the total net quantity does not exceed the lowest permitted maximum net quantity per package as shown in Column 9a or 9b, as appropriate, of the § 172.101 table. The permitted maximum net quantity must be calculated in kilograms if a package contains both a liquid and a solid.

(2) A packaging containing inner packagings of Division 6.2 materials

may not contain other hazardous materials except—

(i) Refrigerants, such as dry ice or liquid nitrogen, as authorized under the HMR;

(ii) Anticoagulants used to stabilize blood or plasma; or

(iii) Small quantities of Class 3, Class 8, Class 9, or other materials in Packing Groups II or III used to stabilize or prevent degradation of the sample, provided the quantity of such materials does not exceed 30 mL (1 ounce) or 30 g (1 ounce) in each inner packaging. The maximum quantity in an outer package, including a hazardous material used to preserve or stabilize a sample, may not exceed 4 L (1 gallon) or 4 kg (8.8 pounds). Such preservatives are not subject to the requirements of this subchapter.

(d) Liquids must not completely fill a receptacle at a temperature of 55 °C (131 °F) or less.

[Amdt. 173–224, 55 FR 52611, Dec. 21, 1990, as amended at 56 FR 66265, Dec. 20, 1991; 57 FR 45460, Oct. 1, 1992; 58 FR 51532, Oct. 1, 1993; Amdt. 173–255, 61 FR 50624, Sept. 26, 1996; 66 FR 45380, Aug. 28, 2001; 68 FR 61941, Oct. 30, 2003; 71 FR 32258, June 2, 2006]

#### § 173.24b Additional general requirements for bulk packagings.

(a) *Outage and filling limits.* (1) Except as otherwise provided in this subchapter, liquids and liquefied gases must be so loaded that the outage is at least five percent for materials poisonous by inhalation, or at least one percent for all other materials, of the total capacity of a cargo tank, portable tank, tank car (including dome capacity), multi-unit tank car tank, or any compartment thereof, at the following reference temperatures—

(i) 46 °C (115 °F) for a noninsulated tank;

(ii) 43 °C (110 °F) for a tank car having a thermal protection system, incorporating a metal jacket that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 10.22 kilojoules per hour per square meter per degree Celsius (0.5 Btu per hour per square foot per degree F) temperature differential; or

(iii) 41 °C (105 °F) for an insulated tank.



## § 173.25

## 49 CFR Ch. I (10–1–08 Edition)

(2) Hazardous materials may not be loaded into the dome of a tank car. If the dome of the tank car does not provide sufficient outage, vacant space must be left in the shell to provide the required outage.

(b) *Equivalent steel.* For the purposes of this section, the reference stainless steel is stainless steel with a guaranteed minimum tensile strength of 51.7 deka newtons per square millimeter (75,000 psi) and a guaranteed elongation of 40 percent or greater. Where the regulations permit steel other than stainless steel to be used in place of a specified stainless steel (for example, as in § 172.102 of this subchapter, special provision B30), the minimum thickness for the steel must be obtained from one of the following formulas, as appropriate:

### *Formula for metric units*

$$e_1 = (12.74e_0) / (Rm_1 A_1)^{1/3}$$

### *Formula for non-metric units*

$$e_1 = (144.2e_0) / (Rm_1 A_1)^{1/3}$$

where:

$e_0$  = Required thickness of the reference stainless steel in mm or inches respectively;

$e_1$  = Equivalent thickness of the steel used in mm or inches respectively;

$Rm_1$  = Specified minimum tensile strength of the steel used in deka-newtons per square millimeter or pounds per square inch respectively; and

$A_1$  = Specified minimum percentage elongation of the steel used multiplied by 100 (for example, 20 percent times 100 equals 20). Elongation values used must be determined from a 50 mm or 2 inch test specimen.

(c) Air pressure in excess of ambient atmospheric pressure may not be used to load or unload any lading which may create an air-enriched mixture within the flammability range of the lading in the vapor space of the tank.

(d) A bulk packaging may not be loaded with a hazardous material that:

(1) Is at a temperature outside of the packaging's design temperature range; or

(2) Except as otherwise provided in this subchapter, exceeds the maximum weight of lading marked on the specification plate.

(e) *UN portable tanks.* (1) A UN portable tank manufactured in the United

States must conform in all details to the applicable requirements in parts 172, 173, 178 and 180 of this subchapter.

(2) *UN portable tanks manufactured outside the United States.* A UN portable tank manufactured outside the United States, in accordance with national or international regulations based on the UN Recommendations (IBR, see § 171.7 of this subchapter), which is an authorized packaging under § 173.24 of this subchapter, may be filled, offered and transported in the United States, if the § 172.101 Table of this subchapter authorizes the hazardous material for transportation in the UN portable tank and it conforms to the applicable T codes, and tank provision codes, or other special provisions assigned to the hazardous material in Column (7) of the Table when manufactured in a country other than the United States. In addition, the portable tank must—

(i) Conform to applicable provisions in the UN Recommendations (IBR, see § 171.7 of this subchapter) and the requirements of this subpart;

(ii) Be capable of passing the prescribed tests and inspections in part 180 of this subchapter applicable to the UN portable tank specification;

(iii) Be designed and manufactured according to the ASME Code (IBR, see § 171.7 of this subchapter) or a pressure vessel design code approved by the Associate Administrator;

(iv) Be approved by the Associate Administrator when the portable tank is designed and constructed under the provisions of an alternative arrangement (see § 178.274(a)(2) of this subchapter); and

(v) The competent authority of the country of manufacture must provide reciprocal treatment for UN portable tanks manufactured in the United States.

[Amdt. 173–224, 55 FR 52612, Dec. 21, 1990, as amended at 56 FR 66266, Dec. 20, 1991; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–243, 60 FR 40038, Aug. 4, 1995; Amdt. 173–252, 61 FR 28676, June 5, 1996; Amdt. 173–255, 61 FR 50624, Sept. 26, 1996; 66 FR 33426, June 21, 2001; 67 15743, Apr. 3, 2002; 68 FR 75742, Dec. 31, 2003]

## § 173.25 Authorized packagings and overpacks.

(a) Authorized packages containing hazardous materials may be offered for

transportation in an overpack as defined in § 171.8 of this subchapter, if all of the following conditions are met:

(1) The package meets the requirements of §§ 173.21 and 173.24 of this subchapter.

(2) The overpack is marked with the proper shipping name and identification number, when applicable, and is labeled as required by this subchapter for each hazardous material contained therein, unless marking and labels representative of each hazardous material in the overpack are visible.

(3) Each package subject to the orientation marking requirements of § 172.312 of this subchapter is packed in the overpack with its filling holes up and the overpack is marked with package orientation marking arrows on two opposite vertical sides of the overpack with the arrows pointing in the correct direction of orientation.

(4) The overpack is marked with the word "OVERPACK" when specification packagings are required, unless specification markings on the inside packages are visible.

(5) Packages containing Class 8 (corrosive) materials in Packing Group I or Division 5.1 (oxidizing) materials in Packing Group I may not be overpacked with any other materials.

(b) Shrink-wrapped or stretch-wrapped trays may be used as outer packagings for inner packagings prepared in accordance with the limited quantity provisions or consumer commodity provisions of this subchapter, provided that—

(1) Inner packagings are not fragile, liable to break or be easily punctured, such as those made of glass, porcelain, stoneware or certain plastics; and

(2) Each complete package does not exceed 20 kg (44 lbs) gross weight.

(c) Hazardous materials which are required to be labeled POISON may be transported in the same motor vehicle with material that is marked or known to be foodstuffs, feed or any edible material intended for consumption by humans or animals provided the hazardous material is marked, labeled, and packaged in accordance with this subchapter, conforms to the requirements of paragraph (a) of this section and is overpacked as specified in § 177.841(e) of this subchapter or in an

overpack which is a UN 1A2, 1B2, or 1N2 drum tested and marked for a Packing Group II or higher performance level.

[Amdt. 173-165, 48 FR 28099, June 20, 1983, as amended by Amdt. 173-224, 55 FR 52612 Dec. 21, 1990; 56 FR 66266, Dec. 20, 1991; Amdt. 173-234, 58 FR 51532, Oct. 1, 1993; Amdt. 173-214, 59 FR 67491, Dec. 29, 1994; 64 FR 10776, Mar. 5, 1999; 68 FR 45032, July 31, 2003; 69 FR 76155, Dec. 20, 2004; 70 FR 34397, June 14, 2005; 73 FR 57005, Oct. 1, 2008]

#### § 173.26 Quantity limitations.

When quantity limitations do not appear in the packaging requirements of this subchapter, the permitted gross weight or capacity authorized for a packaging is as shown in the packaging specification or standard in part 178 or 179, as applicable, of this subchapter.

[Amdt. 173-224, 55 FR 52612, Dec. 21, 1990]

#### § 173.27 General requirements for transportation by aircraft.

(a) The requirements of this section are in addition to the requirements in § 173.24 and apply to packages offered or intended for transportation aboard aircraft. Except for materials not subject to performance packaging requirements in subpart E of this part, a packaging containing a Packing Group III material with a primary or subsidiary risk of Division 4.1, 4.2, 4.3, 5.1, or Class 8 must meet the Packing Group II performance level when offered or intended for transportation by aircraft.

(b) *Packages authorized onboard aircraft.* (1) When Column 9a of the § 172.101 table indicates that a material is "Forbidden", that material may not be offered for transportation or transported aboard passenger-carrying aircraft.

(2) When Column 9b of the § 172.101 table indicates that a material is "Forbidden", that material may not be offered for transportation or transported aboard aircraft.

(3) The maximum quantity of hazardous material in a package that may be offered for transportation or transported aboard a passenger-carrying aircraft or cargo aircraft may not exceed that quantity prescribed for the material in Column 9a or 9b, respectively, of the § 172.101 table.

(4) A package containing a hazardous material which is authorized aboard

cargo aircraft but not aboard passenger aircraft must be labeled with the CARGO AIRCRAFT ONLY label required by § 172.402(c) of this subchapter and may not be offered for transportation or transported aboard passenger-carrying aircraft.

(c) *Pressure requirements.* (1) Packagings must be designed and constructed to prevent leakage that may be caused by changes in altitude and temperature during transportation aboard aircraft.

(2) Packagings for which retention of liquid is a basic function must be capable of withstanding without leakage the greater of—

(i) An internal pressure which produces a gauge pressure of not less than 75 kPa (11 psig) for liquids in Packing Group III of Class 3 or Division 6.1; or 95 kPa (14 psig) for other liquids; or

(ii) A pressure related to the vapor pressure of the liquid to be conveyed, determined by one of the following:

(A) The total gauge pressure measured in the receptacle (i.e., the vapor pressure of the material and the partial pressure of air or other inert gases, less 100 kPa (15 psia)) at 55 °C (131 °F), multiplied by a safety factor of 1.5; determined on the basis of a filling temperature of 15 °C (59 °F) and a degree of filling such that the receptacle is not completely liquid full at a temperature of 55 °C (131 °F) or less;

(B) 1.75 times the vapor pressure at 50 °C (122 °F) less 100 kPa (15 psia); or

(C) 1.5 times the vapor pressure at 55 °C (131 °) less 100 kPa (15 psia).

(3) Notwithstanding the provisions of paragraph (c)(2) of this section—

(i) Hazardous materials may be contained in an inner packaging which does not itself meet the pressure requirement provided that the inner packaging is packed within a supplementary packaging which does meet the pressure requirement and other applicable packaging requirements of this subchapter.

(ii) Packagings which are subject to the hydrostatic pressure test and marking requirements of §§ 178.605 and 178.503(a)(5), respectively, of this subchapter must have a marked test pressure of not less than 250 kPa (36 psig) for liquids in Packing Group I, 80 kPa (12 psig) for liquids in Packing Group

III of Class 3 or Division 6.1, and 100 kPa (15 psig) for other liquids.

(d) *Closures.* Stoppers, corks or other such friction-type closures must be held securely, tightly and effectively in place by positive means. Each screw-type closure on any packaging must be secured to prevent closure from loosening due to vibration or substantial change in temperature.

(e) *Absorbent materials.* Except as otherwise provided in this subchapter, liquid hazardous materials of Class 3, 4, or 8, or Division 5.1, 5.2 or 6.1 that are packaged and offered for transport in glass, earthenware, plastic or metal inner packagings must be packaged using absorbent material as follows:

(1) Packing Group I liquids on passenger aircraft must be packaged using materials capable of absorbing the entire contents of the inner packagings.

(2) Packing Group I liquids on cargo aircraft, and Packing Group II liquids including Division 5.2 liquids on passenger and cargo aircraft, must be packaged using a sufficient quantity of absorbent material to absorb the entire contents of any one of the inner packagings containing such liquids. When the inner packagings are of different sizes and quantities, sufficient absorbent material must be used to absorb the entire contents of the inner packaging with the greatest volume of liquid.

(3) When absorbent materials are required and the outer packaging is not liquid tight, a means of containing the liquid in the event of a leakage must be provided in the form of a leakproof liner, plastic bag or other equally efficient means of containment.

(4) Absorbent material must not react dangerously with the liquid (see §§ 173.24 and 173.24a.).

(5) Absorbent material is not required if the inner packagings are so protected that they are unlikely to break and leak their contents from the outer packaging under normal conditions of transportation.

(f) *Combination packagings.* Unless otherwise specified in this part, or in § 171.11 of this subchapter, when combination packagings are offered for transportation aboard aircraft, inner packagings must conform to the quantity limitations set forth in table 1 of

this paragraph for transport aboard of this paragraph for transport aboard passenger-carrying aircraft and table 2 cargo aircraft only, as follows:

TABLE 1—MAXIMUM NET CAPACITY OF INNER PACKAGING FOR TRANSPORTATION ON PASSENGER-CARRYING AIRCRAFT

| Maximum net quantity per package from Column 9a of the § 172.101 table | Maximum authorized net capacity of each inner packaging |                                   |
|------------------------------------------------------------------------|---------------------------------------------------------|-----------------------------------|
|                                                                        | Glass, earthenware or fiber inner packagings            | Metal or plastic inner packagings |
| Liquids:                                                               |                                                         |                                   |
| Not greater than 0.5L .....                                            | 0.5L .....                                              | 0.5L.                             |
| Greater than 0.5L, not greater than 1L .....                           | 0.5L .....                                              | 1L.                               |
| Greater than 1L, not greater than 5L .....                             | 1L .....                                                | 5L.                               |
| Greater than 5L, not greater than 60L .....                            | 2.5L .....                                              | 10L.                              |
| Greater than 60L, not greater than 220L .....                          | 5L .....                                                | 25L.                              |
| Greater than 220L .....                                                | No limit .....                                          | No limit.                         |
| Solids:                                                                |                                                         |                                   |
| Not greater than 5 kg .....                                            | 0.5 kg .....                                            | 1 kg.                             |
| Greater than 5 kg, not greater than 25 kg .....                        | 1 kg .....                                              | 2.5 kg.                           |
| Greater than 25 kg, not greater than 200 kg .....                      | 5 kg .....                                              | 10 kg.                            |
| Greater than 200 kg .....                                              | No limit .....                                          | No limit.                         |

TABLE 2—MAXIMUM NET CAPACITY OF INNER PACKAGING FOR TRANSPORTATION ON CARGO AIRCRAFT

| Maximum net quantity per package from Column 9b of the § 172.101 table | Maximum authorized net capacity of each inner packaging |                                   |
|------------------------------------------------------------------------|---------------------------------------------------------|-----------------------------------|
|                                                                        | Glass, earthenware or fiber inner packagings            | Metal or plastic inner packagings |
| Liquids:                                                               |                                                         |                                   |
| Not greater than 2.5L .....                                            | 1L .....                                                | 1L.                               |
| Greater than 2.5L, not greater than 30L .....                          | 2.5L .....                                              | 2.5L.                             |
| Greater than 30L, not greater than 60L .....                           | 5L .....                                                | 10L.                              |
| Greater than 60L, not greater than 220L .....                          | 5L .....                                                | 25L.                              |
| Greater than 220L .....                                                | No limit .....                                          | No limit.                         |
| Solids:                                                                |                                                         |                                   |
| Not greater than 15 kg .....                                           | 1 kg .....                                              | 2.5 kg.                           |
| Greater than 15 kg, not greater than 50 kg .....                       | 2.5 kg .....                                            | 5 kg.                             |
| Greater than 50 kg, not greater than 200 kg .....                      | 5 kg .....                                              | 10 kg.                            |
| Greater than 200 kg .....                                              | No limit .....                                          | No limit.                         |

(g) *Cylinders*. For any cylinder containing hazardous materials and incorporating valves, sufficient protection must be provided to prevent operation of, and damage to, the valves during transportation, by one of the following methods:

(1) By equipping each cylinder with securely attached valve caps or protective headrings; or

(2) By boxing or crating the cylinder.

(h) Tank cars and cargo tanks. Any tank car or cargo tank containing a hazardous material may not be transported aboard aircraft.

(i) Effective October 1, 2006, each person who offers a hazardous material for transportation by aircraft must in-

clude the certification statement specified in § 172.204(c)(3).

[Amdt. 173–224, 55 FR 52612, Dec. 21, 1990, as amended at 56 FR 66266, Dec. 20, 1991; Amdt. 173–138, 59 FR 49133, Sept. 26, 1994; 65 FR 58629, Sept. 29, 2000; 66 FR 45380, Aug. 28, 2001; 68 FR 45032, July 31, 2003; 69 FR 76155, Dec. 20, 2004; 71 FR 14602, Mar. 22, 2006; 73 FR 57006, Oct. 1, 2008]

#### § 173.28 Reuse, reconditioning and re-manufacture of packagings.

(a) *General*. Packagings and receptacles used more than once must be in such condition, including closure devices and cushioning materials, that they conform in all respects to the prescribed requirements of this subchapter. Before reuse, each packaging

§ 173.28

49 CFR Ch. I (10–1–08 Edition)

must be inspected and may not be reused unless free from incompatible residue, rupture, or other damage which reduces its structural integrity.

(b) *Reuse of non-bulk packaging.* A non-bulk packaging used more than once must conform to the following provisions and limitations:

(1) A non-bulk packaging which, upon inspection, shows evidence of a reduction in integrity may not be reused unless it is reconditioned in accordance with paragraph (c) of this section.

(2) Before reuse, packagings subject to the leakproofness test with air prescribed in §178.604 of this subchapter shall be—

(i) Retested without failure in accordance with §178.604 of this subchapter using an internal air pressure (gauge) of at least 48 kPa (7.0 psig) for Packing Group I and 20 kPa (3.0 psig) for Packing Group II and Packing Group III; and

(ii) Marked with the letter “L”, with the name and address or symbol of the person conducting the test, and the last two digits of the year the test was conducted. Symbols, if used, must be registered with the Associate Administrator.

(3) Packagings made of paper (other than fiberboard), plastic film, or textile are not authorized for reuse;

(4) Metal and plastic drums and jerricans used as single packagings or the outer packagings of composite packagings are authorized for reuse only when they are marked in a permanent manner (e.g., embossed) in mm with the nominal (for metal packagings) or minimum (for plastic packagings) thickness of the packaging material, as required by §178.503(a)(9) of this subchapter, and—

(i) Except as provided in paragraph (b)(4)(ii) of this section, conform to the following minimum thickness criteria:

| Maximum capacity not over | Minimum thickness of packaging material |                          |
|---------------------------|-----------------------------------------|--------------------------|
|                           | Metal drum or jerrican                  | Plastic drum or jerrican |
| 20 L .....                | 0.63 mm (0.025 inch)                    | 1.1 mm (0.043 inch).     |
| 30 L .....                | 0.73 mm (0.029 inch)                    | 1.1 mm (0.043 inch).     |
| 40 L .....                | 0.73 mm (0.029 inch)                    | 1.8 mm (0.071 inch).     |
| 60 L .....                | 0.92 mm (0.036 inch)                    | 1.8 mm (0.071 inch).     |
| 120 L .....               | 0.92 mm (0.036 inch)                    | 2.2 mm (0.087 inch).     |
| 220 L .....               | 0.92 mm (0.036 inch) <sup>1</sup> .     | 2.2 mm (0.087 inch).     |
| 450 L .....               | 1.77 mm (0.070 inch)                    | 5.0 mm (0.197 inch).     |

<sup>1</sup>Metal drums or jerricans with a minimum thickness of 0.82 mm body and 1.09 mm heads which are manufactured and marked prior to January 1, 1997 may be reused. Metal drums or jerricans manufactured and marked on or after January 1, 1997, and intended for reuse, must be constructed with a minimum thickness of 0.82 mm body and 1.11 mm heads.

(ii) For stainless steel drums and jerricans, conform to a minimum wall thickness as determined by the following equivalence formula:

FORMULA FOR METRIC UNITS

$$e_1 = \frac{21.4 \times e_0}{\sqrt[3]{Rm_1 \times A_1}}$$

FORMULA FOR U.S. STANDARD UNITS

$$e_1 = \frac{21.4 \times e_0}{\sqrt[3]{(Rm_1 \times A_1)/145}}$$

where:

$e_1$  = required equivalent wall thickness of the metal to be used (in mm or, for U.S. Standard units, use inches).

$e_0$  = required minimum wall thickness for the reference steel (in mm or, for U.S. Standard units, use inches).

$Rm_1$  = guaranteed minimum tensile strength of the metal to be used (in N/mm<sup>2</sup> or for U.S. Standard units, use psi).

$A_1$  = guaranteed minimum elongation (as a percentage) of the metal to be used on fracture under tensile stress (see paragraph (c)(1) of this section).

(5) Plastic inner receptacles of composite packagings must have a minimum thickness of 1.0 mm (0.039 inch).

(6) A previously used non-bulk packaging may be reused for the shipment of hazardous waste, not subject to the reconditioning and reuse provisions of this section, in accordance with §173.12(c).

(7) Notwithstanding the provisions of paragraph (b)(2) of this section, a packaging otherwise authorized for reuse may be reused without being leakproofness tested with air provided the packaging—

(i) Is refilled with a material which is compatible with the previous lading;

(ii) Is refilled and offered for transportation by the original filler;

(iii) Is transported in a transport vehicle or freight container under the exclusive use of the refiller of the packaging; and

(iv) Is constructed of—

(A) Stainless steel, monel or nickel with a thickness not less than one and one-half times the minimum thickness prescribed in paragraph (b)(4) of this section;

(B) Plastic, provided the packaging is not refilled for reuse on a date more than five years from the date of manufacture marked on the packaging in accordance with § 178.503(a)(6) of this subchapter; or

(C) Another material or thickness when approved under the conditions established by the Associate Administrator for reuse without retesting.

(c) *Reconditioning of non-bulk packaging.* (1) For the purpose of this subchapter, reconditioning of metal drums is:

(i) Cleaning to base material of construction, with all former contents, internal and external corrosion, and any external coatings and labels removed;

(ii) Restoring to original shape and contour, with chimes (if any) straightened and sealed, and all non-integral gaskets replaced; and

(iii) Inspecting after cleaning but before painting. Packagings that have visible pitting, significant reduction in material thickness, metal fatigue, damaged threads or closures, or other significant defects, must be rejected.

(2) For the purpose of this subchapter, reconditioning of a non-bulk packaging other than a metal drum includes:

(i) Removal of all former contents, external coatings and labels, and cleaning to the original materials of construction;

(ii) Inspection after cleaning with rejection of packagings with visible damage such as tears, creases or cracks, or damaged threads or closures, or other significant defects;

(iii) Replacement of all non-integral gaskets and closure devices with new or refurbished parts, and cushioning and cushioning materials; and components including gaskets, closure devices and cushioning and cushioning

material. (For a UN 1H1 plastic drum, replacing a removable gasket or closure device with another of the same design and material that provides equivalent performance does not constitute reconditioning); and

(iv) Ensuring that the packagings are restored to a condition that conforms in all respects with the prescribed requirements of this subchapter.

(3) A person who reconditions a packaging manufactured and marked under the provisions of subpart L of part 178 of this subchapter, shall mark that packaging as required by § 178.503(c) and (d) of this subchapter. The marking is the certification of the reconditioner that the packaging conforms to the standard for which it is marked and that all functions performed by the reconditioner which are prescribed by this subchapter have been performed in compliance with this subchapter.

(4) The markings applied by the reconditioner may be different from those applied by the manufacturer at the time of original manufacture, but may not identify a greater performance capability than that for which the original design type had been tested (for example, the reconditioner may mark a drum which was originally marked as 1A1/Y1.8 as 1A1/Y1.2 or 1A1/Z2.0).

(5) Packagings which have significant defects which cannot be repaired may not be reused.

(d) *Remanufacture of non-bulk packagings.* For the purpose of this subchapter, remanufacture is the conversion of a non-specification, non-bulk packaging to a DOT specification or U.N. standard, the conversion of a packaging meeting one specification or standard to another specification or standard (for example, conversion of 1A1 non-removable head drums to 1A2 removable head drums) or the replacement of integral structural packaging components (such as non-removable heads on drums). A person who remanufactures a non-bulk packaging to conform to a specification or standard in part 178 of this subchapter is subject to the requirements of part 178 of this subchapter as a manufacturer.

(e) *Non-reusable containers.* A packaging marked as NRC according to the

## § 173.29

## 49 CFR Ch. I (10–1–08 Edition)

DOT specification or UN standard requirements of part 178 of this subchapter may be reused for the shipment of any material not required by this subchapter to be shipped in a DOT specification or UN standard packaging.

(f) A Division 6.2 packaging to be reused must be disinfected prior to reuse by any means effective for neutralizing the infectious substance the packaging previously contained. A secondary packaging or outer packaging conforming to the requirements of §173.196 or §173.199 need not be disinfected prior to reuse if no leakage from the primary receptacle has occurred.

[Amdt. 173–224, 55 FR 52614, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §173.28, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 173.29 Empty packagings.

(a) General. Except as otherwise provided in this section, an empty packaging containing only the residue of a hazardous material shall be offered for transportation and transported in the same manner as when it previously contained a greater quantity of that hazardous material.

(b) Notwithstanding the requirements of paragraph (a) of this section, an empty packaging is not subject to any other requirements of this subchapter if it conforms to the following provisions:

(1) Any hazardous material shipping name and identification number markings, any hazard warning labels or placards, and any other markings indicating that the material is hazardous (e.g., RQ, INHALATION HAZARD) are removed, obliterated, or securely covered in transportation. This provision does not apply to transportation in a transport vehicle or a freight container if the packaging is not visible in transportation and the packaging is loaded by the shipper and unloaded by the shipper or consignee;

(2) The packaging—

(i) Is unused;

(ii) Is sufficiently cleaned of residue and purged of vapors to remove any potential hazard;

(iii) Is refilled with a material which is not hazardous to such an extent that any residue remaining in the packaging no longer poses a hazard; or

(iv) Contains only the residue of—

(A) An ORM-D material; or

(B) A Division 2.2 non-flammable gas, other than ammonia, anhydrous, and with no subsidiary hazard, at an absolute pressure less than 280 kPa (40.6 psia); at 20 °C (68 °F); and

(3) Any material contained in the packaging does not meet the definitions in §171.8 of this subchapter for a hazardous substance, a hazardous waste, or a marine pollutant.

(c) A non-bulk packaging containing only the residue of a hazardous material covered by Table 2 of §172.504 of this subchapter that is not a material poisonous by inhalation or its residue shipped under the subsidiary placarding provisions of §172.505—

(1) Does not have to be included in determining the applicability of the placarding requirements of subpart F of part 172 of this subchapter; and

(2) Is not subject to the shipping paper requirements of this subchapter when collected and transported by a contract or private carrier for reconditioning, remanufacture or reuse.

(d) Notwithstanding the stowage requirements in Column 10a of the §172.101 table for transportation by vessel, an empty drum or cylinder may be stowed on deck or under deck.

(e) Specific provisions for describing an empty packaging on a shipping paper appear in §172.203(e) of this subchapter.

(f) [Reserved]

(g) A package which contains a residue of an elevated temperature material may remain marked in the same manner as when it contained a greater quantity of the material even though it no longer meets the definition in §171.8 of this subchapter for an elevated temperature material.

(h) A package that contains a residue of a hazardous substance, Class 9, listed in the §172.101 Table, Appendix A, Table I, that does not meet the definition of another hazard class and is not a hazardous waste or marine pollutant, may remain marked, labeled and, if applicable, placarded in the same manner

as when it contained a greater quantity of the material even though it no longer meets the definition in § 171.8 of this subchapter for a hazardous substance.

[Amdt. 173-224, 55 FR 52614, Dec. 21, 1990, as amended by Amdt. 173-227, 56 FR 49989, Oct. 2, 1991; Amdt. 173-231, 57 FR 52939, Nov. 5, 1992; Amdt. 173-251, 61 FR 28676, June 5, 1996; Amdt. 173-260, 62 FR 1236, Jan. 8, 1997; 64 FR 10776, Mar. 5, 1999; 68 FR 48569, Aug. 14, 2003; 69 FR 64473, Nov. 4, 2004]

### § 173.30 Loading and unloading of transport vehicles.

A person who is subject to the loading and unloading regulations in this subchapter must load or unload hazardous materials into or from a transport vehicle or vessel in conformance with the applicable loading and unloading requirements of parts 174, 175, 176, and 177 of this subchapter.

[68 FR 61941, Oct. 30, 2003]

### § 173.31 Use of tank cars.

(a) *General.* (1) No person may offer a hazardous material for transportation in a tank car unless the tank car meets the applicable specification and packaging requirements of this subchapter or, when this subchapter authorizes the use of a non-DOT specification tank car, the applicable specification to which the tank was constructed.

(2) Tank cars and appurtenances may be used for the transportation of any commodity for which they are authorized in this part and specified on the certificate of construction (AAR Form 4-2 or by addendum on Form R-1). See § 179.5 of this subchapter. Transfer of a tank car from one specified service on its certificate of construction to another may be made only by the owner or with the owner's authorization. A tank car proposed for a commodity service other than specified on its certificate of construction must be approved for such service by the AAR's Tank Car Committee.

(3) No person may fill a tank car overdue for periodic inspection with a hazardous material and then offer it for transportation. Any tank car marked as meeting a DOT specification and any non-specification tank car transporting a hazardous material must have a periodic inspection and

test conforming to subpart F of part 180 of this subchapter.

(4) No railroad tank car, regardless of its construction date, may be used for the transportation in commerce of any hazardous material unless the air brake equipment support attachments of such tank car conform to the standards for attachments set forth in §§ 179.100-16 and 179.200-19 of this subchapter.

(5) No railroad tank car, regardless of its construction date, may be used for the transportation in commerce of any hazardous material with a self-energized manway located below the liquid level of the lading.

(6) Unless otherwise specifically provided in this part:

(i) When the tank car delimiter is an "A," offerors may also use tank cars with a delimiter "S," "J" or "T".

(ii) When the tank car delimiter is an "S," offerors may also use tank cars with a delimiter "J" or "T".

(iii) When a tank car delimiter is a "T" offerors may also use tank cars with a delimiter of "J".

(iv) When a tank car delimiter is a "J", offerors may not use a tank car with any other delimiter.

(7) A class DOT-103 or DOT-104 tank car may continue to be used for the transportation of a hazardous material if it meets the requirements of this subchapter and the design requirements in Part 179 of this subchapter in effect on September 30, 2003; however, no new construction is authorized.

(8) A tank car authorized by the Transport Canada TDG Regulations (IBR, see § 171.7 of this subchapter) may be used provided it conforms to the applicable requirements in § 171.12 of this subchapter.

(b) *Safety systems—(1) Coupler vertical restraint.* Each tank car conforming to a DOT specification and any other tank car used for transportation of a hazardous material must be equipped with a coupler vertical restraint system that meets the requirements of § 179.14 of this subchapter.

(2) *Pressure relief devices.* (i) Pressure relief devices on tank cars must conform to part 179 of this subchapter.

(ii) A single-unit tank car transporting a Division 6.1 PG I or II, or



Class 2, 3, or 4 material must have a reclosing pressure relief device. However, a single-unit tank car built before January 1, 1991, and equipped with a non-reclosing pressure relief device may be used to transport a Division 6.1 PG I or II material or a Class 4 liquid provided such materials do not meet the definition of a material poisonous by inhalation.

(3) *Tank-head puncture-resistance requirements.* The following tank cars must have a tank-head puncture-resistance system that conforms to the requirements in §179.16 of this subchapter, or to the corresponding requirements in effect at the time of installation:

(i) Tank cars transporting a Class 2 material.

(ii) Tank cars constructed from aluminum or nickel plate that are used to transport hazardous material.

(iii) Except as provided in paragraph (b)(3)(iv) of this section, those tank cars specified in paragraphs (b)(3)(i) and (ii) of this section not requiring a tank-head puncture resistance system prior to July 1, 1996, must have a tank-head puncture resistance system installed no later than July 1, 2006.

(iv) Class DOT 105A tank cars built prior to September 1, 1981, having a tank capacity less than 70 kl (18,500 gallons), and used to transport a Division 2.1 (flammable gas) material, must have a tank-head puncture-resistant system installed no later than July 1, 2001.

(4) *Thermal protection requirements.* The following tank cars must have thermal protection that conforms to the requirements of §179.18 of this subchapter:

(i) Tank cars transporting a Class 2 material, except for a class 106, 107A, 110, and 113 tank car. A tank car equipped with a thermal protection system conforming to §179.18 of this subchapter, or that has an insulation system having an overall thermal conductance of no more than 0.613 kilojoules per hour, per square meter, per degree Celsius temperature differential (0.03 B.t.u. per square foot, per hour, per degree Fahrenheit temperature differential), conforms to this requirement.

(ii) A tank car transporting a Class 2 material that was not required to have thermal protection prior to July 1, 1996, must be equipped with thermal protection no later than July 1, 2006.

(5) *Bottom-discontinuity protection requirements.* No person may offer for transportation a hazardous material in a tank car with bottom-discontinuity protection unless the tank car has bottom-discontinuity protection that conforms to the requirements of E9.00 and E10.00 of the AAR Specifications for Tank Cars (IBR, see §171.7 of this subchapter). Tank cars not requiring bottom-discontinuity protection under the terms of Appendix Y of the AAR Specifications for Tank Cars as of July 1, 1996, must conform to these requirements no later than July 1, 2006, except that tank cars transporting a material that is hazardous only because it meets the definition of an elevated temperature material or because it is molten sulfur do not require bottom discontinuity protection.

(6) *Scheduling of modifications and progress reporting.* The date of conformance for the continued use of tank cars subject to paragraphs (b)(3), (b)(4), (b)(5), (e)(2), and (f) of this section and §§173.314(j) and 173.323(c)(1) is subject to the following conditions and limitations.

(i) Each tank car owner shall modify, reassign, retire, or remove at least 50 percent of their in-service tank car fleet within the first half of the compliance period and the remainder of their in-service tank car fleet during the second half of the compliance period.

(ii) By October 1 of each year, each owner of a tank car subject to this paragraph (b)(6) shall submit to the Federal Railroad Administration, Hazardous Materials Division, Office of Safety Assurance and Compliance, 1120 Vermont Avenue, Mail Stop 25, Washington, DC 20590, a progress report that shows the total number of in-service tank cars that need head protection, thermal protection, or bottom-discontinuity protection; the number of new or different tank cars acquired to replace those tank cars required to be upgraded to a higher service pressure; and the total number of tank cars modified, reassigned, acquired, retired,

or removed from service the previous year.

(c) *Tank car test pressure.* A tank car used for the transportation of a hazardous material must have a tank test pressure equal to or greater than the greatest of the following:

(1) Except for shipments of carbon dioxide, anhydrous hydrogen chloride, vinyl fluoride, ethylene, or hydrogen, 133 percent of the sum of lading vapor pressure at the reference temperature of 46 °C (115 °F) for non-insulated tank cars or 41 °C (105 °F) for insulated tank cars plus static head, plus gas padding pressure in the vacant space of a tank car;

(2) 133 percent of the maximum loading or unloading pressure, whichever is greater;

(3) 20.7 Bar (300 psig) for materials that are poisonous by inhalation (see § 173.31(e)(2)(ii) for compliance dates);

(4) The minimum pressure prescribed by the specification in part 179 of this subchapter; or

(5) The minimum test pressure prescribed for the specific hazardous material in the applicable packaging section in subpart F or G of this part.

(d) *Examination before shipping.* (1) No person may offer for transportation a tank car containing a hazardous material or a residue of a hazardous material unless that person determines that the tank car is in proper condition and safe for transportation. As a minimum, each person offering a tank car for transportation must perform an external visual inspection that includes:

(i) Except where insulation or a thermal protection system precludes an inspection, the tank shell and heads for abrasion, corrosion, cracks, dents, distortions, defects in welds, or any other condition that makes the tank car unsafe for transportation;

(ii) The piping, valves, fittings, and gaskets for corrosion, damage, or any other condition that makes the tank car unsafe for transportation;

(iii) For missing or loose bolts, nuts, or elements that make the tank car unsafe for transportation;

(iv) All closures on tank cars and determine that the closures and all fastenings securing them are properly tightened in place by the use of a bar, wrench, or other suitable tool;

(v) Protective housings for proper securement;

(vi) The pressure relief device, including a careful inspection of the rupture disc in non-reclosing pressure relief devices, for corrosion or damage that may alter the intended operation of the device;

(vii) Each tell-tale indicator after filling and prior to transportation to ensure the integrity of the rupture disc;

(viii) The external thermal protection system, tank-head puncture resistance system, coupler vertical restraint system, and bottom discontinuity protection for conditions that make the tank car unsafe for transportation;

(ix) The required markings on the tank car for legibility; and

(x) The periodic inspection date markings to ensure that the inspection and test intervals are within the prescribed intervals.

(2) Closures on tank cars are required, in accordance with this subchapter, to be designed and closed so that under conditions normally incident to transportation, including the effects of temperature and vibration, there will be no identifiable release of a hazardous material to the environment. In any action brought to enforce this section, the lack of securement of any closure to a tool-tight condition, detected at any point, will establish a rebuttable presumption that a proper inspection was not performed by the offeror of the car. That presumption may be rebutted by any evidence indicating that the lack of securement resulted from a specific cause not within the control of the offeror.

(e) *Special requirements for materials poisonous by inhalation*—(1) *Interior heater coils.* Tank cars used for materials poisonous by inhalation may not have interior heater coils.

(2) *Tank car specifications.* A tank car used for a material poisonous by inhalation must have a tank test pressure of 20.7 Bar (300 psig) or greater, head protection, and a metal jacket (e.g., DOT 105S300W), except that—

(i) A higher test pressure is required if otherwise specified in this subchapter; and

(ii) Other than as provided in paragraph (b)(6) of this section, a tank car which does not conform to the requirements of this paragraph (e)(2), and was authorized for the material poisonous by inhalation under the regulations in effect on June 30, 1996, may continue in use until July 1, 2006.

(f) *Special requirements for hazardous substances.* (1) A tank car used for a hazardous substance listed in paragraph (f)(2) of this section must have a tank test pressure of at least 13.8 Bar (200 psig), head protection and a metal jacket, except that—

(i) No metal jacket is required if—

(A) The tank test pressure is 23.4 Bar (340 psig) or higher; or

(B) The tank shell and heads are manufactured from AAR steel specification TC-128, normalized;

(ii) A higher test pressure is required if otherwise specified in this subchapter; and

(iii) Other than as provided in paragraph (b)(6) of this section, a tank car which does not conform to the requirements of this paragraph (f)(1), and was authorized for a hazardous substance under the regulations in effect on June 30, 1996, may continue in use until July 1, 2006.

(2) *List of hazardous substances.* Hazardous substances for which the provisions of this paragraph (f) apply are as follows:

Aldrin  
Allyl chloride  
alpha-BHC  
beta-BHC  
delta-BHC  
gamma-BHC  
Bis(2-chloroethyl) ether  
Bromoform  
Carbon tetrachloride  
Chlordane  
p-Chloroaniline  
Chlorobenzene  
Chlorobenzilate  
p-Chloro-m-cresol  
2-Chloroethyl vinyl ether  
Chloroform  
2-Chloronaphthalene  
o-Chlorophenol  
3-Chloropropionitrile  
DDE  
DDT  
1,2-Dibromo-3-chloropropane  
m-Dichlorobenzene  
o-Dichlorobenzene  
p-Dichlorobenzene  
3,3'-Dichlorobenzidine

1,4-Dichloro-2-butene  
1,1-Dichloroethane  
1,2-Dichloroethane  
1,1-Dichloroethylene  
Dichloroisopropyl ether  
Dichloromethane @  
2,4-Dichlorophenol  
2,6-Dichlorophenol  
1,2-Dichloropropane  
1,3-Dichloropropene  
Dieldrin  
alpha-Endosulfan  
beta-Endosulfan  
Endrin  
Endrin aldehyde  
Heptachlor  
Heptachlor epoxide  
Hexachlorobenzene  
Hexachlorobutadiene  
Hexachloroethane  
Hexachlorophene  
Hexachloropropene  
Isodrin  
Kepone  
Methoxychlor  
4,4'-Methylenebis(2-chloroaniline)  
Methylene bromide  
Pentachlorobenzene  
Pentachloroethane  
Pentachloronitrobenzene (PCNB)  
Pentachlorophenol  
Polychlorinated biphenyls (PCBs)  
Pronamide  
Silvex (2,4,5-TP)  
2,4,5-T  
TDE  
1,2,4,5-Tetrachlorobenzene  
2,3,7,8-Tetrachlorodibenzo-p-dioxin (TCDD)  
Tetrachloroethane  
Tetrachloroethylene  
2,3,4,6-Tetrachlorophenol  
Toxaphene  
1,2,4-Trichlorobenzene  
1,1,1-Trichloroethane  
1,1,2-Trichloroethane  
Trichloroethylene  
2,4,5-Trichlorophenol  
2,4,6-Trichlorophenol  
Tris(2,3-dibromopropyl) phosphate

(g) *Tank car loading and unloading.* When placed for loading or unloading and before unsecuring any closure, a tank car must be protected against movement or coupling as follows:

(1) Each hazmat employee who is responsible for loading or unloading a tank car must secure access to the track to prevent entry by other rail equipment, including motorized service vehicles. Derails, lined and locked switches, portable bumper blocks, or other equipment that provides an equivalent level of security may be used to satisfy this requirement.

(2) Caution signs must be displayed on the track or on the tank cars to warn persons approaching the cars from the open end of the track and must be left up until after all closures are secured and the cars are in proper condition for transportation. The caution signs must be of metal or other durable material, rectangular, at 30.48 cm (12 inches) high by 38.10 cm (15 inches) wide, and bear the word "STOP." The word "STOP" must appear in letters at least 10.16 cm (4 inches) high. The letters must be white on a blue background. Additional words, such as "Tank Car Connected" or "Crew at Work," may also appear in white letters under the word "STOP."

(3) At least one wheel on the tank car must be blocked against movement in both directions, and the hand brakes must be set. If multiple tank cars are coupled together, sufficient hand brakes must be set and wheels blocked to prevent movement in both directions.

[Amdt. 173-245, 60 FR 49072, Sept. 21, 1995, as amended by Amdt. 173-245, 61 FR 33254, June 26, 1996; Amdt. 173-256, 61 FR 51338, Oct. 1, 1996; 65 FR 58629, Sept. 29, 2000; 66 FR 33427, June 21, 2001; 66 FR 45379, 45381, Aug. 28, 2001; 68 FR 48569, Aug. 14, 2003; 68 FR 75743, Dec. 31, 2003; 68 FR 61941, Oct. 30, 2003; 70 FR 34075, June 13, 2005; 72 FR 25176, May 3, 2007; 72 FR 55692, Oct. 1, 2007]

#### § 173.32 Requirements for the use of portable tanks.

(a) *General requirements.* No person may offer a hazardous material for transportation in a portable tank except as authorized by this subchapter.

(1) Except as otherwise provided in this subpart, no person may use a portable tank for the transportation of a hazardous material unless it meets the requirements of this subchapter.

(2) No person may fill and offer for transportation a portable tank when the prescribed periodic test or inspection under subpart G of part 180 of this subchapter has become due until the test or inspection has been successfully completed. This requirement does not apply to any portable tank filled prior to the test or inspection due date.

(3) When a portable tank is used as a cargo tank motor vehicle, it must conform to all the requirements prescribed

for cargo tank motor vehicles. (See § 173.33.)

(b) *Substitute packagings.* A particular Specification portable tank may be substituted for another portable tank as follows:

(1) An IM or UN portable tank may be used whenever an IM or UN portable tank having less stringent requirements is authorized provided the portable tank meets or exceeds the requirements for pressure-relief devices, bottom outlets and any other special provisions specified in § 172.102(c)(7)(vi) of this subchapter.

(2) Where a Specification IM101 or IM102 portable tank is prescribed, a UN portable tank or Specification 51 portable tank otherwise conforming to the special commodity requirements of § 172.102(c)(7) of this subchapter for the material to be transported may be used.

(3) A DOT Specification 51 portable tank may be used whenever a DOT Specification 56, 57, or 60 portable tank is authorized. A DOT Specification 60 portable tank may be used whenever a DOT Specification 56 or 57 portable tank is authorized. A higher integrity tank used instead of a specified portable tank must meet the same design profile; for example, a DOT Specification 51 portable tank must be lined if used instead of a lined DOT Specification 60 portable tank.

(4) A portable tank authorized by the Transport Canada TDG Regulations (IBR, see § 171.7 of this subchapter) may be used provided it conforms to the applicable requirements in § 171.12 of this subchapter.

(c) *Grandfather provisions for portable tanks—(1) Continued use of Specification 56 and 57 portable tanks.* Continued use of an existing portable tank constructed to DOT Specification 56 or 57 is authorized only for a portable tank constructed before October 1, 1996. A stainless steel portable tank internally lined with polyethylene that was constructed on or before October 1, 1996, and that meets all requirements of DOT Specification 57 except for being equipped with a polypropylene discharge ball valve and polypropylene secondary discharge opening closure, may be marked as a Specification 57

portable tank and used in accordance with the provisions of this section.

(2) A DOT Specification 51, IM 101, or IM 102 portable tank may not be manufactured after January 1, 2003; however, such tanks may continue to be used for the transportation of a hazardous material provided they meet the requirements of this subchapter, including the specification requirements and the requirements of this subchapter for the transportation of the particular hazardous material according to the T codes in effect on September 30, 2001 or the new T codes in § 172.102(c)(7)(i) (see § 171.14(d)(4) for transitional provisions applicable to T codes), and provided the portable tanks conform to the periodic inspection and tests specified for the particular portable tank in subpart G of part 180 of this subchapter. After January 1, 2003, all newly manufactured portable tanks must conform to the requirements for the design, construction and approval of UN portable tanks as specified in §§ 178.273, 178.274, 178.275, 178.276, 178.277 and part 180, subpart G, of this subchapter.

(3) A DOT Specification portable tank manufactured prior to January 1, 1992 that is equipped with a non-reclosing pressure relief device may continue in service for the hazardous materials for which it is authorized. Except for a DOT Specification 56 or 57 portable tank, a DOT Specification portable tank manufactured after January 1, 1992, used for materials meeting the definition for Division 6.1 liquids, Packing Group I or II, Class 2 gases, or Class 3 or 4 liquids, must be equipped with a reclosing pressure relief valve having adequately sized venting capacity unless otherwise specified in this subchapter (see §§ 178.275(f)(1) and 178.277 of this subchapter).

(4) Any portable tank container constructed prior to May 15, 1950, complying with the requirements of either the ASME Code for Unfired Pressure Vessels, 1946 Edition, or the API ASME Code for Unfired Pressure Vessels, 1943 Edition, may be used for the transportation of liquefied compressed gas, provided it fulfills all the requirements of the part and specifications for the particular gas or gases to be transported. Such portable tanks must be marked “ICC Specification 51X” on the plate

required by the specification, except as modified by any or all of the following:

(i) Portable tanks designed and constructed in accordance with Pars. U–68, U–69, or U–201 of the ASME Code, 1943 and 1946 editions, may be used. Portable tanks designed and constructed in accordance with Par. U–68 or Par. U–69 may be re-rated at a working pressure 25 percent in excess of the design pressure for which the portable tank was originally constructed. If the portable tank is re-rated, the re-rated pressure must be marked on the plate as follows: “Re-rated working pressure—psig”.

(ii) Loading and unloading accessories, valves, piping, fittings, safety and gauging devices, do not have to comply with the requirements for the particular location on the portable tank.

(5) Any ICC Specification 50 portable tank fulfilling the requirements of that specification may be continued in service for transportation of a liquefied petroleum gas if it is retested every five years in accordance with the requirements in § 180.605 of this subchapter. Use of existing portable tanks is authorized. New construction is not authorized.

(d) *Determination of an authorized portable tank.* Prior to filling and offering a portable tank for transportation, the shipper must ensure that the portable tank conforms to the authorized specification and meets the applicable requirements in this subchapter for the hazardous material. The shipper must ensure that the MAWP, design pressure or test pressure of the portable tank, as applicable, is appropriate for the hazardous material being transported. Determination of the applicable pressure must take into account the maximum pressure used to load or unload the hazardous material, the vapor pressure, static head and surge pressures of the hazardous material and the temperatures that the hazardous material will experience during transportation.

(e) *External inspection prior to filling.* Each portable tank must be given a complete external inspection prior to filling. Any unsafe condition must be corrected prior to its being filled and

offered for transportation. The external inspection shall include a visual inspection of:

(1) The shell, piping, valves and other appurtenances for corroded areas, dents, defects in welds and other defects such as missing, damaged, or leaking gaskets;

(2) All flanged connections or blank flanges for missing or loose nuts and bolts;

(3) All emergency devices for corrosion, distortion, or any damage or defect that could prevent their normal operation;

(4) All required markings on the tank for legibility; and

(5) Any device for tightening manhole covers to ensure such devices are operative and adequate to prevent leakage at the manhole cover.

(f) *Loading requirements.* (1) A hazardous material may not be loaded into a portable tank if the hazardous material would:

(i) Damage the portable tank;

(ii) React with the portable tank; or

(iii) Otherwise compromise its product retention capability.

(2) A hazardous material may not be loaded in a DOT Specification 51, DOT Specification 60, an IM or UN portable tank unless the portable tank has a pressure relief device that provides total relieving capacity meeting the requirements of this subchapter.

(3) Except during a pressure test, a portable tank may not be subjected to a pressure greater than its marked maximum allowable working pressure or, when appropriate, its marked design pressure.

(4) A portable tank may not be loaded to a gross mass greater than the maximum allowable gross mass specified on its identification plate.

(5) Except for a non-flowable solid or a liquid with a viscosity of 2,680 centistokes (millimeters squared per second) or greater at 20 °C (68 °F), an IM or UN portable tank, or compartment thereof, having a volume greater than 7,500 L (1,980 gallons) may not be loaded to a filling density of more than 20% and less than 80% by volume. This filling restriction does not apply if a portable tank is divided by partitions or surge plates into compartments of not more than 7,500 L (1,980 gallons) ca-

capacity; this portable tank must not be offered for transportation in an ullage condition liable to produce an unacceptable hydraulic force due to surge.

(6) The outage for a portable tank may not be less than 2% at a temperature of 50 °C (122 °F) unless otherwise specified in this subchapter. For UN portable tanks, the applicable maximum filling limits apply as specified according to the assigned TP codes in Column (7) of the §172.101 Table of this subchapter except when transported domestically.

(7) Each tell-tale indicator or pressure gauge located in the space between a frangible disc and a safety relief valve mounted in series must be checked after the tank is filled and prior to transportation to ensure that the frangible disc is leak free. Any leakage through the frangible disc must be corrected prior to offering the tank for transportation.

(8) During filling, the temperature of the hazardous materials shall not exceed the limits of the design temperature range of the portable tank.

(9) The maximum mass of liquefied compressed gas per liter (gallon) of shell capacity (kg/L or lbs./gal.) may not exceed the density of the liquefied compressed gas at 50 °C (122 °F). The portable tank must not be liquid full at 60 °C (140 °F).

(g) *Additional requirements for specific modal transport.* In addition to other applicable requirements, the following apply:

(1) A portable tank containing a hazardous material may not be loaded onto a highway or rail transport vehicle unless loaded entirely within the horizontal outline of the vehicle, without overhang or projection of any part of the tank assembly.

(2) An IM or UN portable tank used for the transportation of flammable liquids by rail may not be fitted with non-reclosing pressure relief devices except in series with reclosing pressure relief valves.

(3) A portable tank or Specification 106A or 110A multi-unit tank car containing a hazardous material may not be offered for transportation aboard a passenger vessel unless:

(i) The vessel is operating under a change to its character of vessel certification as defined in §171.8 of this subchapter; and

(ii) The material is permitted to be transported aboard a passenger vessel in the §172.101 Table of this subchapter.

(h) *Additional general commodity-specific requirements.* In addition to other applicable requirements, the following requirements apply:

(1) Each uninsulated portable tank used for the transportation of a liquefied compressed gas must have an exterior surface finish that is significantly reflective, such as a light-reflecting color if painted, or a bright reflective metal or other material if unpainted.

(2) If a hazardous material is being transported in a molten state, the portable tank must be thermally insulated with suitable insulation material of sufficient thickness that the overall thermal conductance is not more than 0.080 Btu per hour per square foot per degree Fahrenheit differential.

(3) No person may offer a liquid hazardous material of Class 3, PG I or II, or PG III with a flash point of less than 100 °F (38 °C); Division 5.1, PG I or II; or Division 6.1, PG I or II, in an IM or UN portable tank that is equipped with a bottom outlet as authorized in Column (7) of the §172.101 Table of this subchapter by assignment of a T Code in the appropriate proper shipping name entry, for unloading to a facility while it remains on a transport vehicle with the power unit attached unless—

(i) The tank outlets conform to §178.275(d)(3) of this subchapter; or

(ii) The facility at which the IM or UN portable tank is to be unloaded conforms to the requirements in §177.834(o) of this subchapter.

(i) *Additional requirements for portable tanks other than IM specification and UN portable tanks.* (1) The bursting strength of any piping and fittings must be at least four times the design pressure of the tank, and at least four times the pressure to which, in any instance, it may be subjected in service by the action of a pump or other device (not including safety relief valves) that may subject piping to pressures greater than the design pressure of the tank.

(2) Pipe joints must be threaded, welded or flanged. If threaded pipe is

used, the pipe and pipe fittings must not be lighter than Schedule 80 weight. Where copper tubing is permitted, joints must be brazed or be of equally strong metal union type. The melting point of brazing material may not be lower than 1,000 °F (537.8 °C). The method of joining tubing must not decrease the strength of the tubing such as by the cutting of threads.

(3) Non-malleable metals may not be used in the construction of valves or fittings.

(4) Suitable provision must be made in every case to allow for expansion, contraction, jarring and vibration of all pipe. Slip joints may not be used for this purpose.

(5) Piping and fittings must be grouped in the smallest practicable space and must be protected from damage as required by the specification.

(6) All piping, valves and fittings on every portable tank must be leakage tested with gas or air after installation and proved tight at not less than the design pressure of the portable tank on which they are used. In the event of replacement, all such piping, valves, or fittings must be tested in accordance with the requirements of this section before the portable tank is returned to transportation service. The requirements of this section apply to all hoses used on portable tanks, except that hoses may be tested either before or after installation on the portable tank.

(7) All materials used in the construction of portable tanks and their appurtenances may not be subject to destructive attack by the contents of the portable tank.

(8) No aluminum, copper, silver, zinc nor their alloys may be used. Brazed joints may not be used. All parts of a portable tank and its appurtenances used for anhydrous ammonia must be steel.

(9) Each outlet of a portable tank used for the transportation of non-refrigerated liquefied compressed gases, except carbon dioxide, must be provided with a suitable automatic excess-flow valve (see definition in §178.337–1(g) of this subchapter). The valve must be located inside the portable tank or at a point outside the portable tank where the line enters or leaves the portable tank. The valve seat must be

located inside the portable tank or may be located within a welded flange or its companion flange, or within a nozzle or within a coupling. The installation must be made in such a manner as to reasonably assure that any undue strain which causes failure requiring functioning of the valve shall cause failure in such a manner that it will not impair the operation of the valve.

(i) A safety device connection or liquid level gauging device that is constructed so that the outward flow of the tank contents will not exceed that passed by an opening of 0.1397 cm (0.0550 inches) is not required to be equipped with excess-flow valves.

(ii) An excess-flow valve must close automatically if the flow reaches the rated flow of gas or liquid specified by the original valve manufacturer when piping mounted directly on the valve is sheared off before the first valve, pump, or fitting downstream from the excess flow valve.

(iii) An excess-flow valve may be designed with a by-pass, not to exceed a 0.1016 cm (0.040 inches) diameter opening to allow equalization of pressure.

(iv) Filling and discharge lines must be provided with manually operated shut-off valves located as close to the tank as practical. Unless this valve is manually operable at the valve, the line must also have a manual shut-off valve. The use of "Stop-Check" valves to satisfy with one valve the requirements of this section is forbidden. For portable tanks used for refrigerated liquefied gases, a "stop check" valve may be used on the vapor side of the pressure buildup circuit.

(10) Each portable tank used for carbon dioxide or nitrous oxide must be lagged with a suitable insulation material of such thickness that the overall thermal conductance is not more than 0.08 Btu per square foot per degree Fahrenheit differential in temperature per hour. The conductance must be determined at 60 °Fahrenheit. Insulation material used on portable tanks for nitrous oxide must be noncombustible.

(11) Refrigerating or heating coils must be installed in portable tanks used for carbon dioxide and nitrous oxide. Such coils must be tested externally to at least the same pressure as the test pressure of the portable tank.

The coils must also be tested internally to at least twice the working pressure of the heating or refrigerating system to be used, but in no case less than the test pressure of the portable tank. Such coils must be securely anchored. In the event of leakage, the refrigerant or heating medium to be circulated through the coil or coils must have no adverse chemical reaction with the portable tank or its contents.

(12) Excess flow valves are not required for portable tanks used for the transport of refrigerated liquefied gases.

[66 FR 33427, June 21, 2001, as amended at 67 FR 15743, Apr. 3, 2002; 68 FR 32413, May 30, 2003; 68 FR 57632, Oct. 6, 2003; 68 FR 75742, 75743, Dec. 31, 2003; 69 FR 54046, Sept. 7, 2004; 72 FR 25176, May 3, 2007]

#### **§ 173.33 Hazardous materials in cargo tank motor vehicles.**

(a) *General requirements.* (1) No person may offer or accept a hazardous material for transportation in a cargo tank motor vehicle except as authorized by this subchapter.

(2) Two or more materials may not be loaded or accepted for transportation in the same cargo tank motor vehicle if, as a result of any mixture of the materials, an unsafe condition would occur, such as an explosion, fire, excessive increase in pressure or heat, or the release of toxic vapors.

(3) No person may fill and offer for transportation a specification cargo tank motor vehicle for which the prescribed periodic retest or reinspection under subpart E of part 180 of this subchapter is past due until the retest or inspection has been successfully completed. This requirement does not apply to a cargo tank supplied by a motor carrier who is other than the person offering the hazardous material for transportation (see § 180.407(a)(1) of this subchapter), or to any cargo tank filled prior to the retest or inspection due date.

(b) *Loading requirements.* (1) A hazardous material may not be loaded in a cargo tank if during transportation any part of the tank in contact with the hazardous material lading would have a dangerous reaction with the hazardous material.



### § 173.33

### 49 CFR Ch. I (10–1–08 Edition)

(2) A cargo tank may not be loaded with a hazardous material that will have an adverse effect on the tank's integrity or—

(i) May combine chemically with any residue or contaminants in the tank to produce an explosion, fire, excessive increase in pressure, release of toxic vapors or other unsafe condition.

(ii)–(iii) [Reserved]

(iv) May severely corrode or react with the tank material at any concentration and temperature that will exist during transportation.

(v) Is prohibited by § 173.21 or § 173.24 of this subchapter.

(3) Air pressure in excess of ambient atmospheric pressure may not be used to load or unload any lading which may create an air-enriched mixture within the flammability range of the lading in the vapor space of the tank.

(4) To prevent cargo tank rupture in a loading or unloading accident, the loading or unloading rate used must be less than or equal to that indicated on the cargo tank specification plate, except as specified in § 173.318(b)(6). If no loading or unloading rate is marked on the specification plate, the loading or unloading rate and pressure used must be limited such that the pressure in the tank may not exceed 130% of the MAWP.

(c) *Maximum Lading Pressure.* (1) Prior to loading and offering a cargo tank motor vehicle for transportation with material that requires the use of a specification cargo tank, the person must confirm that the cargo tank motor vehicle conforms to the specification required for the lading and that the MAWP of the cargo tank is greater than or equal to the largest pressure obtained under the following conditions:

(i) For compressed gases and certain refrigerated liquids that are not cryogenic liquids, the pressure prescribed in § 173.315 of this subchapter.

(ii) For cryogenic liquids, the pressure prescribed in § 173.318 of this subchapter.

(iii) For liquid hazardous materials loaded in DOT specification cargo tanks equipped with a 1 psig normal vent, the sum of the tank static head plus 1 psig. In addition, for hazardous materials loaded in these cargo tanks,

the vapor pressure of the lading at 115 °F must be not greater than 1 psig, except for gasoline transported in accordance with Special Provision B33 in § 172.102(c)(3) of this subchapter.

(iv) For liquid hazardous materials not covered in paragraph (c)(1)(i), (ii), or (iii) of this section, the sum of the vapor pressure of the lading at 115 °F, plus the tank static head exerted by the lading, plus any pressure exerted by the gas padding, including air in the ullage space or dome.

(v) The pressure prescribed in subpart B, D, E, F, G, or H of this part, as applicable.

(vi) The maximum pressure in the tank during loading or unloading.

(2) Any Specification MC 300, MC 301, MC 302, MC 303, MC 305, MC 306 or MC 312, cargo tank motor vehicle with no marked design pressure or marked with a design pressure of 3 psig or less may be used for an authorized lading where the pressure derived from § 173.33(c)(1) is less than or equal to 3 psig. After December 31, 1990, a cargo tank may not be loaded and offered for transportation unless marked or remarked with an MAWP or design pressure in accordance with 49 CFR 180.405(k).

(3) Any Specification MC 310 or MC 311 cargo tank motor vehicle may be used for an authorized lading where the pressure derived from § 173.33(c)(1) is less than or equal to the MAWP or MWP, respectively, as marked on the specification plate.

(4) Any cargo tank marked or certified before August 31, 1995, marked with a design pressure rather than an MAWP may be used for an authorized lading where the largest pressure derived from § 173.33(c)(1) is less than or equal to the design pressure marked on the cargo tank.

(5) Any material that meets the definition of a Division 6.1, Packing Group I or II (poisonous liquid) material must be loaded in a cargo tank motor vehicle having a MAWP of 25 psig or greater.

(6) *Substitute packagings.* Unless otherwise specified, where MC 307, MC 312, DOT 407 or DOT 412 cargo tanks are authorized, minimum tank design pressure is 172.4 kPa (25 psig) for any Packing Group I or Packing Group II liquid

lading that meets more than one hazard class definition.

(d) *Relief system.* (1) Non-reclosing pressure relief devices are not authorized in any cargo tank except when in series with a reclosing pressure relief device. However, a cargo tank marked or certified before August 31, 1995 which is fitted with non-reclosing pressure relief devices may continue to be used in any hazardous material service for which it is authorized. The requirements in this paragraph do not apply to MC 330, MC 331 and MC 338 cargo tanks.

(2) Each cargo tank motor vehicle used to transport a liquid hazardous material with a gas pad must have a pressure relief system that provides the venting capacity prescribed in § 178.345–10(e) of this subchapter. The requirements in this paragraph do not apply to MC 330, MC 331 and MC 338 cargo tanks.

(3) A cargo tank motor vehicle made to a specification listed in column 1 may have pressure relief devices or outlets conforming to the applicable specification to which the tank was constructed, or the pressure relief devices or outlets may be modified to meet the applicable requirement for the specification listed in column 2 without changing the markings on the tank specification plate. The venting capacity requirements of the original DOT cargo tank specification must be met whenever a pressure relief valve is modified.

| Column 1                                | Column 2           |
|-----------------------------------------|--------------------|
| MC 300, MC 301, MC 302, MC 303, MC 305. | MC 306 or DOT 406. |
| MC 306 .....                            | DOT 406.           |
| MC 304 .....                            | MC 307 or DOT 407. |
| MC 307 .....                            | DOT 407.           |
| MC 310, MC 311 .....                    | MC 312 or DOT 412. |
| MC 312 .....                            | DOT 412.           |
| MC 330 .....                            | MC 331.            |

(e) *Retention of hazardous materials in product piping during transportation.* DOT specification cargo tanks used for the transportation of any material that is a Division 6.1 (poisonous liquid) material, oxidizer liquid, liquid organic peroxide or corrosive liquid (corrosive to skin only) may not be transported with hazardous materials lading retained in the piping, unless the cargo tank motor vehicle is equipped with

bottom damage protection devices meeting the requirements of § 178.337–10 or § 178.345–8(b) of this subchapter, or the accident damage protection requirements of the specification under which it was manufactured. This requirement does not apply to a residue which remains after the piping is drained. A sacrificial device (see § 178.345–1 of this subchapter) may not be used to satisfy the accident damage protection requirements of this paragraph.

(f) An MC 331 type cargo tank may be used where MC 306, MC 307, MC 312, DOT 406, DOT 407 or DOT 412 type cargo tanks are authorized. An MC 307, MC 312, DOT 407 or DOT 412 type cargo tank may be used where MC 306 or DOT 406 type cargo tanks are authorized. A higher integrity tank used instead of a specified tank must meet the same design profile (for example, an MC 331 cargo tank must be lined if used in place of a lined MC 312 cargo tank.)

(g) *Remote control of self-closing stop valves—MC 330, MC 331 and MC 338 cargo tanks.* Each liquid or vapor discharge opening in an MC 330 or MC 331 cargo tank and each liquid filling and liquid discharge line in an MC 338 cargo tank must be provided with a remotely controlled internal self-closing stop valve, except when an MC 330 or MC 331 cargo tank is marked and used exclusively to transport carbon dioxide, or except when an MC 338 is used to transport argon, carbon dioxide, helium, krypton, neon, nitrogen, and xenon. However, if the cargo tank motor vehicle was certified before January 1, 1995, this requirement is applicable only when an MC 330 or MC 331 cargo tank is used to transport a flammable liquid, flammable gas, hydrogen chloride (refrigerated liquid), or anhydrous ammonia; or when an MC 338 cargo tank is used to transport flammable ladings.

(h) A cargo tank motor vehicle authorized by the Transport Canada TDG Regulations (IBR, see § 171.7 of this subchapter) may be used provided it conforms to the applicable requirements in § 171.12 of this subchapter.

[Amdt. 173–212, 54 FR 25005, June 12, 1989]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 173.33, see the List of CFR

## § 173.34

Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 173.34 [Reserved]

### § 173.35 Hazardous materials in IBCs.

(a) No person may offer or accept a hazardous material for transportation in an IBC except as authorized by this subchapter. Each IBC used for the transportation of hazardous materials must conform to the requirements of its specification and regulations for the transportation of the particular commodity. A specification IBC, for which the prescribed periodic retest or inspection under subpart D of part 180 of this subchapter is past due, may not be filled and offered for transportation until the retest or inspection have been successfully completed. This requirement does not apply to any IBC filled prior to the retest or inspection due date.

(b) *Initial use and reuse of IBCs.* (Also see § 180.352 of this subchapter.) An IBC other than a multiwall paper IBC (13M1 and 13M2) may be reused. If an inner liner is required, the inner liner must be replaced before each reuse. Before an IBC is filled and offered for transportation, the IBC and its service equipment must be given an external visual inspection, by the person filling the IBC, to ensure that:

(1) The IBC is free from corrosion, contamination, cracks, cuts, or other damage which would render it unable to pass the prescribed design type test to which it is certified and marked; and

(2) The IBC is marked in accordance with requirements in § 178.703 of this subchapter. Additional marking allowed for each design type may be present. Required markings that are missing, damaged or difficult to read must be restored or returned to original condition.

(c) A metal IBC, or a part thereof, subject to thinning by mechanical abrasion or corrosion due to the lading, must be protected by providing a suitable increase in thickness of material, a lining or some other suitable method of protection. Increased thickness for corrosion or abrasion protection must be added to the wall thickness specified in § 178.705(c)(1)(iv) of this subchapter.

## 49 CFR Ch. I (10–1–08 Edition)

(d) Notwithstanding requirements in § 173.24b of this subpart, when filling an IBC with liquids, sufficient ullage must be left to ensure that, at the mean bulk temperature of 50 °C (122 °F), the IBC is not filled to more than 98 percent of its water capacity.

(e) Where two or more closure systems are fitted in series, the system nearest to the hazardous material being carried must be closed first.

(f) During transportation—

(1) No hazardous material may remain on the outside of the IBC; and

(2) Each IBC must be securely fastened to or contained within the transport unit.

(g) Each IBC used for transportation of solids which may become liquid at temperatures likely to be encountered during transportation must also be capable of containing the substance in the liquid state.

(h) Liquid hazardous materials may only be offered for transportation in a metal, rigid plastic, or composite IBC that is appropriately resistant to an increase of internal pressure likely to develop during transportation.

(1) A rigid plastic or composite IBC may only be filled with a liquid having a vapor pressure less than or equal to the greater of the following two values: the first value is determined from any of the methods in paragraphs (h)(1)(i), (ii) or (iii) of this section. The second value is determined by the method in paragraph (h)(1)(iv) of this section.

(i) The gauge pressure (pressure in the IBC above ambient atmospheric pressure) measured in the IBC at 55 °C (131 °F). This gauge pressure must not exceed two-thirds of the marked test pressure and must be determined after the IBC was filled and closed at 15 °C (60 °F) to less than or equal to 98 percent of its capacity.

(ii) The absolute pressure (vapor pressure of the hazardous material plus atmospheric pressure) in the IBC at 50 °C (122 °F). This absolute pressure must not exceed four-sevenths of the sum of the marked test pressure and 100 kPa (14.5 psia).

(iii) The absolute pressure (vapor pressure of the hazardous material plus atmospheric pressure) in the IBC at 55 °C (131 °F). This absolute pressure must not exceed two-thirds of the sum of the

marked test pressure and 100 kPa (14.5 psia).

(iv) Twice the static pressure of the substance, measured at the bottom of the IBC. This value must not be less than twice the static pressure of water.

(2) Gauge pressure (pressure in the IBC above ambient atmospheric pressure) in metal IBC must not exceed 110 kPa (16 psig) at 50 °C (122 °F) or 130 kPa (18.9 psig) at 55 °C (131 °F).

(i) The requirements in this section do not apply to DOT-56 or -57 portable tanks.

(j) No IBC may be filled with a Packing Group I liquid. Rigid plastic, composite, flexible, wooden or fiberboard IBC used to transport Packing Group I solid materials may not exceed 1.5 cubic meters (53 cubic feet) capacity. For Packing Group I solids, a metal IBC may not exceed 3 cubic meters (106 cubic feet) capacity.

(k) When an IBC is used for the transportation of liquids with a flash point of 60 °C (140 °F) (closed cup) or lower, or powders with the potential for dust explosion, measures must be taken during product loading and unloading to prevent a dangerous electrostatic discharge.

(1) *IBC filling limits.* (1) Except as provided in this section, an IBC may not be filled with a hazardous material in excess of the maximum gross mass marked on that container.

(2) An IBC which is tested and marked for Packing Group II liquid materials may be filled with a Packing Group III liquid material to a gross mass not exceeding 1.5 times the maximum gross mass marked on that container, if all the performance criteria can still be met at the higher gross mass.

(3) An IBC which is tested and marked for liquid hazardous materials may be filled with a solid hazardous material to a gross mass not exceeding the maximum gross mass marked on that container. In addition, an IBC intended for the transport of liquids which is tested and marked for Packing Group II liquid materials may be filled with a Packing Group III solid hazardous material to a gross mass not exceeding the marked maximum gross mass multiplied by 1.5 if all the per-

formance criteria can still be met at the higher gross mass.

(4) An IBC which is tested and marked for Packing Group I solid materials may be filled with a Packing Group II solid material to a gross mass not exceeding the maximum gross mass marked on that container, multiplied by 1.5, if all the performance criteria can be met at the higher gross mass; or a Packing Group III solid material to a gross mass not exceeding the maximum gross mass marked on the IBC, multiplied by 2.25, if all the performance criteria can be met at the higher gross mass. An IBC which is tested and marked for Packing Group II solid materials may be filled with a Packing Group III solid material to a gross mass not exceeding the maximum gross mass marked on the IBC, multiplied by 1.5.

[Amdt. 173-238, 59 FR 38064, July 26, 1994, as amended by Amdt. 173-243, 60 FR 40038, Aug. 4, 1995; 64 FR 10777, Mar. 5, 1999; 66 FR 45380, 45381, Aug. 28, 2001; 68 FR 48569, Aug. 14, 2003; 71 FR 78631, Dec. 29, 2006]

**§ 173.40 General packaging requirements for toxic materials packaged in cylinders.**

When this section is referenced for a Hazard Zone A or B hazardous material elsewhere in this subchapter, the requirements in this section are applicable to cylinders used for that material.

(a) *Authorized cylinders.* (1) A cylinder must conform to a DOT specification or a UN standard prescribed in subpart C of part 178 of this subchapter, except that acetylene cylinders and non-refillable cylinders are not authorized. The use of UN tubes and MEGCs is prohibited for Hazard Zone A materials.

(2) The use of a specification 3AL cylinder made of aluminum alloy 6351-T6 is prohibited for a Division 2.3 Hazard Zone A material or a Division 6.1 Hazard Zone A material.

(3) A UN composite cylinder certified to ISO-11119-3 is not authorized for a Division 2.3 Hazard Zone A or B material.

(4) For UN seamless cylinders used for Hazard Zone A materials, the maximum water capacity is 85 L.

(b) *Outage and pressure requirements.* For DOT specification cylinders, the pressure at 55 °C (131 °F) of Hazard

## § 173.50

## 49 CFR Ch. I (10–1–08 Edition)

Zone A and Hazard Zone B materials may not exceed the service pressure of the cylinder. Sufficient outage must be provided so that the cylinder will not be liquid full at 55 °C (131 °F).

(c) *Closures.* Each cylinder containing a Hazard Zone A material must be closed with a plug or valve conforming to the following:

(1) Each plug or valve must have a taper-threaded connection directly to the cylinder and be capable of withstanding the test pressure of the cylinder without damage or leakage.

(2) Each valve must be of the packless type with non-perforated diaphragm, except that, for corrosive materials, a valve may be of the packed type with an assembly made gas-tight by means of a seal cap with gasketed joint attached to the valve body or the cylinder to prevent loss of material through or past the packing.

(3) Each valve outlet must be sealed by a threaded cap or threaded solid plug and inert gasketing material.

(4) The materials of construction for the cylinder, valves, plugs, outlet caps, luting, and gaskets must be compatible with each other and with the lading.

(d) *Additional handling protection.* Each cylinder or cylinder overpack combination offered for transportation containing a Division 2.3 or 6.1 Hazard Zone A or B material must conform to the valve damage protection performance requirements of this section. In addition to the requirements of this section, overpacks must conform to the overpack provisions of § 173.25.

(1) DOT specification cylinders must conform to the following:

(i) Each cylinder with a wall thickness at any point of less than 2.03 mm (0.08 inch) and each cylinder that does not have fitted valve protection must be overpacked in a box. The box must conform to overpack provisions in § 173.25. Box and valve protection must be of sufficient strength to protect all parts of the cylinder and valve, if any, from deformation and breakage resulting from a drop of 2.0 m (7 ft) or more onto a non-yielding surface, such as concrete or steel, impacting at an orientation most likely to cause damage. “Deformation” means a cylinder or valve that is bent, distorted, mangled,

misshapen, twisted, warped, or in a similar condition.

(ii) Each cylinder with a valve must be equipped with a protective metal cap, other valve protection device, or an overpack which is sufficient to protect the valve from breakage or leakage resulting from a drop of 2.0 m (7 ft) onto a non-yielding surface, such as concrete or steel. Impact must be at an orientation most likely to cause damage.

(2) Each UN cylinder containing a Hazard Zone A or Hazard Zone B material must have a minimum test pressure in accordance with P200 of the UN Recommendations (IBR, see § 171.7 of this subchapter). For Hazard Zone A gases, the cylinder must have a minimum wall thickness of 3.5 mm if made of aluminum alloy or 2 mm if made of steel or, alternatively, cylinders may be packed in a rigid outer packaging that meets the Packing Group 1 performance level when tested as prepared for transport, and that is designed and constructed to protect the cylinder and valve from puncture or damage that may result in release of the gas.

(e) *Interconnection.* Cylinders may not be manifolded or connected. This provision does not apply to MEGCs containing Hazard Zone B materials in accordance with § 173.312.

[67 FR 51642, Aug. 8, 2002, as amended at 67 FR 61289, Sept. 30, 2002; 68 FR 24660, May 8, 2003; 71 FR 33880, June 12, 2006]

## Subpart C—Definitions, Classification and Packaging for Class 1

SOURCE: Amdt. 173–224, 55 FR 52617, Dec. 21, 1990, unless otherwise noted.

### § 173.50 Class 1—Definitions.

(a) *Explosive.* For the purposes of this subchapter, an *explosive* means any substance or article, including a device, which is designed to function by explosion (*i.e.*, an extremely rapid release of gas and heat) or which, by chemical reaction within itself, is able to function in a similar manner even if not designed to function by explosion, unless the substance or article is otherwise classed under the provisions of this

subchapter. The term includes a pyrotechnic substance or article, unless the substance or article is otherwise classed under the provisions of this subchapter.

(b) Explosives in Class 1 are divided into six divisions as follows:

(1) *Division 1.1* consists of explosives that have a mass explosion hazard. A mass explosion is one which affects almost the entire load instantaneously.

(2) *Division 1.2* consists of explosives that have a projection hazard but not a mass explosion hazard.

(3) *Division 1.3* consists of explosives that have a fire hazard and either a minor blast hazard or a minor projection hazard or both, but not a mass explosion hazard.

(4) *Division 1.4* consists of explosives that present a minor explosion hazard. The explosive effects are largely confined to the package and no projection of fragments of appreciable size or range is to be expected. An external fire must not cause virtually instantaneous explosion of almost the entire contents of the package.

(5) *Division 1.5*<sup>1</sup> consists of very insensitive explosives. This division is comprised of substances which have a mass explosion hazard but are so insensitive that there is very little probability of initiation or of transition from burning to detonation under normal conditions of transport.

(6) *Division 1.6*<sup>2</sup> consists of extremely insensitive articles which do not have a mass explosive hazard. This division is comprised of articles which contain only extremely insensitive detonating substances and which demonstrate a negligible probability of accidental initiation or propagation.

[Amdt. 173-224, 55 FR 52617 Dec. 21, 1990, as amended at 56 FR 66267, Dec. 20, 1991; 66 FR 45183, Aug. 28, 2001; 68 FR 48569, Aug. 14, 2003]

<sup>1</sup>The probability of transition from burning to detonation is greater when large quantities are transported in a vessel.

<sup>2</sup>The risk from articles of Division 1.6 is limited to the explosion of a single article.

#### **§ 173.51 Authorization to offer and transport explosives.**

(a) Unless otherwise provided in this subpart, no person may offer for transportation or transport an explosive, unless it has been tested and classed and approved by the Associate Administrator (§ 173.56).

(b) Reports of explosives approved by the Department of Defense or the Department of Energy must be filed with, and receive acknowledgement in writing by, the Associate Administrator prior to such explosives being offered for transportation.

[Amdt. 173-224, 55 FR 52617, Dec. 21, 1990, as amended by 66 FR 45379, Aug. 28, 2001]

#### **§ 173.52 Classification codes and compatibility groups of explosives.**

(a) The classification code for an explosive, which is assigned by the Associate Administrator in accordance with this subpart, consists of the division number followed by the compatibility group letter. Compatibility group letters are used to specify the controls for the transportation, and storage related thereto, of explosives and to prevent an increase in hazard that might result if certain types of explosives were stored or transported together. Transportation compatibility requirements for carriers are prescribed in §§ 174.81, 175.78, 176.83 and 177.848 of this subchapter for transportation by rail, air, vessel, and public highway, respectively, and storage incidental thereto.

(b) Compatibility groups and classification codes for the various types of explosives are set forth in the following tables. Table 1 sets forth compatibility groups and classification codes for substances and articles described in the first column of table 1. Table 2 shows the number of classification codes that are possible within each explosive division. Altogether, there are 35 possible classification codes for explosives.

TABLE 1—CLASSIFICATION CODES

| Description of substances or article to be classified                                                                                                                                                                                                                                                                                     | Compat-<br>ibility<br>group | Classi-<br>fication<br>code  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|------------------------------|
| Primary explosive substance .....                                                                                                                                                                                                                                                                                                         | A                           | 1.1A                         |
| Article containing a primary explosive substance and not containing two or more effective protective features. Some articles, such as detonators for blasting, detonator assemblies for blasting and primers, cap-type, are included, even though they do not contain primary explosives..                                                | B                           | 1.1B<br>1.2B<br>1.4B         |
| Propellant explosive substance or other deflagrating explosive substance or article containing such explosive substance.                                                                                                                                                                                                                  | C                           | 1.1C<br>1.2C<br>1.3C<br>1.4C |
| Secondary detonating explosive substance or black powder or article containing a secondary detonating explosive substance, in each case without means of initiation and without a propelling charge, or article containing a primary explosive substance and containing two or more effective protective features.                        | D                           | 1.1D<br>1.2D<br>1.4D<br>1.5D |
| Article containing a secondary detonating explosive substance, without means of initiation, with a propelling charge (other than one containing flammable liquid or gel or hypergolic liquid).                                                                                                                                            | E                           | 1.1E<br>1.2E<br>1.4E         |
| Article containing a secondary detonating explosive substance with its means of initiation, with a propelling charge (other than one containing flammable liquid or gel or hypergolic liquid) or without a propelling charge.                                                                                                             | F                           | 1.1F<br>1.2F<br>1.3F<br>1.4F |
| Pyrotechnic substance or article containing a pyrotechnic substance, or article containing both an explosive substance and an illuminating, incendiary, tear-producing or smoke-producing substance (other than a water-activated article or one containing white phosphorus, phosphide or flammable liquid or gel or hypergolic liquid). | G                           | 1.1G<br>1.2G<br>1.3G<br>1.4G |
| Article containing both an explosive substance and white phosphorus .....                                                                                                                                                                                                                                                                 | H                           | 1.2H<br>1.3H                 |
| Article containing both an explosive substance and flammable liquid or gel .....                                                                                                                                                                                                                                                          | J                           | 1.1J<br>1.2J<br>1.3J         |
| Article containing both an explosive substance and a toxic chemical agent .....                                                                                                                                                                                                                                                           | K                           | 1.2K<br>1.3K                 |
| Explosive substance or article containing an explosive substance and presenting a special risk (e.g., due to water-activation or presence of hypergolic liquids, phosphides or pyrophoric substances) needing isolation of each type.                                                                                                     | L                           | 1.1L<br>1.2L<br>1.3L         |
| Articles containing only extremely insensitive detonating substances. ....                                                                                                                                                                                                                                                                | N                           | 1.6N                         |
| Substance or article so packed or designed that any hazardous effects arising from accidental functioning are limited to the extent that they do not significantly hinder or prohibit fire fighting or other emergency response efforts in the immediate vicinity of the package.                                                         | S                           | 1.4S                         |

TABLE 2—SCHEME OF CLASSIFICATION OF EXPLOSIVES, COMBINATION OF HAZARD DIVISION WITH COMPATIBILITY GROUP

| Hazard<br>division | Compatibility group |       |       |       |       |       |       |       |       |       |       |       |       |     |
|--------------------|---------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----|
|                    | A                   | B     | C     | D     | E     | F     | G     | H     | J     | K     | L     | N     | S     | A-S |
| 1.1                | 1.1A                | 1.1B  | 1.1C  | 1.1D  | 1.1E  | 1.1F  | 1.1G  | ..... | 1.1J  | ..... | 1.1L  | ..... | ..... | 9   |
| 1.2                | .....               | 1.2B  | 1.2C  | 1.2D  | 1.2E  | 1.2F  | 1.2G  | 1.2H  | 1.2J  | 1.2K  | 1.2L  | ..... | ..... | 10  |
| 1.3                | .....               | ..... | 1.3C  | ..... | ..... | 1.3F  | 1.3G  | 1.3H  | 1.3J  | 1.3K  | 1.3L  | ..... | ..... | 7   |
| 1.4                | .....               | 1.4B  | 1.4C  | 1.4D  | 1.4E  | 1.4F  | 1.4G  | ..... | ..... | ..... | ..... | ..... | 1.4S  | 7   |
| 1.5                | .....               | ..... | ..... | 1.5D  | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 1   |
| 1.6                | .....               | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 1.6N  | ..... | 1   |
| 1.6                | 1                   | 3     | 4     | 4     | 3     | 4     | 4     | 2     | 3     | 2     | 3     | 1     | 1     | 35  |

[Amdt. 173–224, 55 FR 52617, Dec. 21, 1990, as amended by Amdt. 173–241, 59 FR 67492, Dec. 29, 1994; 64 FR 51918, Sept. 27, 1999; 66 FR 45379, Aug. 28, 2001]

### § 173.53 Provisions for using old classifications of explosives.

Where the classification system in effect prior to January 1, 1991, is referenced in State or local laws, ordinances or regulations not pertaining to

the transportation of hazardous materials, the following table may be used to compare old and new hazard class names:

| Current classification | Class name prior to Jan. 1, 1991 |
|------------------------|----------------------------------|
| Division 1.1 .....     | Class A explosives.              |
| Division 1.2 .....     | Class A or Class B explosives.   |
| Division 1.3 .....     | Class B explosive.               |
| Division 1.4 .....     | Class C explosives.              |
| Division 1.5 .....     | Blasting agents.                 |
| Division 1.6 .....     | No applicable hazard class.      |

**§ 173.54 Forbidden explosives.**

Unless otherwise provided in this subchapter, the following explosives shall not be offered for transportation or transported:

(a) An explosive that has not been approved in accordance with § 173.56 of this subpart.

(b) An explosive mixture or device containing a chlorate and also containing:

(1) An ammonium salt, including a substituted ammonium or quaternary ammonium salt; or

(2) An acidic substance, including a salt of a weak base and a strong acid.

(c) A leaking or damaged package or article containing an explosive.

(d) Propellants that are unstable, condemned or deteriorated.

(e) Nitroglycerin, diethylene glycol dinitrate, or any other liquid explosives not specifically authorized by this subchapter.

(f) A loaded firearm (except as provided in 49 CFR 1544.219).

(g) Fireworks that combine an explosive and a detonator.

(h) Fireworks containing yellow or white phosphorus.

(i) A toy torpedo, the maximum outside dimension of which exceeds 23 mm (0.906 inch), or a toy torpedo containing a mixture of potassium chlorate, black antimony (antimony sulfide), and sulfur, if the weight of the explosive material in the device exceeds 0.26 g (0.01 ounce).

(j) Explosives specifically forbidden in the § 172.101 table of this subchapter.

(k) Explosives not meeting the acceptance criteria specified in § 173.57 of this subchapter.

(l) An explosive article with its means of initiation or ignition installed, unless approved in accordance with § 173.56.

[Amdt. 173–224, 55 FR 52617 Dec. 21, 1990, as amended at 56 FR 66267, Dec. 20, 1991; Amdt. 173–236, 58 FR 50236, Sept. 24, 1993; 67 FR 61013, Sept. 27, 2002; 68 FR 48569, Aug. 14, 2003]

**§ 173.55 [Reserved]****§ 173.56 New explosives—definition and procedures for classification and approval.**

(a) Definition of new explosive. For the purposes of this subchapter a *new explosive* means an explosive produced by a person who:

(1) Has not previously produced that explosive; or

(2) Has previously produced that explosive but has made a change in the formulation, design or process so as to alter any of the properties of the explosive. An explosive will not be considered a “new explosive” if an agency listed in paragraph (b) of this section has determined, and confirmed in writing to the Associate Administrator, that there are no significant differences in hazard characteristics from the explosive previously approved.

(b) Examination, classing and approval. Except as provided in paragraph (j) of this section, no person may offer a new explosive for transportation unless that person has specified to the examining agency the ranges of composition of ingredients and compounds, showing the intended manufacturing tolerances in the composition of substances or design of articles which will be allowed in that material or device, and unless it has been examined, classed and approved as follows:

(1) Except for an explosive made by or under the direction or supervision of the Department of Defense (DOD) or the Department of Energy (DOE), a new explosive must be examined and assigned a recommended shipping description, division and compatibility group, based on the tests and criteria prescribed in §§ 173.52, 173.57 and 173.58. The person requesting approval of the new explosive must submit to the Associate Administrator a report of the examination and assignment of a recommended shipping description, division, and compatibility group. If the Associate Administrator finds the approval request meets the regulatory criteria, the new explosive will be approved in writing and assigned an EX number. The examination must be performed by a person who is approved by the Associate Administrator under the



provisions of subpart H of part 107 of this chapter and who—

(i) Has (directly, or through an employee involved in the examination) at least ten years of experience in the examination, testing and evaluation of explosives;

(ii) Does not manufacture or market explosives, and is not controlled by or financially dependent on any entity that manufactures or markets explosives, and whose work with respect to explosives is limited to examination, testing and evaluation; and

(iii) Is a resident of the United States.

(2) A new explosive made by or under the direction or supervision of a component of the DOD may be examined, classed, and concurred in by:

(i) U.S. Army Technical Center for Explosives Safety (SMCAC-EST), Naval Sea Systems Command (SEA-9934), or Air Force Safety Agency (SEW), when approved by the Chairman, DOD Explosives Board, in accordance with the DOD Explosives Hazard Classification Procedures (IBR, see §171.7 of the subchapter); or

(ii) The agencies and procedures specified in paragraph (b)(1) of this section.

(3) A new explosive made by or under the direction or supervision of the Department of Energy (DOE) may be—

(i) Examined by the DOE in accordance with the DOD Explosives Hazard Classification Procedures, and must be classed and approved by DOE; or

(ii) Examined, classed, and approved in accordance with paragraph (b)(1) of this section.

(4) For a material shipped under the description of “ammonium nitrate-fuel oil mixture (ANFO)”, the only test required for classification purposes is the Cap Sensitivity Test—Test Method 5(a) prescribed in the Explosive Test Manual (UN Manual of Tests and Criteria) (IBR, see §171.7 of the subchapter). The test must be performed by an agency listed in paragraph (b)(1), (b)(2), or (b)(3) of this section, the manufacturer, or the shipper. A copy of the test report must be submitted to the Associate Administrator before the material is offered for transportation, and a copy of the test report must be retained by the shipper for as long as that material is shipped. At a minimum,

the test report must contain the name and address of the person or organization conducting the test, date of the test, quantitative description of the mixture, including prill size and porosity, and a description of the test results.

(c) Filing DOD or DOE approval report. DOD or DOE must file a copy of each approval, accompanied by supporting laboratory data, with the Associate Administrator and receive acknowledgement in writing before offering the new explosive for transportation, unless the new explosive is:

(1) Being transported under paragraph (d) or (e) of this section; or

(2) Covered by a national security classification currently in effect.

(d) Transportation of explosive samples for examination. Notwithstanding the requirements of paragraph (b) of this section with regard to the transportation of a new explosive that has not been approved, a person may offer a sample of a new explosive for transportation, by railroad, highway, or vessel from the place where it was produced to an agency identified in paragraph (b) of this section, for examination if—

(1) The new explosive has been assigned a tentative shipping description and class in writing by the testing agency;

(2) The new explosive is packaged as required by this part according to the tentative description and class assigned, unless otherwise specified in writing by the testing agency; and,

(3) The package is labeled as required by this subchapter and the following is marked on the package:

(i) The words “SAMPLE FOR LABORATORY EXAMINATION”;

(ii) The net weight of the new explosive; and

(iii) The tentative shipping name and identification number.

(e) Transportation of unapproved explosives for developmental testing. Notwithstanding the requirements of paragraph (b) of this section, the owner of a new explosive that has not been examined or approved may transport that new explosive from the place where it was produced to an explosives testing range if—

(1) It is not a primary (a 1.1A initiating) explosive or a forbidden explosive according to this subchapter;

(2) It is described as a Division 1.1 explosive (substance or article) and is packed, marked, labeled, described on shipping papers and is otherwise offered for transportation in conformance with the requirements of this subchapter applicable to Division 1.1;

(3) It is transported in a motor vehicle operated by the owner of the explosive; and

(4) It is accompanied by a person, in addition to the operator of the motor vehicle, who is qualified by training and experience to handle the explosive.

(f) Notwithstanding the requirements of paragraphs (b) and (d) of this section, the Associate Administrator may approve a new explosive on the basis of an approval issued for the explosive by the competent authority of a foreign government, or when examination of the explosive by a person approved by the Associate Administrator is impracticable, on the basis of reports of tests conducted by disinterested third parties, or may approve the transportation of an explosives sample for the purpose of examination by a person approved by the Associate Administrator.

(g) An explosive may be transported under subparts B or C of part 171 or § 176.11 of this subchapter without the approval of the Associate Administrator as required by paragraph (b) of this section if the Associate Administrator has acknowledged in writing the acceptability of an approval issued by the competent authority of a foreign government pursuant to the provisions of the UN Recommendations, the ICAO Technical Instructions, the IMDG Code (IBR, see § 171.7 of this subchapter), or other national or international regulations based on the UN Recommendations. In such a case, a copy of the foreign competent authority approval, and a copy of the written acknowledgement of its acceptance must accompany each shipment of that explosive.

(h) The requirements of this section do not apply to cartridges, small arms which are:

(1) Not a forbidden explosive under § 173.54 of this subchapter;

(2) Ammunition for rifle, pistol, or shotgun;

(3) Ammunition with inert projectile or blank ammunition; and

(4) Ammunition not exceeding 50 caliber for rifle or pistol cartridges or 8 gauge for shotgun shells.

Cartridges, small arms meeting the criteria of this paragraph (h) may be assigned a classification code of 1.4S by the manufacturer.

(i) If experience or other data indicate that the hazard of a material or a device containing an explosive composition is greater or less than indicated according to the definition and criteria specified in §§ 173.50, 173.56, and 173.58 of this subchapter, the Associate Administrator may specify a classification or except the material or device from the requirements of this subchapter.

(j) Fireworks. Notwithstanding the requirements of paragraph (b) of this section, Division 1.3 and 1.4 fireworks may be classed and approved by the Associate Administrator without prior examination and offered for transportation if the following conditions are met:

(1) The fireworks are manufactured in accordance with the applicable requirements in APA Standard 87-1 (IBR, see § 171.7 of this subchapter);

(2) A thermal stability test is conducted on the device by the BOE, the BOM, or the manufacturer. The test must be performed by maintaining the device, or a representative prototype of a large device such as a display shell, at a temperature of 75 °C (167 °F) for 48 consecutive hours. When a device contains more than one component, those components which could be in physical contact with each other in the finished device must be placed in contact with each other during the thermal stability test; and

(3) The manufacturer applies in writing to the Associate Administrator following the applicable requirements in APA Standard 87-1, and is notified in writing by the Associate Administrator that the fireworks have been classed, approved, and assigned an EX-number. Each application must be complete, including all relevant background data and copies of all applicable drawings, test results, and any other pertinent information on each device for which

## § 173.57

## 49 CFR Ch. I (10–1–08 Edition)

approval is being requested. The manufacturer must sign the application and certify that the device for which approval is requested conforms to APA Standard 87–1 and that the descriptions and technical information contained in the application are complete and accurate. If the application is denied, the manufacturer will be notified in writing of the reasons for the denial. The Associate Administrator may require that the fireworks be examined by an agency listed in paragraph (b)(1) of this section.

[Amdt. 173–224, 55 FR 52617 Dec. 21, 1990, as amended at 56 FR 66267, Dec. 20, 1991; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; 62 FR 51560, Oct. 1, 1997; 63 FR 37461, July 10, 1998; 64 FR 10777, Mar. 5, 1999; 66 FR 45379, Aug. 28, 2001; 68 FR 75743, Dec. 31, 2003; 72 FR 25177, May 3, 2007]

### § 173.57 Acceptance criteria for new explosives.

(a) Unless otherwise excepted, an explosive substance must be subjected to the Drop Weight Impact Sensitivity Test (Test Method 3(a)(i)), the Friction Sensitivity Test (Test Method 3(b)(iii)), the Thermal Stability Test (Test Method 3(c)) at 75 °C (167 °F) and the Small-Scale Burning Test (Test Method 3(d)(i)), each as described in the Explosive Test Manual (UN Manual of Tests and Criteria) (IBR, see § 171.7 of this subchapter). A substance is forbidden for transportation if any one of the following occurs:

- (1) For a liquid, failure to pass the test criteria when tested in the Drop Weight Impact Sensitivity Test apparatus for liquids;
  - (2) For a solid, failure to pass the test criteria when tested in the Drop Weight Impact Sensitivity Test apparatus for solids;
  - (3) The substance has a friction sensitiveness equal to or greater than that of dry pentaerythrite tetranitrate (PETN) when tested in the Friction Sensitivity Test;
  - (4) The substance fails to pass the test criteria specified in the Thermal Stability Test at 75 °C (167 °F); or
  - (5) Explosion occurs when tested in the Small-Scale Burning Test.
- (b) An explosive article, packaged or unpackaged, or a packaged explosive substance must be subjected to the

Thermal Stability Test for Articles and Packaged Articles (Test method 4(a)(i)) and the Twelve Meter Drop Test (Test Method 4(b)(ii)), when appropriate, in the Explosive Test Manual. An article or packaged substance is forbidden for transportation if evidence of thermal instability or excessive impact sensitivity is found in those tests according to the criteria and methods of assessing results prescribed therein.

(c) Dynamite (explosive, blasting, type A) is forbidden for transportation if any of the following occurs:

(1) It does not have uniformly mixed with the absorbent material a satisfactory antacid in a quantity sufficient to have the acid neutralizing power of an amount of magnesium carbonate equal to one percent of the nitroglycerin or other liquid explosive ingredient;

(2) During the centrifuge test (Test Method D–2, in appendix D to this part) or the compression test (Test Method D–3 in appendix D to this part), a non-gelatin dynamite loses more than 3 percent by weight of the liquid explosive or a gelatin dynamite loses more than 10 percent by weight of the liquid explosive; or

(3) During the leakage test (Test Method D–1 in appendix D to this part), there is any loss of liquid.

[Amdt. 173–224, 55 FR 52617 Dec. 21, 1990, as amended at 58 FR 51532, Oct. 1, 1993; 64 FR 51918, Sept. 27, 1999; 68 FR 75743, Dec. 31, 2003]

### § 173.58 Assignment of class and division for new explosives.

(a) *Division 1.1, 1.2, 1.3, and 1.4 explosives.* In addition to the test prescribed in § 173.57 of this subchapter, a substance or article in these divisions must be subjected to Test Methods 6(a), 6(b), and 6(c), as described in the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter), for assignment to an appropriate division. The criteria for assignment of class and division are as follows:

- (1) Division 1.1 if the major hazard is mass explosion;
- (2) Division 1.2 if the major hazard is dangerous projections;
- (3) Division 1.3 if the major hazard is radiant heat or violent burning, or both, but there is no blast or projection hazard;

(4) Division 1.4 if there is a small hazard with no mass explosion and no projection of fragments of appreciable size or range;

(5) Division 1.4 Compatibility Group S (1.4S) if the hazardous effects are confined within the package or the blast and projection effects do not significantly hinder emergency response efforts; or

(6) Not in the explosive class if the substance or article does not have significant explosive hazard or if the effects of explosion are completely confined within the article.

(b) Division 1.5 explosive. Except for ANFO, a substance that has been examined in accordance with the provisions §173.57(a) of this subchapter, must be subjected to the following additional tests: Cap Sensitivity Test, Princess Incendiary Spark Test, DDT Test, and External Fire Test, each as described in the Explosive Test Manual. A material may not be classed as a Division 1.5 explosive if any of the following occurs:

(1) Detonation occurs in the Cap Sensitivity Test (Test Method 5(a));

(2) Detonation occurs in the DDT Test (Test Method 5(b)(ii));

(3) An explosion, evidenced by a loud noise and projection of fragments, occurs in the External Fire Test (Test Method 5(c), or

(4) Ignition or explosion occurs in the Princess Incendiary Spark Test (Test Method 5(d)).

(c) Division 1.6 explosive. (1) In order to be classed as a 1.6 explosive, an article must pass all of the following tests, as prescribed in the Explosive Test Manual:

(i) The 1.6 Article External Fire Test;

(ii) The 1.6 Article Slow Cook-off Test;

(iii) The 1.6 Article Propagation Test;

and

(iv) The 1.6 Article Bullet Impact Test.

(2) A substance intended for use as the explosive load in an article of Division 1.6 must be an extremely insensitive detonating substance (EIDS). In order to determine if a substance is an EIDS, it must be subjected to the tests in paragraphs (c)(2)(i) through (c)(2)(x) of this section, which are described in the Explosive Test Manual. The sub-

stance must be tested in the form (i.e., composition, granulation, density, etc.) in which it is to be used in the article. A substance is not an EIDS if it fails any of the following tests:

(i) The Drop Weight Impact Sensitivity Test;

(ii) The Friction Sensitivity Test;

(iii) The Thermal Sensitivity Test at 75 °C (167 °F);

(iv) The Small Scale Burning Test;

(v) The EIDS Cap Test;

(vi) The EIDS Gap Test;

(vii) The Susan Test;

(viii) The EIDS Bullet Impact Test;

(ix) The EIDS External Fire Test; and

(x) The EIDS Slow Cook-off Test.

(d) The Associate Administrator may waive or modify certain test(s) identified in §§173.57 and 173.58 of this subchapter, or require additional testing, if appropriate. In addition, the Associate Administrator may limit the quantity of explosive in a device.

(e) Each explosive is assigned a compatibility group letter by the Associate Administrator based on the criteria prescribed in §173.52(b) of this subchapter.

[Amdt. 173-224, 55 FR 52617 Dec. 21, 1990, as amended at 56 FR 66267, Dec. 20, 1991; 63 FR 52849, Oct. 1, 1998; 66 FR 45379, Aug. 28, 2001; 68 FR 75743, Dec. 31, 2003]

#### § 173.59 Description of terms for explosives.

For the purpose of this subchapter, a description of the following terms is provided for information only. They must not be used for purposes of classification or to replace proper shipping names prescribed in §172.101 of this subchapter.

*Ammonium-nitrate—fuel oil mixture (ANFO).* A blasting explosive containing no essential ingredients other than prilled ammonium nitrate and fuel oil.

*Ammunition.* Generic term related mainly to articles of military application consisting of all types of bombs, grenades, rockets, mines, projectiles and other similar devices or contrivances.

*Ammunition, illuminating, with or without burster, expelling charge or propelling charge.* Ammunition designed to produce a single source of intense light

for lighting up an area. The term includes illuminating cartridges, grenades and projectiles, and illuminating and target identification bombs. The term excludes the following articles which are listed separately: *cartridges, signal; signal devices; hand signals; distress flares, aerial and flares, surface.*

*Ammunition, incendiary.* Ammunition containing an incendiary substance which may be a solid, liquid or gel including white phosphorus. Except when the composition is an explosive *per se*, it also contains one or more of the following: a propelling charge with primer and igniter charge, or a fuze with burster or expelling charge. The term includes: *Ammunition, incendiary, liquid or gel, with burster, expelling charge or propelling charge; Ammunition, incendiary with or without burster, expelling charge or propelling charge; and Ammunition, incendiary, white phosphorus, with burster, expelling charge or propelling charge.*

*Ammunition, practice.* Ammunition without a main bursting charge, containing a burster or expelling charge. Normally it also contains a fuze and propelling charge. The term excludes the following article which is listed separately: *Grenades, practice.*

*Ammunition, proof.* Ammunition containing pyrotechnic substance, used to test the performance or strength of new ammunition, weapon component or assemblies.

*Ammunition, smoke.* Ammunition containing a smoke-producing substance such as chlorosulphonic acid mixture (CSAM), titanium tetrachloride (FM), white phosphorus, or smoke-producing substance whose composition is based on hexachlorothannol (HC) or red phosphorus. Except when the substance is an explosive *per se*, the ammunition also contains one or more of the following: a propelling charge with primer and igniter charge, or a fuze with burster or expelling charge. The term includes: *Ammunition, smoke, with or without burster, expelling charge or propelling charge; Ammunition, smoke, white phosphorus with burster, expelling charge or propelling charge.*

*Ammunition, tear-producing with burster, expelling charge or propelling charge.* Ammunition containing tear-producing substance. It may also contain one or

more of the following: a pyrotechnic substance, a propelling charge with primer and igniter charge, or a fuze with burster or expelling charge.

*Ammunition, toxic.* Ammunition containing toxic agent. It may also contain one or more of the following: a pyrotechnic substance, a propelling charge with primer and igniter charge, or a fuze with burster or expelling charge.

*Articles, explosive, extremely insensitive (Articles, EEI).* Articles that contain only extremely insensitive detonating substances and which demonstrate a negligible probability of accidental initiation or propagation under normal conditions of transport and which have passed Test Series 7.

*Articles, pyrophoric.* Articles which contain a pyrophoric substance (capable of spontaneous ignition when exposed to air) and an explosive substance or component. The term excludes articles containing white phosphorus.

*Articles, pyrotechnic for technical purposes.* Articles which contain pyrotechnic substances and are used for technical purposes, such as heat generation, gas generation, theatrical effects, etc. The term excludes the following articles which are listed separately: all ammunition; *cartridges, signal; cutters, cable, explosive; fireworks; flares, aerial; flares, surface; release devices, explosives; rivets, explosive; signal devices, hand; signals, distress; signals, railway track, explosive; and signals, smoke.*

*Black powder (gunpowder).* Substance consisting of an intimate mixture of charcoal or other carbon and either potassium or sodium nitrate, and sulphur. It may be meal, granular, compressed, or pelletized.

*Bombs.* Explosive articles which are dropped from aircraft. They may contain a flammable liquid with bursting charge, a photo-flash composition or bursting charge. The term excludes *torpedoes (aerial)* and includes *bombs, photo-flash; bombs with bursting charge; bombs with flammable liquids, with bursting charge.*

*Boosters.* Articles consisting of a charge of detonating explosive without means of initiation. They are used to

increase the initiating power of detonators or detonating cord.

*Bursters, explosive.* Articles consisting of a small charge of explosive to open projectiles or other ammunition in order to disperse their contents.

*Cartridges, blank.* Articles which consist of a cartridge case with a center or rim fire primer and a confined charge of smokeless or black powder, but no projectile. Used in training, saluting, or in starter pistols, etc.

*Cartridges, flash.* Articles consisting of a casing, a primer and flash powder, all assembled in one piece for firing.

*Cartridges for weapons.* (1) Fixed (assembled) or semi-fixed (partially assembled) ammunition designed to be fired from weapons. Each cartridge includes all the components necessary to function the weapon once. The name and description should be used for military small arms cartridges that cannot be described as cartridges, small arms. Separate loading ammunition is included under this name and description when the propelling charge and projectile are packed together (see also Cartridges, blank).

(2) Incendiary, smoke, toxic, and tear-producing cartridges are described under *ammunition, incendiary*, etc.

*Cartridges for weapons, inert projectile.* Ammunition consisting of a casing with propelling charge and a solid or empty projectile.

*Cartridges, oil well.* Articles consisting of a casing of thin fiber, metal or other material containing only propellant explosive. The term excludes charges, shaped, commercial.

*Cartridges, power device.* Articles designed to accomplish mechanical actions. They consist of a casing with a charge of deflagrating explosive and a means of ignition. The gaseous products of the deflagration produce inflation, linear or rotary motion; activate diaphragms, valves or switches, or project fastening devices or extinguishing agents.

*Cartridges, signal.* Articles designed to fire colored flares or other signals from signal pistols or devices.

*Cartridges, small arms.* Ammunition consisting of a cartridge case fitted with a center or rim fire primer and containing both a propelling charge and solid projectile(s). They are de-

signed to be fired in weapons of caliber not larger than 19.1 mm. Shotgun cartridges of any caliber are included in this description. The term excludes: Cartridges, small arms, blank, and some military small arms cartridges listed under *Cartridges for weapons, inert projectile*.

*Cases, cartridge, empty with primer.* Articles consisting of a cartridge case made from metal, plastics or other non-flammable materials, in which only the explosive component is the primer.

*Cases, combustible, empty, without primer.* Articles consisting of cartridge cases made partly or entirely from nitrocellulose.

*Charges, bursting.* Articles consisting of a charge of detonating explosive such as hexolite, octolite, or plastics-bonded explosive designed to produce effect by blast or fragmentation.

*Charges, demolition.* Articles consisting of a charge of detonating explosive in a casing of fiberboard, plastics, metal or other material. The term excludes articles identified as bombs, mines, etc.

*Charges, depth.* Articles consisting of a charge of detonating explosive contained in a drum or projectile. They are designed to detonate under water.

*Charges, expelling.* A charge of deflagrating explosive designed to eject the payload from the parent article without damage.

*Charges, explosive, without detonator.* Articles consisting of a charge of detonating explosive without means of initiation, used for explosive welding, joining, forming, and other processes.

*Charges, propelling.* Articles consisting of propellant charge in any physical form, with or without a casing, for use in cannon or for reducing drag for projectiles or as a component of rocket motors.

*Charges, propelling for cannon.* Articles consisting of a propellant charge in any physical form, with or without a casing, for use in a cannon.

*Charges, shaped, without detonator.* Articles consisting of a casing containing a charge of detonating explosive with a cavity lined with rigid material, without means of initiation. They are designed to produce a powerful, penetrating jet effect.

*Charges, shaped, flexible, linear.* Articles consisting of a V-shaped core of a detonating explosive clad by a flexible metal sheath.

*Charges, supplementary, explosive.* Articles consisting of a small removable booster used in the cavity of a projectile between the fuze and the bursting charge.

*Components, explosive train, n.o.s.* Articles containing an explosive designed to transmit a detonation or deflagration within an explosive train.

*Contrivance, water-activated with burster, expelling charge or propelling charge.* Articles whose functioning depends of physico-chemical reaction of their contents with water.

*Cord, detonating, flexible.* Articles consisting of a core of detonating explosive enclosed in spun fabric with plastics or other covering.

*Cord (fuse) detonating, metal clad.* Articles consisting of a core of detonating explosive clad by a soft metal tube with or without protective covering. When the core contains a sufficiently small quantity of explosive, the words “mild effect” are added.

*Cord igniter.* Articles consisting of textile yarns covered with black powder or another fast-burning pyrotechnic composition and a flexible protective covering, or consisting of a core of black powder surrounded by a flexible woven fabric. It burns progressively along its length with an external flame and is used to transmit ignition from a device to a charge or primer.

*Cutters, cable, explosive.* Articles consisting of a knife-edged device which is driven by a small charge of deflagrating explosive into an anvil.

*Detonator assemblies, non-electric, for blasting.* Non-electric detonators assembled with and activated by such means as safety fuse, shock tube, flash tube, or detonating cord. They may be of instantaneous design or incorporate delay elements. Detonating relays incorporating detonating cord are included. Other detonating relays are included in Detonators, nonelectric.

*Detonators.* Articles consisting of a small metal or plastic tube containing explosives such as lead azide, PETN, or combinations of explosives. They are designed to start a detonation train. They may be constructed to detonate

instantaneously, or may contain a delay element. They may contain no more than 10 g of total explosives weight, excluding ignition and delay charges, per unit. The term includes: detonators for ammunition; detonators for blasting, both electric and non-electric; and detonating relays without flexible detonating cord.

*Dynamite.* A detonating explosive containing a liquid explosive ingredient (generally nitroglycerin, similar organic nitrate esters, or both) that is uniformly mixed with an absorbent material, such as wood pulp, and usually contains materials such as nitrocellulose, sodium and ammonium nitrate.

*Entire load and total contents.* The phrase means such a substantial portion of the material explodes that the practical hazard should be assessed by assuming simultaneous explosion of the whole of the explosive content of the load or package.

*Explode.* The term indicates those explosive effects capable of endangering life and property through blast, heat, and projection of missiles. It encompasses both deflagration and detonation.

*Explosion of the total contents.* The phrase is used in testing a single article or package or a small stack of articles or packages.

*Explosive, blasting.* Detonating explosive substances used in mining, construction, and similar tasks. Blasting explosives are assigned to one of five types. In addition to the ingredients listed below for each type, blasting explosives may also contain inert components, such as kieselguhr, and other minor ingredients, such as coloring agents and stabilizers.

*Explosive, blasting, type A.* Substances consisting of liquid organic nitrates, such as nitroglycerin, or a mixture of such ingredients with one or more of the following: nitrocellulose, ammonium nitrate or other inorganic nitrates, aromatic nitro-derivatives, or combustible materials, such as woodmeal and aluminum powder. Such explosives must be in powdery, gelatinous, plastic or elastic form. The term includes dynamite, blasting gelatine and gelatine dynamites.

*Explosive, blasting, type B.* Substances consisting of a mixture of ammonium nitrate or other inorganic nitrates with an explosive, such as trinitrotoluene, with or without other substances, such as wood-meal or aluminum powder, or a mixture of ammonium nitrate or other inorganic nitrates with other combustible substances which are not explosive ingredients. Such explosives may not contain nitroglycerin, similar liquid organic nitrates, or chlorates.

*Explosive, blasting, type C.* Substances consisting of a mixture of either potassium or sodium chlorate or potassium, sodium or ammonium perchlorate with organic nitro-derivatives or combustible materials, such as wood-meal or aluminum powder, or a hydrocarbon. Such explosives must not contain nitroglycerin or any similar liquid organic nitrate.

*Explosive, blasting, type D.* Substances consisting of a mixture of organic nitrate compounds and combustible materials, such as hydrocarbons and aluminum powder. Such explosives must not contain nitroglycerin, any similar liquid organic nitrate, chlorate or ammonium-nitrate. The term generally includes plastic explosives.

*Explosive, blasting, type E.* Substances consisting of water as an essential ingredient and high proportions of ammonium nitrate or other oxidizer, some or all of which are in solution. The other constituents may include nitro-derivatives, such as trinitrotoluene, hydrocarbons or aluminum powder. The term includes: explosives, emulsion; explosives, slurry; and explosives, watergel.

*Explosive, deflagrating.* A substance, e.g., propellant, which reacts by deflagration rather than detonation when ignited and used in its normal manner.

*Explosive, detonating.* A substance which reacts by detonation rather than deflagration when initiated and used in its normal manner.

*Explosive, extremely insensitive detonating substance (EIDS).* A substance which, although capable of sustaining a detonation, has demonstrated through tests that it is so insensitive that there is very little probability of accidental initiation.

*Explosive, primary.* Explosive substance which is manufactured with a view to producing a practical effect by explosion, is very sensitive to heat, impact, or friction, and even in very small quantities, detonates. The major primary explosives are mercury fulminate, lead azide, and lead styphnate.

*Explosive, secondary.* An explosive substance which is relatively insensitive (when compared to primary explosives) and is usually initiated by primary explosives with or without the aid of boosters or supplementary charges. Such an explosive may react as a deflagrating or as a detonating explosive.

*Fireworks.* Pyrotechnic articles designed for entertainment.

*Flares.* Articles containing pyrotechnic substances which are designed to illuminate, identify, signal, or warn. The term includes: flares, aerial and flares, surface.

*Flash powder.* Pyrotechnic substance which, when ignited, produces an intense light.

*Fracturing devices, explosive, for oil wells, without detonators.* Articles consisting of a charge of detonating explosive contained in a casing without the means of initiation. They are used to fracture the rock around a drill shaft to assist the flow of crude oil from the rock.

*Fuse/Fuze.* Although these two words have a common origin (French fusee, fusil) and are sometimes considered to be different spellings, it is useful to maintain the convention that fuse refers to a cord-like igniting device, whereas fuze refers to a device used in ammunition which incorporates mechanical, electrical, chemical, or hydrostatic components to initiate a train by deflagration or detonation.

*Fuse, igniter.* Articles consisting of a metal tube with a core of deflagrating explosives.

*Fuse, instantaneous, non-detonating (Quickmatch).* Article consisting of cotton yarns impregnated with fine black powder. It burns with an external flame and is used in ignition trains for fireworks, etc.

*Fuse, safety.* Article consisting of a core of fine-grained black powder surrounded by a flexible woven fabric with one or more protective outer coverings.



When ignited, it burns at a predetermined rate without any explosive effect.

**Fuzes.** Articles designed to start a detonation or deflagration in ammunition. They incorporate mechanical, electrical, chemical, or hydrostatic components and generally protective features. The term includes: Fuzes, detonating; fuzes detonating with protective features; and fuzes igniting.

**Grenades, hand or rifle.** Articles which are designed to be thrown by hand or to be projected by rifle. The term includes: grenades, hand or rifle, with bursting charge; and grenades, practice, hand or rifle. The term excludes: grenades, smoke.

**Igniters.** Articles containing one or more explosive substance used to start deflagration of an explosive train. They may be actuated chemically, electrically, or mechanically. The term excludes: cord, igniter; fuse, igniter; fuse, instantaneous, non-detonating; fuze, igniting; lighters, fuse, instantaneous, non-detonating; fuzes, igniting; lighters, fuse; primers, cap type; and primers, tubular.

**Ignition, means of.** A general term used in connection with the method employed to ignite a deflagrating train of explosive or pyrotechnic substances (for example: a primer for propelling charge, an igniter for a rocket motor or an igniting fuze).

**Initiation, means of.** (1) A device intended to cause the detonation of an explosive (for example: detonator, detonator for ammunition, or detonating fuze).

(2) The term *with its own means of initiation* means that the contrivance has its normal initiating device assembled to it and this device is considered to present a significant risk during transport but not one great enough to be unacceptable. The term does not apply, however, to a contrivance packed together with its means of initiation, provided the device is packaged so as to eliminate the risk of causing detonation of the contrivance in the event of functioning of the initiating device. The initiating device can even be assembled in the contrivance provided there are protective features ensuring that the device is very unlikely to cause detonation of the contrivance

under conditions which are associated with transport.

(3) For the purposes of classification, any means of initiation without two effective protective features should be regarded as Compatibility Group B; an article with its own means of initiation, without two effective protective features, is Compatibility Group F. A means of initiation which itself possesses two effective protective features is Compatibility Group D, and an article with its own means of initiation which possesses two effective features is Compatibility Group D or E. A means of initiation, adjudged as having two effective protective features, must be approved by the Associate Administrator. A common and effective way of achieving the necessary degree of protection is to use a means of initiation which incorporates two or more independent safety features.

**Jet perforating guns, charged, oil well, without detonator.** Articles consisting of a steel tube or metallic strip, into which are inserted shaped charges connected by detonating cord, without means of initiation.

**Lighters, fuse.** Articles of various design actuated by friction, percussion, or electricity and used to ignite safety fuse.

**Mass explosion.** Explosion which affects almost the entire load virtually instantaneously.

**Mines.** Articles consisting normally of metal or composition receptacles and bursting charge. They are designed to be operated by the passage of ships, vehicles, or personnel. The term includes Bangalore torpedoes.

**Powder cake (powder paste).** Substance consisting of nitrocellulose impregnated with not more than 60 percent of nitroglycerin or other liquid organic nitrates or a mixture of these.

**Powder, smokeless.** Substance based on nitrocellulose used as propellant. The term includes propellants with a single base (nitrocellulose (NC) alone), those with a double base (such as NC and nitroglycerin (NG)) and those with a triple base (such as NC/NG/nitroguanidine). Cast pressed or bag-charges of smokeless powder are listed under *charges, propelling* and *charges, propelling for cannon*.

*Primers, cap type.* Articles consisting of a metal or plastic cap containing a small amount of primary explosive mixture that is readily ignited by impact. They serve as igniting elements in small arms cartridges and in percussion primers for propelling charges.

*Primers, tubular.* Articles consisting of a primer for ignition and an auxiliary charge of deflagrating explosive, such as black powder, used to ignite the propelling charge in a cartridge case for cannon, etc.

*Projectiles.* Articles, such as a shell or bullet, which are projected from a cannon or other artillery gun, rifle, or other small arm. They may be inert, with or without tracer, or may contain a burster, expelling charge or bursting charge. The term includes: projectiles, inert, with tracer; projectiles, with burster or expelling charge; and projectiles, with bursting charge.

*Propellant, liquid.* Substances consisting of a deflagrating liquid explosive, used for propulsion.

*Propellant, solid.* Substances consisting of a deflagrating solid explosive, used for propulsion.

*Propellants.* Deflagrating explosives used for propulsion or for reducing the drag of projectiles.

*Release devices, explosive.* Articles consisting of a small charge of explosive with means of initiation. They sever rods or links to release equipment quickly.

*Rocket motors.* Articles consisting of a solid, liquid, or hypergolic propellant contained in a cylinder fitted with one or more nozzles. They are designed to propel a rocket or guided missile. The term includes: rocket motors; rocket motors with hypergolic liquids with or without an expelling charge; and rocket motors, liquid fuelled.

*Rockets.* Articles containing a rocket motor and a payload which may be an explosive warhead or other device. The term includes: guided missiles; rockets, line-throwing; rockets, liquid fuelled, with bursting charge; rockets, with bursting charge; rockets, with expelling charge; and rockets, with inert head.

*Signals.* Articles consisting of pyrotechnic substances designed to produce signals by means of sound, flame, or smoke or any combination thereof. The

term includes: signal devices, hand; signals, distress ship; signals, railway track, explosive; signals, smoke.

*Sounding devices, explosive.* Articles consisting of a charge of detonating explosive. They are dropped from ships and function when they reach a predetermined depth or the sea bed.

*Substance, explosive, very insensitive (Substance, EVI) N.O.S.* Substances which present a mass explosive hazard but which are so insensitive that there is very little probability of initiation, or of transition from burning to detonation under normal conditions of transport and which have passed test series 5.

*Torpedoes.* Articles containing an explosive or non-explosive propulsion system and designed to be propelled through water. They may contain an inert head or warhead. The term includes: torpedoes, liquid fuelled, with inert head; torpedoes, liquid fuelled, with or without bursting charge; and torpedoes, with bursting charge.

*Tracers for ammunition.* Sealed articles containing pyrotechnic substances, designed to reveal the trajectory of a projectile.

*Warheads.* Articles containing detonating explosives, designed to be fitted to a rocket, guided missile, or torpedo. They may contain a burster or expelling charge or bursting charge. The term includes: warhead rocket with bursting charge; and warheads, torpedo, with bursting charge.

[Amdt. 173-224, 55 FR 52617 Dec. 21, 1990, as amended at 56 FR 66267, Dec. 20, 1991; Amdt. 173-241, 59 FR 67492, Dec. 29, 1994; 64 FR 10777, Mar. 5, 1999; 66 FR 45379, Aug. 28, 2001]

#### **§ 173.60 General packaging requirements for explosives.**

(a) Unless otherwise provided in this subpart and in §173.7(a), packaging used for Class 1 (explosives) materials must meet Packing Group II requirements. Each packaging used for an explosive must be capable of meeting the test requirements of subpart M of part 178 of this subchapter, at the specified level of performance, and the applicable general packaging requirements of paragraph (b) of this section.

(b) The general requirements for packaging of explosives are as follows:

(1) Nails, staples, and other closure devices, made of metal, having no protective covering may not penetrate to the inside of the outer packaging unless the inner packaging adequately protects the explosive against contact with the metal.

(2) The closure device of containers for liquid explosives must provide double protection against leakage, such as a screw cap secured in place with tape.

(3) Inner packagings, fittings, and cushioning materials, and the placing of explosive substances or articles in packages, must be such that the explosive substance is prevented from becoming loose in the outer packaging during transportation. Metallic components of articles must be prevented from making contact with metal packagings. Articles containing explosive substances not enclosed in an outer casing must be separated from each other in order to prevent friction and impact. Padding, trays, partitioning in the inner or outer packaging, molded plastics or receptacles may be used for this purpose.

(4) When the packaging includes water that could freeze during transportation, a sufficient amount of anti-freeze, such as denatured ethyl alcohol, must be added to the water to prevent freezing. If the anti-freeze creates a fire hazard, it may not be used. When a percentage of water in the substance is specified, the combined weight of water and anti-freeze may be substituted.

(5) If an article is fitted with its own means of ignition or initiation, it must be effectively protected from accidental actuation during normal conditions of transportation.

(6) The entry of explosive substances into the recesses of double-seamed metal packagings must be prevented.

(7) The closure device of a metal drum must include a suitable gasket; if the closure device includes metal-to-metal screw-threads, the ingress of explosive substances into the threading must be prevented.

(8) Whenever loose explosive substances or the explosive substance of an uncased or partly cased article may come into contact with the inner surface of metal packagings (1A2, 1B2, 4A, 4B and metal receptacles), the metal

packaging should be provided with an inner liner or coating.

(9) Packagings must be made of materials compatible with, and impermeable to, the explosives contained in the package, so that neither interaction between the explosives and the packaging materials, nor leakage, causes the explosive to become unsafe in transportation, or the hazard division or compatibility group to change (see § 173.24(e)(2)).

(10) An explosive article containing an electrical means of initiation that is sensitive to external electromagnetic radiation, must have its means of initiation effectively protected from electromagnetic radiation sources (for example, radar or radio transmitters) through either design of the packaging or of the article, or both.

(11) Plastic packagings may not be able to generate or accumulate sufficient static electricity to cause the packaged explosive substances or articles to initiate, ignite or inadvertently function. Metal packagings must be compatible with the explosive substance they contain.

(12) Explosive substances may not be packed in inner or outer packagings where the differences in internal and external pressures, due to thermal or other effects, could cause an explosion or rupture of the package.

(13) Packagings for water soluble substances must be water resistant. Packagings for desensitized or phlegmatized substances must be closed to prevent changes in concentration during transport. When containing less alcohol, water, or phlegmatizer than specified in its proper shipping description, the substance is a “forbidden” material.

(14) Large and robust explosives articles, normally intended for military use, without their means of initiation or with their means of initiation containing at least two effective protective features, may be carried unpackaged provided that a negative result was obtained in Test Series 4 of the UN Manual of Tests and Criteria on an unpackaged article. When such articles have propelling charges or are self-propelled, their ignition systems shall be protected against stimuli encountered during normal conditions of

transport. Such unpackaged articles may be fixed to cradles or contained in crates or other suitable handling, storage or launching devices in such a way that they will not become loose during normal conditions of transport and are in accordance with DOD-approved procedures.

[Amdt. 173-260, 62 FR 24719, May 6, 1997, as amended at 65 FR 50461, Aug. 18, 2000]

**§ 173.61 Mixed packaging requirements.**

(a) An explosive may not be packed in the same outside packaging with any other material that could, under normal conditions of transportation, adversely affect the explosive or its packaging unless packaged by DOD or DOE in accordance with § 173.7(a).

(b) Hardware necessary for assembly of explosive articles at the point-of-use may be packed in the same outside packaging with the explosive articles. The hardware must be securely packed in a separate inside packaging. Sufficient cushioning materials must be used to ensure that all inside packagings are securely packed in the outside packaging.

(c) The following explosives may not be packed together with other Class 1 explosives: UN 0029, UN 0030, UN 0073, UN 0106, UN 0107, UN 0255, UN 0257, UN 0267, UN 0350, UN 0360, UN 0361, UN 0364, UN 0365, UN 0366, UN 0367, UN 0408, UN 0409, UN 0410, UN 0455, UN 0456, and UN 0500. These explosives may be mixed-packed with each other in accordance with the compatibility requirements prescribed in paragraph (e) of this section.

(d) Division 1.1 and 1.2 explosives may not be packed with the following explosives: UN 0333, UN 0334, UN 0335, UN 0336, and UN 0337.

(e) Except as prescribed in paragraphs (c) and (d) of this section, different explosives may be packed in one outside packaging in accordance with the following compatibility requirements:

(1) Explosives of the same compatibility group and same division number may be packed together.

(2) Explosives of the same compatibility group or authorized combination of compatibility group but different division number may be packed

together, provided that the whole package is treated as though its entire contents were comprised of the lower division number. For example, a mixed package of Division 1.2 explosives and Division 1.4 explosives, compatibility group D, must be treated as 1.2D explosives. However, when 1.5D explosives are packed together with 1.2D explosives, the whole package must be treated as 1.1D explosives.

(3) Explosives of compatibility group S may be packaged together with explosives of any other compatibility group except A or L, and the combined package may be treated as belonging to any of the packaged compatibility groups except S.

(4) Explosives of compatibility group L shall only be packed with an identical explosive.

(5) Explosives articles of compatibility groups C, D, or E may be packed together and the entire package shall be treated as belonging to compatibility group E.

(6) Explosives articles of compatibility groups C, D, E, or N may be packed together and the entire package shall be treated as belonging to compatibility group D.

(7) Explosives substances of compatibility groups C and D may be packaged together and the entire package shall be treated as belonging to compatibility group D.

(8) Explosive articles of compatibility group G, except for fireworks and articles requiring special packaging, may be packaged together with explosive articles of compatibility groups C, D or E and the combined package shall be treated as belonging to compatibility group E.

[Amdt. 173-224, 55 FR 52617 Dec. 21, 1990, as amended at 56 FR 66267, Dec. 20, 1991; 65 FR 50461, Aug. 18, 2000; 66 FR 33429, June 21, 2001; 66 FR 45381, Aug. 28, 2001; 69 FR 54046, Sept. 7, 2004; 73 FR 4717, Jan. 28 2008]

**§ 173.62 Specific packaging requirements for explosives.**

(a) Except as provided in § 173.7 of this subchapter, when the § 172.101 Table specifies that an explosive must be packaged in accordance with this section, only packagings which conform to the provisions of paragraphs (b) and (c) of this section or § 173.7(e) of

§ 173.62

49 CFR Ch. I (10–1–08 Edition)

this subchapter and the applicable requirements in §§173.60 and 173.61 may be used unless otherwise approved by the Associate Administrator.

(b) *Explosives Table*. The Explosives Table specifies the Packing Instructions assigned to each explosive. Explosives are identified in the first column in numerical sequence by their identification number (ID #), which is listed in column 4 of the §172.101 table, of this subchapter. The second column of the Explosives Table specifies the Packing Instruction (PI) which must be used for packaging the explosive. The Explosives Packing Method Table in paragraph (c) of this section defines the methods of packaging. The Packing Instructions are identified using a 3 digit designation. The Packing Instruction prefixed by the letters “US” is particular to the United States and not found in applicable international regulations.

EXPLOSIVES TABLE

| ID#          | PI     |
|--------------|--------|
| UN0004 ..... | 112    |
| UN0005 ..... | 130    |
| UN0006 ..... | 130    |
| UN0007 ..... | 130    |
| UN0009 ..... | 130    |
| UN0010 ..... | 130    |
| UN0012 ..... | 130    |
| UN0014 ..... | 130    |
| UN0015 ..... | 130    |
| UN0016 ..... | 130    |
| UN0018 ..... | 130    |
| UN0019 ..... | 130    |
| UN0020 ..... | 101    |
| UN0021 ..... | 101    |
| UN0027 ..... | 113    |
| UN0028 ..... | 113    |
| UN0029 ..... | 131    |
| UN0030 ..... | 131    |
| UN0033 ..... | 130    |
| UN0034 ..... | 130    |
| UN0035 ..... | 130    |
| UN0037 ..... | 130    |
| UN0038 ..... | 130    |
| UN0039 ..... | 130    |
| UN0042 ..... | 132    |
| UN0043 ..... | 133    |
| UN0044 ..... | 133    |
| UN0048 ..... | 130    |
| UN0049 ..... | 135    |
| UN0050 ..... | 135    |
| UN0054 ..... | 135    |
| UN0055 ..... | 136    |
| UN0056 ..... | 130    |
| UN0059 ..... | 137    |
| UN0060 ..... | 132    |
| UN0065 ..... | 139    |
| UN0066 ..... | 140    |
| UN0070 ..... | 134    |
| UN0072 ..... | 112(a) |
| UN0073 ..... | 133    |

EXPLOSIVES TABLE—Continued

| ID#          | PI               |
|--------------|------------------|
| UN0074 ..... | 110(a) or 110(b) |
| UN0075 ..... | 115              |
| UN0076 ..... | 112              |
| UN0077 ..... | 114(a) or 114(b) |
| UN0078 ..... | 112              |
| UN0079 ..... | 112(b) or 112(c) |
| UN0081 ..... | 116              |
| UN0082 ..... | 116 or 117       |
| UN0083 ..... | 116              |
| UN0084 ..... | 116              |
| UN0092 ..... | 135              |
| UN0093 ..... | 135              |
| UN0094 ..... | 113              |
| UN0099 ..... | 134              |
| UN0101 ..... | 140              |
| UN0102 ..... | 139              |
| UN0103 ..... | 140              |
| UN0104 ..... | 139              |
| UN0105 ..... | 140              |
| UN0106 ..... | 141              |
| UN0107 ..... | 141              |
| UN0110 ..... | 141              |
| UN0113 ..... | 110(a) or 110(b) |
| UN0114 ..... | 110(a) or 110(b) |
| UN0118 ..... | 112              |
| UN0121 ..... | 142              |
| UN0124 ..... | US1              |
| UN0129 ..... | 110(a) or 110(b) |
| UN0130 ..... | 110(a) or 110(b) |
| UN0131 ..... | 142              |
| UN0132 ..... | 114(b)           |
| UN0133 ..... | 112(a)           |
| UN0135 ..... | 110(a) or 110(b) |
| UN0136 ..... | 130              |
| UN0137 ..... | 130              |
| UN0138 ..... | 130              |
| UN0143 ..... | 115              |
| UN0144 ..... | 115              |
| UN0146 ..... | 112              |
| UN0147 ..... | 112(b)           |
| UN0150 ..... | 112(a) or 112(b) |
| UN0151 ..... | 112              |
| UN0153 ..... | 112(b) or 112(c) |
| UN0154 ..... | 112              |
| UN0155 ..... | 112(b) or 112(c) |
| UN0159 ..... | 111              |
| UN0160 ..... | 114(b)           |
| UN0161 ..... | 114(b)           |
| UN0167 ..... | 130              |
| UN0168 ..... | 130              |
| UN0169 ..... | 130              |
| UN0171 ..... | 130              |
| UN0173 ..... | 134              |
| UN0174 ..... | 134              |
| UN0180 ..... | 130              |
| UN0181 ..... | 130              |
| UN0182 ..... | 130              |
| UN0183 ..... | 130              |
| UN0186 ..... | 130              |
| UN0190 ..... | 101              |
| UN0191 ..... | 135              |
| UN0192 ..... | 135              |
| UN0193 ..... | 135              |
| UN0194 ..... | 135              |
| UN0195 ..... | 135              |
| UN0196 ..... | 135              |
| UN0197 ..... | 135              |
| UN0204 ..... | 134              |
| UN0207 ..... | 112(b) or 112(c) |
| UN0208 ..... | 112(b) or 112(c) |
| UN0209 ..... | 112              |
| UN0212 ..... | 133              |

Pipeline and Hazardous Materials Safety Admin., DOT

§ 173.62

EXPLOSIVES TABLE—Continued

| ID#          | PI               |
|--------------|------------------|
| UN0213 ..... | 112(b) or 112(c) |
| UN0214 ..... | 112              |
| UN0215 ..... | 112              |
| UN0216 ..... | 112(b) or 112(c) |
| UN0217 ..... | 112(b) or 112(c) |
| UN0218 ..... | 112(b) or 112(c) |
| UN0219 ..... | 112              |
| UN0220 ..... | 112              |
| UN0221 ..... | 130              |
| UN0222 ..... | 112(b) or 112(c) |
| UN0224 ..... | 110(a) or 110(b) |
| UN0225 ..... | 133              |
| UN0226 ..... | 112(a)           |
| UN0234 ..... | 114(a) or 114(b) |
| UN0235 ..... | 114(a) or 114(b) |
| UN0236 ..... | 114(a) or 114(b) |
| UN0237 ..... | 138              |
| UN0238 ..... | 130              |
| UN0240 ..... | 130              |
| UN0241 ..... | 116 or 117       |
| UN0242 ..... | 130              |
| UN0243 ..... | 130              |
| UN0244 ..... | 130              |
| UN0245 ..... | 130              |
| UN0246 ..... | 130              |
| UN0247 ..... | 101              |
| UN0248 ..... | 144              |
| UN0249 ..... | 144              |
| UN0250 ..... | 101              |
| UN0254 ..... | 130              |
| UN0255 ..... | 131              |
| UN0257 ..... | 141              |
| UN0266 ..... | 112              |
| UN0267 ..... | 131              |
| UN0268 ..... | 133              |
| UN0271 ..... | 143              |
| UN0272 ..... | 143              |
| UN0275 ..... | 134              |
| UN0276 ..... | 134              |
| UN0277 ..... | 134              |
| UN0278 ..... | 134              |
| UN0279 ..... | 130              |
| UN0280 ..... | 130              |
| UN0281 ..... | 130              |
| UN0282 ..... | 112              |
| UN0283 ..... | 132              |
| UN0284 ..... | 141              |
| UN0285 ..... | 141              |
| UN0286 ..... | 130              |
| UN0287 ..... | 130              |
| UN0288 ..... | 138              |
| UN0289 ..... | 139              |
| UN0290 ..... | 139              |
| UN0291 ..... | 130              |
| UN0292 ..... | 141              |
| UN0293 ..... | 141              |
| UN0294 ..... | 130              |
| UN0295 ..... | 130              |
| UN0296 ..... | 134              |
| UN0297 ..... | 130              |
| UN0299 ..... | 130              |
| UN0300 ..... | 130              |
| UN0301 ..... | 130              |
| UN0303 ..... | 130              |
| UN0305 ..... | 113              |
| UN0306 ..... | 133              |
| UN0312 ..... | 135              |
| UN0313 ..... | 135              |
| UN0314 ..... | 142              |
| UN0315 ..... | 142              |
| UN0316 ..... | 141              |
| UN0317 ..... | 141              |

EXPLOSIVES TABLE—Continued

| ID#          | PI               |
|--------------|------------------|
| UN0318 ..... | 141              |
| UN0319 ..... | 133              |
| UN0320 ..... | 133              |
| UN0321 ..... | 130              |
| UN0322 ..... | 101              |
| UN0323 ..... | 134              |
| UN0324 ..... | 130              |
| UN0325 ..... | 142              |
| UN0326 ..... | 130              |
| UN0327 ..... | 130              |
| UN0328 ..... | 130              |
| UN0329 ..... | 130              |
| UN0330 ..... | 130              |
| UN0331 ..... | 116 or 117       |
| UN0332 ..... | 116 or 117       |
| UN0333 ..... | 135              |
| UN0334 ..... | 135              |
| UN0335 ..... | 135              |
| UN0336 ..... | 135              |
| UN0337 ..... | 135              |
| UN0338 ..... | 130              |
| UN0339 ..... | 130              |
| UN0340 ..... | 112(a) or 112(b) |
| UN0341 ..... | 112(b)           |
| UN0342 ..... | 114(a)           |
| UN0343 ..... | 111              |
| UN0344 ..... | 130              |
| UN0345 ..... | 130              |
| UN0346 ..... | 130              |
| UN0347 ..... | 130              |
| UN0348 ..... | 130              |
| UN0349 ..... | 101              |
| UN0350 ..... | 101              |
| UN0351 ..... | 101              |
| UN0352 ..... | 101              |
| UN0353 ..... | 101              |
| UN0354 ..... | 101              |
| UN0355 ..... | 101              |
| UN0356 ..... | 101              |
| UN0357 ..... | 101              |
| UN0358 ..... | 101              |
| UN0359 ..... | 101              |
| UN0360 ..... | 131              |
| UN0361 ..... | 131              |
| UN0362 ..... | 130              |
| UN0363 ..... | 130              |
| UN0364 ..... | 133              |
| UN0365 ..... | 133              |
| UN0366 ..... | 133              |
| UN0367 ..... | 141              |
| UN0368 ..... | 141              |
| UN0369 ..... | 130              |
| UN0370 ..... | 130              |
| UN0371 ..... | 130              |
| UN0372 ..... | 141              |
| UN0373 ..... | 135              |
| UN0374 ..... | 134              |
| UN0375 ..... | 134              |
| UN0376 ..... | 133              |
| UN0377 ..... | 133              |
| UN0378 ..... | 133              |
| UN0379 ..... | 136              |
| UN0380 ..... | 101              |
| UN0381 ..... | 134              |
| UN0382 ..... | 101              |
| UN0383 ..... | 101              |
| UN0384 ..... | 101              |
| UN0385 ..... | 112(b) or 112(c) |
| UN0386 ..... | 112(b) or 112(c) |
| UN0387 ..... | 112(b) or 112(c) |
| UN0388 ..... | 112(b) or 112(c) |
| UN0389 ..... | 112(b) or 112(c) |

EXPLOSIVES TABLE—Continued

| ID#          | PI               |
|--------------|------------------|
| UN0390 ..... | 112(b) or 112(c) |
| UN0391 ..... | 112(a)           |
| UN0392 ..... | 112(b) or 112(c) |
| UN0393 ..... | 112(b)           |
| UN0394 ..... | 112(a)           |
| UN0395 ..... | 101              |
| UN0396 ..... | 101              |
| UN0397 ..... | 101              |
| UN0398 ..... | 101              |
| UN0399 ..... | 101              |
| UN0400 ..... | 101              |
| UN0401 ..... | 112              |
| UN0402 ..... | 112(b) or 112(c) |
| UN0403 ..... | 135              |
| UN0404 ..... | 135              |
| UN0405 ..... | 135              |
| UN0406 ..... | 114(b)           |
| UN0407 ..... | 114(b)           |
| UN0408 ..... | 141              |
| UN0409 ..... | 141              |
| UN0410 ..... | 141              |
| UN0411 ..... | 112(b) or 112(c) |
| UN0412 ..... | 130              |
| UN0413 ..... | 130              |
| UN0414 ..... | 130              |
| UN0415 ..... | 143              |
| UN0417 ..... | 130              |
| UN0418 ..... | 135              |
| UN0419 ..... | 135              |
| UN0420 ..... | 135              |
| UN0421 ..... | 135              |
| UN0424 ..... | 130              |
| UN0425 ..... | 130              |
| UN0426 ..... | 130              |
| UN0427 ..... | 130              |
| UN0428 ..... | 135              |
| UN0429 ..... | 135              |
| UN0430 ..... | 135              |
| UN0431 ..... | 135              |
| UN0432 ..... | 135              |
| UN0433 ..... | 111              |
| UN0434 ..... | 130              |
| UN0435 ..... | 130              |
| UN0436 ..... | 130              |
| UN0437 ..... | 130              |
| UN0438 ..... | 130              |
| UN0439 ..... | 137              |
| UN0440 ..... | 137              |
| UN0441 ..... | 137              |
| UN0442 ..... | 137              |
| UN0443 ..... | 137              |
| UN0444 ..... | 137              |
| UN0445 ..... | 137              |
| UN0446 ..... | 136              |
| UN0447 ..... | 136              |
| UN0448 ..... | 114(b)           |
| UN0449 ..... | 101              |
| UN0450 ..... | 101              |
| UN0451 ..... | 130              |
| UN0452 ..... | 141              |
| UN0453 ..... | 130              |
| UN0454 ..... | 142              |
| UN0455 ..... | 131              |
| UN0456 ..... | 131              |
| UN0457 ..... | 130              |
| UN0458 ..... | 130              |
| UN0459 ..... | 130              |
| UN0460 ..... | 130              |
| UN0461 ..... | 101              |
| UN0462 ..... | 101              |
| UN0463 ..... | 101              |
| UN0464 ..... | 101              |

EXPLOSIVES TABLE—Continued

| ID#          | PI               |
|--------------|------------------|
| UN0465 ..... | 101              |
| UN0466 ..... | 101              |
| UN0467 ..... | 101              |
| UN0468 ..... | 101              |
| UN0469 ..... | 101              |
| UN0470 ..... | 101              |
| UN0471 ..... | 101              |
| UN0472 ..... | 101              |
| UN0473 ..... | 101              |
| UN0474 ..... | 101              |
| UN0475 ..... | 101              |
| UN0476 ..... | 101              |
| UN0477 ..... | 101              |
| UN0478 ..... | 101              |
| UN0479 ..... | 101              |
| UN0480 ..... | 101              |
| UN0481 ..... | 101              |
| UN0482 ..... | 101              |
| UN0483 ..... | 112(b) or 112(c) |
| UN0484 ..... | 112(b) or 112(c) |
| UN0486 ..... | 101              |
| UN0487 ..... | 135              |
| UN0488 ..... | 130              |
| UN0489 ..... | 112(b) or 112(c) |
| UN0490 ..... | 112(b) or 112(c) |
| UN0491 ..... | 143              |
| UN0492 ..... | 135              |
| UN0493 ..... | 135              |
| UN0494 ..... | US1              |
| UN0495 ..... | 115              |
| UN0496 ..... | 112(b) or 112(c) |
| UN0497 ..... | 115              |
| UN0498 ..... | 114(b)           |
| UN0499 ..... | 114(b)           |
| UN0500 ..... | 131              |
| UN0502 ..... | 130              |
| UN0503 ..... | 135              |
| UN0504 ..... | 112(c)           |
| NA0124 ..... | US1              |
| NA0276 ..... | 134              |
| NA0323 ..... | 134              |
| NA0331 ..... | 116 or 117       |
| NA0337 ..... | 135              |
| NA0349 ..... | 133              |
| NA0494 ..... | US1              |

(c) Explosives must be packaged in accordance with the following table:

(1) The first column lists, in alpha-numeric sequence, the packing methods prescribed for explosives in the Explosives Table of paragraph (b) of this section.

(2) The second column specifies the inner packagings that are required. If inner packagings are not required, a notation of “Not necessary” appears in the column. The term “Not necessary” means that a suitable inner packaging may be used but is not required.

(3) The third column specifies the intermediate packagings that are required. If intermediate packagings are not required, a notation of “Not necessary” appears in the column. The term “Not necessary” means that a

suitable intermediate packaging may be used but is not required.

(4) The fourth column specifies the outer packagings which are required. If inner packagings and/or intermediate packagings are specified in the second and third columns, then the packaging specified in the fourth column must be used as the outer packaging of a com-

bination packaging; otherwise it may be used as a single packaging.

(5) Packing Instruction 101 may be used for any explosive substance or article if an equivalent level of safety is shown to be maintained subject to the approval of the Associate Administrator.

TABLE OF PACKING METHODS

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Inner packagings                                                                                                                                                                                                                                                    | Intermediate packagings                                                                                                                                                                                                                            | Outer packagings                                                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>101 ..... This Packing Instruction may be used as an alternative to a specifically assigned packing method with the approval of the Associate Administrator prior to transportation. When this packing instruction is used, the following must be marked on the shipping documents:</p> <p>"Packaging approved by the competent authority of the United States of America (USA)".</p> <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <p>1. Samples of new or existing explosive substances or articles may be transported as directed by the Associate Administrator for purposes including: testing, classification, research and development, quality control, or as a commercial sample. Explosive samples which are wetted or desensitized must be limited to 25 kg. Explosive samples which are not wetted or desensitized must be limited to 10 kg in small packages as specified by the Associate Administrator for Hazardous Materials Safety</p> <p>110(a) ..... PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <p>1. The Intermediate packagings must be filled with water saturated material such as an anti-freeze solution or wetted cushioning</p> <p>2. Outer packagings must be filled with water saturated material such as an anti-freeze solution or wetted cushioning. Outer packagings must be constructed and sealed to prevent evaporation of the wetting solution, except when 0224 is being carried dry</p> <p>110(b) ..... PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS</p> <p>For UN 0074, 0113, 0114, 0129, 0130, 0135 and 0224, the following conditions must be satisfied:</p> <p>a. inner packagings must not contain more than 50 g of explosive substance (quantity corresponding to dry substance);</p> <p>b. each inner packaging must be separated from other inner packagings by dividing partitions; and</p> <p>c. the outer packaging must not be partitioned with more than 25 compartments</p> | <p>Bags ..... plastics ..... textile, plastic coated or lined. rubber ..... textile, rubberized .. textile ..</p> <p>Bags ..... rubber, conductive plastics, conductive</p> <p>Receptacles ..... metal ..... wood ..... rubber, conductive plastics, conductive</p> | <p>Bags ..... plastics ..... textile, plastic coated or lined. rubber ..... textile, rubberized ..</p> <p>Receptacles ..... plastics ..... metal .....</p> <p>Dividing partitions ..... metal ..... wood ..... plastics ..... fibreboard .....</p> | <p>Drums. steel, removable head (1A2). plastics, removable head (1H2)</p> <p>Boxes. natural wood, sift-proof wall (4C2). plywood (4D). reconstituted wood (4F).</p> |



TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                   | Inner packagings                                                                                                                                                                                             | Intermediate packagings                                                                                                                    | Outer packagings                                                                                                                                                                                                                                                                                                                                                                                                                   |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>111</b> .....<br><b>PARTICULAR PACKING REQUIREMENTS OR EX-<br/> CEPTIONS:</b><br>For UN 0159, inner packagings are not required<br>when metal (1A2 or 1B2) or plastics (1H2)<br>drums are used as outer packagings.                                                                                                                                                                                                | <b>Bags</b> .....<br>paper, waterproofed<br>plastics .....<br>textile, rubberized ..<br><b>Sheets</b> .....<br>plastics .....<br>textile, rubberized ..                                                      | <b>Not necessary</b> .....                                                                                                                 | <b>Boxes.</b><br>steel (4A).<br>aluminium (4B).<br>natural wood, ordi-<br>nary (4C1).<br>natural wood, sift<br>proof (4C2).<br>plywood (4D).<br>reconstituted wood<br>(4F).<br>fibreboard (4G).<br>plastics, expanded<br>(4H1).<br>plastics, solid<br>(4H2).<br><b>Drums</b><br>steel, removable<br>head (1A2).<br>aluminum, remov-<br>able head (1B2).<br>plywood (1D).<br>fibreboard (1G).<br>plastics, removable<br>head (1H2). |
| <b>112(a)</b> This packing instruction applies to wetted sol-<br>ids.<br><b>PARTICULAR PACKING REQUIREMENTS OR EX-<br/> CEPTIONS:</b><br>1. For UN Nos. 0004, 0076, 0078, 0154, 0219<br>and 0394, packagings must be lead free<br>2. Intermediate packagings are not required if<br>leakproof drums are used as the outer pack-<br>aging<br>3. For UN 0072 and UN 0226, intermediate pack-<br>agings are not required | <b>Bags</b> .....<br>paper, multiwall,<br>water resistant.<br>plastics .....<br>textile .....<br>textile, rubberized ..<br>woven plastics .....<br><b>Receptacles</b> .....<br>metal .....<br>plastics ..... | <b>Bags</b> .....<br>plastics .....<br>textile, plastic coat-<br>ed or lined.<br><b>Receptacles</b> .....<br>metal .....<br>plastics ..... | <b>Boxes.</b><br>steel (4A).<br>aluminium (4B).<br>natural wood, ordi-<br>nary (4C1).<br>natural wood, sift<br>proof (4C2).<br>plywood (4D).<br>reconstituted wood<br>(4F).<br>fibreboard (4G).<br>plastics, expanded<br>(4H1).<br>plastics, solid<br>(4H2).<br><b>Drums</b><br>steel, removable<br>head (1A2).<br>aluminium, remov-<br>able head (1B2).<br>Plywood (1D).<br>fibre (1G).<br>plastics, removable<br>head (1H2).     |

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Inner packagings                                                                                                                                                                                                          | Intermediate packagings                                                                                                                                               | Outer packagings                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>112(b) This packing instruction applies to dry solids other than powders.</p> <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:.</p> <ol style="list-style-type: none"> <li>1. For UN 0004, 0076, 0078, 0154, 0216, 0219 and 0386, packagings must be lead free.</li> <li>2. For UN 0209, bags, sift-proof (5H2) are recommended for flake or prilled TNT in the dry state and a maximum net mass of 30 kg..</li> <li>3. For UN 0222, inner packagings are not required.</li> </ol>                                                                                              | <p>Bags .....</p> <p>paper, Kraft .....</p> <p>paper, multiwall, water resistant.</p> <p>plastics .....</p> <p>textile .....</p> <p>textile, rubberized plastics.</p> <p>woven plastics .....</p>                         | <p>Bags (for UN 0150 only).</p> <p>plastics .....</p> <p>textile, plastic coated or lined.</p>                                                                        | <p>Bags.</p> <p>woven plastics sift-proof (5H2/3).</p> <p>plastics, film (5H4).</p> <p>textile, sift-proof (5L2).</p> <p>textile, water resistant (5L3).</p> <p>paper, multiwall, water resistant (5M2).</p> <p>Boxes</p> <p>steel (4A).</p> <p>aluminium (4B).</p> <p>natural wood, ordinary (4C1).</p> <p>natural wood, sift proof (4C2).</p> <p>plywood (4D)</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>plastics, expanded (4H1).</p> <p>plastics, solid (4H2).</p> <p>Drums</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>Plywood (1D).</p> <p>fibre (1G).</p> <p>plastics, removable head (1H2).</p> |
| <p>112(c) This packing instruction applies to solid dry powders.</p> <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <ol style="list-style-type: none"> <li>1. For UN 0004, 0076, 0078, 0154, 0216, 0219 and 0386, packagings must be lead free</li> <li>2. For UN 0209, bags, sift-proof (5H2) are recommended for flake or prilled TNT in the dry state. Bags must not exceed a maximum net mass of 30 kg.</li> <li>3. Inner packagings are not required if drums are used as the outer packaging.</li> <li>4. At least one of the packagings must be sift-proof</li> </ol> | <p>Bags .....</p> <p>paper, multiwall, water resistant.</p> <p>plastics .....</p> <p>woven plastics .....</p> <p>Receptacles .....</p> <p>fibreboard .....</p> <p>metal .....</p> <p>plastics .....</p> <p>wood .....</p> | <p>Bags .....</p> <p>paper, multiwall, water resistant with inner lining.</p> <p>plastics .....</p> <p>Receptacles .....</p> <p>metal .....</p> <p>plastics .....</p> | <p>Boxes.</p> <p>steel (4A).</p> <p>natural wood, aluminum (4B).</p> <p>ordinary (4C1).</p> <p>natural wood, sift proof (4C2).</p> <p>plywood (4D).</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>plastics, solid (4H2).</p> <p>Drums.</p> <p>plastics, removable head (1H2).</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>Plywood (1D).</p> <p>fibre (1G).</p>                                                                                                                                                                                                                                             |
| 113 .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Bags .....                                                                                                                                                                                                                | Not necessary .....                                                                                                                                                   | Boxes.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Inner packagings                                                                                                                                                                                                                                                                      | Intermediate packagings                                                                                                                            | Outer packagings                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <ol style="list-style-type: none"> <li>For UN 0094 and UN 0305, no more than 50 g of substance must be packed in an inner packaging</li> <li>For UN 0027, inner packagings are not necessary when drums are used as the outer packaging</li> <li>At least one of the packagings must be sift-proof</li> <li>Sheets must only be used for UN 0028</li> </ol>                                                                                                                                                                                                       | <p>paper .....</p> <p>plastics .....</p> <p>textile, rubberized ..</p> <p>Receptacles .....</p> <p>fibreboard .....</p> <p>metal .....</p> <p>plastics .....</p> <p>wood .....</p> <p>Sheets .....</p> <p>paper, kraft .....</p> <p>paper, waxed .....</p>                            |                                                                                                                                                    | <p>steel (4A).</p> <p>aluminum (4B).</p> <p>natural wood, ordinary (4C1).</p> <p>natural wood, sift-proof walls (4C2).</p> <p>plywood (4D).</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>plastics, solid (4H2).</p> <p>Drums</p> <p>plastics, removable head (1H2).</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>Plywood (1D).</p> <p>fibre (1G).</p> <p>Boxes.</p> <p>steel (4A).</p> <p>natural wood, ordinary (4C1).</p> <p>natural wood, sift-proof walls (4C2).</p> <p>plywood (4D).</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>plastics, solid (4H2).</p> <p>Drums.</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>plywood (1D).</p> <p>fibre (1G).</p> <p>plastics, removable head (1H2).</p> |
| <p>114(a) This packing instruction applies to wetted solids.</p> <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <ol style="list-style-type: none"> <li>For UN 0077, 0234, 0235 and 0236, packagings must be lead free.</li> <li>For UN 0342, inner packagings are not required when metal (1A2 or 1B2) or plastics (1H2) drums are used as outer packagings.</li> <li>Intermediate packagings are not required if leakproof removable head drums are used as the outer packaging.</li> </ol>                                                                                                                     | <p>Bags .....</p> <p>plastics .....</p> <p>textile .....</p> <p>woven plastics .....</p> <p>Receptacles .....</p> <p>metal .....</p> <p>plastics .....</p>                                                                                                                            | <p>Bags .....</p> <p>plastics .....</p> <p>textile, plastic coated or lined.</p> <p>Receptacles .....</p> <p>metal .....</p> <p>plastics .....</p> | <p>Boxes.</p> <p>steel (4A).</p> <p>natural wood, ordinary (4C1).</p> <p>natural wood, sift-proof walls (4C2).</p> <p>plywood (4D).</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>plastics, solid (4H2).</p> <p>Drums.</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>plywood (1D).</p> <p>fibre (1G).</p> <p>plastics, removable head (1H2).</p>                                                                                                                                                                                                                                                                                                                                                                                                               |
| <p>114(b) This packing instruction applies to dry solids ....</p> <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <ol style="list-style-type: none"> <li>For UN 0077, 0132, 0234, 0235 and 0236, packagings must be lead free</li> <li>For UN 0160 and UN 0161, when metal drums (1A2 or 1B2) are used as the outer packaging, metal packagings must be so constructed that the risk of explosion, by reason of increased internal pressure from internal or external causes is prevented</li> <li>For UN 0160 and UN 0161, inner packagings are not required if drums are used as the outer packaging</li> </ol> | <p>Bags .....</p> <p>paper, kraft .....</p> <p>plastics .....</p> <p>textile, sift-proof .....</p> <p>woven plastics, sift-proof.</p> <p>Receptacles .....</p> <p>fibreboard .....</p> <p>metal .....</p> <p>paper .....</p> <p>plastics .....</p> <p>woven plastics, sift-proof.</p> | <p>Not necessary .....</p>                                                                                                                         | <p>Boxes.</p> <p>natural wood, ordinary (4C1).</p> <p>natural wood, sift-proof walls (4C2).</p> <p>plywood (4D).</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>Drums.</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>plywood (1D).</p> <p>fibre (1G).</p> <p>plastics, removable head (1H2).</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
| 115 .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Receptacles .....                                                                                                                                                                                                                                                                     | Bags .....                                                                                                                                         | Boxes.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Inner packagings                                                                                                                                                                                                                                                                                                                                                                                                             | Intermediate packagings                                                     | Outer packagings                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <p>1. For liquid explosives, inner packagings must be surrounded with non-combustible absorbent cushioning material in sufficient quantity to absorb the entire liquid content. Metal receptacles should be cushioned from each other. The net mass of explosive per package may not exceed 30 kg when boxes are used as outer packaging. The net volume of explosive in each package other than boxes must not exceed 120 litres</p> <p>2. For UN 0075, 0143, 0495 and 0497 when boxes are used as the outer packaging, inner packagings must have taped screw cap closures and be not more than 5 litres capacity each. A composite packaging consisting of a plastic receptacle in a metal drum (6HA1) may be used in lieu of combination packagings. Liquid substances must not freeze at temperatures above -15 °C (+5 °F)</p> <p>3. For UN 0144, intermediate packagings are not necessary.</p> | <p>metal .....</p> <p>plastics .....</p>                                                                                                                                                                                                                                                                                                                                                                                     | <p>plastics in metal receptacles.</p> <p>Drums .....</p> <p>metal .....</p> | <p>natural wood, ordinary (4C1).</p> <p>natural wood, sift proof walls (4C2).</p> <p>plywood (4D).</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>Drums.</p> <p>plastics, removable head (1H2).</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>plywood (1D).</p> <p>fibre (1G).</p> <p>Specification MC-200 containers may be used for transport by motor vehicle.</p>                                                                                                                                                                                                                                                                                                       |
| <p>116 .....</p> <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <p>1. For UN 0082, 0241, 0331 and 0332, inner packagings are not necessary if leakproof removable head drums are used as the outer packaging</p> <p>2. For UN 0082, 0241, 0331 and 0332, inner packagings are not required when the explosive is contained in a material impervious to liquid</p> <p>3. For UN 0081, inner packagings are not required when contained in rigid plastic which is impervious to nitric esters</p> <p>4. For UN 0331, inner packagings are not required when bags (5H2), (5H3) or (5H4) are used as outer packagings</p> <p>5. Bags (5H2 or 5H3) must be used only for UN 0082, 0241, 0331 and 0332</p> <p>6. For UN 0081, bags must not be used as outer packagings</p>                                                                                                                                                                                | <p>Bags .....</p> <p>paper, water and oil ..</p> <p>resistant .....</p> <p>plastics .....</p> <p>textile, plastic coated or</p> <p>lined .....</p> <p>woven plastics, sift-proof.</p> <p>Receptacles .....</p> <p>fibreboard, water resistant.</p> <p>metal .....</p> <p>plastics .....</p> <p>wood, sift-proof .....</p> <p>Sheets .....</p> <p>paper, water resistant.</p> <p>paper, waxed .....</p> <p>plastics .....</p> | <p>Not necessary .....</p> <p>.....</p>                                     | <p>Bags.</p> <p>woven plastics (5H1/2/3).</p> <p>paper, multithick, water resistant (5M2).</p> <p>plastics, film (5H4).</p> <p>textile, sift-proof (5L2).</p> <p>textile, water resistant (5L3).</p> <p>Boxes.</p> <p>steel (4A).</p> <p>aluminium (4B).</p> <p>wood, natural, ordinary (4C1).</p> <p>natural wood, sift proof walls (4C2).</p> <p>plywood (4D).</p> <p>reconstituted wood (4F).</p> <p>fibreboard (4G).</p> <p>plastics, solid (4H2).</p> <p>Drums.</p> <p>steel, removable head (1A2).</p> <p>aluminium, removable head (1B2).</p> <p>Plywood (1D).</p> <p>fibre (1G).</p> <p>plastics, removable head (1H2).</p> <p>Jerricans.</p> <p>steel, removable head (3A2).</p> <p>plastics, removable head (3H2).</p> |
| 117 .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Not necessary .....                                                                                                                                                                                                                                                                                                                                                                                                          | Not necessary .....                                                         | IBCs.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Inner packagings                                                                                                                                             | Intermediate packagings | Outer packagings                                                                                                                                                                                                                                                                                                                                             |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <p>1. This packing instruction may only be used for explosives of 0082 when they are mixtures of ammonium nitrate or other inorganic nitrates with other combustible substances which are not explosive ingredients. Such explosives must not contain nitroglycerin, similar liquid organic nitrates, liquid or solid nitrocarbons, or chlorates.</p> <p>2. This packing instruction may only be used for explosives of UN 0241 which consist of water as an essential ingredient and high proportions of ammonium nitrate or other oxidizers, some or all of which are in solution. The other constituents may include hydrocarbons or aluminium powder, but must not include nitroderivatives such as trinitrotoluene.</p> <p>3. Metal IBCs must not be used for UN 0082 and 0241.</p> <p>4. Flexible IBCs may only be used for solids.</p>                                                                                                                                                                                                                                         | .....                                                                                                                                                        | .....                   | <p>metal (11A), (11B), (11N), (21A), (21B), (21N), (31A), (31B), (31N), flexible (13H2), (13H3), (13H4), (13L2), (13L3), (13L4), (13M2). rigid plastics (11H1), (11H2), (21H1), (21H2), (31H1), (31H2). composite (11HZ1), (11HZ2), (21HZ1), (21HZ2), (31HZ1), (31HZ2).</p>                                                                                  |
| <p>130 .....<br/>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <p>1. The following applies to UN 0006, 0009, 0010, 0015, 0016, 0018, 0019, 0034, 0035, 0038, 0039, 0048, 0056, 0137, 0138, 0168, 0169, 0171, 0181, 0182, 0183, 0186, 0221, 0238, 0243, 0244, 0245, 0246, 0254, 0280, 0281, 0286, 0287, 0297, 0299, 0300, 0301, 0303, 0321, 0328, 0329, 0344, 0345, 0346, 0347, 0362, 0363, 0370, 0412, 0424, 0425, 0434, 0435, 0436, 0437, 0438, 0451, 0459 and 0488. Large and robust explosives articles, normally intended for military use, without their means of initiation or with their means of initiation containing at least two effective protective features, may be carried unpackaged. When such articles have propelling charges or are self-propelled, their ignition systems must be protected against stimuli encountered during normal conditions of transport. A negative result in Test Series 4 on an unpackaged article indicates that the article can be considered for transport unpackaged. Such unpackaged articles may be fixed to cradles or contained in crates or other suitable handling devices.</p> | Not necessary .....                                                                                                                                          | Not necessary .....     | <p>Boxes.</p> <p>steel (4A). aluminium (4B). wood natural, ordinary (4C1). natural wood, sift proof walls (4C2). plywood (4D). reconstituted wood (4F). fibreboard (4G). plastics, expanded (4H1). plastics, solid (4H2). Drums. steel, removable head (1A2). aluminium, removable head (1B2). Plywood (1D). fibre (1G). plastics, removable head (1H2).</p> |
| <p>131 .....<br/>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:</p> <p>1. For UN 0029, 0267 and 0455, bags and reels may not be used as inner packagings</p> <p>2. For UN 0030, 0255 and 0456, inner packagings are not required when detonators are packed in pasteboard tubes, or when their leg wires are wound on spools with the caps either placed inside the spool or securely taped to the wire on the spool, so as to restrict free moving of the caps and to protect them from impact forces</p> <p>3. For UN 0360, 0361 and 0500, detonators are not required to be attached to the safety fuse, metal-clad mild detonating cord, detonating cord, or shock tube. Inner packagings are not required if the packing configuration restricts free moving of the caps and protects them from impact forces</p>                                                                                                                                                                                                                                                                                                                      | <p>Bags .....<br/>paper.<br/>plastics .....<br/>Receptacles .....<br/>fibreboard .....<br/>metal .....<br/>plastics .....<br/>wood .....<br/>Reels .....</p> | Not necessary .....     | <p>Boxes.</p> <p>steel (4A). aluminium (4B). wood, natural, ordinary (4C1). natural wood, sift proof walls (4C2). plywood (4D). reconstituted wood (4F). fibreboard (4G). Drums. steel, removable head (1A2). aluminium, removable head (1B2). Plywood (1D). fibre (1G). plastics, removable head (1H2).</p>                                                 |

**§ 173.62**

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                       | Inner packagings                                                                                                                                                                                                                                                                   | Intermediate packagings                                                              | Outer packagings                                                                                                                                                                                                                                                                                                                                                           |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 132(a) For articles consisting of closed metal, plastic or fiberboard casings that contain detonating explosives, or consisting of plastics-bonded detonating explosives. | Not necessary .....                                                                                                                                                                                                                                                                | Not necessary .....                                                                  | Boxes.<br>steel (4A).<br>aluminum (4B).<br>wood, natural; ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fiberboard (4G).<br>plastics, solid (4H2).                                                                                                                                                             |
| 132(b) For articles without closed casings .....                                                                                                                          | Receptacles fiberboard metal plastics. Sheets paper plastics.                                                                                                                                                                                                                      | Not necessary .....                                                                  | Boxes.<br>steel (4A); aluminum (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fiberboard (4G).<br>plastics, solid (4H2).                                                                                                                                                                |
| 133 .....<br>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:<br>1. For UN 0043, 0212, 0225, 0268 and 0306 trays are not authorized as inner packagings                     | Receptacles .....<br>Intermediate packagings are only required when trays are used as inner packagings.<br>fiberboard .....<br>metal .....<br>plastics .....<br>wood .....<br>Trays, fitted with dividing.<br>partitions .....<br>fiberboard .....<br>plastics .....<br>wood ..... | Receptacles .....<br>fiberboard .....<br>metal .....<br>plastics .....<br>wood ..... | Boxes.<br>steel (4A).<br>aluminum (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fiberboard (4G).<br>plastics, solid (4H2).                                                                                                                                                             |
| 134 .....                                                                                                                                                                 | Bag .....<br>water resistant .....<br>Receptacles .....<br>fiberboard .....<br>metal .....<br>plastics .....<br>wood .....<br>Sheets .....<br>fiberboard (4G). .....<br>fiberboard, corrugated.<br>Tubes .....<br>fiberboard .....                                                 | Not necessary .....                                                                  | Boxes<br>steel (4A).<br>aluminum (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>plastics, expanded (4H1).<br>plastics, solid (4H2).<br>Drums<br>fiberboard (1G).<br>plastics, removable head (1H2).<br>steel, removable head (1A2).<br>aluminum, removable head (1B2).<br>Plywood (1D). |

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                     | Inner packagings                                                                                                                                                                     | Intermediate packagings | Outer packagings                                                                                                                                                                                                                                                                                                                                                                              |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 135 .....                                                                                                                                                                                                                                                                                                                                                               | Bags .....<br>paper .....<br>plastics .....<br>Receptacles .....<br>fibreboard .....<br>metal .....<br>plastics .....<br>wood .....<br>Sheets .....<br>paper .....<br>plastics ..... | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminium (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fibreboard (4G).<br>plastics, expanded (4H1).<br>plastics, solid (4H2).<br>Drums.<br>steel, removable head (1A2).<br>aluminium, removable head (1B2).<br>Plywood (1D).<br>fibre (1G).<br>plastics, removable head (1H2). |
| 136 .....                                                                                                                                                                                                                                                                                                                                                               | Bags .....<br>plastics .....<br>textile .....<br>Boxes. ....<br>fibreboard .....<br>plastics .....<br>wood .....<br>Dividing partitions in the outer packagings .....                | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminium (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fibreboard (4G).<br>plastics, solid (4H2).<br>Drums.<br>steel, removable head (1A2).<br>aluminium, removable head (1B2).<br>Plywood (1D).<br>fibre (1G).<br>plastics, removable head (1H2).                              |
| 137 PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS: For UN 0059, 0439, 0440 and 0441, when the shaped charges are packed singly, the conical cavity must face downwards and the package marked "THIS SIDE UP". When the shaped charges are packed in pairs, the conical cavities must face inwards to minimize the jetting effect in the event of accidental initiation. | Bags .....<br>plastics .....<br>Boxes .....<br>fibreboard .....<br>Tubes .....<br>fibreboard .....<br>metal .....<br>plastics .....<br>Dividing partitions in the outer packagings.  | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminium (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fibreboard (4G).                                                                                                                                                                                                         |
| 138 .....                                                                                                                                                                                                                                                                                                                                                               | Bags .....                                                                                                                                                                           | Not necessary .....     | Boxes.                                                                                                                                                                                                                                                                                                                                                                                        |

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                         | Inner packagings                                                                                                                                                                     | Intermediate packagings | Outer packagings                                                                                                                                                                                                                                                                                                                                                 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:<br>If the ends of the articles are sealed, inner packagings are not necessary                                                                                                                                                                                                                                                                                | plastics .....                                                                                                                                                                       | .....                   | steel (4A).<br>aluminium (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fibreboard (4G).<br>plastics, solid (4H2).<br>Drums.<br>fibreboard (1G).<br>plastics, removable head (1H2).<br>steel, removable head (1A2).<br>aluminium, removable head (1B2).                       |
| 139 .....<br>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:<br>1. For UN 0065, 0102, 0104, 0289 and 0290, the ends of the detonating cord must be sealed, for example, by a plug firmly fixed so that the explosive cannot escape. The ends of CORD DETONATING flexible must be fastened securely<br>2. For UN 0065 and UN 0289, inner packagings are not required when they are fastened securely in coils | Bags .....<br>plastics .....<br>Receptacles .....<br>fibreboard .....<br>metal .....<br>plastics .....<br>wood .....<br>Reels .....<br>Sheets .....<br>paper .....<br>plastics ..... | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminium (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fibreboard (4G).<br>plastics, solid (4H2).<br>Drums.<br>steel, removable head (1A2).<br>aluminium, removable head (1B2).<br>plywood (1D).<br>fibre (1G).<br>plastics, removable head (1H2). |
| 140 .....<br>PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:<br>1. If the ends of UN 0105 are sealed, no inner packagings are required<br>2. For UN 0101, the packaging must be sift-proof except when the fuse is covered by a paper tube and both ends of the tube are covered with removable caps<br>3. For UN 0101, steel or aluminium boxes or drums must not be used                                   | Bags .....<br>plastics .....<br>Reels .....<br>Sheets .....<br>paper, kraft .....<br>plastics .....                                                                                  | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminium (4B).<br>wood, natural, ordinary (4C1).<br>wood, natural, sift proof walls (4C2).<br>plywood (4D).<br>reconstituted wood (4F).<br>fibreboard (4G).<br>plastics, solid (4H2).<br>Drums.<br>plastics, removable head (1H2).<br>steel, removable head (1A2).<br>aluminium, removable head (1B2).<br>Plywood (1D).<br>fibre (1G). |



TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                                                  | Inner packagings                                                                                                                                                                                                                                                 | Intermediate packagings | Outer packagings                                                                                                                                                                                                                                                                                                                                                                           |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 141 .....                                                                                                                                                                                                                                                                                                                                                                                                                                            | Receptacles .....<br>fibregboard .....<br>metal .....<br>plastics .....<br>wood .....<br>.....<br>Trays, fitted with di-<br>viding partitions.<br>plastics .....<br>wood .....<br>.....<br>Dividing partitions in<br>the outer pack-<br>agings.                  | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminium (4B).<br>wood, natural, ordi-<br>nary (4C1).<br>wood, natural, sift<br>proof walls (4C2).<br>plywood (4D).<br>reconstituted wood<br>(4F).<br>fibregboard (4G).<br>plastics, solid<br>(4H2).<br>Drums.<br>steel, removable<br>head (1A2).<br>aluminium, remov-<br>able head (1B2).<br>Plywood (1D).<br>fibre (1G).<br>plastics, removable<br>head (1H2). |
| 142 .....                                                                                                                                                                                                                                                                                                                                                                                                                                            | Bags .....<br>paper .....<br>plastics .....<br>Receptacles .....<br>fibregboard .....<br>metal .....<br>plastics .....<br>wood .....<br>.....<br>Sheets .....<br>paper .....<br>.....<br>Trays, fitted with di-<br>viding partitions.<br>plastics .....          | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminium (4B).<br>wood, natural, ordi-<br>nary (4C1).<br>wood, natural, sift<br>proof walls (4C2).<br>plywood (4D).<br>reconstituted wood<br>(4F).<br>fibregboard (4G).<br>plastics, solid<br>(4H2).<br>Drums.<br>steel, removable<br>head (1A2).<br>aluminium, remov-<br>able head (1B2).<br>Plywood (1D).<br>fibre (1G).<br>plastics, removable<br>head (1H2). |
| 143 .....<br>PARTICULAR PACKING REQUIREMENTS OR EX-<br>CEPTIONS:<br>1. For UN 0271, 0272, 0415 and 0491 when<br>metal packagings are used, metal packagings<br>must be so constructed that the risk of explo-<br>sion, by reason of increase in internal pressure<br>from internal or external causes is prevented<br>2. Composite packagings (6HH2) (plastic recep-<br>tacle with outer solid box) may be used in lieu<br>of combination packagings | Bag .....<br>paper, kraft .....<br>plastics .....<br>textile .....<br>textile, rubberized ..<br>Receptacles .....<br>fibregboard .....<br>metal .....<br>plastics .....<br>.....<br>Trays, fitted with di-<br>viding partitions.<br>plastics .....<br>wood ..... | Not necessary .....     | Boxes.<br>steel (4A).<br>aluminum (4B).<br>wood, natural, ordi-<br>nary (4C1).<br>wood, natural, sift<br>proof walls (4C2).<br>plywood (4D).<br>reconstituted wood<br>(4F).<br>fibregboard (4G).<br>plastics, solid<br>(4H2).<br>Drums.<br>steel, removable<br>head (1A2).<br>aluminium, remov-<br>able head (1B2).<br>plywood (1D).<br>fibre (1G).<br>plastics, removable<br>head (1H2).  |

TABLE OF PACKING METHODS—Continued

| Packing instruction                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Inner packagings                                                                                  | Intermediate packagings | Outer packagings                                                                                                                                                                                                                                                                                                                                                    |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|-------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 144 .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Receptacles .....                                                                                 | Not necessary .....     | Boxes.<br>Drums.<br>steel, removable head (1A2).<br>aluminium, removable head (1B2).<br>plastics, removable head (1H2).<br>Plywood (1D).<br>2steel (4A).<br>aluminum (4B).<br>wood, natural, ordinary (4C1) with metal liner.<br>plywood (4D) with metal liner.<br>reconstituted wood (4F) with metal liner.<br>plastics, expanded (4H1).<br>plastics, solid (4H2). |
| PARTICULAR PACKING REQUIREMENTS OR EXCEPTIONS:<br>For UN 0248 and UN 0249, packagings must be protected against the ingress of water. When CONTRIVANCES, WATER ACTIVATED are transported unpackaged, they must be provided with at least two independent protective features which prevent the ingress of water                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | fibreboard .....<br>metal .....<br>plastics .....<br>Dividing partitions in the outer packagings. | .....                   |                                                                                                                                                                                                                                                                                                                                                                     |
| US 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                                                                                   |                         |                                                                                                                                                                                                                                                                                                                                                                     |
| <p>1. A jet perforating gun, charged, oil well may be transported under the following conditions:</p> <p>a. Initiation devices carried on the same motor vehicle or offshore supply vessel must be segregated; each kind from every other kind, and from any gun, tool or other supplies, unless approved in accordance with §173.56. Segregated initiation devices must be carried in a container having individual pockets for each such device or in a fully enclosed steel container lined with a non-sparking material. No more than two segregated initiation devices per gun may be carried on the same motor vehicle.</p> <p>b. Each shaped charge affixed to the gun may not contain more than 112 g (4 ounces) of explosives.</p> <p>c. Each shaped charge if not completely enclosed in glass or metal, must be fully protected by a metal cover after installation in the gun.</p> <p>d. A jet perforating gun classed as 1.1D or 1.4D may be transported by highway by private or contract carriers engaged in oil well operations.</p> <p>(i) A motor vehicle transporting a gun must have specially built racks or carrying cases designed and constructed so that the gun is securely held in place during transportation and is not subject to damage by contact, one to the other or any other article or material carried in the vehicle; and</p> <p>(ii) The assembled gun packed on the vehicle may not extend beyond the body of the motor vehicle.</p> <p>e. A jet perforating gun classed as 1.4D may be transported by a private offshore supply vessel only when the gun is carried in a motor vehicle as specified in paragraph (d) of this packing method or on offshore well tool pallets provided that:</p> <p>(i) All the conditions specified in paragraphs (a), (b), and (c) of this packing method are met;</p> <p>(ii) The total explosive contents do not exceed 90.8 kg (200 pounds) per tool pallet;</p> <p>(iii) Each cargo vessel compartment may contain up to 90.8 kg (200 pounds) of explosive content if the segregation requirements in §176.83(b) of this subchapter are met; and</p> <p>(iv) When more than one vehicle or tool pallet is stowed "on deck" a minimum horizontal separation of 3 m (9.8 feet) must be provided.</p> |                                                                                                   |                         |                                                                                                                                                                                                                                                                                                                                                                     |

[Amdt. 173–260, 62 FR 24720, May 6, 1997; 62 FR 45702, Aug. 28, 1997; 62 FR 51560, Oct. 1, 1997; 63 FR 1884, Jan. 12, 1998; 63 FR 52849, Oct. 1, 1998; 64 FR 51918, Sept. 27, 1999; 65 FR 50461, Aug. 18, 2000; 65 FR 58629, Sept. 29, 2000; 65 FR 60383, Oct. 11, 2000; 66 FR 33429, 33430, June 21, 2001; 66 FR 45183, 45379, 45382, Aug. 28, 2001; 68 FR 45033, July 31, 2003; 68 FR 48569, Aug. 14, 2003; 68 FR 61941, Oct. 30, 2003; 73 FR 4717, Jan. 28, 2008]

### § 173.63 Packaging exceptions.

(a) Cord, detonating (UN 0065), having an explosive content not exceeding 6.5 g (0.23 ounces) per 30 centimeter length (one linear foot) may be offered for transportation domestically and transported as Cord, detonating (UN 0289), Division 1.4 Compatibility Group D (1.4D) explosives, if the gross weight of all packages containing Cord, deto-

nating (UN 0065), does not exceed 45 kg (99 pounds) per:

- (1) Transport vehicle, freight container, or cargo-only aircraft;
- (2) Off-shore down-hole tool pallet carried on an off-shore supply vessel;
- (3) Cargo compartment of a cargo vessel; or
- (4) Passenger-carrying aircraft used to transport personnel to remote work sites, such as offshore drilling units.

## § 173.115

## 49 CFR Ch. I (10–1–08 Edition)

(b) *Cartridges, small arms, and cartridges power devices.* (1) Cartridges, small arms, and cartridges power devices (which are used to project fastening devices) which have been classed as a Division 1.4S explosive may be reclassified, offered for transportation, and transported as ORM-D material when packaged in accordance with paragraph (b)(2) of this section. For transportation by aircraft, the package must also comply with the applicable requirements of § 173.27 of this subchapter. Such transportation is excepted from the requirements of subparts E (Labeling) and F (Placarding) of part 172 of this subchapter. Cartridges, small arms, and cartridges power devices that may be shipped as ORM-D material are limited to:

(i) Ammunition for rifle, pistol or shotgun;

(ii) Ammunition with inert projectiles or blank ammunition;

(iii) Ammunition having no tear gas, incendiary, or detonating explosive projectiles;

(iv) Ammunition not exceeding 12.7 mm (50 caliber or 0.5 inch) for rifle or pistol, cartridges or 8 gauge for shotshells; and

(v) Cartridges, power devices which are used to project fastening devices.

(2) Packaging for cartridges, small arms, and cartridges power devices as ORM-D material must be as follows:

(i) Ammunition must be packed in inside boxes, or in partitions which fit snugly in the outside packaging, or in metal clips;

(ii) Primers must be protected from accidental initiation;

(iii) Inside boxes, partitions or metal clips must be packed in securely-closed strong outside packagings;

(iv) Maximum gross weight is limited to 30 kg (66 pounds) per package; and

(v) Cartridges, power devices which are used to project fastening devices and 22 caliber rim-fire cartridges may be packaged loose in strong outside packagings.

(c)–(e) [Reserved]

(f) Detonators containing no more than 1 g explosive (excluding ignition and delay charges) that are electric blasting caps with leg wires 4 feet long or longer, delay connectors in plastic sheaths, or blasting caps with empty

plastic tubing 12 feet long or longer may be packed as follows in which case they are excepted from the packaging requirements of § 173.62:

(1) No more than 50 detonators in one inner packaging;

(2) IME Standard 22 container (IBR, see § 171.7 of this subchapter) or compartment is used as the outer packaging;

(3) No more than 1000 detonators in one outer packaging; and

(4) No material may be loaded on top of the IME Standard 22 container and no material may be loaded against the outside door of the IME Standard 22 compartment.

(g) Detonators that are classed as 1.4B or 1.4S and contain no more than 1 g of explosive (excluding ignition and delay charges) may be packed as follows in which case they are excepted from the packaging requirements of § 173.62:

(1) No more than 50 detonators in one inner packaging;

(2) IME Standard 22 container is used as the outer packaging;

(3) No more than 1000 detonators in one outer packaging; and

(4) Each inner packaging is marked “1.4B Detonators” or “1.4S Detonators”, as appropriate.

[Amdt. 173–224, 55 FR 52617, Dec. 21, 1990, as amended at 56 FR 66268, Dec. 20, 1991; Amdt. 173–236, 58 FR 50536, Sept. 24, 1993; Amdt. 173–253, 61 FR 27175, May 30, 1996; 68 FR 75743, Dec. 31, 2003; 71 FR 14602, Mar. 22, 2006]

### Subpart D—Definitions Classification, Packing Group Assignments and Exceptions for Hazardous Materials Other Than Class 1 and Class 7

SOURCE: Amdt. 173–224, 55 FR 52634 Dec. 21, 1990, unless otherwise noted.

#### § 173.115 Class 2, Divisions 2.1, 2.2, and 2.3—Definitions.

(a) *Division 2.1 (Flammable gas).* For the purpose of this subchapter, a *flammable gas* (Division 2.1) means any material which is a gas at 20 °C (68 °F) or less and 101.3 kPa (14.7 psia) of pressure (a material which has a boiling point of 20 °C (68 °F) or less at 101.3 kPa (14.7 psia)) which—

(1) Is ignitable at 101.3 kPa (14.7 psia) when in a mixture of 13 percent or less by volume with air; or

(2) Has a flammable range at 101.3 kPa (14.7 psia) with air of at least 12 percent regardless of the lower limit. Except for aerosols, the limits specified in paragraphs (a)(1) and (a)(2) of this section shall be determined at 101.3 kPa (14.7 psia) of pressure and a temperature of 20 °C (68 °F) in accordance with the ASTM E681-85, Standard Test Method for Concentration Limits of Flammability of Chemicals or other equivalent method approved by the Associate Administrator. The flammability of aerosols is determined by the tests specified in §173.115 (k) of this section.

(b) *Division 2.2 (non-flammable, nonpoisonous compressed gas—including compressed gas, liquefied gas, pressurized cryogenic gas, compressed gas in solution, asphyxiant gas and oxidizing gas)*. For the purpose of this subchapter, a non-flammable, nonpoisonous compressed gas (Division 2.2) means any material (or mixture) which—

(1) Exerts in the packaging an absolute pressure of 280 kPa (40.6 psia) or greater at 20 °C (68 °F), or is a cryogenic liquid, and

(2) Does not meet the definition of Division 2.1 or 2.3.

(c) *Division 2.3 (Gas poisonous by inhalation)*. For the purpose of this subchapter, a *gas poisonous by inhalation* (Division 2.3) means a material which is a gas at 20 °C (68 °F) or less and a pressure of 101.3 kPa (14.7 psia) (a material which has a boiling point of 20 °C (68 °F) or less at 101.3 kPa (14.7 psia)) and which—

(1) Is known to be so toxic to humans as to pose a hazard to health during transportation, or

(2) In the absence of adequate data on human toxicity, is presumed to be toxic to humans because when tested on laboratory animals it has an LC<sub>50</sub> value of not more than 5000 mL/m<sup>3</sup> (see §173.116(a) of this subpart for assignment of Hazard Zones A, B, C or D). LC<sub>50</sub> values for mixtures may be determined using the formula in §173.133(b)(1)(i) or CGA Pamphlet P-20 (IBR, see §171.7 of this subchapter).

(d) *Non-liquefied compressed gas*. A gas, which when packaged under pres-

sure for transportation is entirely gaseous at -50 °C (-58 °F) with a critical temperature less than or equal to -50 °C (-58 °F), is considered to be a non-liquefied compressed gas.

(e) *Liquefied compressed gas*. A gas, which when packaged under pressure for transportation is partially liquid at temperatures above -50 °C (-58 °F), is considered to be a liquefied compressed gas. A liquefied compressed gas is further categorized as follows:

(1) *High pressure liquefied gas* which is a gas with a critical temperature between -50 °C (-58 °F) and + 65 °C (149 °F), and

(2) *Low pressure liquefied gas* which is a gas with a critical temperature above + 65 °C (149 °F).

(f) *Compressed gas in solution*. A *compressed gas in solution* is a non-liquefied compressed gas which is dissolved in a solvent.

(g) *Cryogenic liquid*. A *cryogenic liquid* means a refrigerated liquefied gas having a boiling point colder than -90 °C (-130 °F) at 101.3 kPa (14.7 psia) absolute. A material meeting this definition is subject to requirements of this subchapter without regard to whether it meets the definition of a non-flammable, non-poisonous compressed gas in paragraph (b) of this section.

(h) *Flammable range*. The term *flammable range* means the difference between the minimum and maximum volume percentages of the material in air that forms a flammable mixture.

(i) *Service pressure*. The term *service pressure* means the authorized pressure marking on the packaging. For example, for a cylinder marked "DOT 3A1800", the service pressure is 12410 kPa (1800 psig).

(j) *Refrigerant gas or Dispersant gas*. The terms *Refrigerant gas* and *Dispersant gas* apply to all nonpoisonous refrigerant gases; dispersant gases (fluorocarbons) listed in §172.101 of this subchapter and §§173.304, 173.314(c), 173.315(a), and 173.315(h) and mixtures thereof; and any other compressed gas having a vapor pressure not exceeding 260 psia at 54 °C(130 °F), used only as a refrigerant, dispersant, or blowing agent.

(k) The following applies to aerosols (see §171.8 of this subchapter):

## § 173.116

(1) An aerosol must be assigned to Division 2.1 if the contents include 85% by mass or more flammable components and the chemical heat of combustion is 30 kJ/g or more;

(2) An aerosol must be assigned to Division 2.2 if the contents contain 1% by mass or less flammable components and the heat of combustion is less than 20 kJ/g.

(3) Aerosols not meeting the provisions of paragraphs (a) or (b) of this section must be classed in accordance with the appropriate tests of the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter). An aerosol which was tested in accordance with the requirements of this subchapter in effect on December 31, 2005 is not required to be retested.

(4) Division 2.3 gases may not be transported in an aerosol container.

(5) When the contents are classified as Division 6.1, PG III or Class 8, PG II or III, the aerosol must be assigned a subsidiary hazard of Division 6.1 or Class 8, as appropriate.

(6) Substances of Division 6.1, PG I or II, and substances of Class 8, PG I are forbidden from transportation in an aerosol container.

(7) Flammable components are Class 3 flammable liquids, Class 4.1 flammable solids, or Division 2.1 flammable gases. The chemical heat of combustion must be determined in accordance with the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter).

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66268, Dec. 20, 1991; 57 FR 45461, Oct. 1, 1992; Amdt. 173–236, 58 FR 50236, Sept. 24, 1993; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–241, 59 FR 67506, Dec. 29, 1994; Amdt. 173–255, 61 FR 50625, Sept. 26, 1996; 66 FR 45379, 45380, 45382, Aug. 28, 2001; 67 FR 51642, Aug. 8, 2002; 67 FR 16013, Sept. 27, 2002; 68 FR 45033, July 31, 2003; 68 FR 75742, Dec. 31, 2003; 69 FR 76155, Dec. 20, 2004; 70 FR 34398, June 14, 2005; 71 FR 78631, Dec. 29, 2006]

### § 173.116 Class 2—Assignment of hazard zone.

(a) The hazard zone of a Class 2, Division 2.3 material is assigned in column 7 of the § 172.101 table. There are no hazard zones for Divisions 2.1 and 2.2. When the § 172.101 table provides more than one hazard zone for a Division 2.3 material, or indicates that the hazard

## 49 CFR Ch. I (10–1–08 Edition)

zone be determined on the basis of the grouping criteria for Division 2.3, the hazard zone shall be determined by applying the following criteria:

| Hazard zone | Inhalation toxicity                                                        |
|-------------|----------------------------------------------------------------------------|
| A .....     | LC <sub>50</sub> less than or equal to 200 ppm.                            |
| B .....     | LC <sub>50</sub> greater than 200 ppm and less than or equal to 1000 ppm.  |
| C .....     | LC <sub>50</sub> greater than 1000 ppm and less than or equal to 3000 ppm. |
| D .....     | LC <sub>50</sub> greater than 3000 ppm or less than or equal to 5000 ppm.  |

(b) The criteria specified in paragraph (a) of this section are represented graphically in § 173.133, Figure 1.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66268, Dec. 20, 1991; Amdt. 173–138, 59 FR 49133, Sept. 26, 1994; 67 FR 61013, Sept. 27, 2002]

### §§ 173.117–173.119 [Reserved]

### § 173.120 Class 3—Definitions.

(a) *Flammable liquid*. For the purpose of this subchapter, a *flammable liquid* (Class 3) means a liquid having a flash point of not more than 60 °C (140 °F), or any material in a liquid phase with a flash point at or above 37.8 °C (100 °F) that is intentionally heated and offered for transportation or transported at or above its flash point in a bulk packaging, with the following exceptions:

(1) Any liquid meeting one of the definitions specified in § 173.115.

(2) Any mixture having one or more components with a flash point of 60 °C (140 °F) or higher, that make up at least 99 percent of the total volume of the mixture, if the mixture is not offered for transportation or transported at or above its flash point.

(3) Any liquid with a flash point greater than 35 °C (95 °F) that does not sustain combustion according to ASTM D 4206 (IBR, see § 171.7 of this subchapter) or the procedure in appendix H of this part.

(4) Any liquid with a flash point greater than 35 °C (95 °F) and with a fire point greater than 100 °C (212 °F) according to ISO 2592 (IBR, see § 171.7 of this subchapter).

(5) Any liquid with a flash point greater than 35 °C (95 °F) which is in a water-miscible solution with a water

content of more than 90 percent by mass.

(b) Combustible liquid. (1) For the purpose of this subchapter, a *combustible liquid* means any liquid that does not meet the definition of any other hazard class specified in this subchapter and has a flash point above 60 °C (140 °F) and below 93 °C (200 °F).

(2) A flammable liquid with a flash point at or above 38 °C (100 °F) that does not meet the definition of any other hazard class may be reclassified as a combustible liquid. This provision does not apply to transportation by vessel or aircraft, except where other means of transportation is impracticable. An elevated temperature material that meets the definition of a Class 3 material because it is intentionally heated and offered for transportation or transported at or above its flash point may not be reclassified as a combustible liquid.

(3) A combustible liquid that does not sustain combustion is not subject to the requirements of this subchapter as a combustible liquid. Either the test method specified in ASTM D 4206 or the procedure in appendix H of this part may be used to determine if a material sustains combustion when heated under test conditions and exposed to an external source of flame.

(c) Flash point. (1) *Flash point* means the minimum temperature at which a liquid gives off vapor within a test vessel in sufficient concentration to form an ignitable mixture with air near the surface of the liquid. It shall be determined as follows:

(i) For a homogeneous, single-phase, liquid having a viscosity less than 45 S.U.S. at 38 °C (100 °F) that does not form a surface film while under test, one of the following test procedures shall be used:

(A) Standard Method of Test for Flash Point by Tag Closed Tester, (ASTM D 56);

(B) Standard Methods of Test for Flash Point of Liquids by Setaflash Closed Tester, (ASTM D 3278); or

(C) Standard Test Methods for Flash Point by Small Scale Closed Tester, (ASTM D 3828).

(ii) For a liquid other than one meeting all of the criteria of paragraph

(c)(1)(i) of this section, one of the following test procedures shall be used:

(A) Standard Method of Test for Flash Point by Pensky—Martens Closed Tester, (ASTM D 93). For cut-back asphalt, use Method B of ASTM D 93 or alternate tests authorized in this standard; or

(B) Standard Methods of Test for Flash Point of Liquids by Setaflash Closed Tester (ASTM D 3278).

(2) For a liquid that is a mixture of compounds that have different volatility and flash points, its flash point shall be determined as specified in paragraph (c)(1) of this section, on the material in the form in which it is to be shipped. If it is determined by this test that the flash point is higher than -7 °C (20 °F) a second test shall be made as follows: a portion of the mixture shall be placed in an open beaker (or similar container) of such dimensions that the height of the liquid can be adjusted so that the ratio of the volume of the liquid to the exposed surface area is 6 to one. The liquid shall be allowed to evaporate under ambient pressure and temperature (20 to 25 °C (68 to 77 °F)) for a period of 4 hours or until 10 percent by volume has evaporated, whichever comes first. A flash point is then run on a portion of the liquid remaining in the evaporation container and the lower of the two flash points shall be the flash point of the material.

(3) For flash point determinations by Setaflash closed tester, the glass syringe specified need not be used as the method of measurement of the test sample if a minimum quantity of 2 mL (0.1 ounce) is assured in the test cup.

(d) If experience or other data indicate that the hazard of a material is greater or less than indicated by the criteria specified in paragraphs (a) and (b) of this section, the Associate Administrator may revise the classification or make the material subject or not subject to the requirements of parts 170–189 of this subchapter.

[Amdt. 173–224, 55 FR 52634 Dec. 21, 1990, as amended by Amdt. 173–227, 56 FR 49989, Oct. 2, 1991; 56 FR 66268, Dec. 20, 1991; 57 FR 45461, Oct. 1, 1992; Amdt. 173–241, 59 FR 67506, 67507, Dec. 29, 1994; Amdt. 173–255, 61 FR 50625, Sept. 26, 1996; Amdt. 173–261, 62 FR 24731, May 6, 1997; 66 FR 45379, 45381, Aug. 28, 2001; 68 FR 75743, Dec. 31, 2003; 71 FR 78631, Dec. 29, 2006]

## § 173.121

## 49 CFR Ch. I (10–1–08 Edition)

### § 173.121 Class 3—Assignment of packing group.

(a) The packing group of a Class 3 material is as assigned in column 5 of the §172.101 table. When the §172.101 table provides more than one packing group for a hazardous material, the packing group shall be determined by applying the following criteria:

| Packing group | Flash point (closed-cup)         | Initial boiling point |
|---------------|----------------------------------|-----------------------|
| I .....       | .....                            | ≤35°C (95 °F)         |
| II .....      | <23°C (73 °F) .....              | >35 °C (95 °F)        |
| III .....     | ≥23 °C, ≤60 °C (≥73 °F, ≤140 °F) | >35 °C (95 °F)        |

(b) *Criteria for inclusion of viscous Class 3 materials in Packing Group III.* (1) Viscous Class 3 materials in Packing Group II with a flash point of less than 23 °C (73 °F) may be grouped in Packing Group III provided that—

(i) Less than 3 percent of the clear solvent layer separates in the solvent separation test;

(ii) The mixture does not contain any substances with a primary or a subsidiary risk of Division 6.1 or Class 8;

(iii) The capacity of the packaging is not more than 30 L (7.9 gallons); and

(iv) The viscosity and flash point are in accordance with the following table:

| Flow time t in seconds | Jet diameter in mm | Flash point c.c.         |
|------------------------|--------------------|--------------------------|
| 20<≤60 .....           | 4                  | above 17 °C (62.6 °F).   |
| 60<≤100 .....          | 4                  | above 10 °C (50 °F).     |
| 20<≤32 .....           | 6                  | above 5 °C (41 °F).      |
| 32<≤44 .....           | 6                  | above –1 °C (31.2 °F).   |
| 44<≤100 .....          | 6                  | above –5 °C (23 °F).     |
| 100<t .....            | 6                  | –5 °C (23 °F) and below. |

(2) The methods by which the tests referred to in paragraph (b)(1) of this section shall be performed are as follows:

(i) *Viscosity test.* The flow time in seconds is determined at 23 °C (73.4 °F) using the ISO standard cup with a 4 mm (0.16 inch) jet as set forth in ISO 2431 (IBR, see §171.7 of this subchapter). Where the flow time exceeds 100 seconds, a further test is carried out using the ISO standard cup with a 6 mm (0.24 inch) jet.

(ii) *Solvent Separation Test.* This test is carried out at 23 °C (73 °F) using a 100.0 mL(3 ounces) measuring cylinder of the stoppered type of approximately 25.0 cm (9.8 inches) total height and of a uniform internal diameter of approxi-

mately 30 mm (1.2 inches) over the calibrated section. The sample should be stirred to obtain a uniform consistency, and poured in up to the 100 mL (3 ounces) mark. The stopper should be inserted and the cylinder left standing undisturbed for 24 hours. After 24 hours, the height of the upper separated layer should be measured and the percentage of this layer as compared with the total height of the sample calculated.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66268, Dec. 20, 1991; Amdt. 173–241, 59 FR 67507, Dec. 29, 1994 Amdt. 173–255, 61 FR 50625, Sept. 26, 1996; 64 FR 10777, Mar. 5, 1999; 64 FR 51918, Sept. 27, 1999; 66 FR 45381, Aug. 28, 2001; 68 FR 75744, Dec. 31, 2003; 71 FR 78631, Dec. 29, 2006]

### § 173.124 Class 4, Divisions 4.1, 4.2 and 4.3—Definitions.

(a) *Division 4.1 (Flammable Solid).* For the purposes of this subchapter, *flammable solid* (Division 4.1) means any of the following three types of materials:

(1) Desensitized explosives that—

(i) When dry are Explosives of Class 1 other than those of compatibility group A, which are wetted with sufficient water, alcohol, or plasticizer to suppress explosive properties; and

(ii) Are specifically authorized by name either in the §172.101Table or have been assigned a shipping name and hazard class by the Associate Administrator under the provisions of—

(A) A special permit issued under subchapter A of this chapter; or

(B) An approval issued under §173.56(i) of this part.

(2)(i) Self-reactive materials are materials that are thermally unstable and that can undergo a strongly exothermic decomposition even without participation of oxygen (air). A material is excluded from this definition if any of the following applies:

(A) The material meets the definition of an explosive as prescribed in subpart C of this part, in which case it must be classed as an explosive;

(B) The material is forbidden from being offered for transportation according to §172.101 of this subchapter or §173.21;

(C) The material meets the definition of an oxidizer or organic peroxide as prescribed in subpart D of this part, in which case it must be so classed;

(D) The material meets one of the following conditions:

(1) Its heat of decomposition is less than 300 J/g; or

(2) Its self-accelerating decomposition temperature (SADT) is greater than 75 °C (167 °F) for a 50 kg package; or

(3) It is an oxidizing substance in Division 5.1 containing less than 5.0% combustible organic substances; or

(E) The Associate Administrator has determined that the material does not present a hazard which is associated with a Division 4.1 material.

(ii) *Generic types.* Division 4.1 self-reactive materials are assigned to a generic system consisting of seven types. A self-reactive substance identified by technical name in the Self-Reactive Materials Table in §173.224 is assigned to a generic type in accordance with that table. Self-reactive materials not identified in the Self-Reactive Materials Table in §173.224 are assigned to generic types under the procedures of paragraph (a)(2)(iii) of this section.

(A) *Type A.* Self-reactive material type A is a self-reactive material which, as packaged for transportation, can detonate or deflagrate rapidly. Transportation of type A self-reactive material is forbidden.

(B) *Type B.* Self-reactive material type B is a self-reactive material which, as packaged for transportation, neither detonates nor deflagrates rapidly, but is liable to undergo a thermal explosion in a package.

(C) Performance of the self-reactive material under the test procedures specified in the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter) and the provisions of paragraph (a)(2)(iii) of this section; and

(D) *Type D.* Self-reactive material type D is a self-reactive material which—

(1) Detonates partially, does not deflagrate rapidly and shows no violent effect when heated under confinement;

(2) Does not detonate at all, deflagrates slowly and shows no violent effect when heated under confinement; or

(3) Does not detonate or deflagrate at all and shows a medium effect when heated under confinement.

(E) *Type E.* Self-reactive material type E is a self-reactive material which, in laboratory testing, neither detonates nor deflagrates at all and shows only a low or no effect when heated under confinement.

(F) *Type F.* Self-reactive material type F is a self-reactive material which, in laboratory testing, neither detonates in the cavitated state nor deflagrates at all and shows only a low or no effect when heated under confinement as well as low or no explosive power.

(G) *Type G.* Self-reactive material type G is a self-reactive material which, in laboratory testing, does not detonate in the cavitated state, will not deflagrate at all, shows no effect when heated under confinement, nor shows any explosive power. A type G self-reactive material is not subject to the requirements of this subchapter for self-reactive material of Division 4.1 provided that it is thermally stable (self-accelerating decomposition temperature is 50 °C (122 °F) or higher for a 50 kg (110 pounds) package). A self-reactive material meeting all characteristics of type G except thermal stability is classed as a type F self-reactive, temperature control material.

(iii) *Procedures for assigning a self-reactive material to a generic type.* A self-reactive material must be assigned to a generic type based on—

(A) Its physical state (i.e. liquid or solid), in accordance with the definition of liquid and solid in §171.8 of this subchapter;

(B) A determination as to its control temperature and emergency temperature, if any, under the provisions of §173.21(f);

(C) Performance of the self-reactive material under the test procedures specified in the UN Recommendations on the Transport of Dangerous Goods, Tests and Criteria (see §171.7 of this subchapter) and the provisions of paragraph (a)(2)(iii) of this section; and

(D) Except for a self-reactive material which is identified by technical name in the Self-Reactive Materials Table in §173.224(b) or a self-reactive material which may be shipped as a sample under the provisions of §173.224, the self-reactive material is approved



## § 173.125

in writing by the Associate Administrator. The person requesting approval shall submit to the Associate Administrator the tentative shipping description and generic type and—

(1) All relevant data concerning physical state, temperature controls, and tests results; or

(2) An approval issued for the self-reactive material by the competent authority of a foreign government.

(iv) *Tests.* The generic type for a self-reactive material must be determined using the testing protocol from Figure 14.2 (Flow Chart for Assigning Self-Reactive Substances to Division 4.1) from the UN Manual of Tests and Criteria.

(3) Readily combustible solids are materials that—

(i) Are solids which may cause a fire through friction, such as matches;

(ii) Show a burning rate faster than 2.2 mm (0.087 inches) per second when tested in accordance with the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter); or

(iii) Any metal powders that can be ignited and react over the whole length of a sample in 10 minutes or less, when tested in accordance with the UN Manual of Tests and Criteria.

(b) *Division 4.2 (Spontaneously Combustible Material).* For the purposes of this subchapter, *spontaneously combustible material* (Division 4.2) means—

(1) A pyrophoric material. A pyrophoric material is a liquid or solid that, even in small quantities and without an external ignition source, can ignite within five (5) minutes after coming in contact with air when tested according to UN Manual of Tests and Criteria.

(2) A self-heating material. A self-heating material is a material that, when in contact with air and without an energy supply, is liable to self-heat. A material of this type which exhibits spontaneous ignition or if the temperature of the sample exceeds 200 °C (392 °F) during the 24-hour test period when tested in accordance with UN Manual of Tests and Criteria, is classed as a Division 4.2 material.

(c) *Division 4.3 (Dangerous when wet material).* For the purposes of this chapter, *dangerous when wet material* (Division 4.3) means a material that, by contact with water, is liable to become

## 49 CFR Ch. I (10–1–08 Edition)

spontaneously flammable or to give off flammable or toxic gas at a rate greater than 1 L per kilogram of the material, per hour, when tested in accordance with UN Manual of Tests and Criteria.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66268, Dec. 20, 1991; 57 FR 45461, Oct. 1, 1992; Amdt. 173–233, 58 FR 33305, June 16, 1993; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–241, 59 FR 67507, Dec. 29, 1994; Amdt. 173–261, 62 FR 24731, May 6, 1997; 66 FR 8647, Feb. 1, 2001; 66 FR 45379, Aug. 28, 2001; 68 FR 75744, Dec. 31, 2003; 70 FR 73165, Dec. 9, 2005; 71 FR 78631, Dec. 29, 2006]

### § 173.125 Class 4—Assignment of packing group.

(a) The packing group of a Class 4 material is assigned in column (5) of the § 172.101 Table. When the § 172.101 Table provides more than one packing group for a hazardous material, the packing group shall be determined on the basis of test results following test methods given in the UN Manual of Tests and Criteria (IBR, see § 171.7 of this subchapter) and by applying the appropriate criteria given in this section.

(b) Packing group criteria for readily combustible materials of Division 4.1 are as follows:

(1) Powdered, granular or pasty materials must be classified in Division 4.1 when the time of burning of one or more of the test runs, in accordance with the UN Manual of Tests and Criteria, is less than 45 seconds or the rate of burning is more than 2.2 mm/s. Powders of metals or metal alloys must be classified in Division 4.1 when they can be ignited and the reaction spreads over the whole length of the sample in 10 minutes or less.

(2) Packing group criteria for readily combustible materials of Division 4.1 are assigned as follows:

(i) For readily combustible solids (other than metal powders), Packing Group II if the burning time is less than 45 seconds and the flame passes the wetted zone. Packing Group II must be assigned to powders of metal or metal alloys if the zone of reaction spreads over the whole length of the sample in 5 minutes or less.

(ii) For readily combustible solids (other than metal powders), Packing

Group III must be assigned if the burning rate time is less than 45 seconds and the wetted zone stops the flame propagation for at least 4 minutes. Packing Group III must be assigned to metal powders if the reaction spreads over the whole length of the sample in more than 5 minutes but not more than 10 minutes.

(c) Packing group criteria for Division 4.2 materials is as follows:

(1) Pyrophoric liquids and solids of Division 4.2 are assigned to Packing Group I.

(2) A self-heating material is assigned to—

(i) Packing Group II, if the material gives a positive test result when tested with a 25 mm cube size sample at 140 °C; or

(ii) Packing Group III, if—

(A) A positive test result is obtained in a test using a 100 mm sample cube at 140 °C and a negative test result is obtained in a test using a 25 mm sample cube at 140 °C and the substance is transported in packagings with a volume of more than 3 cubic meters; or

(B) A positive test result is obtained in a test using a 100 mm sample cube at 120 °C and a negative result is obtained in a test using a 25 mm sample cube at 140 °C and the substance is transported in packagings with a volume of more than 450 L; or

(C) A positive result is obtained in a test using a 100 mm sample cube at 100 °C and a negative result is obtained in a test using a 25 mm sample cube at 140 °C and the substance is transported in packagings with a volume of less than 450 L.

(d) A Division 4.3 dangerous when wet material is assigned to—

(1) Packing Group I, if the material reacts vigorously with water at ambient temperatures and demonstrates a tendency for the gas produced to ignite spontaneously, or which reacts readily with water at ambient temperatures such that the rate of evolution of flammable gases is equal or greater than 10 L per kilogram of material over any one minute;

(2) Packing Group II, if the material reacts readily with water at ambient temperatures such that the maximum rate of evolution of flammable gases is equal to or greater than 20 L per kilo-

gram of material per hour, and which does not meet the criteria for Packing Group I; or

(3) Packing Group III, if the material reacts slowly with water at ambient temperatures such that the maximum rate of evolution of flammable gases is greater than 1 L per kilogram of material per hour, and which does not meet the criteria for Packing Group I or II.

[Amdt. 173-224, 55 FR 52634 Dec. 21, 1990, as amended by Amdt. 173-255, 61 FR 50625, Sept. 26, 1996; Amdt. 173-261, 62 FR 24731, May 6, 1997; 62 FR 51560, Oct. 1, 1997; 66 FR 45380, Aug. 28, 2001; 68 FR 75744, Dec. 31, 2003]

**§ 173.127 Class 5, Division 5.1—Definition and assignment of packing groups.**

(a) *Definition.* For the purpose of this subchapter, *oxidizer* (Division 5.1) means a material that may, generally by yielding oxygen, cause or enhance the combustion of other materials.

(1) A solid material is classed as a Division 5.1 material if, when tested in accordance with the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter), its mean burning time is less than or equal to the burning time of a 3:7 potassium bromate/cellulose mixture.

(2) A liquid material is classed as a Division 5.1 material if, when tested in accordance with the UN Manual of Tests and Criteria, it spontaneously ignites or its mean time for a pressure rise from 690 kPa to 2070 kPa gauge is less than the time of a 1:1 nitric acid (65 percent)/cellulose mixture.

(b) *Assignment of packing groups.* (1) The packing group of a Division 5.1 material which is a solid shall be assigned using the following criteria:

(i) Packing Group I, for any material which, in either concentration tested, exhibits a mean burning time less than the mean burning time of a 3:2 potassium bromate/cellulose mixture.

(ii) Packing Group II, for any material which, in either concentration tested, exhibits a mean burning time less than or equal to the mean burning time of a 2:3 potassium bromate/cellulose mixture and the criteria for Packing Group I are not met.

(iii) Packing Group III for any material which, in either concentration tested, exhibits a mean burning time

## § 173.128

## 49 CFR Ch. I (10–1–08 Edition)

less than or equal to the mean burning time of a 3:7 potassium bromate/cellulose mixture and the criteria for Packing Group I and II are not met.

(2) The packing group of a Division 5.1 material which is a liquid shall be assigned using the following criteria:

(i) Packing Group I for:

(A) Any material which spontaneously ignites when mixed with cellulose in a 1:1 ratio; or

(B) Any material which exhibits a mean pressure rise time less than the pressure rise time of a 1:1 perchloric acid (50 percent)/cellulose mixture.

(ii) Packing Group II, any material which exhibits a mean pressure rise time less than or equal to the pressure rise time of a 1:1 aqueous sodium chlorate solution (40 percent)/cellulose mixture and the criteria for Packing Group I are not met.

(iii) Packing Group III, any material which exhibits a mean pressure rise time less than or equal to the pressure rise time of a 1:1 nitric acid (65 percent)/cellulose mixture and the criteria for Packing Group I and II are not met.

[Amdt. 173–261, 62 FR 24732, May 6, 1997, as amended at 68 FR 75744, Dec. 31, 2003]

### § 173.128 Class 5, Division 5.2—Definitions and types.

(a) *Definitions.* For the purposes of this subchapter, *organic peroxide* (Division 5.2) means any organic compound containing oxygen (O) in the bivalent -O-O- structure and which may be considered a derivative of hydrogen peroxide, where one or more of the hydrogen atoms have been replaced by organic radicals, unless any of the following paragraphs applies:

(1) The material meets the definition of an explosive as prescribed in subpart C of this part, in which case it must be classed as an explosive;

(2) The material is forbidden from being offered for transportation according to § 172.101 of this subchapter or § 173.21;

(3) The Associate Administrator has determined that the material does not present a hazard which is associated with a Division 5.2 material; or

(4) The material meets one of the following conditions:

(i) For materials containing no more than 1.0 percent hydrogen peroxide, the

available oxygen, as calculated using the equation in paragraph (a)(4)(ii) of this section, is not more than 1.0 percent, or

(ii) For materials containing more than 1.0 percent but not more than 7.0 percent hydrogen peroxide, the available oxygen, content ( $O_a$ ) is not more than 0.5 percent, when determined using the equation:

$$O_a = 16 \times \sum_{i=1}^k \frac{n_i c_i}{m_i}$$

where, for a material containing  $k$  species of organic peroxides:

$n_i$  = number of -O-O- groups per molecule of the  $i$ th species

$c_i$  = concentration (mass percent) of the  $i$ th species

$m_i$  = molecular mass of the  $i$ th species

(b) *Generic types.* Division 5.2 organic peroxides are assigned to a generic system which consists of seven types. An organic peroxide identified by technical name in the Organic Peroxides Table in § 173.225 is assigned to a generic type in accordance with that table. Organic peroxides not identified in the Organic Peroxides table are assigned to generic types under the procedures of paragraph (c) of this section.

(1) *Type A.* Organic peroxide type A is an organic peroxide which can detonate or deflagrate rapidly as packaged for transport. Transportation of type A organic peroxides is forbidden.

(2) *Type B.* Organic peroxide type B is an organic peroxide which, as packaged for transport, neither detonates nor deflagrates rapidly, but can undergo a thermal explosion.

(3) *Type C.* Organic peroxide type C is an organic peroxide which, as packaged for transport, neither detonates nor deflagrates rapidly and cannot undergo a thermal explosion.

(4) *Type D.* Organic peroxide type D is an organic peroxide which—

(i) Detonates only partially, but does not deflagrate rapidly and is not affected by heat when confined;

(ii) Does not detonate, deflagrates slowly, and shows no violent effect if heated when confined; or

(iii) Does not detonate or deflagrate, and shows a medium effect when heated under confinement.

(5) *Type E.* Organic peroxide type E is an organic peroxide which neither detonates nor deflagrates and shows low, or no, effect when heated under confinement.

(6) *Type F.* Organic peroxide type F is an organic peroxide which will not detonate in a cavitated state, does not deflagrate, shows only a low, or no, effect if heated when confined, and has low, or no, explosive power.

(7) *Type G.* Organic peroxide type G is an organic peroxide which will not detonate in a cavitated state, will not deflagrate at all, shows no effect when heated under confinement, and shows no explosive power. A type G organic peroxide is not subject to the requirements of this subchapter for organic peroxides of Division 5.2 provided that it is thermally stable (self-accelerating decomposition temperature is 50 °C (122 °F) or higher for a 50 kg (110 pounds) package). An organic peroxide meeting all characteristics of type G except thermal stability and requiring temperature control is classed as a type F, temperature control organic peroxide.

(c) *Procedure for assigning an organic peroxide to a generic type.* An organic peroxide shall be assigned to a generic type based on—

(1) Its physical state (i.e., liquid or solid), in accordance with the definitions for liquid and solid in §171.8 of this subchapter;

(2) A determination as to its control temperature and emergency temperature, if any, under the provisions of §173.21(f); and

(3) Performance of the organic peroxide under the test procedures specified in the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter), and the provisions of paragraph (d) of this section.

(d) *Approvals.* (1) An organic peroxide must be approved, in writing, by the Associate Administrator, before being offered for transportation or transported, including assignment of a generic type and shipping description, except for—

(i) An organic peroxide which is identified by technical name in the Organic Peroxides Table in §173.225(c);

(ii) A mixture of organic peroxides prepared according to §173.225(b); or

(iii) An organic peroxide which may be shipped as a sample under the provisions of §173.225(b).

(2) A person applying for an approval must submit all relevant data concerning physical state, temperature controls, and tests results or an approval issued for the organic peroxide by the competent authority of a foreign government.

(e) *Tests.* The generic type for an organic peroxide shall be determined using the testing protocol from Figure 20.1(a) (Classification and Flow Chart Scheme for Organic Peroxides) from the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter).

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66268, Dec. 20, 1991; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–241, 59 FR 67508, Dec. 29, 1994; Amdt. 173–261, 62 FR 24732, May 6, 1997; 65 FR 58629, Sept. 29, 2000; 66 FR 8647, Feb. 1, 2001; 66 FR 45379, Aug. 28, 2001; 68 FR 75744, Dec. 31, 2003; 69 FR 76155, Dec. 20, 2004]

#### § 173.129 Class 5, Division 5.2—Assignment of packing group.

All Division 5.2 materials are assigned to Packing Group II in column 5 of the §172.101 table.

#### § 173.132 Class 6, Division 6.1—Definitions.

(a) For the purpose of this subchapter, *poisonous material* (Division 6.1) means a material, other than a gas, which is known to be so toxic to humans as to afford a hazard to health during transportation, or which, in the absence of adequate data on human toxicity:

(1) Is presumed to be toxic to humans because it falls within any one of the following categories when tested on laboratory animals (whenever possible, animal test data that has been reported in the chemical literature should be used):

(i) *Oral Toxicity.* A liquid or solid with an LD<sub>50</sub> for acute oral toxicity of not more than 300 mg/kg.

(ii) *Dermal Toxicity.* A material with an LD<sub>50</sub> for acute dermal toxicity of not more than 1000 mg/kg.

(iii) *Inhalation Toxicity.* (A) A dust or mist with an LC<sub>50</sub> for acute toxicity on inhalation of not more than 4 mg/L; or

(B) A material with a saturated vapor concentration in air at 20 °C (68

°F) greater than or equal to one-fifth of the LC<sub>50</sub> for acute toxicity on inhalation of vapors and with an LC<sub>50</sub> for acute toxicity on inhalation of vapors of not more than 5000 mL/m<sup>3</sup>; or

(2) Is an irritating material, with properties similar to tear gas, which causes extreme irritation, especially in confined spaces.

(b) For the purposes of this subchapter—

(1) LD<sub>50</sub> (median lethal dose) for acute oral toxicity is the statistically derived single dose of a substance that can be expected to cause death within 14 days in 50% of young adult albino rats when administered by the oral route. The LD<sub>50</sub> value is expressed in terms of mass of test substance per mass of test animal (mg/kg).

(2) LD<sub>50</sub> for acute dermal toxicity means that dose of the material which, administered by continuous contact for 24 hours with the shaved intact skin (avoiding abrading) of an albino rabbit, causes death within 14 days in half of the animals tested. The number of animals tested must be sufficient to give statistically valid results and be in conformity with good pharmacological practices. The result is expressed in mg/kg body mass.

(3) LC<sub>50</sub> for acute toxicity on inhalation means that concentration of vapor, mist, or dust which, administered by continuous inhalation for one hour to both male and female young adult albino rats, causes death within 14 days in half of the animals tested. If the material is administered to the animals as a dust or mist, more than 90 percent of the particles available for inhalation in the test must have a diameter of 10 microns or less if it is reasonably foreseeable that such concentrations could be encountered by a human during transport. The result is expressed in mg/L of air for dusts and mists or in mL/m<sup>3</sup> of air (parts per million) for vapors. See § 173.133(b) for LC<sub>50</sub> determination for mixtures and for limit tests.

(i) When provisions of this subchapter require the use of the LC<sub>50</sub> for acute toxicity on inhalation of dusts and mists based on a one-hour exposure and such data is not available, the LC<sub>50</sub> for acute toxicity on inhalation based on a four-hour exposure may be multi-

plied by four and the product substituted for the one-hour LC<sub>50</sub> for acute toxicity on inhalation.

(ii) When the provisions of this subchapter require the use of the LC<sub>50</sub> for acute toxicity on inhalation of vapors based on a one-hour exposure and such data is not available, the LC<sub>50</sub> for acute toxicity on inhalation based on a four-hour exposure may be multiplied by two and the product substituted for the one-hour LC<sub>50</sub> for acute toxicity on inhalation.

(iii) A solid substance should be tested if at least 10 percent of its total mass is likely to be dust in a respirable range, e.g. the aerodynamic diameter of that particle-fraction is 10 microns or less. A liquid substance should be tested if a mist is likely to be generated in a leakage of the transport containment. In carrying out the test both for solid and liquid substances, more than 90% (by mass) of a specimen prepared for inhalation toxicity testing must be in the respirable range as defined in this paragraph (b)(3)(iii).

(c) For purposes of classifying and assigning packing groups to mixtures possessing oral or dermal toxicity hazards according to the criteria in § 173.133(a)(1), it is necessary to determine the acute LD<sub>50</sub> of the mixture. If a mixture contains more than one active constituent, one of the following methods may be used to determine the oral or dermal LD<sub>50</sub> of the mixture:

(1) Obtain reliable acute oral and dermal toxicity data on the actual mixture to be transported;

(2) If reliable, accurate data is not available, classify the formulation according to the most hazardous constituent of the mixture as if that constituent were present in the same concentration as the total concentration of all active constituents; or

(3) If reliable, accurate data is not available, apply the formula:

$$\frac{C_A}{T_A} + \frac{C_B}{T_B} + \frac{C_Z}{T_Z} = \frac{100}{T_M}$$

where:

C = the % concentration of constituent A, B ... Z in the mixture;

T = the oral LD<sub>50</sub> values of constituent A, B ... Z;

T<sub>M</sub> = the oral LD<sub>50</sub> value of the mixture.

NOTE TO FORMULA IN PARAGRAPH (C)(3): This formula also may be used for dermal toxicities provided that this information is available on the same species for all constituents. The use of this formula does not take into account any potentiation or protective phenomena.

(d) The foregoing categories shall not apply if the Associate Administrator has determined that the physical characteristics of the material or its probable hazards to humans as shown by documented experience indicate that the material will not cause serious sickness or death.

[Amdt. 173-224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66268, Dec. 20, 1991; Amdt. 173-234, 58 FR 51532, Oct. 1, 1993; Amdt. 173-261, 62 FR 24732, May 6, 1997; 62 FR 45702, August 28, 1997; 65 FR 58629, Sept. 29, 2000; 66 FR 45379, 45382, Aug. 28, 2001; 69 FR 76155, Dec. 20, 2004; 72 FR 55692, Oct. 1, 2007]

### § 173.133 Assignment of packing group and hazard zones for Division 6.1 materials.

(a) The packing group of Division 6.1 materials shall be as assigned in column 5 of the §172.101 table. When the §172.101 table provides more than one packing group or hazard zone for a hazardous material, the packing group and hazard zone shall be determined by applying the following criteria:

(1) The packing group assignment for routes of administration other than inhalation of vapors shall be in accordance with the following table:

| Packing group | Oral toxicity LD <sub>50</sub> (mg/kg) | Dermal toxicity LD <sub>50</sub> (mg/kg) | Inhalation toxicity by dusts and mists LC <sub>50</sub> (mg/L) |
|---------------|----------------------------------------|------------------------------------------|----------------------------------------------------------------|
| I .....       | ≤5.0 .....                             | ≤50                                      | ≤0.2                                                           |
| II .....      | >5.0 and ≤50 .....                     | >50 and ≤200                             | >0.2 and ≤2.0                                                  |
| III .....     | >50 and ≤300 .....                     | >200 and ≤1000                           | >2.0 and ≤4.0                                                  |

(2)(i) The packing group and hazard zone assignments for liquids (see §173.115(c) of this subpart for gases)


based on inhalation of vapors shall be in accordance with the following table:

| Packing Group           | Vapor concentration and toxicity                                                                                                       |
|-------------------------|----------------------------------------------------------------------------------------------------------------------------------------|
| I (Hazard Zone A) ..... | V ≥ 500 LC <sub>50</sub> and LC <sub>50</sub> ≤ 200 mL/M <sup>3</sup> .                                                                |
| I (Hazard Zone B) ..... | V ≥ 10 LC <sub>50</sub> ; LC <sub>50</sub> ≤ 1000 mL/m <sup>3</sup> ; and the criteria for Packing Group I, Hazard Zone A are not met. |
| II .....                | V ≥ LC <sub>50</sub> ; LC <sub>50</sub> ≤ 3000 mL/m <sup>3</sup> ; and the criteria for Packing Group I, are not met.                  |
| III .....               | V ≥ .2 LC <sub>50</sub> ; LC <sub>50</sub> ≤ 5000 mL/m <sup>3</sup> ; and the criteria for Packing Groups I and II, are not met.       |

NOTE 1: V is the saturated vapor concentration in air of the material in mL/m<sup>3</sup> at 20 °C and standard atmospheric pressure.  
NOTE 2: A liquid in Division 6.1 meeting criteria for Packing Group I, Hazard Zones A or B stated in paragraph (a)(2) of this section is a material poisonous by inhalation subject to the additional hazard communication requirements in §§172.203(m)(2), 172.313 and table 1 of §172.504(e) of this subchapter.

(ii) These criteria are represented graphically in Figure 1:

**Figure 1**  
**Inhalation Toxicity: Packing Group and**  
**Hazard Zone Borderlines**



(3) When the packing group determined by applying these criteria is different for two or more (oral, dermal or inhalation) routes of administration,

the packing group assigned to the material shall be that indicated for the highest degree of toxicity for any of the routes of administration.

(4) Notwithstanding the provisions of this paragraph, the packing group and hazard zone of a tear gas substance is as assigned in column 5 of the § 172.101 table.

(b) The packing group and hazard zone for Division 6.1 mixtures that are poisonous (toxic) by inhalation may be determined by one of the following methods:

(1) Where  $LC_{50}$  data is available on each of the poisonous (toxic) substances comprising the mixture—

(i) The  $LC_{50}$  of the mixture is estimated using the formula:

$$LC_{50}(\text{mixture}) = \frac{1}{\sum_{i=1}^n \frac{f_i}{LC_{50i}}}$$

where

$f_i$  = mole fraction of the  $i^{\text{th}}$  component substance of the liquid.

$LC_{50i}$  = mean lethal concentration of the  $i^{\text{th}}$  component substance in mL/m<sup>3</sup>

(ii) The volatility of each component substance is estimated using the formula:

$$V_i = P_i \times \frac{10^6}{101.3} \text{ mL/m}^3$$

where:

$P_i$  = partial pressure of the  $i^{\text{th}}$  component substance in kPa at 20 °C and one atmospheric pressure.  $P_i$  may be calculated according to Raoult's Law using appropriate activity coefficients. Where activity coefficients are not available, the coefficient may be assumed to be 1.0.

(iii) The ratio of the volatility to the  $LC_{50}$  is calculated using the formula:

$$R = \sum_{i=1}^n \frac{V_i}{LC_{50i}}$$

(iv) Using the calculated values  $LC_{50}$  (mixture) and  $R$ , the packing group for the mixture is determined as follows:

| Packaging group (hazard zone) | Ratio of volatility and $LC_{50}$                                                                                                           |
|-------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------|
| I (Hazard Zone A) ..          | $R \geq 500$ and $LC_{50}(\text{mixture}) \leq 200 \text{ mL/m}^3$ .                                                                        |
| I (Hazard Zone B) ..          | $R \geq 10$ and $LC_{50}(\text{mixture}) \leq 1000 \text{ mL/m}^3$ ; and the criteria for Packing Group I, Hazard Zone A are not met.       |
| II .....                      | $R \geq 1$ and $LC_{50}(\text{mixture}) \leq 3000 \text{ mL/m}^3$ ; and the criteria for Packing Group I, Hazard Zones A and B are not met. |

| Packaging group (hazard zone) | Ratio of volatility and $LC_{50}$                                                                                                                                  |
|-------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| III .....                     | $R \geq 1/5$ and $LC_{50}(\text{mixture}) \leq 5000 \text{ mL/m}^3$ ; and the criteria for Packing Group I, Hazard Zones A and B and Packing Group II are not met. |

(2) In the absence of  $LC_{50}$  data on the poisonous (toxic) constituent substances, the mixture may be assigned a packing group and hazard zone based on the following simplified threshold toxicity tests. When these threshold tests are used, the most restrictive packing group and hazard zone must be determined and used for the transportation of the mixture.

(i) A mixture is assigned to Packing Group I, Hazard Zone A only if both the following criteria are met:

(A) A sample of the liquid mixture is vaporized and diluted with air to create a test atmosphere of 200 mL/m<sup>3</sup> vaporized mixture in air. Ten albino rats (five male and five female) are exposed to the test atmosphere as determined by an analytical method appropriate for the material being classified for one hour and observed for fourteen days. If five or more of the animals die within the fourteen-day observation period, the mixture is presumed to have an  $LC_{50}$  equal to or less than 200 mL/m<sup>3</sup>.

(B) A sample of the vapor in equilibrium with the liquid mixture is diluted with 499 equal volumes of air to form a test atmosphere. Ten albino rats (five male and five female) are exposed to the test atmosphere for one hour and observed for fourteen days. If five or more of the animals die within the fourteen-day observation period, the mixture is presumed to have a volatility equal to or greater than 500 times the mixture  $LC_{50}$ .

(ii) A mixture is assigned to Packing Group I, Hazard Zone B only if both the following criteria are met, and the mixture does not meet the criteria for Packing Group I, Hazard Zone A:

(A) A sample of the liquid mixture is vaporized and diluted with air to create a test atmosphere of 1000 mL/m<sup>3</sup> vaporized mixture in air. Ten albino rats (five male and five female) are exposed to the test atmosphere for one hour and observed for fourteen days. If five or more of the animals die within the fourteen-day observation period, the



mixture is presumed to have an LC<sub>50</sub> equal to or less than 1000 mL/m<sup>3</sup>.

(B) A sample of the vapor in equilibrium with the liquid mixture is diluted with 9 equal volumes of air to form a test atmosphere. Ten albino rats (five male and five female) are exposed to the test atmosphere for one hour and observed for fourteen days. If five or more of the animals die within the fourteen-day observation period, the mixture is presumed to have a volatility equal to or greater than 10 times the mixture LC<sub>50</sub>.

(iii) A mixture is assigned to Packing Group II only if both the following criteria are met, and the mixture does not meet the criteria for Packing Group I (Hazard Zones A or B):

(A) A sample of the liquid mixture is vaporized and diluted with air to create a test atmosphere of 3000 mL/m<sup>3</sup> vaporized mixture in air. Ten albino rats (five male and five female) are exposed to the test atmosphere for one hour and observed for fourteen days. If five or more of the animals die within the fourteen-day observation period, the mixture is presumed to have an LC<sub>50</sub> equal to or less than 3000 mL/m<sup>3</sup>.

(B) A sample of the vapor in equilibrium with the liquid mixture is used to form a test atmosphere. Ten albino rats (five male and five female) are exposed to the test atmosphere for one hour and observed for fourteen days. If five or more of the animals die within the fourteen-day observation period, the mixture is presumed to have a volatility equal to or greater than the mixture LC<sub>50</sub>.

(iv) A mixture is assigned to Packing Group III only if both the following criteria are met, and the mixture does not meet the criteria for Packing Groups I (Hazard Zones A or B) or Packing Group II (Hazard Zone C):

(A) A sample of the liquid mixture is vaporized and diluted with air to create a test atmosphere of 5000 mL/m<sup>3</sup> vaporized mixture in air. Ten albino rats (five male and five female) are exposed to the test atmosphere for one hour and observed for fourteen days. If five or more of the animals die within the fourteen-day observation period, the mixture is presumed to have an LC<sub>50</sub> equal to or less than 5000 mL/m<sup>3</sup>.

(B) The vapor pressure of the liquid mixture is measured and if the vapor concentration is equal to or greater than 1000 mL/m<sup>3</sup>, the mixture is presumed to have a volatility equal to or greater than 1/5 the mixture LC<sub>50</sub>.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66268–66270, Dec. 20, 1991; 57 FR 45461–45463, Oct. 1, 1992; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–138, 59 FR 49133, Sept. 26, 1994; Amdt. 173–255, 61 FR 50626, Sept. 26, 1996; 66 FR 45183, 45380, Aug. 28, 2001; 66 FR 49556, Sept. 28, 2001; 69 FR 54046, Sept. 7, 2004; 71 FR 54395, Sept. 14, 2006; 71 FR 78631, Dec. 29, 2006]

**§ 173.134 Class 6, Division 6.2—Definitions and exceptions.**

(a) *Definitions and classification criteria.* For the purposes of this subchapter, the following definitions and classification criteria apply to Division 6.2 materials.

(1) *Division 6.2 (Infectious substance)* means a material known or reasonably expected to contain a pathogen. A pathogen is a microorganism (including bacteria, viruses, rickettsiae, parasites, fungi) or other agent, such as a proteinaceous infectious particle (prion), that can cause disease in humans or animals. An infectious substance must be assigned the identification number UN 2814, UN 2900, UN 3373, or UN 3291 as appropriate, and must be assigned to one of the following categories:

(i) *Category A:* An infectious substance in a form capable of causing permanent disability or life-threatening or fatal disease in otherwise healthy humans or animals when exposure to it occurs. An exposure occurs when an infectious substance is released outside of its protective packaging, resulting in physical contact with humans or animals. A Category A infectious substance must be assigned to identification number UN 2814 or UN 2900, as appropriate. Assignment to UN 2814 or UN 2900 must be based on the known medical history or symptoms of the source patient or animal, endemic local conditions, or professional judgment concerning the individual circumstances of the source human or animal.

(ii) *Category B:* An infectious substance that is not in a form generally

capable of causing permanent disability or life-threatening or fatal disease in otherwise healthy humans or animals when exposure to it occurs. This includes Category B infectious substances transported for diagnostic or investigational purposes. A Category B infectious substance must be described as “Biological substance, Category B” and assigned identification number UN 3373. This does not include regulated medical waste, which must be assigned identification number UN 3291.

(2) *Biological product* means a virus, therapeutic serum, toxin, antitoxin, vaccine, blood, blood component or derivative, allergenic product, or analogous product, or arsphenamine or derivative of arsphenamine (or any other trivalent arsenic compound) applicable to the prevention, treatment, or cure of a disease or condition of human beings or animals. A *biological product* includes a material subject to regulation under 42 U.S.C. 262 or 21 U.S.C. 151–159. Unless otherwise excepted, a *biological product* known or reasonably expected to contain a pathogen that meets the definition of a Category A or B infectious substance must be assigned the identification number UN 2814, UN 2900, or UN 3373, as appropriate.

(3) *Culture* means an infectious substance containing a pathogen that is intentionally propagated. *Culture* does not include a human or animal patient specimen as defined in paragraph (a)(4) of this section.

(4) *Patient specimen* means human or animal material collected directly from humans or animals and transported for research, diagnosis, investigational activities, or disease treatment or prevention. *Patient specimen* includes excreta, secreta, blood and its components, tissue and tissue swabs, body parts, and specimens in transport media (e.g., transwabs, culture media, and blood culture bottles).

(5) *Regulated medical waste or clinical waste or (bio) medical waste* means a waste or reusable material derived from the medical treatment of an animal or human, which includes diagnosis and immunization, or from biomedical research, which includes the production and testing of biological

products. Regulated medical waste or clinical waste or (bio) medical waste containing a Category A infectious substance must be classed as an infectious substance, and assigned to UN2814 or UN2900, as appropriate.

(6) *Sharps* means any object contaminated with a pathogen or that may become contaminated with a pathogen through handling or during transportation and also capable of cutting or penetrating skin or a packaging material. *Sharps* includes needles, syringes, scalpels, broken glass, culture slides, culture dishes, broken capillary tubes, broken rigid plastic, and exposed ends of dental wires.

(7) *Toxin* means a Division 6.1 material from a plant, animal, or bacterial source. A *toxin* containing an infectious substance or a *toxin* contained in an infectious substance must be classed as Division 6.2, described as an infectious substance, and assigned to UN 2814 or UN 2900, as appropriate.

(8) *Used health care product* means a medical, diagnostic, or research device or piece of equipment, or a personal care product used by consumers, medical professionals, or pharmaceutical providers that does not meet the definition of a patient specimen, biological product, or regulated medical waste, is contaminated with potentially infectious body fluids or materials, and is not decontaminated or disinfected to remove or mitigate the infectious hazard prior to transportation.

(b) *Exceptions.* The following are not subject to the requirements of this subchapter as Division 6.2 materials:

(1) A material that does not contain an infectious substance or that is unlikely to cause disease in humans or animals.

(2) Non-infectious biological materials from humans, animals, or plants. Examples include non-infectious cells, tissue cultures, blood or plasma from individuals not suspected of having an infectious disease, DNA, RNA or other non-infectious genetic elements.

(3) A material containing micro-organisms that are non-pathogenic to humans or animals.

(4) A material containing pathogens that have been neutralized or inactivated such that they no longer pose a health risk.

(5) A material with a low probability of containing an infectious substance, or where the concentration of the infectious substance is at a level naturally occurring in the environment so it cannot cause disease when exposure to it occurs. Examples of these materials include: Foodstuffs; environmental samples, such as water or a sample of dust or mold; and substances that have been treated so that the pathogens have been neutralized or deactivated, such as a material treated by steam sterilization, chemical disinfection, or other appropriate method, so it no longer meets the definition of an infectious substance.

(6) A biological product, including an experimental or investigational product or component of a product, subject to Federal approval, permit, review, or licensing requirements, such as those required by the Food and Drug Administration of the U.S. Department of Health and Human Services or the U.S. Department of Agriculture.

(7) Blood collected for the purpose of blood transfusion or the preparation of blood products; blood products; plasma; plasma derivatives; blood components; tissues or organs intended for use in transplant operations; and human cell, tissues, and cellular and tissue-based products regulated under authority of the Public Health Service Act (42 U.S.C. 264–272) and/or the Food, Drug, and Cosmetic Act (21 U.S.C. 332 *et seq.*).

(8) Blood, blood plasma, and blood components collected for the purpose of blood transfusion or the preparation of blood products and sent for testing as part of the collection process, except where the person collecting the blood has reason to believe it contains an infectious substance, in which case the test sample must be shipped as a Category A or Category B infectious substance in accordance with § 173.196 or § 173.199, as appropriate.

(9) Dried blood spots or specimens for fecal occult blood detection placed on absorbent filter paper or other material.

(10) A Division 6.2 material, other than a Category A infectious substance, contained in a patient sample being transported for research, diagnosis, investigational activities, or disease treatment or prevention, or a bio-

logical product, when such materials are transported by a private or contract carrier in a motor vehicle used exclusively to transport such materials. Medical or clinical equipment and laboratory products may be transported aboard the same vehicle provided they are properly packaged and secured against exposure or contamination. If the human or animal sample or biological product meets the definition of regulated medical waste in paragraph (a)(5) of this section, it must be offered for transportation and transported in conformance with the appropriate requirements for regulated medical waste.

(11) A human or animal sample (including, but not limited to, secretta, excreta, blood and its components, tissue and tissue fluids, and body parts) being transported for routine testing not related to the diagnosis of an infectious disease, such as for drug/alcohol testing, cholesterol testing, blood glucose level testing, prostate specific antibody testing, testing to monitor kidney or liver function, or pregnancy testing, or for tests for diagnosis of non-infectious diseases, such as cancer biopsies, and for which there is a low probability the sample is infectious.

(12) Laundry and medical equipment and used health care products, as follows:

(i) Laundry or medical equipment conforming to the regulations of the Occupational Safety and Health Administration of the Department of Labor in 29 CFR 1910.1030. This exception includes medical equipment intended for use, cleaning, or refurbishment, such as reusable surgical equipment, or equipment used for testing where the components within which the equipment is contained essentially function as packaging. This exception does not apply to medical equipment being transported for disposal.

(ii) Used health care products not conforming to the requirements in 29 CFR 1910.1030 and being returned to the manufacturer or the manufacturer's designee are excepted from the requirements of this subchapter when offered for transportation or transported in accordance with this paragraph (b)(12). For purposes of this paragraph, a health care product is used when it has

been removed from its original packaging. Used health care products contaminated with or suspected of contamination with a Category A infectious substance may not be transported under the provisions of this paragraph.

(A) Each used health care product must be drained of free liquid to the extent practicable and placed in a watertight primary container designed and constructed to assure that it remains intact under conditions normally incident to transportation. For a used health care product capable of cutting or penetrating skin or packaging material, the primary container must be capable of retaining the product without puncture of the packaging under normal conditions of transport. Each primary container must be marked with a BIOHAZARD marking conforming to 29 CFR 1910.1030(g)(1)(i).

(B) Each primary container must be placed inside a watertight secondary container designed and constructed to assure that it remains intact under conditions normally incident to transportation. The secondary container must be marked with a BIOHAZARD marking conforming to 29 CFR 1910.1030(g)(1)(i).

(C) The secondary container must be placed inside an outer packaging with sufficient cushioning material to prevent movement between the secondary container and the outer packaging. An itemized list of the contents of the primary container and information concerning possible contamination with a Division 6.2 material, including its possible location on the product, must be placed between the secondary container and the outside packaging.

(D) Each person who offers or transports a used health care product under the provisions of this paragraph must know about the requirements of this paragraph.

(13) Any waste or recyclable material, other than regulated medical waste, including—

- (i) Household waste as defined in § 171.8;
- (ii) Sanitary waste or sewage;
- (iii) Sewage sludge or compost;
- (iv) Animal waste generated in animal husbandry or food production; or
- (v) Medical waste generated from households and transported in accord-

ance with applicable state, local, or tribal requirements.

(14) Corpses, remains, and anatomical parts intended for interment, cremation, or medical research at a college, hospital, or laboratory.

(15) Forensic material transported on behalf of a U.S. Government, state, local or Indian tribal government agency, except that—

(i) Forensic material known or suspected to contain a Category B infectious substance must be shipped in a packaging conforming to the provisions of § 173.24.

(ii) Forensic material known or suspected to contain a Category A infectious substance or an infectious substance listed as a select agent in 42 CFR Part 73 must be transported in packaging capable of meeting the test standards in § 178.609 of this subchapter. The secondary packaging must be marked with a BIOHAZARD symbol conforming to specifications in 29 CFR 1910.1030(g)(1)(i). An itemized list of contents must be enclosed between the secondary packaging and the outer packaging.

(16) Agricultural products and food as defined in the Federal Food, Drug, and Cosmetics Act (21 U.S.C. 332 *et seq.*).

(c) *Exceptions for regulated medical waste.* The following provisions apply to the transportation of regulated medical waste:

(1) A regulated medical waste transported by a private or contract carrier is excepted from—

(i) The requirement for an “INFECTIOUS SUBSTANCE” label if the outer packaging is marked with a “BIOHAZARD” marking in accordance with 29 CFR 1910.1030; and

(ii) The specific packaging requirements of § 173.197, if packaged in a rigid non-bulk packaging conforming to the general packaging requirements of §§ 173.24 and 173.24a and packaging requirements specified in 29 CFR 1910.1030, provided the material does not include a waste concentrated stock culture of an infectious substance. Sharps containers must be securely closed to prevent leaks or punctures.

(2) A waste stock or culture of a Category B infectious substance may be offered for transportation and transported as a regulated medical waste

## § 173.136

when it is packaged in a rigid non-bulk packaging conforming to the general packaging requirements of §§ 173.24 and 173.24a and packaging requirements specified in 29 CFR 1910.1030 and transported by a private or contract carrier in a vehicle used exclusively to transport regulated medical waste. Medical or clinical equipment and laboratory products may be transported aboard the same vehicle provided they are properly packaged and secured against exposure or contamination. Sharps containers must be securely closed to prevent leaks or punctures.

(d) If an item listed in paragraph (b) or (c) of this section meets the definition of another hazard class or if it is a hazardous substance, hazardous waste, or marine pollutant, it must be offered for transportation and transported in accordance with applicable requirements of this subchapter.

[67 FR 53138, Aug. 14, 2002, as amended at 68 FR 57632, Oct. 6, 2003; 70 FR 56098, Sept. 23, 2005; 71 FR 32258, June 2, 2006; 71 FR 78631, Dec. 29, 2006; 72 FR 55692, Oct. 1, 2007; 73 FR 4718, Jan. 28, 2008]

## § 173.136 Class 8—Definitions.

(a) For the purpose of this subchapter, “corrosive material” (Class 8) means a liquid or solid that causes full thickness destruction of human skin at the site of contact within a specified period of time. A liquid, or a solid which may become liquid during transportation, that has a severe corrosion rate on steel or aluminum based on the criteria in § 173.137(c)(2) is also a corrosive material..

(b) If human experience or other data indicate that the hazard of a material is greater or less than indicated by the results of the tests specified in paragraph (a) of this section, PHMSA may revise its classification or make the determination that the material is not subject to the requirements of this subchapter.

(c) Skin corrosion test data produced no later than September 30, 1995, using the procedures of part 173, appendix A, in effect on September 30, 1995 (see 49 CFR part 173, appendix A, revised as of October 1, 1994) for appropriate exposure times may be used for classifica-

## 49 CFR Ch. I (10–1–08 Edition)

tion and assignment of packing group for Class 8 materials corrosive to skin.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–241, 59 FR 67508, Dec. 29, 1994; Amdt. 173–261, 62 FR 24732, May 6, 1997; 69 FR 76155, Dec. 20, 2004; 71 FR 78631, Dec. 29, 2006]

## § 173.137 Class 8—Assignment of packing group.

The packing group of a Class 8 material is indicated in Column 5 of the § 172.101 Table. When the § 172.101 Table provides more than one packing group for a Class 8 material, the packing group must be determined using data obtained from tests conducted in accordance with the 1992 OECD Guideline for Testing of Chemicals, Number 404, “Acute Dermal Irritation/Corrosion” (IBR, see § 171.7 of this subchapter) as follows:

(a) *Packing Group I.* Materials that cause full thickness destruction of intact skin tissue within an observation period of up to 60 minutes starting after the exposure time of three minutes or less.

(b) *Packing Group II.* Materials other than those meeting Packing Group I criteria that cause full thickness destruction of intact skin tissue within an observation period of up to 14 days starting after the exposure time of more than three minutes but not more than 60 minutes.

(c) *Packing Group III.* Materials, other than those meeting Packing Group I or II criteria—

(1) That cause full thickness destruction of intact skin tissue within an observation period of up to 14 days starting after the exposure time of more than 60 minutes but not more than 4 hours; or

(2) That do not cause full thickness destruction of intact skin tissue but exhibit a corrosion on steel or aluminum surfaces exceeding 6.25 mm (0.25 inch) a year at a test temperature of 55 °C (130 °F). The corrosion may be determined in accordance with the UN Manual of Tests and Criteria (IBR, see

§ 171.7 of this subchapter) or other equivalent test methods.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; Amdt. 173–241, 59 FR 67508, Dec. 29, 1994; Amdt. 173–261, 62 FR 24733, May 6, 1997; 68 FR 75744, Dec. 31, 2003; 69 FR 76155, Dec. 20, 2004; 71 FR 78631, Dec. 29, 2006]

#### § 173.140 Class 9—Definitions.

For the purposes of this subchapter, *miscellaneous hazardous material* (Class 9) means a material which presents a hazard during transportation but which does not meet the definition of any other hazard class. This class includes:

(a) Any material which has an anesthetic, noxious or other similar property which could cause extreme annoyance or discomfort to a flight crew member so as to prevent the correct performance of assigned duties; or

(b) Any material that meets the definition in § 171.8 of this subchapter for an elevated temperature material, a hazardous substance, a hazardous waste, or a marine pollutant.

[Amdt. 173–224, 57 FR 45463, Oct. 1, 1992, as amended by Amdt. 173–231, 57 FR 52939, Nov. 5, 1992; Amdt. 173–233, 58 FR 33305, June 16, 1993]

#### § 173.141 Class 9—Assignment of packing group.

The packing group of a Class 9 material is as indicated in column 5 of the § 172.101 table.

#### § 173.144 Other Regulated Materials (ORM)—Definitions.

For the purpose of this subchapter, “ORM-D material” means a material such as a consumer commodity, which, although otherwise subject to the regulations of this subchapter, presents a limited hazard during transportation due to its form, quantity and packaging. It must be a material for which exceptions are provided in the § 172.101 table. Each ORM-D material and category of ORM-D material is listed in the § 172.101 table.

#### § 173.145 Other Regulated Materials—Assignment of packing group.

Packing groups are not assigned to ORM-D materials.

#### § 173.150 Exceptions for Class 3 (flammable and combustible liquids).

(a) *General.* Exceptions for hazardous materials shipments in the following paragraphs are permitted only if this section is referenced for the specific hazardous material in the § 172.101 Table of this subchapter.

(b) *Limited quantities.* Limited quantities of flammable liquids (Class 3) and combustible liquids are excepted from labeling requirements, unless the material also meets the definition of Division 6.1 or is offered for transportation or transported by aircraft, and the specification packaging requirements of this subchapter when packaged in combination packagings according to this paragraph. For transportation by aircraft, the package must also comply with the applicable requirements of § 173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments of limited quantities are not subject to subpart F (Placarding) of part 172 of this subchapter. Each package must conform to the packaging requirements of subpart B of this part and may not exceed 30 kg (66 pounds) gross weight. The following combination packagings are authorized:

(1) For flammable liquids in Packing Group I, inner packagings not over 0.5 L (0.1 gallon) net capacity each, packed in strong outer packagings;

(2) For flammable liquids in Packing Group II, inner packagings not over 1.0 L (0.3 gallons) net capacity each, unless the material has a subsidiary hazard of Division 6.1, Packing Group II, in which case the inner packagings may not exceed 100 mL (3.38 ounces) net capacity each, packed in a strong outer packaging.

(3) For flammable liquids in Packing Group III and combustible liquids, inner packagings not over 5.0 L (1.3 gallons) net capacity each, packed in strong outer packagings.

(c) *Consumer commodities.* Except for a material that has a subsidiary hazard of Division 6.1, Packing Group II, a limited quantity which conforms to the provisions of paragraph (b) of this section and is a “consumer commodity” as defined in 171.8 of this subchapter,

may be renamed “Consumer commodity” and reclassified as ORM–D material. In addition to the exceptions provided by paragraph (b) of this section, shipments of ORM–D materials are not subject to the shipping paper requirements of subpart C of part 172 of this subchapter, unless the material meets the definition of a hazardous substance, hazardous waste, marine pollutant, or are offered for transportation and transported by aircraft, and are eligible for the exceptions provided in § 173.156.

(d) *Alcoholic beverages.* An alcoholic beverage (wine and distilled spirits as defined in 27 CFR 4.10 and 5.11) is not subject to the requirements of this subchapter if it—

(1) Contains 24 percent or less alcohol by volume;

(2) Is in an inner packaging of 5 L (1.3 gallons) or less, and for transportation on passenger-carrying aircraft conforms to § 175.10(a)(4) of this subchapter as checked or carry-on baggage; or

(3) Is a Packing Group III alcoholic beverage in a packaging of 250 L (66 gallons) or less, unless transported by air.

(e) *Aqueous solutions of alcohol.* An aqueous solution containing 24 percent or less alcohol by volume and no other hazardous material—

(1) May be reclassified as a combustible liquid.

(2) Is not subject to the requirements of this subchapter if it contains no less than 50 percent water.

(f) *Combustible liquids.* (1) A flammable liquid with a flash point at or above 38 °C (100 °F) that does not meet the definition of any other hazard class may be reclassified as a combustible liquid. This provision does not apply to transportation by vessel or aircraft, except where other means of transportation is impracticable.

(2) The requirements in this subchapter do not apply to a material classed as a combustible liquid in a non-bulk packaging unless the combustible liquid is a hazardous substance, a hazardous waste, or a marine pollutant.

(3) A combustible liquid that is in a bulk packaging or a combustible liquid that is a hazardous substance, a hazardous waste, or a marine pollutant is

not subject to the requirements of this subchapter except those pertaining to:

(i) Shipping papers, waybills, switching orders, and hazardous waste manifests;

(ii) Marking of packages;

(iii) Display of identification numbers on bulk packages;

(iv) For bulk packagings only, placarding requirements of subpart F of part 172 of this subchapter;

(v) Carriage aboard aircraft and vessels (for packaging requirements for transport by vessel, see § 176.340 of this subchapter);

(vi) Reporting incidents as prescribed by §§ 171.15 and 171.16 of this subchapter;

(vii) Packaging requirements of subpart B of this part and, in addition, non-bulk packagings must conform with requirements of § 173.203;

(viii) The requirements of §§ 173.1, 173.21, 173.24, 173.24a, 173.24b, 174.1, 177.804, 177.817, 177.834(j), and 177.837(d) of this subchapter;

(ix) The training requirements of subpart H of part 172 of this subchapter.

(x) Emergency response information requirements of subpart G of part 172.

(4) A combustible liquid that is not a hazardous substance, a hazardous waste, or a marine pollutant is not subject to the requirements of this subchapter if it is a mixture of one or more components that—

(i) Has a flash point at or above 93 °C (200 °F),

(ii) Comprises at least 99 percent of the volume of the mixture, and

(iii) Is not offered for transportation or transported as a liquid at a temperature at or above its flash point.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 173.150, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 173.151 Exceptions for Class 4.

(a) *General.* Exceptions for hazardous materials shipments in the following paragraphs are permitted only if this section is referenced for the specific hazardous material in the § 172.101 table of this subchapter.

(b) *Limited quantities of Division 4.1.* Limited quantities of flammable solids (Division 4.1) in Packing Group II or III are excepted from labeling requirements, unless the material also meets the definition of Division 6.1 or is offered for transportation or transported by aircraft, and the specification packaging requirements of this subchapter when packaged in combination packagings according to this paragraph. For transportation by aircraft, the package must also comply with the applicable requirements of §173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments of limited quantities are not subject to subpart F (Placarding) of part 172 of this subchapter. Each package must conform to the packaging requirements of subpart B of this part and may not exceed 30 kg (66 pounds) gross weight. The following combination packagings are authorized:

(1) For flammable solids in Packing Group II, inner packagings not over 1.0 kg (2.2 pounds) net capacity each, unless the material has a subsidiary hazard of Division 6.1, Packing Group II, in which case the inner packagings may not exceed 0.5 kg (1.1 pounds) net capacity each, packed in a strong outer packaging.

(2) For flammable solids in Packing Group III, inner packagings not over 5.0 kg (11 pounds) net capacity each, packed in a strong outer packaging.

(c) *Consumer commodities.* Except for a material that has a subsidiary hazard of Division 6.1, Packing Group II, a limited quantity which conforms to the provisions of paragraph (b) of this section, and charcoal briquettes in packagings not exceeding 30 kg (66 pounds) gross weight, may be renamed “Consumer commodity” and reclassified as ORM-D material if the material is a “consumer commodity” as defined in §171.8 of this subchapter. In addition to the exceptions provided by paragraph (b) of this section, shipments of ORM-D materials are not subject to the shipping paper requirements of subpart C of part 172 of this subchapter, unless the material meets the definition of a hazardous substance, hazardous waste, marine pollutant, or is offered for

transportation and transported by aircraft, and are eligible for the exceptions provided in §173.156.

(d) *Limited quantities of Division 4.3.* Limited quantities of Division 4.3 (dangerous when wet) solids in Packing Group II or III are excepted from labeling requirements, unless the material also meets the definition of Division 6.1 or is offered for transportation or transported by aircraft, and the specification packaging requirements of this subchapter when packaged in combination packagings according to this paragraph. For transportation by aircraft, the package must also comply with the applicable requirements of §173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments of limited quantities are not subject to subpart F (Placarding) of part 172 of this subchapter. Each package must conform to the packaging requirements of subpart B of this part and may not exceed 30 kg (66 pounds) gross weight. The following combination packagings are authorized:

(1) For Division 4.3 solids in Packing Group II, inner packagings not over 0.5 kg (1.1 pound) net capacity each, packed in strong outer packagings; and

(2) For Division 4.3 solids in Packing Group III, inner packagings not over 1 kg (2.2 pounds) net capacity each, packed in strong outer packagings.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended by Amdt. 173–231, 57 FR 52940, Nov. 5, 1992; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–255, 61 FR 50626, Sept. 26, 1996; 69 FR 76156, Dec. 20, 2004; 70 FR 34398, June 14, 2005; 71 FR 14602, Mar. 22, 2006; 72 FR 55692, Oct. 1, 2007]

**§173.152 Exceptions for Division 5.1 (oxidizers) and Division 5.2 (organic peroxides).**

(a) *General.* Exceptions for hazardous materials shipments in the following paragraphs are permitted only if this section is referenced for the specific hazardous material in the §172.101 table of this subchapter.

(b) *Limited quantities.* Limited quantities of oxidizers (Division 5.1) in Packing Group II and III and organic peroxides (Division 5.2) are excepted from labeling requirements, unless the



material also meets the definition of Division 6.1 or is offered for transportation or transported by aircraft, and the specification packaging requirements of this subchapter when packaged in combination packagings according to this paragraph. For transportation by aircraft, the package must also comply with the applicable requirements of § 173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments of these limited quantities are not subject to subpart F of part 172 (Placarding) of this subchapter. Each package must conform to the packaging requirements of subpart B of this part and may not exceed 30 kg (66 pounds) gross weight. The following combination packagings are authorized:

(1) For oxidizers in Packing Group II, inner packagings not over 1.0 L (0.3 gallon) net capacity each for liquids or not over 1.0 kg (2.2 pounds) net capacity each for solids, unless the material has a subsidiary hazard of Division 6.1, Packing Group II, in which case the inner packagings may not exceed 100 mL (3.38 ounces) for liquids or 0.5 kg (1.1 pounds) for solids, packed in a strong outer packaging.

(2) For oxidizers in Packing Group III, inner packagings not over 5 L (1.3 gallons) net capacity each for liquids or not over 5.0 kg (11 lbs) net capacity each for solids, and packed in strong outer packagings.

(3) For organic peroxides which do not require temperature control during transportation—

(i) For Type D, E, or F organic peroxides, inner packagings not over 125 mL (4.22 ounces) net capacity each for liquids or 500 g (17.64 ounces) net capacity for solids, packed in strong outer packagings.

(ii) For Type B or C organic peroxides, inner packagings not over 25 mL (0.845 ounces) net capacity each for liquids or 100 g (3.528 ounces) net capacity for solids, packed in strong outer packagings.

(4) For polyester resin kits consisting of a base material component (Class 3, Packing Group II or III) and an activator component (Type C, D, E, or F

organic peroxide which does not require temperature control)—

(i) The organic peroxide component must be packed in inner packagings not over 125 mL (4.22 ounces) net capacity each for liquids or 500 g (17.64 ounces) net capacity each for solids;

(ii) The flammable liquid component must be packed in inner packagings not over 5 L (1.3 gallons) net capacity each for Packing Group II or III liquid; and

(iii) The flammable liquid component and the organic peroxide component may be packed in the same strong outer packaging provided they will not interact dangerously in the event of leakage.

(c) *Consumer commodities.* Except for a material that has a subsidiary hazard of Division 6.1, Packing Group II, a limited quantity which conforms to the provisions of paragraph (b) of this section, and is a “consumer commodity” as defined in § 171.8 of this subchapter, may be renamed “Consumer commodity” and reclassified as ORM-D. In addition to the exceptions provided by paragraph (b) of this section, shipments of ORM-D materials are not subject to the shipping paper requirements of subpart C of part 172 of this subchapter, unless the material meets the definition of a hazardous substance, hazardous waste, marine pollutant, or are offered for transportation and transported by aircraft, and are eligible for the exceptions provided in § 173.156.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended by Amdt. 173–231, 57 FR 52940, Nov. 5, 1992; Amdt. 173–241, 59 FR 67508, Dec. 29, 1994; Amdt. 173–261, 62 FR 24733, May 6, 1997; 66 FR 45381, Aug. 28, 2001; 68 FR 45033, July 31, 2003; 69 FR 76156, Dec. 20, 2004; 71 FR 14603, Mar. 22, 2006; 72 FR 55692, Oct. 1, 2007]

#### **§ 173.153 Exceptions for Division 6.1 (poisonous materials).**

(a) *General.* Exceptions for hazardous materials shipments in the following paragraphs are permitted only if this section is referenced for the specific hazardous material in the § 172.101 table of this subchapter.

(b) *Limited quantities of Division 6.1 materials.* The exceptions in this paragraph do not apply to poison-by-inhalation materials. Limited quantities of

poisonous materials (Division 6.1) in Packing Group II and III are excepted from the specification packaging requirements of this subchapter when packaged in combination packagings according to this paragraph. For transportation by aircraft, the package must also comply with the applicable requirements of §173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments of these limited quantities are not subject to subpart F of part 172 (Placarding) of this subchapter. Each package must conform to the packaging requirements of subpart B of this part and may not exceed 30 kg (66 pounds) gross weight. The following combination packagings are authorized:

(1) For poisonous materials in Packing Group II, inner packagings not over 100 mL (3.38 ounces) each for liquids or 0.5 kg (1.1 pounds) each for solids, packed in a strong outer packaging.

(2) For poisonous materials in Packing Group III, inner packagings not over 4 L (1.0 gallon) each for liquids or 5.0 kg (11 pounds) each for solids, packed in a strong outer packaging.

(c) *Consumer commodities.* The following provisions apply to consumer commodities:

(1) A limited quantity of poisonous material in Packing Group III which conforms to the provisions of paragraph (b) of this section, and is a “consumer commodity” as defined in §171.8 of this subchapter, may be renamed “Consumer commodity” and reclassified as ORM-D.

(2) A poisonous material which is a drug or medicine and is a “consumer commodity” as defined in §171.8 of this subchapter, may be renamed “Consumer commodity” and reclassified as ORM-D material if packaged in a combination packaging not exceeding 30 kg (66 pounds) with inner packagings not over 250 mL (8 ounces) net capacity for liquids or 250 g (8.8 ounces) net capacity for solids packed in strong outer packagings. Each package must conform to the packaging requirements of subpart B of this part.

(3) Packages of ORM-D material are excepted from the specification packaging requirements of this subchapter

and from the labeling requirements of subpart E of part 172 of this subchapter. Shipments of ORM-D material are eligible for the exceptions provided in §173.156 and in paragraph (b) of this section and are not subject to the shipping paper requirements of subpart C of part 172 of this subchapter, unless the material meets the definition of a hazardous substance, a hazardous waste, or a marine pollutant or unless offered for transportation or transported by aircraft.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended by Amdt. 173–231, 57 FR 52940, Nov. 5, 1992; 66 FR 45381, Aug. 28, 2001; 68 FR 45033, July 31, 2003; 69 FR 76156, Dec. 20, 2004; 71 FR 14603, Mar. 22, 2006; 71 FR 54938, Sept. 20, 2006]

#### § 173.154 Exceptions for Class 8 (corrosive materials).

(a) *General.* Exceptions for hazardous materials shipments in the following paragraphs are permitted only if this section is referenced for the specific hazardous material in the §172.101 table of this subchapter.

(b) *Limited quantities.* Limited quantities of corrosive materials (Class 8) in Packing Group II and III are excepted from labeling requirements, unless the material also meets the definition of Division 6.1 or is offered for transportation or transported by aircraft, and the specification packaging requirements of this subchapter when packaged in combination packagings according to this paragraph. For transportation by aircraft, the package must also comply with the applicable requirements of §173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments of these limited quantities are not subject to subpart F (Placarding) of part 172 of this subchapter. Each package must conform to the packaging requirements of subpart B of this part and may not exceed 30 kg (66 pounds) gross weight. The following combination packagings are authorized:

(1) For corrosive materials in Packing Group II, inner packagings not over 1.0 L (0.3 gallon) net capacity each for liquids or not over 1.0 kg (2.2 pounds) net capacity each for solids, unless the

## § 173.155

## 49 CFR Ch. I (10–1–08 Edition)

material has a subsidiary hazard of Division 6.1, Packing Group II in which case the inner packagings may not exceed 100 mL (3.38 ounces) for liquids or 0.5 kg (1.1 pounds) for solids, packed in a strong outer packaging.

(2) For corrosive materials in Packing Group III, in inner packagings not over 5.0 L (1.3 gallons) net capacity each for liquids, or not over 5.0 kg (11 lbs) net capacity each for solids, and packed in strong outer packagings.

(c) *Consumer commodities.* Except for a material that has a subsidiary hazard of Division 6.1, Packing Group II, a limited quantity which conforms to the provisions of paragraph (b) of this section, and is a “consumer commodity” as defined in §171.8 of this subchapter, may be renamed “Consumer commodity” and reclassified as ORM-D. In addition to the exceptions provided by paragraph (b) of this section, shipments of ORM-D materials are not subject to the shipping paper requirements of subpart C of part 172 of this subchapter, unless the material meets the definition of a hazardous substance, hazardous waste, marine pollutant, or are offered for transportation and transported by aircraft, and are eligible for the exceptions provided in §173.156.

(d) *Materials corrosive to aluminum or steel only.* Except for a hazardous substance, a hazardous waste, or a marine pollutant, a material classed as a Class 8, Packing Group III, material solely because of its corrosive effect—

(1) On aluminum is not subject to any other requirements of this subchapter when transported by motor vehicle or rail car in a packaging constructed of materials that will not react dangerously with or be degraded by the corrosive material; or

(2) On steel is not subject to any other requirements of this subchapter when transported by motor vehicle or rail car in a bulk packaging constructed of materials that will not react dangerously with or be degraded by the corrosive material.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; 57 FR 45463, Oct. 1, 1992; Amdt. 173–231, 57 FR 52940, Nov. 5, 1992; 68 FR 45033, July 31, 2003; 69 FR 76157, Dec. 20, 2004; 71 FR 14603, Mar. 22, 2006; 72 FR 55693, Oct. 1, 2007]

## § 173.155 Exceptions for Class 9 (miscellaneous hazardous materials).

(a) *General.* Exceptions for hazardous materials shipments in the following paragraphs are permitted only if this section is referenced for the specific hazardous material in the §172.101 table of this subchapter.

(b) *Limited quantities.* Limited quantities of miscellaneous hazardous materials (Class 9) are excepted from labeling, unless offered for transportation or transported by aircraft, and the specification packaging requirements of this subchapter when packaged in combination packagings according to this paragraph. For transportation by aircraft, the package must also comply with the applicable requirements of §173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments of these limited quantities are not subject to subpart F (Placarding) of part 172 of this subchapter. Each package must conform to the packaging requirements of subpart B of this part and may not exceed 30 kg (66 pounds) gross weight. The following combination packagings are authorized:

(1) For liquids, inner packagings not over 5.0 L (1.3 gallons) net capacity each, packed in strong outer packagings.

(2) For solids, inner packagings not over 5.0 kg (11 pounds) net capacity each, packed in strong outer packagings.

(c) *Consumer commodities.* A limited quantity which conforms to the provisions of paragraph (b) of this section and is a “consumer commodity” as defined in §171.8 of this subchapter, may be renamed “Consumer commodity” and reclassified as ORM-D material. In addition to the exceptions provided by paragraph (b) of this section, shipments of ORM-D materials are not subject to the shipping paper requirements of subpart C of part 172 of this subchapter, unless the material meets the definition of a hazardous substance, a hazardous waste, or a marine pollutant or unless offered for transportation or

transported by aircraft, and are eligible for the exceptions provided in § 173.156.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; Amdt. 173–231, 57 FR 52940, Nov. 5, 1992; Amdt. 173–253, 61 FR 27174, May 30, 1996; 71 FR 14603, Mar. 22, 2006]

#### § 173.156 Exceptions for ORM materials.

(a) Exceptions for hazardous materials shipments in the following paragraphs are permitted only if this section is referenced for the specific hazardous material in the § 172.101 table or in a packaging section in this part.

(b) *ORM-D*. Packagings for ORM-D materials are specified according to hazard class in §§ 173.150 through 173.155 and in § 173.306. In addition to other exceptions specified for ORM-D materials in this part:

(1) Strong outer packagings as specified in this part, marking requirements specified in subpart D of part 172 of this subchapter, and the 30 kg (66 pounds) gross weight limitation are not required for materials classed as ORM-D when—

(i) Unitized in cages, carts, boxes or similar overpacks;

(ii) Offered for transportation or transported by:

(A) Rail;

(B) Private or contract motor carrier; or

(C) Common carrier in a vehicle under exclusive use for such service; and

(iii) Transported to or from a manufacturer, a distribution center, or a retail outlet, or transported to a disposal facility from one offeror.

(2) The 30 kg (66 pounds) gross weight limitation does not apply to materials classed as ORM-D when offered for transportation, or transported, by highway or rail between a manufacturer, a distribution center, and a retail outlet provided—

(i) Inner packagings conform to the quantity limits for inner packagings specified in §§ 173.150(b), 173.152(b), 173.154(b), 173.155(b) and 173.306 (a) and (b), as appropriate;

(ii) The inner packagings are packed into corrugated fiberboard trays to prevent them from moving freely;

(iii) The trays are placed in a fiberboard box which is banded and secured to a wooden pallet by metal, fabric, or plastic straps, to form a single palletized unit;

(iv) The package conforms to the general packaging requirements of subpart B of this part;

(v) The maximum net quantity of hazardous material permitted on one palletized unit is 250 kg (550 pounds); and

(vi) The package is properly marked in accordance with § 172.316 of this subchapter.

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; 57 FR 45463, Oct. 1, 1992; Amdt. 173–255, 61 FR 50626, Sept. 26, 1996; 63 FR 37461, July 10, 1998]

#### Subpart E—Non-bulk Packaging for Hazardous Materials Other Than Class 1 and Class 7

SOURCE: Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, unless otherwise noted.

#### § 173.158 Nitric acid.

(a) Nitric acid exceeding 40 percent concentration may not be packaged with any other material.

(b) Nitric acid in any concentration which does not contain sulfuric acid or hydrochloric acid as impurities, when offered for transportation or transported by rail, highway, or water shall be packaged in specification containers as follows:

(1) 1A1 stainless steel drums are authorized, subject to the following limitations:

(i) Stainless steel used in drums must conform to the following thicknesses:

| Nominal (marked) capacity (in liters) of 1A1 drum | Minimum thickness (in mm) of stainless steel |
|---------------------------------------------------|----------------------------------------------|
| 55                                                | 0.9                                          |
| 115                                               | 1.2                                          |
| 210                                               | 1.5                                          |
| 450                                               | 2.0                                          |

(ii) Drums weighing less than 85 percent of their original tare weight may not be used.

(iii) Type 304 or other grades of equivalent corrosion-resistant steels in the as-welded condition are permissible for nitric acid concentrations up to and including 78 percent.

(iv) For all concentrations of nitric acid, the following are permissible:

(A) Type 304 heat-treated (quenched in water at 1040 °C (1900 °F)),

(B) Stabilized Type 347 in the as-welded condition,

(C) Stabilized Type 347 stress-relieved (845–900 °C (1550–1650 °F)),

(D) Stabilized Type 347 heat-treated (quenched in water at 1040 °C (1900 °F)), or

(E) Other grades of equivalent corrosion resistance.

(v) All parts of drum exposed to lading must be capable of withstanding the corrosive effect of nitric acid to the extent that 65 percent boiling nitric acid does not penetrate the metal more than 0.0381 mm (0.002 inches) per month. (ASTM A 262 may be used for a suitable corrosion test procedure.)

(vi) In addition to marking required by §178.503 of this subchapter, the following marks, in lettering of at least 12.7 mm (0.5 inch) height, must be placed on drums used to transport nitric acid:

(A) The type of steel used in body and head sheets as identified by American Iron and Steel Institute type number, and, in addition, the letters “HT” following the steel designation on containers subject to stress relieving or heat treatment during manufacture.

(B) The thickness in mm of metal in thinnest part. When the thickness of metal in the body differs from that in the head, both must be indicated with slanting line between and with the gauge of the body indicated first.

(C) Original tare weight in kilograms, preceded by the letters “TW.”

An example of the markings required by paragraphs (b)(1)(vi) (A), (B), and (C) of this section is “304HT/1.9/2.7/TW55.”

(2) 4H1 expanded plastics outer packagings with glass inner receptacles of not greater than 2.5 L (0.66 gallon) capacity each. No more than four 2.5 L (0.66 gallon) inner receptacles may be packed in one outer packaging.

(c) Nitric acid of 80 percent or greater concentration which does not contain sulfuric acid or hydrochloric acid as impurities, when offered for transportation or transported by rail, highway, or water may be packaged in 1B1 aluminum drums.

(d) Nitric acid of 90 percent or greater concentration, when offered for transportation or transported by rail, highway, or water may be packaged as follows:

(1) In 4C1, 4C2, 4D or 4F wooden boxes with inner packagings consisting of glass bottles further individually overpacked in tightly closed metal packagings. Glass bottles must be of 2.5 L (0.66 gallon) or less capacity and cushioned with a non-reactive, absorbent material within the metal packagings.

(2) In combination packagings with 1A2, 1B2, 1D, 1G, 1H2, 3H2 or 4G outer packagings with inner glass packagings of 2.5 L (0.66 gallons) or less capacity cushioned with a non-reactive, absorbent material and packed within a tightly closed intermediate packaging of metal or plastic.

(e) Nitric acid of less than 90 percent concentration, when offered for transportation or transported by rail, highway, or water may be packaged in 4G fiberboard boxes or 4C1, 4C2, 4D or 4F wooden boxes with inside glass packagings of not over 2.5 L (0.66 gallon) capacity each.

(f) Nitric acid of 70 percent or less concentration, when offered for transportation or transported by rail, highway, or water, may be packaged as follows:

(1) In composite packagings 6PA1, 6PA2, 6PB1, 6PB2, 6PC, 6PD1, 6PH1, or 6PH2. 6HH1 and 6HA1 composite packaging with plastic inner receptacles meeting the compatibility requirements §173.24(e) (e.g., PFA Teflon) are authorized.

(2) In 4H1 expanded plastic boxes with inner glass packagings of not over 2.5 L (0.66 gallon) each.

(3) In combination packagings with 1A2, 1B2, 1D, 1G, 1H2, 3H2, 4C1, 4C2, 4D, 4F or 4G outer packagings and plastic inner packagings not over 2.5 L (0.66 gallon) capacity further individually overpacked in tightly closed metal packagings.

(g) Nitric acid of more than 70 percent concentration, when offered for transportation or transported by cargo aircraft only, must be packaged in combination packagings with 1A2, 1B2, 1D, 1G, 1H2, 3H2, 4C1, 4C2, 4D, 4F or 4G outer packagings with glass or earthenware inner packagings of not over 1

L (0.3 gallon) or glass ampoules of not over 0.5 L (0.1 gallon).

(h) Nitric acid of less than 70 percent concentration, when offered for transportation in cargo aircraft only must be packaged in combination packagings with 1A2, 1B2, 1D, 1G, 1H2, 3H2, 4C1, 4C2, 4D, 4F or 4G outer packagings with inner packagings of—

(1) Glass or earthenware not over 2.5 L (0.66 gallon) capacity;

(2) Plastic not over 2.5 L (0.66 gallon) capacity further individually overpacked in tightly closed metal packagings; or

(3) Glass ampoule not over 0.5 L (0.1 gallon) capacity.

[Amdt. 173-224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; Amdt. 173-241, 59 FR 67509, Dec. 29, 1994; Amdt. 173-255, 61 FR 50626, Sept. 26, 1996; 68 FR 75744, Dec. 31, 2003]

#### § 173.159 Batteries, wet.

(a) Electric storage batteries, containing electrolyte acid or alkaline corrosive battery fluid, must be completely protected so that short circuits will be prevented (e.g., by the use of non-conductive caps that entirely cover the terminals); they may not be packed with other materials except as provided in paragraphs (g) and (h) of this section and in §§ 173.220 and 173.222. For transportation by aircraft, the packaging for wet cell batteries must incorporate an acid- or alkali-proof liner, or include a supplementary packaging with sufficient strength and be adequately sealed to prevent leakage of electrolyte fluid in the event of spillage.

(b) The following specification packagings are authorized for batteries packed without other materials:

(1) 4C1, 4C2, 4D, or 4F wooden boxes.

(2) 4G fiberboard boxes.

(3) 1D plywood drums.

(4) 1G fiber drums.

(5) 1H2 and 3H2 plastic drums and jerricans.

(6) 4H2 plastic boxes.

(c) The following non-specification packagings are authorized for batteries packed without other materials:

(1) Electric storage batteries protected against short circuits (e.g., by the use of non-conductive caps that entirely cover the terminals) and firmly

secured to skids or pallets capable of withstanding the shocks normally incident to transportation, are authorized for transportation by rail, highway, or water. The height of the completed unit must not exceed 1½ times the width of the skid or pallet. The unit must be capable of withstanding, without damage, a superimposed weight equal to two times the weight of the unit or, if the weight of the unit exceeds 907 kg (2000 pounds), a superimposed weight of 1814 kg (4000 pounds). Battery terminals must not be relied upon to support any part of the superimposed weight.

(2) Electric storage batteries weighing 225 kg (500 pounds) or more, consisting of carriers' equipment, may be shipped by rail when mounted on suitable skids and protected against short circuits (e.g., by the use of non-conductive caps that entirely cover the terminals). Such shipments may not be offered in interchange service.

(3) One to three batteries not over 11.3 kg (25 pounds) each, packed in outer boxes. The maximum authorized gross weight is 34 kg (75 pounds).

(4) Not more than four batteries not over 7 kg (15 pounds) each, packed in strong outer fiberboard or wooden boxes. Batteries must be securely cushioned and packed to prevent short circuits (e.g., by the use of non-conductive caps that entirely cover the terminals). The maximum authorized gross weight is 30 kg (65 pounds).

(5) Not more than five batteries not over 4.5 kg (10 pounds) each, packed in strong outer fiberboard or wooden boxes. Batteries must be securely cushioned and packed to prevent short circuits (e.g., by the use of non-conductive caps that entirely cover the terminals). The maximum authorized gross weight is 30 kg (65 pounds).

(6) Single batteries not exceeding 34 kg (75 pounds) each, packed in 5-sided slip covers or in completely closed fiberboard boxes. Slip covers and boxes must be of solid or double-faced corrugated fiberboard of at least 91 kg (200 pounds) Mullen test strength. The slip cover or fiberboard box must fit snugly and provide inside top clearance of at least 1.3 cm (0.5 inch) above battery

terminals and filler caps with reinforcement in place. Assembled for shipment, the bottom edges of the slipcover must come to within 2.5 cm (1 inch) of the bottom of the battery. The completed package (battery and box or slip cover) must be capable of withstanding a top-to-bottom compression test of at least 225 kg (500 pounds) without damage to battery terminals, cell covers or filler caps.

(7) Single batteries exceeding 34 kg (75 pounds) each may be packed in completely closed fiberboard boxes. Boxes must be of double-wall corrugated fiberboard of at least 181 kg (400 pounds) test, or solid fiberboard testing at least 181 kg (400 pounds); a box may have hand holes in its ends provided that the handholes will not materially weaken the box. Sides and ends of the box must have cushioning between the battery and walls of the box; combined thickness of cushioning material and walls of the box must not be less than 1.3 cm (0.5 inch); and cushioning must be excelsior pads, corrugated fiberboard, or other suitable cushioning material. The bottom of the battery must be protected by a minimum of one excelsior or double-wall corrugated fiberboard pad. The top of the battery must be protected by a wood frame, corrugated trays or scored sheets of corrugated fiberboard having minimum test of 91 kg (200 pounds), or other equally effective cushioning material. Top protection must bear evenly on connectors and/or edges of the battery cover to facilitate stacking of batteries. No more than one battery may be placed in one box. The maximum authorized gross weight is 91 kg (200 pounds).

(d) A nonspillable wet electric storage battery is excepted from all other requirements of this subchapter under the following conditions:

(1) The battery must be protected against short circuits (e.g., by the use of non-conductive caps that entirely cover the terminals) and securely packaged;

(2) For batteries manufactured after September 30, 1995, the battery and the outer packaging must be plainly and durably marked “NONSPILLABLE” or “NONSPILLABLE BATTERY”; and

(3) The battery must be capable of withstanding the following two tests,

without leakage of battery fluid from the battery:

(i) *Vibration test.* The battery must be rigidly clamped to the platform of a vibration machine, and a simple harmonic motion having an amplitude of 0.8 mm (0.03 inches), with a 1.6 mm (0.063 inches) maximum total excursion must be applied. The frequency must be varied at the rate of 1 Hz/min between the limits of 10 Hz to 55 Hz. The entire range of frequencies and return must be traversed in 95±5 minutes for each mounting position (direction of vibrator) of the battery. The battery must be tested in three mutually perpendicular positions (to include testing with fill openings and vents, if any, in an inverted position) for equal time periods.

(ii) *Pressure differential test.* Following the vibration test, the battery must be stored for six hours at 24 °C±4 °C (75 °F±7 °F) while subjected to a pressure differential of at least 88 kPa (13 psig). The battery must be tested in three mutually perpendicular positions (to include testing with fill openings and vents, if any, in an inverted position) for at least six hours in each position.

(4) At a temperature of 55 °C (131 °F), the battery must not contain any unabsorbed free-flowing liquid, and must be designed so that electrolyte will not flow from a ruptured or cracked case.

(e) Electric storage batteries containing electrolyte or corrosive battery fluid are not subject to the requirements of this subchapter for transportation by highway or rail if all of the following requirements are met:

(1) No other hazardous materials may be transported in the same vehicle;

(2) The batteries must be loaded or braced so as to prevent damage and short circuits in transit (e.g., by the use of non-conductive caps that entirely cover the terminals);

(3) Any other material loaded in the same vehicle must be blocked, braced, or otherwise secured to prevent contact with or damage to the batteries; and

(4) The transport vehicle may not carry material shipped by any person other than the shipper of the batteries.

(f) Electric storage batteries, containing electrolyte or corrosive battery fluid in a coil from which it is injected into the battery cells by a gas generator and initiator assembled with the battery, and which are nonspillable under the criteria of paragraph (d) of this section, are excepted from other requirements of this subchapter when examined by the Bureau of Explosives and approved by the Associate Administrator.

(g) Electrolyte, acid, or alkaline corrosive battery fluid, packed with storage batteries wet or dry, must be packed in one of the following specification packagings:

(1) In 4C1, 4C2, 4D, or 4F wooden boxes with inner receptacles of glass, not over 4.0 L (1 gallon) each with not over 8.0 L (2 gallons) total in each outside container. Inside containers must be well-cushioned and separated from batteries by a strong solid wooden partition. The completed package must conform to Packing Group III requirements.

(2) Electrolyte, acid, or alkaline corrosive battery fluid included with storage batteries and filling kits may be packed in strong rigid outer packagings when shipments are made by, for, or to the Departments of the Army, Navy, or Air Force of the United States. Packagings must conform to military specifications. The electrolyte, acid, or alkaline corrosive battery fluid must be packed in polyethylene bottles of not over 1.0 L (0.3 gallon) capacity each. Not more than 24 bottles, securely separated from storage batteries and kits, may be offered for transportation or transported in each package.

(3) In 4G fiberboard boxes with not more than 12 inside packagings of polyethylene or other material resistant to the lading, each not over 2.0 L (0.5 gallon) capacity each. Completed packages must conform to Packing Group III requirements. Inner packagings must be adequately separated from the storage battery. The maximum authorized gross weight is 29 kg (64 pounds). These packages are not authorized for transportation by aircraft.

(h) Dry storage batteries or battery charger devices may be packaged in 4G fiberboard boxes with inner receptacles

containing battery fluid. Completed packagings must conform to Packing Group III requirements. Not more than 12 inner receptacles may be packed in one outer box. The maximum authorized gross weight is 34 kg (75 pounds).

[Amdt. 173-224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; 57 FR 45463, Oct. 1, 1992; Amdt. 173-235, 58 FR 50502, Sept. 27, 1993; Amdt. 173-234, 58 FR 51532, Oct. 1, 1993; Amdt. 173-246, 60 FR 49110, Sept. 21, 1995; 64 FR 10777, Mar. 5, 1999; 65 FR 58629, Sept. 29, 2000; 66 FR 45379, 45380, Aug. 28, 2001; 68 FR 45033, July 31, 2003; 71 FR 78631, Dec. 29, 2006]

#### **§ 173.160 Bombs, smoke, non-explosive (corrosive).**

Bombs, smoke, non-explosive may be shipped provided they are without ignition elements, bursting charges, detonating fuses or other explosive components. They must be packaged in wooden (4C1, 4C2), plywood (4D) or reconstituted wood (4F) boxes, or plywood drums (1D), which meet Packing Group II requirements.

#### **§ 173.161 Chemical kits and first aid kits.**

(a) Chemical kits and First aid kits must conform to the following requirements:

(1) The kits may only contain hazardous materials for which packaging exceptions are provided in column 8(A) the § 172.101 Table of this subchapter.

(2) The kits must be packed in a strong outer packaging conforming to the packaging requirements of subpart B of this subchapter.

(3) The kits must include sufficient absorbent material to completely absorb the contents of any liquid hazardous materials contained in the kits. The contents must be separated, placed, or packed, and closed with cushioning material to protect them from damage.

(4) The contents of the kits must be packed so there will be no possibility of the mixture of contents causing dangerous evolution of heat or gas.

(5) The packing group assigned to the kits as a whole must be the most stringent packing group assigned to any individual substance contained in the kits.

(6) Inner receptacles containing hazardous materials within the kits must



## § 173.162

not contain more than 250 ml for liquids or 250 g for solids per receptacle.

(7) The total quantity of hazardous materials in any one outer package must not exceed either 10 L or 10 kg.

(b) Chemical kits and First aid kits are excepted from the specification packaging requirements of this subchapter. Chemical kits and First aid kits are also excepted from the labeling requirements of this subchapter except when offered for transportation or transported by air. In addition, Chemical kits and First aid kits are not subject to subpart F of part 172 of this subchapter (Placarding), part 174 (Carriage by rail) of this subchapter except §174.24 (Shipping papers), and part 177 (Carriage by highway) of this subchapter except §177.817 (Shipping papers). Kits that meet the definition for a consumer commodity in §171.8 of this subchapter may be transported in accordance with the exceptions for ORM materials in §173.156.

[Doc. No. 2002-13658, 68 FR 45033, July 31, 2003]

### § 173.162 Gallium.

(a) Except when packaged in cylinders or steel flasks, gallium must be packaged in packagings which meet the requirements of part 178 of this subchapter at the Packing Group I performance level for transportation by aircraft, and at the Packing Group III performance level for transport by highway, rail or vessel, as follows:

(1) In combination packagings intended to contain liquids consisting of glass, earthenware or rigid plastic inner packagings with a maximum net mass of 15 kg (33 pounds) each. The inner packagings must be packed in wood boxes (4C1, 4C2, 4D, 4F), fiberboard boxes (4G), plastic boxes (4H1, 4H2), fiber drums (1G) or removable head steel and plastic drums or jerricans (1A2, 1H2, 3A2 or 3H2) with sufficient cushioning materials to prevent breakage. Either the inner packagings or the outer packagings must have an inner liner that is leakproof or bags of strong leakproof and puncture-resistant material impervious to the contents and completely surrounding the contents to prevent it from escaping from the package, irrespective of its position.

## 49 CFR Ch. I (10-1-08 Edition)

(2) In packagings intended to contain liquids consisting of semi-rigid plastic inner packagings of not more than 2.5 kg (5.5 pounds) net capacity each, individually enclosed in a sealed, leak-tight bag of strong puncture-resistant material. The sealed bags must be packed in wooden (4C1, 4C2), plywood (4D), reconstituted wood (4F), fiberboard (4G) or plastic (4H1, 4H2) boxes or in fiber (1G) or steel (1A2) drums, which are lined with leak-tight, puncture-resistant material. Bags and liner material must be chemically resistant to gallium.

(3) Cylinders and steel flasks with vaulted bottoms are also authorized.

(b) When it is necessary to transport gallium at low temperatures in order to maintain it in a completely solid state, the above packagings may be overpacked in a strong, water-resistant outer packaging which contains dry ice or other means of refrigeration. If a refrigerant is used, all of the above materials used in the packaging of gallium must be chemically and physically resistant to the refrigerant and must have impact resistance at the low temperatures of the refrigerant employed. If dry ice is used, the outer packaging must permit the release of carbon dioxide gas.

(c) Manufactured articles or apparatuses, each containing not more than 100 mg (0.0035 ounce) of gallium and packaged so that the quantity of gallium per package does not exceed 1 g (0.35 ounce) are not subject to the requirements of this subchapter.

[64 FR 10777, Mar. 5, 1999; as amended at 66 FR 33430, June 21, 2001]

### § 173.163 Hydrogen fluoride.

(a) Hydrogen fluoride (hydrofluoric acid, anhydrous) must be packaged as follows:

(1) In specification 3, 3A, 3AA, 3B, 3BN, or 3E cylinders; or in specification 4B, 4BA, or 4BW cylinders except that brazed 4B, 4BA, and 4BW cylinders are not authorized. The filling density may not exceed 85 percent of the cylinder's water weight capacity. In place of the periodic volumetric expansion test, cylinders used in exclusive service may be given a complete external visual inspection in conformance with part 180,

subpart C, of this subchapter, at the time such requalification becomes due.

(2) In a UN cylinder, as specified in part 178 of this subchapter, having a minimum test pressure of 10 bar and a maximum filling ratio of 0.84.

(b) A cylinder removed from hydrogen fluoride service must be condemned in accordance with §180.205 of this subchapter. Alternatively, at the direction of the owner, the requalifier may render the cylinder incapable of holding pressure.

[71 FR 33880, June 12, 2006]

**§ 173.164 Mercury (metallic and articles containing mercury).**

(a) For transportation by aircraft, mercury must be packaged in packagings which meet the requirements of part 178 of this subchapter at the Packing Group I performance level, as follows:

(1) In inner packagings of earthenware, glass or plastic containing not more than 3.5 kg (7.7 pounds) of mercury, or inner packagings which are glass ampoules containing not more than 0.5 kg (1.1 pounds) of mercury, or iron or steel quicksilver flasks containing not more than 35 kg (77 pounds) of mercury. The inner packagings or flasks must be packed in steel drums (1A2), steel jerricans (3A2), wooden boxes (4C1), (4C2), plywood boxes (4D), reconstituted wood boxes (4F), fiberboard boxes (4G), plastic boxes (4H2), plywood drums (1D) or fiber drums (1G).

(2) [Reserved]

(3) When inner packagings of earthenware, glass or plastic are used, they must be packed in the outer packaging with sufficient cushioning material to prevent breakage.

(4) Either the inner packagings or the outer packagings must have inner linings or bags of strong leakproof and puncture-resistant material impervious to mercury, completely surrounding the contents, so that the escape of mercury will be prevented irrespective of the position of the package.

(b) Manufactured articles or apparatuses, each containing not more than 100 mg (0.0035 ounce) of mercury and packaged so that the quantity of mercury per package does not exceed 1

g (0.035 ounce) are not subject to the requirements of this subchapter.

(c) Manufactured articles or apparatuses containing mercury are excepted from the specification packaging requirements of this subchapter when packaged as follows:

(1) Manufactured articles or apparatuses of which metallic mercury is a component part, such as manometers, pumps, thermometers, switches, etc. (for electron tubes, mercury vapor tubes and similar tubes, see paragraph (c)(3) of this section), must be in strong outer packagings, having sealed inner liners or bags of strong leakproof and puncture-resistant material impervious to mercury, which will prevent the escape of mercury from the package irrespective of its position. Mercury switches and relays are excepted from these packaging requirements, if they are totally enclosed, leakproof and in sealed metal or plastic units.

(2) Thermometers, switches and relays, each containing a total quantity of not more than 15 g (0.53 ounces) of mercury, are excepted from the requirements of this subchapter if installed as an integral part of a machine or apparatus and so fitted that shock of impact damage, leading to leakage of mercury, is unlikely to occur under conditions normally incident to transport.

(3) Electron tubes, mercury vapor tubes and similar tubes must be packaged as follows:

(i) Tubes which are packed in strong outer packagings with all seams and joints sealed with self-adhesive, pressure-sensitive tape which will prevent the escape of mercury from the package, are authorized up to a total net quantity of 450 g (15.9 ounces) of mercury per package;

(ii) Tubes with more than 450 g (15.9 ounces) of mercury are authorized only when packed in strong outer packagings, having sealed inner liners or bags of strong leakproof and puncture-resistant material impervious to mercury which will prevent escape of mercury from the package irrespective of its position;

(iii) Tubes which do not contain more than 5 g (0.2 ounce) of mercury each

and which are packed in the manufacturer's original packagings, are authorized up to a total net quantity of 30 g (1.1 ounces) of mercury per package;

(iv) Tubes which are completely jacketed in sealed leakproof metal cases are authorized in the manufacturer's original packagings.

(4) A person offering for transportation electron tubes, mercury vapor tubes, and similar tubes shall indicate the quantity of mercury therein on the shipping paper.

(5) Mercurial barometers conforming to paragraph (c)(1) of this section, which are loaded and unloaded from an aircraft under the supervision of, and accompanied in flight by, a National Weather Service official or similar United States agency official, are excepted from any other requirements of this subchapter.

(d) For transportation by other than aircraft, mercury must be packaged—

(1) In any packaging which meets the requirements of part 178 of this subchapter at the Packing Group III performance level; or

(2) In non-specification reusable metal packagings.

(e) Except for a hazardous substance or a hazardous waste or for transportation by aircraft or vessel, packages containing less than 0.45 kg (1.0 pound) net weight of mercury are not subject to the requirements of this subchapter.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; Amdt. 173–241, 59 FR 67509, Dec. 29, 1994; Amdt. 173–246, 60 FR 49110, Sept. 21, 1995; 64 FR 10777, 10778, Mar. 5, 1999; 68 FR 57632, Oct. 6, 2003]

**§ 173.166 Air bag inflators, air bag modules and seat-belt pretensioners.**

(a) *Definitions.* An *air bag inflator* (consisting of a casing containing an igniter, a booster material, a gas generant and, in some cases, a pressure vessel (cylinder)) is a gas generator used to inflate an air bag in a supplemental restraint system in a motor vehicle. An *air bag module* is the air bag inflator plus an inflatable bag assembly. A *seat-belt pre-tensioner* contains similar hazardous materials and is used in the operation of a seat-belt restraining system in a motor vehicle.

(b) *Classification.* An air bag inflator, air bag module, or seat-belt pretensioner may be classed as Class 9 (UN3268) if:

(1) The manufacturer has submitted each design type air bag inflator, air bag module, or seat-belt pretensioner to a person approved by the Associate Administrator, in accordance with § 173.56(b), for examination and testing. The submission must contain a detailed description of the inflator or pretensioner or, if more than a single inflator or pretensioner is involved, the maximum parameters of each particular inflator or pretensioner design type for which approval is sought and details on the complete package. The manufacturer must submit an application, including the test results and report recommending the shipping description and classification for each device or design type to the Associate Administrator, and must receive written notification from the Associate Administrator that the device has been approved for transportation and assigned an EX number; or,

(2) The manufacturer has submitted an application, including a classification issued by the competent authority of a foreign government to the Associate Administrator, and received written notification from the Associate Administrator that the device has been approved for transportation and assigned an EX number.

(c) *EX numbers.* When offered for transportation, the shipping paper must contain the EX number or product code for each approved inflator, module or pretensioner in association with the basic description required by § 172.202(a) of this subchapter. Product codes must be traceable to the specific EX number assigned to the inflator, module or pretensioner by the Associate Administrator. The EX number or product code is not required to be marked on the outside package.

(d) *Exceptions.* (1) An air bag module or seat-belt pretensioner that has been approved by the Associate Administrator and is installed in a motor vehicle, aircraft, boat or other transport conveyance or its completed components, such as steering columns or door panels, is not subject to the requirements of this subchapter.

(2) An air bag module containing an inflator that has been previously approved for transportation is not required to be submitted for further examination or approval.

(3) An air bag module containing an inflator that has previously been approved as a Division 2.2 material is not required to be submitted for further examination to be reclassified as a Class 9 material.

(4) *Shipments for recycling.* When offered for domestic transportation by highway, rail freight, cargo vessel or cargo aircraft, a serviceable air bag module or seat-belt pretensioner removed from a motor vehicle that was manufactured as required for use in the United States may be offered for transportation and transported without compliance with the shipping paper requirement prescribed in paragraph (c) of this section. However, the word "Recycled" must be entered on the shipping paper immediately after the basic description prescribed in § 172.202 of this subchapter. No more than one device is authorized in the packaging prescribed in paragraph (e)(1), (2) or (3) of this section. The device must be cushioned and secured within the package to prevent movement during transportation.

(e) *Packagings.* Rigid, outer packagings, meeting the general packaging requirements of part 173, and the packaging specification and performance requirements of part 178 of this subchapter at the Packing Group III performance level are authorized as follows. The packagings must be designed and constructed to prevent movement of the articles and inadvertent operation.

(1) 1A2, 1B2, 1G or 1H2 drums.

(2) 3A2 or 3H2 jerricans.

(3) 4C1, 4C2, 4D, 4F, 4G or 4H2 boxes.

(4) Reusable high strength plastic or metal containers or dedicated handling devices are authorized for shipment of air bag inflators, air bag modules, and seat-belt pretensioners from a manufacturing facility to the assembly facility, subject to the following conditions:

(i) The gross weight of the container or handling device may not exceed 1000 kg (2205 pounds). The container or handling device structure must provide adequate support to allow them to be

stacked at least three high with no damage to the containers or devices.

(ii) If not completely enclosed by design, the container or handling device must be covered with plastic, fiberboard, or metal. The covering must be secured to the container by banding or other comparable methods.

(iii) Internal dunnage must be sufficient to prevent shifting of the devices within the container.

(5) Packagings specified in the approval document issued by the Associate Administrator in accordance with paragraph (e) of this section are also authorized.

(f) *Labeling.* Notwithstanding the provisions of § 172.402 of this subchapter, each package or handling device must display a CLASS 9 label. Additional labeling is not required when the package contains no hazardous materials other than the devices.

[Amdt. 173-230, 57 FR 1878, Jan. 16, 1992, as amended by Amdt. 173-241, 59 FR 67509, Dec. 29, 1994; Amdt. 173-261, 62 FR 24733, May 6, 1997; 62 FR 51560, Oct. 1, 1997; 64 FR 10778, Mar. 5, 1999; 65 FR 50461, Aug. 18, 2000; 65 FR 58629, Sept. 29, 2000; 66 FR 8647, Feb. 1, 2001; 66 FR 45183, 45379, Aug. 28, 2001; 68 FR 45034, July 31, 2003; 68 FR 57632, Oct. 6, 2003; 68 FR 61941, Oct. 30, 2003; 71 FR 54395, Sept. 14, 2006; 71 FR 78632, Dec. 29, 2006]

#### § 173.168 Chemical oxygen generators.

An oxygen generator, chemical (defined in § 171.8 of this subchapter) may be transported only under the following conditions:

(a) *Approval.* A chemical oxygen generator that is shipped with a means of initiation attached must be classed and approved by the Associate Administrator in accordance with the procedures specified in § 173.56 of this subchapter.

(b) *Impact resistance.* A chemical oxygen generator, without any packaging, must be capable of withstanding a 1.8 meter drop onto a rigid, non-resilient, flat and horizontal surface, in the position most likely to cause actuation or loss of contents.

(c) *Protection against inadvertent actuation.* A chemical oxygen generator must incorporate one of the following means of preventing inadvertent actuation:

(1) A chemical oxygen generator that is not installed in protective breathing equipment (PBE):

(i) Mechanically actuated devices:

(A) Two pins, installed so that each is independently capable of preventing the actuator from striking the primer;

(B) One pin and one retaining ring, each installed so that each is independently capable of preventing the actuator from striking the primer; or

(C) A cover securely installed over the primer and a pin installed so as to prevent the actuator from striking the primer and cover.

(ii) Electrically actuated devices: The electrical leads must be mechanically shorted and the mechanical short must be shielded in metal foil.

(iii) Devices with a primer but no actuator: A chemical oxygen generator that has a primer but no actuating mechanism must have a protective cover over the primer to prevent actuation from external impact.

(2) A chemical oxygen generator installed in a PBE must contain a pin installed so as to prevent the actuator from striking the primer, and be placed in a protective bag, pouch, case or cover such that the protective breathing equipment is fully enclosed in such a manner that the protective bag, pouch, case or cover prevents unintentional actuation of the oxygen generator.

(d) *Packaging.* A chemical oxygen generator and a chemical oxygen generator installed in equipment, (e.g., a PBE) must be placed in a rigid outer packaging that—

(1) Conforms to the requirements of either:

(i) Part 178, subparts L and M, of this subchapter at the Packing Group I or II performance level; or

(ii) The performance criteria in Air Transport Association (ATA) Specification No. 300 for a Category I Shipping Container.

(2) After September 30, 2009, with its contents, is capable of meeting the following additional requirements when transported by cargo-only aircraft:

(i) The Flame Penetration Resistance Test in Appendix E to part 178 of this subchapter;

(A) At least three specimens of the outer packaging materials must be tested;

(B) Each test must be conducted on a flat 16 inch x 24 inch test specimen mounted in the horizontal ceiling position of the test apparatus to represent the outer packaging design;

(C) Testing must be conducted on all design features (latches, seams, hinges, etc.) affecting the ability of the outer packaging to safely prevent the passage of fire in the horizontal ceiling position; and

(D) There must be no flame penetration of any specimen within 5 minutes after application of the flame source, and the maximum allowable temperature at a point 4 inches above the test specimen, centered over the burner cone, must not exceed 205 °C (400 °F).

(ii) The Thermal Resistance Test specified in Appendix D to part 178 of this subchapter.

(iii) None of the following conditions may occur when one generator in the package is actuated:

(A) Actuation of other generators in the package;

(B) Ignition of the packaging materials; and

(C) A temperature above 100 °C (212 °F) on the outside surface temperature of the package.

(iv) All features of the packaging must be in good condition, including all latches, hinges, seams, and other features, and the packaging must be free from perforations, cracks, dents, or other abrasions that may negatively affect the flame penetration resistance and thermal resistance characteristics of the packaging, verified by a visual inspection of the package before each shipment.

(e) *Equipment marking.* The outside surface of a chemical oxygen generator must be marked to indicate the presence of an oxygen generator (e.g., “oxygen generator, chemical”). The outside surface of equipment containing a chemical oxygen generator that is not readily apparent (e.g., a sealed passenger service unit) must be clearly marked to indicate the presence of the oxygen generator (example: “Oxygen Generator Inside”).

(f) *Items forbidden in air transportation.* (1) A chemical oxygen generator

is forbidden for transportation on board a passenger-carrying aircraft.

(2) A chemical oxygen generator is forbidden for transportation by both passenger-carrying and cargo-only aircraft after:

- (i) The manufacturer's expiration date; or
- (ii) The contents of the generator have been expended.

[72 FR 4455, Jan. 31, 2007, as amended at 72 FR 55097, Sept. 28, 2007]

#### § 173.170 Black powder for small arms.

Black powder for small arms that has been classed in Division 1.1 may be reclassified as a Division 4.1 material, for domestic transportation by motor vehicle, rail freight, and cargo vessel only, subject to the following conditions:

(a) The powder must be examined and approved for Division 1.1 and Division 4.1 classification in accordance with §§ 173.56 and 173.58;

(b) The total quantity of black powder in one motor vehicle, rail car, or freight container may not exceed 45.4 kg (100 pounds) net mass, and no more than four freight containers may be on board one cargo vessel;

(c) The black powder must be packed in inner metal or heavy wall conductive plastic receptacles not over 454 g (16 ounces) net capacity each, with no more than 25 cans in one outer UN 4G fiberboard box. The inner packagings must be arranged and protected so as to prevent simultaneous ignition of the contents. The complete package must be of the same type which has been examined as required in § 173.56;

(d) Each completed package must be marked "BLACK POWDER FOR SMALL ARMS" and "NA 0027"; and

(e) Each package must bear the FLAMMABLE SOLID label.

[Amdt. 173-255, 61 FR 50626, Sept. 26, 1996, as amended at Amdt. 173-255, 62 FR 14338, Mar. 26, 1997]

#### § 173.171 Smokeless powder for small arms.

Smokeless powder for small arms which has been classed in Division 1.3 may be reclassified in Division 4.1, for transportation by motor vehicle, rail car, vessel, or cargo-only aircraft, subject to the following conditions:

(a) The powder must be examined and approved for a Division 1.3 and Division 4.1 classification in accordance with §§ 173.56 and 173.58 of this part.

(b) The total quantity of smokeless powder may not exceed 45.4 kg (100 pounds) net mass in:

(1) One rail car, motor vehicle, or cargo-only aircraft; or

(2) One freight container on a vessel, not to exceed four freight containers per vessel.

(c) Only combination packagings with inner packagings not exceeding 3.6 kg (8 pounds) net mass are authorized. Inner packagings must be arranged and protected so as to prevent simultaneous ignition of the contents. The complete package must be of the same type which has been examined as required in § 173.56 of this part.

(d) Inside packages that have been examined and approved by the Associate Administrator may be packaged in UN 4G fiberboard boxes meeting the Packing Group I performance level, provided all inside containers are packed to prevent shifting and the net weight of smokeless powder in any one box does not exceed 7.3 kg (16 pounds).

[Amdt. 173-224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; Amdt. 173-241, 59 FR 67509, Dec. 29, 1994; Amdt. 173-253, 61 FR 27174, May 30, 1996; 66 FR 45379, Aug. 28, 2001; 68 FR 61941, Oct. 30, 2003]

#### § 173.172 Aircraft hydraulic power unit fuel tank.

Aircraft hydraulic power unit fuel tanks containing a mixture of anhydrous hydrazine and monomethyl hydrazine (M86 fuel) and designed for installation as complete units in aircraft are excepted from the specification packaging requirements of this subchapter when they conform to either of the following conditions:

(a) The unit must consist of an aluminum pressure vessel made from tubing and having welded heads. Primary containment of the fuel within this vessel must consist of a welded aluminum bladder having a maximum internal volume of 46 L (12 gallons). The outer vessel must have a minimum design gauge pressure of 1,275 kPa (185 psig) and a minimum burst gauge pressure of 2,755 kPa (400 psig). Each vessel

## § 173.173

must be leak-checked during manufacture and before shipment and must be found leakproof. The complete inner unit must be securely packed in non-combustible cushioning material, such as vermiculite, in a strong outer tightly closed metal packaging which will adequately protect all fittings. Maximum quantity of fuel per unit and package is 42 L (11 gallons); or

(b) The unit must consist of an aluminum pressure vessel. Primary containment of the fuel within this vessel must consist of a welded hermetically sealed fuel compartment with an elastomeric bladder having a maximum internal volume of 46 L (12 gallons). The pressure vessel must have a minimum design gauge pressure of 5,170 kPa (750 psig). Each vessel must be leak-checked during manufacture and before shipment and must be securely packed in non-combustible cushioning material, such as vermiculite, in a strong outer tightly closed metal packaging which will adequately protect all fittings. Maximum quantity of fuel per unit and package is 42 L (11 gallons).

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended by 66 FR 45380]

## § 173.173 Paint, paint-related material, adhesives, ink and resins.

(a) When the § 172.101 table specifies that a hazardous material be packaged under this section, the following requirements apply. Except as otherwise provided in this part, the description “Paint” is the proper shipping name for paint, lacquer, enamel, stain, shellac, varnish, liquid aluminum, liquid bronze, liquid gold, liquid wood filler, and liquid lacquer base. The description “Paint-related material” is the proper shipping name for a paint thinning, drying, reducing or removing compound. However, if a more specific description is listed in the § 172.101 table of this subchapter, that description must be used.

(b) Paint, paint-related material, adhesives, ink and resins must be packaged as follows:

(1) As prescribed in § 173.202 of this part if it is a Packing Group II material or § 173.203 of this part if it is a Packing Group III material; or

(2) In inner glass packagings of not over 1 L (0.3 gallon) capacity each or

## 49 CFR Ch. I (10–1–08 Edition)

inner metal packagings of not over 5 L (1 gallon) each, packed in a strong outer packaging. Packages must conform to the packaging requirements of subpart B of this part but need not conform to the requirements of part 178 of this subchapter.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; Amdt. 173–241, 59 FR 67509, Dec. 29, 1994]

## § 173.174 Refrigerating machines.

A refrigerating machine assembled for shipment and containing 7 kg (15 pounds) or less of a flammable liquid for its operation in a strong, tight receptacle is excepted from labeling (except when offered for transportation or transported by air) and the specification packaging requirements of this subchapter. In addition, shipments are not subject to subpart F of part 172 of this subchapter (Placarding), to part 174 of this subchapter (Carriage by rail) except § 174.24 (Shipping papers) and to part 177 (Carriage by highway) of this subchapter except § 177.817 (Shipping papers).

## § 173.181 Pyrophoric materials (liquids).

When the § 172.101 table specifies that a hazardous material be packaged under this section, only the following non-bulk packagings are authorized:

(a) Specification steel or nickel cylinders prescribed for any compressed gas except acetylene having a minimum design pressure of 1206 kPa (175 psig). Cylinders with valves must be:

(1) Equipped with steel valve protection caps or collars, unless overpacked; or

(2) Overpacked in a wooden box (4C1, 4C2, 4D or 4F); fiberboard box (4G), or plastic box (4H1 or 4H2). Cylinders must be secured to prevent shifting in the box and, when offered for transportation or transported, must be so loaded that pressure relief devices remain in the vapor space of the cylinder. (See § 177.838(h) of this subchapter.)

(b) Wooden boxes (4C1, 4C2, 4D, or 4F) or fiberboard boxes (4G) enclosing not more than four strong, tight metal cans with inner receptacles of glass or

metal, not over 1 L (0.3 gallon) capacity each, having positive screwcap closures adequately gasketed. Inner packagings must be cushioned on all sides with dry, absorbent, incombustible material in a quantity sufficient to absorb the entire contents. The strong, tight metal cans must be closed by positive means, not by friction.

(c) Steel drums (1A2) or fiber drums (1G) not exceeding 220 L (58 gallons) capacity each with strong tight inner metal cans not over 4.0 L (1 gallon) capacity each, closed by positive means, not friction.

(1) Inner packagings must have no opening exceeding 25 mm (1 inch) diameter and must be surrounded with noncombustible cushioning material.

(2) Net quantity of pyrophoric liquids may not exceed two-thirds of the rated capacity of the outer drum. For example, a 220 L (58 gallons) outer drum may contain no more than 147 L (39 gallons) of pyrophoric liquids.

(3) Each layer of inner containers must be separated by a metal plate separator in addition to cushioning material.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66270, Dec. 20, 1991; 65 FR 58629, Sept. 29, 2000; 66 FR 45183, 45380, Aug. 28, 2001; 68 FR 24660, May 8, 2003; 68 FR 61941, Oct. 30, 2003]

#### **§ 173.182 Barium azide—50 percent or more water wet.**

Barium azide—50 percent or more water wet, must be packed in wooden boxes (4C1, 4C2, 4D, or 4F) or fiber drums (1G) with inner glass packagings not over 0.5 kg (1.1 pounds) capacity each. Packagings must have rubber stoppers wire tied for securement. If transportation is to take place when and where freezing weather is possible, a suitable antifreeze solution must be used to prevent freezing. Each packaging must conform to the requirements of part 178 of this subchapter at the Packing Group I performance level.

#### **§ 173.183 Nitrocellulose base film.**

Films, nitrocellulose base, must be packaged in packagings conforming to the requirements of part 178 of this subchapter at the Packing Group III performance level, as follows:

(a) In steel drums (1A2), aluminum drums (1B2), steel jerricans (3A2), wooden (4C1, 4C2), plywood (4D) or reconstituted wood (4F) boxes or plywood drums (1D) with each reel in a tightly closed metal can, polypropylene canister, or strong cardboard or fiberboard inner packaging with cover held in place by adhesive tape or paper; or

(b) In fiberboard (4G) boxes or fiber drums (1G) with a single tightly closed metal can, polypropylene canister, or strong cardboard or fiberboard inner packaging with cover held in place by adhesive tape or paper; authorized only for not over 600 m (1969 feet) of film.

[Amdt. 173–224, 55 FR 52643 Dec. 21, 1990, as amended by Amdt. 173–255, 61 FR 50627, Sept. 26, 1996]

#### **§ 173.184 Highway or rail fusee.**

(a) A fusee is a device designed to burn at a controlled rate and to produce visual effects for signaling purposes. The composition of the fusee must be such that the fusee will not ignite spontaneously or undergo marked decomposition when subjected to a temperature of 75 °C (167 °F) for 48 consecutive hours.

(b) Fusees (highway and railway) must be packaged in steel drums (1A2), steel jerricans (3A2), wooden (4C1, 4C2), plywood (4D) or reconstituted wood (4F) boxes or in fiberboard boxes (4G), plywood (1D) or fiber (1G) drums. If the fusees are equipped with spikes packagings must have reinforced ends to prevent penetration of spikes through the outer packagings; packages must be capable of passing drop test requirements (§ 178.603 of this subchapter), including at least one drop with spike in a downward position, and other requirements of part 178 of this subchapter, at the Packing Group II performance level.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 66 FR 45379]

#### **§ 173.185 Lithium cells and batteries.**

(a) *Cells and batteries.* A lithium cell or battery, including a lithium polymer cell or battery and a lithium-ion cell or battery, must conform to all of the following requirements:

(1) Be of a type proven to meet the requirements of each test in the UN



Manual of Tests and Criteria (IBR; see § 171.7 of this subchapter). A cell or battery and equipment containing a cell or battery that was first transported prior to January 1, 2006 and is of a type proven to meet the criteria of Class 9 by testing in accordance with the tests in the UN Manual of Tests and Criteria, Third Revised Edition, 1999, need not be retested.

(2) Incorporate a safety venting device or otherwise be designed in a manner that will preclude a violent rupture under conditions normally incident to transportation.

(3) Be equipped with an effective means to prevent dangerous reverse current flow (e.g., diodes, fuses, etc.) if a battery contains cells or series of cells that are connected in parallel.

(4) Be packaged in combination packagings conforming to the requirements of part 178, subparts L and M, of this subchapter at the Packing Group II performance level. The lithium battery or cell must be packed in inner packagings in such a manner as to prevent short circuits, including movement which could lead to short circuits. The inner packaging must be packed within one of the following outer packagings: metal boxes (4A or 4B); wooden boxes (4C1, 4C2, 4D, or 4F); fiberboard boxes (4G); solid plastic boxes (4H2); fiber drums (1G); metal drums (1A2 or 1B2); plywood drums (1D); plastic jerricans (3H2); or metal jerricans (3A2 or 3B2).

(5) Be equipped with an effective means of preventing external short circuits.

(6) Except as provided in paragraph (d) of this section, cells and batteries with a liquid cathode containing sulfur dioxide, sulfur chloride or thionyl chloride may not be offered for transportation or transported if any cell has been discharged to the extent that the open circuit voltage is less than two volts or is less than 2/3 of the voltage of the fully charged cell, whichever is less.

(b) *Lithium cells or batteries packed with equipment.* Lithium cells or batteries packed with equipment may be transported as Class 9 materials if the batteries and cells meet all the requirements of paragraph (a) of this section. The equipment and the packages of cells or batteries must be further

packed in a strong outer packaging. The cells or batteries must be packed in such a manner as to prevent short circuits, including movement that could lead to short circuits.

(c) *Lithium cells or batteries contained in equipment.* Lithium cells or batteries contained in equipment may be transported as Class 9 materials if the cells and batteries meet all the requirements of paragraph (a) of this section, except paragraph (a)(4) of this section, and the equipment is packed in a strong outer packaging that is waterproof or is made waterproof through the use of a liner unless the equipment is made waterproof by nature of its construction. The equipment and cells or batteries must be secured within the outer packaging and be packed so as to prevent movement, short circuits, and accidental operation during transport.

(d) *Cells and batteries, for disposal or recycling.* A lithium cell or battery offered for transportation or transported by motor vehicle to a permitted storage facility, disposal site or for purposes of recycling is excepted from the specification packaging requirements of paragraph (a)(4) of this section and the requirements of paragraphs (a)(1) and (a)(6) of this section when protected against short circuits and packed in a strong outer packaging conforming to the requirements of §§ 173.24 and 173.24a.

(e) *Shipments for testing (prototypes).* A lithium cell or battery is excepted from the requirements of (a)(1) of this section when transported by motor vehicle for purposes of testing. The cell or battery must be individually packed in an inner packaging, surrounded by cushioning material that is non-combustible and nonconductive. The cell or battery must be transported as a Class 9 material.

(f) A lithium cell or battery that does not comply with the provisions of this subchapter may be transported only under conditions approved by the Associate Administrator.

(g) Batteries employing a strong, impact-resistant outer casing and exceeding a gross weight of 12 kg (26.5 lbs.), and assemblies of such batteries, may be packed in strong outer packagings, in protective enclosures (for example, in fully enclosed wooden slatted crates)

or on pallets. Batteries must be secured to prevent inadvertent movement, and the terminals may not support the weight of other superimposed elements. Batteries packaged in this manner are not permitted for transportation by passenger aircraft, and may be transported by cargo aircraft only if approved by the Associate Administrator prior to transportation.

[72 FR 44949, Aug. 9, 2007]

#### § 173.186 Matches.

(a) Matches must be of a type which will not ignite spontaneously or undergo marked decomposition when subjected for 8 consecutive hours to a temperature of 93 °C (200 °F).

(b) *Definitions.* (1) *Fusee matches* are matches the heads of which are prepared with a friction-sensitive igniter composition and a pyrotechnic composition which burns with little or no flame, but with intense heat.

(2) *Safety matches* are matches combined with or attached to the box, book or card that can be ignited by friction only on a prepared surface.

(3) *Strike anywhere matches* are matches that can be ignited by friction on a solid surface.

(4) *Wax "Vesta" matches* are matches that can be ignited by friction either on a prepared surface or on a solid surface.

(c) Safety matches and wax "Vesta" matches must be tightly packed in securely closed inner packagings to prevent accidental ignition under conditions normally incident to transportation, and further packed in outer fiberboard, wooden, or other equivalent-type packagings. These matches in outer packagings not exceeding 23 kg (50 pounds) gross weight are not subject to any other requirement (except marking) of this subchapter. These matches may be packed in the same outer packaging with materials not subject to this subchapter.

(d) Strike-anywhere matches may not be packed in the same outer packaging with any material other than safety matches or wax "Vesta" matches, which must be packed in separate inner packagings.

(e) Packagings. Strike-anywhere matches must be tightly packed in securely closed chipboard, fiberboard,

wooden, or metal inner packagings to prevent accidental ignition under conditions normally incident to transportation. Each inner packaging may contain no more than 700 strike-anywhere matches and must be packed in outer steel drums (1A2), aluminum drums (1B2), steel jerricans (3A2), wooden (4C1, 4C2), plywood (4D), reconstituted wood (4F) or fiberboard (4G) boxes, plywood (1D) or fiber (1G) drums. Gross weight of fiberboard boxes (4G) must not exceed 30 kg (66 pounds). Gross weight of other outer packagings must not exceed 45 kg (100 pounds).

[Amdt. 173-224, 55 FR 52643, Dec. 21, 1990, as amended at 69 FR 76157, Dec. 20, 2004]

#### § 173.187 Pyrophoric solids, metals or alloys, n.o.s.

Packagings for pyrophoric solids, metals, or alloys, n.o.s. must conform to the requirements of part 178 of this subchapter at the packing group performance level specified in the §172.101 Table. These materials must be packaged as follows:

(a) In steel boxes (4A) and contain not more than 15 kg (33 pounds) each.

(b) In wooden boxes (4C1, 4C2, 4D, or 4F) with inner metal receptacles which have a positive (not friction) means of closure and contain not more than 15 kg (33 pounds) each.

(c) In fiberboard boxes (4G) with inner metal receptacles which have a positive (not friction) means of closure and contain not more than 7.5 kg (17 pounds) each.

(d) In steel drums (1A1 or 1A2) with a gross mass not exceeding 150 kg (331 pounds) per drum.

(e) In plywood drums (1D) with inner metal receptacles which have a positive (not friction) means of closure and contain not more than 15 kg (33 pounds) each.

(f) In fiber drums (1G) with inner metal receptacles which have a positive (not friction) means of closure and contain not more than 15 kg (33 pounds) each.

(g) In specification cylinders, as prescribed for any compressed gas, except for Specifications 8 and 3HT.

[71 FR 78632, Dec. 29, 2006]

**§ 173.188 White or yellow phosphorus.**

Phosphorus, white or yellow, when offered for transportation or transported by rail, highway, or water, must be packaged in water or dry in packagings conforming to the requirements of part 178 of this subchapter at the Packing Group I performance level, as follows:

(a) When placed in water, it must be packaged in specification packagings as follows:

(1) Wooden boxes (4C1, 4C2, 4D, or 4F) with:

(i) Inner hermetically sealed (soldered) metal cans, enclosed in other hermetically sealed (soldered) metal cans, or

(ii) Inner water-tight metal cans containing not over 0.5 kg (1 pound) of phosphorus with screw-top closures; or

(2) Steel drums (1A1) not over 250 L (66 gallons) capacity each or steel drums (1A2) not over 115 L (30 gallons) capacity each.

(b) When dry, it must be cast solid and shipped in packagings as follows:

(1) Steel drums (1A2) not over 115 L (30 gallons) capacity each, or

(2) In projectiles or bombs when shipped by, for, or to the Departments of the Army, Navy, or Air Force of the United States Government, without bursting elements.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66271, Dec. 20, 1991]

**§ 173.189 Batteries containing sodium or cells containing sodium.**

(a) Batteries and cells may not contain any hazardous material other than sodium, sulfur or polysulfides. Cells not forming a component of a completed battery may not be offered for transportation at a temperature at which any liquid sodium is present in the cell. Batteries may only be offered for transportation, or transported, at a temperature at which any liquid sodium present in the battery conforms to the conditions prescribed in paragraph (d) of this section.

(b) Cells must consist of hermetically sealed metal casings which fully enclose the hazardous materials and which are so constructed and closed as to prevent the release of the hazardous materials under normal conditions of transport. Cells must be placed in suit-

able outer packagings with sufficient cushioning material to prevent contact between cells and between cells and the internal surfaces of the outer packaging, and to ensure that no dangerous shifting of the cells within the outer packaging occurs in transport. Cells must be packaged in 1A2, 1B2, 1D, 1G, 1H2, 4C1, 4C2, 4D, 4F, 4G or 4H2 outer packagings which meet the requirements of part 178 of this subchapter at the Packing Group II performance level.

(c) Batteries must consist of cells secured within, and fully enclosed by a metal casing so constructed and closed as to prevent the release of the hazardous materials under normal conditions of transport. Batteries may be offered for transportation, and transported, unpacked or in protective packagings that are not subject to the requirements of part 178 of this subchapter.

(d) Batteries containing any liquid sodium may not be offered for transportation, or transported, by aircraft. Batteries containing liquid sodium may be transported by motor vehicle, rail car or vessel under the following conditions:

(1) Batteries must be equipped with an effective means of preventing external short circuits, such as by providing complete electrical insulation of battery terminals or other external electrical connectors. Battery terminals or other electrical connectors penetrating the heat insulation fitted in battery casings must be provided with thermal insulation sufficient to prevent the temperature of the exposed surfaces of such devices from exceeding 55 °C (130 °F).

(2) No battery may be offered for transportation if the temperature at any point on the external surface of the battery exceeds 55 °C (130 °F).

(3) If any external source of heating is used during transportation to maintain sodium in batteries in a molten state, means must be provided to ensure that the internal temperature of the battery does not reach or exceed 400 °C (752 °F).

(4) When loaded in a transport vehicle or freight container:

(i) Batteries must be secured so as to prevent significant shifting within the

transport vehicle or freight container under conditions normally incident to transportation;

(ii) Adequate ventilation and/or separation between batteries must be provided to ensure that the temperature at any point on the external surface of the battery casing will not exceed 240 °C (464 °F) during transportation; and

(iii) No other hazardous materials, with the exception of cells containing sodium, may be loaded in the same transport vehicle or freight container. Batteries must be separated from all other freight by a distance of not less than 0.5 m (1.6 feet).

(e) Batteries containing sodium or cells containing sodium, when installed as part of a motor vehicle, are not subject to the requirements of this subchapter.

[Amdt. 173-241, 59 FR 67511, Dec. 29, 1994, as amended by Amdt. 173-256, 61 FR 51338, Oct. 1, 1996; 66 FR 45380, Aug. 28, 2001; 68 FR 61941, Oct. 30, 2003]

#### § 173.192 Packaging for certain toxic gases in Hazard Zone A.

When § 172.101 of this subchapter specifies a toxic material must be packaged under this section, only the following cylinders are authorized:

(a) Specification 3A1800, 3AA1800, 3AL1800, 3E1800, or seamless UN cylinders with a minimum test pressure in accordance with P200 of the UN Recommendations (IBR, see § 171.7 of this subchapter).

(1) Specification 3A, 3AA, or 3AL cylinders may not exceed 57 kg (125 lb) water capacity (nominal).

(2) Specification 3AL cylinders may only be offered for transportation or transported by highway and rail.

(b) Packagings must conform to the requirements of § 173.40.

(c) For cylinders used for phosgene:

(1) The filling density may not exceed 125 percent;

(2) A cylinder may not contain more than 68 kg (150 lb) of phosgene; and

(3) Each cylinder containing phosgene must be tested for leakage before it is offered for transportation or transported and must show no leakage. The leakage test must consist of immersing the cylinder and valve, without the protective cap attached, in a bath of water at a temperature of ap-

proximately 66 °C (150 °F) for at least 30 minutes, during which time frequent examinations must be made to note any escape of gas. The valve of the cylinder may not be loosened after this test. Suitable safeguards must be provided to protect personnel and facilities should failure occur during the test. As an alternative, each cylinder containing phosgene may be tested for leakage by a method approved in writing by the Associate Administrator.

[67 FR 51643, Aug. 8, 2002, as amended at 71 FR 33880, June 12, 2006]

#### § 173.193 Bromoacetone, methyl bromide, chloropicrin and methyl bromide or methyl chloride mixtures, etc.

(a) Bromoacetone must be packaged as follows in wooden boxes (4C1, 4C2, 4D or 4F) with inner glass receptacles or tubes in hermetically sealed metal receptacles in corrugated fiberboard cartons. Bottles may not contain over 500 g (17.6 ounces) of liquid each and must be cushioned in cans with at least 12.7 mm (0.5 inch) of absorbent material. Total amount of liquid in the outer box must not exceed 11 kg (24 pounds). Packagings must conform to the requirements of part 178 of this subchapter at the Packing Group I performance level.

(b) Bromoacetone, methyl bromide, chloropicrin and methyl bromide mixtures, chloropicrin and methyl chloride mixtures, and chloropicrin mixtures charged with non-flammable, non-liquefied compressed gas must be packed in Specification 3A, 3AA, 3B, 3C, 3E, 4A, 4B, 4BA, 4BW, or 4C cylinders having not over 113 kg (250 pounds) water capacity (nominal). This capacity does not apply to shipments of methyl bromide.

(c) Methyl bromide mixtures containing up to 2% chloropicrin must be packaged in 4G fiberboard boxes with inside metal cans containing not over one pound each, or inside metal cans with a minimum wall thickness of 0.007 inch containing not over 1¾ pounds each. The one-pound can must be capable of withstanding an internal pressure of 130 psig without leakage or permanent distortion. Vapor pressure of the contents must not exceed 130 psig at 55 °C (130 °F). The 1¾-pound can

## § 173.194

must be capable of withstanding an internal pressure of 140 psig without leakage or permanent distortion. Vapor pressure of the contents must not exceed 140 psig at 55 °C (130 °F). Cans must not be liquid full at 130 °F. Cans must be constructed of tinplate or lined with suitable material and must have concave or pressure ends.

(d) Cylinders, except those containing methyl bromide, must conform to § 173.40 of this part.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66271, Dec. 20, 1991; 57 FR 45463, Oct. 1, 1992]

### § 173.194 Gas identification sets.

Gas identification sets containing poisonous material must be packaged in packagings conforming to the requirements of part 178 of this subchapter at the Packing Group I performance level, as follows:

(a) In glass inner receptacles, hermetically sealed, of not over 40 mL (1.4 fluid ounces) each. Each glass inner receptacle must in turn be placed in a sealed fiberboard receptacle, cushioned with absorbent material. Not more than 12 fiberboard receptacles must in turn be placed in a 4G fiberboard box. No more than four boxes, well-cushioned, may in turn be placed in a steel cylinder. The cylinder must have a wall thickness of at least 3.7 mm (0.146 inch) and must have a hermetically sealed steel closure.

(b) When the poisonous material is absorbed in a medium such as activated charcoal or silical gel, gas identification sets may be shipped as follows:

(1) If the poisonous material does not exceed 5 mL (0.2 fluid ounce) if a liquid or 5 g (0.2 ounce) if a solid, it may be packed in glass inner receptacles of not over 120 mL (4.1 fluid ounces) each. Each glass receptacle, cushioned with absorbent material must be packed in a hermetically sealed metal can of not less than 0.30 mm (0.012 inch) wall thickness. Metal cans, surrounded on all sides by at least 25 mm (1 inch) of dry sawdust, must be packed in 4C1, 4C2, 4D or 4F wooden boxes. Not more than 100 mL (3.4 fluid ounces) or 100 g (3.5 ounces) of poisonous materials may be packed in one outer wooden box.

(2) If the poisonous material does not exceed 5 mL (0.2 fluid ounce) if a liquid

## 49 CFR Ch. I (10–1–08 Edition)

or 20 g (0.7 ounce) if a solid, it may be packed in glass inner receptacles with screw-top closures of not less than 60 mL (2 ounces), hermetically sealed. Twelve bottles containing poisonous material, not to exceed 100 mL (3.4 ounces) or 100 g (3.5 ounces), or both, may be placed in a plastic carrying case, each glass receptacle surrounded by absorbent cushioning and each separated from the other by sponge rubber partitions. The plastic carrying case must be placed in a tightly fitting fiberboard box which in turn must be placed in a tightly fitting 4C1, 4C2, 4D or 4F wooden box.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 66 FR 45183, 45381, Aug. 28, 2001]

### § 173.195 Hydrogen cyanide, anhydrous, stabilized (hydrocyanic acid, aqueous solution).

(a) Hydrogen cyanide, anhydrous, stabilized, must be packed in specification cylinders or UN pressure receptacles as follows:

(1) As prescribed in § 173.192;

(2) Specification 3A480, 3A480X, 3AA480, or 3A1800 metal cylinders of not over 126 kg (278 pounds) water capacity (nominal);

(3) Shipments in 3AL cylinders are authorized only when transported by highway and rail; or

(4) UN cylinders, as specified in part 178, with a minimum test pressure of 100 bar and a maximum filling ratio of 0.55. The use of UN tubes and MEGCs is not authorized.

(b) Cylinders may not be charged with more than 0.27 kg (0.6 pound) of liquid per 0.45 kg (1 pound) water capacity of cylinder. Each filled cylinder must be tested for leakage before being offered for transportation or transported and must show absolutely no leakage; this test must consist of passing a piece of Guignard's sodium picrate paper over the closure of the cylinder, without the protection cap attached, to detect any escape of hydrogen cyanide from the cylinder. Other equally efficient test methods may be used in place of sodium picrate paper.

(c) Packagings for hydrogen cyanide must conform to § 173.40.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66271, Dec. 20, 1991; 71 FR 33880, June 12, 2006]

**§ 173.196 Category A infectious substances.**

(a) *Category A infectious substances packaging.* A packaging for a Division 6.2 material that is a Category A infectious substance must meet the test standards of § 178.609 of this subchapter and must be marked in conformance with § 178.503(f) of this subchapter. A packaging for a Category A infectious substance is a triple packaging consisting of the following components:

- (1) A watertight primary receptacle.
- (2) A watertight secondary packaging. If multiple fragile primary receptacles are placed in a single secondary packaging, they must be either wrapped individually or separated to prevent contact between them.
- (3) A rigid outer packaging of adequate strength for its capacity, mass and intended use. The outer packaging must measure not less than 100 mm (3.9 inches) at its smallest overall external dimension.
- (4) For a liquid infectious substance, an absorbent material placed between the primary receptacle and the secondary packaging. The absorbent material must be sufficient to absorb the entire contents of all primary receptacles.
- (5) An itemized list of contents enclosed between the secondary packaging and the outer packaging.
- (6) The primary receptacle or secondary packaging used for infectious substances must be capable of withstanding, without leakage, an internal pressure producing a pressure differential of not less than 95 kPa (0.95 bar, 14 psi).
- (7) The primary receptacle or secondary packaging used for infectious substances must be capable of withstanding without leakage temperatures in the range of  $-40^{\circ}\text{C}$  to  $+55^{\circ}\text{C}$  ( $-40^{\circ}\text{F}$  to  $+131^{\circ}\text{F}$ ).

(b) *Additional requirements for packaging Category A infectious substances.* Category A infectious substances must be packaged according to the following requirements, depending on the physical state and other characteristics of the material.

(1) *Infectious substances shipped at ambient temperatures or higher.* Primary receptacles must be made of glass, metal, or plastic. Positive means of ensuring a

leakproof seal must be provided, such as heat seal, skirted stopper, or metal crimp seal. If screw caps are used, they must be secured by positive means, such as with adhesive tape, paraffin sealing tape, or manufactured locking closure. Lyophilized substances may also be transported in primary receptacles that are flame-sealed with glass ampoules or rubber-stoppered glass vials fitted with metal seals.

(2) *Infectious substances shipped refrigerated or frozen (ice, pre-frozen packs, dry ice).* Ice, dry ice, or other refrigerant must be placed around the secondary packagings or in an overpack with one or more complete packages marked in accordance with § 178.503 of this subchapter. Interior supports must be provided to secure the secondary packagings in the original position after the ice or dry ice has dissipated. If ice is used, the outer packaging or overpack must be leakproof. If dry ice is used, the outer packaging or overpack must permit the release of carbon dioxide gas and otherwise meet the provisions in § 173.217. The primary receptacle and the secondary packaging must maintain their integrity at the temperature of the refrigerant used, as well as the temperatures and pressures of transport by aircraft to which they could be subjected if refrigeration were lost.

(3) *Infectious substances shipped in liquid nitrogen.* The primary receptacle and the secondary packaging must maintain their integrity at the temperature of the liquid nitrogen as well as the temperatures and pressures of transport by aircraft to which they could be subjected if refrigeration were lost. Refrigerated liquid nitrogen packagings must be metal vacuum insulated vessels or flasks vented to the atmosphere to prevent any increase in pressure within the packaging. The use of safety relief valves, check valves, frangible discs, or similar devices in the vent lines is prohibited. Fill and discharge openings must be protected against the entry of foreign materials that might cause an increase in the internal pressure. The package orientation markings specified in § 172.312(a) of this subchapter must be marked on the

packaging. The packaging must be designed to prevent the release of any refrigerated liquid nitrogen irrespective of the packaging orientation.

(c) Live animals may not be used to transport infectious substances unless such substances cannot be sent by any other means. An animal containing or contaminated with an infectious substance must be transported under terms and conditions approved by the Associate Administrator for Hazardous Materials Safety.

(d) Body parts, organs or whole bodies meeting the definition of Division 6.2 material must be packaged as follows:

(1) In Division 6.2 packaging, as specified in paragraphs (a) and (b) of this section; or

(2) In packaging meeting the requirements of § 173.197.

[67 FR 53140, Aug. 14, 2002, as amended at 71 FR 32260, June 2, 2006]

#### § 173.197 Regulated medical waste.

(a) *General provisions.* Non-bulk packagings, Large Packagings, and non-specification bulk outer packagings used for the transportation of regulated medical waste or clinical waste or (bio) medical waste must be rigid containers meeting the provisions of subpart B of this part.

(b) *Non-bulk packagings.* Except as provided in § 173.134(c) of this subpart, non-bulk packagings for regulated medical waste or clinical waste or (bio) medical waste must be UN standard packagings conforming to the requirements of Part 178 of this subchapter at the Packing Group II performance level. A non-bulk packaging used as a sharps container must be puncture-resistant for sharps and sharps with residual fluid as demonstrated by conducting the performance tests in Part 178, subpart M, of this subchapter on packagings containing materials representative of the sharps and fluids (such as sterile sharps) intended to be transported in the packagings. Sharps containers must be securely closed to prevent leaks or punctures in conformance with the instructions provided by the packaging manufacturer in accordance with § 178.2(c) of this subchapter.

(c) *Large Packagings.* Large Packagings constructed, tested, and marked

in accordance with the requirements of the UN Recommendations (IBR, see § 171.7 of this subchapter) and conforming to other requirements of this paragraph (c) may be used for the transportation of regulated medical waste, provided the waste is contained in inner packagings conforming to the requirements of paragraph (e) of this section. Each Large Packaging design must be capable of meeting the vibration test specified in § 178.819 of this subchapter. Each Large Packaging is subject to the periodic design requalification requirements for IBCs in § 178.801(e) of this subchapter, and to the proof of compliance requirements of § 178.801(j) and record retention requirements of § 178.801(l) of this subchapter. Inner packagings used for liquids must be rigid.

(1) *Authorized packagings.* Only the following Large Packagings are authorized for the transportation of liquid or solid regulated medical waste:

(i) Metal: 50A, 50B, or 50N.

(ii) Rigid plastic: 50H.

(2) *Additional requirements.* Each Large Packaging used to transport liquid regulated medical waste must contain absorbent material in sufficient quantity and appropriate location to absorb the entire amount of liquid present in the event of an unintentional release of contents. Each Large Packaging design intended for the transportation of sharps containers must be puncture resistant and capable of retaining liquids. The design must also be tested and certified as meeting the performance tests specified for intermediate bulk containers intended for the transportation of liquids in subpart O of part 178 of this subchapter.

(d) *Non-specification bulk packaging.* A wheeled cart (Cart) or bulk outer packaging (BOP) is authorized as an outer packaging for the transportation of regulated medical waste in accordance with the provisions of this paragraph (d).

(1) *General requirements.* The following requirements apply to the transportation of regulated medical waste in Carts or BOPs:

(i) Regulated medical waste in each Cart or BOP must be contained in non-bulk inner packagings conforming to paragraph (e) of this section.

(ii) Each Cart or BOP must have smooth, non-porous interior surfaces free of cracks, crevices, and other defects that could damage plastic film inner packagings or impede disinfection operations.

(iii) Except as otherwise provided in this paragraph (d), each Cart or BOP must be used exclusively for the transportation of regulated medical waste. Prior to reuse, each Cart or BOP must be disinfected by any means effective for neutralizing the infectious substance the packaging previously contained.

(iv) Untreated concentrated stock cultures of infectious substances containing Category A materials may not be transported in a Cart or BOP.

(v) Division 6.1 toxic waste or Class 7 radioactive waste, with the exception of chemotherapeutic waste, may not be transported in a Cart or BOP.

(vi) Division 6.1 or Class 7 chemotherapeutic waste; untreated concentrated stock cultures of infectious substances containing Category B infectious substances; unabsorbed liquids; and sharps containers may be transported in a Cart or BOP only if packaged in rigid non-bulk packagings conforming to paragraph (a) of this section.

(2) *Wheeled cart (Cart).* A Cart is authorized as an outer packaging for the transportation of regulated medical waste if it conforms to the following requirements:

(i) Each Cart must consist of a solid, one-piece body with a nominal volume not exceeding 1,655 L (437 gallons).

(ii) Each Cart must be constructed of metal, rigid plastic, or fiberglass fitted with a lid to prevent leakage during transport.

(iii) Each Cart must be capable of meeting the requirements of §178.810 (drop test) at the Packing Group II performance level.

(iv) Inner packagings must be placed into a Cart and restrained in such a manner as to minimize the risk of breakage.

(3) *Bulk outer packaging (BOP).* A BOP is authorized as an outer packaging for regulated medical waste if it conforms to the following requirements:

(i) Each BOP must be constructed of metal or fiberglass and have a capacity

of at least 3.5 cubic meters (123.6 cubic feet) and not more than 45 cubic meters (1,590 cubic feet).

(ii) Each BOP must have bottom and side joints of fully welded or seamless construction and a rigid, weatherproof top to prevent the intrusion of water (e.g., rain or snow).

(iii) Each opening in a BOP must be fitted with a closure to prevent the intrusion of water or the release of any liquid during all loading, unloading, and transportation operations.

(iv) In the upright position, each BOP must be leakproof and able to contain a liquid quantity of at least 300 liters (79.2 gallons) with closures open.

(v) Inner packagings must be placed in a BOP in such a manner as to minimize the risk of breakage. Rigid inner packagings may not be placed in the same BOP with plastic film bag inner packagings unless separated from each other by rigid barriers or dividers to prevent damage to the packagings caused by load shifting during normal conditions of transportation.

(vi) Division 6.1 or Class 7 chemotherapeutic waste, untreated concentrated stock cultures of infectious substances containing Category B infectious substances, unabsorbed liquids, and sharps may be transported in a BOP only if separated and secured as required in paragraph (d)(3)(v) of this section.

(e) *Inner packagings authorized for Large Packagings, Carts, and BOPs.* After September 30, 2003, inner packagings must be durably marked or tagged with the name and location (city and state) of the offeror, except when the entire contents of the Large Packaging, Cart, or BOP originates at a single location and is delivered to a single location.

(1) *Solids.* A plastic film bag is authorized as an inner packaging for solid regulated medical waste transported in a Cart, Large Packaging, or BOP. Waste material containing absorbed liquid may be packaged as a solid in a plastic film bag if the bag contains sufficient absorbent material to absorb and retain all liquid during transportation.

(i) The film bag may not exceed a volume of 175 L (46 gallons). The film bag must be marked and certified by



its manufacturer as having passed the tests prescribed for tear resistance in ASTM D 1922, “Standard Test Method for Propagation Tear Resistance of Plastic Film and Thin Sheeting by Pendulum Method” (IBR, § 171.7 of this subchapter) and for impact resistance in ASTM D 1709, “Standard Test Methods for Impact Resistance of Plastic Film by the Free-Falling Dart Method” (IBR, § 171.7 of this subchapter). The film bag must meet an impact resistance of 165 grams and a tearing resistance of 480 grams in both the parallel and perpendicular planes with respect to the length of the bag.

(ii) The plastic film bag must be closed with a minimum of entrapped air to prevent leakage in transportation. The bag must be capable of being held in an inverted position with the closed end at the bottom for a period of 5 minutes without leakage.

(iii) When used as an inner packaging for Carts or BOPs, a plastic film bag may not weigh more than 10 kg (22 lbs.) when filled.

(2) *Liquids.* Liquid regulated medical waste or clinical waste or (bio) medical waste transported in a Large Packaging, Cart, or BOP must be packaged in a rigid inner packaging conforming to the provisions of subpart B of this part, conforming to the provisions of subpart B of this part. Liquid materials are not authorized for transportation in inner packagings having a capacity greater than 19 L (5 gallons).

(3) *Sharps.* Sharps transported in a Large Packaging, Cart, or BOP must be packaged in a puncture-resistant inner packaging (sharps container). Each sharps container must be securely closed to prevent leaks or punctures in conformance with instructions provided by the packaging manufacturer. Each sharps container exceeding 76 L (20 gallons) in volume must be capable of passing the performance tests in Part 178, subpart M, of this subchapter at the Packing Group II performance level. A sharps container may be reused only if it conforms to the following criteria:

(i) The sharps container is specifically approved and certified by the U.S. Food and Drug Administration as a medical device for reuse.

(ii) The sharps container must be permanently marked for reuse.

(iii) The sharps container must be disinfected prior to reuse by any means effective for the infectious substance the container previously contained.

(iv) The sharps container must have a capacity greater than 7.57 L (2 gallons) and not greater than 151.42 L (40 gallons) in volume.

[67 FR 53140, Aug. 14, 2002, as amended at 68 FR 57632, Oct. 6, 2003; 68 FR 75744, Dec. 31, 2003; 71 FR 32261, June 2, 2006; 71 FR 78632, Dec. 29, 2006]

**§ 173.198 Nickel carbonyl.**

(a) Nickel carbonyl must be packed in specification steel or nickel cylinders as prescribed for any compressed gas except acetylene. A cylinder used exclusively for nickel carbonyl may be given a complete external visual inspection instead of the pressure test required by § 180.205 of this subchapter. Visual inspection must be in accordance with CGA Pamphlet C–6 (IBR, see § 171.7 of this subchapter).

(b) Packagings for nickel carbonyl must conform to § 173.40.

[Amdt. 173–224, 55 FR 52643, Dec 21, 1990, as amended at 67 FR 51643, Aug. 8, 2002; 68 FR 75742, Dec. 31, 2003]

**§ 173.199 Category B infectious substances.**

(a) *Category B infectious substances.* Except as provided in this paragraph (a), Category B infectious substances are excepted from all other requirements of this subchapter when offered for transportation or transported in accordance with this section. Category B infectious substances offered for transportation or transported under the provisions of this section are subject to the incident reporting requirements in §§ 171.15 and 171.16 of this subchapter and to the requirements in § 175.75(b) of this subchapter concerning cargo location. Except as provided in paragraph (a)(9) of this section, a Category B infectious substance meeting the definition of a hazard class other than Division 6.2 must be offered for transportation or transported in accordance with applicable requirements of this subchapter.

(1) A Category B infectious substance must be packaged in a triple packaging


consisting of a primary receptacle, a secondary packaging, and a rigid outer packaging.

(2) Primary receptacles must be packed in secondary packaging in such a way that, under normal conditions of transport, they cannot break, be punctured, or leak their contents into the secondary packaging.

(3) Secondary packagings must be secured in rigid outer packagings with suitable cushioning material such that any leakage of the contents will not impair the protective properties of the cushioning material or the outer packaging.

(4) The completed package must be designed, constructed, maintained, filled, its contents limited, and closed so that under conditions normally encountered in transportation, including removal from a pallet or overpack for subsequent handling, there will be no release of hazardous material into the environment. Package effectiveness must not be substantially reduced for minimum and maximum temperatures, changes in humidity and pressure, and shocks, loadings and vibrations normally encountered during transportation. The packaging must be capable of successfully passing the drop tests in §§178.609(d) and (h) of this subchapter at a drop height of at least 1.2 meters (3.9 feet). Following the drop tests, there must be no leakage from the primary receptacle, which must remain protected by absorbent material, when required, in the secondary packaging. At least one surface of the outer packaging must have a minimum dimension of 100 mm by 100 mm (3.9 inches).

(5) The following mark must be displayed on the outer packaging on a background of contrasting color. The width of the line must be at least 2 mm (0.08 inches) and the letters and numbers must be at least 6 mm (0.24 inches) high. The size of the mark must be such that no side of the diamond is less than 50 mm (1.97 inches) in length. The proper shipping name "Biological substances, Category B" must be marked on the outer packaging adjacent to the diamond-shaped mark in letters that are at least 6 mm (0.24 inches) high.



(6) When packages are placed in an overpack, the package markings required by this section must be either clearly visible or reproduced on the outside of the overpack.

(7) The name and telephone number of a person who is either knowledgeable about the material being shipped and has comprehensive emergency response and incident mitigation information for the material, or has immediate access to a person who possesses such knowledge and information, must be included on a written document (such as an air waybill or bill of lading) or on the outer packaging.

(8) For transportation by aircraft, each package, overpack, pallet, or unit load device containing a Category B infectious substance must be inspected for leakage when it is unloaded from the aircraft. If evidence of leakage is found, the cargo compartment in which the package, overpack, pallet, or unit load device was transported must be disinfected. Disinfection may be by any means that will make the material released ineffective at transmitting disease.

(9) A packaging containing inner packagings of Category B infectious substances may not contain other hazardous materials except—

(i) Refrigerants, such as dry ice or liquid nitrogen, as authorized under paragraph (d) of this section;

(ii) Anticoagulants used to stabilize blood or plasma; or

(iii) Small quantities of Class 3, Class 8, Class 9, or other materials in Packaging Groups II and III used to stabilize

or prevent degradation of the sample, provided the quantity of such materials does not exceed 30 mL (1 ounce) or 30 g (1 ounce) in each inner packaging. Such preservatives are not subject to the requirements of this subchapter.

(10) Clear instructions on filling and closing a packaging used to transport a Category B infectious substance must be provided by the packaging manufacturer and subsequent distributors to the consignor or person who prepares the package to enable the package to be correctly prepared for transport. A copy or electronic image of these instructions must be retained by the manufacturer and subsequent distributors for at least one year from the date of issuance, and made available for inspection by a Federal or state government representative upon request. Packagings must be filled and closed in accordance with the information provided by the packaging manufacturer or subsequent distributor.

(b) *Liquid Category B infectious substances.* Liquid Category B infectious substances must be packaged in conformance with the following provisions:

(1) The primary receptacle must be leakproof.

(2) Absorbent material must be placed between the primary receptacle and secondary packaging. If several fragile primary receptacles are placed in a single secondary packaging, they must be either individually wrapped or separated to prevent contact between them. The absorbent material must be of sufficient quantity to absorb the entire contents of the primary receptacles and not compromise the integrity of the cushioning material or the outer packaging.

(3) The secondary packaging must be leakproof.

(4) For shipments by aircraft, the primary receptacle or the secondary packaging must be capable of withstanding without leakage an internal pressure producing a pressure differential of not less than 95 kPa (0.95 bar, 14 psi).

(5) For shipments by aircraft, the maximum quantity contained in each primary receptacle, including any material used to stabilize or prevent degradation of the sample, may not exceed 1 L (34 ounces), and the maximum

quantity contained in each outer packaging, including any material used to stabilize or prevent degradation of the samples, may not exceed 4 L (1 gallon). The outer packaging limitation does not include ice, dry ice, or liquid nitrogen when used to maintain the integrity of the material.

(c) *Solid Category B infectious substances.* Solid Category B infectious substances must be packaged in a triple packaging, consisting of a primary receptacle, secondary packaging, and outer packaging, conforming to the following provisions:

(1) The primary receptacle must be siftproof.

(2) If several fragile primary receptacles are placed in a single secondary packaging, they must be either individually wrapped or separated to prevent contact between them.

(3) The secondary packaging must be siftproof.

(4) If residual liquid may be present in the primary receptacle during transportation, then the material must be transported in accordance with requirements in paragraph (b) of this section. A solid material that may become liquid during transportation must be transported in accordance with paragraph (b) of this section.

(5) Except for packages containing body parts, organs, or whole bodies, for shipment by aircraft, the outer packaging may not contain more than 4 kg (8.8 pounds), including any material used to stabilize or prevent degradation of the samples. The outer packaging limitation does not include ice, dry ice, or liquid nitrogen when used to maintain the integrity of the material.

(d) *Refrigerated or frozen specimens (ice, dry ice, and liquid nitrogen).* In addition to complying with the requirements in this paragraph (d), dry ice and liquid nitrogen must be offered for transportation or transported in accordance with the applicable requirements of this subchapter.

(1) Ice or dry ice must be placed outside the secondary packaging or in an overpack. Interior supports must be provided to secure the secondary packagings in the original position after the ice or dry ice has dissipated. If ice is used, the outside packaging must be leakproof or must have a leakproof

liner. If dry ice is used, the outside packaging must permit the release of carbon dioxide gas and otherwise meet the provisions in § 173.217. The primary receptacle and secondary packaging must maintain their integrity at the temperature of the refrigerant used, as well as the temperatures and pressures of transport by aircraft they could be subjected to if refrigeration were lost, and sufficient absorbent material must be provided to absorb all liquid, including melted ice.

(2) The package is marked "Carbon dioxide, solid" or "Dry ice" and an indication that the material being refrigerated is used for diagnostic treatment purposes (e.g., frozen medical specimens).

(e) *Training.* Each person who offers or transports a Category B infectious substance under the provisions of this section must know about the requirements of this section.

[67 FR 53142, Aug. 14, 2002, as amended at 71 FR 32261, June 2, 2006; 72 FR 55693, Oct. 1, 2007]

#### **§ 173.201 Non-bulk packagings for liquid hazardous materials in Packing Group I.**

(a) When § 172.101 of this subchapter specifies that a liquid hazardous material be packaged under this section, only non-bulk packagings prescribed in this section may be used for its transportation. Each packaging must conform to the general packaging requirements of subpart B of part 173, to the requirements of part 178 of this subchapter at the Packing Group I performance level, and to the requirements of the special provisions of column 7 of the § 172.101 table.

(b) The following combination packagings are authorized:

##### *Outer packagings:*

Steel drum: 1A1 or 1A2  
 Aluminum drum: 1B1 or 1B2  
 Metal drum other than steel or aluminum: 1N1 or 1N2  
 Plywood drum: 1D  
 Fiber drum: 1G  
 Plastic drum: 1H1 or 1H2  
 Steel jerrican: 3A1 or 3A2  
 Plastic jerrican: 3H1 or 3H2  
 Aluminum jerrican: 3B1 or 3B2  
 Steel box: 4A  
 Aluminum box: 4B  
 Natural wood box: 4C1 or 4C2

Plywood box: 4D  
 Reconstituted wood box: 4F  
 Fiberboard box: 4G  
 Expanded plastic box: 4H1  
 Solid plastic box: 4H2

##### *Inner packagings:*

Glass or earthenware receptacles  
 Plastic receptacles  
 Metal receptacles  
 Glass ampoules

(c) Except for transportation by passenger aircraft, the following single packagings are authorized:

Steel drum: 1A1 or 1A2  
 Aluminum drum: 1B1 or 1B2  
 Metal drum other than steel, or aluminum: 1N1 or 1N2  
 Plastic drum: 1H1 or 1H2  
 Steel jerrican: 3A1 or 3A2  
 Plastic jerrican: 3H1 or 3H2  
 Aluminum jerrican: 3B1 or 3B2  
 Plastic receptacle in steel, aluminum, fiber or plastic drum: 6HA1, 6HB1, 6HG1, 6HH1  
 Plastic receptacle in steel, aluminum, wood, plywood or fiberboard box: 6HA2, 6HB2, 6HC, 6HD2 or 6HG2  
 Glass, porcelain or stoneware in steel, aluminum or fiber drum: 6PA1, 6PB1 or 6PG1  
 Glass, porcelain or stoneware in steel, aluminum, wooden or fiberboard box: 6PA2, 6PB2, 6PC or 6PG2  
 Glass, porcelain or stoneware in solid or expanded plastic packaging: 6PH1 or 6PH2  
 Cylinders, specification or UN standard, as prescribed for any compressed gas, except 3HT and those prescribed for acetylene.

[Amdt. 173-224, 55 FR 52634, Dec. 21, 1990, as amended by Amdt. 173-241, 59 FR 67518, Dec. 29, 1994; Amdt. 173-261, 62 FR 24734, May 6, 1997; 71 FR 33880, June 12, 2006]

#### **§ 173.202 Non-bulk packagings for liquid hazardous materials in Packing Group II.**

(a) When § 172.101 of this subchapter specifies that a liquid hazardous material be packaged under this section, only non-bulk packagings prescribed in this section may be used for its transportation. Each packaging must conform to the general packaging requirements of subpart B of part 173, to the requirements of part 178 of this subchapter at the Packing Group I or II performance level (unless otherwise excepted), and to the particular requirements of the special provisions of column 7 of the § 172.101 table.

(b) The following combination packagings are authorized:

##### *Outer packagings:*

Steel drum: 1A1 or 1A2

## § 173.203

Aluminum drum: 1B1 or 1B2  
Metal drum other than steel or aluminum:  
1N1 or 1N2  
Plywood drum: 1D  
Fiber drum: 1G  
Plastic drum: 1H1 or 1H2  
Wooden barrel: 2C2  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Steel box: 4A  
Aluminum box: 4B  
Natural wood box: 4C1 or 4C2  
Plywood box: 4D  
Reconstituted wood box: 4F  
Fiberboard box: 4G  
Expanded plastic box: 4H1  
Solid plastic box: 4H2

### *Inner packagings:*

Glass or earthenware receptacles  
Plastic receptacles  
Metal receptacles  
Glass ampoules

(c) Except for transportation by passenger aircraft, the following single packagings are authorized:

Steel drum: 1A1 or 1A2  
Aluminum drum: 1B1 or 1B2  
Metal drum other than steel or aluminum:  
1N1 or 1N2  
Plastic drum: 1H1 or 1H2  
Fiber drum: 1G (with liner)  
Wooden barrel: 2C1  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Plastic receptacle in steel, aluminum, fiber or plastic drum: 6HA1, 6HB1, 6HG1 or 6HH1  
Plastic receptacle in steel, aluminum, wood-  
en, plywood or fiberboard box: 6HA2, 6HB2,  
6HC, 6HD2 or 6HG2  
Glass, porcelain or stoneware in steel, alu-  
minum or fiber drum: 6PA1, 6PB1 or 6PG1  
Glass, porcelain or stoneware in steel, alu-  
minum, wooden or fiberboard box: 6PA2,  
6PB2, 6PC or 6PG2  
Glass, porcelain or stoneware in solid or ex-  
panded plastic packaging: 6PH1 or 6PH2  
Plastic receptacle in plywood drum: 6HD1  
Glass, porcelain or stoneware in plywood  
drum or wickerwork hamper: 6PD1 or 6PD2  
Cylinders, specification, as prescribed for  
any compressed gas, except for Specifica-  
tions 8 and 3HT

[Amdt. 173-224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66271, Dec. 20, 1991; Amdt 173-241, 59 FR 67518, Dec. 29, 1994; Amdt. 173-261, 62 FR 24734, May 6, 1997; 62 FR 51560, Oct. 1, 1997]

## 49 CFR Ch. I (10-1-08 Edition)

### § 173.203 Non-bulk packagings for liq- uid hazardous materials in Packing Group III.

(a) When §172.101 of this subchapter specifies that a liquid hazardous mate-  
rial be packaged under this section,  
only non-bulk packagings prescribed in  
this section may be used for its trans-  
portation. Each packaging must con-  
form to the general packaging require-  
ments of subpart B of part 173, to the  
requirements of part 178 of this sub-  
chapter at the Packing Group I, II or  
III performance level, and to the re-  
quirements of the special provisions of  
column 7 of the §172.101 table.

(b) The following combination pack-  
agings are authorized:

### *Outer packagings:*

Steel drum: 1A1 or 1A2  
Aluminum drum: 1B1 or 1B2  
Metal drum other than steel or aluminum:  
1N1 or 1N2  
Plywood drum: 1D  
Fiber drum: 1G  
Plastic drum: 1H1 or 1H2  
Wooden barrel: 2C2  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Steel box: 4A  
Aluminum box: 4B  
Natural wood box: 4C1 or 4C2  
Plywood box: 4D  
Reconstituted wood box: 4F  
Fiberboard box: 4G  
Expanded plastic box: 4H1  
Solid plastic box: 4H2

### *Inner packagings:*

Glass or earthenware receptacles  
Plastic receptacles  
Metal receptacles  
Glass ampoules

(c) The following single packagings  
are authorized:

Steel drum: 1A1 or 1A2  
Aluminum drum: 1B1 or 1B2  
Metal drum other than steel or aluminum:  
1N1  
Plastic drum: 1H1 or 1H2  
Fiber drum: 1G (with liner)  
Wooden barrel: 2C1  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Plastic receptacle in steel, aluminum, fiber  
or plastic drum: 6HA1, 6HB1, 6HG1 or 6HH1  
Plastic receptacle in steel, aluminum, wood-  
en, plywood or fiberboard box: 6HA2, 6HB2,  
6HC, 6HD2 or 6HG2  
Glass, porcelain or stoneware in steel, alu-  
minum or fiber drum: 6PA1, 6PB1, or 6PG1

Glass, porcelain or stoneware in steel, aluminum, wooden or fiberboard box: 6PA2, 6PB2, 6PC or 6PG2

Glass, porcelain or stoneware in solid or expanded plastic packaging: 6PH1 or 6PH2

Plastic receptacle in plywood drum: 6HD1

Glass, porcelain or stoneware in plywood drum or wickerwork hamper: 6PD1 or 6PD2

Cylinders, as prescribed for any compressed gas, except for Specifications 8 and 3HT

[Amdt. 173-224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66271, Dec. 20, 1991; Amdt. 173-241, 59 FR 67518, Dec. 29, 1994; Amdt. 173-261, 62 FR 24734, May 6, 1997]

**§ 173.204 Non-bulk, non-specification packagings for certain hazardous materials.**

When § 172.101 of this subchapter specifies that a liquid or solid hazardous material be packaged under this section, any appropriate non-bulk packaging which conforms to the general packaging requirements of subpart B of part 173 may be used for its transportation. Packagings need not conform to the requirements of part 178 of this subchapter.

**§ 173.205 Specification cylinders for liquid hazardous materials.**

When § 172.101 of this subchapter specifies that a hazardous material must be packaged under this section, the use of any specification or UN cylinder, except those specified for acetylene, is authorized. Cylinders used for toxic materials in Division 6.1 or 2.3 must conform to the requirements of § 173.40.

[71 FR 33881, June 12, 2006]

**§ 173.211 Non-bulk packagings for solid hazardous materials in Packing Group I.**

(a) When § 172.101 of this subchapter specifies that a solid hazardous material be packaged under this section, only non-bulk packagings prescribed in this section may be used for its transportation. Each package must conform to the general packaging requirements of subpart B of part 173, to the requirements of part 178 of this subchapter at the Packing Group I performance level, and to the requirements of the special provisions of column 7 of the § 172.101 table.

(b) The following combination packagings are authorized:

*Outer packagings:*

Steel drum: 1A1 or 1A2

Aluminum drum: 1B1 or 1B2

Metal drum other than steel or aluminum: 1N1 or 1N2

Plywood drum: 1D

Fiber drum: 1G

Plastic drum: 1H1 or 1H2

Wooden barrel: 2C2

Steel jerrican: 3A1 or 3A2

Plastic jerrican: 3H1 or 3H2

Aluminum jerrican: 3B1 or 3B2

Steel box: 4A

Aluminum box: 4B

Natural wood box: 4C1 or 4C2

Plywood box: 4D

Reconstituted wood box: 4F

Fiberboard box: 4G

Solid plastic box: 4H2

*Inner packagings:*

Glass or earthenware receptacles

Plastic receptacles

Metal receptacles

Glass ampoules

(c) Except for transportation by passenger aircraft, the following single packagings are authorized:

Steel drum: 1A1 or 1A2

Aluminum drum: 1B1 or 1B2

Metal drum other than steel or aluminum: 1N1 or 1N2

Plastic drum: 1H1 or 1H2

Fiber drum: 1G

Steel jerrican: 3A1 or 3A2

Plastic jerrican: 3H1 or 3H2

Aluminum jerrican: 3B1 or 3B2

Steel box with liner: 4A

Aluminum box with liner: 4B

Natural wood box, sift proof: 4C2

Plastic receptacle in steel, aluminum, plywood, fiber or plastic drum: 6HA1, 6HB1, 6HD1, 6HG1 or 6HH1

Glass, porcelain or stoneware in steel, aluminum, plywood or fiber drum: 6PA1, 6PB1, 6PD1 or 6PG1

Glass, porcelain or stoneware in steel, aluminum, wooden or fiberboard box: 6PA2, 6PB2, 6PC or 6PG2

Glass, porcelain or stoneware in expanded or solid plastic packaging: 6PH1 or 6PH2

Cylinders, as prescribed for any compressed gas, except for Specification 8 and 3HT

[Amdt. 173-224, 55 FR 52643, Dec. 21, 1990, as amended at 56 FR 66271, Dec. 20, 1991; 57 FR 45463, Oct. 1, 1992; Amdt. 173-241, 59 FR 67511, 67518, Dec. 29, 1994; Amdt. 173-261, 62 FR 24734, May 6, 1997; 69 FR 76157, Dec. 20, 2004]

**§ 173.212 Non-bulk packagings for solid hazardous materials in Packing Group II.**

(a) When § 172.101 of this subchapter specifies that a solid hazardous material be packaged under this section,

## § 173.213

only non-bulk packagings prescribed in this section may be used for its transportation. Each package must conform to the general packaging requirements of subpart B of part 173, to the requirements of part 178 of this subchapter at the Packing Group I or II performance level, and to the requirements of the special provisions of column 7 of the §172.101 table.

(b) The following combination packagings are authorized:

*Outer packagings:*

Steel drum: 1A1 or 1A2  
Aluminum drum: 1B1 or 1B2  
Metal drum other than steel or aluminum:  
1N1 or 1N2  
Plywood drum: 1D  
Fiber drum: 1G  
Plastic drum: 1H1 or 1H2  
Wooden barrel: 2C2  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Steel box: 4A  
Aluminum box: 4B  
Natural wood box: 4C1 or 4C2  
Plywood box: 4D  
Reconstituted wood box: 4F  
Fiberboard box: 4G  
Solid plastic box: 4H2

*Inner packagings:*

Glass or earthenware receptacles  
Plastic receptacles  
Metal receptacles  
Glass ampoules

(c) Except for transportation by passenger aircraft, the following single packagings are authorized:

Steel drum: 1A1 or 1A2  
Aluminum drum: 1B1 or 1B2  
Plywood drum: 1D  
Plastic drum: 1H1 or 1H2  
Fiber drum: 1G  
Metal drum other than steel or aluminum:  
1N1 or 1N2  
Wooden barrel: 2C1 or 2C2  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Steel box: 4A  
Steel box with liner: 4A  
Aluminum box: 4B  
Aluminum box with liner: 4B  
Natural wood box: 4C1  
Natural wood box, sift proof: 4C2  
Plywood box: 4D  
Reconstituted wood box: 4F  
Fiberboard box: 4G  
Expanded plastic box: 4H1  
Solid plastic box: 4H2  
Bag, woven plastic: 5H1, 5H2 or 5H3  
Bag, plastic film: 5H4

## 49 CFR Ch. I (10–1–08 Edition)

Bag, textile: 5L1, 5L2 or 5L3  
Bag, paper, multiwall, water resistant: 5M2  
Plastic receptacle in steel, aluminum, plywood, fiber or plastic drum: 6HA1, 6HB1, 6HD1, 6HG1 or 6HH1  
Plastic receptacle in steel, aluminum, wood, plywood or fiberboard box: 6HA2, 6HB2, 6HC, 6HD2 or 6HG2  
Glass, porcelain or stoneware in steel, aluminum, plywood or fiber drum: 6PA1, 6PB1, 6PD1 or 6PG1  
Glass, porcelain or stoneware in steel, aluminum, wooden or fiberboard box: 6PA2, 6PB2, 6PC or 6PG2  
Glass, porcelain or stoneware in expanded or solid plastic packaging: 6PH1 or 6PH2  
Cylinders, as prescribed for any compressed gas, except for Specification 8 and 3HT

[Amdt. 173–224, 55 FR 52634, Dec. 21, 1990, as amended by Amdt. 173–241, 59 FR 67511, 67518, Dec. 29, 1994; Amdt. 173–261, 62 FR 24734, May 6, 1997; 69 FR 76157, Dec. 20, 2004; 70 FR 34398, June 14, 2005]

### § 173.213 Non-bulk packagings for solid hazardous materials in Packing Group III.

(a) When §172.101 of this subchapter specifies that a solid hazardous material be packaged under this section, only non-bulk packagings prescribed in this section may be used for its transportation. Each package must conform to the general packaging requirements of subpart B of part 173, to the requirements of part 178 of this subchapter at the Packing Group I, II or III performance level, and to the requirements of the special provisions of column 7 of the §172.101 table.

(b) The following combination packagings are authorized:

*Outer packagings:*

Steel drum: 1A1 or 1A2  
Aluminum drum: 1B1 or 1B2  
Metal drum other than steel or aluminum:  
1N1 or 1N2  
Plywood drum: 1D  
Fiber drum: 1G  
Plastic drum: 1H1 or 1H2  
Wooden barrel: 2C2  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Steel box: 4A  
Aluminum box: 4B  
Natural wood box: 4C1 or 4C2  
Plywood box: 4D  
Reconstituted wood box: 4F  
Fiberboard box: 4G  
Solid plastic box: 4H2

*Inner packagings:*

Glass or earthenware receptacles

Plastic receptacles  
Metal receptacles  
Glass ampoules

(c) The following single packagings are authorized:

Steel drum: 1A1 or 1A2  
Aluminum drum: 1B1 or 1B2  
Plywood drum: 1D  
Plastic drum: 1H1 or 1H2  
Fiber drum: 1G  
Metal drum other than steel or aluminum: 1N1 or 1N2  
Wooden barrel: 2C1 or 2C2  
Steel jerrican: 3A1 or 3A2  
Plastic jerrican: 3H1 or 3H2  
Aluminum jerrican: 3B1 or 3B2  
Steel box: 4A  
Steel box with liner: 4A  
Aluminum box: 4B  
Aluminum box with liner: 4B  
Natural wood box: 4C1  
Natural wood box, sift proof: 4C2  
Plywood box: 4D  
Reconstituted wood box: 4F  
Fiberboard box: 4G  
Expanded plastic box: 4H1  
Solid plastic box: 4H2  
Bag, woven plastic: 5H1, 5H2 or 5H3  
Bag, plastic film: 5H4  
Bag, textile: 5L1, 5L2 or 5L3  
Bag, paper, multiwall, water resistant: 5M2  
Plastic receptacle in steel, aluminum, plywood, fiber or plastic drum: 6HA1, 6HB1, 6HD1, 6HG1 or 6HH1  
Plastic receptacle in steel, aluminum, wood, plywood or fiberboard box: 6HA2, 6HB2, 6HC, 6HD2 or 6HG2  
Glass, porcelain or stoneware in steel, aluminum, plywood or fiber drum: 6PA1, 6PB1, 6PD1 or 6PG1  
Glass, porcelain or stoneware in steel, aluminum, wooden or fiberboard box: 6PA2, 6PB2, 6PC or 6PG2  
Glass, porcelain or stoneware in expanded or solid plastic packaging: 6PH1 or 6PH2  
Cylinders, as prescribed for any compressed gas, except for Specification 8 and 3HT

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended by Amdt. 173–241, 59 FR 67511, 67518, Dec. 29, 1994; Amdt. 173–261, 62 FR 24734, May 6, 1997; 69 FR 76158, Dec. 20, 2004; 70 FR 34398, June 14, 2005]

**§ 173.214 Packagings which require approval by the Associate Administrator.**

When § 172.101 of this subchapter specifies that a hazardous material be packaged under this section, packagings and method of shipment must be approved by the Associate Administrator prior to the first shipment.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 66 FR 45379, Aug. 28, 2001]

**§ 173.216 Asbestos, blue, brown or white.**

(a) Asbestos, blue, brown or white, includes each of the following hydrated mineral silicates: chrysolite, crocidolite, amosite, anthophyllite asbestos, tremolite asbestos, actinolite asbestos, and every product containing any of these materials.

(b) [Reserved]

(c) Packagings for asbestos must conform to the general packaging requirements of subpart B of this part but need not conform to the requirements of part 178 of this subchapter. Asbestos must be offered for transportation and transported in—

(1) Rigid, leaktight packagings, such as metal, plastic or fiber drums, portable tanks, hopper-type rail cars, or hopper-type motor vehicles;

(2) Bags or other non-rigid packagings in closed freight containers, motor vehicles, or rail cars that are loaded by and for the exclusive use of the consignor and unloaded by the consignee;

(3) Bags or other non-rigid packagings which are dust and sift proof must be placed in rigid outer packagings or closed freight containers.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 66 FR 45379, Aug. 28, 2001; 68 FR 45034, July 31, 2003; 71 CFR 78632, Dec. 29, 2006]

**§ 173.217 Carbon dioxide, solid (dry ice).**

(a) Carbon dioxide, solid (dry ice), when offered for transportation or transported by aircraft or water, must be packed in packagings designed and constructed to permit the release of carbon dioxide gas to prevent a buildup of pressure that could rupture the packagings. Packagings must conform to the general packaging requirements of subpart B of this part but need not conform to the requirements of part 178 of this subchapter.

(b) For transportation by vessel:

(1) Each transport vehicle and freight container containing solid carbon dioxide must be conspicuously marked on two sides “WARNING CO<sub>2</sub> SOLID (DRY ICE).”



## § 173.218

(2) Other packagings containing solid carbon dioxide must be marked “CARBON DIOXIDE, SOLID—DO NOT STOW BELOW DECKS.”

(c) For transportation by aircraft:

(1) In addition to the applicable marking requirements in subpart D of part 172, the net mass of the carbon dioxide, solid (dry ice) must be marked on the outside of the package. This provision also applies to unit load devices (ULDs) when the ULD contains dry ice and is considered the packaging.

(2) The shipper must make arrangements with the operator for each shipment.

(3) The quantity limits per package shown in Columns (9A) and (9B) of the Hazardous Materials Table in § 172.101 are not applicable to dry ice being used as a refrigerant for other than hazardous materials loaded in a unit load device or other type of pallet. In such a case, the unit load device or other type of pallet must allow the venting of the carbon dioxide gas to prevent a dangerous build up of pressure, and be identified to the operator.

(4) Dry ice is excepted from the shipping paper requirements of subpart C of part 172 of this subchapter provided alternative written documentation is supplied containing the following information: proper shipping name (Dry ice or Carbon dioxide, solid), class 9, UN number 1845, the number of packages, and the net quantity of dry ice in each package. The information must be included with the description of the materials.

(5) Carbon dioxide, solid (dry ice), in quantities not exceeding 2.5 kg (5.5 pounds) per package and used as a refrigerant for the contents of the package is excepted from all other requirements of this subchapter if the requirements of paragraph (a) of this section are complied with and the package is marked “Carbon dioxide, solid” or “Dry ice”, is marked with the name of the contents being cooled, and is marked with the net weight of the dry ice or an indication that the net weight is 2.5 kg (5.5 pounds) or less.

(d) Carbon dioxide, solid (dry ice), when used to refrigerate materials being shipped for diagnostic or treatment purposes (e.g., frozen medical

## 49 CFR Ch. I (10–1–08 Edition)

specimens), is excepted from the shipping paper and certification requirements of this subchapter if the requirements of paragraphs (a) and (c)(2) of this section are met and the package is marked “Carbon dioxide, solid” or “Dry ice” and is marked with an indication that the material being refrigerated is being transported for diagnostic or treatment purposes.

[73 FR 4718, Jan. 28, 2008]

### § 173.218 Fish meal or fish scrap.

(a) Except as provided in Column (7) of the HMT in § 172.101 of this subchapter, fish meal or fish scrap, containing at least 6%, but not more than 12% water, is authorized for transportation by vessel only when packaged as follows:

- (1) Burlap (jute) bag;
  - (2) Multi-wall paper bag;
  - (3) Polyethylene-lined burlap or paper bag;
  - (4) Cargo tank;
  - (5) Portable tank;
  - (6) Rail car; or
  - (7) Freight container.
- (b) [Reserved]

(c) When fish scrap or fish meal is offered for transportation by vessel in bulk in freight containers, the fish meal must contain at least 100 ppm of anti-oxidant (ethoxyquin) at the time of shipment.

[Amdt. 173–224, 55 FR 52643, Dec. 21, 1990, as amended at 68 FR 45034, July 31, 2003]

### § 173.219 Life-saving appliances.

(a) A life-saving appliance, self-inflating or non-self-inflating, containing small quantities of hazardous materials that are required as part of the life-saving appliance must conform to the requirements of this section. Packagings must conform to the general packaging requirements of subpart B of this part but need not conform to the requirements of part 178 of this subchapter. The appliances must be packed, so that they cannot be accidentally activated and, except for life vests, the hazardous materials must be in inner packagings packed so as to prevent shifting within the outer packaging. The hazardous materials must be an integral part of the appliance and in quantities that do not exceed those

appropriate for the actual appliance when in use.

(b) Life saving appliances may contain:

(1) Division 2.2 compressed gases, including oxygen. However, oxygen generators are not permitted;

(2) Signal devices (Class 1), which may include smoke and illumination signal flares;

(3) Electric storage batteries and lithium batteries (Life saving appliances containing lithium batteries must be transported in accordance with §173.185, and Special Provisions 188, 189, A101, A103 and A104 as applicable.);

(4) First aid or repair kits conforming to the applicable material and quantity limitations of §173.161 of this subchapter;

(5) Strike-anywhere matches;

(6) For self-inflating life saving appliances only, cartridges power device of Division 1.4S, for purposes of the self-inflating mechanism provided that the quantity of explosives per appliance does not exceed 3.2 g; or

(7) Limited quantities of other hazardous materials.

(c) Hazardous materials in life saving appliances must be packaged as follows:

(1) Division 2.2 compressed gases must be packaged in cylinders in accordance with the requirements of this subchapter;

(2) Signal devices (Class 1) must be in packagings that prevent them from being inadvertently activated;

(3) Strike-anywhere matches must be cushioned to prevent movement or friction in a metal or composition receptacle with a screw-type closure in a manner that prevents them from being inadvertently activated;

(4) Limited quantities of other hazardous materials must be packaged in accordance with the requirements of this subchapter; and

(5) For other than transportation by aircraft, life saving appliances containing no hazardous materials other than carbon dioxide cylinders with a capacity not exceeding 100 cm<sup>3</sup> are not subject to the provisions of this subchapter provided they are overpacked

in rigid outer packagings with a maximum gross mass of 40 kg.

[69 FR 76158, Dec. 20, 2004, as amended at 72 FR 44950, Aug. 9, 2007; 73 FR 57006, Oct. 1, 2008]

**§ 173.220 Internal combustion engines, self-propelled vehicles, mechanical equipment containing internal combustion engines, and battery powered vehicles or equipment.**

(a) *Applicability.* An internal combustion engine, self-propelled vehicle, mechanized equipment containing an internal combustion engine, or a battery powered vehicle or equipment is subject to the requirements of this subchapter when transported as cargo on a transport vehicle, vessel, or aircraft if—

(1) The engine or fuel tank contains a liquid or gaseous fuel. An engine may be considered as not containing fuel when the fuel tank, engine components, and fuel lines have been completely drained, sufficiently cleaned of residue, and purged of vapors to remove any potential hazard and the engine when held in any orientation will not release any liquid fuel;

(2) It is equipped with a wet electric storage battery other than a non-spillable battery, or with a sodium or lithium battery; or

(3) Except as provided in paragraph (e)(1) of this section, it contains other hazardous materials subject to the requirements of this subchapter.

(b) *Requirements.* Unless otherwise excepted in paragraph (b)(4) of this section, vehicles, engines and equipment are subject to the following requirements:

(1) *Flammable liquid fuel.* A fuel tank containing a flammable liquid fuel must be drained and securely closed, except that up to 500 mL (17 ounces) of residual fuel may remain in the tank, engine components, or fuel lines provided they are securely closed to prevent leakage of fuel during transportation. Self-propelled vehicles containing diesel fuel are excepted from the requirement to drain the fuel tanks, provided that sufficient ullage space has been left inside the tank to allow fuel expansion without leakage, and the tank caps are securely closed.

(2) *Flammable liquefied or compressed gas fuel.* (i) For transportation by motor vehicle, rail car or vessel, fuel tanks and fuel systems containing flammable liquefied or compressed gas fuel must be securely closed. For transportation by vessel, the requirements of §§ 176.78(k) and 176.905 of this subchapter apply.

(ii) For transportation by aircraft:

(A) Flammable gas-powered vehicles, machines, equipment or cylinders containing the flammable gas must be completely emptied of flammable gas. Lines from vessels to gas regulators, and gas regulators themselves, must also be drained of all traces of flammable gas. To ensure that these conditions are met, gas shut-off valves must be left open and connections of lines to gas regulators must be left disconnected upon delivery of the vehicle to the operator. Shut-off valves must be closed and lines reconnected at gas regulators before loading the vehicle aboard the aircraft; or alternatively

(B) Flammable gas powered vehicles, machines or equipment, which have cylinders (fuel tanks) that are equipped with electrically operated valves, may be transported under the following conditions:

(1) The valves must be in the closed position and in the case of electrically operated valves, power to those valves must be disconnected;

(2) After closing the valves, the vehicle, equipment or machinery must be operated until it stops from lack of fuel before being loaded aboard the aircraft;

(3) In no part of the closed system shall the pressure exceed 5% of the maximum allowable working pressure of the system or 290 psig (2000 kPa), whichever is less; and

(4) There must not be any residual liquefied gas in the system, including the fuel tank.

(3) *Truck bodies or trailers on flat cars—flammable liquid or gas powered.* Truck bodies or trailers with automatic heating or refrigerating equipment of the flammable liquid type may be shipped with fuel tanks filled and equipment operating or inoperative, when used for the transportation of other freight and loaded on flat cars as part of a joint rail and highway movement, provided the equipment and fuel

supply conform to the requirements of § 177.834(l) of this subchapter.

(4) *Modal exceptions.* Quantities of flammable liquid fuel greater than 500 mL (17 ounces) may remain in self-propelled vehicles and mechanical equipment only under the following conditions:

(i) For transportation by motor vehicle or rail car, the fuel tanks must be securely closed.

(ii) For transportation by vessel, the shipment must conform to § 176.905 of this subchapter.

(iii) For transportation by aircraft, when carried in aircraft designed or modified for vehicle ferry operations and when all of the following conditions are met:

(A) Authorization for this type operation has been given by the appropriate authority in the government of the country in which the aircraft is registered;

(B) Each vehicle is secured in an upright position;

(C) Each fuel tank is filled in a manner and only to a degree that will preclude spillage of fuel during loading, unloading, and transportation; and

(D) Each area or compartment in which a self-propelled vehicle is being transported is suitably ventilated to prevent the accumulation of fuel vapors.

(c) *Battery powered or installed.* Batteries must be securely installed, and wet batteries fastened in an upright position. Batteries must be protected against short circuits (e.g., by the use of non-conductive caps that entirely cover the terminals) and leakage or removed and packaged separately under § 173.159. Battery powered vehicles, machinery or equipment including battery powered wheelchairs and mobility aids are excepted from the requirements of this subchapter when transported by rail, highway or vessel.

(d) *Lithium batteries.* Except as provided in § 172.102, Special Provision A101, of this subchapter, vehicles and machinery powered by primary lithium batteries that are transported with these batteries installed are forbidden aboard passenger-carrying aircraft.

Lithium batteries contained in vehicles or engines must be securely fastened in the battery holder of the vehicle or engine, and be protected in such a manner as to prevent damage and short circuits (e.g., by the use of non-conductive caps that entirely cover the terminals). Lithium batteries must be of a type that have successfully passed each test in the UN Manual of Tests and Criteria as specified in §173.185, unless approved by the Associate Administrator. Equipment, other than vehicles or engines, containing lithium batteries must be transported in accordance with §173.185.

(e) *Other hazardous materials.* (1) Items of equipment containing hazardous materials, fire extinguishers, compressed gas accumulators, safety devices and other hazardous materials which are integral components of the motor vehicle, engine or mechanical equipment and are necessary for the operation of the vehicle, engine or equipment, or for the safety of its operator or passengers must be securely installed in the motor vehicle, engine or mechanical equipment. Such items are not otherwise subject to the requirements of this subchapter.

(2) Other hazardous materials must be packaged and transported in accordance with the requirements of this subchapter.

(f) *Additional requirements for internal combustion engines and vehicles with certain electronic equipment when transported by aircraft or vessel.* When an internal combustion engine that is not installed in a vehicle or equipment is offered for transportation by aircraft or vessel, all fuel, coolant or hydraulic systems remaining in the engine must be drained as far as practicable, and all disconnected fluid pipes that previously contained fluid must be sealed with leak-proof caps that are positively retained. When offered for transportation by aircraft, vehicles equipped with theft-protection devices, installed radio communications equipment or navigational systems must have such devices, equipment or systems disabled.

(g) *Exceptions.* Except as provided in paragraph (e)(2) of this section, shipments made under the provisions of this section—

(1) Are not subject to any other requirements of this subchapter, for transportation by motor vehicle or rail car; and

(2) Are not subject to the requirements of subparts D, E and F (marking, labeling and placarding, respectively) of part 172 of this subchapter or §172.604 of this subchapter (emergency response telephone number) for transportation by vessel or aircraft. For transportation by aircraft, all other applicable requirements of this subchapter, including shipping papers, emergency response information, notification of pilot-in-command, general packaging requirements, and the requirements specified in §173.27 must be met. For transportation by vessel, additional exceptions are specified in §176.905 of this subchapter.

[64 FR 10778, Mar. 5, 1999, as amended at 66 45381, Aug. 28, 2001; 68 FR 45035, July 31, 2003; 69 FR 75216, Dec. 15, 2004; 69 FR 76158, Dec. 20, 2004; 70 FR 34398, June 14, 2005; 71 FR 14603, Mar. 22, 2006; 71 FR 78632, Dec. 29, 2006; 72 FR 44950, Aug. 9, 2007]

**§ 173.221 Polymeric beads, expandable and Plastic molding compound.**

(a) Non-bulk shipments of Polymeric beads (or granules), expandable, *evolving flammable vapor* and Plastic molding compound *in dough, sheet or extruded rope form, evolving flammable vapor* must be packed in: wooden (4C1 or 4C2), plywood (4D), fiberboard (4G), reconstituted wood (4F) boxes, plywood drums (1D) or fiber drums (1G) with sealed inner plastic liners; in vapor tight metal or plastic drums (1A1, 1A2, 1B1, 1B2, 1H1 or 1H2); or packed in non-specification packagings when transported in dedicated vehicles or freight containers. The packagings need not conform to the requirements for package testing in part 178 of this subchapter, but must be capable of containing any evolving gases from the contents during normal conditions of transportation.

(b) Bulk shipments of Polymeric beads (or granules), expandable, *evolving flammable vapor* or Plastic molding compounds *in dough, sheet or extruded rope, evolving flammable vapor* may be packed in non-specification bulk packagings. Except for transportation by highway and rail, bulk packagings

## § 173.222

must be capable of containing any gases evolving from the contents during normal conditions of transportation.

[64 FR 10779, Mar. 5, 1999]

### § 173.222 Dangerous goods in machinery or apparatus.

Hazardous materials in machinery or apparatus are excepted from the specification packaging requirements of this subchapter when packaged according to this section. Hazardous materials in machinery or apparatus must be packaged in strong outer packagings, unless the receptacles containing the hazardous materials are afforded adequate protection by the construction of the machinery or apparatus. Each package must conform to the packaging requirements of subpart B of this part, except for the requirements in §§ 173.24(a)(1) and 173.27(e), and the following requirements:

(a) If the machinery or apparatus contains more than one hazardous material, the materials must not be capable of reacting dangerously together.

(b) The nature of the containment must be as follows—

(1) Damage to the receptacles containing the hazardous materials during transport is unlikely. However, in the event of damage to the receptacles containing the hazardous materials, no leakage of the hazardous materials from the machinery or apparatus is possible. A leakproof liner may be used to satisfy this requirement.

(2) Receptacles containing hazardous materials must be secured and cushioned so as to prevent their breakage or leakage and so as to control their movement within the machinery or apparatus during normal conditions of transportation. Cushioning material must not react dangerously with the content of the receptacles. Any leakage of the contents must not substantially impair the protective properties of the cushioning material.

(3) Receptacles for gases, their contents and filling densities must conform to the applicable requirements of this subchapter, unless otherwise approved by the Associate Administrator.

(c) The total net quantity of hazardous materials contained in one item

## 49 CFR Ch. I (10–1–08 Edition)

of machinery or apparatus must not exceed the following:

(1) 1 kg (2.2 pounds) in the case of solids;

(2) 0.5 L (0.1 gallons) in the case of liquids;

(3) 0.5 kg (1.1 pounds) in the case of Division 2.2 gases; and

(4) A total quantity of not more than the aggregate of that permitted in paragraphs (c)(1) through (c)(3) of this section, for each category of material in the package, when a package contains hazardous materials in two or more of the categories in paragraphs (c)(1) through (c)(3) of this section.

(d) Except for transportation by aircraft, when a package contains hazardous materials in two or more of the categories listed in paragraphs (c)(1) through (c)(3) of this section the total quantity required by § 172.202(c) of this subchapter to be entered on the shipping paper must be either the aggregate quantity, or the estimated quantity, of all hazardous materials, expressed as net mass.

[64 FR 10779, Mar. 5, 1999, as amended at 64 FR 44428, Aug. 16, 1999; 66 FR 45379, Aug. 28, 2001; 70 FR 56098, Sept. 23, 2005; 71 FR 78633, Dec. 29, 2006]

### § 173.223 Musk xylene.

(a) Packagings for “Musk xylene” or “5-tert-Butyl-2,4,6-trinitro-m-xylene,” when offered for transportation or transported by rail, highway, or vessel, must conform to the general packaging requirements of subpart B of part 173, and to the requirements of part 178 of this subchapter at the Packing Group III performance level and may only be transported in the following packagings:

(1) Fiberboard box (4G) with a single inner plastic bag, and a maximum net mass of not more than 50 kg (110 lbs).

(2) Fiberboard box (4G) or fiber drum (1G), with a plastic inner packaging not exceeding 5 kg (11 lbs), and a maximum net mass of not more than 25 kg (55 lbs).

(3) Fiber drum (1G), and a maximum net mass of not more than 50 kg (110 lbs), that may be fitted with a coating or lining.

(b) [Reserved]

[Doc. No. 2002–13658, 68 FR 45035, July 31, 2003]

**§ 173.224 Packaging and control and emergency temperatures for self-reactive materials.**

(a) *General.* When the § 172.101 table of this subchapter specifies that a Division 4.1 material be packaged in accordance with this section, only packagings which conform to the provisions of this section may be used. Each packaging must conform to the general packaging requirements of subpart B of this part and the applicable requirements of part 178 of this subchapter. Non-bulk packagings must meet Packing Group II performance levels. To avoid unnecessary confinement, metallic non-bulk packagings meeting Packing Group I are not authorized. Self-reactive materials which require temperature control are subject to the provisions of § 173.21(f). Packagings required to bear a Class 1 subsidiary label must conform to §§ 173.60 through 173.62.

(b) *Self-Reactive Materials Table.* The Self-Reactive Materials Table specifies, by technical name, those self-reactive materials that are authorized for transportation and not subject to the approval provisions of § 173.124(a)(2)(iii). A self-reactive material identified by technical name in the following table is authorized for transportation only if it conforms to all applicable provisions of the table. The column headings of the Self-Reactive Materials Table are as follows:

(1) *Technical name.* Column 1 specifies the technical name.

(2) *ID number.* Column 2 specifies the identification number which is used to

identify the proper shipping name in the § 172.101 table.

(3) *Concentration of self-reactive material.* Column 3 specifies the concentration (percent) limitations, if any, in mixtures or solutions for the self-reactive material. Limitations are given as minimums, maximums, or a range, as appropriate. A range includes the lower and upper limits (i.e., “53–100” means from, and including, 53 percent to, and including 100 percent).

(4) *Packing method.* Column 4 specifies the highest packing method which is authorized for the self-reactive material. A packing method corresponding to a smaller package size may be used, but a packing method corresponding to a larger package size may not be used. The Table of Packing Methods in § 173.225(d) defines the packing methods. Bulk packagings for Type F self-reactive substances are authorized by § 173.225(f) for IBCs and § 173.225(h) for bulk packagings other than IBCs. Additional bulk packagings are authorized if approved by the Associate Administrator.

(5) *Control temperature.* Column 5 specifies the control temperature in °C. Temperatures are specified only when temperature controls are required (see § 173.21(f)).

(6) *Emergency temperature.* Column 6 specifies the emergency temperature in °C. Temperatures are specified only when temperature controls are required (see § 173.21(f)).

(7) *Notes.* Column 7 specifies other applicable provisions, as set forth in notes following the table.

SELF-REACTIVE MATERIALS TABLE

| Self-reactive substance<br>(1)                                | Identification<br>No.<br>(2) | Concentration—<br>(%)<br>(3) | Packing<br>method<br>(4) | Control tem-<br>perature—(°C)<br>(5) | Emergency<br>temperature<br>(6) | Notes<br>(7) |
|---------------------------------------------------------------|------------------------------|------------------------------|--------------------------|--------------------------------------|---------------------------------|--------------|
| Acetone-pyrogallol copolymer 2-diazo-1-naphthol-5-sulphonate. | 3228                         | 100 .....                    | OP8                      | .....                                | .....                           | .....        |
| Azodicarbonamide formulation type B, temperature controlled.  | 3232                         | <100 .....                   | OP5                      | .....                                | .....                           | 1            |
| Azodicarbonamide formulation type C .....                     | 3224                         | <100 .....                   | OP6                      | .....                                | .....                           | .....        |
| Azodicarbonamide formulation type C, temperature controlled.  | 3234                         | <100 .....                   | OP6                      | .....                                | .....                           | 1            |
| Azodicarbonamide formulation type D .....                     | 3226                         | <100 .....                   | OP7                      | .....                                | .....                           | .....        |
| Azodicarbonamide formulation type D, temperature controlled.  | 3236                         | <100 .....                   | OP7                      | .....                                | .....                           | 1            |
| 2,2'-Azodi(2,4-dimethyl-4-methoxyvaleronitrile).              | 3236                         | 100 .....                    | OP7                      | −5 .....                             | +5 .....                        | .....        |
| 2,2'-Azodi(2,4-dimethylvaleronitrile) .....                   | 3236                         | 100 .....                    | OP7                      | +10 .....                            | +15 .....                       | .....        |
| 2,2'-Azodi(ethyl 2-methylpropionate) .....                    | 3235                         | 100 .....                    | OP7                      | +20 .....                            | +25 .....                       | .....        |
| 1,1-Azodi(hexahydrobenzonitrile) .....                        | 3226                         | 100 .....                    | OP7                      | .....                                | .....                           | .....        |

SELF-REACTIVE MATERIALS TABLE—Continued

| Self-reactive substance<br>(1)                                                                                       | Identi-<br>fication<br>No.<br>(2) | Concentration—<br>(%)<br>(3) | Packing<br>method<br>(4) | Control tem-<br>perature—(°C)<br>(5) | Emergency<br>temperature<br>(6) | Notes<br>(7) |
|----------------------------------------------------------------------------------------------------------------------|-----------------------------------|------------------------------|--------------------------|--------------------------------------|---------------------------------|--------------|
| 2,2-Azodi(isobutyronitrile) .....                                                                                    | 3234                              | 100 .....                    | OP6                      | +40 .....                            | +45 .....                       | .....        |
| 2,2'-Azodi(isobutyronitrile) as a water<br>based paste.                                                              | 3224                              | ≤50 .....                    | OP6                      | .....                                | .....                           | .....        |
| 2,2-Azodi(2-methylbutyronitrile) .....                                                                               | 3236                              | 100 .....                    | OP7                      | +35 .....                            | +40 .....                       | .....        |
| Benzene-1,3-disulphonylhydrazide, as a<br>paste.                                                                     | 3226                              | 52 .....                     | OP7                      | .....                                | .....                           | .....        |
| Benzene sulphonylhydrazide .....                                                                                     | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| 4-(Benzyl(ethyl)amino)-3-<br>ethoxybenzenediazonium zinc chloride.                                                   | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| 4-(Benzyl(methyl)amino)-3-<br>ethoxybenzenediazonium zinc chloride.                                                  | 3236                              | 100 .....                    | OP7                      | +40 .....                            | +45 .....                       | .....        |
| 3-Chloro-4-<br>diethylaminobenzenediazonium zinc<br>chloride.                                                        | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| 2-Diazo-1-Naphthol sulphonic acid ester<br>mixture.                                                                  | 3226                              | <100 .....                   | OP7                      | .....                                | .....                           | 4            |
| 2-Diazo-1-Naphthol-4-sulphonyl chloride                                                                              | 3222                              | 100 .....                    | OP5                      | .....                                | .....                           | .....        |
| 2-Diazo-1-Naphthol-5-sulphonyl chloride                                                                              | 3222                              | 100 .....                    | OP5                      | .....                                | .....                           | .....        |
| 2,5-Dibutoxy-4-(4-morpholinyl)-Benzene-<br>diazonium, tetrachlorozincate (2:1).                                      | 3228                              | 100 .....                    | OP8                      | .....                                | .....                           | .....        |
| 2,5-Diethoxy-4-<br>morpholinobenzenediazonium zinc<br>chloride.                                                      | 3236                              | 67–100 .....                 | OP7                      | +35 .....                            | +40 .....                       | .....        |
| 2,5-Diethoxy-4-<br>morpholinobenzenediazonium zinc<br>chloride.                                                      | 3236                              | 66 .....                     | OP7                      | +40 .....                            | +45 .....                       | .....        |
| 2,5-Diethoxy-4-<br>morpholinobenzenediazonium<br>tetrafluoroborate.                                                  | 3236                              | 100 .....                    | OP7                      | +30 .....                            | +35 .....                       | .....        |
| 2,5-Diethoxy-4-<br>(phenylsulphonyl)benzenediazonium<br>zinc chloride.                                               | 3236                              | 67 .....                     | OP7                      | +40 .....                            | +45 .....                       | .....        |
| 2,5-Diethoxy-4-(4-morpholinyl)-benzene-<br>diazonium sulphate.                                                       | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| Diethylene glycol bis(allyl carbonate) +<br>Diisopropylperoxydicarbonate.                                            | 3237                              | ≥88+≤12 .....                | OP8                      | –10 .....                            | 0 .....                         | .....        |
| 2,5-Dimethoxy-4-(4-<br>methylphenylsulphon-<br>y)benzenediazonium zinc chloride.                                     | 3236                              | 79 .....                     | OP7                      | +40 .....                            | +45 .....                       | .....        |
| 4-Dimethylamino-6-(2-<br>dimethylaminoethoxy)toluene-2-diazo-<br>nium zinc chloride.                                 | 3236                              | 100 .....                    | OP7                      | +40 .....                            | +45 .....                       | .....        |
| 4-(Dimethylamino)-benzenediazonium<br>trichlorozincate (-1).                                                         | 3228                              | 100 .....                    | OP8                      | .....                                | .....                           | .....        |
| N,N'-Dinitroso-N, N'-dimethyl-<br>terephthalamide, as a paste.                                                       | 3224                              | 72 .....                     | OP6                      | .....                                | .....                           | .....        |
| N,N'-Dinitrosopentamethylenetetramine ..                                                                             | 3224                              | 82 .....                     | OP6                      | .....                                | .....                           | 2            |
| Diphenyl oxide-4,4'-disulphonylhydrazide .....                                                                       | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| Diphenyl oxide-4,4'-disulphonylhydrazide                                                                             | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| 4-Dipropylaminobenzenediazonium zinc<br>chloride.                                                                    | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| 2-(N,N-Ethoxycarbonylphenylamino)-3-<br>methoxy-4-(N-methyl-N-<br>cyclohexylamino)benzenediazonium<br>zinc chloride. | 3236                              | 63–92 .....                  | OP7                      | +40 .....                            | +45 .....                       | .....        |
| 2-(N,N-Ethoxycarbonylphenylamino)-3-<br>methoxy-4-(N-methyl-N-<br>cyclohexylamino)benzenediazonium<br>zinc chloride. | 3236                              | 62 .....                     | OP7                      | +35 .....                            | +40 .....                       | .....        |
| N-Formyl-2-(nitromethylene)-1,3-<br>perhydrothiazine.                                                                | 3236                              | 100 .....                    | OP7                      | +45 .....                            | +50 .....                       | .....        |
| 2-(2-Hydroxyethoxy)-1-(pyrrolidin-1-<br>yl)benzene-4-diazonium zinc chloride.                                        | 3236                              | 100 .....                    | OP7                      | +45 .....                            | +50 .....                       | .....        |
| 3-(2-Hydroxyethoxy)-4-(pyrrolidin-1-<br>yl)benzenediazonium zinc chloride.                                           | 3236                              | 100 .....                    | OP7                      | +40 .....                            | +45 .....                       | .....        |
| 2-(N,N-Methylaminoethylcarbonyl)-4-(3,4-<br>dimethyl-phenylsulphonyl)benzene dia-<br>zonium zinc chloride.           | 3236                              | 96 .....                     | OP7                      | +45 .....                            | +50 .....                       | .....        |
| 4-Methylbenzenesulphonylhydrazide .....                                                                              | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |

SELF-REACTIVE MATERIALS TABLE—Continued

| Self-reactive substance<br>(1)                                  | Identi-<br>fication<br>No.<br>(2) | Concentration—<br>(%)<br>(3) | Packing<br>method<br>(4) | Control tem-<br>perature—(°C)<br>(5) | Emergency<br>temperature<br>(6) | Notes<br>(7) |
|-----------------------------------------------------------------|-----------------------------------|------------------------------|--------------------------|--------------------------------------|---------------------------------|--------------|
| 3-Methyl-4-(pyrrolidin-1-yl)benzenediazonium tetrafluoroborate. | 3234                              | 95 .....                     | OP6                      | +45 .....                            | +50 .....                       | .....        |
| 4-Nitrosophenol .....                                           | 3236                              | 100 .....                    | OP7                      | +35 .....                            | +40 .....                       | .....        |
| Self-reactive liquid, sample .....                              | 3223                              | .....                        | OP2                      | .....                                | .....                           | 3            |
| Self-reactive liquid, sample, temperature control.              | 3233                              | .....                        | OP2                      | .....                                | .....                           | 3            |
| Self-reactive solid, sample .....                               | 3224                              | .....                        | OP2                      | .....                                | .....                           | 3            |
| Self-reactive solid, sample, temperature control.               | 3234                              | .....                        | OP2                      | .....                                | .....                           | 3            |
| Sodium 2-diazo-1-naphthol-4-sulphonate                          | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| Sodium 2-diazo-1-naphthol-5-sulphonate                          | 3226                              | 100 .....                    | OP7                      | .....                                | .....                           | .....        |
| Tetramine palladium (II) nitrate .....                          | 3234                              | 100 .....                    | OP6                      | +30 .....                            | +35 .....                       | .....        |

NOTES: 1. The emergency and control temperatures must be determined in accordance with § 173.21(f).

2. With a compatible diluent having a boiling point of not less than 150 °C.

3. Samples may only be offered for transportation under the provisions of paragraph(c)(3) of this section.

4. This entry applies to mixtures of esters of 2-diazo-1-naphthol-4-sulphonic acid and 2-diazo-1-naphthol-5-sulphonic acid.

(c) *New self-reactive materials, formulations and samples.* (1) Except as provided for samples in paragraph (c)(3) of this section, no person may offer, accept for transportation, or transport a self-reactive material which is not identified by technical name in the Self-Reactive Materials Table of this section, or a formulation of one or more self-reactive materials which are identified by technical name in the table, unless the self-reactive material is assigned a generic type and shipping description and is approved by the Associate Administrator under the provisions of § 173.124(a)(2)(iii).

(2) Except as provided by an approval issued under § 173.124(a)(2)(iii), intermediate bulk and bulk packagings are not authorized.

(3) *Samples.* Samples of new self-reactive materials or new formulations of self-reactive materials identified in the Self-Reactive Materials Table in paragraph (b) of this section, for which complete test data are not available, and which are to be transported for further testing or product evaluation, may be assigned an appropriate shipping description for Self-reactive materials Type C, packaged and offered for transportation under the following conditions:

(i) Data available to the person offering the material for transportation must indicate that the sample would pose a level of hazard no greater than that of a self-reactive material Type B and that the control temperature, if

any, is sufficiently low to prevent any dangerous decomposition and sufficiently high to prevent any dangerous phase separation;

(ii) The sample must be packaged in accordance with packing method OP2;

(iii) Packages of the self-reactive material may be offered for transportation and transported in a quantity not to exceed 10 kg (22 pounds) per transport vehicle; and

(iv) One of the following shipping descriptions must be assigned:

(A) Self-reactive, liquid, type C, 4.1, UN3223.

(B) Self-reactive, solid, type C, 4.1, UN3224.

(C) Self-reactive, liquid, type C, temperature controlled, 4.1, UN3233.

(D) Self-reactive, solid, type C, temperature controlled, 4.1, UN3234.

[Amdt. 173–241, 59 FR 67511, Dec. 29, 1994, as amended by Amdt. 173–242, 60 FR 26806, May 18, 1995; Amdt. 173–246, 60 FR 49110, Sept. 21, 1995; Amdt. 173–256, 61 FR 51338, Oct. 1, 1996; Amdt. 173–261, 62 FR 24734, 24735, May 6, 1997; 62 FR 45702, Aug. 28, 1997; 64 FR 10779, Mar. 5, 1999; 65 FR 58630, Sept. 29, 2000; 66 FR 33431, June 21, 2001; 66 FR 45379, Aug. 28, 2001; 68 FR 45035, July 31, 2003; 69 FR 76159, Dec. 20, 2004; 71 FR 78633, Dec. 29, 2006]

#### § 173.225 Packaging requirements and other provisions for organic peroxides.

(a) *General.* When the § 172.101 table specifies that an organic peroxide must be packaged under this section, the organic peroxide must be packaged and



offered for transportation in accordance with the provisions of this section. Each packaging must conform to the general requirements of subpart B of part 173 and to the applicable requirements of part 178 of this subchapter. Non-bulk packagings must meet Packing Group II performance levels. To avoid unnecessary confinement, metallic non-bulk packagings meeting Packing Group I are not authorized. No used material, other than production residues or regrind from the same production process, may be used in plastic packagings. Organic peroxides that require temperature control are subject to the provisions of § 173.21(f). When an IBC or bulk packaging is authorized and meets the requirements of paragraph (f) or (h) of this section, respectively, lower control temperatures than those specified for non-bulk packaging may be required. An organic peroxide not identified in paragraph (c), (e), or (g) of this section by technical name, or not assigned to a generic type in accordance with the provisions in paragraph (b)(3) of this section, must conform to the provisions of paragraph (c) of § 173.128.

(b) *New organic peroxides, formulations and samples.* (1) Except as provided for samples in paragraph (b)(2) of this section, no person may offer for transportation an organic peroxide that is not identified by technical name in the Organic Peroxides Table, Organic Peroxide IBC Table, or the Organic Peroxide Portable Tank Table of this section, or a formulation of one or more organic peroxides that are identified by technical name in one of those tables, unless the organic peroxide is assigned a generic type and shipping description and is approved by the Associate Administrator under the provisions of § 173.128(d) of this subchapter.

(2) *Samples.* Samples of new organic peroxides or new formulations of organic peroxides identified in the Organic Peroxides Table in paragraph (c) of this section, for which complete test data are not available, and that are to be transported for further testing or product evaluation, may be assigned an appropriate shipping description for organic peroxide Type C, packaged and offered for transportation, under the following conditions:

(i) Data available to the person offering the material for transportation must indicate that the sample would pose a level of hazard no greater than that of an organic peroxide Type B and that the control temperature, if any, is sufficiently low to prevent any dangerous decomposition and sufficiently high to prevent any dangerous phase separation;

(ii) The sample must be packaged in accordance with packing method OP2, for a liquid or solid, respectively;

(iii) Packages of the organic peroxide may be offered for transportation and transported in a quantity not to exceed 10 kg (22 pounds) per transport vehicle; and

(iv) One of the following shipping descriptions must be assigned:

(A) Organic peroxide Type C, liquid, 5.2, UN 3103;

(B) Organic peroxide Type C, solid, 5.2, UN 3104;

(C) Organic peroxide Type C, liquid, temperature controlled, 5.2, UN 3113; or

(D) Organic peroxide Type C, solid, temperature controlled, 5.2, UN 3114.

(3) *Mixtures.* Mixtures of organic peroxides individually identified in the Organic Peroxides Table in paragraph (c) of this section may be classified as the same type of organic peroxide as that of the most dangerous component and be transported under the conditions for transportation given for this type. If the stable components form a thermally less stable mixture, the SADT of the mixture must be determined and the new control and emergency temperature derived under the provisions of § 173.21(f).

(c) *Organic peroxides table.* The following Organic Peroxides Table specifies by technical name those organic peroxides that are authorized for transportation and not subject to the approval provisions of § 173.128 of this part. An organic peroxide identified by technical name in the following table is authorized for transportation only if it conforms to all applicable provisions of the table. The column headings of the Organic Peroxides Table are as follows:

(1) *Technical name.* The first column specifies the technical name.

(2) *ID number.* The second column specifies the identification (ID) number

which is used to identify the proper shipping name in the §172.101 table. The word “EXEMPT” appearing in the column denotes that the material is not regulated as an organic peroxide.

(3) *Concentration of organic peroxide.* The third column specifies concentration (mass percent) limitations, if any, in mixtures or solutions for the organic peroxide. Limitations are given as minimums, maximums, or a range, as appropriate. A range includes the lower and upper limits (*i.e.*, “53–100” means from, and including, 53% to, and including 100%). See introductory paragraph of §172.203(k) of this subchapter for additional description requirements for an organic peroxide that may qualify for more than one generic listing, depending on its concentration.

(4) *Concentration of diluents.* The fourth column specifies the type and concentration (mass percent) of diluent or inert solid, when required. Other types and concentrations of diluents may be used if approved by the Associate Administrator.

(i) The required mass percent of “Diluent type A” is specified in column 4a. A diluent type A is an organic liquid that does not detrimentally affect the thermal stability or increase the hazard of the organic peroxide and with a boiling point not less than 150 °C at atmospheric pressure. Type A diluents may be used for desensitizing all organic peroxides.

(ii) The required mass percent of “Diluent type B” is specified in column 4b. A diluent type B is an organic liquid which is compatible with the organic peroxide and which has a boiling

point, at atmospheric pressure, of less than 150 °C (302 °F) but at least 60 °C (140 °F), and a flash point greater than 5 °C (41 °F). Type B diluents may be used for desensitizing all organic peroxides, when specified in the organic peroxide tables, provided that the boiling point is at least 60 °C (140 °F) above the SADT of the peroxide in a 50 kg (110 lbs) package. A type A diluent may be used to replace a type B diluent in equal concentration.

(iii) The required mass percent of “Inert solid” is specified in column 4c. An inert solid is a solid that does not detrimentally affect the thermal stability or hazard of the organic peroxide.

(5) *Concentration of water.* Column 5 specifies, in mass percent, the minimum amount of water, if any, which must be in formulation.

(6) *Packing method.* Column 6 specifies the highest packing method (largest packaging capacity) authorized for the organic peroxide. Lower numbered packing methods (smaller packaging capacities) are also authorized. For example, if OP3 is specified, then OP2 and OP1 are also authorized. The Table of Packing Methods in paragraph (d) of this section defines the non-bulk packing methods.

(7) *Temperatures.* Column 7a specifies the control temperature. Column 7b specifies the emergency temperature. Temperatures are specified only when temperature controls are required. (See §173.21(f)).

(8) *Notes.* Column 8 specifies other applicable provisions, as set forth in notes following the table.

ORGANIC PEROXIDE TABLE

| Technical name<br>(1)                                                          | ID number<br>(2) | Concentration (mass %)<br>(3) | Diluent (mass %) |           |           | Water (mass %)<br>(5) | Packing method<br>(6) | Temperature (°C) |                   | Notes<br>(8) |
|--------------------------------------------------------------------------------|------------------|-------------------------------|------------------|-----------|-----------|-----------------------|-----------------------|------------------|-------------------|--------------|
|                                                                                |                  |                               | A<br>(4a)        | B<br>(4b) | I<br>(4c) |                       |                       | Control<br>(7a)  | Emergency<br>(7b) |              |
| Acetyl acetone peroxide .....                                                  | UN3105           | ≤42 .....                     | ≥48              | ....      | ....      | ≥8                    | OP7 .....             | .....            | .....             | 2            |
| Acetyl acetone peroxide [as a paste] .....                                     | UN3106           | ≤32 .....                     | ....             | ....      | ....      | .....                 | OP7 .....             | .....            | .....             | 21           |
| Acetyl cyclohexanesulfonyl peroxide .....                                      | UN3112           | ≤82 .....                     | ....             | ....      | ....      | ≥12                   | OP4 .....             | −10              | 0                 | .....        |
| Acetyl cyclohexanesulfonyl peroxide .....                                      | UN3115           | ≤32 .....                     | ....             | ≥68       | ....      | .....                 | OP7 .....             | −10              | 0                 | .....        |
| tert-Amyl hydroperoxide .....                                                  | UN3107           | ≤88 .....                     | ≥6               | ....      | ....      | ≥6                    | OP8 .....             | .....            | .....             | .....        |
| tert-Amyl peroxyacetate .....                                                  | UN3105           | ≤62 .....                     | ≥38              | ....      | ....      | .....                 | OP7 .....             | .....            | .....             | .....        |
| tert-Amyl peroxybenzoate .....                                                 | UN3103           | ≤100 .....                    | ....             | ....      | ....      | .....                 | OP5 .....             | .....            | .....             | .....        |
| tert-Amyl peroxy-2-ethylhexanoate .....                                        | UN3115           | ≤100 .....                    | ....             | ....      | ....      | .....                 | OP7 .....             | +20              | +25               | ..           |
| tert-Amyl peroxy-2-ethylhexyl carbonate .....                                  | UN3105           | ≤100 .....                    | ....             | ....      | ....      | .....                 | OP7 .....             | .....            | .....             | .....        |
| tert-Amyl peroxy isopropyl carbonate .....                                     | UN3103           | ≤77 .....                     | ≥23              | ....      | ....      | .....                 | OP5 .....             | .....            | .....             | .....        |
| tert-Amyl peroxyneodecanoate .....                                             | UN3115           | ≤77 .....                     | ....             | ≥23       | ....      | .....                 | OP7 .....             | 0                | +10               | ..           |
| tert-Amyl peroxy-pivalate .....                                                | UN3113           | ≤77 .....                     | ....             | ≥23       | ....      | .....                 | OP5 .....             | +10              | +15               | ..           |
| tert-Amyl peroxy-3,5,5-trimethylhexanoate .....                                | UN3101           | ≤100 .....                    | ....             | ....      | ....      | .....                 | OP5 .....             | .....            | .....             | .....        |
| tert-Butyl cumyl peroxide .....                                                | UN3107           | >42–100 .....                 | ....             | ....      | ....      | .....                 | OP8 .....             | .....            | .....             | 9            |
| tert-Butyl cumyl peroxide .....                                                | UN3108           | ≤52 .....                     | ....             | ....      | ≥48       | .....                 | OP8 .....             | .....            | .....             | 9            |
| n-Butyl-4,4-di-(tert-butylperoxy)valerate .....                                | UN3103           | >52–100 .....                 | ....             | ....      | ....      | .....                 | OP5 .....             | .....            | .....             | .....        |
| n-Butyl-4,4-di-(tert-butylperoxy)valerate .....                                | UN3108           | ≤52 .....                     | ....             | ....      | ≥48       | .....                 | OP8 .....             | .....            | .....             | .....        |
| tert-Butyl hydroperoxide .....                                                 | UN3103           | >79–90 .....                  | ....             | ....      | ....      | ≥10                   | OP5 .....             | .....            | .....             | 13           |
| tert-Butyl hydroperoxide .....                                                 | UN3105           | ≤80 .....                     | ≥20              | ....      | ....      | .....                 | OP7 .....             | .....            | .....             | 4, 13        |
| tert-Butyl hydroperoxide .....                                                 | UN3107           | ≤79 .....                     | ....             | ....      | ....      | >14                   | OP8 .....             | .....            | .....             | 13, 16       |
| tert-Butyl hydroperoxide .....                                                 | UN3109           | ≤72 .....                     | ....             | ....      | ....      | ≥28                   | OP8 .....             | .....            | .....             | 13           |
| tert-Butyl hydroperoxide [and] Di-tert-butylperoxide .....                     | UN3103           | <82+>9 .....                  | ....             | ....      | ....      | ≥7                    | OP5 .....             | .....            | .....             | 13           |
| tert-Butyl monoperoxy-maleate .....                                            | UN3102           | >52–100 .....                 | ....             | ....      | ....      | .....                 | OP5 .....             | .....            | .....             | .....        |
| tert-Butyl monoperoxy-maleate .....                                            | UN3103           | ≤52 .....                     | ≥48              | ....      | ....      | .....                 | OP6 .....             | .....            | .....             | .....        |
| tert-Butyl monoperoxy-maleate .....                                            | UN3108           | ≤52 .....                     | ....             | ....      | ≥48       | .....                 | OP8 .....             | .....            | .....             | .....        |
| tert-Butyl monoperoxy-maleate [as a paste] .....                               | UN3108           | ≤52 .....                     | ....             | ....      | ....      | .....                 | OP8 .....             | .....            | .....             | .....        |
| tert-Butyl peroxyacetate .....                                                 | UN3101           | >52–77 .....                  | ≥23              | ....      | ....      | .....                 | OP5 .....             | .....            | .....             | .....        |
| tert-Butyl peroxyacetate .....                                                 | UN3103           | >32–52 .....                  | ≥48              | ....      | ....      | .....                 | OP6 .....             | .....            | .....             | .....        |
| tert-Butyl peroxyacetate .....                                                 | UN3109           | ≤32 .....                     | ....             | ≥68       | ....      | .....                 | OP8 .....             | .....            | .....             | .....        |
| tert-Butyl peroxybenzoate .....                                                | UN3103           | >77–100 .....                 | ....             | ....      | ....      | .....                 | OP5 .....             | .....            | .....             | .....        |
| tert-Butyl peroxybenzoate .....                                                | UN3105           | >52–77 .....                  | ≥23              | ....      | ....      | .....                 | OP7 .....             | .....            | .....             | 1            |
| tert-Butyl peroxybenzoate .....                                                | UN3106           | ≤52 .....                     | ....             | ....      | ≥48       | .....                 | OP7 .....             | .....            | .....             | .....        |
| tert-Butyl peroxybutyl fumarate .....                                          | UN3105           | ≤52 .....                     | ≥48              | ....      | ....      | .....                 | OP7 .....             | .....            | .....             | .....        |
| tert-Butyl peroxy-crotonate .....                                              | UN3105           | ≤77 .....                     | ≥23              | ....      | ....      | .....                 | OP7 .....             | .....            | .....             | .....        |
| tert-Butyl peroxydiethylacetate .....                                          | UN3113           | ≤100 .....                    | ....             | ....      | ....      | .....                 | OP5 .....             | +20              | +25               | ..           |
| tert-Butyl peroxy-2-ethylhexanoate .....                                       | UN3113           | >52–100 .....                 | ....             | ....      | ....      | .....                 | OP6 .....             | +20              | +25               | ..           |
| tert-Butyl peroxy-2-ethylhexanoate .....                                       | UN3117           | >32–52 .....                  | ....             | ≥48       | ....      | .....                 | OP8 .....             | +30              | +35               | ..           |
| tert-Butyl peroxy-2-ethylhexanoate .....                                       | UN3118           | ≤52 .....                     | ....             | ....      | ≥48       | .....                 | OP8 .....             | +20              | +25               | ..           |
| tert-Butyl peroxy-2-ethylhexanoate .....                                       | UN3119           | ≤32 .....                     | ....             | ≥68       | ....      | .....                 | OP8 .....             | +40              | +45               | ..           |
| tert-Butyl peroxy-2-ethylhexanoate [and] 2,2-di-(tert-butylperoxy)butane ..... | UN3106           | ≤12+≤14 .....                 | ≥14              | ....      | ≥60       | .....                 | OP7 .....             | .....            | .....             | .....        |
| tert-Butyl peroxy-2-ethylhexanoate [and] 2,2-di-(tert-butylperoxy)butane ..... | UN3115           | ≤31+≤36 .....                 | ....             | ≥33       | ....      | .....                 | OP7 .....             | +35              | +40               | ..           |

|                                                                          |        |         |       |       |       |       |       |        |       |       |        |
|--------------------------------------------------------------------------|--------|---------|-------|-------|-------|-------|-------|--------|-------|-------|--------|
| tert-Butyl peroxy-2-ethylhexylcarbonate                                  | UN3105 | ≤100    | ..... | ..... | ..... | ..... | ..... | OP7    | ..... | ..... | .....  |
| tert-Butyl peroxyisobutyrate                                             | UN3111 | >52–77  | ..... | ≥23   | ..... | ..... | ..... | OP5    | +15   | +20   | .....  |
| tert-Butyl peroxyisobutyrate                                             | UN3115 | ≤52     | ..... | ≥48   | ..... | ..... | ..... | OP7    | +15   | +20   | .....  |
| tert-Butylperoxy isopropylcarbonate                                      | UN3103 | ≤77     | ..... | ≥23   | ..... | ..... | ..... | OP5    | ..... | ..... | .....  |
| 1-(2-tert-Butylperoxy isopropyl)-3-isopropenylbenzene                    | UN3105 | ≤77     | ..... | ≥23   | ..... | ..... | ..... | OP7    | ..... | ..... | .....  |
| 1-(2-tert-Butylperoxy isopropyl)-3-isopropenylbenzene                    | UN3108 | ≤42     | ..... | ..... | ..... | ≥58   | ..... | OP8    | ..... | ..... | .....  |
| tert-Butyl peroxy-2-methylbenzoate                                       | UN3103 | ≤100    | ..... | ..... | ..... | ..... | ..... | OP5    | ..... | ..... | .....  |
| tert-Butyl peroxyneodecanoate                                            | UN3115 | >77–100 | ..... | ..... | ..... | ..... | ..... | OP7    | –5    | +5    | .....  |
| tert-Butyl peroxyneodecanoate                                            | UN3115 | ≤77     | ..... | ≥23   | ..... | ..... | ..... | OP7    | 0     | +10   | .....  |
| tert-Butyl peroxyneodecanoate [as a stable dispersion in water]          | UN3119 | ≤52     | ..... | ..... | ..... | ..... | ..... | OP8    | 0     | +10   | .....  |
| tert-Butyl peroxyneodecanoate [as a stable dispersion in water (frozen)] | UN3118 | ≤42     | ..... | ..... | ..... | ..... | ..... | OP8    | 0     | +10   | .....  |
| tert-Butyl peroxyneodecanoate                                            | UN3119 | ≤32     | ..... | ≥68   | ..... | ..... | ..... | OP8    | 0     | +10   | .....  |
| tert-Butyl peroxyneohexanoate                                            | UN3115 | ≤77     | ..... | ≥23   | ..... | ..... | ..... | OP7    | 0     | +10   | .....  |
| tert-Butyl peroxyneohexanoate [as a stable dispersion in water]          | UN3117 | ≤42     | ..... | ..... | ..... | ..... | ..... | OP8    | 0     | +10   | .....  |
| tert-Butyl peroxyvalate                                                  | UN3113 | >67–77  | ..... | ≥23   | ..... | ..... | ..... | OP5    | 0     | +10   | .....  |
| tert-Butyl peroxyvalate                                                  | UN3115 | >27–67  | ..... | ≥33   | ..... | ..... | ..... | OP7    | 0     | +10   | .....  |
| tert-Butyl peroxyvalate                                                  | UN3119 | ≤27     | ..... | ≥73   | ..... | ..... | ..... | OP8    | +30   | +35   | .....  |
| tert-Butylperoxy stearylcarbonate                                        | UN3106 | ≤100    | ..... | ..... | ..... | ..... | ..... | OP7    | ..... | ..... | .....  |
| tert-Butyl peroxy-3,5,5-trimethylhexanoate                               | UN3105 | >32–100 | ..... | ..... | ..... | ..... | ..... | OP7    | ..... | ..... | .....  |
| tert-Butyl peroxy-3,5,5-trimethylhexanoate                               | UN3109 | ≤32     | ..... | ≥68   | ..... | ..... | ..... | OP8    | ..... | ..... | .....  |
| 3-Chloroperoxybenzoic acid                                               | UN3102 | >57–86  | ..... | ..... | ..... | ≥14   | ..... | OP1    | ..... | ..... | .....  |
| 3-Chloroperoxybenzoic acid                                               | UN3106 | ≤57     | ..... | ≥3    | ..... | ≥40   | ..... | OP7    | ..... | ..... | .....  |
| 3-Chloroperoxybenzoic acid                                               | UN3106 | ≤77     | ..... | ..... | ..... | ≥6    | ..... | OP7    | ..... | ..... | .....  |
| Cumyl hydroperoxide                                                      | UN3107 | >90–98  | ..... | ≤10   | ..... | ..... | ..... | OP8    | ..... | ..... | 13     |
| Cumyl hydroperoxide                                                      | UN3109 | ≤90     | ..... | ≥10   | ..... | ..... | ..... | OP8    | ..... | ..... | 13, 15 |
| Cumyl peroxyneodecanoate                                                 | UN3115 | ≤77     | ..... | ≥23   | ..... | ..... | ..... | OP7    | –10   | 0     | .....  |
| Cumyl peroxyneodecanoate [as a stable dispersion in water]               | UN3119 | ≤52     | ..... | ..... | ..... | ..... | ..... | OP8    | –10   | 0     | .....  |
| Cumyl peroxyneohexanoate                                                 | UN3115 | ≤77     | ..... | ≥23   | ..... | ..... | ..... | OP7    | –10   | 0     | .....  |
| Cumyl peroxyvalate                                                       | UN3115 | ≤77     | ..... | ..... | ..... | ..... | ..... | OP7    | –5    | +5    | .....  |
| Cyclohexanone peroxide(s)                                                | UN3104 | ≤91     | ..... | ..... | ..... | ≥9    | ..... | OP6    | ..... | ..... | 13     |
| Cyclohexanone peroxide(s)                                                | UN3105 | ≤72     | ..... | ≥28   | ..... | ..... | ..... | OP7    | ..... | ..... | 5      |
| Cyclohexanone peroxide(s) [as a paste]                                   | UN3106 | ≤72     | ..... | ..... | ..... | ..... | ..... | OP7    | ..... | ..... | 5, 21  |
| Cyclohexanone peroxide(s)                                                | Exempt | ≤32     | ..... | ..... | ..... | ≥68   | ..... | Exempt | ..... | ..... | .....  |
| Diacetone alcohol peroxides                                              | UN3115 | ≤57     | ..... | ≥26   | ..... | ≥8    | ..... | OP7    | +40   | +45   | 5      |
| Diacetyl peroxide                                                        | UN3115 | ≤27     | ..... | ≥73   | ..... | ..... | ..... | OP7    | +20   | +25   | 8,13   |
| Di-tert-amyl peroxide                                                    | UN3107 | ≤100    | ..... | ..... | ..... | ..... | ..... | OP8    | ..... | ..... | .....  |
| 1,1-Di-(tert-amylperoxy)cyclohexane                                      | UN3103 | ≤82     | ..... | ≥18   | ..... | ..... | ..... | OP6    | ..... | ..... | .....  |
| Dibenzoyl peroxide                                                       | UN3102 | >51–100 | ..... | ..... | ..... | ≤48   | ..... | OP2    | ..... | ..... | 3      |
| Dibenzoyl peroxide                                                       | UN3102 | >77–94  | ..... | ..... | ..... | ..... | ≥6    | OP4    | ..... | ..... | 3      |
| Dibenzoyl peroxide                                                       | UN3104 | ≤77     | ..... | ..... | ..... | ..... | ≥23   | OP6    | ..... | ..... | .....  |
| Dibenzoyl peroxide                                                       | UN3106 | ≤62     | ..... | ..... | ..... | ≥28   | ≥10   | OP7    | ..... | ..... | .....  |
| Dibenzoyl peroxide [as a paste]                                          | UN3106 | >52–62  | ..... | ..... | ..... | ..... | ..... | OP7    | ..... | ..... | 21     |

ORGANIC PEROXIDE TABLE—Continued

| Technical name<br>(1)                                                         | ID number<br>(2) | Concentration (mass %)<br>(3) | Diluent (mass %) |           |           | Water (mass %)<br>(5) | Packing method<br>(6) | Temperature (°C) |                   | Notes<br>(8) |
|-------------------------------------------------------------------------------|------------------|-------------------------------|------------------|-----------|-----------|-----------------------|-----------------------|------------------|-------------------|--------------|
|                                                                               |                  |                               | A<br>(4a)        | B<br>(4b) | I<br>(4c) |                       |                       | Control<br>(7a)  | Emergency<br>(7b) |              |
| Di-tert-butyl peroxide .....                                                  | UN3107           | >52–100                       | ...              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             | 24           |
| Di-tert-butyl peroxide .....                                                  | UN3109           | ≤52 .....                     | ...              | ≥48       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| Di-tert-butyl peroxyazelaate .....                                            | UN3105           | ≤52 .....                     | ≥48              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |
| 2,2-Di-(tert-butylperoxy)butane .....                                         | UN3103           | ≤52 .....                     | ≥48              | ...       | ...       | ...                   | OP6 .....             | .....            | .....             |              |
| 1,6-Di-(tert-butylperoxycarbonyloxy)hexane .....                              | UN3103           | ≤72 .....                     | ≥28              | ...       | ...       | ...                   | OP5 .....             | .....            | .....             | 22           |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3101           | >80–100                       | ...              | ...       | ...       | ...                   | OP5 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3103           | >52–80 ...                    | ≥20              | ...       | ...       | ...                   | OP5 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3105           | >42–52 ...                    | ≥48              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3106           | ≤42 .....                     | ≥13              | ...       | ≥45       | ...                   | OP7 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3107           | ≤27 .....                     | ≥25              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3109           | ≤42 .....                     | ≥58              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3109           | ≤25 .....                     | ≥25              | ≥50       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)cyclohexane .....                                    | UN3109           | ≤13 .....                     | ≥13              | ≥74       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| Di-n-butyl peroxydicarbonate .....                                            | UN3115           | >27–52 ...                    | ...              | ≥48       | ...       | ...                   | OP7 .....             | –15              | –5 ...            | 6            |
| Di-n-butyl peroxydicarbonate .....                                            | UN3117           | ≤27 .....                     | ...              | ≥73       | ...       | ...                   | OP8 .....             | –10              | 0 ...             |              |
| Di-n-butyl peroxydicarbonate [as a stable dispersion in water (frozen)] ..... | UN3118           | ≤42 .....                     | ...              | ...       | ...       | ...                   | OP8 .....             | –15              | –5 ...            |              |
| Di-sec-butyl peroxydicarbonate .....                                          | UN3113           | >52–100                       | ...              | ...       | ...       | ...                   | OP4 .....             | –20              | –10               |              |
| Di-sec-butyl peroxydicarbonate .....                                          | UN3115           | ≤52 .....                     | ...              | ≥48       | ...       | ...                   | OP7 .....             | –15              | –5 ...            | 1, 9         |
| Di-(2-tert-butylperoxyisopropyl)benzene(s) .....                              | UN3106           | >42–100                       | ...              | ...       | ≤57       | ...                   | OP7 .....             | .....            | .....             |              |
| Di-(2-tert-butylperoxyisopropyl)benzene(s) .....                              | Exempt           | ≤42 .....                     | ...              | ...       | ≥58       | ...                   | Exempt .....          | .....            | .....             | 21           |
| Di-(tert-butylperoxy)phthalate .....                                          | UN3105           | >42–52 ...                    | ≥48              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |
| Di-(tert-butylperoxy)phthalate [as a paste] .....                             | UN3106           | ≤52 .....                     | ...              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |
| Di-(tert-butylperoxy)phthalate .....                                          | UN3107           | ≤42 .....                     | ≥58              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| 2,2-Di-(tert-butylperoxy)propane .....                                        | UN3105           | ≤52 .....                     | ≥48              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             | 21           |
| 2,2-Di-(tert-butylperoxy)propane .....                                        | UN3106           | ≤42 .....                     | ≥13              | ...       | ≥45       | ...                   | OP7 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)-3,3,5-trimethylcyclohexane .....                    | UN3101           | >90–100                       | ...              | ...       | ...       | ...                   | OP5 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)-3,3,5-trimethylcyclohexane .....                    | UN3103           | >57–90 ...                    | ≥10              | ...       | ...       | ...                   | OP5 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)-3,3,5-trimethylcyclohexane .....                    | UN3103           | ≤77 .....                     | ...              | ≥23       | ...       | ...                   | OP5 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)-3,3,5-trimethylcyclohexane .....                    | UN3110           | ≤57 .....                     | ...              | ≥43       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)-3,3,5-trimethylcyclohexane .....                    | UN3107           | ≤57 .....                     | ≥43              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| 1,1-Di-(tert-butylperoxy)-3,3,5-trimethylcyclohexane .....                    | UN3107           | ≤32 .....                     | ≥26              | ≥42       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| Dicetyl peroxydicarbonate .....                                               | UN3116           | ≤100 .....                    | ...              | ...       | ...       | ...                   | OP7 .....             | +30              | +35 ..            |              |
| Dicetyl peroxydicarbonate [as a stable dispersion in water] .....             | UN3119           | ≤42 .....                     | ...              | ...       | ...       | ...                   | OP8 .....             | +30              | +35 ..            |              |
| Di-4-chlorobenzoyl peroxide .....                                             | UN3102           | ≤77 .....                     | ...              | ...       | ...       | ≥23 ..                | OP5 .....             | .....            | .....             | 9            |
| Di-4-chlorobenzoyl peroxide [as a paste] .....                                | UN3106           | ≤52 .....                     | ...              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |
| Di-4-chlorobenzoyl peroxide .....                                             | Exempt           | ≤32 .....                     | ...              | ...       | ≥68       | ...                   | Exempt .....          | .....            | .....             |              |
| Dicumyl peroxide .....                                                        | UN3110           | >52–100                       | ...              | ...       | ≤48       | ...                   | OP8 .....             | .....            | .....             |              |
| Dicumyl peroxide .....                                                        | Exempt           | ≤52 .....                     | ...              | ...       | ≥48       | ...                   | Exempt .....          | .....            | .....             | 21           |
| Dicyclohexyl peroxydicarbonate .....                                          | UN3112           | >91–100                       | ...              | ...       | ...       | ...                   | OP3 .....             | +10              | +15 ..            |              |
| Dicyclohexyl peroxydicarbonate .....                                          | UN3114           | ≤91 .....                     | ...              | ...       | ...       | ≥9 ...                | OP5 .....             | +10              | +15 ..            |              |
| Dicyclohexyl peroxydicarbonate [as a stable dispersion in water] .....        | UN3119           | ≤42 .....                     | ...              | ...       | ...       | ...                   | OP8 .....             | +15              | +20 ..            |              |

|                                                                                               |        |               |       |      |      |      |           |         |         |
|-----------------------------------------------------------------------------------------------|--------|---------------|-------|------|------|------|-----------|---------|---------|
| Didecanoyl peroxide .....                                                                     | UN3114 | ≤100 .....    | ....  | .... | .... | .... | OP6 ..... | +30     | +35 ..  |
| 2,2-Di-(4,4-di(tert-butylperoxy)cyclohexyl)propane .....                                      | UN3106 | ≤42 .....     | ....  | .... | ≥58  | .... | OP7 ..... | ....    | ....    |
| 2,2-Di-(4,4-di(tert-butylperoxy)cyclohexyl)propane .....                                      | UN3107 | ≤22 .....     | ....  | ≥78  | .... | .... | OP8 ..... | ....    | ....    |
| Di-2,4-dichlorobenzoyl peroxide .....                                                         | UN3102 | ≤77 .....     | ....  | .... | .... | ≥23  | OP5 ..... | ....    | ....    |
| Di-2,4-dichlorobenzoyl peroxide [as a paste with silicone oil] .....                          | UN3106 | ≤52 .....     | ....  | .... | .... | .... | OP7 ..... | ....    | ....    |
| Di-(2-ethoxyethyl) peroxydicarbonate .....                                                    | UN3115 | ≤52 .....     | ....  | ≥48  | .... | .... | OP7 ..... | -10     | 0 ..... |
| Di-(2-ethylhexyl) peroxydicarbonate .....                                                     | UN3113 | >77-100 ..... | ....  | .... | .... | .... | OP5 ..... | -20     | -10     |
| Di-(2-ethylhexyl) peroxydicarbonate .....                                                     | UN3115 | ≤77 .....     | ....  | ≥23  | .... | .... | OP7 ..... | -15     | -5 ..   |
| Di-(2-ethylhexyl) peroxydicarbonate [as a stable dispersion in water] .....                   | UN3117 | ≤62 .....     | ....  | .... | .... | .... | OP8 ..... | -15     | -5 ..   |
| Di-(2-ethylhexyl) peroxydicarbonate [as a stable dispersion in water] .....                   | UN3119 | ≤52 .....     | ....  | .... | .... | .... | OP8 ..... | -15     | -5 ..   |
| Di-(2-ethylhexyl) peroxydicarbonate [as a stable dispersion in water (frozen)] .....          | UN3120 | ≤52 .....     | ....  | .... | .... | .... | OP8 ..... | -15     | -5 ..   |
| 2,2-Dihydroperoxypropane .....                                                                | UN3102 | ≤27 .....     | ....  | .... | ≥73  | .... | OP5 ..... | ....    | ....    |
| Di-(1-hydroxycyclohexyl)peroxide .....                                                        | UN3106 | ≤100 .....    | ....  | .... | .... | .... | OP7 ..... | ....    | ....    |
| Diisobutyl peroxide .....                                                                     | UN3111 | >32-52 ..     | ....  | ≥48  | .... | .... | OP5 ..... | -20     | -10     |
| Diisobutyl peroxide .....                                                                     | UN3115 | ≤32 .....     | ....  | ≥68  | .... | .... | OP7 ..... | -20     | -10     |
| Diisopropylbenzene dihydroperoxide .....                                                      | UN3106 | ≤82 .....     | ≥5 .. | .... | .... | ≥5   | OP7 ..... | ....    | ....    |
| Diisopropyl peroxydicarbonate .....                                                           | UN3112 | >52-100 ..    | ....  | .... | .... | .... | OP2 ..... | -15     | -5 ..   |
| Diisopropyl peroxydicarbonate .....                                                           | UN3115 | ≤52 .....     | ....  | ≥48  | .... | .... | OP7 ..... | -20     | -10     |
| Diisopropyl peroxydicarbonate .....                                                           | UN3115 | ≤28 .....     | ≥72   | .... | .... | .... | OP7 ..... | -15     | -5 ..   |
| Dilauroyl peroxide .....                                                                      | UN3106 | ≤100 .....    | ....  | .... | .... | .... | OP7 ..... | ....    | ....    |
| Dilauroyl peroxide [as a stable dispersion in water] .....                                    | UN3109 | ≤42 .....     | ....  | .... | .... | .... | OP8 ..... | ....    | ....    |
| Di-(3-methoxybutyl) peroxydicarbonate .....                                                   | UN3115 | ≤52 .....     | ....  | ≥48  | .... | .... | OP7 ..... | -5 ..   | +5 ..   |
| Di-(2-methylbenzoyl)peroxide .....                                                            | UN3112 | ≤87 .....     | ....  | .... | .... | ≥13  | OP5 ..... | +30     | +35 ..  |
| Di-(4-methylbenzoyl)peroxide [as a paste with silicone oil] .....                             | UN3106 | ≤52 .....     | ....  | .... | .... | .... | OP7 ..... | ....    | ....    |
| Di-(3-methylbenzoyl) peroxide + Benzoyl (3-methylbenzoyl) peroxide + Dibenzoyl peroxide ..... | UN3115 | ≤20+ .....    | ....  | ≥58  | .... | .... | OP7 ..... | +35     | +40 ..  |
| 2,5-Dimethyl-2,5-di-(benzoylperoxy)hexane .....                                               | UN3102 | >82-100 ..    | ....  | .... | .... | .... | OP5 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(benzoylperoxy)hexane .....                                               | UN3106 | ≤82 .....     | ....  | .... | ≥18  | .... | OP7 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(benzoylperoxy)hexane .....                                               | UN3104 | ≤82 .....     | ....  | .... | .... | ≥18  | OP5 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(tert-butylperoxy)hexane .....                                            | UN3105 | >52-100 ..    | ....  | .... | .... | .... | OP7 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(tert-butylperoxy)hexane .....                                            | UN3108 | ≤77 .....     | ....  | .... | ≥23  | .... | OP8 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(tert-butylperoxy)hexane .....                                            | UN3109 | ≤52 .....     | ≥48   | .... | .... | .... | OP8 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(tert-butylperoxy)hexane [as a paste] .....                               | UN3108 | ≤47 .....     | ....  | .... | .... | .... | OP8 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(tert-butylperoxy)hexyne-3 .....                                          | UN3101 | >86-100 ..    | ....  | .... | .... | .... | OP5 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(tert-butylperoxy)hexyne-3 .....                                          | UN3103 | >52-86 ..     | ≥14   | .... | .... | .... | OP5 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(tert-butylperoxy)hexyne-3 .....                                          | UN3106 | ≤52 .....     | ....  | .... | ≥48  | .... | OP7 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(2-ethylhexanoylperoxy)hexane .....                                       | UN3113 | ≤100 .....    | ....  | .... | .... | .... | OP5 ..... | +20     | +25 ..  |
| 2,5-Dimethyl-2,5-dihydroperoxyhexane .....                                                    | UN3104 | ≤82 .....     | ....  | .... | .... | ≥18  | OP6 ..... | ....    | ....    |
| 2,5-Dimethyl-2,5-di-(3,5,5-trimethylhexanoylperoxy)hexane .....                               | UN3105 | ≤77 .....     | ≥23   | .... | .... | .... | OP7 ..... | ....    | ....    |
| 1,1-Dimethyl-3-hydroxybutylperoxyneohexanoate .....                                           | UN3117 | ≤52 .....     | ≥48   | .... | .... | .... | OP8 ..... | 0 ..... | +10 ..  |
| Dimyristyl peroxydicarbonate .....                                                            | UN3116 | ≤100 .....    | ....  | .... | .... | .... | OP7 ..... | +20     | +25 ..  |
| Dimyristyl peroxydicarbonate [as a stable dispersion in water] .....                          | UN3119 | ≤42 .....     | ....  | .... | .... | .... | OP8 ..... | +20     | +25 ..  |
| Di-(2-neodecanoylperoxyisopropyl)benzene .....                                                | UN3115 | ≤52 .....     | ≥48   | .... | .... | .... | OP7 ..... | -10     | 0 ..... |
| Di-n-nonanoyl peroxide .....                                                                  | UN3116 | ≤100 .....    | ....  | .... | .... | .... | OP7 ..... | 0 ..... | +10 ..  |
| Di-n-octanoyl peroxide .....                                                                  | UN3114 | ≤100 .....    | ....  | .... | .... | .... | OP5 ..... | +10     | +15 ..  |
| Di-(2-phenoxyethyl)peroxydicarbonate .....                                                    | UN3102 | >85-100 ..    | ....  | .... | .... | .... | OP5 ..... | ....    | ....    |
| Di-(2-phenoxyethyl)peroxydicarbonate .....                                                    | UN3106 | ≤85 .....     | ....  | .... | .... | ≥15  | OP7 ..... | ....    | ....    |
| Dipropionyl peroxide .....                                                                    | UN3117 | ≤27 .....     | ....  | ≥73  | .... | .... | OP8 ..... | +15     | +20 ..  |
| Di-n-propyl peroxydicarbonate .....                                                           | UN3113 | ≤100 .....    | ....  | .... | .... | .... | OP3 ..... | -25     | -15     |
| Di-n-propyl peroxydicarbonate .....                                                           | UN3113 | ≤77 .....     | ....  | ≥23  | .... | .... | OP5 ..... | -20     | -10     |

17

ORGANIC PEROXIDE TABLE—Continued

| Technical name<br>(1)                                                                                | ID number<br>(2) | Concentration (mass %)<br>(3) | Diluent (mass %) |           |           | Water (mass %)<br>(5) | Packing method<br>(6) | Temperature (°C) |                   | Notes<br>(8) |
|------------------------------------------------------------------------------------------------------|------------------|-------------------------------|------------------|-----------|-----------|-----------------------|-----------------------|------------------|-------------------|--------------|
|                                                                                                      |                  |                               | A<br>(4a)        | B<br>(4b) | I<br>(4c) |                       |                       | Control<br>(7a)  | Emergency<br>(7b) |              |
| Disuccinic acid peroxide .....                                                                       | UN3102           | >72–100                       | ...              | ...       | ...       | ...                   | OP4 .....             | .....            | .....             | 18           |
| Disuccinic acid peroxide .....                                                                       | UN3116           | ≤72 .....                     | ...              | ...       | ...       | ≥28 ..                | OP7 .....             | +10              | +15 ..            |              |
| Di-(3,5,5-trimethylhexanoyl)peroxide .....                                                           | UN3115           | >38–82 ...                    | ≥18              | ...       | ...       | ...                   | OP7 .....             | 0 .....          | +10 ..            |              |
| Di-(3,5,5-trimethylhexanoyl)peroxide [as a stable dispersion in water] .....                         | UN3119           | ≤52 .....                     | ...              | ...       | ...       | ...                   | OP8 .....             | +10              | +15 ..            |              |
| Di-(3,5,5-trimethylhexanoyl)peroxide .....                                                           | UN3119           | ≤38 .....                     | ≥62              | ...       | ...       | ...                   | OP8 .....             | +20              | +25 ..            |              |
| Ethyl 3,3-di-(tert-amylperoxy)butyrate .....                                                         | UN3105           | ≤67 .....                     | ≥33              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |
| Ethyl 3,3-di-(tert-butylperoxy)butyrate .....                                                        | UN3103           | >77–100                       | ...              | ...       | ...       | ...                   | OP5 .....             | .....            | .....             |              |
| Ethyl 3,3-di-(tert-butylperoxy)butyrate .....                                                        | UN3105           | ≤77 .....                     | ≥23              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |
| Ethyl 3,3-di-(tert-butylperoxy)butyrate .....                                                        | UN3106           | ≤52 .....                     | ...              | ...       | ≥48       | ...                   | OP7 .....             | .....            | .....             |              |
| 1-(2-ethylhexanoylperoxy)-1,3-Dimethylbutyl peroxy-pivalate .....                                    | UN3115           | ≤52 .....                     | ≥45              | ≥10       | ...       | ...                   | OP7 .....             | –20              | –10               |              |
| tert-Hexyl peroxyneodecanoate .....                                                                  | UN3115           | ≤71 .....                     | ≥29              | ...       | ...       | ...                   | OP7 .....             | 0 .....          | +10 ..            |              |
| tert-Hexyl peroxy-pivalate .....                                                                     | UN3115           | ≤72 .....                     | ...              | ≥28       | ...       | ...                   | OP7 .....             | +10              | +15 ..            |              |
| Isopropyl sec-butyl peroxydicarbonat +Di-sec-butyl peroxydicarbonate+Di-isopropyl peroxydicarbonate. | UN3111           | ≤52+≤28                       | ...              | ...       | ...       | ...                   | OP5 .....             | –20              | –10               |              |
| Isopropyl sec-butyl peroxydicarbonate+Di-sec-butyl peroxydicarbonate+Di-isopropyl peroxydicarbonate. | UN3115           | +≤22 .....                    | ≥38              | ...       | ...       | ...                   | OP7 .....             | –20              | –10               |              |
|                                                                                                      |                  | –18 .....                     | ...              | ...       | ...       | ...                   | ...                   | ...              | ...               |              |
|                                                                                                      |                  | +≤12 .....                    | ...              | ...       | ...       | ...                   | ...                   | ...              | ...               |              |
|                                                                                                      |                  | –15 .....                     | ...              | ...       | ...       | ...                   | ...                   | ...              | ...               |              |
| Isopropylcumyl hydroperoxide .....                                                                   | UN3109           | ≤72 .....                     | ≥28              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             | 13           |
| p-Menthyl hydroperoxide .....                                                                        | UN3105           | > 72–100                      | ...              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             | 13           |
| p-Menthyl hydroperoxide .....                                                                        | UN3109           | ≤72 .....                     | ≥28              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| Methylcyclohexanone peroxide(s) .....                                                                | UN3115           | ≤67 .....                     | ...              | ≥33       | ...       | ...                   | OP7 .....             | +35              | +40 ..            |              |
| Methyl ethyl ketone peroxide(s) .....                                                                | UN3101           | ≤52 .....                     | ≥48              | ...       | ...       | ...                   | OP5 .....             | .....            | .....             | 5, 13        |
| Methyl ethyl ketone peroxide(s) .....                                                                | UN3105           | ≤45 .....                     | ≥55              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             | 5            |
| Methyl ethyl ketone peroxide(s) .....                                                                | UN3107           | ≤40 .....                     | ≥60              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             | 7            |
| Methyl isobutyl ketone peroxide(s) .....                                                             | UN3105           | ≤62 .....                     | ≥19              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             | 5, 23        |
| Organic peroxide, liquid, sample .....                                                               | UN3103           | .....                         | ...              | ...       | ...       | ...                   | OP2 .....             | .....            | .....             | 12           |
| Organic peroxide, liquid, sample, temperature controlled .....                                       | UN3113           | .....                         | ...              | ...       | ...       | ...                   | OP2 .....             | .....            | .....             | 12           |
| Organic peroxide, solid, sample .....                                                                | UN3104           | .....                         | ...              | ...       | ...       | ...                   | OP2 .....             | .....            | .....             | 12           |
| Organic peroxide, solid, sample, temperature controlled .....                                        | UN3114           | .....                         | ...              | ...       | ...       | ...                   | OP2 .....             | .....            | .....             | 12           |
| Peroxyacetic acid, type D, stabilized .....                                                          | UN3105           | ≤43 .....                     | ...              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             | 13, 20       |
| Peroxyacetic acid, type E, stabilized .....                                                          | UN3107           | ≤43 .....                     | ...              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             | 13, 20       |
| Peroxyacetic acid, type F, stabilized .....                                                          | UN3109           | ≤43 .....                     | ...              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             | 13, 20, 28   |
| Peroxyacetic acid or peracetic acid [with not more than 7% hydrogen peroxide] .....                  | UN3107           | ≤36 .....                     | ...              | ...       | ...       | ≥15 ..                | OP8 .....             | .....            | .....             | 13, 20, 28   |
| Peroxyacetic acid or peracetic acid [with not more than 20% hydrogen peroxide] .....                 | Exempt           | ≤6 .....                      | ...              | ...       | ...       | ≥60 ..                | Exempt .....          | .....            | .....             | 28           |
| Peroxyacetic acid or peracetic acid [with not more than 26% hydrogen peroxide] .....                 | UN3109           | ≤17 .....                     | ...              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             | 13, 20, 28   |
| Peroxy-lauric acid .....                                                                             | UN3118           | ≤100 .....                    | ...              | ...       | ...       | ...                   | OP8 .....             | +35              | +40 ..            |              |
| Pinanyl hydroperoxide .....                                                                          | UN3105           | >56–100                       | ...              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             | 13           |
| Pinanyl hydroperoxide .....                                                                          | UN3109           | ≤56 .....                     | ≥44              | ...       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| Polyether poly-tert-butylperoxycarbonate .....                                                       | UN3107           | ≤52 .....                     | ...              | ≥48       | ...       | ...                   | OP8 .....             | .....            | .....             |              |
| Tetrahydronaphthyl hydroperoxide .....                                                               | UN3106           | ≤100 .....                    | ...              | ...       | ...       | ...                   | OP7 .....             | .....            | .....             |              |

§ 173.225

49 CFR Ch. I (10–1–08 Edition)

|                                                                                     |        |            |      |      |      |       |           |       |        |
|-------------------------------------------------------------------------------------|--------|------------|------|------|------|-------|-----------|-------|--------|
| 1,1,3,3-Tetramethylbutyl hydroperoxide .....                                        | UN3105 | ≤100 ..... | .... | .... | .... | ..... | OP7 ..... | ..... | .....  |
| 1,1,3,3-Tetramethylbutyl peroxy-2-ethylhexanoate .....                              | UN3115 | ≤100 ..... | .... | .... | .... | ..... | OP7 ..... | +15   | +20 .. |
| 1,1,3,3-Tetramethylbutyl peroxyneodecanoate .....                                   | UN3115 | ≤72 .....  | .... | ≥28  | .... | ..... | OP7 ..... | -5    | +5     |
| 1,1,3,3-Tetramethylbutyl peroxyneodecanoate [as a stable dispersion in water] ..... | UN3119 | ≤52 .....  | .... | .... | .... | ..... | OP8 ..... | -5    | +5     |
| 1,1,3,3-tetramethylbutyl peroxy-pivalate .....                                      | UN3115 | ≤77 .....  | ≥23  | .... | .... | ..... | OP7 ..... | 0     | +10    |
| 3,6,9-Triethyl-3,6,9-trimethyl-1,4,7-triperoxonane .....                            | UN3105 | ≤42 .....  | ≥58  | .... | .... | ..... | OP7 ..... | ..... | .....  |
|                                                                                     |        |            |      |      |      |       |           |       | 26     |



## NOTES

1. For domestic shipments, OP8 is authorized.
2. Available oxygen must be <4.7%.
3. For concentrations <80% OP5 is allowed. For concentrations of at least 80% but <85%, OP4 is allowed. For concentrations of at least 85%, maximum package size is OP2.
4. The diluent may be replaced by di-tert-butyl peroxide.
5. Available oxygen must be ≤9% with or without water.
6. For domestic shipments, OP5 is authorized.
7. Available oxygen must be ≤8.2% with or without water.
8. Only non-metallic packagings are authorized.
9. For domestic shipments this material may be transported under the provisions of paragraph (h)(3)(xii) of this section.
10. [Reserved]
11. [Reserved]
12. Samples may only be offered for transportation under the provisions of paragraph (b)(2) of this section.
13. “Corrosive” subsidiary risk label is required.
14. [Reserved]
15. No “Corrosive” subsidiary risk label is required for concentrations below 80%.
16. With <6% di-tert-butyl peroxide.
17. With ≤8% 1-isopropylhydroperoxy-4-isopropylhydroxybenzene.
18. Addition of water to this organic peroxide will decrease its thermal stability.
19. [Reserved]
20. Mixtures with hydrogen peroxide, water and acid(s).
21. With diluent type A, with or without water.
22. With ≥36% diluent type A by mass, and in addition ethylbenzene.
23. With ≥19% diluent type A by mass, and in addition methyl isobutyl ketone.
24. Diluent type B with boiling point >100 °C.
25. No “Corrosive” subsidiary risk label is required for concentrations below 56%.

26. Available oxygen must be ≤7.6%.

27. Formulations derived from distillation of peroxyacetic acid originating from peroxyacetic acid in a concentration of not more than 41% with water, total active oxygen less than or equal to 9.5% (peroxyacetic acid plus hydrogen peroxide).

28. For the purposes of this section, the names “Peroxyacetic acid” and “Peracetic acid” are synonymous.

(d) *Packing Method Table*. Packagings for organic peroxides and self-reactive substances are listed in the Maximum Quantity per Packing Method Table. The packing methods are designated OP1 to OP8. The quantities specified for each packing method represent the maximum that is authorized.

(1) The following types of packagings are authorized:

(i) Drums: 1A1, 1A2, 1B1, 1B2, 1D, 1G, 1H1, 1H2;

(ii) Jerricans: 3A1, 3A2, 3B1, 3B2, 3H1, 3H2;

(iii) Boxes: 4C1, 4C2, 4D, 4F, 4G, 4H1, 4H2, 4A, 4B; or

(iv) Composite packagings with a plastic inner receptacle: 6HA1, 6HA2, 6HB1, 6HB2, 6HC, 6HD1, 6HD2, 6HG1, 6HG2, 6HH1, 6HH2.

(2) Metal packaging (including inner packagings of combination packagings and outer packagings of combination or composite packagings) are used only for packing methods OP7 and OP8.

(3) In combination packagings, glass receptacles are used only as inner packagings with a maximum content of 0.5 kg for solids or 0.5 L for liquids.

(4) The maximum quantity per packaging or package for Packing Methods OP1–OP8 must be as follows:

## MAXIMUM QUANTITY PER PACKAGING/PACKAGE

[For Packing Methods OP1 to OP8]

| Maximum quantity                                                | Packing Method |        |     |                  |     |     |     |                  |
|-----------------------------------------------------------------|----------------|--------|-----|------------------|-----|-----|-----|------------------|
|                                                                 | OP1            | OP2    | OP3 | OP4 <sup>1</sup> | OP5 | OP6 | OP7 | OP8              |
| Solids and combination packagings (liquid and solid) (kg) ..... | 0.5            | 0.5/10 | 5   | 5                | 25  | 50  | 50  | <sup>2</sup> 400 |
| Liquids (L) .....                                               | 0.5            | .....  | 5   | .....            | 30  | 60  | 60  | <sup>3</sup> 225 |

<sup>1</sup> If two values are given, the first applies to the maximum net mass per inner packaging and the second to the maximum net mass of the complete package.

<sup>2</sup> 60 kg for jerricans/200 kg for boxes and, for solids, 400 kg in combination packagings with outer packagings comprising boxes (4C1, 4C2, 4D, 4F, 4G, 4H1, and 4H2) and with inner packagings of plastics or fiber with a maximum net mass of 25 kg.

<sup>3</sup> 60 L for jerricans.

(e) *Organic Peroxide IBC Table.* The following Organic Peroxide IBC Table specifies, by technical name, those organic peroxides that are authorized for transportation in certain IBCs and not subject to the approval provisions of § 173.128 of this part. Additional requirements for authorized IBCs are found in paragraph (f) of this section.

ORGANIC PEROXIDE IBC TABLE

| UN No.     | Organic peroxide                                                                 | Type of IBC | Maximum quantity (litres) | Control temperature | Emergency temperature |
|------------|----------------------------------------------------------------------------------|-------------|---------------------------|---------------------|-----------------------|
| 3109 ..... | ORGANIC PEROXIDE, TYPE F, LIQUID.                                                |             |                           |                     |                       |
|            | tert-Butyl hydroperoxide, not more than 72% with water.                          | 31A         | 1250                      |                     |                       |
|            | tert-Butyl peroxyacetate, not more than 32% in diluent type A.                   | 31A         | 1250                      |                     |                       |
|            | .....                                                                            | 31HA1       | 1000                      |                     |                       |
|            | tert-Butyl peroxy-3,5,5-trimethylhexanoate, not more than 32% in diluent type A. | 31A         | 1250                      |                     |                       |
|            | .....                                                                            | 31HA1       | 1000                      |                     |                       |
|            | Cumyl hydroperoxide, not more than 90% in diluent type A.                        | 31HA1       | 1250                      |                     |                       |
|            | Dibenzoyl peroxide, not more than 42% as a stable dispersion.                    | 31H1        | 1000                      |                     |                       |
|            | Di-tert-butyl peroxide, not more than 52% in diluent type B.                     | 31A         | 1250                      |                     |                       |
|            | .....                                                                            | 31HA1       | 1000                      |                     |                       |
|            | 1,1-Di-(tert-butylperoxy) cyclohexane, not more than 42% in diluent type A.      | 31H1        | 1000                      |                     |                       |
|            | Dicumyl peroxide, less than or equal to 100%.                                    | 31A         | 1250                      |                     |                       |
|            | .....                                                                            | 31HA1       | 1000                      |                     |                       |
|            | Dilauroyl peroxide, not more than 42%, stable dispersion, in water.              | 31HA1       | 1000                      |                     |                       |
|            | Isopropyl cumyl hydroperoxide, not more than 72% in diluent type A.              | 31HA1       | 1250                      |                     |                       |
|            | p-Menthyl hydroperoxide, not more than 72% in diluent type A.                    | 31HA1       | 1250                      |                     |                       |
|            | Peroxyacetic acid, stabilized, not more than 17%.                                | 31H1        | 1500                      |                     |                       |
|            | .....                                                                            | 31HA1       | 1500                      |                     |                       |
|            | .....                                                                            | 31A         | 1500                      |                     |                       |
|            | Peroxyacetic acid, with not more than 26% hydrogen peroxide.                     | 31A         | 1500                      |                     |                       |
|            | .....                                                                            | 31HA1       | 1500                      |                     |                       |
|            | Peroxyacetic acid, type F, stabilized.                                           | 31A         | 1500                      |                     |                       |
|            | .....                                                                            | 31HA1       | 1500                      |                     |                       |
| 3110 ..... | ORGANIC PEROXIDE TYPE F, SOLID.                                                  |             |                           |                     |                       |
|            | Dicumyl peroxide, less than or equal to 100%.                                    | 31A         | 2000                      |                     |                       |
|            | .....                                                                            | 31H1        |                           |                     |                       |
|            | .....                                                                            | 31HA1       |                           |                     |                       |
| 3119 ..... | ORGANIC PEROXIDE, TYPE F, LIQUID, TEMPERATURE CONTROLLED.                        |             |                           |                     |                       |
|            | tert-Butyl peroxy-2-ethylhexanoate, not more than 32% in diluent type B.         | 31HA1       | 1000                      | +30 °C              | +35 °C                |
|            | .....                                                                            | 31A         | 1250                      | +30 °C              | +35 °C                |
|            | tert-Butyl peroxyneodecanoate, not more than 32% in diluent type A.              | 31A         | 1250                      | 0 °C                | +10 °C                |

ORGANIC PEROXIDE IBC TABLE—Continued

| UN No. | Organic peroxide                                                                               | Type of IBC | Maximum quantity (litres) | Control temperature | Emergency temperature |
|--------|------------------------------------------------------------------------------------------------|-------------|---------------------------|---------------------|-----------------------|
|        | tert-Butyl peroxyneodecanoate, not more than 42% stable dispersion, in water.                  | 31A         | 1250                      | –5 °C               | +5 °C                 |
|        | tert-Butyl peroxyvalerate, not more than 27% in diluent type B.                                | 31HA1       | 1000                      | +10 °C              | +15 °C                |
|        | .....                                                                                          | 31A         | 1250                      | +10 °C              | +15 °C                |
|        | Cumyl peroxyneodecanoate, not more than 52%, stable dispersion, in water.                      | 31A         | 1250                      | –15 °C              | –5 °C                 |
|        | Dicyclohexylperoxydicarbonate, not more than 42% as a stable dispersion, in water.             | 31A         | 1250                      | +10 °C              | +15 °C                |
|        | Di-(4-tert-butylcyclohexyl) peroxydicarbonate, not more than 42%, stable dispersion, in water. | 31HA1       | 1000                      | +30 °C              | +35 °C                |
|        | Dicetyl peroxydicarbonate, not more than 42%, stable dispersion, in water.                     | 31HA1       | 1000                      | +30 °C              | +35 °C                |
|        | Di-(2-ethylhexyl) peroxydicarbonate, not more than 52%, stable dispersion, in water.           | 31A         | 1250                      | –20 °C              | –10 °C                |
|        | Dimyristyl peroxydicarbonate, not more than 42%, stable dispersion, in water.                  | 31HA1       | 1000                      | +15 °C              | +20 °C                |
|        | Di-(3,5,5-trimethylhexanoyl) peroxide, not more than 38% in diluent type A.                    | 31HA1       | 1000                      | +10 °C              | +15 °C                |
|        | .....                                                                                          | 31A         | 1250                      | +10 °C              | +15 °C                |
|        | Di-(3,5,5-trimethylhexanoyl) peroxide, not more than 52%, stable dispersion, in water.         | 31A         | 1250                      | +10 °C              | +15 °C                |
|        | 1,1,3,3-Tetramethylbutyl peroxyneodecanoate, not more than 52%, stable dispersion, in water.   | 31A         | 1250                      | –5 °C               | +5 °C                 |

(f) IBCs. IBCs are authorized subject to the conditions and limitations of this section if the IBC type is authorized according to paragraph (e) of this section, as applicable, and the IBC conforms to the requirements in subpart O of part 178 of this subchapter at the Packing Group II performance level. Type F organic peroxides or self-reactive substances are not authorized for transportation in IBCs other than those specified, unless approved by the Associate Administrator.

(1) IBCs shall be provided with a device to allow venting during transportation. The inlet to the pressure relief device shall be sited in the vapor space of the IBC under maximum filling conditions during transportation.

(2) To prevent explosive rupture of metal IBCs or composite IBCs with a complete metal casing, the emergency-

relief devices shall be designed to vent all the decomposition products and vapors evolved during self-accelerating decomposition or during a period of not less than one hour of complete fire-engulfment as calculated by the formula in paragraph (h)(3)(v) of this section. The control and emergency temperatures specified in the Organic Peroxide IBC Table are based on a non-insulated IBC.

(g) Organic Peroxide Portable Tank Table. The following Organic Peroxide Portable Tank Table provides certain portable tank requirements and identifies, by technical name, those organic peroxides that are authorized for transportation in the bulk packagings listed in paragraph (h). Organic peroxides listed in this table, provided they meet the specific packaging requirements found in paragraph (h), are not subject

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 173.225**

to the approval provisions of § 173.128 of  
this part.

ORGANIC PEROXIDE PORTABLE TANK TABLE

| UN No.     | Hazardous material                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Minimum test pressure (bar) | Minimum shell thickness (mm-reference steel)<br>See. . . | Bottom opening requirements<br>See. . . | Pressure-relief requirements<br>See. . . | Filling limits                     | Control temperature | Emergency temperature |
|------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|----------------------------------------------------------|-----------------------------------------|------------------------------------------|------------------------------------|---------------------|-----------------------|
| 3109 ..... | ORGANIC PEROXIDE, TYPE F, LIQUID.<br>tert-Butyl hydroperoxide, not more than 72% with water.<br>*Provided that steps have been taken to achieve the safety equivalence of 65% tert-Butyl hydroperoxide and 35% water.<br>Cumyl hydro-peroxide, not more than 90% in diluent type A.<br>Di-tert-butyl peroxide, not more than 32% in diluent type A.<br>Dicumyl peroxide, less than or equal to 100% in diluent type B.<br>Isopropyl cumyl hydro-peroxide, not more than 72% in diluent type A.<br>p-Menthyl hydro-peroxide, not more than 72% in diluent type A.<br>Pinanyl hydro-peroxide, not more than 56% in diluent type A. | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) |                     |                       |
|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) |                     |                       |
|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) |                     |                       |
|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) |                     |                       |
|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) |                     |                       |
|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) |                     |                       |
| 3110 ..... | ORGANIC PEROXIDE, TYPE F, SOLID.<br>Dicumyl peroxide less than or equal to 100% with inert solids.<br>*Maximum quantity per portable tank 2,000 kg.                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) |                     |                       |
| 3119 ..... | ORGANIC PEROXIDE, TYPE F, LIQUID, TEMPERATURE CONTROLLED.<br>tert-Butyl peroxyacetate, not more than 32% in diluent type B.<br>tert-Butyl peroxy-2-ethylhexanoate, not more than 32% in diluent B.<br>tert-Butylperoxypivalate, not more than 27% in diluent type B.                                                                                                                                                                                                                                                                                                                                                             | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) | +30 °C              | +35 °C                |
|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) | +15 °C              | +20 °C                |
|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4                           | § 178.274(d)(2)                                          | § 178.275(d)(3)                         | § 178.275(g)(1)                          | Not more than 90% at 59 °F (15 °C) | +5 °C               | +10 °C                |

|                                                                                   |   |                 |                 |                 |                                    |        |        |
|-----------------------------------------------------------------------------------|---|-----------------|-----------------|-----------------|------------------------------------|--------|--------|
| tert-Butyl peroxy-3,5,5-trimethyl-hexanoate, not more than 32% in diluent type B. | 4 | § 178.274(d)(2) | § 178.275(d)(3) | § 178.275(g)(1) | Not more than 90% at 59 °F (15 °C) | +35 °C | +40 °C |
| Di-(3,5,5-trimethyl-hexanoyl) peroxide, not more than 38% in diluent type A.      | 4 | § 178.274(d)(2) | § 178.275(d)(3) | § 178.275(g)(1) | Not more than 90% at 59 °F (15 °C) | 0 °C   | +5 °C  |
| Peroxyacetic acid, distilled, stabilized, not more than 41%.                      | 4 | § 178.274(d)(2) | § 178.275(d)(3) | § 178.275(g)(1) | Not more than 90% at 59 °F (15 °C) | +30 °C | +35 °C |

(h) *Bulk packagings other than IBCs.* The following bulk packagings are authorized, subject to the conditions and limitations of this section, if the organic peroxide is listed in the Organic Peroxide Portable Tank Table and bulk packagings are authorized, or if the organic peroxide is specifically authorized for transport in a bulk packaging by this paragraph (h), and the bulk packaging conforms to the requirements of this subchapter:

(1) *Rail cars.* Class DOT 103, 104, 105, 109, 111, 112, 114, 115, or 120 fusion-weld tank car tanks are authorized. DOT 103W, 111A60F1 and 111A60W1 tank car tanks must have bottom outlets effectively sealed from inside. Gauging devices are required on DOT 103W tank car tanks. Riveted tank car tanks are not authorized.

(2) *Cargo tanks.* Specification MC 307, MC 310, MC 311, MC 312, DOT 407, and DOT 412 cargo tank motor vehicles with a tank design pressure of at least 172 kPa (25 psig) are authorized.

(3) *Portable tanks.* The following requirements apply to portable tanks intended for the transport of organic peroxides or self-reactive substances. DOT 51, 57, IM 101 portable tanks, and UN portable tanks that conform to the requirements of paragraph (g) of this section, are authorized. Type F organic peroxide or self-reactive substance formulations other than those indicated in the Organic Peroxide Portable Tank Table may be transported in portable tanks if approved by the Associate Administrator. The following conditions also apply:

(i) The portable tank must be designed for a test pressure of at least 0.4 MPa (4 bar).

(ii) The portable tank must be fitted with temperature-sensing devices.

(iii) The portable tank must be fitted with pressure relief devices and emergency-relief devices. Vacuum-relief devices may also be used. Pressure relief devices must operate at pressures determined according to both the properties of the hazardous material and the construction characteristics of the portable tank. Fusible elements are not allowed in the shell.

(iv) The pressure relief devices must consist of reclosing devices fitted to prevent significant build-up within the

portable tank of the decomposition products and vapors released at a temperature of 50 °C (122 °F). The capacity and start-to-discharge pressure of the relief devices must be in accordance with the applicable requirements of this subchapter specified for the portable tank. The pressure relief devices must not allow liquid to escape in the event the portable tank is overturned in a loaded condition.

(v)(A) The emergency-relief devices may be of the reclosing or frangible types, or a combination of the two, designed to vent all the decomposition products and vapors evolved during a period of not less than one hour of complete fire engulfment as calculated by the following formula:

$$q = 70961 F A^{0.82}$$

Where:

q = heat absorption (W)

A = wetted area (m<sup>2</sup>)

F = insulation factor (–)

(B) Insulation factor (F) in the formula in paragraph (h)(3)(v)(A) of this section equals 1 for non-insulated vessels and for insulated vessels F is calculated using the following formula:

$$F = \frac{U (923 - T_{PO})}{47032}$$

Where:

U = K/L = heat transfer coefficient of the insulation (W·m<sup>-2</sup>·K<sup>-1</sup>); where K = heat conductivity of insulation layer (W·m<sup>-1</sup>·K<sup>-1</sup>), and L = thickness of insulation layer (m).  
T<sub>PO</sub> = temperature of material at relieving conditions (K).

(vi) The start-to-discharge pressure of emergency-relief devices must be higher than that specified for the pressure relief devices in paragraph (h)(3)(iv) of this section. The emergency-relief devices must be sized and designed in such a way that the maximum pressure in the shell never exceeds the test pressure of the portable tank.

NOTE TO PARAGRAPH (h)(3)(vi): An example of a method to determine the size of emergency-relief devices is given in Appendix 5 of the UN Manual of Tests and Criteria (IBR, see §171.7 of this subchapter). A second example of a test method for venting sizing is given in the American Institute of Chemical Engineers Process Safety Progress Journal,

June 2002 issue (Vol. 21, No. 2) (Informational materials not requiring incorporation by reference, see § 171.7(b)).

(vii) For insulated portable tanks, the capacity and setting of emergency-relief devices must be determined assuming a loss of insulation from 1% of the surface area.

(viii) Vacuum-relief devices and reclosing devices on portable tanks used for flammable hazardous materials must be provided with flame arresters. Any reduction of the relief capacity caused by the flame arrester must be taken into account and the appropriate relief capacity must be provided.

(ix) Service equipment such as devices and external piping must be designed and constructed so that no hazardous material remains in them after filling the portable tank.

(x) Portable tanks may be either insulated or protected by a sun-shield. If the SADT of the hazardous material in the portable tank is 55 °C (131 °F) or less, the portable tank must be completely insulated. The outer surface must be finished in white or bright metal.

(xi) The degree of filling must not exceed 90% at 15 °C (59 °F).

(xii) DOT 57 metal portable tanks are authorized only for those materials or mixtures of two or more materials that are provided with a reference to Note 9 in Column 8 of the Organic Peroxide Table, found in paragraph (c) of this section. DOT 57 portable tanks must conform to the venting requirements of paragraph (f) of this section. These portable tanks are not subject to any other requirements of paragraph (h) of this section.

(4) For tertiary butyl hydroperoxide (TBHP), each tank car, cargo tank or portable tank must contain 7.6 cm (3.0 inches) low density polyethylene (PE) saddles having a melt index of at least 0.2 grams per 10 minutes (for example see, ASTM D1238, condition E) as part of the lading, with a ratio of PE to TBHP over a range of 0.008 to 0.012 by mass. Alternatively, plastic or metal containers equipped with fusible plugs having a melting point between 69 °C (156 °F) and 71 °C (160 °F) and filled with a sufficient quantity of water to dilute the TBHP to 65% or less by mass may be used. The PE saddles must be vis-

ually inspected after each trip and, at a minimum, once every 12 months, and replaced when discoloration, fracture, severe deformation, or other indication of change is noted.

[69 FR 76159, Dec. 20, 2004, as amended at 70 FR 34398, June 14, 2005; 72 FR 55693, Oct. 1, 2007]

**§ 173.226 Materials poisonous by inhalation, Division 6.1, Packing Group I, Hazard Zone A.**

Division 6.1, Packing Group I, Zone A materials poisonous by inhalation (see § 173.133) must be packed in non-bulk packagings in accordance with the following paragraphs:

(a) In seamless specification or UN cylinders conforming to the requirements of § 173.40.

(b) In 1A1, 1B1, 1H1, 1N1, or 6HA1 drums further packed in a 1A2 or 1H2 drum. Both inner and outer drums must conform to the performance test requirements of subpart M of part 178 of this subchapter at the Packing Group I performance level. The outer drums may be tested either as a package intended to contain inner packagings (combination package) or as a single packaging intended to contain solids or liquids at a mass corresponding to the mass of the assembled packaging system. All outer drums, even those tested to contain inner packaging or as single packagings for solids, must withstand a hydrostatic test pressure of 100 kPa (15 psig). The outer drum must have a minimum thickness of 1.35 mm (0.053 inch) for a 1A2 outer drum or 6.3 mm (0.248 inch) for a 1H2 outer drum. In addition, the inner drum must—

(1) Be capable of satisfactorily withstanding the hydrostatic pressure test in § 178.605 of this subchapter at a test pressure of 300 kPa (45 psig);

(2) Satisfactorily withstand the leakproofness test in § 178.604 of this subchapter using an internal air pressure of at least twice the vapor pressure at 55 °C (131 °F) of the material to be packaged;

(3) Have screw-type closures that are—



**§ 173.226**

**49 CFR Ch. I (10–1–08 Edition)**

(i) Closed and tightened to a torque prescribed by the closure manufacturer, using a properly calibrated device that is capable of measuring torque;

(ii) Physically held in place by any means capable of preventing back-off or loosening of the closure by impact or vibration during transportation; and

(iii) Provided with a cap seal that is properly applied in accordance with the cap seal manufacturer's recommendations and is capable of withstanding an internal pressure of at least 100 kPa (15 psig).

(4) Have a minimum thickness as follows:

(i) For a 1A1 or 1N1 drum, 1.3 mm (0.051 inch);

(ii) For a 1B1 drum, 3.9 mm (0.154 inch);

(iii) For a 1H1 drum, 3.16 mm (0.124 inch); and

(iv) For a 6HA1 drum, the plastic inner container shall be 1.58 mm (0.0622 inch) and the outer steel drum shall be 0.96 mm (0.0378 inch).

(5) Be isolated from the outer drum by a shock-mitigating, non-reactive material, which completely surrounds the inner packaging on all sides.

(c) In combination packagings, consisting of an inner packaging system and an outer packaging, as follows:

(1) Outer packagings:

Steel drum: 1A2

Aluminum drum: 1B2

Metal drum, other than steel or aluminum: 1N2

Plywood drum: 1D

Fiber drum: 1G

Plastic drum: 1H2

Steel box: 4A

Aluminum box: 4B

Natural wood box: 4C1 or 4C2

Plywood box: 4D

Reconstituted wood box: 4F

Fiberboard box: 4G

Expanded plastic box: 4H2

Solid plastic box: 4H2

(2) Inner packaging system. The inner packaging system consists of two packagings:

(i) an impact-resistant receptacle of glass, earthenware, plastic or metal securely cushioned with a non-reactive, absorbent material, and

(A) Capacity of each inner receptacle may not exceed 4 L (1 gallon).

(B) An inner receptacle that has a closure must have a closure which is physically held in place by any means capable of preventing back-off or loosening of the closure by impact or vibration during transportation.

(ii) Packed within a leak-tight packaging of metal or plastic.

(iii) This combination packaging in turn is packed within the outer packaging.

(A) The total amount of liquid contained in the outer packaging may not exceed 16 L (4 gallons).

(iv) the inner packaging system must conform to the performance test requirements of subpart M of part 178 of this subchapter, at the Packaging Group I performance level when subjected to the following tests:

(A) § 178.603—Drop Test

(B) § 178.604—Leakproofness Test

(C) § 178.605—Hydrostatic Pressure Test

(v) The inner packaging system must meet the above tests without the benefit of the outer packaging.

(vi) The leakproofness and hydrostatic pressure test may be conducted on either the inner receptacle or the outer packaging of the inner packaging system.

(vii) In addition to the requirements in § 173.226(b), the outer package must conform to the performance test requirements of subpart M of part 178 of this subchapter, at the Packaging Group I performance level as applicable for the type of package being used.

(d) If approved by the Associate Administrator, 1A1, 1B1, 1H1, 1N1, 6HA1 or 6HH1 drums described in paragraph (b) of this section may be used without being further packed in a 1A2 or 1H2 drum if the shipper loads the material, palletizes the drums, blocks and braces the drums within the transport vehicle and seals the transport vehicle used. Drums may not be stacked (double decked) within the transport vehicle. Shipments must be from one origin to one destination only without any intermediate pickup or delivery.

(e) Prior to reuse, all authorized inner drums must be leakproofness tested and marked in accordance with § 173.28 using a minimum test pressure

as indicated in paragraph (b)(2) of this section.

[69 FR 76172, Dec. 20, 2004, as amended at 71 FR 33881, June 12, 2006]

**§ 173.227 Materials poisonous by inhalation, Division 6.1, Packing Group I, Hazard Zone B.**

(a) In packagings as authorized in § 173.226 and seamless and welded specification cylinders or UN seamless cylinders conforming to the requirements of § 173.40.

(b) 1A1, 1B1, 1H1, 1N1, 6HA1, or 6HH1 drums further packed in a 1A2 or 1H2 drum. Both the inner and outer drums must conform to the performance test requirements of subpart M of part 178 of this subchapter at the Packing Group I performance level. Both the inner and outer drums must conform to the performance test requirements of subpart M of part 178 of this subchapter at the Packing Group I performance level. The outer drums may be tested either as a package intended to contain inner packagings (combination package) or as a single packaging intended to contain solids or liquids at a mass corresponding to the mass of the assembled packaging system. The outer drum must have a minimum thickness of 1.35 mm (0.053 inches) for a 1A2 outer drum or 6.30 mm (0.248 inches) for a 1H2 outer drum. Outer 1A2 and 1H2 drums must withstand a hydrostatic test pressure of 100 kPa (15 psig). Capacity of the inner drum may not exceed 220 liters. In addition, the inner drum must conform to all of the following requirements:

(1) Satisfactorily withstand the leakproofness test in § 178.604 of this subchapter using an internal air pressure of at least two times the vapor pressure at 55 °C (131 °F) of the material to be packaged;

(2) Have screw closures that are—

(i) Closed and tightened to a torque prescribed by the closure manufacturer, using a properly calibrated device that is capable of measuring torque;

(ii) Physically held in place by any means capable of preventing back-off or loosening of the closure by impact or vibration during transportation; and

(iii) Provided with a cap seal that is properly applied in accordance with the

cap seal manufacturer's recommendations and is capable of withstanding an internal pressure of at least 100 kPa (15 psig).

(3) Have a minimum thickness as follows:

(i) For a 1A1 drum, 0.69 mm (0.027 inch);

(ii) For a 1B1 drum, 2.79 mm (0.110 inch);

(iii) For a 1H1 drum, 1.14 mm (0.045 inch); or

(iv) For a 6HA1 drum, the plastic inner container shall be 1.58 mm (0.0625 inch), the outer steel drum shall be 0.70 mm (0.027 inch).

(4) Be isolated from the outer drum by a shock-mitigating, non-reactive material which completely surrounds the inner packaging on all sides.

(5) Prior to reuse, all authorized inner drums must be leakproofness tested and marked in accordance with § 173.28 using a minimum test pressure as indicated in paragraph (b)(1) of this section.

(c) 1A1, 1B1, 1H1, 1N1, 6HA1 or 6HH1 drums described in paragraph (b) of this section may be used without being further packed in a 1A2 or 1H2 drum if the shipper loads the material, blocks and braces the drums within the transport vehicle and seals the transport vehicle used. Drums may not be stacked (double decked) within the transport vehicle. Shipments must be from one origin to one destination only without any intermediate pickup or delivery.

[70 FR 34398, June 14, 2005, as amended at 71 FR 33881, June 12, 2006; 73 FR 57006, Oct. 1, 2008]

**§ 173.228 Bromine pentafluoride or bromine trifluoride.**

(a) Bromine pentafluoride and bromine trifluoride are authorized in packagings as follows:

(1) Specification 3A150, 3AA150, 3B240, 3BN150, 4B240, 4BA240, 4BW240, and 3E1800 cylinders.

(2) UN cylinders as specified in part 178 of this subchapter, except acetylene cylinders and non-refillable cylinders, with a minimum test pressure of 10 bar and a minimum outage of 8 percent by volume. The use of UN tubes and MEGCs is not authorized.

(3) The use of a pressure relief device is not authorized.

## § 173.229

(b) A material in Hazard Zone A must be transported in a seamless specification cylinder conforming to the requirements of § 173.40. However, a welded cylinder filled before October 1, 2002, in accordance with the requirements of this subchapter in effect at the time of filling, may be transported for reprocessing or disposal of the cylinder's contents until December 31, 2003. No cylinder may be equipped with a pressure relief device.

[67 FR 51643, Aug. 8, 2002, as amended at 67 FR 61289, Sept. 30, 2002; 68 FR 24660, May 8, 2003, as amended at 71 FR 33881, June 12, 2006]

### § 173.229 Chloric acid solution or chlorine dioxide hydrate, frozen.

When the § 172.101 table specifies that a hazardous material be packaged in accordance with this section, only 4G fiberboard boxes, with inner packagings of polyethylene or other suitable material, are authorized. Fiberboard boxes must be reinforced and insulated and sufficient dry ice must be used to maintain the hydrate or acid in a frozen state during transportation. Each packaging must conform to the general packaging requirements of subpart B of part 173, and to the requirements of part 178 of this subchapter at the Packing Group I performance level. Transportation is authorized only by private or contract carrier by motor vehicle.

### § 173.230 Fuel cell cartridges containing flammable liquids.

(a) A fuel cell cartridge must be designed and constructed to prevent the fuel it contains from leaking during normal conditions of transportation and be free of electric charge generating components.

(b) Fuel cell cartridges containing flammable liquids, including methanol or methanol/water solutions, must conform to the following:

(1) The fuel cell cartridge design type without its packaging must be shown to pass an internal pressure test at a pressure of 15 psig (100 kPa);

(2) Fuel cell cartridges must be packaged in rigid outer packagings which meet the requirements of part 178 at the Packing Group II performance level and conform to the general pack-

## 49 CFR Ch. I (10–1–08 Edition)

aging requirements of subpart B of part 173.

(c) Fuel cell cartridges packed in or with equipment are excepted from the packaging requirements in paragraph (b)(2) of this section if the cartridges are packed in a strong outer packaging conforming to the requirements of §§ 173.24 and 173.24a. For cartridges installed in equipment, the equipment may be considered the outer packaging if it provides an equivalent level of protection. The packaging need not conform to performance requirements of part 178 of this subchapter. The cartridges must be protected against damage that may be caused by the movement or placement of the equipment and the cartridges within the outer packaging.

(d) Fuel cells intended for transportation in carry-on baggage on board passenger aircraft must also meet the applicable provisions prescribed in § 175.10 of this subchapter.

[71 FR 78633, Dec. 29, 2006, as amended at 73 FR 23366, Apr. 30, 2008]

## Subpart F—Bulk Packaging for Hazardous Materials Other Than Class 1 and Class 7

### § 173.240 Bulk packaging for certain low hazard solid materials.

When § 172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions specified in column 7 of the § 172.101 table.

(a) *Rail cars*: Class DOT 103, 104, 105, 109, 111, 112, 114, 115, or 120 tank car tanks; Class 106 or 110 multi-unit tank car tanks; and metal non-DOT specification, sift-proof tank car tanks and sift-proof closed cars.

(b) *Motor vehicles*: Specification MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, MC 312, MC 330, MC 331, DOT 406, DOT 407, and DOT 412 cargo tank motor vehicles; non-DOT specification, sift-proof cargo tank motor vehicles; and sift-proof closed vehicles.

(c) *Portable tanks and closed bulk bins*. DOT 51, 56, 57 and 60 portable tanks;

IMO type 1, 2 and 5, and IM 101 and IM 102 portable tanks; UN portable tanks; marine portable tanks conforming to 46 CFR part 64; and sift-proof non-DOT Specification portable tanks and closed bulk bins are authorized.

(d) *IBCs*. IBCs are authorized subject to the conditions and limitations of this section provided the IBC type is authorized according to the IBC packaging code specified for the specific hazardous material in Column (7) of the §172.101 Table of this subchapter and the IBC conforms to the requirements in subpart O of part 178 of this subchapter at the Packing Group performance level as specified in Column (5) of the §172.101 Table of this subchapter for the material being transported.

(1) IBCs may not be used for the following hazardous materials:

(i) Packing Group I liquids; and  
(ii) Packing Group I solids that may become liquid during transportation.

(2) The following IBCs may not be used for Packing Group II and III solids that may become liquid during transportation:

(i) Wooden: 11C, 11D and 11F;  
(ii) Fiberboard: 11G;  
(iii) Flexible: 13H1, 13H2, 13H3, 13H4, 13H5, 13L1, 13L2, 13L3, 13L4, 13M1 and 13M2; and  
(iv) Composite: 11HZ2 and 21HZ2.

[Amdt. 173-224, 55 FR 52663, Dec. 21, 1990, as amended at 56 FR 66274, Dec. 20, 1991; Amdt. 173-238, 59 FR 38067, July 26, 1994; Amdt. 173-252, 61 FR 28676, June 5, 1996; 66 FR 33435, June 21, 2001]

EDITORIAL NOTE: Amendments published at 66 FR 45380, Aug. 28, 2001, could not be incorporated because of inaccurate amendatory instruction.

#### **§173.241 Bulk packagings for certain low hazard liquid and solid materials.**

When §172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions specified in column 7 of the §172.101 table.

(a) *Rail cars*: Class DOT 103, 104, 105, 109, 111, 112, 114, 115, or 120 tank car tanks; Class 106 or 110 multi-unit tank

car tanks and AAR Class 203W, 206W, and 211W tank car tanks.

(b) *Cargo tanks*: DOT specification MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, MC 312, MC 330, MC 331, DOT 406, DOT 407, and DOT 412 cargo tank motor vehicles; and non-DOT specification cargo tank motor vehicles suitable for transport of liquids.

(c) *Portable tanks*. DOT Specification 51, 56, 57 and 60 portable tanks; IMO type 1, 2 and 5, and IM 101 and IM 102 portable tanks; UN portable tanks; marine portable tanks conforming to 46 CFR part 64; and non-DOT Specification portable tanks suitable for transport of liquids are authorized. For transportation by vessel, also see §176.340 of this subchapter. For transportation of combustible liquids by vessel, additional requirements are specified in §176.340 of this subchapter.

(d) *IBCs*. IBCs are authorized subject to the conditions and limitations of this section provided the IBC type is authorized according to the IBC packaging code specified for the specific hazardous material in Column (7) of the §172.101 Table of this subchapter and the IBC conforms to the requirements in subpart O of part 178 of this subchapter at the Packing Group performance level as specified in Column (5) of the §172.101 Table for the material being transported.

(1) IBCs may not be used for the following hazardous materials:

(i) Packing Group I liquids; and  
(ii) Packing Group I solids that may become liquid during transportation.

(2) The following IBCs may not be used for Packing Group II and III solids that may become liquid during transportation:

(i) Wooden: 11C, 11D and 11F;  
(ii) Fiberboard: 11G;  
(iii) Flexible: 13H1, 13H2, 13H3, 13H4, 13H5, 13L1, 13L2, 13L3, 13L4, 13M1 and 13M2; and  
(iv) Composite: 11HZ2 and 21HZ2.

[Amdt. 173-224, 55 FR 52663, Dec. 21, 1990, as amended at 56 FR 66275, Dec. 20, 1991; Amdt. 173-238, 59 FR 38067, July 26, 1994; Amdt. 173-252, 61 FR 28676, June 5, 1996; 66 FR 33435, June 21, 2001; 68 FR 57632, Oct. 6, 2003; 70 FR 34075, June 13, 2005.]

EDITORIAL NOTE: Amendments published at 66 FR 45380, Aug. 28, 2001, could not be incorporated because of inaccurate amendatory instruction.

**§ 173.242 Bulk packagings for certain medium hazard liquids and solids, including solids with dual hazards.**

When § 172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions specified in column 7 of the § 172.101 table.

(a) *Rail cars*: Class DOT 103, 104, 105, 109, 111, 112, 114, 115, or 120 tank car tanks; Class 106 or 110 multi-unit tank car tanks and AAR Class 206W tank car tanks.

(b) *Cargo tanks*: Specification MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, MC 312, MC 330, MC 331, DOT 406, DOT 407, and DOT 412 cargo tank motor vehicles. Cargo tanks used to transport Class 3, Packing Group I or II, or Packing Group III with a flash point of less than 38 °C (100 °F); Class 6, Packing Group I or II; and Class 8, Packing Group I or II materials must conform to the following special requirements:

(1) *Pressure relief system*: Except as provided by § 173.33(d), each cargo tank must be equipped with a pressure relief system meeting the requirements of § 178.346–3 or § 178.347–4 of this subchapter. However, pressure relief devices on MC 310, MC 311 and MC 312 cargo tanks must meet the requirements for a Specification MC 307 cargo tank (except for Class 8, Packing Group I and II). Pressure relief devices on MC 330 and MC 331 cargo tanks must meet the requirement in § 178.337–9 of this subchapter.

(2) *Bottom outlets*: DOT 406, DOT 407 and DOT 412 must be equipped with stop-valves meeting the requirements of § 178.345–11 of this subchapter; MC 304, MC 307, MC 310, MC 311, and MC 312 cargo tanks must be equipped with stop-valves capable of being remotely closed within 30 seconds of actuation by manual or mechanic means and (except for Class 8, Packing Group I and II) by a closure activated at a temperature not over 121 °C (250 °F); MC 330 and MC 331 cargo tanks must be equipped

with internal self-closing stop-valves meeting the requirements in § 178.337–11 of this subchapter.

(c) *Portable tanks*. DOT Specification 51, 56, 57 and 60 portable tanks; Specification IM 101, IM 102, and UN portable tanks when a T Code is specified in Column (7) of the § 172.101 Hazardous Materials Table for a specific hazardous material; and marine portable tanks conforming to 46 CFR part 64 are authorized. DOT Specification 57 portable tanks used for the transport by vessel of Class 3, Packaging Group II materials must conform to the following:

(1) *Minimum design pressure*. Each tank must have a minimum design pressure of 62 kPa (9 psig);

(2) *Pressure relief devices*. Each tank must be equipped with at least one pressure relief device, such as a spring-loaded valve or fusible plug, conforming to the following:

(i) Each pressure relief device must communicate with the vapor space of the tank when the tank is in a normal transportation attitude. Shutoff valves may not be installed between the tank opening and any pressure relief device. Pressure relief devices must be mounted, shielded, or drained to prevent the accumulation of any material that could impair the operation or discharge capability of the device;

(ii) Frangible devices are not authorized;

(iii) No pressure relief device may open at less than 34.4 kPa (5 psig);

(iv) If a fusible device is used for relieving pressure, the device must have a minimum area of 1.25 square inches. The device must function at a temperature between 104 °C. and 149 °C. (220 °F. and 300 °F.) and at a pressure less than the design test pressure of the tank, unless this latter function is accomplished by a separate device; and

(v) No relief device may be used which would release flammable vapors under normal conditions of transportation (temperature up to and including 54 °C. (130 °F.)); and

(3) *Venting capacity*. The minimum venting capacity for pressure activated vents must be 6,000 cubic feet of free air per hour (measured at 101.3 kPa (14.7 psi) and 15.6 °C. (60 °F.)) at not more than 34.4 kPa (5 psi). The total

emergency venting capacity (cu. ft./hr.) of each portable tank must be at least that determined from the following table:

| Total surface area square feet <sup>1,2</sup> | Cubic feet free air per hour |
|-----------------------------------------------|------------------------------|
| 20 .....                                      | 15,800                       |
| 30 .....                                      | 23,700                       |
| 40 .....                                      | 31,600                       |
| 50 .....                                      | 39,500                       |
| 60 .....                                      | 47,400                       |
| 70 .....                                      | 55,300                       |
| 80 .....                                      | 63,300                       |
| 90 .....                                      | 71,200                       |
| 100 .....                                     | 79,100                       |
| 120 .....                                     | 94,900                       |
| 140 .....                                     | 110,700                      |
| 160 .....                                     | 126,500                      |

<sup>1</sup> Interpolate for intermediate sizes.

<sup>2</sup> Surface area excludes area of legs.

(4) Unless provided by §173.32(h)(3), an IM 101, 102 or UN portable tank with a bottom outlet and used to transport a liquid hazardous material that is a Class 3, PG I or II, or PG III with a flash point of less than 38 °C (100 °F); Division 5.1 PG I or II; or Division 6.1, PG I or II, must have internal valves conforming to §178.275(d)(3) of this subchapter.

(d) *IBCs.* IBCs are authorized subject to the conditions and limitations of this section provided the IBC type is authorized according to the IBC packaging code specified for the specific hazardous material in Column (7) of the §172.101 Table of this subchapter and the IBC conforms to the requirements in subpart O of part 178 of this subchapter at the Packing Group performance level as specified in Column (5) of the §172.101 Table of this subchapter for the material being transported.

(1) IBCs may not be used for the following hazardous materials:

- (i) Packing Group I liquids; and
- (ii) Packing Group I solids that may become liquid during transportation.

(2) The following IBCs may not be used for Packing Group II and III solids that may become liquid during transportation:

- (i) Wooden: 11C, 11D and 11F;
- (ii) Fiberboard: 11G;
- (iii) Flexible: 13H1, 13H2, 13H3, 13H4, 13H5, 13L1, 13L2, 13L3, 13L4, 13M1 and 13M2; and

(iv) Composite: 11HZ2 and 21HZ2.

[Amdt. 173-224, 55 FR 52663, Dec. 21, 1990, as amended at 56 FR 66275, Dec. 20, 1991; Amdt. 173-238, 59 FR 38067, July 26, 1994; Amdt. 173-243, 60 FR 40038, Aug. 4, 1995; Amdt. 173-246, 60 FR 49110, Sept. 21, 1995; Amdt. 173-252, 61 FR 28676, June 5, 1996; 62 FR 51560, Oct. 1, 1997; 65 FR 50461, Aug. 18, 2000; 66 FR 33435, June 21, 2001; 67 FR 15743, Apr. 3, 2002; 68 FR 32413, May 30, 2003]

EDITORIAL NOTE: Amendments published at 66 FR 45380, Aug. 28, 2001, could not be incorporated because of inaccurate amendatory instruction.

**§ 173.243 Bulk packaging for certain high hazard liquids and dual hazard materials which pose a moderate hazard.**

When §172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions specified in column 7 of the §172.101 table.

(a) *Rail cars:* Class DOT 103, 104, 105, 109, 111, 112, 114, 115, or 120 fusion-welded tank car tanks; and Class 106 or 110 multi-unit tank car tanks.

(b) *Cargo tanks.* Specification MC 304, MC 307, MC 330, MC 331 cargo tank motor vehicles; and MC 310, MC 311, MC 312, DOT 407, and DOT 412 cargo tank motor vehicles with tank design pressure of at least 172.4 kPa (25 psig). Cargo tanks used to transport Class 3 or Division 6.1 materials, or Class 8, Packing Group I or II materials must conform to the following special requirements:

(1) Pressure relief system: Except as provided by §173.33(d), each cargo tank must be equipped with a pressure relief system meeting the requirements of §178.346-3 or 178.347-4 of this subchapter. However, pressure relief devices on MC 310, MC 311 and MC 312 cargo tanks must meet the requirements for a Specification MC 307 cargo tank (except for Class 8, Packing Group I and II). Pressure relief devices on MC 330 and MC 331 cargo tanks must meet the requirement in §178.337-9 of this subchapter.

(2) Bottom outlets: DOT 407 and DOT 412 cargo tanks must be equipped with stop-valves meeting the requirements of §178.345-11 of this subchapter; MC

## § 173.244

## 49 CFR Ch. I (10–1–08 Edition)

304, MC 307, MC 310, MC 311, and MC 312 cargo tanks must be equipped with stop-valves capable of being remotely closed within 30 seconds of actuation by manual or mechanic means and (except for Class 8, Packing Group I and II) by a closure activated at a temperature not over 121 °C (250 °F); MC 330 and MC 331 cargo tanks must be equipped with internal self-closing stop-valves meeting the requirements in § 178.337–11 of this subchapter.

(c) *Portable tanks.* DOT Specification 51 and 60 portable tanks; UN portable tanks and IM 101 and IM 102 portable tanks when a T code is specified in Column (7) of the § 172.101 Table of this subchapter for a specific hazardous material; and marine portable tanks conforming to 46 CFR part 64 with design pressure of at least 172.4 kPa (25 psig) are authorized. Unless provided by § 173.32(h)(3), an IM 101, 102 or UN portable tank, with a bottom outlet, used to transport a liquid hazardous material that is a Class 3, PG I or II, or PG III with a flash point of less than 38 °C (100 °F); Division 5.1, PG I or II; or Division 6.1, PG I or II, must have internal valves conforming to § 178.275(d)(3) of this subchapter.

(d) *IBCs.* IBCs are authorized subject to the conditions and limitations of this section provided the IBC type is authorized according to the IBC packaging code specified for the specific hazardous material in Column (7) of the § 172.101 Table of this subchapter and the IBC conforms to the requirements in subpart O of part 178 of this subchapter at the Packing Group performance level as specified in Column (5) of the § 172.101 Table of this subchapter for the material being transported.

(1) IBCs may not be used for the following hazardous materials:

- (i) Packing Group I liquids; and
- (ii) Packing Group I solids that may become liquid during transportation.

(2) The following IBCs may not be used for Packing Group II and III solids that may become liquid during transportation:

- (i) Wooden: 11C, 11D and 11F;
- (ii) Fiberboard: 11G;
- (iii) Flexible: 13H1, 13H2, 13H3, 13H4, 13H5, 13L1, 13L2, 13L3, 13L4, 13M1 and 13M2; and

(iv) Composite: 11HZ2 and 21HZ2.

(e) A dual hazard material may be packaged in accordance with § 173.242 if:

(1) The subsidiary hazard is Class 3 with a flash point greater than 38 °C (100 °F); or

(2) The subsidiary hazard is Division 6.1, Packing Group III; or

(3) The subsidiary hazard is Class 8, Packaging Group, III.

[Amdt. 173–224, 55 FR 52663, Dec. 21, 1990, as amended at 56 FR 66275, Dec. 20, 1991; Amdt. 173–138, 59 FR 49134, Sept. 26, 1994; Amdt. 173–238, 59 FR 38068, July 26, 1994; Amdt. 173–243, 60 FR 40038, Aug. 4, 1995; Amdt. 173–246, 60 FR 49110, Sept. 21, 1995; Amdt. 173–252, 61 FR 28676, June 5, 1996; 62 FR 51560, Oct. 1, 1997; 64 FR 10780, Mar. 5, 1999; 66 FR 33435, June 21, 2001; 67 FR 15743, Apr. 3, 2002; 68 FR 32413, May 30, 2003]

EDITORIAL NOTE: Amendments published at 66 FR 45380, Aug. 28, 2001, could not be incorporated because of inaccurate amendatory instruction.

### **§ 173.244 Bulk packaging for certain pyrophoric liquids (Division 4.2), dangerous when wet (Division 4.3) materials, and poisonous liquids with inhalation hazards (Division 6.1).**

When § 172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions specified in column 7 of the § 172.101 table.

(a) *Rail cars:* Class DOT 105, 109, 112, 114, or 120 fusion-welded tank car tanks; and Class 106 or 110 multi-unit tank car tanks.

(b) *Cargo tanks:* Specifications MC 330 and MC 331 cargo tank motor vehicles and, except for Division 4.2 materials, MC 312 and DOT 412 cargo tank motor vehicles.

(c) *Portable tanks:* DOT 51 portable tanks and UN portable tanks that meet the requirements of this subchapter, when a T code is specified in Column (7) of the § 172.101 Table of this subchapter for the specific hazardous material, are authorized. Additionally, a DOT 51 or UN portable tank used for Division 6.1 liquids, Hazard Zone A or B, must be certified and stamped to the

ASME Code as specified in § 178.273(b)(6) of this subchapter.

[Amdt. 173–224, 55 FR 52663, Dec. 21, 1990, as amended at 56 FR 66275, Dec. 20, 1991; 57 FR 45463, Oct. 1, 1992; Amdt. 173–252, 61 FR 28676, June 5, 1996; 68 FR 45037, July 31, 2003; 72 FR 55693, Oct. 1, 2007]

**§ 173.245 Bulk packaging for extremely hazardous materials such as poisonous gases (Division 2.3).**

When § 172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions specified in column 7 of the § 172.101 table.

(a) Tank car tanks and multi-unit tank car tanks, when approved by the Associate Administrator.

(b) Cargo tank motor vehicles and portable tanks, when approved by the Associate Administrator.

[Amdt. 173–224, 55 FR 52663, Dec. 21, 1990, as amended at 56 FR 66275, Dec. 20, 1991; 66 FR 45379, Aug. 28, 2001]

**§ 173.247 Bulk packaging for certain elevated temperature materials.**

When § 172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions in column 7 of the § 172.101 table. On or after October 1, 1993, authorized packagings must meet all requirements in paragraph (g) of this section, unless otherwise excepted.

(a) *Rail cars*: Class DOT 103, 104, 105, 109, 111, 112, 114, 115, or 120 tank car tanks; Class DOT 106, 110 multi-unit tank car tanks; AAR Class 203W, 206W, 211W tank car tanks; and non-DOT specification tank car tanks equivalent in structural design and accident damage resistance to specification packagings.

(b) *Cargo tanks*: Specification MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, MC 312, MC 330, MC 331 cargo tank motor vehicles; DOT 406, DOT 407, DOT 412 cargo tank motor vehicles; and non-DOT specification cargo tank motor vehi-

cles equivalent in structural design and accident damage resistance to specification packagings. A non-DOT specification cargo tank motor vehicle constructed of carbon steel which is in elevated temperature material service is excepted from § 178.345–7(d)(5) of this subchapter.

(c) *Portable tanks*. DOT Specification 51, 56, 57 and 60 portable tanks; IM 101 and IM 102 portable tanks; UN portable tanks; marine portable tanks conforming to 46 CFR part 64; metal IBCs and non-specification portable tanks equivalent in structural design and accident damage resistance to specification packagings are authorized.

(d) *Crucibles*: Nonspecification crucibles designed and constructed such that the stress in the packaging does not exceed one fourth (0.25) of the ultimate strength of the packaging material at any temperature within the design temperature range. Stress is determined under a load equal to the sum of the static or working pressure in combination with the loads developed from accelerations and decelerations incident to normal transportation. For highway transportation, these forces are assumed to be “1.7g” vertical, “0.75g” longitudinal, and “0.4g” transverse, in reference to the axes of the transport vehicle. Each accelerative or decelerative load may be considered separately.

(e) *Kettles*: A kettle, for the purpose of this section, is a bulk packaging (portable tank or cargo tank) having a capacity not greater than 5678 L (1500 gallons) with an integral heating apparatus used for melting various bituminous products such as asphalt. Kettles used for the transport of asphalt or bitumen are subject to the following requirements:

(1) *Low stability kettles*. Kettles with a ratio of track-width to fully loaded center of gravity (CG) height less than 2.5 must meet all requirements of paragraph (g) of this section (track-width is the distance measured between the outer edge of the kettle tires; CG height is measured perpendicular from the road surface).

(2) *High stability kettles*. (i) Kettles with a total capacity of less than 2650 L (700 gallons) and a ratio of track-width to fully loaded CG height of 2.5



or more are excepted from all requirements of paragraph (g)(2) of this section and the rollover protection requirements of paragraph (g)(6) of this section, if closures meet the requirements of paragraph (e)(2)(iii) of this section.

(ii) Kettles with a total capacity of 2650 L (700 gallons) or more and a ratio of track-width to fully loaded CG height of 2.5 or more are excepted from the “substantially leak tight” requirements of paragraph (g)(2) of this section and the rollover protection requirements of paragraph (g)(6) of this section if closures meet the requirements of paragraph (e)(2)(iii) of this section.

(iii) Closures must be securely closed during transportation. Closures also must be designed to prevent opening and the expulsion of lading in a rollover accident.

(f) *Other bulk packagings:* Bulk packagings, other than those specified in paragraphs (a) through (e) of this section, which are used for the transport of elevated temperature materials, must conform to all requirements of paragraph (g) of this section on or after October 1, 1993.

(g) *General requirements.* Bulk packagings authorized or used for transport of elevated temperature materials must conform to the following requirements:

(1) *Pressure and vacuum control equipment.* When pressure or vacuum control equipment is required on a packaging authorized in this section, such equipment must be of a self-reclosing design, must prevent package rupture or collapse due to pressure, must prevent significant release of lading due to packaging overturn or splashing or surging during normal transport conditions, and may be external to the packaging.

(i) Pressure control equipment is not required if pressure in the packaging would increase less than 10 percent as a result of heating the lading from the lowest design operating temperature to a temperature likely to be encountered if the packaging were engulfed in a fire. When pressure control equipment is required, it must prevent rupture of the packaging from heating, including fire engulfment.

(ii) Vacuum control equipment is not required if the packaging is designed to withstand an external pressure of 100 kPa (14.5 psig) or if pressure in the packaging would decrease less than 10 percent as a result of the lading cooling from the highest design operating temperature to the lowest temperature incurred in transport. When vacuum control equipment is required, it must prevent collapse of the packaging from a cooling-induced pressure differential.

(iii) When the regulations require a reclosing pressure relief device, the lading must not render the devices inoperable (i.e. from clogging, freezing, or fouling). If the lading affects the proper operation of the device, the packaging must have:

(A) A safety relief device incorporating a frangible disc or a permanent opening, each having a maximum effective area of 22 cm<sup>2</sup> (3.4 in.<sup>2</sup>), for transportation by highway;

(B) For transportation of asphalt by highway, a safety relief device incorporating a frangible disc or a permanent opening, each having a maximum effective area of 48 cm<sup>2</sup> (7.4 in.<sup>2</sup>); or

(C) For transportation by rail, a non-reclosing pressure relief device incorporating a rupture disc conforming to the requirements of § 179.15 of this subchapter.

(iv) Reclosing pressure relief devices, rupture discs or permanent openings must not allow the release of lading during normal transportation conditions (i.e., due to splashing or surging).

(2) *Closures.* All openings, except permanent vent openings authorized in paragraph (g)(1)(iii) of this section, must be securely closed during transportation. Packagings must be substantially leak-tight so as not to allow any more than dripping or trickling of a non-continuous flow when overturned. Closures must be designed and constructed to withstand, without exceeding the yield strength of the packaging, twice the static loading produced by the lading in any packaging orientation and at all operating temperatures.

(3) *Strength.* Each packaging must be designed and constructed to withstand, without exceeding the yield strength of the packaging, twice the static loading

produced by the lading in any orientation and at all operating temperatures.

(4) *Compatibility.* The packaging and lading must be compatible over the entire operating temperature range.

(5) *Markings.* In addition to any other markings required by this subchapter, each packaging must be durably marked in a place readily accessible for inspection in characters at least 4.8 mm (3/16 inch) with the manufacturer's name, date of manufacture, design temperature range, and maximum product weight (or "load limit" for tank cars) or volumetric capacity.

(6) *Accident damage protection.* For transportation by highway, external loading and unloading valves and closures must be protected from impact damage resulting from collision or overturn. Spraying equipment and the road oil application portion of a packaging are excepted from this requirement.

(7) *New construction.* Specification packagings that are being manufactured for the transport of elevated temperature materials must be authorized for current construction.

(h) *Exceptions—(1) General.* Packagings manufactured for elevated temperature materials service prior to October 1, 1993, which are not in full compliance with the requirements in paragraph (g) of this section, may continue in service if they meet the applicable requirements of subparts A and B of this part and meet the closure requirements in paragraph (g)(2) of this section by March 30, 1995.

(2) *Kettles.* Kettles in service prior to October 1, 1993, which are used to transport asphalt or bitumen, are excepted from specific provisions of this section as follows:

(i) Kettles with a total capacity of less than 2650 L (700 gallons), which are not in full compliance with the requirements of paragraph (g) of this section, may continue in elevated temperature material service if they meet the applicable requirements of subparts A and B of this part and if, after March 30, 1995, closures are secured during transport to resist opening in an overturn.

(ii) Kettles with a total capacity of 2650 L (700 gallons) or more, which are not in full compliance with the re-

quirements of paragraph (g) of this section, may continue in elevated temperature material service if they meet the applicable requirements of subparts A and B of this part and if, after March 30, 1995, closures are secured during transport to resist opening in an overturn and no opening exceeds 46 cm<sup>2</sup> (7.1 in<sup>2</sup>).

(3) *Molten metals and molten glass.* This section does not apply to packagings used for transportation of molten metals and molten glass by rail when movement is restricted to operating speeds less than 15 miles per hour. (See §172.203(g)(3) of this subchapter for shipping paper requirements.)

(4) *Solid elevated temperature materials.* A material which meets the definition of a solid elevated temperature material is excepted from all requirements of this subchapter except §172.325 of this subchapter.

[Amdt. 173-227, 58 FR 3349, Jan. 8, 1993, as amended by Amdt. 173-234, 58 FR 51532, Oct. 1, 1993; 173-237, 59 FR 28493, June 2, 1994; 62 FR 51560, Oct. 1, 1997; 63 FR 52849, Oct. 1, 1998; 65 FR 50461, Aug. 18, 2000; 66 FR 33436, June 21, 2001; 66 FR 45382, Aug. 28, 2001; 67 FR 61013, Sept. 27, 2002]

#### § 173.249 Bromine.

When §172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of part 173 of this subchapter and the special provisions specified in column 7 of the §172.101 table.

(a) Class DOT 105A300W or 105A500W tank cars. Class 105A500W tank cars may be equipped with manway cover plates, pressure relief valves, vent valves, and loading/unloading valves that are required on Class 105A-300W tank cars. Tank cars must conform with paragraphs (d) through (f) of this section.

(b) Specification MC 310, MC 311, MC 312 or DOT 412 cargo tank motor vehicles conforming with paragraphs (d) through (f) of this section. The total quantity in one tank may not be less than 88 percent nor more than 96 percent of the volume of the tank. Cargo tanks in bromine service built prior to August 31, 1991 may continue in service

## § 173.300

under the requirements contained in § 173.252(a)(4) of this part in effect on September 30, 1991.

(c) UN portable tanks conforming to tank code T22 (see § 172.102 of this subchapter) or specification IM 101 portable tanks conforming with paragraphs (d) through (f) of this section. Except when transported as a residue, the total quantity in one tank may not be less than 88% nor more than 92% of the volume of the tank.

(d) The tank must be made from nickel-clad or lead-lined steel plate. Nickel cladding or lead lining must be on the inside of the tank. Nickel cladding must comprise at least 20 percent of the required minimum total thickness. Nickel cladding must conform to ASTM B 162 (IBR, see § 171.7 of this subchapter). Lead lining must be at least 4.763 mm (0.188 inch) thick. All tank equipment and appurtenances in contact with the lading must be lined or made from metal not subject to deterioration by contact with lading.

(e) Maximum filling density is 300 percent of the tank's water capacity. Minimum filling density is 287 percent of the tank's water capacity. Maximum water capacity is 9,253 kg (20,400 pounds) for DOT 105A300W tank cars. Maximum quantity of lading in DOT 105A300W tank cars is 27,216 kg (60,000 pounds). Maximum water capacity is 16,964 kg (37,400 pounds) for DOT 105A500W tank cars and DOT 105A500W tank cars equipped as described in paragraph (a) of this section. Maximum quantity of lading in DOT 105A500W tank cars is 49,895 kg (110,000 pounds).

(f) Tank shell and head thickness for cargo tank motor vehicles and portable tanks must be at least 9.5 mm (0.375 inch) excluding lead lining.

[Amdt. 173-224, 55 FR 52663, Dec. 21, 1990, as amended at 56 FR 66275, Dec. 20, 1991; 68 FR 75745, Dec. 31, 2003; 69 FR 76174, Dec. 20, 2004]

## 49 CFR Ch. I (10-1-08 Edition)

### Subpart G—Gases; Preparation and Packaging

#### § 173.300 [Reserved]

#### § 173.301 General requirements for shipment of compressed gases and other hazardous materials in cylinders, UN pressure receptacles and spherical pressure vessels.

(a) *General qualifications for use of cylinders.* Unless otherwise stated, as used in this section, the term “cylinder” includes a UN pressure receptacle. As used in this subpart, filled or charged means an introduction or presence of a hazardous material in a cylinder. A cylinder filled with a Class 2 hazardous material (gas) and offered for transportation must meet the requirements in this section and §§ 173.301a through 173.305, as applicable.

(1) Compressed gases must be in UN pressure receptacles built in accordance with the UN standards or in metal cylinders and containers built in accordance with the DOT and ICC specifications and part 178 of this subchapter in effect at the time of manufacture, and requalified and marked as prescribed in subpart C in part 180 of this subchapter, if applicable. The DOT and ICC specifications authorized for use are as follows:

#### Packagings

2P  
2Q  
ICC-3<sup>1</sup>  
3A  
3AA  
3AL  
3AX  
3A480X  
3AAX  
3B  
3BN  
3E  
3HT  
3T  
4AA480  
4B  
4B240ET  
4BA  
4BW  
4D  
4DA  
4DS  
4E

<sup>1</sup>Use of existing cylinders is authorized. New construction is not authorized.

4L  
8  
8AL  
39

(2) A cylinder must be filled in accordance with this part. Before each filling of a cylinder, the person filling the cylinder must visually inspect the outside of the cylinder. A cylinder that has a crack or leak, is bulged, has a defective valve or a leaking or defective pressure relief device, or bears evidence of physical abuse, fire or heat damage, or detrimental rusting or corrosion, may not be filled and offered for transportation. A cylinder may be repaired and requalified only as prescribed in subpart C of part 180 of this subchapter.

(3) Pressure relief devices must be tested for leaks before a filled cylinder is shipped from the cylinder filling plant. It is expressly forbidden to repair a leaking fusible plug device where the leak is through the fusible metal or between the fusible metal and the opening in the plug body, except by removal and replacement of the pressure relief device.

(4) A cylinder that previously contained a Class 8 material must be requalified in accordance with § 180.205(e) of this subchapter.

(5) When a cylinder with a marked pressure limit is prescribed, another cylinder made under the same specification but with a higher marked pressure limit is authorized. For example, a cylinder marked "DOT-4B500" may be used when "DOT-4B300" is specified.

(6) No person may fill a cylinder overdue for periodic requalification with a hazardous material and then offer it for transportation. The prohibition against offering a cylinder for transportation that is overdue for periodic requalification does not apply to a cylinder filled prior to the requalification due date.

(7) A cylinder with an authorized service life may not be offered for transportation in commerce after its authorized service life has expired. However, a cylinder in transportation or a cylinder filled prior to the expiration of its authorized service life may be transported for reprocessing or disposal of the cylinder's contents. After emptying, the cylinder must be con-

demned in accordance with § 180.205 of this subchapter.

(8) The pressure of the hazardous material at 55 °C (131 °F) may not exceed 5/4 of the service pressure of the cylinder. Sufficient outage must be provided so the cylinder will not be liquid full at 55 °C (131 °F).

(9) Specification 2P, 2Q, 3E, 3HT, spherical 4BA, 4D, 4DA, 4DS, and 39 cylinders must be packed in strong non-bulk outer packagings. The outside of the combination packaging must be marked with an indication that the inner packagings conform to the prescribed specifications.

(10) Any person who installs a valve into an aluminum cylinder in oxygen service must verify the valve and the cylinder have the same thread type.

(b) *Cylinder markings.* Required markings on a cylinder must be legible and must meet the applicable requirements of subpart C of part 180 of this subchapter. Additional information may be marked on the cylinder provided it does not affect the required markings prescribed in the applicable cylinder specification.

(c) *Toxic gases and mixtures.* Cylinders containing toxic gases and toxic gas mixtures meeting the criteria of Division 2.3 Hazard Zone A or B must conform to the requirements of § 173.40 and CGA S-1.1 (compliance with paragraph 9.1.1.1 is not required) (IBR; see § 171.7 of this subchapter) and CGA S-7 (IBR; see § 171.7 of this subchapter). A DOT 39 cylinder, UN non-refillable cylinder, or a UN composite cylinder certified to ISO-11119-3 may not be used for a toxic gas or toxic gas mixture meeting the criteria for Division 2.3, Hazard Zone A or B.

(d) *Gases capable of combining chemically.* A filled cylinder may not contain any gas or material capable of combining chemically with the cylinder's contents or with the cylinder's material of construction, so as to endanger the cylinder's serviceability.

(e) *Ownership of cylinder.* A cylinder filled with a hazardous material may not be offered for transportation unless it was filled by the owner of the cylinder or with the owner's consent.

(f) *Pressure relief device systems.* (1) Except as provided in paragraphs (f)(5),

(f)(6), and (l)(2) of this section, a cylinder filled with a gas and offered for transportation must be equipped with one or more pressure relief devices sized and selected as to type, location, and quantity, and tested in accordance with CGA S–1.1 (compliance with paragraph 9.1.1.1 is not required) and CGA S–7. The pressure relief device must be capable of preventing rupture of the normally filled cylinder when subjected to a fire test conducted in accordance with CGA C–14 (IBR, see § 171.7 of this subchapter), or, in the case of an acetylene cylinder, CGA C–12 (IBR, see § 171.7 of this subchapter).

(2) After December 31, 2003, a pressure relief device, when installed, must be in communication with the vapor space of a cylinder containing a Division 2.1 (flammable gas) material.

(3) For a specification 3, 3A, 3AA, 3AL, 3AX, 3AXX, 3B, 3BN, or 3T cylinder filled with gases in other than Division 2.2 (except oxygen and oxidizing gases transported by aircraft, see §§ 173.302(f) and 173.304(f)), beginning with the first requalification due after December 31, 2003, the burst pressure of a CG–1, CG–4, or CG–5 pressure relief device must be at test pressure with a tolerance of plus zero to minus 10%. An additional 5% tolerance is allowed when a combined rupture disk is placed inside a holder. This requirement does not apply if a CG–2, CG–3, or CG–9 thermally activated relief device or a CG–7 reclosing pressure valve is used on the cylinder.

(4) A pressure relief device is required on a DOT 39 cylinder regardless of cylinder size or filled pressure. A DOT 39 cylinder used for liquefied Division 2.1 materials must be equipped with a metal pressure relief device. Fusible pressure relief devices are not authorized on a DOT 39 cylinder containing a liquefied gas.

(5) A pressure relief device is not required on—

(i) A cylinder 305 mm (12 inches) or less in length, exclusive of neck, and 114 mm (4.5 inches) or less in outside diameter, except when the cylinder is filled with a liquefied gas for which this part requires a service pressure of 1800 psig or higher or a nonliquefied gas to a pressure of 1800 psig or higher at 21 °C (70 °F);

(ii) A cylinder with a water capacity of less than 454 kg (1000 lbs) filled with a nonliquefied gas to a pressure of 300 psig or less at 21 °C (70 °F), except for a DOT 39 cylinder or a cylinder used for acetylene in solution; or

(iii) A cylinder containing a Class 3 or a Class 8 material without pressurization, unless otherwise specified for the hazardous material.

(6) A pressure relief device is prohibited on a cylinder filled with a Division 2.3 or 6.1 material in Hazard Zone A.

(iv) A UN pressure receptacle transported in accordance with paragraph (k) or (l) or this section.

(g) *Manifolding cylinders in transportation.* (1) Cylinder manifolding is authorized only under conditions prescribed in this paragraph (g). Manifolded cylinders must be supported and held together as a unit by structurally adequate means. Except for Division 2.2 materials, each cylinder must be equipped with an individual shutoff valve that must be tightly closed while in transit. Manifold branch lines must be sufficiently flexible to prevent damage to the valves that otherwise might result from the use of rigid branch lines. Each cylinder must be individually equipped with a pressure relief device as required in paragraph (f) of this section, except that pressure relief devices on manifolded horizontal cylinders that are mounted on a motor vehicle or framework may be selected as to type, location, and quantity according to the lowest marked pressure limit of an individual cylinder in the manifolded unit. The pressure relief devices selected for the manifolded unit must have been tested in accordance with CGA S–1.1 and CGA S–7. Pressure relief devices on manifolded horizontal cylinders filled with a compressed gas must be arranged to discharge unobstructed to the open air. In addition, for Division 2.1 (flammable gas) material, the pressure relief devices (PRDs) must be arranged to discharge upward to prevent any escaping gas from contacting personnel or any adjacent cylinders. Valves and pressure relief devices on manifolded cylinders filled

with a compressed gas must be protected from damage by framing, a cabinet or other method. Manifolding is authorized for cylinders containing the following gases:

(i) Nonliquefied (permanent) compressed gases authorized by § 173.302.

(ii) Liquefied compressed gases authorized by § 173.304. Each manifolded cylinder containing a liquefied compressed gas must be separately filled and means must be provided to ensure no interchange of cylinder contents can occur during transportation.

(iii) Acetylene as authorized by § 173.303.

(2) For the checking of tare weights or replacing solvent, the cylinder must be removed from the manifold. This requirement is not intended to prohibit filling acetylene cylinders while manifolded.

(h) *Cylinder valve protection.* UN pressure receptacles must meet the valve protection requirements in § 173.301b(c). A DOT specification cylinder used to transport a hazardous material must meet the requirements specified in this paragraph (h).

(1) The following specification cylinders are not subject to the cylinder valve protection requirements in this paragraph (h):

(i) A cylinder containing only a Division 2.2 material without a Division 5.1 subsidiary hazard;

(ii) A cylinder containing a Class 8 liquid corrosive only to metal;

(iii) A cylinder with a water capacity of 4.8 liters (293 in<sup>3</sup>) or less containing oxygen, compressed;

(iv) A cylinder containing oxygen, refrigerated liquid (cryogenic liquid);

(v) A Medical E cylinder with a water capacity of 4.9 liters (300 in<sup>3</sup>) or less;

(vi) A fire extinguisher; or

(vii) A "B" style cylinder with a capacity of 40 ft<sup>3</sup> (1.13 m<sup>3</sup>) or an "MC" style cylinder with a capacity of 10 ft<sup>3</sup> (0.28 m<sup>3</sup>) containing acetylene.

(2) For cylinders manufactured before October 1, 2007, a cylinder must have its valves protected by one of the following methods:

(i) By equipping the cylinder with securely attached metal caps of sufficient strength to protect valves from damage during transportation;

(ii) By boxing or crating the cylinders so as to protect valves from damage during transportation;

(iii) By constructing the cylinder so that the valve is recessed into the cylinder or otherwise protected to the extent that it will not be subjected to a blow when the container is dropped onto a flat surface; or

(iv) By loading the cylinders in an upright position and securely bracing the cylinders in rail cars or motor vehicles, when loaded by the consignor and unloaded by the consignee.

(3) For cylinders manufactured on or after October 1, 2007, each cylinder valve assembly must be of sufficient strength or protected such that no leakage occurs when a cylinder with the valve installed is dropped 1.8 m (6 ft.) or more onto a non-yielding surface, such as concrete or steel, impacting the valve assembly or protection device at an orientation most likely to cause damage. The cylinder valve assembly protection may be provided by any method meeting the performance requirement in this paragraph (h)(3). Examples include:

(i) Equipping the cylinder with a securely attached metal cap.

(ii) Packaging the cylinder in a box, crate, or other strong outside packaging conforming to the requirements of § 173.25.

(iii) Constructing the cylinder such that the valve is recessed into the cylinder or otherwise protected.

(i) *Cylinders mounted on motor vehicles or in frames.* MEGCs must conform to the requirements in § 173.312. DOT specification cylinders mounted on motor vehicles or in frames must conform to the requirements specified in this paragraph (i). Seamless DOT specification cylinders longer than 2 m (6.5 feet) are authorized for transportation only when horizontally mounted on a motor vehicle or in an ISO framework or other framework of equivalent structural integrity. Cylinders may not be transported by rail in container on freight car (COFC) or trailer on flat car (TOFC) service except under conditions approved by the Associate Administrator for Safety, Federal Railroad Administration. The cylinder must be configured as follows:

## § 173.301a

## 49 CFR Ch. I (10–1–08 Edition)

(1) Each cylinder must be fixed at one end of the vehicle or framework with provision for thermal expansion at the opposite end attachment;

(2) The valve and pressure relief device protective structure must be sufficiently strong to withstand a force equal to twice the weight of the cylinder and framework assembly with a safety factor of four, based on the ultimate strength of the material used; and

(3) The pressure relief device must be arranged to discharge unobstructed to the open air. In addition, for Division 2.1 (flammable gas) material, the pressure relief devices must be arranged to discharge upward to prevent any escaping gas from contacting personnel or any adjacent cylinders.

(j) *Non-specification cylinders in domestic use.* Except as provided in §§ 171.12(a) and 173.23(g) of this subchapter, a filled cylinder manufactured to other than a DOT specification or a UN standard in accordance with part 178 of this subchapter, or a DOT exemption or special permit cylinder or a cylinder used as a fire extinguisher in conformance with § 173.309(a), may not be transported to, from, or within the United States.

(k) *Metal attachments.* Metal attachments to cylinders must have rounded or chamfered corners, or be otherwise protected, so as to prevent the likelihood of causing puncture or damage to other hazardous materials packages. This requirement applies to anything temporarily or permanently attached to the cylinder, such as metal skids.

(o) *Cylinders made of aluminum alloy 6351–T6.* A DOT 3AL cylinder manufactured of aluminum alloy 6351–T6 may not be filled and offered for transportation or transported with pyrophoric gases. The use of UN cylinders manufactured of aluminum alloy 6351–T6 is prohibited.

[67 FR 51643, Aug. 8, 2002, as amended at 67 FR 61289, Sept. 30, 2002; 68 FR 24660, May 8, 2003; 68 FR 32680, June 2, 2003; 68 FR 75742, 75745, Dec. 31, 2003; 70 FR 34075, June 13, 2005; 70 FR 73165, Dec. 9, 2005; 71 FR 33881, June 12, 2006; 71 FR 54395, Sept. 14, 2006; 71 FR 51127, Aug. 29, 2006; 71 FR 78633, Dec. 29, 2006; 72 FR 25177, May 3, 2007; 72 FR 55098, Sept. 28, 2007; 73 FR 4718, Jan. 28, 2008]

### § 173.301a Additional general requirements for shipment of specification cylinders.

(a) *General.* The requirements in this section are in addition to the requirements in § 173.301 and apply to the shipment of gases in specification cylinders.

(b) *Authorized cylinders not marked with a service pressure.* For authorized cylinders not marked with a service pressure, the service pressure is designated as follows:

| Specification marking | Service Pressure psig |
|-----------------------|-----------------------|
| 3 .....               | 1800                  |
| 3E .....              | 1800                  |
| 8 .....               | 250                   |

(c) *Cylinder pressure at 21 °C (70 °F).* The pressure in a cylinder at 21 °C (70 °F) may not exceed the service pressure for which the cylinder is marked or designated, except as provided in § 173.302a(b). For certain liquefied gases, the pressure at 21 °C (70 °F) must be lower than the marked service pressure to avoid having a pressure at a temperature of 55 °C (131 °F) that is greater than permitted.

(d) *Cylinder pressure at 55 °C (131 °F).* The pressure in a cylinder at 55 °C (131 °F) may not exceed 5/4 times the service pressure, except:

(1) For a cylinder filled with acetylene, liquefied nitrous oxide, or carbon dioxide.

(2) For a cylinder filled in accordance with § 173.302a(b), the pressure in the cylinder at 55 °C (131 °F) may not exceed 5/4 times the filling pressure.

(3) The pressure at 55 °C (131 °F) of Hazard Zone A and, after December 31, 2003, Hazard Zone B materials, may not exceed the service pressure of the cylinder. Sufficient outage must be provided so that the cylinder will not be liquid full at 55 °C (131 °F).

(e) *Grandfather clause.* A cylinder in domestic use prior to the date on which the specification for the cylinder was first made effective may be used if the cylinder has been properly tested and

otherwise conforms to the requirements applicable to the gas with which it is charged.

[67 FR 51645, Aug. 8, 2002, as amended at 67 FR 61289, Sept. 30, 2002; 68 FR 24661, May 8, 2003]

**§ 173.301b Additional general requirements for shipment of UN pressure receptacles.**

(a) *General.* The requirements of this section are in addition to the requirements in § 173.301 and apply to the shipment of gases in UN pressure receptacles. A UN pressure receptacle, including closures, must conform to the design, construction, inspection and testing requirements specified in parts 178 and 180 of this subchapter, as applicable. Bundles of cylinders must conform to the requirements in § 178.70(e) of this subchapter.

(1) A UN pressure receptacle may not be filled and offered for transportation when damaged to such an extent that the integrity of the UN pressure receptacle or its service equipment may be affected. Prior to filling, the service equipment must be examined and found to be in good working condition (see § 178.70(d) of this subchapter). In addition, the required markings must be legible on the pressure receptacle.

(2) The gases or gas mixtures must be compatible with the UN pressure receptacle and valve materials as prescribed for metallic materials in ISO 11114-1 (IBR, see § 171.7 of this subchapter) and for non-metallic materials in ISO 11114-2 (IBR, see § 171.7 of this subchapter).

(3) A refillable UN pressure receptacle may not be filled with a gas or gas mixture different from that previously contained in the UN pressure receptacle unless the necessary operations for change of gas service have been performed in accordance with ISO 11621 (IBR, see § 171.7 of this subchapter).

(4) When a strong outer packaging is prescribed, for example as provided by paragraph (c)(2)(vi) or (d)(1) of this section, the UN pressure receptacles must be protected to prevent movement. Unless otherwise specified in this part, more than one UN pressure receptacle may be enclosed in the strong outer packaging.

(b) *Individual shut-off valves and pressure relief devices.* Except for Division 2.2 permanent gases, each UN pressure receptacle must be equipped with an individual shutoff valve that must be tightly closed while in transit. Each UN pressure receptacle must be individually equipped with a pressure relief device as prescribed by § 173.301(f), except that pressure relief devices on bundles of cylinders or manifolded horizontal cylinders must have a set-to-discharge pressure that is based on the lowest marked pressure of any cylinder in the bundle or manifolded unit.

(c) *Pressure receptacle valve requirements.* (1) When the use of a valve is prescribed, the valve must conform to the requirements in ISO 10297 (IBR, see § 171.7 of this subchapter).

(2) A UN pressure receptacle must have its valves protected from damage that could cause inadvertent release of the contents of the UN pressure receptacle by one of the following methods:

(i) By constructing the pressure receptacle so that the valves are recessed inside the neck of the UN pressure receptacle and protected by a threaded plug or cap;

(ii) By equipping the UN pressure receptacle with a valve cap conforming to the requirements in ISO 11117 (IBR, see § 171.7 of this subchapter). The cap must have vent-holes of sufficient cross-sectional area to evacuate the gas if leakage occurs at the valve;

(iii) By protecting the valves by shrouds or guards conforming to the requirements in ISO 11117;

(iv) By using valves designed and constructed with sufficient inherent strength to withstand damage in accordance with Annex B of ISO 10297;

(v) By enclosing the UN pressure receptacles in frames, e.g., bundles of cylinders; or

(vi) By packing the UN pressure receptacles in a strong outer package, such as a box or crate, capable of meeting the drop test specified in § 178.603 of this subchapter at the Packing Group I performance level.

(d) *Non-refillable UN pressure receptacles.* Non-refillable UN pressure receptacles must conform to the following requirements:



(1) The receptacles must be transported as an inner package of a combination package;

(2) The receptacle must have a water capacity not exceeding 1.25 L when used for a flammable or toxic gas; and

(3) The receptacle is prohibited for Hazard Zone A material.

(e) *Pyrophoric gases.* A UN pressure receptacle must have valves equipped with gas-tight plugs or caps when used for pyrophoric or flammable mixtures of gases containing more than 1% pyrophoric compounds.

(f) *Hydrogen bearing gases.* A steel UN pressure receptacle bearing an “H” mark must be used for hydrogen bearing gases or other embrittling gases that have the potential of causing hydrogen embrittlement.

(g) *Composite cylinders in underwater use.* A composite cylinder certified to ISO–11119–2 or ISO–11119–3 may not be used for underwater applications unless the cylinder is manufactured in accordance with the requirements for underwater use and is marked “UW” as prescribed in §178.71(o)(17) of this subchapter.

[71 FR 33882, June 12, 2006, as amended at 71 FR 54395, Sept. 14, 2006]

**§ 173.302 Filling of cylinders with non-liquefied (permanent) compressed gases.**

(a) *General requirements.* A cylinder filled with a non-liquefied compressed gas (except gas in solution) must be offered for transportation in accordance with the requirements of this section and §173.301. In addition, a DOT specification cylinder must meet the requirements in §§173.301a, 173.302a and 173.305, as applicable. UN pressure receptacles must meet the requirements in §§173.301b and 173.302b, as applicable. Where more than one section applies to a cylinder, the most restrictive requirements must be followed.

(b) *Aluminum cylinders in oxygen service.* Each aluminum cylinder filled with oxygen must meet all of the following conditions:

(1) Metallic portions of a valve that may come into contact with the oxygen in the cylinder must be constructed of brass or stainless steel.

(2) Except for UN cylinders, each cylinder opening must be configured with straight threads only.

(3) Each UN pressure receptacle must be cleaned in accordance with the requirements of ISO 11621 (IBR, see §171.7 or this subchapter). Each DOT cylinder must be cleaned in accordance with the requirements of GSA Federal Specification RR–C–901D, paragraphs 3.3.1 and 3.3.2 (IBR, see §171.7 of this subchapter). Cleaning agents equivalent to those specified in Federal Specification RR–C–901D may be used provided they do not react with oxygen. One cylinder selected at random from a group of 200 or fewer and cleaned at the same time must be tested for oil contamination in accordance with Federal Specification RR–C–901D, paragraph 4.3.2, and meet the specified standard of cleanliness.

(4) The pressure in each cylinder may not exceed 3000 psig at 21 °C (70 °F).

(c) Notwithstanding the provisions of §§173.24(b)(1) and paragraph (f) of this section, an authorized cylinder containing oxygen continuously fed to tanks containing live fish may be offered for transportation and transported.

(d) Shipment of Division 2.1 materials in aluminum cylinders is authorized for transportation only by motor vehicle, rail car, or cargo-only aircraft.

(e) *DOT 3AL cylinders manufactured of 6351–T6 aluminum alloy.* Suitable safeguards should be provided to protect personnel and facilities should failure occur while filling cylinders manufactured of aluminum alloy 6351–T6 used in self-contained underwater breathing apparatus (SCUBA), self-contained breathing apparatus (SCBA) or oxygen service. The cylinder filler should allow only those individuals essential to the filling process to be in the vicinity of the cylinder during the filling process.

(f) *Compressed oxygen and oxidizing gases by aircraft.* A cylinder containing oxygen, compressed; compressed gas, oxidizing, n.o.s.; or nitrogen trifluoride is authorized for transportation by aircraft only when it meets the following requirements:

(1) Only DOT specification 3A, 3AA, 3AL, 3E, 3HT, and 39 cylinders, and UN pressure receptacles ISO 9809–1, ISO

9809-2, ISO 9809-3 and ISO 7866 cylinders are authorized.

(2) Cylinders must be equipped with a pressure relief device in accordance with §173.301(f) and, for DOT 39 cylinders offered for transportation after October 1, 2008, for the other DOT specification cylinders with the first requalification due after October 1, 2008, or for the UN pressure receptacles prior to initial use:

(i) The rated burst pressure of a rupture disc for DOT 3A, 3AA, 3AL, 3E, and 39 cylinders, and UN pressure receptacles ISO 9809-1, ISO 9809-2, ISO 9809-3 and ISO 7866 cylinders must be 100% of the cylinder minimum test pressure with a tolerance of plus zero to minus 10%; and

(ii) The rated burst pressure of a rupture disc for a DOT 3HT cylinder must be 90% of the cylinder minimum test pressure with a tolerance of plus zero to minus 10%.

(3) The cylinder must be placed in a rigid outer packaging that—

(i) Conforms to the requirements of either part 178, subparts L and M of this subchapter at the Packing Group I or II performance level or the performance criteria in Air Transport Association (ATA) Specification No. 300 for a Category I Shipping Container;

(ii) After September 30, 2009, is capable of passing, as demonstrated by design testing, the Flame Penetration Resistance Test in Appendix E to part 178 of this subchapter; and

(iii) Prior to each shipment, passes a visual inspection that verifies that all features of the packaging are in good condition, including all latches, hinges, seams, and other features, and that the packaging is free from perforations, cracks, dents, or other abrasions that may negatively affect the flame penetration resistance and thermal resistance characteristics of the packaging.

(4) After September 30, 2009, the cylinder and the outer packaging must be capable of passing, as demonstrated by design testing, the Thermal Resistance Test specified in Appendix D to part 178 of this subchapter.

(5) The cylinder and the outer packaging must both be marked and labeled in accordance with part 172, subparts D and E of this subchapter. The additional marking “DOT31FP,” is allowed

to indicate that the cylinder and the outer packaging are capable of passing, as demonstrated by design testing, the Thermal Resistance Test specified in Appendix D to part 178 of this subchapter.

(6) A cylinder of compressed oxygen that has been furnished by an aircraft operator to a passenger in accordance with 14 CFR §§121.574, 125.219, or 135.91 is excepted from the outer packaging requirements of paragraph (f)(3) of this section.

[67 FR 51646, Aug. 8, 2002, as amended at 67 FR 61289, Sept. 30, 2002; 68 FR 75745, Dec. 31, 2003; 71 FR 33883; June 12, 2006; 71 FR 51127, Aug. 29, 2006; 72 FR 55098, Sept. 28, 2007]

**§ 173.302a Additional requirements for shipment of nonliquefied (permanent) compressed gases in specification cylinders.**

(a) *Detailed filling requirements.* Nonliquefied compressed gases (except gas in solution) for which filling requirements are not specifically prescribed in §173.304a must be shipped subject to the requirements in this section and §§173.301, 173.301a, 173.302, and 173.305 in specification cylinders, as follows:

(1) DOT 3, 3A, 3AA, 3AL, 3B, 3E, 4B, 4BA and 4BW cylinders.

(2) DOT 3HT cylinders. These cylinders are authorized for aircraft use only and only for nonflammable gases. They have a maximum service life of 24 years from the date of manufacture. The cylinders must be equipped with frangible disc type pressure relief devices that meet the requirements of §173.301(f). Each frangible disc must have a rated bursting pressure not exceeding 90 percent of the minimum required test pressure of the cylinder. Discs with fusible metal backing are not permitted. Specification 3HT cylinders may be offered for transportation only when packaged in accordance with §173.301(a)(9).

(3) *DOT 39 cylinders.* When the cylinder is filled with a Division 2.1 material, the internal volume of the cylinder may not exceed 1.23 L (75 in<sup>3</sup>).

(4) DOT 3AX, 3AAX, and 3T cylinders are authorized for Division 2.1 and 2.2 materials and for carbon monoxide. DOT 3T cylinders are not authorized for hydrogen. When used in methane

§ 173.302a

49 CFR Ch. I (10–1–08 Edition)

service, the methane must be a non-liquefied gas with a minimum purity of 98.0 percent methane and commercially free of corroding components.

(5) Aluminum cylinders manufactured in conformance with specifications DOT 39 and 3AL are authorized for oxygen only under the conditions specified in §173.302(b).

(b) *Special filling limits for DOT 3A, 3AX, 3AA, 3AAX, and 3T cylinders.* A DOT 3A, 3AX, 3AA, 3AAX, and 3T cylinder may be filled with a compressed gas, other than a liquefied, dissolved, Division 2.1, or Division 2.3 gas, to a pressure 10 percent in excess of its marked service pressure, provided:

(1) The cylinder is equipped with a frangible disc pressure relief device (without fusible metal backing) having a bursting pressure not exceeding the minimum prescribed test pressure.

(2) The cylinder's elastic expansion was determined at the time of the last test or retest by the water jacket method.

(3) Either the average wall stress or the maximum wall stress does not exceed the wall stress limitation shown in the following table:

| Type of steel                                                             | Average wall stress limitation | Maximum wall stress limitation |
|---------------------------------------------------------------------------|--------------------------------|--------------------------------|
| I. Plain carbon steels over 0.35 carbon and medium manganese steels ..... | 53,000                         | 58,000                         |
| II. Steels of analysis and heat treatment specified in spec. 3AA .....    | 67,000                         | 73,000                         |
| III. Steels of analysis and heat treatment specified in spec. DOT-3T .... | 87,000                         | 94,000                         |
| IV. Plain carbon steels less than 0.35 carbon made prior to 1920 .....    | 45,000                         | 48,000                         |

(i)(A) The average wall stress must be computed from the elastic expansion data using the following formula:

$$S = 1.7EE / KV - 0.4P$$

Where:

S = wall stress, pounds per square inch;

EE = elastic expansion (total less permanent) in cubic centimeters;

K = factor  $\times 10^{-7}$  experimentally determined for the particular type of cylinder being tested or derived in accordance with CGA C-5 (IBR, see §171.7 of this subchapter);

V = internal volume in cubic centimeter (1 cubic inch = 16.387 cubic centimeters);

P = test pressure, pounds per square inch.

(B) The formula in paragraph (b)(3)(i)(A) of this section is derived

from the formula in paragraph (b)(3)(ii) of this section and the following:

$$EE = (PKVD^2) / (D^2 - d^2)$$

(ii) The maximum wall stress must be computed from the formula:

$$S = (P(1.3D^2 + 0.4d^2)) / (D^2 - d^2)$$

Where:

S = wall stress, pounds per square inch;

P = test pressure, pounds per square inch;

D = outside diameter, inches;

d = D-2t, where t=minimum wall thickness determined by a suitable method.

(iii) Compliance with average wall stress limitation may be determined by computing the elastic expansion rejection limit in accordance with CGA C-5, by reference to data tabulated in CGA C-5, or by the manufacturer's marked elastic expansion rejection limit (REE) on the cylinder.

(4) An external and internal visual examination made at the time of test or retest shows the cylinder to be free from excessive corrosion, pitting, or dangerous defects.

(5) A plus sign (+) is added following the test date marking on the cylinder to indicate compliance with paragraphs (b) (2), (b)(3), and (b)(4) of this section.

(c) *Carbon monoxide.* Carbon monoxide must be offered in a DOT 3, 3A, 3AX, 3AA, 3AAX, 3AL, 3E, or 3T cylinder having a minimum service pressure of 1800 psig. The pressure in a steel cylinder may not exceed 1000 psig at 21 °C (70 °F), except that if the gas is dry and sulfur free, the cylinder may be filled to 5/6 of the cylinder's service pressure or 2000 psig, whichever is less. A DOT 3AL cylinder may be filled to its marked service pressure. A DOT 3AL cylinder is authorized only when transported by motor vehicle, rail car, or cargo-only aircraft.

(d) *Diborane and diborane mixtures.* Diborane and diborane mixed with compatible compressed gas must be offered in a DOT 3AL1800 or 3AA1800 cylinder. The maximum filling density of the diborane may not exceed 7 percent. Diborane mixed with compatible compressed gas may not have a pressure exceeding the service pressure of the cylinder if complete decomposition of the diborane occurs. Cylinder valve assemblies must be protected in accordance with §173.301(h).

(e) *Fluorine*. Fluorine must be shipped in specification 3A1000, 3AA1000, or 3BN400 cylinders without pressure relief devices and equipped with valve protection cap. The cylinder may not be charged to over 400 psig at 21 °C (70 °F) and may not contain over 2.7 kg (6 lbs) of gas.

[67 FR 51646, Aug. 8, 2002, as amended at 68 FR 75745, Dec. 31, 2003; 70 FR 34075, June 13, 2005; 71 FR 54395, Sept. 14, 2006; 72 FR 4455, Jan. 31, 2007; 72 FR 55098, Sept. 28, 2007]

**§ 173.302b Additional requirements for shipment of non-liquefied (permanent) compressed gases in UN pressure receptacles.**

(a) *General*. A cylinder filled with a non-liquefied gas must be offered for transportation in UN pressure receptacles subject to the requirements in this section and § 173.302. In addition, the requirements in §§ 173.301 and 173.301b must be met.

(b) *UN pressure receptacles filling limits*. A UN pressure receptacle is authorized for the transportation of non-liquefied compressed gases as specified in this section. Except where filling limits are specifically prescribed in this section, the working pressure of a UN pressure receptacle may not exceed  $\frac{2}{3}$  of the test pressure of the receptacle. Alternatively, the filling limits specified for non-liquefied gases in Table 1 of P200 of the UN Recommendations (IBR, see § 171.7 of this subchapter) are authorized. In no case may the internal pressure at 65 °C (149 °F) exceed the test pressure.

(c) *Fluorine, compressed, UN 1045 and Oxygen difluoride, compressed, UN 2190*. Fluorine, compressed and Oxygen difluoride, compressed must be packaged in a UN pressure receptacle with a minimum test pressure of 200 bar and a maximum working pressure not to exceed 30 bar. A UN pressure receptacle made of aluminum alloy is not authorized. The maximum quantity of gas authorized in each UN pressure receptacle is 5 kg.

(d) *Diborane and diborane mixtures, UN 1911*. Diborane and diborane mixtures must be packaged in a UN pressure receptacle with a minimum test pressure of 250 bar and a maximum filling ratio dependent on the test pressure not to exceed 0.07. Filling should be further

limited so that if complete decomposition of diborane occurs, the pressure of diborane or diborane mixtures will not exceed the working pressure of the cylinder. The use of UN tubes and MEGCs is not authorized.

(e) *Carbon monoxide, compressed UN 1016*. Carbon monoxide, compressed is authorized in UN pressure receptacles. The settled pressure in a steel pressure receptacle containing carbon monoxide may not exceed  $\frac{1}{3}$  of the pressure receptacle's test pressure at 65 °C (149 °F) except, if the gas is dry and sulfur-free, the settled pressure may not exceed  $\frac{1}{2}$  of the marked test pressure.

[71 FR 33883, June 12, 2006]

**§ 173.303 Charging of cylinders with compressed gas in solution (acetylene).**

(a) *Cylinder, filler and solvent requirements*. (Refer to applicable parts of Specification 8 and 8AL). Acetylene gas must be shipped in Specification 8 or 8AL cylinders (§ 178.59 or § 178.60 of this subchapter). The cylinders shall consist of metal shells filled with a porous material, and this material must be charged with a suitable solvent. The cylinders containing the porous material and solvent shall be successfully tested in accordance with CGA C-12 (IBR, see § 171.7 of this subchapter). Representative samples of cylinders charged with acetylene must be successfully tested in accordance with CGA C-12.

(b) *Filling limits*. For DOT specification cylinders, the pressure in the cylinder containing acetylene gas may not exceed 250 psig at 70 °F. If cylinders are marked for a lower allowable charging pressure at 70 °F., that pressure must not be exceeded. For UN cylinders, the pressure in the cylinder may not exceed the limits specified in § 173.304b(b)(2).

(c) *Data requirements on filler and solvent*. Cylinders containing acetylene gas must not be shipped unless they were charged by or with the consent of the owner, and by a person, firm, or company having possession of complete information as to the nature of the porous filling, the kind and quantity of solvent in the cylinders, and the meaning of such markings on the cylinders as are prescribed by the Department's

## § 173.304

## 49 CFR Ch. I (10–1–08 Edition)

regulations and specifications applying to containers for the transportation of acetylene gas.

(d) *Verification of container pressure.*

(1) Each day, the pressure in a container representative of that day's compression must be checked by the charging plant after the container has cooled to a settled temperature and a record of this test kept for at least 30 days.

(e) *Prefill requirements.* Before each filling of an acetylene cylinder, the person filling the cylinder must visually inspect the outside of the cylinder in accordance with the prefill requirements contained in CGA C-13, Section 3 (IBR, see §171.7 of this subchapter).

(f) *UN cylinders.* (1) UN cylinders and bundles of cylinders are authorized for the transport of acetylene gas as specified in this section. Each UN acetylene cylinder must conform to ISO 3807-2 (IBR, see §171.7 of this subchapter), have a homogeneous monolithic porous mass filler and be charged with acetone or a suitable solvent as specified in the standard. UN acetylene cylinders must have a minimum test pressure of 52 bar and may be filled up to the pressure limits specified in ISO 3807-2. The use of UN tubes and MEGCs is not authorized.

(2) UN cylinders equipped with pressure relief devices or that are manifolded together must be transported upright.

[29 FR 18743, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §173.303, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 173.304 Filling of cylinders with liquefied compressed gases.

(a) *General requirements.* A cylinder filled with a liquefied compressed gas (except gas in solution) must be offered for transportation in accordance with the requirements of this section and the general requirements in §173.301. In addition, a DOT specification cylinder must meet the requirement in §§173.301a, 173.304a, and 173.305, as applicable. UN pressure receptacles must be shipped in accordance with the require-

ments in 173.301b and 173.304b, as applicable.

(1) A DOT 3AL cylinder may not be used for any material with a primary or subsidiary hazard of Class 8.

(2) Shipments of Division 2.1 materials in aluminum cylinders are authorized only when transported by motor vehicle, rail car, or cargo-only aircraft.

(b) *Filling limits.* Except for carbon dioxide; 1,1-Difluoroethylene (R-1132A); nitrous oxide; and vinyl fluoride, inhibited, the liquid portion of a liquefied gas may not completely fill the packaging at any temperature up to and including 55 °C (131 °F). The liquid portion of vinyl fluoride, inhibited, may completely fill the cylinder at 55 °C (131 °F) provided the pressure at the critical temperature does not exceed 1.25 times the service pressure of the cylinder.

(c) *Mixture of compressed gas and other material.* A mixture of compressed gas must be shipped in accordance with §173.305.

(d) *Refrigerant and dispersant gases.* Nontoxic and nonflammable refrigerant or dispersant gases must be offered for transportation in cylinders prescribed in §173.304a, or in DOT 2P and 2Q containers (§§178.33, 178.33a of this subchapter). DOT 2P and 2Q containers must be packaged in a strong wooden or fiberboard box of such design as to protect valves from damage or accidental functioning under conditions incident to transportation. Pressure in the inside metal containers may not exceed 87 psia at 21 °C (70 °F). Each completed metal container filled for shipment must be heated until its contents reach a minimum temperature of 55 °C (131 °F) without evidence of leakage, distortion, or other defect. Each outside package must be plainly marked "INSIDE CONTAINERS COMPLY WITH PRESCRIBED SPECIFICATIONS".

(e) *Engine starting fluid.* Engine starting fluid containing a flammable compressed gas or gases must be shipped in a cylinder as prescribed in §173.304a or as follows:

(1) Inside non-refillable metal containers having a capacity not greater than 500 mL (32 in<sup>3</sup>). The containers must be packaged in strong, tight

outer packagings. The pressure in the container may not exceed 145 psia at 54 °C (130 °F). If the pressure exceeds 145 psia at 54 °C (130 °F), a DOT 2P container must be used. In either case, the metal container must be capable of withstanding, without bursting, a pressure of 1.5 times the pressure of the contents at 54 °C (130 °F). The liquid content of the material and gas may not completely fill the container at 54 °C (130 °F). Each container filled for shipment must have been heated until its contents reach a minimum temperature of 54 °C (130 °F), without evidence of leakage, distortion, or other defect. Each outside shipping container must be plainly marked, "INSIDE CONTAINERS COMPLY WITH PRESCRIBED SPECIFICATIONS".

(2) [Reserved]

(f) *Oxidizing gases by aircraft.* A cylinder containing carbon dioxide and oxygen mixture, compressed; liquefied gas, oxidizing, n.o.s.; or nitrous oxide is authorized for transportation by aircraft only when it meets the following requirements:

(1) Only DOT specification 3A, 3AA, 3AL, 3E, 3HT, and 39 cylinders, and UN pressure receptacles ISO 9809-1, ISO 9809-2, ISO 9809-3 and ISO 7866 cylinders are authorized.

(2) Cylinders must be equipped with a pressure relief device in accordance with §173.301(f) and, for DOT 39 cylinders offered for transportation after October 1, 2008, for the other DOT specification cylinders with the first requalification due after October 1, 2008, or for the UN pressure receptacles prior to initial use:

(i) The rated burst pressure of a rupture disc for DOT 3A, 3AA, 3AL, 3E and 39 cylinders, and UN pressure receptacles ISO 9809-1, ISO 9809-2, ISO 9809-3 and ISO 7866 cylinders must be 100% of the cylinder minimum test pressure with a tolerance of plus zero to minus 10%; and

(ii) The rated burst pressure of a rupture disc for a DOT 3HT cylinder must be 90% of the cylinder minimum test pressure with a tolerance of plus zero to minus 10%.

(3) The cylinder must be placed in a rigid outer packaging that—

(i) Conforms to the requirements of either part 178, subparts L and M, of

this subchapter at the Packing Group I or II performance level, or the performance criteria in Air Transport Association (ATA) Specification No. 300 for a Category I Shipping Container;

(ii) After September 30, 2009, is capable of passing, as demonstrated by design testing, the Flame Penetration Resistance Test in part III of Appendix E to part 78 of this subchapter; and

(iii) Prior to each shipment, passes a visual inspection that verifies that all features of the packaging are in good condition, including all latches, hinges, seams, and other features, and the packaging is free from perforations, cracks, dents, or other abrasions that may negatively affect the flame penetration resistance and thermal resistance characteristics of the container.

(4) After September 30, 2009, the cylinder and the outer packaging must be capable of passing, as demonstrated by design testing, the Thermal Resistance Test specified in Appendix D to part 178 of this subchapter.

(5) The cylinder and the outer packaging must both be marked and labeled in accordance with part 172, subparts D and E of this subchapter. The additional marking "DOT31FP," is allowed to indicate that the cylinder and the outer packaging are capable of passing, as demonstrated by design testing, the Thermal Resistance Test specified in Appendix D to part 178 of this subchapter.

(6) A cylinder of compressed oxygen that has been furnished by an aircraft operator to a passenger in accordance with 14 CFR 121.574, 125.219, or 135.91 is excepted from the outer packaging requirements of paragraph (f)(3) of this section.

[67 FR 51647, Aug. 8, 2002, as amended at 68 FR 24661, May 8, 2003; 71 FR 33883, June 12, 2006; 72 FR 55098, Sept. 28, 2007]

**§ 173.304a Additional requirements for shipment of liquefied compressed gases in specification cylinders.**

(a) *Detailed filling requirements.* Liquefied gases (except gas in solution) must be offered for transportation, subject to the requirements in this section and §§173.301 and 173.304, in specification cylinders, as follows:

(1) DOT 3, 3A, 3AA, 3AL, 3B, 3BN, 3E, 4B, 4BA, 4B240ET, 4BW, 4E, 39, except

**§ 173.304a**

**49 CFR Ch. I (10–1–08 Edition)**

that no DOT 4E or 39 packaging may be filled and shipped with a mixture containing a pyrophoric liquid, carbon bisulfide (disulfide), ethyl chloride, ethylene oxide, nickel carbonyl, spirits of nitroglycerin, or toxic material (Di-

vision 6.1 or 2.3), unless specifically authorized in this part.

(2) For the gases named, the following requirements apply (for cryogenic liquids, see § 173.316):

| Kind of gas                                                                                         | Maximum permitted filling density (percent) (see Note 1) | Packaging marked as shown in this column or of the same type with higher service pressure must be used, except as provided in §§ 173.301(i), 173.301a(e), and 180.205(a) (see notes following table) |
|-----------------------------------------------------------------------------------------------------|----------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Anhydrous ammonia .....                                                                             | 54 .....                                                 | DOT-3A480; DOT-3AA480; DOT-3A480X; DOT-4AA480; DOT-3; DOT-3E1800; DOT-3AL480.                                                                                                                        |
| Bromotrifluoromethane (R–13B1 or H–1301) .....                                                      | 124 .....                                                | DOT-3A400; DOT-3AA400; DOT-3B400; DOT-4AA480; DOT-4B400; DOT-4BA400; DOT-4BW400; DOT-3E1800; DOT-39; DOT-3AL400.                                                                                     |
| Carbon dioxide (see Notes 4, 7, and 8) .....                                                        | 68 .....                                                 | DOT-3A1800; DOT-3AX1800; DOT-3AA1800; DOT-3AAX1800; DOT-3; DOT-3E1800; DOT-3T1800; DOT-3HT2000; DOT-39; DOT-3AL1800.                                                                                 |
| Carbon dioxide, refrigerated liquid (see paragraph (e) of this section).                            | .....                                                    | DOT-4L.                                                                                                                                                                                              |
| Chlorine (see Note 2) .....                                                                         | 125 .....                                                | DOT-3A480; DOT-3AA480; DOT-3; DOT-3BN480; DOT-3E1800.                                                                                                                                                |
| Chlorodifluoroethane or 1-Chloro-1, 1-difluoroethane (R–142b).                                      | 100 .....                                                | DOT-3A150; DOT-3AA150; DOT-3B150; DOT-4B150; DOT-4BA225; DOT-4BW225; DOT-3E1800; DOT-39; DOT-3AL150.                                                                                                 |
| Chlorodifluoromethane (R–22) (see Note 8) .....                                                     | 105 .....                                                | DOT-3A240; DOT-3AA240; DOT-3B240; DOT-4B240; DOT-4BA240; DOT-4BW240; DOT-4B240ET; DOT-4E240; DOT-39; DOT-3E1800; DOT-3AL240.                                                                         |
| Chloropentafluoroethane (R–115) .....                                                               | 110 .....                                                | DOT-3A225; DOT-3AA225; DOT-3B225; DOT-4BA225; DOT-4B225; DOT-4BW225; DOT-3E1800; DOT-39; DOT-3AL225.                                                                                                 |
| Chlorotrifluoromethane (R–13) (see Note 8) .....                                                    | 100 .....                                                | DOT-3A1800; DOT-3AA1800; DOT-3; DOT-3E1800; DOT-39; DOT-3AL1800.                                                                                                                                     |
| Cyclopropane (see Note 8) .....                                                                     | 55 .....                                                 | DOT-3A225; DOT-3A480X; DOT-3AA225; DOT-3B225; DOT-4AA480; DOT-4B225; DOT-4BA225; DOT-4BW225; DOT-4B240ET; DOT-3; DOT-3E1800; DOT-39; DOT-3AL225.                                                     |
| Dichlorodifluoromethane (R–12) (see Note 8) .....                                                   | 119 .....                                                | DOT-3A225; DOT-3AA225; DOT-3B225; DOT-4B225; DOT-4BA225; DOT-4BW225; DOT-4B240ET; DOT-4E225; DOT-39; DOT-3E1800; DOT-3AL225.                                                                         |
| Dichlorodifluoromethane and difluoroethane mixture (constant boiling mixture) (R–500) (see Note 8). | Not liquid full at 131 °F                                | DOT-3A240; DOT-3AA240; DOT-3B240; DOT-3E1800; DOT-4B240; DOT-4BA240; DOT-4BW240; DOT-4E240; DOT-39.                                                                                                  |
| 1,1-Difluoroethane (R–152a) (see note 8) .....                                                      | 79 .....                                                 | DOT-3A150; DOT-3AA150; DOT-3B150; DOT-4B150; DOT-4BA225; DOT-4BW225; DOT-3E1800; DOT-3AL150.                                                                                                         |
| 1,1-Difluoroethylene (R–1132A) .....                                                                | 73 .....                                                 | DOT-3A2200; DOT-3AA2200; DOT-3AX2200; DOT-3AAX2200; DOT-3T2200; DOT-39.                                                                                                                              |
| Dimethylamine, anhydrous .....                                                                      | 59 .....                                                 | DOT-3A150; DOT-3AA150; DOT-3B150; DOT-4B150; DOT-4BA225; DOT-4BW225; ICC–3E1800.                                                                                                                     |
| Ethane (see Note 8) .....                                                                           | 35.8 .....                                               | DOT-3A1800; DOT-3AX1800; DOT-3AA1800; DOT-3AAX1800; DOT-3; DOT-3E1800; DOT-3T1800; DOT-39; DOT-3AL1800.                                                                                              |
| Ethane (see Note 8) .....                                                                           | 36.8 .....                                               | DOT-3A2000; DOT-3AX2000; DOT-3AA2000; DOT-3AAX2000; DOT-3T2000; DOT-39; DOT-3AL2000.                                                                                                                 |
| Ethylene (see Note 8) .....                                                                         | 31.0 .....                                               | DOT-3A1800; DOT-3AX1800; DOT-3AA1800; DOT-3AAX1800; DOT-3; DOT-3E1800; DOT-3T1800; DOT-39; DOT-3AL1800.                                                                                              |
| Ethylene (see Note 8) .....                                                                         | 32.5 .....                                               | DOT-3A2000; DOT-3AX2000; DOT-3AA2000; DOT-3AAX2000; DOT-3T2000; DOT-39; DOT-3AL2000.                                                                                                                 |
| Ethylene (see Note 8) .....                                                                         | 35.5 .....                                               | DOT-3A2400; DOT-3AX2400; DOT-3AA2400; DOT-3AAX2400; DOT-3T2400; DOT-39; DOT-3AL2400.                                                                                                                 |

Pipeline and Hazardous Materials Safety Admin., DOT

§ 173.304a

| Kind of gas                                                                                                                                                                    | Maximum permitted filling density (percent) (see Note 1) | Packaging marked as shown in this column or of the same type with higher service pressure must be used, except as provided in §§ 173.301(l), 173.301a(e), and 180.205(a) (see notes following table)                      |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Hydrogen chloride, anhydrous .....                                                                                                                                             | 65 .....                                                 | DOT-3A1800; DOT-3AA1800; DOT-3AX1800; DOT-3AAX1800; DOT-3; DOT-3T1800; DOT-3E1800.                                                                                                                                        |
| Hydrogen sulfide (see Notes 10 and 14) .....                                                                                                                                   | 62.5 .....                                               | DOT-3A; DOT-3AA; DOT-3B; DOT-4A; DOT-4B; DOT-4BA; DOT-4BW; DOT-3E1800; DOT-3AL.                                                                                                                                           |
| Insecticide, gases liquefied (see Notes 8 and 12)                                                                                                                              | Not liquid full at 131 °F                                | DOT-3A300; DOT-3AA300; DOT-3B300; DOT-4B300; DOT-4BA300; DOT-4BW300; DOT-3E1800.                                                                                                                                          |
| Liquefied nonflammable gases, other than classified flammable, corrosive, toxic & mixtures or solution thereof filled w/nitrogen, carbon dioxide, or air (see Notes 7 and 8).. | Not liquid full at 131 °F                                | Specification packaging authorized in paragraph (a)(1) of this section and DOT-3HT; DOT 4D; DOT-4DA; DOT-4DS.                                                                                                             |
| Methyl acetylene-propadiene, mixtures, stabilized; (see Note 5)..                                                                                                              | Not liquid at 131 °F .....                               | DOT-4B240 without brazed seams; DOT-4BA240 without brazed seams; DOT-3A240; DOT-3AA240; DOT-3B240; DOT-3E1800; DOT-4BW240; DOT-4E240; DOT-4B240ET; DOT-3AL240.                                                            |
| Methyl chloride .....                                                                                                                                                          | 84 .....                                                 | DOT-3A225; DOT-3AA225; DOT-3B225; DOT-4B225; DOT-4BA225; DOT-4BW225; DOT-3; DOT-3E1800; DOT-4B240ET. Cylinders complying with DOT-3A150; DOT-3B150; and DOT-4B150 manufactured prior to Dec. 7, 1936 are also authorized. |
| Methyl mercaptan .....                                                                                                                                                         | 80 .....                                                 | DOT-3A240; DOT-3AA240; DOT-3B240; OT-4B240; DOT-4B240ET; DOT-3E1800; DOT-4BA240; DOT-4BW240.                                                                                                                              |
| Nitrosyl chloride .....                                                                                                                                                        | 110 .....                                                | DOT-3BN400 only.                                                                                                                                                                                                          |
| Nitrous oxide (see Notes 7, 8, and 11) .....                                                                                                                                   | 68 .....                                                 | DOT-3A1800; DOT-3AX1800; DOT-3AA1800; DOT-3AAX1800; DOT-3; DOT-3E1800; DOT-3T1800; DOT-3HT2000; DOT-39; DOT-3AL1800.                                                                                                      |
| Nitrous oxide, refrigerated liquid (see paragraph (e) of this section).                                                                                                        | .....                                                    | DOT-4L.                                                                                                                                                                                                                   |
| Refrigerant gas, n.o.s. or Dispersant gas, n.o.s. (see Notes 8 and 13).                                                                                                        | Not liquid full at 130 °F                                | DOT-3A240; DOT-3AA240; DOT-3B240; DOT-3E1800; DOT-4B240; DOT-4BA240; DOT-4BW240; DOT-4E240; DOT-39; DOT-3AL240.                                                                                                           |
| Sulfur dioxide (see note 8) .....                                                                                                                                              | 125 .....                                                | DOT-3A225; DOT-3AA225; DOT-3B225; DOT-4B225; DOT-4BA225; DOT-4BW225; DOT-4B240ET; DOT-3; DOT-39; DOT-3E1800; DOT-3AL225.                                                                                                  |
| Sulfur hexafluoride .....                                                                                                                                                      | 120 .....                                                | DOT-3A1000; DOT-3AA1000; DOT-AAX2400; DOT-3; DOT-3AL1000; DOT-3E1800; DOT-3T1800.                                                                                                                                         |
| Sulfuryl fluoride .....                                                                                                                                                        | 106 .....                                                | DOT-3A480; DOT-3AA480; DOT-3E1800; DOT-4B480; DOT-4BA480; DOT-4BW480.                                                                                                                                                     |
| Tetrafluoroethylene, stabilized .....                                                                                                                                          | 90 .....                                                 | DOT-3A1200; DOT-3AA1200; DOT-3E1800.                                                                                                                                                                                      |
| Trifluorochloroethylene, stabilized .....                                                                                                                                      | 115 .....                                                | DOT-3A300; DOT-3AA300; DOT-3B300; DOT-4B300; DOT-4BA300; DOT-4BW300; DOT-3E1800.                                                                                                                                          |
| Trimethylamine, anhydrous .....                                                                                                                                                | 57 .....                                                 | DOT-3A150; DOT-3AA150; DOT-3B150; DOT-4B150; DOT-4BA225; DOT-4BW225; DOT-3E1800.                                                                                                                                          |
| Vinyl chloride (see Note 5) .....                                                                                                                                              | 84 .....                                                 | DOT-4B150 without brazed seams; DOT-4BA225 without brazed seams; DOT-4BW225; DOT-3A150; DOT-3AA150; DOT-3E1800; DOT-3AL150.                                                                                               |
| Vinyl fluoride, stabilized .....                                                                                                                                               | 62 .....                                                 | DOT-3A1800; DOT-3AA1800; DOT-3E1800; DOT-3AL1800.                                                                                                                                                                         |
| Vinyl methyl ether, stabilized(see Note 5) .....                                                                                                                               | 68 .....                                                 | DOT-4B150, without brazed seams; DOT-4BA225 without brazed seams; DOT-4BW225; DOT-3A150; DOT-3AA150; DOT-3B1800; DOT-3E1800.                                                                                              |

NOTE 1: "Filling density" means the percent ratio of the weight of gas in a packaging to the weight of water that the container will hold at 16 °C (60 °F). (1 lb of water=27.737 in<sup>3</sup> at 60 °F.).

NOTE 2: Cylinders purchased after Oct. 1, 1944, for the transportation of chlorine must contain no aperture other than that provided in the neck of the cylinder for attachment of a valve equipped with an approved pressure relief device. Cylinders purchased after Nov. 1, 1935, and filled with chlorine may not contain over 68.04 kg (150 lb) of gas.

NOTE 3: [Reserved]



§ 173.304a

49 CFR Ch. I (10–1–08 Edition)

NOTE 4: Special carbon dioxide mining devices containing a heating element and filled with not over 2.72 kg (6 lb) of carbon dioxide may be filled to a density of not over 85 percent, provided the cylinder is made of steel with a calculated bursting pressure in excess of 39000 psig, fitted with a frangible disc that will operate at not over 57 percent of that pressure, and is able to withstand a drop of 10 feet when striking crosswise on a steel rail while under a pressure of at least 3000 psig. Such devices must be shipped in strong boxes or must be wrapped in heavy burlap and bound by 12-gauge wire with the wire completely covered by friction tape. Wrapping must be applied so as not to interfere with the functioning of the frangible disc pressure relief device. Shipments must be described as "liquefied carbon dioxide gas (mining device)" and marked, labeled, and certified as prescribed for liquefied carbon dioxide.

NOTE 5: All parts of valve and pressure relief devices in contact with contents of cylinders must be of a metal or other material, suitably treated if necessary, that will not cause formation of any acetylides.

NOTE 6: [Reserved]

NOTE 7: Specification 3HT cylinders for aircraft use only, having a maximum service life of 24 years. Authorized only for non-flammable gases. Cylinders must be equipped with pressure relief devices of the frangible disc type that meet the requirements of § 173.301(f). Each frangible disc must have a rated bursting pressure that does not exceed 90 percent of the minimum required test pressure of the cylinder. Discs with fusible metal backing are not permitted. Cylinders may be offered for transportation only when packaged in accordance with § 173.301(a)(9).

NOTE 8: See § 173.301(a)(9).

NOTE 9: [Reserved]

NOTE 10: Each valve outlet must be sealed by a threaded cap or a threaded solid plug.

NOTE 11: Must meet the valve and cleaning requirements in § 173.302(b).

NOTE 12: For an insecticide gas that is nontoxic and nonflammable, see § 173.305(c).

NOTE 13: For a refrigerant or dispersant gas that is nontoxic and nonflammable, see § 173.304(d).

NOTE 14: The use of DOT specification cylinder with a marked service pressure of 480 psi is authorized until December 31, 2003.

(b) [Reserved]

(c) *Verification of content in cylinder.*

Except as noted in paragraph (d)(4) of this section, the amount of liquefied gas filled into a cylinder must be by weight or, when the gas is lower in pressure than required for liquefaction, a pressure-temperature chart for the specific gas may be used to ensure that the service pressure at 55 °C (131 °F) will not exceed 5/4 of the service pressure at 21 °C (70 °F). The weight of liquefied gas filled into the cylinder also must be checked, after disconnecting the cylinder from the filling line, by the use of an accurate scale.

(d) Requirements for liquefied petroleum gas. (1) Filling density limits are as follows:

| Minimum specific gravity of liquid material at 60 °F | Maximum the filling density in percent of the water-weight capacity of the cylinder |
|------------------------------------------------------|-------------------------------------------------------------------------------------|
| 0.271 to 0.289                                       | 26                                                                                  |
| 0.290 to 0.306                                       | 27                                                                                  |
| 0.307 to 0.322                                       | 28                                                                                  |
| 0.323 to 0.338                                       | 29                                                                                  |
| 0.339 to 0.354                                       | 30                                                                                  |
| 0.355 to 0.371                                       | 31                                                                                  |
| 0.372 to 0.398                                       | 32                                                                                  |
| 0.399 to 0.425                                       | 33                                                                                  |
| 0.426 to 0.440                                       | 34                                                                                  |
| 0.441 to 0.452                                       | 35                                                                                  |
| 0.453 to 0.462                                       | 36                                                                                  |
| 0.463 to 0.472                                       | 37                                                                                  |
| 0.473 to 0.480                                       | 38                                                                                  |
| 0.481 to 0.488                                       | 39                                                                                  |
| 0.489 to 0.495                                       | 40                                                                                  |
| 0.496 to 0.503                                       | 41                                                                                  |
| 0.504 to 0.510                                       | 42                                                                                  |

| Minimum specific gravity of liquid material at 60 °F | Maximum the filling density in percent of the water-weight capacity of the cylinder |
|------------------------------------------------------|-------------------------------------------------------------------------------------|
| 0.511 to 0.519                                       | 43                                                                                  |
| 0.520 to 0.527                                       | 44                                                                                  |
| 0.528 to 0.536                                       | 45                                                                                  |
| 0.537 to 0.544                                       | 46                                                                                  |
| 0.545 to 0.552                                       | 47                                                                                  |
| 0.553 to 0.560                                       | 48                                                                                  |
| 0.561 to 0.568                                       | 49                                                                                  |
| 0.569 to 0.576                                       | 50                                                                                  |
| 0.577 to 0.584                                       | 51                                                                                  |
| 0.585 to 0.592                                       | 52                                                                                  |
| 0.593 to 0.600                                       | 53                                                                                  |
| 0.601 to 0.608                                       | 54                                                                                  |
| 0.609 to 0.617                                       | 55                                                                                  |
| 0.618 to 0.626                                       | 56                                                                                  |
| 0.627 to 0.634                                       | 57                                                                                  |

(2) Subject to § 173.301a(d), any filling density percentage prescribed in this section is authorized to be increased by a factor of 2 for liquefied petroleum gas in DOT 3 cylinders or in DOT 3A cylinders marked for 1800 psig, or higher, service pressure.

(3) Liquefied petroleum gas must be shipped in specification cylinders as follows:

(i) DOT 3, 3A, 3AA, 3B, 3E, 3AL, 4B, 4BA, 4B240ET, 4BW, 4E, or 39 cylinders. Shipments of flammable gases in DOT 3AL cylinders are authorized only when transported by motor vehicle, rail car, or cargo-only aircraft.

(ii) Additional containers may be used within the limits of quantity and pressure as follows:

| Type of container             | Maximum capacity (cubic inches) | Maximum filling pressure (psig)                       |
|-------------------------------|---------------------------------|-------------------------------------------------------|
| DOT-2P or DOT-2Q (see Note 1) | 31.83                           | 45 psig at 70 °F and 105 psig at 130 °F (see Note 2). |

| Type of container                   | Maximum capacity (cubic inches) | Maximum filling pressure (psig)          |
|-------------------------------------|---------------------------------|------------------------------------------|
| DOT-2P or DOT-2Q (see Note 1) ..... | 31.83                           | 35 psig at 70 °F and 100 psig at 130 °F. |

NOTE 1: Containers must be packed in strong wooden or fiber boxes of such design as to protect valves from damage or accidental functioning under conditions normally incident to transportation. Each completed container filled for shipment must have been heated until its contents reach a temperature of 54 °C (130 °F), without evidence of leakage, distortion, or other defect. Each outside shipping container must be plainly marked "INSIDE CONTAINERS COMPLY WITH PRESCRIBED SPECIFICATIONS".

NOTE 2: A container must be equipped with a pressure relief device that will prevent rupture of the container and dangerous projection of a closing device when exposed to fire.

(4) *Verification of content.* A cylinder with a water capacity of 90.72 kg (200 lb) or more and for use with a liquefied petroleum gas with a specific gravity of 0.504 or greater at 16 °C (60 °F) may have the quantity of its contents determined by using a fixed length dip tube gauging device. The length of the dip tube must be such that when a liquefied petroleum gas, with a specific volume of 0.03051 cu. ft./lb. at a temperature of 40 °F, is filled into the container, the liquid just reaches the bottom of the tube. The weight of this liquid may not exceed 42 percent of the water capacity of the container, which must be stamped on the cylinder. The length of the dip tube, expressed in inches carried out to one decimal place and prefixed with the letters "DT", must be stamped on the container and on the exterior of removable type dip tube. For the purpose of this requirement, the marked length must be expressed as the distance measured along the axis of a straight tube from the top of the boss through which the tube is inserted to the proper level of the liquid in the container. The length of each dip tube must be checked when installed by weighing each container after filling except when installed in groups of substantially identical containers, in which case one of each 25 containers must be weighed. The quantity of liquefied gas in each container must be checked by means of the dip

tube after disconnecting from the filling line. The outlet from the dip tube may not be larger than 0.1016 centimeters (0.040 inch; No. 54 drill bit size orifice). A container representative of each day's filling at each filling plant must have its contents checked by weighing after disconnecting from the filling line.

(e) *Carbon dioxide, refrigerated liquid or nitrous oxide, refrigerated liquid.* (1) The following provisions apply to carbon dioxide, refrigerated liquid, and nitrous oxide, refrigerated liquid:

(i) DOT 4L cylinders conforming to the provisions of this paragraph are authorized.

(ii) Each cylinder must be protected with at least one pressure relief device and at least one frangible disc conforming to §173.301(f) and paragraph (a)(2) of this section. The relieving capacity of the pressure relief device system must be equal to or greater than that calculated by the applicable formula in paragraph 5.8.3 of CGA S-1.1 (IBR, see §171.7 of this subchapter).

(iii) The temperature and pressure of the gas at the time the shipment is offered for transportation may not exceed -18 °C (0 °F) and 290 psig for carbon dioxide and -15.6 °C (+4 °F) and 290 psig for nitrous oxide. Maximum time in transit may not exceed 120 hours.

(2) The following pressure relief device settings, design service temperatures and filling densities apply:

| Pressure relief device setting maximum start—to discharge gauge pressure in psig | Maximum permitted filling density (percent by weight) |                                    |
|----------------------------------------------------------------------------------|-------------------------------------------------------|------------------------------------|
|                                                                                  | Carbon dioxide, refrigerated liquid                   | Nitrous oxide, refrigerated liquid |
| 105 psig .....                                                                   | 108                                                   | 104                                |
| 170 psig .....                                                                   | 105                                                   | 101                                |
| 230 psig .....                                                                   | 104                                                   | 99                                 |
| 295 psig .....                                                                   | 102                                                   | 97                                 |
| 360 psig .....                                                                   | 100                                                   | 95                                 |
| 450 psig .....                                                                   | 98                                                    | 83                                 |
| 540 psig .....                                                                   | 92                                                    | 87                                 |

§ 173.304b

49 CFR Ch. I (10–1–08 Edition)

| Pressure relief device setting maximum start—to discharge gauge pressure in psig | Maximum permitted filling density (percent by weight) |                                    |
|----------------------------------------------------------------------------------|-------------------------------------------------------|------------------------------------|
|                                                                                  | Carbon dioxide, refrigerated liquid                   | Nitrous oxide, refrigerated liquid |
| 625 psig .....                                                                   | 86                                                    | 80                                 |
| Design service temperature °C(°F) .....                                          | –196 °C(–320 °F)                                      | –196 °C(–320 °F)                   |

[67 FR 51647, Aug. 8, 2002, as amended at 68 FR 24661, May 8, 2003; 68 FR 57632, Oct. 6, 2003; 68 FR 75742, Dec. 31, 2003; 70 FR 34076, June 13, 2005; 72 FR 4456, Jan. 31, 2007; 72 FR 55098, Sept. 28, 2007; 73 FR 4719, Jan. 28, 2008]

EDITORIAL NOTE: At 70 FR 34076, June 13, 2005, §173.304a was amended in the table in paragraph (a)(2) by removing the phrase “DOT-4A480” from the entry “Hydrogen sulfide”; however, the amendment could not be incorporated because that phrase does not exist in the entry.

**§ 173.304b Additional requirements for shipment of liquefied compressed gases in UN pressure receptacles.**

(a) *General.* Liquefied gases and gas mixtures must be offered for transportation in UN pressure receptacles subject to the requirements in this section and §173.304. In addition, the general requirements applicable to UN pressure receptacles in §§173.301 and 173.301b must be met.

(b) *UN pressure receptacle filling limits.* A UN pressure receptacle is authorized for the transportation of liquefied compressed gases and gas mixtures as specified in this section. When a liquefied compressed gas or gas mixture is transported in a UN pressure receptacle, the filling ratio may not exceed the maximum filling ratio (FR) prescribed in this section and the applicable ISO standard. Compliance with the filling limits may be determined by referencing the numerical values and data in Table 2 of P200 of the UN Recommendations (IBR, see §171.7 of this subchapter). Alternatively, the maximum allowable filling limits may be determined as follows:

(1) For high pressure liquefied gases, in no case may the filling ratio of the

settled pressure at 65 °C (149 °F) exceed the test pressure of the UN pressure receptacle.

(2) For low pressure liquefied gases, the filling factor (maximum mass of contents per liter of water capacity) must be less than or equal to 95 percent of the liquid phase at 50 °C. In addition, the UN pressure receptacle may not be liquid full at 60 °C. The test pressure of the pressure receptacle must be equal to or greater than the vapor pressure of the liquid at 65 °C.

(3) For high pressure liquefied gases or gas mixtures, the maximum filling ratio may be determined using the formulas in (3)(b) of P200 of the UN Recommendations.

(4) For low pressure liquefied gases or gas mixtures, the maximum filling ratio may be determined using the formulas in (3)(c) of P200 of the UN Recommendations.

(c) *Special filling limits.* Notwithstanding the numerical values shown in Table 2 of P200, the maximum allowable filling limits authorized for the following gases in UN pressure receptacles must be in accordance with the following table:

| Identification No. | Proper shipping name                                                                | P-200 filling limit | HMR filling limit |
|--------------------|-------------------------------------------------------------------------------------|---------------------|-------------------|
| UN1020 .....       | Chloropentafluoroethane or Refrigerant gas R 115 .....                              | 1.08                | 1.05              |
| UN1048 .....       | Hydrogen bromide .....                                                              | 1.54                | 1.51              |
| UN1973 .....       | Chlorodifluoromethane and chloropentafluoroethane mixture or Refrigerant gas R 502. | 1.05                | 1.01              |
| UN1976 .....       | Octafluorocyclobutane, or Refrigerant gas RC 318 .....                              | 1.34                | 1.32              |
| UN1982 .....       | Tetrafluoromethane or Refrigerant gas R 14 .....                                    | 0.94                | 0.90              |
| UN2035 .....       | 1,1,1-Trifluoroethane, or Refrigerant gas R 143a .....                              | 0.75                | 0.73              |
| UN2192 .....       | Germane .....                                                                       | 1.02                | 1.00              |
| UN2198 .....       | Phosphorous Pentafluoride .....                                                     | 1.34                | 1.25              |
| UN2424 .....       | Octafluoropropane or Refrigerant gas R 218 .....                                    | 1.09                | 1.04              |

| Identification No. | Proper shipping name                                                                     | P-200 filling limit | HMR filling limit |
|--------------------|------------------------------------------------------------------------------------------|---------------------|-------------------|
| UN2599 .....       | Chlorotrifluoromethane and trifluoromethane azeotropic mixture or Refrigerant gas R 503. | 0.20, 0.66          | 0.17, 0.64        |

(d) *Tetrafluoroethylene, stabilized, UN1081* must be packaged in a pressure receptacle with a minimum test pressure of 200 bar and a working pressure not exceeding 5 bar.

(e) *Fertilizer ammoniating solution with free ammonia, UN1043* is not authorized in UN tubes or MEGCs.

[71 FR 33883, June 12, 2006]

**§ 173.305 Charging of cylinders with a mixture of compressed gas and other material.**

(a) *Detailed requirements.* A mixture of a compressed gas and any other material must be shipped as a compressed gas if the mixture is a compressed gas as designated in § 173.115 and when not in violation of § 173.301(a).

(b) *Filling limits.* (See § 173.301.) For mixtures, the liquid portion of the liquefied compressed gas at 131 °F. plus any additional liquid or solid must not completely fill the container.

(c) *Nonpoisonous and nonflammable mixtures.* Mixtures containing compressed gas or gases including insecticides, which mixtures are nonpoisonous and nonflammable under this part must be shipped in cylinders as prescribed in § 173.304(a) or as follows:

(1) Specification 2P (§ 178.33 of this subchapter). Inside metal containers equipped with safety relief devices of a type examined by the Bureau of Explosives and approved by the Associate Administrator, and packed in strong wooden or fiber boxes of such design as to protect valves from damage or accidental functioning under conditions incident to transportation. Pressure in the container may not exceed 85 psia at 70 °F. Each completed metal container filled for shipment must be heated until content reaches a minimum temperature of 130 °F., without evidence of leakage, distortion or other defect. Each outside shipping container must be plainly marked "INSIDE CONTAINERS COMPLY WITH PRESCRIBED SPECIFICATIONS."

(2) [Reserved]

(d) *Poisonous mixtures.* A mixture containing any poisonous material (Division 6.1 or 2.3) in such proportions that the mixture would be classed as poisonous under § 173.115 or § 173.132 must be shipped in packagings as authorized for these poisonous materials.

[29 FR 18743, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 173-70, 38 FR 5309, Feb. 27, 1973, Amdt. 173-94, 41 FR 16079, Apr. 15, 1976; 45 FR 32697, May 19, 1980; Amdt. 173-224, 56 FR 66275, 66279, Dec. 20, 1991; 66 FR 45379, Aug. 28, 2001; 67 FR 61013, Sept. 27, 2002; 67 FR 51651, Aug. 8, 2002; 68 FR 24662, May 8, 2003]

**§ 173.306 Limited quantities of compressed gases.**

(a) Limited quantities of compressed gases for which exceptions are permitted as noted by reference to this section in § 172.101 of this subchapter are excepted from labeling, except when offered for transportation or transported by air, and, unless required as a condition of the exception, specification packaging requirements of this subchapter when packaged in accordance with the following paragraphs. For transportation by aircraft, the package must also comply with the applicable requirements of § 173.27 of this subchapter and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments are not subject to subpart F (Placarding) of part 172 of this subchapter, to part 174 of this subchapter except § 174.24, and to part 177 of this subchapter except § 177.817. Each package may not exceed 30 kg (66 pounds) gross weight.

(1) When in containers of not more than 4 fluid ounces capacity (7.22 cubic inches or less) except cigarette lighters. Special exceptions for shipment of certain compressed gases in the ORM-D class are provided in paragraph (i) of this section.

(2) When in metal containers filled with a material that is not classed as a hazardous material to not more than 90

percent of capacity at 70 °F. and then charged with nonflammable, nonliquefied gas. Each container must be tested to three times the pressure at 70 °F. and, when refilled, be retested to three times the pressure of the gas at 70 °F. Also, one of the following conditions must be met:

(i) Container is not over 1 quart capacity and charged to not more than 170 psig at 70 °F. and must be packed in a strong outside packaging, or

(ii) Container is not over 30 gallons capacity and charged to not more than 75 psig at 70 °F.

(3) When in a metal container for the sole purpose of expelling a nonpoisonous (other than a Division 6.1 Packing Group III material) liquid, paste or powder, provided all of the following conditions are met. Special exceptions for shipment of aerosols in the ORM-D class are provided in paragraph (i) of this section.

(i) Capacity must not exceed 1 L (61.0 cubic inches).

(ii) Pressure in the container must not exceed 180 psig at 130 °F. If the pressure exceeds 140 psig at 130 °F., but does not exceed 160 psig at 130 °F., a specification DOT 2P (§178.33 of this subchapter) inside metal container must be used; if the pressure exceeds 160 psig at 130 °F., a specification DOT 2Q (§178.33a of this subchapter) inside metal container must be used. In any event, the metal container must be capable of withstanding without bursting a pressure of one and one-half times the equilibrium pressure of the content at 130 °F.

(iii) Liquid content of the material and gas must not completely fill the container at 130 °F.

(iv) The container must be packed in strong outside packagings.

(v) Each container must be subjected to a test performed in a hot water bath; the temperature of the bath and the duration of the test must be such that the internal pressure reaches that which would be reached at 55 °C (131 °F) (50 °C (122 °F) if the liquid phase does not exceed 95% of the capacity of the container at 50 °C (122 °F)). If the contents are sensitive to heat, the temperature of the bath must be set at between 20 °C (68 °F) and 30 °C (86 °F) but, in addition, one container in 2,000 must

be tested at the higher temperature. No leakage or permanent deformation of a container may occur.

(vi) Each outside packaging must be marked "INSIDE CONTAINERS COMPLY WITH PRESCRIBED REGULATIONS."

(4) Gas samples must be transported under the following conditions:

(i) A gas sample may only be transported as non-pressurized gas when its pressure corresponding to ambient atmospheric pressure in the container is not more than 105 kPa absolute (15.22 psia).

(ii) Non-pressurized gases, toxic (or toxic and flammable) must be packed in hermetically sealed glass or metal inner packagings of not more than one L (0.3 gallons) overpacked in a strong outer packaging.

(iii) Non-pressurized gases, flammable must be packed in hermetically sealed glass or metal inner packagings of not more than 5 L (1.3 gallons) and overpacked in a strong outer packaging.

(b) *Exceptions for foodstuffs, soap, biologicals, electronic tubes, and audible fire alarm systems.* Limited quantities of compressed gases (except Division 2.3 gases) for which exceptions are provided as indicated by reference to this section in §172.101 of this subchapter, when accordance with one of the following paragraphs, are excepted from labeling, except when offered for transportation or transported by aircraft, and the specification packaging requirements of this subchapter. For transportation by aircraft, the package must comply with the applicable requirements of §173.27 of this subchapter; the net quantity per package may not exceed the quantity specified in column (9A) of the Hazardous Materials Table in §172.101 of this subchapter; and only hazardous materials authorized aboard passenger-carrying aircraft may be transported as a limited quantity. In addition, shipments are not subject to subpart F (Placarding) of part 172 of this subchapter, to part 174 of this subchapter, except §174.24, and to part 177 of this subchapter, except §177.817. Special exceptions for shipment of certain compressed gases in the ORM-D class are

provided in paragraph (i) of this section.

(1) Foodstuffs or soaps in a nonrefillable metal container not exceeding 1 L (61.0 cubic inches), with soluble or emulsified compressed gas, provided the pressure in the container does not exceed 140 p.s.i.g. at 130 °F. The metal container must be capable of withstanding without bursting a pressure of one and one-half times the equilibrium pressure of the content at 130 °F.

(i) Containers must be packed in strong outside packagings.

(ii) Liquid content of the material and the gas must not completely fill the container at 130 °F.

(iii) Each outside packaging must be marked "INSIDE CONTAINERS COMPLY WITH PRESCRIBED REGULATIONS."

(2) Cream in refillable metal receptacles with soluble or emulsified compressed gas. Containers must be of such design that they will hold pressure without permanent deformation up to 375 psig and must be equipped with a device designed so as to release pressure without bursting of the container or dangerous projection of its parts at higher pressures. This exception applies to shipments offered for transportation by refrigerated motor vehicles only.

(3) Nonrefillable metal containers charged with a Division 6.1 Packing Group III or nonflammable solution containing biological products or a medical preparation which could be deteriorated by heat, and compressed gas or gases. The capacity of each container may not exceed 35 cubic inches (19.3 fluid ounces). The pressure in the container may not exceed 140 psig at 130 °F., and the liquid content of the product and gas must not completely fill the containers at 130 °F. One completed container out of each lot of 500 or less, filled for shipment, must be heated, until the pressure in the container is equivalent to equilibrium pressure of the content at 130 °F. There must be no evidence of leakage, distortion, or other defect. Container must be packed in strong outside packagings.

(4) Electronic tubes, each having a volume of not more than 30 cubic inches and charged with gas to a pres-

sure of not more than 35 psig and packed in strong outside packagings.

(5) Audible fire alarm systems powered by a compressed gas contained in an inside metal container when shipped under the following conditions:

(i) Each inside container must have contents which are not flammable, poisonous, or corrosive as defined under this part,

(ii) Each inside container may not have a capacity exceeding 35 cubic inches (19.3 fluid ounces),

(iii) Each inside container may not have a pressure exceeding 70 psig at 70 °F. and the liquid portion of the gas may not completely fill the inside container at 130 °F., and

(iv) Each nonrefillable inside container must be designed and fabricated with a burst pressure of not less than four times its charged pressure at 130 °F. Each refillable inside container must be designed and fabricated with a burst pressure of not less than five times its charged pressure at 130 °F.

(c)-(d) [Reserved]

(e) *Refrigerating machines.* (1) New (unused) refrigerating machines or components thereof are excepted from the specification packaging requirements of this part if they meet the following conditions. In addition, shipments are not subject to subpart F of part 172 of this subchapter, to part 174 of this subchapter except § 174.24 and to part 177 of this subchapter except § 177.817.

(i) Each pressure vessel may not contain more than 5,000 pounds of Group A1 refrigerant as classified in ANSI/ASHRAE Standard 15 or not more than 50 pounds of refrigerant other than Group A1.

(ii) Machines or components having two or more charged vessels may not contain an aggregate of more than 2,000 pounds of Group I refrigerant or more than 100 pounds of refrigerant other than Group I.

(iii) Each pressure vessel must be equipped with a safety device meeting the requirements of ANSI/ASHRAE 15 (IBR, see § 171.7 of this subchapter).

(iv) Each pressure vessel must be equipped with a shut-off valve at each opening except openings used for safety devices and with no other connection.

## § 173.306

## 49 CFR Ch. I (10–1–08 Edition)

These valves must be closed prior to and during transportation.

(v) Pressure vessels must be manufactured, inspected and tested in accordance with ANSI/ASHRAE 15, or when over 6 inches internal diameter, in accordance with Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter).

(vi) All parts subject to refrigerant pressure during shipment must be tested in accordance with ANSI/ASHRAE 15.

(vii) The liquid portion of the refrigerant, if any, may not completely fill any pressure vessel at 130 °F.

(viii) The amount of refrigerant, if liquefied, may not exceed the filling density prescribed in § 173.304.

(f) *Accumulators (Articles, pressurized pneumatic or hydraulic containing non-flammable gas).* The following applies to accumulators, which are hydraulic accumulators containing nonliquefied, nonflammable gas, and nonflammable liquids or pneumatic accumulators containing nonliquefied, nonflammable gas, fabricated from materials which will not fragment upon rupture.

(1) Accumulators installed in motor vehicles, construction equipment, and assembled machinery and designed and fabricated with a burst pressure of not less than five times their charged pressure at 70 °F., when shipped, are not subject to the requirements of this subchapter.

(2) Accumulators charged with limited quantities of compressed gas to not more than 200 p.s.i.g. at 70 °F. are excepted from labeling (except when offered for transportation by air) and the specification packaging requirements of this subchapter when shipped under the following conditions. In addition, shipments are not subject to subpart F of part 172 of this subchapter, to part 174 of this subchapter except § 174.24 and to part 177 of this subchapter except § 177.817.

(i) Each accumulator must be shipped as an inside packaging,

(ii) Each accumulator may not have a gas space exceeding 2,500 cubic inches under stored pressure, and

(iii) Each accumulator must be tested, without evidence of failure or damage, to at least three times its charged pressure of 70 °F., but not less than 120

p.s.i. before initial shipment and before each refilling and reshipment.

(3) Accumulators with a charging pressure exceeding 200 p.s.i.g. at 70 °F. are excepted from labeling (except when offered for transportation by air) and the specification packaging requirements of this subchapter when shipped under the following conditions:

(i) Each accumulator must be in compliance with the requirements stated in paragraph (f)(2), (i), (ii), and (iii) of this section, and

(ii) Each accumulator must be designed and fabricated with a burst pressure of not less than five times its charged pressure at 70 °F. when shipped.

(4) Accumulators intended to function as shock absorbers, struts, gas springs, pneumatic springs or other impact or energy-absorbing devices are not subject to the requirements of this subchapter provided each:

(i) Has a gas space capacity not exceeding 1.6 L and a charge pressure not exceeding 280 bar, where the product of the capacity expressed in liters and charge pressure expressed in bars does not exceed 80 (for example, 0.5 L gas space and 160 bar charge pressure);

(ii) Has a minimum burst pressure of 4 times the charge pressure at 20°C for products not exceeding 0.5 L gas space capacity and 5 times the charge pressure for products greater than 0.5 L gas space capacity;

(iii) Design type has been subjected to a fire test demonstrating that the article relieves its pressure by means of a fire degradable seal or other pressure relief device, such that the article will not fragment and that the article does not rocket; and

(iv) Accumulators must be manufactured under a written quality assurance program which monitors parameters controlling burst strength, burst mode and performance in a fire situation as specified in paragraphs (f)(4)(i) through (f)(4)(iii) of this section. A copy of the quality assurance program must be maintained at each facility at which the accumulators are manufactured.

(5) Accumulators not conforming to the provisions of paragraphs (f)(1) through (f) (4) of this section, may only

be transported subject to the approval of the Associate Administrator.

(g) *Water pump system tank.* Water pump system tanks charged with compressed air or limited quantities of nitrogen to not over 40 psig for single-trip shipment to installation sites are excepted from labeling (transportation by air not authorized) and the specification packaging requirements of this subchapter when shipped under the following conditions. In addition, shipments are not subject to subpart F of this subchapter, to part 174 of this subchapter except § 174.24 and part 177 except § 177.817.

(1) The tank must be of steel, welded with heads concave to pressure, having a rated water capacity not exceeding 120 gallons and with outside diameter not exceeding 24 inches. Safety relief devices not required.

(2) The tank must be pneumatically tested to 100 psig. Test pressure must be permanently marked on the tank.

(3) The stress at prescribed pressure must not exceed 20,000 psi using formula:

$$S = Pd / 2t$$

where:

S = wall stress in psi;

P = prescribed pressure for the tank of at least 3 times charged pressure at 70 °F or 100 psig, whichever is greater;

d = inside diameter in inches;

t = minimum wall thickness, in inches.

(4) The burst pressure must be at least 6 times the charge pressure at 70 °F.

(5) Each tank must be overpacked in a strong outer packaging in accordance with § 173.301(h).

(h) *Lighter refills.* (1) Lighter refills (see § 171.8 of this subchapter) must not contain an ignition element but must contain a release device. Lighter refills offered for transportation under this section may not exceed 4 fluid ounces capacity (7.22 cubic inches) or contain more than 65 grams of a Division 2.1 fuel. For transportation by highway or rail, lighter refills must be tightly packed and secured against movement in strong outer packagings. For transportation by aircraft or vessel, lighter refills must be tightly packed and secured against movement in any rigid specification outer packaging author-

ized in Subpart L of Part 178 of this subchapter at the Packing Group II performance level.

(2) *Exceptions.* For highway transportation, when no more than 1,500 lighter refills covered by this paragraph are transported in one motor vehicle, the requirements of subparts C through H of part 172, and Part 177 of this subchapter do not apply. Lighter refills covered under this paragraph must be packaged in rigid, strong outer packagings meeting the general packaging requirements of subpart B of this part. Outer packagings must be plainly and durably marked, on two opposing sides or ends, with the word "LIGHTER REFILLS" and the number of devices contained therein in letters measuring at least 20 mm (0.79 in) in height. No person may offer for transportation or transport the lighter refills or prepare the lighter refills for shipment unless that person has been specifically informed of the requirements of this section.

(i) A limited quantity which conforms to the provisions of paragraph (a)(1), (a)(3), or (b) of this section and is a "consumer commodity" as defined in § 171.8 of this subchapter, may be renamed "consumer commodity" and reclassified as ORM-D material. Each package may not exceed 30 kg (66 pounds) gross weight. In addition to the exceptions provided by paragraphs (a) and (b) of this section—

(1) Outside packagings are not required to be marked "INSIDE CONTAINERS COMPLY WITH PRESCRIBED REGULATIONS";

(2) Shipments of ORM-D materials are not subject to the shipping paper requirements of subpart C of part 172 of this subchapter, unless the material meets the definition of a hazardous substance, a hazardous waste, or a marine pollutant or unless offered for transportation or transported by aircraft; and

(3) Shipments of ORM-D materials are eligible for the exceptions provided in § 173.156.

(j) *Aerosols and receptacles small, containing gas with a capacity of less than 50 mL.* Aerosols, as defined in § 171.8 of this subchapter, and receptacles small,



## § 173.307

containing gas, with a capacity not exceeding 50 mL (1.7 oz.) and with a pressure not exceeding 970 kPa (141 psig) at 55 °C (131 °F), containing no hazardous materials other than a Division 2.2 gas, are not subject to the requirements of this subchapter. The pressure limit may be increased to 2000 kPa (290 psig) at 55 °C (131 °F) provided the aerosols are transported in outer packages that conform to the packaging requirements of Subpart B of this part. This paragraph does not apply to a self-defense spray (e.g., pepper spray).

(k) For additional exceptions, also see § 173.307.

[Amdt. 173-94, 41 FR 16079, Apr. 15, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 173.306, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

## § 173.307 Exceptions for compressed gases.

(a) The following materials are not subject to the requirements of this subchapter:

(1) Carbonated beverages.

(2) Tires when inflated to pressures not greater than their rated inflation pressures. For transportation by air, tires and tire assemblies must meet the conditions in § 175.8(b)(4) of this subchapter.

(3) Balls used for sports.

(4) Refrigerating machines, including dehumidifiers and air conditioners, and components thereof, such as precharged tubing containing:

(i) 12 kg (25 pounds) or less of a non-flammable, non-toxic gas;

(ii) 12 L (3 gallons) or less of ammonia solution (UN2672);

(iii) Except when offered or transported by air, 12 kg (25 pounds) or less of a flammable, non-toxic gas;

(iv) Except when offered or transported by air or vessel, 20 kg (44 pounds) or less of a Group A1 refrigerant specified in ANSI/ASHRAE Standard 15 (IBR, see § 171.7 of this subchapter); or

(v) 100 g (4 ounces) or less of a flammable, non-toxic liquefied gas.

## 49 CFR Ch. I (10-1-08 Edition)

(b) [Reserved]

[Amdt. 173-94, 41 FR 16081, Apr. 15, 1976, as amended by Amdt. 173-135, 45 FR 13090, Feb. 28, 1980; 65 FR 50462, Aug. 18, 2000; 68 FR 45038, July 31, 2003; 68 FR 75745, Dec. 31, 2003; 69 FR 76174, Dec. 20, 2004; 71 FR 14604, Mar. 22, 2006]

## § 173.308 Lighters.

(a) *General requirements.* No person may offer for transportation or transport a lighter (see § 171.8 of this subchapter) containing a Division 2.1 (flammable gas) material except under the following conditions:

(1) The lighter must contain a fuel reservoir not exceeding 4 fluid ounces capacity (7.22 cubic inches), and must contain not more than 10 grams (0.35 ounce) of flammable gas.

(2) The maximum filling density may not exceed 85 percent of the volumetric capacity of each fluid reservoir at 15 °C (59 °F).

(3) Each lighter design, including closures, must be capable of withstanding, without leakage or rupture, an internal pressure of at least two times the pressure of the flammable gas at 55 °C (131 °F).

(4) Each appropriate lighter design must be examined and successfully tested by a person or agency (authorized testing agency) who is authorized by the Associate Administrator to perform such examination and testing under the provisions of subpart E of part 107 of this chapter and who—

(i) Has the equipment necessary to perform the testing required to the level of accuracy required;

(ii) Is able to demonstrate, upon request, the knowledge of the testing procedures and requirements of the HMR relative to lighters;

(iii) Does not manufacture or market lighters, is not financially dependent or owned in whole or in part, by any entity that manufactures or markets lighters;

(iv) Is a resident of the United States; and

(v) Performs all examination and testing in accordance with the requirements of paragraph (b)(3) and (4) of this section.

(5) The Associate Administrator will assign an identification code to each person who is authorized to examine and test lighters. This identification

code must be incorporated into a unique test report identifier for each successfully tested lighter design.

(b) *Examination and testing of lighter design types*—(1) *Lighter design type definition*. A new lighter design is one that has never been examined and tested or one that differs from a previous design in any manner that may affect the escape (leakage) of gas. Lighter characteristics that may affect the escape of gas include changes in materials of construction, ignition mechanism, burner valve design, wall thickness, sealing materials, and type of fuel (e.g., vapor pressure differences).

(2) *Lighter samples submitted for examination and testing*. Samples of a new lighter design are excepted from the requirements of (a)(4) and (d) of this section and may be offered for transportation and transported under the following conditions:

(i) The samples must be transported only to an authorized testing agency;

(ii) No more than 12 lighters may be packaged in a single outer packaging;

(iii) Inner packagings must conform to the requirements of paragraph (c)(1) of this section. For transportation by aircraft, intermediate or outer packagings must meet the pressure differential requirements of §173.27(c) of this part;

(iv) The outer packaging must conform to the requirements of Subpart M of Part 178 of this subchapter at the Packing Group I performance level and to the requirements of §173.24 of this subpart;

(v) The word “sample” must appear on the shipping paper as part of the proper shipping name or in association with the basic description; and

(vi) In addition to other required markings and labels, the package must be marked “SAMPLE FOR EXAMINATION AND TESTING.”

(vii) All other applicable requirements of this subchapter must be met.

(3) *Examination and testing of sample lighters by an authorized testing agency*. Each sample lighter must be examined for conformance with paragraph (a) of this section by a person authorized by the Associate Administrator. In addition, lighters must be subjected to the following leakage test:

(i) A minimum of six lighters must be examined and tested at one time. Store the lighters in a desiccator for 24 hours. After drying, weigh each lighter on an analytical balance capable of accurately measuring to within  $\frac{1}{10}$  of a milligram (0.0001 grams).

(ii) After weighing, place the lighters together in an explosion-proof, controlled-temperature laboratory oven capable of maintaining  $38 \pm 1$  °C ( $100 \pm 2$  °F) for 96 continuous hours (4 days). At the end of 96 hours, remove the lighters from the oven and place them in the same desiccator and allow the lighters to cool to ambient temperature.

(iii) After cooling, weigh each lighter and determine the net weight differences for each lighter tested (subtract the mass after oven exposure from the original mass before oven exposure).

(iv) Weight losses must be assessed to determine the quantity of gas that leaked from the lighters and from the weight change as a result of absorbed moisture. If the net weight has increased, the test facility must run the required test using six empty lighters in parallel with the six filled lighters. The parallel tests are conducted to determine the weight of moisture absorbed in the plastic in order to determine the weight loss of the lighters from gas leakage.

(v) If the net weight loss for any one of the six lighters exceeds 20 milligrams (0.020 grams), the design must be rejected.

(vi) Lighters manufactured to a rejected lighter design may not be offered for transportation or transported in commerce unless approved in writing by the Associate Administrator.

(4) *Recordkeeping requirements*. (i) Following the examination of each new lighter design, the person or agency that conducted the examination and test must prepare a test report and make that test report available to the manufacturer. At a minimum, the test report must contain the following information:

(A) Name and address of test facility;

(B) Name and address of applicant;

(C) A test report identifier, that is, the authorized person or agency identifier code immediately followed by an

alpha/numeric identifier of four or more characters assigned to the specific lighter design by the authorized person or agency (e.g., “LAA\*\*\*\*,” where, “LAA” is the identification code assigned to the authorized person or agency by the Associate Administrator and “\*\*\*\*” is replaced with the unique test report identifier assigned to the specific lighter design by the authorized person or agency);

(D) Manufacturer of the lighter. For a foreign manufacturer, the U.S. agent or importer must be identified;

(E) Description of the lighter design type (e.g., model, dimensions, ignition mechanism, reservoir capacity, lot/batch number) in sufficient detail to ensure conformance with paragraph (b)(4)(iii) of this section; and

(F) A certification by the authorized testing agency that the lighter design conforms to paragraph (a) of this section and passes or does not pass the required leakage test in paragraph (b) of this section.

(ii) For as long as any lighter design is in production and for at least three years thereafter, a copy of each lighter’s test report must be maintained by the authorized testing agency that performed the examination and testing and the manufacturer of the design. For a foreign manufacturer, each test report must be maintained in accordance with this paragraph by the foreign manufacturer’s U.S. agent or importer.

(iii) Test reports must be traceable to a specific lighter design and must be made available to a representative of the Department upon request.

(5) *Transitional provisions.* Until January 1, 2012, approval numbers issued by the Associate Administrator prior to January 1, 2007 may continue to be marked on packages and annotated on shipping papers, where applicable. After that time, previously issued approvals (i.e., T-\*\*\*) will no longer be valid and each lighter design currently in production must be re-examined and tested under the provisions of this section.

(c) *Packaging requirements—(1) Inner containment.* Lighters must be placed in an inner packaging that is designed to prevent movement of the lighters and inadvertent ignition or leakage. The ignition device and gas control lever of

each lighter must be designed, or securely sealed, taped, or otherwise fastened or packaged to protect against accidental functioning or leakage of the contents during transport. If lighters are packed vertically in a plastic tray, a plastic, fiberboard or paperboard partition must be used to prevent friction between the ignition device and the inner packaging.

(2) *Outer packaging.* Lighters and their inner packagings must be tightly packed and secured against movement in any rigid specification outer packaging authorized in Subpart L of Part 178 of this subchapter at the Packing Group II performance level.

(d) *Shipping paper and marking requirements.* (1) In addition to the requirements of subpart C of part 172, shipping papers must be annotated with the lighter design test report identifier (see paragraph (b)(4)(i)(C) of this section) traceable to the test report assigned to the lighters or, if applicable, the previously issued approval number (i.e., T\*\*\*), in association with the basic description.

(2) In addition to the requirements of subpart D of part 172, a lighter design test report identifier (see paragraph (b)(4)(i)(C) of this section) or, if applicable, the previously issued approval number (i.e., T\*\*\*), must be marked on a package containing lighters.

(3) For transportation by vessel in a closed transport vehicle or a closed freight container, the following warning must be affixed to the access doors:

**WARNING—MAY CONTAIN EXPLOSIVE MIXTURES WITH AIR—KEEP IGNITION SOURCES AWAY WHEN OPENING**

The warning must be on a contrasting background and must be in letters measuring at least 12.7 mm (0.5 inch) in height.

(e) *Exceptions—(1) Common or contract carriage.* For highway transportation by common or contract carrier, when no more than 1,500 lighters covered by this section are transported in one motor vehicle, the requirements of subparts C through H of part 172, and Part 177 of this subchapter do not apply. Lighters transported in accordance with this paragraph are also excepted

from the specification packaging, shipping paper, and marking requirements specified in §§173.308(c) and (d). Inner packagings must conform to paragraph (c)(1) of this section. Lighters must be further packaged in rigid, strong outer packagings meeting the general packaging requirements of subpart B of part 173. Outer packagings must be plainly and durably marked, on two opposing sides or ends, with the word "LIGHTERS" and the number of devices contained therein in letters measuring at least 20 mm (0.79 in) in height. In addition, the package must include the test report identifier for each lighter design as specified in paragraph (b)(4)(i)(C) of this section or, if applicable, the previously issued approval number (i.e., T\*\*\*). The test report identifier or approval number must be durable, legible, in English, and located in, attached to, or marked directly on the package. No person may offer for transportation or transport the lighters or prepare the lighters for shipment unless that person has been specifically informed of the requirements of this section.

(2) *Private carriage.* For highway transportation by a private carrier, lighters that have been examined and successfully tested in accordance with this section are not subject to any other requirements of this subchapter under the following conditions:

(i) No person may offer for transportation or transport the lighters or prepare the lighters for shipment unless that person has been specifically informed of the requirements of this section;

(ii) Lighters must be placed in an inner packaging that is designed to prevent accidental activation of the ignition device or valve, release of gas, and movement of the lighters (e.g., tray, blister pack, etc.);

(iii) Inner packagings must be placed in a securely closed rigid outer packaging that limits movement of the inner packagings and protects them from damage;

(iv) The outer package may contain not more than 300 lighters;

(v) A transport vehicle may carry not more than 1,500 lighters at any one time;

(vi) The lighters may not be placed in an outer packaging with other hazardous materials; and

(vii) Outer packagings must be plainly and durably marked with the words "LIGHTERS, excepted quantity."

[71 FR 3427, Jan. 23, 2006, as amended at 73 FR 57006, Oct. 1, 2008]

#### § 173.309 Fire extinguishers.

(a) Fire extinguishers charged with a limited quantity of compressed gas to not more than 1660 kPa (241 psig) at 21 °C (70 °F) are excepted from labeling (except when offered for transportation by air) and the specification packaging requirements of this subchapter when shipped under the following conditions. In addition, shipments are not subject to subpart F of part 172 of this subchapter, to part 174 of this subchapter except § 174.24 or to part 177 of this subchapter except § 177.817.

(1) Each fire extinguisher must have contents which are nonflammable, nonpoisonous, and noncorrosive as defined under this subchapter.

(2) Each fire extinguisher must be shipped as an inner packaging.

(3) Nonspecification cylinders are authorized subject to the following conditions:

(i) The internal volume of each cylinder may not exceed 18 L (1,100 cubic inches). For fire extinguishers not exceeding 900 mL (55 cubic inches) capacity, the liquid portion of the gas plus any additional liquid or solid must not completely fill the container at 55 °C (130 °F). Fire extinguishers exceeding 900 mL (55 cubic inches) capacity may not contain any liquefied compressed gas;

(ii) Each fire extinguisher manufactured on and after January 1, 1976, must be designed and fabricated with a burst pressure of not less than six times its charged pressure at 21 °C (70 °F) when shipped;

(iii) Each fire extinguisher must be tested, without evidence of failure or damage, to at least three times its charged pressure at 21 °C (70 °F) but not less than 825 kPa (120 psig) before initial shipment, and must be marked to indicate the year of the test (within 90 days of the actual date of the original test) and with the words "MEETS DOT REQUIREMENTS." This marking is

## § 173.312

## 49 CFR Ch. I (10–1–08 Edition)

considered a certification that the fire extinguisher is manufactured in accordance with the requirements of this section. The words “This extinguisher meets all requirements of 49 CFR 173.306” may be displayed on fire extinguishers manufactured prior to January 1, 1976; and

(iv) For any subsequent shipment, each fire extinguisher must be in compliance with the retest requirements of the Occupational Safety and Health Administration Regulations of the Department of Labor, 29 CFR 1910.157.

(4) Specification 2P or 2Q (§§ 178.33 and 178.33a of this subchapter) inner nonrefillable metal packagings are authorized for use as fire extinguishers subject to the following conditions:

(i) The liquid portion of the gas plus any additional liquid or solid may not completely fill the packaging at 55 °C (130 °F);

(ii) Pressure in the packaging shall not exceed 1250 kPa (181 psig) at 55 °C (130 °F). If the pressure exceeds 920 kPa (141 psig) at 55 °C (130 °F), but does not exceed 1100 kPa (160 psig) at 55 °C (130 °F), a specification DOT 2P inner metal packaging must be used; if the pressure exceeds 1100 kPa (160 psig) at 55 °C (130 °F), a specification DOT 2Q inner metal packaging must be used. The metal packaging must be capable of withstanding, without bursting, a pressure of one and one-half times the equilibrium pressure of the contents at 55 °C (130 °F); and

(iii) Each completed inner packaging filled for shipment must have been heated until the pressure in the container is equivalent to the equilibrium pressure of the contents at 55 °C (130 °F) without evidence of leakage, distortion, or other defect.

(b) Specification 3A, 3AA, 3E, 3AL, 4B, 4BA, 4B240ET or 4BW (§§ 178.36, 178.37, 178.42, 178.46, 178.50, 178.51, 178.55 and 178.61 of this subchapter) cylinders are authorized for use as fire extinguishers.

[Amdt. 173–235, 58 FR 50503, Sept. 27, 1993, as amended by Amdt. 173–138, 59 FR 49134, Sept. 26, 1994; Amdt. 173–258, 61 FR 51240, Oct. 1, 1996; 66 FR 45380, 45381, Aug. 28, 2001; 71 FR 54395, Sept. 14, 2006]

### § 173.312 Requirements for shipment of MEGCs.

(a) *General requirements.* (1) Unless otherwise specified, a MEGC is authorized for the shipment of liquefied and non-liquefied compressed gases. Each pressure receptacle contained in a MEGC must meet the requirements in §§ 173.301, 173.301b, 173.302b and 173.304b, as applicable.

(2) The MEGC must conform to the design, construction, inspection and testing requirements prescribed in § 178.75 of this subchapter.

(3) No person may offer or accept a hazardous material for transportation in a MEGC that is damaged to such an extent that the integrity of the pressure receptacles or the MEGC’s structural or service equipment may be affected.

(4) No person may fill or offer for transportation a pressure receptacle in a MEGC if the pressure receptacle or the MEGC is due for periodic requalification, as prescribed in subpart C to part 180 of this subchapter. However, this restriction does not preclude transportation of pressure receptacles filled and offered for transportation prior to the requalification due date.

(5) Prior to filling and offering a MEGC for transportation, the MEGC’s structural and service equipment must be visually inspected. Any unsafe condition must be corrected before the MEGC is offered for transportation. All required markings must be legible.

(6) Except for Division 2.2 permanent gases, each pressure receptacle must be equipped with an individual shutoff valve that must be tightly closed while in transit. For Division 2.1, Division 2.2 liquefied gases and 2.3 gases, the manifold must be designed so that each pressure receptacle can be filled separately and be kept isolated by a valve capable of being closed during transit. For Division 2.1 gases, the pressure receptacles must be isolated by a valve into assemblies of not more than 3,000 L.

(b) *Filling.* (1) A MEGC may not be filled to a pressure greater than the lowest marked working pressure of any pressure receptacle. A MEGC may not be filled above its marked maximum permissible gross mass.

(2) After each filling, the shipper must verify the leakproofness of the closures and equipment. Each fill opening must be closed by a cap or plug.

(c) *Damage protection.* During transportation, a MEGC must be protected against damage to the pressure receptacles and service equipment resulting from lateral and longitudinal impact and overturning as prescribed in § 178.75 of this subchapter.

[71 FR 33884, June 12, 2006]

### § 173.313 UN Portable Tank Table for Liquefied Compressed Gases.

The UN Portable Tank Table for Liquefied Compressed Gases is referenced in § 172.102(c)(7)(iii) of this subchapter for portable tanks that are used to transport liquefied compressed gases. The table applies to each liquefied compressed gas that is identified with Special Provision T50 in Column (7) of the § 172.101 Table. In addition to providing the UN identification number

and proper shipping name, the table provides maximum allowable working pressures, bottom opening requirements, pressure relief device requirements, and degree of filling requirements for liquefied compressed gas permitted for transportation in a T50 portable tank. In the minimum test pressure column, “small” means a portable tank with a diameter of 1.5 meters or less when measured at the widest part of the shell, “sunshield” means a portable tank with a shield covering at least the upper third of the shell, “bare” means no sunshield or insulation is provided, and “insulated” means a complete cladding of sufficient thickness of insulating material necessary to provide a minimum conductance of not more than 0.67 w/m<sup>2</sup>/k. In the pressure relief requirements column, the word “Normal” denotes that a frangible disc as specified in § 178.276(e)(3) of this subchapter is not required.

UN PORTABLE TANK TABLE FOR LIQUEFIED COMPRESSED GASES

| UN No.     | Non-refrigerated liquefied compressed gases       | Minimum design pressure (bar)<br>small; bare;<br>sunshield; insulated | Openings below liquid level | Pressure relief requirements (See § 178.276(e)) | Maximum filling density (kg/l) |
|------------|---------------------------------------------------|-----------------------------------------------------------------------|-----------------------------|-------------------------------------------------|--------------------------------|
| 1005 ..... | Ammonia, anhydrous .....                          | 29.0<br>25.7<br>22.0<br>19.7<br>38.0                                  | Allowed                     | § 178.276(e)(3)                                 | 0.53                           |
| 1009 ..... | Bromotrifluoromethane or Refrigerant gas R 13B1.  | 34.0<br>30.0<br>27.5                                                  | Allowed                     | Normal                                          | 1.13                           |
| 1010 ..... | Butadienes, stabilized .....                      | 7.5<br>7.0<br>7.0<br>7.0                                              | Allowed                     | Normal                                          | 0.55                           |
| 1011 ..... | Butane .....                                      | 7.0<br>7.0<br>7.0<br>7.0                                              | Allowed                     | Normal                                          | 0.51                           |
| 1012 ..... | Butylene .....                                    | 8.0<br>7.0<br>7.0<br>7.0                                              | Allowed                     | Normal                                          | 0.53                           |
| 1017 ..... | Chlorine .....                                    | 19.0<br>17.0<br>15.0<br>13.5                                          | Not Allowed                 | § 178.276(e)(3)                                 | 1.25                           |
| 1018 ..... | Chlorodifluoromethane or Refrigerant gas R 22.    | 26.0<br>24.0<br>21.0<br>19.0<br>23.0                                  | Allowed                     | Normal                                          | 1.03                           |
| 1020 ..... | Chloropentafluoroethane or Refrigerant gas R 115. | 20.0<br>18.0<br>16.0                                                  | Allowed                     | Normal                                          | 1.06                           |

UN PORTABLE TANK TABLE FOR LIQUEFIED COMPRESSED GASES—Continued

| UN No.     | Non-refrigerated liquefied compressed gases                                                       | Minimum design pressure (bar) small; bare; sunshield; insulated | Openings below liquid level | Pressure relief requirements (See § 178.276(e)) | Maximum filling density (kg/l) |
|------------|---------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------|-------------------------------------------------|--------------------------------|
| 1021 ..... | 1-Chloro-1,2,2,2-tetrafluoroethane or Refrigerant gas R 124.                                      | 10.3                                                            | Allowed                     | Normal                                          | 1.2                            |
|            |                                                                                                   | 9.8                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.9                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1027 ..... | Cyclopropane .....                                                                                | 18.0                                                            | Allowed                     | Normal                                          | 0.53                           |
|            |                                                                                                   | 16.0                                                            |                             |                                                 |                                |
|            |                                                                                                   | 14.5                                                            |                             |                                                 |                                |
|            |                                                                                                   | 13.0                                                            |                             |                                                 |                                |
| 1028 ..... | Dichlorodifluoromethane or Refrigerant gas R 12.                                                  | 16.0                                                            | Allowed                     | Normal                                          | 1.15                           |
|            |                                                                                                   | 15.0                                                            |                             |                                                 |                                |
|            |                                                                                                   | 13.0                                                            |                             |                                                 |                                |
|            |                                                                                                   | 11.5                                                            |                             |                                                 |                                |
| 1029 ..... | Dichlorofluoromethane or Refrigerant gas R 21.                                                    | 7.0                                                             | Allowed                     | Normal                                          | 1.23                           |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1030 ..... | 1,1-Difluoroethane or Refrigerant gas R 152a.                                                     | 16.0                                                            | Allowed                     | Normal                                          | 0.79                           |
|            |                                                                                                   | 14.0                                                            |                             |                                                 |                                |
|            |                                                                                                   | 12.4                                                            |                             |                                                 |                                |
|            |                                                                                                   | 11.0                                                            |                             |                                                 |                                |
| 1032 ..... | Dimethylamine, anhydrous .....                                                                    | 7.0                                                             | Allowed                     | Normal                                          | 0.59                           |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1033 ..... | Dimethyl ether .....                                                                              | 15.5                                                            | Allowed                     | Normal                                          | 0.58                           |
|            |                                                                                                   | 13.8                                                            |                             |                                                 |                                |
|            |                                                                                                   | 12.0                                                            |                             |                                                 |                                |
|            |                                                                                                   | 10.6                                                            |                             |                                                 |                                |
| 1036 ..... | Ethylamine .....                                                                                  | 7.0                                                             | Allowed                     | Normal                                          | 0.61                           |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1037 ..... | Ethyl chloride .....                                                                              | 7.0                                                             | Allowed                     | Normal                                          | 0.8                            |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1040 ..... | Ethylene oxide with nitrogen up to a total pressure of 1MPa (10 bar) at 50 °C.                    | Only authorized in 10 bar insulated portable tanks—             | Not Allowed                 | § 178.276(e)(3)                                 | 0.78                           |
| 1041 ..... | Ethylene oxide and carbon dioxide mixture with more than 9% but not more than 87% ethylene oxide. | See MAWP definition in § 178.276(a)                             | Allowed                     | Normal                                          | See § 173.32(f)                |
| 1055 ..... | Isobutylene .....                                                                                 | 8.1                                                             | Allowed                     | Normal                                          | 0.52                           |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1060 ..... | Methyl acetylene and propadiene mixture, stabilized.                                              | 28.0                                                            | Allowed                     | Normal                                          | 0.43                           |
|            |                                                                                                   | 24.5                                                            |                             |                                                 |                                |
|            |                                                                                                   | 22.0                                                            |                             |                                                 |                                |
|            |                                                                                                   | 20.0                                                            |                             |                                                 |                                |
| 1061 ..... | Methylamine, anhydrous .....                                                                      | 10.8                                                            | Allowed                     | Normal                                          | 0.58                           |
|            |                                                                                                   | 9.6                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.8                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1062 ..... | Methyl bromide .....                                                                              | 7.0                                                             | Not Allowed                 | § 178.276(e)(3)                                 | 1.51                           |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
|            |                                                                                                   | 7.0                                                             |                             |                                                 |                                |
| 1063 ..... | Methyl chloride or Refrigerant gas R 40                                                           | 14.5                                                            | Allowed                     | Normal                                          | 0.81                           |
|            |                                                                                                   | 12.7                                                            |                             |                                                 |                                |
|            |                                                                                                   | 11.3                                                            |                             |                                                 |                                |
|            |                                                                                                   | 10.0                                                            |                             |                                                 |                                |
| 1064 ..... | Methyl mercaptan .....                                                                            | 7.0                                                             | Not Allowed                 | § 178.276(e)(3)                                 | 0.78                           |

## UN PORTABLE TANK TABLE FOR LIQUEFIED COMPRESSED GASES—Continued

| UN No.     | Non-refrigerated liquefied compressed gases                      | Minimum design pressure (bar) small; bare; sunshield; insulated | Openings below liquid level | Pressure relief requirements (See § 178.276(e)) | Maximum filling density (kg/l) |
|------------|------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------|-------------------------------------------------|--------------------------------|
| 1067 ..... | Dinitrogen tetroxide .....                                       | 7.0<br>7.0<br>7.0<br>7.0<br>7.0<br>7.0                          | Not Allowed                 | § 178.276(e)(3)                                 | 1.3                            |
| 1075 ..... | Petroleum gas, liquefied .....                                   | See MAWP definition in § 178.276(a)                             | Allowed                     | Normal                                          | See § 173.32(f)                |
| 1077 ..... | Propylene .....                                                  | 28.0<br>24.5<br>22.0<br>20.0                                    | Allowed                     | Normal                                          | 0.43                           |
| 1078 ..... | Refrigerant gas, n.o.s. ....                                     | See MAWP definition in § 178.276(a)                             | Allowed                     | Normal                                          | See § 173.32(f)                |
| 1079 ..... | Sulphur dioxide .....                                            | 11.6<br>10.3<br>8.5<br>7.6                                      | Not Allowed                 | § 178.276(e)(3)                                 | 1.23                           |
| 1082 ..... | Trifluorochloroethylene, stabilized or Refrigerant gas R 1113.   | 17.0                                                            | Not Allowed                 | § 178.276(e)(3)                                 | 1.13                           |
| 1083 ..... | Trimethylamine, anhydrous .....                                  | 15.0<br>13.1<br>11.6<br>7.0<br>7.0<br>7.0                       | Allowed                     | Normal                                          | 0.56                           |
| 1085 ..... | Vinyl bromide, stabilized .....                                  | 7.0<br>7.0<br>7.0<br>7.0                                        | Allowed                     | Normal                                          | 1.37                           |
| 1086 ..... | Vinyl chloride, stabilized .....                                 | 10.6<br>9.3<br>8.0                                              | Allowed                     | Normal                                          | 0.81                           |
| 1087 ..... | Vinyl methyl ether, stabilized .....                             | 7.0<br>7.0<br>7.0<br>7.0                                        | Allowed                     | Normal                                          | 0.67                           |
| 1581 ..... | Chloropicrin and methyl bromide mixture.                         | 7.0<br>7.0<br>7.0                                               | Not Allowed                 | § 178.276(e)(3)                                 | 1.51                           |
| 1582 ..... | Chloropicrin and methyl chloride mixture.                        | 19.2                                                            | Not Allowed                 | § 178.276(e)(3)                                 | 0.81                           |
| 1858 ..... | Hexafluoropropylene compressed or Refrigerant gas R 1216.        | 16.9<br>15.1<br>13.1<br>19.2                                    | Allowed                     | Normal                                          | 1.11                           |
| 1912 ..... | Methyl chloride and methylene chloride mixture.                  | 16.9<br>15.1<br>13.1<br>15.2                                    | Allowed                     | Normal                                          | 0.081                          |
| NA, 1954   | Insecticide gases, <i>flammable</i> , n.o.s. ....                | 13.0<br>11.6<br>10.1<br>See MAWP definition in § 178.276(a)     | Allowed                     | Normal                                          | § 173.32(f)                    |
| 1958 ..... | 1,2-Dichloro-1,1,2,2-tetrafluoroethane or Refrigerant gas R 114. | 7.0<br>7.0<br>7.0                                               | Allowed                     | Normal                                          | 1.3                            |



UN PORTABLE TANK TABLE FOR LIQUEFIED COMPRESSED GASES—Continued

| UN No.     | Non-refrigerated liquefied compressed gases                                                                                                                | Minimum design pressure (bar) small; bare; sunshield; insulated | Openings below liquid level | Pressure relief requirements (See § 178.276(e)) | Maximum filling density (kg/l) |
|------------|------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------|-------------------------------------------------|--------------------------------|
| 1965 ..... | Hydrocarbon gas, mixture liquefied, n.o.s..                                                                                                                | 7.0<br>See MAWP definition in 178.276(a)                        | Allowed                     | Normal                                          | See § 173.32(f)                |
| 1969 ..... | Isobutane .....                                                                                                                                            | 8.5<br>7.5<br>7.0<br>7.0                                        | Allowed                     | Normal                                          | 0.49                           |
| 1973 ..... | Chlorodifluoromethane and chloropentafluoroethane mixture with fixed boiling point, with approximately 49% chlorodifluoromethane or Refrigerant gas R 502. | 28.3                                                            | Allowed                     | Normal                                          | 1.05                           |
| 1974 ..... | Chlorodifluorobromomethane or Refrigerant gas R 12B1.                                                                                                      | 25.3<br>22.8<br>20.3<br>7.4                                     | Allowed                     | Normal                                          | 1.61                           |
| 1976 ..... | Octafluorocyclobutane or Refrigerant gas RC 318.                                                                                                           | 7.0<br>7.0<br>7.0<br>8.8                                        | Allowed                     | Normal                                          | 1.34                           |
| 1978 ..... | Propane .....                                                                                                                                              | 7.8<br>7.0<br>7.0<br>22.5                                       | Allowed                     | Normal                                          | 0.42                           |
| 1983 ..... | 1-Chloro-2,2,2-trifluoroethane or Refrigerant gas R 133a.                                                                                                  | 20.4<br>18.0<br>16.5<br>7.0                                     | Allowed                     | Normal                                          | 1.18                           |
| 2035 ..... | 1,1,1-Trifluoroethane compressed or Refrigerant gas R 143a.                                                                                                | 7.0<br>7.0<br>7.0<br>31.0                                       | Allowed                     | Normal                                          | 0.76                           |
| 2424 ..... | Octafluoropropane or Refrigerant gas R 218.                                                                                                                | 27.5<br>24.2<br>21.8<br>23.1                                    | Allowed                     | Normal                                          | 1.07                           |
| 2517 ..... | 1-Chloro-1,1-difluoroethane or Refrigerant gas R 142b.                                                                                                     | 20.8<br>18.6<br>16.6<br>8.9                                     | Allowed                     | Normal                                          | 0.99                           |
| 2602 ..... | Dichlorodifluoromethane and difluoroethane azeotropic mixture with approximately 74% dichlorodifluoromethane or Refrigerant gas R 500.                     | 7.8<br>7.0<br>7.0<br>20.0                                       | Allowed                     | Normal                                          | 1.01                           |
| 3057 ..... | Trifluoroacetyl chloride                                                                                                                                   | 18.0<br>16.0<br>14.5<br>14.6<br>12.9<br>11.3<br>9.9             | Not allowed                 | § 178.276(e)(3)                                 | 1.17                           |
| 3070 ..... | Ethylene oxide and dichlorodifluoromethane mixture with not more than 12.5% ethylene oxide.                                                                | 14.0                                                            | Allowed                     | § 178.276(e)(3)                                 | 1.09                           |
| 3153 ..... | Perfluoro (methyl vinyl ether) .....                                                                                                                       | 12.0<br>11.0<br>9.0<br>14.3<br>13.4                             | Allowed                     | Normal                                          | 1.14                           |

UN PORTABLE TANK TABLE FOR LIQUEFIED COMPRESSED GASES—Continued

| UN No.     | Non-refrigerated liquefied compressed gases                                                       | Minimum design pressure (bar) small; bare; sunshield; insulated | Openings below liquid level | Pressure relief requirements (See § 178.276(e)) | Maximum filling density (kg/l) |
|------------|---------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|-----------------------------|-------------------------------------------------|--------------------------------|
| 3159 ..... | 1,1,1,2-Tetrafluoroethane or Refrigerant gas R 134a.                                              | 11.2<br>10.2<br>17.7                                            | Allowed                     | Normal                                          | 1.04                           |
| 3161 ..... | Liquefied gas, flammable, n.o.s. ....                                                             | 15.7<br>13.8<br>12.1<br>See MAWP definition in § 178.276(a)     | Allowed                     | Normal                                          | § 173.32(f)                    |
| 3163 ..... | Liquefied gas, n.o.s. ....                                                                        | See MAWP definition in § 178.276(a)                             | Allowed                     | Normal                                          | § 173.32(f)                    |
| 3220 ..... | Pentafluoroethane or Refrigerant gas R 125.                                                       | 34.4                                                            | Allowed                     | Normal                                          | 0.95                           |
| 3252 ..... | Difluoromethane or Refrigerant gas R 32.                                                          | 30.8<br>27.5<br>24.5<br>43.0                                    | Allowed                     | Normal                                          | 0.78                           |
| 3296 ..... | Heptafluoropropane or Refrigerant gas R 227.                                                      | 39.0<br>34.4<br>30.5<br>16.0                                    | Allowed                     | Normal                                          | 1.2                            |
| 3297 ..... | Ethylene oxide and chlorotetrafluoroethane mixture, with not more than 8.8% ethylene oxide.       | 14.0<br>12.5<br>11.0<br>8.1                                     | Allowed                     | Normal                                          | 1.16                           |
| 3298 ..... | Ethylene oxide and pentafluoroethane mixture, with not more than 7.9% ethylene oxide.             | 7.0<br>7.0<br>7.0<br>25.9                                       | Allowed                     | Normal                                          | 1.02                           |
| 3299 ..... | Ethylene oxide and tetrafluoroethane mixture, with not more than 5.6% ethylene oxide.             | 23.4<br>20.9<br>18.6<br>16.7                                    | Allowed                     | Normal                                          | 1.03                           |
| 3318 ..... | Ammonia solution, relative density less than 0.880 at 15 °C in water, with more than 50% ammonia. | 14.7<br>12.9<br>11.2<br>See MAWP definition in § 178.276(a)     | Allowed                     | § 178.276(e)(3)                                 | § 173.32(f)                    |
| 3337 ..... | Refrigerant gas R 404A .....                                                                      | 31.6<br>28.3<br>25.3<br>22.5                                    | Allowed                     | Normal                                          | 0.84                           |
| 3338 ..... | Refrigerant gas R 407A .....                                                                      | 31.3<br>28.1<br>25.1<br>22.4                                    | Allowed                     | Normal                                          | 0.95                           |
| 3339 ..... | Refrigerant gas R 407B .....                                                                      | 33.0<br>29.6<br>26.5<br>23.6                                    | Allowed                     | Normal                                          | 0.95                           |
| 3340 ..... | Refrigerant gas R 407C .....                                                                      | 29.9<br>26.8<br>23.9<br>21.3                                    | Allowed                     | Normal                                          | 0.95                           |

## § 173.314

## 49 CFR Ch. I (10–1–08 Edition)

[69 FR 76174, Dec. 20, 2004, as amended at 70 FR 34399, June 14, 2005]

### § 173.314 Compressed gases in tank cars and multi-unit tank cars.

(a) *Definitions.* For definitions of compressed gases, see § 173.115.

(b) *General requirements.* (1) Tank car tanks containing compressed gases must not be shipped unless they were loaded by or with the consent of the owner thereof.

(2) Tank car tanks must not contain gases capable of combining chemically and must not be loaded with any gas which combines chemically with the gas previously loaded therein, until all residue has been removed and interior of tank thoroughly cleaned.

(3) For tanks of the DOT-106A and 110A class, the tanks must be placed in position and attached to car structure by the shipper.

(4) Wherever the word “approved” is used in this part of the regulations, it means approval by the Association of

American Railroads Committee on Tank Cars as prescribed in § 179.3 of this subchapter.

(5) Each tank car used for the transportation of anhydrous ammonia or any material that meets the criteria of Division 2.1 or 2.3 must have gaskets for manway cover plates and for mounting of fittings designed (for temperature, application, media, pressure, and size) to create a positive seal so that, under conditions normally incident to transportation, there will not be an identifiable release of the material to the environment. The use of sealants to install gaskets is prohibited.

(c) *Authorized gases, filling limits for tank cars.* A compressed gas in a tank car or a multi-unit tank car must be offered for transportation in accordance with § 173.31 and this section. The named gases must be loaded and offered for transportation in accordance with the following table:

| Proper shipping name                                                          | Outage and filling limits (see note 1) | Authorized tank car class          |
|-------------------------------------------------------------------------------|----------------------------------------|------------------------------------|
| Ammonia, anhydrous, or ammonia solutions > 50 percent ammonia.                | Notes 2, 10 .....                      | 105, 112, 114, 120.                |
| Ammonia solutions with > 35 percent, but ≤ 50 percent ammonia by mass.        | Note 3 .....                           | 106.                               |
| Argon, compressed .....                                                       | Note 3 .....                           | 105, 109, 112, 114, 120.           |
| Boron trichloride .....                                                       | Note 4 .....                           | 107.                               |
| Carbon dioxide, refrigerated liquid .....                                     | Note 3 .....                           | 105, 106.                          |
| Chlorine .....                                                                | Note 5 .....                           | 105.                               |
| Chlorine trifluoride .....                                                    | Note 6 .....                           | 105.                               |
| Chlorine pentafluoride .....                                                  | 125 .....                              | 106.                               |
| Dimethyl ether .....                                                          | Note 3 .....                           | 106, 110.                          |
| Dimethylamine, anhydrous .....                                                | Note 3 .....                           | 106, 110.                          |
| Dinitrogen tetroxide, inhibited .....                                         | Note 3 .....                           | 105, 106, 110, 112, 114, 120.      |
| Division 2.1 materials not specifically identified in this table .....        | Note 3 .....                           | 105, 106, 112.                     |
| Division 2.2 materials not specifically identified in this table .....        | Note 3 .....                           | 105, 106, 110.                     |
| Division 2.3 Zone A materials not specifically identified in this table ..... | Notes 9, 10 .....                      | 105, 106, 110, 112, 114, 120.      |
| Division 2.3 Zone B materials not specifically identified in this table ..... | Note 3 .....                           | 105, 106, 109, 110, 112, 114, 120. |
| Division 2.3 Zone C materials not specifically identified in this table ..... | None .....                             | See § 173.245.                     |
| Division 2.3 Zone D materials not specifically identified in this table ..... | Note 3 .....                           | 105, 106, 110, 112, 114, 120.      |
| Ethylamine .....                                                              | Note 3 .....                           | 105, 106, 110, 112, 114, 120.      |
| Helium, compressed .....                                                      | Note 4 .....                           | 107.                               |
| Hydrogen .....                                                                | Note 4 .....                           | 107.                               |
| Hydrogen chloride, refrigerated liquid .....                                  | Note 7 .....                           | 105.                               |
| Hydrogen sulphide, liquified .....                                            | 68 .....                               | 106.                               |
| Methyl bromide .....                                                          | Note 3 .....                           | 105, 106.                          |
| Methyl chloride .....                                                         | Note 3 .....                           | 105, 106, 112.                     |
| Methyl mercaptan .....                                                        | Note 3 .....                           | 105, 106.                          |
| Methylamine, anhydrous .....                                                  | Note 3 .....                           | 105, 106, 112.                     |
| Nitrogen, compressed .....                                                    | Note 4 .....                           | 107.                               |
| Nitrosyl chloride .....                                                       | 124 .....                              | 105.                               |
| Nitrous oxide, refrigerated liquid .....                                      | 110 .....                              | 106.                               |
| Oxygen, compressed .....                                                      | Note 5 .....                           | 105.                               |
| Phosgene .....                                                                | Note 4 .....                           | 107.                               |
|                                                                               | Note 3 .....                           | 106.                               |

| Proper shipping name             | Outage and filling limits (see note 1) | Authorized tank car class |
|----------------------------------|----------------------------------------|---------------------------|
| Sulfur dioxide, liquefied .....  | 125 .....                              | 105, 106, 110.            |
| Sulfuryl fluoride .....          | 120 .....                              | 105.                      |
| Vinyl fluoride, stabilized ..... | Note 8 .....                           | 105.                      |

NOTES: 1. The percent filling density for liquefied gases is hereby defined as the percent ratio of the mass of gas in the tank to the mass of water that the tank will hold. For determining the water capacity of the tank in kilograms, the mass of 1 L of water at 15.5 °C in air is 1 kg. (the mass of one gallon of water at 60 °F in air is 8.32828 pounds).

2. The liquefied gas must be loaded so that the outage is at least two percent of the total capacity of the tank at the reference temperature of 46 °C (115 °F) for a noninsulated tank; 43 °C (110 °F) for a tank having a thermal protection system incorporating a metal jacket that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 10.22 kilojoules per hour per square meter per degree Celsius (0.5 Btu per hour per square foot per degree F) temperature differential; and 41 °C (105 °F) for an insulated tank having an insulation system incorporating a metal jacket that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 1.5333 kilojoules per hour per square meter per degree Celsius (0.075 Btu per hour per square foot per degree F) temperature differential.

3. The requirements of § 173.24(b) apply.

4. The gas pressure at 54.44 °C (130 °F.) in any non-insulated tank car may not exceed 7/10 of the marked test pressure, except that a tank may be charged with helium to a pressure 10 percent in excess of the marked maximum gas pressure at 54.44 °C (130 °F.) of each tank.

5. The liquid portion of the gas at -17.77 °C (0 °F.) must not completely fill the tank.

6. The maximum permitted filling density is 125 percent. The quantity of chlorine loaded into a single unit-tank car may not be loaded in excess of the normal lading weights nor in excess of 81.65 Mg (90 tons).

7. 89 percent maximum to 80.1 percent minimum at a test pressure of 6.2 Bar (90 psig).

8. 59.6 percent maximum to 53.6 percent minimum at a test pressure of 7.2 Bar (105 psig).

9. For a liquefied petroleum gas, the liquefied gas must be loaded so that the outage is at least one percent of the total capacity of the tank at the reference temperature of 46 °C (115 °F) for a noninsulated tank; 43 °C (110 °F) for a tank having a thermal protection system incorporating a metal jacket that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 10.22 kilojoules per hour per square meter per degree Celsius (0.5 Btu per hour per square foot per degree F) temperature differential; and 41 °C (105 °F) for an insulated tank having an insulation system incorporating a metal jacket that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 1.5333 kilojoules per hour per square meter per degree Celsius (0.075 Btu per hour per square foot per degree F) temperature differential.

10. For liquefied petroleum gas and anhydrous ammonia, during the months of November through March (winter), the following reference temperatures may be used: 38 °C (100 °F) for a noninsulated tank; 32 °C (90 °F) for a tank having a thermal protection system incorporating a metal jacket that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 10.22 kilojoules per hour per square meter per degree Celsius (0.5 Btu per hour per square foot per degree F) temperature differential; and 29 °C (85 °F) for an insulated tank having an insulation system incorporating a metal jacket and insulation that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 1.5333 kilojoules per hour per square meter per degree Celsius (0.075 Btu per hour per square foot per degree F) temperature differential. The winter reference temperatures may only be used for a tank car shipped directly to a consumer for unloading and not stored in transit. The owner of the tank must inform each customer that the tank car was filled based on winter reference temperatures. The tank must be unloaded as soon as possible after March in order to retain the specified outage and to prevent a release of hazardous material which might occur due to the tank car becoming liquid full at higher temperatures.

(d) [Reserved]

(e) *Verification of content.* The amount of liquefied gas loaded into each tank may be determined either by measurement or calculation of the weight. If by measurement, the weight must be checked after disconnecting the loading line by the use of proper scales. If by calculation, the weight of liquefied petroleum gas, methylacetylene propadiene, stabilized, dimethylamine, methylamine anhydrous, or trimethylamine may be calculated using the outage tables supplied by the tank car owners and the specific gravities as determined at the plant, and this computation must be checked by determination of specific gravity of product after loading. Carriers may verify calculated weights by use of proper scales. The use of a fixed tube gauge device is authorized for determining the weight of methyl mercaptan in Specification 105A300W tanks instead of weighing.

(f) [Reserved]

(g) Special requirements for hydrogen chloride, refrigerated liquid, and vinyl fluoride, stabilized.

(1) The shipper shall notify the Federal Railroad Administration whenever a tank car is not received by the consignee within 20 days from the date of shipment. Notification to the Federal Railroad Administration may be made by e-mail to [Hmassist@fra.dot.gov](mailto:Hmassist@fra.dot.gov) or telephone call to (202) 493-6229.

(2) A tank car containing hydrogen chloride, refrigerated liquid must have the auxiliary valve on the pressure relief device closed during transportation.

(3) See § 179.102-17 of this subchapter for additional requirements.

(4) Tank cars containing hydrogen chloride, refrigerated liquid, must be unloaded to such an extent that any residue remaining in the tank at a reference temperature of 32 °C (90 °F) will not actuate the reclosing pressure relief device.

(h)-(i) [Reserved]

(j) *Special requirements for materials having a primary or secondary Division 2.1 (flammable gas) hazard.* For single unit tank cars, interior pipes of loading and unloading valves, sampling devices, and gauging devices with an opening for the passage of the lading exceeding 1.52 mm (0.060 inch) diameter must be equipped with excess flow valves. For single unit tank cars constructed before January 1, 1972, gauging devices must conform to this paragraph by no later than July 1, 2006. The protective housing cover must be provided with an opening, with a weather-proof cover, above each pressure relief valve that is concentric with the discharge of the pressure relief valve and that has an area at least equal to the valve outlet area. Class DOT 109 tank cars and tank cars manufactured from aluminum or nickel plate are not authorized.

(k) *Special requirements for chlorine.* Tank cars built after September 30, 1991, must have an insulation system consisting of 5.08 cm (2 inches) glass fiber placed over 5.08 cm (2 inches) of ceramic fiber. Tank cars must have excess flow valves on the interior pipes of liquid discharge valves. Tank cars constructed to a DOT 105A500W specification may be marked as a DOT 105A300W specification with the size and type of reclosing pressure relief valves required by the marked specification.

(l) *Special requirements for hydrogen sulphide.* Each multi-unit tank car must be equipped with adequate pressure relief devices of the fusible plug type having a yield temperature not over 76.66 °C (170 °F.), and not less than 69.44 °C (157 °F.). Each device must be resistant to extrusion of the fusible alloy and leak tight at 55 °C (130 °F.). A threaded solid plug must seal each valve outlet. In addition, a metal cover must protect all valves.

(m) *Special requirements for nitrosyl chloride.* Single unit tank cars and their associated service equipment, such as venting, loading and unloading valves, and reclosing pressure relief valves, must be made of metal or clad with a material that is not subject to rapid deterioration by the lading. Multi-unit tank car tanks must be nickel-clad and have reclosing pressure relief devices incorporating a fusible

plug having a yield temperature of 79.44 °C (175 °F.). Reclosing pressure relief devices must be vapor tight at 54.44 °C (130 °F.).

(n) *Special requirements for hydrogen.* Each tank car must be equipped with one or more pressure relief devices. The discharge outlet for each pressure relief device must be connected to a manifold having a non-obstructed discharge area of at least 1.5 times the total discharge area of the pressure relief devices connected to the manifold. All manifolds must be connected to a single common header having a non-obstructed discharge pointing upward and extending above the top of the car. The header and the header outlet must each have a non-obstructed discharge area at least equal to the total discharge area of the manifolds connected to the header. The header outlet must be equipped with an ignition device that will instantly ignite any hydrogen discharged through the pressure relief device.

(o) *Special requirements for carbon dioxide, refrigerated liquid and nitrous oxide, refrigerated liquid.* Each tank car must have an insulation system so that the thermal conductance is not more than 0.613 kilojoules per hour, per square meter, per degree Celsius (0.03 B.t.u. per square foot per hour, per degree Fahrenheit) temperature differential. Each tank car must be equipped with one reclosing pressure relief valve having a start-to-discharge pressure not to exceed 75 percent of the tank test pressure and one non-reclosing pressure relief valve having a rupture disc design to burst at a pressure less than the tank test pressure. The discharge capacity of each pressure relief device must be sufficient to prevent building up of pressure in the tank in excess of 82.5 percent of the test pressure of the tank. Tanks must be equipped with two regulating valves set to open at a pressure not to exceed 24.1 Bar (350 psi) on DOT 105A500W tanks and at a pressure not to exceed 27.6 Bar (400 psi) on DOT 105A600W tanks. Each regulating valve and pressure relief device must have its final discharge piped to the outside of the protective housing.

[Amdt. 173–224, 55 FR 52665, Dec. 21, 1990]

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 173.315**

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 173.314, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 173.315 Compressed gases in cargo tanks and portable tanks.**

(a) Liquefied compressed gases that are transported in UN portable tanks, DOT specification portable tanks, or cargo tanks must be prepared in accordance with this section, § 173.32, § 173.33 and subpart E or subpart G of part 180 of this subchapter, as applica-

ble. For cryogenic liquid in cargo tanks, see § 173.318. For marking requirements for portable tanks and cargo tanks, see § 172.326 and § 172.328 of this subchapter, as applicable.

(1) *UN portable tanks*: UN portable tanks must be loaded and offered for transportation in accordance with portable tank provision T50 in § 172.102 of this subchapter.

(2) *Cargo tanks and DOT specification portable tanks*: Cargo tanks and DOT specification portable tanks must be loaded and offered for transportation in accordance with the following table:

| Kind of gas                                                                                         | Maximum permitted filling density |                                                     | Specification container required                 |                                    |
|-----------------------------------------------------------------------------------------------------|-----------------------------------|-----------------------------------------------------|--------------------------------------------------|------------------------------------|
|                                                                                                     | Percent by weight<br>(see Note 1) | Percent by volume<br>(see par. (f) of this section) | Type (see Note 2)                                | Minimum design pressure (psig)     |
| Ammonia, anhydrous or Ammonia solutions with greater than 50 percent ammonia (see Notes 14 and 17). | 56 .....                          | 82, See Note 5 .....                                | DOT-51, MC-330, MC-331; See Notes 12, 17 and 27. | 265; See Note 17.                  |
| Ammonia solutions with more than 35 percent but not more than 50 percent ammonia.                   | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331; see Note 12.             | 100; See par. (c) of this section. |
| Bromotrifluoromethane (R-13B1 or H-1301); (See Note 9).                                             | 133 .....                         | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | 365.                               |
| Butadiene, stabilized .....                                                                         | See par. (b) of this section.     | See par. (b) of this section.                       | DOT-51, MC-330, MC-331.                          | 100.                               |
| Carbon dioxide, refrigerated liquid .....                                                           | See par. (c)(1) of this section.  | 95 .....                                            | .....do .....                                    | 200; see Note 3.                   |
| Chlorine .....                                                                                      | 125 .....                         | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | 225; See Notes 4 and 8.            |
| Chlorodifluoroethane (R-142b) (1-Chloro 1,1-difluoroethane); (See Note 9).                          | 100 .....                         | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | 100.                               |
| Chlorodifluoromethane (R-22); (See Note 9).                                                         | 105 .....                         | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | 250.                               |
| Chloropentafluoroethane (R-115); (See Note 9).                                                      | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | See par. (c) of this section.      |
| Chlorotrifluoromethane (R-13); (See Note 9).                                                        | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | See par. (c) of this section.      |
| Dichlorodifluoromethane (R-12); (See Note 9).                                                       | 119 .....                         | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | 150.                               |
| Difluoroethane (R-152a); (See Note 9)                                                               | 79 .....                          | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | 150.                               |
| Dimethyl ether (see Note 16) .....                                                                  | 59 .....                          | .....do .....                                       | .....do .....                                    | 200.                               |
| Dimethylamine, anhydrous .....                                                                      | 59 .....                          | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | 150.                               |
| Division 2.1, materials not specifically provided for in this table.                                | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | See Note 18.                       |
| Division 2.2, materials not specifically provided for in this table.                                | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331.                          | See Note 19.                       |
| Division 2.3, Hazard Zone A, materials not specifically provided for in this table.                 | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331; See Note 23.             | See Note 20.                       |
| Division 2.3, Hazard Zone B, materials not specifically provided for in this table.                 | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331; See Note 23.             | See Note 20.                       |
| Division 2.3, Hazard Zone C, materials not specifically provided for in this table.                 | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331; See Note 24.             | See Note 21.                       |
| Division 2.3, Hazard Zone D, materials not specifically provided for in this table.                 | See par. (c) of this section.     | See Note 7 .....                                    | DOT-51, MC-330, MC-331; See Note 25.             | See Note 22.                       |
| Ethane, refrigerated liquid .....                                                                   | .....                             | See par. (c) of this section.                       | MC-331, MC-338                                   | 100; see Note 11.                  |

| Kind of gas                                                                              | Maximum permitted filling density |                                                        | Specification container required     |                                   |
|------------------------------------------------------------------------------------------|-----------------------------------|--------------------------------------------------------|--------------------------------------|-----------------------------------|
|                                                                                          | Percent by weight<br>(see Note 1) | Percent by volume<br>(see par. (f) of this<br>section) | Type (see Note 2)                    | Minimum design<br>pressure (psig) |
| Ethane-propane mixture, refrigerated liquid.                                             | .....                             | See par. (c) of this section.                          | MC–331, MC–338                       | 275; see Note 11.                 |
| Hexafluoropropylene .....                                                                | 110 .....                         | See Note 7 .....                                       | DOT-51, MC–330, MC–331.              | 250.                              |
| Hydrogen chloride, refrigerated liquid ....                                              | 103.0 .....                       | See Note 7 .....                                       | MC–331, MC–338                       | 100; see Note 11.                 |
|                                                                                          | 91.6 .....                        | .....do .....                                          | .....do .....                        | 300; see Note 11.                 |
|                                                                                          | 86.7 .....                        | .....do .....                                          | .....do .....                        | 450; see Note 11.                 |
| Liquefied petroleum gas (see Note 15)                                                    | See par. (b) of this section.     | See par. (b) of this section.                          | DOT-51, MC–330, MC–331; See Note 26. | See par. (c) of this section.     |
| Methylacetylene-propadiene, stabilized (see Note 13).                                    | 53 .....                          | 90 .....                                               | DOT 51, MC 330, MC 331.              | 200.                              |
| Methylamine, anhydrous .....                                                             | 60 .....                          | See Note 7 .....                                       | DOT-51, MC–330, MC–331..             |                                   |
| Methyl chloride .....                                                                    | 84 .....                          | 88.5 .....                                             | .....do .....                        | 150.                              |
| Methyl chloride (optional portable tank 2,000 pounds water capacity, fusible plug).      | .....do .....                     | See Note 6 .....                                       | DOT-51 .....                         | 225.                              |
| Methyl mercaptan .....                                                                   | 80 .....                          | 90 .....                                               | DOT-51, MC–330, MC–331; See Note 23. | 100.                              |
| Nitrous oxide, refrigerated liquid .....                                                 | See par. (c)(1) of this section.  | 95 .....                                               | DOT-51, MC–330, MC–331.              | 200; See Note 3.                  |
| Refrigerant gas, n.o.s. or Dispersant gas, n.o.s. (See Note 9).                          | See par. (c) of this section.     | See Note 7 .....                                       | DOT-51, MC–330, MC–331.              | See par. (c) of this section.     |
| Sulfur dioxide (tanks not over 1,200 gallons water capacity).                            | 125 .....                         | 87.5 .....                                             | DOT-51, MC–330, MC–331; See Note 24. | 150; See Note 4.                  |
| Sulfur dioxide (tanks over 1,200 gallons water capacity).                                | 125 .....                         | 87.5 .....                                             | DOT-51, MC–330, MC–331; See Note 24. | 125; See Note 4.                  |
| Sulfur dioxide (optional portable tank 1,000–2,000 pounds water capacity, fusible plug). | 125 .....                         | See Note 6 .....                                       | DOT-51; See Note 24.                 | 225.                              |
| Trimethylamine, anhydrous .....                                                          | 57 .....                          | See Note 7 .....                                       | DOT-51, MC–330, MC–331.              | 150.                              |
| Vinyl chloride .....                                                                     | 84 (see Note 13) ...              | See Note 7 .....                                       | MC–330, MC–331                       | 150.                              |
| Vinyl fluoride, stabilized .....                                                         | 66 .....                          | .....do .....                                          | .....do .....                        | 250; see Note 11.                 |
| Vinyl methyl ether .....                                                                 | 68 .....                          | See Notes 7 and 13.                                    | .....do .....                        | 100.                              |

NOTE 1: Maximum filling density for liquefied gases is hereby defined as the percent ratio of the weight of gas in the tank to the weight of water that the tank will hold. For determining the water capacity of the tank in pounds, the weight of a gallon (231 cubic inches) of water at 60 °F. in air shall be 8.32828 pounds.

NOTE 2: See § 173.32 for authority to use other portable tanks and for manifolding cargo tanks and for manifolding cargo tanks, see paragraph (q) of this section. Specifications MC 330 cargo tanks may be painted as specified for MC 331 cargo tanks.

NOTE 3: If cargo tanks and portable tank containers for carbon dioxide, refrigerated liquid, and nitrous oxide, refrigerated liquid, are designed to conform to the requirements in Section VIII of the ASME Code for low temperature operation (IBR, see § 171.7 of this subchapter), the design pressure may be reduced to 100 psig or the controlled pressure, whichever is greater.

NOTE 4: Material must be steel. Packagings must have a corrosion allowance of 20 percent or 0.10 inch, whichever is less, added to the metal thickness. The minimum wall thickness for chlorine packagings is 0.300 inch for stainless steel or 0.625 inch for carbon steel, including corrosion allowance.

NOTE 5: Unlagged cargo tanks and portable tank containers for liquid anhydrous ammonia may be filled to 87.5 percent by volume provided the temperature of the anhydrous ammonia being loaded into such tanks is determined to be not lower than 30 °F. or provided the filling of such tanks is stopped at the first indication of frost or ice formation on the outside surface of the tank and is not resumed until such frost or ice has disappeared.

NOTE 6: Tanks equipped with fusible plugs must be filled by weight.

NOTE 7: Tanks must be filled by weight.

NOTE 8: Chlorine packagings may be shipped only if the contents are to be unloaded at one unloading point.

NOTE 9: This gas may be transported in authorized cargo tanks and portable tanks marked "DISPERSANT GAS," or "REFRIGERANT GAS."

NOTE 10: [Reserved]

NOTE 11: MC–330, MC–331 and MC–338 cargo tanks must be insulated. Cargo tanks must meet all the following requirements. Each tank must have a design service temperature of minus 100 °F., or no warmer than the boiling point at one atmosphere of the hazardous material to be shipped therein, whichever is colder, and must conform to the low-temperature requirements in Section VIII of the ASME Code. When the normal travel time is 24 hours or less, the tank's holding time as loaded must be at least twice the normal travel time. When the normal travel time exceeds 24 hours, the tank's holding time as loaded must be at least 24 hours greater than the normal travel time. The holding time is the elapsed time from loading until venting occurs under equilibrium conditions. The cargo tank must have an outer jacket made of steel when the cargo tank is used to transport a flammable gas.

NOTE 12: No aluminum, copper, silver, zinc or an alloy of any of these metals shall be used in packaging construction where it comes into contact with the lading.

NOTE 13: All parts of valves and safety devices in contact with contents of tank must be of a metal or other material suitably treated if necessary, which will not cause formation of any acetylides.

## Pipeline and Hazardous Materials Safety Admin., DOT

## § 173.315

NOTE 14: Specifications MC 330 and MC 331 cargo tanks constructed of other than quenched and tempered steel "(NOT)" are authorized for all grades of anhydrous ammonia. Specifications MC 330 and MC 331 cargo tanks constructed of quenched and tempered steel "(QT)" (see marking requirements of § 172.328(c) of this subchapter) are authorized for anhydrous ammonia having a minimum water content of 0.2 percent by weight. Any tank being placed in anhydrous ammonia service or a tank which has been in other service or has been opened for inspection, test, or repair, must be cleaned of the previous product and must be purged of air before loading. See § 172.203(h) of this subchapter for special shipping paper requirements.

NOTE 15: Specifications MC 330 and MC 331 cargo tanks constructed of other than quenched and tempered steel "(NOT)" are authorized for all grades of liquefied petroleum gases. Only grades of liquefied petroleum gases determined to be "noncorrosive" are authorized in Specification MC 330 and MC 331 cargo tanks constructed of quenched and tempered steel "(QT)". "Noncorrosive" means the corrosiveness of the gas does not exceed the limitations for classification 1 of the ASTM Copper Strip Classifications when tested in accordance with ASTM D 1838, "Copper Strip Corrosion by Liquefied Petroleum (LP) Gases" (IBR, see § 171.7 of this subchapter). (For (QT) and (NOT) marking requirements, see § 172.328(c) of this subchapter. For special shipping paper requirements, see § 172.203(h) of this subchapter.)

NOTE 16: Openings, inlets, and outlets on MC 330 and MC 331 cargo tanks must conform to § 178.337-8(a) of this subchapter. MC 330 and MC 331 cargo tanks must be equipped with emergency discharge control equipment as specified in § 178.337-11(a) of this subchapter.

NOTE 17: A Specification MC-330 or MC-331 cargo tank or a nonspecification cargo tank meeting, and marked in conformance with, the edition of the ASME Code in effect when it was fabricated, may be used for the transportation of anhydrous ammonia if it:

- (1) Has a minimum design pressure not lower than 250 psig;
- (2) Was manufactured in conformance with the ASME Code prior to January 1, 1981, according to its ASME name plate and manufacturer's data report;
- (3) Is painted white or aluminum;
- (4) Complies with Note 12 of this paragraph;
- (5) Has been inspected and tested in accordance with subpart E of part 180 of this subchapter as specified for MC 331 cargo tanks.

(6) Was used to transport anhydrous ammonia prior to January 1, 1981;

(7) Is operated exclusively in intrastate commerce (including its operation by a motor carrier otherwise engaged in interstate commerce) in a state where its operation was permitted by the laws of that State (not including the incorporation of this subchapter) prior to January 1, 1981; and

(8) Is operated in conformance with all other requirements of this subchapter.

NOTE 18: The minimum packaging design pressure must not be less than the vapor pressure at the reference temperature of the lading plus one percent or 173.4 kPa (25 psig), whichever is less.

NOTE 19: The minimum packaging design pressure must not be less than the vapor pressure at the reference temperature of the lading.

NOTE 20: The minimum packaging design pressure must not be less than 1.5 times the vapor pressure of the lading at 46 °C (115 °F).

NOTE 21: The minimum packaging design pressure must not be less than 1.3 times the vapor pressure of the lading at 46 °C (115 °F).

NOTE 22: The minimum packaging design pressure must not be less than 1.1 times the vapor pressure of the lading at 46 °C (115 °F).

NOTE 23: Packagings must be made of stainless steel except that steel other than stainless steel may be used in accordance with the provisions of § 173.24b(b) of this part. Thickness of stainless steel for shell and heads must be the greater of 7.62 mm (0.300 inch) or the thickness required for the packaging at its minimum design pressure.

NOTE 24: Packagings must be made of stainless steel except that steel other than stainless steel may be used in accordance with the provisions of § 173.24b(b) of this part. Thickness of stainless steel for shell and heads must be the greater of 6.35 mm (0.250 inch) or the thickness required for the packaging at its minimum design pressure. For sulphur dioxide, this Note does not apply until October 1, 1994.

NOTE 25: Packagings must be made of stainless steel except that steel other than stainless steel may be used in accordance with the provisions of § 173.24b(b) of this part. Thickness for shell and heads must be as calculated for the packaging at its minimum design pressure.

NOTE 26: Non-specification cargo tanks may be used for the transportation of liquefied petroleum gas, subject to the conditions prescribed in paragraph (k) of this section.

NOTE 27: Non-specification cargo tanks may be used for transportation of Ammonia, anhydrous and ammonia solutions with greater than 50% ammonia, subject to the conditions prescribed in paragraph (m) of this section.

(b) Maximum permitted filling densities for cargo and portable tank containers for transportation of butadiene, stabilized, and liquefied petroleum gas are as follows:

| Maximum specific gravity of the liquid material at 60 °F. | Maximum permitted filling density in percent of the water-weight capacity of the tanks (percent) See Note 1 |                   |
|-----------------------------------------------------------|-------------------------------------------------------------------------------------------------------------|-------------------|
|                                                           | 1200 gallons or less                                                                                        | Over 1200 gallons |
| 0.473 to 0.480 .....                                      | 38                                                                                                          | 41                |
| 0.481 to 0.488 .....                                      | 39                                                                                                          | 42                |
| 0.489 to 0.495 .....                                      | 40                                                                                                          | 43                |
| 0.496 to 0.503 .....                                      | 41                                                                                                          | 44                |
| 0.504 to 0.510 .....                                      | 42                                                                                                          | 45                |
| 0.511 to 0.519 .....                                      | 43                                                                                                          | 46                |
| 0.520 to 0.527 .....                                      | 44                                                                                                          | 47                |
| 0.528 to 0.536 .....                                      | 45                                                                                                          | 48                |
| 0.537 to 0.544 .....                                      | 46                                                                                                          | 49                |
| 0.545 to 0.552 .....                                      | 47                                                                                                          | 50                |

| Maximum specific gravity of the liquid material at 60 °F. | Maximum permitted filling density in percent of the water-weight capacity of the tanks (percent) See Note 1 |                   |
|-----------------------------------------------------------|-------------------------------------------------------------------------------------------------------------|-------------------|
|                                                           | 1200 gallons or less                                                                                        | Over 1200 gallons |
| 0.553 to 0.560 .....                                      | 48                                                                                                          | 51                |
| 0.561 to 0.568 .....                                      | 49                                                                                                          | 52                |
| 0.569 to 0.576 .....                                      | 50                                                                                                          | 53                |
| 0.577 to 0.584 .....                                      | 51                                                                                                          | 54                |
| 0.585 to 0.592 .....                                      | 52                                                                                                          | 55                |
| 0.593 to 0.600 .....                                      | 53                                                                                                          | 56                |
| 0.601 to 0.608 .....                                      | 54                                                                                                          | 57                |
| 0.609 to 0.617 .....                                      | 55                                                                                                          | 58                |
| 0.618 to 0.626 .....                                      | 56                                                                                                          | 59                |
| 0.627 and over .....                                      | 57                                                                                                          | 60                |

NOTE 1: Filling is permitted by volume provided the same filling density is used as permitted by weight, except when using fixed length dip tube or other fixed maximum liquid level indicators (paragraph (f) of this section), in which case the maximum permitted filling density shall not exceed 97 percent of the maximum permitted filling density by weight contained in the table.



(1) *Odorization.* All liquefied petroleum gas shall be effectively odorized as required in Note 2 of this paragraph to indicate positively, by a distinctive odor, the presence of gas down to a concentration in air of not over one-fifth the lower limit of combustibility provided, however, that odorization is not required if harmful in the use or further processing of the liquefied petroleum gas, or if odorization will serve no useful purpose as a warning agent in such use or further processing.

NOTE 1: The lower limits of combustibility of the more commonly used liquefied petroleum gases are: Propane, 2.15 percent; butane, 1.55 percent. These figures represent volumetric percentages of gas-air mixtures in each case.

NOTE 2: The use of 1.0 pound of ethyl mercaptan, 1.0 pound of thiophane, or 1.4 pounds of amyl mercaptan per 10,000 gallons of liquefied petroleum gas shall be considered sufficient to meet the requirements of § 173.315(b)(1). This note does not exclude the use of any other odorant in sufficient quantity to meet the requirements of § 173.315(b)(1).

(c) Except as otherwise provided, the loading of a liquefied gas into a cargo tank or portable tank shall be determined by weight or by a suitable liquid level gauging device. The vapor pressure (psig) at 115 °F. must not exceed the design pressure of the cargo tank or portable tank container. The outage and filling limits for liquefied gases must be as prescribed in § 173.24b of this part, except that this requirement does not apply to:

(1) *A tank containing carbon dioxide, refrigerated liquid or nitrous oxide, refrigerated liquid.* Such tank is required to be equipped with suitable pressure control valves and may not be filled to a level exceeding 95 percent of the volumetric capacity of the tank.

(2) *A tank containing ethane, refrigerated liquid; ethane-propane mixture, refrigerated liquid; or hydrogen chloride, refrigerated liquid.* Such tank must be filled to allow at least two percent outage below the inlet of the pressure relief valve or pressure control valve under conditions of incipient opening, with the tank in a level attitude.

(d) If the loading of cargo tanks and portable tank containers with liquefied gases is to be determined by weight, the gross weight shall be checked after

the filling line is disconnected in each instance. The gross weight shall be calculated from the tank capacity and tare weight set forth on the metal plate required by the specification, and the maximum filling density permitted for the material being loaded into the tank as set forth in the table, paragraph (a) of this section.

(e) If the loading of cargo tanks and portable tank containers with liquefied gases is to be determined by adjustable liquid level device, each tank and each compartment thereof shall have a thermometer well, so that the internal liquid temperature can easily be determined, and the amount of liquid in the tank shall be corrected to a 60 °F. basis. Liquid levels shall not exceed a level corresponding to the maximum filling density permitted for the material being loaded into the tank as set forth in the table in paragraph (a) of this section.

(f) When the loading of cargo tanks and portable tank containers with liquefied gases is determined only by fixed length dip tube or other fixed maximum liquid level indicator, the device shall be arranged to function at a level not to exceed the maximum permitted volume prescribed by the table, paragraph (a) of this section. Loading shall be stopped when the device functions.

(g) Containers, the liquid level of which has been determined by means of a fixed length dip tube gauging device, shall not be acceptable for stowage as cargo on vessels in commerce subject to the jurisdiction of the United States Coast Guard. Nothing contained in this section shall be so construed as to prohibit the transportation on car floats or car ferries of motor vehicles laden with containers nor cargo tanks the liquid level of either of which has been determined by means of fixed length dip tube devices.

(h) Each cargo tank and portable tank, except a tank filled by weight, must be equipped with one or more of the gauging devices described in the following table which indicate accurately the maximum permitted liquid level. Additional gauging devices may be installed but may not be used as primary controls for filling of cargo tanks and portable tanks. Gauge glasses are

not permitted on any cargo tank or portable tank. Primary gauging devices used on cargo tanks of less than 3500 gallons water capacity are exempt from the longitudinal location requirements specified in paragraphs (h)(2) and (3) of this section provided: The tank length does not exceed three times the tank diameter; and the cargo tank is unloaded within 24 hours after each filling of the tank.

| Kind of gas                                         | Gaging device permitted for filling purposes              |
|-----------------------------------------------------|-----------------------------------------------------------|
| Anhydrous ammonia .....                             | Rotary tube; adjustable slip tube; fixed length dip tube. |
| Anhydrous dimethylamine .....                       | None.                                                     |
| Anhydrous monomethylamine .....                     | Do.                                                       |
| Anhydrous trimethylamine .....                      | Do.                                                       |
| Aqua ammonia solution containing anhydrous ammonia. | Rotary tube; adjustable slip tube; fixed length dip tube. |
| Butadiene, stabilized .....                         | Do.                                                       |
| Carbon dioxide, refrigerated liquid                 | Do.                                                       |
| Chlorine .....                                      | None.                                                     |
| Dichlorodifluoromethane .....                       | Do.                                                       |
| Difluoroethane .....                                | Do.                                                       |
| Difluoromonochloroethane .....                      | Do.                                                       |
| Dimethyl ether .....                                | Do.                                                       |
| Ethane, refrigerated liquid .....                   | Rotary tube; adjustable slip tube; fixed length dip tube. |
| Ethane-propane mixture, refrigerated liquid.        | Do.                                                       |
| Hexafluoropropylene .....                           | None.                                                     |
| Hydrogen chloride, refrigerated liquid.             | Do.                                                       |
| Liquefied petroleum gases .....                     | Rotary tube; adjustable slip tube; fixed length dip tube. |
| Methyl chloride .....                               | Fixed length dip tube.                                    |
| Methyl mercaptan .....                              | Rotary tube; adjustable slip tube; fixed length dip tube. |
| Monochlorodifluoromethane .....                     | None.                                                     |
| Nitrous oxide, refrigerated liquid ..               | Rotary tube; adjustable slip tube; fixed length dip tube. |
| Methylacetylenepropadiene, stabilized.              | Do.                                                       |
| Refrigerant gas, n.o.s. or Dispersant gas, n.o.s.   | None.                                                     |
| Sulfur dioxide .....                                | Fixed length dip tube.                                    |
| Vinyl chloride .....                                | None.                                                     |
| Vinyl fluoride, inhibited .....                     | Do.                                                       |

(1) The design pressure of the liquid level gauging devices shall be at least equal to the design pressure of the tank.

(2) If the primary gauging device is adjustable, it must be capable of adjustment so that the end of the tube will be in the location specified in paragraph (h)(3) of this section for at least one of the loadings to be transported, at the filling level corresponding to an average loading tem-

perature. Exterior means must be provided to indicate this adjustment. The gauging device must be legibly and permanently marked in increments not exceeding 20 Fahrenheit degrees (or not exceeding 25 p.s.i.g. on tanks for carbon dioxide, refrigerated liquid or nitrous oxide, refrigerated liquid), to indicate the maximum levels to which the tank may be filled with liquid at temperatures above 20 °F. However, if it is not practicable to so mark the gauging device, this information must be legibly and permanently marked on a plate affixed to the tank adjacent to the gauging device.

(3) A dip tube gauging device consists of a pipe or tube with a valve at its outer end with its intake limited by an orifice not larger than 0.060 inch in diameter. If a fixed length dip tube is used, the intake must be located midway of the tank both longitudinally and laterally and at maximum permitted filling level. In tanks for liquefied petroleum gases, the intake must be located at the level reached by the lading when the tank is loaded to maximum filling density at 40 °F.

(4) Except on a tank used exclusively for the transportation of carbon dioxide, refrigerated liquid or nitrous oxide, refrigerated liquid, each opening for a pressure gauge must be restricted at or inside the tank by an orifice no larger than 0.060 inch in diameter. For carbon dioxide, refrigerated liquid or nitrous oxide, refrigerated liquid service, the pressure gauge need only be used during the filling operation.

(i) Each tank must be provided with one or more pressure relief devices which, unless otherwise specified in this part, must be of the spring-loaded type. Each valve must be arranged to discharge upward and unobstructed to the outside of the protective housing to prevent any impingement of escaping gas upon the tank. For each chlorine tank the protective housing must be in compliance with the requirements set forth in the applicable specification.

(1) The safety relief valves on each tank must meet the following conditions:

(i) The total relieving capacity, as determined by the flow formulas contained in Section 5 of CGA S-1.2 (IBR, see §171.7 of this subchapter), must be

sufficient to prevent a maximum pressure in the tank of more than 120 percent of the design pressure;

(ii) The flow capacity rating, testing and marking must be in accordance with Sections 5, 6 and 7 of CGA Pamphlet S–1.2.

(iii) For an insulated tank, the required relieving capacity of the relief devices must be the same as for an uninsulated tank, unless the insulation will remain in place and will be effective under fire conditions. In this case, except for UN portable tanks, each insulated tank must be covered by a sheet metal jacket of not less than 16 gauge thickness. For UN portable tanks where the relieving capacity of the valves has been reduced on the basis of the insulation system, the insulation system must remain effective at all temperatures less than 649 °C (1200.2 °F) and be jacketed with a material having a melting point of 700 °C (1292.0 °F) or greater.

(iv) An MC 330 cargo tank that has relief valves sized by Fetterly's formula dated November 27, 1928, may be continued in service.

(2) Each safety relief valve must be arranged to minimize the possibility of tampering. If the pressure setting or adjustment is external to the valve, the safety relief valve must be provided with means for sealing the adjustment and it must be sealed.

(3) Each safety relief valve on a portable tank, other than a UN portable tank, must be set to start-to-discharge at pressure no higher than 110% of the tank design pressure and no lower than the design pressure specified in paragraph (a) of this section for the gas transported. For UN portable tanks used for liquefied compressed gases and constructed in accordance with the requirements of §178.276 of this subchapter, the pressure relief device(s) must conform to §178.276(e) of this subchapter.

(4) Except for UN portable tanks, each safety relief valve must be plainly and permanently marked with the pressure in p.s.i.g. at which it is set to discharge, with the actual rate of discharge of the device in cubic feet per minute of the gas or of air at 60 °F (15.6 °C) and 14.7 p.s.i.a., and with the manufacturer's name or trade name and

catalog number. The start-to-discharge valve marking must be visible after the valve is installed. The rated discharge capacity of the device must be determined at a pressure of 120% of the design pressure of the tank. For UN portable tanks, each pressure relief device must be clearly and permanently marked as specified in §178.274(f)(1) of this subchapter.

(5) Each safety relief valve must have direct communication with the vapor space in the tank.

(6) Each connection to a safety relief valve must be of sufficient size to provide the required rate of discharge through the safety relief valve.

(7) [Reserved]

(8) Each pressure relief valve outlet must be provided with a protective device to prevent the entrance and accumulation of dirt and water. This device must not impede flow through the valve. Pressure relief devices must be designed to prevent the entry of foreign matter, the leakage of liquid and the development of any dangerous excess pressure.

(9) On tanks for carbon dioxide, refrigerated liquid or nitrous oxide, refrigerated liquid each safety relief device must be installed and located so that the cooling effect of the contents will not prevent the effective operation of the device. In addition to the required safety relief valves, these tanks may be equipped with one or more pressure controlling devices.

(10) Each tank for carbon dioxide, refrigerated liquid also may be equipped with one or more non-reclosing pressure relief devices set to function at a pressure not over two times nor less than 1.5 times the design pressure of the tank.

(11) Each portion of connected liquid piping or hose that can be closed at both ends must be provided with a safety relief valve without an intervening shut-off valve to prevent excessive hydrostatic pressure that could burst the piping or hose.

(12) Subject to conditions of paragraph (a) of this section for the methyl chloride and sulfur dioxide optional portable tanks, one or more fusible plugs examined by the Bureau of Explosives and approved by the Associate Administrator may be used on these

tanks in place of safety relief valves of the spring-loaded type. The fusible plug or plugs must be in accordance with CGA Pamphlet S-1.2, to prevent a pressure rise in the tank of more than 120 percent of the design pressure. If the tank is over 30 inches long, each end must have the total specified safety discharge area.

(13) A safety relief valve on a chlorine cargo tank must conform to one of the following standards of The Chlorine Institute, Inc.: Type 1 ½ JQ225, Dwg. H51970 (IBR, see § 171.7 of this subchapter); or Type 1 ½ JQ225, Dwg. H50155 (IBR, see § 171.7 of this subchapter).

(j) Storage containers for liquefied petroleum gas for permanent installation on consumer premises may be shipped by private motor carrier only under the following conditions:

(1) Each container must be constructed in compliance with the requirements in Section VIII of the ASME Code (containers built in compliance with earlier editions starting with 1943 are authorized) and must be marked to indicate compliance in the manner specified by the respective Code.

(2) Each container must be equipped with safety devices in compliance with the requirements for safety devices on containers as specified in NFPA 58 (IBR, see § 171.7 of this subchapter).

(3) The containers must be braced or otherwise secured on the vehicle to prevent relative motion while in transit. Valves or other fittings must be adequately protected against damage during transportation. (See § 177.834(a) of this subchapter.)

(4) Except as provided in paragraph (j)(5) of this section, containers shall not be shipped when charged with liquefied petroleum gas to more than 5 percent of their water capacity.

(5) Storage containers of less than 1,042 pounds water capacity (125 gallons) may be shipped when charged with liquefied petroleum gas in compliance with DOT filling density.

(k) A nonspecification cargo tank meeting, and marked in conformance with, the edition of Section VIII of the ASME Code in effect when it was fabricated may be used for the transportation of liquefied petroleum gas pro-

vided it meets all of the following conditions:

(1) It must have a minimum design pressure no lower than 250 psig.

(2) It must have a capacity of 13,247.5 L (3,500 water gallons) or less.

(3) It must have been manufactured in conformance with Section VIII of the ASME Code prior to January 1, 1981, according to its ASME name plate and manufacturer's data report.

(4) It must conform to the applicable provisions of NFPA 58, except to the extent that provisions in NFPA 58 are inconsistent with requirements in parts 178 and 180 of this subchapter.

(5) It must be inspected, tested, and equipped in accordance with subpart E of part 180 of this subchapter as specified for MC 331 cargo tank motor vehicles.

(6) Except as provided in this paragraph (k), it must be operated exclusively in intrastate commerce, including its operation by a motor carrier otherwise engaged in interstate commerce, in a state where its operation was permitted by law (not including the incorporation of this subchapter) prior to January 1, 1981. A cargo tank motor vehicle operating under authority of this section may cross state lines to travel to and from a qualified assembly, repair, maintenance, or requalification facility. The cargo tank need not be cleaned and purged, but it may not contain liquefied petroleum gas in excess of five percent of the water capacity of the cargo tank. If the vehicle engine is supplied fuel from the cargo tank, enough fuel in excess of five percent of the cargo tank's water capacity may be carried for the trip to or from the facility.

(7) It must have been used to transport liquefied petroleum gas prior to January 1, 1981.

(8) It must be operated in conformance with all other requirements of this subchapter.

(l) Anhydrous ammonia must not be offered for transportation or transported in specification MC 330 and MC 331 cargo tanks constructed of quenched and tempered ("QT") steel except as provided in this paragraph.

(1) The ammonia must have a minimum water content of 0.2 percent by weight. Any addition of water must be

**§ 173.315**

**49 CFR Ch. I (10–1–08 Edition)**

made using steam condensate, deionized, or distilled water.

(2) Except as otherwise provided in this paragraph, each person offering for transportation or transporting anhydrous ammonia shall perform a periodic analysis for prescribed water content in the ammonia. The analysis must be performed:

(i) From a sample of the ammonia in storage taken at least once every 7 days, or each time ammonia is added to the storage tanks, whichever is less frequent; or

(ii) At the time the cargo tanks are loaded, then a sample of the ammonia taken from at least one loaded cargo tank out of each 10 loads, or from one cargo tank every 24 hours, whichever is less frequent; or

(iii) At the same frequency as described in paragraph (l)(2)(ii) of this section, from a sample taken from the loading line to the cargo tank.

(3) If water is added at the time of loading:

(i) The sample for analysis must be taken from a point in the loading line between the water injection equipment and the cargo tank; and

(ii) Positive provisions must be made to assure water injection equipment is operating.

(4) If water injection equipment becomes inoperative, suitable corrective maintenance must be performed after which a sample from the first loaded cargo tank must be analyzed for prescribed water content.

(5) The analysis method for water content must be as prescribed in CGA G-2.2, "Tentative Standard Method for Determining Minimum of 0.2 percent water in Anhydrous Ammonia," (IBR, see § 171.7 of this subchapter).

(6) Records indicating the results of the analysis taken, as required by this paragraph, must be retained for 2 years and must be open to inspection by a representative of the Department.

(7) Each person receiving anhydrous ammonia containing 0.2 per cent water by weight may offer for transportation

or transport that ammonia without performing the prescribed analysis for water content provided:

(i) The ammonia received was certified as containing 0.2 percent water as prescribed in §§ 172.203(h)(1)(i) and 177.817(a) of this subchapter; and

(ii) The amount of water in the ammonia has not been reduced by any means.

(m) A cargo tank (commonly known as a nurse tank and considered an implement of husbandry) transporting anhydrous ammonia, and operated by a private carrier exclusively for agricultural purposes does not have to meet the specification requirements of part 178 of this subchapter if it:

(1) Has a minimum design pressure of 250 psig and meets the requirements of the edition of Section VIII of the ASME Code in effect at the time it was manufactured and is marked accordingly;

(2) Is equipped with safety relief valves meeting the requirements of CGA pamphlet S1.2;

(3) Is painted white or aluminum;

(4) Has capacity of 3,000 gallons or less;

(5) Is loaded to a filling density no greater than 56 percent;

(6) Is securely mounted on a farm wagon; and

(7) Is in conformance with the requirements of part 172 of this subchapter except that shipping papers are not required; and it need not be marked or placarded on one end if that end contains valves, fittings, regulators or gauges when those appurtenances prevent the markings and placard from being properly placed and visible.

(n) *Emergency discharge control for cargo tank motor vehicles in liquefied compressed gas service.*—(1) *Required emergency discharge control equipment.* Each cargo tank motor vehicle in liquefied compressed gas service must have an emergency discharge control capability as specified in the following table:

| § 173.315(n)(1)(*) | Material                                                                                                                                                                                    | Delivery service                                               | Required emergency discharge control capability                                                                                                                             |
|--------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| (i) .....          | Division 2.2 materials with no subsidiary hazard, excluding anhydrous ammonia.                                                                                                              | All .....                                                      | None.                                                                                                                                                                       |
| (ii) .....         | Division 2.3 materials .....                                                                                                                                                                | All .....                                                      | Paragraph (n)(2) of this section.                                                                                                                                           |
| (iii) .....        | Division 2.2 materials with a subsidiary hazard, Division 2.1 materials, and anhydrous ammonia.                                                                                             | Other than metered delivery service.                           | Paragraph (n)(2) of this section.                                                                                                                                           |
| (iv) .....         | Division 2.2 materials with a subsidiary hazard, Division 2.1 materials, and anhydrous ammonia in a cargo tank motor vehicle with a capacity of 13,247.5 L (3,500 water gallons) or less.   | Metered delivery service .....                                 | Paragraph (n)(3) of this section.                                                                                                                                           |
| (v) .....          | Division 2.2 materials with a subsidiary hazard, Division 2.1 materials, and anhydrous ammonia in a cargo tank motor vehicle with a capacity greater than 13,247.5 L (3,500 water gallons). | Metered delivery service .....                                 | Paragraph (n)(3) of this section, and, for obstructed view deliveries where permitted by §177.840(p) of this subchapter, paragraph (n)(2) or (n)(4) of this section.        |
| (vi) .....         | Division 2.2 materials with a subsidiary hazard, Division 2.1 materials, and anhydrous ammonia in a cargo tank with a capacity of greater than 13,247.5 L (3,500 water gallons).            | Both metered delivery and other than metered delivery service. | Paragraph (n)(2) of this section, provided the system operates for both metered and other than metered deliveries; otherwise, paragraphs (n)(2) and (n)(3) of this section. |

(2) *Cargo tank motor vehicles in other than metered delivery service.* A cargo tank motor vehicle in other than metered delivery service must have a means to automatically shut off the flow of product without the need for human intervention within 20 seconds of an unintentional release caused by a complete separation of a liquid delivery hose (passive shut-down capability).

(i) Designed flow of product through a bypass in the valve is acceptable when authorized by this subchapter.

(ii) The design for the means to automatically shut off product flow must be certified by a Design Certifying Engineer. The certification must consider any specifications of the original component manufacturer and must explain how the passive means to shut off the flow of product operates. It must also outline the parameters (e.g., temperature, pressure, types of product) within which the passive means to shut off the flow of product is designed to operate. All components of the discharge system that are integral to the design must be included in the certification. A

copy of the design certification must be provided to the owner of the cargo tank motor vehicle on which the equipment will be installed.

(iii) Installation must be performed under the supervision of a Registered Inspector unless the equipment is installed and removed as part of regular operation (e.g., a hose). The Registered Inspector must certify that the equipment is installed and tested, if it is possible to do so without damaging the equipment, in accordance with the Design Certifying Engineer's certification. The Registered Inspector must provide the certification to the owner of the cargo tank motor vehicle.

(3) *Cargo tank motor vehicles in metered delivery service.* When required by the table in paragraph (n)(1) of this section, a cargo tank motor vehicle must have an off-truck remote means to close the internal self-closing stop valve and shut off all motive and auxiliary power equipment upon activation by a qualified person attending the unloading of the cargo tank motor vehicle (off-truck remote shut-off). It must function reliably at a distance of 45.72

m (150 feet). The off-truck remote shut-off activation device must not be capable of reopening the internal self-closing stop valve after emergency activation.

(i) The emergency discharge control equipment must be installed under the supervision of a Registered Inspector. Each wireless transmitter/receiver must be tested to demonstrate that it will close the internal self-closing stop valve and shut off all motive and auxiliary power equipment at a distance of 91.44 m (300 feet) under optimum conditions. Emergency discharge control equipment that does not employ a wireless transmitter/receiver must be tested to demonstrate its functioning at the maximum length of the delivery hose.

(ii) The Registered Inspector must certify that the remote control equipment is installed in accordance with the original component manufacturer's specifications and is tested in accordance with paragraph (n)(3)(i) of this section. The Registered Inspector must provide the owner of the cargo tank motor vehicle with this certification.

(4) *Query systems.* When a transmitter/receiver system is used to satisfy the requirements of paragraph (n)(1)(v) of this section, it must close the internal self-closing stop valve and shut off all motive and auxiliary power equipment unless the qualified person attending the unloading operation prevents it from doing so at least once every five minutes. Testing and certification must be as specified in paragraph (n)(3) of this section.

(5) *Compliance dates.* (i) Each specification MC 331 cargo tank motor vehicle with a certificate of construction issued two or more years after July 1, 1999, must have an appropriate emergency discharge control capability as specified in this paragraph (n).

(ii) No MC 330, MC 331, or nonspecification cargo tank motor vehicle authorized under paragraph (k) of this section may be operated unless it has an appropriate emergency discharge control capability as specified in this paragraph (n) no later than the date of its first scheduled pressure retest required after July 1, 2001. No MC 330, MC 331 or nonspecification cargo tank motor vehicle authorized under para-

graph (k) of this section may be operated after July 1, 2006, unless it has been equipped with emergency discharge control equipment as specified in this paragraph (n).

(iii) No MC 330 or MC 331 cargo tank motor vehicle with a capacity over 13,247 L (3,500 gallons) used in metered delivery service may be operated unless it has an appropriate discharge control capability as specified in this paragraph (n) no later than July 1, 2003, or the date of its first scheduled pressure retest required after July 1, 2001, whichever is earlier.

(o) *Chlorine cargo tank motor vehicles.* Each cargo tank motor vehicle used for the transportation of chlorine must meet the requirements in the following:

(1) Any hose, piping, or tubing used for loading or unloading that is mounted or carried on the motor vehicle may not be attached to any valve and must be capped at all ends to prevent the entry of moisture, except at the time of loading or unloading. Except at the time of loading and unloading, the pipe connection of each angle valve must be closed with a screw plug which is chained or otherwise fastened to prevent misplacement.

(2) Each chlorine cargo tank motor vehicle angle valve must be tested to be leak free at not less than 225 psig using dry air or inert gas before installation and thereafter every 2 years when performing the required periodic retest in §180.407(c) of this subchapter. Prior to each loading, the cargo tank motor vehicle must be inspected and the angle valves and gasketed joints must be examined and tested at a pressure of not less than 50 psig to determine that they are not leaking and are in proper condition for transportation. Any leaks must be corrected before the cargo tank motor vehicle is offered for transportation.

(3) Excess flow valves on the cargo tank motor vehicle must meet the requirements of paragraph (n) of this section.

(p) *Fusible elements.* Each MC 330, MC 331, or nonspecification cargo tank authorized under paragraph (k) of this section must have a thermal means of closure for each internal self-closing

stop valve as specified in § 178.337–8(a)(4) of this subchapter.

(q) Manifolding is authorized for cargo tanks containing anhydrous ammonia provided each individual cargo tank is equipped with a pressure relief device or valves and gauging devices as required by paragraphs (h) and (i) of this section. Each valve must be tightly closed while the cargo tank is in transit. Each cargo tank must be filled separately.

[29 FR 18743, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 173.315, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 173.316 Cryogenic liquids in cylinders.

(a) *General requirements.* (1) A cylinder may not be loaded with a cryogenic liquid colder than the design service temperature of the packaging.

(2) A cylinder may not be loaded with any material which may combine chemically with any residue in the packaging to produce an unsafe condition.

(3) The jacket covering the insulation on a cylinder used to transport any flammable cryogenic liquid must be made of steel.

(4) A valve or fitting made of aluminum with internal rubbing or abrading aluminum parts that may come in contact with oxygen in the cryogenic liquid form may not be installed on any cylinder used to transport oxygen, cryogenic liquid unless the parts are anodized in accordance with ASTM Standard B 580 (IBR, see § 171.7 of this subchapter).

(5) An aluminum valve, pipe or fitting may not be installed on any cylinder used to transport any flammable cryogenic liquid.

(6) Each cylinder must be provided with one or more pressure relief devices, which must be installed and maintained in compliance with the requirements of this subchapter.

(7) Each pressure relief device must be installed and located so that the cooling effect of the contents during venting will not prevent effective operation of the device.

(8) The maximum weight of the contents in a cylinder with a design service temperature colder than  $-320^{\circ}\text{F}$ . may not exceed the design weight marked on the cylinder (see § 178.35 of this subchapter).

(b) *Pressure control systems.* Each cylinder containing a cryogenic liquid must have a pressure control system that conforms to § 173.301(f) and is designed and installed so that it will prevent the cylinder from becoming liquid full.

(c) *Specification cylinder requirements and filling limits.* Specification DOT-4L cylinders (§ 178.57 of this subchapter) are authorized for the transportation of cryogenic liquids when carried in the vertical position as follows:

(1) For purposes of this section, “filling density,” except for hydrogen, is defined as the percent ratio of the weight of lading in the packaging to the weight of water that the packaging will hold at  $60^{\circ}\text{F}$ . (1 lb. of water = 27.737 cubic inches at  $60^{\circ}\text{F}$ .)

(2) The cryogenic liquids of argon, nitrogen, oxygen, helium and neon must be loaded and shipped in accordance with the following table:

| Pressure control valve setting (maximum start-to-discharge pressure psig) | Maximum permitted filling density (percent by weight) |        |          |        |        |        |
|---------------------------------------------------------------------------|-------------------------------------------------------|--------|----------|--------|--------|--------|
|                                                                           | Air                                                   | Argon  | Nitrogen | Oxygen | Helium | Neon   |
| 45 .....                                                                  | 82.5                                                  | 133    | 76       | 108    | 12.5   | 109    |
| 75 .....                                                                  | 80.3                                                  | 130    | 74       | 105    | 12.5   | 104    |
| 105 .....                                                                 | 78.4                                                  | 127    | 72       | 103    | 12.5   | 100    |
| 170 .....                                                                 | 76.2                                                  | 122    | 70       | 100    | 12.5   | 92     |
| 230 .....                                                                 | 75.1                                                  | 119    | 69       | 98     | 12.5   | 85     |
| 295 .....                                                                 | 73.3                                                  | 115    | 68       | 96     | 12.5   | 77     |
| 360 .....                                                                 | 70.7                                                  | 113    | 65       | 93     | 12.5   | .....  |
| 450 .....                                                                 | 65.9                                                  | 111    | 61       | 91     | 12.5   | .....  |
| 540 .....                                                                 | 62.9                                                  | 107    | 58       | 88     | 12.5   | .....  |
| 625 .....                                                                 | 60.1                                                  | 104    | 55       | 86     | 12.5   | .....  |
| Design service temperature ( $^{\circ}\text{F}$ .) .....                  | $-320$                                                | $-320$ | $-320$   | $-320$ | $-452$ | $-411$ |



**§ 173.318**

**49 CFR Ch. I (10–1–08 Edition)**

(3) Hydrogen (minimum 95 percent parahydrogen) must be loaded and shipped as follows:

| Column 1                                                                                                    | Column 2                 |
|-------------------------------------------------------------------------------------------------------------|--------------------------|
| Design service temperature .....                                                                            | Minus 423 °F. or colder. |
| Maximum permitted filling density, based on cylinder capacity at minus 423 °F (see Note 1).                 | 6.7 percent.             |
| The pressure control valve must be designed and set to limit the pressure in the cylinder to not more than. | 17 psig.                 |

NOTE 1: The filling density for hydrogen, cryogenic liquid is defined as the percent ratio of the weight of lading in a packaging to the weight of water that the packaging will hold at minus 423 °F. The volume of the packaging at minus 423 °F is determined in cubic inches. The volume is converted to pounds of water (1 lb. of water = 27.737 cubic inches).

(i) Each cylinder must be constructed, insulated and maintained so that during transportation the total rate of venting shall not exceed 30 SCF of hydrogen per hour.

(ii) In addition to the marking requirements in § 178.35 of this subchapter, the total rate of venting in SCF per hour (SCFH) shall be marked on the top head or valve protection band in letters at least one-half inch high as follows: “VENT RATE\*\*SCFH” (with the asterisks replaced by the number representing the total rate of venting, in SCF per hour).

(iii) Carriage by highway is subject to the conditions specified in § 177.840(a) of this subchapter.

(d) *Mixtures of cryogenic liquid.* Where charging requirements are not specifically prescribed in paragraph (c) of this section, the cryogenic liquid must be shipped in packagings and under conditions approved by the Associate Administrator.

[Amdt. 173–166, 48 FR 27695, June 16, 1983, as amended by Amdt. 173–166, 49 FR 24314, June 12, 1984; Amdt. 173–180, 49 FR 42735, Oct. 24, 1984; Amdt. 173–201, 52 FR 13041, Apr. 20, 1987; Amdt. 173–250, 61 FR 25942, May 23, 1996; Amdt. 173–261, 62 FR 24741, May 6, 1997; 66 FR 45379, Aug. 28, 2001; 67 FR 16013, Sept. 27, 2002; 68 FR 75742, Dec. 31, 2003; 69 FR 54046, Sept. 7, 2004]

**§ 173.318 Cryogenic liquids in cargo tanks.**

(a) *General requirements.* (1) A cargo tank may not be loaded with a cryo-

genic liquid colder than the design service temperature of the packaging.

(2) A cargo tank may not be loaded with any material that may combine chemically with any residue in the packaging to produce an unsafe condition (see § 178.338–15).

(3) The jacket covering the insulation on a tank used to transport a cryogenic liquid must be made of steel if the cryogenic liquid:

(i) Is to be transported by vessel (see § 176.76(g) of this subchapter); or

(ii) Is oxygen or a flammable material.

(4) A valve or fitting made of aluminum with internal rubbing or abrading aluminum parts that may come in contact with oxygen in the cryogenic liquid form may not be installed on any cargo tank used to transport oxygen, cryogenic liquid unless the parts are anodized in accordance with ASTM Standard B 580 (IBR, see § 171.7 of this subchapter).

(5) An aluminum valve, pipe or fitting, external to the jacket that retains lading during transportation may not be installed on any cargo tank used to transport oxygen, cryogenic liquid or any flammable cryogenic liquid.

(6) A cargo tank used to transport oxygen, cryogenic liquid must be provided with a manhole (see § 178.338–6 of this subchapter).

(b) *Pressure relief systems and pressure control valves*—(1) *Types of pressure relief systems*—(i) *Tanks in oxygen and flammable cryogenic liquid service.* Except as otherwise provided in this paragraph, each tank in oxygen and flammable cryogenic liquid service must be protected by two independent pressure relief systems which are not connected in series, namely:

(A) A primary system of one or more pressure relief valves; and

(B) A secondary system of one of more frangible discs or pressure relief valves. For a tank in carbon monoxide service, the secondary system must be pressure relief valves only.

(ii) *Tanks in helium and atmospheric gas (except oxygen) cryogenic liquid service.* For a tank used in helium and atmospheric gas (except oxygen) cryogenic liquid service, the tank must be protected by at least one pressure relief system consisting of:

(A) One or more pressure relief valves; or

(B) A combination of one or more pressure relief valves and one or more frangible discs.

(2) *Capacities of pressure relief systems*—(i) *Tanks in oxygen or flammable cryogenic liquid service.* For tanks in oxygen or flammable cryogenic liquid service, the primary system and the secondary system of pressure relief devices must each have a flow capacity equal to or greater than that calculated by the applicable formula in paragraph 5.3.2 or paragraph 5.3.3 of CGA S-1.2 (IBR, see §171.7 of this subchapter). In addition:

(A) The primary pressure relief system must have a total flow capacity at a pressure not exceeding 120 percent of the tank's design pressure.

(B) The secondary pressure relief system must have a total flow capacity at a pressure not exceeding 150 percent of the tank's design pressure.

(C) The flow capacity and rating must be verified and marked by the manufacturer of the device in accordance with CGA Pamphlet S-1.2.

(ii) *Tanks in helium and atmospheric gas (except oxygen) cryogenic liquid service.* For tanks in helium and atmospheric gas (except oxygen) cryogenic liquid service, the pressure relief system must have a flow capacity equal to or greater than that calculated by the applicable formula in paragraphs 5.3.2 or 5.3.3 of CGA Pamphlet S-1.2. If the pressure relief system consists of a combination of pressure relief valves and frangible discs, the pressure relief valves must have a total venting capacity equal to or greater than that calculated by the applicable formula in paragraph 4.1.10.1.1 of CGA Pamphlet S-1.2. The pressure relief system must have this total flow capacity at a pressure not exceeding 150 percent of the tank's design pressure. The flow capacity and rating must be verified and marked by the manufacturer of the device in accordance with CGA Pamphlet S-1.2.

(3) *Type and construction of pressure relief devices.* (i) Each pressure relief device must be designed and constructed for a pressure equal to or exceeding the tank's design pressure at the coldest

temperature reasonably expected to be encountered.

(ii) Pressure relief devices must be either spring-loaded pressure relief valves or frangible discs. Pressure relief valves must be of a type that automatically open and close at predetermined pressures.

(4) *Setting of pressure relief devices.* (i) On a tank used in oxygen or flammable cryogenic liquid service, the pressure relief devices must perform as follows.

(A) Each pressure relief valve in the primary relief system must be set-to-discharge at a pressure no higher than 110 percent of the tank's design pressure.

(B) Each pressure relief device in the secondary pressure relief system must be designed to commence functioning at a pressure no lower than 130 percent and no higher than 150 percent of the tank's design pressure.

(ii) On a tank used in helium and atmospheric gas (except oxygen) cryogenic liquid service, the pressure relief devices in the pressure relief system must be designed to commence functioning at no higher than 150 percent of the tank's design pressure.

(5) *Optional pressure relief devices and pressure control valves.* In addition to the required pressure relief devices, a cargo tank in cryogenic liquid (except carbon monoxide) service may be equipped with one or both of the following:

(i) One or more pressure control valves set at a pressure below the tank's design pressure.

(ii) One or more frangible discs set to function at a pressure not less than one and one-half times or more than two times the tank's design pressure.

(6) *Maximum filling rate.* (i) For a tank used in oxygen and flammable cryogenic liquid service, the maximum rate at which the tank is filled must not exceed the liquid flow capacity of the primary pressure relief system rated at a pressure not exceeding 120 percent of the tank's design pressure.

(ii) On a tank used in helium and atmospheric gas (except oxygen) cryogenic liquid service, the maximum rate at which the tank is filled must not exceed the liquid flow capacity of the pressure relief valves rated at 150 percent of the tank's design pressure.

(7) *Arrangement and location of pressure relief devices.* (i) The discharge from any pressure relief system must be directed upward and be unobstructed to the outside of the protective housing in such a manner as to prevent impingement of gas upon the jacket or any structural part of the vehicle.

(ii) Each pressure relief valve must be arranged or protected to prevent the accumulation of foreign material between the relief valve and the atmospheric discharge opening in any relief piping. The arrangement must not impede flow through the device.

(iii) Each pressure relief valve must be designed and located to minimize the possibility of tampering. If the pressure setting or adjustment is external to the valve, the valve adjustment must be sealed.

(iv) Each pressure relief device must have direct communication with the vapor space of the tank at the midlength of the top centerline.

(v) Each pressure relief device must be installed and located so that the cooling effect of the contents during venting will not prevent the effective operation of the device.

(8) *Connections.* (i) Each connection to a pressure relief device must be of sufficient size to allow the required rate of discharge through the pressure relief device. The inlet connection must be not less than one-half inch nominal pipe size.

(ii) A shut-off valve may be installed in a pressure relief system only when the required relief capacity is provided at all times.

(9) *Pressure relief devices for piping hose and vacuum-insulated jackets.* (i) Each portion of connected liquid piping or hose that can be closed at both ends must be provided with either a hydrostatic pressure relief valve without an intervening shut-off valve, or a check valve permitting flow from the pipe or hose into the tank. If used, the relief valve must be located so as to prevent its discharge from impinging on the tank, piping, or operating personnel.

(ii) On a vacuum-insulated cargo tank the jacket must be protected by a suitable relief device to release internal pressure. The discharge area of this device must be at least 0.00024 square

inch per pound of water capacity of the tank. This relief device must function at a pressure not exceeding the internal design pressure of the jacket, calculated in accordance with Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), or 25 psig, whichever is less.

(10) *Tank inlet, outlet, pressure relief device and pressure control valve markings.* (i) Each tank inlet and outlet, except pressure relief devices and pressure control valves, must be permanently marked to indicate whether it communicates with “vapor” or “liquid” when the tank is filled to the maximum permitted filling density.

(ii) Each pressure relief valve must be plainly and permanently marked with the pressure, in psig, at which it is set-to-discharge, the discharge rate of the device in SCF per minute (SCFM) of free air, and the manufacturer’s name or trade name and catalog number. The marked set-to-discharge pressure valve must be visible with the valve in its installed position. The rated discharge capacity of the device must be determined at a pressure of 120 percent of the design pressure of the tank.

(iii) Each pressure control valve must be plainly and permanently marked with the pressure, in psig, at which it is set-to-discharge.

(c) *Weight of lading requirements.* The weight of a cryogenic liquid in the tank must be determined by weighing or by the use of a liquid level gauging device authorized in § 178.338–14(a) of this subchapter, and may not exceed the lesser of:

(1) The weight of lading in the tank, based on the water capacity stamped on the nameplate (§ 178.338–18(a)(4) of this subchapter) and the appropriate maximum permitted filling density specified in paragraph (f) of this section; or

(2) The maximum weight of lading for which the cargo tank was designed, as marked on the specification plate (see § 178.338–18(b) of this subchapter).

(d) *Outage.* Except for a cargo tank containing helium, cryogenic liquid, a cargo tank offered for transportation must have an outage of at least two percent below the inlet of the pressure relief device or pressure control valve,

under conditions of incipient opening, with the tank in a level attitude.

(e) *Temperature.* A flammable cryogenic liquid in a cargo tank at the start of travel must be at a temperature sufficiently cold that the pressure setting of the pressure control valve or the required pressure relief valve, whichever is lower, will not be reached in less time than the marked rated holding time for the cryogenic liquid (see paragraph (g)(3) of this section and § 178.338–9(b) of this subchapter).

(f) *Specification MC–338 (§ 178.338 of this subchapter) cargo tanks* are authorized for the shipment of the following

cryogenic liquids subject to the following additional requirements:

(1) For purposes of this section, “filling density” is defined as the percent ratio of the weight of lading in the tank to the weight of water that the tank will hold at the design service temperature (one pound of water=27.737 cubic inches at 60 °F., or one gallon of water = 231 cubic inches at 60 °F. and weighs 8.32828 pounds).

(2) *Air, argon, helium, nitrogen, and oxygen, cryogenic liquids* must be loaded and shipped in accordance with the following table:

PRESSURE CONTROL VALVE SETTING OR RELIEF VALVE SETTING

| Maximum set-to-discharge pressure (psig) | Maximum permitted filling density (percent by weight) |                |                |                |          |
|------------------------------------------|-------------------------------------------------------|----------------|----------------|----------------|----------|
|                                          | Air                                                   | Argon          | Helium         | Nitrogen       | Oxygen   |
| 26 .....                                 |                                                       |                | 12.5 .....     |                |          |
| 30 .....                                 | 80.3 .....                                            | 129 .....      | 12.5 .....     | 74 .....       | 105      |
| 40 .....                                 | 79.2 .....                                            |                | 12.5 .....     |                |          |
| 50 .....                                 | 78.0 .....                                            |                | 12.5 .....     |                |          |
| 55 .....                                 | 77.3 .....                                            | 125 .....      | 12.5 .....     | 71 .....       | 102      |
| 60 .....                                 | 76.9 .....                                            |                | 12.5 .....     |                |          |
| 80 .....                                 | 75.3 .....                                            |                | 12.5 .....     |                |          |
| 85 .....                                 | 75.1 .....                                            | 121 .....      | 12.5 .....     |                | 99       |
| 100 .....                                | 73.0 .....                                            |                | 12.5 .....     |                |          |
| 105 .....                                | 73.7 .....                                            |                | 12.5 .....     | 67 .....       |          |
| 120 .....                                | 72.2 .....                                            |                | 12.5 .....     |                |          |
| 140 .....                                | 71.4 .....                                            |                | 12.5 .....     |                |          |
| 145 .....                                | 70.9 .....                                            | 115 .....      | 12.5 .....     | 64 .....       | 94       |
| 180 .....                                | 68.3 .....                                            |                | 12.5 .....     |                |          |
| 200 .....                                | 67.3 .....                                            | 110 .....      | 12.5 .....     | 61 .....       | 91       |
| 250 .....                                | 63.3 .....                                            | 106 .....      | 12.5 .....     | 57 .....       | 87       |
| 275 .....                                | 62.3 .....                                            | 105 .....      | 12.5 .....     | 56 .....       | 86       |
| 325 .....                                | 59.4 .....                                            | 101 .....      |                | 53 .....       | 83       |
| Design service temperature.              | – 320 °F .....                                        | – 320 °F ..... | – 452 °F ..... | – 320 °F ..... | – 320 °F |

(3) *Carbon monoxide, hydrogen (minimum 95 percent para-hydrogen), ethylene, and methane or natural gas, cryo-*

*genic liquids* must be loaded and shipped in accordance with the following table:

PRESSURE CONTROL VALVE SETTING OR RELIEF VALVE SETTING

| Maximum set-to-discharge pressure (psig) | Maximum permitted filling density (percent by weight) |            |           |                        |
|------------------------------------------|-------------------------------------------------------|------------|-----------|------------------------|
|                                          | Carbon monoxide                                       | Ethylene   | Hydrogen  | Methane or natural gas |
| 13 .....                                 |                                                       |            | 6.6 ..... |                        |
| 15 .....                                 | 75.0 .....                                            |            | 6.6 ..... | 40.5                   |
| 17 .....                                 | 74.0 .....                                            |            | 6.6 ..... |                        |
| 20 .....                                 |                                                       | 53.5 ..... |           | 40.0                   |
| 25 .....                                 | 73.0 .....                                            |            |           |                        |
| 30 .....                                 | 72.0 .....                                            | 52.7 ..... | 6.3 ..... | 39.1                   |
| 35 .....                                 |                                                       |            |           |                        |
| 40 .....                                 |                                                       | 52.0 ..... |           | 38.6                   |
| 45 .....                                 | 71.5 .....                                            |            |           |                        |
| 50 .....                                 |                                                       | 51.4 ..... | 6.0 ..... | 38.2                   |
| 55 .....                                 |                                                       |            |           |                        |
| 60 .....                                 |                                                       | 50.8 ..... |           |                        |
| 70 .....                                 |                                                       | 50.2 ..... | 5.7 ..... | 37.5                   |
| 90 .....                                 |                                                       | 49.2 ..... |           |                        |

## PRESSURE CONTROL VALVE SETTING OR RELIEF VALVE SETTING—Continued

| Maximum set-to-discharge pressure (psig) | Maximum permitted filling density (percent by weight) |                |                |                        |
|------------------------------------------|-------------------------------------------------------|----------------|----------------|------------------------|
|                                          | Carbon monoxide                                       | Ethylene       | Hydrogen       | Methane or natural gas |
| 95 .....                                 | .....                                                 | .....          | .....          | 36.6                   |
| 100 .....                                | .....                                                 | 48.4 .....     | 5.4 .....      |                        |
| 115 .....                                | .....                                                 | 48.2 .....     | .....          |                        |
| 125 .....                                | .....                                                 | .....          | 5.0 .....      |                        |
| 150 .....                                | .....                                                 | .....          | 4.5 .....      |                        |
| 175 .....                                | 62.5 .....                                            | 45.8 .....     | .....          |                        |
| 285 .....                                | 56.0 .....                                            | .....          | .....          |                        |
| Design service temperature.              | – 320 °F .....                                        | – 155 °F ..... | – 423 °F ..... | – 260 °F               |

(4) *Mixtures of cryogenic liquid.* Where charging requirements are not specifically prescribed in this paragraph (f), the cryogenic liquid must be shipped in packagings and under conditions approved by the Associate Administrator.

(g) *One-way travel time; marking.* The jacket of a cargo tank to be used to transport a flammable cryogenic liquid must be marked on its right side near the front, in letters and numbers at least two inches high, “One-Way-Travel-Time \_\_\_\_ hrs.”, with the blank filled in with a number indicating the one-way travel time (OWTT), in hours, of the cargo tank for the flammable cryogenic liquid to be transported. A cargo tank that is partially unloaded at one or more locations must have additional marking “One-Way-Travel-Time \_\_\_\_ hrs. \_\_\_\_ psig to \_\_\_\_ psig at \_\_\_\_ percent filling density,” with the second blank filled in with the pressure existing after partial unloading and the third blank filled in with the set-to-discharge pressure of the control valve or pressure relief valve, and the fourth blank with the filling density following partial unloading. Multiple OWTT markings for different pressure levels are permitted. The abbreviation “OWTT” may be used in place of the words “One-way-travel-time” in the marking required by this paragraph.

(1) OWTT is based on the marked rated holding time (MRHT) of the cargo tank for the cryogenic liquid to be transported in the cargo tank. If the MRHT for the flammable cryogenic liquid is not displayed on or adjacent to the specification plate, this MRHT may be derived.

(2) The MRHT is converted to OWTT, in hours, as follows:

(i) For a tank with an MRHT of 72 hours or less,

$$\text{OWTT} = (\text{MRHT} - 24) / 2$$

(ii) For a tank with an MRHT greater than 72 hours,

$$\text{OWTT} = \text{MRHT} - 48$$

(3) Each cargo tank motor vehicle used to transport a flammable cryogenic liquid must be examined after each shipment to determine its actual holding time. The record required by § 177.840(h) of this subchapter may be used for this determination. If the examination indicates that the actual holding time of the cargo tank, after adjustment to reflect an average ambient temperature of 85 °F, is less than 90 percent of the marked rated holding time (MRHT) for the cryogenic liquid marked on the specification plate or adjacent thereto (see § 178.338–18(b) of this subchapter), the tank may not be refilled with any flammable cryogenic liquid until it is restored to its marked rated holding time value or it is re-marked with the actual marked rated holding time determined by this examination. If the name of the flammable cryogenic liquid that was transported and its marked rated holding time is not displayed on or adjacent to the specification plate, this requirement may be met by deriving the MRHT of the cargo tank for that flammable cryogenic liquid and comparing that derived MRHT with the actual holding time after adjustment.

[Amdt. 173–166, 48 FR 27696, June 16, 1983]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 173.318, see the List of CFR

Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 173.319 Cryogenic liquids in tank cars.**

(a) *General requirements.* (1) A tank car containing a flammable cryogenic liquid may not be shipped unless it was loaded by, or with the consent of, the owner of the tank car.

(2) The amount of flammable cryogenic liquid loaded into a tank car must be determined, either by direct measurement or by calculation based on weight, to verify that the tank has not been filled to a level in excess of the limits specified in paragraph (d)(2) of this section. The weight of any flammable cryogenic liquid loaded, except hydrogen, must be checked by use of scales after disconnecting the loading line.

(3) The shipper shall notify the Federal Railroad Administration whenever a tank car containing any flammable cryogenic liquid is not received by the consignee within 20 days from the date of shipment. Notification to the Federal Railroad Administration may be made by e-mail to [Hmassist@fra.dot.gov](mailto:Hmassist@fra.dot.gov) or telephone call to (202) 493-6229.

(4) A tank car may not be loaded with any flammable cryogenic liquid:

(i) That may combine chemically with any residue in the tank to produce an unsafe condition,

(ii) That is colder than the design service temperature of the tank,

(iii) If the average daily pressure rise in the tank exceeded 3 psig during the prior shipment,

(iv) Unless it is marked with the name of contents, in accordance with § 172.330 of this subchapter.

(b) When a tank car containing a flammable cryogenic liquid is offered for transportation:

(1) At least 0.5 percent outage must be provided below the inlet of the pressure relief or pressure control valve at the start-to-discharge pressure setting of the valve, with the tank car in a level attitude, and

(2) The absolute pressure in the annular space must be less than 75 microns of mercury.

(c) *Temperature.* A flammable cryogenic liquid must be loaded into a tank car at such a temperature that the average daily pressure rise during transportation will not exceed 3 psig (see paragraph (a)(4)(iii) of this section).

(d) A Class DOT-113 tank car is authorized for the shipment of the following cryogenic liquids subject to the following additional requirements:

(1) For purposes of this section, “filling density” is defined as the percent ratio of the weight of lading in the tank to the weight of water that the tank will hold at the design service temperature (one pound of water = 27.737 cubic inches at 60 °F., or one gallon of water = 231 cubic inches at 60 °F. and weighs 8.32828 pounds).

(2) *Ethylene, and hydrogen (minimum 95 percent parahydrogen), cryogenic liquids* must be loaded and shipped in accordance with the following table:

PRESSURE CONTROL VALVE SETTING OR RELIEF VALVE SETTING

| Maximum start-to-discharge pressure (psig)              | Maximum permitted filling density (percent by weight) |                    |                    |                       |
|---------------------------------------------------------|-------------------------------------------------------|--------------------|--------------------|-----------------------|
|                                                         | Ethylene                                              | Ethylene           | Ethylene           | Hydrogen              |
| 17 .....                                                | .....                                                 | .....              | .....              | 6.60.                 |
| 45 .....                                                | 52.8 .....                                            | .....              | .....              |                       |
| 75 .....                                                | .....                                                 | 51.1 .....         | 51.1 .....         |                       |
| Maximum pressure when offered for transportation.       | 10 psig .....                                         | 10 psig .....      | 20 psig .....      |                       |
| Design service temperature .....                        | Minus 260 °F .....                                    | Minus 260 °F ..... | Minus 155 °F ..... | Minus 423 °F.         |
| Specification (see § 180.507(b)(3) of this subchapter). | 113D60W .....                                         | 113C120W .....     | 113D120W .....     | 113A175W.<br>113A60W. |

(e) *Special requirements for class DOT 113 tank cars*—(1) A class DOT-113 tank car need not be periodically pressure tested; however, each shipment must

be monitored to determine the average daily pressure rise in the tank car. If the average daily pressure rise during any shipment exceeds 0.2 Bar (3 psig)

## § 173.320

## 49 CFR Ch. I (10–1–08 Edition)

per day, the tank must be tested for thermal integrity prior to any subsequent shipment.

(2) *Thermal integrity test.* When required by paragraph (e)(1) of this section, either of the following thermal integrity tests may be used:

(i) *Pressure rise test.* The pressure rise in the tank may not exceed 0.34 Bar (5 psig) in 24 hours. When the pressure rise test is performed, the absolute pressure in the annular space of the loaded tank car may not exceed 75 microns of mercury at the beginning of the test and may not increase more than 25 microns during the 24-hour period; or

(ii) *Calculated heat transfer rate test.* The insulation system must be performance tested as prescribed in § 179.400–4 of this subchapter. When the calculated heat transfer rate test is performed, the absolute pressure in the annular space of the loaded tank car may not exceed 75 microns of mercury at the beginning of the test and may not increase more than 25 microns during the 24-hour period. The calculated heat transfer rate in 24 hours may not exceed:

(A) 120 percent of the appropriate standard heat transfer rate specified in § 179.401–1 of this subchapter, for DOT-113A60W and DOT-113C120W tank cars;

(B) 122,808 joules (0.1164 Btu/day/lb.) of inner tank car water capacity, for DOT-113A175W tank cars;

(C) 345,215 joules (0.3272 Btu/day/lb.) of inner tank car water capacity, for DOT-113C60W and 113D60W tank cars; or

(D) 500.09 joules (0.4740 Btu/day/lb.) of inner tank car water capacity, for DOT-113D120W tank cars.

(3) A tank car that fails a test prescribed in paragraph (e)(2) of this section must be removed from hazardous materials service. A tank car removed from hazardous materials service because it failed a test prescribed in paragraph (e)(2) of this section may not be used to transport a hazardous material unless the tank car conforms to all applicable requirements of this subchapter.

(4) Each rupture disc must be replaced every 12 months, and the replacement date must be marked on the

car near the pressure relief valve information.

(5) Pressure relief valves and alternate pressure relief valves must be tested every five years. The start-to-discharge pressure and vapor tight pressure requirements for the pressure relief valves must be as specified in § 179.401–1 of this subchapter. The alternate pressure relief device values specified in § 179.401–1 of this subchapter for a DOT-113C120W tank car apply to a DOT-113D120W tank car.

(49 U.S.C. 1803, 1804, 1808; 49 CFR 1.53, app. A to part 1)

[Amdt. 173–166, 48 FR 27698, June 16, 1983, as amended by Amdt. 173–245, Sept. 21, 1995; 65 FR 58630, Sept. 29, 2000; 66 FR 45184, 45379, 45383, Aug. 28, 2001; 70 FR 34076, June 13, 2005]

## § 173.320 Cryogenic liquids; exceptions.

(a) Atmospheric gases and helium, cryogenic liquids, in Dewar flasks, insulated cylinders, insulated portable tanks, insulated cargo tanks, and insulated tank cars, designed and constructed so that the pressure in such packagings will not exceed 25.3 psig under ambient temperature conditions during transportation are not subject to the requirements of this subchapter when transported by motor vehicle or railcar except as specified in paragraphs (a)(1), (a)(2), and (a)(3) of this section.

(1) Sections 171.15 and 171.16 of this subchapter pertaining to the reporting of incidents, not including a release that is the result of venting through a pressure control valve, or the neck of the Dewar flask.

(2) Subparts A, B, C, D, G and H of part 172, (§§ 174.24 for rail and 177.817 for highway) and in addition, part 172 in its entirety for oxygen.

(3) Subparts A and B of part 173, and §§ 174.1 and 177.800, 177.804, and 177.823 of this subchapter.

(b) The requirements of this subchapter do not apply to atmospheric gases and helium:

(1) During loading and unloading operations (pressure rises may exceed 25.3 psig); or

(2) When used in operation of a process system; such as a refrigeration system (pressure may exceed 25.3 psig).

(c) For transportation aboard aircraft, see the ICAO Technical Instructions (IBR, see §171.7 of this subchapter), Packing Instruction 202 and the packaging specifications in part 6, chapter 5.

[Amdt. 173–201, 52 FR 13043, Apr. 20, 1987, as amended at 62 FR 51561, Oct. 1, 1997; 66 FR 33436, June 21, 2001; 67 FR 61014, Sept. 27, 2002; 68 FR 48570, Aug. 14, 2003; 68 FR 75746, Dec. 31, 2003]

#### § 173.321 Ethylamine.

Ethylamine must be packaged as follows:

(a) In 1A1 drums which meet Packing Group I performance level requirements.

(b) In specification cylinders as prescribed for any compressed gas except acetylene.

[Amdt. 173–224, 55 FR 52667, Dec. 21, 1990]

#### § 173.322 Ethyl chloride.

Ethyl chloride must be packaged in any of the following single or combination non-bulk packagings which meet Packing Group I performance level requirements:

(a) In 4C1, 4C2, 4D or 4F wooden boxes with glass, earthenware, or metal inner receptacles not over 500 g (17.6 ounces) capacity each;

(b) In 4G fiberboard boxes with glass, earthenware, or metal inner receptacles not over 500 g (17.6 ounces) capacity each. Outer packagings may not exceed 30 kg (66 pounds) gross weight;

(c) In 1A1 drums of not over 100 L (26 gallons) capacity each; or

(d) In specification cylinders as prescribed for any compressed gas except acetylene.

[Amdt. 173–224, 55 FR 52667, Dec. 21, 1990]

#### § 173.323 Ethylene oxide.

(a) For packaging ethylene oxide in non-bulk packagings, silver mercury or any of its alloys or copper may not be used in any part of a packaging, valve, or other packaging appurtenance if that part, during normal conditions of transportation, may come in contact with ethylene oxide liquid or vapor. Copper alloys may be used only where gas mixtures do not contain free acetylene at any concentration that will form copper acetylene. All pack-

aging and gaskets must be constructed of materials which are compatible with ethylene oxide and do not lower the auto-ignition temperature of ethylene oxide.

(b) Ethylene oxide must be packaged in one of the following:

(1) In hermetically sealed glass or metal inner packagings suitably cushioned in an outer package authorized by §173.201(b). The maximum quantity permitted in any glass inner packaging is 100 g (3.5 ounces), and the maximum quantity permitted in any metal inner packaging is 340 g (12 ounces). After filling, each inner packaging shall be determined to be leak-tight by placing the inner packaging in a hot water bath at a temperature, and for a period of time, sufficient to ensure that an internal pressure equal to the vapor pressure of ethylene oxide at 55 °C is achieved. The total quantity in any outer packaging shall not exceed 100 g (3.5 ounces), and the total quantity in any outer packaging containing only metal inner packagings shall not exceed 2.5 kg (5.5 pounds). Each completed package must be capable of passing all Packing Group I performance tests.

(2) In specification cylinders or UN pressure receptacles, as authorized for any compressed gas except acetylene. Pressurizing valves and insulation are required for cylinders over 4 L (1 gallon) capacity. Eductor tubes must be provided for cylinders over 19 L (5 gallons) capacity. Cylinders must be seamless or welded steel (not brazed) with a nominal capacity of no more than 115 L (30 gallons) and may not be liquid full below 82 °C (180 °F). Before each refilling, each cylinder must be tested for leakage at no less than 103.4 kPa (15 psig) pressure. In addition, each cylinder must be equipped with a fusible type relief device with yield temperature of 69 °C to 77 °C (157 °F to 170 °F). The capacity of the relief device and the effectiveness of the insulation must be such that the charged cylinder will not explode when tested by the method described in CGA Pamphlet C-14 or other equivalent method.

(3) In 1A1 steel drums of no more than 231 L (61 gallons) and meeting Packing Group I performance standards. The drum must be lagged of all



welded construction with the inner shell having a minimum thickness of 1.7 mm (0.068 inches) and the outer shell having a minimum thickness of 2.4 mm (0.095 inches). Drums must be capable of withstanding a hydrostatic test pressure of 690 kPa (100 psig). Lagging must be of sufficient thickness so that the drum, when filled with ethylene oxide and equipped with the required pressure relief device, will not rupture when exposed to fire. The drum may not be liquid full below 85 °C (185 °F), and must be marked “THIS END UP” on the top head. Before each refilling, each drum must be tested for leakage at no less than 103 kPa (15 psig) pressure. Each drum must be equipped with a fusible type relief device with yield temperature of 69 °C to 77 °C (157 °F to 170 °F), and the capacity of the relief device must be such that the filled drum is capable of passing, without rupture, the test method described in CGA Pamphlet C-14 or other equivalent method.

(c) When § 172.101 of this subchapter specifies that a hazardous material be packaged under this section, only the following bulk packagings are authorized, subject to the requirements of subparts A and B of this part, the special provisions specified in column 7 of the § 172.101 table, and paragraphs (d) through (j) of this section:

(1) *Tank cars.* Class DOT 105J tank cars: Notwithstanding the requirements of § 173.31(c), each tank car must have a tank test pressure of at least 20.7 Bar (300 psig) no later than July 1, 2006.

(2) *Cargo tanks.* Specification MC 330 and MC 331 cargo tank motor vehicles.

(3) *Portable tanks.* DOT 51 portable tanks.

(d) The pressure relief devices must be set to function at 517 kPa (75 psig). Portable tanks fitted with non-reclosing devices made and in use prior to December 31, 1987, may continue to be used in ethylene oxide service.

(e) In determining outage, consideration must be given to the lading temperature and solubility of inert gas padding in ethylene oxide as well as the partial pressure exerted by the gas padding.

(f) Each tank, loaded or empty, must be padded with dry nitrogen or other

suitable inert gas of sufficient quantity to render the vapor space of the tank nonflammable up to 41 °C (105 °F). The gas used for padding must be free of impurities which may cause the ethylene oxide to polymerize, decompose or undergo other violent chemical reaction.

(g) Copper, silver, mercury, magnesium or their alloys may not be used in any part of the tank or appurtenances that are normally in contact with the lading.

(h) Neoprene, natural rubber and asbestos gaskets are prohibited. All packing and gaskets must be made of materials which do not react with or lower the autoignition temperature of the lading.

(i) Each tank must be insulated with cork (at least 10 cm (4 inches) thick), or mineral wool, fiberglass or other suitable insulation material of sufficient thickness so that the thermal conductance at 16 °C (60 °F) is not more than 0.075 Btu per hour per square foot per degree F. temperature differential. Portable tanks made and in use prior to December 31, 1987 equipped with fusible plugs instead of a pressure relief valve or rupture disc, must have sufficient insulation so that the tank as filled for shipment will not rupture in a fire. The insulation on portable tanks or cargo tank motor vehicles must be protected with a steel jacket at least 2.54 mm (0.100 inch) thick, or as required by the specification.

(j) Tank car tanks built after December 30, 1971 must be equipped with a thermometer well.

[Amdt. 173–224, 55 FR 52667, Dec. 21, 1990, as amended at 56 FR 66279, Dec. 20, 1991; Amdt. 173–236, 58 FR 50237, Sept. 24, 1993; Amdt. 173–234, 58 FR 51532, Oct. 1, 1993; Amdt. 173–145, 60 FR 49076, Sept. 21, 1995; 66 FR 45380, 45383, Aug. 28, 2001; 68 FR 75746, Dec. 31, 2003; 69 FR 76178, Dec. 20, 2004; 71 FR 33884, June 12, 2006]

#### **§ 173.334 Organic phosphates mixed with compressed gas.**

Hexaethyl tetraphosphate, parathion, tetraethyl dithio pyrophosphate, tetraethyl pyrophosphate, or other Division 6.1 organic phosphates (including a compound or mixture), may be mixed with a non-flammable compressed gas. This mixture may not contain more than 20 percent by weight of organic

phosphate and must be packaged in DOT 3A240, 3AA240, 3B240, 4B240, 4BA240, 4BW240 or UN cylinders meeting all of the following requirements:

(a) Each cylinder may be filled with not more than 5 kg (11.0 lb) of the mixture, to a maximum filling density of not more than 80 percent of the water capacity.

(b) No cylinder may be equipped with an education tube or a fusible plug.

(c) No cylinder may be equipped with any valve unless the valve is a type approved by the Associate Administrator.

(d) Cylinders must be overpacked in a box, crate, or other strong outside packaging conforming to the requirements of §173.25 and arranged to protect each valve or other closing device from damage. Except as provided in paragraph (e) of this section, no more than four cylinders may be packed in a strong outside packaging. Each strong outside packaging with its closing device protection must be sufficiently strong to protect all parts of each cylinder from deformation or leakage if the completed package is dropped 1.8 m (6 feet) onto a non-yielding surface, such as concrete or steel, impacting at the packaging's weakest point.

(e) Cylinders may be packed in strong wooden boxes with valves or other closing devices protected from damage, with not more than twelve cylinders in one outside wooden box. An outer fiberboard box may be used when not more than four such cylinders are to be shipped in one packaging. Valves must be adequately protected. Box and valve protection must be of sufficient strength to protect all parts of inner packagings and valves from deformation or breakage resulting from a drop of at least 1.8 m (6 feet) onto a non-yielding surface, such as concrete or steel, impacting at the weakest point.

[67 FR 51651, Aug. 8, 2002, as amended at 71 FR 54395, Sept. 14, 2006]

EDITORIAL NOTE: At 67 FR 61014, Sept. 27, 2002, §173.334(f) was amended, however, paragraph (f) does not exist in this section.

#### § 173.335 [Reserved]

#### § 173.336 Nitrogen dioxide, liquefied, or dinitrogen tetroxide, liquefied.

(a) Nitrogen dioxide, liquefied, or dinitrogen tetroxide, liquefied, must be

packaged in specification or UN cylinders as prescribed in §173.192, except valves are not authorized. UN tubes and MEGCs are not authorized for use. Cylinders must be equipped with a stainless steel valve and valve seat that will not deteriorate in contact with nitrogen dioxide. Each valve opening must be closed by a solid metal plug with tapered thread properly luted to prevent leakage. Transportation in DOT 3AL cylinders is authorized only by highway and rail.

(b) Each UN pressure receptacle must be cleaned in accordance with the requirements of ISO 11621 (IBR, see §171.7 of this subchapter). Each DOT specification cylinder must be cleaned according to the requirements of GSA Federal Specification RR-C-901D, paragraphs 3.3.1 and 3.3.2 (IBR, see §171.7 of this subchapter). Cleaning agents equivalent to those specified in RR-C-901D may be used; however, any cleaning agent must not be capable of reacting with oxygen. One cylinder selected at random from a group of 200 or fewer and cleaned at the same time must be tested for oil contamination in accordance with Specification RR-C-901D, paragraph 4.3.2 (IBR, see §171.7 of this subchapter) and meet the standard of cleanliness specified therein.

[71 FR 33885, June 12, 2006]

#### § 173.337 Nitric oxide.

(a) Nitric oxide must be packaged in cylinders conforming to the requirements of §173.40 and as follows:

(1) *DOT specification cylinder.* In a DOT 3A1800, 3AA1800, 3E1800, or 3AL1800 cylinder. A DOT specification cylinder must be charged to a pressure of not more than 5,170 kPa (750 psi) at 21 °C (70 °F). Transportation of nitric oxide in a DOT 3AL is cylinder is authorized only by highway and rail.

(2) *UN cylinder.* In a UN cylinder with a minimum test pressure of 200 bar. The maximum working pressure of the cylinder must not exceed 50 bar. The pressure in the cylinder at 65 °C (149 °F) may not exceed the test pressure. The use of UN tubes and MEGCs is not authorized.

(3) *Valves.* Cylinders must be equipped with a stainless steel valve and valve seat that will not deteriorate in contact with nitric oxide. Cylinders

## § 173.338

or valves may not be equipped with pressure relief devices of any type.

(b) Each UN cylinder must be cleaned in accordance with the requirements of ISO 11621 (IBR, see §171.7 of this subchapter). Each DOT specification cylinder must be cleaned in compliance with the requirements of GSA Federal Specification RR-C-901D, paragraphs 3.3.1 and 3.3.2 (IBR, see §171.7 of this subchapter). Cleaning agents equivalent to those specified in Federal Specification RR-C-901D may be used; however, any cleaning agent must not be capable of reacting with oxygen. One cylinder selected at random from a group of 200 or fewer and cleaned at the same time must be tested for oil contamination in accordance with Federal Specification RR-C-901D paragraph 4.3.2 and meet the standard of cleanliness specified therein.

[71 FR 33885, June 12, 2006]

### § 173.338 Tungsten hexafluoride.

Tungsten hexafluoride must be packed in specification 3A, 3AA, 3BN, or 3E (§§178.36, 178.37, 178.39, 178.42 of this subchapter) cylinders. Cylinders must be equipped with a valve protection cap or be packed in a strong outside container complying with the provisions of §173.40. Outlets of any valves must be capped or plugged. As an alternative, the cylinder opening may be closed by the use of a metal plug. Specification 3E cylinders must be shipped in an overpack that complies with the provisions of §173.40.

][Amdt. 173-224, 55 FR 52669, Dec. 21, 1990]

### § 173.340 Tear gas devices.

(a) Packagings for tear gas devices must be approved prior to initial transportation by the Associate Administrator.

(b) Tear gas devices may not be assembled with, or packed in the same packaging with, mechanically- or manually-operated firing, igniting, bursting, or other functioning elements unless of a type and design which has been approved by the Associate Administrator.

(c) Tear gas grenades, tear gas candles, and similar devices must be packaged in one of the following packagings conforming to the requirements of part

## 49 CFR Ch. I (10-1-08 Edition)

178 of this subchapter at the Packing Group II performance level:

(1) In UN 4C1, 4C2, 4D, or 4F metal-strapped wooden boxes. Functioning elements not assembled in grenades or devices must be in a separate compartment of these boxes, or in inner or separate outer boxes, UN 4C1, 4C2, 4D, or 4F, and must be so packed and cushioned that they may not come in contact with each other or with the walls of the box during transportation. Not more than 50 tear gas devices and 50 functioning elements must be packed in one box, and the gross weight of the outer box may not exceed 35 kg (77 pounds).

(2) In a UN 1A2 metal drum. Functioning elements must be packed in a separate inner packaging or compartment. Not more than 24 tear gas devices and 24 functioning elements must be packed in one outer drum, and the gross weight of the drum may not exceed 35 kg (77 pounds).

(3) In a UN 4G fiberboard box with inside tear gas devices meeting Specifications 2P or 2Q. Each inside packaging must be placed in fiberboard tubes fitted with metal ends or a fiber box with suitable padding. Not more than 30 inner packagings must be packed in one outer box, and the gross weight of the outer box may not exceed 16 kg (35 pounds).

(4) In other packagings of a type or design which has been approved by the Associate Administrator.

(d) Tear gas devices may be shipped completely assembled when offered by or consigned to the U.S. Department of Defense, provided the functioning elements are so packed that they cannot accidentally function. Outer packagings must be UN 4C1, 4C2, 4D, or 4F metal-strapped wooden boxes.

[Amdt. 173-224, 55 FR 52669, Dec. 21, 1990, as amended 66 FR 45379, Aug. 28, 2001]

## Subpart H [Reserved]

## Subpart I—Class 7 (Radioactive) Materials

SOURCE: Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, unless otherwise noted.

**§ 173.401 Scope.**

(a) This subpart sets forth requirements for the packaging and transportation of Class 7 (radioactive) materials by offerors and carriers subject to this subchapter. The requirements prescribed in this subpart are in addition to, not in place of, other requirements set forth in this subchapter for Class 7 (radioactive) materials and those of the Nuclear Regulatory Commission in 10 CFR part 71.

(b) This subpart does not apply to:

(1) Class 7 (radioactive) materials produced, used, transported, or stored within an establishment other than during the course of transportation, including storage in transportation.

(2) Class 7 (radioactive) materials that have been implanted or incorporated into, and are still in, a person or live animal for diagnosis or treatment.

(3) Class 7 (radioactive) material that is an integral part of the means of transport.

(4) Natural material and ores containing naturally occurring radionuclides which are not intended to be processed for use of these radionuclides, provided the activity concentration of the material does not exceed 10 times the values specified in § 173.436.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 69 FR 3670, Jan. 26, 2004]

**§ 173.403 Definitions.**

For purposes of this subpart—

A<sub>1</sub> means the maximum activity of special form Class 7 (radioactive) material permitted in a Type A package. This value is either listed in § 173.435 or may be derived in accordance with the procedures prescribed in § 173.433.

A<sub>2</sub> means the maximum activity of Class 7 (radioactive) material, other than special form material, LSA material, and SCO, permitted in a Type A package. This value is either listed in § 173.435 or may be derived in accordance with the procedures prescribed in § 173.433.

*Class 7 (radioactive) material* See the definition of *Radioactive material* in this section.

*Closed transport vehicle* means a transport vehicle or conveyance equipped

with a securely attached exterior enclosure that during normal transportation restricts the access of unauthorized persons to the cargo space containing the Class 7 (radioactive) materials. The enclosure may be either temporary or permanent, and in the case of packaged materials may be of the “see-through” type, and must limit access from top, sides, and bottom.

*Consignment* means a package or group of packages or load of radioactive material offered by a person for transport in the same shipment.

*Containment system* means the assembly of components of the packaging intended to retain the Class 7 (radioactive) material during transport.

*Contamination* means the presence of a radioactive substance on a surface in quantities in excess of 0.4 Bq/cm<sup>2</sup> for beta and gamma emitters and low toxicity alpha emitters or 0.04 Bq/cm<sup>2</sup> for all other alpha emitters. Contamination exists in two phases.

(1) *Fixed radioactive contamination* means radioactive contamination that cannot be removed from a surface during normal conditions of transport.

(2) *Non-fixed radioactive contamination* means radioactive contamination that can be removed from a surface during normal conditions of transport.

*Conveyance* means:

(1) For transport by public highway or rail: any transport vehicle or large freight container;

(2) For transport by water: any vessel, or any hold, compartment, or defined deck area of a vessel including any transport vehicle on board the vessel; and

(3) For transport by aircraft, any aircraft.

*Criticality Safety Index (CSI)* means a number (rounded up to the next tenth) which is used to provide control over the accumulation of packages, overpacks or freight containers containing fissile material. The CSI for packages containing fissile material is determined in accordance with the instructions provided in 10 CFR 71.22, 71.23, and 71.59. The CSI for an overpack, freight container, or consignment containing fissile material packages is the arithmetic sum of the criticality safety indices of all the fissile material

packages contained within the overpack, freight container, or consignment.

*Design* means the description of a special form Class 7 (radioactive) material, a package, packaging, or LSA-III, that enables those items to be fully identified. The description may include specifications, engineering drawings, reports showing compliance with regulatory requirements, and other relevant documentation.

*Deuterium* means, for the purposes of § 173.453, deuterium and any deuterium compound, including heavy water, in which the ratio of deuterium atoms to hydrogen atoms exceeds 1:5000.

*Exclusive use* means sole use by a single consignor of a conveyance for which all initial, intermediate, and final loading and unloading are carried out in accordance with the direction of the consignor or consignee. The consignor and the carrier must ensure that any loading or unloading is performed by personnel having radiological training and resources appropriate for safe handling of the consignment. The consignor must provide to the initial carrier specific written instructions for maintenance of exclusive use shipment controls, including the vehicle survey requirement of § 173.443 (c) as applicable, and include these instructions with the shipping paper information provided to the carrier by the consignor.

*Exemption value* means either an exempt material activity concentration or an exempt consignment activity limit listed in the table in § 173.436, or determined according to the procedures described in § 173.433, and used to determine whether a given physically radioactive material is sufficiently radioactive to be subject to the HMR (see definition of radioactive material). An exemption value is different from an exemption, as specified under the definition for special permit in § 171.8 of this subchapter.

*Fissile material* means plutonium<sup>239</sup>, plutonium<sup>241</sup>, uranium<sup>233</sup>, uranium<sup>235</sup>, or any combination of these radionuclides. This term does not apply to material containing fissile nuclides, unirradiated natural uranium and unirradiated depleted uranium, or to natural uranium or depleted uranium

that has been irradiated in thermal reactors only.

*Freight container* means a reusable container having a volume of 1.81 cubic meters (64 cubic feet) or more, designed and constructed to permit it being lifted with its contents intact and intended primarily for containment of packages in unit form during transportation. A “small freight container” is one which has either one outer dimension less than 1.5 m (4.9 feet) or an internal volume of not more than 3.0 cubic meters (106 cubic feet). All other freight containers are designated as “large freight containers.”

*Graphite* means, for the purposes of § 173.453, graphite with a boron equivalent content less than 5 parts per million and density greater than 1.5 grams per cubic centimeter.

*Highway route controlled quantity* means a quantity within a single package which exceeds:

(1) 3,000 times the  $A_1$  value of the radionuclides as specified in § 173.435 for special form Class 7 (radioactive) material;

(2) 3,000 times the  $A_2$  value of the radionuclides as specified in § 173.435 for normal form Class 7 (radioactive) material; or

(3) 1,000 TBq (27,000 Ci), whichever is least.

*Limited quantity of Class 7 (radioactive) material* means a quantity of Class 7 (radioactive) material not exceeding the material's package limits specified in § 173.425 and conforming with requirements specified in § 173.421.

*Low Specific Activity (LSA) material* means Class 7 (radioactive) material with limited specific activity which satisfies the descriptions and limits set forth below. Shielding material surrounding the LSA material may not be considered in determining the estimated average specific activity of the package contents. LSA material must be in one of three groups:

(1) LSA-I:

(i) Uranium and thorium ores, concentrates of uranium and thorium ores, and other ores containing naturally occurring radionuclides which are intended to be processed for the use of these radionuclides; or

(ii) Solid unirradiated natural uranium or depleted uranium or natural

thorium or their solid or liquid compounds or mixtures; or

(iii) Radioactive material other than fissile material, for which the  $A_2$  value is unlimited; or

(iv) Other radioactive material, excluding fissile material in quantities not excepted under § 173.453, in which the activity is distributed throughout and the estimated average specific activity does not exceed 30 times the values for activity concentration specified in § 173.436, or 30 times the default values listed in Table 8 of § 173.433.

(2) LSA-II:

(i) Water with tritium concentration up to 0.8 TBq/L (20.0 Ci/L); or

(ii) Other radioactive material in which the activity is distributed throughout and the average specific activity does not exceed  $10^{-4}$   $A_2/g$  for solids and gases, and  $10^{-5}$   $A_2/g$  for liquids.

(3) LSA-III. Solids (e.g., consolidated wastes, activated materials), excluding powders, that meet the requirements of § 173.468 and in which:

(i) The radioactive material is distributed throughout a solid or a collection of solid objects, or is essentially uniformly distributed in a solid compact binding agent (such as concrete, bitumen, ceramic, etc.);

(ii) The radioactive material is relatively insoluble, or it is intrinsically contained in a relatively insoluble material, so that, even under loss of packaging, the loss of Class 7 (radioactive) material per package by leaching when placed in water for seven days would not exceed 0.1  $A_2$ ; and

(iii) The estimated average specific activity of the solid, excluding any shielding material, does not exceed  $2 \times 10^{-3}$   $A_2/g$ .

*Low toxicity alpha emitters* means natural uranium; depleted uranium; natural thorium; uranium-235 or uranium-238; thorium-232; thorium-228 and thorium-230 when contained in ores or physical and chemical concentrates; and alpha emitters with a half-life of less than 10 days.

*Maximum normal operating pressure* means the maximum gauge pressure that would develop in a containment system during a period of one year, in the absence of venting or cooling, under the heat conditions specified in 10 CFR 71.71(c)(1).

*Multilateral approval* means approval of a package design or shipment by the relevant Competent Authority of the country of origin and of each country through or into which the package or shipment is to be transported. This definition does not include approval from a country over which Class 7 (radioactive) materials are carried in aircraft, if there is no scheduled stop in that country.

*Natural thorium* means thorium with the naturally occurring distribution of thorium isotopes (essentially 100 percent by weight of thorium-232).

*Normal form Class 7 (radioactive) material* means Class 7 (radioactive) which has not been demonstrated to qualify as "special form Class 7 (radioactive) material."

*Package* means the packaging together with its radioactive contents as presented for transport.

(1) "Excepted package" means a packaging together with its excepted Class 7 (radioactive) materials as specified in §§ 173.421–173.426 and 173.428.

(2) "Industrial package" means a packaging that, together with its low specific activity (LSA) material or surface contaminated object (SCO) contents, meets the requirements of §§ 173.410 and 173.411. Industrial packages are categorized in § 173.411 as either:

(i) "Industrial package Type 1 (IP-1)";

(ii) "Industrial package Type 2 (IP-2)"; or

(iii) "Industrial package Type 3 (IP-3)".

(3) "Type A package" means a packaging that, together with its radioactive contents limited to  $A_1$  or  $A_2$  as appropriate, meets the requirements of §§ 173.410 and 173.412 and is designed to retain the integrity of containment and shielding required by this part under normal conditions of transport as demonstrated by the tests set forth in § 173.465 or § 173.466, as appropriate. A Type A package does not require Competent Authority approval.

(4) "Type B package" means a packaging designed to transport greater than an  $A_1$  or  $A_2$  quantity of radioactive material that, together with its radioactive contents, is designed to retain the integrity of containment and

§ 173.403

49 CFR Ch. I (10–1–08 Edition)

shielding required by this part when subjected to the normal conditions of transport and hypothetical accident test conditions set forth in 10 CFR part 71.

(i) “Type B(U) package” means a Type B packaging that, together with its radioactive contents, for international shipments requires unilateral approval only of the package design and of any stowage provisions that may be necessary for heat dissipation.

(ii) “Type B(M) package” means a Type B packaging, together with its radioactive contents, that for international shipments requires multilateral approval of the package design, and may require approval of the conditions of shipment. Type B(M) packages are those Type B package designs which have a maximum normal operating pressure of more than 700 kPa/cm<sup>2</sup> (100 lb/in<sup>2</sup>) gauge or a relief device which would allow the release of Class 7 (radioactive) material to the environment under the hypothetical accident conditions specified in 10 CFR part 71.

(5) “Fissile material package” means a packaging, together with its fissile material contents, which meets the requirements for fissile material packages described in subpart E of 10 CFR 71. A fissile material package may be a Type AF package, a Type B(U)F package, or a Type B(M)F package.

*Packaging* means, for Class 7 (radioactive) materials, the assembly of components necessary to ensure compliance with the packaging requirements of this subpart. It may consist of one or more receptacles, absorbent materials, spacing structures, thermal insulation, radiation shielding, service equipment for filling, emptying, venting and pressure relief, and devices for cooling or absorbing mechanical shocks. The conveyance, tie-down system, and auxiliary equipment may sometimes be designated as part of the packaging.

*Quality assurance* means a systematic program of controls and inspections applied by each person involved in the transport of radioactive material which provides confidence that a standard of safety prescribed in this subchapter is achieved in practice.

*Radiation level* means the radiation dose-equivalent rate expressed in

millisieverts per hour or mSv/h (milliremms per hour or mrem/h). Neutron flux densities may be converted into radiation levels according to Table 1:

TABLE 1—NEUTRON FLUENCE RATES TO BE REGARDED AS EQUIVALENT TO A RADIATION LEVEL OF 0.01 MSV/H (1MREM/H)<sup>1</sup>

| Energy of neutron            | Flux density equivalent to 0.01 mSv/h (1 mrem/h) neutrons per square centimeter per second (n/cm <sup>2</sup> /s) |
|------------------------------|-------------------------------------------------------------------------------------------------------------------|
| Thermal (2.510E–8) MeV ..... | 272.0                                                                                                             |
| 1 keV .....                  | 272.0                                                                                                             |
| 10 keV .....                 | 281.0                                                                                                             |
| 100 keV .....                | 47.0                                                                                                              |
| 500 keV .....                | 11.0                                                                                                              |
| 1 MeV .....                  | 7.5                                                                                                               |
| 5 MeV .....                  | 6.4                                                                                                               |
| 10 MeV .....                 | 6.7                                                                                                               |

<sup>1</sup>Flux densities equivalent for energies between those listed in this table may be obtained by linear interpolation.

*Radioactive contents* means a Class 7 (radioactive) material, together with any contaminated or activated solids, liquids and gases within the packaging.

*Radioactive instrument or article* means any manufactured instrument or article such as an instrument, clock, electronic tube or apparatus, or similar instrument or article having Class 7 (radioactive) material in gaseous or non-dispersible solid form as a component part.

*Radioactive material* means any material containing radionuclides where both the activity concentration and the total activity in the consignment exceed the values specified in the table in §173.436 or values derived according to the instructions in §173.433.

*Special form Class 7 (radioactive) material* means either an indispersible solid radioactive material or a sealed capsule containing radioactive material which satisfies the following conditions:

(1) It is either a single solid piece or a sealed capsule containing radioactive material that can be opened only by destroying the capsule;

(2) The piece or capsule has at least one dimension not less than 5 mm (0.2 in); and

(3) It satisfies the test requirements of §173.469. Special form encapsulations designed in accordance with the requirements of §173.389(g) in effect on

June 30, 1983 (see 49 CFR part 173, revised as of October 1, 1982), and constructed prior to July 1, 1985 and special form encapsulations designed in accordance with the requirements of § 173.403 in effect on March 31, 1996 (see 49 CFR part 173, revised as of October 1, 1995), and constructed prior to April 1, 1997, may continue to be used. Any other special form encapsulation must meet the requirements of this paragraph (3).

*Specific activity* of a radionuclide means the activity of the radionuclide per unit mass of that nuclide. The specific activity of a material in which the radionuclide is essentially uniformly distributed is the activity per unit mass of the material.

*Surface Contaminated Object (SCO)* means a solid object which is not itself radioactive but which has radioactive material distributed on its surface. SCO exists in two phases:

(1) SCO-I: A solid object on which:

(i) The non-fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 4 Bq/cm<sup>2</sup> (10<sup>-4</sup> microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 0.4 Bq/cm<sup>2</sup> (10<sup>-5</sup> microcurie/cm<sup>2</sup>) for all other alpha emitters;

(ii) The fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 4 × 10<sup>4</sup> Bq/cm<sup>2</sup> (1.0 microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 4 × 10<sup>3</sup> Bq/cm<sup>2</sup> (0.1 microcurie/cm<sup>2</sup>) for all other alpha emitters; and

(iii) The non-fixed contamination plus the fixed contamination on the inaccessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 4 × 10<sup>4</sup> Bq/cm<sup>2</sup> (1 microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 4 × 10<sup>3</sup> Bq/cm<sup>2</sup> (0.1 microcurie/cm<sup>2</sup>) for all other alpha emitters.

(2) SCO-II: A solid object on which the limits for SCO-I are exceeded and on which:

(i) The non-fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less

than 300 cm<sup>2</sup>) does not exceed 400 Bq/cm<sup>2</sup> (10<sup>-2</sup> microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 40 Bq/cm<sup>2</sup> (10<sup>-3</sup> microcurie/cm<sup>2</sup>) for all other alpha emitters;

(ii) The fixed contamination on the accessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 8 × 10<sup>5</sup> Bq/cm<sup>2</sup> (20 microcurie/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 8 × 10<sup>4</sup> Bq/cm<sup>2</sup> (2 microcuries/cm<sup>2</sup>) for all other alpha emitters; and

(iii) The non-fixed contamination plus the fixed contamination on the inaccessible surface averaged over 300 cm<sup>2</sup> (or the area of the surface if less than 300 cm<sup>2</sup>) does not exceed 8 × 10<sup>5</sup> Bq/cm<sup>2</sup> (20 microcuries/cm<sup>2</sup>) for beta and gamma and low toxicity alpha emitters, or 8 × 10<sup>4</sup> Bq/cm<sup>2</sup> (2 microcuries/cm<sup>2</sup>) for all other alpha emitters.

*Transport index (TI)* means the dimensionless number (rounded up to the next tenth) placed on the label of a package, to designate the degree of control to be exercised by the carrier during transportation. The transport index is determined by multiplying the maximum radiation level in millisieverts (mSv) per hour at 1 m (3.3 ft) from the external surface of the package by 100 (equivalent to the maximum radiation level in millirem per hour at 1 m (3.3 ft)).

*Type A quantity* means a quantity of Class 7 (radioactive) material, the aggregate radioactivity which does not exceed A<sub>1</sub> for special form Class 7 (radioactive) material of A<sub>2</sub> for normal form Class 7 (radioactive) material, where A<sub>1</sub> and A<sub>2</sub> values are given in § 173.435 or are determined in accordance with § 173.433.

*Type B quantity* means a quantity of material greater than a Type A quantity.

*Unilateral approval* means approval of a package design solely by the Competent Authority of the country of origin of the design.

*Unirradiated thorium* means thorium containing not more than 10<sup>-7</sup> grams uranium-233 per gram of thorium-232.

*Unirradiated uranium* means uranium containing not more than 2 × 10<sup>3</sup> Bq of plutonium per gram of uranium-235,



## § 173.410

## 49 CFR Ch. I (10–1–08 Edition)

not more than  $9 \times 10^6$  Bq of fission products per gram of uranium-235 and not more than  $5 \times 10^{-3}$  g of uranium-236 per gram of uranium-235.

*Uranium—natural, depleted or enriched* means the following:

(1)(i) “Natural uranium” means chemically separated uranium containing the naturally occurring distribution of uranium isotopes (approximately 99.28% uranium-238 and 0.72% uranium-235 by mass).

(ii) “Depleted uranium” means uranium containing a lesser mass percentage of uranium-235 than in natural uranium.

(iii) “Enriched uranium” means uranium containing a greater mass percentage of uranium-235 than 0.72%.

(2) In all cases listed in this definition, a very small mass percentage of uranium-234 is present.

[69 FR 3670, Jan. 26, 2004; 69 FR 55116, Sept. 13, 2004; 69 FR 58843, Oct. 1, 2004; 70 FR 56098, Sept. 23, 2005; 70 FR 73165, Dec. 9, 2005]

### § 173.410 General design requirements.

In addition to the requirements of subparts A and B of this part, each package used for the shipment of Class 7 (radioactive) materials must be designed so that—

(a) The package can be easily handled and properly secured in or on a conveyance during transport.

(b) Each lifting attachment that is a structural part of the package must be designed with a minimum safety factor of three against yielding when used to lift the package in the intended manner, and it must be designed so that failure of any lifting attachment under excessive load would not impair the ability of the package to meet other requirements of this subpart. Any other structural part of the package which could be used to lift the package must be capable of being rendered inoperable for lifting the package during transport or must be designed with strength equivalent to that required for lifting attachments.

(c) The external surface, as far as practicable, will be free from protruding features and will be easily decontaminated.

(d) The outer layer of packaging will avoid, as far as practicable, pockets or crevices where water might collect.

(e) Each feature that is added to the package will not reduce the safety of the package.

(f) The package will be capable of withstanding the effects of any acceleration, vibration or vibration resonance that may arise under normal conditions of transport without any deterioration in the effectiveness of the closing devices on the various receptacles or in the integrity of the package as a whole and without loosening or unintentionally releasing the nuts, bolts, or other securing devices even after repeated use (see §§ 173.24, 173.24a, and 173.24b).

(g) The materials of construction of the packaging and any components or structure will be physically and chemically compatible with each other and with the package contents. The behavior of the packaging and the package contents under irradiation will be taken into account.

(h) All valves through which the package contents could escape will be protected against unauthorized operation.

(i) For transport by air—

(1) The temperature of the accessible surfaces of the package will not exceed 50 °C (122 °F) at an ambient temperature of 38 °C (100 °F) with no account taken for insulation;

(2) The integrity of containment will not be impaired if the package is exposed to ambient temperatures ranging from –40 °C (–40 °F) to +55 °C (131 °F); and

(3) Packages containing liquid contents will be capable of withstanding, without leakage, an internal pressure that produces a pressure differential of not less than 95 kPa (13.8 lb/in<sup>2</sup>).

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by Amdt. 173–244, 61 FR 20750, May 8, 1996; 64 FR 51919, Sept. 27, 1999]

### § 173.411 Industrial packagings.

(a) *General.* Each industrial packaging must comply with the requirements of this section which specifies packaging tests, and record retention applicable to Industrial Packaging Type 1 (IP–1), Industrial Packaging Type 2 (IP–2), and Industrial Packaging Type 3 (IP–3).

(b) *Industrial packaging certification and tests.* (1) Each IP–1 must meet the

general design requirements prescribed in § 173.410.

(2) Each IP-2 must meet the general design requirements prescribed in § 173.410 and when subjected to the tests specified in § 173.465(c) and (d) or evaluated against these tests by any of the methods authorized by § 173.461(a), must prevent:

(i) Loss or dispersal of the radioactive contents; and

(ii) A significant increase in the radiation levels recorded or calculated at the external surfaces for the condition before the test.

(3) Each IP-3 packaging must meet the requirements for an IP-1 and an IP-2, and must meet the requirements specified in § 173.412(a) through (j).

(4) Tank containers may be used as Industrial package Types 2 or 3 (Type IP-2 or Type IP-3) provided that:

(i) They satisfy the requirements for Type IP-1 specified in paragraph (b)(1);

(ii) They are designed to conform to the standards prescribed in Chapter 6.7, of the United Nations Recommendations on the Transport of Dangerous Goods, (IBR, see § 171.7 of this subchapter), "Requirements for the Design, Construction, Inspection and Testing of Portable Tanks and Multiple-Element Gas Containers (MEGCs)," or other requirements at least equivalent to those standards;

(iii) They are capable of withstanding a test pressure of 265 kPa (37.1 psig); and

(iv) They are designed so that any additional shielding which is provided shall be capable of withstanding the static and dynamic stresses resulting from handling and routine conditions of transport and of preventing a loss of shielding integrity which would result in more than a 20% increase in the radiation level at any external surface of the tank containers.

(5) Tanks, other than tank containers, including DOT Specification IM 101 or IM 102 steel portable tanks, may be used as Industrial package Types 2 or 3 (Type IP-2) or (Type IP-3) for transporting LSA-I and LSA-II liquids and gases as prescribed in Table 6, provided that they conform to standards at least equivalent to those prescribed in paragraph (b)(4) of this section.

(6) Freight containers may be used as Industrial packages Types 2 or 3 (Type IP-2) or (Type IP-3) provided that:

(i) The radioactive contents are restricted to solid materials;

(ii) They satisfy the requirements for Type IP-1 specified in paragraph (b)(1); and

(iii) They are designed to conform to the standards prescribed in the International Organization for Standardization document ISO 1496-1: "Series 1 Freight Containers—Specifications and Testing—Part 1: General Cargo Containers; excluding dimensions and ratings (IBR, see § 171.7 of this subchapter). They shall be designed such that if subjected to the tests prescribed in that document and the accelerations occurring during routine conditions of transport they would prevent:

(A) Loss or dispersal of the radioactive contents; and

(B) Loss of shielding integrity which would result in more than a 20% increase in the radiation level at any external surface of the freight containers.

(7) Metal intermediate bulk containers may also be used as Industrial package Type 2 or 3 (Type IP-2 or Type IP-3), provided that:

(i) They satisfy the requirements for Type IP-1 specified in paragraph (b)(1); and

(ii) They are designed to conform to the standards prescribed in Chapter 6.5 of the United Nations Recommendations on the Transport of Dangerous Goods, (IBR, see § 171.7 of this subchapter), "Requirements for the Construction and Testing of Intermediate Bulk Containers," for Packing Group I or II, and if they were subjected to the tests prescribed in that document, but with the drop test conducted in the most damaging orientation, they would prevent:

(A) Loss or dispersal of the radioactive contents; and

(B) Loss of shielding integrity which would result in more than a 20% increase in the radiation level at any external surface of the intermediate bulk containers.

(c) Except for IP-1 packagings, each offeror of an industrial package must maintain on file for at least one year after the latest shipment, and shall provide to the Associate Administrator

## § 173.412

## 49 CFR Ch. I (10–1–08 Edition)

on request, complete documentation of tests and an engineering evaluation or comparative data showing that the construction methods, packaging design, and materials of construction comply with that specification.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by Amdt. 173–244, 61 FR 20750, May 8, 1996; 66 FR 45379, 45383, Aug. 28, 2001; 68 FR 75747, Dec. 31, 2003; 69 FR 3673, Jan. 26, 2004; 69 FR 55117, Sept. 13, 2004; 69 FR 58843, Oct. 1, 2004; 72 FR 55693, Oct. 1, 2007]

### § 173.412 Additional design requirements for Type A packages.

In addition to meeting the general design requirements prescribed in § 173.410, each Type A packaging must be designed so that—

(a) The outside of the packaging incorporates a feature, such as a seal, that is not readily breakable, and that, while intact, is evidence that the package has not been opened. In the case of packages shipped in closed transport vehicles in exclusive use, the cargo compartment, instead of the individual packages, may be sealed.

(b) The smallest external dimension of the package is not less than 10 cm (4 inches).

(c) Containment and shielding is maintained during transportation and storage in a temperature range of  $-40^{\circ}\text{C}$  ( $-40^{\circ}\text{F}$ ) to  $70^{\circ}\text{C}$  ( $158^{\circ}\text{F}$ ). Special attention shall be given to liquid contents and to the potential degradation of the packaging materials within the temperature range.

(d) The packaging must include a containment system securely closed by a positive fastening device that cannot be opened unintentionally or by pressure that may arise within the package during normal transport. Special form Class 7 (radioactive) material, as demonstrated in accordance with § 173.469, may be considered as a component of the containment system. If the containment system forms a separate unit of the package, it must be securely closed by a positive fastening device that is independent of any other part of the package.

(e) For each component of the containment system account is taken, where applicable, of radiolytic decomposition of materials and the genera-

tion of gas by chemical reaction and radiolysis.

(f) The containment system will retain its radioactive contents under the reduction of ambient pressure to 25 kPa (3.6 psi).

(g) Each valve, other than a pressure relief device, is provided with an enclosure to retain any leakage.

(h) Any radiation shield that encloses a component of the packaging specified as part of the containment system will prevent the unintentional escape of that component from the shield.

(i) Failure of any tie-down attachment that is a structural part of the packaging, under both normal and accident conditions, must not impair the ability of the package to meet other requirements of this subpart.

(j) When evaluated against the performance requirements of this section and the tests specified in § 173.465 or using any of the methods authorized by § 173.461(a), the packaging will prevent—

(1) Loss or dispersal of the radioactive contents; and

(2) A significant increase in the radiation levels recorded or calculated at the external surfaces for the condition before the test.

(k) Each packaging designed for liquids will—

(1) Be designed to provide for ullage to accommodate variations in temperature of the contents, dynamic effects and filling dynamics;

(2) Meet the conditions prescribed in paragraph (j) of this section when subjected to the tests specified in § 173.466 or evaluated against these tests by any of the methods authorized by § 173.461(a); and

(3) Either—

(i) Have sufficient suitable absorbent material to absorb twice the volume of the liquid contents. The absorbent material must be compatible with the package contents and suitably positioned to contact the liquid in the event of leakage; or

(ii) Have a containment system composed of primary inner and secondary outer containment components designed to assure retention of the liquid contents within the secondary outer component in the event that the primary inner component leaks.

(l) Each package designed for gases, other than tritium not exceeding 40 TBq (1080Ci) or noble gases not exceeding the  $A_2$  value appropriate for the noble gas, will be able to prevent loss or dispersal of contents when the package is subjected to the tests prescribed in § 173.466 or evaluated against these tests by any of the methods authorized by § 173.461(a).

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended by 66 FR 45379, Aug. 28, 2001; 68 FR 57633, Oct. 6, 2003]

#### **§ 173.413 Requirements for Type B packages.**

Except as provided in § 173.416, each Type B(U) or Type B(M) package must be designed and constructed to meet the applicable requirements specified in 10 CFR part 71.

#### **§ 173.415 Authorized Type A packages.**

The following packages are authorized for shipment if they do not contain quantities exceeding  $A_1$  or  $A_2$  as appropriate:

(a) DOT Specification 7A (see § 178.350 of this subchapter) Type A general packaging. Each offeror of a Specification 7A package must maintain on file for at least one year after the latest shipment, and shall provide to DOT on request, complete documentation of tests and an engineering evaluation or comparative data showing that the construction methods, packaging design, and materials of construction comply with that specification.

(b) Any other Type A packaging that also meets the applicable standards for fissile materials in 10 CFR part 71 and is used in accordance with § 173.471.

(c) Any Type B(U) or Type B(M) packaging authorized pursuant to § 173.416.

(d) Any foreign-made packaging that meets the standards in “IAEA Regulations for the Safe Transport of Radioactive Material No. TS-R-1” (IBR, see § 171.7 of this subchapter) and bears the marking “Type A”. Such packagings may be used for domestic and export shipments of Class 7 (radioactive) materials provided the offeror obtains the applicable documentation of tests and engineering evaluations and maintains the documentation on file in accordance with paragraph (a) of this section.

These packagings must conform with requirements of the country of origin (as indicated by the packaging marking) and the IAEA regulations applicable to Type A packagings.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 67 FR 61014, Sept. 27, 2002; 68 FR 75742, Dec. 31, 2003; 69 FR 3673, Jan. 26, 2004; 69 FR 55117, Sept. 13, 2004]

#### **§ 173.416 Authorized Type B packages.**

Each of the following packages is authorized for shipment of quantities exceeding  $A_1$  or  $A_2$ , as appropriate:

(a) Any Type B(U) or Type B(M) packaging that meets the applicable requirements of 10 CFR part 71 and that has been approved by the U.S. Nuclear Regulatory Commission may be shipped pursuant to § 173.471.

(b) Any Type B(U) or B(M) packaging that meets the applicable requirements in “IAEA Regulations for the Safe Transport of Radioactive Material, No. TS-R-1” (IBR, see § 171.7 of this subchapter) and for which the foreign Competent Authority Certificate has been revalidated by DOT pursuant to § 173.473. These packagings are authorized only for export and import shipments.

(c) Continued use of an existing Type B packaging constructed to DOT Specification 6M, 20WC, or 21WC is authorized until October 1, 2008 if it conforms in all aspects to the requirements of this subchapter in effect on October 1, 2003.

[69 FR 3673, Jan. 26, 2004]

#### **§ 173.417 Authorized fissile materials packages.**

(a) Except as provided in § 173.453, fissile materials containing not more than  $A_1$  or  $A_2$  as appropriate, must be packaged in one of the following packagings:

(1)(i) Any packaging listed in § 173.415, limited to the Class 7 (radioactive) materials specified in 10 CFR part 71, subpart C;

(ii) Any Type AF, Type B(U)F, or Type B(M)F packaging that meets the applicable standards for fissile material packages in 10 CFR part 71; or

(iii) Any Type AF, Type B(U)F, or Type B(M)F packaging that meets the applicable requirements for fissile material packages in Section VI of the

**§ 173.417**

**49 CFR Ch. I (10–1–08 Edition)**

International Atomic Energy Agency “Regulations for the Safe Transport of Radioactive Material, No. TS-R-1 (IBR, see § 171.7 of this subchapter),” and for which the foreign Competent Authority certificate has been revalidated by the U.S. Competent Authority, in accordance with § 173.473. These packages are authorized only for export and import shipments.

(2) A residual “heel” of enriched solid uranium hexafluoride may be trans-

ported without a protective overpack in any metal cylinder that meets both the requirements of § 173.415 and § 178.350 of this subchapter for Specification 7A Type A packaging, and the requirements of § 173.420 for packagings containing greater than 0.1 kg of uranium hexafluoride. Any such shipment must be made in accordance with Table 2, as follows:

**TABLE 2—ALLOWABLE CONTENT OF URANIUM HEXAFLUORIDE (UF<sub>6</sub> “HEEL” IN A SPECIFICATION 7A CYLINDER)**

| Maximum cylinder diameter |        | Cylinder volume |                    | Maximum Uranium 235-enrichment (weight) percent | Maximum "Heel" weight per cylinder |      |             |      |
|---------------------------|--------|-----------------|--------------------|-------------------------------------------------|------------------------------------|------|-------------|------|
| Centi-meters              | Inches | Liters          | Cubic feet         |                                                 | UF <sub>6</sub>                    |      | Uranium-235 |      |
|                           |        |                 |                    |                                                 | kg                                 | lb   | kg          | lb   |
| 12.7                      | 5      | 8.8             | 0.311              | 100.0                                           | 0.045                              | 0.1  | 0.031       | 0.07 |
| 20.3                      | 8      | 39.0            | 1.359              | 12.5                                            | 0.227                              | 0.5  | 0.019       | 0.04 |
| 30.5                      | 12     | 68.0            | 2.410              | 5.0                                             | 0.454                              | 1.0  | 0.015       | 0.03 |
| 76.0                      | 30     | 725.0           | 25.64              | 5.0                                             | 11.3                               | 25.0 | 0.383       | 0.84 |
| 122.0                     | 48     | 3,084.0         | <sup>1</sup> 108.9 | 4.5                                             | 22.7                               | 50.0 | 0.690       | 1.52 |
| 122.0                     | 48     | 4,041.0         | <sup>2</sup> 142.7 | 4.5                                             | 22.7                               | 50.0 | 0.690       | 1.52 |

<sup>1</sup>10 ton.

<sup>2</sup>14 ton

(3) DOT Specification 20PF–1, 20PF–2, or 20PF–3 (see § 178.356 of this subchapter), or Specification 21PF–1A, 21PF–1B, or 21PF–2 (see § 178.358 of this subchapter) phenolic-foam insulated overpack with snug fittings inner metal cylinders, meeting all requirements of §§ 173.24, 173.410, 173.412, and 173.420 and the following:

(i) Handling procedures and packaging criteria must be in accordance with United States Enrichment Corporation Report No. USEC–651 or ANSI N14.1 (IBR, see § 171.7 of this subchapter); and

(ii) Quantities of uranium hexafluoride are authorized as shown in Table 3 of this section, with each package assigned a minimum criticality safety index as also shown.

(b) Fissile Class 7 (radioactive) materials with radioactive content exceeding A<sub>1</sub> or A<sub>2</sub> must be packaged in one of the following packagings:

(1) Type B(U), or Type B(M) packaging that meets the standards for packaging of fissile materials in 10 CFR part 71, and is approved by the U.S. Nuclear Regulatory Commission and used in accordance with § 173.471;

(2) Type B(U) or Type B(M) packaging that also meets the applicable requirements for fissile material packaging in Section VI of the International Atomic Energy Agency “Regulations for the Safe Transport of Radioactive Material, No. TS-R-1,” and for which the foreign Competent Authority certificate has been revalidated by the U.S. Competent Authority in accordance with § 173.473. These packagings are authorized only for import and export shipments; or

(3) DOT Specifications 20PF–1, 20PF–2, or 20PF–3 (see § 178.356 of this subchapter), for DOT Specifications 21PF–1A or 21PF–1B (see § 178.356 of this subchapter) phenolic-foam insulated overpack with snug fitting inner metal cylinders, meeting all requirements of §§ 173.24, 173.410, and 173.412, and the following:

(i) Handling procedures and packaging criteria must be in accordance with United States Enrichment Corporation Report No. USEC–651 or ANSI N14.1; and

(ii) Quantities of uranium hexafluoride are authorized as shown in Table 3, with each package assigned

a minimum criticality safety index as also shown:

TABLE 3—AUTHORIZED QUANTITIES OF URANIUM HEXAFLUORIDE

| Protective overpack specification number            | Maximum inner cylinder diameter |        | Maximum weight of UF <sub>6</sub> contents |        | Maximum U-235 enrichment (weight/percent) | Minimum criticality safety index |
|-----------------------------------------------------|---------------------------------|--------|--------------------------------------------|--------|-------------------------------------------|----------------------------------|
|                                                     | Centimeters                     | Inches | Kilograms                                  | Pounds |                                           |                                  |
| 20PF-1 .....                                        | 12.7                            | 5      | 25                                         | 55     | 100.0                                     | 0.1                              |
| 20PF-2 .....                                        | 20.3                            | 8      | 116                                        | 255    | 12.5                                      | 0.4                              |
| 20PF-3 .....                                        | 30.5                            | 12     | 209                                        | 460    | 5.0                                       | 1.1                              |
| 21PF-1A <sup>1</sup> or 21PF-1B <sup>1,2</sup> 76.0 | <sup>2</sup> 30                 | 2,250  | 4,950                                      | 5.0    | 5.0                                       |                                  |
| 21PF-1A <sup>1</sup> or 21PF-1B <sup>1</sup> 76.0   | <sup>3</sup> 30                 | 2,282  | 5,020                                      | 5.0    | 5.0                                       | 5.0                              |
| 21PF-2 <sup>1</sup> .....                           | 76.0                            | 230    | 2,250                                      | 4,950  | 5.0                                       | 5.0                              |
| 21PF-2 <sup>1</sup> .....                           | 76.0                            | 330    | 2,282                                      | 5,020  | 5.0                                       | 5.0                              |

<sup>1</sup>For 76 cm (30 in) cylinders, the maximum H/U atomic ratio is 0.088.

<sup>2</sup>Model 30A inner cylinder (reference USEC-651).

<sup>3</sup>Model 30B inner cylinder (reference USEC-651).

(c) Continued use of an existing fissile material packaging constructed to DOT Specification 6L, 6M, or 1A2, is authorized until October 1, 2008 if it conforms in all respects to the requirements of this subchapter in effect on October 1, 2003.

[69 FR 3673, Jan. 26, 2004; 69 FR 55118, Sept. 13, 2004]

#### § 173.418 Authorized packages—pyrophoric Class 7 (radioactive) materials.

Pyrophoric Class 7 (radioactive) materials, as referenced in the §172.101 table of this subchapter, in quantities not exceeding A<sub>2</sub> per package must be transported in DOT Specification 7A packagings constructed of materials that will not react with, nor be decomposed by, the contents. Contents of the package must be—

(a) In solid form and must not be fissile unless excepted by §173.453;

(b) Contained in sealed and corrosion resistant receptacles with positive closures (friction or slip-fit covers or stoppers are not authorized);

(c) Free of water and contaminants that would increase the reactivity of the material; and

(d) Inerted to prevent self-ignition during transport by either—

(1) Mixing with large volumes of inerting materials, such as graphite, dry sand, or other suitable inerting material, or blended into a matrix of hardened concrete; or

(2) Filling the innermost receptacle with an appropriate inert gas or liquid.

(e) Pyrophoric Class 7 (radioactive) materials transported by aircraft must be packaged in Type B packages.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 68 FR 45038, July 31, 2003; 70 FR 56098, Sept. 23, 2005]

#### § 173.419 Authorized packages—oxidizing Class 7 (radioactive) materials.

(a) An oxidizing Class 7 (radioactive) material, as referenced in the §172.101 table of this subchapter, is authorized in quantities not exceeding an A<sub>2</sub> per package, in a DOT Specification 7A package provided that—

(1) The contents are:

(i) Not fissile;

(ii) Packed in inside packagings of glass, metal or compatible plastic; and

(iii) Cushioned with a material that will not react with the contents; and

(2) The outside packaging is made of wood, metal, or plastic.

(b) The package must be capable of meeting the applicable test requirements of §173.465 without leakage of contents.

(c) For shipment by air, the maximum quantity in any package may not exceed 11.3 kg (25 pounds).

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 66 FR 45380, Aug. 28, 2001]

#### § 173.420 Uranium hexafluoride (fissile, fissile excepted and non-fissile).

(a) In addition to any other applicable requirements of this subchapter, quantities greater than 0.1 kg of fissile,

## § 173.421

fissile excepted or non-fissile uranium hexafluoride must be offered for transportation as follows:

(1) Before initial filling and during periodic inspection and test, packagings must be cleaned in accordance with American National Standard N14.1 (IBR, see §171.7 of this subchapter).

(2) Packagings must be designed, fabricated, inspected, tested and marked in accordance with—

(i) American National Standard N14.1 in effect at the time the packaging was manufactured;

(ii) Specifications for Class DOT-106A multi-unit tank car tanks (see §§179.300 and 179.301 of this subchapter); or

(iii) Section VIII of the ASME Code (IBR, see §171.7 of this subchapter), provided the packaging—

(A) Was manufactured on or before June 30, 1987;

(B) Conforms to the edition of the ASME Code in effect at the time the packaging was manufactured;

(C) Is used within its original design limitations; and

(D) Has shell and head thicknesses that have not decreased below the minimum value specified in the following table:

| Packaging model                         | Minimum thickness, millimeters (inches) |
|-----------------------------------------|-----------------------------------------|
| 1S, 2S .....                            | 1.58 (0.062)                            |
| 5A, 5B, 8A .....                        | 3.17 (0.125)                            |
| 12A, 12B .....                          | 4.76 (0.187)                            |
| 30B .....                               | 7.93 (0.312)                            |
| 48A, F, X, and Y .....                  | 12.70 (0.500)                           |
| 48T, O, OM, OM Allied, HX, H, and G ... | 6.35 (0.250)                            |

(3) Each package shall be designed so that it will:

(i) withstand a hydraulic test at an internal pressure of at least 1.4 MPa (200 psi) without leakage;

(ii) withstand the test specified in §173.465(c) without loss or dispersal of the uranium hexafluoride; and

(iii) withstand the test specified in 10 CFR 71.73(c)(4) without rupture of the containment system.

(4) Uranium hexafluoride must be in solid form.

(5) The volume of solid uranium hexafluoride, except solid depleted uranium hexafluoride, at 20 °C (68 °F) may not exceed 61% of the certified volumetric capacity of the packaging. The

## 49 CFR Ch. I (10–1–08 Edition)

volume of solid depleted uranium hexafluoride at 20 °C (68 °F) may not exceed 62% of the certified volumetric capacity of the packaging.

(6) The pressure in the package at 20 °C (68 °F) must be less than 101.3 kPa (14.8 psig).

(b) Each packaging for uranium hexafluoride must be periodically inspected, tested, marked and otherwise conform with the American National Standard N14.1.

(c) Each repair to a packaging for uranium hexafluoride must be performed in accordance with the American National Standard N14.1.

(d) Non-fissile uranium hexafluoride, in quantities of less than 0.1 kg, may be shipped in packaging that meets §§173.24, 173.24a, and 173.410.

[69 FR 3675, Jan. 26, 2004; 69 FR 55118, Sept. 13, 2004]

### § 173.421 Excepted packages for limited quantities of Class 7 (radioactive) materials.

(a) A Class 7 (radioactive) material with an activity per package which does not exceed the limited quantity package limits specified in Table 4 in §173.425, and its packaging, are excepted from requirements in this subchapter for specification packaging, labeling, marking (except for the UN identification number marking requirement described in §173.422(a)), and if not a hazardous substance or hazardous waste, shipping papers, and the requirements of this subpart if:

(1) Each package meets the general design requirements of §173.410;

(2) The radiation level at any point on the external surface of the package does not exceed 0.005 mSv/hour (0.5 mrem/hour);

(3) The nonfixed (removable) radioactive surface contamination on the external surface of the package does not exceed the limits specified in §173.443(a);

(4) The outside of the inner packaging or, if there is no inner packaging, the outside of the packaging itself bears the marking “Radioactive”;

(5) The package does not contain fissile material unless excepted by §173.453.

(6) The material is otherwise prepared for shipment as specified in accordance with § 173.422.

(b) A limited quantity of Class 7 (radioactive) material that is a hazardous substance or a hazardous waste, is not subject to the provisions in § 172.203(d) or § 172.204(c)(4) of this subchapter.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 69 FR 3675, Jan. 26, 2004; 70 FR 56098, Sept. 23, 2005]

**§ 173.422 Additional requirements for excepted packages containing Class 7 (radioactive) materials.**

An excepted package of Class 7 (radioactive) material that is prepared for shipment under the provisions of § 173.421, § 173.424, § 173.426, or § 173.428 is not subject to any additional requirements of this subchapter, except for the following:

(a) The outside of each package must be marked with the four digit UN identification number for the material preceded by the letters UN, as shown in column (4) of the Hazardous Materials Table in § 172.101 of this subchapter;

(b) Sections 171.15 and 171.16 of this subchapter, pertaining to the reporting of incidents;

(c) Sections 174.750, 175.700(b), and 176.710 of this subchapter (depending on the mode of transportation), pertaining to the reporting of decontamination;

(d) The training requirements of subpart H of part 172 of this subchapter; and

(e) For materials that meet the definition of a hazardous substance or a hazardous waste, the shipping paper requirements of subpart C of part 172 of this subchapter.

[69 FR 3675, Jan. 26, 2004]

**§ 173.423 Requirements for multiple hazard limited quantity Class 7 (radioactive) materials.**

(a) Except as provided in § 173.4, when a limited quantity radioactive material meets the definition of another hazard class or division, it must be—

(1) Classed for the additional hazard;

(2) Packaged to conform with the requirements specified in § 173.421(a)(1) through (a)(5) or § 173.424(a) through (g), as appropriate; and

(3) Offered for transportation in accordance with the requirements appli-

cable to the hazard for which it is classed.

(b) A limited quantity Class 7 (radioactive) material which is classed other than Class 7 in accordance with this subchapter is excepted from the requirements of §§ 173.422(a), 172.203(d), and 172.204(c)(4) of this subchapter if the entry “Limited quantity radioactive material” appears on the shipping paper in association with the basic description.

**§ 173.424 Excepted packages for radioactive instruments and articles.**

A radioactive instrument or article and its packaging are excepted from requirements in this subchapter for specification packaging, labeling, marking (except for the UN identification number marking requirement described in § 173.422(a)), and if not a hazardous substance or hazardous waste, shipping papers and the requirements of this subpart if:

(a) Each package meets the general design requirements of § 173.410;

(b) The activity of the instrument or article does not exceed the relevant limit listed in Table 4 in § 173.425;

(c) The total activity per package does not exceed the relevant limit listed in Table 4 in § 173.425;

(d) The radiation level at 10 cm (4 in) from any point on the external surface of any unpackaged instrument or article does not exceed 0.1 mSv/hour (10 mrem/hour);

(e) The active material is completely enclosed by non-active components (a device performing the sole function of containing radioactive material shall not be considered to be an instrument or manufactured article);

(f) The radiation level at any point on the external surface of a package bearing the article or instrument does not exceed 0.005 mSv/hour (0.5 mrem/hour), or, for exclusive use domestic shipments, 0.02 mSv/hour (2 mrem/hour);

(g) The nonfixed (removable) radioactive surface contamination on the external surface of the package does not exceed the limits specified in § 173.443(a);

(h) Except as provided in § 173.426, the package does not contain more than 15 g of uranium-235; and



§ 173.425

49 CFR Ch. I (10–1–08 Edition)

(i) The package is otherwise prepared for shipment as specified in § 173.422.

[69 FR 3675, Jan. 26, 2004]

§ 173.425 Table of activity limits—excepted quantities and articles.

The limits applicable to instruments, articles, and limited quantities subject to exceptions under §§ 173.421 and 173.424 are set forth in table 4 as follows:

TABLE 4—ACTIVITY LIMITS FOR LIMITED QUANTITIES, INSTRUMENTS, AND ARTICLES

| Nature of contents                                   | Instruments and articles                           |                             | Limited quantity package limits <sup>1</sup> |
|------------------------------------------------------|----------------------------------------------------|-----------------------------|----------------------------------------------|
|                                                      | Limits for each instrument or article <sup>1</sup> | Package limits <sup>1</sup> |                                              |
| Solids:                                              |                                                    |                             |                                              |
| Special form .....                                   | $10^{-2} A_1$                                      | $A_1$                       | $10^{-3} A_1$                                |
| Normal form .....                                    | $10^{-2} A_2$                                      | $A_2$                       | $10^{-3} A_2$                                |
| Liquids:                                             |                                                    |                             |                                              |
| Tritiated water:                                     |                                                    |                             |                                              |
| <0.0037 TBq/L (0.1 Ci/L) .....                       |                                                    |                             | 37 TBq (1,000 Ci)                            |
| 0.0037 TBq to 0.037 TBq/L (0.1 Ci to 1.0 Ci/L) ..... |                                                    |                             | 3.7 TBq (100 Ci)                             |
| >0.037 TBq/L (1.0 Ci/L) .....                        |                                                    |                             | 0.037 TBq (1.0 Ci)                           |
| Other Liquids .....                                  | $10^{-3} A_2$                                      | $10^{-1} A_2$               | $10^{-4} A_2$                                |
| Gases:                                               |                                                    |                             |                                              |
| Tritium <sup>2</sup> .....                           | $2 \times 10^{-2} A_2$                             | $2 \times 10^{-1} A_2$      | $2 \times 10^{-2} A_2$                       |
| Special form .....                                   | $10^{-3} A_1$                                      | $10^{-2} A_1$               | $10^{-3} A_1$                                |
| Normal form .....                                    | $10^{-3} A_2$                                      | $10^{-2} A_2$               | $10^{-3} A_2$                                |

<sup>1</sup> For mixtures of radionuclides see § 173.433(d).

<sup>2</sup> These values also apply to tritium in activated luminous paint and tritium adsorbed on solid carriers.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by Amdt. 173–244, 61 FR 20751, May 8, 1996; 63 FR 52849, Oct. 1, 1998; 65 FR 58630, Sept. 29, 2000; 66 FR 45383, Aug. 28, 2001; 69 FR 3676, Jan. 26, 2004]

§ 173.426 Excepted packages for articles containing natural uranium or thorium.

A manufactured article in which the sole Class 7 (radioactive) material content is natural uranium, unirradiated depleted uranium or natural thorium, and its packaging, are excepted from the requirements in this subchapter for specification packaging, labeling, marking (except for the UN identification number marking requirement described in § 173.422(a)), and if not a hazardous substance or hazardous waste, shipping papers and the requirements of this subpart if:

(a) Each package meets the general design requirements of § 173.410;

(b) The outer surface of the uranium or thorium is enclosed in an inactive sheath made of metal or other durable protective material;

(c) The conditions specified in § 173.421(a) (2), (3) and (4) are met; and

(d) The article is otherwise prepared for shipment as specified in § 173.422.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by Amdt. 173–244, 61 FR 20752, May 8, 1996; 69 FR 3676, Jan. 26, 2004]

§ 173.427 Transport requirements for low specific activity (LSA) Class 7 (radioactive) materials and surface contaminated objects (SCO).

(a) In addition to other applicable requirements specified in this subchapter, LSA materials and SCO, unless excepted by paragraph (c) or (d) of this section, must be packaged in accordance with paragraph (b) of this section and must be transported in accordance with the following conditions:

(1) The external dose rate may not exceed an external radiation level of 10 mSv/h (1 rem/h) at 3 m from the unshielded material;

(2) The quantity of LSA and SCO material in any single conveyance may not exceed the limits specified in Table 5;

(3) LSA material and SCO that are or contain fissile material must conform

to the applicable requirements of § 173.453;

(4) Packaged and unpackaged Class 7 (radioactive) materials must conform to the contamination control limits specified in § 173.443;

(5) External radiation levels may not exceed those specified in § 173.441; and

(6) For LSA material and SCO consigned as exclusive use:

(i) Shipments shall be loaded by the consignor and unloaded by the consignee from the conveyance or freight container in which originally loaded;

(ii) There may be no loose radioactive material in the conveyance; however, when the conveyance is the packaging, there may not be any leakage of radioactive material from the conveyance;

(iii) Packaged and unpackaged Class 7 (radioactive) materials must be braced so as to prevent shifting of loading under conditions normally incident to transportation;

(iv) Specific instructions for maintenance of exclusive use shipment controls shall be provided by the offeror to the carrier. Such instructions must be included with the shipping paper information;

(v) Except for shipments of unconcentrated uranium or thorium ores, the transport vehicle must be placarded in accordance with subpart F of part 172 of this subchapter;

(vi) For domestic transportation only, packaged and unpackaged Class 7 (radioactive) materials containing less than an A<sub>2</sub> quantity are excepted from the marking and labeling requirements of this subchapter. However, the exterior of each package or unpackaged Class 7 (radioactive) materials must be stenciled or otherwise marked "RADIOACTIVE—LSA" or "RADIOACTIVE—SCO", as appropriate, and packages or unpackaged Class 7 (radioactive) materials that contain a hazardous substance must be stenciled or otherwise marked with the letters "RQ" in association with the description in this paragraph (a)(6)(vi); and

(vii) Transportation by aircraft is prohibited except when transported in an industrial package in accordance with Table 6 of this section, or in an authorized Type A or Type B package.

(b) Except as provided in paragraph (c) of this section, LSA material and SCO must be packaged as follows:

(1) In an industrial package (IP-1, IP-2 or IP-3; § 173.411), subject to the limitations of Table 6;

(2) In a DOT Specification 7A (§ 178.350 of this subchapter) Type A package;

(3) In any Type B(U) or B(M) packaging authorized pursuant to § 173.416;

(4) In a packaging which meets the requirements of §§ 173.24, 173.24a, and 173.410, but only for domestic transportation of an exclusive use shipment that is less than an A<sub>2</sub> quantity.

(5) For exclusive use transport of liquid LSA-I only, in either:

(i) Specification 103CW, 111A60W7 (§§ 173.31, and 179.201-1 to 179.201-11 of this subchapter) tank cars. Bottom openings in tanks are prohibited; or

(ii) Specification MC 310, MC 311, MC 312, MC 331 or DOT 412 (§ 178.348 or § 178.337 of this subchapter) cargo tank motor vehicles. Bottom outlets are not authorized. Trailer-on-flat-car service is not authorized.

(c) LSA material and SCO in groups LSA-I and SCO-I may be transported unpackaged under the following conditions:

(1) All unpackaged material, other than ores containing only naturally occurring radionuclides, shall be transported in such a manner that under normal conditions of transport there will be no escape of the radioactive contents from the conveyance nor will there be any loss of shielding;

(2) Each conveyance must be under exclusive use, except when only transporting SCO-I on which the contamination on the accessible and the inaccessible surfaces is not greater than 4.0 Bq/cm<sup>2</sup> for beta and gamma emitters and low toxicity alpha emitters and 0.4 Bq/cm<sup>2</sup> for all other alpha emitters; and

(3) For SCO-I where it is suspected that non-fixed contamination exists on inaccessible surfaces in excess of the values specified in paragraph (c)(2) of this section, measures shall be taken to ensure that the radioactive material is not released into the conveyance or to the environment.

(d) LSA and SCO that exceed the packaging limits in this section must

## § 173.428

be packaged in accordance with 10 CFR part 71.

(e) Tables 5 and 6 are as follows:

TABLE 5—CONVEYANCE ACTIVITY LIMITS FOR LSA MATERIAL AND SCO

| Nature of material                                                   | Activity limit for conveyances |
|----------------------------------------------------------------------|--------------------------------|
| 1. LSA-I .....                                                       | No limit.                      |
| 2. LSA-II and LSA-III; Non-combustible solids ....                   | No limit.                      |
| 3. LSA-II and LSA-III; Combustible solids and all liquids and gases. | 100 A <sub>2</sub>             |
| 4. SCO .....                                                         | 100 A <sub>2</sub>             |

TABLE 6—INDUSTRIAL PACKAGE INTEGRITY REQUIREMENTS FOR LSA MATERIAL AND SCO

| Contents             | Industrial packaging type |                            |
|----------------------|---------------------------|----------------------------|
|                      | Exclusive use shipment    | Non exclusive use shipment |
| 1. LSA-I:            |                           |                            |
| Solid .....          | IP-1 ...                  | IP-1                       |
| Liquid .....         | IP-1 ...                  | IP-2                       |
| 2. LSA-II:           |                           |                            |
| Solid .....          | IP-2 ...                  | IP-2                       |
| Liquid and gas ..... | IP-2 ...                  | IP-3                       |
| 3. LSA-III .....     | IP-2 ...                  | IP-3                       |
| 4. SCO-I .....       | IP-1 ...                  | IP-1                       |
| 5. SCO-II .....      | IP-2 ...                  | IP-2                       |

[69 FR 3676, Jan. 26, 2004; 69 FR 55118, Sept. 13, 2004; 69 FR 58843, Oct. 1, 2004; 70 FR 56098, Sept. 23, 2005]

## § 173.428 Empty Class 7 (radioactive) materials packaging.

A packaging which previously contained Class 7 (radioactive) materials and has been emptied of contents as far as practical, is excepted from the shipping paper and marking (except for the UN identification number marking requirement described in § 173.422(a)) requirements of this subchapter, provided that—

(a) The packaging meets the requirements of § 173.421(a) (2), (3), and (5) of this subpart;

(b) The packaging is in unimpaired condition and is securely closed so that there will be no leakage of Class 7 (radioactive) material under conditions normally incident to transportation;

(c) The outer surface of any uranium or thorium in its structure is covered

## 49 CFR Ch. I (10–1–08 Edition)

with an inactive sheath made of metal or some other substantial material;

(d) Internal contamination does not exceed 100 times the limits in § 173.443(a);

(e) Any labels previously applied in conformance with subpart E of part 172 of this subchapter are removed, obliterated, or covered and the “Empty” label prescribed in § 172.450 of this subchapter is affixed to the packaging; and

(f) The packaging is prepared for shipment as specified in § 173.422.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by Amdt. 173–244, 61 FR 20752, May 8, 1996; 64 FR 51919, Sept. 27, 1999; 69 FR 3677, Jan. 26, 2004]

## § 173.431 Activity limits for Type A and Type B packages.

(a) Except for LSA material and SCO, a Type A package may not contain a quantity of Class 7 (radioactive) materials greater than A<sub>1</sub> for special form Class 7 (radioactive) material or A<sub>2</sub> for normal form Class 7 (radioactive) material as listed in § 173.435, or, for Class 7 (radioactive) materials not listed in § 173.435, as determined in accordance with § 173.433.

(b) The limits on activity contained in a Type B(U) or Type B(M) package are those prescribed in §§ 173.416 and 173.417, or in the applicable approval certificate under §§ 173.471, 173.472 or 173.473.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended at 69 FR 3677, Jan. 26, 2004]

## § 173.433 Requirements for determining basic radionuclide values, and for the listing of radionuclides on shipping papers and labels.

(a) For individual radionuclides listed in the table in § 173.435 and § 173.436:

(1) A<sub>1</sub> and A<sub>2</sub> values are given in the table in § 173.435; and

(2) Activity concentration exemption values and consignment activity exemption values are given in the table in § 173.436.

(b) For individual radionuclides which are not listed in the tables in § 173.435 or § 173.436:

(1) the radionuclide values in Tables 7 or 8 of this section may be used; or

(2) other basic radionuclide values may be used provided they are first approved by the Associate Administrator

or, for international transport, multilateral approval is obtained from the pertinent Competent Authorities.

(c) In calculating  $A_1$  or  $A_2$  values for a radionuclide not listed in the table in § 173.435:

(1) Where the chemical form of each radionuclide is known, it is permissible to use the  $A_2$  value related to its solubility class as recommended by the International Commission on Radiological Protection, if the chemical forms under both normal and accident conditions of transport are taken into consideration.

(2) A single radioactive decay chain in which the radionuclides are present in their naturally-occurring proportions, and in which no daughter nuclide has a half life either longer than 10 days or longer than that of the parent nuclide, will be considered as a single radionuclide, and the activity to be taken into account and the  $A_1$  or  $A_2$  value to be applied will be those corresponding to the parent nuclide of that chain. Otherwise, the parent and daughter nuclides will be considered as a mixture of different nuclides.

(d) Mixtures of radionuclides whose identities and respective activities are known must conform to the following conditions:

(1) For special form Class 7 (radioactive) material, the activity which may be transported in a Type A package must satisfy:

$$\sum_i \frac{B(i)}{A_1(i)} \leq 1$$

Where:

$B(i)$  is the activity of radionuclide  $i$  in special form; and

$A_1(i)$  is the  $A_1$  value for radionuclide  $i$ .

(2) For normal form Class 7 (radioactive) material, the activity which may be transported in a Type A package must satisfy:

$$\sum_j \frac{C(j)}{A_2(j)} \leq 1$$

Where:

$C(j)$  is the activity of radionuclide  $j$  in normal form; and

$A_2(j)$  is the  $A_2$  value for radionuclide  $j$ .

(3) If the package contains both special and normal form Class 7 (radioactive) material, the activity which may be transported in a Type A package must satisfy:

$$\sum_i \frac{B(i)}{A_1(i)} + \sum_j \frac{C(j)}{A_2(j)} \leq 1$$

Where:

The symbols are defined as in paragraphs (d)(2) and (d)(3) of this section.

(4) Alternatively, the  $A_1$  value for a mixture of special form material may be determined as follows:

$$A_1 \text{ for mixture} = \frac{1}{\sum_i \frac{f(i)}{A_1(i)}}$$

Where:

$f(i)$  is the fraction of activity for radionuclide  $i$  in the mixture; and

$A_1(i)$  is the appropriate  $A_1$  value for radionuclide  $i$ .

(5) Alternatively, the  $A_2$  value for mixtures of normal form material may be determined as follows:

$$A_2 \text{ for mixture} = \frac{1}{\sum_i \frac{f(i)}{A_2(i)}}$$

Where:

$f(i)$  is the fraction of activity for normal form radionuclide  $i$  in the mixture; and

$A_2(i)$  is the appropriate  $A_2$  value for radionuclide  $i$ .

(6) The exempt activity concentration for mixtures of nuclides may be determined as follows:

$$\text{Exempt activity concentration limit for mixture} = \frac{1}{\sum_i \frac{f(i)}{[A](i)}}$$

Where:

f(i) is the fraction of activity concentration of nuclide i in the mixture; and [A](i) is the activity concentration for exempt material containing nuclide i.

(7) The activity limit for an exempt consignment for mixtures of nuclides may be determined as follows:

$$\text{Exempt consignment activity limit for mixture} = \frac{1}{\sum_i \frac{f(i)}{A(i)}}$$

Where:

f(i) is the fraction of activity of nuclide i in the mixture; and

A(i) is the activity limit for exempt consignments for nuclide i.

(e) When the identity of each nuclide is known but the individual activities of some of the radionuclides are not known, the radionuclides may be grouped and the lowest A<sub>1</sub> or A<sub>2</sub> value, as appropriate, for the radionuclides in each group may be used in applying the formulas in paragraphs (d)(1) through (d)(5) of this section. Groups may be based on the total alpha activity and the total beta/gamma activity when these are known, using the lowest A<sub>1</sub> or A<sub>2</sub> values for the alpha emitters or beta/gamma emitters, respectively.

(f) When the identity of each nuclide is known but the individual activities of some of the radionuclides are not known, the radionuclides may be grouped and the lowest [A] (activity concentration for exempt material) or A (activity limit for exempt consignment) value, as appropriate, for the radionuclides in each group may be used in applying the formulas in para-

graphs (d)(6) and (d)(7) of this section. Groups may be based on the total alpha activity and the total beta/gamma activity when these are known, using the lowest [A] or A values for the alpha emitters or beta/gamma emitters, respectively.

(g) *Shipping papers and labeling.* For mixtures of radionuclides, the radionuclides (n) that must be shown on shipping papers and labels in accordance with §§172.203 and 172.403 of this subchapter, respectively, must be determined on the basis of the following formula:

$$\sum_{i=1}^n \frac{a_{(i)}}{A_{(i)}} \geq 0.95 \sum_{i=1}^{n+m} \frac{a_{(i)}}{A_{(i)}}$$

Where:

n + m represents all the radionuclides in the mixture;

m are the radionuclides that do not need to be considered;

a<sub>(i)</sub> is the activity of radionuclide i in the mixture; and

A<sub>(i)</sub> is the A<sub>1</sub> or A<sub>2</sub> value, as appropriate for radionuclide i.

(h) Tables 7 and 8 are as follows:

TABLE 7—GENERAL VALUES FOR A<sub>1</sub> AND A<sub>2</sub>

| Radioactive contents                                                  | A <sub>1</sub>       |                        | A <sub>2</sub>       |                        |
|-----------------------------------------------------------------------|----------------------|------------------------|----------------------|------------------------|
|                                                                       | (TBq)                | (Ci)                   | (TBq)                | (Ci)                   |
| 1. Only beta or gamma emitting nuclides are known to be present ..... | 1 × 10 <sup>-1</sup> | 2.7 × 10 <sup>0</sup>  | 2 × 10 <sup>-2</sup> | 5.4 × 10 <sup>-1</sup> |
| 2. Only alpha emitting nuclides are known to be present ....          | 2 × 10 <sup>-1</sup> | 5.4 × 10 <sup>0</sup>  | 9 × 10 <sup>-5</sup> | 2.4 × 10 <sup>-3</sup> |
| 3. No relevant data are available .....                               | 1 × 10 <sup>-3</sup> | 2.7 × 10 <sup>-2</sup> | 9 × 10 <sup>-5</sup> | 2.4 × 10 <sup>-3</sup> |

TABLE 8—GENERAL EXEMPTION VALUES

| Radioactive contents                                                  | Activity concentration for exempt material |                         | Activity limits for exempt consignments |                        |
|-----------------------------------------------------------------------|--------------------------------------------|-------------------------|-----------------------------------------|------------------------|
|                                                                       | (Bq/g)                                     | (Ci/g)                  | (Bq)                                    | (Ci)                   |
| 1. Only beta or gamma emitting nuclides are known to be present ..... | 1 × 10 <sup>1</sup>                        | 2.7 × 10 <sup>-10</sup> | 1 × 10 <sup>4</sup>                     | 2.7 × 10 <sup>-7</sup> |
| 2. Only alpha emitting nuclides are known to be present ....          | 1 × 10 <sup>-1</sup>                       | 2.7 × 10 <sup>-12</sup> | 1 × 10 <sup>3</sup>                     | 2.7 × 10 <sup>-8</sup> |

TABLE 8—GENERAL EXEMPTION VALUES—Continued

| Radioactive contents                    | Activity concentration for exempt material |                       | Activity limits for exempt consignments |                      |
|-----------------------------------------|--------------------------------------------|-----------------------|-----------------------------------------|----------------------|
|                                         | (Bq/g)                                     | (Ci/g)                | (Bq)                                    | (Ci)                 |
| 3. No relevant data are available ..... | $1 \times 10^{-1}$                         | $2.7 \times 10^{-12}$ | $1 \times 10^3$                         | $2.7 \times 10^{-8}$ |

[69 FR 3677, Jan. 26, 2004; 69 FR 55119, Sept. 13, 2004]

**§ 173.434 Activity-mass relationships for uranium and natural thorium.**

The table of activity-mass relationships for uranium and natural thorium are as follows:

| Thorium and uranium enrichment <sup>1</sup> (Wt% <sup>235</sup> U present) | Specific activity    |                   |                      |                   |
|----------------------------------------------------------------------------|----------------------|-------------------|----------------------|-------------------|
|                                                                            | TBq/gram             | Grams/Tbq         | Ci/gram              | Grams/Ci          |
| 0.45 (depleted) .....                                                      | $1.9 \times 10^{-8}$ | $5.4 \times 10^7$ | $5.0 \times 10^{-7}$ | $2.0 \times 10^6$ |
| 0.72 (natural) .....                                                       | $2.6 \times 10^{-8}$ | $3.8 \times 10^7$ | $7.1 \times 10^{-7}$ | $1.4 \times 10^6$ |
| 1.0 .....                                                                  | $2.8 \times 10^{-8}$ | $3.6 \times 10^7$ | $7.6 \times 10^{-7}$ | $1.3 \times 10^6$ |
| 1.5 .....                                                                  | $3.7 \times 10^{-8}$ | $2.7 \times 10^7$ | $1.0 \times 10^{-6}$ | $1.0 \times 10^6$ |
| 5.0 .....                                                                  | $1.0 \times 10^{-7}$ | $1.0 \times 10^7$ | $2.7 \times 10^{-6}$ | $3.7 \times 10^5$ |
| 10.0 .....                                                                 | $1.8 \times 10^{-7}$ | $5.6 \times 10^6$ | $4.8 \times 10^{-6}$ | $2.1 \times 10^5$ |
| 20.0 .....                                                                 | $3.7 \times 10^{-7}$ | $2.7 \times 10^6$ | $1.0 \times 10^{-5}$ | $1.0 \times 10^5$ |
| 35.0 .....                                                                 | $7.4 \times 10^{-7}$ | $1.4 \times 10^6$ | $2.0 \times 10^{-5}$ | $5.0 \times 10^4$ |
| 50.0 .....                                                                 | $9.3 \times 10^{-7}$ | $1.1 \times 10^6$ | $2.5 \times 10^{-5}$ | $4.0 \times 10^4$ |
| 90.0 .....                                                                 | $2.1 \times 10^{-6}$ | $4.7 \times 10^5$ | $5.8 \times 10^{-5}$ | $1.7 \times 10^4$ |
| 93.0 .....                                                                 | $2.6 \times 10^{-6}$ | $3.9 \times 10^5$ | $7.0 \times 10^{-5}$ | $1.4 \times 10^4$ |
| 95.0 .....                                                                 | $3.4 \times 10^{-6}$ | $3.0 \times 10^5$ | $9.1 \times 10^{-5}$ | $1.1 \times 10^4$ |
| Natural thorium .....                                                      | $8.1 \times 10^{-9}$ | $1.2 \times 10^8$ | $2.2 \times 10^{-7}$ | $4.6 \times 10^6$ |

<sup>1</sup> The figures for uranium include representative values for the activity of uranium-234 which is concentrated during the enrichment process. The activity for thorium includes the equilibrium concentration of thorium-228.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by 63 FR 52849, Oct. 1, 1998]

**§ 173.435 Table of A<sub>1</sub> and A<sub>2</sub> values for radionuclides.**

The table of A<sub>1</sub> and A<sub>2</sub> values for radionuclides is as follows:

| Symbol of radionuclide | Element and atomic number | A <sub>1</sub> (TBq) | A <sub>1</sub> (Ci) <sup>b</sup> | A <sub>2</sub> (TBq) | A <sub>2</sub> (Ci) <sup>b</sup> | Specific activity    |                      |
|------------------------|---------------------------|----------------------|----------------------------------|----------------------|----------------------------------|----------------------|----------------------|
|                        |                           |                      |                                  |                      |                                  | (TBq/g)              | (Ci/g)               |
| Ac-225 (a) .....       | Actinium (89) .....       | $8.0 \times 10^{-1}$ | $2.2 \times 10^1$                | $6.0 \times 10^{-3}$ | $1.6 \times 10^{-1}$             | $2.1 \times 10^3$    | $5.8 \times 10^4$    |
| Ac-227 (a) .....       | .....                     | $9.0 \times 10^{-1}$ | $2.4 \times 10^1$                | $9.0 \times 10^{-5}$ | $2.4 \times 10^{-3}$             | 2.7                  | $7.2 \times 10^1$    |
| Ac-228 .....           | .....                     | $6.0 \times 10^{-1}$ | $1.6 \times 10^1$                | $5.0 \times 10^{-1}$ | $1.4 \times 10^1$                | $8.4 \times 10^4$    | $2.2 \times 10^6$    |
| Ag-105 .....           | Silver (47) .....         | 2.0                  | $5.4 \times 10^1$                | 2.0                  | $5.4 \times 10^1$                | $1.1 \times 10^3$    | $3.0 \times 10^4$    |
| Ag-108m (a) .....      | .....                     | $7.0 \times 10^{-1}$ | $1.9 \times 10^1$                | $7.0 \times 10^{-1}$ | $1.9 \times 10^1$                | $9.7 \times 10^{-1}$ | $2.6 \times 10^1$    |
| Ag-110m (a) .....      | .....                     | $4.0 \times 10^{-1}$ | $1.1 \times 10^1$                | $4.0 \times 10^{-1}$ | $1.1 \times 10^1$                | $1.8 \times 10^2$    | $4.7 \times 10^3$    |
| Ag-111 .....           | .....                     | 2.0                  | $5.4 \times 10^1$                | $6.0 \times 10^{-1}$ | $1.6 \times 10^1$                | $5.8 \times 10^3$    | $1.6 \times 10^5$    |
| Al-26 .....            | Aluminum (13) .....       | $1.0 \times 10^{-1}$ | 2.7                              | $1.0 \times 10^{-1}$ | 2.7                              | $7.0 \times 10^{-4}$ | $1.9 \times 10^{-2}$ |
| Am-241 .....           | Americium (95) .....      | $1.0 \times 10^1$    | $2.7 \times 10^2$                | $1.0 \times 10^{-3}$ | $2.7 \times 10^{-2}$             | $1.3 \times 10^{-1}$ | 3.4                  |
| Am-242m (a) .....      | .....                     | $1.0 \times 10^1$    | $2.7 \times 10^2$                | $1.0 \times 10^{-3}$ | $2.7 \times 10^{-2}$             | $3.6 \times 10^{-1}$ | $1.0 \times 10^1$    |
| Am-243 (a) .....       | .....                     | 5.0                  | $1.4 \times 10^2$                | $1.0 \times 10^{-3}$ | $2.7 \times 10^{-2}$             | $7.4 \times 10^{-3}$ | $2.0 \times 10^{-1}$ |
| Ar-37 .....            | Argon (18) .....          | $4.0 \times 10^1$    | $1.1 \times 10^3$                | $4.0 \times 10^1$    | $1.1 \times 10^3$                | $3.7 \times 10^3$    | $9.9 \times 10^4$    |
| Ar-39 .....            | .....                     | $4.0 \times 10^1$    | $1.1 \times 10^3$                | $2.0 \times 10^1$    | $5.4 \times 10^2$                | 1.3                  | $3.4 \times 10^1$    |
| Ar-41 .....            | .....                     | $3.0 \times 10^{-1}$ | 8.1                              | $3.0 \times 10^{-1}$ | 8.1                              | $1.5 \times 10^6$    | $4.2 \times 10^7$    |
| As-72 .....            | Arsenic (33) .....        | $3.0 \times 10^{-1}$ | 8.1                              | $3.0 \times 10^{-1}$ | 8.1                              | $6.2 \times 10^4$    | $1.7 \times 10^6$    |
| As-73 .....            | .....                     | $4.0 \times 10^1$    | $1.1 \times 10^3$                | $4.0 \times 10^1$    | $1.1 \times 10^3$                | $8.2 \times 10^2$    | $2.2 \times 10^4$    |
| As-74 .....            | .....                     | 1.0                  | $2.7 \times 10^1$                | $9.0 \times 10^{-1}$ | $2.4 \times 10^1$                | $3.7 \times 10^3$    | $9.9 \times 10^4$    |
| As-76 .....            | .....                     | $3.0 \times 10^{-1}$ | 8.1                              | $3.0 \times 10^{-1}$ | 8.1                              | $5.8 \times 10^4$    | $1.6 \times 10^6$    |
| As-77 .....            | .....                     | $2.0 \times 10^1$    | $5.4 \times 10^2$                | $7.0 \times 10^{-1}$ | $1.9 \times 10^1$                | $3.9 \times 10^4$    | $1.0 \times 10^6$    |
| At-211 (a) .....       | Astatine (85) .....       | $2.0 \times 10^1$    | $5.4 \times 10^2$                | $5.0 \times 10^{-1}$ | $1.4 \times 10^1$                | $7.6 \times 10^4$    | $2.1 \times 10^6$    |
| Au-193 .....           | Gold (79) .....           | 7.0                  | $1.9 \times 10^2$                | 2.0                  | $5.4 \times 10^1$                | $3.4 \times 10^4$    | $9.2 \times 10^5$    |
| Au-194 .....           | .....                     | 1.0                  | $2.7 \times 10^1$                | 1.0                  | $2.7 \times 10^1$                | $1.5 \times 10^4$    | $4.1 \times 10^5$    |
| Au-195 .....           | .....                     | $1.0 \times 10^1$    | $2.7 \times 10^2$                | 6.0                  | $1.6 \times 10^2$                | $1.4 \times 10^2$    | $3.7 \times 10^3$    |
| Au-198 .....           | .....                     | 1.0                  | $2.7 \times 10^1$                | $6.0 \times 10^{-1}$ | $1.6 \times 10^1$                | $9.0 \times 10^3$    | $2.4 \times 10^5$    |
| Au-199 .....           | .....                     | $1.0 \times 10^1$    | $2.7 \times 10^2$                | $6.0 \times 10^{-1}$ | $1.6 \times 10^1$                | $7.7 \times 10^3$    | $2.1 \times 10^5$    |
| Ba-131 (a) .....       | Barium (56) .....         | 2.0                  | $5.4 \times 10^1$                | 2.0                  | $5.4 \times 10^1$                | $3.1 \times 10^3$    | $8.4 \times 10^4$    |
| Ba-133 .....           | .....                     | 3.0                  | $8.1 \times 10^1$                | 3.0                  | $8.1 \times 10^1$                | 9.4                  | $2.6 \times 10^2$    |
| Ba-133m .....          | .....                     | $2.0 \times 10^1$    | $5.4 \times 10^2$                | $6.0 \times 10^{-1}$ | $1.6 \times 10^1$                | $2.2 \times 10^4$    | $6.1 \times 10^5$    |
| Ba-140 (a) .....       | .....                     | $5.0 \times 10^{-1}$ | $1.4 \times 10^1$                | $3.0 \times 10^{-1}$ | 8.1                              | $2.7 \times 10^3$    | $7.3 \times 10^4$    |

| Symbol of radionuclide | Element and atomic number | A <sub>1</sub> (TBq) | A <sub>1</sub> (Ci) <sup>b</sup> | A <sub>2</sub> (TBq) | A <sub>2</sub> (Ci) <sup>b</sup> | Specific activity    |                      |
|------------------------|---------------------------|----------------------|----------------------------------|----------------------|----------------------------------|----------------------|----------------------|
|                        |                           |                      |                                  |                      |                                  | (TBq/g)              | (Ci/g)               |
| Be-7                   | Beryllium (4)             | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 1.3×10 <sup>4</sup>  | 3.5×10 <sup>5</sup>  |
| Be-10                  |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 8.3×10 <sup>-4</sup> | 2.2×10 <sup>-2</sup> |
| Bi-205                 | Bismuth (83)              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 1.5×10 <sup>3</sup>  | 4.2×10 <sup>4</sup>  |
| Bi-206                 |                           | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 3.8×10 <sup>3</sup>  | 1.0×10 <sup>5</sup>  |
| Bi-207                 |                           | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 1.9                  | 5.2×10 <sup>1</sup>  |
| Bi-210                 |                           | 1.0                  | 2.7×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 4.6×10 <sup>3</sup>  | 1.2×10 <sup>5</sup>  |
| Bi-210m (a)            |                           | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 2.1×10 <sup>-5</sup> | 5.7×10 <sup>-4</sup> |
| Bi-212 (a)             |                           | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 5.4×10 <sup>5</sup>  | 1.5×10 <sup>7</sup>  |
| Bk-247                 | Berkelium (97)            | 8.0                  | 2.2×10 <sup>2</sup>              | 8.0×10 <sup>-4</sup> | 2.2×10 <sup>-2</sup>             | 3.8×10 <sup>-2</sup> | 1.0                  |
| Bk-249 (a)             |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0×10 <sup>-1</sup> | 8.1                              | 6.1×10 <sup>1</sup>  | 1.6×10 <sup>3</sup>  |
| Br-76                  | Bromine (35)              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 9.4×10 <sup>4</sup>  | 2.5×10 <sup>6</sup>  |
| Br-77                  |                           | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 2.6×10 <sup>4</sup>  | 7.1×10 <sup>5</sup>  |
| Br-82                  |                           | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>4</sup>  | 1.1×10 <sup>6</sup>  |
| C-11                   | Carbon (6)                | 1.0                  | 2.7×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.1×10 <sup>7</sup>  | 8.4×10 <sup>8</sup>  |
| C-14                   |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 1.6×10 <sup>-1</sup> | 4.5                  |
| Ca-41                  | Calcium (20)              | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 3.1×10 <sup>-3</sup> | 8.5×10 <sup>-2</sup> |
| Ca-45                  |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 6.6×10 <sup>2</sup>  | 1.8×10 <sup>4</sup>  |
| Ca-47 (a)              |                           | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0×10 <sup>-1</sup> | 8.1                              | 2.3×10 <sup>4</sup>  | 6.1×10 <sup>5</sup>  |
| Cd-109                 | Cadmium (48)              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 9.6×10 <sup>1</sup>  | 2.6×10 <sup>3</sup>  |
| Cd-113m                |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 8.3                  | 2.2×10 <sup>2</sup>  |
| Cd-115 (a)             |                           | 3.0                  | 8.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.9×10 <sup>4</sup>  | 5.1×10 <sup>5</sup>  |
| Cd-115m                |                           | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 9.4×10 <sup>2</sup>  | 2.5×10 <sup>4</sup>  |
| Ce-139                 | Cerium (58)               | 7.0                  | 1.9×10 <sup>2</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 2.5×10 <sup>2</sup>  | 6.8×10 <sup>3</sup>  |
| Ce-141                 |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.1×10 <sup>3</sup>  | 2.8×10 <sup>4</sup>  |
| Ce-143                 |                           | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.5×10 <sup>4</sup>  | 6.6×10 <sup>5</sup>  |
| Ce-144 (a)             |                           | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 1.2×10 <sup>2</sup>  | 3.2×10 <sup>3</sup>  |
| Cf-248                 | Californium (98)          | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 6.0×10 <sup>-3</sup> | 1.6×10 <sup>-1</sup>             | 5.8×10 <sup>1</sup>  | 1.6×10 <sup>3</sup>  |
| Cf-249                 |                           | 3.0                  | 8.1×10 <sup>1</sup>              | 8.0×10 <sup>-4</sup> | 2.2×10 <sup>-2</sup>             | 1.5×10 <sup>-1</sup> | 4.1                  |
| Cf-250                 |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>-3</sup> | 5.4×10 <sup>-2</sup>             | 4.0                  | 1.1×10 <sup>2</sup>  |
| Cf-251                 |                           | 7.0                  | 1.9×10 <sup>2</sup>              | 7.0×10 <sup>-4</sup> | 1.9×10 <sup>-2</sup>             | 5.9×10 <sup>-2</sup> | 1.6                  |
| Cf-252 (h)             |                           | 5.0×10 <sup>-2</sup> | 1.4                              | 3.0×10 <sup>-3</sup> | 8.1×10 <sup>-2</sup>             | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>  |
| Cf-253 (a)             |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>-2</sup> | 1.1                              | 1.1×10 <sup>3</sup>  | 2.9×10 <sup>4</sup>  |
| Cf-254                 |                           | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 3.1×10 <sup>2</sup>  | 8.5×10 <sup>3</sup>  |
| Cl-36                  | Chlorine (17)             | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.2×10 <sup>-3</sup> | 3.3×10 <sup>-2</sup> |
| Cl-38                  |                           | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 4.9×10 <sup>6</sup>  | 1.3×10 <sup>8</sup>  |
| Cm-240                 | Curium (96)               | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 7.5×10 <sup>2</sup>  | 2.0×10 <sup>4</sup>  |
| Cm-241                 |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 6.1×10 <sup>2</sup>  | 1.7×10 <sup>4</sup>  |
| Cm-242                 |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0×10 <sup>-2</sup> | 2.7×10 <sup>-1</sup>             | 1.2×10 <sup>2</sup>  | 3.3×10 <sup>3</sup>  |
| Cm-243                 |                           | 9.0                  | 2.4×10 <sup>2</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 1.9                  | 5.2×10 <sup>1</sup>  |
| Cm-244                 |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>-3</sup> | 5.4×10 <sup>-2</sup>             | 3.0                  | 8.1×10 <sup>1</sup>  |
| Cm-245                 |                           | 9.0                  | 2.4×10 <sup>2</sup>              | 9.0×10 <sup>-4</sup> | 2.4×10 <sup>-2</sup>             | 6.4×10 <sup>-3</sup> | 1.7×10 <sup>-1</sup> |
| Cm-246                 |                           | 9.0                  | 2.4×10 <sup>2</sup>              | 9.0×10 <sup>-4</sup> | 2.4×10 <sup>-2</sup>             | 1.1×10 <sup>-2</sup> | 3.1×10 <sup>-1</sup> |
| Cm-247 (a)             |                           | 3.0                  | 8.1×10 <sup>1</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 3.4×10 <sup>-6</sup> | 9.3×10 <sup>-5</sup> |
| Cm-248                 |                           | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 3.0×10 <sup>-4</sup> | 8.1×10 <sup>-3</sup>             | 1.6×10 <sup>-4</sup> | 4.2×10 <sup>-3</sup> |
| Co-55                  | Cobalt (27)               | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 1.1×10 <sup>5</sup>  | 3.1×10 <sup>6</sup>  |
| Co-56                  |                           | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 1.1×10 <sup>3</sup>  | 3.0×10 <sup>4</sup>  |
| Co-57                  |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 3.1×10 <sup>2</sup>  | 8.4×10 <sup>3</sup>  |
| Co-58                  |                           | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.2×10 <sup>3</sup>  | 3.2×10 <sup>4</sup>  |
| Co-58m                 |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.2×10 <sup>5</sup>  | 5.9×10 <sup>6</sup>  |
| Co-60                  |                           | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.2×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>  |
| Cr-51                  | Chromium (24)             | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.4×10 <sup>3</sup>  | 9.2×10 <sup>4</sup>  |
| Cs-129                 | Cesium (55)               | 4.0                  | 1.1×10 <sup>2</sup>              | 4.0                  | 1.1×10 <sup>2</sup>              | 2.8×10 <sup>4</sup>  | 7.6×10 <sup>5</sup>  |
| Cs-131                 |                           | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.8×10 <sup>3</sup>  | 1.0×10 <sup>5</sup>  |
| Cs-132                 |                           | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 5.7×10 <sup>3</sup>  | 1.5×10 <sup>5</sup>  |
| Cs-134                 |                           | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 4.8×10 <sup>1</sup>  | 1.3×10 <sup>3</sup>  |
| Cs-134m                |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.0×10 <sup>5</sup>  | 8.0×10 <sup>6</sup>  |
| Cs-135                 |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 4.3×10 <sup>-5</sup> | 1.2×10 <sup>-3</sup> |
| Cs-136                 |                           | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 2.7×10 <sup>3</sup>  | 7.3×10 <sup>4</sup>  |
| Cs-137 (a)             |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.2                  | 8.7×10 <sup>1</sup>  |
| Cu-64                  | Copper (29)               | 6.0                  | 1.6×10 <sup>2</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.4×10 <sup>5</sup>  | 3.9×10 <sup>6</sup>  |
| Cu-67                  |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 2.8×10 <sup>4</sup>  | 7.6×10 <sup>5</sup>  |
| Dy-159                 | Dysprosium (66)           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.1×10 <sup>2</sup>  | 5.7×10 <sup>3</sup>  |
| Dy-165                 |                           | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.0×10 <sup>5</sup>  | 8.2×10 <sup>6</sup>  |
| Dy-166 (a)             |                           | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 3.0×10 <sup>-1</sup> | 8.1                              | 8.6×10 <sup>3</sup>  | 2.3×10 <sup>5</sup>  |
| Er-169                 | Erbium (68)               | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 3.1×10 <sup>3</sup>  | 8.3×10 <sup>4</sup>  |
| Er-171                 |                           | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 9.0×10 <sup>4</sup>  | 2.4×10 <sup>6</sup>  |
| Eu-147                 | Europium (63)             | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 1.4×10 <sup>3</sup>  | 3.7×10 <sup>4</sup>  |
| Eu-148                 |                           | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 6.0×10 <sup>2</sup>  | 1.6×10 <sup>4</sup>  |
| Eu-149                 |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 3.5×10 <sup>2</sup>  | 9.4×10 <sup>3</sup>  |
| Eu-150 (short lived)   |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 6.1×10 <sup>4</sup>  | 1.6×10 <sup>6</sup>  |
| Eu-150 (long lived)    |                           | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 6.1×10 <sup>4</sup>  | 1.6×10 <sup>6</sup>  |
| Eu-152                 |                           | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 6.5                  | 1.8×10 <sup>2</sup>  |

| Symbol of radionuclide | Element and atomic number | A <sub>1</sub> (TBq) | A <sub>1</sub> (Ci) <sup>b</sup> | A <sub>2</sub> (TBq) | A <sub>2</sub> (Ci) <sup>b</sup> | Specific activity    |                      |
|------------------------|---------------------------|----------------------|----------------------------------|----------------------|----------------------------------|----------------------|----------------------|
|                        |                           |                      |                                  |                      |                                  | (TBq/g)              | (Ci/g)               |
| Eu-152m                | .....                     | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 8.2×10 <sup>4</sup>  | 2.2×10 <sup>6</sup>  |
| Eu-154                 | .....                     | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 9.8                  | 2.6×10 <sup>2</sup>  |
| Eu-155                 | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 1.8×10 <sup>1</sup>  | 4.9×10 <sup>2</sup>  |
| Eu-156                 | .....                     | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 2.0×10 <sup>3</sup>  | 5.5×10 <sup>4</sup>  |
| F-18                   | Fluorine (9)              | 1.0                  | 2.7×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.5×10 <sup>6</sup>  | 9.5×10 <sup>7</sup>  |
| Fe-52 (a)              | Iron (26)                 | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 2.7×10 <sup>5</sup>  | 7.3×10 <sup>6</sup>  |
| Fe-55                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 8.8×10 <sup>1</sup>  | 2.4×10 <sup>3</sup>  |
| Fe-59                  | .....                     | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 1.8×10 <sup>3</sup>  | 5.0×10 <sup>4</sup>  |
| Fe-60 (a)              | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>-1</sup> | 5.4                              | 7.4×10 <sup>-4</sup> | 2.0×10 <sup>-2</sup> |
| Ga-67                  | Gallium (31)              | 7.0                  | 1.9×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 2.2×10 <sup>4</sup>  | 6.0×10 <sup>5</sup>  |
| Ga-68                  | .....                     | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 1.5×10 <sup>6</sup>  | 4.1×10 <sup>7</sup>  |
| Ga-72                  | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.1×10 <sup>5</sup>  | 3.1×10 <sup>6</sup>  |
| Gd-146 (a)             | Gadolinium (64)           | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 6.9×10 <sup>2</sup>  | 1.9×10 <sup>4</sup>  |
| Gd-148                 | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>-3</sup> | 5.4×10 <sup>-2</sup>             | 1.2                  | 3.2×10 <sup>1</sup>  |
| Gd-153                 | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 9.0                  | 2.4×10 <sup>2</sup>              | 1.3×10 <sup>2</sup>  | 3.5×10 <sup>3</sup>  |
| Gd-159                 | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.9×10 <sup>4</sup>  | 1.1×10 <sup>6</sup>  |
| Ge-68 (a)              | Germanium (32)            | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 2.6×10 <sup>2</sup>  | 7.1×10 <sup>3</sup>  |
| Ge-71                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 5.8×10 <sup>3</sup>  | 1.6×10 <sup>5</sup>  |
| Ge-77                  | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 1.3×10 <sup>5</sup>  | 3.6×10 <sup>6</sup>  |
| Hf-172 (a)             | Hafnium (72)              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 4.1×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>  |
| Hf-175                 | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 3.9×10 <sup>2</sup>  | 1.1×10 <sup>4</sup>  |
| Hf-181                 | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 6.3×10 <sup>2</sup>  | 1.7×10 <sup>4</sup>  |
| Hf-182                 | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 8.1×10 <sup>-6</sup> | 2.2×10 <sup>-4</sup> |
| Hg-194 (a)             | Mercury (80)              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.3×10 <sup>-1</sup> | 3.5                  |
| Hg-195m (a)            | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 1.5×10 <sup>4</sup>  | 4.0×10 <sup>5</sup>  |
| Hg-197                 | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 9.2×10 <sup>3</sup>  | 2.5×10 <sup>5</sup>  |
| Hg-197m                | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 2.5×10 <sup>4</sup>  | 6.7×10 <sup>5</sup>  |
| Hg-203                 | .....                     | 5.0                  | 1.4×10 <sup>2</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 5.1×10 <sup>2</sup>  | 1.4×10 <sup>4</sup>  |
| Ho-166                 | Holmium (67)              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 2.6×10 <sup>4</sup>  | 7.0×10 <sup>5</sup>  |
| Ho-166m                | .....                     | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 6.6×10 <sup>-2</sup> | 1.8                  |
| I-123                  | Iodine (53)               | 6.0                  | 1.6×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 7.1×10 <sup>4</sup>  | 1.9×10 <sup>6</sup>  |
| I-124                  | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 9.3×10 <sup>3</sup>  | 2.5×10 <sup>5</sup>  |
| I-125                  | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 6.4×10 <sup>2</sup>  | 1.7×10 <sup>4</sup>  |
| I-126                  | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 2.9×10 <sup>3</sup>  | 8.0×10 <sup>4</sup>  |
| I-129                  | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 6.5×10 <sup>-6</sup> | 1.8×10 <sup>-4</sup> |
| I-131                  | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 4.6×10 <sup>3</sup>  | 1.2×10 <sup>5</sup>  |
| I-132                  | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 3.8×10 <sup>5</sup>  | 1.0×10 <sup>7</sup>  |
| I-133                  | .....                     | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 4.2×10 <sup>4</sup>  | 1.1×10 <sup>6</sup>  |
| I-134                  | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 9.9×10 <sup>5</sup>  | 2.7×10 <sup>7</sup>  |
| I-135 (a)              | .....                     | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.3×10 <sup>5</sup>  | 3.5×10 <sup>6</sup>  |
| In-111                 | Indium (49)               | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 1.5×10 <sup>4</sup>  | 4.2×10 <sup>5</sup>  |
| In-113m                | .....                     | 4.0                  | 1.1×10 <sup>2</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 6.2×10 <sup>5</sup>  | 1.7×10 <sup>7</sup>  |
| In-114m (a)            | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 8.6×10 <sup>2</sup>  | 2.3×10 <sup>4</sup>  |
| In-115m                | .....                     | 7.0                  | 1.9×10 <sup>2</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 2.2×10 <sup>5</sup>  | 6.1×10 <sup>6</sup>  |
| Ir-189 (a)             | Iridium (77)              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.9×10 <sup>3</sup>  | 5.2×10 <sup>4</sup>  |
| Ir-190                 | .....                     | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 2.3×10 <sup>3</sup>  | 6.2×10 <sup>4</sup>  |
| Ir-192 (c)             | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.4×10 <sup>2</sup>  | 9.2×10 <sup>3</sup>  |
| Ir-194                 | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 3.1×10 <sup>4</sup>  | 8.4×10 <sup>5</sup>  |
| K-40                   | Potassium (19)            | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 2.4×10 <sup>-7</sup> | 6.4×10 <sup>-6</sup> |
| K-42                   | .....                     | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 2.2×10 <sup>5</sup>  | 6.0×10 <sup>6</sup>  |
| K-43                   | .....                     | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.2×10 <sup>5</sup>  | 3.3×10 <sup>6</sup>  |
| Kr-81                  | Krypton (36)              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 7.8×10 <sup>-4</sup> | 2.1×10 <sup>-2</sup> |
| Kr-85                  | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.5×10 <sup>1</sup>  | 3.9×10 <sup>2</sup>  |
| Kr-85m                 | .....                     | 8.0                  | 2.2×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0×10 <sup>5</sup>  | 8.2×10 <sup>6</sup>  |
| Kr-87                  | .....                     | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 1.0×10 <sup>6</sup>  | 2.8×10 <sup>7</sup>  |
| La-137                 | Lanthanum (57)            | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 6.0                  | 1.6×10 <sup>2</sup>              | 1.6×10 <sup>-3</sup> | 4.4×10 <sup>-2</sup> |
| La-140                 | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 2.1×10 <sup>4</sup>  | 5.6×10 <sup>5</sup>  |
| Lu-172                 | Lutetium (71)             | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 4.2×10 <sup>3</sup>  | 1.1×10 <sup>5</sup>  |
| Lu-173                 | .....                     | 8.0                  | 2.2×10 <sup>2</sup>              | 8.0                  | 2.2×10 <sup>2</sup>              | 5.6×10 <sup>1</sup>  | 1.5×10 <sup>3</sup>  |
| Lu-174                 | .....                     | 9.0                  | 2.4×10 <sup>2</sup>              | 9.0                  | 2.4×10 <sup>2</sup>              | 2.3×10 <sup>1</sup>  | 6.2×10 <sup>2</sup>  |
| Lu-174m                | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 2.0×10 <sup>2</sup>  | 5.3×10 <sup>3</sup>  |
| Lu-177                 | .....                     | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 4.1×10 <sup>3</sup>  | 1.1×10 <sup>5</sup>  |
| Mg-28 (a)              | Magnesium (12)            | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 2.0×10 <sup>5</sup>  | 5.4×10 <sup>6</sup>  |
| Mn-52                  | Manganese (25)            | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 1.6×10 <sup>4</sup>  | 4.4×10 <sup>5</sup>  |
| Mn-53                  | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 6.8×10 <sup>-5</sup> | 1.8×10 <sup>-3</sup> |
| Mn-54                  | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 2.9×10 <sup>2</sup>  | 7.7×10 <sup>3</sup>  |
| Mn-56                  | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 8.0×10 <sup>5</sup>  | 2.2×10 <sup>7</sup>  |
| Mo-93                  | Molybdenum (42)           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 4.1×10 <sup>-2</sup> | 1.1                  |
| Mo-99 (a) (i)          | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.8×10 <sup>4</sup>  | 4.8×10 <sup>5</sup>  |
| N-13                   | Nitrogen (7)              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 5.4×10 <sup>7</sup>  | 1.5×10 <sup>9</sup>  |
| Na-22                  | Sodium (11)               | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 2.3×10 <sup>2</sup>  | 6.3×10 <sup>3</sup>  |
| Na-24                  | .....                     | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 3.2×10 <sup>5</sup>  | 8.7×10 <sup>6</sup>  |



| Symbol of radionuclide | Element and atomic number | A <sub>1</sub> (TBq) | A <sub>1</sub> (Ci) <sup>b</sup> | A <sub>2</sub> (TBq) | A <sub>2</sub> (Ci) <sup>b</sup> | Specific activity    |                      |
|------------------------|---------------------------|----------------------|----------------------------------|----------------------|----------------------------------|----------------------|----------------------|
|                        |                           |                      |                                  |                      |                                  | (TBq/g)              | (Ci/g)               |
| Nb-93m                 | Niobium (41)              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 8.8                  | 2.4×10 <sup>2</sup>  |
| Nb-94                  |                           | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 6.9×10 <sup>-3</sup> | 1.9×10 <sup>-1</sup> |
| Nb-95                  |                           | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.5×10 <sup>3</sup>  | 3.9×10 <sup>4</sup>  |
| Nb-97                  |                           | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 9.9×10 <sup>5</sup>  | 2.7×10 <sup>7</sup>  |
| Nd-147                 | Neodymium (60)            | 6.0                  | 1.6×10 <sup>2</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.0×10 <sup>3</sup>  | 8.1×10 <sup>4</sup>  |
| Nd-149                 |                           | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 4.5×10 <sup>5</sup>  | 1.2×10 <sup>7</sup>  |
| Ni-59                  | Nickel (28)               | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 3.0×10 <sup>-3</sup> | 8.0×10 <sup>-2</sup> |
| Ni-63                  |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 2.1                  | 5.7×10 <sup>1</sup>  |
| Ni-65                  |                           | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 7.1×10 <sup>5</sup>  | 1.9×10 <sup>7</sup>  |
| Np-235                 | Neptunium (93)            | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 5.2×10 <sup>1</sup>  | 1.4×10 <sup>3</sup>  |
| Np-236 (short-lived)   |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 4.7×10 <sup>-4</sup> | 1.3×10 <sup>-2</sup> |
| Np-236 (long-lived)    |                           | 9.0×10 <sup>0</sup>  | 2.4×10 <sup>2</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 4.7×10 <sup>-4</sup> | 1.3×10 <sup>-2</sup> |
| Np-237                 |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>-3</sup> | 5.4×10 <sup>-2</sup>             | 2.6×10 <sup>-5</sup> | 7.1×10 <sup>-4</sup> |
| Np-239                 |                           | 7.0                  | 1.9×10 <sup>2</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 8.6×10 <sup>3</sup>  | 2.3×10 <sup>5</sup>  |
| Os-185                 | Osmium (76)               | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 2.8×10 <sup>2</sup>  | 7.5×10 <sup>3</sup>  |
| Os-191                 |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 1.6×10 <sup>3</sup>  | 4.4×10 <sup>4</sup>  |
| Os-191m                |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 4.6×10 <sup>4</sup>  | 1.3×10 <sup>6</sup>  |
| Os-193                 |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.0×10 <sup>4</sup>  | 5.3×10 <sup>5</sup>  |
| Os-194 (a)             |                           | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 1.1×10 <sup>1</sup>  | 3.1×10 <sup>2</sup>  |
| P-32                   | Phosphorus (15)           | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 1.1×10 <sup>4</sup>  | 2.9×10 <sup>5</sup>  |
| P-33                   |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 5.8×10 <sup>3</sup>  | 1.6×10 <sup>5</sup>  |
| Pa-230 (a)             | Protactinium (91)         | 2.0                  | 5.4×10 <sup>1</sup>              | 7.0×10 <sup>-2</sup> | 1.9                              | 1.2×10 <sup>3</sup>  | 3.3×10 <sup>4</sup>  |
| Pa-231                 |                           | 4.0                  | 1.1×10 <sup>2</sup>              | 4.0×10 <sup>-4</sup> | 1.1×10 <sup>-2</sup>             | 1.7×10 <sup>-3</sup> | 4.7×10 <sup>-2</sup> |
| Pa-233                 |                           | 5.0                  | 1.4×10 <sup>2</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.7×10 <sup>2</sup>  | 2.1×10 <sup>4</sup>  |
| Pb-201                 | Lead (82)                 | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 6.2×10 <sup>4</sup>  | 1.7×10 <sup>6</sup>  |
| Pb-202                 |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 1.2×10 <sup>-4</sup> | 3.4×10 <sup>-3</sup> |
| Pb-203                 |                           | 4.0                  | 1.1×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 1.1×10 <sup>4</sup>  | 3.0×10 <sup>5</sup>  |
| Pb-205                 |                           | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 4.5×10 <sup>-6</sup> | 1.2×10 <sup>-4</sup> |
| Pb-210 (a)             |                           | 1.0                  | 2.7×10 <sup>1</sup>              | 5.0×10 <sup>-2</sup> | 1.4                              | 2.8                  | 7.6×10 <sup>1</sup>  |
| Pb-212 (a)             |                           | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 2.0×10 <sup>-1</sup> | 5.4                              | 5.1×10 <sup>4</sup>  | 1.4×10 <sup>6</sup>  |
| Pd-103 (a)             | Palladium (46)            | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.8×10 <sup>3</sup>  | 7.5×10 <sup>4</sup>  |
| Pd-107                 |                           | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 1.9×10 <sup>-5</sup> | 5.1×10 <sup>-4</sup> |
| Pd-109                 |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 7.9×10 <sup>4</sup>  | 2.1×10 <sup>6</sup>  |
| Pm-143                 | Promethium (61)           | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 1.3×10 <sup>2</sup>  | 3.4×10 <sup>3</sup>  |
| Pm-144                 |                           | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 9.2×10 <sup>1</sup>  | 2.5×10 <sup>3</sup>  |
| Pm-145                 |                           | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 5.2                  | 1.4×10 <sup>2</sup>  |
| Pm-147                 |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 3.4×10 <sup>1</sup>  | 9.3×10 <sup>2</sup>  |
| Pm-148m (a)            |                           | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 7.9×10 <sup>2</sup>  | 2.1×10 <sup>4</sup>  |
| Pm-149                 |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.5×10 <sup>4</sup>  | 4.0×10 <sup>5</sup>  |
| Pm-151                 |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.7×10 <sup>4</sup>  | 7.3×10 <sup>5</sup>  |
| Po-210                 | Polonium (84)             | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 1.7×10 <sup>2</sup>  | 4.5×10 <sup>3</sup>  |
| Pr-142                 | Praseodymium (59)         | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.3×10 <sup>4</sup>  | 1.2×10 <sup>6</sup>  |
| Pr-143                 |                           | 3.0                  | 8.1×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.5×10 <sup>3</sup>  | 6.7×10 <sup>4</sup>  |
| Pt-188 (a)             | Platinum (78)             | 1.0                  | 2.7×10 <sup>1</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 2.5×10 <sup>3</sup>  | 6.8×10 <sup>4</sup>  |
| Pt-191                 |                           | 4.0                  | 1.1×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 8.7×10 <sup>3</sup>  | 2.4×10 <sup>5</sup>  |
| Pt-193                 |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.4                  | 3.7×10 <sup>1</sup>  |
| Pt-193m                |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.8×10 <sup>3</sup>  | 1.6×10 <sup>5</sup>  |
| Pt-195m                |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 6.2×10 <sup>3</sup>  | 1.7×10 <sup>5</sup>  |
| Pt-197                 |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.2×10 <sup>4</sup>  | 8.7×10 <sup>5</sup>  |
| Pt-197m                |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.7×10 <sup>5</sup>  | 1.0×10 <sup>7</sup>  |
| Pu-236                 | Plutonium (94)            | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.0×10 <sup>-3</sup> | 8.1×10 <sup>-2</sup>             | 2.0×10 <sup>1</sup>  | 5.3×10 <sup>2</sup>  |
| Pu-237                 |                           | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 4.5×10 <sup>2</sup>  | 1.2×10 <sup>4</sup>  |
| Pu-238                 |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 6.3×10 <sup>-1</sup> | 1.7×10 <sup>1</sup>  |
| Pu-239                 |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 2.3×10 <sup>-3</sup> | 6.2×10 <sup>-2</sup> |
| Pu-240                 |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 8.4×10 <sup>-3</sup> | 2.3×10 <sup>-1</sup> |
| Pu-241 (a)             |                           | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 6.0×10 <sup>-2</sup> | 1.6                              | 3.8                  | 1.0×10 <sup>2</sup>  |
| Pu-242                 |                           | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 1.5×10 <sup>-4</sup> | 3.9×10 <sup>-3</sup> |
| Pu-244 (a)             |                           | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 6.7×10 <sup>-7</sup> | 1.8×10 <sup>-5</sup> |
| Ra-223 (a)             | Radium (88)               | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 7.0×10 <sup>-3</sup> | 1.9×10 <sup>-1</sup>             | 1.9×10 <sup>3</sup>  | 5.1×10 <sup>4</sup>  |
| Ra-224 (a)             |                           | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 5.9×10 <sup>3</sup>  | 1.6×10 <sup>5</sup>  |
| Ra-225 (a)             |                           | 2.0×10 <sup>-1</sup> | 5.4                              | 4.0×10 <sup>-3</sup> | 1.1×10 <sup>-1</sup>             | 1.5×10 <sup>3</sup>  | 3.9×10 <sup>4</sup>  |
| Ra-226 (a)             |                           | 2.0×10 <sup>-1</sup> | 5.4                              | 3.0×10 <sup>-3</sup> | 8.1×10 <sup>-2</sup>             | 3.7×10 <sup>-2</sup> | 1.0                  |
| Ra-228 (a)             |                           | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>  |
| Rb-81                  | Rubidium (37)             | 2.0                  | 5.4×10 <sup>1</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 3.1×10 <sup>5</sup>  | 8.4×10 <sup>6</sup>  |
| Rb-83 (a)              |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 6.8×10 <sup>2</sup>  | 1.8×10 <sup>4</sup>  |
| Rb-84                  |                           | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.8×10 <sup>3</sup>  | 4.7×10 <sup>4</sup>  |
| Rb-86                  |                           | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 3.0×10 <sup>3</sup>  | 8.1×10 <sup>4</sup>  |
| Rb-87                  |                           | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 3.2×10 <sup>-9</sup> | 8.6×10 <sup>-8</sup> |
| Rb(nat)                |                           | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 6.7×10 <sup>6</sup>  | 1.8×10 <sup>8</sup>  |
| Re-184                 | Rhenium (75)              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 6.9×10 <sup>2</sup>  | 1.9×10 <sup>4</sup>  |
| Re-184m                |                           | 3.0                  | 8.1×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.6×10 <sup>2</sup>  | 4.3×10 <sup>3</sup>  |
| Re-186                 |                           | 2.0                  | 5.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.9×10 <sup>3</sup>  | 1.9×10 <sup>5</sup>  |

| Symbol of radionuclide | Element and atomic number | A <sub>1</sub> (TBq) | A <sub>1</sub> (Ci) <sup>b</sup> | A <sub>2</sub> (TBq) | A <sub>2</sub> (Ci) <sup>b</sup> | Specific activity    |                      |
|------------------------|---------------------------|----------------------|----------------------------------|----------------------|----------------------------------|----------------------|----------------------|
|                        |                           |                      |                                  |                      |                                  | (TBq/g)              | (Ci/g)               |
| Re-187                 | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 1.4×10 <sup>-9</sup> | 3.8×10 <sup>-8</sup> |
| Re-188                 | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 3.6×10 <sup>4</sup>  | 9.8×10 <sup>5</sup>  |
| Re-189 (a)             | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.5×10 <sup>4</sup>  | 6.8×10 <sup>5</sup>  |
| Re(nat)                | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 0.0                  | 2.4×10 <sup>-8</sup> |
| Rh-99                  | Rhodium (45) .....        | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 3.0×10 <sup>3</sup>  | 8.2×10 <sup>4</sup>  |
| Rh-101                 | .....                     | 4.0                  | 1.1×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 4.1×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>  |
| Rh-102                 | .....                     | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 4.5×10 <sup>1</sup>  | 1.2×10 <sup>3</sup>  |
| Rh-102m                | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 2.3×10 <sup>2</sup>  | 6.2×10 <sup>3</sup>  |
| Rh-103m                | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.2×10 <sup>6</sup>  | 3.3×10 <sup>7</sup>  |
| Rh-105                 | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 3.1×10 <sup>4</sup>  | 8.4×10 <sup>5</sup>  |
| Rn-222 (a)             | Radon (86) .....          | 3.0×10 <sup>-1</sup> | 8.1                              | 4.0×10 <sup>-3</sup> | 1.1×10 <sup>-1</sup>             | 5.7×10 <sup>3</sup>  | 1.5×10 <sup>5</sup>  |
| Ru-97                  | Ruthenium (44) .....      | 5.0                  | 1.4×10 <sup>2</sup>              | 5.0                  | 1.4×10 <sup>2</sup>              | 1.7×10 <sup>4</sup>  | 4.6×10 <sup>5</sup>  |
| Ru-103 (a)             | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 1.2×10 <sup>3</sup>  | 3.2×10 <sup>4</sup>  |
| Ru-105                 | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.5×10 <sup>5</sup>  | 6.7×10 <sup>6</sup>  |
| Ru-106 (a)             | .....                     | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 1.2×10 <sup>2</sup>  | 3.3×10 <sup>3</sup>  |
| S-35                   | Sulphur (16) .....        | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 1.6×10 <sup>3</sup>  | 4.3×10 <sup>4</sup>  |
| Sb-122                 | Antimony (51) .....       | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.5×10 <sup>4</sup>  | 4.0×10 <sup>5</sup>  |
| Sb-124                 | .....                     | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.5×10 <sup>2</sup>  | 1.7×10 <sup>4</sup>  |
| Sb-125                 | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 3.9×10 <sup>1</sup>  | 1.0×10 <sup>3</sup>  |
| Sb-126                 | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 3.1×10 <sup>3</sup>  | 8.4×10 <sup>4</sup>  |
| Sc-44                  | Scandium (21) .....       | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 6.7×10 <sup>5</sup>  | 1.8×10 <sup>7</sup>  |
| Sc-46                  | .....                     | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 1.3×10 <sup>3</sup>  | 3.4×10 <sup>4</sup>  |
| Sc-47                  | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 3.1×10 <sup>4</sup>  | 8.3×10 <sup>5</sup>  |
| Sc-48                  | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 5.5×10 <sup>4</sup>  | 1.5×10 <sup>6</sup>  |
| Se-75                  | Selenium (34) .....       | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 5.4×10 <sup>2</sup>  | 1.5×10 <sup>4</sup>  |
| Se-79                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 2.6×10 <sup>-3</sup> | 7.0×10 <sup>-2</sup> |
| Si-31                  | Silicon (14) .....        | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.4×10 <sup>6</sup>  | 3.9×10 <sup>7</sup>  |
| Si-32                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 3.9                  | 1.1×10 <sup>2</sup>  |
| Sm-145                 | Samarium (62) .....       | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 9.8×10 <sup>1</sup>  | 2.6×10 <sup>3</sup>  |
| Sm-147                 | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 8.5×10 <sup>-1</sup> | 2.3×10 <sup>-8</sup> |
| Sm-151                 | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 9.7×10 <sup>-1</sup> | 2.6×10 <sup>1</sup>  |
| Sm-153                 | .....                     | 9.0                  | 2.4×10 <sup>2</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.6×10 <sup>4</sup>  | 4.4×10 <sup>5</sup>  |
| Sn-113 (a)             | Tin (50) .....            | 4.0                  | 1.1×10 <sup>2</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 3.7×10 <sup>2</sup>  | 1.0×10 <sup>4</sup>  |
| Sn-117m                | .....                     | 7.0                  | 1.9×10 <sup>2</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 3.0×10 <sup>3</sup>  | 8.2×10 <sup>4</sup>  |
| Sn-119m                | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 1.4×10 <sup>2</sup>  | 3.7×10 <sup>3</sup>  |
| Sn-121m (a)            | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>  |
| Sn-123                 | .....                     | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 3.0×10 <sup>2</sup>  | 8.2×10 <sup>3</sup>  |
| Sn-125                 | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>3</sup>  | 1.1×10 <sup>5</sup>  |
| Sn-126 (a)             | .....                     | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.0×10 <sup>-3</sup> | 2.8×10 <sup>-2</sup> |
| Sr-82 (a)              | Strontium (38) .....      | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 2.3×10 <sup>3</sup>  | 6.2×10 <sup>4</sup>  |
| Sr-85                  | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 8.8×10 <sup>2</sup>  | 2.4×10 <sup>4</sup>  |
| Sr-85m                 | .....                     | 5.0                  | 1.4×10 <sup>2</sup>              | 5.0                  | 1.4×10 <sup>2</sup>              | 1.2×10 <sup>6</sup>  | 3.3×10 <sup>7</sup>  |
| Sr-87m                 | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 4.8×10 <sup>5</sup>  | 1.3×10 <sup>7</sup>  |
| Sr-89                  | .....                     | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.1×10 <sup>3</sup>  | 2.9×10 <sup>4</sup>  |
| Sr-90 (a)              | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 5.1                  | 1.4×10 <sup>2</sup>  |
| Sr-91 (a)              | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 1.3×10 <sup>5</sup>  | 3.6×10 <sup>6</sup>  |
| Sr-92 (a)              | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 3.0×10 <sup>-1</sup> | 8.1                              | 4.7×10 <sup>5</sup>  | 1.3×10 <sup>7</sup>  |
| T(H-3)                 | Tritium (1) .....         | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.6×10 <sup>2</sup>  | 9.7×10 <sup>3</sup>  |
| Ta-178 (long-lived)    | Tantalum (73) .....       | 1.0                  | 2.7×10 <sup>1</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 4.2×10 <sup>6</sup>  | 1.1×10 <sup>8</sup>  |
| Ta-179                 | .....                     | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 4.1×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>  |
| Ta-182                 | .....                     | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 2.3×10 <sup>2</sup>  | 6.2×10 <sup>3</sup>  |
| Tb-157                 | Terbium (65) .....        | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 5.6×10 <sup>-1</sup> | 1.5×10 <sup>1</sup>  |
| Tb-158                 | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 5.6×10 <sup>-1</sup> | 1.5×10 <sup>1</sup>  |
| Tb-160                 | .....                     | 1.0                  | 2.7×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 4.2×10 <sup>2</sup>  | 1.1×10 <sup>4</sup>  |
| Tc-95m (a)             | Technetium (43) .....     | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 8.3×10 <sup>2</sup>  | 2.2×10 <sup>4</sup>  |
| Tc-96                  | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.2×10 <sup>4</sup>  | 3.2×10 <sup>5</sup>  |
| Tc-96m (a)             | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.4×10 <sup>6</sup>  | 3.8×10 <sup>7</sup>  |
| Tc-97                  | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 5.2×10 <sup>-5</sup> | 1.4×10 <sup>-3</sup> |
| Tc-97m                 | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 5.6×10 <sup>2</sup>  | 1.5×10 <sup>4</sup>  |
| Tc-98                  | .....                     | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 3.2×10 <sup>-5</sup> | 8.7×10 <sup>-4</sup> |
| Tc-99                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.3×10 <sup>-4</sup> | 1.7×10 <sup>-2</sup> |
| Tc-99m                 | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 4.0                  | 1.1×10 <sup>2</sup>              | 1.9×10 <sup>5</sup>  | 5.3×10 <sup>6</sup>  |
| Te-121                 | Tellurium (52) .....      | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 2.4×10 <sup>3</sup>  | 6.4×10 <sup>4</sup>  |
| Te-121m                | .....                     | 5.0                  | 1.4×10 <sup>2</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 2.6×10 <sup>2</sup>  | 7.0×10 <sup>3</sup>  |
| Te-123m                | .....                     | 8.0                  | 2.2×10 <sup>2</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 3.3×10 <sup>2</sup>  | 8.9×10 <sup>3</sup>  |
| Te-125m                | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.7×10 <sup>2</sup>  | 1.8×10 <sup>4</sup>  |
| Te-127                 | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 9.8×10 <sup>4</sup>  | 2.6×10 <sup>6</sup>  |
| Te-127m (a)            | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 3.5×10 <sup>2</sup>  | 9.4×10 <sup>3</sup>  |
| Te-129                 | .....                     | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 7.7×10 <sup>5</sup>  | 2.1×10 <sup>7</sup>  |
| Te-129m (a)            | .....                     | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.1×10 <sup>3</sup>  | 3.0×10 <sup>4</sup>  |
| Te-131m (a)            | .....                     | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 3.0×10 <sup>4</sup>  | 8.0×10 <sup>5</sup>  |
| Te-132 (a)             | .....                     | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 1.1×10 <sup>4</sup>  | 3.0×10 <sup>5</sup>  |

| Symbol of radionuclide                             | Element and atomic number | A <sub>1</sub> (TBq) | A <sub>1</sub> (Ci) <sup>b</sup> | A <sub>2</sub> (TBq) | A <sub>2</sub> (Ci) <sup>b</sup> | Specific activity    |                      |
|----------------------------------------------------|---------------------------|----------------------|----------------------------------|----------------------|----------------------------------|----------------------|----------------------|
|                                                    |                           |                      |                                  |                      |                                  | (TBq/g)              | (Ci/g)               |
| Th-227 .....                                       | Thorium (90) .....        | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 5.0×10 <sup>-3</sup> | 1.4×10 <sup>-1</sup>             | 1.1×10 <sup>3</sup>  | 3.1×10 <sup>4</sup>  |
| Th-228 (a) .....                                   | .....                     | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 3.0×10 <sup>1</sup>  | 8.2×10 <sup>2</sup>  |
| Th-229 .....                                       | .....                     | 5.0                  | 1.4×10 <sup>2</sup>              | 5.0×10 <sup>-4</sup> | 1.4×10 <sup>-2</sup>             | 7.9×10 <sup>-3</sup> | 2.1×10 <sup>-1</sup> |
| Th-230 .....                                       | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 7.6×10 <sup>-4</sup> | 2.1×10 <sup>-2</sup> |
| Th-231 .....                                       | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 2.0×10 <sup>4</sup>  | 5.3×10 <sup>5</sup>  |
| Th-232 .....                                       | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 4.0×10 <sup>-9</sup> | 1.1×10 <sup>-7</sup> |
| Th-234 (a) .....                                   | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 8.6×10 <sup>2</sup>  | 2.3×10 <sup>4</sup>  |
| Th(nat) .....                                      | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 8.1×10 <sup>-9</sup> | 2.2×10 <sup>-7</sup> |
| Ti-44 (a) .....                                    | Titanium (22) .....       | 5.0×10 <sup>-1</sup> | 1.4×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 6.4                  | 1.7×10 <sup>2</sup>  |
| Tl-200 .....                                       | Thallium (81) .....       | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 2.2×10 <sup>4</sup>  | 6.0×10 <sup>5</sup>  |
| Tl-201 .....                                       | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 4.0                  | 1.1×10 <sup>2</sup>              | 7.9×10 <sup>3</sup>  | 2.1×10 <sup>5</sup>  |
| Tl-202 .....                                       | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0×10 <sup>3</sup>  | 5.3×10 <sup>4</sup>  |
| Tl-204 .....                                       | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 1.7×10 <sup>1</sup>  | 4.6×10 <sup>2</sup>  |
| Tm-167 .....                                       | Thulium (69) .....        | 7.0                  | 1.9×10 <sup>2</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 3.1×10 <sup>3</sup>  | 8.5×10 <sup>4</sup>  |
| Tm-170 .....                                       | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.2×10 <sup>2</sup>  | 6.0×10 <sup>3</sup>  |
| Tm-171 .....                                       | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>  |
| U-230 (fast lung absorption) (a)(d).               | Uranium (92) .....        | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0×10 <sup>-1</sup> | 2.7                              | 1.0×10 <sup>3</sup>  | 2.7×10 <sup>4</sup>  |
| U-230 (medium lung absorption) (a)(e).             | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>-3</sup> | 1.1×10 <sup>-1</sup>             | 1.0×10 <sup>3</sup>  | 2.7×10 <sup>4</sup>  |
| U-230 (slow lung absorption) (a)(f).               | .....                     | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.0×10 <sup>-3</sup> | 8.1×10 <sup>-2</sup>             | 1.0×10 <sup>3</sup>  | 2.7×10 <sup>4</sup>  |
| U-232 (fast lung absorption) (d).                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 1.0×10 <sup>-2</sup> | 2.7×10 <sup>-1</sup>             | 8.3×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>  |
| U-232 (medium lung absorption) (e).                | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 7.0×10 <sup>-3</sup> | 1.9×10 <sup>-1</sup>             | 8.3×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>  |
| U-232 (slow lung absorption) (f).                  | .....                     | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 1.0×10 <sup>-3</sup> | 2.7×10 <sup>-2</sup>             | 8.3×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>  |
| U-233 (fast lung absorption) (d).                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 9.0×10 <sup>-2</sup> | 2.4                              | 3.6×10 <sup>-4</sup> | 9.7×10 <sup>-3</sup> |
| U-233 (medium lung absorption) (e).                | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 3.6×10 <sup>-4</sup> | 9.7×10 <sup>-3</sup> |
| U-233 (slow lung absorption) (f).                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 6.0×10 <sup>-3</sup> | 1.6×10 <sup>-1</sup>             | 3.6×10 <sup>-4</sup> | 9.7×10 <sup>-3</sup> |
| U-234 (fast lung absorption) (d).                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 9.0×10 <sup>-2</sup> | 2.4                              | 2.3×10 <sup>-4</sup> | 6.2×10 <sup>-3</sup> |
| U-234 (medium lung absorption) (e).                | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 2.3×10 <sup>-4</sup> | 6.2×10 <sup>-3</sup> |
| U-234 (slow lung absorption) (f).                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 6.0×10 <sup>-3</sup> | 1.6×10 <sup>-1</sup>             | 2.3×10 <sup>-4</sup> | 6.2×10 <sup>-3</sup> |
| U-235 (all lung absorption types) (a),(d),(e),(f). | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 8.0×10 <sup>-8</sup> | 2.2×10 <sup>-6</sup> |
| U-236 (fast lung absorption) (d).                  | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 2.4×10 <sup>-6</sup> | 6.5×10 <sup>-5</sup> |
| U-236 (medium lung absorption) (e).                | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 2.0×10 <sup>-2</sup> | 5.4×10 <sup>-1</sup>             | 2.4×10 <sup>-6</sup> | 6.5×10 <sup>-5</sup> |
| U-236 (slow lung absorption) (f).                  | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 6.0×10 <sup>-3</sup> | 1.6×10 <sup>-1</sup>             | 2.4×10 <sup>-6</sup> | 6.5×10 <sup>-5</sup> |
| U-238 (all lung absorption types) (d),(e),(f).     | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 1.2×10 <sup>-8</sup> | 3.4×10 <sup>-7</sup> |
| U (nat) .....                                      | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 2.6×10 <sup>-8</sup> | 7.1×10 <sup>-7</sup> |
| U (enriched to 20% or less)(g).                    | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | see § 173.434        | see § 173.434        |
| U (dep) .....                                      | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | see § 173.434        | see § 173.434        |
| V-48 .....                                         | Vanadium (23) .....       | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 6.3×10 <sup>3</sup>  | 1.7×10 <sup>5</sup>  |
| V-49 .....                                         | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.0×10 <sup>2</sup>  | 8.1×10 <sup>3</sup>  |
| W-178 (a) .....                                    | Tungsten (74) .....       | 9.0                  | 2.4×10 <sup>2</sup>              | 5.0                  | 1.4×10 <sup>2</sup>              | 1.3×10 <sup>3</sup>  | 3.4×10 <sup>4</sup>  |
| W-181 .....                                        | .....                     | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 2.2×10 <sup>2</sup>  | 6.0×10 <sup>3</sup>  |
| W-185 .....                                        | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 3.5×10 <sup>2</sup>  | 9.4×10 <sup>3</sup>  |
| W-187 .....                                        | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 2.6×10 <sup>4</sup>  | 7.0×10 <sup>5</sup>  |
| W-188 (a) .....                                    | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 3.0×10 <sup>-1</sup> | 8.1                              | 3.7×10 <sup>2</sup>  | 1.0×10 <sup>4</sup>  |
| Xe-122 (a) .....                                   | Xenon (54) .....          | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.8×10 <sup>4</sup>  | 1.3×10 <sup>6</sup>  |
| Xe-123 .....                                       | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 7.0×10 <sup>-1</sup> | 1.9×10 <sup>1</sup>              | 4.4×10 <sup>5</sup>  | 1.2×10 <sup>7</sup>  |
| Xe-127 .....                                       | .....                     | 4.0                  | 1.1×10 <sup>2</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 1.0×10 <sup>3</sup>  | 2.8×10 <sup>4</sup>  |
| Xe-131m .....                                      | .....                     | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 4.0×10 <sup>1</sup>  | 1.1×10 <sup>3</sup>              | 3.1×10 <sup>3</sup>  | 8.4×10 <sup>4</sup>  |
| Xe-133 .....                                       | .....                     | 2.0×10 <sup>1</sup>  | 5.4×10 <sup>2</sup>              | 1.0×10 <sup>1</sup>  | 2.7×10 <sup>2</sup>              | 6.9×10 <sup>3</sup>  | 1.9×10 <sup>5</sup>  |
| Xe-135 .....                                       | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 9.5×10 <sup>4</sup>  | 2.6×10 <sup>6</sup>  |
| Y-87 (a) .....                                     | Yttrium (39) .....        | 1.0                  | 2.7×10 <sup>1</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 1.7×10 <sup>4</sup>  | 4.5×10 <sup>5</sup>  |
| Y-88 .....                                         | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 5.2×10 <sup>2</sup>  | 1.4×10 <sup>4</sup>  |
| Y-90 .....                                         | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 2.0×10 <sup>4</sup>  | 5.4×10 <sup>5</sup>  |

| Symbol of radionuclide | Element and atomic number | A <sub>1</sub> (TBq) | A <sub>1</sub> (Ci) <sup>b</sup> | A <sub>2</sub> (TBq) | A <sub>2</sub> (Ci) <sup>b</sup> | Specific activity    |                      |
|------------------------|---------------------------|----------------------|----------------------------------|----------------------|----------------------------------|----------------------|----------------------|
|                        |                           |                      |                                  |                      |                                  | (TBq/g)              | (Ci/g)               |
| Y-91 .....             | .....                     | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 9.1×10 <sup>2</sup>  | 2.5×10 <sup>4</sup>  |
| Y-91m .....            | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 1.5×10 <sup>6</sup>  | 4.2×10 <sup>7</sup>  |
| Y-92 .....             | .....                     | 2.0×10 <sup>-1</sup> | 5.4                              | 2.0×10 <sup>-1</sup> | 5.4                              | 3.6×10 <sup>5</sup>  | 9.6×10 <sup>6</sup>  |
| Y-93 .....             | .....                     | 3.0×10 <sup>-1</sup> | 8.1                              | 3.0×10 <sup>-1</sup> | 8.1                              | 1.2×10 <sup>5</sup>  | 3.3×10 <sup>6</sup>  |
| Yb-169 .....           | Ytterbium (70) .....      | 4.0                  | 1.1×10 <sup>2</sup>              | 1.0                  | 2.7×10 <sup>1</sup>              | 8.9×10 <sup>2</sup>  | 2.4×10 <sup>4</sup>  |
| Yb-175 .....           | .....                     | 3.0×10 <sup>1</sup>  | 8.1×10 <sup>2</sup>              | 9.0×10 <sup>-1</sup> | 2.4×10 <sup>1</sup>              | 6.6×10 <sup>3</sup>  | 1.8×10 <sup>5</sup>  |
| Zn-65 .....            | Zinc (30) .....           | 2.0                  | 5.4×10 <sup>1</sup>              | 2.0                  | 5.4×10 <sup>1</sup>              | 3.0×10 <sup>2</sup>  | 8.2×10 <sup>3</sup>  |
| Zn-69 .....            | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.8×10 <sup>6</sup>  | 4.9×10 <sup>7</sup>  |
| Zn-69m (a) .....       | .....                     | 3.0                  | 8.1×10 <sup>1</sup>              | 6.0×10 <sup>-1</sup> | 1.6×10 <sup>1</sup>              | 1.2×10 <sup>5</sup>  | 3.3×10 <sup>6</sup>  |
| Zr-88 .....            | Zirconium (40) .....      | 3.0                  | 8.1×10 <sup>1</sup>              | 3.0                  | 8.1×10 <sup>1</sup>              | 6.6×10 <sup>2</sup>  | 1.8×10 <sup>4</sup>  |
| Zr-93 .....            | .....                     | Unlimited            | Unlimited                        | Unlimited            | Unlimited                        | 9.3×10 <sup>-5</sup> | 2.5×10 <sup>-3</sup> |
| Zr-95 (a) .....        | .....                     | 2.0                  | 5.4×10 <sup>1</sup>              | 8.0×10 <sup>-1</sup> | 2.2×10 <sup>1</sup>              | 7.9×10 <sup>2</sup>  | 2.1×10 <sup>4</sup>  |
| Zr-97 (a) .....        | .....                     | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 4.0×10 <sup>-1</sup> | 1.1×10 <sup>1</sup>              | 7.1×10 <sup>4</sup>  | 1.9×10 <sup>6</sup>  |

<sup>a</sup>A<sub>1</sub> and/or A<sub>2</sub> values include contributions from daughter nuclides with half-lives less than 10 days.

<sup>b</sup>The values of A<sub>1</sub> and A<sub>2</sub> in curies (Ci) are approximate and for information only; the regulatory standard units are Terabecquerels (TBq), (see § 171.10).

<sup>c</sup>The quantity may be determined from a measurement of the rate of decay or a measurement of the radiation level at a prescribed distance from the source.

<sup>d</sup>These values apply only to compounds of uranium that take the chemical form of UF<sub>6</sub>, UO<sub>2</sub>F<sub>2</sub> and UO<sub>2</sub>(NO<sub>3</sub>)<sub>2</sub> in both normal and accident conditions of transport.

<sup>e</sup>These values apply only to compounds of uranium that take the chemical form of UO<sub>3</sub>, UF<sub>4</sub>, UCl<sub>4</sub> and hexavalent compounds in both normal and accident conditions of transport.

<sup>f</sup>These values apply to all compounds of uranium other than those specified in notes (d) and (e) of this table.

<sup>g</sup>These values apply to unirradiated uranium only.

<sup>h</sup>A<sub>1</sub> = 0.1 TBq (2.7 Ci) and A<sub>2</sub> = 0.001 TBq (0.027 Ci) for Cf-252 for domestic use.

<sup>i</sup>A<sub>2</sub> = 0.74 TBq (20 Ci) for Mo-99 for domestic use.

[69 FR 3678, Jan. 26, 2004; 69 FR 55119, Sept. 13, 2004, as amended at 71 FR 54395, Sept. 14, 2006]

### § 173.436 Exempt material activity concentrations and exempt consignment activity limits for radionuclides.

The Table of Exempt material activity concentrations and exempt consignment activity limits for radionuclides is as follows:

| Symbol of radionuclide | Element and atomic number | Activity concentration for exempt material (Bq/g) | Activity concentration for exempt material (Ci/g) | Activity limit for exempt consignment (Bq) | Activity limit for exempt consignment (Ci) |
|------------------------|---------------------------|---------------------------------------------------|---------------------------------------------------|--------------------------------------------|--------------------------------------------|
| Ac-225 .....           | Actinium (89) .....       | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Ac-227 .....           | .....                     | 1.0×10 <sup>-1</sup>                              | 2.7×10 <sup>-12</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Ac-228 .....           | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ag-105 .....           | Silver (47) .....         | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ag-108m (b) .....      | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ag-110m .....          | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ag-111 .....           | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Al-26 .....            | Aluminum (13) .....       | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Am-241 .....           | Americium (95) .....      | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Am-242m (b) .....      | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Am-243 (b) .....       | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Ar-37 .....            | Argon (18) .....          | 1.0×10 <sup>6</sup>                               | 2.7×10 <sup>-5</sup>                              | 1.0×10 <sup>8</sup>                        | 2.7×10 <sup>-3</sup>                       |
| Ar-39 .....            | .....                     | 1.0×10 <sup>7</sup>                               | 2.7×10 <sup>-4</sup>                              | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Ar-41 .....            | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>9</sup>                        | 2.7×10 <sup>-2</sup>                       |
| As-72 .....            | Arsenic (33) .....        | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| As-73 .....            | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| As-74 .....            | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| As-76 .....            | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| As-77 .....            | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| At-211 .....           | Astatine (85) .....       | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Au-193 .....           | Gold (79) .....           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Au-194 .....           | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Au-195 .....           | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Au-198 .....           | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Au-199 .....           | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ba-131 .....           | Barium (56) .....         | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ba-133 .....           | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ba-133m .....          | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |

| Symbol of radionuclide     | Element and atomic number | Activity concentration for exempt material (Bq/g) | Activity concentration for exempt material (Ci/g) | Activity limit for exempt consignment (Bq) | Activity limit for exempt consignment (Ci) |
|----------------------------|---------------------------|---------------------------------------------------|---------------------------------------------------|--------------------------------------------|--------------------------------------------|
| Ba-140 (b) .....           | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Be-7 .....                 | Beryllium (4) .....       | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Be-10 .....                | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Bi-205 .....               | Bismuth (83) .....        | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Bi-206 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Bi-207 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Bi-210 .....               | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Bi-210m .....              | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Bi-212 (b) .....           | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Bk-247 .....               | Berkelium (97) .....      | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Bk-249 .....               | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Br-76 .....                | Bromine (35) .....        | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Br-77 .....                | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Br-82 .....                | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| C-11 .....                 | Carbon (6) .....          | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| C-14 .....                 | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Ca-41 .....                | Calcium (20) .....        | 1.0×10 <sup>5</sup>                               | 2.7×10 <sup>-6</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Ca-45 .....                | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Ca-47 .....                | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cd-109 .....               | Cadmium (48) .....        | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cd-113m .....              | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cd-115 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cd-115m .....              | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ce-139 .....               | Cerium (58) .....         | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ce-141 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Ce-143 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ce-144 (b) .....           | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cf-248 .....               | Californium (98) .....    | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cf-249 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Cf-250 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cf-251 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Cf-252 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cf-253 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cf-254 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Cl-36 .....                | Chlorine (17) .....       | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cl-38 .....                | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cm-240 .....               | Curium (96) .....         | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cm-241 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cm-242 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cm-243 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cm-244 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cm-245 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Cm-246 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Cm-247 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cm-248 .....               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Co-55 .....                | Cobalt (27) .....         | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Co-56 .....                | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Co-57 .....                | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Co-58 .....                | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Co-58m .....               | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Co-60 .....                | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cr-51 .....                | Chromium (24) .....       | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Cs-129 .....               | Cesium (55) .....         | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cs-131 .....               | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cs-132 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cs-134 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cs-134m .....              | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cs-135 .....               | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Cs-136 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Cs-137 (b) .....           | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Cu-64 .....                | Copper (29) .....         | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Cu-67 .....                | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Dy-159 .....               | Dysprosium (66) .....     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Dy-165 .....               | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Dy-166 .....               | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Er-169 .....               | Erbium (68) .....         | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Er-171 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Eu-147 .....               | Europium (63) .....       | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Eu-148 .....               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Eu-149 .....               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Eu-150 (short lived) ..... | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |

| Symbol of radionuclide | Element and atomic number | Activity concentration for exempt material (Bq/g) | Activity concentration for exempt material (Ci/g) | Activity limit for exempt consignment (Bq) | Activity limit for exempt consignment (Ci) |
|------------------------|---------------------------|---------------------------------------------------|---------------------------------------------------|--------------------------------------------|--------------------------------------------|
| Eu-150 (long lived)    |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Eu-152                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Eu-152m                |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Eu-154                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Eu-155                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Eu-156                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| F-18                   | Fluorine (9)              | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Fe-52                  | Iron (26)                 | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Fe-55                  |                           | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Fe-59                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Fe-60                  |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Ga-67                  | Gallium (31)              | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ga-68                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Ga-72                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Gd-146                 | Gadolinium (64)           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Gd-148                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Gd-153                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Gd-159                 |                           | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ge-68                  | Germanium (32)            | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Ge-71                  |                           | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>8</sup>                        | 2.7×10 <sup>-3</sup>                       |
| Ge-77                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Hf-172                 | Hafnium (72)              | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Hf-175                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Hf-181                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Hf-182                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Hg-194                 | Mercury (80)              | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Hg-195m                |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Hg-197                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Hg-197m                |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Hg-203                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Ho-166                 | Holmium (67)              | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Ho-166m                |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| I-123                  | Iodine (53)               | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| I-124                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| I-125                  |                           | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| I-126                  |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| I-129                  |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| I-131                  |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| I-132                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| I-133                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| I-134                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| I-135                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| In-111                 | Indium (49)               | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| In-113m                |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| In-114m                |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| In-115m                |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ir-189                 | Iridium (77)              | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Ir-190                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Ir-192                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Ir-194                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| K-40                   | Potassium (19)            | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| K-42                   |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| K-43                   |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Kr-81                  | Krypton (36)              | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Kr-85                  |                           | 1.0×10 <sup>5</sup>                               | 2.7×10 <sup>-6</sup>                              | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Kr-85m                 |                           | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>10</sup>                       | 2.7×10 <sup>-1</sup>                       |
| Kr-87                  |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>9</sup>                        | 2.7×10 <sup>-2</sup>                       |
| La-137                 | Lanthanum (57)            | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| La-140                 |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Lu-172                 | Lutetium (71)             | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Lu-173                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Lu-174                 |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Lu-174m                |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Lu-177                 |                           | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Mg-28                  | Magnesium (12)            | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Mn-52                  | Manganese (25)            | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Mn-53                  |                           | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>9</sup>                        | 2.7×10 <sup>-2</sup>                       |
| Mn-54                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Mn-56                  |                           | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Mo-93                  | Molybdenum (42)           | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>8</sup>                        | 2.7×10 <sup>-3</sup>                       |
| Mo-99                  |                           | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |

| Symbol of radionuclide | Element and atomic number | Activity concentration for exempt material (Bq/g) | Activity concentration for exempt material (Ci/g) | Activity limit for exempt consignment (Bq) | Activity limit for exempt consignment (Ci) |
|------------------------|---------------------------|---------------------------------------------------|---------------------------------------------------|--------------------------------------------|--------------------------------------------|
| N-13                   | Nitrogen (7)              | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^9$                          | $2.7 \times 10^{-2}$                       |
| Na-22                  | Sodium (11)               | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Na-24                  |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Nb-93m                 | Niobium (41)              | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Nb-94                  |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Nb-95                  |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Nb-97                  |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Nd-147                 | Neodymium (60)            | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Nd-149                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Ni-59                  | Nickel (28)               | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Ni-63                  |                           | $1.0 \times 10^5$                                 | $2.7 \times 10^{-6}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Ni-65                  |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Np-235                 | Neptunium (93)            | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Np-236 (short-lived)   |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Np-236 (long-lived)    |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Np-237 (b)             |                           | 1.0                                               | $2.7 \times 10^{-11}$                             | $1.0 \times 10^3$                          | $2.7 \times 10^{-8}$                       |
| Np-239                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Os-185                 | Osmium (76)               | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Os-191                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Os-191m                |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Os-193                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Os-194                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| P-32                   | Phosphorus (15)           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| P-33                   |                           | $1.0 \times 10^5$                                 | $2.7 \times 10^{-6}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Pa-230                 | Protactinium (91)         | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pa-231                 |                           | 1.0                                               | $2.7 \times 10^{-11}$                             | $1.0 \times 10^3$                          | $2.7 \times 10^{-8}$                       |
| Pa-233                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Pb-201                 | Lead (82)                 | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pb-202                 |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pb-203                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pb-205                 |                           | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Pb-210 (b)             |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Pb-212 (b)             |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Pd-103                 | Palladium (46)            | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Pd-107                 |                           | $1.0 \times 10^5$                                 | $2.7 \times 10^{-6}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Pd-109                 |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pm-143                 | Promethium (61)           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pm-144                 |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pm-145                 |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Pm-147                 |                           | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Pm-148m                |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pm-149                 |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pm-151                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Po-210                 | Polonium (84)             | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Pr-142                 | Praseodymium (59)         | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Pr-143                 |                           | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pt-188                 | Platinum (78)             | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pt-191                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pt-193                 |                           | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Pt-193m                |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Pt-195m                |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pt-197                 |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pt-197m                |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Pu-236                 | Plutonium (94)            | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Pu-237                 |                           | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Pu-238                 |                           | 1.0                                               | $2.7 \times 10^{-11}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Pu-239                 |                           | 1.0                                               | $2.7 \times 10^{-11}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Pu-240                 |                           | 1.0                                               | $2.7 \times 10^{-11}$                             | $1.0 \times 10^3$                          | $2.7 \times 10^{-8}$                       |
| Pu-241                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Pu-242                 |                           | 1.0                                               | $2.7 \times 10^{-11}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Pu-244                 |                           | 1.0                                               | $2.7 \times 10^{-11}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Ra-223 (b)             | Radium (88)               | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Ra-224 (b)             |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Ra-225                 |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Ra-226 (b)             |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Ra-228 (b)             |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Rb-81                  | Rubidium (37)             | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Rb-83                  |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Rb-84                  |                           | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Rb-86                  |                           | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Rb-87                  |                           | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |

| Symbol of radionuclide    | Element and atomic number | Activity concentration for exempt material (Bq/g) | Activity concentration for exempt material (Ci/g) | Activity limit for exempt consignment (Bq) | Activity limit for exempt consignment (Ci) |
|---------------------------|---------------------------|---------------------------------------------------|---------------------------------------------------|--------------------------------------------|--------------------------------------------|
| Rb(nat) .....             | .....                     | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Re-184 .....              | Rhenium (75) .....        | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Re-184m .....             | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Re-186 .....              | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Re-187 .....              | .....                     | $1.0 \times 10^6$                                 | $2.7 \times 10^{-5}$                              | $1.0 \times 10^9$                          | $2.7 \times 10^{-2}$                       |
| Re-188 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Re-189 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Re(nat) .....             | .....                     | $1.0 \times 10^6$                                 | $2.7 \times 10^{-5}$                              | $1.0 \times 10^9$                          | $2.7 \times 10^{-2}$                       |
| Rh-99 .....               | Rhodium (45) .....        | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Rh-101 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Rh-102 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Rh-102m .....             | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Rh-103m .....             | .....                     | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Rh-105 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Rn-222 (b) .....          | Radon (86) .....          | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Ru-97 .....               | Ruthenium (44) .....      | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Ru-103 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Ru-105 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Ru-106 (b) .....          | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| S-35 .....                | Sulphur (16) .....        | $1.0 \times 10^5$                                 | $2.7 \times 10^{-6}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Sb-122 .....              | Antimony (51) .....       | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Sb-124 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sb-125 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sb-126 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Sc-44 .....               | Scandium (21) .....       | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Sc-46 .....               | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sc-47 .....               | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sc-48 .....               | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Se-75 .....               | Selenium (34) .....       | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Se-79 .....               | .....                     | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Si-31 .....               | Silicon (14) .....        | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Si-32 .....               | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sm-145 .....              | Samarium (62) .....       | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Sm-147 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Sm-151 .....              | .....                     | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Sm-153 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sn-113 .....              | Tin (50) .....            | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Sn-117m .....             | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sn-119m .....             | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Sn-121m .....             | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Sn-123 .....              | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sn-125 .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Sn-126 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Sr-82 .....               | Strontium (38) .....      | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Sr-85 .....               | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sr-85m .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Sr-87m .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sr-89 .....               | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Sr-90 (b) .....           | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Sr-91 .....               | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Sr-92 .....               | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| T(H-3) .....              | Tritium (1) .....         | $1.0 \times 10^6$                                 | $2.7 \times 10^{-5}$                              | $1.0 \times 10^9$                          | $2.7 \times 10^{-2}$                       |
| Ta-178 (long-lived) ..... | Tantalum (73) .....       | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Ta-179 .....              | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Ta-182 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^4$                          | $2.7 \times 10^{-7}$                       |
| Tb-157 .....              | Terbium (65) .....        | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Tb-158 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Tb-160 .....              | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Tc-95m .....              | Technetium (43) .....     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Tc-96 .....               | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Tc-96m .....              | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Tc-97 .....               | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^8$                          | $2.7 \times 10^{-3}$                       |
| Tc-97m .....              | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Tc-98 .....               | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Tc-99 .....               | .....                     | $1.0 \times 10^4$                                 | $2.7 \times 10^{-7}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Tc-99m .....              | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Te-121 .....              | Tellurium (52) .....      | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |
| Te-121m .....             | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |
| Te-123m .....             | .....                     | $1.0 \times 10^2$                                 | $2.7 \times 10^{-9}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Te-125m .....             | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^7$                          | $2.7 \times 10^{-4}$                       |
| Te-127 .....              | .....                     | $1.0 \times 10^3$                                 | $2.7 \times 10^{-8}$                              | $1.0 \times 10^6$                          | $2.7 \times 10^{-5}$                       |



| Symbol of radionuclide                             | Element and atomic number | Activity concentration for exempt material (Bq/g) | Activity concentration for exempt material (Ci/g) | Activity limit for exempt consignment (Bq) | Activity limit for exempt consignment (Ci) |
|----------------------------------------------------|---------------------------|---------------------------------------------------|---------------------------------------------------|--------------------------------------------|--------------------------------------------|
| Te-127m                                            | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Te-129                                             | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Te-129m                                            | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Te-131m                                            | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Te-132                                             | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Th-227                                             | Thorium (90)              | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Th-228 (b)                                         | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Th-229 (b)                                         | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Th-230                                             | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Th-231                                             | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Th-232                                             | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Th-234 (b)                                         | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Th (nat) (b)                                       | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| Ti-44                                              | Titanium (22)             | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Tl-200                                             | Thallium (81)             | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Tl-201                                             | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Tl-202                                             | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Tl-204                                             | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Tm-167                                             | Thulium (69)              | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Tm-170                                             | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Tm-171                                             | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>8</sup>                        | 2.7×10 <sup>-3</sup>                       |
| U-230 (fast lung absorption) (b),(d)               | Uranium (92)              | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| U-230 (medium lung absorption) (e)                 | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-230 (slow lung absorption) (f)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-232 (fast lung absorption) (b),(d)               | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| U-232 (medium lung absorption) (e)                 | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-232 (slow lung absorption) (f)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-233 (fast lung absorption) (d)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-233 (medium lung absorption) (e)                 | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| U-233 (slow lung absorption) (f)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| U-234 (fast lung absorption) (d)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-234 (medium lung absorption) (e)                 | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| U-234 (slow lung absorption) (f)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| U-235 (all lung absorption types) (b),(d),(e),(f). | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-236 (fast lung absorption) (d)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-236 (medium lung absorption) (e)                 | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| U-236 (slow lung absorption) (f)                   | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U-238 (all lung absorption types) (b),(d),(e),(f). | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| U (nat) (b)                                        | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| U (enriched to 20% or less)(g)                     | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| U (dep)                                            | .....                     | 1.0                                               | 2.7×10 <sup>-11</sup>                             | 1.0×10 <sup>3</sup>                        | 2.7×10 <sup>-8</sup>                       |
| V-48                                               | Vanadium (23)             | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| V-49                                               | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| W-178                                              | Tungsten (74)             | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| W-181                                              | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| W-185                                              | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| W-187                                              | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| W-188                                              | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Xe-122                                             | Xenon (54)                | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>9</sup>                        | 2.7×10 <sup>-2</sup>                       |
| Xe-123                                             | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>9</sup>                        | 2.7×10 <sup>-2</sup>                       |
| Xe-127                                             | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Xe-131m                                            | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Xe-133                                             | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>4</sup>                        | 2.7×10 <sup>-7</sup>                       |
| Xe-135                                             | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>10</sup>                       | 2.7×10 <sup>-1</sup>                       |
| Y-87                                               | Yttrium (39)              | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Y-88                                               | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Y-90                                               | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Y-91                                               | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Y-91m                                              | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Y-92                                               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Y-93                                               | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>5</sup>                        | 2.7×10 <sup>-6</sup>                       |
| Yb-169                                             | Ytterbium (70)            | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Yb-175                                             | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Zn-65                                              | Zinc (30)                 | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Zn-69                                              | .....                     | 1.0×10 <sup>4</sup>                               | 2.7×10 <sup>-7</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Zn-69m                                             | .....                     | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Zr-88                                              | Zirconium (40)            | 1.0×10 <sup>2</sup>                               | 2.7×10 <sup>-9</sup>                              | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |
| Zr-93 (b)                                          | .....                     | 1.0×10 <sup>3</sup>                               | 2.7×10 <sup>-8</sup>                              | 1.0×10 <sup>7</sup>                        | 2.7×10 <sup>-4</sup>                       |
| Zr-95                                              | .....                     | 1.0×10 <sup>1</sup>                               | 2.7×10 <sup>-10</sup>                             | 1.0×10 <sup>6</sup>                        | 2.7×10 <sup>-5</sup>                       |

| Symbol of radionuclide | Element and atomic number | Activity concentration for exempt material (Bq/g) | Activity concentration for exempt material (Ci/g) | Activity limit for exempt consignment (Bq) | Activity limit for exempt consignment (Ci) |
|------------------------|---------------------------|---------------------------------------------------|---------------------------------------------------|--------------------------------------------|--------------------------------------------|
| Zr-97 (b) .....        | .....                     | $1.0 \times 10^1$                                 | $2.7 \times 10^{-10}$                             | $1.0 \times 10^5$                          | $2.7 \times 10^{-6}$                       |

<sup>a</sup>[Reserved]

<sup>b</sup>Parent nuclides and their progeny included in secular equilibrium are listed in the following:

Sr-90 Y-90  
 Zr-93 Nb-93m  
 Zr-97 Nb-97  
 Ru-106 Rh-106  
 Cs-137 Ba-137m  
 Ce-134 La-134  
 Ce-144 Pr-144  
 Ba-140 La-140  
 Bi-212 Tl-208 (0.36), Po-212 (0.64)  
 Pb-210 Bi-210, Po-210  
 Pb-212 Bi-212, Tl-208 (0.36), Po-212 (0.64)  
 Rn-220 Po-216  
 Rn-222 Po-218, Pb-214, Bi-214, Po-214  
 Ra-223 Rn-219, Po-215, Pb-211, Bi-211, Tl-207  
 Ra-224 Rn-220, Po-216, Pb-212, Bi-212, Tl-208(0.36), Po-212 (0.64)  
 Ra-226 Rn-222, Po-218, Pb-214, Bi-214, Po-214, Pb-210, Bi-210, Po-210  
 Ra-228 Ac-228  
 Th-226 Ra-222, Rn-218, Po-214  
 Th-228 Ra-224, Rn-220, Po-216, Pb-212, Bi-212, Tl-208 (0.36), Po-212 (0.64)  
 Th-229 Ra-225, Ac-225, Fr-221, At-217, Bi-213, Po-213, Pb-209  
 Th-nat Ra-228, Ac-228, Th-228, Ra-224, Rn-220, Po-216, Pb-212, Bi-212, Tl-208 (0.36), Po-212 (0.64)  
 Th-234 Pa-234m  
 U-230 Th-226, Ra-222, Rn-218, Po-214  
 U-232 Th-228, Ra-224, Rn-220, Po-216, Pb-212, Bi-212, Tl-208 (0.36), Po-212 (0.64)  
 U-235 Th-231  
 U-238 Th-234, Pa-234m  
 U-nat Th-234, Pa-234m, U-234, Th-230, Ra-226, Rn-222, Po-218, Pb-214, Bi-214, Po-214, Pb-210, Bi-210, Po-210  
 U-240 Np-240m  
 Np-237 Pa-233  
 Am-242 mAm-242  
 Am-243 Np-239

<sup>c</sup>[Reserved]

<sup>d</sup>These values apply only to compounds of uranium that take the chemical form of UF<sub>6</sub>, UO<sub>2</sub>F<sub>2</sub> and UO<sub>2</sub>(NO<sub>3</sub>)<sub>2</sub> in both normal and accident conditions of transport.

<sup>e</sup>These values apply only to compounds of uranium that take the chemical form of UO<sub>3</sub>, UF<sub>4</sub>, UCl<sub>4</sub> and hexavalent compounds in both normal and accident conditions of transport.

<sup>f</sup>These values apply to all compounds of uranium other than those specified in notes (d) and (e) of this table.

<sup>g</sup>These values apply to unirradiated uranium only.

[69 FR 3685, Jan. 26, 2004]

#### § 173.441 Radiation level limitations and exclusive use provisions.

(a) Except as provided in paragraph (b) of this section, each package of Class 7 (radioactive) materials offered for transportation must be designed and prepared for shipment, so that under conditions normally incident to transportation, the radiation level does not exceed 2 mSv/hour (200 mrem/hour) at any point on the external surface of the package, and the transport index does not exceed 10.

(b) A package which exceeds the radiation level limits specified in paragraph (a) of this section must be transported by exclusive use shipment, and the radiation levels for such shipment may not exceed the following during transportation:

(1) 2 mSv/h (200 mrem/h) on the external surface of the package unless the following conditions are met, in which

case the limit is 10 mSv/h (1000 mrem/h):

(i) The shipment is made in a closed transport vehicle;

(ii) The package is secured within the vehicle so that its position remains fixed during transportation; and

(iii) There are no loading or unloading operations between the beginning and end of the transportation;

(2) 2 mSv/h (200 mrem/h) at any point on the outer surfaces of the vehicle, including the top and underside of the vehicle; or in the case of a flat-bed style vehicle, at any point on the vertical planes projected from the outer edges of the vehicle, on the upper surface of the load or enclosure if used, and on the lower external surface of the vehicle;

(3) 0.1 mSv/h (10 mrem/h) at any point 2 m (6.6 feet) from the outer lateral surfaces of the vehicle (excluding the top and underside of the vehicle); or in the case of a flat-bed style vehicle, at

## § 173.442

any point 2 m (6.6 feet) from the vertical planes projected by the outer edges of the vehicle (excluding the top and underside of the vehicle); and

(4) 0.02 mSv/h (2mrem/h) in any normally occupied space, except that this provision does not apply to carriers if they operate under the provisions of a State or federally regulated radiation protection program and if personnel under their control who are in such an occupied space wear radiation dosimetry devices.

(c) For shipments made under the provisions of paragraph (b) of this section, the offeror shall provide specific written instructions for maintenance of the exclusive use shipment controls to the carrier. The instructions must be included with the shipping paper information. The instructions must be sufficient so that, when followed, they will cause the carrier to avoid actions that will unnecessarily delay delivery or unnecessarily result in increased radiation levels or radiation exposures to transport workers or members of the general public.

(d) Conveyance limits on the sum of package transport indices are as follows:

(1) Except for shipments by cargo aircraft only or by seagoing vessel, the sum of transport indices for a non-exclusive use shipment may not exceed 50.

(2) Where a consignment is transported under exclusive use, there is no limit on the sum of the transport indices aboard a single conveyance. The conditions of paragraphs (b)(2), (b)(3), (b)(4) and (c) must be met.

(3) Provisions for shipments of Class 7 (radioactive) materials by air are described in §§175.700–175.705 of this subchapter.

(4) Provisions for shipment of Class 7 (radioactive) materials by vessel are described in §§176.700–176.720 of this subchapter.

(e) A package exceeding the maximum surface radiation level or maximum transport index prescribed in paragraph (a) of this section may not be transported by aircraft.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended at 63 FR 48568, Sept. 10, 1998; 66 FR 45380, Aug. 28, 2001; 69 FR 3691, Jan. 26, 2004]

## 49 CFR Ch. I (10–1–08 Edition)

### § 173.442 Thermal limitations.

A package of Class 7 (radioactive) material must be designed, constructed, and loaded so that—

(a) The heat generated within the package by the radioactive contents will not, during conditions normally incident to transport, affect the integrity of the package; and

(b) The temperature of the accessible external surfaces of the loaded package will not, assuming still air in the shade at an ambient temperature of 38 °C (100 °F), exceed either—

(1) 50 °C (122 °F) in other than an exclusive use shipment; or

(2) 85 °C (185 °F) in an exclusive use shipment.

### § 173.443 Contamination control.

(a) The level of non-fixed (removable) radioactive contamination on the external surfaces of each package offered for transport must be kept as low as reasonable achievable. The level of non-fixed radioactive contamination may not exceed the limits set forth in Table 9 and must be determined by either:

(1) Wiping an area of 300 cm<sup>2</sup> of the surface concerned with an absorbent material, using moderate pressure, and measuring the activity on the wiping material. Sufficient measurements must be taken in the most appropriate locations to yield a representative assessment of the non-fixed contamination levels. The amount of radioactivity measured on any single wiping material, divided by the surface area wiped and divided by the efficiency of the wipe procedure (the fraction of removable contamination transferred from the surface to the absorbent material), may not exceed the limits set forth in Table 9 at any time during transport. For this purpose the actual wipe efficiency may be used, or the wipe efficiency may be assumed to be 0.10; or

(2) Alternatively, the level of non-fixed radioactive contamination may be determined by using other methods of equal or greater efficiency.

Table 9 is as follows:

TABLE 9—NON-FIXED EXTERNAL RADIOACTIVE CONTAMINATION LIMITS FOR PACKAGES

| Contaminant                                                | Maximum permissible limits |                     |                     |
|------------------------------------------------------------|----------------------------|---------------------|---------------------|
|                                                            | Bq/cm <sup>2</sup>         | uCi/cm <sup>2</sup> | dpm/cm <sup>2</sup> |
| 1. Beta and gamma emitters and low toxicity alpha emitters | 4                          | 10 <sup>-4</sup>    | 220                 |
| 2. All other alpha emitting radionuclides .....            | 0.4                        | 10 <sup>-5</sup>    | 22                  |

(b) Except as provided in paragraph (d) of this section, in the case of packages transported as exclusive use shipments by rail or public highway only, the removable (non-fixed) radioactive contamination on any package at any time during transport may not exceed ten times the levels prescribed in paragraph (a) of this section. The levels at the beginning of transport may not exceed the levels prescribed in paragraph (a) of this section.

(c) Except as provided in paragraph (d) of this section, each transport vehicle used for transporting Class 7 (radioactive) materials as an exclusive use shipment that utilizes the provisions of paragraph (b) of this section must be surveyed with appropriate radiation detection instruments after each use. A vehicle may not be returned to service until the radiation dose rate at each accessible surface is 0.005 mSv per hour (0.5 mrem per hour) or less, and there is no significant removable (non-fixed) radioactive surface contamination as specified in paragraph (a) of this section.

(d) Paragraphs (b) and (c) of this section do not apply to any closed transport vehicle used solely for the transportation by highway or rail of Class 7 (radioactive) material packages with contamination levels that do not exceed 10 times the levels prescribed in paragraph (a) of this section if—

(1) A survey of the interior surfaces of the empty vehicle shows that the radiation dose rate at any point does not exceed 0.1 mSv per hour (10 mrem per hour) at the surface or 0.02 mSv per hour (2 mrem per hour) at 1 m (3.3 feet) from the surface;

(2) Each vehicle is stenciled with the words “For Radioactive Materials Use Only” in letters at least 76 millimeters (3 inches) high in a conspicuous place

on both sides of the exterior of the vehicle; and

(3) Each vehicle is kept closed except for loading or unloading.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by Amdt. 173–244, 61 FR 20753, May 8, 1996; 66 FR 45380, Aug. 28, 2001; 69 FR 3691, Jan. 26, 2004; 69 FR 55119, Sept. 13, 2004]

#### § 173.447 Storage incident to transportation—general requirements.

The following requirements apply to temporary storage during the course of transportation but not to Nuclear Regulatory Commission or Agreement State-licensed facilities or U.S. Government-owned or contracted facilities.

(a) The number of packages and overpacks bearing FISSILE labels stored in any one storage area, such as a transit area, terminal building, storeroom, waterfront pier, or assembly yard, must be limited so that the total sum of the criticality safety indices in any individual group of such packages and overpacks does not exceed 50. Groups of such packages and overpacks must be stored so as to maintain a spacing of at least 6 m (20 feet) from all other groups of such packages and overpacks.

(b) Storage requirements for Class 7 (radioactive) material transported in vessels are described in subpart M of part 176 of this subchapter.

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by 66 FR 45380, Aug. 28, 2001; 69 FR 3691, Jan. 26, 2004]

#### § 173.448 General transportation requirements.

(a) Each shipment of Class 7 (radioactive) materials must be secured to prevent shifting during normal transportation conditions.

(b) Except as provided in §§ 174.81, 176.83, and 177.848 of this subchapter, or as otherwise required by the Competent Authority in the applicable certificate, a package or overpack of Class 7 (radioactive) materials may be carried among packaged general cargo without special stowage provisions, if—

(1) The heat output in watts does not exceed 0.1 times the minimum package dimension in centimeters; or

(2) The average surface heat flux of the package or overpack does not exceed 15 watts per square meter and the

**§ 173.453**

**49 CFR Ch. I (10–1–08 Edition)**

immediately surrounding cargo is not in sacks or bags or otherwise in a form that would seriously impede air circulation for heat removal.

(c) Packages or overpacks bearing labels prescribed in §172.403 of this subchapter may not be carried in compartments occupied by passengers, except in those compartments exclusively reserved for couriers accompanying those packages.

(d) Mixing of different kinds of packages that include fissile packages is authorized only in accordance with §173.459.

(e) No person shall offer for transportation or transport aboard a passenger-carrying aircraft any single package or overpack with a transport index greater than 3.0.

(f) No person shall offer for transportation or transport aboard a passenger-carrying aircraft any Class 7 (radioactive) material unless that material is intended for use in, or incident to, research, medical diagnosis or treatment.

(g) If an overpack is used to consolidate individual packages or to enclose a single package of Class 7 (radioactive) materials, the package(s) must comply with the packaging, marking, and labeling requirements of this subchapter, and:

(1) The overpack must be labeled as prescribed in §172.403(h) of this subchapter;

(2) The overpack must be marked as prescribed in subpart D of part 172 of this subchapter and §173.25(a); and

(3) The transport index of the overpack may not exceed 3.0 for passenger-carrying aircraft shipments, or 10.0 for cargo-aircraft shipments.

[69 FR 3691, Jan. 26, 2004]

**§ 173.453 Fissile materials—exceptions.**

Fissile materials meeting the requirements of at least one of the paragraphs (a) through (f) of this section are excepted from the requirements of this subpart for fissile materials, including the requirements of §§173.457 and 173.459, but are subject to all other requirements of this subpart, except as noted.

(a) An individual package containing 2 grams or less of fissile material.

(b) An individual or bulk packaging containing 15 grams or less of fissile

material provided the package has at least 200 grams of solid nonfissile material for every gram of fissile material. Lead, beryllium, graphite, and hydrogenous material enriched in deuterium may be present in the package but must not be included in determining the required mass for solid nonfissile material.

(c) Low concentrations of solid fissile material commingled with solid nonfissile material, provide that:

(1) There is at least 2000 grams of nonfissile material for every gram of fissile material, and

(2) There is no more than 180 grams of fissile material distributed within 360 kg of contiguous nonfissile material. Lead, beryllium, graphite, and hydrogenous material enriched in deuterium may be present in the package but must not be included in determining the required mass of solid nonfissile material.

(d) Uranium enriched in uranium-235 to a maximum of 1 percent by weight, and with total plutonium and uranium-233 content of up to 1 percent of the mass of uranium-235, provided that the mass of any beryllium, graphite, and hydrogenous material enriched in deuterium constitute less than 5 percent of the uranium mass.

(e) Liquid solutions of uranyl nitrate enriched in uranium-235 to a maximum of 2 percent by mass, with a total plutonium and uranium-233 content not exceeding 0.002 percent of the mass of uranium, and with a minimum nitrogen to uranium atomic ratio (N/U) of 2. The material must be contained in at least a DOT Type A package.

(f) Packages containing, individually, a total plutonium mass of not more than 1000 grams, of which not more than 20 percent by mass may consist of plutonium-239, plutonium-241, or any combination of these radionuclides.

[69 FR 3692, Jan. 26, 2004]

**§ 173.457 Transportation of fissile material packages—specific requirements.**

(a) Packages containing fissile radioactive material which are not excepted under §173.453 must be assigned by the offeror, in accordance with their definitions in §173.403, a criticality safety index (CSI) and a transport index (TI).

(b) Fissile material packages and conveyances transporting fissile material packages must satisfy the radiation level restrictions of § 173.441.

(c) Except for consignments under exclusive use, the CSI of any package or overpack may not exceed 50. A fissile material package with CSI greater than 50 must be transported by exclusive use.

(d) For non-exclusive use shipments of fissile material packages, except on vessels, the total sum of CSI's in a freight container or on a conveyance may not exceed 50.

(e) For exclusive use shipments of fissile material packages, except on vessels, the total sum of CSI's in a freight container or on a conveyance may not exceed 100.

(f) Exclusive use shipments of fissile material packages must satisfy the radiation level and administrative requirements of § 173.441(b).

(g) The number of packages, overpacks and freight containers containing fissile material stored in transit in any one storage area must be so limited that the total sum of the CSI's in any group of packages, overpacks or freight containers does not exceed 50. Groups of packages shall be stored so as to maintain a spacing of at least 6 m (20 ft) between the closest surfaces of any two groups.

(h) Provisions for shipment by vessel of Class 7 (radioactive) material packages, including fissile material packages by vessel are described in §§ 176.700–176.720 of this subchapter.

[69 FR 3692, Jan. 26, 2004]

**§ 173.459 Mixing of fissile material packages with non-fissile or fissile-excepted material packages.**

Mixing of fissile material packages with other types of Class 7 (radioactive) materials in any conveyance or storage location is authorized only if the TI of any single package does not exceed 10, the CSI of any single package does not exceed 50, and the provisions of §§ 173.441 and 173.457 are satisfied.

[69 FR 3692, Jan. 26, 2004]

**§ 173.461 Demonstration of compliance with tests.**

(a) Compliance with the design requirements in § 173.412 and the test requirements in §§ 173.465 through 173.469 must be shown by any of the methods prescribed in this paragraph, or by a combination of these methods appropriate for the particular feature being evaluated:

(1) Performance of tests with prototypes or samples of the specimens representing LSA-III, special form Class 7 (radioactive) material, or packaging, in which case the contents of the packaging for the test must simulate as closely as practicable the expected range of physical properties of the radioactive contents or packaging to be tested, must be prepared as normally presented for transport. The use of non-radioactive substitute contents is encouraged provided that the results of the testing take into account the radioactive characteristics of the contents for which the package is being tested;

(2) Reference to a previous, satisfactory demonstration of compliance of a sufficiently similar nature;

(3) Performance of tests with models of appropriate scale incorporating those features that are significant with respect to the item under investigation, when engineering experience has shown results of those tests to be suitable for design purposes. When a scale model is used, the need for adjusting certain test parameters, such as the penetrator diameter or the compressive load, must be taken into account; or

(4) Calculations or reasoned evaluation, using reliable and conservative procedures and parameters.

(b) With respect to the initial conditions for the tests under §§ 173.465 through 173.469, except for the water immersion tests, compliance must be based upon the assumption that the package is in equilibrium at an ambient temperature of 38 °C (100 °F).

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended by 63 FR 52850, Oct. 1, 1998]

**§ 173.462 Preparation of specimens for testing.**

(a) Each specimen (i.e., sample, prototype or scale model) must be examined before testing to identify and record faults or damage, including:

- (1) Divergence from the specifications or drawings;
- (2) Defects in construction;
- (3) Corrosion or other deterioration; and
- (4) Distortion of features.

(b) Any deviation found under paragraph (a) of this section from the specified design must be corrected or appropriately taken into account in the subsequent evaluation.

(c) The containment system of the packaging must be clearly specified.

(d) The external features of the specimen must be clearly identified so that reference may be made to any part of it.

**§ 173.465 Type A packaging tests.**

(a) The packaging, with contents, must be capable of withstanding the water spray, free drop, stacking and penetration tests prescribed in this section. One prototype may be used for all tests if the requirements of paragraph (b) of this section are met.

(b) *Water spray test.* The water spray test must precede each test or test sequence prescribed in this section. The water spray test must simulate exposure to rainfall of approximately 5 cm (2 inches) per hour for at least one hour. The time interval between the end of the water spray test and the beginning of the next test must be such that the water has soaked in to the maximum extent without appreciable drying of the exterior of the specimen. In the absence of evidence to the contrary, this interval may be assumed to be two hours if the water spray is applied from four different directions simultaneously. However, no time interval may elapse if the water spray is applied from each of the four directions consecutively.

(c) *Free drop test.* The specimen must drop onto the target so as to suffer maximum damage to the safety features being tested, and:

- (1) The height of the drop measured from the lowest point of the specimen to the upper surface of the target may

not be less than the distance specified in table 10, for the applicable package mass. The target must be as specified in § 173.465(c)(5). Table 10 is as follows:

**TABLE 10—FREE DROP DISTANCE FOR TESTING PACKAGES TO NORMAL CONDITIONS OF TRANSPORT**

| Package mass                                  | Free drop distance |        |
|-----------------------------------------------|--------------------|--------|
|                                               | Meters             | (Feet) |
| Kilograms (pounds)                            |                    |        |
| < Mass 5000 (11,000) .....                    | 1.2                | (4)    |
| 5,000 (11,000) Mass to 10,000 (22,000) .....  | 0.9                | (3)    |
| 10,000 (22,000) Mass to 15,000 (33,000) ..... | 0.6                | (2)    |
| > 15,000 (33,000) Mass .....                  | 0.3                | (1)    |

(2) For packages containing fissile material, the free drop test specified in paragraph (c)(1) of this section must be preceded by a free drop from a height of 0.3 m (1 foot) on each corner, or in the case of cylindrical packages, onto each of the quarters of each rim.

(3) For fiberboard or wood rectangular packages with a mass of 50 kg (110 pounds) or less, a separate specimen must be subjected to a free drop onto each corner from a height of 0.3 m (1 foot).

(4) For cylindrical fiberboard packages with a mass of 100 kg (220 pounds) or less, a separate specimen must be subjected to a free drop onto each of the quarters of each rim from a height of 0.3 m (1 foot).

(5) The target for the free drop test must be a flat, horizontal surface of such mass and rigidity that any increase in its resistance to displacement or deformation upon impact by the specimen would not significantly increase the damage to the specimen.

(d) *Stacking test.* (1) The specimen must be subjected for a period of at least 24 hours to a compressive load equivalent to the greater of the following:

- (i) Five times the mass of the actual package; or
- (ii) The equivalent of 13 kilopascals (1.9 psi) multiplied by the vertically projected area of the package.

(2) The compressive load must be applied uniformly to two opposite sides of the specimen, one of which must be the base on which the package would normally rest.

(e) *Penetration test.* For the penetration test, the specimen must be placed

on a rigid, flat, horizontal surface that will not move significantly while the test is being performed.

(1) A bar of 3.2 cm (1.25 inches) in diameter with a hemispherical end and a mass of 6 kg (13.2 pounds) must be dropped and directed to fall with its longitudinal axis vertical, onto the center of the weakest part of the specimen, so that, if it penetrates far enough, it will hit the containment system. The bar may not be significantly deformed by the test; and

(2) The height of the drop of the bar measured from its lower end to the intended point of impact on the upper surface of the specimen must be 1 m (3.3 feet) or greater.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended by Amdt. 173-244, 61 FR 20753, May 8, 1996; 66 FR 45380, Aug. 28, 2001; 69 FR 3692, Jan. 26, 2004; 70 FR 56099, Sept. 23, 2005]

**§ 173.466 Additional tests for Type A packagings designed for liquids and gases.**

(a) In addition to the tests prescribed in § 173.465, Type A packagings designed for liquids and gases must be capable of withstanding the following tests:

(1) *Free drop test.* The packaging specimen must drop onto the target so as to suffer the maximum damage to its containment. The height of the drop measured from the lowest part of the packaging specimen to the upper surface of the target must be 9 m (30 feet) or greater. The target must be as specified in § 173.465(c)(5).

(2) *Penetration test.* The specimen must be subjected to the test specified in § 173.465(e) except that the height of the drop must be 1.7 m (5.5 feet).

(b) [Reserved]

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 66 FR 45380, Aug. 28, 2001]

**§ 173.467 Tests for demonstrating the ability of Type B and fissile materials packagings to withstand accident conditions in transportation.**

Each Type B packaging or packaging for fissile material must meet the test requirements prescribed in 10 CFR part 71 for ability to withstand accident conditions in transportation.

**§ 173.468 Test for LSA-III material.**

(a) LSA-III Class 7 (radioactive) material must meet the test requirement of paragraph (b) of this section. Any differences between the material to be transported and the test material must be taken into account in determining whether the test requirements have been met.

(b) *Test method.* (1) The specimen representing no less than the entire contents of the package must be immersed for 7 days in water at ambient temperature.

(2) The volume of water to be used in the test must be sufficient to ensure that at the end of the test period the free volume of the unabsorbed and unreacted water remaining will be at least 10% of the volume of the specimen itself.

(3) The water must have an initial pH of 6-8 and a maximum conductivity of 10 micromho/cm at 20 °C (68 °F).

(4) The total activity of the free volume of water must be measured following the 7 day immersion test and must not exceed 0.1 A<sub>2</sub>.

**§ 173.469 Tests for special form Class 7 (radioactive) materials.**

(a) Special form Class 7 (radioactive) materials must meet the test requirements of paragraph (b) of this section. Each solid Class 7 (radioactive) material or capsule specimen to be tested must be manufactured or fabricated so that it is representative of the actual solid material or capsule that will be transported with the proposed radioactive content duplicated as closely as practicable. Any differences between the material to be transported and the test material, such as the use of non-radioactive contents, must be taken into account in determining whether the test requirements have been met. The following additional conditions apply:

(1) A different specimen may be used for each of the tests;

(2) The specimen may not break or shatter when subjected to the impact, percussion, or bending tests;

(3) The specimen may not melt or disperse when subjected to the heat test; and



(4) After each test, leaktightness or indispersibility of the specimen must be determined by—

(i) A method no less sensitive than the leaching assessment prescribed in paragraph (c) of this section. For a capsule resistant to corrosion by water, and which has an internal void volume greater than 0.1 milliliter, an alternative to the leaching assessment is a demonstration of leaktightness of  $10^{-4}$  torr-1/s ( $1.3 \times 10^{-4}$  atm-cm<sup>3</sup>/s) based on air at 25 °C (77 °F) and one atmosphere differential pressure for solid radioactive content, or  $10^{-6}$  torr-1/s ( $1.3 \times 10^{-6}$  atm-cm<sup>3</sup>/s) for liquid or gaseous radioactive content; or

(ii) A specimen that comprises or simulates Class 7 (radioactive) material contained in a sealed capsule need not be subjected to the leaching assessment specified in paragraph (c) of this section provided it is alternatively subjected to any of the volumetric leakage assessment tests prescribed in the International Organization for Standardization document ISO 9978–1992(E): “Radiation protection—Sealed radioactive sources—Leakage test methods” (IBR, see § 171.7 of this subchapter).

(b) *Test methods.*—(1) *Impact Test.* The specimen must fall onto the target from a height of 9 m (30 feet) or greater. The target must be as specified in § 173.465(c)(5).

(2) *Percussion Test.* (i) The specimen must be placed on a sheet of lead that is supported by a smooth solid surface, and struck by the flat face of a steel billet so as to produce an impact equivalent to that resulting from a free drop of 1.4 kg (3 pounds) through 1 m (3.3 feet).

(ii) The flat face of the billet must be 2.5 cm (1 inch) in diameter with the edges rounded off to a radius of 3 mm  $\pm 0.3$  mm (0.12 inch  $\pm 0.012$  inch).

(iii) The lead must be of hardness number 3.5 to 4.5 on the Vickers scale and thickness 2.5 cm (1 inch) or greater, and must cover an area greater than that covered by the specimen.

(iv) A fresh surface of lead must be used for each impact.

(v) The billet must strike the specimen so as to cause maximum damage.

(3) *Bending test.* (i) This test applies only to long, slender sources with a length of 10 cm (4 inches) or greater

and a length to width ratio of 10 or greater.

(ii) The specimen must be rigidly clamped in a horizontal position so that one half of its length protrudes from the face of the clamp.

(iii) The orientation of the specimen must be such that the specimen will suffer maximum damage when its free end is struck by the flat face of a steel billet.

(iv) The billet must strike the specimen so as to produce an impact equivalent to that resulting from a free vertical drop of 1.4 kg (3 pounds) through 1 m (3.3 feet).

(v) The flat face of the billet must be 2.5 cm (1 inch) in diameter with the edges rounded off to a radius of 3 mm  $\pm 0.3$  mm (.12 inch  $\pm 0.012$  inch).

(4) *Heat test.* The specimen must be heated in air to a temperature of not less than 800 °C (1475 °F), held at that temperature for a period of 10 minutes, and then allowed to cool.

(c) *Leaching assessment methods.* (1) For indispersible solid material—

(i) The specimen shall be immersed for seven days in water at ambient temperature. The volume of water to be used in the test shall be sufficient to ensure that at the end of the seven day test period the free volume of the unabsorbed and unreacted water remaining shall be at least 10% of the volume of the solid test sample itself. The water shall have an initial pH of 6–8 and a maximum conductivity of 1 mS/m (10 micromho/cm) at 20 °C (68 °F).

(ii) The water with specimen must then be heated to a temperature of 50 °C  $\pm 5^\circ$  (122 °F  $\pm 9^\circ$ ) and maintained at this temperature for four hours.

(iii) The activity of the water must then be determined.

(iv) The specimen shall then be kept for at least seven days in still air at not less than 30 °C (86 °F) and relative humidity not less than 90%.

(v) The specimen must then be immersed in water under the same conditions as in paragraph (c)(1)(i) of this section, and the water with specimen must be heated to 50 °C  $\pm 5^\circ$  (122 °F  $\pm 9^\circ$ ) and maintained at that temperature for four hours.

(vi) The activity of the water must then be determined. The activities determined in paragraph (c)(1)(iii) of this

section and this paragraph, (c)(1)(vi), may not exceed 2 kilobecquerels (0.05 microcurie).

(2) For encapsulated material—

(i) The specimen shall be immersed in water at ambient temperature. The water shall have an initial pH of 6–8 and a maximum conductivity of 1 mS/m (10 micromho/cm) at 20 °C (68 °F).

(ii) The water and specimen must be heated to a temperature of 50 °C  $\pm$ 5° (122 °F  $\pm$ 9°) and maintained at this temperature for four hours.

(iii) The activity of the water must then be determined.

(iv) The specimen shall then be kept for at least seven days in still air at not less than 30 °C (86 °F) and relative humidity not less than 90%.

(v) The process in paragraphs (c)(2)(i), (c)(2)(ii), and (c)(2)(iii) of this section must be repeated.

(vi) The activity determined in paragraph (c)(2)(iii) of this section may not exceed 2 kilobecquerels (0.05 microcurie).

(d) A specimen that comprises or simulates Class 7 (radioactive) material contained in a sealed capsule need not be subjected to—

(1) The impact test and the percussion test of this section provided that the mass of the special form radioactive material is less than 200 g and it is alternatively subjected to the Class 4 impact test prescribed in ISO 2919, “Sealed Radioactive Sources—Classification” (IBR, see §171.7 of this subchapter); and

(2) The heat test of this section, provided the specimen is alternatively subjected to the Class 6 temperature test specified in the International Organization for Standardization document ISO 2919–1980(e), “Sealed Radioactive Sources—Classification.” (see §171.7 of this subchapter)

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended at 63 FR 37461, July 10, 1998; 64 FR 51919, Sept. 27, 1999; 66 FR 45184, 45380, 45381, Aug. 28, 2001; 68 FR 75742, 75747, Dec. 31, 2003; 69 FR 3692, Jan. 26, 2004]

#### **§173.471 Requirements for U.S. Nuclear Regulatory Commission approved packages.**

In addition to the applicable requirements of the U.S. Nuclear Regulatory Commission (NRC) and other require-

ments of this subchapter, any offeror of a Type B(U), Type B(M), or fissile material package that has been approved by the NRC in accordance with 10 CFR part 71 must also comply with the following requirements:

(a) The offeror shall be registered with the USNRC as a party to the packaging approval, and make the shipment in compliance with the terms of the packaging approval;

(b) The outside of each package must be durably and legibly marked with the package identification marking indicated in the USNRC packaging approval;

(c) Each shipping paper related to the shipment of the package must bear the package identification marking indicated in the USNRC packaging approval;

(d) Before export shipment of the package, the offeror shall obtain a U.S. Competent Authority Certificate for that package design, or if one has already been issued, the offeror shall register in writing (including a description of the quality assurance program required by 10 CFR part 71) with the U.S. Competent Authority as a user of the certificate. (NOTE: The person who originally applies for a U.S. Competent Authority Certificate will be registered automatically.) The registration request must be sent to the Associate Administrator for Hazardous Materials Safety (PHH–23), Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington DC 20590–0001. Alternatively, the application with any attached supporting documentation in an appropriate format may be submitted by facsimile (fax) to (202) 366–3753 or (202) 366–3650, or by electronic mail (e-mail) to “ramcert@dot.gov.” Upon registration, the offeror will be furnished with a copy of the certificate. The offeror shall then submit a copy of the U.S. Competent Authority Certificate applying to that package design to the national competent authority of each country into or through which the package will be transported, unless the offeror has documentary evidence that a copy has already been furnished; and

(e) Each request for a U.S. Competent Authority Certificate as required by

the IAEA regulations must be submitted in writing to the Associate Administrator. The request must be in triplicate and include copies of the applicable USNRC packaging approval, USNRC Quality Assurance Program approval number, and a reproducible 22 cm × 30 cm (8.5"×11") drawing showing the make-up of the package. The request and accompanying documentation must be sent to the Associate Administrator for Hazardous Materials Safety (PHH-23), Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington DC 20590-0001. Alternatively, the application with any attached supporting documentation in an appropriate format may be submitted by facsimile (fax) to (202) 366-3753 or (202) 366-3650, or by electronic mail (e-mail) to "ramcert@dot.gov." Each request is considered in the order in which it is received. To allow sufficient time for consideration, requests must be received at least 90 days before the requested effective date.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 66 FR 45379, Aug. 28, 2001; 67 FR 61014, Sept. 27, 2002; 69 FR 3693, Jan. 26, 2004; 70 FR 56099, Sept. 23, 2005; 72 FR 55693, Oct. 1, 2007]

**§ 173.472 Requirements for exporting DOT Specification Type B and fissile packages.**

(a) Any offeror who exports a DOT Specification Type B or fissile material package authorized by §173.416 or §173.417 shall comply with paragraphs (b) through (f) of this section.

(b) The shipment must be made in accordance with the conditions of the U.S. Certificate of Competent Authority.

(c) The outside of each package must be durably and legibly marked with the package identification marking indicated in the U.S. Competent Authority Certificate.

(d) Each shipping paper related to the shipment of the package must bear the package identification marking indicated in the U.S. Competent Authority Certificate.

(e) Before export of the package, the offeror shall obtain a U.S. Competent Authority Certificate for that package design, or if one has already been

issued, the offeror shall register in writing (including a description of the quality assurance program required by 10 CFR part 71, subpart H, or 49 CFR 173.474 and 173.475) with the U.S. Competent Authority as a user of the certificate. Upon registration, the offeror will be furnished with a copy of the certificate. The offeror shall then submit a copy of the U.S. Competent Authority Certificate applying to that package design to the national competent authority of each country into or through which the package will be transported, unless the offeror has documentary evidence that a copy has already been furnished.

(f) Each request for a U.S. Competent Authority Certificate as required by the IAEA regulations must be submitted in writing to the Associate Administrator. The request must be in triplicate and must include a description of the quality assurance program required by 10 CFR part 71, subpart H, or 49 CFR 173.474 and 173.475, and a reproducible 22 cm × 30 cm (8.5"×11") drawing showing the make-up of the package. A copy of the USNRC quality assurance program approval will satisfy the requirement for describing the quality assurance program. The request and accompanying documentation may be sent by mail or other delivery service. Alternatively, the request with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to (202) 366-3753 or (202) 366-3650, or by electronic mail (e-mail) to "ramcert@dot.gov." Each request is considered in the order in which it is received. To allow sufficient time for consideration, requests must be received at least 90 days before the requested effective date.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 66 FR 45379, Aug. 28, 2001; 67 FR 61014, Sept. 27, 2002]

**§ 173.473 Requirements for foreign-made packages.**

In addition to other applicable requirements of this subchapter, each offeror of a foreign-made Type B(U), Type B(M), Type C, Type CF, Type H(U), Type H(M), or fissile material package for which a Competent Authority Certificate is required by

IAEA's "Regulations for the Safe Transport of Radioactive Material, No. TS-R-1," (IBR, see §171.7 of this subchapter) shall also comply with the following requirements:

(a) Prior to the shipment of such a package of Class 7 (radioactive) materials into or from the U.S., the offeror shall—

(1) Have the foreign competent authority certificate revalidated by the U.S. Competent Authority, unless this has been done previously. Each request for revalidation must be submitted to the Associate Administrator. The request must be in triplicate, contain all the information required by Section VII of the IAEA regulations in Safety Series No. 6, and include a copy in English of the foreign competent authority certificate. Alternatively, the request with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to (202) 366-3753 or (202) 366-3650, or by electronic mail to "ramcert@dot.gov." Each request is considered in the order in which it is received.

To allow sufficient time for consideration, requests must be received at least 90 days before the requested effective date;

(2) Register in writing with the U.S. Competent Authority as a user of the package covered by the foreign competent authority certificate and its U.S. revalidation. Alternatively, the registration request with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to (202) 366-3753 or (202) 366-3650, or by electronic mail (e-mail) to "ramcert@dot.gov." If the offeror is requesting the revalidation, registration is automatic; and

(3) Supply to the carrier, upon request, the applicable competent authority certificates. However, the competent authority certificates are not required to accompany the packages to which they apply.

(b) The outside of each package must be durably and legibly marked with the competent authority identification marking indicated on the Competent Authority Certificate and revalidation.

(c) Each shipping paper for a shipment of Class 7 (radioactive) materials

must bear a notation of the package identification marking indicated on the competent authority certificate or revalidation.

(d) All requirements of the foreign competent authority certificate and the U.S. Competent Authority revalidation must be fulfilled.

[Amdt. 173-244, 60 FR 50307, Sept. 28, 1995, as amended at 66 FR 45379, Aug. 28, 2001; 67 FR 16015, Sept. 27, 2002; 68 FR 75742, 75747, Dec. 31, 2003; 69 FR 3693, Jan. 26, 2004]

#### **§ 173.474 Quality control for construction of packaging.**

Prior to the first use of any packaging for the shipment of Class 7 (radioactive) material, the offeror shall determine that—

(a) The packaging meets the quality of design and construction requirements as specified in this subchapter; and

(b) The effectiveness of the shielding, containment and, when required, the heat transfer characteristics of the package, are within the limits specified for the package design.

#### **§ 173.475 Quality control requirements prior to each shipment of Class 7 (radioactive) materials.**

Before each shipment of any Class 7 (radioactive) materials package, the offeror must ensure, by examination or appropriate tests, that—

(a) The packaging is proper for the contents to be shipped;

(b) The packaging is in unimpaired physical condition, except for superficial marks;

(c) Each closure device of the packaging, including any required gasket, is properly installed, secured, and free of defects;

(d) For fissile material, each moderator and neutron absorber, if required, is present and in proper condition;

(e) Each special instruction for filling, closing, and preparation of the packaging for shipment has been followed;

(f) Each closure, valve, or other opening of the containment system through which the radioactive content might escape is properly closed and sealed;

(g) Each packaging containing liquid in excess of an A<sub>2</sub> quantity and intended for air shipment has been tested

to show that it will not leak under an ambient atmospheric pressure of not more than 25 kPa, absolute (3.6 psia). The test must be conducted on the entire containment system, or on any receptacle or vessel within the containment system, to determine compliance with this requirement;

(h) The internal pressure of the containment system will not exceed the design pressure during transportation; and

(i) External radiation and contamination levels are within the allowable limits specified in this subchapter.

**§ 173.476 Approval of special form Class 7 (radioactive) materials.**

(a) Each offeror of special form Class 7 (radioactive) materials must maintain on file for at least one year after the latest shipment, and provide to the Associate Administrator on request, a complete safety analysis, including documentation of any tests, demonstrating that the special form material meets the requirements of § 173.469. An IAEA Certificate of Competent Authority issued for the special form material may be used to satisfy this requirement.

(b) Prior to the first export shipment of a special form Class 7 (radioactive) material from the United States, each offeror shall obtain a U.S. Competent Authority Certificate for the specific material. For special form material manufactured outside the United States, an IAEA Certificate of Competent Authority from the country of origin may be used to meet this requirement.

(c) Each request for a U.S. Competent Authority Certificate as required by the IAEA regulations must be submitted in writing, in triplicate, by mail or other delivery service to the Associate Administrator. Alternatively, the request with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to (202) 366–3753 or (202) 366–3650, or by electronic mail (e-mail) to “ramcert@dot.gov.”. Each request is considered in the order in which it is received. To allow sufficient time for consideration, requests must be received at least 90 days before the requested effective date. Each petition

for a U.S. Competent Authority Certificate must include the following information:

(1) A detailed description of the material, or if a capsule, a detailed description of the contents. Particular reference must be made to both physical and chemical states;

(2) A detailed statement of the capsule design and dimensions, including complete engineering drawings [22cm × 30cm (8½ inches × 11 inches)] and schedules of material, and methods of construction;

(3) A statement of the tests that have been made and their results; or evidence based on calculative methods to show that the material is able to pass the tests; or other evidence that the special form Class 7 (radioactive) material complies with § 173.469;

(4) For the original request for a Competent Authority Certificate, evidence of a quality assurance program based on international, national or other standards, for the design, manufacture, testing, documentation, use, maintenance and inspection, as appropriate, of all special form material offered for transport by the requester; and

(5) A description of any proposed pre-shipment actions, such as leak testing, for use in the consignment of special form radioactive material for transport.

(d) Paragraphs (a) and (b) of this section do not apply in those cases where  $A_1$  equals  $A_2$  and the material is not required to be described on the shipping papers as “Radioactive Material, Special Form, n.o.s.”

[Amdt. 173–244, 60 FR 50307, Sept. 28, 1995, as amended at 66 FR 45379, Aug. 28, 2001; 67 FR 61015, Sept. 27, 2002; 69 FR 3693, Jan. 26, 2004]

**§ 173.477 Approval of packagings containing greater than 0.1 kg of non-fissile or fissile-excepted uranium hexafluoride.**

(a) Each offeror of a package containing more than 0.1 kg of uranium hexafluoride must maintain on file for at least one year after the latest shipment, and provide to the Associate Administrator on request, a complete safety analysis, including documentation of any tests, demonstrating that the package meets the requirements of

§173.420. An IAEA Certificate of Competent Authority issued for the design of the packaging containing greater than 0.1 kg of non-fissile or fissile-excepted uranium hexafluoride may be used to satisfy this requirement.

(b) Prior to the first export shipment of a package containing greater than 0.1 kg of uranium hexafluoride from the United States, each offeror shall obtain a U.S. Competent Authority Certificate for the packaging design. For packagings manufactured outside the United States, each offeror shall comply with §173.473.

(c) Each request for a U.S. Competent Authority Certificate as required by the IAEA regulations must be submitted in writing, in triplicate, by mail or other delivery service to the Associate Administrator. Alternatively, the request with any attached supporting documentation submitted in an appropriate format may be sent by facsimile (fax) to (202) 366-3753 or (202) 366-3650, or by electronic mail (e-mail) to *ramcert@dot.gov*. Each request is considered in the order in which it is received. To allow sufficient time for consideration, requests must be received at least 90 days before the requested effective date. Each request for a U.S. Competent Authority Certificate must include the following information:

(1) A safety analysis report which, at a minimum, provides a detailed description of the packaging and contents; a description of the manufacturing process used for the packaging; and details of the tests conducted and copy of their results, evidence based on calculative methods to show that the package is able to pass the tests, or other evidence that the package complies with §173.420; and

(2) For the original request for a Competent Authority Certificate, evidence of a quality assurance program.

[69 FR 3693, Jan. 26, 2004]

### Subparts J–O [Reserved]

#### APPENDIX A TO PART 173 [RESERVED]

#### APPENDIX B TO PART 173—PROCEDURE FOR TESTING CHEMICAL COMPATIBILITY AND RATE OF PERMEATION IN PLASTIC PACKAGING AND RECEPTACLES

1. The purpose of this procedure is to determine the chemical compatibility and permeability of liquid hazardous materials packaged in plastic packaging and receptacles. Alternatives for this procedure are permitted as specified in §173.24(e)(3)(iii) of this subchapter.

2. Compatibility and rate of permeation are determined by subjecting full size plastic containers (or smaller containers as permitted in paragraph 4 of this appendix) and hazardous material lading to one of the following combinations of time and temperature:

a. Test Method 1: 180 days at a temperature no lower than 18 °C. (64 °F.)

b. Test Method 2: 28 days at a temperature no lower than 50 °C. (122 °F.)

c. Test Method 3: 14 days at a temperature no lower than 60 °C. (140 °F.)

3. Regardless of which test method is used, at least three sample containers shall be tested for each combination of hazardous material and size and design of container. Fill containers to rated capacity with the specific hazardous material (at the concentration to be transported) and close as for shipment. For the first and last 24 hours of storage under the selected test method, place the containers with closures downward, except that containers fitted with a vent are so placed on each occasion for five minutes only.

4. For testing under Test Method 2 or 3 in those instances where it is not practicable to use full size containers, smaller containers may be used. The small container shall be manufactured by the same process as the larger container (for example, using the same method of molding and processing temperatures) and be made of identical resins, pigments and additives.

5. Determine filled container weight or net weight of contents both before and after storage under the selected test method. Rate of permeation is determined from loss of hazardous materials contents, during the conduct of the test, expressed as a percentage of the original weight.

6. After storage under the selected test method, the container shall be drained, rinsed, filled to rated capacity with water and, with filled container at ambient temperature, dropped from a height determined in accordance with §178.603(e) of this subchapter onto a rigid non-resilient, flat and horizontal surface.

7. Each of the following constitute test failure:

a. Visible evidence of permanent deformation due to vapor pressure build-up or collapse of walls, deterioration, swelling, crazing, cracking, excessive corrosion, oxidization, embrittlement, leakage, rupture or other defects likely to cause premature failure or a hazardous condition.

b. For materials meeting the definition of a poison according to this subchapter, a rate of permeation in excess of 0.5% determined over the test period. For all other hazardous materials, a rate of permeation in excess of 2.0% determined over the test period.

[Amdt. 173–176, 49 FR 24691, June 14, 1984, as amended by Amdt. 173–224, 55 FR 52670 Dec. 21, 1990; 56 FR 66279, Dec. 20, 1991; Amdt. 173–234, 58 FR 51533, Oct. 1, 1993; 66 FR 45379, Aug. 28, 2001]

#### APPENDIX C TO PART 173—PROCEDURE FOR BASE-LEVEL VIBRATION TESTING

Base-level vibration testing shall be conducted as follows:

1. Three sample packagings, selected at random, must be filled and closed as for shipment. A non-hazardous material may be used in place of the hazardous material if it has essentially the same physical characteristics.

2. The three packages must be placed on a vibrating platform that has a vertical double-amplitude (peak-to-peak displacement) of one inch. The packages should be constrained horizontally to prevent them from falling off the platform, but must be left free to move vertically, bounce and rotate.

3. The test must be performed continuously for one hour at a frequency that causes each package to be raised from the vibrating platform to such a degree that a piece of material of approximately 1.6 mm (0.063 inch) thickness (such as steel strapping or paperboard) can be passed between the bottom of any package and the platform.

4. Immediately following the period of vibration, each package shall be removed from the platform, turned on its side and observed for any evidence of leakage.

5. Rupture or leakage from any of the packages constitutes failure of the test.

[Amdt. 173–224, 55 FR 52671, Dec. 21, 1990]

#### APPENDIX D TO PART 173—TEST METHODS FOR DYNAMITE (EXPLOSIVE, BLASTING, TYPE A)

##### 1. TEST METHOD D-1—LEAKAGE TEST

A wooden stick, 114 mm (4.5 inches) long and 4.8 mm (0.2 inch) inch in diameter, with a sharpened end is used to punch 5 holes in

one end of the wrapper of a dynamite cartridge. A cork stopper is placed on the bottom of a glass volumetric cylinder. The dynamite cartridge is placed, perforated end down, resting on the cork stopper in the cylinder. The entire assembly is placed in an oven at 38 °C (100 °F) for 48 hours and then examined visually for evidence of leakage.

##### 2. TEST METHOD D-2—Centrifugal Exudation Test

The test apparatus consists of a glass tube, 135 mm (5.3 inches) long and one inch in diameter, with both ends open, and is assembled in the following manner:

(a) Close the bottom with a plastic plug of diameter equal to the inner diameter of the glass tube;

(b) Place a small amount of absorbent cotton on top of the plug;

(c) Place a plastic disk that matches the inner diameter to the glass tube and has seven small perforations on top of the cotton; and

(d) Place 10 g (0.35 ounce) of the dynamite sample on top of the disk.

The assembled glass tube is then placed in a hand-operated centrifuge and spun for one minute at 600 rpm (revolutions per minute). The dynamite sample is then removed from the glass tube and weighed to determine the percent of weight loss.

##### 3. TEST METHOD D-3—Compression Exudation Test

The entire apparatus for this test is shown in Figure 1 of this appendix. The test is conducted using the following procedures:

(a) A glass tube, 135 mm (5.3 inches) long and one inch in diameter, is held on a wooden base;

(b) A small amount of absorbent cotton is placed into the bottom of the glass tube;

(c) Ten g (0.35 ounce) of dynamite sample are placed on top of the cotton in the glass tube;

(d) A small amount of absorbent cotton is placed on top of the dynamite sample;


(e) A plastic disk that matches the inner diameter of the glass tube and has seven small perforations is placed on top of the cotton;

(f) A plastic plug matching the inner diameter of the glass tube is then placed on top of the disk;

(g) The glass tube assembly is placed under the compression rod, and compression is applied by means of the weight on the metal lever rod. The sample is compressed for one minute; and

(h) The dynamite sample is then removed from the glass tube and weighed to determine the percent of weight loss.

## FIGURE 1 COMPRESSION APPARATUS



BILLING CODE 4910-60-C

[Amdt. 173-224, 55 FR 52671, Dec. 21, 1990, as amended by Amdt. 173-234, 58 FR 51533, Oct. 1, 1993]

### APPENDIXES E-G TO PART 173 [RESERVED]

#### APPENDIX H TO PART 173—METHOD OF TESTING FOR SUSTAINED COMBUSTIBILITY

##### 1. METHOD

The method describes a procedure for determining if the material when heated under the test conditions and exposed to an external source of flame applied in a standard manner sustains combustion.

##### 2. PRINCIPLE OF THE METHOD

A metal block with a concave depression (test portion well) is heated to a specified temperature. A specified volume of the material under test is transferred to the well, and its ability to sustain combustion is noted after application and subsequent removal of a standard flame under specified conditions.

##### 3. APPARATUS

A combustibility tester consisting of a block of aluminum alloy or other corrosion-resistant metal of high thermal conductivity is used. The block has a concave well and a pocket drilled to take a thermometer. A small gas jet assembly on a swivel is attached to the block. The handle and gas inlet

for the gas jet may be fitted at any convenient angle to the gas jet. A suitable apparatus is shown in Figure 32.5.2.1 of the UN Manual of Test and Criteria (IBR, see (171.7 of this subchapter), and the essential dimensions are given in Figures 32.5.2.1 and 32.5.2.2 of the UN Manual and Tests and Criteria. The following equipment is needed:

- (a) *Gauge*, for checking that the height of the center of the gas jet above the top of the test portion well is 2.2 mm (see Figure 32.5.2.1);
- (b) *Thermometer*, mercury in glass, for horizontal operation, with a sensitivity not less than 1 mm/°C, or other measuring device of equivalent sensitivity permitting reading at 0.5 °C intervals. When in position in the block, the thermometer bulb must be surrounded with thermally conducting thermoplastic compound;
- (c) *Hotplate*, fitted with a temperature-control device. (Other types of apparatus with suitable temperature-control facilities may be employed to heat the metal block);
- (d) *Stopwatch*, or other suitable timing device;
- (e) *Syringe*, capable of delivering 2 mL to an accuracy of  $\pm 0.1$  mL; and
- (f) *Fuel source*, butane test fuel.

##### 4. SAMPLING

The sample must be representative of the material to be tested and must be supplied and kept in a tightly closed container prior



to test. Because of the possibility of loss of volatile constituents, the sample must receive only the minimum treatment necessary to ensure its homogeneity. After removing each test portion, the sample container must be immediately closed tightly to ensure that no volatile components escape from the container; if this closure is incomplete, an entirely new sample must be taken.

#### 5. PROCEDURE

Carry out the determination in triplicate.

**WARNING**—Do not carry out the test in a small confined area (for example a glove box) because of the hazard of explosions.

(a) It is essential that the apparatus be set up in a completely draft-free area (see warning) and in the absence of strong light to facilitate observation of flash, flame, etc.

(b) Place the metal block on the hotplate or heat the metal block by other suitable means so that its temperature, as indicated by the thermometer placed in the metal block, is maintained at the specified temperature within a tolerance of  $\pm 1$  °C. For the appropriate test temperature, see paragraph 5.(h) of this appendix. Correct this temperature for the difference in barometric pressure from the standard atmospheric pressure (101.3 kPa) by raising the test temperature for a higher pressure or lowering the test temperature for a lower pressure by 1.0 °C for each 4 kPa difference. Ensure that the top of the metal block is exactly horizontal. Use the gauge to check that the jet is 2.2 mm above the top of the well when in the test position.

(c) Light the butane test fuel with the jet away from the test position (i.e. in the “off” position, away from the well). Adjust the size of the flame so that it is 8 mm to 9 mm high and approximately 5 mm wide.

(d) Using the syringe, take from the sample container at least 2 mL of the sample and rapidly transfer a test portion of 2 mL  $\pm 0.1$  mL to the well of the combustibility tester and immediately start the timing device.

(e) After a heating time of 60 seconds (s), by which time the test portion is deemed to have reached its equilibrium temperature, and if the test fluid has not ignited, swing the test flame into the test position over the edge of the pool of liquid. Maintain it in this position for 15 s and then return it to the “off” position while observing the behavior of the test portion. The test flame must remain lighted throughout the test.

(f) For each test observe and record:

(i) whether there is ignition and sustained combustion or flashing, or neither, of the test portion before the test flame is moved into the test position;

(ii) whether the test portion ignites while the test flame is in the test position, and, if so, how long combustion is sustained after the test flame is returned to the “off” position.

(g) If sustained combustion interpreted in accordance with paragraph 6. of this appendix is not found, repeat the complete procedure with new test portions, but with a heating time of 30 s.

(h) If sustained combustion interpreted in accordance with paragraph 6. of this appendix is not found at a test temperature of 60 °C (140 °F), repeat the complete procedure with new test portions, but at a test temperature of 75 °C (167 °F). In the case of a material which has a flash point above 60 °C (140 °F) and below 93 °C (200 °F), if sustained combustion interpreted in accordance with paragraph 6. of this appendix is not found at a test temperature of 5 °C (9 °F) above its flash point, repeat the complete procedure with new test portions, but at a test temperature of 20 °C (36 °F) above its flash point.

#### 6. INTERPRETATION OF OBSERVATIONS

The material must be assessed either as not sustaining combustion or as sustaining combustion. Sustained combustion must be reported at either of the heating times if one of the following occurs with either of the test portions:

(a) When the test flame is in the “off” position, the test portion ignites and sustains combustion;

(b) The test portion ignites while the test flame is in the test position for 15 s, and sustains combustion for more than 15 s after the test flame has been returned to the “off” position.

**NOTE TO PARAGRAPH 6 OF THIS APPENDIX:** Intermittent flashing may not be interpreted as sustained combustion. Normally, at the end of 15 s, the combustion has either clearly ceased or continues. In cases of doubt, the material must be deemed to sustain combustion.

[Amdt. 173–241, 59 FR 67517, Dec. 29, 1994, as amended by Amdt. 173–255, 61 FR 50627, Sept. 26, 1996; 66 FR 45381, Aug. 28, 2001; 68 FR 75747, Dec. 31, 2003; 69 FR 76179, Dec. 20, 2004; 71 FR 78634, Dec. 29, 2006]

## PART 174—CARRIAGE BY RAIL

### Subpart A—General Requirements

#### Sec.

174.1 Purpose and scope.

174.3 Unacceptable hazardous materials shipments.

174.5 Carrier’s materials and supplies.

174.9 Safety and security inspection and acceptance.

174.14 Movements to be expedited.

174.16 Removal and disposition of hazardous materials at destination.

174.20 Local or carrier restrictions.

**Subpart B—General Operating Requirements**

- 174.24 Shipping papers.
- 174.26 Notice to train crews.
- 174.50 Nonconforming or leaking packages.

**Subpart C—General Handling and Loading Requirements**

- 174.55 General requirements.
- 174.57 Cleaning cars.
- 174.59 Marking and placarding of rail cars.
- 174.61 Transport vehicles and freight containers on flat cars.
- 174.63 Portable tanks, IM portable tanks, IBCs, cargo tanks, and multi-unit tank car tanks.
- 174.67 Tank car unloading.
- 174.81 Segregation of hazardous materials.

**Subpart D—Handling of Placarded Rail Cars, Transport Vehicles and Freight Containers**

- 174.82 General requirements for the handling of placarded rail cars, transport vehicles, freight containers, and bulk packages.
- 174.83 Switching placarded rail cars, transport vehicles, freight containers, and bulk packagings.
- 174.84 Position in train of loaded placarded rail cars, transport vehicles, freight containers or bulk packagings when accompanied by guards or technical escorts.
- 174.85 Position in train of placarded cars, transport vehicles, freight containers, and bulk packagings.
- 174.86 Maximum allowable operating speed.

**Subpart E—Class I (Explosive) Materials**

- 174.101 Loading Class 1 (explosive) materials.
- 174.102 Forbidden mixed loading and storage.
- 174.103 Disposition of damaged or astray shipments.
- 174.104 Division 1.1 or 1.2 (explosive) materials; car selection, preparation, inspection, and certification.
- 174.105 Routing shipments, Division 1.1 or 1.2 (explosive) materials.
- 174.106 “Order-Notify” or “C.O.D.” shipments, Division 1.1 or 1.2 (explosive) materials.
- 174.110 Car magazine.
- 174.112 Loading Division 1.3 and Division 1.2 (explosive) materials (Also see §174.101).
- 174.114 Record to be made of change of seals on “Cars loaded with Division 1.1 or 1.2 (explosive) materials”.
- 174.115 Loading Division 1.4 (explosive) materials.

**Subpart F—Detailed Requirements for Class 2 (Gases) Materials**

- 174.200 Special handling requirements.
- 174.201 Class 2 (gases) material cylinders.
- 174.204 Tank car delivery of gases, including cryogenic liquids.
- 174.290 Materials extremely poisonous by inhalation shipped by, for, or to the Department of Defense.

**Subpart G—Detailed Requirements for Class 3 (Flammable Liquid) Materials**

- 174.300 Special handling requirements.
- 174.304 Class 3 (flammable liquid) materials in tank cars.

**Subparts H–I [Reserved]****Subpart J—Detailed Requirements for Division 6.1 (Poisonous) Materials**

- 174.600 Special handling requirements for materials extremely poisonous by inhalation.
- 174.615 Cleaning cars.
- 174.680 Division 6.1 (poisonous) materials with foodstuffs.

**Subpart K—Detailed Requirements for Class 7 (Radioactive) Materials**

- 174.700 Special handling requirements for Class 7 (radioactive) materials.
- 174.715 Cleanliness of transport vehicles after use.
- 174.750 Incidents involving leakage.

AUTHORITY: 49 U.S.C. 5101–5127; 49 CFR 1.53.

**Subpart A—General Requirements****§ 174.1 Purpose and scope.**

This part prescribes requirements in addition to those contained in parts 171, 172, 173, and 179 of this subchapter, to be observed with respect to the transportation of hazardous materials in or on rail cars.

[Amdt. 174–26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174–26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174–74, 58 FR 51533, Oct. 1, 1993]

**§ 174.3 Unacceptable hazardous materials shipments.**

No person may accept for transportation or transport by rail any shipment of hazardous material that is not in conformance with the requirements of this subchapter.

[Amdt. 174–83, 61 FR 28677, June 5, 1996]

## § 174.5

## 49 CFR Ch. I (10–1–08 Edition)

### § 174.5 Carrier's materials and supplies.

This subchapter applies to the transportation of a carrier's materials and supplies moving by rail, except that the shipper's certification is not required when these materials and supplies are being transported by the carrier who owns them. The requirements of this subchapter do not apply to railway torpedoes or fusees when carried in engines or rail cars. Railway torpedoes must be in closed metal boxes when not in use.

[Amdt. 174–26B, 41 FR 57071, Dec. 30, 1976]

### § 174.9 Safety and security inspection and acceptance.

(a) At each location where a hazardous material is accepted for transportation or placed in a train, the carrier must inspect each rail car containing the hazardous material, at ground level, for required markings, labels, placards, securement of closures, and leakage. These inspections may be performed in conjunction with inspections required under parts 215 and 232 of this title.

(b) For each rail car containing an amount of hazardous material requiring placarding in accordance with § 172.504 of this subchapter, the carrier must visually inspect the rail car at ground level for signs of tampering, including closures and seals, for suspicious items or items that do not belong, and for other signs that the security of the car may have been compromised, including the presence of an improvised explosive device. As used in this section, an improvised explosive device is a device fabricated in an improvised manner incorporating explosives or destructive, lethal, noxious, pyrotechnic, or incendiary chemicals in its design, and generally includes a power supply, a switch or timer, and a detonator or initiator. The carrier should be particularly attentive to signs that security may have been compromised on rail cars transporting materials covered by § 172.820 of this subchapter, rail carload quantities of ammonium nitrate or ammonium nitrate mixtures in solid form, or hazardous materials of interest based on current threat information.

(c) If a rail car does not conform to the safety and security requirements of this subchapter, the carrier may not forward or transport the rail car until the deficiencies are corrected or the car is approved for movement in accordance with § 174.50.

(d) Where an indication of tampering or suspicious item is found, a carrier must take appropriate action to ensure the security of the rail car and its contents have not been compromised before accepting the rail car for further movement. If the carrier determines that the security of the rail car has been compromised, the carrier must take action, in conformance with its existing security plan (see subpart I of part 172 of this subchapter) to address the security issues before forwarding the rail car for further movement.

[73 FR 20773, April 16, 2008]

### § 174.14 Movements to be expedited.

(a) A carrier must forward each shipment of hazardous materials promptly and within 48 hours (Saturdays, Sundays, and holidays excluded), after acceptance at the originating point or receipt at any yard, transfer station, or interchange point, except that where biweekly or weekly service only is performed, a shipment of hazardous materials must be forwarded on the first available train.

(b) A tank car loaded with any Division 2.1 (flammable gas), Division 2.3 (poisonous gas) or Class 3 (flammable liquid) material, may not be received and held at any point, subject to forwarding orders, so as to defeat the purpose of this section or of § 174.204 of this subchapter.

[Amdt. 174–26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174–68, 55 FR 52677, Dec. 21, 1990]

### § 174.16 Removal and disposition of hazardous materials at destination.

(a) *Delivery at non-agency stations.* A shipment of Class 1 (explosive) materials may not be unloaded at non-agency stations unless the consignee is there to receive it or unless properly locked and secure storage facilities are provided at that point for its protection. If delivery cannot be so made, the

shipment must be taken to next or nearest agency station for delivery.

(b) *Delivery at agency stations.* A carrier shall require the consignee of each shipment of hazardous materials to remove the shipment from carrier's property within 48 hours (exclusive of Saturdays, Sundays, and holidays) after notice of arrival has been sent or given. If not so removed, the carrier shall immediately dispose of the shipments as follows:

(1) *Division 1.1 or 1.2 (explosive) materials:* If safe storage is available, by storage at the owner's expense; if safe storage is not available, by return to the shipper, sale, or destruction under supervision of a competent person; or if safety requires, by destruction under supervision of a competent person.

(2) *Hazardous materials, except Division 1.1 or 1.2 (explosive) materials, in carload shipments:* By storage on the carrier's property; by storage on other than the carrier's property, if safe storage on the carrier's property is not available; or by sale at expiration of 15 calendar days after notice of arrival has been sent or given to the consignee, provided the consignor has been notified of the non-delivery at the expiration of a 48-hour period and orders for disposition have not been received.

(3) *Hazardous materials, except Division 1.1 or 1.2 (Class A explosive) materials, in less-than-carload shipments:* By return to the shipper if notice of non-delivery was requested and given the consignor as prescribed by the carrier's tariff, and orders for return to shipper have been received; by storage on the carrier's property; by storage on other than the carrier's property, if safe storage on carrier's property is not available; or by sale at expiration of 15 calendar days after notice of arrival has been sent or given to the consignee, provided the consignor has been notified of non-delivery at expiration of a 48-hour period and orders for disposition have not been received.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-68, 55 FR 52677, Dec. 21, 1990; 66 FR 45383, Aug. 28, 2001]

#### § 174.20 Local or carrier restrictions.

(a) When local conditions make the acceptance, transportation, or delivery of hazardous materials unusually haz-

ardous, local restrictions may be imposed by the carrier.

(b) Each carrier must report to the Bureau of Explosives for publication the full information as to any restrictions which it imposes against the acceptance, delivery, or transportation of hazardous materials, over any portion of its lines under this section.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976]

### Subpart B—General Operating Requirements

#### § 174.24 Shipping papers.

(a) A person may not accept a hazardous material for transportation or transport a hazardous material by rail unless that person receives a shipping paper prepared in accordance with part 172 of this subchapter, unless the material is excepted from shipping paper requirements under this subchapter. Only an initial carrier within the United States must receive and retain a copy of the shipper's certification as required by § 172.204 of this subchapter. This section does not apply to a material that is excepted from shipping paper requirements by this subchapter.

(b) Each person receiving a shipping paper required by this section must retain a copy or an electronic image thereof, that is accessible at or through its principal place of business and must make the shipping paper available, upon request, to an authorized official of a Federal, State, or local government agency at reasonable times and locations. For a hazardous waste, each shipping paper copy must be retained for three years after the material is accepted by the initial carrier. For all other hazardous materials, each shipping paper copy must be retained for one year after the material is accepted by the initial carrier. Each shipping paper copy must include the date of acceptance by the initial carrier. The date on the shipping paper may be the date a shipper notifies the rail carrier that a shipment is ready for transportation, as indicated on the

## **§ 174.26**

waybill or bill of lading, as an alternative to the date the shipment is picked up, or accepted, by the carrier.

[67 FR 46128, July 12, 2002, as amended at 67 FR 66574, Nov. 1, 2002; 70 FR 73165, Dec. 9, 2005]

### **§ 174.26 Notice to train crews.**

(a) The train crew must have a document that reflects the current position in the train of each rail car containing a hazardous material. The train crew must update the document to indicate changes in the placement of a rail car within the train. For example, the train crew may update the document by handwriting on it or by appending or attaching another document to it.

(b) A member of the crew of a train transporting a hazardous material must have a copy of a document for the hazardous material being transported showing the information required by part 172 of this subchapter.

[Amdt. 174-84, 62 FR 1236, Jan. 8, 1997]

### **§ 174.50 Nonconforming or leaking packages.**

A leaking non-bulk package may not be forwarded until repaired, reconditioned, or overpacked in accordance with §173.3 of this subchapter. Except as otherwise provided in this section, a bulk packaging that no longer conforms to this subchapter may not be forwarded by rail unless repaired or approved for movement by the Associate Administrator for Safety, Federal Railroad Administration. Notification and approval must be in writing, or through telephonic or electronic means, with subsequent written confirmation provided within two weeks. For the applicable address and telephone number, see §107.117(d)(4) of this chapter. A leaking bulk package containing a hazardous material may be moved without repair or approval only so far as necessary to reduce or to eliminate an immediate threat or harm to human health or to the environment when it is determined its movement would provide greater safety than allowing the package to remain in place. In the case of a liquid leak, measures must be taken to prevent the spread of liquid.

[65 FR 50462, Aug. 18, 2000]

## **49 CFR Ch. I (10-1-08 Edition)**

### **Subpart C—General Handling and Loading Requirements**

#### **§ 174.55 General requirements.**

(a) Each package containing a hazardous material being transported by rail in a freight container or transport vehicle must be loaded so that it cannot fall or slide and must be safeguarded in such a manner that other freight cannot fall onto or slide into it under conditions normally incident to transportation. When this protection cannot be provided by using other freight, it must be provided by blocking and bracing. For examples of blocking and bracing in freight containers and transport vehicles, see Bureau of Explosives Pamphlet Nos. 6 and 6C.

(b) Each package containing a hazardous material bearing package orientation markings prescribed in §172.312 of this subchapter must be loaded within a transport vehicle or freight container to remain in the correct position indicated by those markings during transportation.

(c) The doors of a freight container or transport vehicle may not be used to secure a load that includes a package containing a hazardous material unless the doors meet the design strength requirements of Specification M-930 (for freight containers) and M-931 (for trailers) in the AAR's specification for "Specially Equipped Freight Car and Intermodal Equipment" (IBR, see §171.7 of this subchapter) and the load is also within the limits of the design strength requirements for the doors.

[Amdt. 174-83, 61 FR 28677, June 5, 1996, as amended at 68 FR 75747, Dec. 31, 2003]

#### **§ 174.57 Cleaning cars.**

All hazardous material which has leaked from a package in any rail car or on other railroad property must be carefully removed.

#### **§ 174.59 Marking and placarding of rail cars.**

No person may transport a rail car carrying hazardous materials unless it is marked and placarded as required by this subchapter. Placards and car certificates lost in transit must be replaced at the next inspection point,

and those not required must be removed at the next terminal where the train is classified. For Canadian shipments, required placards lost in transit, must be replaced either by those required by part 172 of this subchapter or by those authorized under § 171.12a.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-48, 50 FR 41521, Oct. 11, 1985]

**§ 174.61 Transport vehicles and freight containers on flat cars.**

(a) A transport vehicle, freight container, or package containing a hazardous material must be designed and loaded so that it will not become damaged to an extent that would affect its integrity under conditions normally incident to transportation. Each unit must be secured on a flatcar so that it cannot permanently change position during transit. Packages of hazardous materials contained therein must be loaded and braced as provided by §§ 174.101, 174.112, 174.115 and 174.55. Placards must be applied when prescribed by part 172 of this subchapter and part 174.

(b) Except as specified in § 173.21, a truck body, trailer, or freight container equipped with heating or refrigerating equipment which has fuel or any article classed as a hazardous material may be loaded and transported on a flat car as part of a joint rail highway movement. The heating or refrigerating equipment is considered to be a part of the truck body or trailer and is not subject to any other requirements of this subchapter. The truck body, trailer, or freight container must be secured on the flatcar so that it cannot change position during transit.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174-38, 45 FR 32698, May 19, 1980; Amdt. 174-39, 45 FR 81572, Dec. 11, 1980; Amdt. 174-59, 51 FR 5974, Feb. 18, 1986; Amdt. 174-68, 57 FR 45464, Oct. 1, 1992; Amdt. 174-79, 59 FR 64744, Dec. 15, 1994]

**§ 174.63 Portable tanks, IM portable tanks, IBCs, cargo tanks, and multi-unit tank car tanks.**

(a) A carrier may not transport a bulk packaging (e.g., portable tank, IM portable tank, IBC, cargo tank, or multi-unit tank car tank) containing a

hazardous material in container-on-flatcar (COFC) or trailer-on-flatcar (TOFC) service except as authorized by this section or unless approved for transportation by the Associate Administrator for Safety, FRA.

(b) A bulk packaging containing a hazardous material (including IM 101 and IM 102 when appropriate according to dimensions and weight distribution) may be transported inside a fully closed transport vehicle or fully closed freight container provided it is properly secured with a restraint system that will prevent it from changing position, sliding into other packages, or contacting the side or end walls (including doors) under conditions normally incident to transportation.

(c) When not transported in conformance with and subject to paragraph (b) of this section, a bulk packaging may be transported in COFC service or TOFC service subject to the following conditions as applicable:

(1) The bulk packaging contains a material packaged in accordance with § 173.240, 173.241, 173.242, or 173.243 of this subchapter;

(2) The tank and flatcar conform to requirements in AAR 600 of the AAR Specifications for Tank Cars, "Specifications for Acceptability of Tank Containers" (IBR, see § 171.7 of this subchapter);

(3) For TOFC service, the trailer chassis conforms to requirements in paragraphs 3, 4, 5, and 6 of AAR Specification M-943, "Container Chassis For TOFC Service" of the AAR specification for "Specially Equipped Freight Car and Intermodal Equipment" (IBR, see § 171.7 of this subchapter);

(4) For COFC service, the container support and securement systems conform to requirements in Specification M-952, "Intermodal Container Support and Securement Systems for Freight Cars", of the AAR specification for "Specially Equipped Freight Car and Intermodal Equipment" (IBR, see § 171.7 of this subchapter);

(5) If transported in a well car—

(i) The tank is not in a double-stacked configuration (i.e., no freight container or portable tank is placed above or below the tank); and

(ii) The tank is transported in the well with its outlet valve facing outward towards the end of the well and away from any adjacent tank or container; and

(6) All securement fittings shall be fully engaged and in the locked position, provided; however, if the tank is transported in a well car, it must be loaded into a well appropriate for the length of the container and any void filling device present must be secured in its designed appropriate position.

(d) An approval in effect on February 28, 1991 for the transportation of portable tanks or IM portable tanks in TOFC or COFC service expires on the date stated in the approval letter or June 15, 1995, whichever is later.

(e) A carrier may not transport a cargo tank or multi-unit tank car tank containing a hazardous material in TOFC or COFC service unless approved for such service by the Associate Administrator for Safety, FRA. However, in the event of an accident or incident, no such approval is necessary for the transportation of a cargo tank containing a hazardous material in TOFC service under the following condition(s):

(1) There is an emergency need for the cargo tank in order to mitigate the consequences of an incident; and

(2) Movement of the cargo tank is limited to transportation necessary for emergency purposes.

[Amdt. 174–79, 59 FR 64744, Dec. 15, 1994, as amended by 66 FR 45383, Aug. 28, 2001; 68 FR 75747, Dec. 31, 2003]

**§ 174.67 Tank car unloading.**

For transloading operations, the following rules must be observed:

(a) *General requirements.* (1) Unloading operations must be performed by hazmat employees properly instructed in unloading hazardous materials and made responsible for compliance with this section.

(2) Each hazmat employee who is responsible for unloading must apply the handbrake and block at least one wheel to prevent movement in any direction. If multiple tank cars are coupled together, sufficient hand brakes must be set and wheels blocked to prevent movement in both directions.

(3) Each hazmat employee who is responsible for unloading must secure access to the track to prevent entry by other rail equipment, including motorized service vehicles. This requirement may be satisfied by lining each switch providing access to the unloading area against movement and securing each switch with an effective locking device, or by using derails, portable bumper blocks, or other equipment that provides an equivalent level of safety.

(4) Each hazmat employee who is responsible for unloading must display caution signs on the track or on the tank cars to warn persons approaching the cars from the open end of the track and must be left up until after all closures are secured and the cars are in proper condition for transportation. The caution signs must be of metal or other durable material, rectangular, at 30.48 cm (12 inches) high by 38.10 cm (15 inches) wide, and bear the word “STOP.” The word “STOP” must appear in letters at least 10.16 cm (4 inches) high. The letters must be white on a blue background. Additional words, such as “Tank Car Connected” or “Crew at Work,” may also appear in white letters under the word “STOP.”

(5) The transloading facility operator must maintain written safety procedures (such as those it may already be required to maintain pursuant to the Department of Labor’s Occupational Safety and Health Administration requirements in 29 CFR 1910.119 and 1910.120) in a location where they are immediately available to hazmat employees responsible for the transloading operation.

(6) Before a manhole cover or outlet valve cap is removed from a tank car, the car must be relieved of all interior pressure by cooling the tank with water or by venting the tank by raising the safety valve or opening the dome vent at short intervals. However, if venting to relieve pressure will cause a dangerous amount of vapor to collect outside the car, venting and unloading must be deferred until the pressure is reduced by allowing the car to stand overnight or otherwise cooling the contents. These precautions are not necessary when the car is equipped with a manhole cover which hinges inward or with an inner manhole cover which

does not have to be removed to unload the car, and when pressure is relieved by piping vapor into a condenser or storage tank.

(b) After the pressure is released, the seal must be broken and the manhole cover removed as follows:

(1) *Screw type.* The cover must be loosened by placing a bar between the manhole cover lug and knob. After two complete turns, so that vent openings are exposed, the operation must be stopped, and if there is any sound of escaping vapor, the cover must be screwed down tightly and the interior pressure relieved as prescribed in paragraph (a)(4) of this section, before again attempting to remove the cover.

(2) *Hinged and bolted type.* All nuts must be unscrewed one complete turn, after which same precautions as prescribed for screw type cover must be observed.

(3) *Interior type.* All dirt and cinders must be carefully removed from around the cover before the yoke is unscrewed.

(c) When the car is unloaded through a bottom outlet valve, the manhole cover must be adjusted as follows:

(1) *Screw type.* The cover must be put in place, but not entirely screwed down, so that air may enter the tank through the vent holes in threaded flange of the cover.

(2) *Hinged and bolted type.* A non-metallic block must be placed under one edge of the cover.

(3) *Interior type.* The screw must be tightened up in the yoke so that the cover is brought up within one-half inch of the closed position.

(d) When unloading through the bottom outlet of a car equipped with an interior manhole type cover, and in each case where unloading is done through the manhole (unless a special cover with a safety vent opening and a tight connection for the discharge outlet is used), the manhole must be protected by asbestos or metal covers against the entrance of sparks or other sources of ignition of vapor, or by being covered and surrounded with wet burlap or similar cloth material. The burlap or other cloth must be kept damp by the replacement or the application of water as needed.

(e) Seals or other substances must not be thrown into the tank and the

contents may not be spilled over the car or tank.

(f) The valve rod handle or control in the dome must be operated several times to see that outlet valve in bottom of tank is on its seat before valve cap is removed.

(g) The valve cap, or the reducer when a large outlet is to be used, must be removed with a suitable wrench after the set screws are loosened and a pail must be placed in position to catch any liquid that may be in the outlet chamber. If the valve cap or reducer does not unscrew easily, it may be tapped lightly with a mallet or wooden block in an upward direction. If leakage shows upon starting the removal, the cap or reducer may not be entirely unscrewed. Sufficient threads must be left engaged and sufficient time allowed to permit controlled escape of any accumulation of liquid in the outlet chamber. If the leakage stops or the rate of leakage diminishes materially, the cap or reducer may be entirely removed. If the initial rate of leakage continues, further efforts must be made to seat the outlet valve (see paragraph (f) of this section). If this fails, the cap or reducer must be screwed up tight and the tank must be unloaded through the dome. If upon removal of the outlet cap the outlet chamber is found to be blocked with frozen liquid or any other matter, the cap must be replaced immediately and a careful examination must be made to determine whether the outlet casting has been cracked. If the obstruction is not frozen liquid, the car must be unloaded through the dome. If the obstruction is frozen liquid and no crack has been found in the outlet casting, the car may, if circumstances require it, be unloaded from the bottom by removing the cap and attaching unloading connections immediately. Before opening the valve inside the tank car, steam must be applied to the outside of the outlet casting or wrap casting with burlap or other rags and hot water must be applied to melt the frozen liquid.

(h) Unloading connections must be securely attached to unloading pipes on the dome or to the bottom discharge outlets before any discharge valves are opened.



## § 174.81

## 49 CFR Ch. I (10–1–08 Edition)

(i) Throughout the entire period of unloading and while a tank car has unloading equipment attached, the facility operator must assure that the tank car is:

(1) Attended by a designated hazmat employee who is physically present and who has an unobstructed view of the unloading operation; or

(2) Monitored by a signaling system (*e.g.*, video system, sensing equipment, or mechanical equipment) that is observed by a designated hazmat employee located either in the immediate area of the tank car or at a remote location within the facility, such as a control room. The signaling system must—

(i) Provide a level of surveillance equivalent to that provided in subparagraph (1) of this paragraph (i); and

(ii) Provide immediate notification to a designated hazmat employee of any system malfunction or other emergency so that, if warranted, responsive actions may be initiated immediately.

(j) Attendance is not required when piping is attached to a top outlet of a tank car, equipped with a protective housing required under § 179.100–12 of this subchapter, for discharge of lading under the following conditions:

(1) All valves are tightly closed.

(2) The piping is not connected to hose or other unloading equipment and is fitted with a cap or plug of appropriate material and construction.

(3) The piping extends no more than 15.24 centimeters (6 inches) from the outer edge of the protective housing.

(k) In the absence of the unloader, a tank car may stand with unloading connections attached when no product is being transferred under the following conditions:

(1) The facility operator must designate a hazmat employee responsible for on-site monitoring of the transfer facility. The designated hazmat employee must be made familiar with the nature and properties of the product contained in the tank car; procedures to be followed in the event of an emergency; and, in the event of an emergency, have the ability and authority to take responsible actions.

(2) When a signaling system is used in accordance with paragraph (i) of this section, the system must be capable of

alerting the designated hazmat employee in the event of an emergency and providing immediate notification of any monitoring system malfunction. If the monitoring system does not have self-monitoring capability, the designated hazmat employee must check the monitoring system hourly for proper operation.

(3) The tank car and facility shutoff valves must be secured in the closed position.

(4) Brakes must be set and wheels locked in accordance with paragraph (a)(2) of this section.

(5) Access to the track must be secured in accordance with paragraph (a)(3) of this section.

(l) As soon as a tank car is completely unloaded, all valves must be made tight by the use of a bar, wrench or other suitable tool, the unloading connections must be removed and all other closures made tight.

(m) Railroad defect cards may not be removed.

(n) If oil or gasoline has been spilled on the ground around connections, it must be covered with fresh, dry sand or dirt.

(o) All tools and implements used in connection with unloading must be kept free of oil, dirt, and grit.

[Amdt. 174–26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174–26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174–43, 48 FR 27699, June 16, 1983; Amdt. 174–68, 55 FR 52678, Dec. 21, 1990; 56 FR 66280, Dec. 20, 1991; Amdt. 174–81, 60 FR 49111, Sept. 21, 1995; Amdt. 174–83, 61 FR 28678, June 5, 1996; 68 FR 61941, Oct. 30, 2003; 70 FR 20034, Apr. 15, 2005; 72 FR 55693, Oct. 1, 2007]

### § 174.81 Segregation of hazardous materials.

(a) This section applies to materials which meet one or more of the hazard classes defined in this subchapter and are in packages which are required to be labeled or placarded under the provisions of part 172 of this subchapter.

(b) When a rail car is to be transported by vessel, other than a ferry vessel, hazardous materials on or within that rail car must be stowed and segregated in accordance with § 176.83(b) of this subchapter.

(c) Except as provided in § 173.12(e) of this subchapter, cyanides, cyanide mixtures or solutions may not be stored, loaded and transported with acids, and

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 174.81**

Division 4.2 materials may not be stored, loaded and transported with Class 8 liquids. must be stored, loaded or transported in accordance with the following table and other provisions of this section:

(d) Except as otherwise provided in this subchapter, hazardous materials

SEGREGATION TABLE FOR HAZARDOUS MATERIALS

| Class or Division                         | Notes          | 1.1,<br>1.2 | 1.3 | 1.4 | 1.5 | 1.6 | 2.1 | 2.2 | 2.3 gas<br>Zone A | 2.3 gas<br>Zone B | 3 | 4.1 | 4.2 | 4.3 | 5.1 | 5.2 | 6.1 liq-<br>uids PG<br>I Zone A | 7 | 8 liquids<br>only |
|-------------------------------------------|----------------|-------------|-----|-----|-----|-----|-----|-----|-------------------|-------------------|---|-----|-----|-----|-----|-----|---------------------------------|---|-------------------|
| Explosives .....                          | 1.1 and<br>1.2 | A           | *   | *   | *   | *   | X   | X   | X                 | X                 | X | X   | X   | X   | X   | X   | X                               | X | X                 |
| Explosives .....                          | 1.3            |             | *   | *   | *   | *   | X   |     | X                 | X                 | X |     | X   | X   | X   | X   | X                               |   | X                 |
| Explosives .....                          | 1.4            |             | *   | *   | *   | *   | O   |     | O                 | O                 | O |     | O   |     |     |     | O                               |   | O                 |
| Very insensitive explo-<br>sives.         | 1.5            | A           | *   | *   | *   | *   | X   | X   | X                 | X                 | X | X   | X   | X   | X   | X   | X                               | X | X                 |
| Extremely insensitive<br>explosives.      | 1.6            |             | *   | *   | *   | *   |     |     |                   |                   |   |     |     |     |     |     |                                 |   |                   |
| Flammable gases .....                     | 2.1            |             | X   | X   | O   | X   |     |     | X                 | O                 |   |     |     |     |     |     | O                               | O |                   |
| Non-toxic, non-flam-<br>mable gases.      | 2.2            |             | X   |     | X   |     |     |     |                   |                   |   |     |     |     |     |     |                                 |   |                   |
| Poisonous gas Zone A                      | 2.3            |             | X   | X   | O   | X   | X   |     |                   |                   | X | X   | X   | X   | X   | X   |                                 |   | X                 |
| Poisonous gas Zone B                      | 2.3            |             | X   | X   | O   | X   | O   |     |                   |                   | O | O   | O   | O   | O   | O   |                                 |   | O                 |
| Flammable liquids .....                   | 3              |             | X   | X   | O   | X   |     |     | X                 | O                 |   |     |     |     | O   |     | X                               |   | O                 |
| Flammable solids .....                    | 4.1            |             | X   |     | X   | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | O                 |
| Spontaneously combus-<br>tible materials. | 4.2            |             | X   | X   | O   | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | X                 |
| Dangerous when wet<br>materials.          | 4.3            |             | X   | X   |     | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | O                 |
| Oxidizers .....                           | 5.1            | A           | X   | X   |     | X   |     |     | X                 | O                 | O |     |     |     |     |     | X                               |   | O                 |
| Organic peroxides .....                   | 5.2            |             | X   | X   |     | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | O                 |
| Poisonous liquids PG I<br>Zone A.         | 6.1            |             | X   | X   | O   | X   | O   |     |                   |                   | X | X   | X   | X   | X   | X   |                                 |   | X                 |
| Radioactive materials ...                 | 7              |             | X   |     | X   |     | O   |     |                   |                   |   | O   | X   | O   | O   | O   | X                               |   |                   |
| Corrosive liquids .....                   | 8              |             | X   | X   | O   | X   |     |     | X                 | O                 |   | O   | X   | O   | O   | O   |                                 |   |                   |

§ 174.81

49 CFR Ch. I (10-1-08 Edition)

(e) Instructions for using the segregation table for hazardous materials in paragraph (d) of this section are as follows:

(1) The absence of any hazard class or division, or a blank space in the table indicates that no restrictions apply.

(2) The letter “X” in the table indicates that these materials may not be loaded, transported, or stored together in the same rail car or storage facility during the course of transportation.

(3) The letter “O” in the table indicates that these materials may not be loaded, transported, or stored together in the same rail car or storage facility during the course of transportation unless separated in a manner that, in the event of leakage from packages under conditions normally incident to transportation, commingling of hazardous materials would not occur. Notwithstanding the methods of separation employed, Class 8 (corrosive) liquids may not be loaded above or adjacent to Class 4 (flammable) or Class 5 (oxidizing) materials; except that shippers may load carload shipments of such materials together when it is known that the mixture of contents would not cause a fire or a dangerous evolution of heat or gas.

(4) The “\*” in the table indicates that segregation among different Class 1 (explosive) materials is governed by the compatibility table in paragraph (f) of this section.

(5) The note “A” in the second column of the table means that, notwithstanding the requirements of the letter “X”, ammonium nitrate fertilizer may be loaded or stored with Division 1.1 (explosive) or Division 1.5 materials.

(6) When the §172.101 table or §172.402 of this subchapter requires a package to bear a subsidiary hazard label, segregation appropriate to the subsidiary hazard must be applied when that segregation is more restrictive than that required by the primary hazard. However, hazardous materials of the same class may be loaded and transported together without regard to segregation required by any secondary hazard if the materials are not capable of reacting dangerously with each other and causing combustion or dangerous evolution of heat, evolution of flammable, poisonous, or asphyxiant gases, or formation of corrosive or unstable materials.

(f) Class 1 (explosive) materials may not be loaded, transported, or stored together, except as provided in this section, and in accordance with the following table:

COMPATIBILITY TABLE FOR CLASS 1 (EXPLOSIVE) MATERIALS

| Compatibility group | A | B   | C   | D   | E   | F   | G   | H   | J   | K   | L | N   | S   |
|---------------------|---|-----|-----|-----|-----|-----|-----|-----|-----|-----|---|-----|-----|
| A .....             |   | X   | X   | X   | X   | X   | X   | X   | X   | X   | X | X   | X   |
| B .....             | X |     | X   | 4   | X   | X   | X   | X   | X   | X   | X | X   | 4/5 |
| C .....             | X | X   |     | 2   | 2   | X   | 6   | X   | X   | X   | X | 3   | 4/5 |
| D .....             | X | 4   | 2   |     | 2   | X   | 6   | X   | X   | X   | X | 3   | 4/5 |
| E .....             | X | X   | 2   | 2   |     | X   | 6   | X   | X   | X   | X | 3   | 4/5 |
| F .....             | X | X   | X   | X   | X   |     | X   | X   | X   | X   | X | X   | 4/5 |
| G .....             | X | X   | 6   | 6   | 6   | X   |     | X   | X   | X   | X | X   | 4/5 |
| H .....             | X | X   | X   | X   | X   | X   | X   |     | X   | X   | X | X   | 4/5 |
| J .....             | X | X   | X   | X   | X   | X   | X   | X   |     | X   | X | X   | 4/5 |
| K .....             | X | X   | X   | X   | X   | X   | X   | X   | X   |     | X | X   | 4/5 |
| L .....             | X | X   | X   | X   | X   | X   | X   | X   | X   | X   |   | 1   | X   |
| N .....             | X | X   | 3   | 3   | 3   | X   | X   | X   | X   | X   | X |     | 4/5 |
| S .....             | X | 4/5 | 4/5 | 4/5 | 4/5 | 4/5 | 4/5 | 4/5 | 4/5 | 4/5 | X | 4/5 |     |

(g) Instructions for using the compatibility table for Class 1 (explosive) materials in paragraph (f) of this section are as follows:

(1) A blank space in the table indicates that no restrictions apply.

(2) The letter “X” in the table indicates that explosives of different compatibility groups may not be carried on

the same rail car, unless packed in separate freight containers (e.g., two or more freight containers mounted upon the same rail car).

(3) The numbers in the table mean the following:

(i) “1” means explosives from compatibility group L may only be carried

## § 174.82

on the same rail car with an identical explosive.

(ii) “2” means any combination of explosives from compatibility group C, D, or E is assigned to compatibility group E.

(iii) “3” means any combination of explosives from compatibility group C, D, or E with those in compatibility group N is assigned to compatibility group D.

(iv) “4” means detonators and detonating primers, Division 1.4S (explosives), may not be loaded in the same car with Division 1.1 and 1.2 (explosive) materials.

(v) “5” means Division 1.4S fireworks may not be loaded in the same car with Division 1.1 or 1.2 (explosive) materials.

(vi) “6” means explosive articles in compatibility group G, other than fireworks and those requiring special stowage, may be loaded and transported with articles of compatibility groups C, D and E, provided no explosive substances are carried in the same rail car.

(h) Except as provided in paragraph (i) of this section, explosives of the same compatibility group but of different divisions may be transported together provided that the whole shipment is transported as though its entire contents were of the lower numerical division (i.e., Division 1.1 being lower than Division 1.2). For example, a mixed shipment of Division 1.2 (explosive) materials and Division 1.4 (explosive) materials, compatibility group D, must be transported as Division 1.2 (explosive) materials.

(i) When Division 1.5 materials, compatibility group D are transported in the same freight container as Division 1.2 (explosive) materials, compatibility group D, the shipment must be transported as Division 1.1 (explosive) materials, compatibility group D.

[Amdt. 174-68, 55 FR 52678, Dec. 21, 1990, as amended at 56 FR 66280-66281, Dec. 20, 1991; 57 FR 45464, Oct. 1, 1992; Amdt. 174-68, 57 FR 59310, Dec. 15, 1992; Amdt. 174-75, 58 FR 50237, Sept. 24, 1993; Amdt. 174-83, 61 FR 51339, Oct. 1, 1996; 64 FR 10781, Mar. 5, 1999; 66 FR 45383, Aug. 28, 2001; 67 15743, Apr. 3, 2002; 70 FR 3310, Jan. 24, 2005]

## 49 CFR Ch. I (10-1-08 Edition)

### Subpart D—Handling of Placarded Rail Cars, Transport Vehicles and Freight Containers

#### § 174.82 General requirements for the handling of placarded rail cars, transport vehicles, freight containers, and bulk packages.

(a) Unless otherwise specified, this subpart does not apply to the handling of rail cars, transport vehicles, freight containers, or bulk packagings, which contain Division 1.6, combustible liquids, Division 6.1 PG III materials, Class 9 materials, or ORM-D materials.

(b) A placarded rail car, transport vehicle, freight container, or bulk package may not be transported in a passenger train.

[Amdt. 174-68, 55 FR 52680, Dec. 21, 1990, as amended at 56 FR 66281, Dec. 20, 1991; 57 FR 45464, Oct. 1, 1992; Amdt. 174-74, 58 FR 51533, Oct. 1, 1993]

#### § 174.83 Switching placarded rail cars, transport vehicles, freight containers, and bulk packagings.

(a) In switching operations where the use of hand brakes is necessary—

(1) It must be determined by trial whether a loaded, placarded car, or a car occupied by a rider in a draft containing a placarded car, has its hand brakes in proper working condition before it is cut off;

(2) A loaded, placarded tank car or a draft which includes a loaded placarded tank car may not be cut off until the preceeding rail car clears the ladder track; and

(3) A loaded, placarded tank car or a draft which includes a loaded placarded tank car must clear the ladder track before another rail car is allowed to follow.

(b) Any loaded rail car placarded for a Division 1.1 or Division 1.2 explosive, a Division 2.3 Hazard Zone A gas or a Division 6.1 PG I Hazard Zone A material, or a Class DOT 113 tank car displaying a Division 2.1 (flammable gas) placard, including a Class DOT 113 tank car containing only a residue of a Division 2.1 material, may not be:

(1) Cut off while in motion;

(2) Coupled into with more force than is necessary to complete the coupling; or

(3) Struck by any car moving under its own momentum.

(c) A placarded flatcar, or a flatcar carrying a placarded transport vehicle, freight container, or bulk packaging under this subchapter may not be cut off while in motion.

(d) No rail car moving under its own momentum may be permitted to strike any placarded flatcar or any flatcar carrying a placarded transport vehicle, freight container, or bulk packaging.

(e) No placarded flatcar or any flatcar carrying a placarded transport vehicle, freight container, or bulk packaging may be coupled into with more force than is necessary to complete the coupling.

(f) When transporting a rail car, transport vehicle, or freight container placarded for Division 1.1 or 1.2 (explosive) materials in a terminal, yard, or on a side track or siding, the placarded rail car must be separated from the engine by at least one non-placarded rail car and must be placed in a location so that it will be safe from danger of fire. A rail car, transport vehicle, or freight container placarded for Division 1.1 or 1.2 (explosive) materials may not be placed under a bridge or overhead crossing, or in or alongside a passenger shed or station, except during transfer operations.

[Amdt. 174-68, 55 FR 52680, Dec. 21, 1990, as amended at 56 FR 66281, Dec. 20, 1991; Amdt. 174-75, 58 FR 50237, Sept. 24, 1993; Amdt. 174-77, 59 FR 48549, Sept. 21, 1994; Amdt. 174-83, 61 FR 51339, Oct. 1, 1996; 66 FR 45383, Aug. 28, 2001]

**§ 174.84 Position in train of loaded placarded rail cars, transport vehicles, freight containers or bulk packagings when accompanied by guards or technical escorts.**

A rail car placarded in Division 1.1 or 1.2 (explosive); Division 2.3 (Hazard Zone A; poisonous gas); or Division 6.1 (PG I, Hazard Zone A; poisonous liquid) in a moving or standing train must be next to and ahead of any car occupied by the guards or technical escorts accompanying the placarded rail car. However, if a rail car occupied by the guards or technical escorts has temperature control equipment in operation, it must be the fourth car behind any car requiring Division 1.1 or 1.2 (explosive) placards.

[Amdt. 174-68, 55 FR 52680, Dec. 21, 1990, as amended at 56 FR 66281, Dec. 20, 1991; 66 FR 45383, Aug. 28, 2001]

**§ 174.85 Position in train of placarded cars, transport vehicles, freight containers, and bulk packagings.**

(a) Except as provided in paragraphs (b) and (c) of this section, the position in a train of each loaded placarded car, transport vehicle, freight container, and bulk packaging must conform to the provisions of this section.

(b) A car placarded "RADIOACTIVE" must comply with train positioning requirements of paragraph (d) of this section and must be separated from a locomotive, occupied caboose, or carload of undeveloped film by at least one non-placarded car.

(c) A tank car containing the residue of a hazardous material must be separated from a locomotive or occupied caboose by at least one rail car other than a placarded tank car.

(d) Position of rail cars in a train. In the following table:

POSITION IN TRAIN OF PLACARDED CARS TRANSPORTING HAZARDOUS MATERIALS

| RESTRICTIONS                                                                                                                                                                                          | Placard Group 1 | Placard Group 2 |          | Placard Group 3 |          | Placard Group 4 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|-----------------|----------|-----------------|----------|-----------------|
|                                                                                                                                                                                                       | Rail Car        | Tank Car        | Rail Car | Tank Car        | Rail Car | Rail Car        |
| 1. When train length permits, placarded car may not be nearer than the sixth car from the engine or occupied caboose.                                                                                 | X               | X               |          | X               |          |                 |
| 2. When train length does not permit, placarded car must be placed near the middle of the train, but not nearer than the second car from an engine or occupied caboose.                               | X               | X               |          | X               |          |                 |
| 3. A placarded car may not be placed next to an open-top car when any of the lading in the open top car protrudes beyond the car ends, or if the lading shifted, would protrude beyond the car ends.. | X               | X               |          | X               |          |                 |

## POSITION IN TRAIN OF PLACARDED CARS TRANSPORTING HAZARDOUS MATERIALS—Continued

| RESTRICTIONS                                                                                                                                                                                                                                                             | Placard Group 1 | Placard Group 2 |          | Placard Group 3 |          | Placard Group 4 |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|-----------------|----------|-----------------|----------|-----------------|
|                                                                                                                                                                                                                                                                          | Rail Car        | Tank Car        | Rail Car | Tank Car        | Rail Car | Rail Car        |
| 4. A placarded car may not be placed next to a loaded flat car, except closed TOFC/COFC equipment, auto carriers, and other specially equipped cars with tie-down devices for securing vehicles. Permanent bulk head flat cars are considered the same as open-top cars. | X               | X               |          | X               |          |                 |
| 5. A placarded car may not be placed next to any transport vehicle or freight container having an internal combustion engine or an open-flame device in operation..                                                                                                      | X               | X               |          | X               |          |                 |
| 6. Placarded cars may not be placed next to each other based on the following:                                                                                                                                                                                           |                 |                 |          |                 |          |                 |
| Placard Group 1 .....                                                                                                                                                                                                                                                    |                 | X               | X        | X               | X        | X               |
| Placard Group 2 .....                                                                                                                                                                                                                                                    | X               |                 |          | X               | X        | X               |
| Placard Group 3 .....                                                                                                                                                                                                                                                    | X               | X               | X        |                 |          | X               |
| Placard Group 4 .....                                                                                                                                                                                                                                                    | X               | X               | X        | X               | X        |                 |

## PLACARD GROUP:

Group 1—Divisions 1.1 and 1.2 (explosive) materials.

Group 2—Divisions 1.3, 1.4, 1.5 (explosive), Class 2 (compressed gas; other than Div 2.3, PG I, Zone A), Class 3 (flammable liquid), Class 4 (flammable solid), Class 5 (oxidizing), Class 6 (poisonous liquid; other than Div 6.1, PG I, Zone A), and Class 8 (corrosive) materials.

Group 3—Divisions 2.3 (Zone A; poisonous gas) and 6.1 (PG I, Zone A; poisonous liquid) materials.

Group 4—Class 7 (radioactive) materials.

(1) Where an “X” appears at the intersection of a Placard Group column and a Restriction row, the corresponding restriction applies.

(2) “Rail Car” means a car other than a tank car.

(3) For purposes of this subpart, each unit of an articulated intermodal rail car shall be considered as one car.

[Amdt. 174–68, 55 FR 52680, Dec. 21, 1990, as amended at 57 FR 45464, Oct. 1, 1992; Amdt. 174–83, 61 FR 28678, June 5, 1996; Amdt. 174–83, 61 FR 50255, Sept. 25, 1996; Amdt. 174–83, 61 FR 51339, Oct. 1, 1996; 64 FR 51919, Sept. 27, 1999; 66 FR 45383, Aug. 28, 2001]

### § 174.86 Maximum allowable operating speed.

For molten metals and molten glass shipped in packagings other than those prescribed in §173.247 of this subchapter, the maximum allowable operating speed may not exceed 15 mph for shipments by rail.

[Amdt. 174–69, 56 FR 49990, Oct. 2, 1991]

## Subpart E—Class I (Explosive) Materials

### § 174.101 Loading Class 1 (explosive) materials.

(a) Boxes containing Division 1.1 or 1.2 (explosive) materials must be loaded so that the ends of wooden boxes

will not bear against sides of any fiber-board boxes and so that the ends of any box will not cause a pressure point on a small area of another box.

(b) Explosive bombs, unfuzed projectiles, rocket ammunition and rocket motors, Division 1.1, 1.2, or 1.3 (explosive) materials, which are not packed in wooden boxes, or large metal packages of incendiary bombs, each weighing 226 kg (500 pounds) or more, may be loaded in stock cars or in flat bottom gondola cars only if they are adequately braced. Boxed bombs, rocket ammunition and rocket motors, Division 1.1, 1.2, or 1.3 (explosive) materials, which due to their size cannot be loaded in closed cars, may be loaded in open-top cars or on flatcars, provided they are protected from the weather and accidental ignition.

(c) Boxes of Division 1.1 or 1.2 (explosive) materials packed in long cartridges, bags, or sift-proof liners, and containing no liquid explosive ingredient, may be loaded on their sides or ends.

(d) Division 1.1 or 1.2 (explosive) materials may not be loaded higher than any permanent car lining unless additional lining is provided as high as the lading.

(e) When the lading of a car includes any Class 1 (explosive) materials, the

weight of the lading must be distributed insofar as possible to equalize the weight on each side of the car and over the trucks.

(f) Except when boxed, metal kegs containing Class 1 (explosive) materials must be loaded on their sides with their ends toward the ends of the car. Packages of Class 1 (explosive) materials may not be placed in the space opposite the doors unless the doorways are boarded on the inside as high as the lading. This paragraph does not apply to palletized packages if they are braced so they cannot fall or slide into the doorways during transportation.

(g) Wooden kegs, fiber kegs, barrels, and drums must be loaded on their sides or ends, to best suit the conditions.

(h) Packages containing any Division 1.1 or 1.2 (explosive) materials for (see § 174.104), detonators, detonator assemblies, or boosters with detonators must be securely blocked and braced to prevent the packages from changing position, falling to the floor, or sliding into each other, under conditions normally incident to transportation. Class 1 (explosive) materials must be loaded so as to avoid transfer at stations. For recommended methods of blocking and bracing, see Bureau of Explosives Pamphlets No. 6 and 6A. Heavy packages or containers must be trucked, rolled, or moved by skids, fork trucks, or other handling devices and may not be dropped from trucks, platforms, or cars. Planks for rolling trucks from platforms to cars must have beveled ends. Loading platforms and the shoes of each workman must be free from grit. All possible precautions must be taken against fire. Class 1 (explosive) materials must be kept in a safe place and inaccessible to unauthorized persons while being held by a carrier for loading or delivery.

(i) To prevent delays of local freight trains, when there are shipments of Class 1 (explosive) materials for different destinations loaded in a "peddler car" or "way car" the shipment for each destination must be stayed separately.

(j) Forwarding and transfer stations for Class 1 (explosive) materials must be provided with the necessary materials for staying.

(k) Shippers must furnish the material for staying packages of Class 1 (explosive) materials loaded by them.

(l) Division 1.1 or 1.2 (explosive) materials may not be loaded, transported, or stored in a rail car equipped with any type of lighted heater or open-flame device, or electric devices having exposed heating coils, or in a rail car equipped with any apparatus or mechanism utilizing an internal combustion engine in its operation.

(m) [Reserved]

(n) A container car or freight container on a flatcar or a gondola car other than a drop-bottom car, when properly loaded, blocked, and braced to prevent change of position under conditions normally incident to transportation, may be used to transport any Division 1.1 or 1.2 (explosive) material except black powder packed in metal containers. A freight container must be designed, constructed, and maintained so as to be weather tight and capable of preventing the entrance of sparks. In addition:

(1) A freight container must be of such design and so braced as to show no evidence of failure of the container or the bracing when subjected to impact from each end of at least 13 km (8.1 miles) per hour. Its efficiency shall be determined by actual test, using dummy loads equal in weight and general character to material to be shipped.

(2) A container car or car which is loaded with freight containers must be placarded with the Class 1 (explosive) materials placards as required by subpart F of part 172 of this subchapter and with properly executed car certificates as required by § 174.104.

(3) Lading must be so loaded, blocked, and braced within the freight container that it will not change position under impact from each end of at least 13 km (8.1 miles) per hour.

(o) Division 1.1, 1.2, or 1.3 (explosive) materials may be loaded and transported in a tight closed truck body or trailer on a flatcar. Wooden boxed bombs, rocket ammunition, and rocket motors, Division 1.1, 1.2, or 1.3 (explosive) materials, which due to their size cannot be loaded in tight, closed truck bodies or trailers, may be loaded in or on open-top truck bodies or trailers.



## § 174.102

However, they must be protected against accidental ignition. In addition:

(1) Each truck body or trailer must meet the requirements of part 177 of this subchapter, applicable to shipments of Class 1 (explosive) materials by motor vehicle.

(2) Each truck body or trailer must be so secured on the rail car so that it will not permanently change position or show evidence of failure or impending failure of the method of securing the truck body or trailer under impact from each end of at least 13 km (8.1 miles) per hour. Its efficiency shall be determined by actual test, using dummy loads equal in weight and general character to the material to be shipped. For recommended methods of blocking and bracing, see Bureau of Explosives Pamphlet 6C.

(3) Lading must be so loaded, blocked, and braced within or on the truck body or trailer that it will not change position under impact from each end of at least 13 km (8.1 miles) per hour. For recommended methods of blocking and bracing see Bureau of Explosives Pamphlet 6C.

(4) Each rail car containing Class 1 (explosive) materials and each rail car loaded with truck bodies, trailers or containers containing Class 1 (explosive) materials must be placarded with Class 1 (explosive) materials placards as required by subpart F of part 172 of this subchapter and with properly executed car certificates as required by § 174.104.

(5) Each fuel tank of a heater or refrigerating machinery on the truck bodies or trailers must be drained and all automatic heating or refrigerating machinery must be made inoperative by disconnection of the automatic controls or the source of power for their operations.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174-26B, 41 FR 57071, Dec. 30, 1976; Amdt. 174-36, 44 FR 70732, Dec. 10, 1979; Amdt. 174-59, 51 FR 5974, Feb. 18, 1986; Amdt. 174-68, 55 FR 52681, Dec. 21, 1990; Amdt. 174-83, 61 FR 51339, Oct. 1, 1996; 66 FR 45383, Aug. 28, 2001]

## 49 CFR Ch. I (10-1-08 Edition)

### § 174.102 Forbidden mixed loading and storage.

(a) Division 1.1 or 1.2 (explosive) materials and initiating or priming explosives may not be transported together in the same rail car. Additionally, they may not be transported or loaded in the same rail car or stored on carrier property with charged electric storage batteries or with any hazardous material for which a NONFLAMMABLE GAS, FLAMMABLE GAS, FLAMMABLE LIQUID, FLAMMABLE SOLID, OXIDIZER, ORGANIC PEROXIDE, RADIOACTIVE or CORROSIVE label is required.

(b) Class 1 (explosive) materials may not be loaded together or with other hazardous materials, except as provided in § 174.81. See § 174.104 for loading shipments of Class 1 (explosive) materials or any other material in a placarded and certified car containing a shipment of Division 1.1 or 1.2 (explosive) materials.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-68, 55 FR 52681, Dec. 21, 1990; 66 FR 45383, Aug. 28, 2001]

### § 174.103 Disposition of damaged or astray shipments.

(a) Packages of Class 1 (explosive) materials found damaged or broken in transit may be repaired when practicable and not dangerous. A broken box of Division 1.1 or 1.2 (explosive) materials that cannot be repaired must be reinforced by stout wrapping paper and twine, placed in another strong box and surrounded by dry, fine sawdust or dry and clean cotton waste or elastic wads made from dry newspapers. A ruptured can or keg must be sealed and enclosed in a strong cloth bag of good quality and boxed. Damaged packages thus protected and properly marked may be forwarded. The box and waybill must be marked to indicate that it has been repacked.

(b) Care must be exercised in repacking damaged containers so that no spark is produced by contact of metal or other hard surfaces which could ignite loose particles of explosive compositions that may be strewn on car floors or freight. In addition, the car floors must be thoroughly swept, and washed with a plentiful supply of

water. Iron-wheel trucks, metal hammers, or other metal tools that may produce sparks may not be used. Metal tools must be limited to those made of brass, bronze, or copper.

(c) Each package of Class 1 (explosive) materials showing evidence of leakage of liquid ingredients must:

(1) Be refused if leakage is discovered before acceptance;

(2) Be disposed of to a person who is competent and willing to remove them from the carrier's property, if the leakage is discovered while the shipment is in transit; or

(3) Be removed immediately by consignee, if the leakage is discovered at the shipment's destination.

(d) When the disposition required by paragraph (c) of this section cannot be made, the leaking package must be packed in other boxes large enough to permit enclosure and the leaking boxes must be surrounded by at least 5 cm (2 inches) of dry, fine sawdust or dry and clean cotton waste, and be stored in a station magazine or other safe place until the arrival of an inspector of the Bureau of Explosives, or other authorized person, to superintend the destruction or disposition of the condemned material.

(e) If careful inspection shows that an astray shipment of Class 1 (explosive) materials is in proper condition for safe transportation, it must be forwarded immediately to its destination if known, or returned to the shipper by the most practicable route.

(f) When a package in an astray shipment is not in proper condition for safe transportation (see paragraphs (a), (c), and (d) of this section), or when the name and address of the consignee and the shipper are unknown, disposition must be made as prescribed by paragraphs (c) and (d) of this section.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-68, 55 FR 52681, Dec. 21, 1990; 66 FR 45383, Aug. 28, 2001]

**§ 174.104 Division 1.1 or 1.2 (explosive) materials; car selection, preparation, inspection, and certification.**

(a) Except as provided in § 174.101 (b), (n), and (o), Division 1.1 or 1.2 (explosive) materials being transported by rail may be transported only in a certified and properly placarded closed car

of not less than 36,300 kg (80,028 pounds) capacity, with steel underframes and friction draft gear or cushioned underframe, except that on a narrow-gauge railroad they may be transported in a car of less capacity as long as the car of greatest capacity and strength available is used.

(b) Each rail car used for transporting Division 1.1 or 1.2 (explosive) materials must meet the following requirements as applicable:

(1) The car must be equipped with air brakes, hand brakes, and roller bearings which are in condition for service.

(2) The car may not have any holes or cracks in the roof, sides, ends, or doors through which sparks may enter, or unprotected decayed spots which may hold sparks and start a fire.

(3) The roof of the car must be carefully inspected from the outside for decayed spots, especially under or near the running board, and such spots must be covered or repaired to prevent their holding fire from sparks. A car with a roof generally decayed, even if tight, may not be used.

(4) The doors must close tightly so that sparks cannot get in at the joints, and, if necessary to achieve this degree of tightness, the doors must be stripped. The stripping should be placed on the inside and fastened to the door frames where it will form a shoulder against which the closed doors are pressed by means of wedges or cleats in door shoes or keepers. The openings under the doors should be similarly closed. The hasp fastenings must be examined with the doors closed and fastened, and the doors must be cleated when necessary to prevent them from shifting. When the car is opened for any reason, the wedges or cleats must be replaced before car containing Class 1 (explosive) materials is permitted to proceed.

(5) The roller bearings and the trucks must be carefully examined and put in such condition as to reduce to a minimum the danger of hotboxes or other failure necessitating the setting out of the car before reaching its destination.

(6) The car must be carefully swept out before it is loaded. For less-than-carload shipments the space in which the packages are to be loaded must be

carefully swept. If evidence of a potential hazardous residue is apparent after the floor has been swept, the carrier must either decontaminate the car or provide a suitable substitute car.

(7) Any holes in the floor or lining must be repaired and special care taken that there are no projecting nails or bolts or exposed pieces of metal which may work loose or produce holes in packages of Class 1 (explosive) materials during transit. Protruding nails in the floor or lining which have worked loose must be drawn, and if necessary for the purpose of fastening the floor or lining, new nails must be driven through other parts thereof.

(8) Metal floor plates must be completely covered with wood, plywood, or fiber or composition sheets of adequate thickness and strength to prevent contact of the floor plates with the packages of Class 1 (explosive) materials under conditions incident to transportation, except that the covering of metal floor plates is not necessary for carload shipments loaded by the Department of Defense provided the Class 1 (explosive) materials are of such nature that they are not liable to leakage of dust, powder, or vapor which might become the cause of an explosion.

(9) If the car is equipped with automobile loading devices, it may not be used unless the loading device is securely attached to the roof of the car with fastenings supplementing those already provided and so fixed that it cannot fall.

(10) The car must be equipped with high-friction composition brake shoes (except metal deck flat cars used for COFC/TOFC service may be equipped with high phosphorus cast iron brake shoes) and brake rigging designed for this type of brake shoe. Each brake shoe on the car must be at least 1 cm (0.4 inch) thick, and in safe and suitable condition for service.

(11) The car must have either a metal subfloor with no combustible material exposed beneath the car, or metal spark shields extending from center sill to side sills and from end sills to at least 30 cm (12 inches) beyond the extreme treads of the inside wheels of each truck, which are tightly fitted against the subfloor so that there is no

vacant space or combustible material exposed. The metal subfloor or spark shields may not have an accumulation of oil, grease, or other debris which could support combustion.

(c) Before Division 1.1 or 1.2 (explosive) materials may be loaded into a rail car, the car must have been inspected and certified to be in compliance with the requirements of paragraph (b) of this section by a qualified person designated under §215.11 of this title. The certification shall be made in Car Certificate No. 1 on the form prescribed in paragraph (f) of this section.

(d) If the carrier furnishes the car to a shipper for loading Division 1.1 or 1.2 (explosive) materials, the shipper or his authorized employee shall, before commencing the loading of the car, inspect the interior thereof, and after loading certify to the proper condition of the car and the loading. This certification shall be made on the first signature line in Car Certificate No. 2 on the form prescribed in paragraph (f) of this section. In addition, the finished load must be inspected and certified to be in compliance with the requirements of this part by a qualified person designated under §215.11 of this title before the car goes forward. This certification shall be made on the second signature line in Car Certificate No. 2 on the form prescribed in paragraph (f) of this section. If the loading is performed by the carrier, Car Certificate No. 2 may only be signed by a qualified person designated under §215.11 of this title.

(e) If a trailer or container containing Division 1.1 or 1.2 (explosive) materials is loaded on a flatcar, the loading and securing of the load on the car must be supervised by a representative of the shipper or carrier. The certification shall be made in Car Certificate No. 3 on the form prescribed in paragraph (f) of this section.

(f) Each car certificate for use in connection with the inspection of rail cars for the carriage of Division 1.1 or 1.2 (explosive) materials shall be printed on strong tag board measuring 18 by 18 cm (7.1 by 7.1 inches) or 15 by 20 cm (5.9 by 7.9 inches). It must be duly executed in triplicate by the carrier, and by the shipper if he loads the shipments. The original must be filed by the carrier at

the forwarding station in a separate file and the other two must be attached to the car, one to each outer side on a fixed placard board or as otherwise provided.

\_\_\_\_\_ Railroad

#### CAR CERTIFICATE

No. 1 \_\_\_\_\_ Station \_\_\_\_\_  
19\_\_\_\_.

I hereby certify that I have this day personally examined Car Number \_\_\_\_\_ and that the car is in condition for service and complies with the FRA Freight Car Safety Standards (49 CFR part 215) and with the requirements for freight cars used to transport explosives prescribed by the DOT Hazardous Materials Regulation (49 CFR part 174).

Qualified Person Designated Under  
49 CFR 215.11

No. 2 \_\_\_\_\_ Station \_\_\_\_\_  
19\_\_\_\_.

I have this day personally examined the above car and hereby certify that the explosives in or on this car, or in or on vehicles or in containers have been loaded and braced; that placards have been applied, according to the regulations prescribed by the Department of Transportation; and that the doors of cars so equipped fit or have been stripped so that sparks cannot enter.

Shipper or his authorized agent

Qualified Person Designated Under  
49 CFR 215.11

No. 3 \_\_\_\_\_ Station \_\_\_\_\_  
19\_\_\_\_.

I hereby certify that I have this day personally supervised the loading of the vehicles or containers on and their securement to the above car.

Shipper or railway employee inspecting  
loading and securement

NOTE 1: A shipper must decline to use a car not in proper condition.

NOTE 2: All certificates, where applicable, must be signed.

NOTE 3: Car certificates remaining on hand as of the effective date of these regulations may be used until stocks are exhausted but not after July 1, 1977.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 174.104, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 174.105 Routing shipments, Division 1.1 or 1.2 (explosive) materials.

Before a shipment of Division 1.1 or 1.2 (explosive) materials destined to a point beyond the lines of the initial carrier is accepted from the shipper, the initial carrier shall ascertain that the shipment can go forward by the route designated. To avoid delays en route, the initial carrier must be in possession of full rate information before forwarding the shipment.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-68, 55 FR 52682, Dec. 21, 1990; 66 FR 45383, Aug. 28, 2001]

#### § 174.106 "Order-Notify" or "C.O.D." shipments, Division 1.1 or 1.2 (explosive) materials.

(a) A carrier may not accept for transportation Division 1.1 or 1.2 (explosive) materials, detonators, or detonating primers in any quantity when consigned to "order-notify" or "C.O.D.," except on a through bill of lading to a place outside the United States.

(b) A carrier may not accept for transportation Division 1.1 or 1.2 (explosive) materials, detonators, or detonating primers which the shipper consigns to himself unless the shipper has a resident representative to receive them at the delivery point.

(c) A carrier may not accept Division 1.1 or 1.2 (explosive) materials for transportation subject to "stop-off privileges en route for partial loading or unloading."

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-36, 44 FR 70732, Dec. 10, 1979; Amdt. 174-68, 55 FR 52682, Dec. 21, 1990; 66 FR 45383, Aug. 28, 2001]

#### § 174.110 Car magazine.

When specially authorized by the carrier, Division 1.1 or 1.2 (explosive) materials in quantity not exceeding 68 kg (150 pounds) may be carried in construction or repair cars if the packages of Class 1 (explosive) materials are placed in a "magazine" box made of sound lumber not less than 2.5 cm (0.98 inch) thick, covered on the exterior with metal, and provided with strong handles. The box must be plainly stenciled on the top, sides, and ends, in letters not less than 5 cm (2 inches) high,

## § 174.112

“EXPLOSIVES—DANGEROUS—HANDLE CAREFULLY”. The box must be provided with strong hinges and with a lock for keeping it securely closed. Vacant space in the box must be filled with a cushioning material such as sawdust or excelsior, and the box must be properly stayed to prevent shifting within the car. The car must be placarded with EXPLOSIVES 1.1 or 1.2 (EXPLOSIVES A) placards when the magazine contains Division 1.1 or 1.2 (explosive) materials.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174-68, 55 FR 52682, Dec. 21, 1990; 66 FR 45383, Aug. 28, 2001; 68 FR 61942, Oct. 30, 2003]

### § 174.112 Loading Division 1.3 materials and Division 1.2 (explosive) materials (Also see § 174.101).

(a) Division 1.3 materials and Division 1.2 (explosive) materials may not be loaded, transported or stored in a rail car equipped with any type of lighted heater or open-flame device, or in a rail car equipped with any apparatus or mechanism utilizing an internal combustion engine in its operation.

(b) Except as provided in § 174.101(b), (n), or (o) Division 1.3 materials and Division 1.2 (explosive) materials must be transported in a closed car or container car which is in good condition, and into which sparks cannot enter. The car does not require the car certificates prescribed in § 174.104(c) through (f). If the doors are not tight, they must be stripped to prevent the entrance of sparks. Wood floored cars must be equipped with spark shields (see § 174.104). Packages of Division 1.3 materials and Division 1.2 (explosive) materials must be blocked and braced to prevent their shifting and possible damage due to shifting of other freight during transportation. For recommended methods of blocking and bracing see Bureau of Explosives Pamphlet No. 6.

(c) Division 1.3 materials and Division 1.2 (explosive) materials may not be transported in a truck body, trailer, or container on a flatcar unless:

- (1) The truck body, trailer, or container is closed and tight;
- (2) All automatic heating or refrigerating machinery with which the

## 49 CFR Ch. I (10-1-08 Edition)

truck body, trailer, or container is equipped is inoperative; and

(3) Packages of Division 1.3 materials and Division 1.2 (explosive) materials are blocked and braced within the truck body, trailer, or container to prevent their shifting and possible damage due to shifting of other freight during transportation (ends, sidewalls, or doors of the truck body, trailer, or container may not be relied on to prevent the shifting of heavy loads). For recommended methods of blocking and bracing see Bureau of Explosives Pamphlet No. 6C. See § 174.101(o).

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-26B, 41 FR 57072, Dec. 30, 1976; Amdt. 174-68, 55 FR 52682, Dec. 21, 1990; Amdt. 174-83, 61 FR 51339, Oct. 1, 1996; 66 FR 45383, Aug. 28, 2001; 68 FR 61942, Oct. 30, 2003]

### § 174.114 Record to be made of change of seals on “Cars loaded with Division 1.1 or 1.2 (explosive) materials”.

When a car seal is changed on a car requiring “EXPLOSIVES 1.1 or EXPLOSIVES 1.2 (EXPLOSIVES A) placards” while en route or before delivery to a consignee, a record of the change showing the following information must be made on or attached to the waybill or other form of memorandum which must accompany the car to its destination:

|                                                        |            |                                      |
|--------------------------------------------------------|------------|--------------------------------------|
| Railroad                                               | Place      | Date                                 |
| Car Initials                                           | Car Number | Number or description of seal broken |
| Number or description of seal used to reseal car _____ |            |                                      |
| Reasons for opening car _____                          |            |                                      |
| Condition of load _____                                |            |                                      |
| Name and occupation of person opening car _____        |            |                                      |

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174-68, 55 FR 52682, Dec. 21, 1990]

**§ 174.115 Loading Division 1.4 (explosive) materials.**

(a) Division 1.4 (explosive) materials may be loaded into any closed car in good condition, or into any container car in good condition. Car certificates are not required. Packages of Division 1.4 (explosive) materials must be blocked and braced to prevent their shifting and possible damage due to shifting of other freight during transportation. For methods of recommended loading and bracing see Bureau of Explosives Pamphlet No. 6.

(b) Division 1.4 (explosive) materials may not be transported in a truck body, trailer, or container on a flatcar unless:

(1) The truck body, trailer, or container is closed and tight;

(2) All automatic heating or refrigerating machinery with which the truck body, trailer, or container is equipped is inoperative; and

(3) Packages of Division 1.4 (explosive) materials are blocked and braced within the truck body, trailer, or container to prevent their shifting and possible damage due to shifting of other freight during transportation. Ends, side walls, or doors of the truck body, trailer, or container may not be relied on to prevent shifting of heavy loads. For recommended methods of blocking and bracing see Bureau of Explosives Pamphlet No. 6C.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-36, 44 FR 70732, Dec. 10, 1979; Amdt. 174-68, 55 FR 52682, Dec. 21, 1990; 66 FR 45383, Aug. 28, 2001; 68 FR 61942, Oct. 30, 2003]

**Subpart F—Detailed Requirements for Class 2 (Gases) Materials****§ 174.200 Special handling requirements.**

(a) Division 2.1 (flammable gas) materials may not be loaded, transported, or stored in a rail car equipped with any type of lighted heater or open-flame device, or in a rail car equipped with any apparatus or mechanism utilizing an internal combustion engine in its operation.

(b) Division 2.1 (flammable gas) materials may not be loaded in a truck body or trailer equipped with any type of lighted heater or any automatic

heating or refrigerating apparatus when such truck bodies or trailers are loaded on flatcars except as provided in paragraph (c) of this section.

(c) Heating or refrigeration apparatus may be operated on a motor vehicle loaded on a flatcar when the motor vehicle is loaded with Division 2.1 (flammable gas) materials only if:

(1) The lading space is not equipped with any electrical apparatus that is not non-sparking or explosion-proof;

(2) There is no combustion apparatus in the lading space;

(3) There is no connection for the return of air from the lading space to any combustion apparatus; and

(4) The heating system conforms to § 393.77 of this title and does not heat any part of the lading over 54 °C (129 °F).

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-68, 55 FR 52682, Dec. 21, 1990; 56 FR 66281, Dec. 20, 1991]

**§ 174.201 Class 2 (gases) material cylinders.**

(a) Except as provided in paragraphs (b) and (c) of this section, cylinders containing Class 2 (gases) materials being transported in a rail car must be:

(1) Securely lashed in an upright position so as to prevent their overturning;

(2) Loaded into racks securely attached to the car;

(3) Packed in boxes or crates of such dimensions as to prevent their overturning; or

(4) Loaded in a horizontal position.

(b) Specification DOT-4L (§ 178.57 of this subchapter) cylinders being transported in a rail car must be loaded in an upright position and be securely braced.

(c) Cylinders containing Class 2 (gases) materials may be transported in stock cars, gondola cars and flat cars. However, they may not be transported in hopper bottom cars.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174-32, 43 FR 48644, Oct. 19, 1978; Amdt. 174-68, 55 FR 52682, Dec. 21, 1990]

**§ 174.204 Tank car delivery of gases, including cryogenic liquids.**

(a) A tank car containing Class 2 (gases) material may not be unloaded

## § 174.290

## 49 CFR Ch. I (10–1–08 Edition)

unless it is consigned for delivery and unloaded on a private track (see § 171.8 of this subchapter). However, if a private track is not available, it may be delivered and unloaded on carrier tracks subject to the following conditions:

(1) A tank car of DOT-106A or 110A type (§ 179.300 or § 179.301 of this subchapter) may not be delivered and the loaded unit tanks may not be removed from the car frame on carrier tracks. However, a carrier may give permission for the unloading of these containers on carrier tracks only if a private siding is not available within a reasonable trucking distance of the final destination. In addition, before the car is accepted for transportation, the shipper must obtain from the delivering carrier and file with the originating carrier, written permission for the removal and the consignee must furnish an adequately strong mechanical hoist by which the tanks can be lifted from the car and deposited directly upon vehicles furnished by the consignee for immediate removal from carrier property.

(2) The following tank cars may not be delivered and unloaded on carrier tracks unless the lading is piped directly from the car to permanent storage tanks of sufficient capacity to receive the entire contents of the car; however, such cars may be stored on a private track (see § 171.8 of this subchapter) or on carrier tracks designated by the carrier for such storage:

(i) A tank car containing Division 2.1 (flammable gas) material that is a cryogenic liquid; or

(ii) A tank car, except for a DOT-106A or 110A multi-unit tank car tank (§ 179.300 or § 179.301 of this subchapter), containing anhydrous ammonia; hydrogen chloride, refrigerated liquid; hydrocarbon gas, liquefied; or liquefied petroleum gas; and having interior pipes for liquid and gas discharge valves equipped with check valves.

(b) [Reserved]

[Amdt. 174–26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174–26A, 41 FR 40685, Sept. 20, 1976; Amdt. 174–32, 43 FR 48644, Oct. 19, 1978; Amdt. 174–43, 48 FR 27699, June 16, 1983; 48 FR 50440, 50441, Nov. 1, 1983; Amdt. 174–68, 55 FR 52682, Dec. 21, 1990]

### **§ 174.290 Materials extremely poisonous by inhalation shipped by, for, or to the Department of Defense.**

(a) General. The provisions of this section apply only to materials extremely poisonous by inhalation which are Division 2.3 materials in Hazard Zone A and Division 6.1 materials in Hazard Zone A, as defined in § 173.133(a)(2) of this subchapter. Such materials when shipped by, for, or to the Department of Defense may be transported by rail only if loaded and handled in accordance with the requirements of this section.

(b) A Division 2.3 Hazard Zone A or a Division 6.1 Hazard Zone A material extremely poisonous by inhalation may be transported in:

(1) UN 1N1 or UN 1N2 metal drums or equivalent military specification metal drums, by boxcar, gondola car (flat bottom), or stock car in carload lots. See §§ 174.55 and 174.600 for blocking, bracing, and stowage requirements;

(2) Tanks which are authorized under this subchapter for a Hazard Zone A material extremely poisonous by inhalation, Specification DOT 106A (§§ 179.300 and 179.301 of this subchapter), mounted on or secured to a multi-unit car or gondola car (flat bottom) in carload lots only;

(3) Bombs, by boxcar, or gondola car (flat bottom) in carload lots only; or

(4) Projectiles or ammunition for cannon with gas filled projectiles, by boxcar in carload or less-than-carload lots.

(c) Each shipment of one or more carloads of a material extremely poisonous by inhalation, as described in paragraph (b) of this section, must be accompanied by a Department of Defense qualified escort supplied with equipment to handle leaks and other packaging failures which could result in escape of the material. The escort shall remain with the shipment during the entire time that it is in the custody of the carrier and in the event of leakage or escape of material, shall make repairs and perform decontamination as necessary.

(d) When a material extremely poisonous by inhalation is transported in a tank, the tank must be securely

mounted on a rail car especially provided for it or on a gondola car prepared with substantial wooden frames and blocks.

(e) Bombs, projectiles, and cannon ammunition being transported by rail must be loaded, blocked and braced as shown in Bureau of Explosives Pamphlet No. 6A, or Department of Defense specifications. When a shipment is loaded in a gondola car it must be securely blocked and braced and not loaded higher than the sides of the car.

(f) When a material extremely poisonous by inhalation is transported in drums with filling holes in the heads, they must be loaded on their bottoms. They may be loaded in rows, lengthwise of the car and any space between the sides of the car and the nearest row of drums must be "filled in" with wooden boards or lumber nailed to sides of the car sufficient in length and width to contact both hoops of drums, or they may be loaded across the car in staggered stacks of which the number of drums in alternate stacks is reduced by one drum. All drums in stacks following the first stack loaded in the end of the car must be placed tightly into the angle of the space formed by the sidewalls of the drum in the preceding stack. Any space between the sides of the car and the drums in stacks having the greater number of drums must be filled in with wooden boards or lumber nailed to sides of the car sufficient in length and width to contact both hoops of the drums.

(g) When a material extremely poisonous by inhalation is transported in drums with filling holes in the sides, they must be loaded on their sides with the filling holes up. They must be loaded lengthwise of the car in rows and any space between the sides of the car and the nearest row of drums must be filled in with wooden boards or lumber nailed to sides of the car sufficient in length and width to contact both hoops of the drums.

(h) When a material extremely poisonous by inhalation is transported in drums in a boxcar, they must be loaded from ends of the car toward the space between the car doors, and there braced by center gates and wedges. See Sketch 1, Bureau of Explosives Pamphlet No. 6.

(i) The doorways of a boxcar in which a material poisonous by inhalation is being transported must be protected by one of the methods prescribed in Sketch 1, Bureau of Explosives Pamphlet No. 6A.

[Amdt. 174-68, 55 FR 52683, Dec. 21, 1990; Amdt. 174-74, 58 FR 51533, Oct. 1, 1993; 65 FR 58630, Sept. 29, 2000]

### Subpart G—Detailed Requirements for Class 3 (Flammable Liquid) Materials

#### § 174.300 Special handling requirements.

(a) Class 3 (flammable liquid) materials may not be loaded, transported, or stored in a rail car equipped with any type of lighted heater or open-flame device, or in a rail car equipped with any apparatus or mechanism utilizing an internal combustion engine in its operation.

(b) A truck body or trailer which is loaded with a Class 3 (flammable liquid) materials and equipped with a lighted heater or any automatic heating or refrigerating apparatus may not be loaded on a flatcar except as provided in paragraph (c) of this section.

(c) Heating or refrigeration apparatus on a motor vehicle loaded with Class 3 (flammable liquid) materials may be operated while the motor vehicle is loaded on a flatcar only if:

(1) The lading space is not equipped with any electrical apparatus that is not non-sparking or explosion-proof;

(2) There is no combustion apparatus in the lading space;

(3) There is no connection for the return of air from the lading space to any combustion apparatus; and

(4) The heating system conforms to § 393.77 of this title and does not heat any part of the lading over 54 °C (129 °F).

(d) Metal barrels or drums containing Class 3 (flammable liquid) materials may be transported in a steel gondola or flatcar or in a stock car. However, they may not be transported in a hopper bottom car.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-31, 43 FR 31143, July 20, 1978; Amdt. 174-68, 55 FR 52683, Dec. 21, 1990]



## **§ 174.304**

### **§ 174.304 Class 3 (flammable liquid) materials in tank cars.**

A tank car containing a Class 3 (flammable liquid) material, other than liquid road asphalt or tar, may not be transported by rail unless it is originally consigned or subsequently reconsigned to a party having a private track on which it is to be delivered and unloaded (see § 171.8 of this subchapter) or to a party using railroad siding facilities which are equipped for piping the liquid from the tank car to permanent storage tanks of sufficient capacity to receive the entire contents of the car.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-32, 43 FR 48644, Oct. 19, 1978; Amdt. 174-68, 55 FR 52683, Dec. 21, 1990]

## **Subparts H-I [Reserved]**

## **Subpart J—Detailed Requirements for Division 6.1 (Poisonous) Materials**

### **§ 174.600 Special handling requirements for materials extremely poisonous by inhalation.**

A tank car containing a material extremely poisonous by inhalation which is a Division 2.3 material in Hazard Zone A or a Division 6.1 material in Hazard Zone A, as defined in § 173.133(a)(2) of this subchapter, may not be transported by rail unless it is originally consigned or subsequently reconsigned to a party having a private track on which it is to be delivered and unloaded (see § 171.8 of this subchapter) or to a party using railroad siding facilities which are equipped for piping the liquid or gas from the tank car to permanent storage tanks or sufficient capacity to receive the entire contents of the car. See the requirements in § 174.290 for materials extremely poisonous by inhalation which are shipped by, for, or to the Department of Defense.

[Amdt. 174-68, 55 FR 52684, Dec. 21, 1990]

### **§ 174.615 Cleaning cars.**

(a) [Reserved]

(b) After Division 6.1 (poisonous) materials are unloaded from a rail car, that car must be thoroughly cleaned

## **49 CFR Ch. I (10-1-08 Edition)**

unless the car is used exclusively in the carriage of Division 6.1 (poisonous) materials.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-68, 55 FR 52684, Dec. 21, 1990; Amdt. 174-82, 61 FR 18933, Apr. 29, 1996]

### **§ 174.680 Division 6.1 (poisonous) materials with foodstuffs.**

(a) Except as provided in paragraph (b) of this section, a carrier may not transport any package bearing a POISON or POISON INHALATION HAZARD label in the same car with any material marked as, or known to be, a foodstuff, feed or any other edible material intended for consumption by humans or animals.

(b) A carrier must separate any package bearing a POISON label displaying the text “PG III,” or bearing a “PG III” mark adjacent to the POISON label, from materials marked as or known to be foodstuffs, feed or any other edible materials intended for consumption by humans or animals, as required in § 174.81(e)(3) for classes identified with the letter “O” in the Segregation Table for Hazardous Materials.

[64 FR 10781, Mar. 5, 1999]

## **Subpart K—Detailed Requirements for Class 7 (Radioactive) Materials**

### **§ 174.700 Special handling requirements for Class 7 (radioactive) materials.**

(a) Each rail shipment of low specific activity materials or surface contaminated objects as defined in § 173.403 of this subchapter must be loaded so as to avoid spillage and scattering of loose material. Loading restrictions are prescribed in § 173.427 of this subchapter.

(b) The number of packages of Class 7 (radioactive) materials that may be transported by rail car or stored at any single location is limited to a total transport index and a total criticality safety index (as defined in § 173.403 of this subchapter) of not more than 50 each. This provision does not apply to exclusive use shipments as described in §§ 173.403, 173.427, 173.441, and 173.457 of this subchapter.

(c) Each package of Class 7 (radioactive) material bearing RADIOACTIVE YELLOW-II or RADIOACTIVE YELLOW-III labels may not be placed closer than 0.9 m (3 feet) to an area (or dividing partition between areas) which may be continuously occupied by any passenger, rail employee, or shipment of one or more animals, nor closer than 4.5 m (15 feet) to any package containing undeveloped film (if so marked). If more than one package of Class 7 (radioactive) materials is present, the distance must be computed from the table below on the basis of the total transport index number (determined by adding together the transport index numbers on the labels of the individual packages) of packages in the rail car or storage area:

| Total transport index | Minimum separation distance to nearest undeveloped film |      | Minimum distance to area of persons or minimum distance from dividing partition of a combination car |      |
|-----------------------|---------------------------------------------------------|------|------------------------------------------------------------------------------------------------------|------|
|                       | Meters                                                  | Feet | Meters                                                                                               | Feet |
|                       |                                                         |      |                                                                                                      |      |
| None .....            | 0                                                       | 0    | 0                                                                                                    | 0    |
| 0.1 to 10.0 .....     | 4.5                                                     | 15   | 0.9                                                                                                  | 3    |
| 10.1 to 20.0 .....    | 6.7                                                     | 22   | 1.2                                                                                                  | 4    |
| 20.1 to 30.0 .....    | 7.7                                                     | 29   | 1.5                                                                                                  | 5    |
| 30.1 to 40.0 .....    | 10                                                      | 33   | 1.8                                                                                                  | 6    |
| 40.1 to 50.0 .....    | 10.9                                                    | 36   | 2.1                                                                                                  | 7    |

NOTE: The distance in this table must be measured from the nearest point on the nearest packages of Class 7 (radioactive) materials.

(d) Each shipment of fissile material packages must conform to requirements of §§ 173.457 and 173.459.

(e) Each fissile material, controlled shipment must be transported in accordance with one of the methods prescribed in § 173.457 of this subchapter. The transport controls must be adequate to assure that no fissile material, controlled shipment is transported in the same transport vehicle with any other fissile Class 7 (radioactive) material shipment. In loading and storage areas, each fissile material, controlled shipment must be segregated by a distance of at least 6 m (20 feet) from other packages required to bear one of the “radioactive” labels described in part 172 of this subchapter.

(f) A person shall not remain unnecessarily in, on or near a transport vehicle containing Class 7 (radioactive) materials.

(g) In the case of packages shipped under the exclusive use provisions of § 173.441(b) of this subchapter for packages with external radiation levels in excess of 2 mSv per hour (200 mrem per hour) at the package surface—

(1) The transport vehicle must meet the requirements for a closed transport vehicle (§ 173.403 of this subchapter);

(2) Each package must be secured so that its position within the transport vehicle remains fixed under conditions normally incident to transportation; and

(3) The radiation level may not exceed 0.02 mSv per hour (2 mrem per hour) in any normally occupied position in the transport vehicle or adjacent rail car.

[Amdt. 174-80, 60 FR 50331, Sept. 28, 1995, as amended by Amdt. 174-80, 61 FR 20753, May 8, 1996; 66 FR 45383, Aug. 28, 2001; 69 FR 3693, Jan. 26, 2004]

#### § 174.715 Cleanliness of transport vehicles after use.

(a) Each transport vehicle used for transporting Class 7 (radioactive) materials as exclusive use, as defined in § 173.403 of this subchapter, must be surveyed with appropriate radiation detection instruments after each use. A transport vehicle may not be returned to service until the radiation dose rate at any accessible surface is 0.005 mSv per hour (0.5 mrem per hour) or less, and there is no significant removable radioactive surface contamination, as defined in § 173.443 of this subchapter.

(b) This section does not apply to any transport vehicle used solely for transporting Class 7 (radioactive) materials if a survey of the interior surface shows that the radiation dose rate does not exceed 0.1 mSv per hour (10 mrem per hour) at the interior surface or 0.02 mSv per hour (2 mrem per hour) at 1 m (3.3 feet) from any interior surface. The transport vehicle must be stenciled with the words “FOR RADIOACTIVE MATERIALS USE ONLY” in lettering at least 7.6 cm (3 inches) high in a conspicuous place on both sides of the exterior of the transport vehicle, and it must be kept closed at all times other than during loading and unloading.

[Amdt. 174-80, 60 FR 50332, Sept. 28, 1995, as amended by 66 FR 45383, Aug. 28, 2001]

## § 174.750

### § 174.750 Incidents involving leakage.

(a) In addition to the incident reporting requirements of §§171.15 and 171.16 of this subchapter, the carrier shall also notify the offeror at the earliest practicable moment following any incident in which there has been breakage, spillage, or suspected radioactive contamination involving Class 7 (radioactive) materials shipments. Transport vehicles, buildings, areas, or equipment in which Class 7 (radioactive) materials have been spilled may not be again placed in service or routinely occupied until the radiation dose rate at every accessible surface is less than 0.005 mSv per hour (0.5 mrem per hour) and there is no significant removable radioactive surface contamination (see § 173.443 of this subchapter).

(b) The package or materials should be segregated as far as practicable from personnel contact. If radiological advice or assistance is needed, the U.S. Department of Energy (DOE) should also be notified. In case of obvious leakage, or if it appears likely that the inside container may have been damaged, care should be taken to avoid inhalation, ingestion, or contact with the Class 7 (radioactive) material. Any loose Class 7 (radioactive) materials should be left in a segregated area and held pending disposal instructions, from qualified persons.

[Amdt. 174-26, 41 FR 16092, Apr. 15, 1976, as amended by Amdt. 174-42, 48 FR 10245, Mar. 10, 1983; Amdt. 174-61, 51 FR 34987, Oct. 1, 1986; Amdt. 174-65, 53 FR 38274, Sept. 29, 1988; Amdt. 174-68, 55 FR 52684, Dec. 21, 1990; Amdt. 174-80, 60 FR 50332, Sept. 28, 1995]

## PART 175—CARRIAGE BY AIRCRAFT

### Subpart A—General Information and Regulations

Sec.

175.1 Purpose, scope and applicability.

175.3 Unacceptable hazardous materials shipments.

175.8 Exceptions for operator equipment and items of replacement.

175.9 Exceptions for special aircraft operations.

175.10 Exceptions for passengers, crewmembers, and air operators.

175.20 Compliance and training.

## 49 CFR Ch. I (10-1-08 Edition)

175.25 Notification at air passenger facilities of hazardous materials restrictions.

175.26 Notification at cargo facilities of hazardous materials requirements.

175.30 Inspecting shipments.

175.31 Reports of discrepancies.

175.33 Shipping paper and notification of pilot-in-command.

### Subpart B—Loading, Unloading and Handling

175.75 Quantity limitations and cargo location.

175.78 Stowage compatibility of cargo.

175.88 Inspection, orientation and securing of packages of hazardous materials.

175.90 Damaged shipments.

### Subpart C—Specific Regulations Applicable According to Classification of Material

175.310 Transportation of flammable liquid fuel; aircraft only means of transportation

175.501 Special requirements for oxidizers and compressed oxygen.

175.630 Special requirements for Division 6.1 (poisonous) material and Division 6.2 (infectious substances) materials.

175.700 Special limitations and requirements for Class 7 materials.

175.701 Separation distance requirements for packages containing Class 7 (radioactive) materials in passenger-carrying aircraft.

175.702 Separation distance requirements for packages containing Class 7 (radioactive) materials in cargo aircraft.

175.703 Other special requirements for the acceptance and carriage of packages containing Class 7 materials.

175.704 Plutonium shipments.

175.705 Radioactive contamination.

175.706 Separation distances for undeveloped film from packages containing Class 7 (radioactive) materials.

175.900 Handling requirements for carbon dioxide, solid (dry ice).

AUTHORITY: 49 U.S.C. 5101-5128, 44701; 49 CFR 1.45 and 1.53.

SOURCE: 71 FR 14604, Mar. 22, 2006, unless otherwise noted.

### Subpart A—General Information and Regulations

#### § 175.1 Purpose, scope and applicability.

(a) This part prescribes requirements that apply to the transportation of hazardous materials in commerce

aboard (including attached to or suspended from) aircraft. The requirements in this part are in addition to other requirements contained in parts 171, 172, 173, 178, and 180 of this subchapter.

(b) This part applies to the offering, acceptance, and transportation of hazardous materials in commerce by aircraft to, from, or within the United States, and to any aircraft of United States registry anywhere in air commerce. This subchapter applies to any person who performs, attempts to perform, or is required to perform any function subject to this subchapter, including—(1) Air carriers, indirect air carriers, and freight forwarders and their flight and non-flight employees, agents, subsidiary and contract personnel (including cargo, passenger and baggage acceptance, handling, loading and unloading personnel); and

(2) Air passengers that carry any hazardous material on their person or in their carry-on or checked baggage.

(c) This part does not apply to aircraft of United States registry under lease to and operated by foreign nationals outside the United States if:

(1) Hazardous materials forbidden aboard aircraft by §172.101 of this subchapter are not carried on the aircraft; and

(2) Other hazardous materials are carried in accordance with the regulations of the State (nation) of the aircraft operator.

### **§175.3 Unacceptable hazardous materials shipments.**

A hazardous material that is not prepared for shipment in accordance with this subchapter may not be offered or accepted for transportation or transported aboard an aircraft.

### **§175.8 Exceptions for operator equipment and items of replacement.**

(a) *Operator equipment.* This subchapter does not apply to—

(1) Aviation fuel and oil in tanks that are in compliance with the installation provisions of 14 CFR, chapter 1.

(2) Hazardous materials required aboard an aircraft in accordance with the applicable airworthiness requirements and operating regulations. Items of replacement for such materials must

be transported in accordance with paragraph (a)(3) of this section.

(3) Items of replacement (company material (COMAT)) for hazardous materials described in paragraph (a)(2) of this section must be transported in accordance with this subchapter. When an operator transports its own replacement items described in paragraph (a)(2), the following exceptions apply:

(i) In place of required packagings, packagings specifically designed for the items of replacement may be used, provided such packagings provide at least an equivalent level of protection to those that would be required by this subchapter.

(ii) Aircraft batteries are not subject to quantity limitations such as those provided in §172.101 or §175.75(c) of this subchapter.

(b) *Other operator exceptions.* This subchapter does not apply to—

(1) Oxygen, or any hazardous material used for the generation of oxygen, for medical use by a passenger, which is furnished by the aircraft operator in accordance with 14 CFR 121.574 or 135.91. For the purposes of this paragraph, an aircraft operator that does not hold a certificate under 14 CFR parts 121 or 135 may apply this exception in conformance with 14 CFR 121.574 or 135.91 in the same manner as required for a certificate holder. See §175.501 for additional requirements applicable to the stowage of oxygen.

(2) Dry ice (carbon dioxide, solid) intended for use by the operator in food and beverage service aboard the aircraft.

(3) Alcoholic beverages, perfumes, colognes, and liquefied gas lighters carried aboard a passenger-carrying aircraft by the operator for use or sale on the aircraft. Liquefied gas lighters must be examined by the Bureau of Explosives and approved by the Associate Administrator.

(4) A tire assembly with a serviceable tire, provided the tire is not inflated to a gauge pressure exceeding the maximum rated pressure for that tire, and the tire (including valve assemblies) is protected from damage during transport. A tire or tire assembly which is unserviceable or damaged is forbidden from air transport; however, a damaged tire is not subject to the requirements

## § 175.9

## 49 CFR Ch. I (10–1–08 Edition)

of this subchapter if it contains no material meeting the definition of a hazardous material (e.g., Division 2.2).

[71 FR 14604, Mar. 22, 2006, as amended at 72 FR 55693, Oct. 1, 2007]

### § 175.9 Exceptions for special aircraft operations.

This subchapter does not apply to the following materials used for special aircraft operations when applicable FAA operator requirements have been met, including training operator personnel on the proper handling and stowage of the hazardous materials carried:

(a) Hazardous materials loaded and carried in hoppers or tanks of aircraft certificated for use in aerial seeding, dusting spraying, fertilizing, crop improvement, or pest control, to be dispensed during such an operation.

(b) Parachute activation devices, lighting equipment, oxygen cylinders, flotation devices, smoke grenades, flares, or similar devices carried during a parachute operation.

(c) Smoke grenades, flares, and pyrotechnic devices affixed to aircraft during any flight conducted as part of a scheduled air show or exhibition of aeronautical skill. The aircraft may not carry any persons other than required flight crewmembers. The affixed installation accommodating the smoke grenades, flares, or pyrotechnic devices on the aircraft must be approved for its intended use by the FAA Flight Standards District Office having responsibility for that aircraft.

(d) Hazardous materials are carried and used during dedicated air ambulance, fire fighting, or search and rescue operations.

(e) A transport incubator unit necessary to protect life or an organ preservation unit necessary to protect human organs, carried in the aircraft cabin, provided:

(1) The compressed gas used to operate the unit is in an authorized DOT specification cylinder and is marked, labeled, filled, and maintained as prescribed by this subchapter;

(2) Each battery used is of the non-spillable type;

(3) The unit is constructed so valves, fittings, and gauges are protected from damage;

(4) The pilot-in-command is advised when the unit is on board, and when it is intended for use;

(5) The unit is accompanied by a person qualified to operate it;

(6) The unit is secured in the aircraft in a manner that does not restrict access to or use of any required emergency or regular exit or of the aisle in the passenger compartment; and,

(7) Smoking within 3 m (10 feet) of the unit is prohibited.

(f) Hazardous materials which are loaded and carried on or in cargo only aircraft, and which are to be dispensed or expended during flight for weather control, environmental restoration or protection, forest preservation and protection, fire fighting and prevention, flood control, or avalanche control purposes, when the following requirements are met:

(1) Operations may not be conducted over densely populated areas, in a congested airway, or near any airport where carrier passenger operations are conducted.

(2) Each operator shall prepare and keep current a manual containing operational guidelines and handling procedures, for the use and guidance of flight, maintenance, and ground personnel concerned in the dispensing or expending of hazardous materials. The manual must be approved by the FAA Principal Operations Inspector assigned to the operator.

(3) No person other than a required flight crewmember, FAA inspector, or person necessary for handling or dispensing the hazardous material may be carried on the aircraft.

(4) The operator of the aircraft must have advance permission from the owner of any airport to be used for the dispensing or expending operation.

(5) When dynamite and blasting caps are carried for avalanche control flights, the explosives must be handled by, and at all times be under the control of, a qualified blaster. When required by a State or local authority, the blaster must be licensed and the State or local authority must be identified in writing to the FAA Principal Operations Inspector assigned to the operator.

**§ 175.10 Exceptions for passengers, crewmembers, and air operators.**

(a) This subchapter does not apply to the following hazardous materials when carried by aircraft passengers or crewmembers provided the requirements of this section are met:

(1) (i) Non-radioactive medicinal and toilet articles for personal use (including aerosols) carried in carry-on and checked baggage. Release devices on aerosols must be protected by a cap or other suitable means to prevent inadvertent release;

(ii) Other aerosols in Div. 2.2 (non-flammable gas) with no subsidiary risk carried in checked baggage only. Release devices on aerosols must be protected by a cap or other suitable means to prevent inadvertent release; and

(iii) The aggregate quantity of these hazardous materials carried by each person may not exceed 2 kg (70 ounces) by mass or 2 L (68 fluid ounces) by volume and the capacity of each container may not exceed 0.5 kg (18 ounces) by mass or 500 ml (17 fluid ounces) by volume.

(2) One packet of safety matches or a lighter intended for use by an individual when carried on one's person or in carry-on baggage only. Lighter fuel, lighter refills, and lighters containing unabsorbed liquid fuel (other than liquefied gas) are not permitted on one's person or in carry-on or checked baggage.

(3) Implanted medical devices in humans or animals that contain hazardous materials, such as a heart pacemaker containing Class 7 (radioactive) material or lithium batteries; and radiopharmaceuticals that have been injected or ingested.

(4) Alcoholic beverages containing:

(i) Not more than 24% alcohol by volume; or

(ii) More than 24% and not more than 70% alcohol by volume when in unopened retail packagings not exceeding 5 liters (1.3 gallons) carried in carry-on or checked baggage, with a total net quantity per person of 5 liters (1.3 gallons) for such beverages.

(5) Perfumes and colognes purchased through duty-free sales and carried on one's person or in carry-on baggage.

(6) Hair curlers (curling irons) containing a hydrocarbon gas such as butane, no more than one per person, in carry-on or checked baggage. The safety cover must be securely fitted over the heating element. Gas refills for such curlers are not permitted in carry-on or checked baggage.

(7) A small medical or clinical mercury thermometer for personal use, when carried in a protective case in carry-on or checked baggage.

(8) Small arms ammunition for personal use carried by a crewmember or passenger in checked baggage only, if securely packed in boxes or other packagings specifically designed to carry small amounts of ammunition. Ammunition clips and magazines must also be securely boxed. This paragraph does not apply to persons traveling under the provisions of 49 CFR 1544.219.

(9) One self-defense spray (see § 171.8 of this subchapter), not exceeding 118 mL (4 fluid ounces) by volume, that incorporates a positive means to prevent accidental discharge may be carried in checked baggage only.

(10) Dry ice (carbon dioxide, solid):

(i) in quantities not exceeding 2.5 kg (5.5 pounds) per person in carry-on baggage, when used to pack perishables not subject to the HMR. The package must permit the release of carbon dioxide gas; and/or

(ii) in checked baggage, with the approval of the operator(s), when each package is marked "DRY ICE" or "CARBON DIOXIDE, SOLID", and marked with the net mass of dry ice or an indication the net weight is 2.5 kg (5.5 pounds) or less.

(11) A self-inflating life jacket fitted with no more than two small gas cartridges (containing no hazardous material other than a Div. 2.2 gas) for inflation purposes plus no more than two spare cartridges. The lifejacket and spare cartridges may be carried in carry-on or checked baggage, with the approval of the aircraft operator.

(12) Small compressed gas cylinders of Division 2.2 (containing no hazardous material other than a Division 2.2 gas) worn by the passenger for the operation of mechanical limbs and, in carry-on and checked baggage, spare cylinders of a similar size for the same purpose in sufficient quantities to ensure an adequate supply for the duration of the journey.

(13) A mercury barometer or thermometer carried as carry-on baggage, by a representative of a government weather bureau or similar official agency, provided that individual advises the operator of the presence of the barometer or thermometer in his baggage. The barometer or thermometer must be packaged in a strong packaging having a sealed inner liner or bag of strong, leak proof and puncture-resistant material impervious to mercury, which will prevent the escape of mercury from the package in any position.

(14) Electrically powered heat-producing articles (e.g., battery-operated equipment such as diving lamps and soldering equipment) as carry-on baggage only and with the approval of the operator of the aircraft. The heat-producing component, or the energy source, must be removed to prevent unintentional functioning during transport.

(15) A wheelchair or other battery-powered mobility aid equipped with a nonspillable battery, when carried as checked baggage, provided—

(i) The battery meets the provisions of §173.159(d) of this subchapter for nonspillable batteries;

(ii) Visual inspection including removal of the battery, where necessary, reveals no obvious defects (removal of the battery from the housing should be performed by qualified airline personnel only);

(iii) The battery is disconnected and terminals are insulated to prevent short circuits; and

(iv) The battery is—

(A) Securely attached to the wheelchair or mobility aid,

(B) Is removed and placed in a strong, rigid packaging marked “NONSPILLABLE BATTERY” (unless fully enclosed in a rigid housing that is properly marked), or

(C) Is handled in accordance with paragraph (a)(16)(iv) of this section.

(16) A wheelchair or other battery-powered mobility aid equipped with a spillable battery, when carried as checked baggage, provided—

(i) Visual inspection including removal of the battery, where necessary, reveals no obvious defects (however, removal of the battery from the housing

should be performed by qualified airline personnel only);

(ii) The battery is disconnected and terminals are insulated to prevent short circuits;

(iii) The pilot-in-command is advised, either orally or in writing, prior to departure, as to the location of the battery aboard the aircraft; and

(iv) The wheelchair or mobility aid is loaded, stowed, secured and unloaded in an upright position, or the battery is removed, and carried in a strong, rigid packaging under the following conditions:

(A) The packaging must be leak-tight and impervious to battery fluid. An inner liner may be used to satisfy this requirement if there is absorbent material placed inside of the liner and the liner has a leakproof closure;

(B) The battery must be protected against short circuits, secured upright in the packaging, and be packaged with enough compatible absorbent material to completely absorb liquid contents in the event of rupture of the battery; and

(C) The packaging must be labeled with a CORROSIVE label, marked to indicate proper orientation, and marked with the words “Battery, wet, with wheelchair.”

(17) Except as provided in §173.21 of this subchapter, consumer electronic and medical devices (watches, calculating machines, cameras, cellular phones, lap-top and notebook computers, camcorders, etc.) containing lithium cells or batteries and spare lithium batteries and cells for these devices, when carried by passengers or crew members for personal use. Each spare battery must be individually protected so as to prevent short circuits (by placement in original retail packaging or by otherwise insulating terminals, e.g., by taping over exposed terminals or placing each battery in a separate plastic bag or protective pouch) and carried in carry-on baggage only. In addition, each installed or spare battery must not exceed the following:

(i) For a lithium metal battery, a lithium content of not more than 2 grams per battery; or

(ii) For a lithium-ion battery, an aggregate equivalent lithium content of not more than 8 grams per battery, except that up to two batteries with an

aggregate equivalent lithium content of more than 8 grams but not more than 25 grams may be carried.

(18) Portable electronic devices (for example, cameras, cellular phones, laptop computers, and camcorders) powered by fuel cell systems, and not more than two spare fuel cell cartridges per passenger or crew member, when transported in carry-on baggage by aircraft under the following conditions:

(i) Fuel cell cartridges may contain only Class 3 flammable liquids (including methanol), Class 8 formic acid, Class 8 borohydride materials, or Division 2.1 butane;

(ii) The maximum quantity of fuel in any fuel cell cartridge may not exceed:

(A) 200 mL (6.76 ounces) for liquids,

(B) 120 mL (4 fluid ounces) for liquefied gases in non-metallic fuel cell cartridges, or 200 mL for liquefied gases in metal fuel cell cartridges;

(C) 200 g (7 ounces) for solids;

(iii) No more than two spare fuel cell cartridges may be carried by a passenger;

(iv) Fuel cell systems containing fuel and fuel cell cartridges including spare cartridges are permitted in carry-on baggage only;

(v) Fuel cell cartridges may not be refillable by the user. Refueling of fuel cell systems is not permitted except that the installation of a spare cartridge is allowed. Fuel cell cartridges that are used to refill fuel cell systems but that are not designed or intended to remain installed (fuel cell refills) in a portable electronic device are not permitted;

(vi) Fuel cell systems and fuel cell cartridges must conform to IEC/PAS 62282-6-1 (IBR; see § 171.7 of this subchapter);

(vii) Interaction between fuel cells and integrated batteries in a device must conform to IEC/PAS 62282-6-1. Fuel cell systems for which the sole function is to charge a battery in the device are not permitted;

(viii) Fuel cell systems must be of a type that will not charge batteries when the portable electronic device is not in use; and

(ix) Each fuel cell cartridge and system that conforms to the requirements in this paragraph (a)(18) must be durably

marked by the manufacturer with the wording: "APPROVED FOR CARRIAGE IN AIRCRAFT CABIN ONLY" to certify that the fuel cell cartridge or system meets the specifications in IEC/PAS 62282-6-1 and all other applicable requirements of this subchapter.

(b) The exceptions provided in paragraph (a) of this section also apply to aircraft operators when transporting passenger or crewmember baggage that has been separated from the passenger or crewmember, including transfer to another carrier for transport to its final destination.

[71 FR 14604, Mar. 22, 2006, as amended at 71 FR 78634, Dec. 29, 2006; 72 FR 44950, Aug. 9, 2007; 73 FR 4719, Jan. 28, 2008; 73 FR 23367, Apr. 30, 2008]

#### **§ 175.20 Compliance and training.**

An air carrier may not transport a hazardous material by aircraft unless each of its hazmat employees involved in that transportation is trained as required by subpart H of part 172 of this subchapter. In addition, air carriers must comply with all applicable hazardous materials training requirements in 14 CFR Part 121 and 135.

#### **§ 175.25 Notification at air passenger facilities of hazardous materials restrictions.**

Each person who engages in for-hire air transportation of passengers shall display notices of the requirements applicable to the carriage of hazardous materials aboard aircraft, and the penalties for failure to comply with those requirements. Each notice must be legible, and be prominently displayed so it can be seen by passengers in locations where the aircraft operator issues tickets, checks baggage, and maintains aircraft boarding areas.

(a) At a minimum, each notice must communicate the following information:

(1) Federal law forbids the carriage of hazardous materials aboard aircraft in your luggage or on your person. A violation can result in five years' imprisonment and penalties of \$250,000 or more (49 U.S.C. 5124). Hazardous materials include explosives, compressed gases, flammable liquids and solids, oxidizers, poisons, corrosives and radioactive materials. Examples: Paints,



## § 175.26

## 49 CFR Ch. I (10–1–08 Edition)

lighter fluid, fireworks, tear gases, oxygen bottles, and radio-pharmaceuticals.

(2) There are special exceptions for small quantities (up to 70 ounces total) of medicinal and toilet articles carried in your luggage and certain smoking materials carried on your person. For further information contact your airline representative.

(b) The information contained in paragraph (a) of this section must be printed:

(1) In legible English and may, in addition to English, be displayed in other languages;

(2) In lettering of at least 1 cm (0.4 inch) in height for the first sentence and 4.0 mm (0.16 inch) in height for the other sentences; and

(3) On a background of contrasting color.

(c) Size and color of the notice is optional. Additional information, examples, or illustrations, if not inconsistent with the required information, may be included.

### § 175.26 Notification at cargo facilities of hazardous materials requirements.

(a) Each person who engages in the acceptance or transport of cargo for transportation by aircraft shall display notices to persons offering such cargo of the requirements applicable to the carriage of hazardous materials aboard aircraft, and the penalties for failure to comply with those requirements, at each facility where cargo is accepted. Each notice must be legible, and be prominently displayed so it can be seen. At a minimum, each notice must communicate the following information:

(1) Cargo containing hazardous materials (dangerous goods) for transportation by aircraft must be offered in accordance with the Federal Hazardous Materials Regulations (49 CFR parts 171 through 180).

(2) A violation can result in five years' imprisonment and penalties of \$250,000 or more (49 U.S.C. 5124).

(3) Hazardous materials (dangerous goods) include explosives, compressed gases, flammable liquids and solids, oxidizers, poisons, corrosives and radioactive materials.

(b) The information contained in paragraph (a) of this section must be printed:

(1) Legibly in English, and, where cargo is accepted outside of the United States, in the language of the host country; and

(2) On a background of contrasting color.

(c) Size and color of the notice are optional. Additional information, examples, or illustrations, if not inconsistent with required information, may be included.

(d) *Exceptions.* Display of a notice required by paragraph (a) of this section is not required at:

(1) An unattended location (e.g., a drop box) provided a general notice advising customers of a prohibition on shipments of hazardous materials through that location is prominently displayed; or

(2) A customer's facility where hazardous materials packages are accepted by a carrier.

### § 175.30 Inspecting shipments.

(a) No person may accept a hazardous material for transportation aboard an aircraft unless the aircraft operator ensures the hazardous material is:

(1) Authorized, and is within the quantity limitations specified for carriage aboard aircraft according to § 172.101 of this subchapter or as otherwise specifically provided by this subchapter.

(2) Described and certified on a shipping paper prepared in duplicate in accordance with part 172 of this subchapter or as authorized by subpart C of part 171 of this subchapter. See § 175.33 for shipping paper retention requirements;

(3) Marked and labeled in accordance with subparts D and E of part 172 or as authorized by subpart C of part 171 of this subchapter, and placarded (when required) in accordance with subpart F of part 172 of this subchapter; and

(4) Labeled with a "CARGO AIRCRAFT ONLY" label (see § 172.448 of this subchapter) if the material as presented is not permitted aboard passenger-carrying aircraft.

(b) Except as provided in paragraph (d) of this section, no person may carry

a hazardous material in a package, outside container, or overpack aboard an aircraft unless the package, outside container, or overpack is inspected by the operator of the aircraft immediately before placing it:

- (1) Aboard the aircraft; or
- (2) In a unit load device or on a pallet prior to loading aboard the aircraft.

(c) A hazardous material may be carried aboard an aircraft only if, based on the inspection by the operator, the package, outside container, or overpack containing the hazardous material:

- (1) Has no holes, leakage or other indication that its integrity has been compromised; and

(2) For Class 7 (radioactive) materials, does not have a broken seal, except packages contained in overpacks need not be inspected for seal integrity.

(d) The requirements of paragraphs (b) and (c) of this section do not apply to Dry ice (carbon dioxide, solid).

(e) An overpack containing packages of hazardous materials may be accepted only if the operator has taken all reasonable steps to establish that:

(1) The overpack does not contain a package bearing the "CARGO AIRCRAFT ONLY" label unless—

(i) The overpack affords clear visibility of and easy access to the package;

(ii) The package contains a material which may be carried inaccessibly under the provisions of §175.75(e); or

(iii) Not more than one package is overpacked.

(2) The proper shipping names, identification numbers, labels and special handling instructions appearing on the inside packages are clearly visible or reproduced on the outside of the overpack, and

(3) Has determined that word "OVERPACK", or until October 1, 2007 a statement to the effect that the inside packages comply with the prescribed specifications, appears on the outside of the overpack, when specification packagings are prescribed.

[71 FR 14604, Mar. 22, 2006, as amended at 72 FR 25177, May 3, 2007; 73 FR 57006, Oct. 1, 2008]

#### § 175.31 Reports of discrepancies.

(a) Each person who discovers a discrepancy, as defined in paragraph (b) of this section, relative to the shipment of a hazardous material following its acceptance for transportation aboard an aircraft shall, as soon as practicable, notify the nearest FAA Regional or Field Security Office by telephone or electronically, and shall provide the following information:

(1) Name and telephone number of the person reporting the discrepancy.

(2) Name of the aircraft operator.

(3) Specific location of the shipment concerned.

(4) Name of the shipper.

(5) Nature of discrepancy.

(6) Address of the shipper or person responsible for the discrepancy, if known, by the air carrier.

(b) Discrepancies which must be reported under paragraph (a) of this section are those involving hazardous materials which are improperly described, certified, labeled, marked, or packaged, in a manner not ascertainable when accepted under the provisions of §175.30(a) of this subchapter including packages or baggage which are found to contain hazardous materials subsequent to their being offered and accepted as other than hazardous materials.

#### § 175.33 Shipping paper and notification of pilot-in-command.

(a) When a hazardous material subject to the provisions of this subchapter is carried in an aircraft, a copy of the shipping paper required by §175.30(a)(2) must accompany the shipment it covers during transportation aboard the aircraft, and the operator of the aircraft must provide the pilot-in-command with accurate and legible written information as early as practicable before departure of the aircraft, which specifies at least the following:

(1) The proper shipping name, hazard class and identification number of the material, including any remaining aboard from prior stops, as specified in §172.101 of this subchapter or the ICAO Technical Instructions. In the case of Class 1 materials, the compatibility group letter also must be shown. If a hazardous material is described by the proper shipping name, hazard class,

### § 175.33

### 49 CFR Ch. I (10–1–08 Edition)

and identification number appearing in:

(i) Section 172.101 of this subchapter, any additional description requirements provided in §§ 172.202 and 172.203 of this subchapter must also be shown in the notification.

(ii) The ICAO Technical Instructions (IBR, see § 171.7 of this subchapter), any additional information required to be shown on shipping papers by subpart C of part 171 of this subchapter must also be shown in the notification.

(2) The total number of packages;

(3) The net quantity or gross weight, as applicable, for each package except those containing Class 7 (radioactive) materials. For a shipment consisting of multiple packages containing hazardous materials bearing the same proper shipping name and identification number, only the total quantity and an indication of the quantity of the largest and smallest package at each loading location need to be provided;

(4) The location of the packages aboard the aircraft;

(5) Confirmation that no damaged or leaking packages have been loaded on the aircraft;

(6) For Class 7 (radioactive) materials, the number of packages, overpacks or freight containers, their category, transport index (if applicable), and their location aboard the aircraft;

(7) The date of the flight;

(8) The telephone number of a person not aboard the aircraft from whom the information contained in the notification of pilot-in-command can be obtained. The aircraft operator must ensure the telephone number is monitored at all times the aircraft is in flight. The telephone number is not required to be placed on the notification of pilot-in-command if the phone number is in a location in the cockpit available and known to the flight crew.

(9) Confirmation that the package must be carried only on cargo aircraft if its transportation aboard passenger-carrying aircraft is forbidden; and

(10) An indication, when applicable, that a hazardous material is being carried under terms of a special permit.

(b) A copy of the written notification to pilot-in-command shall be readily available to the pilot-in-command dur-

ing flight. Emergency response information required by subpart G of part 172 of this subchapter must be maintained in the same manner as the written notification to pilot-in-command during transport of the hazardous material aboard the aircraft.

(c) The aircraft operator must—

(1) Retain a copy of the shipping paper required by § 175.30(a)(2) or an electronic image thereof, that is accessible at or through its principal place of business and must make the shipping paper available, upon request, to an authorized official of a federal, state, or local government agency at reasonable times and locations. For a hazardous waste, each shipping paper copy must be retained for three years after the material is accepted by the initial carrier. For all other hazardous materials, each shipping paper copy must be retained by the operator for one year after the material is accepted by the initial carrier. Each shipping paper copy must include the date of acceptance by the carrier. The date on the shipping paper may be the date a shipper notifies the air carrier that a shipment is ready for transportation, as indicated on the air bill or bill of lading, as an alternative to the date the shipment is picked up or accepted by the carrier. Only an initial carrier must receive and retain a copy of the shipper's certification, as required by § 172.204 of this subchapter.

(2) Retain a copy of each notification of pilot-in-command, an electronic image thereof, or the information contained therein for 90 days at the airport of departure or the operator's principal place of business.

(3) Have the information required to be retained under this paragraph readily accessible at the airport of departure and the intended airport of arrival for the duration of the flight leg.

(4) Make available, upon request, to an authorized official of a Federal, State, or local government agency (including an emergency responders) at reasonable times and locations, the documents or information required to be retained by this paragraph.

(d) The documents required by paragraphs (a) and (b) this section may be combined into one document if it is

given to the pilot-in-command before departure of the aircraft.

[71 FR 14604, Mar. 22, 2006, as amended at 72 FR 25177, May 3, 2007; 73 FR 57006, Oct. 1, 2008]

### Subpart B—Loading, Unloading and Handling

#### § 175.75 Quantity limitations and cargo location.

(a) No person may carry on an aircraft a hazardous material except as permitted by this subchapter.

(b) Except as otherwise provided in this subchapter, no person may carry a hazardous material in the cabin of a passenger-carrying aircraft or on the flight deck of any aircraft, and the hazardous material must be located in a place that is inaccessible to persons other than crew-members. Hazardous materials may be carried in a main deck cargo compartment of a passenger aircraft provided that the compartment is inaccessible to passengers and that it meets all certification requirements for a Class B aircraft cargo compartment in 14 CFR 25.857(b) or for a Class C aircraft cargo compartment in 14 CFR 25.857(c). A package bearing a KEEP AWAY FROM HEAT handling marking must be protected from direct sunshine and stored in a cool and ventilated place, away from sources of heat.

(c) For each package containing a hazardous material acceptable for carriage aboard passenger-carrying aircraft, no more than 25 kg (55 pounds) net weight of hazardous material may be loaded in an inaccessible manner. Loaded in an inaccessible manner means cargo that is loaded in such a manner that a crew member or other authorized person cannot handle, and when size and weight permit, separate such packages from other cargo during flight. This includes materials loaded in a freight container in an accessible cargo compartment. In addition to the 25 kg limitation above, an additional 75 kg (165 pounds) net weight of Division 2.2 (non-flammable compressed gas) may be loaded in an inaccessible manner. These requirements do not apply to Class 9 and ORM-D materials.

(d) Each package containing a hazardous material acceptable only for cargo aircraft must be loaded in such a manner that a crew member or other authorized person can access, handle and when size and weight permit, separate such packages from other cargo during flight.

(e) For cargo aircraft only, the requirements of paragraph (c) and (d) do not apply to the following hazardous materials:

(1) Class 3—Packing Group III (that do not meet the definition of another hazard class), Division 6.1 (except those also labeled FLAMMABLE), Division 6.2, Class 7, Class 9 or ORM-D;

(2) Division 2.2 in that an additional 75 kg (165 pounds) net weight of Division 2.2 material is authorized in inaccessible locations.

(3) Packages of hazardous materials transported aboard a cargo aircraft, when other means of transportation are impracticable or not available, in accordance with procedures approved in writing by the FAA Regional or Field Security Office in the region where the operator is located.

(4) Packages of hazardous materials carried on small, single pilot, cargo aircraft if:

(i) No person is carried on the aircraft other than the pilot, an FAA inspector, the shipper or consignee of the material, a representative of the shipper or consignee so designated in writing, or a person necessary for handling the material;

(ii) The pilot is provided with written instructions on the characteristics and proper handling of the materials; and

(iii) Whenever a change of pilots occurs while the material is on board, the new pilot is briefed under a hand-to-hand signature service provided by the operator of the aircraft.

(5) At a minimum, quantity limits and loading instructions in the following Quantity and Loading Tables must be followed to maintain acceptable quantity and loading between packages containing hazardous materials. The Quantity and Loading Tables are as follows:

Section 175.75 Quantity and Loading Tables

PASSENGER AIRCRAFT

Packages Authorized for Transport Onboard a Passenger Aircraft

| In an accessible cargo compartment                                                     |                                                                                        |                                                                                      |
|----------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| If packages are accessible                                                             | If packages are inaccessible                                                           | If packages are in a freight container                                               |
| No limit .....                                                                         | 25 kg per compartment plus an additional 75 kg of Division 2.2 material. (see Note 1). | 25 kg per container plus an additional 75 kg of Division 2.2 material. (see Note 1). |
| In an inaccessible cargo compartment                                                   |                                                                                        |                                                                                      |
| If packages are not in a freight container                                             | If packages are in a freight container                                                 |                                                                                      |
| 25 kg per compartment plus an additional 75 kg of Division 2.2 material. (see Note 1). | 25 kg per compartment plus an additional 75 kg of Division 2.2 material. (see Note 1). |                                                                                      |

CARGO ONLY AIRCRAFT

Packages Authorized for Transport Onboard a Passenger Aircraft

| In an accessible cargo compartment                                                     |                                                                                        |                                                                                      |
|----------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|
| If packages are accessible                                                             | If packages are inaccessible                                                           | If packages are in a freight container                                               |
| No limit .....                                                                         | 25 kg per compartment plus an additional 75 kg of Division 2.2 material. (see Note 1). | 25 kg per container plus an additional 75 kg of Division 2.2 material. (see Note 1). |
| In an inaccessible cargo compartment                                                   |                                                                                        |                                                                                      |
| If packages are not in a freight container                                             | If packages are in a freight container                                                 |                                                                                      |
| 25 kg per compartment plus an additional 75 kg of Division 2.2 material. (see Note 1). | 25 kg per compartment plus an additional 75 kg of Division 2.2 material. (see Note 1). |                                                                                      |

Packages Only Authorized for Transport Aboard a Cargo Aircraft

| In an accessible cargo compartment         |                                        |                                                           |                                                             |
|--------------------------------------------|----------------------------------------|-----------------------------------------------------------|-------------------------------------------------------------|
| If packages are accessible                 | If packages are inaccessible           | If packages are in a freight container and are accessible | If packages are in a freight container and are inaccessible |
| No limit .....                             | Forbidden. (see Note 1) .....          | No Limit .....                                            | Forbidden. (see Note 1).                                    |
| In an inaccessible cargo compartment       |                                        |                                                           |                                                             |
| If packages are not in a freight container | If packages are in a freight container |                                                           |                                                             |
| Forbidden. (see Note 1) .....              | Forbidden. (see Note 1).               |                                                           |                                                             |

**Note 1:** The following materials are not subject to this restriction:

- Class 3, PG III (unless the hazardous material meets the definition of another hazard class).
- Class 6 (unless also labeled as a flammable liquid).
- Class 7 (unless the hazardous material meets the definition of another hazard class).

[71 FR 14604, Mar. 22, 2006, as amended at 72 FR 55693, Oct. 1, 2007]

EDITORIAL NOTE: The following amendment could not be incorporated into §175.75 because of the inaccurate amendatory instruction. For the convenience of the user the amendatory instruction and text is set forth as follows:

At 71 FR 54395, Sept. 14, 2006, §175.75 was amended in part by revising paragraph (e)(5).

**§ 175.75 Quantity limitations and cargo location.**

\* \* \* \* \*

(e) \* \* \*

(5) At a minimum, quantity limits and loading instructions in the following quantity and loading tables must be followed to maintain acceptable quantity and loading distances between packages containing hazardous materials. These requirements do not apply to Class 9 or ORM-D materials. The quantity and loading tables are as follows:

## Section 175.75 Quantity and Loading Tables

## CARGO ONLY AIRCRAFT

[Packages authorized for transport onboard a passenger aircraft]

|                                                |  |  |  |  |                                                                                       |                                                                                       |                                                                                     |
|------------------------------------------------|--|--|--|--|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| * * * * *                                      |  |  |  |  | In an accessible cargo compartment                                                    |                                                                                       |                                                                                     |
|                                                |  |  |  |  | If packages are accessible                                                            | If packages are inaccessible                                                          | If packages are in a Freight Container                                              |
|                                                |  |  |  |  | No limit .....                                                                        | 25 kg per compartment plus an additional 75 kg of Division 2.2 material (see Note 1). | 25 kg per container plus an additional 75 kg of Division 2.2 material (see Note 1). |
| In an inaccessible cargo compartment           |  |  |  |  |                                                                                       |                                                                                       |                                                                                     |
| If packages are not in a freight container     |  |  |  |  | If packages are in a freight container                                                |                                                                                       |                                                                                     |
| 25 kg per compartment plus an additional ..... |  |  |  |  | 25 kg per compartment plus an additional 75 kg of Division 2.2 material (see Note 1). |                                                                                       |                                                                                     |
| 75 kg of Division 2.2 material .....           |  |  |  |  | 25 kg per compartment plus an additional 75 kg of Division 2.2 material (see Note 1). |                                                                                       |                                                                                     |

## PACKAGES ONLY AUTHORIZED FOR TRANSPORT ABOARD A CARGO AIRCRAFT

|                                            |                              |                                                           |                                                             |
|--------------------------------------------|------------------------------|-----------------------------------------------------------|-------------------------------------------------------------|
| In an accessible cargo compartment         |                              |                                                           |                                                             |
| If packages are accessible                 | If packages are inaccessible | If packages are in a freight container and are accessible | If packages are in a freight container and are inaccessible |
| No limit .....                             | Forbidden (see Note 1) ..... | No Limit .....                                            | Forbidden (see Note 1).                                     |
| In an inaccessible cargo compartment       |                              |                                                           |                                                             |
| If packages are not in a freight container |                              | If packages are in a freight container                    |                                                             |
| Forbidden (see Note 1) .....               |                              | Forbidden (see Note 1).                                   |                                                             |

NOTE 1: Except the following materials are not subject to this restriction:

- a. Class 3, PG III (unless the hazardous material meets the definition of another hazard class)
- b. Class 6 (unless also labeled as a flammable liquid)
- c. Class 7 (unless the hazardous material meets the definition of another hazard class)

## § 175.78 Stowage compatibility of cargo.

(a) For stowage on an aircraft, in a cargo facility, or in any other area at an airport designated for the stowage of hazardous materials, packages containing hazardous materials which

might react dangerously with one another may not be placed next to each other or in a position that would allow a dangerous interaction in the event of leakage.

(b) At a minimum, the segregation instructions prescribed in the following Segregation Table must be followed to maintain acceptable segregation between packages containing hazardous materials with different hazards. The Segregation Table instructions apply whether or not the class or division is the primary or subsidiary risk. The Segregation Table follows:

SEGREGATION TABLE

| Hazard label | Class or division |        |        |        |        |        |        |        |
|--------------|-------------------|--------|--------|--------|--------|--------|--------|--------|
|              | 1                 | 2      | 3      | 4.2    | 4.3    | 5.1    | 5.2    | 8      |
| 1 .....      | Note 1            | Note 2 | Note 2 | Note 2 | Note 2 | Note 2 | Note 2 | Note 2 |
| 2 .....      | Note 2            | .....  | .....  | .....  | .....  | .....  | .....  | .....  |
| 3 .....      | Note 2            | .....  | .....  | .....  | .....  | X      | .....  | .....  |
| 4.2 .....    | Note 2            | .....  | .....  | .....  | .....  | X      | .....  | .....  |

SEGREGATION TABLE—Continued

| Hazard label | Class or division |       |       |       |       |       |       |       |
|--------------|-------------------|-------|-------|-------|-------|-------|-------|-------|
|              | 1                 | 2     | 3     | 4.2   | 4.3   | 5.1   | 5.2   | 8     |
| 4.3 .....    | Note 2            | ..... | ..... | ..... | ..... | ..... | ..... | X     |
| 5.1 .....    | Note 2            | ..... | X     | X     | ..... | ..... | ..... | ..... |
| 5.2 .....    | Note 2            | ..... | ..... | ..... | ..... | ..... | ..... | ..... |
| 8 .....      | Note 2            | ..... | ..... | ..... | X     | ..... | ..... | ..... |

(c) Instructions for using the Segregation Table are as follows:

(1) Hazard labels, classes or divisions not shown in the table are not subject to segregation requirements.

(2) Dots at the intersection of a row and column indicate that no restrictions apply.

(3) The letter “X” at the intersection of a row and column indicates that packages containing these classes of hazardous materials may not be stowed next to or in contact with each other, or in a position which would allow interaction in the event of leakage of the contents.

(4) Note 1. “Note 1” at the intersection of a row and column means the following:

(i) Only Division 1.4, Compatibility Group S, explosives are permitted to be transported aboard a passenger aircraft. Only certain Division 1.3, Compatibility Groups C and G, and Division 1.4, Compatibility Groups B, C, D, E, G and S, explosives may be transported aboard a cargo aircraft.

(ii) Division 1.4 explosives in Compatibility Group S may be stowed with Division 1.3 and 1.4 explosives in compatibility groups as permitted aboard aircraft under paragraph (c)(4)(i) above.

(iii) Except as otherwise provided in this Note, explosives of different compatibility groups may be stowed together whether or not they belong to the same division.

(iv) Division 1.4B and Division 1.3 explosives may not be stowed together. Division 1.4B explosives must be loaded into separate unit load devices and, when stowed aboard the aircraft, the unit load devices must be separated by other cargo with a minimum separation of 2 m (6.5 feet). When not loaded in unit load devices, Division 1.4B and Division 1.3 explosives must be loaded into different, non-adjacent loading positions and separated by other cargo

with a minimum separation of 2 m (6.5 feet).

(5) Note 2. “Note 2” at the intersection of a row and column means that other than explosives of Division 1.4, Compatibility Group S, explosives may not be stowed together with that class.

(6) Packages containing hazardous materials with multiple hazards in the class or divisions, which require segregation in accordance with the Segregation Table, need not be segregated from other packages bearing the same UN number.

(7) A package labeled “BLASTING AGENT” may not be stowed next to or in a position that will allow contact with a package of special fireworks or railway torpedoes.

[71 FR 14604, Mar. 22, 2006, as amended at 71 FR 54396, Sept. 14, 2006; 71 FR 78634, Dec. 29, 2006]

#### § 175.88 Inspection, orientation and securing packages of hazardous materials.

(a) A unit load device may not be loaded on an aircraft unless the device has been inspected and found to be free from any evidence of leakage from, or damage to, any package containing hazardous materials.

(b) A package containing hazardous materials marked “THIS SIDE UP” or “THIS END UP”, or with arrows to indicate the proper orientation of the package, must be stored and loaded aboard an aircraft in accordance with such markings. A package without orientation markings containing liquid hazardous materials must be stored and loaded with top closure facing upward.

(c) Packages containing hazardous materials must be secured in an aircraft in a manner that will prevent any movement in flight which would result

in damage to or change in the orientation of the packages. Packages containing Class 7 (radioactive) materials must be secured in a manner that ensures that the separation requirements of §§ 175.701 and 175.702 will be maintained at all times during flight.

**§ 175.90 Damaged shipments.**

(a) Packages or overpacks containing hazardous materials must be inspected for damage or leakage after being unloaded from an aircraft. When packages or overpacks containing hazardous materials have been transported in a unit load device, the area where the unit load device was stowed must be inspected for evidence of leakage or contamination immediately upon removal of the unit load device from the aircraft, and the packages or overpacks must be inspected for evidence of damage or leakage when the unit load device is unloaded. In the event of leakage or suspected leakage, the compartment in which the package, overpack, or unit load device was carried must be inspected for contamination and decontaminated, if applicable.

(b) Except as provided in § 175.700, the operator of an aircraft must remove from the aircraft any package, baggage or cargo that appears to be leaking or contaminated by a hazardous material. In the case of a package, baggage or cargo that appears to be leaking, the operator must ensure that other packages, baggage or cargo in the same shipment are in proper condition for transport aboard the aircraft and that no other package, baggage or cargo has been contaminated or is leaking. If an operator becomes aware that a package, baggage or cargo not identified as containing a hazardous material has been contaminated, or the operator has cause to believe that a hazardous material may be the cause of the contamination, the operator must take reasonable steps to identify the nature and source of contamination before proceeding with the loading of the contaminated baggage or cargo. If the contaminating substance is found or suspected to be hazardous material, the operator must isolate the package, baggage or cargo and take appropriate steps to eliminate any identified haz-

ard before continuing the transportation of the item by aircraft.

(c) No person may place aboard an aircraft a package, baggage or cargo that is contaminated with a hazardous material or appears to be leaking.

(d) If a package containing a material in Division 6.2 (infectious substance) is found to be damaged or leaking, the person finding the package must:

(1) Avoid handling the package or keep handling to a minimum;

(2) Inspect packages adjacent to the leaking package for contamination and withhold from further transportation any contaminated packages until it is ascertained that they can be safely transported;

(3) Comply with the reporting requirement of §§ 171.15 and 175.31 of this subchapter; and

(4) Notify the consignor or consignee.

**Subpart C—Specific Regulations  
Applicable According to  
Classification of Material**

**§ 175.310 Transportation of flammable liquid fuel; aircraft only means of transportation.**

(a) When other means of transportation are impracticable, flammable liquid fuels may be carried on certain passenger and cargo aircraft as provided in this section, without regard to the packaging references and quantity limits listed in Columns 7, 8 and 9 of the § 172.101 Hazardous Materials Table. All requirements of this subchapter that are not specifically covered in this section continue to apply to shipments made under the provisions of this section. For purposes of this section “impracticable” means transportation is not physically possible or cannot be performed by routine and frequent means of other transportation, due to extenuating circumstances. Extenuating circumstances include: conditions precluding highway or water transportation, such as a frozen vessel route; road closures due to catastrophic weather or volcanic activity; or a declared state of emergency. The desire for expedience of a shipper, carrier, or consignor, is not relevant in determining whether other means of transportation are impracticable. The



**§ 175.310**

**49 CFR Ch. I (10–1–08 Edition)**

stowage requirements of § 175.75(a) do not apply to a person operating an aircraft under the provisions of this section which, because of its size and configuration, makes it impossible to comply.

(b) A small passenger-carrying aircraft operated entirely within the State of Alaska or into a remote area, in other than scheduled passenger operations, may carry up to 76 L (20 gallons) of flammable liquid fuel (in Packing Group II or Packing Group III), when:

(1) The flight is necessary to meet the needs of a passenger; and

(2) The fuel is carried in one of the following types of containers:

(i) Strong tight metal containers of not more than 20 L (5.3 gallons) capacity, each packed inside a UN 4G fiberboard box, at the Packing Group II performance level, or each packed inside a UN 4C1 wooden box, at the Packing Group II performance level;

(ii) Airtight, leakproof, inside containers of not more than 40 L (11 gallons) capacity and of at least 28-gauge metal, each packed inside a UN 4C1 wooden box, at the Packing Group II performance level;

(iii) UN 1A1 steel drums, at the Packing Group I or II performance level, of not more than 20 L (5.3 gallons) capacity; or

(iv) In fuel tanks attached to flammable liquid fuel powered equipment under the following conditions:

(A) Each piece of equipment is secured in an upright position;

(B) Each fuel tank is filled in a manner that will preclude spillage of fuel during loading, unloading, and transportation; and

(C) Fueling and refueling of the equipment is prohibited in or on the aircraft.

(3) In the case of a passenger-carrying helicopter, the fuel or fueled equipment must be carried on external cargo racks or slings.

(c) Flammable liquid fuels may be carried on a cargo aircraft, subject to the following conditions:

(1)(i) The flammable liquid fuel is in Packing Group II or Packing Group III except as indicated in paragraph (c)(1)(iv) of this section;

(ii) The fuel is carried in packagings authorized in paragraph (b) of this section;

(iii) The fuel is carried in metal drums (UN 1A1, 1B1, 1N1) authorized for Packing Group I or Packing Group II liquid hazardous materials and having rated capacities of 220 L (58 gallons) or less. These single packagings may not be transported in the same aircraft with Class 1, Class 5, or Class 8 materials.

(iv) Combustible and flammable liquid fuels (including those in Packing Group I) may be carried in installed aircraft tanks each having a capacity of more than 450 L (118.9 gallons), subject to the following additional conditions:

(A) The tanks and their associated piping and equipment and the installation thereof must have been approved for the material to be transported by the appropriate FAA Flight Standards District Office.

(B) In the case of an aircraft being operated by a certificate holder, the operator shall list the aircraft and the approval information in its operating specifications. If the aircraft is being operated by other than a certificate holder, a copy of the FAA Flight Standards District Office approval required by this section must be carried on the aircraft.

(C) The crew of the aircraft must be thoroughly briefed on the operation of the particular bulk tank system being used.

(D) During loading and unloading and thereafter until any remaining fumes within the aircraft are dissipated:

(1) Only those electrically operated bulk tank shutoff valves that have been approved under a supplemental type certificate may be electrically operated.

(2) No engine or electrical equipment, avionic equipment, or auxiliary power units may be operated, except position lights in the steady position and equipment required by approved loading or unloading procedures, as set forth in the operator's operations manual, or for operators that are not certificate holders, as set forth in a written statement.

(3) Static ground wires must be connected between the storage tank or fueler and the aircraft, and between the aircraft and a positive ground device.

(2) [Reserved]

(d) The following restrictions apply to loading, handling, or carrying fuel under the provisions of this section:

(1) During loading and unloading, no person may smoke, carry a lighted cigarette, cigar, or pipe, or operate any device capable of causing an open flame or spark within 15 m (50 feet) of the aircraft.

(2) No person may fill a container, other than an approved bulk tank, with a Class 3 material or combustible liquid or discharge a Class 3 material or combustible liquid from a container, other than an approved bulk tank, while that container is inside or within 15 m (50 feet) of the aircraft.

(3) When filling an approved bulk tank by hose from inside the aircraft, the doors and hatches of the aircraft must be fully open to insure proper ventilation.

(4) Each area or compartment in which the fuel is loaded is suitably ventilated to prevent the accumulation of fuel vapors.

(5) Fuel is transferred to the aircraft fuel tanks only while the aircraft is on the ground.

(6) Before each flight, the pilot-in-command:

(i) Prohibits smoking, lighting matches, the carrying of any lighted cigar, pipe, cigarette or flame, and the use of anything that might cause an open flame or spark, while in flight; and

(ii) For passenger aircraft, informs each passenger of the location of the fuel and the hazards involved.

(e) Operators must comply with the following:

(1) If the aircraft is being operated by a holder of a certificate issued under 14 CFR part 121 or part 135, operations must be conducted in accordance with conditions and limitations specified in the certificate holder's operations specifications or operations manual accepted by the FAA. If the aircraft is being operated under 14 CFR part 91, operations must be conducted in accordance with an operations plan accepted and acknowledged in writing by

the FAA Principal Operations Inspector assigned to the operator.

(2) The aircraft and the loading arrangement to be used must be approved for the safe carriage of the particular materials concerned by the FAA Principal Operations Inspector assigned to the operator.

**§ 175.501 Special requirements for oxidizers and compressed oxygen.**

(a) Compressed oxygen, when properly labeled Oxidizer or Oxygen, may be loaded and transported as provided in this section. Except for Oxygen, compressed, no person may load or transport a hazardous material for which an OXIDIZER label is required under this subchapter in an inaccessible cargo compartment that does not have a fire or smoke detection system and a fire suppression system.

(b) In addition to the quantity limitations prescribed in § 175.75, no more than a combined total of six cylinders of compressed oxygen may be stowed on an aircraft in the inaccessible aircraft cargo compartment(s) that do not have fire or smoke detection systems and fire suppression systems.

(c) When loaded into a passenger-carrying aircraft or in an inaccessible cargo location on a cargo-only aircraft, cylinders of compressed oxygen must be stowed horizontally on the floor or as close as practicable to the floor of the cargo compartment or unit load device. This provision does not apply to cylinders stowed in the cabin of the aircraft in accordance with paragraph (e) of this section.

(d) When transported in a Class B aircraft cargo compartment (see 14 CFR 25.857(b)) or its equivalent (i.e., an accessible cargo compartment equipped with a fire or smoke detection system, but not a fire suppression system), cylinders of compressed oxygen must be loaded in a manner that a crew member can see, handle and, when size and weight permit, separate the cylinders from other cargo during flight. No more than six cylinders of compressed oxygen and, in addition, one cylinder of medical-use compressed oxygen per passenger needing oxygen at destination—with a rated capacity of 1000 L (34 cubic feet) or less of oxygen—may

## § 175.630

be carried in a Class B aircraft cargo compartment or its equivalent.

(e) A cylinder containing medical-use compressed oxygen, owned or leased by an aircraft operator or offered for transportation by a passenger needing it for personal medical use at destination, may be carried in the cabin of a passenger-carrying aircraft in accordance with the following provisions:

(1) No more than six cylinders belonging to the aircraft operator and, in addition, no more than one cylinder per passenger needing the oxygen at destination, may be transported in the cabin of the aircraft under the provisions of this paragraph (e);

(2) The rated capacity of each cylinder may not exceed 1,000 L (34 cubic feet);

(3) Each cylinder must conform to the provisions of this subchapter and be placed in:

(i) An outer packaging that conforms to the performance criteria of Air Transport Association (ATA) Specification 300 for a Category I Shipping Container; or

(ii) A metal, plastic or wood outer packaging that conforms to a UN standard at the Packing Group I or II performance level.

(4) The aircraft operator shall securely stow the cylinder in its overpack or outer packaging in the cabin of the aircraft and shall notify the pilot-in-command as specified in §175.33 of this part; and

(5) Shipments under this paragraph (e) are not subject to—

(i) Sections 173.302(f) and 173.304(f) of this subchapter, subpart C of part 172 of this subchapter, and, for passengers only, subpart H of part 172 of this subchapter;

(ii) Section 173.25(a)(4) of this subchapter; and

(iii) Paragraph (b) of this section.

[72 FR 4456, Jan. 31, 2007, as amended at 72 FR 55099, Sept. 28, 2007]

### **§ 175.630 Special requirements for Division 6.1 (poisonous) material and Division 6.2 (infectious substances) materials.**

(a) A package required to bear a POISON, POISON INHALATION HAZARD, or INFECTIOUS SUBSTANCE label may not be carried in the same com-

## 49 CFR Ch. I (10–1–08 Edition)

partment of an aircraft with material which is marked as or known to be a foodstuff, feed, or any other edible material intended for consumption by humans or animals unless:

(1) The Division 6.1 or Division 6.2 material and the foodstuff, feed, or other edible material are loaded in separate unit load devices which, when stowed on the aircraft, are not adjacent to each other; or

(2) The Division 6.1 or Division 6.2 material are loaded in one closed unit load device and the foodstuff, feed or other material is loaded in another closed unit load device.

(b) No person may operate an aircraft that has been used to transport any package required to bear a POISON or POISON INHALATION HAZARD label unless, upon removal of such package, the area in the aircraft in which it was carried is visually inspected for evidence of leakage, spillage, or other contamination. All contamination discovered must be either isolated or removed from the aircraft. The operation of an aircraft contaminated with such Division 6.1 materials is considered to be the carriage of poisonous materials under paragraph (a) of this section.

(c) When unloaded from the aircraft, each package, overpack, pallet, or unit load device containing a Division 6.2 material must be inspected for signs of leakage. If evidence of leakage is found, the cargo compartment in which the package, overpack, or unit load device was transported must be disinfected. Disinfection may be by any means that will make the material released ineffective at transmitting disease.

[71 FR 14604, Mar. 22, 2006, as amended at 71 FR 32263, June 2, 2006]

### **§ 175.700 Special limitations and requirements for Class 7 materials.**

(a) Except as provided in §§173.4, 173.422 and 173.423 of this subchapter, no person may carry any Class 7 materials aboard a passenger-carrying aircraft unless that material is intended for use in, or incident to research (See §171.8 of this subchapter), medical diagnosis or treatment. Regardless of its intended use, no person may carry a Type B(M) package aboard a passenger-carrying aircraft, a vented Type B(M)

package aboard any aircraft, or a liquid pyrophoric Class 7 material aboard any aircraft.

(b) *Limits for transport index and criticality safety index.* A person may carry the following Class 7 (radioactive) materials aboard an aircraft only when—

(1) On a passenger-carrying aircraft—

(i) Each single package on the aircraft has a transport index no greater than 3.0;

(ii) The combined transport index and the combined criticality index of all the packages on the aircraft are each no greater than 50.

(2) On a cargo aircraft—

(i) Each single package on the aircraft has a transport index no greater than 10.0.

(ii) The combined transport index of all the packages on the aircraft is no greater than 200, and the combined criticality index of all the packages on the aircraft is no greater than—

(A) 50 on a non-exclusive use cargo aircraft, or

(B) 100 on an aircraft assigned for the exclusive use of the shipper [offeror] for the specific shipment of fissile Class 7 material. Instructions for the exclusive use must be developed by the shipper [offeror] and carrier, and the instructions must accompany the shipping papers.

(3) The combined transport index and combined criticality index are determined by adding together the transport index and criticality index numbers, respectively, shown on the labels of the individual packages.

(c) No person may carry in a passenger-carrying aircraft any package required to be labeled RADIOACTIVE YELLOW-II or RADIOACTIVE YELLOW-III label unless the package is carried on the floor of the cargo compartment or freight container.

**§ 175.701 Separation distance requirements for packages containing Class 7 (radioactive) materials in passenger-carrying aircraft.**

(a) The following table prescribes the minimum separation distances that must be maintained in a passenger-carrying aircraft between Class 7 (radioactive) materials labeled RADIOACTIVE YELLOW-II or RADIOACTIVE YELLOW-III and passengers and crew:

| Transport index or sum of transport indexes of all packages in the aircraft or predesignated area | Minimum separation distances |        |
|---------------------------------------------------------------------------------------------------|------------------------------|--------|
|                                                                                                   | Centimeters                  | Inches |
| 0.1 to 1.0 .....                                                                                  | 30                           | 12     |
| 1.1 to 2.0 .....                                                                                  | 50                           | 20     |
| 2.1 to 3.0 .....                                                                                  | 70                           | 28     |
| 3.1 to 4.0 .....                                                                                  | 85                           | 34     |
| 4.1 to 5.0 .....                                                                                  | 100                          | 40     |
| 5.1 to 6.0 .....                                                                                  | 115                          | 46     |
| 6.1 to 7.0 .....                                                                                  | 130                          | 52     |
| 7.1 to 8.0 .....                                                                                  | 145                          | 57     |
| 8.1 to 9.0 .....                                                                                  | 155                          | 61     |
| 9.1 to 10.0 .....                                                                                 | 165                          | 65     |
| 10.1 to 11.0 .....                                                                                | 175                          | 69     |
| 11.1 to 12.0 .....                                                                                | 185                          | 73     |
| 12.1 to 13.0 .....                                                                                | 195                          | 77     |
| 13.1 to 14.0 .....                                                                                | 205                          | 81     |
| 14.1 to 15.0 .....                                                                                | 215                          | 85     |
| 15.1 to 16.0 .....                                                                                | 225                          | 89     |
| 16.1 to 17.0 .....                                                                                | 235                          | 93     |
| 17.1 to 18.0 .....                                                                                | 245                          | 97     |
| 18.1 to 20.0 .....                                                                                | 260                          | 102    |
| 20.1 to 25.0 .....                                                                                | 290                          | 114    |
| 25.1 to 30.0 .....                                                                                | 320                          | 126    |
| 30.1 to 35.0 .....                                                                                | 350                          | 138    |
| 35.1 to 40.0 .....                                                                                | 375                          | 148    |
| 40.1 to 45.0 .....                                                                                | 400                          | 157    |
| 45.1 to 50.0 .....                                                                                | 425                          | 167    |

(b) When transported aboard passenger-carrying aircraft packages, overpacks or freight containers labeled Radioactive Yellow-II or Radioactive Yellow-III must be separated from live animals by a distance of at least 0.5 m (20 inches) for journeys not exceeding 24 hours, and by a distance of at least 1.0 m (39 inches) for journeys longer than 24 hours.

(c) Except as provided in paragraph (d) of this section, the minimum separation distances prescribed in paragraphs (a) and (b) of this section are determined by measuring the shortest distance between the surfaces of the Class 7 (radioactive) materials package and the surfaces bounding the space occupied by passengers or animals. If more than one package of Class 7 (radioactive) materials is placed in a passenger-carrying aircraft, the minimum separation distance for these packages shall be determined in accordance with paragraphs (a) and (b) of this section on the basis of the sum of the transport index numbers of the individual packages or overpacks.

(d) *Predesignated areas.* A package labeled RADIOACTIVE YELLOW-II or RADIOACTIVE YELLOW-III may be carried in a passenger-carrying aircraft in accordance with a system of predesignated areas established by the

**§ 175.702**

**49 CFR Ch. I (10–1–08 Edition)**

aircraft operator. Each aircraft operator that elects to use a system of predesignated areas shall submit a detailed description of the proposed system to the Associate Administrator for approval prior to implementation of the system. A proposed system of predesignated areas is approved if the Associate Administrator determines that it is designed to assure that:

(1) The packages can be placed in each predesignated area in accordance with the minimum separation distances prescribed in paragraph (a) of this section; and

(2) The predesignated areas are separated from each other by minimum distance equal to at least four times the distances required by paragraphs (a) and (b) of this section for the predesignated area containing packages with the largest sum of transport indexes.

**§ 175.702 Separation distance requirements for packages containing Class 7 (radioactive) materials in cargo aircraft.**

(a) No person may carry in a cargo aircraft any package required by § 172.403 of this subchapter to be labeled Radioactive Yellow–II or Radioactive Yellow–III unless:

(1) The total transport index for all packages does not exceed 50.0 and the packages are carried in accordance with § 175.701(a); or

(2) The total transport index for all packages exceeds 50.0; and

(i) The separation distance between the surfaces of the radioactive materials packages, overpacks or freight containers and any space occupied by live animals is at least 0.5 m (20 inches) for journeys not exceeding 24 hours and at least 1.0 m (39 inches) for journeys longer than 24 hours; and

(ii) The minimum separation distances between the radioactive material and any areas occupied by persons that are specified in the following table are maintained:

| Transport index or sum of transport indexes of all packages in the aircraft of predesignated area | Minimum separation distances |        |
|---------------------------------------------------------------------------------------------------|------------------------------|--------|
|                                                                                                   | Centimeters                  | Inches |
| 50.1 to 60.0 .....                                                                                | 465                          | 183    |
| 60.1 to 70.0 .....                                                                                | 505                          | 199    |
| 70.1 to 80.0 .....                                                                                | 545                          | 215    |
| 80.1 to 90.0 .....                                                                                | 580                          | 228    |
| 90.1 to 100.0 .....                                                                               | 610                          | 240    |
| 100.1 to 110.0 .....                                                                              | 645                          | 254    |
| 110.1 to 120.0 .....                                                                              | 670                          | 264    |
| 120.1 to 130.0 .....                                                                              | 700                          | 276    |
| 130.1 to 140.0 .....                                                                              | 730                          | 287    |
| 140.1 to 150.0 .....                                                                              | 755                          | 297    |
| 150.1 to 160.0 .....                                                                              | 780                          | 307    |
| 160.1 to 170.0 .....                                                                              | 805                          | 317    |
| 170.1 to 180.0 .....                                                                              | 830                          | 327    |
| 180.1 to 190.0 .....                                                                              | 855                          | 337    |
| 190.1 to 200.0 .....                                                                              | 875                          | 344    |

(b) The criticality safety index of any single group of packages must not exceed 50.0 (as used in this section, the term “group of packages” means packages that are separated from each other in an aircraft by a distance of 6 m (20 feet) or less); and

(c) Each group of packages must be separated from every other group in the aircraft by not less than 6 m (20

feet), measured from the outer surface of each group.

[71 FR 14604, Mar. 22, 2006, as amended at 71 FR 54396, Sept. 14, 2006]

**§ 175.703 Other special requirements for the acceptance and carriage of packages containing Class 7 materials.**

(a) No person may accept for carriage in an aircraft packages of Class 7 materials, other than limited quantities,

contained in a rigid or non-rigid over-pack, including a fiberboard box or plastic bag, unless they have been prepared for shipment in accordance with § 172.403(h) of this subchapter.

(b) Each shipment of fissile material packages must conform to the requirements of §§ 173.457 and 173.459 of this subchapter.

(c) No person shall offer or accept for transportation, or transport, by air—

(1) Vented Type B(M) packages, packages which require external cooling by an ancillary cooling system or packages subject to operational controls during transport; or

(2) Liquid pyrophoric Class 7 (radioactive) materials.

(d) Packages with radiation levels at the package surface or a transport index in excess of the limits specified in § 173.441(a) of this subchapter may not be transported by aircraft except under special arrangements approved by the Associate Administrator.

#### § 175.704 Plutonium shipments.

Shipments of plutonium which are subject to 10 CFR 71.88(a)(4) must comply with the following:

(a) Each package containing plutonium must be secured and restrained to prevent shifting under normal conditions.

(b) A package of plutonium having a gross mass less than 40 kg (88 pounds) and both its height and diameter less than 50 cm (19.7 inches)—

(1) May not be transported aboard an aircraft carrying other cargo required to bear a Division 1.1 label; and

(2) Must be stowed aboard the aircraft on the main deck or the lower cargo compartment in the aft-most location that is possible for cargo of its size and weight, and no other cargo may be stowed aft of packages containing plutonium.

(c) A package of plutonium exceeding the size and weight limitations in paragraph (b) of this section—

(1) May not be transported aboard an aircraft carrying other cargo required to bear any of the following labels: Class 1 (all Divisions), Class 2 (all Divisions), Class 3, Class 4 (all Divisions), Class 5 (all Divisions), or Class 8; and

(2) Must be securely cradled and tied down to the main deck of the aircraft

in a manner that restrains the package against the following internal forces acting separately relative to the deck of the aircraft; Upward, 2g; Forward, 9g; Sideward, 1.5g; Downward, 4.5g.

#### § 175.705 Radioactive contamination.

(a) A carrier shall take care to avoid possible inhalation, ingestion, or contact by any person with Class 7 (radioactive) materials that may have been released from their packagings.

(b) When contamination is present or suspected, the package containing a Class 7 material, any loose Class 7 material, associated packaging material, and any other materials that have been contaminated must be segregated as far as practicable from personnel contact until radiological advice or assistance is obtained from the U.S. Department of Energy or appropriate State or local radiological authorities.

(c) An aircraft in which Class 7 material has been released must be taken out of service and may not be returned to service or routinely occupied until the aircraft is checked for radioactive contamination and it is determined in accordance with § 173.443 of this subchapter that the dose rate at every accessible surface is less than 0.005 mSv per hour (0.5 mrem per hour) and there is no significant removable surface contamination.

(d) Each aircraft used routinely for transporting Class 7 materials shall be periodically checked for radioactive contamination, and an aircraft must be taken out of service if contamination exceeds the level specified in paragraph (c). The frequency of these checks shall be related to the likelihood of contamination and the extent to which Class 7 materials are transported.

(e) In addition to the reporting requirements of (§§ 171.15 and 171.16 of this subchapter and § 175.31 of this part, an aircraft operator shall notify the offeror at the earliest practicable moment following any incident in which there has been breakage, spillage, or suspected radioactive contamination involving Class 7 (radioactive) materials shipments.

## § 175.706

## 49 CFR Ch. I (10–1–08 Edition)

### § 175.706 Separation distances for undeveloped film from packages containing Class 7 (radioactive) materials.

No person may carry in an aircraft any package of Class 7 (radioactive)

materials required by §172.403 of this subchapter to be labeled Radioactive Yellow–II or Radioactive Yellow–III closer than the distances shown in the table below to any package marked as containing undeveloped film.

| Transport index   | Minimum separation distance to nearest undeveloped film for various times in transit |      |              |      |              |      |               |      |               |      |
|-------------------|--------------------------------------------------------------------------------------|------|--------------|------|--------------|------|---------------|------|---------------|------|
|                   | Up to 2 hours                                                                        |      | 2 to 4 hours |      | 4 to 8 hours |      | 8 to 12 hours |      | Over 12 hours |      |
|                   | Meters                                                                               | Feet | Meters       | Feet | Meters       | Feet | Meters        | Feet | Meters        | Feet |
| 0.1 to 1.0 .....  | 0.3                                                                                  | 1    | 0.6          | 2    | 0.9          | 3    | 1.2           | 4    | 1.5           | 5    |
| 1.1 to 5.0 .....  | 0.9                                                                                  | 3    | 1.2          | 4    | 1.8          | 6    | 2.4           | 8    | 3.3           | 11   |
| 5.1 to 10.0 ..... | 1.2                                                                                  | 4    | 1.8          | 6    | 2.7          | 9    | 3.3           | 11   | 4.5           | 15   |
| 10.1 to 20.0 ...  | 1.5                                                                                  | 5    | 2.4          | 8    | 3.6          | 12   | 4.8           | 16   | 6.6           | 22   |
| 20.1 to 30.0 ...  | 2.1                                                                                  | 7    | 3            | 10   | 4.5          | 15   | 6             | 20   | 8.7           | 29   |
| 30.1 to 40.0 ...  | 2.4                                                                                  | 8    | 3.3          | 11   | 5.1          | 17   | 6.6           | 22   | 9.9           | 33   |
| 40.1 to 50.0 ...  | 2.7                                                                                  | 9    | 3.6          | 12   | 5.7          | 19   | 7.2           | 24   | 10.8          | 36   |

### § 175.900 Handling requirements for carbon dioxide, solid (dry ice).

Carbon dioxide, solid (dry ice) when shipped by itself or when used as a refrigerant for other commodities, may be carried only if the operator has made suitable arrangements based on the aircraft type, the aircraft ventilation rates, the method of packing and stowing, whether animals will be carried on the same flight and other factors. The operator must ensure that the ground staff is informed that the dry ice is being loaded or is on board the aircraft. For arrangements between the shipper and operator, see §173.217 of this subchapter. Where dry ice is contained in a unit load device (ULD) or other type of pallet prepared by a single shipper in accordance with §173.217 and the operator after the acceptance adds additional dry ice, the operator must ensure that the information provided to the Pilot-in-Command and the marking on the ULD when used as a packaging reflects that revised quantity of dry ice.

[73 FR 4719, Jan. 28, 2008]

## PART 176—CARRIAGE BY VESSEL

### Subpart A—General

Sec.

- 176.1 Purpose and scope.
- 176.2 Definitions.
- 176.3 Unacceptable hazardous materials shipments.
- 176.4 Port security and safety regulations.
- 176.5 Application to vessels.

- 176.7 Documentation for vessel personnel.
- 176.9 “Order-Notify” or “C.O.D.” shipments.
- 176.11 Exceptions.
- 176.13 Responsibility for compliance and training.
- 176.15 Enforcement.
- 176.18 Assignment and certification.

### Subpart B—General Operating Requirements

- 176.24 Shipping papers.
- 176.27 Certificate.
- 176.30 Dangerous cargo manifest.
- 176.31 Special permits.
- 176.36 Preservation of records.
- 176.39 Inspection of cargo.
- 176.45 Emergency situations.
- 176.48 Situation requiring report.
- 176.50 Acceptance of damaged or leaking packages.
- 176.52 Rejections of shipments in violation.
- 176.54 Repairs involving welding, burning, and power-actuated tools and appliances.

### Subpart C—General Handling and Stowage

- 176.57 Supervision of handling and stowage.
- 176.58 Preparation of the vessel.
- 176.60 “No Smoking” signs.
- 176.63 Stowage locations.
- 176.65 Alternative stowage procedures.
- 176.69 General stowage requirements for hazardous materials.
- 176.70 Stowage requirements for marine pollutants.
- 176.72 Handling of break-bulk hazardous materials.
- 176.74 On deck stowage of break-bulk hazardous materials.
- 176.76 Transport vehicles, freight containers, and portable tanks containing hazardous materials.

- 176.77 Stowage of barges containing hazardous materials on board barge-carrying vessels.  
 176.78 Use of power-operated industrial trucks on board vessels.

#### **Subpart D—General Segregation Requirements**

- 176.80 Applicability.  
 176.83 Segregation.  
 176.84 Other requirements for stowage and segregation for cargo vessels and passenger vessels.

#### **Subpart E—Special Requirements for Transport Vehicles Loaded With Hazardous Materials and Transported on Board Ferry Vessels**

- 176.88 Applicability.  
 176.89 Control of transport vehicles.  
 176.90 Private automobiles.  
 176.91 Motorboats.  
 176.92 Cylinders laden in vehicles.  
 176.93 Vehicles having refrigerating or heating equipment.

#### **Subpart F—Special Requirements for Barges**

- 176.95 Applicability.  
 176.96 Materials of construction.  
 176.97 Prohibition of dump scows.  
 176.98 Stowage of hazardous materials on board barges.  
 176.99 Permit requirements for certain hazardous materials.

#### **Subpart G—Detailed Requirements for Class 1 (Explosive) Materials**

- 176.100 Permit for Divisions 1.1 and 1.2 (explosive) materials.  
 176.102 Supervisory detail.  
 176.104 Loading and unloading Class 1 (explosive) materials.  
 176.108 Supervision of Class 1 (explosive) materials during loading, unloading, handling and stowage.

##### **STOWAGE**

- 176.112 Applicability.  
 176.116 General stowage conditions for Class 1 (explosive) materials.  
 176.118 Electrical requirement.  
 176.120 Lightning protection.  
 176.122–176.124 [Reserved]  
 176.128 Magazine stowage types “A”, “C” and Special Stowage.  
 176.130 Magazine stowage Type A.  
 176.132 [Reserved]  
 176.133 Magazine stowage Type C.  
 176.134 Vehicles.  
 176.136 Special stowage.  
 176.137 Portable magazine.  
 176.138 Deck stowage.

##### **SEGREGATION**

- 176.140 Segregation from other classes of hazardous materials.  
 176.142 Hazardous materials of extreme flammability.  
 176.144 Segregation of Class 1 (explosive) materials.  
 176.145 Segregation in single hold vessels.  
 176.146 Segregation from non-hazardous materials.

##### **PRECAUTIONS DURING LOADING AND UNLOADING**

- 176.148 Artificial lighting.  
 176.150 Radio and radar.  
 176.154 Fueling (bunkering).  
 176.156 Defective packages.  
 176.160 Protection against weather.  
 176.162 Security.  
 176.164 Fire precautions and firefighting.

##### **PASSENGER VESSELS**

- 176.166 Transport of Class 1 (explosive) materials on passenger vessels.

##### **CARGO TRANSPORT UNITS AND SHIPBORNE BARGES**

- 176.168 Transport of Class 1 (explosive) materials in vehicle spaces.  
 176.170 Transport of Class 1 (explosive) materials in freight containers.  
 176.172 Structural serviceability of freight containers and vehicles carrying Class 1 (explosive) materials on ships.  
 176.174 Transport of Class 1 (explosive) materials in shipborne barges.

##### **HANDLING CLASS 1 (EXPLOSIVE) MATERIALS IN PORT**

- 176.176 Signals.  
 176.178 Mooring lines.  
 176.180 Watchkeeping.  
 176.182 Conditions for handling on board ship.  
 176.184 Class 1 (explosive) materials of Compatibility Group L.  
 176.190 Departure of vessel.  
 176.192 Cargo handling equipment for freight containers carrying Class 1 (explosive) materials.

##### **MAGAZINE VESSELS**

- 176.194 Stowage of Class 1 (explosive) materials on magazine vessels.

#### **Subpart H—Detailed Requirements for Class 2 (Compressed Gas) Materials**

- 176.200 General stowage requirements.  
 176.205 Under deck stowage requirements.  
 176.210 On deck stowage requirements.  
 176.220 Smoking or open flame and posting of warning signs.  
 176.225 Stowage of chlorine.



## § 176.1

176.230 Stowage of Division 2.1 (flammable gas) materials.

### Subpart I—Detailed Requirements for Class 3 (Flammable) and Combustible Liquid Materials

176.305 General stowage requirements.  
176.315 Fire protection requirements.  
176.320 Use of hand flashlights.  
176.325 Smoking or open flame and posting of warning signs.  
176.340 Combustible liquids in portable tanks.

### Subpart J—Detailed Requirements for Class 4 (Flammable Solids), Class 5 (Oxidizers and Organic Peroxides), and Division 1.5 Materials

176.400 Stowage of Division 1.5, Class 4 (flammable solids) and Class 5 (oxidizers and organic peroxides) materials.  
176.405 Stowage of charcoal.  
176.410 Division 1.5 materials, ammonium nitrate and ammonium nitrate mixtures.  
176.415 Permit requirements for Division 1.5, ammonium nitrates, and certain ammonium nitrate fertilizers.

### Subpart K [Reserved]

### Subpart L—Detailed Requirements for Division 2.3 (Poisonous Gas) and Division 6.1 (Poisonous) Materials

176.600 General stowage requirements.  
176.605 Care following leakage or sifting of Division 2.3 (poisonous gas) and Division 6.1 (poisonous) materials.

### Subpart M—Detailed Requirements for Radioactive Materials

176.700 General stowage requirements.  
176.704 Requirements relating to transport indices and criticality safety indices.  
176.708 Segregation distances.  
176.710 Care following leakage or sifting of radioactive materials.  
176.715 Contamination control.  
176.720 Requirements for carriage of INF cargo in international transportation.

### Subpart N—Detailed Requirements for Class 8 (Corrosive Materials) Materials

176.800 General stowage requirements.  
176.805 On deck stowage.

### Subpart O—Detailed Requirements for Cotton and Vegetable Fibers, Motor Vehicles, and Asbestos

176.900 Packaging and stowage of cotton and vegetable fibers; general.

## 49 CFR Ch. I (10–1–08 Edition)

176.901 Stowage of cotton or vegetable fibers with rosin or pitch.

176.903 Stowage of cotton or vegetable fibers with coal.

176.905 Motor vehicles or mechanical equipment powered by internal combustion engines.

AUTHORITY: 49 U.S.C. 5101–5128; 49 CFR 1.53.

## Subpart A—General

### § 176.1 Purpose and scope.

This part prescribes requirements in addition to those contained in parts 171, 172, and 173 of this subchapter to be observed with respect to the transportation of hazardous materials by vessel.

### § 176.2 Definitions.

As used in this part—

*Cantline* means the v-shaped groove between two abutting, parallel horizontal cylinders.

*Cargo net* means a net made of fiber or wire used to provide convenience in handling loose or packaged cargo to and from a vessel.

*Cargo transport unit* means a transport vehicle, a freight container or a portable tank. A *closed cargo transport unit* means a cargo transport unit in which the contents are totally enclosed by permanent structures. An *open cargo transport unit* means a cargo transport unit that is not a closed cargo transport unit. Cargo transport units with fabric sides or tops are not closed cargo transport units for the purposes of this part.

*Clear of living quarters* means that the hazardous material must be located so that in the event of release of the material, leakage or vapors will not penetrate accommodations, machinery spaces or other work areas by means of entrances or other openings in bulkheads or ventilation ducts.

*Closed freight container* means a freight container which totally encloses its contents by permanent structures. A freight container formed partly by a tarpaulin, plastic sheet, or similar material is not a closed freight container.

*Commandant (G-MSO), USCG* means the Chief, Office of Operating and Environmental Standards, United States

Coast Guard, Washington, DC 20593–0001.

*Compartment* means any space on a vessel that is enclosed by the vessel's decks and its sides or permanent steel bulkheads.

*CSC safety approval plate* means the safety approval plate specified in Annex I of the International Convention for Safe Containers (1972) and conforming to the specifications in 49 CFR 451.23 and 451.25. The plate is evidence that a freight container was designed, constructed, and tested under international rules incorporated into U.S. regulations in 49 CFR parts 450 through 453. The plate is found in the door area of the container.

*Deck structure* means a structure of substantial weight and size located on the weather deck of a vessel and integral with the deck. This term includes superstructures, deck houses, mast houses, and bridge structures.

*Draft* means a load or combination of loads capable of being hoisted into or out of a vessel in a single lift.

*Dunnage* means lumber of not less than 25 mm (0.98 inch) commercial thickness or equivalent material laid over or against structures such as tank tops, decks, bulkheads, frames, plating, or ladders, or used for filling voids or fitting around cargo, to prevent damage during transportation.

*Explosives anchorage* means an anchorage so designated under 33 CFR part 110, subpart B.

*Explosive article* means an article or device that contains one or more explosive substances. Individual explosive substances are identified in column 17 of the Dangerous Goods List in the IMDG Code (IBR, see § 171.7 of this subchapter).

*Explosives handling facility* means—

(1) A “designated waterfront facility” designated under 33 CFR part 126 when loading, handling, and unloading Class 1 (explosives) materials; or

(2) A facility for loading, unloading, and handling military Class 1 (explosives) materials which is operated or controlled by an agency of the Department of Defense.

*Explosive substance* means a solid or liquid material, or a mixture of materials, which is in itself capable by chemical reaction of producing gas at

such a temperature and pressure and at such a speed as to cause damage to its surroundings. Individual explosive substances are identified in column 17 of the Dangerous Goods List in the IMDG Code.

*Handling* means the operation of loading and unloading a vessel; transfer to, from, or within a vessel, and any ancillary operations.

*Hold* means a compartment below deck that is used exclusively for the carriage of cargo.

*In containers or the like* means any clean, substantial, weatherproof box structure which can be secured to the vessel's structure, including a portable magazine or a closed cargo transport unit. Whenever this stowage is specified, stowage in deckhouses, mast lockers and oversized weatherproof packages (overpacks) is also acceptable.

*Incompatible materials* means two materials whose stowage together may result in undue hazards in the case of leakage, spillage, or other accident.

*INF cargo* means packaged irradiated nuclear fuel, plutonium or high-level radioactive wastes as those terms are defined in the “International Code for the Safe Carriage of Packaged Irradiated Nuclear Fuel, Plutonium and High-Level Radioactive Wastes on Board Ships” (INF Code) contained in the IMDG Code.

*Landing mat* means a shock absorbing pad used in loading Class 1 (explosive) materials on vessels.

*Machinery Spaces of Category A* are those spaces, and trunks to such spaces, which contain:

(1) Internal combustion machinery used for main propulsion;

(2) Internal combustion machinery used for purposes other than main propulsion where such machinery has in the aggregate a total power output of not less than 375 kw; or

(3) any oil-fired boiler or fuel unit.

*Magazine* means an enclosure designed to protect certain goods of Class 1 (explosive) materials from damage by other cargo and adverse weather conditions during loading, unloading, and when in transit; and to prevent unauthorized access. A magazine may be a fixed structure or compartment in the vessel, a closed freight container, a closed transport vehicle, or a portable

### § 176.3

magazine. Magazines may be positioned in any part of the ship conforming with the relevant provisions for Class 1 (explosive) materials contained in Subpart G of this part provided that magazines which are fixed structures are sited so that their doors, where fitted, are easily accessible.

*Master of the Vessel*, as used in this part, includes the person in charge of an unmanned vessel or barge.

*Open freight container* means a freight container that does not totally enclose its contents by permanent structures.

*Overstowed* means a package or container is stowed directly on top of another. However, with regard to Class 1 (explosive) stowage, such goods may themselves be stacked to a safe level but other goods should not be stowed directly on top of them.

*Pallet* means a portable platform for stowing, handling, and moving cargo.

*Palletized unit* means packages or unpackaged objects stacked on a pallet, banded and secured to the pallet by metal, fabric, or plastic straps for the purpose of handling as a single unit.

*Pie plate* means a round, oval, or hexagonal pallet without sideboards, used in conjunction with a cargo net to handle loose cargo on board a vessel.

*Portable magazine* means a strong, closed, prefabricated, steel or wooden, closed box or container, other than a freight container, designed and used to handle Class 1 (explosive) materials either by hand or mechanical means.

*Readily combustible material* means a material which may or may not be classed as a hazardous material but which is easily ignited and supports combustion. Examples of readily combustible materials include wood, paper, straw, vegetable fibers, products made from such materials, coal, lubricants, and oils. This definition does not apply to packaging material or dunnage.

*Responsible person* means a person empowered by the master of the vessel to make all decisions relating to his or her specific task, and having the necessary knowledge and experience for that purpose.

*Safe working load* means the maximum gross weight that cargo handling equipment is approved to lift.

### 49 CFR Ch. I (10–1–08 Edition)

*Skilled person* means a person having the knowledge and experience to perform a certain duty.

*Skipboard* means a square or rectangular pallet without sideboards, usually used in conjunction with a cargo net to handle loose cargo on board a vessel.

*Splice* as used in § 176.172 of this part, means any repair of a freight container main structural member which replaces material, other than complete replacement of the member.

*Tray* means a type of pallet constructed to specific dimensions for handling a particular load.

[Amdt. 176–30, 55 FR 52687, Dec. 21, 1990, as amended at 66 FR 8647, Feb. 1, 2001; 66 FR 33438, June 21, 2001; 66 FR 45184, Aug. 28, 2001; 67 FR 61015, Sept. 27, 2002; 68 FR 75747, 75748, Dec. 31, 2003; 69 FR 76179, Dec. 20, 2004; 73 FR 57006, Oct. 1, 2008]

### § 176.3 Unacceptable hazardous materials shipments.

(a) A carrier may not transport by vessel any shipment of a hazardous material that is not prepared for transportation in accordance with parts 172 and 173 of this subchapter.

(b) A carrier may not transport by vessel any explosive or explosive composition described in § 173.54 of this subchapter.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–30, 55 FR 52688, Dec. 21, 1990]

### § 176.4 Port security and safety regulations.

(a) Each carrier, master, agent, and charterer of a vessel and all other persons engaged in handling hazardous materials on board vessels shall comply with the applicable provisions of 33 CFR parts 6, 109, 110, 125, 126, and 160.

(b) Division 1.1 and 1.2 (explosive) materials may only be loaded on and unloaded from a vessel at—

(1) A facility of particular hazard as defined in 33 CFR 126.05(b);

(2) An explosives anchorage listed in 33 CFR part 110; or

(3) A facility operated or controlled by the Department of Defense.

(c) With the concurrence of the COTP, Division 1.1 and 1.2 (explosive)

materials may be loaded on or unloaded from a vessel in any location acceptable to the COTP.

[Amdt. 176-30, 55 FR 52688, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

#### § 176.5 Application to vessels.

(a) Except as provided in paragraph (b) of this section, this subchapter applies to each domestic or foreign vessel when in the navigable waters of the United States, regardless of its character, tonnage, size, or service, and whether self-propelled or not, whether arriving or departing, underway, moored, anchored, aground, or while in dry dock.

(b) This subchapter does not apply to:

(1) A public vessel not engaged in commercial service;

(2) A vessel constructed or converted for the principal purpose of carrying flammable or combustible liquid cargo in bulk in its own tanks, when only carrying these liquid cargoes;

(3) A vessel of 15 gross tons or smaller when not engaged in carrying passengers for hire;

(4) A vessel used exclusively for pleasure;

(5) A vessel of 500 gross tons or smaller when engaged in fisheries;

(6) A tug or towing vessel, except when towing another vessel having Class 1 (explosive) materials, Class 3 (flammable liquids), or Division 2.1 (flammable gas) materials, in which case the owner/operator of the tug or towing vessel shall make such provisions to guard against and extinguish fire as the Coast Guard may prescribe;

(7) A cable vessel, dredge, elevator vessel, fireboat, icebreaker, pile driver, pilot boat, welding vessel, salvage vessel, or wrecking vessel; or

(8) A foreign vessel transiting the territorial sea of the United States without entering the internal waters of the United States, if all hazardous materials being carried on board are being carried in accordance with the requirements of the IMDG Code (IBR, see § 171.7 of this subchapter).

(c) [Reserved]

(d) Except for transportation in bulk packagings (as defined in § 171.8 of this subchapter), the bulk carriage of hazardous materials by water is governed

by 46 CFR chapter I, subchapters D, I, N and O.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1A, 41 FR 40687, Sept. 20, 1976; Amdt. 176-14, 47 FR 44471, Oct. 7, 1982; Amdt. 176-24, 51 FR 5974, Feb. 18, 1986; Amdt. 176-30, 55 FR 52688, Dec. 21, 1990; 56 FR 66281, Dec. 20, 1991; Amdt. 176-34, 58 FR 51533, Oct. 1, 1993; 66 FR 8647, Feb. 1, 2001; 68 FR 75747, Dec. 31, 2003]

#### § 176.7 Documentation for vessel personnel.

Each owner, operator, master, agent, person in charge, and charterer must ensure that vessel personnel required to have a license, certificate of registry, or merchant mariner's document by 46 CFR parts 10 and 12 possess a license, certificate or document, as appropriate.

[68 FR 23842, May 5, 2003]

#### § 176.9 "Order-Notify" or "C.O.D." shipments.

A carrier may not transport Division 1.1 or 1.2 (explosive) materials, detonators, or boosters with detonators which are:

(a) Consigned to "order-notify" or "C.O.D.", except on a through bill of lading to a place outside the United States; or

(b) Consigned by the shipper to himself unless he has a resident representative to receive the shipment at the port of discharge.

[Amdt. 176-30, 55 FR 52688, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

#### § 176.11 Exceptions.

(a) A hazardous material may be offered and accepted for transport by vessel when in conformance with the IMDG Code (IBR, see § 171.7 of this subchapter), subject to the conditions and limitations set forth in subpart C of part 171 of this subchapter. The requirements of §§ 176.83, 176.84, and 176.112 through 176.174 are not applicable to shipments of Class 1 (explosive) materials made in accordance with the IMDG Code. A hazardous material which conforms to the provisions of this paragraph (a) is not subject to the requirement specified in § 172.201(d) of this subchapter for an emergency response telephone number, when transportation of the hazardous material

### § 176.13

originates and terminates outside the United States and the hazardous material—

- (1) Is not offloaded from the vessel; or
- (2) Is offloaded between ocean vessels at a U.S. port facility without being transported by public highway.

(b) Canadian shipments and packages may be transported by vessel if they are transported in accordance with this subchapter. (See subparts B and C of part 171 of this subchapter.)

(c) The requirements of this subchapter governing the transportation of combustible liquids do not apply to the transportation of combustible liquids in non-bulk (see definitions in § 171.8 of this subchapter) packages on board vessels.

(d) Transport vehicles, containing hazardous materials loaded in accordance with specific requirements of this subchapter applicable to such vehicles, may be transported on board a ferry vessel or carfloat, subject to the applicable requirements specified in §§ 176.76, 176.100, and subpart E of this part.

(e) Hazardous materials classed and shipped as ORM-D are not subject to the requirements of this part unless they are offered for transportation as hazardous wastes.

(f) Paragraph (a) of this section does not apply to hazardous materials, including certain hazardous wastes and hazardous substances as defined in § 171.8 of this subchapter, which are not subject to the requirements of the IMDG Code.

(g) The requirements of this subchapter do not apply to atmospheric gases used in a refrigeration system.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 176.11, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 176.13 Responsibility for compliance and training.

(a) Unless this subchapter specifically provides that another person shall perform a particular duty, each carrier shall perform the duties specified and comply with all applicable requirements in this part and shall en-

### 49 CFR Ch. I (10–1–08 Edition)

sure its hazmat employees receive training in relation thereto.

(b) A carrier may not transport a hazardous material by vessel unless each of its hazmat employees involved in that transportation is trained as required by subpart H of part 172 of this subchapter.

(c) The record of training required by § 172.704(d) of this subchapter for a crewmember who is a hazmat employee subject to the training requirements of this subchapter must be kept on board the vessel while the crewmember is in service on board the vessel.

[Amdt. 176–31, 57 FR 20954, May 15, 1992, as amended by Amdt. 176–35, 59 FR 49134, Sept. 26, 1994]

### § 176.15 Enforcement.

(a) An enforcement officer of the U.S. Coast Guard may at any time and at any place, within the jurisdiction of the United States, board any vessel for the purpose of enforcement of this subchapter and inspect any shipment of hazardous materials as defined in this subchapter.

(b) [Reserved]

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–1A, 41 FR 40687, Sept. 20, 1976; Amdt. 176–24, 51 FR 5974, Feb. 18, 1986]

### § 176.18 Assignment and certification.

(a) The National Cargo Bureau, Inc., is authorized to assist the Coast Guard in administering this subchapter with respect to the following:

(1) Inspection of vessels for suitability for loading hazardous materials;

(2) Examination of stowage of hazardous materials;

(3) Making recommendations for stowage requirements of hazardous materials cargo; and

(4) Issuance of certificates of loading setting forth that the stowage of hazardous materials is in accordance with the requirements of this subchapter.

(b) A certificate of loading issued by the National Cargo Bureau, Inc., may be accepted by the Coast Guard as prima facie evidence that the cargo is

stowed in conformity with the requirements of this subchapter.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-24, 51 FR 5974, Feb. 18, 1986]

### Subpart B—General Operating Requirements

#### § 176.24 Shipping papers.

(a) A person may not accept a hazardous material for transportation or transport a hazardous material by vessel unless that person has received a shipping paper prepared in accordance with part 172 of this subchapter, or as authorized by subpart C of part 171 of this subchapter, unless the material is excepted from shipping paper requirements under this subchapter.

(b) Each person receiving a shipping paper required by this section must retain a copy or an electronic image thereof, that is accessible at or through its principal place of business and must make the shipping paper available, upon request, to an authorized official of a Federal, State, or local government agency at reasonable times and locations. For a hazardous waste, each shipping paper copy must be retained for three years after the material is accepted by the initial carrier. For all other hazardous materials, each shipping paper copy must be retained for one year after the material is accepted by the carrier. Each shipping paper copy must include the date of acceptance by the carrier. The date on the shipping paper may be the date a shipper presents a booking for carriage with the carrier as an alternative to the date the shipment is picked up, accepted, or loaded on the vessel by the carrier.

[67 FR 66574, Nov. 1, 2002, as amended at 70 FR 73165, Dec. 9, 2005; 72 FR 25177, May 3, 2007]

#### § 176.27 Certificate.

(a) A carrier may not transport a hazardous material by vessel unless a certificate prepared in accordance with § 172.204 of this subchapter has been received.

(b) In the case of an import or export shipment of a hazardous material that will not be transported by rail, high-

way, or air, the shipper may certify on the bill of lading or other shipping paper that the hazardous material is properly classed, described, marked, packaged, and labeled according to part 172 of this subchapter or in accordance with the requirements of the IMDG Code (IBR, *see* § 171.7 of this subchapter). See subpart C of part 171 of this subchapter.

(c)(1) A person responsible for packing or loading a freight container or transport vehicle with packages of hazardous materials for transportation by a manned vessel in ocean or coastwise service, must provide the vessel operator, at the time the shipment is offered for transportation by vessel, with a signed container packing certificate stating, at a minimum, that—

(i) The freight container or transport vehicle is serviceable for the materials loaded therein, contains no incompatible goods, and is properly marked, labeled or placarded, as applicable; and

(ii) When the freight container or transport vehicle contains packages, those packages have been inspected prior to loading, are properly marked, labeled or placarded, as applicable; are not damaged; and are properly secured.

(2) The certification may appear on a shipping paper or on a separate document as a statement, such as “It is declared that the packing of the container has been carried out in accordance with the applicable provisions [of 49 CFR], [of the IMDG Code], or [of 49 CFR and the IMDG Code].”

[69 FR 76180, Dec. 20, 2004; 72 FR 25177, May 3, 2007]

#### § 176.30 Dangerous cargo manifest.

(a) The carrier, its agents, and any person designated for this purpose by the carrier or agents shall prepare a dangerous cargo manifest, list, or stowage plan. This document may not include a material which is not subject to the requirements of 49 CFR or the IMDG Code (IBR, *see* § 171.7 of this subchapter). This document must be kept in a designated holder on or near the vessel's bridge. It must contain the following information:

(1) Name of vessel and official number. (If the vessel has no official number, the international radio call sign must be substituted.);

## § 176.31

## 49 CFR Ch. I (10–1–08 Edition)

(2) Nationality of vessel;

(3) Shipping name and identification number of each hazardous material on board as listed in §172.101 of this subchapter or as listed in the IMDG Code and an emergency response telephone number as prescribed in subpart G of part 172 of this subchapter.

(4) The number and description of packages (barrels, drums, cylinders, boxes, etc.) and gross weight for each type of packaging;

(5) Classification of the hazardous material in accordance with either:

(i) The Hazardous Materials Table, the §172.101 table; or

(ii) The IMDG Code.

(6) Any additional description required by §172.203 of this subchapter.

(7) Stowage location of the hazardous material on board the vessel.

(8) In the case of a vessel used for the storage of explosives or other hazardous materials, the following additional information is required:

(i) Name and address of vessel's owner;

(ii) Location of vessel's mooring;

(iii) Name of person in charge of vessel;

(iv) Name and address of the owner of the cargo; and

(v) A complete record, by time intervals of one week, of all receipts and disbursements of hazardous materials. The name and address of the consignor must be shown against all receipts and the name and address of the consignee against all deliveries.

(b) The hazardous material information on the dangerous cargo manifest must be the same as the information furnished by the shipper on the shipping order or other shipping paper, except that the IMO "correct technical name" and the IMO class may be indicated on the manifest as provided in paragraphs (a)(3) and (a)(5) of this section. The person who supervises the preparation of the manifest, list, or stowage plan shall ensure that the information is correctly transcribed, and shall certify to the truth and accuracy of this information to the best of his knowledge and belief by his signature and notation of the date prepared.

(c) The carrier and its agents shall insure that the master, or a licensed deck officer designated by the master

and attached to the vessel, or in the case of a barge, the person in charge of the barge, acknowledges the correctness of the dangerous cargo manifest, list or stowage plan by his signature.

(d) For barges, manned or unmanned, the requirements of this section apply except for the following:

(1) In the case of a manned barge, the person in charge of the barge shall prepare the dangerous cargo manifest.

(2) In the case of an unmanned barge, the person responsible for loading the barge is responsible for the preparation of a dangerous cargo manifest, list, or stowage plan and must designate an individual for that purpose.

(3) For all barges, manned or unmanned, the dangerous cargo manifest must be on board the barge in a readily accessible location and a copy must be furnished to the person in charge of the towing vessel.

(e) Each carrier who transports or stores hazardous materials on a vessel shall retain a copy of the dangerous cargo manifest, list, or stowage plan for at least one year, and shall make that document available for inspection in accordance with §176.36(b) of this subchapter.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §176.30, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### § 176.31 Special permits.

If a hazardous material is being transported by vessel under the authority of an exemption or special permit and a copy of the exemption or special permit is required to be on board the vessel, it must be kept with the dangerous cargo manifest.

[70 FR 73165, Dec. 9, 2005]

### § 176.36 Preservation of records.

(a) When this part requires shipping orders, manifest, cargo lists, stowage plans, reports, or any other papers, documents or similar records to be prepared, the carrier shall preserve them or copies of them in his place of business or office in the United States for a period of one year after their preparation.

(b) Any record required to be preserved must be made available upon request to an authorized representative of the Department.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended at 66 FR 45384, Aug. 28, 2001]

#### § 176.39 Inspection of cargo.

(a) *Manned vessels.* The carrier, its agents, and any person designated for this purpose by the carrier or agents shall cause an inspection of each hold or compartment containing hazardous materials to be made after stowage is complete, and at least once every 24 hours thereafter, weather permitting, in order to ensure that the cargo is in a safe condition and that no damage caused by shifting, spontaneous heating, leaking, sifting, wetting, or other cause has been sustained by the vessel or its cargo since loading and stowage. However, freight containers or individual barges need not be opened. A vessel's holds equipped with smoke or fire detecting systems having an automatic monitoring capability need not be inspected except after stowage is complete and after periods of heavy weather. The carrier, its agents, and any person designated for this purpose by the carrier or agents shall cause an entry to be made in the vessel's deck log book for each inspection of the stowage of hazardous materials performed.

(b) *Unmanned and magazine vessels.* An inspection of the cargo must be made after stowage has been completed to ensure that stowage has been accomplished properly and that there are no visible signs of damage to any packages or evidence of heating, leaking, or sifting. This inspection must be made by the individual who is responsible to the carrier and who is in charge of loading and stowing the cargo on the unmanned vessels or the individual in charge in the case of a magazine vessel.

(c) The carrier, its agents, and any person designated for this purpose by the carrier or agents of each ocean-going vessel carrying hazardous material shall, immediately prior to entering a port in the United States, cause an inspection of that cargo to be made.

(d) When inspecting a cargo of hazardous materials capable of evolving flammable vapors, any artificial means

of illumination must be of an explosion-proof type.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-8, 44 FR 23228, Apr. 19, 1979; Amdt. 176-9, 44 FR 49458, Aug. 23, 1979]

#### § 176.45 Emergency situations.

(a) When an accident occurs on board a vessel involving hazardous materials, and the safety of the vessel, its passengers or crew are endangered, the master shall adopt such procedures as will, in his judgment, provide maximum safety for the vessel, its passengers, and its crew. When the accident results in damaged packages or the emergency use of unauthorized packagings, these packages may not be offered to any forwarding carrier for transportation. The master shall notify the nearest Captain of the Port, U.S. Coast Guard, and request instructions for disposition of the packages.

(b) Hazardous materials may be jettisoned only if the master believes this action necessary to prevent or substantially reduce a hazard to human life or reduce a substantial hazard to property.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1B, 41 FR 57072, Dec. 30, 1976]

#### § 176.48 Situation requiring report.

(a) When a fire or other hazardous condition exists on a vessel transporting hazardous materials, the master shall notify the nearest Captain of the Port as soon as possible and shall comply with any instructions given by the Captain of the Port.

(b) When an incident occurs during transportation in which a hazardous material is involved, a report may be required (see §§171.15 and 171.16 of this subchapter).

(c) If a package, portable tank, freight container, highway or railroad vehicle containing hazardous materials is jettisoned or lost, the master shall notify the nearest Captain of the Port as soon as possible of the location, quantity, and type of the material.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1A, 41 FR 40687, Sept. 20, 1976; Amdt. 176-1B, 41 FR 57072, Dec. 30, 1976; Amdt. 176-24, 51 FR 5974, Feb. 18, 1986; Amdt. 176-25, 52 FR 8592, Mar. 19, 1987]



## **§ 176.50**

### **§ 176.50 Acceptance of damaged or leaking packages.**

A carrier may not transport by vessel any package that is so damaged as to permit the escape of its contents, that appears to have leaked, or that gives evidence of failure to properly contain the contents unless it is restored or repaired to the satisfaction of the master of the vessel. A package containing radioactive materials (other than low specific activity materials) may not be repaired or restored.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1A, 41 FR 40687, Sept. 20, 1976]

### **§ 176.52 Rejections of shipments in violation.**

(a) A carrier may not knowingly transport by vessel any hazardous material offered under a false or deceptive name, marking, invoice, shipping paper or other declaration, or without the shipper furnishing written information about the true nature of the material at the time of delivery.

(b) If a shipment in violation is found in transit, the master of the vessel shall adopt procedures which in his judgment provide maximum safety to the vessel, its passengers and its crew and which are in compliance with § 176.45. If the vessel is in port, the material may not be delivered to any party, and the master shall immediately notify the nearest Captain of the Port and request instructions for disposition of the material.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1B, 41 FR 57072, Dec. 30, 1976]

### **§ 176.54 Repairs involving welding, burning, and power-actuated tools and appliances.**

(a) Except as provided in paragraph (b) of this section, repairs or work involving welding or burning, or the use of power-actuated tools or appliances which may produce intense heat may not be undertaken on any vessel having on board explosives or other hazardous materials as cargo.

(b) Paragraph (a) of this section does not apply if:

(1) The repairs or work are approved by the COTP under 33 CFR 126.15(c); or

## **49 CFR Ch. I (10-1-08 Edition)**

(2) Emergency repairs to the vessel's main propelling or boiler plant or auxiliaries are necessary for the safety of the vessel. If such repairs are performed, the master of the vessel must immediately notify the nearest COTP.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-30, 55 FR 52689, Dec. 21, 1990]

## **Subpart C—General Handling and Stowage**

### **§ 176.57 Supervision of handling and stowage.**

(a) Hazardous materials may be handled or stowed on board a vessel only under the direction and observation of a responsible person assigned this duty.

(b) For a vessel engaged in coastwise voyages, or on rivers, bays, sounds or lakes, including the Great Lakes when the voyage is not foreign-going, the responsible person may be an employee of the carrier and assigned this duty by the carrier, or a licensed officer attached to the vessel and assigned by the master of the vessel.

(c) For a domestic vessel engaged in a foreign-going or intercoastal voyage, the responsible person must be an officer possessing an unexpired license issued by the USCG and assigned this duty by the master of the vessel.

(d) For a foreign vessel, the responsible person must be an officer of the vessel assigned this duty by the master of the vessel.

[Amdt. 176-30, 55 FR 52689, Dec. 21, 1990]

### **§ 176.58 Preparation of the vessel.**

(a) Each hold or compartment in which hazardous materials are to be stowed must be free of all debris before the hazardous materials are stowed. Bilges must be examined and all residue of previous cargo removed.

(b) All decks, gangways, hatches, and cargo ports over or through which hazardous materials must be passed or handled in loading or unloading must be free of all loose materials before cargo handling operations begin.

(c) No debris that creates a fire hazard or a hazardous condition for persons engaged in handling hazardous materials may be on the weather deck

of a vessel during loading or unloading operations.

(d) Hatch beams and hatch covers may not be stowed in a location that would interfere with cargo handling.

[Amdt. 176-30, 55 FR 52689, Dec. 21, 1990]

#### § 176.60 “No Smoking” signs.

When smoking is prohibited during the loading, stowing, storing, transportation, or unloading of hazardous materials by this part, the carrier and the master of the vessel are jointly responsible for posting “NO SMOKING” signs in conspicuous locations.

#### § 176.63 Stowage locations.

(a) The table in §172.101 of this subchapter specifies generally the locations authorized for stowage of the various hazardous materials on board vessels. This part prescribes additional requirements with respect to the stowage of specific hazardous materials in addition to those authorized in §172.101 of this subchapter. This section sets forth the basic physical requirements for the authorized locations.

(b) To qualify as “on deck” stowage, the location must be on the weather deck. If it is in a house on the weather deck, it must have a permanent structural opening to the atmosphere, such as a door, hatch, companionway or manhole, and must be vented to the atmosphere. It may not have any structural opening to any living quarters, cargo, or other compartment unless the opening has means for being closed off and secured. Any deck house containing living quarters, a steering engine, a refrigerating unit, a refrigerated stowage box, or a heating unit may not be used unless that area is isolated from the cargo stowage area by a permanent, and tight metallic bulkhead. Stowage in a shelter or ’tween deck is not considered to be “on deck”. A barge which is vented to the atmosphere and is stowed on deck on a barge-carrying ship is considered to be “on deck”. When an entry in §172.101 of this subchapter requires “on-deck” stowage and is qualified by the requirement “shade from radiant heat”, the stowage must be protected from the direct rays of the sun by means of structural erections or awnings except that such

protection is not required for shipment in portable tanks.

(c) To qualify as “under deck” stowage, the location must be in a hold or compartment below the weather deck capable of being ventilated and allotted entirely to the carriage of cargo. It must be bounded by permanent steel decks and bulkheads or the shell of the vessel. The deck openings must have means for effectively closing the hold or compartment against the weather, and in the case of superimposed holds, for effectively closing off each hold. A hold or compartment containing a crew passage formed by battens or by mesh or wire screen bulkhead may not be used for the stowage of any hazardous material unless a watchman is provided for this area.

(d) To qualify as “under deck away from heat”, the location must be under deck and have built-in means for ventilation. If it is subject to heat from any artificial source, it only qualifies for the stowage of those hazardous materials for which “under deck” stowage is authorized.

(e) *Closed cargo transport unit*, for the purpose of stowage of Class 1 (explosive) materials on board a vessel, means a unit which fully encloses the contents by permanent structures and can be secured to the ship’s structure, and includes a magazine. Cargo transport units with fabric sides or tops are not closed cargo transport units. Where this stowage is specified, stowage in small compartments such as deck-houses and mast lockers are acceptable alternatives. The floor of any closed cargo transport unit or compartment shall either be constructed of wood, close-boarded or so arranged that goods are stowed on sparred gratings, wooden pallets or dunnage. Provided that the necessary additional specifications are met, a closed cargo transport unit may be used for type “A” or “C” class 1 stowage or as a magazine.”

(f) *Stowage of containers on board hatchless container ships.* (1) Containers holding a hazardous material may be stowed in or vertically above a hatchless container hold if the following conditions are met:

## § 176.65

(1) All hazardous materials are permitted for *under deck* stowage as specified in the Table in §172.101 of this subchapter; and

(2) The hatchless container hold is in full compliance with the provisions of IMO's "International Convention for the Safety of Life at Sea (SOLAS)," Regulation II-2/19 of SOLAS 1974, as amended (incorporation by reference; see §171.7 of this subchapter), applicable to enclosed container cargo spaces, as appropriate for the cargo transported.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1A, 41 FR 40687, Sept. 20, 1976; Amdt. 176-1B, 41 FR 57072, Dec. 30, 1976; Amdt. 176-12, 45 FR 81572, Dec. 11, 1980; 66 FR 33438, June 21, 2001; 66 FR 45184, Aug. 28, 2001; 68 FR 45038, July 31, 2003; 69 FR 76180, Dec. 20, 2004]

### § 176.65 Alternative stowage procedures.

When a hazardous material is to be loaded on board a vessel and it is shown to the satisfaction of the Coast Guard Captain of the Port for the place where the vessel is being loaded that it is impracticable to comply with a stowage location requirement specified in the §172.101 table of this subchapter or a segregation, handling or stowage requirement specified in this part, the Captain of the Port may authorize in writing the use of an alternative stowage location or method of segregation, handling or stowage subject to such conditions as he finds will insure a level of safety at least equal to that afforded by the regulatory requirement concerned.

[Amdt. 176-30, 55 FR 52689, Dec. 21, 1990]

### § 176.69 General stowage requirements for hazardous materials.

(a) Hazardous materials (except as provided in paragraph (c) of this section and Class 9 (miscellaneous hazardous) materials) must be stowed in a manner that will facilitate inspection during the voyage, their removal from a potentially dangerous situation, and the removal of packages in case of fire.

(b) Each package marked in accordance with §172.312(a)(2) of this subchapter must be stowed as to remain in the position indicated during transportation.

## 49 CFR Ch. I (10-1-08 Edition)

(c) If a vessel designed for and carrying hazardous materials in freight containers or a vessel designed for and carrying hazardous materials in barges is equipped with a fixed fire extinguishing and fire detection system, the freight containers or barges need not be stowed in the manner required by paragraph (a) of this section. When freight containers or barges containing hazardous materials are stowed on deck, they need not be stowed in the manner required by paragraph (a) of this section if fire fighting equipment capable of reaching and piercing the freight container or barge is on board the vessel.

(d) Packages of hazardous materials must be secured and dunnaged to prevent shifting in any direction. Vertical restraints are not required if the shape of the package and the stuffing pattern preclude shifting of the load.

(e) Packages of hazardous materials must be braced and dunnaged so that they are not likely to be pierced by the dunnage or crushed by a superimposed load.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1A, 41 FR 40687, Sept. 20, 1976; Amdt. 176-12, 45 FR 81573, Dec. 11, 1980; Amdt. 176-30, 55 FR 52689, Dec. 21, 1990; 56 FR 66282, Dec. 20, 1991; 68 FR 61942, Oct. 30, 2003]

### § 176.70 Stowage requirements for marine pollutants.

(a) Marine pollutants must be properly stowed and secured to minimize the hazards to the marine environment without impairing the safety of the ship and the persons on board.

(b) Where stowage is permitted "on deck or under deck", under deck stowage is preferred except when a weather deck provides equivalent protection.

(c) Where stowage "on deck only" is required, preference should be given to stowage on well-protected decks or to stowage inboard in sheltered areas of exposed decks.

[Amdt. 176-31, 57 FR 52940, Nov. 5, 1992]

### § 176.72 Handling of break-bulk hazardous materials.

(a) A metal bale hook may not be used for handling any package of hazardous materials.

(b) The use of equipment designed to lift or move cargo by means of pressure exerted on the packages may not be used for handling any package of hazardous materials if the device can damage the package or the package is not designed to be moved in that manner.

(c) Pallets, slings, cargo nets and other related equipment used in loading packages of hazardous materials must give adequate support to the packages. The packages must be contained so that they are not able to fall during loading.

**§ 176.74 On deck stowage of break-bulk hazardous materials.**

(a) Packages containing hazardous materials must be secured by enclosing in boxes, cribs or cradles and proper lashing by use of wire rope, strapping or other means, including shoring and bracing, or both. Lashing of deck cargo is permitted if eye pads are used to attach the lashings. Lashings may not be secured to guard rails. Bulky articles must be shored.

(b) A packaging susceptible to weather or water damage must be protected so that it will not be exposed to the weather or to sea water.

(c) Not more than fifty percent of the total open deck area should be used for stowage of hazardous materials (except Class 9 (miscellaneous hazardous material)).

(d) Fireplugs, hoses, sounding pipes, and access to these must be free and clear of all cargo.

(e) Crew and passenger spaces and areas set aside for the crew's use may not be used to stow any hazardous material.

(f) A hazardous material may not be stowed within a horizontal distance of 25 feet of an operating or embarkation point of a lifeboat.

(g) Hazardous materials must be stowed to permit safe access to the crew's quarters and to all parts of the deck required in navigation and necessary working of the vessel.

(h) When runways for use of the crew are built over stowed hazardous materials, they must be constructed and fitted with rails and lifelines so as to

afford complete protection to the crew when in use.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-1B, 41 FR 57072, Dec. 30, 1976; Amdt. 176-30, 55 FR 52689, Dec. 21, 1990; 56 FR 66282, Dec. 20, 1991; 66 FR 45181, Aug. 28, 2001]

**§ 176.76 Transport vehicles, freight containers, and portable tanks containing hazardous materials.**

(a) Except as provided in paragraphs (b) through (f) of this section, hazardous materials authorized to be transported by vessel may be carried on board a vessel in a transport vehicle or freight container, subject to the following conditions (see additional requirements concerning the transport of Class 1 (explosive) materials in §§176.168 through 176.172 of this subchapter):

(1) The material must be in proper condition for transportation according to the requirements of this subchapter;

(2) All packages in the transport vehicle or freight container must be secured to prevent shifting in any direction. Vertical restraint is not required if the shape of the packages, loading pattern, and horizontal restraint preclude vertical shifting of the load within the freight container or transport vehicle;

(3) Bulkheads made of dunnage which extend to the level of the cargo must be provided unless the packages are stowed flush with the sides or ends;

(4) Dunnage must be secured to the floor when the cargo consists of dense materials or heavy packages;

(5) Each package marked in accordance with §172.312(a)(2) of this subchapter must be stowed as marked;

(6) Any slack spaces between packages must be filled with dunnage;

(7) The weight in a container must be distributed throughout as evenly as possible and the maximum permissible weight must not be exceeded;

(8) Adjacent levels of bagged and baled cargo must be stowed in alternate directions so that each tier binds the tier above and below it;

(9) [Reserved]

(10) The lading must be contained entirely within the freight container or

vehicle body without overhang or projection except that oversized machinery such as tractors or vehicles with batteries attached may overhang or project outside the intermodal container provided all of that portion of the lading that consists of hazardous materials is contained entirely within the freight container. No open-bed container or vehicle is permitted to carry hazardous materials unless it is equipped with a means of properly securing the lading.

(b) A transport vehicle containing hazardous materials may be carried only on board a trailership, trainship, ferry vessel or car float.

(c) [Reserved]

(d) A transport vehicle or freight container equipped with heating or refrigeration equipment may be operated on board a vessel. However, the equipment may not be operated in any hold or compartment in which any flammable liquid or gas is stowed. Any heating or air conditioning equipment having a fuel tank containing a flammable liquid or gas may be stowed only “on deck”. Equipment electrically powered and designed to operate within an environment containing flammable vapors may be operated below deck in a hold or compartment containing a flammable liquid or gas.

(e) A transport vehicle, loaded with any hazardous material which is required to be stowed “on deck” by § 172.101 of this subchapter, may be stowed one deck below the weather deck when transported on a trainship or trailership which is unable to provide “on deck” stowage because of the vessel’s design. Otherwise, the transport vehicle or container must be transported “on deck.”

(f) A hazardous material may be carried on board a vessel in a portable tank subject to the following conditions:

(1) Small passenger vessels of 100 gross tons, or less, may carry a hazardous material in a portable tank only when 16 or less passengers are on board and only when specifically authorized by the Officer-in-Charge, Marine Inspection, by endorsement of the vessel’s Certificate of Inspection.

(2) Portable tanks containing flammable liquids or gases, combustible liq-

uids with flashpoints below 60 °C (140 °F), that are insoluble in water, or organic peroxides, spontaneously combustible materials, or water reactive materials must be stowed on deck irrespective of the stowage authorized in § 172.101 of this subchapter. Portable tanks containing hazardous materials not restricted to on deck stowage by the previous sentence must be stowed in accordance with the requirements specified in § 172.101 of this subchapter.

(3) Aluminum, magnesium, and their alloys are specifically prohibited as materials of construction of portable tanks.

(g) *Cryogenic liquids*. For shipment of cryogenic liquids on board a vessel the packaging must be designed and filled so that:

(1) Any cryogenic liquid being transported in a cargo tank, regardless of the pressure in the package, must be contained in a steel jacketed Specification MC-338 (§ 178.338 of this subchapter) insulated cargo tank.

(2) Any valve or fitting with moving or abrading parts that may come in contact with any cryogenic liquid may not be made of aluminum.

(3) For a flammable cryogenic liquid being transported in a cargo tank, the elapsed time between the loading of the cargo tank and the subsequent unloading of the cargo tank at its final destination may not exceed the marked rated holding time (MRHT) of the cargo tank for the cryogenic liquid being transported, which must be displayed on or adjacent to the specification plate.

(4) Portable tanks, cargo tanks, and tank cars containing cryogenic liquids must be stowed “on deck” regardless of the stowage authorized in § 172.101 of this subchapter. Cargo tanks or tank cars containing cryogenic liquids may be stowed one deck below the weather deck when transported on a trailership or trainship that is unable to provide “on deck” stowage because of the vessel’s design. Tank cars must be Class DOT-113 or AAR-204W tank cars.

(h) A fumigated cargo transport unit may only be transported on board a vessel subject to the following conditions and limitations:

(1) The fumigated cargo transport unit may be placed on board a vessel

only if at least 24 hours have elapsed since the unit was last fumigated;

(2) The fumigated cargo transport unit is accompanied by a document showing the date of fumigation and the type and amount of fumigant used;

(3) Prior to loading, the master is informed of the intended placement of the fumigated cargo transport unit on board the vessel and the information provided on the accompanying document;

(4) Equipment that is capable of detecting the fumigant and instructions for the equipment's use is provided on the vessel;

(5) The fumigated cargo transport unit must be stowed at least 5 m from any opening to accommodation spaces;

(6) Fumigated cargo transport units may only be transported on deck on vessels carrying more than 25 passengers; and

(7) Fumigants may not be added to cargo transport units while on board a vessel.

(i) A cargo transport unit packed or loaded with flammable gas or flammable liquid having a flashpoint below +23 °C transported on deck must be stowed "away from" possible sources of ignition. In the case of container ships, a distance equivalent to one container space athwartships away from possible sources of ignition applied in any direction will satisfy this requirement.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 176.76, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 176.77 Stowage of barges containing hazardous materials on board barge-carrying vessels.**

(a) A barge which contains hazardous materials may be transported on board a barge-carrying vessel if it is stowed in accordance with the requirements of this section.

(b) A barge which contains hazardous materials for which only "on deck" stowage is authorized must be stowed above the weather deck and be vented to the atmosphere.

(c) A barge which contains hazardous materials for which both "on deck" and "below deck" storage is authorized

may be stowed above or below the weather deck.

**§ 176.78 Use of power-operated industrial trucks on board vessels.**

(a) *Power Operated trucks.* A power-operated truck (including a power-operated tractor, forklift, or other specialized truck used for cargo handling) may not be used on board a vessel in a space containing a hazardous material unless the truck conforms to the requirements of this section. The COTP may suspend or prohibit the use of cargo handling vehicles or equipment when that use constitutes a safety hazard.

(b) Each truck must have a specific designation of Underwriter's Laboratories or Factory Mutual Laboratories. Any repair or alteration to a truck must be equivalent to that required on the original designation.

(c) *Description of designations.* The recognized testing laboratory type designations are as follows:

(1) An "E" designated unit is an electrically-powered unit that has minimum acceptable safeguards against inherent fire hazards.

(2) An "EE" designated unit is an electrically-powered unit that has, in addition to all the requirements for the "E" unit, the electric motor and all other electrical equipment completely enclosed.

(3) An "EX" designated unit is an electrically-powered unit that differs from the "E" and "EE" unit in that the electrical fittings and equipment are so designed, constructed, and assembled that the unit may be used in certain atmospheres containing flammable vapors or dusts.

(4) A "G" designated unit is a gasoline-powered unit having minimum acceptable safeguards against inherent fire hazards.

(5) A "GS" designated unit is a gasoline-powered unit that is provided with additional safeguards to the exhaust, fuel, and electrical systems.

(6) An "LP" designated unit is similar to a "G" unit except that it is powered by liquefied petroleum gas instead of gasoline.

(7) An "LPS" designated unit is a unit similar to a "GS" unit except that

liquefied petroleum gas is used for fuel instead of gasoline.

(8) A “D” designated unit is a unit similar to a “G” unit except that it is powered by a diesel engine instead of a gasoline engine.

(9) A “DS” designated unit is a unit powered by a diesel engine provided with additional safeguards to the exhaust, fuel, and electrical systems.

(d) *Class 1 (explosive) materials.* No power-operated truck may be used to handle Class 1 (explosive) materials or other cargo in an area near Class 1 (explosive) materials on board a vessel except:

(1) A power-operated truck designated EE or EX.

(2) A power-operated truck designated LPS, GS, D, or DS may be used under conditions acceptable to the COTP.

(e) *Other hazardous materials.* (1) Only an “EX”, “EE”, “GS”, “LPA”, or “DS” truck may be used in a hold or compartment containing Division 2.1 (flammable gas) materials, Class 3 (flammable liquids), Class 4 (flammable solids) materials, or Class 5 (oxidizers or organic peroxides) materials, cottons or other vegetable fibers, or bulk sulfur.

(2) Only a designated truck may be used to handle any other hazardous material not covered in paragraph (d) or (e)(1) of this section.

(f) *Minimum safety features.* In addition to the construction and design safety features required, each truck must have at least the following minimum safety features:

(1) The truck must be equipped with a warning horn, whistle, gong, or other device that may be heard clearly above normal shipboard noises.

(2) When the truck operation may expose the operator to danger from a falling object, the truck must be equipped with a driver’s overhead guard. When the overall height of the truck with forks in the lowered position is limited by head room the overhead guard may be omitted. This overhead guard is only intended to offer protection from impact of small packages, boxes, bagged material, or similar hazards.

(3) A forklift truck used to handle small objects or unstable loads must be equipped with a load backrest exten-

sion having height, width, and strength sufficient to prevent any load, or part of it, from falling toward the mast when the mast is in a position of maximum backward tilt. The load backrest extension must be constructed in a manner that does not interfere with good visibility.

(4) The forks on a fork lift truck must be secured to the carriage so as to prevent any unintentional lifting of the toe which could create a hazard. The forks may not display permanent deformation when subjected to a test load of three times the rated capacity.

(5) Each fork extension or other attachment must be secured to prevent unintentional lifting or displacement on primary forks.

(6) Tires extending beyond the confines of the truck shall be provided with a guard to prevent the tires from throwing particles at the operator.

(7) Unless the steering mechanism is a type that prevents road reactions from causing the steering handwheel to spin, a mushroom type steering knob must be used to engage the palm of the operator’s hand, or the steering mechanism must be arranged in some other manner to prevent injury. The knob must be mounted within the perimeter of the wheel.

(8) All steering controls must be confined within the clearnace of the truck or guarded so that moving of the controls will not result in injury to the operator when passing stanchions, obstructions or other.

(g) *Special operating conditions.* (1) A truck may not be used on board a vessel unless prior notification of its use is given to the master or senior deck officer on board.

(2) Before a truck is operated on board a vessel, it must be in a safe operating condition as determined by the master or senior deck officer on board.

(3) Any truck that emits sparks or flames from the exhaust system must immediately be removed from service and may not be returned to service until the cause of these sparks or flames has been eliminated.

(4)–(5) [Reserved]

(6) All truck motors must be shut off immediately when a breakage or leakage of packages containing flammable liquids or gases, flammable solids,

oxidizers, or organic peroxides occurs or is discovered.

(7) The rated capacity of the truck must be posted on the truck at all times in a conspicuous place. This capacity may not be exceeded.

(8) At least one Coast Guard approved marine type size 1 Type B, or UL approved 5BC portable fire extinguisher, or its approved equivalent, must be affixed to the truck in a readily accessible position or must be kept in close proximity, available for immediate use.

(9) The vessel's fire fighting equipment, both fixed (where installed) and portable, must be kept ready for immediate use in the vicinity of the space being worked.

(h) *Refueling.* (1) A truck using gasoline as fuel may not be refueled in the hold or on the weather deck of a vessel unless a portable non-spilling fuel handling system of not over five gallons capacity is used. Gasoline may not be transferred to a portable non-spilling fuel handling device on board the vessel.

(2) A truck using liquefied petroleum gas as fuel may not be refueled in the hold or on the weather deck of a vessel unless it is fitted with a removable tank and the hand-operated shutoff valve of the depleted tank is closed. In addition, the motor must be run until it stalls from lack of fuel and then the hand-operated shut off valve closed before the quick disconnect fitting to the fuel tank is disconnected.

(3) A truck using diesel oil as fuel may not be refueled on the weather deck or in the hold of a vessel unless a portable container of not over a five gallon capacity is used. A truck may be refueled or a portable container may be refilled from a larger container of diesel fuel on the weather deck of a vessel if a suitable pump is used for the transfer operation and a drip pan of adequate size is used to prevent any dripping of fuel on the deck.

(4) Refueling must be performed under the direct supervision of an experienced and responsible person specifically designated for this duty by the person in charge of the loading or unloading of the vessel.

(5) Refueling may not be undertaken with less than two persons specifically

assigned and present for the complete operation, at least one of whom must be experienced in using the portable fire extinguishers required in the fuel area.

(6) At least one Coast Guard approved marine type size 1 Type B or UL approved 5BC portable fire extinguisher or its approved equivalent, must be provided in the fueling area. This is in addition to the extinguisher required by paragraph (g)(8) of this section.

(7) The location for refueling trucks must be designated by the master or senior deck officer on board the vessel. "NO SMOKING" signs must be conspicuously posted in the area.

(8) The location designated for refueling must be adequately ventilated to insure against accumulation of any hazardous concentration of vapors.

(9) Before any truck in a hold is refueled or before any fuel handling device or unmounted liquefied petroleum gas cylinder is placed in a hold, the motors of all trucks in the same hold must be stopped.

(10) All fuel handling devices and unmounted liquefied petroleum gas containers must be removed from a hold before any truck motor is started and the trucks are placed in operation in that hold.

(i) *Replacing batteries.* Batteries for electrically powered trucks and for the ignition systems of internal combustion powered trucks may be changed in the hold of a vessel subject to the following conditions:

(1) Only suitable handling equipment may be employed.

(2) Adequate precautions must be taken to avoid damage to the battery, short circuiting of the battery, and spillage of the electrolyte.

(j) *Charging of batteries.* Batteries of industrial trucks may be recharged in a hold of a vessel subject to the following conditions:

(1) The batteries must be housed in a suitable, ventilated, portable metal container with a suitable outlet at the top for connection of a portable air hose, or must be placed directly beneath a suitable outlet at the top for connection of a portable air hose. The air hose must be permanently connected to an exhaust duct leading to the open deck and terminate in a



## § 176.80

gooseneck or other suitable weather head. If natural ventilation is not practicable or adequate, mechanical means of exhaust must be employed in conjunction with the duct. The air outlet on the battery container must be equipped with an interlock switch so arranged that the charging of the battery cannot take place unless the air hose is properly connected to the box.

(2) If mechanical ventilation is used, an additional interlock must be provided between the fan and the charging circuit so that the fan must be in operation in order to complete the charging circuit for operation. It is preferable that this interlock switch be of a centrifugal type driven by the fan shaft.

(3) The hold may not contain any hazardous materials.

(4) The charging facilities may be part of the truck equipment or may be separate from the truck and located inside or outside the cargo hold. The power supply or charging circuit (whichever method is used) must be connected to the truck by a portable plug connection of the break-away type. This portable plug must be so engaged with the truck battery charging outlet that any movement of the truck away from the charging station will break the connection between the plug and receptacle without exposing any live parts to contact with a conducting surface or object and without the plug falling to the deck where it may become subject to damage.

(5) All unmounted batteries must be suitably protected or removed from an area in the hold of the vessel before any truck is operated in that area.

(k) *Stowage of power-operated industrial trucks on board a vessel.* Trucks stowed on board a vessel must meet vessel stowage requirements in § 176.905.

(l) *Packaging and stowage of fuel on board a vessel.* Division 2.1 (flammable gas) materials and flammable liquids used as fuel for industrial trucks must be packaged and stowed as authorized

## 49 CFR Ch. I (10–1–08 Edition)

in 46 CFR 147.60 or 46 CFR 147.45, respectively.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–1A, 41 FR 40687, Sept. 20, 1976; Amdt. 176–30, 55 FR 52689, Dec. 21, 1990; Amdt. 176–39, 61 FR 18933, Apr. 29, 1996; Amdt. 176–43, 62 FR 24741, May 6, 1997; 65 FR 58630, Sept. 29, 2000; 68 FR 61942, Oct. 30, 2003]

### Subpart D—General Segregation Requirements

#### § 176.80 Applicability.

(a) This subpart sets forth segregation requirements in addition to any segregation requirements set forth elsewhere in this subchapter.

(b) Hazardous materials in limited quantities when loaded in transport vehicles and freight containers, are excepted from the segregation requirements of this subpart and any additional segregation specified in this subchapter for transportation by vessel.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–3, 42 FR 57967, Nov. 7, 1977]

#### § 176.83 Segregation.

(a) *General.* (1) The requirements of this section apply to all cargo spaces on deck or under deck of all types of vessels, and to all cargo transport units.

(2) Segregation is obtained by maintaining certain distances between incompatible hazardous materials or by requiring the presence of one or more steel bulkheads or decks between them or a combination thereof. Intervening spaces between such hazardous materials may be filled with other cargo which is not incompatible with the hazardous materials.

(3) The general requirements for segregation between the various classes of dangerous goods are shown in the segregation table. In addition to these general requirements, there may be a need to segregate a particular material from other materials which would contribute to its hazard. Such segregation requirements are indicated by code numbers in Column 10B of the § 172.101 Table.

(4) Segregation is not required:

(i) Between hazardous materials of different classes which comprise the same substance but vary only in their

water content (for example, sodium sulfide in Division 4.2 or Class 8) or quantity for Class 7 materials; or

(ii) Between hazardous materials of different classes which comprise a group of substances that do not react dangerously with each other. The following materials are grouped by compatibility:

(A) Hydrogen peroxide, aqueous solutions with not less than 8 percent but less than 20 percent hydrogen peroxide (stabilized as necessary); Hydrogen peroxide, aqueous solutions with not less than 20 percent but not more than 40 percent hydrogen peroxide; Hydrogen peroxide, aqueous solutions with more than 40 percent but not more than 60 percent hydrogen peroxide; Hydrogen peroxide and peroxyacetic acid mixtures, stabilized with acids, water and not more than 5 percent peroxyacetic acid; Organic peroxide type D, liquid; Organic peroxide type E, liquid; Organic peroxide type F, liquid; and

(B) Dichlorosilane, Silicon tetrachloride, and Trichlorosilane.

(5) Whenever hazardous materials are stowed together, whether or not in a cargo transport unit, the segregation of such hazardous materials from others must always be in accordance with the most restrictive requirements for any of the hazardous materials concerned.

(6) When the § 172.101 Table or § 172.402 requires packages to bear a subsidiary hazard label or labels, the segregation appropriate to the subsidiary hazards must be applied when that segregation is more restrictive than that required by the primary hazard. For the purposes of this paragraph, the segregation requirements corresponding to an explosive subsidiary hazard are—except for organic peroxides which are those corresponding to Division 1.3—those for Division 1.4 (explosive) materials.

(7) Where, for the purposes of segregation, terms such as “away from” a particular hazard class are used in the § 172.101 Table, the segregation requirement applies to:

(i) All hazardous materials within the hazard class; and

(ii) All hazardous materials for which a secondary hazard label of that class is required.

(8) Notwithstanding the requirements of paragraphs (a)(6) and (a)(7) of this section, hazardous materials of the same class may be stowed together without regard to segregation required by secondary hazards (subsidiary risk label(s)), provided the substances do not react dangerously with each other and cause:

(i) Combustion and/or evolution of considerable heat;

(ii) Evolution of flammable, toxic or asphyxiant gases;

(iii) The formation of corrosive substances; or

(iv) The formation of unstable substances.

(9) Stowage in a shelter-'tween deck cargo space is not considered to be “on deck” stowage.

(10) Where the code in column (10B) of the § 172.101 Table specifies that “Segregation as for. . .” applies, the segregation requirements applicable to that class in the § 176.83(b) General Segregation Table must be applied. However, for the purposes of paragraph (a)(8) of this section, which permits substances of the same class to be stowed together provided they do not react dangerously with each other, the segregation requirements of the class as represented by the primary hazard class in the § 172.101 Table entry must be applied.

(11) Certain exceptions from segregation for waste cyanides or waste cyanide mixtures or solutions transported with acids and waste Division 4.2 materials transported with Class 8 liquids are set forth in § 173.12(e) of this subchapter.

(b) *General Segregation Table.* The following table sets forth the general requirements for segregation between the various classes (divisions) of hazardous materials. Certain divisions are listed as separate hazard classes for the purpose of this table (e.g., “2.1” and “2.2”). The properties of materials within each class may vary greatly and may require greater segregation than is reflected in this table. If the § 172.101 Table sets forth particular requirements for segregation, they take precedence over these general requirements.

TABLE 176.83(b)—GENERAL SEGREGATION REQUIREMENTS FOR HAZARDOUS MATERIALS  
[Segregation must also take account of a single secondary hazard label, as required by paragraph (a)(6) of this section.]

| Class                                             | 1.1<br>1.2<br>1.5 | 1.3 | 1.4<br>1.6 | 2.1 | 2.2 | 2.3 | 3 | 4.1 | 4.2 | 4.3 | 5.1 | 5.2 | 6.1 | 6.2 | 7 | 8 | 9 |
|---------------------------------------------------|-------------------|-----|------------|-----|-----|-----|---|-----|-----|-----|-----|-----|-----|-----|---|---|---|
| Explosives, 1.1, 1.2, 1.5 .....                   | (*)               | (*) | (*)        | 4   | 2   | 2   | 4 | 4   | 4   | 4   | 4   | 4   | 2   | 4   | 2 | 4 | X |
| Explosives, 1.3 .....                             | (*)               | (*) | (*)        | 4   | 2   | 2   | 4 | 3   | 3   | 4   | 4   | 4   | 2   | 4   | 2 | 2 | X |
| Explosives, 1.4, 1.6 .....                        | (*)               | (*) | (*)        | 2   | 1   | 1   | 2 | 2   | 2   | 2   | 2   | 2   | X   | 4   | 2 | 2 | X |
| Flammable gases 2.1 .....                         | 4                 | 4   | 2          | X   | X   | X   | 2 | 1   | 2   | X   | 2   | 2   | X   | 4   | 2 | 1 | X |
| Non-toxic, non-flammable gases 2.2 .....          | 2                 | 2   | 1          | X   | X   | X   | 1 | X   | 1   | X   | X   | 1   | X   | 2   | 1 | X | X |
| Poisonous gases 2.3 .....                         | 2                 | 2   | 1          | X   | X   | X   | 2 | X   | 2   | X   | X   | 2   | X   | 2   | 1 | X | X |
| Flammable liquids 3 .....                         | 4                 | 4   | 2          | 2   | 1   | 2   | X | X   | 2   | 1   | 2   | 2   | X   | 3   | 2 | X | X |
| Flammable solids 4.1 .....                        | 4                 | 3   | 2          | 1   | X   | X   | X | X   | 1   | X   | 1   | 2   | X   | 3   | 2 | 1 | X |
| Spontaneously combustible substances 4.2 .....    | 4                 | 3   | 2          | 2   | 1   | 2   | 2 | 1   | X   | 1   | 2   | 2   | 1   | 3   | 2 | 1 | X |
| Substances which are dangerous when wet 4.3 ..... | 4                 | 4   | 2          | X   | X   | X   | 1 | X   | 1   | X   | 2   | 2   | X   | 2   | 2 | 1 | X |
| Oxidizing substances 5.1 .....                    | 4                 | 4   | 2          | 2   | X   | X   | 2 | 1   | 2   | 2   | X   | 2   | 1   | 3   | 1 | 2 | X |
| Organic peroxides 5.2 .....                       | 4                 | 4   | 2          | 2   | 1   | 2   | 2 | 2   | 2   | 2   | 2   | X   | 1   | 3   | 2 | 2 | X |
| Poisons 6.1 .....                                 | 2                 | 2   | X          | X   | X   | X   | X | X   | 1   | X   | 1   | 1   | X   | 1   | X | X | X |
| Infectious substances 6.2 .....                   | 4                 | 4   | 4          | 4   | 2   | 2   | 3 | 3   | 3   | 2   | 3   | 3   | 1   | X   | 3 | 3 | X |
| Radioactive materials 7 .....                     | 2                 | 2   | 2          | 2   | 1   | 1   | 2 | 2   | 2   | 2   | 1   | 2   | X   | 3   | X | 2 | X |
| Corrosives 8 .....                                | 4                 | 2   | 2          | 1   | X   | X   | X | 1   | 1   | 1   | 2   | 2   | X   | 3   | 2 | X | X |
| Miscellaneous dangerous substances 9 .....        | X                 | X   | X          | X   | X   | X   | X | X   | X   | X   | X   | X   | X   | X   | X | X | X |

Numbers and symbols relate to the following terms as defined in this section:

1—"Away from."

2—"Separated from."

3—"Separated by a complete compartment or hold from."

4—"Separated longitudinally by an intervening complete compartment or hold from."

X—The segregation, if any, is shown in the § 172.101 table.


\*—See § 176.144 of this part for segregation within Class 1.

(c) *Segregation requirements for breakbulk cargo.* (1) The requirements of this paragraph apply to the segregation of packages containing hazardous materials and stowed as breakbulk cargo;


(2) Definition of the segregation terms:

(i) Legend:

(A) Package containing incompatible goods.



(B) Reference package.




(C) Deck resistant to fire and liquid.




NOTE: Full vertical lines represent transverse bulkheads between compartments or holds resistant to fire and liquid.

(ii) "Away from": Effectively segregated so that the incompatible materials cannot interact dangerously in the event of an accident but may be carried in the same compartment or hold or on deck provided a minimum horizontal separation of 3 m (10 feet) projected vertically is obtained.




(iii) "Separated From": In different compartments or holds when stowed under deck. If the intervening deck is

resistant to fire and liquid, a vertical separation (i.e., in different compartments) is acceptable as equivalent to this segregation. For "on deck" stowage, this segregation means a separation by a distance of at least 6 m (20 feet) horizontally.



(iv) "Separated by a complete compartment or hold from": Either a vertical or horizontal separation. If the intervening decks are not resistant to fire and liquid, then only a longitudinal separation (i.e., by an intervening complete compartment or hold) is acceptable. For "on deck" stowage, this segregation means a separation by a distance of at least 12 m (39 feet) horizontally. The same distance must be applied if one package is stowed "on deck", and the other one in an upper compartment.




# § 176.83

# 49 CFR Ch. I (10–1–08 Edition)

NOTE: One of the two decks must be resistant to fire and liquid.

(v) “Separated longitudinally by an intervening complete compartment or hold from”: Vertical separation alone does not meet this requirement. Between a package “under deck” and one “on deck” a minimum distance of 24 m (79 feet) including a complete compartment must be maintained longitudinally. For “on deck” stowage, this segregation means a separation by a distance of at least 24 m (79 feet) longitudinally.



(d) *Segregation in cargo transport units:* Two hazardous materials for which any segregation is required may not be stowed in the same cargo transport unit.

(e) *Segregation of hazardous materials stowed as breakbulk cargo from those packed in cargo transport units:* (1) Hazardous materials stowed as breakbulk cargo must be segregated from materials packed in open cargo transport

units in accordance with paragraph (c) of this section.

(2) Hazardous materials stowed as breakbulk cargo must be segregated from materials packed in closed cargo transport units in accordance with paragraph (c) of this section, except that:

(i) Where “away from” is required, no segregation between packages and the closed cargo transport units is required; and

(ii) Where “separated from” is required, the segregation between the packages and the closed cargo transport units may be the same as for “away from”.

(f) *Segregation of cargo transport units on board container vessels:* (1) Except for hatchless container ships, this paragraph applies to segregation of cargo transport units that are carried on board container vessels, or on other types of vessels, provided these cargo spaces are properly fitted for permanent stowage of containers during transport.

(2) For container vessels which have cargo spaces used for breakbulk cargo or any other method of stowage, the appropriate paragraph of this section applies to the relevant cargo space.

(3) *Segregation Table.* Table §176.83(f) sets forth the general requirements for segregation between cargo transport units on board container vessels.

(4) In table §176.83(f), a *container space* means a distance of not less than 6 m (20 feet) fore and aft or not less than 2.5 m (8 feet) athwartship.

TABLE 176.83(f)—SEGREGATION OF CONTAINERS ON BOARD CONTAINER SHIPS

| Segregation requirement                                                            | Vertical                                                   |                                    |                                                            | Horizontal       |                        |                                          |                        |                                       |                         |                                       |
|------------------------------------------------------------------------------------|------------------------------------------------------------|------------------------------------|------------------------------------------------------------|------------------|------------------------|------------------------------------------|------------------------|---------------------------------------|-------------------------|---------------------------------------|
|                                                                                    | Closed versus closed                                       | Closed versus open                 | Open versus open                                           |                  | Closed versus closed   |                                          | Closed versus open     |                                       | Open versus open        |                                       |
|                                                                                    |                                                            |                                    |                                                            |                  | On deck                | Under deck                               | On deck                | Under deck                            | On deck                 | Under deck                            |
| 1. "Away from"                                                                     | One on top of the other permitted.                         | Open on top of closed permitted.   | Not in the same vertical line unless segregated by a deck. | Fore and aft ... | No restriction         | No restriction                           | No restriction         | No restriction                        | One container space.    | One container space or one bulk-head. |
|                                                                                    |                                                            | Otherwise as for open versus open. |                                                            | Athwartships ..  | No restriction         | No restriction                           | No restriction         | No restriction                        | One container space.    | One container space.                  |
| 2. "Separated from".                                                               | Not in the same vertical line unless segregated by a deck. | As for open versus open.           | Not in the same vertical line unless segregated by a deck. | Fore and aft ... | One container space.   | One container space or one bulk-head.    | One container space.   | One container space or one bulk-head. | One container space..   | One bulkhead.                         |
|                                                                                    |                                                            |                                    |                                                            | Athwartships ..  | One container space.   | One container space.                     | One container space.   | Two container spaces.                 | Two container spaces..  | One bulkhead.                         |
| 3. "Separated by a complete compartment or hold from".                             | Not in the same vertical line unless segregated by a deck. | As for open versus open.           | Not in the same vertical line unless segregated by a deck. | Fore and aft ... | One container space.   | One bulkhead                             | One container space.   | One bulkhead                          | Two container spaces.   | Two bulk-heads.                       |
|                                                                                    |                                                            |                                    |                                                            | Athwartships ..  | Two container spaces.  | One bulkhead                             | Two container spaces.  | One bulkhead                          | Three container spaces. | Two bulk-heads.                       |
| 4. "Separated longitudinally by an intervening complete compartment or hold from". | Prohibited .....                                           | .....                              | .....                                                      | Fore and aft ... | Four container spaces. | One bulkhead and four container spaces*. | Four container spaces. | Two bulk-heads.                       | Four container spaces.  | Two bulk-heads.                       |
|                                                                                    |                                                            |                                    |                                                            | Athwartships ..  | Prohibited .....       | Prohibited .....                         | Prohibited .....       | Prohibited .....                      | Prohibited .....        | Prohibited.                           |

\*Containers not less than 6 m (20 feet) from intervening bulkhead.

NOTE: All bulkheads and decks must be resistant to fire and liquid.

(g) *Segregation of cargo transport units on board trailerships and trainships:* (1) The requirements of this paragraph apply to the segregation of cargo transport units which are carried on board trailerships and trainships or in “roll-on/roll-off” cargo spaces.

(2) For trailerships and trainships which have spaces suitable for

breakbulk cargo, containers, or any other method of stowage, the appropriate paragraph of this section applies to the relevant cargo space.

(3) *Segregation Table.* Table §176.83(g) sets forth the general requirements for segregation between transport units on board trailerships and trainships.

TABLE 176.83(g)—SEGREGATION OF CARGO TRANSPORT UNITS ON BOARD TRAILERSHIPS AND TRAINSHIPS.

| Segregation requirement                                                            |              | Closed versus closed |                                             | Closed versus open |                                        | Open versus open |                               |
|------------------------------------------------------------------------------------|--------------|----------------------|---------------------------------------------|--------------------|----------------------------------------|------------------|-------------------------------|
|                                                                                    |              | On deck              | Under deck                                  | On deck            | Under deck                             | On deck          | Under deck                    |
|                                                                                    |              |                      |                                             |                    |                                        |                  |                               |
| 1. “Away From”                                                                     | Fore and aft | No restriction       | No restriction                              | No restriction     | No restriction                         | At least 3 m     | At least 3 m.                 |
| 2. “Separated from”.                                                               | Athwartships | No restriction       | No restriction                              | No restriction     | No restriction                         | At least 3 m     | At least 3 m.                 |
|                                                                                    | Fore and aft | At least 6 m         | At least 6 m or one bulkhead.               | At least 6 m       | At least 6 m or one bulkhead.          | At least 6 m     | At least 12 m or one bulkhead |
| 3. “Separated by a complete compartment or hold from”.                             | Athwartships | At least 3 m         | At least 3 m or one bulkhead.               | At least 3 m       | At least 6 m or one bulkhead.          | At least 6 m     | At least 12 m or one bulkhead |
|                                                                                    | Fore and aft | At least 12 m        | At least 24 m + deck.                       | At least 24 m      | At least 24 m + deck.                  | At least 36 m    | Two decks or two bulkheads.   |
| 4. “Separated longitudinally by an intervening complete compartment or hold from”. | Athwartships | At least 12 m        | At least 24 m + deck.                       | At least 24 m      | At least 24 m + deck.                  | At least 36 m    | Prohibited.                   |
|                                                                                    | Fore and aft | At least 36 m        | Two bulkheads or at least 36 m + two decks. | At least 36 m      | At least 48 m including two bulkheads. | At least 48 m    | Prohibited.                   |
|                                                                                    | Athwartships | Prohibited ....      | Prohibited ....                             | Prohibited ....    | Prohibited ....                        | Prohibited ....  | Prohibited.                   |

NOTE: All bulkheads and decks must be resistant to fire and liquid.

(h) *Segregation on board barge carrying vessels:* (1) The requirements of this section apply to the segregation in shipborne barges as well as to the segregation between shipborne barges carried on board vessels specially designed and equipped to carry such barges.

(2) On barge-carrying vessels which incorporate other stowage spaces or any other method of stowage, barges containing hazardous materials must be segregated from hazardous materials not stowed in barges as prescribed in paragraphs (b) and (j) of this section.

(i) *Segregation in shipborne barges:* Hazardous materials transported in shipborne barges must be segregated as prescribed in paragraphs (a), (b), and (c) of this section.

(j) *Segregation between shipborne barges on barge-carrying vessels:* (1) When a shipborne barge is loaded with two or more hazardous materials with different requirements for segregation,

the most stringent applicable segregation requirement must be applied.

(2) “Away from” and “separated from” require no segregation between shipborne barges.

(3) For barge-carrying vessels with vertical holds, “Separated by a complete compartment or hold from” means that separate holds are required. On barge-carrying vessels having horizontal barge levels, separate barge levels are required and the barges may not be in the same vertical line.

(4) “Separated longitudinally by an intervening complete compartment or hold from” means, for barge-carrying vessels with vertical holds, that separation by an intervening hold or engine room is required. On barge-carrying vessels having horizontal barge levels, separate barge levels and a longitudinal separation by at least two intervening barge spaces are required.

(k) *Segregation requirements for ferry vessels:* A ferry vessel (when operating either as a passenger or cargo vessel) that cannot provide the separation required in this section may carry incompatible hazardous materials in separate transport vehicles if they are stowed to give the maximum possible separation.

(l) *Segregation of containers on board hatchless (open-top) container ships:* (1) This paragraph applies to the segregation of cargo transport units that are transported on board hatchless container ships provided that the cargo spaces are properly fitted to give permanent stowage of the cargo transport units during transport.

(2) For container ships that have both hatchless container spaces and other spaces suitable for breakbulk cargo, conventional container stowage, or any other method of stowage, the appropriate requirements of this section apply to the relevant cargo space.

(3) *Segregation Table.* Table §176.83(1)(3) sets forth the general requirements for segregation of cargo transport units on board hatchless container ships.

(4) In Table §176.83(1)(3), a container space means a distance of not less than 6 m (20 feet) fore and aft or not less than 2.5 m (8 feet) athwartship.



TABLE § 176.83(L)(3)—SEGREGATION OF CARGO TRANSPORT UNITS ON BOARD HATCHLESS CONTAINER SHIPS

| Segregation require-<br>ment                                                                       | Vertical                             |                                               |                                         | Horizontal        |                                                                                       |                                                                             |                                                                                       |                                                 |                                                                                       |                                                 |
|----------------------------------------------------------------------------------------------------|--------------------------------------|-----------------------------------------------|-----------------------------------------|-------------------|---------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|---------------------------------------------------------------------------------------|-------------------------------------------------|---------------------------------------------------------------------------------------|-------------------------------------------------|
|                                                                                                    | Closed<br>versus<br>closed           | Closed<br>versus open                         | Open versus<br>open                     |                   | Closed versus closed                                                                  |                                                                             | Closed versus open                                                                    |                                                 | Open versus open                                                                      |                                                 |
|                                                                                                    |                                      |                                               |                                         |                   | On deck                                                                               | Under deck                                                                  | On deck                                                                               | Under deck                                      | On deck                                                                               | Under deck                                      |
| 1. "Away from" .....                                                                               | On top of<br>the other<br>permitted. | Open on top<br>of closed<br>permitted.        | .....                                   | Fore and aft      | No restriction                                                                        | No restriction                                                              | No restriction                                                                        | No restriction                                  | One container<br>space.                                                               | One container<br>space or<br>one bulk-<br>head. |
|                                                                                                    |                                      | Otherwise as<br>for "Open<br>versus<br>open". | .....                                   | Athwart<br>ships. | No restriction                                                                        | No restriction                                                              | No restriction                                                                        | No restriction                                  | One container<br>space.                                                               | One container<br>space.                         |
| 2. "Separated from" ...                                                                            | .....                                | .....                                         | Not in the<br>same<br>vertical<br>line. | Fore and aft      | One container<br>space.                                                               | One container<br>space or<br>one bulk-<br>head.                             | One container<br>space.                                                               | One container<br>space or<br>one bulk-<br>head. | One container<br>space and<br>not in or<br>above same<br>hold.                        | One bulkhead.                                   |
|                                                                                                    |                                      | As for "Open<br>versus<br>open".              | .....                                   | Athwart<br>ships. | One container<br>space.                                                               | One container<br>space.                                                     | Two container<br>spaces.                                                              | Two container<br>spaces.                        | Two container<br>spaces and<br>not in or<br>above same<br>hold.                       | One bulkhead.                                   |
| 3. "Separated by a<br>complete compart-<br>ment or hold from".                                     | .....                                | .....                                         | .....                                   | Fore and aft      | One container<br>space and<br>not in or<br>above same<br>hold.                        | One bulkhead                                                                | One container<br>space and<br>not in or<br>above same<br>hold.                        | One bulkhead                                    | Two container<br>spaces and<br>not in or<br>above same<br>hold.                       | Two bulk-<br>heads.                             |
|                                                                                                    |                                      | .....                                         | .....                                   | Athwart<br>ships. | Two container<br>spaces and<br>not in or<br>above same<br>hold.                       | One bulkhead                                                                | Two container<br>spaces and<br>not in or<br>above same<br>hold.                       | One bulkhead                                    | Three con-<br>tainer<br>spaces and<br>not in or<br>above same<br>hold.                | Two bulk-<br>heads.                             |
| 4. "Separated longitu-<br>dinally by an inter-<br>vening complete<br>compartment or hold<br>from". | Prohibited ...                       | Prohibited ...                                | .....                                   | Fore and aft      | Minimum hori-<br>zontal dis-<br>tance of 24<br>m and not in<br>or above<br>same hold. | One bulkhead<br>and min-<br>imum hori-<br>zontal dis-<br>tance of 24<br>m*. | Minimum hori-<br>zontal dis-<br>tance of 24<br>m and not in<br>or above<br>same hold. | Two bulk-<br>heads.                             | Minimum hori-<br>zontal dis-<br>tance of 24<br>m and not in<br>or above<br>same hold. | Two bulk-<br>heads.                             |
|                                                                                                    |                                      |                                               |                                         | Athwart<br>ships. | Prohibited .....                                                                      | Prohibited .....                                                            | Prohibited .....                                                                      | Prohibited .....                                | Prohibited .....                                                                      | Prohibited.                                     |

\*Containers not less than 6 m (20 feet) from intervening bulkhead.

**Note:** All bulkheads and decks must be resistant to fire and liquid.

(m) *Provisions for segregation groups:*

(1) For the purpose of segregation, materials having certain similar chemical properties have been grouped together in segregation groups. The segregation groups (such as “acids”, “chlorates”, “permanganates”) and the entries allocated to each of these groups include the substances identified in section 3.1.4 of the IMDG Code. When column (10B) of the §172.101 Table refers to a numbered stowage provision set forth in §176.84(b) such as “Stow ‘away from’ acids”, that particular stowage/segregation requirement applies to all the materials allocated to the respective segregation group.

(2) Not all hazardous materials falling within a segregation group are listed by name in the regulations. These materials are shipped under “n.o.s.” entries. Although these “n.o.s.” entries are not listed themselves in the above groups, the shipper must decide whether allocation under a segregation group is appropriate. Mixtures, solutions or preparations containing hazardous materials falling within a segregation group and shipped under an “n.o.s.” entry are also considered to fall within that segregation group.

(3) The segregation groups described above do not address materials which fall outside the classification criteria of the hazardous materials regulations although it is recognized that some non-hazardous materials have certain chemical properties similar to hazardous materials listed in the segregation groups. A shipper or the person responsible for packing the materials into a cargo transport unit who does have knowledge of the chemical properties of such non-hazardous materials may identify a relevant segregation group and apply the segregation requirements for that segregation group.

[Amdt. 176–30, 55 FR 52690, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; 57 FR 45465, Oct. 1, 1992; Amdt. 176–34, 58 FR 51533, Oct. 1, 1993; Amdt. 176–38, 60 FR 49111, Sept. 21, 1995; 64 FR 10781, 10782, Mar. 5, 1999; 66 FR 45184, 45384, Aug. 28, 2001; 68 FR 45039, July 31, 2003; 69 FR 76180, Dec. 20, 2004; 70 FR 3310, Jan. 24, 2005; 70 FR 34399, June 14, 2005; 71 FR 78634, Dec. 29, 2006; 72 FR 55694, Oct. 1, 2007; 73 FR 57006, Oct. 1, 2008]

**§ 176.84 Other requirements for stowage and segregation for cargo vessels and passenger vessels.**

(a) *General.* When Column 10B of the §172.101 Table refers to a numbered or alpha-numeric stowage provision for water shipments, the meaning and requirements of that provision are set forth in this section. Terms in quotation marks are defined in §176.83. Other terms used in the table in this section such as “acids”, “chlorates” and “permanganates” indicate different chemical groups referred to here as segregation groups. Materials falling within a segregation group are considered to have certain similar chemical properties and, although not exhaustive in nature, the materials belonging to each group include those substances identified in section 3.1.4 of the IMDG Code as set forth in §176.83(m).

(b) *Table of provisions:*

| Code     | Provisions                                                                                               |
|----------|----------------------------------------------------------------------------------------------------------|
| 1 .....  | [Reserved]                                                                                               |
| 2 .....  | Temperature controlled material.                                                                         |
| 3 .....  | Do not stow with high explosives.                                                                        |
| 4 .....  | Stow “Separated from” liquid organic materials.                                                          |
| 5 .....  | Stow “Separated from” powdered metals and their compounds.                                               |
| 6 .....  | Emergency temperature material.                                                                          |
| 7 .....  | [Reserved]                                                                                               |
| 8 .....  | Glass carboys not permitted on passenger vessels.                                                        |
| 9 .....  | Glass carboys not permitted under deck.                                                                  |
| 10 ..... | Glass bottles not permitted under deck.                                                                  |
| 11 ..... | Keep away from heat and open flame.                                                                      |
| 12 ..... | Keep as cool as reasonably practicable.                                                                  |
| 13 ..... | Keep as dry as reasonably practicable.                                                                   |
| 14 ..... | For metal drums, stowage permitted under deck on cargo vessels.                                          |
| 15 ..... | May be stowed in portable magazine or metal locker.                                                      |
| 16 ..... | No other cargo may be stowed in the same hold with this material.                                        |
| 17 ..... | Segregation same as for flammable gases but “away from” dangerous when wet.                              |
| 18 ..... | Prohibited on any vessel carrying explosives (except explosives in Division 1.4, Compatibility group S). |
| 19 ..... | Protect from sparks and open flames.                                                                     |
| 20 ..... | Segregation same as for corrosives.                                                                      |
| 21 ..... | Segregation same as for flammable liquids.                                                               |
| 22 ..... | Segregation same as for flammable liquids if flash point is below 60 °C (140 °F).                        |
| 23 ..... | Segregation same as for flammable liquids if flash point is between 23 °C (73 °F) and 60 °C (140 °F).    |
| 24 ..... | Segregation same as for flammable solids.                                                                |
| 25 ..... | Shade from radiant heat.                                                                                 |
| 26 ..... | Stow “away from” acids. <sup>2</sup>                                                                     |
| 27 ..... | Stow “away from” alkaline compounds. <sup>2</sup>                                                        |
| 28 ..... | Stow “away from” flammable liquids.                                                                      |
| 29 ..... | Stow “away from” ammonium compounds.                                                                     |
| 30 ..... | Stow “away from” animal or vegetable oils.                                                               |

§ 176.84

49 CFR Ch. I (10–1–08 Edition)

| Code     | Provisions                                                                                                                            | Code      | Provisions                                                                                                                                                                                                                                                                                                     |
|----------|---------------------------------------------------------------------------------------------------------------------------------------|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 31 ..... | Stow "away from" combustible materials.                                                                                               | 81 .....  | Under deck stowage permitted only if an indicating substance such as chloropicrin has been added.                                                                                                                                                                                                              |
| 32 ..... | Stow "away from" copper, its alloys and its salts.                                                                                    | 82 .....  | Under deck stowage is permitted only if containing not more than 36 percent by weight of hydrazine.                                                                                                                                                                                                            |
| 33 ..... | Stow "away from" fluorides.                                                                                                           | 83 .....  | [Reserved]                                                                                                                                                                                                                                                                                                     |
| 34 ..... | Stow "away from" foodstuffs.                                                                                                          | 84 .....  | Under deck stowage must be in well-ventilated space.                                                                                                                                                                                                                                                           |
| 35 ..... | Stow "away from" all odor-absorbing cargo.                                                                                            | 85 .....  | Under deck stowage must be in mechanically ventilated space.                                                                                                                                                                                                                                                   |
| 36 ..... | Stow "away from" heavy metals and their compounds.                                                                                    | 86 .....  | Stow "separated by a complete compartment or hold from" explosives Division 1.3.                                                                                                                                                                                                                               |
| 37 ..... | Stow "away from" hydrazine.                                                                                                           | 87 .....  | Stow "separated from" Class 1 (explosives) except Division 1.4.                                                                                                                                                                                                                                                |
| 38 ..... | Stow "away from" all other corrosives.                                                                                                | 88 .....  | Stow "separated by a complete compartment or hold from" Class 1 (explosives) except Division 1.4.                                                                                                                                                                                                              |
| 39 ..... | Stow "away from" liquid halogenated hydrocarbons.                                                                                     | 89 .....  | Segregation same as for oxidizers.                                                                                                                                                                                                                                                                             |
| 40 ..... | Stow "clear of living quarters".                                                                                                      | 90 .....  | Stow "separated from" radioactive materials.                                                                                                                                                                                                                                                                   |
| 41 ..... | Stow "away from" mercury and its compounds.                                                                                           | 91 .....  | Stow "separated from" flammable liquids.                                                                                                                                                                                                                                                                       |
| 42 ..... | Stow "away from" nitric acids and perchloric acids not exceeding 50 percent acid by weight.                                           | 92 .....  | Stow "separated from" powdered materials.                                                                                                                                                                                                                                                                      |
| 43 ..... | Stow "away from" organic materials.                                                                                                   | 93 .....  | Stow not accessible to unauthorized persons on passenger vessels.                                                                                                                                                                                                                                              |
| 44 ..... | Stow "away from" oxidizers.                                                                                                           | 94 .....  | Plastic jerricans and plastic drums not permitted under deck.                                                                                                                                                                                                                                                  |
| 45 ..... | Stow "away from" permanganates.                                                                                                       | 95 .....  | Stow "separated from" foodstuffs.                                                                                                                                                                                                                                                                              |
| 46 ..... | Stow "away from" powdered metals.                                                                                                     | 96 .....  | Glass carboys not permitted under deck on passenger vessels.                                                                                                                                                                                                                                                   |
| 47 ..... | Stow "away from" sodium compounds.                                                                                                    | 97 .....  | Stow "away from" azides.                                                                                                                                                                                                                                                                                       |
| 48 ..... | Stow "away from" sources of heat.                                                                                                     | 98 .....  | Stow "away from" all flammable materials.                                                                                                                                                                                                                                                                      |
| 49 ..... | Stow "away from" corrosives.                                                                                                          | 99 .....  | Only new metal drums permitted on passenger vessels.                                                                                                                                                                                                                                                           |
| 50 ..... | Stow "away from" sources of heat where temperatures in excess of 55 °C (131 °F) for a period of 24 hours or more will be encountered. | 100 ..... | Stow "away from" flammable solids.                                                                                                                                                                                                                                                                             |
| 51 ..... | Stow "separated from" acetylene.                                                                                                      | 101 ..... | Stow "separated from" iron oxide.                                                                                                                                                                                                                                                                              |
| 52 ..... | Stow "separated from" acids. <sup>1,2</sup>                                                                                           | 102 ..... | Stow "separated from" all odor absorbing cargoes.                                                                                                                                                                                                                                                              |
| 53 ..... | Stow "separated from" alkaline compounds. <sup>2</sup>                                                                                | 103 ..... | Only to be loaded under dry weather conditions.                                                                                                                                                                                                                                                                |
| 54 ..... | Stow "separated from" animal or vegetable oils.                                                                                       | 104 ..... | Stow "separated from" bromine.                                                                                                                                                                                                                                                                                 |
| 55 ..... | Stow "separated from" ammonia.                                                                                                        | 105 ..... | As approved by the Competent Authority of the country concerned.                                                                                                                                                                                                                                               |
| 56 ..... | Stow "separated from" ammonium compounds.                                                                                             | 106 ..... | Stow "separated from" powdered metal.                                                                                                                                                                                                                                                                          |
| 57 ..... | Stow "separated from" chlorine.                                                                                                       | 107 ..... | Stow "separated from" peroxides and superoxides.                                                                                                                                                                                                                                                               |
| 58 ..... | Stow "separated from" cyanides.                                                                                                       | 108 ..... | The transport temperature should be indicated on the tank.                                                                                                                                                                                                                                                     |
| 59 ..... | Stow "separated from" combustible materials.                                                                                          | 109 ..... | Label as a flammable liquid if flash point is 60 °C (140 °F) or below.                                                                                                                                                                                                                                         |
| 60 ..... | Stow "separated from" chlorates, chlorites, hypochlorites, nitrites, perchlorates, permanganates, and metallic powders.               | 110 ..... | Packaging Group II if concentration does not exceed 70 percent acid.                                                                                                                                                                                                                                           |
| 61 ..... | Stow "separated from" corrosive materials.                                                                                            | 111 ..... | If concentration exceeds 50 percent acid, notes 66, 74, 89, and 90 apply.                                                                                                                                                                                                                                      |
| 62 ..... | Stow "separated from" diborane.                                                                                                       | 112 ..... | Packaging Group II for concentrations not less than 50 percent and Packaging Group III for concentrations less than 50 percent.                                                                                                                                                                                |
| 63 ..... | Stow "separated from" diethylene triamine.                                                                                            | 113 ..... | Packaging Group II if concentrations does not exceed 60 percent acid.                                                                                                                                                                                                                                          |
| 64 ..... | Stow "separated from" explosives.                                                                                                     | 114 ..... | Corrosive subsidiary risk label required unless concentration is less than 80 percent.                                                                                                                                                                                                                         |
| 65 ..... | Stow "separated from" flammable substances.                                                                                           | 115 ..... | If packaged in glass or earthenware inner packagings in wooden or fiberboard outer packagings, the maximum quantity on any vessel is 500 kg (equivalent to 450 L).                                                                                                                                             |
| 66 ..... | Stow "separated from" flammable solids.                                                                                               | 116 ..... | In a cargo space capable of being opened up in an emergency. The possible need to open hatches in case of fire to provide maximum ventilation and to apply water in an emergency and the consequent risk to the stability of the ship through flooding of the cargo space should be considered before loading. |
| 67 ..... | Stow "separated from" halides.                                                                                                        |           |                                                                                                                                                                                                                                                                                                                |
| 68 ..... | Stow "separated from" hydrogen.                                                                                                       |           |                                                                                                                                                                                                                                                                                                                |
| 69 ..... | Stow "separated from" hydrogen peroxide.                                                                                              |           |                                                                                                                                                                                                                                                                                                                |
| 70 ..... | Stow "separated from" mercury salts.                                                                                                  |           |                                                                                                                                                                                                                                                                                                                |
| 71 ..... | Stow "separated from" nitric acid.                                                                                                    |           |                                                                                                                                                                                                                                                                                                                |
| 72 ..... | Stow "separated from" nitrogen compounds.                                                                                             |           |                                                                                                                                                                                                                                                                                                                |
| 73 ..... | Stow "separated from" chlorates.                                                                                                      |           |                                                                                                                                                                                                                                                                                                                |
| 74 ..... | Stow "separated from" oxidizers.                                                                                                      |           |                                                                                                                                                                                                                                                                                                                |
| 75 ..... | Stow "separated from" permanganates.                                                                                                  |           |                                                                                                                                                                                                                                                                                                                |
| 76 ..... | Stow "separated by a complete compartment or hold from" organic peroxides.                                                            |           |                                                                                                                                                                                                                                                                                                                |
| 77 ..... | Stow "separated longitudinally by a complete compartment or hold from" explosives.                                                    |           |                                                                                                                                                                                                                                                                                                                |
| 78 ..... | Stow "separated longitudinally by an intervening complete compartment or hold from" explosives.                                       |           |                                                                                                                                                                                                                                                                                                                |
| 79 ..... | The maximum net quantity in one package for this material shipped aboard a passenger vessel is limited to 22.7 kg (50 pounds).        |           |                                                                                                                                                                                                                                                                                                                |
| 80 ..... | Toy torpedoes must not be packed with other special fireworks.                                                                        |           |                                                                                                                                                                                                                                                                                                                |

| Code      | Provisions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Code        | Provisions                                                                                                                                                                                                   |
|-----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 117 ..... | In a clean cargo space capable of being opened up in an emergency. In the case of bagged fertilizer in freight containers, it is sufficient if in the case of an emergency, the cargo is accessible through free approaches (hatch entries) and mechanical ventilation enables the master to exhaust any gases or fumes resulting from decomposition. The possible need to open hatches in case of fire to provide maximum ventilation and to apply water in an emergency and the consequent risk to the stability of the ship through flooding of the cargo space should be considered before loading. | 142 .....   | Packages in cargo transport units must be stowed so as to allow for adequate air circulation throughout the cargo.                                                                                           |
| 118 ..... | Stowage—Category D, Category E freight containers and pallet boxes only. Ventilation may be required. The possible need to open hatches in a case of fire to provide maximum ventilation and to supply water in an emergency, and the consequent risk to the stability of the ship through flooding of the cargo space, should be considered before loading.                                                                                                                                                                                                                                            | 143 .....   | Prohibited on any vessel carrying explosives (except explosives in Division 1.4, Compatibility group S).                                                                                                     |
| 119 ..... | Double strip stowage recommended.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 144 .....   | When stowed under deck, mechanical ventilation shall be in accordance with SOLAS, Chapter II-2/Regulation 19 (IBR, see §171.7 of this subchapter) for flammable liquids with flashpoint below 23 °C (73 °F). |
| 120 ..... | Provide good surface and through ventilation.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | M1—M6 ..... | [Reserved]                                                                                                                                                                                                   |
| 121 ..... | Packaging group III when the flash point of the flammable liquid is 23°C (73°F) or above.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |             |                                                                                                                                                                                                              |
| 122 ..... | Stow "separated from" infectious substances.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |             |                                                                                                                                                                                                              |
| 123 ..... | Stow "away from" infectious substances.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |             |                                                                                                                                                                                                              |
| 124 ..... | Stow "separated from" bromates.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |             |                                                                                                                                                                                                              |
| 125 ..... | Segregation same as for flammable liquids, but also "away from" flammable solids.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |             |                                                                                                                                                                                                              |
| 126 ..... | Segregation same as for Class 9, miscellaneous hazardous materials.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |             |                                                                                                                                                                                                              |
| 127 ..... | For packages carrying a subsidiary risk of Class 1 (explosives), segregation same as for Class 1, Division 1.3.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |             |                                                                                                                                                                                                              |
| 128 ..... | Stow in accordance with the IMDG Code, Sub-section 7.1.10.3 (incorporated by reference; see §171.7 of this subchapter).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |             |                                                                                                                                                                                                              |
| 129 ..... | Stowage Category A applies, except for uranyl nitrate hexahydrate solution for which Category D applies.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |             |                                                                                                                                                                                                              |
| 130 ..... | Stowage Category A applies, except for uranyl nitrate hexahydrate solution, uranium metal hexahydrate solution, uranium metal pyrophoric and thorium metal pyrophoric for which Category D applies.                                                                                                                                                                                                                                                                                                                                                                                                     |             |                                                                                                                                                                                                              |
| 131 ..... | Stowage Category A applies, except for uranyl nitrate hexahydrate solution, uranium metal pyrophoric and thorium metal pyrophoric for which Category D applies, and taking into account any supplementary requirements specified in the transport documents.                                                                                                                                                                                                                                                                                                                                            |             |                                                                                                                                                                                                              |
| 132 ..... | Stowage A applies, taking into account any supplementary requirements specified in the transport documents.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |             |                                                                                                                                                                                                              |
| 133 ..... | Stow "separated from" sulfur.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |             |                                                                                                                                                                                                              |
| 134 ..... | Stow "separated from" UN2716.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |             |                                                                                                                                                                                                              |
| 135 ..... | Stow "Separated from" mercury and mercury compounds.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |             |                                                                                                                                                                                                              |
| 136 ..... | Stow "Separated from" carbon tetrachloride.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |             |                                                                                                                                                                                                              |
| 137 ..... | For arsenic sulphides, Stow "separated from" acids.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |             |                                                                                                                                                                                                              |
| 138 ..... | Stow "Separated from" peroxides.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |             |                                                                                                                                                                                                              |
| 139 ..... | Stow "Separated from" mercury salts.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |             |                                                                                                                                                                                                              |
| 140 ..... | Stow "Separated from" UN3052 and UN3461.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |             |                                                                                                                                                                                                              |
| 141 ..... | Stow "away from" radioactive materials.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |             |                                                                                                                                                                                                              |

<sup>1</sup>For waste cyanides or waste cyanide mixtures or solutions, refer to §173.12(e) of this subchapter.

<sup>2</sup>Class 8 materials in PG II or III that otherwise are required to be segregated from one another may be transported in the same cargo transport unit, whether in the same packaging or not, provided the substances do not react dangerously with each other to cause combustion and/or evolution of considerable heat, or of flammable, toxic or asphyxiant gases, or the formation of corrosive or unstable substances; and the package does not contain more than 30 L (7.8 gallons) for liquids or 30 kg (66 lbs.) for solids.

(c) *Provisions for the stowage of Class 1 (explosive) materials:* (1) Explosive substances and explosive articles must be stowed in accordance with Column (10A) and Column (10B) of the 172.101 Table of this subchapter.

(2) The following notes in column 10B of the §172.101 Table apply to the transport of Class 1 (explosive) materials by vessel:

| Notes     | Provisions                                                                                                                                                                                                                                           |
|-----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 5E .....  | Stow "away from" lead and its compounds.                                                                                                                                                                                                             |
| 7E .....  | Stowage category "04" for projectiles or cartridges for guns, cannons or mortars; Stowage category "08" for other types.                                                                                                                             |
| 8E .....  | When under deck, special stowage is required.                                                                                                                                                                                                        |
| 14E ..... | On deck, cargo transport unit must be steel.                                                                                                                                                                                                         |
| 15E ..... | On deck, cargo transport unit must be leak-proof.                                                                                                                                                                                                    |
| 17E ..... | On deck stowage is recommended.                                                                                                                                                                                                                      |
| 19E ..... | "Away from" explosives containing chlorates or perchlorates.                                                                                                                                                                                         |
| 20E ..... | Stowage category "03" for projectiles or cartridges for guns, cannons or mortars; Stowage category "07" for other types; magazines must be of steel construction that prevents leakage.                                                              |
| 21E ..... | Cargo space ventilation must be carefully controlled to avoid excessive condensation.                                                                                                                                                                |
| 22E ..... | "Away from" ammonium compounds and explosives containing ammonium compounds or salts.                                                                                                                                                                |
| 23E ..... | "Separated from" Division 1.4 and "separated longitudinally by an intervening complete compartment or hold from" Division 1.1, 1.2, 1.3, 1.5, and 1.6 except from explosives of compatibility group J.                                               |
| 26E ..... | Stowage category "13" and, for on deck stowage, non-metallic lining of closed cargo transport unit is required when not in effectively sealed, sift-proof packages; Stowage category "10" permitted when in effectively sealed, sift-proof packages. |

## § 176.88

| Notes     | Provisions                                                           |
|-----------|----------------------------------------------------------------------|
| 27E ..... | For closed cargo transport units, a non-metallic lining is required. |

[Amdt. 176–30, 55 FR 52693, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; Amdt. 176–43, 62 FR 24742, May 6, 1997; 66 FR 33438, June 21, 2001; 66 FR 45185, 45384, Aug. 28, 2001; 67 FR 15744, Apr. 3, 2002; 68 FR 45040, July 31, 2003; 69 FR 76183, Dec. 20, 2004; 70 FR 3310, Jan. 24, 2005; 71 FR 78634, Dec. 29, 2006]

### Subpart E—Special Requirements for Transport Vehicles Loaded With Hazardous Materials and Transported on Board Ferry Vessels

#### § 176.88 Applicability.

The requirements in this subpart are applicable to transport vehicles containing hazardous materials being transported on board ferry vessels and are in addition to any prescribed elsewhere in this subchapter. Vessels in a service similar to a ferry service, but not over a designated ferry route, may be treated as a ferry vessel for the purpose of this subpart if approved in writing by the District Commander.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–1A, 41 FR 40690, Sept. 20, 1976]

#### § 176.89 Control of transport vehicles.

(a) A transport vehicle containing hazardous materials may be transported on board a ferry vessel, subject to the following conditions:

(1) The operator or person in charge of the vehicle shall deliver to the vessel's representative a copy of the shipping papers and certificate required by §§ 176.24 and 176.27;

(2) The vehicle shall be placed at the location indicated by the vessel's representative;

(3) The parking brakes of the vehicle shall be set securely to prevent movement;

(4) The motor of a highway vehicle shall be shut off and not restarted until the vessel has completed its voyage and docked;

(5) All vehicle lights shall be cut off and not relighted until the vessel has completed its voyage and docked;

## 49 CFR Ch. I (10–1–08 Edition)

(6) The operator of a highway vehicle shall remain with the vehicle;

(7) No repairs or adjustments must be made to the vehicle while it is on the vessel;

(8) No hazardous materials are to be released from the vehicle; and

(9) Any instructions given by the vessel's representative during the voyage, and during “roll on” and “roll off” operations must be observed.

(b) Smoking by any person in or around a vehicle is prohibited.

#### § 176.90 Private automobiles.

A private automobile which is carrying any Class 1 (explosive) material (except permitted fireworks or small arms ammunition) may not be transported on a passenger-carrying ferry vessel unless the Class 1 (explosive) material is in compliance with packaging, labeling, marking, and certification requirements of this subchapter. Permitted fireworks and small arms ammunition may be carried without the required packaging, labeling, marking, or certification if they are in tight containers.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–30, 55 FR 52695, Dec. 21, 1990]

#### § 176.91 Motorboats.

A motorboat may be transported on board a ferry vessel with gasoline in the tank and two other containers not exceeding 23 L (six gallons) capacity each if they are in the motorboat, closed, and in good condition.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–30, 55 FR 52695, Dec. 21, 1990]

#### § 176.92 Cylinders laden in vehicles.

Any cylinder of Class 2 (compressed gas) material which is required to have a valve protection cap fitted in place may be transported on board a ferry vessel without having the valve protection cap in place when it is laden in a transport vehicle and is not removed from the vehicle while on the vessel.

[Amdt. 176–1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176–30, 55 FR 52695, Dec. 21, 1990]

**§ 176.93 Vehicles having refrigerating or heating equipment.**

(a) A transport vehicle fitted with refrigerating or heating equipment using a flammable liquid or Division 2.1 (flammable gas) material, or diesel oil as fuel, may be transported on a ferry vessel. However, the refrigerating or heating equipment may not be operated while the vehicle is on the vessel, unless the equipment complies with the following requirements:

(1) The installation is rigidly mounted and free of any motion other than normal vibration in operation;

(2) An easily accessible shutoff control is fitted to the fuel and electrical supply of the refrigerating or heating equipment; and

(3) The fuel storage tank, the fuel lines, the carburetor and any other fuel devices are tight and show no signs of leakage.

(b) If the vehicle operator desires to operate the refrigerating or heating equipment while on the vessel and the equipment is not fitted with automatic starting and stopping devices, it must be started before the vehicle is taken on board. It may continue in operation while the vehicle is on the vessel, but if the motor stops it may not be restarted.

(c) In the case of a ferry vessel on a voyage exceeding 30 minutes' duration, stowage must be provided for transport vehicles having refrigerating or heating equipment operated by internal combustion engines which will permit ready diffusion of exhaust gases to the open air. Passenger vehicles may not be stowed in a position adjacent to vehicles operating internal combustion motors which expose the occupants of the passenger vehicles to excessive concentrations of exhaust fumes from such motors.

(d) A transport vehicle containing solid carbon dioxide as a refrigerant may be transported on a ferry vessel only if it is stowed in a well ventilated location.

[Amdt. 176-1, 41 FR 16110, Apr. 15, 1976, as amended by Amdt. 176-30, 55 FR 52695, Dec. 21, 1990; 68 FR 61942, Oct. 30, 2003]

**Subpart F—Special Requirements for Barges**

SOURCE: Amdt. 176-8, 44 FR 23228, Apr. 19, 1979, unless otherwise noted.

**§ 176.95 Applicability.**

The requirements prescribed in this subpart are applicable to the transportation of packaged hazardous materials on board barges. The requirements prescribed elsewhere in this subchapter for vessels similarly apply, except as provided in this subpart, to the transportation of packaged hazardous materials on board barges.

**§ 176.96 Materials of construction.**

Barges used to transport hazardous materials must be constructed of steel.

[Amdt. 176-30, 55 FR 52695, Dec. 21, 1990]

**§ 176.97 Prohibition of dump scows.**

Dump scows are barges having cargo carrying compartments of the hopper type and fitted with a bottom dump or a side dump. This type of barge is prohibited from the carriage of any class of hazardous material.

**§ 176.98 Stowage of hazardous materials on board barges.**

A material for which "on deck" stowage only is required by column (10) of the Hazardous Materials Table (§ 172.101 of this subchapter) may be stowed "under deck" on unmanned barges.

[Amdt. 176-8, 44 FR 23228, Apr. 19, 1979, as amended by Amdt. 176-30, 55 FR 52695, Dec. 21, 1990]

**§ 176.99 Permit requirements for certain hazardous materials.**

The permits required by §§ 176.100 and 176.415 for loading, unloading, and handling Divisions 1.1 and 1.2 (explosives) materials, Division 1.5 materials, ammonium nitrate and certain ammonium nitrate mixtures and fertilizers must be obtained before these materials may be loaded on, unloaded from, or handled on board a barge or barge-carrying vessel. However, a barge loaded with these materials being placed on, removed from, or handled on board

## § 176.100

## 49 CFR Ch. I (10–1–08 Edition)

a barge-carrying vessel is not subject to these permit requirements.

[Amdt. 176–30, 55 FR 52695, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; 66 FR 45384, Aug. 28, 2001]

### Subpart G—Detailed Requirements for Class 1 (Explosive) Materials

SOURCE: Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, unless otherwise noted.

#### § 176.100 Permit for Divisions 1.1 and 1.2 (explosive) materials.

Before Divisions 1.1 and 1.2 (explosive) materials may be discharged from, loaded on, handled or restowed on board a vessel at any place in the United States, the carrier must obtain a permit from the COTP in accordance with the procedures in 33 CFR 126.19. Exceptions to this permit requirement may be authorized by the COTP.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended by Amdt. 176–34, 58 FR 51533, Oct. 1, 1993; 66 FR 45385, Aug. 28, 2001]

#### § 176.102 Supervisory detail.

(a) Except as provided in paragraph (c) of this section, the COTP may assign a USCG supervisory detail to any vessel to supervise the loading, handling or unloading of Class 1 (explosive) materials.

(b) The owner, agent, charterer, master or person in charge of the vessel, and all persons engaged in the handling, loading, unloading, and stowage of Class 1 (explosive) materials shall obey all orders that are given by the officer in charge of the supervisory detail.

(c) If Class 1 (explosive) materials are loaded onto or unloaded from a vessel at a facility operated or controlled by the Department of Defense, the Commanding Officer of that facility may decline the USCG supervisory detail. Whenever the supervisory detail is declined, the Commanding Officer of the facility shall ensure compliance with the regulations in this part.

#### § 176.104 Loading and unloading Class 1 (explosive) materials.

(a) Packages of Class 1 (explosive) materials may not be thrown, dropped,

rolled, dragged, or slid over each other or over a deck.

(b) When Class 1 (explosive) materials are stowed in a hold below one in which any cargo is being handled, the hatch in the deck dividing the two holds must have all covers securely in place.

(c) Drafts of Class 1 (explosive) materials must be handled in accordance with the following:

(1) A draft may not be raised, lowered, or stopped by sudden application of power or brake.

(2) A draft may not be released by tripping or freeing one side of the cargo-handling equipment and tumbling the Class 1 (explosive) materials off.

(3) All drafts, beams, shackles, bridle, slings, and hoods must be manually freed before the winch takes control.

(4) Slings may not be dragged from under a draft by winching except for the topmost layer in the hold when power removal is the only practical method and when the cargo cannot be toppled.

(5) Handles or brackets on packages in a draft may not be used for slinging purposes.

(d) A combination woven rope and wire sling or a sling that is formed by use of an open hook may not be used in handling Class 1 (explosive) materials.

(e) Only a safety hook or a hook that has been closed by wire may be used in handling drafts of Class 1 (explosive) materials.

(f) Wire rope or wire rope assemblies, including splices and fittings, used in handling Class 1 (explosive) materials must be unpainted and kept bare to permit inspection of their safe working condition. A mechanical end fitting (pressed fitting) may be used in place of an eye splice, if the efficiency of the mechanical end fitting is at least equal to the efficiency of an eye splice prepared as prescribed in 29 CFR 1918.51(c)(1).

(g) Packages of Division 1.1 and 1.2 materials that are not part of a palletized unit must be loaded and unloaded from a vessel using a chute, conveyor or a mechanical hoist and a pallet, skipboard, tray or pie plate fitted with a cargo net or sideboards.

(h) Packages of Division 1.1 and 1.2 (explosive) materials must be loaded or unloaded in accordance with the following:

(1) A cargo net with a pallet, skipboard, tray, or pie plate, must be loaded so that no more than a minimum displacement of packages occurs when it is lifted.

(2) A cargo net must completely encompass the bottom and sides of the draft. The mesh of the cargo net must be of a size and strength that will prevent a package in the draft from passing through the net.

(3) When a tray is used in handling packages, no package may extend more than one-third its vertical dimension above the sideboard of the tray.

(i) A landing mat must be used when a draft of nonpalletized Division 1.1 or 1.2 (explosive) materials is deposited on deck. The landing mat must have dimensions of at least 1 m (3 feet) wide, 2 m (7 feet) long, and 10 cm (3.9 inches) thick, and be made of woven hemp, sisal, or similar fiber, or foam rubber, polyurethane or similar resilient material.

(j) In addition to the other requirements of this section, packages of Division 1.1 and 1.2 (explosive) materials must be handled in accordance with the following:

(1) Packages may not be loaded or unloaded through a hatch at the same time that other cargo is being handled in any hold served by that hatch.

(2) Packages may not be loaded or unloaded from the same hatch by using two pieces of cargo equipment unless the equipment is positioned at the forward and aft ends of the hatch.

(3) Packages may not be lifted over any hazardous materials.

(4) The height of any structure, equipment, or load on a deck over which packages must be lifted may not be higher than the hatch coaming or bulwark, or 1 m (3 feet), whichever is greater.

(k) Unpackaged explosive devices may not be handled by their lifting lugs or suspension lugs.

(l) A chute may not be used when loading or unloading Class 1 (explosive)

materials in compatibility group A or B.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended by Amdt. 176-40, 61 FR 27175, May 30, 1996; 65 FR 58630, Sept. 29, 2000; 66 FR 45384, 45385, Aug. 28, 2001]

**§ 176.108 Supervision of Class 1 (explosive) materials during loading, unloading, handling and stowage.**

(a) During the loading, unloading, handling and stowage of Class 1 (explosive) materials, a responsible person shall be in constant attendance during the entire operation to direct the loading, unloading, handling and stowage of Class 1 (explosive) materials, including the preparation of the holds. The responsible person must be aware of the hazards involved and the steps to be taken in an emergency, and must maintain sufficient contact with the master to ensure proper steps are taken in an emergency.

(b) Each person involved in the handling of Class 1 (explosive) materials on a vessel shall obey the orders of the responsible person.

(c) The responsible person must inspect all cargo-handling equipment to determine that it is in safe operating condition before it is used to handle Class 1 (explosive) materials.

**STOWAGE**

**§ 176.112 Applicability.**

The provisions of §§ 176.116(e), 176.118, and 176.120 of this subpart do not apply to Division 1.4 (explosive) materials, compatibility group S. Such materials may be stowed together with all other Class 1 (explosive) materials except those of compatibility group A or L. They must be segregated from other hazardous materials in accordance with table 176.83(b) of this part.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

**§ 176.116 General stowage conditions for Class 1 (explosive) materials.**

(a) *Heat and sources of ignition:* (1) Class 1 (explosive) materials must be stowed in a cool part of the ship and must be kept as cool as practicable while on board. Stowage must be well



away from all sources of heat, including steam pipes, heating coils, sparks, and flame.

(2) Except where the consignment of Class 1 (explosive) materials consists only of explosive *articles*, the wearing of shoes or boots with unprotected metal nails, heels, or tips of any kind is prohibited.

(b) *Wetness*: (1) Spaces where Class 1 (explosive) materials are stowed below deck must be dry. In the event of the contents of packages being affected by water when on board immediate advice must be sought from the shippers; pending this advice handling of the packages must be avoided.

(2) Bilges and bilge sections must be examined and any residue of previous cargo removed before Class 1 materials (explosive) are loaded onto the vessel.

(c) *Security*: All compartments, magazines, and cargo transport units containing Class 1 (explosive) materials must be locked or suitably secured in order to prevent unauthorized access.

(d) *Secure stowage*: Class 1 (explosive) materials must be securely stowed to prevent shifting in transit; where necessary, precautions must be taken to prevent cargo sliding down between the frames at the ship's sides.

(e) *Separation from accommodation spaces and machinery spaces*: (1) Class 1 (explosive) materials must be stowed as far away as practicable from any accommodation spaces or any machinery space and may not be stowed directly above or below such a space. The requirements in paragraphs (e)(2) through (e)(4) of this section are minimum requirements in addition to the applicable requirements of 46 CFR chapter I. Where the requirements of this subpart are less stringent than those of 46 CFR chapter I, the 46 CFR chapter I requirements must be satisfied for ships to which they are applicable.

(2) There must be a permanent A Class steel bulkhead between any accommodation space and any compartment containing Class 1 (explosive) materials. Division 1.1, 1.2, 1.3, or 1.5 materials may not be stowed within 3 m (10 feet) of this bulkhead; in the decks immediately above or below an accommodation space they must be stowed at least 3 m (10 feet) from the

line of this bulkhead projected vertically.

(3) There must be a permanent A Class steel bulkhead between a compartment containing Class 1 (explosive) materials and any machinery space. Class 1 (explosive) materials, except those in Division 1.4 (explosive), may not be stowed within 3 m (10 feet) of this bulkhead; and in the decks above or below the machinery space they must be stowed at least 3 m (10 feet) from the line of this bulkhead projected vertically. In addition to this separation, there must be insulation to Class A60 standard as defined in 46 CFR 72.05–10(a)(1) if the machinery space is one of Category ‘A’ unless the only Class 1 (explosive) materials carried are in Division 1.4S (explosive).

(4) Where Class 1 (explosive) materials are stowed away from bulkheads bounding any accommodation space or machinery space, the intervening space may be filled with cargo that is not readily combustible.

(f) *Under deck stowage of Class 1 (explosive) materials allocated stowage categories 09 and 10*:

(1) These Class 1 (explosive) materials must not be stowed in the same compartment or hold with other cargo that is readily combustible (such as items packaged in straw).

(2) The position of stowage of these Class 1 (explosive) materials must be such as to maintain direct access to the hatchway by not overstuffing with other cargo except for other Class 1 (explosive) materials.

(3) In all cases, all cargo within the compartment or hold, including Class 1 (explosive) materials stowed in cargo transport units, must be secured so as to eliminate the possibility of significant movement. Where an entire deck is used as a magazine, the stowage must be so arranged that the Class 1 (explosive) materials stowed therein must be removed from the ship before working any cargo in any decks above or below the space in the same hold.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, 45385, Aug. 28, 2001; 69 FR 76183, Dec. 20, 2004; 68 FR 61942, Oct. 30, 2003]

**§ 176.118 Electrical requirement.**

(a) Electrical equipment and cables installed in compartments in which Class 1 (explosive) materials are stowed which do not need to be energized during the voyage must be isolated from the supply so that no part of the circuit within the compartment is energized. The method of isolation may be by withdrawal of fuses, opening of switches or circuit breakers, or disconnection from bus bars. The means, or access to the means, of disconnection/reconnection must be secured by a locked padlock under the control of a responsible person.

(b) Electrical equipment and cables in a cargo space in which Class 1 (explosive) materials are stowed which are energized during the voyage for the safe operation of the ship must meet the requirements of subchapter J of 46 CFR chapter I. Before Class 1 (explosive) materials are loaded aboard a vessel, all cables must be tested by a skilled person to ensure that they are safe and to determine satisfactory grounding, insulation resistance, and continuity of the cable cores, metal sheathing or armoring.

(c) All Class 1 (explosive) materials must be stowed in a safe position relative to electrical equipment and cables. Additional physical protection must be provided where necessary to minimize possible damage to the electrical equipment or cables, especially during loading and unloading.

(d) Cable joints in the compartments must be enclosed in metal-clad junction boxes.

(e) All lighting equipment and cables must be of the fixed type, and must meet the relevant inspection, test, and installation standards of 46 CFR chapter I, subchapter J.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended by Amdt. 176-34, 58 FR 51533, Oct. 1, 1993]

**§ 176.120 Lightning protection.**

A lightning conductor grounded to the sea must be provided on any mast or similar structure on a vessel on which Class 1 (explosive) materials are stowed unless effective electrical bonding is provided between the sea and the mast or structure from its extremity

and throughout to the main body of the hull structure. (Steel masts in ships of all welded construction comply with this requirement).

**§§ 176.122-176.124 [Reserved]****§ 176.128 Magazine stowage types “A”, “C” and Special Stowage.**

(a) The stowage arrangements of Class 1 (explosive) substances and certain articles are subject to varying levels of containment, (except for compatibility group S substances), when stowed below deck. The levels are dependent on the hazard presented and the nature of the particular explosives involved. Columns (10A) and (10B) of the Hazardous Materials Table specify the stowage applicable to each substance or article. The different levels of containment are defined below as “A”, “C” and “Special”.

(b) *Magazine stowage type “A”*. Magazine stowage type A is required for those substances that must be kept clear of steelwork.

(c) *Magazine stowage type “C”*. Magazine stowage type C is required for those substances in compatibility group A.

(d) *Special Stowage*. Special Stowage is required for Explosive substances, n.o.s. in compatibility groups G or L, and for articles in compatibility groups G, H, L and K, which are particularly hazardous.

[69 FR 76183, Dec. 20, 2004]

**§ 176.130 Magazine stowage Type A.**

(a) In addition to protecting the Class 1 (explosive) materials and preventing unauthorized access, magazine stowage type A guards against friction between any spilled contents of packages and the vessel's sides and bulkheads.

(b) Class 1 (explosive) materials requiring magazine stowage type A must be stowed in a magazine which is tightly sheathed with wood on its inner sides and floor.

(c) When utilized as part of the magazine structure, the vessel's sides and bulkheads must be clean, free from rust or scale, and protected by battening or sweatboards spaced not more

## § 176.132

than 150 mm (6 inches) apart. All stanchions and other unprotected structural members must be similarly clean and battened. The underside of the deck above the magazine must be clean and free of rust and scale, but need not be battened.

(d) The top of the stow within the magazine must be at least 30 cm (12 inches) from the underside of the deck above.

(e) A type A magazine constructed in the square of a cargo space may not be loaded from the top.

(f) When other Class 1 (explosive) materials are stowed with Class 1 (explosive) materials for which magazine stowage type A is required, they or their packagings may have no exposed external parts made of ferrous metal or aluminum alloy.

## § 176.132 [Reserved]

EDITORIAL NOTE: For further information see 68 FR 61942, Oct. 30, 2003 and 69 FR 76184, Dec. 20, 2004.

## § 176.133 Magazine stowage Type C.

The construction requirements for magazine stowage type C are the same as for a closed cargo transport unit in § 176.63(e). In addition, the magazine must be located as near as practicable to the centerline of the vessel and must not be closer to the vessel's side than a distance equal to one-eighth of the vessel's beam or 2.4 m (8 feet), whichever is less.

[69 FR 76184, Dec. 20, 2004]

## § 176.134 Vehicles.

Closed vehicles may be used to transport Class 1 (explosive) materials requiring magazine stowage when carried by vessel if they meet the requirements of the appropriate magazine stowage type. See § 176.168 of this subpart for additional requirements relating to the transport of Class 1 (explosive) materials in vehicles.

## § 176.136 Special stowage.

(a) Special stowage is required for certain articles presenting both explosive and chemical hazards, such as smoke or lachrymatory (compatibility group G or H), toxic (compatibility group K), or substances and articles

## 49 CFR Ch. I (10–1–08 Edition)

which present a special risk (compatibility group L). Except as permitted in paragraph (c) of this section, Class 1 (explosive) materials requiring special stowage must be stowed on deck unless such stowage is impracticable and the COTP authorizes special stowage below deck. Where on deck stowage is recommended and an alternative stowage below deck is permitted by the COTP, the stowage must always be subject to special stowage.

(b) Class 1 (explosive) materials for which special stowage is required must be stowed as far away as practicable from living, accommodation, and working areas, and may not be overstowed. Closed cargo transport units in which such Class 1 (explosive) materials are stowed may not be located closer to the vessel's side than a distance equal to one-eighth of the vessel's beam or 2.4 m (8 feet), whichever is less.

(c) Class 1 (explosive) materials in compatibility groups G and H may be transported in steel magazines or in freight containers. If a freight container is used for this purpose, the floor of the freight container must be leakproof; for example, an all-metal container may be used and a fillet of cement or other material worked across the bottom of the door opening.

(d) Class 1 (explosive) materials stowed in one compartment may not be of more than one compatibility group, except the COTP may allow Class 1 (explosive) materials of compatibility groups G and H in separate steel magazines to be stowed in the same compartment, not less than 3 m (10 feet) apart.

(e) Class 1 (explosive) materials in compatibility groups K and L must be stowed in a steel magazine regardless of the stowage position in the vessel.

[69 FR 76184, Dec. 20, 2004]

## § 176.137 Portable magazine.

(a) Each portable magazine used for the stowage of Class 1 (explosive) materials on board vessels must meet the following requirements:

(1) It must be weather-tight, constructed of wood or metal lined with wood at least 2 cm (0.787 inch) thick, and with a capacity of no more than 3.1 cubic m (110 cubic feet).

(2) All inner surfaces must be smooth and free of any protruding nails, screws or other projections.

(3) If constructed of wood, a portable magazine must be framed of nominal 5 cm × 10 cm (2×4 inch) lumber, and sheathed with nominal 20 mm (0.787 inch) thick boards or plywood.

(4) When constructed of metal, the metal must be not less than 3.2 mm (0.126 inch) thick.

(5) Runners, bearers, or skids must be provided to elevate the magazine at least 10 cm (3.9 inches) from the deck. Padeyes, ring bolts, or other suitable means must be provided for securing.

(6) If the portable magazine has a door or hinged cover, the door or cover must have a strong hasp and padlock or equally effective means of securing.

(7) The portable magazine must be marked on its top and four sides, in letters at least 8 cm (3 inches) high, as follows:

EXPLOSIVES—HANDLE CAREFULLY—  
KEEP LIGHTS AND FIRE AWAY.

(b) A portable magazine which meets the requirements for a type 2 or type 3 magazine under 27 CFR part 55 subpart K may be used for the stowage of Class 1 (explosive) materials on board vessels.

(c) A portable magazine with a capacity exceeding 3.1 m<sup>3</sup> (110 cubic feet) may be used for the stowage of Class 1 (explosive) materials under such construction, handling, and stowage requirements as the COTP approves.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45185, Aug. 28, 2001]

#### § 176.138 Deck stowage.

(a) [Reserved]

(b) Class 1 (explosive) materials may not be stowed within a horizontal distance of 6 m (20 feet) from any fire, machinery exhaust, galley uptake, locker used for combustible stores, or other potential sources of ignition. They must be clear of walkways and cargo working areas, fire hydrants, steam pipes, and means of access; away from all other facilities necessary for the safe working of the vessel, and not less than a horizontal distance of 8 m (26 feet) from the bridge, accommodation areas, and lifesaving appliances.

(c) Where vessels are fitted with container fastening arrangements, freight containers containing Class 1 (explosive) materials may be overstowed by containers of compatible Class 1 (explosive) materials or non-hazardous cargo. Where vessels are not fitted with container fastening arrangements, freight containers loaded with Class 1 (explosive) materials may be stowed only on the bottom tier of the stowage.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 69 FR 76184, Dec. 20, 2004]

#### SEGREGATION

#### § 176.140 Segregation from other classes of hazardous materials.

(a) Class 1 (explosive) materials must be segregated from other packaged hazardous materials in accordance with § 176.83.

(b) Class 1 (explosive) materials must be segregated from bulk solid dangerous cargoes in accordance with the IMDG Code (IBR, see § 171.7 of this subchapter). Notwithstanding § 176.83(b), ammonium nitrate and sodium nitrate may be stowed together with blasting explosives, except those containing chlorates, provided the mixed stowage is treated as blasting explosives (see § 176.410(e)).

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 68 FR 45041, July 31, 2003; 68 FR 75748, Dec. 31, 2003]

#### § 176.142 Hazardous materials of extreme flammability.

(a) Except as allowed by paragraph (b) of this section, certain hazardous materials of extreme flammability may not be transported in a vessel carrying Class 1 (explosive) materials. This prohibition applies to the following liquid hazardous materials:

|                                                     |            |              |
|-----------------------------------------------------|------------|--------------|
| Carbon disulfide.                                   | UN1131 ... | Class 3      |
| Diethylzinc ...                                     | UN1366 ... | Division 4.2 |
| Dimethylzinc                                        | UN1370 ... | Division 4.2 |
| Magnesium alkyls.                                   | UN3053 ... | Division 4.2 |
| Methyl phosphonous di-chloride, pyrophoric liquid.. | NA2845 ... | Division 6.1 |

§ 176.144

49 CFR Ch. I (10–1–08 Edition)

|                                                                |            |              |
|----------------------------------------------------------------|------------|--------------|
| Nickel carbonyl.                                               | UN1259 ... | Division 6.1 |
| Pyrophoric liquid, inorganic, n.o.s..                          | UN3194 ... | Division 4.2 |
| Pyrophoric liquid, organic, n.o.s..                            | UN2845 ... | Division 4.2 |
| Organometallic substance, liquid, pyrophoric..                 | UN3392 ... | Division 4.2 |
| Organometallic substance, liquid, pyrophoric, water-reactive.. | UN3394 ... | Division 4.2 |

(b) The hazardous materials listed in paragraph (a) of this section may be transported in a vessel carrying the following Class 1 (explosive) materials as cargo:

(1) Division 1.4 (explosive) materials, compatibility group S.

(2) Explosive articles having the following proper shipping names and identification numbers (see column (4) of the §172.101 table) if designed for life-saving purposes and their total net explosive mass (weight) does not exceed 50 kg (110 lbs) per vessel:

(i) ARTICLES, PYROTECHNIC: UN Nos. 0428, 0429, 0430, 0431.

(ii) CARTRIDGES, FLASH: UN Nos. 0049, 0050.

(iii) CARTRIDGES, SIGNAL: UN Nos. 0054, 0312.

(iv) SIGNAL DEVICES, HAND: UN No. 0191.

(v) SIGNALS, DISTRESS: UN Nos. 0194, 0195.

(vi) SIGNALS, SMOKE: UN Nos. 0196, 0197, 0313.

(3) Class 1 (explosive) materials in compatibility groups C, D, and E if the total net explosive mass (weight) does not exceed 10 kg (22 pounds) per vessel.

(4) Explosive articles in compatibility group G, except fireworks and Class 1 (explosive) materials requiring special stowage if the total net explosive mass (weight) does not exceed 10 kg (22 pounds) per vessel.

(c) When a vessel carrying Class 1 (explosive) materials allowed under paragraph (b) of this section also carries a hazardous material of extreme flammability, that hazardous material must be stowed in a part of the vessel as remote as practicable from the Class 1 (explosive) materials.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 33438, June 21, 2001; 66 FR 45384, Aug. 28, 2001; 69 FR 76184, Dec. 20, 2004]

§ 176.144 Segregation of Class 1 (explosive) materials.

(a) Except as provided in §176.145 of this subchapter, stowage of Class 1 (explosive) materials within the same compartment, magazine, or cargo transport unit is subject to provisions contained in table 176.144(a).

TABLE 176.144(A)—AUTHORIZED MIXED STOWAGE FOR EXPLOSIVES

[An “X” indicates that explosives in the two different compatibility groups reflected by the location of the “X” may not be stowed in the same compartment, magazine, or cargo transport unit]

| Compatibility groups | A | B | C | D | E | F | G | H | J | K | L | N | S |
|----------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A .....              |   | X | X | X | X | X | X | X | X | X | X | X | X |
| B .....              | X |   | X | X | X | X | X | X | X | X | X | X |   |
| C .....              | X | X |   | 6 | 6 | 1 | X | X | X | X | X | 4 |   |
| D .....              | X | X | 6 |   | 6 | 1 | X | X | X | X | X | 4 |   |
| E .....              | X | X | 6 | 6 |   | 1 | X | X | X | X | X | 4 |   |
| F .....              | X | X | X | X | X |   | X | X | X | X | X | X |   |
| G .....              | X | X | 1 | 1 | 1 | X |   | X | X | X | X | X |   |
| H .....              | X | X | X | X | X | X |   | X | X | X | X | X |   |
| J .....              | X | X | X | X | X | X | X |   | X | X | X | X |   |
| K .....              | X | X | X | X | X | X | X | X |   | X | X | X |   |
| L .....              | X | X | X | X | X | X | X | X | X |   | 2 | X | X |
| N .....              | X | X | 4 | 4 | 4 | X | X | X | X | X | X | 3 | 5 |
| S .....              | X |   |   |   |   |   |   |   |   |   | X | 5 |   |

NOTES: 1. Explosive articles in compatibility group G, other than fireworks and those requiring special stowage, may be stowed with articles of compatibility groups C, D, and E, provided no explosive substances are carried in the same compartment, magazine or cargo transport unit.

2. Explosives in compatibility group L may only be stowed in the same compartment, magazine or cargo transport unit with identical explosives within compatibility group L.

3. Different types of articles of Division 1.6, compatibility group N, may only be transported together when it is proven that there is no additional risk of sympathetic detonation between the articles. Otherwise they must be treated as division 1.1.

4. When articles of compatibility group N are transported with articles or substances of compatibility groups C, D or E, the goods of compatibility group N must be treated as compatibility group D.

5. When articles of compatibility group N are transported together with articles or substances of compatibility group S, the entire load must be treated as compatibility group N.

6. Any combination of articles in compatibility groups C, D and E must be treated as compatibility group E. Any combination of substances in compatibility groups C and D must be treated as the most appropriate compatibility group shown in Table 2 of § 173.52 taking into account the predominant characteristics of the combined load. This overall classification code must be displayed on any label or placard on a unit load or cargo transport unit as prescribed in subpart E (Labeling) and subpart F (Placarding).

(b) Where Class 1 (explosive) materials of different compatibility groups are allowed to be stowed in the same compartment, magazine, or cargo transport unit, the stowage arrangements must conform to the most stringent requirements for the entire load.

(c) Where a mixed load of Class 1 (explosive) materials of different hazard divisions and/or stowage arrangements is carried within a compartment, magazine, or cargo transport unit, the entire load must be treated as belonging to the hazard division having the greatest hazard. (For example, if a load of Division 1.1 (explosive) materials is mixed with Division 1.3 (explosive) materials, the load is treated as a Division 1.1 (explosive) material as defined in § 173.50(b) of this subchapter and the stowage must conform to the most stringent requirements for the entire load).

(d) If some of the Class 1 (explosive) materials in a stowage mixture require magazine stowage, Class 1 (explosive) materials requiring ordinary stowage may be stowed in the same magazine. When the magazine is used for substances requiring Type A stowage, the other Class 1 (explosive) materials stowed therein must have no exposed parts of any ferrous metal or aluminum alloy, unless separated by a partition.

(e) Segregation on deck: When Class 1 (explosive) materials in different compatibility groups are carried on deck, they must be stored not less than 6 m (20 feet) apart unless they are allowed under Table 176.144(a) to be stowed in the same compartment, magazine, or cargo transport unit.

(f) On a barge used to transfer class 1 (explosive) materials from a waterfront facility to a vessel at an explosives anchorage (or from the vessel to the water front facility), if compliance with paragraph (e) of this section is not practicable, a sandbag barrier at least 0.6 m (2 feet) in thickness may be sub-

stituted for the 6 m (20 feet) separation.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, 45385, Aug. 28, 2001; 69 FR 76184, Dec. 20, 2004; 70 FR 56099, Sept. 23, 2005]

#### § 176.145 Segregation in single hold vessels.

(a) On board a vessel having a single cargo hold, Class 1 (explosive) materials in hazard division/compatibility group 1.1B and 1.2B may be stowed in the same compartment with substances of compatibility group D, provided:

(1) The net explosive weight of the compatibility group B explosive does not exceed 50 kg (110 pounds); and

(2) The compatibility group B explosive materials are stowed in a steel portable magazine that is stowed at least 6 m (20 feet) from the compatibility group D substances.

(b) Division/compatibility group 1.4B (explosive) materials may be stowed in the same compartment with substances of compatibility group D provided the Class 1 (explosive) materials of different compatibility groups are separated by either a distance of at least 6 m (20 feet) or by a steel partition.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

#### § 176.146 Segregation from non-hazardous materials.

(a) Except as required by paragraphs (b) and (c) of this section, Class 1 (explosive) materials need not be segregated from other cargo of a non-dangerous nature.

(b) Mail, baggage, and personal and household effects may not be stowed in the same compartment as, or in compartments immediately above or below, Class 1 (explosive) materials other than those in compatibility group S.

(c) Where Class 1 (explosive) materials are stowed against an intervening bulkhead, any mail on the other side of

## § 176.148

the bulkhead must be stowed away from it.

(d) In order to avoid contamination:

(1) An explosive substance or article which has a secondary POISON hazard label must be stowed “separated from” all foodstuffs, except when such materials are stowed in separate closed cargo transport units, the requirements for “away from” segregation apply.

(2) An explosive substance or article which has a secondary CORROSIVE hazard label must be stowed “away from” foodstuffs.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; 69 FR 76185, Dec. 20, 2004]

### PRECAUTIONS DURING LOADING AND UNLOADING

#### § 176.148 Artificial lighting.

Electric lights, except arc lights, are the only form of artificial lighting permitted when loading and unloading Class 1 (explosive) materials.

#### § 176.150 Radio and radar.

(a) Except as provided in paragraph (b) of this section, when Class 1 (explosive) materials (other than explosive articles in Division 1.4 [explosive] or any explosive substance) are loaded, unloaded, or handled, the responsible person must ensure that all sources of electromagnetic radiation such as radio and radar transmitters are deenergized by opening the main switches controlling the sources and tagging them to warn that the devices are not to be energized until loading or unloading has ceased.

(b) During the loading or unloading of all explosive articles (except those in Division 1.4 [explosive]), no radio or radar transmitter may be used within 50 m (164 feet) of such articles except for VHF transmitters the power output of which does not exceed 25 watts and of which no part of the antenna system is within 2 m (7 feet) of the Class 1 (explosive) materials.

(c) Explosive articles which are sensitive to electromagnetic radiation from external sources must be stowed at a safe distance from the vessel’s radio cabin, receiving and transmitting apparatus radio antenna or lead-in, and

## 49 CFR Ch. I (10–1–08 Edition)

radar installation, with due regard to the character of the vessel and the degree of screening-off of the explosive articles.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

#### § 176.154 Fueling (bunkering).

(a) Class 1 (explosive) materials, except those in compatibility group S, may not be loaded or unloaded when fueling (bunkering) is in progress except with the prior authorization of the COTP, and under conditions prescribed by that officer.

(b) Vessels containing Class 1 (explosive) materials may not be fueled (bunkered) with the hatches open unless authorized by the COTP.

#### § 176.156 Defective packages.

(a) No leaking, broken, or otherwise defective package containing Class 1 (explosive) materials, including packages which have been adversely affected by moisture, may be accepted for shipment. The master or person in charge of a vessel on which there is a defective package containing Class 1 (explosive) materials must seek advice from the shipper concerning withdrawal, repair, or replacement. No repair of damaged or defective package containing Class 1 (explosive) materials may be performed on board a vessel.

(b) No Class 1 (explosive) material, which for any reason has deteriorated or undergone a change of condition that increases the hazard attendant upon its conveyance or handling, may be moved in the port area, except as directed by the COTP.

(c) If any package of Class 1 (explosive) materials, or seal of a package of Class 1 (explosive) materials, appears to be damaged, that package must be set aside for examination and repair or otherwise legally disposed of as directed by the shipper.

(d) If any Class 1 (explosive) materials are spilled or released from a package, the responsible person must ensure that an appropriate emergency response is undertaken in accordance with the emergency response information required under § 172.602 of this subchapter. The master of the vessel must report each incident involving spillage

or release of Class 1 (explosive) materials to the COTP as soon as practicable.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991]

#### § 176.160 Protection against weather.

Any person loading or unloading packages containing Class 1 (explosive) materials shall take adequate measures to prevent these packages from becoming wet.

#### § 176.162 Security.

A responsible person must be present at all times when the hatches of spaces containing Class 1 (explosive) materials are open. No unauthorized person may be permitted to access spaces in which Class 1 (explosive) materials are stowed. Magazines must be secured against unauthorized entry when loading has been completed, or when loading or unloading is stopped. Packages containing Class 1 (explosive) materials may not be opened on board ship.

#### § 176.164 Fire precautions and fire-fighting.

(a) Matches, lighters, fire, and other ignition sources are prohibited on and near any vessel on which Class 1 (explosive) materials are being loaded, unloaded, or handled except in places designated by the master or the COTP.

(b) A fire hose of sufficient length to reach every part of the loading area with an effective stream of water must be laid and connected to the water main, ready for immediate use.

(c) No repair work may be carried out in a cargo space containing Class 1 (explosive) materials other than those of Division 1.4 (explosive). No welding, burning, cutting, or riveting operations involving the use of fire, flame, spark, or arc-producing equipment may be conducted on board except in an emergency; and, if in port, with the consent of the COTP.

(d) Each compartment, including a closed vehicle deck space, which contains Class 1 (explosive) materials must be provided with a fixed fire extinguishing system. Each adjacent cargo compartment either must be protected by a fixed fire extinguishing installation or must be accessible for firefighting operations.

(e) A vessel must have two sets of breathing apparatus and a power-operated fire pump, which, together with its source of power and sea connections, must be located outside the machinery space.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

#### PASSENGER VESSELS

#### § 176.166 Transport of Class 1 (explosive) materials on passenger vessels.

(a) Only the following Class 1 (explosive) materials may be transported as cargo on passenger vessels:

(1) Division 1.4 (explosive) materials, compatibility group S.

(2) Explosive articles designed for lifesaving purposes as identified in § 176.142(b)(2), if the total net explosive mass (weight) does not exceed 50 kg (110 pounds).

(3) Class 1 (explosive) materials in compatibility groups C, D, and E, if the total net explosive mass (weight) does not exceed 10 kg (22 pounds) per vessel.

(4) Articles in compatibility group G other than those requiring special stowage, if the total net explosive mass (weight) does not exceed 10 kg (22 pounds) per vessel.

(5) Articles in compatibility group B, if the total net explosive mass (weight) does not exceed 5 kg (11 pounds).

(b) Class 1 (explosive) materials which may be carried on passenger vessels are identified in column (10) of the § 172.101 table. They must be stowed in accordance with table 176.166(b).

TABLE 176.166(b)—STOWAGE ARRANGEMENTS IN PASSENGER VESSELS

| Class/Division | Samples, explosive | Goods, N.O.S. Class 1 | Goods shipped under a specific proper shipping name |   |   |   |   |     |   |     |     |     |     |   |   |
|----------------|--------------------|-----------------------|-----------------------------------------------------|---|---|---|---|-----|---|-----|-----|-----|-----|---|---|
|                |                    |                       | Compatibility group                                 |   |   |   |   |     |   |     |     |     |     |   |   |
|                |                    |                       | A                                                   | B | C | D | E | F   | G | H   | J   | K   | L   | N | S |
| 1.1 .....      | d .....            | d .....               | c..                                                 | e | e | e | e | c.. | e | —   | c.. | —   | c.. | — | — |
| 1.2 .....      | d .....            | d .....               | —                                                   | e | e | e | e | c.. | e | c.. | c.. | c.. | c.. | — | — |



TABLE 176.166(b)—STOWAGE ARRANGEMENTS IN PASSENGER VESSELS—Continued

| Class/Division | Samples, explosive | Goods, N.O.S. Class 1 | Goods shipped under a specific proper shipping name |   |   |   |   |     |   |     |     |     |     |   |   |
|----------------|--------------------|-----------------------|-----------------------------------------------------|---|---|---|---|-----|---|-----|-----|-----|-----|---|---|
|                |                    |                       | Compatibility group                                 |   |   |   |   |     |   |     |     |     |     |   |   |
|                |                    |                       | A                                                   | B | C | D | E | F   | G | H   | J   | K   | L   | N | S |
| 1.3 .....      | d .....            | d .....               | —                                                   | — | e | e | — | c.. | e | c.. | c.. | c.. | c.. | — | — |
| 1.4 .....      | d .....            | d .....               | —                                                   | b | b | b | b | c.. | b | —   | —   | —   | —   | — | a |
| 1.5 .....      | d .....            | d .....               | —                                                   | — | — | e | — | —   | — | —   | —   | —   | —   | — | — |
| 1.6 .....      | d .....            | d .....               | —                                                   | — | — | — | — | —   | — | —   | —   | —   | —   | e | — |

a—As for cargo ships, on deck or under deck.

b—As for cargo ships, on deck or under deck, in portable magazines only.

c—Prohibited.

d—As specified by the Associate Administrator, or the competent authority of the country in which the Class 1 (explosive) materials are loaded on the vessel.

e—In containers or the like, on deck only.

(c) Notwithstanding the provisions of paragraph (a) of this section, a combination of the substances and articles listed in paragraphs (a)(1) through (a)(5) of this section may be transported on the same passenger vessel provided the total net explosive mass (weight) of the combination of Class 1 (explosive) materials carried does not exceed the smallest quantity specified for any one of the substances or articles in the combination.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 65 FR 58630, Sept. 29, 2000; 66 FR 45384, 45385, Aug. 28, 2001].

#### CARGO TRANSPORT UNITS AND SHIPBORNE BARGES

#### § 176.168 Transport of Class 1 (explosive) materials in vehicle spaces.

(a) All transport vehicles and cargo must be properly secured.

(b) All transport vehicles used for the carriage of Class 1 (explosive) materials must be structurally serviceable as defined in § 176.172(a)(2).

(c) Vehicles used to transport Class 1 (explosive) materials must conform to the requirements in §§ 177.834 and 177.835 of this subchapter.

(d) Class 1 (explosive) materials which require special stowage must be transported in transport vehicles approved for the purpose by the Associate Administrator except that Class 1 (explosive) materials in compatibility group G or H may be carried in steel portable magazines or freight containers. Closed transport vehicles may be used as magazines; transport vehicles of other types may be used to transport Class 1 (explosive) materials which require ordinary stowage.

(e) Class 1 (explosive) materials of different compatibility groups may not be stowed in the same vehicle except as allowed in § 176.144 of this subpart.

(f) Vehicles containing different Class 1 (explosive) materials require no segregation from each other, except that these materials may be carried together under the provisions of § 176.144 of this subchapter. In all other instances, the vehicles must be “separated from” one another.

(g) All transport vehicles used for the transport of Class 1 (explosive) materials must have lashing arrangements for securing the vehicle on the ship and preventing the moving of the vehicle on its springs during the sea passage.

(h) Where a portable magazine or closed freight container is carried on a chassis, twist locks or other suitable securing arrangements must be provided and made secure.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001; 68 FR 61942, Oct. 30, 2003]

#### § 176.170 Transport of Class 1 (explosive) materials in freight containers.

(a) When Class 1 (explosive) materials are stowed in a freight container, the freight container, for the purposes of this subpart, may be regarded as a magazine but not as a separate compartment.

(b) Freight containers loaded with Class 1 (explosive) materials, except for explosives in Division 1.4, must not be stowed in the outermost row of containers.

(c) Freight containers used to transport Class 1 (explosive) materials for

which magazine stowage type A is required must have a floor consisting of tightly fitted wooden boards, plywood or equivalent non-metallic material, and a non-metallic lining.

(d) Class 1 (explosive) materials of different compatibility groups may not be stowed within the same freight container except as allowed in §176.144 of this subpart.

(e) On vessels, other than specially fitted container ships, freight containers containing Class 1 (explosive) materials must be stowed only in the lowest tier.

(f) Freight containers carrying different Class 1 (explosive) materials require no segregation from each other, if the provisions of §176.144 of this subpart allow the Class 1 (explosive) materials to be carried together in the same compartment. In all other instances, the containers must be "separated from" one another in accordance with §176.83(f) of this part.

(g) Freight containers carrying Class 1 (explosive) materials may not be handled on board a vessel with fork lift trucks unless approved by the COTP. This does not preclude the use of front-loading trucks using side-frame lifting equipment.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; 68 FR 45041, July 31, 2003; 69 FR 76185, Dec. 20, 2004]

**§176.172 Structural serviceability of freight containers and vehicles carrying Class 1 (explosive) materials on ships.**

(a) A freight container may not be offered for the carriage of Class 1 (explosive) materials unless the container is structurally serviceable as evidenced by a current CSC (International Convention for Safe Containers) approval plate and verified by a detailed visual examination as follows:

(1) Before a freight container or transport vehicle is packed with Class 1 (explosive) materials, it must be visually examined by the shipper to ensure it is structurally serviceable, free of any residue of previous cargo, and its interior walls and floors are free from protrusions.

(2) *Structurally serviceable* means the freight container or the vehicle cannot have major defects in its structural

components, such as top and bottom side rails, top and bottom end rails, door sill and header, floor cross members, corner posts, and corner fittings in a freight container. Major defects include—

(i) Dents or bends in the structural members greater than 19 mm (0.75 inch) in depth, regardless of length;

(ii) Cracks or breaks in structural members;

(iii) More than one splice or an improper splice (such as a lapped splice) in top or bottom end rails or door headers;

(iv) More than two splices in any one top or bottom side rail;

(v) Any splice in a door sill or corner post;

(vi) Door hinges and hardware that are seized, twisted, broken, missing, or otherwise inoperative;

(vii) Gaskets and seals that do not seal; or

(viii) For freight containers, any distortion of the overall configuration great enough to prevent proper alignment of handling equipment, mounting and securing chassis or vehicle, or insertion into ships' cells.

(3) In addition, deterioration of any component of the freight container or vehicle, regardless of the material of construction, such as rusted-out metal in sidewalls or disintegrated fiberglass, is prohibited. Normal wear, however, including oxidation (rust), slight dents and scratches, and other damage that does not affect serviceability or the weather-tight integrity of the units, is not prohibited.

(b) As used in paragraph (a) of this section, *splice* means any repair of a freight container main structural member which replaces material, except complete replacement of the member.

(c) All shipments of Class 1 (explosive) materials except those in Division 1.4 (explosive) must be accompanied by a statement, which may appear on the shipping paper, certifying that the freight container or the vehicle is structurally serviceable as defined in paragraph (a)(2) of this section.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

## § 176.174

### § 176.174 Transport of Class 1 (explosive) materials in shipborne barges.

(a) Fixed magazines may be built within a shipboard barge. Freight containers may be used as magazines within a barge.

(b) Shipborne barges may be used for the carriage of all types of Class 1 (explosive) materials. When carrying Class 1 (explosive) materials requiring special stowage, the following requirements apply:

(1) Class 1 (explosive) materials in compatibility group G or H must be stowed in freight containers.

(2) Class 1 (explosive) materials in compatibility group K or L must be stowed in steel magazines.

(c) Class 1 (explosive) materials of different compatibility groups may not be stowed within the same shipborne barge unless under § 176.144(b) of this subpart they are authorized to be stowed in the same compartment.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 69 FR 76185, Dec. 20, 2004]

#### HANDLING CLASS 1 (EXPLOSIVE) MATERIALS IN PORT

### § 176.176 Signals.

When Class 1 (explosive) materials are being loaded, handled, or unloaded on a vessel, the vessel must exhibit the following signals:

(a) By day, flag "B" (Bravo) of the international code of signals; and

(b) By night, an all-round fixed red light.

### § 176.178 Mooring lines.

(a) All lines used in mooring the vessel must be of sufficient strength, type, and number for the size of the vessel and local conditions.

(b) While the vessel is moored or anchored in a port area, towing wires of adequate size and length must be properly secured to mooring bits at the bow and stern ready for immediate use with the towing eyes passed outboard and kept at about water level.

(c) The mooring arrangements must be such that the vessel can be released quickly in an emergency.

### § 176.180 Watchkeeping.

Whenever Class 1 (explosive) materials are on board a vessel in port,

## 49 CFR Ch. I (10-1-08 Edition)

there must be sufficient crew on board to maintain a proper watch and to operate the propulsion and firefighting equipment in case of an emergency.

### § 176.182 Conditions for handling on board ship.

(a) *Weather conditions.* Class 1 (explosive) materials may not be handled in weather conditions which may seriously increase the hazards presented by the Class 1 (explosive) materials. During electrical storms, cargo operations must be halted and all hatches containing Class 1 (explosive) materials must be closed.

(b) *Darkness.* Class 1 (explosive) materials may not be handled on board a vessel during the hours of darkness unless prior consent has been obtained from the COTP.

(c) *Lighting.* The area where Class 1 (explosive) materials are handled, or where preparations are being made to handle Class 1 (explosive) materials, must be illuminated with lighting that is sufficient to safely perform the handling operation.

(d) *Protective equipment.* (1) A sufficient quantity of appropriate protective equipment must be provided for the personnel involved in handling Class 1 (explosive) materials.

(2) The protective equipment must provide adequate protection against the hazards specific to the Class 1 (explosive) materials handled.

(e) *Intoxicated persons.* No person under the influence of alcohol or drugs to such an extent that the person's judgment or behavior is impaired may participate in any operation involving the handling of Class 1 (explosive) materials. The master of the vessel must keep any such person clear of any areas where Class 1 (explosive) materials are being handled.

(f) *Smoking.* (1) Smoking is prohibited on the vessel while Class 1 (explosive) materials are being handled or stowed except in places designated by the master of the vessel.

(2) Conspicuous notices prohibiting smoking must be posted and clearly visible at all locations where Class 1 (explosive) materials are handled or stored.

(g) All hatches and cargo ports opening into a compartment in which Class

1 (explosive) materials are stowed must be kept closed except during loading and unloading of the compartment. After loading, hatches must be securely closed.

**§ 176.184 Class 1 (explosive) materials of Compatibility Group L.**

Class 1 (explosive) materials in compatibility group L may not be handled in a port area without the special permission of, and subject to any special precautions required by, the COTP.

**§ 176.190 Departure of vessel.**

When loading of Class 1 (explosive) materials is completed, the vessel must depart from the port area as soon as is reasonably practicable.

**§ 176.192 Cargo handling equipment for freight containers carrying Class 1 (explosive) materials.**

(a) Except in an emergency, only cargo handling equipment that has been specifically designed or modified for the handling of freight containers may be used to load, unload, or handle freight containers containing Division 1.1 or 1.2 (explosive) materials.

(b) The gross weight of a freight container containing Class 1 (explosive) materials may not exceed the safe working load of the cargo handling equipment by which it is handled.

[Amdt. 176-30, 55 FR 52696, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

**MAGAZINE VESSELS**

**§ 176.194 Stowage of Class 1 (explosive) materials on magazine vessels.**

(a) *General.* The requirements of this section are applicable to magazine vessels and are in addition to any other requirements in this subchapter.

(b) *Type vessel authorized.* A single deck vessel with or without a house on deck is the only type vessel that may be used as a magazine vessel. A magazine vessel may not be moved while Class 1 (explosive) materials are on board.

(c) *Location of explosives.* Division 1.1, 1.2, or 1.3 (explosive) materials, in excess of 2268 kg (5000 pounds), stored in any magazine vessel must be stowed below deck. No Class 1 (explosive) materials may be stowed on deck unless

the vessel is fitted with a deck house having a stowage area which meets the requirements in this subpart for the stowage of Class 1 (explosive) materials. Detonators, detonator assemblies and boosters with detonators, Division 1.1 (explosive) may not be stored on the same magazine vessel with other Division 1.1, 1.2, and 1.3 (explosive) materials.

(d) *Class 1 (explosive) materials storage spaces.* Any compartment on a magazine vessel used for the stowage of Class 1 (explosive) materials must be completely sealed with wood so as to provide a smooth interior surface. Each metal stanchion in the compartment must be boxed in the same manner. An overhead ceiling is not required when the overdeck is weather tight. All nail and bolt heads must be countersunk and any exposed metal must be covered with wood.

(e) *Initiating explosives, detonators and boosters with detonators.* No explosive substance in Division 1.1, compatibility group A may be stowed in the same compartment with any other Class 1 (explosive) materials when there are explosive substances in Division 1.1 or 1.2 (explosive) on the same magazine vessel. Detonators, detonator assemblies and boosters with detonators must be stowed at least 8 m (26 feet) from any bulkhead forming a boundary of a compartment containing any other Class 1 (explosive) materials.

(f) *Dry storage spaces.* A magazine vessel having a dry storage space capable of being used for any purpose whatsoever must have a cofferdam at least 61 cm (24 inches) wide fitted between the dry storage space and each adjacent compartment containing Class 1 (explosive) materials. The cofferdam must be constructed of wood or steel, formed by two tight athwartship bulkheads extending from the skin of the vessel to the overdeck. If the cofferdam extends to the weather deck, a watertight hatch must be fitted in the deck to provide access to the cofferdam.

(g) *Lighting.* Non-sparking, battery-powered, self-contained electric lanterns or non-sparking hand flashlights are the only means of artificial light authorized.

(h) *Living quarters.* Living quarters must be fitted on the inside with a non-

## § 176.200

combustible material approved by the Commandant, USCG. Bracketed ship's lamps are the only lighting fixtures authorized to be used in the living quarters. Any stove used for heating or cooking must be securely fastened and may not be mounted closer than 15 cm (5.9 inches) to the deck or sides of the house. Any smoke pipe for the stove which passes through the roof of the house must be kept at least 8 cm (3 inches) away from any woodwork. Each smoke pipe must be protected by a layer of non-combustible material approved by the Commandant, USCG, an air space of at least 2.54 cm (1 inch), and a metal collar of at least 1.5 mm (0.059 inch) sheet secured only on the weather side of the roof. There may be no opening from any living quarters into any stowage compartment.

(i) *Storage of other hazardous materials.* Magazine vessels having Class 1 (explosive) materials on board may not be used for the storage of any other hazardous material.

(j) *Magazine vessel's stores.* Hazardous materials used as stores on board any magazine vessel must comply with the requirements of 46 CFR part 147.

(k) *Matches.* Safety matches requiring a prepared surface for ignition are the only type of matches authorized to be possessed or used on board a magazine vessel. They must be kept in a metal box or can with a metal cover and stored in the custodian's living quarters.

(l) *Firearms.* Firearms and ammunition (other than cargo) are not permitted on board a magazine vessel.

(m) *Fire extinguishing equipment.* No Class 1 (explosive) materials may be loaded or stowed in, unloaded from, or handled on any magazine vessel unless four fire extinguishers that meet the requirements for Type A Size II or Type B Size III in 46 CFR part 95, subpart 95.50 are near and accessible to the magazines.

(n) *Supervision.* A magazine vessel containing Class 1 (explosive) materials must be continuously attended by a custodian employed for that purpose by the vessel's owner.

(o) *Unauthorized persons on magazine vessels.* The custodian of a magazine vessel shall prevent unauthorized persons from coming on board unless it is

## 49 CFR Ch. I (10–1–08 Edition)

necessary to abate a hazard to human life or a substantial hazard to property.

(p) *Repacking of Class 1 (explosive) materials on board.* No Class 1 (explosive) materials may be repacked on board a magazine vessel. Broken or damaged packages must be handled in accordance with the requirements of § 176.156. Packages requiring an emergency response must be handled in accordance with the emergency response information required under § 172.602 of this subchapter.

(q) *Work boat.* Each magazine vessel must be equipped with a work boat.

(r) *Life preservers.* One approved personal flotation device must be available for each person employed on a magazine vessel.

(s) *Fenders.* Each magazine vessel must be fitted with fenders in sufficient number and size to prevent any vessel tying up alongside from coming in contact with the hull.

[Amdt. 176–30, 55 FR 52696, Dec. 21, 1990, as amended by Amdt. 176–41, 61 FR 51339, Oct. 1, 1996; 66 FR 45185, 45384, 45385, Aug. 28, 2001]

### Subpart H—Detailed Requirements for Class 2 (Compressed Gas) Materials

SOURCE: Amdt. 176–30, 55 FR 52704, Dec. 21, 1990, unless otherwise noted.

#### § 176.200 General stowage requirements.

(a) Each package of Class 2 (compressed gas) material being transported by vessel must be prevented from making direct contact with the vessel's deck, side, or bulwark by dunnage, shoring, or other effective means.

(b) When cylinders of Class 2 (compressed gas) materials being transported by vessel are stowed in a horizontal position, each tier must be stowed in the cantlines of the tier below it, and the valves on cylinders in adjacent tiers must be at alternate ends of the stow. Each tier may be stepped back and the ends alternated in order to clear the flange. Lashing must be provided to prevent any shifting.

(c) When cylinders of Class 2 (compressed gas) materials being transported by vessel are stowed in a

vertical position they must be stowed upright in a block and cribbed or boxed in with suitable dunnage. The box or crib must be dunnaged at least 10 cm (3.9 inches) off any metal deck. The cylinders in the box or crib must be braced to prevent any shifting. The box or crib must be securely chocked and lashed to prevent any shifting.

(d) Any package containing Division 2.3 (poison gas) materials must be stowed separate from all foodstuffs.

(e) Class 2 (compressed gas) materials may not be stowed "on deck" over a hold or compartment containing coal.

(f) Class 2 (compressed gas) material must be kept as cool as practicable and be stowed away from all sources of heat and ignition.

[Amdt. 176-30, 55 FR 52704, Dec. 21, 1990, as amended at 68 FR 61942, Oct. 30, 2003]

#### **§ 176.205 Under deck stowage requirements.**

(a) When a Class 2 (compressed gas) material is stowed below deck, it must be stowed in a mechanically ventilated cargo space with no source of artificial heat and clear of living quarters. No bulkhead or deck of that hold or compartment may be a common boundary with any boiler room, engine room, coal bunker, galley or boiler room uptake.

(b) When Division 2.1 (flammable gas) materials are stowed below deck, they must be stowed in a hold or compartment which complies with paragraph (a) of this section and the following requirements:

(1) Each hold or compartment must be ventilated.

(2) Each hold or compartment must be equipped with an overhead water sprinkler system or fixed fire extinguishing system.

(3) Each electrical power line in the hold or compartment must be protected by a strong metal covering to prevent crushing by cargo being stowed against it.

(4) Except when fitted with electrical fixtures of the explosion-proof type, each electrical circuit serving the hold or compartment must be disconnected from all sources of power. No circuit may be energized until the Division 2.1 (flammable gas) cargo and any vapors have been removed from the hold or

compartment. Explosion-proof portable lighting may be used if the source of power is from electrical outlets outside the hold or compartment and above the weather deck.

(5) Any opening in a common bulkhead of an adjacent hold or compartment must be securely closed off and made gas-tight, unless the adjacent hold or compartment is also used for the stowage of Division 2.1 (flammable gas) materials.

(6) Full and efficient hatch covers must be used. Tarpaulins, if fitted, must be protected by dunnaging before overstowing with any cargo. Each tarpaulin must be in one piece and free of rents, tears, and holes.

(7) A fire screen must be fitted at the weather end of each vent duct leading from the hold or compartment. The fire screen must completely cover the open area. It must consist of two layers of corrosion-resistant metal wire of 20×20 mesh or finer, spaced not less than 1 cm (0.4 inch) or more than 4 cm (1.6 inches) apart. The screen may be removable if means for securing it in place when in service are provided.

(8) The hold or compartment may not be fitted with any gooseneck type vent trunk head.

(9) Any electrical apparatus located in the hold or compartment must be capable of being disconnected from its power source by a positive means located outside the hold or compartment.

[Amdt. 176-30, 55 FR 52704, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991]

#### **§ 176.210 On deck stowage requirements.**

Cylinders of Class 2 (compressed gas) materials being transported by vessel must be protected from radiant heat, including the direct rays of the sun, by structural erections or awnings. A tarpaulin covering the cylinders is not acceptable if it comes in contact with them.

[Amdt. 176-30, 55 FR 52704, Dec. 21, 1990, as amended at 66 FR 45185, Aug. 28, 2001]

#### **§ 176.220 Smoking or open flame and posting of warning signs.**

(a) Smoking or the use of open flame is prohibited in any hold or compartment containing a Division 2.1 (flammable gas) material, near any Division

## § 176.225

2.1 (flammable gas) material stowed on deck, or near any ventilator leading to a hold containing this material.

(b) A sign carrying the legend:

FLAMMABLE VAPORS  
KEEP LIGHTS AND FIRE AWAY  
NO SMOKING

must be conspicuously posted at each approach to an “on deck” Division 2.1 (flammable gas) material stowage area and near each cargo hold ventilator leading to a hold containing this material. The sign must be painted on a white background using red letters. The letters may not be less than 8 cm (3 inches) high.

### § 176.225 Stowage of chlorine.

Chlorine (UN 1017) must be stowed separate from copper or brass leaf sheets and from finely divided organic material.

### § 176.230 Stowage of Division 2.1 (flammable gas) materials.

Division 2.1 (flammable gas) materials transported in Specification 106A or 110A multi-unit car tanks must be stowed on deck only, and must be shaded from radiant heat.

## Subpart I—Detailed Requirements for Class 3 (Flammable) and Combustible Liquid Materials

SOURCE: Amdt. 176–30, 55 FR 52705, Dec. 21, 1990, unless otherwise noted.

### § 176.305 General stowage requirements.

(a) A Class 3 (flammable) or combustible liquid must be kept as cool as reasonably practicable and be stowed away from all sources of heat and ignition.

(b) Except as otherwise provided in § 176.76(g), a package containing a Class 3 (flammable) liquid and equipped with a vent or safety relief device must be stowed “on deck” only.

(c) The following requirements apply to each hold or compartment in which any Class 3 (flammable) or combustible liquids are being transported:

(1) The hold or compartment must be ventilated except that the stowage of non-bulk packages of Class 3 (flammable) liquids with a flash point above

## 49 CFR Ch. I (10–1–08 Edition)

23°C (73°F) (see 49 CFR 171.8 definitions) may be in non-ventilated holds.

(2) Stowage of a Class 3 (flammable) or combustible liquid within 6 m (20 feet) of a bulkhead which forms a boundary or deck of a boiler room, engine room, coal bunker, galley, or boiler room uptake is not permitted. If the amount of the liquid to be stowed in a hold will not permit compliance with the requirement for a 6 m (20 foot) separation, less separation distance is authorized if at least one of the following conditions exists:

(i) The bulkhead or deck is covered with at least 8 cm (3 inches) of insulation on the entire area subject to heat;

(ii) A temporary wooden bulkhead at least 5 cm (2 inches) thick is constructed in the hold at least 8 cm (3 inches) off an engine room or 15 cm (5.9 inches) off a boiler room bulkhead, covering the entire area of the bulkhead that is subject to heat, and the space between the permanent bulkhead and the temporary wooden bulkhead is filled with mineral wool or equivalent bulk noncombustible insulating material; or

(iii) A temporary wooden bulkhead is constructed of at least 2.5 cm (1 inch) thick tongue and groove sheathing, located 1 m (3 feet) from the boiler room or engine room bulkhead, and filled with sand to a height of 2 m (7 feet) above the tank top, or, if the cargo compartment is located between decks, 1 m (3 feet) of sand.

(3) Combustible liquids may not be stowed in a hold within 6 m (20 feet) of a common bulkhead with the engine room unless the means of vessel propulsion is internal combustion engines.

(4) Each cargo opening in a bulkhead of an adjacent hold must be securely closed off and made gas-tight, unless the adjacent hold is also used for the stowage of a Class 3 (flammable) or combustible liquid.

(d) In addition to the requirements specified in paragraph (b) of this section, the following requirements apply to each hold or compartment in which a Class 3 (flammable) liquid is transported:

(1) Full and effective hatch covers must be used. Tarpaulins, if fitted, must be protected by dunnaging before

overstowing with any cargo. Each tarpaulin must be in one piece and free of rents, tears, and holes;

(2) If Class 3 (flammable) liquids in excess of 1016 kg (2240 pounds) are stowed under deck in any one hold or compartment, a fire screen must be fitted at the weather end of each vent duct leading from that hold or compartment. The fire screen must completely cover the open area. It must consist of two layers of corrosion-resistant metal wire of 20×20 mesh or finer, spaced not less than 1 cm (0.4 inch) or more than 4 cm (1.6 inches) apart. The screen may be removable only if means for securing it in place when in service are provided;

(3) Each electrical power line in the hold or compartment must be protected by a strong metal covering to prevent crushing by cargo being stowed against it;

(4) Except when fitted with explosion-proof type electrical fixtures, each electrical circuit serving the hold or compartment must be disconnected from all sources of power from a point outside the hold or compartment containing flammable liquids. No circuit may be energized until the flammable liquids and any vapors have been removed from the hold or compartment. Explosion-proof type portable lighting may be used if the source of power is from electrical outlets outside the hold or compartment and above the weather deck; and

(5) A Class 3 (flammable) liquid in excess of 1016 kg (2240 pounds) may not be transported in any hold or compartment that is fitted with a gooseneck type of vent head.

(e) On a passenger vessel, each hold or compartment used to transport a Class 3 (flammable) liquid must be equipped with an overhead water sprinkler system or fixed fire-extinguishing system.

(f) On a passenger vessel, each hold or compartment used to transport Class 3 (flammable) liquids under a passenger space must have an overdeck of an A-60 type construction (see 46 CFR 72.05-10(c)(1)) or equivalent or have its underside covered with at least 8 cm (3 inches) of noncombustible insulation.

(g) No Class 3 (flammable) liquid in a drum or wooden case, having inside

packagings of more than 1 L (0.3 gallon) capacity each, may be stowed as a beam filler. A wooden barrel, a wooden box or a fiberboard box, with any Class 3 (flammable) liquid material in inside packagings of not more than 1 L (0.3 gallon) capacity each, may only be stowed as a beam filler if it is possible to stow and observe any "THIS SIDE UP" marking.

[Amdt. 176-30, 55 FR 52705, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991]

#### § 176.315 Fire protection requirements.

(a) For each 79,500 L (21,000 U.S. gallons) or part thereof of any Class 3 (flammable) or combustible liquid being transported on board a vessel in a portable tank, rail tank car, or a motor vehicle cargo tank, there must be provided at least one B-V semiportable foam (152 L/40 gallon capacity) (see 46 CFR 95.50), dry chemical (45.4 kg (100 pounds) minimum capacity) or equivalent fire extinguisher, or a fire hose fitted with an approved portable mechanical foam nozzle with pick-up tube and two 19 L (5 gallon) cans of foam liquid concentrate. Each foam system must be suitable for use with each Class 3 (flammable) or combustible liquid for which it is required. Each fire extinguisher must be accessible to the tank it is intended to cover.

(b) The fire hose at each fire hydrant in the vicinity of Class 3 (flammable) and combustible liquids stowage areas must be fitted with an approved combination solid stream and water spray nozzle.

(c) The pressure must be maintained in the vessel's fire mains during the loading and unloading of any Class 3 (flammable) or combustible liquids.

(d) Two 7 kg (15-pound) capacity hand portable dry chemical or two portable 10 L (2.6 gallons) foam-type extinguishers must be accessible to any packaged Class 3 (flammable) or combustible liquid and suitable for use with the lading.

(e) The requirements of this section do not apply to portable tanks and their contents authorized under 46 CFR part 98 or 46 CFR part 64.

[Amdt. 176-30, 55 FR 52705, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; 66 FR 45384, 45385, Aug. 28, 2001]



## § 176.320

### § 176.320 Use of hand flashlights.

Each hand flashlight used on deck near or in any hold or compartment containing a Class 3 (flammable) liquid, must be suitable for use in hazardous locations where fire or explosion hazards may exist.

### § 176.325 Smoking or open flame and posting of warning signs.

(a) Smoking or the use of open flame is prohibited in any hold or compartment containing a Class 3 (flammable) or combustible liquid, near any Class 3 (flammable) or combustible liquid stowed on deck, or near any ventilator leading to a hold containing such material.

(b) A sign carrying the legend:

FLAMMABLE VAPORS  
KEEP LIGHTS AND FIRE AWAY  
NO SMOKING

must be conspicuously posted at each approach to a Class 3 (flammable) or combustible liquid stowed “on deck” and near each cargo hold ventilator leading to a hold or compartment containing this material. This sign must be painted on a white background using red letters. The letters may not be less than 8 cm (3 inches) high.

### § 176.340 Combustible liquids in portable tanks.

Combustible liquids, having a flash point of 38°C (100°F) or higher, may be transported by vessel only in one of the portable tanks as specified below:

(a) Specification portable tanks authorized in § 173.241 of this subchapter.

(b) In nonspecification portable tanks, subject to the following conditions:

(1) Each portable tank must conform to a DOT specification 57 portable tank, except as otherwise provided in this paragraph;

(2) The rated capacity of the tank may not exceed 4,542 L (1,200 gallons), and the rated gross weight may not exceed 13,608 kg (30,000 pounds);

(3) The vibration test need not be performed;

(4) When the total surface area of the tank exceeds 14.9 square meters (160 square feet), the total emergency venting capacity must be determined in ac-

## 49 CFR Ch. I (10–1–08 Edition)

cordance with table I in § 178.345–10 of this subchapter;

(5) In place of a specification identification marking, the tank must be marked, on two sides in letters at least 5 cm (2 inches) high on contrasting background: “FOR COMBUSTIBLE LIQUIDS ONLY” and “49 CFR 176.340”. This latter marking constitutes certification by the person offering the combustible liquid materials for transportation that the portable tank conforms to this paragraph;

(6) Each tank must be made of steel;

(7) The design pressure of the tank must be not less than 62 kPa (9 psig);

(8) No pressure relief device may open at less than 34.4 kPa (5 psig);

(9) Each tank must be retested and marked at least once every 2 years in accordance with the requirements applicable to a DOT specification 57 portable tank in § 180.605 of this subchapter; and

(10) Each tank must conform to the provisions of § 173.24 of this subchapter and § 180.605(b) and (j) of this subchapter.

(c) Portable tanks approved by the Commandant (G-MSO), USCG.

[Amdt. 176–30, 55 FR 52705, Dec. 21, 1990, as amended by Amdt. 176–41, 61 FR 51339, Oct. 1, 1996; 62 FR 51561, Oct. 1, 1997; 66 FR 45185, 45384, Aug. 28, 2001; 67 FR 61015, Sept. 27, 2002; 68 FR 57633, Oct. 6, 2003]

## Subpart J—Detailed Requirements for Class 4 (Flammable Solids), Class 5 (Oxidizers and Organic Peroxides), and Division 1.5 Materials

SOURCE: Amdt. 176–30, 55 FR 52706, Dec. 21, 1990, unless otherwise noted.

### § 176.400 Stowage of Division 1.5, Class 4 (flammable solids) and Class 5 (oxidizers and organic peroxides) materials.

(a) Class 4 (flammable solid) material and Division 5.2 (organic peroxide) material must be kept as cool as reasonably practicable and be stowed away from all sources of heat and ignition.

(b) Division 5.2 (organic peroxide) material must be stowed away from living quarters or access to them. Division 5.2 (organic peroxide) material not requiring temperature control should

be protected from radiant heat, which includes direct rays of the sun, and stowed in a cool, well-ventilated area.

(c) No Division 1.5 or Class 5 (oxidizers and organic peroxides) material being transported by vessel may be stowed in the same hold or compartment with any readily combustible material such as a combustible liquid, a textile product, or with a finely divided substance, such as an organic powder.

(d) No Division 1.5 or Class 5 (oxidizers and organic peroxides) material being transported by vessel may be stowed in a hold or compartment containing sulfur in bulk, or in any hold or compartment above, below, or adjacent to one containing sulfur in bulk.

[Amdt. 176-30, 55 FR 52706, Dec. 21, 1990, as amended at 66 FR 45384, Aug. 28, 2001]

#### § 176.405 Stowage of charcoal.

(a) Before stowing charcoal Division 4.2 (flammable solid), UN 1361, NA 1361, or UN 1362 on a vessel for transportation, the hold or compartment in which it is to be stowed must be swept as clean as practicable. All residue of any former cargo, including especially a petroleum product, a vegetable or animal oil, nitrate, or sulfur, must be removed.

(b) Charcoal packed in bags and offered for transportation on board a vessel in a quantity over 1016 kg (2240 pounds) must be loaded so that the bags are laid horizontally and stacked with space for efficient air circulation. If the bags are not compactly filled and closed to avoid free space within, vertical and horizontal dunnage strips must be laid between the bags. Space for ventilating must be maintained near bulkheads, the shell of the vessel, the deck, and the overhead. No more than 40,600 kg (89,508 pounds) of charcoal may be stowed in a hold or compartment when other stowage space is available. If the unavailability of hold or compartment space requires the stowage of a larger amount, the arrangement of the stow for ventilation must be adjusted to ensure a sufficient venting effect.

(c) Any loose material from bags broken during loading must be removed. Broken bags may be repacked or have the closures repaired and the repaired bags restowed.

(d) Charcoal “screenings” packed in bags must be stowed to provide spaces for air circulation between tiers regardless of the quantity stowed.

#### § 176.410 Division 1.5 materials, ammonium nitrate and ammonium nitrate mixtures.

(a) This section prescribes requirements to be observed with respect to transportation of each of the following hazardous materials by vessel:

(1) Explosives, blasting, type E, and Explosives, blasting, type B, Division 1.5 compatibility group D, UN 0331 and UN 0332.

(2) Ammonium nitrate, Division 5.1 (oxidizer), UN1942.

(3) Ammonium nitrate fertilizer, Division 5.1 (oxidizer), UN 2067.

(b) This section does not apply to Ammonium nitrate fertilizer, Class 9, UN 2071 or to any non-acidic ammonium nitrate mixed fertilizer containing 13 percent or less ammonium nitrate, less than 5 percent organic material, and no other oxidizing material, and which does not meet the criteria for any other hazard set forth in part 173 of this subchapter.

(c) When Division 1.5 compatibility group D materials, ammonium nitrate, or any of the ammonium nitrate fertilizers listed in paragraph (a) of this section are transported by vessel:

(1) They must be stowed well away from any steam pipe, electric circuit, or other source of heat;

(2) Smoking is prohibited except in designated areas away from the material and “No-Smoking” signs must be posted in accordance with § 176.60;

(3) Fire hoses must be connected, laid out, and tested before loading or unloading commences; and

(4) A fire watch must be posted in the hold or compartment where the material is being loaded or unloaded.

(d) When any of the hazardous materials listed in paragraph (a) of this section is transported in bags by vessel:

(1) The requirements specified in paragraph (c) of this section must be complied with;

(2) The temperature of the bagged material may not exceed 54 °C (130 °F);

(3) Minimum dunnage and sweatboards must be used to prevent any friction or abrasion of bags, and to

## § 176.415

## 49 CFR Ch. I (10–1–08 Edition)

allow for the circulation of air and access of water in the event of fire;

(4) The bags must be stowed from side to side, out to the sweatboards;

(5) A space of 46 cm (18 inches) must be provided between any transverse bulkhead and the bags;

(6) The bags must be stowed so as to provide a 46 cm (18 inch) athwartship trench along the centerline of the compartment, continuous from top to bottom;

(7) The bags must be stowed so as to provide a 46 cm (18 inch) amidship trench running fore and aft from bulkhead to bulkhead;

(8) The bags may not be stowed less than 46 cm (18 inches) from any overhead deck beam;

(9) The bags must be stowed so as to provide vent flues 36 cm (14 inches) square at each corner of the hatch continuous from top to bottom;

(10) Trenching must be accomplished by alternating the direction of the bags in each tier (bulkheading); and

(11) The bags must be blocked and braced as necessary to prevent shifting of the bagged cargo adjacent to any trench area.

(e) Notwithstanding § 176.83(b) of this part, ammonium nitrate and ammonium nitrate fertilizers classed as Division 5.1 (oxidizers) materials, may be stowed in the same hold, compartment, magazine, or freight container with Class 1 materials (explosive), except those containing chlorates, in accordance with the segregation and separation requirements of § 176.144 of this part applying to Explosives, blasting, type B, and Explosives, blasting, type E, Division 1.5 compatibility group D.

(f) No mixture containing ammonium nitrate and any ingredient which would accelerate the decomposition of ammonium nitrate under conditions incident to transportation may be transported by vessel.

[Amdt. 176–30, 55 FR 52706, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; Amdt. 176–34, 58 FR 51533, Oct. 1, 1993; Amdt. 176–38, 60 FR 49111, Sept. 21, 1995; 65 FR 58630, Sept. 29, 2000; 66 FR 45384, Aug. 28, 2001; 68 FR 45041, July 31, 2003]

### **§ 176.415 Permit requirements for Division 1.5, ammonium nitrates, and certain ammonium nitrate fertilizers.**

(a) Except as provided in paragraph (b) of this section, before any of the following material is loaded on or unloaded from a vessel at any waterfront facility, the owner/operator must obtain written permission from the Captain of the Port (COTP).

(1) Ammonium nitrate UN1942, ammonium nitrate fertilizers containing more than 70% ammonium nitrate, or Division 1.5 compatibility group D materials packaged in a paper bag, burlap bag, or other nonrigid combustible packaging, or any rigid packaging with combustible inside packagings,

(2) Any other ammonium nitrate or ammonium nitrate fertilizer not listed in § 176.410(a) or (b).

(b) Any of the following may be loaded on or unloaded from a vessel at any waterfront facility without a permit:

(1) Ammonium nitrate, Division 5.1 (oxidizer) UN1942, in a rigid packaging with a noncombustible inside packaging.

(2) Ammonium nitrate fertilizer, Division 5.1 (oxidizer) UN 2067, if the nearest COTP is notified at least 24 hours in advance of any loading or unloading in excess of 454 kg (1,000 pounds).

(3) Division 1.5 compatibility group D material in a rigid packaging with noncombustible inside packaging.

(4) Ammonium nitrate fertilizer, Class 9, UN 2071.

(c) Before a permit may be issued, the following requirements must be met in addition to any others the COTP may impose:

(1) If the material is Explosives, blasting, type E, Division 1.5 compatibility group D, UN0332 in a combustible packaging or in a rigid packaging with a combustible inside packaging, it must be loaded or unloaded at a facility remote from populous areas, or high-value or high-hazard industrial facilities, so that in the event of fire or explosion, loss of lives and property may be minimized;

(2) If the material is a Division 1.5 compatibility group D material in a non-rigid combustible packaging and

loaded in a freight container or transport vehicle, it may be loaded or unloaded at a non-isolated facility if the facility is approved by the COTP.

(3) Each facility at which the material is to be loaded or unloaded must conform with the requirements of the port security and local regulations and must have an abundance of water readily available for fire fighting;

(4) Each facility at which the material is to be loaded or unloaded must be located so that each vessel to be loaded or unloaded has an unrestricted passage to open water. Each vessel must be moored bow to seaward, and must be maintained in a mobile status during loading, unloading, or handling operations by the presence of tugs or the readiness of engines. Each vessel must have two wire towing hawsers, each having an eye splice, lowered to the water's edge, one at the bow and the other at the stern; and

[Amdt. 176-30, 55 FR 52706, Dec. 21, 1990, as amended at 56 FR 66282, Dec. 20, 1991; Amdt. 176-35, 59 FR 49134, Sept. 26, 1994; 65 FR 58630, Sept. 29, 2000; 66 FR 45185, 45384, 45385, Aug. 28, 2001; 68 FR 45041, July 31, 2003]

### Subpart K [Reserved]

### Subpart L—Detailed Requirements for Division 2.3 (Poisonous Gas) and Division 6.1 (Poisonous) Materials

SOURCE: Amdt. 176-30, 55 FR 52708, Dec. 21, 1990, unless otherwise noted.

#### § 176.600 General stowage requirements.

(a) Each package required to have a POISON GAS, POISON INHALATION HAZARD, or POISON label, being transported on a vessel, must be stowed clear of living quarters and any ventilation ducts serving living quarters and separated from foodstuffs, except when the hazardous materials and the foodstuffs are in different closed cargo transport units.

(b) Each package required to have both a POISON GAS label and a FLAMMABLE GAS label thereon must be segregated as a Division 2.1 (flammable gas) material.

(c) Each package bearing a POISON label displaying the text “PG III” or bearing a “PG III” mark adjacent to the poison label must be stowed away from foodstuffs.

(d) Each package of Division 2.3 (poisonous gas) material or Division 6.1 (poison) material which also bears a FLAMMABLE LIQUID or FLAMMABLE GAS label must be stowed in a mechanically ventilated space, kept as cool as reasonably practicable, and be stowed away from all sources of heat and ignition.

[Amdt. 176-30, 55 FR 52708, Dec. 21, 1990, as amended at 57 FR 45465, Oct. 1, 1992; Amdt. 176-35, 59 FR 49134, Sept. 26, 1994; Amdt. 176-42, 62 FR 1236, Jan. 8, 1997; 64 FR 10782, Mar. 5, 1999; 69 FR 76185, Dec. 20, 2004]

#### § 176.605 Care following leakage or sifting of Division 2.3 (poisonous gas) and Division 6.1 (poisonous) materials.

A hold or compartment containing a package of a Division 2.3 (poisonous gas) or Division 6.1 (poisonous) material which has leaked or sifted must be thoroughly cleaned and decontaminated after the cargo is unloaded and before the hold or compartment is used for the stowage of any other cargo.

### Subpart M—Detailed Requirements for Radioactive Materials

SOURCE: Amdt. 176-15, 48 FR 10245, Mar. 10, 1983, unless otherwise noted.

#### § 176.700 General stowage requirements.

(a) [Reserved]

(b) A package of radioactive materials which in still air has a surface temperature more than 5 °C (9 °F) above the ambient air may not be over-stowed with any other cargo. If the package is stowed under deck, the hold or compartment in which it is stowed must be ventilated.

(c) For a shipment of radioactive materials requiring supplemental operational procedures, the shipper must furnish the master or person in charge of the vessel a copy of the necessary operational instructions.

(d) A person may not remain unnecessarily in a hold, or compartment, or

## § 176.704

in the immediate vicinity of any package on deck, containing radioactive materials.

(The information collection requirements in paragraph (d) were approved by the Office of Management and Budget under control numbers 2137-0534, 2137-0535 and 2137-0536)

[Amdt. 176-15, 48 FR 10245, Mar. 10, 1983, as amended by Amdt. 176-15, 48 FR 31220, July 7, 1983; Amdt. 176-23, 50 FR 41523, Oct. 11, 1985; Amdt. 176-37, 60 FR 50333, Sept. 28, 1995; 66 FR 45385, Aug. 28, 2001; 69 FR 3694, Jan. 26, 2004]

### § 176.704 Requirements relating to transport indices and criticality safety indices.

(a) The sum of the transport indices (TI's) for all packages of Class 7 (radioactive) materials on board a vessel may not exceed the limits specified in Table IIIA of this section.

(b) For freight containers containing packages and overpacks of Class 7 (radioactive) materials, the radiation level may not exceed 2 mSv per hour (200 mrem per hour) at any point on the outside surface and 0.1 mSv per hour (10 mrem per hour) at 2 m (6.6 ft) from the outside surface of the freight container.

(c) The limitations specified in Table IIIA of this section do not apply to consignments of LSA-I material.

(d) The sum of the criticality safety indices (CSI's) for all packages and overpacks of fissile Class 7 (radioactive) materials on board a vessel may not exceed the limits specified in Table IIIB of this section.

(e) Each group of fissile Class 7 (radioactive) material packages and overpacks, containing a sum of CSIs no greater than 50 for a non-exclusive use shipment, or no greater than 100 for an exclusive use shipment, must be separated from all other groups containing fissile material packages and overpacks by a distance of at least 6 m (20 ft) at all times.

(f) The limitations specified in paragraphs (a) through (c) of this section do not apply when the entire vessel is reserved or chartered for use by a single offeror under exclusive use conditions if—

(1) The number of packages of fissile Class 7 (radioactive) material satisfies the individual package CSI limits of

## 49 CFR Ch. I (10-1-08 Edition)

§ 173.457 of this subchapter, except that the total sums of CSI's in the last column of Table IIIB of this section, including table note (d) apply;

(2) A radiation protection program for the shipment has been established and approved by the competent authority of the flag state of the vessel and, when requested, by the competent authority at each port of call;

(3) Stowage arrangements have been predetermined for the whole voyage, including any consignments to be loaded at ports of call;

(4) The loading, transport and unloading are to be supervised by persons qualified in the transport of radioactive material; and

(5) The entire shipment operation is approved by the Associate Administrator in advance.

(g) Table IIIA is as follows:

TABLE IIIA—TI LIMITS FOR FREIGHT CONTAINERS AND CONVEYANCES

| Type of freight container or conveyance           | Limit on total sum of transport indices in a single freight container or aboard a conveyance |                     |
|---------------------------------------------------|----------------------------------------------------------------------------------------------|---------------------|
|                                                   | Not under exclusive use                                                                      | Under exclusive use |
| I. Freight container—small .....                  | 50 .....                                                                                     | N/A.                |
| II. Freight container—large .....                 | 50 .....                                                                                     | No limit.           |
| III. Vessel: <sup>a,b</sup>                       |                                                                                              |                     |
| 1. Hold, compartment or defined deck area:        |                                                                                              |                     |
| i. Packages, overpacks, small freight containers. | 50 .....                                                                                     | No limit.           |
| ii. Large freight containers.                     | 200 .....                                                                                    | No limit.           |
| 2. Total vessel:                                  |                                                                                              |                     |
| i. Packages, overpacks, small freight containers. | 200 .....                                                                                    | No limit.           |
| ii. Large freight containers.                     | No limit ....                                                                                | No limit.           |

#### NOTES:

<sup>a</sup>For vessels, the requirements in both 1 and 2 must be fulfilled.

<sup>b</sup>Packages or overpacks transported in or on a vehicle which are offered for transport in accordance with the provisions of § 173.441(b) of this subchapter may be transported by vessels provided that they are not removed from the vehicle at any time while on board the vessel.

(h) Table IIIB is as follows:

TABLE IIIB—CSI LIMITS FOR FREIGHT CONTAINERS AND CONVEYANCES

| Type of freight container or conveyance           | Limit on total sum of criticality safety indices in a single freight container or aboard a conveyance |                         |
|---------------------------------------------------|-------------------------------------------------------------------------------------------------------|-------------------------|
|                                                   | Not under exclusive use                                                                               | Under exclusive use     |
| I. Freight container—small .....                  | 50 .....                                                                                              | N/A.                    |
| II. Freight container—large .....                 | 50 .....                                                                                              | 100.                    |
| III. Vessel: <sup>a,b</sup>                       |                                                                                                       |                         |
| 1. Hold, compartment or defined deck area:        |                                                                                                       |                         |
| i. Packages, overpacks, small freight containers. | 50 .....                                                                                              | 100.                    |
| ii. Large freight containers.                     | 50 .....                                                                                              | 100.                    |
| 2. Total vessel:                                  |                                                                                                       |                         |
| i. Packages, overpacks, small freight containers. | 200 <sup>c</sup> .....                                                                                | 200 <sup>d</sup> .      |
| ii. Large freight containers.                     | No limit <sup>c</sup> ..                                                                              | No limit <sup>d</sup> . |

## NOTES:

<sup>a</sup>For vessels, the requirements in both 1 and 2 must be fulfilled.

<sup>b</sup>Packages or overpacks transported in or on a vehicle which are offered for transport in accordance with the provisions of § 173.441(b) of this subchapter may be transported by vessels provided that they are not removed from the vehicle at any time while on board the vessel. In that case, the entries under the heading "under exclusive use" apply.

<sup>c</sup>The consignment must be handled and stowed such that the total sum of CSIs in any group does not exceed 50, and such that each group is handled and stowed so that the groups are separated from each other by at least 6 m (20 ft).

<sup>d</sup>The consignment must be handled and stowed such that the total sum of CSIs in any group does not exceed 100, and such that each group is handled and stowed so that the groups are separated from each other by at least 6 m (20 ft). The intervening space between groups may be occupied by other cargo.

[69 FR 3694, Jan. 26, 2004]

**§ 176.708 Segregation distances.**

(a) Table IV lists minimum separation distances between radioactive materials and spaces regularly occupied by crew members or passengers, or between radioactive materials and undeveloped photographic film. It expresses the separation distances as a function of the sum of the TIs of all packages in a single consignment, in the case of 0 or 3 feet of intervening cargo of unit

density for persons, and 0, 3, or 6 feet of intervening cargo of unit density for undeveloped film. Cargo of unit density is stowed cargo with a density of 1 long ton (2240 lbs.) per 36 cubic feet. Separation distances may be interpolated from the table where appropriate.

(b) Table IV is to be used to determine the separation distance for undeveloped film.

(c) Category YELLOW-II or YELLOW-III packages or overpacks must not be transported in spaces occupied by passengers, except those exclusively reserved for couriers specially authorized to accompany such packages or overpacks.

(d) The separation distances for crew members and passengers may be determined by one of two methods:

(1) By using Table IV to determine the minimum distances between the radioactive material packages and regularly occupied spaces or living quarters; or

(2) For one or more consignments of Class 7 (radioactive) material to be loaded on board a vessel under the exclusive use conditions described in § 176.704(f), by demonstration through direct measurement, made and documented by a suitably qualified person, that for the indicated exposure times the dose rate in regularly occupied spaces or living quarters is less than—

(i) For the crew: 7.0  $\mu\text{Sv/h}$  (0.70 mrem/h) up to 700 hours in a year, or 1.8  $\mu\text{Sv/h}$  (0.18 mrem/h) up to 2750 hours in a year; and

(ii) For the passengers: 1.8  $\mu\text{Sv/h}$  (0.18 mrem/h) up to 550 hours in a year, taking into account any relocation of cargo during the voyage.

(e) Any departure from the segregation provisions should be approved by the competent authority of the flag state of the ship and, when requested, by the competent authority at each port of call.

(f) Table IV is as follows:

TABLE IV

| Sum of transport indexes of the packages | Minimum distance in feet from living accommodation or regularly occupied working space |    | Minimum distance in feet from undeveloped film and plates |    |   |              |    |    |              |    |    |               |     |    |               |     |    |               |     |    |               |     |    |               |     |    |
|------------------------------------------|----------------------------------------------------------------------------------------|----|-----------------------------------------------------------|----|---|--------------|----|----|--------------|----|----|---------------|-----|----|---------------|-----|----|---------------|-----|----|---------------|-----|----|---------------|-----|----|
|                                          |                                                                                        |    | 1 day voyage                                              |    |   | 2 day voyage |    |    | 4 day voyage |    |    | 10 day voyage |     |    | 20 day voyage |     |    | 30 day voyage |     |    | 40 day voyage |     |    | 50 day voyage |     |    |
|                                          |                                                                                        |    |                                                           |    |   |              |    |    |              |    |    |               |     |    |               |     |    |               |     |    |               |     |    |               |     |    |
|                                          |                                                                                        |    | Cargo thickness in feet (unit density)                    |    |   |              |    |    |              |    |    |               |     |    |               |     |    |               |     |    |               |     |    |               |     |    |
|                                          | Nil                                                                                    | 3  | Nil                                                       | 3  | 6 | Nil          | 3  | 6  | Nil          | 3  | 6  | Nil           | 3   | 6  | Nil           | 3   | 6  | Nil           | 3   | 6  | Nil           | 3   | 6  | Nil           | 3   | 6  |
| 0.1 to 0.5 .....                         | 5                                                                                      | X  | 6                                                         | X  | X | 8            | X  | X  | 11           | X  | X  | 17            | 4   | X  | 25            | 6   | X  | 30            | 7   | X  | 35            | 8   | X  | 39            | 9   | X  |
| 0.6 to 1 .....                           | 6                                                                                      | X  | 8                                                         | X  | X | 11           | X  | X  | 16           | 4  | X  | 25            | 6   | X  | 35            | 8   | X  | 42            | 10  | X  | 50            | 12  | X  | 55            | 13  | X  |
| 1.1 to 2 .....                           | 9                                                                                      | X  | 11                                                        | X  | X | 16           | 4  | X  | 22           | 5  | X  | 35            | 8   | X  | 50            | 12  | X  | 61            | 14  | X  | 70            | 17  | X  | 78            | 19  | X  |
| 2.1 to 3 .....                           | 10                                                                                     | X  | 14                                                        | X  | X | 19           | 5  | X  | 27           | 6  | X  | 42            | 10  | X  | 61            | 14  | X  | 74            | 18  | X  | 86            | 20  | X  | 96            | 23  | X  |
| 3.1 to 5 .....                           | 13                                                                                     | X  | 17                                                        | 4  | X | 25           | 6  | X  | 35           | 8  | X  | 55            | 13  | X  | 78            | 19  | X  | 96            | 23  | X  | 110           | 26  | X  | 124           | 29  | 7  |
| 5.1 to 10 .....                          | 19                                                                                     | 4  | 25                                                        | 6  | X | 35           | 8  | X  | 50           | 12 | X  | 78            | 19  | X  | 110           | 26  | X  | 135           | 33  | 8  | 155           | 37  | 9  | 175           | 42  | 10 |
| 10.1 to 20 .....                         | 26                                                                                     | 6  | 35                                                        | 8  | X | 50           | 12 | X  | 69           | 17 | X  | 110           | 26  | X  | 155           | 37  | 9  | 190           | 46  | 11 | 220           | 53  | 13 | 250           | 59  | 14 |
| 20.1 to 30 .....                         | 32                                                                                     | 8  | 43                                                        | 10 | X | 61           | 14 | X  | 85           | 20 | X  | 135           | 32  | 8  | 190           | 45  | 11 | 235           | 56  | 13 | 270           | 65  | 16 | 305           | 72  | 17 |
| 30.1 to 50 .....                         | 42                                                                                     | 10 | 55                                                        | 13 | X | 78           | 19 | X  | 110          | 26 | X  | 175           | 42  | 10 | 245           | 58  | 14 | 300           | 73  | 17 | 350           | 84  | 20 | 390           | 94  | 22 |
| 50.1 to 100 .....                        | 59                                                                                     | 14 | 78                                                        | 19 | X | 110          | 26 | X  | 155          | 37 | 9  | 245           | 59  | 14 | 350           | 82  | 20 | 430           | 105 | 24 | 515           | 118 | 28 | 550           | 130 | 32 |
| 100.1 to 150 .....                       | 72                                                                                     | 17 | 96                                                        | 23 | X | 135          | 32 | 8  | 190          | 46 | 11 | 300           | 72  | 17 | 425           | 100 | 24 | 525           | 125 | 30 | 600           | 145 | 35 | (7)           | 165 | 39 |
| 150.1 to 200 .....                       | 84                                                                                     | 20 | 110                                                       | 26 | X | 155          | 37 | 9  | 200          | 53 | 13 | 350           | 84  | 20 | 490           | 115 | 28 | 600           | 140 | 35 | (7)           | 165 | 40 | (7)           | 190 | 45 |
| 200.1 to 300 .....                       | 105                                                                                    | 24 | 135                                                       | 32 | X | 190          | 46 | 11 | 270          | 64 | 15 | 425           | 105 | 25 | 600           | 145 | 35 | (7)           | 180 | 42 | (7)           | 205 | 49 | (7)           | 230 | 55 |
| 300.1 to 400 .....                       | 120                                                                                    | 28 | 160                                                       | 37 | 9 | 220          | 53 | 13 | 310          | 75 | 18 | 500           | 120 | 28 | (7)           | 165 | 40 | (7)           | 205 | 49 | (7)           | 235 | 57 | (7)           | 265 | 63 |

NOTE:

(1) X—indicates that thickness of screening cargo is sufficient without any additional segregation distance.

(2) By using 6 feet of intervening unit density cargo for persons and 10 feet for film and plates, no distance shielding is necessary for any length of voyage specified.

(3) Using 1 steel bulkhead or steel deck—multiply segregation distance by 0.8. Using 2 steel bulkheads or steel decks—multiply segregation distance by 0.64.

(4) "Cargo of Unit Density" means cargo stowed at a density of 1 ton (long) per 36 cubic feet; where the density is less than this the depth of cargo specified must be increased in proportion.

(5) "Minimum distance" means the least in any direction whether vertical or horizontal from the outer surface of the nearest package.

(6) The figures below the double line of the table shall be used in those cases where the appropriate provisions of this class permit the sum of the transport indices to exceed 200.

(7) Not to be carried unless screening by other cargo and bulkheads can be arranged in accordance with the other columns.

[Amdt. 176-15, 48 FR 10245, Mar. 10, 1983, as amended by Amdt. 176-37, 60 FR 50334, Sept. 28, 1995; 69 FR 3695, Jan. 26, 2004]

**§ 176.710 Care following leakage or sifting of radioactive materials.**

(a) In case of fire, collision, or breakage involving any shipment of radioactive materials, other than materials of low specific activity, the radioactive materials must be segregated from unnecessary contact with personnel. In case of obvious leakage, or if the inside container appears to be damaged, the stowage area (hold, compartment, or deck area) containing this cargo must be isolated as much as possible to prevent radioactive material from entering any person's body through contact, inhalation, or ingestion. No person may handle the material or remain in the vicinity unless supervised by a qualified person.

(b) A hold or compartment in which leakage of radioactive materials has occurred may not be used for other cargo until it is decontaminated in accordance with the requirements of § 176.715.

(c) For reporting requirements, see § 171.15 of this subchapter.

**§ 176.715 Contamination control.**

Each hold, compartment, or deck area used for the transportation of low specific activity or surface contaminated object Class 7 (radioactive) materials under exclusive use conditions must be surveyed with appropriate radiation detection instruments after each use. Such holds, compartments, and deck areas may not be used again until the radiation dose rate at every accessible surface is less than 5 microSieverts per hour (0.5 mrem per hour), and the removable (non-fixed) radioactive surface contamination is not greater than the limits prescribed in § 173.443 of this subchapter.

[Amdt. 176-37, 60 FR 50334, Sept. 28, 1995]

**§ 176.720 Requirements for carriage of INF cargo in international transportation.**

In addition to all other applicable requirements of this subchapter, a vessel carrying INF cargo (see § 176.2, under INF cargo definition) in international transportation must meet the requirements of the INF Code contained in the

IMDG Code (IBR, see § 171.7 of this subchapter).

[68 FR 75748, Dec. 31, 2003]

**Subpart N—Detailed Requirements for Class 8 (Corrosive Materials) Materials**

SOURCE: Amdt. 176-30, 55 FR 52708, Dec. 21, 1990, unless otherwise noted.

**§ 176.800 General stowage requirements.**

(a) Each package required to have a Class 8 (corrosive) label thereon being transported on a vessel must be stowed clear of living quarters, and away from foodstuffs and cargo of an organic nature.

(b) A package of Class 8 (corrosive material) material may not be stowed over any readily combustible material.

(c) Glass carboys containing Class 8 (corrosive material) material may not be stowed on board any vessel, other than a barge, more than two tiers high unless each carboy is boxed or crated with neck protection extending to the sides of the carboy box. This protective construction must be strong enough to permit stacking one on top of the other.

(d) A Class 8 (corrosive material) material may not be stowed over a hold or compartment containing cotton unless the deck is of steel and the hatch is fitted with a tight coaming. In addition, the deck must be tight against leakage and the Class 8 (corrosive material) material may not be stowed over the square of the hatch.

(e) Each package of Class 8 (corrosive material) which also bears a FLAMMABLE LIQUID label must be stowed away from all sources of heat and ignition.

[Amdt. 176-30, 55 FR 52708, Dec. 21, 1990, as amended by Amdt. 176-39, 61 FR 18933, Apr. 29, 1996]

**§ 176.805 On deck stowage.**

When break bulk Class 8 (corrosive materials) materials being transported on a vessel are stowed on deck:

(a) Provisions must be made for leakage from any package to drain away from other cargo into an overboard scupper or freeing port. The drainage



## § 176.900

## 49 CFR Ch. I (10–1–08 Edition)

may not enter an enclosed drainage system other than a direct overboard scupper. If this stowage is not practical, sufficient clean dry sand must be placed under and around the lower tier of packages to absorb any leakage.

(b) Dunnage must be provided on the deck and arranged so that any leakage will be apparent.

(c) Any leakage that occurs must be washed down, using liberal quantities of water.

### **Subpart O—Detailed Requirements for Cotton and Vegetable Fibers, Motor Vehicles, and Asbestos**

SOURCE: Amdt. 176–30, 55 FR 52708, Dec. 21, 1990, unless otherwise noted.

#### **§ 176.900 Packaging and stowage of cotton and vegetable fibers; general.**

(a) Cotton, Class 9, NA 1365, Cotton, wet, Division 4.2, UN 1365, and other vegetable fibers, Division 4.1, being transported on a vessel must be securely baled and bound. Each bale of cotton or vegetable fibers must be covered with bagging on at least three-fourths of its surface, including both ends. Cut cotton linters may be accepted for transportation by vessel when baled and covered with bagging on the soft sides only if the bale is compressed to a density of at least 512 kg/m<sup>3</sup> (32 pounds per cubic foot) and it is bound with at least six bands per bale. Any poorly compressed bale or any bale having damaged bindings may not be transported by vessel.

(b) Each bale of Cotton, wet, Division 4.2, UN 1365 must be stowed separately from any bales of dry cotton or vegetable fibers, in a 'tween deck space, and not overstowed. Any bale of cotton or vegetable fibers which is saturated with water may not be transported by vessel.

(c) Bales of cotton or vegetable fibers showing contact with oil or grease may not be accepted for transportation by vessel.

(d) Cotton or vegetable fibers must be stowed in a hold or compartment in accordance with the following requirements:

(1) All traces of oil or residue in the hold or compartment must be removed;

(2) A recently painted hold or compartment may not be used unless it is thoroughly dry;

(3) Each ventilation cowl serving the hold or compartment must be fitted with a spark screen;

(4) When a bulkhead of the hold or compartment is common with a boiler room, engine room, coal bunker, or galley and subjected to heat, a wooden bulkhead must be erected between the bulkhead and any cotton or vegetable fibers. This wooden bulkhead must be at least 15 cm (6 inches) from a boiler room bulkhead, and at least 5 cm (2 inches) from an engine room, coal bunker, or galley bulkhead;

(5) Each 'tween deck hatch must be closed with hatch covers, tarpaulins, and dunnage; however, metal hatch covers which are sealed by other means to provide equivalent protection may be used;

(6) Each hold or compartment must be equipped with a carbon dioxide or overhead water sprinkler system or other approved fixed extinguishing system. Before loading, the extinguishing system must be examined to ensure that it is in good working condition; and

(7) Each hold or compartment must be clear of all debris and swept as clean as practicable before loading.

(e) Naked lights or any fire likely to produce sparks are not permitted on the vessel, dock area, or on any lighters alongside a vessel during loading or unloading of cotton or vegetable fibers.

(f) Upon completion of stowage, each opening must be completely closed. Where required, tarpaulins must be fitted and secured in place to provide a tight hold. During a period of temporary stoppage of loading or unloading, a hatch may be left open. However, during that period, a fire watch, designated by the master or officer-in-charge, must be stationed in the hold or compartment in which the cotton or vegetable fibers are stowed.

(g) At least one fire hose must be connected while cotton or vegetable fibers are being loaded or unloaded. Each fire pump must be operated before any loading or unloading. Pressure must be maintained on each fire main during

the loading and the fire hose laid out ready for immediate use. Portable fire extinguishers must be placed to be readily available. The fire hose, fire pumps, and fire extinguishers may be the vessel's equipment or shore equipment.

(h) Smoking is not permitted on a vessel during the loading or unloading of cotton or vegetable fibers except at those times and in those places designated by the master. "NO SMOKING" signs must be conspicuously posted in appropriate places, and the responsible person in charge of the loading or unloading (see § 176.57 of this part) must ensure that they are observed.

(i) Cotton or vegetable fibers may be stowed in the same hold over bulk sulfur if the sulfur has been trimmed and leveled and the hold is thoroughly cleaned of sulfur dust. A tight floor of two layers of 2.54 cm (1 inch) crossed clean dunnage boards must be laid on the sulfur before cotton or vegetable fibers are stowed. These substances may be stowed alongside each other in the same hold if they are separated by a tight dustproof wood bulkhead.

(j) Cotton or vegetable fibers may not be stowed in a 'tween deck hold over bulk sulfur in a lower hold unless the 'tween deck hold has been thoroughly cleaned of all sulfur dust and the 'tween deck hatch covers are in place and covered with tarpaulins and dunnage.

**§ 176.901 Stowage of cotton or vegetable fibers with rosin or pitch.**

(a) Unless impracticable, cotton or vegetable fibers being transported on a vessel may not be stowed in the same hold or compartment with rosin or pitch being transported on the same vessel.

(b) When separate stowage is impracticable, the cotton or vegetable fibers may be stowed in the same hold or compartment with rosin or pitch if they are separated by clean dunnage or a cargo of a non-combustible nature. When such stowage within the same hold or compartment involves large amounts of cotton or fibers or of rosin or pitch, the rosin or pitch must be floored off with at least two layers of

2.54 cm (1 inch) dunnaging and the cotton or vegetable fibers stowed above.

**§ 176.903 Stowage of cotton or vegetable fibers with coal.**

Cotton or vegetable fibers being transported on a vessel may not be stowed in the same hold with coal. They may be stowed in adjacent holds if the holds are separated by a tight steel bulkhead and the cotton or vegetable fibers are dunnaged at least 5 cm (2 inches) off the bulkhead. Cotton or vegetable fibers may be stowed in a hold above or below one in which coal is stowed if there is a tight steel intervening deck and all hatch covers are in place and covered with tarpaulins.

**§ 176.905 Motor vehicles or mechanical equipment powered by internal combustion engines.**

(a) A motor vehicle or any mechanized equipment powered by an internal combustion engine is subject to the following requirements when carried as cargo on a vessel:

(1) Before being loaded on a vessel, each motor vehicle or mechanical equipment must be inspected for fuel leaks and identifiable faults in the electrical system that could result in short circuit or other unintended electrical source of ignition. A motor vehicle or mechanical equipment showing any signs of leakage or electrical fault may not be transported.

(2) The fuel tank of a motor vehicle or mechanical equipment powered by liquid fuel may not be more than one-fourth full.

(3) Whenever possible, each vehicle or mechanical equipment must be stowed to allow for its inspection during transit.

(4) Motor vehicles or mechanical equipment may be refueled when necessary in the hold of a vessel in accordance with § 176.78.

(5) When a motor vehicle or mechanical equipment with fuel in its tanks is stowed in a closed freight container, a warning, displayed on a contrasting background and readily legible from a distance of 8 m (26 feet), must be affixed to the access doors to read as follows:

**WARNING—MAY CONTAIN EXPLOSIVE MIXTURES WITH AIR—KEEP IGNITION SOURCES AWAY WHEN OPENING**

(6) A motor vehicle or mechanical equipment's ignition key may not be in the ignition while the vehicle or mechanical equipment is stowed aboard a vessel.

(b) All equipment used for handling vehicles or mechanical equipment must be designed so that the fuel tank and fuel system of the vehicle or mechanical equipment are protected from stress that might cause rupture or other damage incident to handling.

(c) Two hand-held, portable, dry chemical fire extinguishers of at least 4.5 kg (10 pounds) capacity each must be separately located in an accessible location in each hold or compartment in which any motor vehicle or mechanical equipment is stowed.

(d) "NO SMOKING" signs must be conspicuously posted at each access opening to the hold or compartment.

(e) Each portable electrical light, including a flashlight, used in the stowage area must be an approved, explosion-proof type. All electrical connections for any portable light must be made to outlets outside the space in which any vehicle or mechanical equipment is stowed.

(f) Each hold or compartment must be ventilated and fitted with an overhead water sprinkler system or fixed fire extinguishing system.

(g) Each hold or compartment must be equipped with a smoke or fire detection system capable of alerting personnel on the bridge.

(h) All electrical equipment in the hold or compartment other than fixed explosion-proof lighting must be disconnected from its power source at a location outside the hold or compartment during the handling and transportation of any vehicle or mechanical equipment. Where the disconnecting means is a switch or circuit breaker, it must be locked in the open position until all vehicles have been removed.

(i) *Exceptions.* A motor vehicle or mechanical equipment is excepted from the requirements of this subchapter if the following requirements are met:

(1) The motor vehicle or mechanical equipment has an internal combustion

engine using liquid fuel that has a flash point less than 38 °C (100 °F), the fuel tank is empty, and the engine is run until it stalls for lack of fuel;

(2) The motor vehicle or mechanical equipment has an internal combustion engine using liquid fuel that has a flash point of 38 °C (100 °F) or higher, the fuel tank contains 418 L (110 gallons) of fuel or less, and there are no fuel leaks in any portion of the fuel system;

(3) The motor vehicle or mechanical equipment is stowed in a hold or compartment designated by the administration of the country in which the vessel is registered to be specially suited for vehicles. *See* 46 CFR 70.10–1 and 90.10–38 for U.S. vessels;

(4) The motor vehicle or mechanical equipment is electrically powered by wet electric storage batteries; or

(5) The motor vehicle or mechanical equipment is equipped with liquefied petroleum gas or other compressed gas fuel tanks, the tanks are completely emptied of liquid and the positive pressure in the tank does not exceed 2 bar (29 psig), the line from the fuel tank to the regulator and the regulator itself is drained of all trace of (liquid) gas, and the fuel shut-off valve is closed.

(j) Except as provided in § 173.220(d) of this subchapter, the provisions of this subchapter do not apply to items of equipment such as fire extinguishers, compressed gas accumulators, airbag inflators and the like which are installed in the motor vehicle or mechanical equipment if they are necessary for the operation of the vehicle or equipment, or for the safety of its operator or passengers.

[Amdt. 176–43, 62 FR 24742, May 6, 1997, as amended at 65 FR 58630, Sept. 29, 2000; 66 FR 45384, 45385, Aug. 28, 2001; 70 FR 56099, Sept. 23, 2005]

## **PART 177—CARRIAGE BY PUBLIC HIGHWAY**

### **Subpart A—General Information and Regulations**

Sec.

177.800 Purpose and scope of this part and responsibility for compliance and training.

177.801 Unacceptable hazardous materials shipments.

177.802 Inspection.

- 177.804 Compliance with Federal Motor Carrier Safety Regulations.
- 177.810 Vehicular tunnels.
- 177.816 Driver training.
- 177.817 Shipping papers.
- 177.823 Movement of motor vehicles in emergency situations.

#### Subpart B—Loading and Unloading

- 177.834 General requirements.
- 177.835 Class 1 materials.
- 177.837 Class 3 materials.
- 177.838 Class 4 (flammable solid) materials, Class 5 (oxidizing) materials, and Division 4.2 (pyroforic liquid) materials.
- 177.839 Class 8 (corrosive) materials.
- 177.840 Class 2 (gases) materials.
- 177.841 Division 6.1 and Division 2.3 materials.
- 177.842 Class 7 (radioactive) material.
- 177.843 Contamination of vehicles.

#### Subpart C—Segregation and Separation Chart of Hazardous Materials

- 177.848 Segregation of hazardous materials.

#### Subpart D—Vehicles and Shipments in Transit; Accidents

- 177.854 Disabled vehicles and broken or leaking packages; repairs.

#### Subpart E—Regulations Applying to Hazardous Material on Motor Vehicles Carrying Passengers for Hire

- 177.870 Regulations for passenger carrying vehicles.

AUTHORITY: 49 U.S.C. 5101–5127; 49 CFR 1.53.

#### Subpart A—General Information and Regulations

##### § 177.800 Purpose and scope of this part and responsibility for compliance and training.

(a) *Purpose and scope.* This part prescribes requirements, in addition to those contained in parts 171, 172, 173, 178 and 180 of this subchapter, that are applicable to the acceptance and transportation of hazardous materials by private, common, or contract carriers by motor vehicle.

(b) *Responsibility for compliance.* Unless this subchapter specifically provides that another person shall perform a particular duty, each carrier, including a connecting carrier, shall perform the duties specified and comply with all applicable requirements in this part

and shall ensure its hazmat employees receive training in relation thereto.

(c) *Responsibility for training.* A carrier may not transport a hazardous material by motor vehicle unless each of its hazmat employees involved in that transportation is trained as required by this part and subpart H of part 172 of this subchapter.

(d) *No unnecessary delay in movement of shipments.* All shipments of hazardous materials must be transported without unnecessary delay, from and including the time of commencement of the loading of the hazardous material until its final unloading at destination.

[Amdt. 177–79, 57 FR 20954, May 15, 1992, as amended by Amdt.177–86, 61 FR 18933, Apr. 29, 1996]

##### § 177.801 Unacceptable hazardous materials shipments.

No person may accept for transportation or transport by motor vehicle a forbidden material or hazardous material that is not prepared in accordance with the requirements of this subchapter.

[Amdt. 177–87, 61 FR 27175, May 30, 1996]

##### § 177.802 Inspection.

Records, equipment, packagings and containers under the control of a motor carrier, insofar as they affect safety in transportation of hazardous materials by motor vehicle, must be made available for examination and inspection by a duly authorized representative of the Department.

[Amdt. 177–71, 54 FR 25015, June 12, 1989]

##### § 177.804 Compliance with Federal Motor Carrier Safety Regulations.

Motor carriers and other persons subject to this part must comply with 49 CFR part 383 and 49 CFR parts 390 through 397 (excluding §§ 397.3 and 397.9) to the extent those regulations apply.

[68 FR 23842, May 5, 2003]

##### § 177.810 Vehicular tunnels.

Except as regards Class 7 (radioactive) materials, nothing contained in parts 170–189 of this subchapter shall be so construed as to nullify or supersede regulations established and published

## § 177.816

under authority of State statute or municipal ordinance regarding the kind, character, or quantity of any hazardous material permitted by such regulations to be transported through any urban vehicular tunnel used for mass transportation.

[Amdt. 177-52, 46 FR 5316, Jan. 19, 1981, as amended by Amdt. 177-78, 55 FR 52710, Dec. 21, 1990; 62 FR 51561, Oct. 1, 1997]

### § 177.816 Driver training.

(a) In addition to the training requirements of § 177.800, no carrier may transport, or cause to be transported, a hazardous material unless each hazmat employee who will operate a motor vehicle has been trained in the applicable requirements of 49 CFR parts 390 through 397 and the procedures necessary for the safe operation of that motor vehicle. Driver training shall include the following subjects:

- (1) Pre-trip safety inspection;
  - (2) Use of vehicle controls and equipment, including operation of emergency equipment;
  - (3) Operation of vehicle, including turning, backing, braking, parking, handling, and vehicle characteristics including those that affect vehicle stability, such as effects of braking and curves, effects of speed on vehicle control, dangers associated with maneuvering through curves, dangers associated with weather or road conditions that a driver may experience (e.g., blizzards, mountainous terrain, high winds), and high center of gravity;
  - (4) Procedures for maneuvering tunnels, bridges, and railroad crossings;
  - (5) Requirements pertaining to attendance of vehicles, parking, smoking, routing, and incident reporting; and
  - (6) Loading and unloading of materials, including—
    - (i) Compatibility and segregation of cargo in a mixed load;
    - (ii) Package handling methods; and
    - (iii) Load securement.
- (b) *Specialized requirements for cargo tanks and portable tanks.* In addition to the training requirement of paragraph (a) of this section, each person who operates a cargo tank or a vehicle with a portable tank with a capacity of 1,000 gallons or more must receive training applicable to the requirements of this

## 49 CFR Ch. I (10-1-08 Edition)

subchapter and have the appropriate State-issued commercial driver's license required by 49 CFR part 383. Specialized training shall include the following:

- (1) Operation of emergency control features of the cargo tank or portable tank;
- (2) Special vehicle handling characteristics, including: high center of gravity, fluid-load subject to surge, effects of fluid-load surge on braking, characteristic differences in stability among baffled, unbaffled, and multi-compartmented tanks; and effects of partial loads on vehicle stability;
- (3) Loading and unloading procedures;
- (4) The properties and hazards of the material transported; and
- (5) Retest and inspection requirements for cargo tanks.

(c) The training required by paragraphs (a) and (b) of this section may be satisfied by compliance with the current requirements for a Commercial Driver's License (CDL) with a tank vehicle or hazardous materials endorsement.

(d) Training required by paragraph (b) of this section must conform to the requirements of § 172.704 of this subchapter with respect to frequency and recordkeeping.

[Amdt. 177-79, 57 FR 20954, May 15, 1992, as amended by Amdt. 177-79, 58 FR 5852, Jan. 22, 1993]

### § 177.817 Shipping papers.

(a) *General requirements.* A person may not accept a hazardous material for transportation or transport a hazardous material by highway unless that person has received a shipping paper prepared in accordance with part 172 of this subchapter or the material is excepted from shipping paper requirements under this subchapter. A subsequent carrier may not transport a hazardous material unless it is accompanied by a shipping paper prepared in accordance with part 172 of this subchapter, except for § 172.204, which is not required.

(b) *Shipper certification.* An initial carrier may not accept a hazardous material offered for transportation unless the shipping paper describing the

material includes a shipper's certification which meets the requirements in §172.204 of this subchapter. Except for a hazardous waste, the certification is not required for shipments to be transported entirely by private carriage and for bulk shipments to be transported in a cargo tank supplied by the carrier.

(c) *Requirements when interlining with carriers by rail.* A motor carrier shall mark on the shipping paper required by this section, if it offers or delivers a freight container or transport vehicle to a rail carrier for further transportation:

(1) A description of the freight container or transport vehicle; and

(2) The kind of placard affixed to the freight container or transport vehicle.

(d) This subpart does not apply to a material that is excepted from shipping paper requirements as specified in §172.200 of this subchapter.

(e) *Shipping paper accessibility—accident or inspection.* A driver of a motor vehicle containing hazardous material, and each carrier using such a vehicle, shall ensure that the shipping paper required by this section is readily available to, and recognizable by, authorities in the event of accident or inspection. Specifically, the driver and the carrier shall:

(1) Clearly distinguish the shipping paper, if it is carried with other shipping papers or other papers of any kind, by either distinctively tabbing it or by having it appear first; and

(2) Store the shipping paper as follows:

(i) When the driver is at the vehicle's controls, the shipping paper shall be: (A) Within his immediate reach while he is restrained by the lap belt; and (B) either readily visible to a person entering the driver's compartment or in a holder which is mounted to the inside of the door on the driver's side of the vehicle.

(ii) When the driver is not at the vehicle's controls, the shipping paper shall be: (A) In a holder which is mounted to the inside of the door on the driver's side of the vehicle; or (B) on the driver's seat in the vehicle.

(f) *Retention of shipping papers.* Each person receiving a shipping paper required by this section must retain a

copy or an electronic image thereof, that is accessible at or through its principal place of business and must make the shipping paper available, upon request, to an authorized official of a Federal, State, or local government agency at reasonable times and locations. For a hazardous waste, the shipping paper copy must be retained for three years after the material is accepted by the initial carrier. For all other hazardous materials, the shipping paper copy must be retained for one year after the material is accepted by the carrier. Each shipping paper copy must include the date of acceptance by the carrier. A motor carrier (as defined in §390.5 of subchapter B of chapter III of subtitle B) using a shipping paper without change for multiple shipments of one or more hazardous materials having the same shipping name and identification number may retain a single copy of the shipping paper, instead of a copy for each shipment made, if the carrier also retains a record of each shipment made that includes shipping name, identification number, quantity transported, and date of shipment.

[Amdt. 177-35, 41 FR 16130, Apr. 15, 1976, as amended by Amdt. 177-35A, 41 FR 40691, Sept. 20, 1976; Amdt. 177-48, 45 FR 47670, Nov. 10, 1980; Amdt. 177-65, 50 FR 11055, Mar. 19, 1985; Amdt. 177-72, 53 FR 17160, May 13, 1988; 67 FR 46128, July 12, 2002; 67 FR 66574, Nov. 1, 2002; 68 FR 19277, Apr. 18, 2003; 68 FR 57633, Oct. 6, 2003; 70 FR 73165, Dec. 9, 2005]

#### **§ 177.823 Movement of motor vehicles in emergency situations.**

(a) A carrier may not move a transport vehicle containing a hazardous material unless the vehicle is marked and placarded in accordance with part 172 or as authorized in §171.12a of this subchapter, or unless, in an emergency:

(1) The vehicle is escorted by a representative of a state or local government;

(2) The carrier has permission from the Department; or

(3) Movement of the transport vehicle is necessary to protect life or property.

(b) *Disposition of contents of cargo tank when unsafe to continue.* In the event of a leak in a cargo tank of such a character as to make further transportation unsafe, the leaking vehicle should be removed from the traveled

portion of the highway and every available means employed for the safe disposal of the leaking material by preventing, so far as practicable, its spread over a wide area, such as by digging trenches to drain to a hole or depression in the ground, diverting the liquid away from streams or sewers if possible, or catching the liquid in containers if practicable. Smoking, and any other source of ignition, in the vicinity of a leaking cargo tank is not permitted.

(c) *Movement of leaking cargo tanks.* A leaking cargo tank may be transported only the minimum distance necessary to reach a place where the contents of the tank or compartment may be disposed of safely. Every available means must be utilized to prevent the leakage or spillage of the liquid upon the highway.

[Amdt. 177–35, 41 FR 16130, Apr. 15, 1976, as amended by Amdt. 177–67, 50 FR 41521, Oct. 11, 1985; Amdt. 177–86, 61 FR 18933, Apr. 29, 1996]

### Subpart B—Loading and Unloading

NOTE: For prohibited loading and storage of hazardous materials, see § 177.848.

#### § 177.834 General requirements.

(a) *Packages secured in a motor vehicle.* Any package containing any hazardous material, not permanently attached to a motor vehicle, must be secured against shifting, including relative motion between packages, within the vehicle on which it is being transported, under conditions normally incident to transportation. Packages having valves or other fittings must be loaded in a manner to minimize the likelihood of damage during transportation.

(b) Each package containing a hazardous material bearing package orientation markings prescribed in § 172.312 of this subchapter must be loaded on a transport vehicle or within a freight container in accordance with such markings and must remain in the correct position indicated by the markings during transportation.

(c) *No smoking while loading or unloading.* Smoking on or about any motor vehicle while loading or unloading any Class 1 (explosive), Class 3 (flammable

liquid), Class 4 (flammable solid), Class 5 (oxidizing), or Division 2.1 (flammable gas) materials is forbidden.

(d) *Keep fire away, loading and unloading.* Extreme care shall be taken in the loading or unloading of any Class 1 (explosive), Class 3 (flammable liquid), Class 4 (flammable solid), Class 5 (oxidizing), or Division 2.1 (flammable gas) materials into or from any motor vehicle to keep fire away and to prevent persons in the vicinity from smoking, lighting matches, or carrying any flame or lighted cigar, pipe, or cigarette.

(e) *Handbrake set while loading and unloading.* No hazardous material shall be loaded into or on, or unloaded from, any motor vehicle unless the handbrake be securely set and all other reasonable precautions be taken to prevent motion of the motor vehicle during such loading or unloading process.

(f) *Use of tools, loading and unloading.* No tools which are likely to damage the effectiveness of the closure of any package or other container, or likely adversely to affect such package or container, shall be used for the loading or unloading of any Class 1 (explosive) material or other dangerous article.

(g) [Reserved]

(h) *Precautions concerning containers in transit; fueling road units.* Reasonable care should be taken to prevent undue rise in temperature of containers and their contents during transit. There must be no tampering with such container or the contents thereof nor any discharge of the contents of any container between point of origin and point of billed destination. Discharge of contents of any container, other than a cargo tank or IM portable tank, must not be made prior to removal from the motor vehicle. Nothing contained in this paragraph shall be so construed as to prohibit the fueling of machinery or vehicles used in road construction or maintenance.

(i) *Attendance requirements—(1) Loading.* A cargo tank must be attended by a qualified person at all times when it is being loaded. The person who is responsible for loading the cargo tank is also responsible for ensuring that it is so attended.

(2) *Unloading.* A motor carrier who transports hazardous materials by a

cargo tank must ensure that the cargo tank is attended by a qualified person at all times during unloading. However, the carrier's obligation to ensure attendance during unloading ceases when:

(i) The carrier's obligation for transporting the materials is fulfilled;

(ii) The cargo tank has been placed upon the consignee's premises; and

(iii) The motive power has been removed from the cargo tank and removed from the premises.

(3) Except for unloading operations subject to §§ 177.837(d), 177.840(p), and 177.840(q), a qualified person "attends" the loading or unloading of a cargo tank if, throughout the process, he is alert and is within 7.62 m (25 feet) of the cargo tank. The qualified person attending the unloading of a cargo tank must have an unobstructed view of the cargo tank and delivery hose to the maximum extent practicable during the unloading operation.

(4) A person is "qualified" if he has been made aware of the nature of the hazardous material which is to be loaded or unloaded, he has been instructed on the procedures to be followed in emergencies, he is authorized to move the cargo tank, and he has the means to do so.

(j) Except for a cargo tank conforming to § 173.29(b)(2) of this subchapter, a person may not drive a cargo tank motor vehicle containing a hazardous material regardless of quantity unless:

(1) All manhole closures are closed and secured; and

(2) All valves and other closures in liquid discharge systems are closed and free of leaks.

(k) [Reserved]

(l) *Use of cargo heaters when transporting certain hazardous material.* Transportation includes loading, carrying, and unloading.

(1) *When transporting Class 1 (explosive) materials.* A motor vehicle equipped with a cargo heater of any type may transport Class 1 (explosive) materials only if the cargo heater is rendered inoperable by: (i) Draining or removing the cargo heater fuel tank; and (ii) disconnecting the heater's power source.

(2) *When transporting certain flammable material—(i) Use of combustion cargo heaters.* A motor vehicle equipped with a combustion cargo heater may be used to transport Class 3 (flammable liquid) or Division 2.1 (flammable gas) materials only if each of the following requirements are met:

(A) It is a catalytic heater.

(B) The heater's surface temperature cannot exceed 54 °C (130 °F)—either on a thermostatically controlled heater or on a heater without thermostatic control when the outside or ambient temperature is 16 °C (61 °F) or less.

(C) The heater is not ignited in a loaded vehicle.

(D) There is no flame, either on the catalyst or anywhere in the heater.

(E) The manufacturer has certified that the heater meets the requirements under paragraph (l)(2)(i) of this section by permanently marking the heater "MEETS DOT REQUIREMENTS FOR CATALYTIC HEATERS USED WITH FLAMMABLE LIQUID AND GAS."

(F) The heater is also marked "DO NOT LOAD INTO OR USE IN CARGO COMPARTMENTS CONTAINING FLAMMABLE LIQUID OR GAS IF FLAME IS VISIBLE ON CATALYST OR IN HEATER."

(G) Heater requirements under § 393.77 of this title are complied with.

(ii) *Effective date for combustion heater requirements.* The requirements under paragraph (l)(2)(i) of this section govern as follows:

(A) Use of a heater manufactured after November 14, 1975, is governed by every requirement under (l)(2)(i) of this section;

(B) Use of a heater manufactured before November 15, 1975, is governed only by the requirements under (l)(2)(i) (A), (C), (D), (F) and (G) of this section until October 1, 1976; and

(C) Use of any heater after September 30, 1976, is governed by every requirement under paragraph (l)(2)(i) of this section.

(iii) *Restrictions on automatic cargo-space-heating temperature control devices.* Restrictions on these devices have two dimensions: Restrictions upon use and restrictions which apply when the device must not be used.



(A) *Use restrictions.* An automatic cargo-space-heating temperature control device may be used when transporting Class 3 (flammable liquid) or Division 2.1 (flammable gas) materials only if each of the following requirements is met:

(1) Electrical apparatus in the cargo compartment is nonsparking or explosion proof.

(2) There is no combustion apparatus in the cargo compartment.

(3) There is no connection for return of air from the cargo compartment to the combustion apparatus.

(4) The heating system will not heat any part of the cargo to more than 54 °C (129 °F).

(5) Heater requirements under §393.77 of this title are complied with.

(B) *Protection against use.* Class 3 (flammable liquid) or Division 2.1 (flammable gas) materials may be transported by a vehicle, which is equipped with an automatic cargo-space-heating temperature control device that does not meet each requirement of paragraph (1)(2)(iii)(A) of this section, only if the device is first rendered inoperable, as follows:

(1) Each cargo heater fuel tank, if other than LPG, must be emptied or removed.

(2) Each LPG fuel tank for automatic temperature control equipment must have its discharge valve closed and its fuel feed line disconnected.

(m) Tanks constructed and maintained in compliance with Spec. 106A or 110A (§§179.300, 179.301 of this subchapter) that are authorized for the shipment of hazardous materials by highway in part 173 of this subchapter must be carried in accordance with the following requirements:

(1) Tanks must be securely chocked or clamped on vehicles to prevent any shifting.

(2) Equipment suitable for handling a tank must be provided at any point where a tank is to be loaded upon or removed from a vehicle.

(3) No more than two cargo carrying vehicles may be in the same combination of vehicles.

(4) Compliance with §§174.200 and 174.204 of this subchapter for combination rail freight, highway shipments

and for trailer-on-flat-car service is required.

(n) Specification 56, 57, IM 101, and IM 102 portable tanks, when loaded, may not be stacked on each other nor placed under other freight during transportation by motor vehicle.

(o) *Unloading of IM and UN portable tanks.* No person may unload an IM or UN portable tank while it remains on a transport vehicle with the motive power unit attached except under the following conditions:

(1) The unloading operation must be attended by a qualified person in accordance with the requirements in paragraph (i) of this section. The person performing unloading functions must be trained in handling emergencies that may occur during the unloading operation.

(2) Prior to unloading, the operator of the vehicle on which the portable tank is transported must ascertain that the conditions of this paragraph (o) are met.

(3) An IM or UN portable tank equipped with a bottom outlet as authorized in Column (7) of the §172.101 Table of this subchapter by assignment of a T Code in the appropriate proper shipping name entry, and that contains a liquid hazardous material of Class 3, PG I or II, or PG III with a flash point of less than 100 °F (38 °C); Division 5.1, PG I or II; or Division 6.1, PG I or II, must conform to the outlet requirements in §178.275(d)(3) of this subchapter; or, until October 1, 2004, be unloaded only at a facility conforming to the following—

(i) The applicable fire suppression requirements in 29 CFR 1910.106(e), (f), (g), (h), and (i);

(ii) The emergency shutdown requirements in 29 CFR 1910.119(f), 1910.120(q) and 1910.38(a);

(iii) The emergency response planning requirements in 29 CFR part 1910 and 40 CFR part 68;

(iv) An emergency discharge control procedure applicable to unloading operations, including instructions on handling emergencies that may occur during the unloading operation; and

(v) Public access to the unloading area must be controlled in a manner ensuring no public access during unloading.

(4) Alternatively, conformance to equivalent or more stringent non-federal requirements is authorized in place of paragraphs (o)(3)(i) through (o)(3)(iv) of this section.

[29 FR 18795, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 177.834, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 177.835 Class 1 materials.

(See also § 177.834 (a) to (j).)

(a) *Engine stopped.* No Class 1 (explosive) materials shall be loaded into or on or be unloaded from any motor vehicle with the engine running.

(b) *Care in loading, unloading, or other handling of Class 1 (explosive) materials.* No bale hooks or other metal tools shall be used for the loading, unloading, or other handling of Class 1 (explosive) materials, nor shall any package or other container of Class 1 (explosive) materials, except barrels or kegs, be rolled. No packages of Class 1 (explosive) materials shall be thrown or dropped during process of loading or unloading of Class 1 (explosive) materials. Special care shall be exercised to the end that packages or other containers containing Class 1 (explosive) materials shall not catch fire from sparks or hot gases from the exhaust tailpipe.

(1) Whenever tarpaulins are used for covering Class 1 (explosive) materials, they shall be secured by means of rope, wire, or other equally efficient tie downs. Class 1 (explosive) materials placards or markings required by § 177.823 shall be secured, in the appropriate locations, directly to the equipment transporting the Class 1 (explosive) materials. If the vehicle is provided with placard boards, the placards must be applied to these boards.

(2) [Reserved]

(c) *Class 1 (explosive) materials on vehicles in combination.* Division 1.1 or 1.2 (explosive) materials may not be loaded into or carried on any vehicle or a combination of vehicles if:

(1) More than two cargo carrying vehicles are in the combination;

(2) Any full trailer in the combination has a wheel base of less than 184 inches;

(3) Any vehicle in the combination is a cargo tank which is required to be marked or placarded under § 177.823; or

(4) The other vehicle in the combination contains any:

(i) Substances, explosive, n.o.s., Division 1.1A (explosive) material (Initiating explosive),

(ii) Packages of Class 7 (radioactive) materials bearing "Yellow III" labels,

(iii) Division 2.3, Hazard Zone A or Hazard Zone B materials or Division 6.1, PG I, Hazard Zone A materials, or

(iv) Hazardous materials in a portable tank or a DOT specification 106A or 110A tank.

(d) [Reserved]

(e) *No sharp projections inside body of vehicles.* No motor vehicle transporting any kind of Class 1 (explosive) material shall have on the interior of the body in which the Class 1 (explosive) materials are contained, any inwardly projecting bolts, screws, nails, or other inwardly projecting parts likely to produce damage to any package or container of Class 1 (explosive) materials during the loading or unloading process or in transit.

(f) *Class 1 (explosive) materials vehicles, floors tight and lined.* Motor vehicles transporting Division 1.1, 1.2, or 1.3 (explosive) materials shall have tight floors; shall have that portion of the interior in contact with the load lined with either non-metallic material or non-ferrous metals, except that the lining is not required for truck load shipments loaded by the Departments of the Army, Navy or Air Force of the United States Government provided the Class 1 (explosive) materials are of such nature that they are not liable to leakage of dust, powder, or vapor which might become the cause of an explosion. The interior of the cargo space must be in good condition so that there will not be any likelihood of containers being damaged by exposed bolts, nuts, broken side panels or floor boards, or any similar projections.

(g) No detonator assembly or booster with detonator may be transported on the same motor vehicle with any Division 1.1, 1.2 or 1.3 material (except other detonator assemblies, boosters

with detonators or detonators), detonating cord Division 1.4 material or Division 1.5 material. No detonator may be transported on the same motor vehicle with any Division 1.1, 1.2 or 1.3 material (except other detonators, detonator assemblies or boosters with detonators), detonating cord Division 1.4 material or Division 1.5 material unless—

(1) It is packed in a specification MC 201 (§178.318 of this subchapter) container; or

(2) The package conforms with requirements prescribed in §173.62 of this subchapter, and its use is restricted to instances when—

(i) There is no Division 1.1, 1.2, 1.3 or 1.5 material loaded on the motor vehicle; and

(ii) A separation of 61 cm (24 inches) is maintained between each package of detonators and each package of detonating cord; or

(3) It is packed and loaded in accordance with a method approved by the Department. One method approved by the Department requires that—

(i) The detonators are in packagings as prescribed in §173.63 of this subchapter which in turn are loaded into suitable containers or separate compartments; and

(ii) That both the detonators and the container or compartment meet the requirements of the Institute of Makers of Explosives' Safety Library Publication No. 22 (IBR, see §171.7 of this subchapter).

(h) *Lading within body or covered tailgate closed.* Except as provided in paragraph (g) of this section, dealing with the transportation of liquid nitroglycerin, desensitized liquid nitroglycerin or diethylene glycol dinitrate, all of that portion of the lading of any motor vehicle which consists of Class 1 (explosive) materials shall be contained entirely within the body of the motor vehicle or within the horizontal outline thereof, without overhang or projection of any part of the load and if such motor vehicle has a tailboard or tailgate, it shall be closed and secured in place during such transportation. Every motor vehicle transporting Class 1 (explosive) materials must either have a closed body or have the body thereof covered with a tarpaulin, and

in either event care must be taken to protect the load from moisture and sparks, except that subject to other provisions of these regulations, Class 1 (explosive) materials other than black powder may be transported on flat-bed vehicles if the explosive portion of the load on each vehicle is packed in fire and water resistant containers or covered with a fire and water resistant tarpaulin.

(i) *Class 1 (explosive) materials to be protected against damage by other lading.* No motor vehicle transporting any Class 1 (explosive) material may transport as a part of its load any metal or other articles or materials likely to damage such Class 1 (explosive) material or any package in which it is contained, unless the different parts of such load be so segregated or secured in place in or on the motor vehicle and separated by bulkheads or other suitable means as to prevent such damage.

(j) *Transfer of Class 1 (explosive) materials en route.* No Division 1.1, 1.2, or 1.3 (explosive) material shall be transferred from one container to another, or from one motor vehicle to another vehicle, or from another vehicle to a motor vehicle, on any public highway, street, or road, except in case of emergency. In such cases red electric lanterns, red emergency reflectors or red flags shall be set out in the manner prescribed for disabled or stopped motor vehicles. (See Motor Carrier Safety Regulations, part 392 of this title.) In any event, all practicable means, in addition to these hereinbefore prescribed, shall be taken to protect and warn other users of the highway against the hazard involved in any such transfer or against the hazard occasioned by the emergency making such transfer necessary.

[29 FR 18795, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 177.835, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 177.837 Class 3 materials.**

(See also §177.834 (a) to (j).)

(a) *Engine stopped.* Unless the engine of a cargo tank motor vehicle is to be used for the operation of a pump, Class

3 material may not be loaded into, or on, or unloaded from any cargo tank motor vehicle while the engine is running. The diesel engine of a cargo tank motor vehicle may be left running during the loading and unloading of a Class 3 material if the ambient atmospheric temperature is at or below  $-12^{\circ}\text{C}$  ( $10^{\circ}\text{F}$ ).

(b) *Bonding and grounding containers other than cargo tanks prior to and during transfer of lading.* For containers which are not in metallic contact with each other, either metallic bonds or ground conductors shall be provided for the neutralization of possible static charges prior to and during transfers of Class 3 (flammable liquid) materials between such containers. Such bonding shall be made by first connecting an electric conductor to the container to be filled and subsequently connecting the conductor to the container from which the liquid is to come, and not in any other order. To provide against ignition of vapors by discharge of static electricity, the latter connection shall be made at a point well removed from the opening from which the Class 3 (flammable liquid) material is to be discharged.

(c) *Bonding and grounding cargo tanks before and during transfer of lading.* (1) When a cargo tank is loaded through an open filling hole, one end of a bond wire shall be connected to the stationary system piping or integrally connected steel framing, and the other end to the shell of the cargo tank to provide a continuous electrical connection. (If bonding is to the framing, it is essential that piping and framing be electrically interconnected.) This connection must be made before any filling hole is opened, and must remain in place until after the last filling hole has been closed. Additional bond wires are not needed around All-Metal flexible or swivel joints, but are required for nonmetallic flexible connections in the stationary system piping. When a cargo tank is unloaded by a suction-piping system through an open filling hole of the cargo tank, electrical continuity shall be maintained from cargo tank to receiving tank.

(2) When a cargo tank is loaded or unloaded through a vapor-tight (not open hole) top or bottom connection,

so that there is no release of vapor at a point where a spark could occur, bonding or grounding is not required. Contact of the closed connection must be made before flow starts and must not be broken until after the flow is completed.

(3) Bonding or grounding is not required when a cargo tank is unloaded through a nonvapor-tight connection into a stationary tank provided the metallic filling connection is maintained in contact with the filling hole.

(d) *Unloading combustible liquids.* For a cargo tank unloading a material meeting the definition for combustible liquid in §173.150(f) of this subchapter, the qualified person attending the unloading operation must remain within 45.72 meters (150 feet) of the cargo tank and 7.62 meters (25 feet) of the delivery hose and must observe both the cargo tank and the receiving container at least once every five minutes during unloading operations that take more than five minutes to complete.

[29 FR 18795, Dec. 29, 1964]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §177.837, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 177.838 Class 4 (flammable solid) materials, Class 5 (oxidizing) materials, and Division 4.2 (pyroforic liquid) materials.**

(See also §177.834 (a) to (j).)

(a) *Lading within body or covered; tailgate closed; pick-up and delivery.* All of that portion of the lading of any motor vehicle transporting Class 4 (flammable solid) or Class 5 (oxidizing) materials shall be contained entirely within the body of the motor vehicle and shall be covered by such body, by tarpaulins, or other suitable means, and if such motor vehicle has a tailboard or tailgate, it shall be closed and secured in place during such transportation: *Provided, however,* That the provisions of this paragraph need not apply to “pick-up and delivery” motor vehicles when such motor vehicles are used in no other transportation than in and about cities, towns, or villages. Shipment in water-tight bulk containers need not be covered by a tarpaulin or other means.

(b) *Articles to be kept dry.* Special care shall be taken in the loading of any motor vehicle with Class 4 (flammable solid) or Class 5 (oxidizing) materials which are likely to become hazardous to transport when wet, to keep them from being wetted during the loading process and to keep them dry during transit. Special care shall also be taken in the loading of any motor vehicle with Class 4 (flammable solid) or Class 5 (oxidizing) materials, which are likely to become more hazardous to transport by wetting, to keep them from being wetted during the loading process and to keep them dry during transit. Examples of such dangerous materials are charcoal screenings, ground, crushed, or pulverized charcoal, and lump charcoal.

(c) *Lading ventilation, precautions against spontaneous combustion.* Whenever a motor carrier has knowledge concerning the hazards of spontaneous combustion or heating of any article to be loaded on a motor vehicle, such article shall be so loaded as to afford sufficient ventilation of the load to provide reasonable assurance against fire from this cause; and in such a case the motor vehicle shall be unloaded as soon as practicable after reaching its destination. Charcoal screenings, or ground, crushed, granulated, or pulverized charcoal, in bags, shall be so loaded that the bags are laid horizontally in the motor vehicle, and so piled that there will be spaces for effective air circulation, which spaces shall not be less than 10 cm (3.9 inches) wide; and air spaces shall be maintained between rows of bags. Bags shall not be piled closer than 15 cm (5.9 inches) from the top of any motor vehicle with a closed body.

(d)–(e) [Reserved]

(f) Nitrates, except ammonium nitrate having organic coating, must be loaded in closed or open type motor vehicles, which must be swept clean and be free of any projections capable of injuring bags when so packaged. When shipped in open type motor vehicles, the lading must be suitably covered. Ammonium nitrate having organic coating must not be loaded in all-metal vehicles, other than those made of aluminum or aluminum alloys of the closed type.

(g) A motor vehicle may only contain 45.4 kg (100 pounds) or less net mass of material described as “Smokeless powder for small arms, Division 4.1”.

(h) *Division 4.2 (pyrophoric liquid) materials in cylinders.* Cylinders containing Division 4.2 (pyrophoric liquid) materials, unless packed in a strong box or case and secured therein to protect valves, must be loaded with all valves and safety relief devices in the vapor space. All cylinders must be secured so that no shifting occurs in transit.

[29 FR 18795, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 177.838, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 177.839 Class 8 (corrosive) materials.**

(See also § 177.834(a) through (j).)

(a) *Nitric acid.* No packaging of nitric acid of 50 percent or greater concentration may be loaded above any packaging containing any other kind of material.

(b) *Storage batteries.* All storage batteries containing any electrolyte must be so loaded, if loaded with other lading, that all such batteries will be protected against other lading falling onto or against them, and adequate means must be provided in all cases for the protection and insulation of battery terminals against short circuits.

[Amdt. 177–87, 61 FR 27175, May 30, 1996]

**§ 177.840 Class 2 (gases) materials.**

(See also § 177.834 (a) to (j).)

(a) *Floors or platforms essentially flat.* Cylinders containing Class 2 (gases) materials shall not be loaded onto any part of the floor or platform of any motor vehicle which is not essentially flat; cylinders containing Class 2 (gases) materials may be loaded onto any motor vehicle not having a floor or platform only if such motor vehicle be equipped with suitable racks having adequate means for securing such cylinders in place therein. Nothing contained in this section shall be so construed as to prohibit the loading of such cylinders on any motor vehicle having a floor or platform and racks as hereinbefore described.

(1) *Cylinders.* Cylinders containing Class 2 gases must be securely restrained in an upright or horizontal position, loaded in racks, or packed in boxes or crates to prevent the cylinders from being shifted, overturned or ejected from the motor vehicle under normal transportation conditions. However, after December 31, 2003, a pressure relief device, when installed, must be in communication with the vapor space of a cylinder containing a Division 2.1 (flammable gas) material.

(2) *Cylinders for hydrogen, cryogenic liquid.* A Specification DOT-4L cylinder containing hydrogen, cryogenic liquid may only be transported on a motor vehicle as follows:

(i) The vehicle must have an open body equipped with a suitable rack or support having a means to hold the cylinder upright when subjected to an acceleration of 2 "g" in any horizontal direction;

(ii) The combined total of the hydrogen venting rates, as marked, on the cylinders transported on one motor vehicle may not exceed 60 SCF per hour;

(iii) The vehicle may not enter a tunnel; and

(iv) Highway transportation is limited to private and contract carriage and to direct movement from point of origin to destination.

(b) Portable tank containers containing Class 2 (gases) materials shall be loaded on motor vehicles only as follows:

(1) Onto a flat floor or platform of a motor vehicle.

(2) Onto a suitable frame of a motor vehicle.

(3) In either such case, such containers shall be safely and securely blocked or held down to prevent shifting relative to each other or to the supporting structure when in transit, particularly during sudden starts and stops and changes of direction of the vehicle.

(4) Requirements of paragraphs (1) and (2) of this paragraph (b) shall not be construed as prohibiting stacking of containers provided the provisions of paragraph (3) of this paragraph (b) are fully complied with.

(c) [Reserved]

(d) *Engine to be stopped in cargo tank motor vehicles, except for transfer pump.*

No Division 2.1 (flammable gas) material shall be loaded into or on or unloaded from any cargo tank motor vehicles with the engine running unless the engine is used for the operation of the transfer pump of the vehicle. Unless the delivery hose is equipped with a shut-off valve at its discharge end, the engine of the motor vehicle shall be stopped at the finish of such loading or unloading operation while the filling or discharge connections are disconnected.

(e) Chlorine cargo tank motor vehicles shall be shipped only when equipped:

(1) With a gas mask of a type approved by the National Institute of Occupational Safety and Health (NIOSH) Pittsburgh Research Center, U.S. Department of Health and Human Services for chlorine service; and

(2) With an emergency kit for controlling leaks in fittings on the dome cover plate.

(f) A cargo tank motor vehicle used for transportation of chlorine may not be moved, coupled or uncoupled, when any loading or unloading connections are attached to the vehicle, nor may it be left without the power unit attached unless the vehicle is chocked or equivalent means are provided to prevent motion. For additional requirements, see § 173.315(o) of this subchapter.

(g) Each liquid discharge valve on a cargo tank motor vehicle, other than an engine fuel line valve, must be closed during transportation except during loading and unloading.

(h) The driver of a motor vehicle transporting a Division 2.1 (flammable gas) material that is a cryogenic liquid in a package exceeding 450 L (119 gallons) of water capacity shall avoid unnecessary delays during transportation. If unforeseen conditions cause an excessive pressure rise, the driver shall manually vent the tank at a remote and safe location. For each shipment, the driver shall make a written record of the cargo tank pressure and ambient (outside) temperature:

(1) At the start of each trip,

(2) Immediately before and after any manual venting,

(3) At least once every five hours, and

(4) At the destination point.

(i) No person may transport a Division 2.1 (flammable gas) material that is a cryogenic liquid in a cargo tank motor vehicle unless the pressure of the lading is equal to or less than that used to determine the marked rated holding time (MRHT) and the one-way travel time (OWTT), marked on the cargo tank in conformance with § 173.318(g) of this subchapter, is equal to or greater than the elapsed time between the start and termination of travel. This prohibition does not apply if, prior to expiration of the OWTT, the cargo tank is brought to full equilibration as specified in paragraph (j) of this section.

(j) Full equilibration of a cargo tank transporting a Division 2.1 (flammable gas) material that is a cryogenic liquid may only be done at a facility that loads or unloads a Division 2.1 (flammable gas) material that is a cryogenic liquid and must be performed and verified as follows:

(1) The temperature and pressure of the liquid must be reduced by a manually controlled release of vapor; and

(2) The pressure in the cargo tank must be measured at least ten minutes after the manual release is terminated.

(k) A carrier of carbon monoxide, cryogenic liquid must provide each driver with a self-contained air breathing apparatus that is approved by the National Institute of Occupational Safety and Health; for example, Mine Safety Appliance Co., Model 401, catalog number 461704.

(l) *Operating procedure.* Each operator of a cargo tank motor vehicle that is subject to the emergency discharge control requirements in § 173.315(n) of this subchapter must carry on or within the cargo tank motor vehicle written emergency discharge control procedures for all delivery operations. The procedures must describe the cargo tank motor vehicle's emergency discharge control features and, for a passive shut-down capability, the parameters within which they are designed to function. The procedures must describe the process to be followed if a facility-provided hose is used for unloading when the cargo tank motor vehicle has a specially equipped delivery hose assembly to meet the requirements of § 173.315(n)(2) of this subchapter.

(m) *Cargo tank motor vehicle safety check.* Before unloading from a cargo tank motor vehicle containing a liquefied compressed gas, the qualified person performing the function must check those components of the discharge system, including delivery hose assemblies and piping, that are readily observed during the normal course of unloading to assure that they are of sound quality, without obvious defects detectable through visual observation and audio awareness, and that connections are secure. This check must be made after the pressure in the discharge system has reached at least equilibrium with the pressure in the cargo tank. Operators need not use instruments or take extraordinary actions to check components not readily visible. No operator may unload liquefied compressed gases from a cargo tank motor vehicle with a delivery hose assembly found to have any condition identified in § 180.416(g)(1) of this subchapter or with piping systems found to have any condition identified in § 180.416(g)(2) of this subchapter.

(n) *Emergency shut down.* If there is an unintentional release of product to the environment during unloading of a liquefied compressed gas, the qualified person unloading the cargo tank motor vehicle must promptly shut the internal self-closing stop valve or other primary means of closure and shut down all motive and auxiliary power equipment.

(o) *Daily test of off-truck remote shut-off activation device.* For a cargo tank motor vehicle equipped with an off-truck remote means to close the internal self-closing stop valve and shut off all motive and auxiliary power equipment, an operator must successfully test the activation device within 18 hours prior to the first delivery of each day. For a wireless transmitter/receiver, the person conducting the test must be at least 45.72 m (150 feet) from the cargo tank and may have the cargo tank in his line of sight.

(p) *Unloading procedures for liquefied petroleum gas and anhydrous ammonia in metered delivery service.* An operator must use the following procedures for unloading liquefied petroleum gas or anhydrous ammonia from a cargo tank

motor vehicle in metered delivery service:

(1) For a cargo tank with a capacity of 13,247.5 L (3,500 water gallons) or less, excluding delivery hose and piping, the qualified person attending the unloading operation must remain within 45.72 meters (150 feet) of the cargo tank and 7.62 meters (25 feet) of the delivery hose and must observe both the cargo tank and the receiving container at least once every five minutes when the internal self-closing stop valve is open during unloading operations that take more than five minutes to complete.

(2) For a cargo tank with a capacity greater than 13,247.5 L (3,500 water gallons), excluding delivery hose and piping, the qualified person attending the unloading operation must remain within 45.72 m (150 feet) of the cargo tank and 7.62 m (25 feet) of the delivery hose when the internal self-closing stop valve is open.

(i) Except as provided in paragraph (p)(2)(ii) of this section, the qualified person attending the unloading operation must have an unobstructed view of the cargo tank and delivery hose to the maximum extent practicable, except during short periods when it is necessary to activate controls or monitor the receiving container.

(ii) For deliveries where the qualified person attending the unloading operation cannot maintain an unobstructed view of the cargo tank, when the internal self-closing stop valve is open, the qualified person must observe both the cargo tank and the receiving container at least once every five minutes during unloading operations that take more than five minutes to complete. In addition, by the compliance dates specified in §§173.315(n)(5) and 180.405(m)(3) of this subchapter, the cargo tank motor vehicle must have an emergency discharge control capability that meets the requirements of §173.315(n)(2) or §173.315(n)(4) of this subchapter.

(q) *Unloading procedures for liquefied petroleum gas and anhydrous ammonia in other than metered delivery service.* An operator must use the following procedures for unloading liquefied petroleum gas or anhydrous ammonia from a cargo tank motor vehicle in other than metered delivery service:

(1) The qualified person attending the unloading operation must remain within 7.62 m (25 feet) of the cargo tank when the internal self-closing stop valve is open.

(2) The qualified person attending the unloading operation must have an unobstructed view of the cargo tank and delivery hose to the maximum extent practicable, except during short periods when it is necessary to activate controls or monitor the receiving container.

(r) *Unloading using facility-provided hoses.* A cargo tank motor vehicle equipped with a specially designed delivery hose assembly to meet the requirements of §173.315(n)(2) of this subchapter may be unloaded using a delivery hose assembly provided by the receiving facility under the following conditions:

(1) The qualified person monitoring unloading must visually examine the facility hose assembly for obvious defects prior to its use in the unloading operation.

(2) The qualified person monitoring unloading must remain within arm's reach of the mechanical means of closure for the internal self-closing stop valve when the internal self-closing stop valve is open except for short periods when it is necessary to activate controls or monitor the receiving container. For chlorine cargo tank motor vehicles, the qualified person must remain within arm's reach of a means to stop the flow of product except for short periods when it is necessary to activate controls or monitor the receiving container.

(3) If the facility hose is equipped with a passive means to shut off the flow of product that conforms to and is maintained to the performance standard in §173.315(n)(2) of this subchapter, the qualified person may attend the unloading operation in accordance with the attendance requirements prescribed for the material being unloaded in §177.834 of this section.

(s) *Off-truck remote shut-off activation device.* For a cargo tank motor vehicle with an off-truck remote control shut-off capability as required by §§173.315(n)(3) or (n)(4) of this subchapter, the qualified person attending the unloading operation must be in



possession of the activation device at all times during the unloading process. This requirement does not apply if the activation device is part of a system that will shut off the unloading operation without human intervention in the event of a leak or separation in the hose.

(t) *Unloading without appropriate emergency discharge control equipment.* Until a cargo tank motor vehicle is equipped with emergency discharge control equipment in conformance with §§ 173.315(n)(2) and 180.405(m)(1) of this subchapter, the qualified person attending the unloading operation must remain within arm's reach of a means to close the internal self-closing stop valve when the internal self-closing stop valve is open except during short periods when the qualified person must activate controls or monitor the receiving container. For chlorine cargo tank motor vehicles unloaded after December 31, 1999, the qualified person must remain within arm's reach of a means to stop the flow of product except for short periods when it is necessary to activate controls or monitor the receiving container.

(u) *Unloading of chlorine cargo tank motor vehicles.* After July 1, 2001, unloading of chlorine from a cargo tank motor vehicle must be performed in compliance with Section 3 of the Chlorine Institute Pamphlet 57, "Emergency Shut-off Systems for Bulk Transfer of Chlorine" (IBR, see § 171.7 of this subchapter).

(Approved by the Office of Management and Budget under control number 2137–0542)

[29 FR 18795, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 177.840, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 177.841 Division 6.1 and Division 2.3 materials.**

(See also § 177.834 (a) to (j).)

(a) *Arsenical compounds in bulk.* Care shall be exercised in the loading and unloading of "arsenical dust", "arsenic trioxide", and "sodium arsenate", allowable to be loaded into sift-proof, steel hopper-type or dump-type motor-vehicle bodies equipped with water-

proof, dust-proof covers well secured in place on all openings, to accomplish such loading with the minimum spread of such compounds into the atmosphere by all means that are practicable; and no such loading or unloading shall be done near or adjacent to any place where there are or are likely to be, during the loading or unloading process assemblages of persons other than those engaged in the loading or unloading process, or upon any public highway or in any public place. Before any motor vehicle may be used for transporting any other articles, all detectable traces of arsenical materials must be removed therefrom by flushing with water, or by other appropriate method, and the marking removed.

(b) [Reserved]

(c) *Division 2.3 (poisonous gas) or Division 6.1 (poisonous) materials.* The transportation of a Division 2.3 (poisonous gas) or Division 6.1 (poisonous) material is not permitted if there is any interconnection between packagings.

(d) [Reserved]

(e) A motor carrier may not transport a package:

(1) Except as provided in paragraph (e)(3) of this section, bearing or required to bear a POISON or POISON INHALATION HAZARD label or placard in the same motor vehicle with material that is marked as or known to be foodstuffs, feed or edible material intended for consumption by humans or animals unless the poisonous material is packaged in accordance with this subchapter and is:

(i) Overpacked in a metal drum as specified in § 173.25(c) of this subchapter; or

(ii) Loaded into a closed unit load device and the foodstuffs, feed, or other edible material are loaded into another closed unit load device;

(2) Bearing or required to bear a POISON, POISON GAS or POISON INHALATION HAZARD label in the driver's compartment (including a sleeper berth) of a motor vehicle; or

(3) Bearing a POISON label displaying the text "PG III," or bearing a "PG III" mark adjacent to the POISON label, with materials marked as, or known to be, foodstuffs, feed or any other edible material intended for consumption by humans or animals, unless

the package containing the Division 6.1, Packing Group III material is separated in a manner that, in the event of leakage from packages under conditions normally incident to transportation, commingling of hazardous materials with foodstuffs, feed or any other edible material would not occur.

[29 FR 18795, Dec. 29, 1964]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 177.841, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 177.842 Class 7 (radioactive) material.**

(a) The number of packages of Class 7 (radioactive) materials in any transport vehicle or in any single group in any storage location must be limited so that the total transport index number does not exceed 50. The total transport index of a group of packages and overpacks is determined by adding together the transport index number on the labels on the individual packages and overpacks in the group. This provision does not apply to exclusive use shipments described in §§ 173.441(b), 173.457, and 173.427 of this subchapter.

(b) Packages of Class 7 (radioactive) material bearing “RADIOACTIVE YELLOW-II” or “RADIOACTIVE YELLOW-III” labels may not be placed in a transport vehicle, storage location or in any other place closer than the distances shown in the following table to any area which may be continuously occupied by any passenger, employee, or animal, nor closer than the distances shown in the table to any package containing undeveloped film (if so marked), and must conform to the following conditions:

(1) If more than one of these packages is present, the distance must be computed from the following table on the basis of the total transport index number determined by adding together the transport index number on the labels on the individual packages and overpacks in the vehicle or storeroom.

(2) Where more than one group of packages is present in any single storage location, a single group may not have a total transport index greater than 50. Each group of packages must be handled and stowed not closer than 6 m (20 feet) (measured edge to edge) to any other group. The following table is to be used in accordance with the provisions of paragraph (b) of this section:

| Total transport index | Minimum separation distance in meters (feet) to nearest undeveloped film in various times of transit |           |           |            |               | Minimum distance in meters (feet) to area of persons, or minimum distance in meters (feet) from dividing partition of cargo compartments |
|-----------------------|------------------------------------------------------------------------------------------------------|-----------|-----------|------------|---------------|------------------------------------------------------------------------------------------------------------------------------------------|
|                       | Up to 2 hours                                                                                        | 2–4 hours | 4–8 hours | 8–12 hours | Over 12 hours |                                                                                                                                          |
| None .....            | 0.0 (0)                                                                                              | 0.0 (0)   | 0.0 (0)   | 0.0 (0)    | 0.0 (0)       | 0.0 (0)                                                                                                                                  |
| 0.1 to 1.0 .....      | 0.3 (1)                                                                                              | 0.6 (2)   | 0.9 (3)   | 1.2 (4)    | 1.5 (5)       | 0.3 (1)                                                                                                                                  |
| 1.1 to 5.0 .....      | 0.9 (3)                                                                                              | 1.2 (4)   | 1.8 (6)   | 2.4 (8)    | 3.4 (11)      | 0.6 (2)                                                                                                                                  |
| 5.1 to 10.0 .....     | 1.2 (4)                                                                                              | 1.8 (6)   | 2.7 (9)   | 3.4 (11)   | 4.6 (15)      | 0.9 (3)                                                                                                                                  |
| 10.1 to 20.0 .....    | 1.5 (5)                                                                                              | 2.4 (8)   | 3.7 (12)  | 4.9 (16)   | 6.7 (22)      | 1.2 (4)                                                                                                                                  |
| 20.1 to 30.0 .....    | 2.1 (7)                                                                                              | 3.0 (10)  | 4.6 (15)  | 6.1 (20)   | 8.8 (29)      | 1.5 (5)                                                                                                                                  |
| 30.1 to 40.0 .....    | 2.4 (8)                                                                                              | 3.4 (11)  | 5.2 (17)  | 6.7 (22)   | 10.1 (33)     | 1.8 (6)                                                                                                                                  |
| 40.1 to 50.0 .....    | 2.7 (9)                                                                                              | 3.7 (12)  | 5.8 (19)  | 7.3 (24)   | 11.0 (36)     | 2.1 (7)                                                                                                                                  |

NOTE: The distance in this table must be measured from the nearest point on the nearest packages of Class 7 (radioactive) material.

(c) Shipments of low specific activity materials and surface contaminated objects, as defined in § 173.403 of this subchapter, must be loaded so as to avoid spillage and scattering of loose materials. Loading restrictions are set forth in § 173.427 of this subchapter.

(d) Packages must be so blocked and braced that they cannot change posi-

tion during conditions normally incident to transportation.

(e) Persons should not remain unnecessarily in a vehicle containing Class 7 (radioactive) materials.

(f) The number of packages of fissile Class 7 (radioactive) material in any non-exclusive use transport vehicle must be limited so that the sum of the

criticality safety indices (CSIs) does not exceed 50. In loading and storage areas, fissile material packages must be grouped so that the sum of CSIs in any one group is not greater than 50; there may be more than one group of fissile material packages in a loading or storage area, so long as each group is at least 6 m (20 feet) away from all other such groups. All pertinent requirements of §§ 173.457 and 173.459 apply.

(g) For shipments transported under exclusive use conditions the radiation dose rate may not exceed 0.02 mSv per hour (2 mrem per hour) in any position normally occupied in the motor vehicle. For shipments transported as exclusive use under the provisions of § 173.441(b) of this subchapter for packages with external radiation levels in excess of 2 mSv (200 mrem per hour) at the package surface, the motor vehicle must meet the requirements of a closed transport vehicle (see § 173.403 of this subchapter). The sum of criticality safety indices (CSIs) for packages containing fissile material may not exceed 100 in an exclusive use vehicle.

[Amdt. 177–85, 60 FR 50334, Sept. 28, 1995, as amended at 63 FR 52850, Oct. 1, 1998; 66 FR 45385, Aug. 28, 2001; 69 FR 3696, Jan. 26, 2004]

**§ 177.843 Contamination of vehicles.**

(a) Each motor vehicle used for transporting Class 7 (radioactive) materials under exclusive use conditions in accordance with § 173.427(b)(3) or (c) or § 173.443(c) of this subchapter must be surveyed with radiation detection instruments after each use. A vehicle may not be returned to service until the radiation dose rate at every accessible surface is 0.005 mSv per hour (0.5 mrem per hour) or less and the removable (non-fixed) radioactive surface contamination is not greater than the level prescribed in § 173.443(a) of this subchapter.

(b) This section does not apply to any vehicle used solely for transporting Class 7 (radioactive) material if a survey of the interior surface shows that the radiation dose rate does not exceed 0.1 mSv per hour (10 mrem per hour) at the interior surface or 0.02 mSv per hour (2 mrem per hour) at 1 meter (3.3 feet) from any interior surface. These vehicles must be stenciled with the

words “For Radioactive Materials Use Only” in lettering at least 7.6 cm (3 inches) high in a conspicuous place, on both sides of the exterior of the vehicle. These vehicles must be kept closed at all times other than loading and unloading.

(c) In case of fire, accident, breakage, or unusual delay involving shipments of Class 7 (radioactive) material, see §§ 171.15, 171.16 and 177.854 of this subchapter.

(d) Each transport vehicle used to transport Division 6.2 materials must be disinfected prior to reuse if a Division 6.2 material is released from its packaging during transportation. Disinfection may be by any means effective for neutralizing the material released.

[Amdt. 177–3, 33 FR 14933, Oct. 4, 1968, as amended by Amdt. 177–35, 41 FR 16131, Apr. 15, 1976; Amdt. 177–57, 48 FR 10247, Mar. 10, 1983; Amdt. 177–78, 55 FR 52712, Dec. 21, 1990; Amdt. 177–85, 60 FR 50335, Sept. 28, 1995; 63 FR 52850, Oct. 1, 1998; 65 FR 58631, Sept. 29, 2000; 67 FR 53142, Aug. 14, 2002]

**Subpart C—Segregation and Separation Chart of Hazardous Materials**

**§ 177.848 Segregation of hazardous materials.**

(a) This section applies to materials which meet one or more of the hazard classes defined in this subchapter and are:

(1) In packages that must be labeled or placarded in accordance with part 172 of this subchapter;

(2) In a compartment within a multi-compartmented cargo tank subject to the restrictions in § 173.33 of this subchapter; or

(3) In a portable tank loaded in a transport vehicle or freight container.

(b) When a transport vehicle is to be transported by vessel, other than a ferry vessel, hazardous materials on or within that vehicle must be stowed and segregated in accordance with § 176.83(b) of this subchapter.

(c) In addition to the provisions of paragraph (d) of this section and except as provided in § 173.12(e) of this subchapter, cyanides, cyanide mixtures or solutions may not be stored, loaded and transported with acids if a mixture

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 177.848**

of the materials would generate hydrogen cyanide, and Division 4.2 materials may not be stored, loaded and transported with Class 8 liquids.

(d) Except as otherwise provided in this subchapter, hazardous materials must be stored, loaded or transported in accordance with the following table and other provisions of this section:

SEGREGATION TABLE FOR HAZARDOUS MATERIALS

| Class or division                         | Notes          | 1.1<br>1.2 | 1.3 | 1.4 | 1.5 | 1.6 | 2.1 | 2.2 | 2.3 gas<br>zone A | 2.3 gas<br>Zone B | 3 | 4.1 | 4.2 | 4.3 | 5.1 | 5.2 | 6.1 liq-<br>uids PG<br>I zone A | 7 | 8 liquids<br>only |
|-------------------------------------------|----------------|------------|-----|-----|-----|-----|-----|-----|-------------------|-------------------|---|-----|-----|-----|-----|-----|---------------------------------|---|-------------------|
| Explosives .....                          | 1.1 and<br>1.2 | A          | *   | *   | *   | *   | X   | X   | X                 | X                 | X | X   | X   | X   | X   | X   | X                               | X | X                 |
| Explosives .....                          | 1.3            |            | *   | *   | *   | *   | X   |     | X                 | X                 | X |     | X   | X   | X   | X   | X                               |   | X                 |
| Explosives .....                          | 1.4            |            | *   | *   | *   | *   | O   |     | O                 | O                 | O |     | O   |     |     |     | O                               |   | O                 |
| Very insensitive explo-<br>sives.         | 1.5            | A          | *   | *   | *   | *   | X   | X   | X                 | X                 | X | X   | X   | X   | X   | X   | X                               | X | X                 |
| Extremely insensitive<br>explosives.      | 1.6            |            | *   | *   | *   | *   |     |     |                   |                   |   |     |     |     |     |     |                                 |   |                   |
| Flammable gases .....                     | 2.1            |            | X   | X   | O   | X   |     |     | X                 | O                 |   |     |     |     |     |     | O                               | O |                   |
| Non-toxic, non-flam-<br>mable gases.      | 2.2            |            | X   |     | X   |     |     |     |                   |                   |   |     |     |     |     |     |                                 |   |                   |
| Poisonous gas Zone A                      | 2.3            |            | X   | X   | O   | X   | X   |     |                   |                   | X | X   | X   | X   | X   | X   |                                 |   | X                 |
| Poisonous gas Zone B                      | 2.3            |            | X   | X   | O   | X   | O   |     |                   |                   | O | O   | O   | O   | O   | O   |                                 |   | O                 |
| Flammable liquids .....                   | 3              |            | X   | X   | O   | X   |     |     | X                 | O                 |   |     |     |     | O   |     | X                               |   | O                 |
| Flammable solids .....                    | 4.1            |            | X   |     | X   | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | O                 |
| Spontaneously combus-<br>tible materials. | 4.2            |            | X   | X   | O   | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | X                 |
| Dangerous when wet<br>materials.          | 4.3            |            | X   | X   |     | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | O                 |
| Oxidizers .....                           | 5.1            | A          | X   | X   |     | X   |     |     | X                 | O                 | O |     |     |     |     |     | X                               |   | O                 |
| Organic peroxides .....                   | 5.2            |            | X   | X   |     | X   |     |     | X                 | O                 |   |     |     |     |     |     | X                               |   | O                 |
| Poisonous liquids PG I<br>Zone A.         | 6.1            |            | X   | X   | O   | X   | O   |     |                   |                   | X | X   | X   | X   | X   | X   |                                 |   | X                 |
| Radioactive materials ...                 | 7              |            | X   |     | X   |     | O   |     |                   |                   |   | O   | X   | O   | O   | O   | X                               |   |                   |
| Corrosive liquids .....                   | 8              |            | X   | X   | O   | X   |     |     | X                 | O                 |   | O   | X   | O   | O   | O   |                                 |   |                   |

(e) Instructions for using the segregation table for hazardous materials are as follows:

(1) The absence of any hazard class or division or a blank space in the table indicates that no restrictions apply.

(2) The letter “X” in the table indicates that these materials may not be loaded, transported, or stored together in the same transport vehicle or storage facility during the course of transportation.

(3) The letter “O” in the table indicates that these materials may not be loaded, transported, or stored together in the same transport vehicle or storage facility during the course of transportation unless separated in a manner that, in the event of leakage from packages under conditions normally incident to transportation, commingling of hazardous materials would not occur. Notwithstanding the methods of separation employed, Class 8 (corrosive) liquids may not be loaded above or adjacent to Class 4 (flammable) or Class 5 (oxidizing) materials; except that shippers may load truckload shipments of such materials together when it is known that the mixture of contents would not cause a fire or a dangerous evolution of heat or gas.

(4) The “\*” in the table indicates that segregation among different Class

1 (explosive) materials is governed by the compatibility table in paragraph (f) of this section.

(5) The note “A” in the second column of the table means that, notwithstanding the requirements of the letter “X”, ammonium nitrate (UN 1942) and ammonium nitrate fertilizer may be loaded or stored with Division 1.1 (explosive) or Division 1.5 materials.

(6) When the §172.101 table or §172.402 of this subchapter requires a package to bear a subsidiary hazard label, segregation appropriate to the subsidiary hazard must be applied when that segregation is more restrictive than that required by the primary hazard. However, hazardous materials of the same class may be stowed together without regard to segregation required for any secondary hazard if the materials are not capable of reacting dangerously with each other and causing combustion or dangerous evolution of heat, evolution of flammable, poisonous, or asphyxiant gases, or formation of corrosive or unstable materials.

(f) Class 1 (explosive) materials shall not be loaded, transported, or stored together, except as provided in this section, and in accordance with the following table:

COMPATIBILITY TABLE FOR CLASS 1 (EXPLOSIVE) MATERIALS

| Compatibility group | A | B                | C   | D                | E   | F   | G   | H   | J   | K   | L | N   | S   |
|---------------------|---|------------------|-----|------------------|-----|-----|-----|-----|-----|-----|---|-----|-----|
| A .....             |   | X                | X   | X                | X   | X   | X   | X   | X   | X   | X | X   | X   |
| B .....             | X |                  | X   | X <sub>(4)</sub> | X   | X   | X   | X   | X   | X   | X | X   | 4/5 |
| C .....             | X | X                |     | 2                | 2   | X   | 6   | X   | X   | X   | X | 3   | 4/5 |
| D .....             | X | X <sub>(4)</sub> | 2   |                  | 2   | X   | 6   | X   | X   | X   | X | 3   | 4/5 |
| E .....             | X | X                | 2   | 2                |     | X   | 6   | X   | X   | X   | X | 3   | 4/5 |
| F .....             | X | X                | X   | X                | X   |     | X   | X   | X   | X   | X | X   | 4/5 |
| G .....             | X | X                | 6   | 6                | 6   | X   |     | X   | X   | X   | X | X   | 4/5 |
| H .....             | X | X                | X   | X                | X   | X   | X   |     | X   | X   | X | X   | 4/5 |
| J .....             | X | X                | X   | X                | X   | X   | X   | X   |     | X   | X | X   | 4/5 |
| K .....             | X | X                | X   | X                | X   | X   | X   | X   | X   |     | X | X   | 4/5 |
| L .....             | X | X                | X   | X                | X   | X   | X   | X   | X   | X   |   | 1   | X   |
| N .....             | X | X                | 3   | 3                | 3   | X   | X   | X   | X   | X   | X |     | 4/5 |
| S .....             | X | 4/5              | 4/5 | 4/5              | 4/5 | 4/5 | 4/5 | 4/5 | 4/5 | 4/5 | X | 4/5 |     |

(g) Instructions for using the compatibility table for Class 1 (explosive) materials are as follows:

(1) A blank space in the table indicates that no restrictions apply.

(2) The letter “X” in the table indicates that explosives of different compatibility groups may not be carried on the same transport vehicle.

(3) The numbers in the table mean the following:

(i) “1” means an explosive from compatibility group L shall only be carried on the same transport vehicle with an identical explosive.

(ii) “2” means any combination of explosives from compatibility groups C,

D, or E is assigned to compatibility group E.

(iii) “3” means any combination of explosives from compatibility groups C, D, or E with those in compatibility group N is assigned to compatibility group D.

(iv) “4” means see §177.835(g) when transporting detonators.

(v) “5” means Division 1.4S fireworks may not be loaded on the same transport vehicle with Division 1.1 or 1.2 (explosive) materials.

(vi) “6” means explosive articles in compatibility group G, other than fireworks and those requiring special handling, may be loaded, transported and stored with other explosive articles of compatibility groups C, D and E, provided that explosive substances (such as those not contained in articles) are not carried in the same vehicle.

(h) Except as provided in paragraph (i) of this section, explosives of the same compatibility group but of different divisions may be transported together provided that the whole shipment is transported as though its entire contents were of the lower numerical division (i.e., Division 1.1 being lower than Division 1.2). For example, a mixed shipment of Division 1.2 (explosive) materials and Division 1.4 (explosive) materials, both of compatibility group D, must be transported as Division 1.2 (explosive) materials.

(i) When Division 1.5 materials, compatibility group D, are transported in the same freight container as Division 1.2 (explosive) materials, compatibility group D, the shipment must be transported as Division 1.1 (explosive) materials, compatibility group D.

[Amdt. 177–78, 55 FR 52712, Dec. 21, 1990]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §177.848, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### Subpart D—Vehicles and Shipments in Transit; Accidents

#### § 177.854 Disabled vehicles and broken or leaking packages; repairs.

(a) *Care of lading, hazardous materials.* Whenever for any cause other than necessary traffic stops any motor vehicle transporting any hazardous material is

stopped upon the traveled portion of any highway or shoulder thereof, special care shall be taken to guard the vehicle and its load or to take such steps as may be necessary to provide against hazard. Special effort shall be made to remove the motor vehicle to a place where the hazards of the materials being transported may be provided against. See §§392.22, 392.24, and 392.25 of this title for warning devices required to be displayed on the highway.

(b) *Disposition of containers found broken or leaking in transit.* When leaks occur in packages or containers during the course of transportation, subsequent to initial loading, disposition of such package or container shall be made by the safest practical means afforded under paragraphs (c), (d), and (e) of this section.

(c) *Repairing or overpacking packages.* (1) Packages may be repaired when safe and practicable, such repairing to be in accordance with the best and safest practice known and available.

(2) Packages of hazardous materials that are damaged or found leaking during transportation, and hazardous materials that have spilled or leaked during transportation, may be forwarded to destination or returned to the shipper in a salvage drum in accordance with the requirements of §173.3(c) of this subchapter.

(d) *Transportation of repaired packages.* Any package repaired in accordance with the requirements of paragraph (c)(1) of this section may be transported to the nearest place at which it may safely be disposed of only in compliance with the following requirements:

(1) The package must be safe for transportation.

(2) The repair of the package must be adequate to prevent contamination of or hazardous admixture with other lading transported on the same motor vehicle therewith.

(3) If the carrier is not himself the shipper, the consignee’s name and address must be plainly marked on the repaired package.

(e) *Disposition of unsafe broken packages.* In the event any leaking package or container cannot be safely and adequately repaired for transportation or

transported, it shall be stored pending proper disposition in the safest and most expeditious manner possible.

(f) *Stopped vehicles; other dangerous articles.* Whenever any motor vehicle transporting Class 3 (flammable liquid), Class 4 (flammable solid), Class 5 (oxidizing), Class 8 (corrosive), Class 2 (gases), or Division 6.1 (poisonous) materials, is stopped for any cause other than necessary traffic stops upon the traveled portion of any highway, or a shoulder next thereto, the following requirements shall be complied with during the period of such stop:

(1) For motor vehicles other than cargo tank motor vehicles used for the transportation of Class 3 (flammable liquid) or Division 2.1 (flammable gas) materials and not transporting Division 1.1, 1.2, or 1.3 (explosive) materials, warning devices must be set out in the manner prescribed in § 392.22 of this title.

(2) For cargo tanks used for the transportation of Class 3 (flammable liquid) or Division 2.1 (flammable gas) materials, whether loaded or empty, and vehicles transporting Division 1.1, 1.2, or 1.3 (explosive) materials, warning devices must be set out in the manner prescribed by § 392.25 of this title.

(g) *Repair and maintenance of vehicles containing certain hazardous materials—*

(1) *General.* No person may use heat, flame or spark producing devices to repair or maintain the cargo or fuel containment system of a motor vehicle required to be placarded, other than COMBUSTIBLE, in accordance with subpart F of part 172 of this subchapter. As used in this section, “containment system” includes all vehicle components intended physically to contain cargo or fuel during loading or filling, transport, or unloading.

(2) *Repair and maintenance inside a building.* No person may perform repair or maintenance on a motor vehicle subject to paragraph (g)(1) of this section inside a building unless:

(i) The motor vehicle’s cargo and fuel containment systems are closed (except as necessary to maintain or repair the vehicle’s motor) and do not show any indication of leakage;

(ii) A means is provided, and a person capable to operate the motor vehicle is available, to immediately remove the

motor vehicle if necessary in an emergency;

(iii) The motor vehicle is removed from the enclosed area upon completion of repair or maintenance work; and

(iv) For motor vehicles loaded with Division 1.1, 1.2, or 1.3 (explosive), Class 3 (flammable liquid), or Division 2.1 (flammable gas) materials, all sources of spark, flame or glowing heat within the area of enclosure (including any heating system drawing air therefrom) are extinguished, made inoperable or rendered explosion-proof by a suitable method. *Exception:* Electrical equipment on the vehicle, necessary to accomplish the maintenance function, may remain operational.

(h) *No repair with flame unless gas-free.* No repair of a cargo tank used for the transportation of any Class 3 (flammable liquid) or Division 6.1 (poisonous liquid) material, or any compartment thereof, or of any container for fuel of whatever nature, may be repaired by any method employing a flame, arc, or other means of welding, unless the tank or compartment shall first have been made gas-free.

[29 FR 18795, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 177.854, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

## **Subpart E—Regulations Applying to Hazardous Material on Motor Vehicles Carrying Passengers for Hire**

### **§ 177.870 Regulations for passenger carrying vehicles.**

(a) *Vehicles transporting passengers and property.* In addition to the regulations in parts 170–189 of this subchapter the following requirements shall apply to vehicles transporting passengers and property.

(b) *No Class 1 (explosive) materials or other hazardous materials on passenger-carrying vehicles, exceptions.* No hazardous materials except small-arms ammunition, emergency shipments of drugs, chemicals and hospital supplies, and the accompanying munitions of



war of the Departments of the Army, Navy, and Air Force of the United States Government, are authorized by parts 170–189 of this subchapter to be transported on motor vehicles carrying passengers for hire where other practicable means of transportation is available.

(c) *Class 1 (explosive) materials in passenger-carrying space forbidden.* No Class 1 (explosive) material, except small-arms ammunition, may be carried in the passenger-carrying space of any motor vehicle transporting passengers for hire.

(d) *Hazardous materials on passenger carrying vehicles; quantity.* Where no other practicable means of transportation is available the following articles in the quantities as shown may be transported in motor vehicles carrying passengers for hire in a space other than that provided for passengers: Not to exceed 45 kg (99 pounds) gross weight of any or all of the kinds of Class 1 (explosive) materials permitted to be transported by passenger-carrying aircraft or rail car may be transported on a motor vehicle transporting passengers: *Provided, however,* That samples of Class 1 (explosive) materials for laboratory examination, not to exceed two samples, or a total of no more than 100 detonators, Division 1.4 (explosive) materials at one time in a single motor vehicle, may be transported in a motor vehicle transporting passengers.

(e) *Articles other than Class 1 (explosive) materials on passenger-carrying vehicles.* The gross weight of any given class of hazardous material other than Class 1 (explosive) materials shall not exceed 45 kg (99 pounds), and the aggregate weight of all such other dangerous articles shall not exceed 225 kg (496 pounds). This provision does not apply to nontoxic, nonflammable refrigerants, when such refrigerant is for servicing operations of a motor carrier on whose motor vehicles the refrigerant is used. A cylinder secured against shifting while in transit and not exceeding 113 kg (250 pounds) gross weight may be transported.

(f) *Division 6.1 (poisonous) or Division 2.3 (poisonous gas) materials on passenger-carrying vehicles.* No motor carrier may transport any extremely dangerous Division 6.1 (poisonous) or Division

2.3 (poisonous gas) material, or any paranitroaniline, in any amount, in or on any bus while engaged in the transportation of passengers; or any less dangerous Division 6.1 (poisonous) material, which is other than a liquid, in any amount exceeding an aggregate of 45 kg (99 pounds) gross weight in or on any such bus.

(g) *Class 7 (radioactive) materials.* In addition to the limitations prescribed in paragraphs (b) and (e) of this section, no person may transport any Class 7 (radioactive) material requiring labels under §§172.436, 172.438, and 172.440 of this subchapter in or on any motor vehicle carrying passengers for hire except where no other practicable means of transportation is available. Packages of Class 7 (radioactive) materials must be stored only in the trunk or baggage compartment of the vehicle, and must not be stored in any compartment occupied by persons. Packages of Class 7 (radioactive) materials must be handled and placed in the vehicle as prescribed in §177.842.

[29 FR 18795, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §177.870 see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

## PART 178—SPECIFICATIONS FOR PACKAGINGS

Sec.

- 178.1 Purpose and scope.
- 178.2 Applicability and responsibility.
- 178.3 Marking of packagings.

### Subpart A [Reserved]

### Subpart B—Specifications for Inside Containers, and Linings

- 178.33 Specification 2P; inner nonrefillable metal receptacles.
- 178.33–1 Compliance.
- 178.33–2 Type and size.
- 178.33–3 Inspection.
- 178.33–4 Duties of inspector.
- 178.33–5 Material.
- 178.33–6 Manufacture.
- 178.33–7 Wall thickness.
- 178.33–8 Tests.
- 178.33–9 Marking.
- 178.33a Specification 2Q; inner nonrefillable metal receptacles.

- 178.33a-1 Compliance.
- 178.33a-2 Type and size.
- 178.33a-3 Inspection.
- 178.33a-4 Duties of inspector.
- 178.33a-5 Material.
- 178.33a-6 Manufacture.
- 178.33a-7 Wall thickness.
- 178.33a-8 Tests.
- 178.33a-9 Marking.

### Subpart C—Specifications for Cylinders

- 178.35 General requirements for specification cylinders.
- 178.36 Specification 3A and 3AX seamless steel cylinders.
- 178.37 Specification 3AA and 3AAX seamless steel cylinders.
- 178.38 Specification 3B seamless steel cylinders.
- 178.39 Specification 3BN seamless nickel cylinders.
- 178.42 Specification 3E seamless steel cylinders.
- 178.44 Specification 3HT seamless steel cylinders for aircraft use.
- 178.45 Specification 3T seamless steel cylinders.
- 178.46 Specification 3AL seamless aluminum cylinders.
- 178.47 Specification 4DS welded stainless steel cylinders for aircraft use.
- 178.50 Specification 4B welded or brazed steel cylinders.
- 178.51 Specification 4BA welded or brazed steel cylinders.
- 178.53 Specification 4D welded steel cylinders for aircraft use.
- 178.55 Specification 4B240ET welded or brazed cylinders.
- 178.56 Specification 4AA480 welded steel cylinders.
- 178.57 Specification 4L welded insulated cylinders.
- 178.58 Specification 4DA welded steel cylinders for aircraft use.
- 178.59 Specification 8 steel cylinders with porous fillings for acetylene.
- 178.60 Specification 8AL steel cylinders with porous fillings for acetylene.
- 178.61 Specification 4BW welded steel cylinders with electric-arc welded longitudinal seam.
- 178.65 Specification 39 non-reusable (non-refillable) cylinders.
- 178.68 Specification 4E welded aluminum cylinders.
- 178.69 Responsibilities and requirements for manufacturers of UN pressure receptacles.
- 178.70 Approval of UN pressure receptacles.
- 178.71 Specifications for UN pressure receptacles.
- 178.74 Approval of MEGCs.
- 178.75 Specifications for MEGCs.

APPENDIX A TO SUBPART C—ILLUSTRATIONS:  
CYLINDER TENSILE SAMPLE

### Subparts D–G [Reserved]

### Subpart H—Specifications for Portable Tanks

- 178.251—178.253-5 [Reserved]
- 178.255 Specification 60; steel portable tanks.
- 178.255-1 General requirements.
- 178.255-2 Material.
- 178.255-3 Expansion domes.
- 178.255-4 Closures for manholes and domes.
- 178.255-5 Bottom discharge outlets.
- 178.255-6 Loading and unloading accessories.
- 178.255-7 Protection of valves and accessories.
- 178.255-8 Safety devices.
- 178.255-9 Compartments.
- 178.255-10 Lining.
- 178.255-11 Tank mountings.
- 178.255-12 Pressure test.
- 178.255-13 Repair of tanks.
- 178.255-14 Marking.
- 178.255-15 Report.
- 178.273 Approval of Specification UN portable tanks.
- 178.274 Specification for UN portable tanks.
- 178.275 Specification for UN Portable Tanks intended for the transportation of liquid and solid hazardous materials.
- 178.276 Requirements for the design, construction, inspection and testing of portable tanks intended for the transportation of non-refrigerated liquefied compressed gases.
- 178.277 Requirements for the design, construction, inspection and testing of portable tanks intended for the transportation of refrigerated liquefied gases.

### Subpart I [Reserved]

### Subpart J—Specifications for Containers for Motor Vehicle Transportation

- 178.318 Specification MC 201; container for detonators and percussion caps.
- 178.318-1 Scope.
- 178.318-2 Container.
- 178.318-3 Marking.
- 178.320 General requirements applicable to all DOT specification cargo tank motor vehicles.
- 178.337 Specification MC 331; cargo tank motor vehicle primarily for transportation of compressed gases as defined in subpart G of part 173 of this subchapter.
- 178.337-1 General requirements.
- 178.337-2 Material.
- 178.337-3 Structural integrity.
- 178.337-4 Joints.
- 178.337-5 Bulkheads, baffles and ring stiffeners.
- 178.337-6 Closure for manhole.
- 178.337-7 Overturn protection.
- 178.337-8 Openings, inlets and outlets.

**Pt. 178**

- 178.337-9 Pressure relief devices, piping, valves, hoses, and fittings.
- 178.337-10 Accident damage protection.
- 178.337-11 Emergency discharge control.
- 178.337-12 [Reserved]
- 178.337-13 Supporting and anchoring.
- 178.337-14 Gauging devices.
- 178.337-15 Pumps and compressors.
- 178.337-16 Testing.
- 178.337-17 Marking.
- 178.337-18 Certification.
- 178.338 Specification MC-338; insulated cargo tank motor vehicle.
- 178.338-1 General requirements.
- 178.338-2 Material.
- 178.338-3 Structural integrity.
- 178.338-4 Joints.
- 178.338-5 Stiffening rings.
- 178.338-6 Manholes.
- 178.338-7 Openings.
- 178.338-8 Pressure relief devices, piping, valves, and fittings.
- 178.338-9 Holding time.
- 178.338-10 Accident damage protection.
- 178.338-11 Discharge control devices.
- 178.338-12 Shear section.
- 178.338-13 Supporting and anchoring.
- 178.338-14 Gauging devices.
- 178.338-15 Cleanliness.
- 178.338-16 Inspection and testing.
- 178.338-17 Pumps and compressors.
- 178.338-18 Marking.
- 178.338-19 Certification.
- 178.340-178.343 [Reserved]
- 178.345 General design and construction requirements applicable to Specification DOT 406 (§178.346), DOT 407 (§178.347), and DOT 412 (§178.348) cargo tank motor vehicles.
- 178.345-1 General requirements.
- 178.345-2 Material and material thickness.
- 178.345-3 Structural integrity.
- 178.345-4 Joints.
- 178.345-5 Manhole assemblies.
- 178.345-6 Supports and anchoring.
- 178.345-7 Circumferential reinforcements.
- 178.345-8 Accident damage protection.
- 178.345-9 Pumps, piping, hoses and connections.
- 178.345-10 Pressure relief.
- 178.345-11 Tank outlets.
- 178.345-12 Gauging devices.
- 178.345-13 Pressure and leakage tests.
- 178.345-14 Marking.
- 178.345-15 Certification.
- 178.346 Specification DOT 406; cargo tank motor vehicle.
- 178.346-1 General requirements.
- 178.346-2 Material and thickness of material.
- 178.346-3 Pressure relief.
- 178.346-4 Outlets.
- 178.346-5 Pressure and leakage tests.
- 178.347 Specification DOT 407; cargo tank motor vehicle.
- 178.347-1 General requirements.

**49 CFR Ch. I (10-1-08 Edition)**

- 178.347-2 Material and thickness of material.
- 178.347-3 Manhole assemblies.
- 178.347-4 Pressure relief.
- 178.347-5 Pressure and leakage test.
- 178.348 Specification DOT 412; cargo tank motor vehicle.
- 178.348-1 General requirements.
- 178.348-2 Material and thickness of material.
- 178.348-3 Pumps, piping, hoses and connections.
- 178.348-4 Pressure relief.
- 178.348-5 Pressure and leakage test.

**Subpart K—Specifications for Packagings for Class 7 (Radioactive) Materials**

- 178.350 Specification 7A; general packaging, Type A.
- 178.356 Specification 20PF phenolic-foam insulated, metal overpack.
- 178.356-1 General requirements.
- 178.356-2 Materials of construction and other requirements.
- 178.356-3 Tests.
- 178.356-4 Required markings.
- 178.356-5 Typical assembly detail.
- 178.358 Specification 21PF fire and shock resistant, phenolic-foam insulated, metal overpack.
- 178.358-1 General requirements.
- 178.358-2 Materials of construction and other requirements.
- 178.358-3 Modification of Specification 21PF-1 overpacks.
- 178.358-4 Construction of Specification 21PF-1B overpacks.
- 178.358-5 Required markings.
- 178.358-6 Typical assembly detail.
- 178.360 Specification 2R; inside containment vessel.
- 178.360-1 General requirements.
- 178.360-2 Manufacture.
- 178.360-3 Dimensions.
- 178.360-4 Closure devices.

**Subpart L—Non-bulk Performance-Oriented Packaging Standards**

- 178.500 Purpose, scope and definitions.
- 178.502 Identification codes for packagings.
- 178.503 Marking of packagings.
- 178.504 Standards for steel drums.
- 178.505 Standards for aluminum drums.
- 178.506 Standards for metal drums other than steel or aluminum.
- 178.507 Standards for plywood drums.
- 178.508 Standards for fiber drums.
- 178.509 Standards for plastic drums and jerricans.
- 178.510 Standards for wooden barrels.
- 178.511 Standards for aluminum and steel jerricans.
- 178.512 Standards for steel or aluminum boxes.
- 178.513 Standards for boxes of natural wood.

- 178.514 Standards for plywood boxes.
- 178.515 Standards for reconstituted wood boxes.
- 178.516 Standards for fiberboard boxes.
- 178.517 Standards for plastic boxes.
- 178.518 Standards for woven plastic bags.
- 178.519 Standards for plastic film bags.
- 178.520 Standards for textile bags.
- 178.521 Standards for paper bags.
- 178.522 Standards for composite packagings with inner plastic receptacles.
- 178.523 Standards for composite packagings with inner glass, porcelain, or stoneware receptacles.

#### **Subpart M—Testing of Non-bulk Packagings and Packages**

- 178.600 Purpose and scope.
- 178.601 General requirements.
- 178.602 Preparation of packagings and packages for testing.
- 178.603 Drop test.
- 178.604 Leakproofness test.
- 178.605 Hydrostatic pressure test.
- 178.606 Stacking test.
- 178.607 Cooperage test for bung-type wooden barrels.
- 178.608 Vibration standard.
- 178.609 Test requirements for packagings for infectious substances.

#### **Subpart N—IBC Performance-Oriented Standards**

- 178.700 Purpose, scope and definitions.
- 178.702 IBC codes.
- 178.703 Marking of IBCs.
- 178.704 General IBC standards.
- 178.705 Standards for metal IBCs.
- 178.706 Standards for rigid plastic IBCs.
- 178.707 Standards for composite IBCs.
- 178.708 Standards for fiberboard IBCs.
- 178.709 Standards for wooden IBCs.
- 178.710 Standards for flexible intermediate bulk containers.

#### **Subpart O—Testing of IBCs**

- 178.800 Purpose and scope.
- 178.801 General requirements.
- 178.802 Preparation of fiberboard IBCs for testing.
- 178.803 Testing and certification of IBCs.
- 178.810 Drop test.
- 178.811 Bottom lift test.
- 178.812 Top lift test.
- 178.813 Leakproofness test.
- 178.814 Hydrostatic pressure test.
- 178.815 Stacking test.
- 178.816 Topple test.
- 178.817 Righting test.
- 178.818 Tear test.
- 178.819 Vibration test.

APPENDIX A TO PART 178—SPECIFICATIONS FOR STEEL

APPENDIX B TO PART 178—ALTERNATIVE LEAKPROOFNESS TEST METHODS

APPENDIX C TO PART 178—NOMINAL AND MINIMUM THICKNESSES OF STEEL DRUMS AND JERRICANS

APPENDIX D TO PART 178—THERMAL RESISTANCE TEST

APPENDIX E TO PART 178—FLAME PENETRATION RESISTANCE TEST

AUTHORITY: 49 U.S.C. 5101–5128; 49 CFR 1.53.

### **§ 178.1 Purpose and scope.**

This part prescribes the manufacturing and testing specifications for packaging and containers used for the transportation of hazardous materials in commerce.

[Amdt. 178–40, 42 FR 2689, Jan. 13, 1977. Redesignated by Amdt. 178–97, 55 FR 52715, Dec. 21, 1990]

### **§ 178.2 Applicability and responsibility.**

(a) *Applicability.* (1) The requirements of this part apply to packagings manufactured—

(i) To a DOT specification, regardless of country of manufacture; or

(ii) To a UN standard, for packagings manufactured within the United States. For UN standard packagings manufactured outside the United States, see §173.24(d)(2) of this subchapter. For UN standard packagings for which standards are not prescribed in this part, see §178.3(b).

(2) A manufacturer of a packaging subject to the requirements of this part is primarily responsible for compliance with the requirements of this part. However, any person who performs a function prescribed in this part shall perform that function in accordance with this part.

(b) *Specification markings.* When this part requires that a packaging be marked with a DOT specification or UN standard marking, marking of the packaging with the appropriate DOT or UN markings is the certification that—

(1) Except as otherwise provided in this section, all requirements of the DOT specification or UN standard, including performance tests, are met; and

(2) All functions performed by, or on behalf of, the person whose name or symbol appears as part of the marking conform to requirements specified in this part.

### § 178.3

### 49 CFR Ch. I (10–1–08 Edition)

(c) *Notification.* Except as specifically provided in §§ 178.337–18 and 178.345–10 of this part, the manufacturer or other person certifying compliance with the requirements of this part, and each subsequent distributor of that packaging shall—

(1) Notify in writing each person to whom that packaging is transferred—

(i) Of all requirements in this part not met at the time of transfer, and

(ii) With information specifying the type(s) and dimensions of the closures, including gaskets and any other components needed to ensure that the packaging is capable of successfully passing the applicable performance tests. This information must include any procedures to be followed, including closure instructions for inner packagings and receptacles, to effectively assemble and close the packaging for the purpose of preventing leakage in transportation. For packagings sold or represented as being in conformance with the requirements of this subchapter applicable to transportation by aircraft, this information must include relevant guidance to ensure that the packaging, as prepared for transportation, will withstand the pressure differential requirements in “ 173.27 of this subchapter.

(2) Retain copies of each written notification for at least one year from date of issuance; and

(3) Make copies of all written notifications available for inspection by a representative of the Department.

(d) Except as provided in paragraph (c) of this section, a packaging not conforming to the applicable specifications or standards in this part may not be marked to indicate such conformance.

(e) *Definitions.* For the purpose of this part—

*Manufacturer* means the person whose name and address or symbol appears as part of the specification markings required by this part or, for a packaging marked with the symbol of an approval agency, the person on whose behalf the approval agency certifies the packaging.

*Specification markings* mean the packaging identification markings required by this part including, where applicable, the name and address or symbol of

the packaging manufacturer or approval agency.

(f) No packaging may be manufactured or marked to a packaging specification that was in effect on September 30, 1991, and that was removed from this part 178 by a rule published in the FEDERAL REGISTER on December 21, 1990 and effective October 1, 1991.

[Amdt. 178–97, 55 FR 52715, Dec. 21, 1990; 56 FR 66284, Dec. 20, 1991, as amended by Amdt. No. 178–106, 59 FR 67519, Dec. 29, 1994; Amdt. 178–117, 62 FR 14338, Mar. 26, 1997; 68 FR 45041, July 31, 2003; 69 FR 34612, June 22, 2004]

### § 178.3 Marking of packagings.

(a) Each packaging represented as manufactured to a DOT specification or a UN standard must be marked on a non-removable component of the packaging with specification markings conforming to the applicable specification, and with the following:

(1) In an unobstructed area, with letters, and numerals identifying the standards or specification (e.g. UN 1A1, DOT 4B240ET, etc.).

(2) Unless otherwise specified in this part, with the name and address or symbol of the packaging manufacturer or, where specifically authorized, the symbol of the approval agency certifying compliance with a UN standard. Symbols, if used, must be registered with the Associate Administrator. Duplicative symbols are not authorized.

(3) The markings must be stamped, embossed, burned, printed or otherwise marked on the packaging to provide adequate accessibility, permanency, contrast, and legibility so as to be readily apparent and understood.

(4) Unless otherwise specified, letters and numerals must be at least 12.0 mm (0.47 inches) in height except that for packagings of less than or equal to 30 L (7.9 gallons) capacity for liquids or 30 kg (66 pounds) capacity for solids the height must be at least 6.0 mm (0.2 inches). For packagings having a capacity of 5 L (1 gallon) or 5 kg (11 pounds) or less, letters and numerals must be of an appropriate size.

(5) For packages with a gross mass of more than 30 kg (66 pounds), the markings or a duplicate thereof must appear on the top or on a side of the packaging.

(b) A UN standard packaging for which the UN standard is set forth in this part may be marked with the United Nations symbol and other specification markings only if it fully conforms to the requirements of this part. A UN standard packaging for which the UN standard is not set forth in this part may be marked with the United Nations symbol and other specification markings for that standard as provided in the ICAO Technical Instructions or the IMDG Code subject to the following conditions:

(1) The U.S. manufacturer must establish that the packaging conforms to the applicable provisions of the ICAO Technical Instructions (IBR, see § 171.7 of this subchapter) or the IMDG Code (IBR, see § 171.7 of this subchapter), respectively.

(2) If an indication of the name of the manufacturer or other identification of the packaging as specified by the competent authority is required, the name and address or symbol of the manufacturer or the approval agency certifying compliance with the UN standard must be entered. Symbols, if used, must be registered with the Associate Administrator.

(3) The letters “USA” must be used to indicate the State authorizing the allocation of the specification marks if the packaging is manufactured in the United States.

(c) Where a packaging conforms to more than one UN standard or DOT specification, the packaging may bear more than one marking, provided the packaging meets all the requirements of each standard or specification. Where more than one marking appears on a packaging, each marking must appear in its entirety.

(d) No person may mark or otherwise certify a packaging or container as meeting the requirements of a manufacturing special permit unless that person is the holder of or a party to that special permit, an agent of the holder or party for the purpose of

marking or certification, or a third party tester.

[Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 56 FR 66284, Dec. 20, 1991, as amended by Amdt. No. 178-106, 59 FR 67519, Dec. 29, 1994; Amdt. 178-113, 61 FR 21102, May 9, 1996; 65 FR 50462, Aug. 18, 2000; 66 FR 45386, Aug. 28, 2001; 67 FR 61015, Sept. 27, 2002; 68 FR 75748, Dec. 31, 2003; 70 FR 73166, Dec. 9, 2005]

### Subpart A [Reserved]

### Subpart B—Specifications for Inside Containers, and Linings

SOURCE: 29 FR 18823, Dec. 29, 1964, unless otherwise noted. Redesignated at 32 FR 5606, Apr. 5, 1967.

#### § 178.33 Specification 2P; inner non-refillable metal receptacles.

##### § 178.33-1 Compliance.

- (a) Required in all details.
- (b) [Reserved]

##### § 178.33-2 Type and size.

(a) Single-trip inside containers. Must be seamless, or with seams, welded, soldered, brazed, double seamed, or swaged.

(b) The maximum capacity of containers in this class shall not exceed one liter (61.0 cubic inches). The maximum inside diameter shall not exceed 3 inches.

[29 FR 18813, Dec. 29, 1964, as amended by Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-101, 58 FR 50237, Sept. 24, 1993; 66 FR 45386, Aug. 28, 2001]

##### § 178.33-3 Inspection.

- (a) By competent inspector.
- (b) [Reserved]

##### § 178.33-4 Duties of inspector.

(a) To inspect material and completed containers and witness tests, and to reject defective materials or containers.

- (b) [Reserved]

##### § 178.33-5 Material.

(a) Uniform quality steel plate such as black plate, electro-tin plate, hot dipped tin plate, tern plate or other commercially accepted can making

## **§ 178.33-6**

plate; or nonferrous metal of uniform drawing quality.

(b) Material with seams, cracks, laminations or other injurious defects not authorized.

### **§ 178.33-6 Manufacture.**

(a) By appliances and methods that will assure uniformity of completed containers; dirt and scale to be removed as necessary; no defect acceptable that is likely to weaken the finished container appreciably; reasonably smooth and uniform surface finish required.

(b) Seams when used must be as follows:

(1) Circumferential seams: By welding, swedging, brazing, soldering, or double seaming.

(2) Side seams: By welding, brazing, or soldering.

(c) Ends: The ends shall be of pressure design.

[29 FR 18823, Dec. 29, 1964, as amended by Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

### **§ 178.33-7 Wall thickness.**

(a) The minimum wall thickness for any container shall be 0.007 inch.

(b) [Reserved]

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

### **§ 178.33-8 Tests.**

(a) One out of each lot of 25,000 containers or less, successively produced per day shall be pressure tested to destruction and must not burst below 240 psig gauge pressure. The container tested shall be complete with end assembled.

(b) Each such 25,000 containers or less, successively produced per day, shall constitute a lot and if the test container shall fail, the lot shall be rejected or ten additional containers may be selected at random and subjected to the test under which failure occurred. These containers shall be complete with ends assembled. Should any of the ten containers thus tested fail, the entire lot must be rejected. All containers constituting a lot shall be of

## **49 CFR Ch. I (10-1-08 Edition)**

like material, size, design construction, finish, and quality.

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967, as amended by 66 FR 45387, Aug. 28, 2001]

### **§ 178.33-9 Marking.**

(a) By means of printing, lithographing, embossing, or stamping, each container must be marked to show:

(1) DOT-2P.

(2) Name or symbol of person making the mark specified in paragraph (a)(1) of this section. Symbol, if used, must be registered with the Associate Administrator.

(b) [Reserved]

[Amdt. 178-40, 41 FR 38181, Sept. 9, 1976, as amended by Amdt. 178-97, 56 FR 66287, Dec. 20, 1991; 66 FR 45386, Aug. 28, 2001]

### **§ 178.33a Specification 2Q; inner non-refillable metal receptacles.**

#### **§ 178.33a-1 Compliance.**

(a) Required in all details.

(b) [Reserved]

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

#### **§ 178.33a-2 Type and size.**

(a) Single-trip inside containers. Must be seamless, or with seams welded, soldered, brazed, double seamed, or swedged.

(b) The maximum capacity of containers in this class shall not exceed 1 L (61.0 cubic inches). The maximum inside diameter shall not exceed 3 inches.

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-43, 42 FR 42208, Aug. 22, 1977; Amdt. 178-101, 58 FR 50237, Sept. 24, 1993; 66 FR 45387, Aug. 28, 2001]

#### **§ 178.33a-3 Inspection.**

(a) By competent inspector.

(b) [Reserved]

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

#### **§ 178.33a-4 Duties of inspector.**

(a) To inspect material and completed containers and witness tests, and to reject defective materials or containers.

(b) [Reserved]

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

**§ 178.33a-5 Material.**

(a) Uniform quality steel plate such as black plate, electrotin plate, hot dipped tinplate, ternplate or other commercially accepted can making plate; or nonferrous metal of uniform drawing quality.

(b) Material with seams, cracks, laminations or other injurious defects not authorized.

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

**§ 178.33a-6 Manufacture.**

(a) By appliances and methods that will assure uniformity of completed containers; dirt and scale to be removed as necessary; no defect acceptable that is likely to weaken the finished container appreciably; reasonably smooth and uniform surface finish required.

(b) Seams when used must be as follows:

(1) Circumferential seams. By welding, swedging, brazing, soldering, or double seaming.

(2) Side seams. By welding, brazing or soldering.

(c) Ends. The ends shall be of pressure design.

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

**§ 178.33a-7 Wall thickness.**

(a) The minimum wall thickness for any container shall be 0.008 inch.

(b) [Reserved]

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967]

**§ 178.33a-8 Tests.**

(a) One out of each lot of 25,000 containers or less, successively produced per day, shall be pressure tested to destruction and must not burst below 270 psig gauge pressure. The container tested shall be complete with end assembled.

(b) Each such 25,000 containers or less, successively produced per day, shall constitute a lot and if the test container shall fail, the lot shall be rejected or ten additional containers may

be selected at random and subjected to the test under which failure occurred. These containers shall be complete with ends assembled. Should any of the ten containers thus tested fail, the entire lot must be rejected. All containers constituting a lot shall be of like material, size, design, construction, finish and quality.

[Order 71, 31 FR 9074, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967, as amended by 66 FR 45387, Aug. 28, 2001]

**§ 178.33a-9 Marking.**

(a) By means of printing, lithographing, embossing, or stamping, each container must be marked to show:

(1) DOT-2Q.

(2) Name or symbol of person making the mark specified in paragraph (a)(1) of this section. Symbol, if used, must be registered with the Associate Administrator.

(b) [Reserved]

[Amdt. 178-40, 41 FR 38181, Sept. 9, 1976, as amended by Amdt. 178-97, 56 FR 66287, Dec. 20, 1991; 66 FR 45386, Aug. 28, 2001]

**Subpart C—Specifications for Cylinders**

**§ 178.35 General requirements for specification cylinders.**

(a) *Compliance.* Compliance with the requirements of this subpart is required in all details.

(b) *Inspections and analyses.* Chemical analyses and tests required by this subchapter must be made within the United States, unless otherwise approved in writing by the Associate Administrator, in accordance with subpart I of part 107 of this chapter. Inspections and verification must be performed by—

(1) An independent inspection agency approved in writing by the Associate Administrator, in accordance with subpart I of part 107 of this chapter; or

(2) For DOT Specifications 3B, 3BN, 3E, 4B, 4BA, 4D (water capacity less than 1,100 cubic inches), 4B240ET, 4AA480, 4L, 8, 8AL, 4BW, 39 (marked service pressure 900 p.s.i.g. or lower) and 4E manufactured in the United States, a competent inspector of the manufacturer.



(c) *Duties of inspector.* The inspector shall determine that each cylinder made is in conformance with the applicable specification. Except as otherwise specified in the applicable specification, the inspector shall perform the following:

(1) Inspect all material and reject any not meeting applicable requirements. For cylinders made by the billet-piercing process, billets must be inspected and shown to be free from pipe, cracks, excessive segregation and other injurious defects after parting or, when applicable, after nick and cold break.

(2) Verify the material of construction meets the requirements of the applicable specification by—

(i) Making a chemical analysis of each heat of material;

(ii) Obtaining a certified chemical analysis from the material manufacturer for each heat of material (a ladle analysis is acceptable); or

(iii) If an analysis is not provided for each heat of material by the material manufacturer, by making a check analysis of a sample from each coil, sheet, or tube.

(3) Verify compliance of cylinders with the applicable specification by—

(i) Verifying identification of material is proper;

(ii) Inspecting the inside of the cylinder before closing in ends;

(iii) Verifying that the heat treatment is proper;

(iv) Obtaining samples for all tests and check chemical analyses (NOTE: Recommended locations for test specimens taken from welded cylinders are depicted in Figures 1 through 5 in Appendix C to this subpart for the specific construction design.);

(v) Witnessing all tests;

(vi) Verify threads by gauge;

(vii) Reporting volumetric capacity and tare weight (see report form) and minimum thickness of wall noted; and

(viii) Verifying that each cylinder is marked in accordance with the applicable specification.

(4) Furnish complete test reports required by this subpart to the maker of the cylinder and, upon request, to the purchaser. The test report must be retained by the inspector for fifteen years from the original test date of the cylinder.

(d) *Defects and attachments.* Cylinders must conform to the following:

(1) A cylinder may not be constructed of material with seams, cracks or laminations, or other injurious defects.

(2) Metal attachments to cylinders must have rounded or chamfered corners or must be protected in such a manner as to prevent the likelihood of causing puncture or damage to other hazardous materials packages. This requirement applies to anything temporarily or permanently attached to the cylinder, such as metal skids.

(e) *Safety devices.* Pressure relief devices and protection for valves, safety devices, and other connections, if applied, must be as required or authorized by the appropriate specification, and as required in §173.301 of this subchapter.

(f) *Markings.* Markings on a DOT Specification cylinder must conform to applicable requirements.

(1) Each cylinder must be marked with the following information:

(i) The DOT specification marking must appear first, followed immediately by the service pressure. For example, DOT-3A1800.

(ii) The serial number must be placed just below or immediately following the DOT specification marking.

(iii) A symbol (letters) must be placed just below, immediately before or following the serial number. Other variations in sequence of markings are authorized only when necessitated by a lack of space. The symbol and numbers must be those of the manufacturer. The symbol must be registered with the Associate Administrator; duplications are not authorized.

(iv) The inspector's official mark and date of test (such as 5-95 for May 1995) must be placed near the serial number. This information must be placed so that dates of subsequent tests can be easily added. An example of the markings prescribed in this paragraph (f)(1) is as follows:

DOT-3A1800

1234

XY

AB 5-95

Or;

DOT-3A1800-1234-XY

AB 5-95

Where:

DOT-3A = specification number  
 1800 = service pressure  
 1234 = serial number  
 XY = symbol of manufacturer  
 AB = inspector's mark  
 5-95 = date of test

(2) Additional required marking must be applied to the cylinder as follows:

(i) The word "spun" or "plug" must be placed near the DOT specification marking when an end closure in the finished cylinder has been welded by the spinning process, or effected by plugging.

(ii) As prescribed in specification 3HT (§ 178.44) or 3T (§ 178.45), if applicable.

(3) *Marking exceptions.* A DOT 3E cylinder is not required to be marked with an inspector's mark or a serial number.

(4) Unless otherwise specified in the applicable specification, the markings on each cylinder must be stamped plainly and permanently on the shoulder, top head, or neck.

(5) The size of each marking must be at least 0.25 inch or as space permits.

(6) Other markings are authorized provided they are made in low stress areas other than the side wall and are not of a size and depth that will create harmful stress concentrations. Such marks may not conflict with any DOT required markings.

(g) *Inspector's report.* Each inspector shall prepare a report containing, at a minimum, the applicable information listed in CGA Pamphlet C-11 (IBR, see § 171.7 of this subchapter) or, until October 1, 1997, in accordance with the applicable test report requirements of this subchapter in effect on September 30, 1996. Any additional information or markings that are required by the applicable specification must be shown on the test report. The signature of the inspector on the reports certifies that the processes of manufacture and heat treatment of cylinders were observed and found satisfactory.

(h) *Report retention.* The manufacturer of the cylinders shall retain the reports required by this subpart for 15 years from the original test date of the cylinder.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45185, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

### § 178.36 Specification 3A and 3AX seamless steel cylinders.

(a) *Type size and service pressure.* In addition to the requirements of § 178.35, cylinders must conform to the following:

(1) A DOT-3A cylinder is a seamless steel cylinder with a water capacity (nominal) not over 1,000 pounds and a service pressure of at least 150 psig.

(2) A DOT-3AX is a seamless steel cylinder with a water capacity not less than 1,000 pounds and a service pressure of at least 500 psig, conforming to the following requirements:

(i) Assuming the cylinder is to be supported horizontally at its two ends only and to be uniformly loaded over its entire length consisting of the weight per unit of length of the straight cylindrical portion filled with water and compressed to the specified test pressure; the sum of two times the maximum tensile stress in the bottom fibers due to bending, plus that in the same fibers (longitudinal stress), due to hydrostatic test may not exceed 80 percent of the minimum yield strength of the steel at such maximum stress. Wall thickness must be increased when necessary to meet the requirement.

(ii) To calculate the maximum longitudinal tensile stress due to bending, the following formula must be used:

$$S = Mc/I$$

(iii) To calculate the maximum longitudinal tensile stress due to hydrostatic test pressure, the following formula must be used:

$$S = A_1 P/A_2$$

where:

S = tensile stress—p.s.i.;

M = bending moment-inch pounds—(wl<sup>2</sup>)/8;

w = weight per inch of cylinder filled with water;

l = length of cylinder-inches;

c = radius (D)/(2) of cylinder-inches;

I = moment of inertia—0.04909 (D<sup>4</sup>—d<sup>4</sup>) inches fourth;

D = outside diameter-inches;

d = inside diameter-inches;

A<sub>1</sub> = internal area in cross section of cylinder-square inches;

A<sub>2</sub> = area of metal in cross section of cylinder-square inches;

P = hydrostatic test pressure-psig.

(b) *Steel.* Open-hearth or electric steel of uniform quality must be used. Content percent may not exceed the following: Carbon, 0.55; phosphorous, 0.045; sulphur, 0.050.

(c) *Identification of material.* Material must be identified by any suitable method, except that plates and billets for hot-drawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No fissure or other defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. If not originally free from such defects, the surface may be machined or otherwise treated to eliminate these defects. The thickness of the bottoms of cylinders welded or formed by spinning is, under no condition, to be less than two times the minimum wall thickness of the cylindrical shell; such bottom thicknesses must be measured within an area bounded by a line representing the points of contact between the cylinder and floor when the cylinder is in a vertical position.

(e) *Welding or brazing.* Welding or brazing for any purpose whatsoever is prohibited except as follows:

(1) Welding or brazing is authorized for the attachment of neckrings and footrings which are non-pressure parts and only to the tops and bottoms of cylinders having a service pressure of 500 psig or less. Cylinders, neckrings, and footrings must be made of weldable steel, the carbon content of which may not exceed 0.25 percent except in the case of 4130X steel which may be used with proper welding procedures.

(2) As permitted in paragraph (d) of this section.

(3) Cylinders used solely in anhydrous ammonia service may have a ½ inch diameter bar welded within their concave bottoms.

(f) *Wall thickness.*

(1) *Wall thickness.* For cylinders with service pressure less than 900 psig, the wall stress may not exceed 24,000 psig. A minimum wall thickness of 0.100 inch is required for any cylinder over 5 inches outside diameter. Wall stress

calculation must be made by using the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test or 450 psig whichever is the greater;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* The completed cylinder must be uniformly and properly heat-treated prior to tests.

(h) *Openings in cylinders and connections (valves, fuse plugs, etc.) for those openings.* Threads are required on openings.

(1) Threads must be clean cut, even, without checks, and to gauge.

(2) Taper threads, when used, must be of length not less than as specified for American Standard taper pipe threads.

(3) Straight threads having at least 6 engaged threads are authorized. Straight threads must have a tight fit and calculated shear strength of at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(i) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test, as follows:

(1) The test must be by water-jacket, or other suitable methods, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus the test pressure cannot be maintained the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent, volumetric expansion may not exceed 10 percent of the total volumetric expansion at test pressure.

(4) Each cylinder must be tested to at least ⅔ times service pressure.

(j) *Flattening test.* A flattening test must be performed on one cylinder taken at random out of each lot of 200 or less, by placing the cylinder between wedge shaped knife edges having a 60° included angle, rounded to ½-inch radius. The longitudinal axis of the cylinder must be at a 90-degree angle to knife edges during the test. For lots of 30 or less, flattening tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(k) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material as follows:

(1) The test is required on 2 specimens cut from 1 cylinder taken at random out of each lot of 200 or less. For lots of 30 or less, physical tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(2) Specimens must conform to the following:

(i) Gauge length of 8 inches with a width of not over 1½ inches, a gauge length of 2 inches with a width of not over 1½ inches, or a gauge length of at least 24 times thickness with width not over 6 times thickness is authorized when cylinder wall is not over ⅜ inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within 1 inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2-percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psig and the strain indicator reading must be set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed ⅛ inch per minute during yield strength determination.

(l) *Acceptable results for physical and flattening tests.* Either of the following is an acceptable result:

(1) An elongation at least 40 percent for a 2-inch gauge length or at least 20 percent in other cases and yield strength not over 73 percent of tensile strength. In this instance, the flattening test is not required.

(2) An elongation at least 20 percent for a 2-inch gauge length or 10 percent in other cases and a yield strength not over 73 percent of tensile strength. In this instance, the flattening test is required, without cracking, to 6 times the wall thickness.

(m) *Leakage test.* All spun cylinders and plugged cylinders must be tested for leakage by gas or air pressure after the bottom has been cleaned and is free from all moisture subject to the following conditions and limitations:

(1) Pressure, approximately the same as but no less than service pressure, must be applied to one side of the finished bottom over an area of at least ⅓ of the total area of the bottom but

## § 178.37

## 49 CFR Ch. I (10–1–08 Edition)

not less than  $\frac{3}{4}$  inch in diameter, including the closure, for at least 1 minute, during which time the other side of the bottom exposed to pressure must be covered with water and closely examined for indications of leakage. Except as provided in paragraph (n) of this section, a cylinder that is leaking must be rejected.

(2) A spun cylinder is one in which an end closure in the finished cylinder has been welded by the spinning process.

(3) A plugged cylinder is one in which a permanent closure in the bottom of a finished cylinder has been effected by a plug.

(4) As a safety precaution, if the manufacturer elects to make this test before the hydrostatic test, the manufacturer should design the test apparatus so that the pressure is applied to the smallest area practicable, around the point of closure, and so as to use the smallest possible volume of air or gas.

(n) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinders. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding or spinning is not authorized. Spun cylinders rejected under the provisions of paragraph (m) of this section may be removed from the spun cylinder category by drilling to remove defective material, tapping and plugging.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 62 FR 51561, Oct. 1, 1997; 66 FR 45185, 45386-45387, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003; 73 FR 57006, Oct. 1, 2008]

### § 178.37 Specification 3AA and 3AAX seamless steel cylinders.

(a) *Type, size and service pressure.* In addition to the requirements of § 178.35, cylinders must conform to the following:

(1) A DOT-3AA cylinder is a seamless steel cylinder with a water capacity (nominal) of not over 1,000 pounds and a service pressure of at least 150 psig.

(2) A DOT-3AAX cylinder is a seamless steel cylinder with a water capacity of not less than 1,000 pounds and a service pressure of at least 500 psig, conforming to the following requirements:

(i) Assuming the cylinder is to be supported horizontally at its two ends only and to be uniformly loaded over its entire length consisting of the weight per unit of length of the straight cylindrical portion filled with water and compressed to the specified test pressure; the sum of two times the maximum tensile stress in the bottom fibers due to bending, plus that in the same fibers (longitudinal stress), due to hydrostatic test pressure may not exceed 80 percent of the minimum yield strength of the steel at such maximum stress. Wall thickness must be increased when necessary to meet the requirement.

(ii) To calculate the maximum tensile stress due to bending, the following formula must be used:

$$S = Mc/I$$

(iii) To calculate the maximum longitudinal tensile stress due to hydrostatic test pressure, the following formula must be used:

$$S = A^1P/A^2$$

Where:

S = tensile stress-p.s.i.;

M = bending moment-inch pounds ( $wl^2/8$ );

w = weight per inch of cylinder filled with water;

l = length of cylinder-inches;

c = radius (D)/(2) of cylinder-inches;

I = moment of inertia- $0.04909 (D^4 - d^4)$  inches fourth;

D = outside diameter-inches;

d = inside diameter-inches;

A<sup>1</sup> = internal area in cross section of cylinder-square inches;

A<sup>2</sup> = area of metal in cross section of cylinder-square inches;

P = hydrostatic test pressure-psig.

(b) *Authorized steel.* Open-hearth, basic oxygen, or electric steel of uniform quality must be used. A heat of steel made under the specifications in table 1 of this paragraph (b), check chemical analysis of which is slightly out of the specified range, is acceptable, if satisfactory in all other respects, provided the tolerances shown in table 2 of this paragraph (b) are not exceeded. When a carbon-boron steel is used, a hardenability test must be performed on the first and last ingot of each heat of steel. The results of this test must be recorded on the Record of

Chemical Analysis of Material for Cylinders required by §178.35. This hardness test must be made  $\frac{5}{16}$ -inch from the quenched end of the Jominy quench bar and the hardness must be at least Rc 33 and no more than Rc 53. The following chemical analyses are authorized:

TABLE 1—AUTHORIZED MATERIALS

| Designation      | 4130X (percent) (see Note 1) | NE-8630 (percent) (see Note 1) | 9115 (percent) (see Note 1) | 9125 (percent) (see Note 1) | Carbon-boron (percent) | Inter-mediate manganese (percent) |
|------------------|------------------------------|--------------------------------|-----------------------------|-----------------------------|------------------------|-----------------------------------|
| Carbon .....     | 0.25/0.35 .....              | 0.28/0.33 .....                | 0.10/0.20 .....             | 0.20/0.30 .....             | 0.27–0.37 .....        | 0.40 max.                         |
| Manganese .....  | 0.40/0.90 .....              | 0.70/0.90 .....                | 0.50/0.75 .....             | 0.50/0.75 .....             | 0.80–1.40 .....        | 1.35/1.65.                        |
| Phosphorus ..... | 0.04 max .....               | 0.04 max .....                 | 0.04 max .....              | 0.04 max .....              | 0.035 max .....        | 0.04 max.                         |
| Sulfur .....     | 0.05 max .....               | 0.04 max .....                 | 0.04 max .....              | 0.04 max .....              | 0.045 max .....        | 0.05 max.                         |
| Silicon .....    | 0.15/0.35 .....              | 0.20/0.35 .....                | 0.60/0.90 .....             | 0.60/0.90 .....             | 0.3 max. ....          | 0.10/0.30.                        |
| Chromium .....   | 0.80/1.10 .....              | 0.40/0.60 .....                | 0.50/0.65 .....             | 0.50/0.65 .....             |                        |                                   |
| Molybdenum ..... | 0.15/0.25 .....              | 0.15/0.25 .....                |                             |                             |                        |                                   |
| Zirconium .....  |                              |                                | 0.05/0.15 .....             | 0.05/0.15 .....             |                        |                                   |
| Nickel .....     |                              | 0.40/0.70 .....                |                             |                             |                        |                                   |
| Boron .....      |                              |                                |                             |                             | 0.0005/0.003.          |                                   |

NOTE 1: This designation may not be restrictive and the commercial steel is limited in analysis as shown in this table.

TABLE 2—CHECK ANALYSIS TOLERANCES

| Element                       | Limit or maximum specified (percent) | Tolerance (percent) over the maximum limit or under the minimum limit |                    |
|-------------------------------|--------------------------------------|-----------------------------------------------------------------------|--------------------|
|                               |                                      | Under minimum limit                                                   | Over maximum limit |
| Carbon .....                  | To 0.15 incl .....                   | 0.02                                                                  | 0.03               |
|                               | Over 0.15 to 0.40 incl .....         | .03                                                                   | .04                |
| Manganese .....               | To 0.60 incl .....                   | .03                                                                   | .03                |
|                               | Over 0.60 to 1.15 incl .....         | 0.04                                                                  | 0.04               |
|                               | Over 1.15 to 2.50 incl .....         | 0.05                                                                  | 0.05               |
| Phosphorus <sup>1</sup> ..... | All ranges .....                     |                                                                       | .01                |
| Sulphur .....                 | All ranges .....                     |                                                                       | .01                |
| Silicon .....                 | To 0.30 incl .....                   | .02                                                                   | .03                |
|                               | Over 0.30 to 1.00 incl .....         | .05                                                                   | .05                |
| Nickel .....                  | To 1.00 incl .....                   | .03                                                                   | .03                |
| Chromium .....                | To 0.90 incl .....                   | .03                                                                   | .03                |
|                               | 0.90 to 2.90 incl .....              | .05                                                                   | .05                |
| Molybdenum .....              | To 0.20 incl .....                   | .01                                                                   | .01                |
|                               | Over 0.20 to 0.40 .....              | .02                                                                   | .02                |
| Zirconium .....               | All ranges .....                     | .01                                                                   | .05                |

<sup>1</sup> Rephosphorized steels not subject to check analysis for phosphorus.

(c) *Identification of material.* Material must be identified by any suitable method except that plates and billets for hot-drawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No fissure or other defects is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. If not originally free from such defects, the surface may be machined or otherwise treated to eliminate these defects. The thickness of the bottoms of cyl-

inders welded or formed by spinning is, under no condition, to be less than two times the minimum wall thickness of the cylindrical shell; such bottom thicknesses must be measured within an area bounded by a line representing the points of contact between the cylinder and floor when the cylinder is in a vertical position.

(e) *Welding or brazing.* Welding or brazing for any purpose whatsoever is prohibited except as follows:

(1) Welding or brazing is authorized for the attachment of neckrings and footrings which are non-pressure parts, and only to the tops and bottoms of cylinders having a service pressure of 500 psig or less. Cylinders, neckrings,

and footrings must be made of weldable steel, the carbon content of which may not exceed 0.25 percent except in the case of 4130X steel which may be used with proper welding procedure.

(2) As permitted in paragraph (d) of this section.

(f) *Wall thickness.* The thickness of each cylinder must conform to the following:

(1) For cylinders with a service pressure of less than 900 psig, the wall stress may not exceed 24,000 psi. A minimum wall thickness of 0.100 inch is required for any cylinder with an outside diameter of over 5 inches.

(2) For cylinders with service pressure of 900 psig or more the minimum wall must be such that the wall stress at the minimum specified test pressure may not exceed 67 percent of the minimum tensile strength of the steel as determined from the physical tests required in paragraphs (k) and (l) of this section and must be not over 70,000 psi.

(3) Calculation must be made by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test or 450 psig whichever is the greater;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* The completed cylinders must be uniformly and properly heat treated prior to tests. Heat treatment of cylinders of the authorized analyses must be as follows:

(1) All cylinders must be quenched by oil, or other suitable medium except as provided in paragraph (g)(5) of this section.

(2) The steel temperature on quenching must be that recommended for the steel analysis, but may not exceed 1750 °F.

(3) All steels must be tempered at a temperature most suitable for that steel.

(4) The minimum tempering temperature may not be less than 1000 °F except as noted in paragraph (g)(6) of this section.

(5) Steel 4130X may be normalized at a temperature of 1650 °F instead of

being quenched and cylinders so normalized need not be tempered.

(6) Intermediate manganese steels may be tempered at temperatures not less than 1150 °F., and after heat treating each cylinder must be submitted to a magnetic test to detect the presence of quenching cracks. Cracked cylinders must be rejected and destroyed.

(7) Except as otherwise provided in paragraph (g)(6) of this section, all cylinders, if water quenched or quenched with a liquid producing a cooling rate in excess of 80 percent of the cooling rate of water, must be inspected by the magnetic particle, dye penetrant or ultrasonic method to detect the presence of quenching cracks. Any cylinder designed to the requirements for specification 3AA and found to have a quenching crack must be rejected and may not be requalified. Cylinders designed to the requirements for specification 3AAX and found to have cracks must have cracks removed to sound metal by mechanical means. Such specification 3AAX cylinders will be acceptable if the repaired area is subsequently examined to assure no defect, and it is determined that design thickness requirements are met.

(h) *Openings in cylinders and connections (valves, fuse plugs, etc.) for those openings.* Threads are required on openings.

(1) Threads must be clean cut, even, without checks, and to gauge.

(2) Taper threads, when used, must be of a length not less than as specified for American Standard taper pipe threads.

(3) Straight threads having at least 6 engaged threads are authorized. Straight threads must have a tight fit and a calculated shear strength of at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(i) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Each cylinder must be tested to at least  $\frac{2}{3}$  times the service pressure.

(j) *Flattening test.* A flattening test must be performed on one cylinder taken at random out of each lot of 200 or less, by placing the cylinder between wedge shaped knife edges having a 60° included angle, rounded to  $\frac{1}{2}$ -inch radius. The longitudinal axis of the cylinder must be at a 90-degree angle to knife edges during the test. For lots of 30 or less, flattening tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(k) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material as follows:

(1) The test is required on 2 specimens cut from 1 cylinder taken at random out of each lot of 200 or less. For lots of 30 or less, physical tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to the same heat treatment as the finished cylinder.

(2) Specimens must conform to the following:

(i) Gauge length of 8 inches with a width of not over  $1\frac{1}{2}$  inches, a gauge length of 2 inches with a width of not over  $1\frac{1}{2}$  inches, or a gauge length of at least 24 times the thickness with width not over 6 times thickness when the thickness of the cylinder wall is not over  $\frac{3}{16}$  inch.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within 1 inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi, the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(l) *Acceptable results for physical and flattening tests.* An acceptable result for physical and flattening tests is elongation at least 20 percent for 2 inches of gauge length or at least 10 percent in other cases. Flattening is required, without cracking, to 6 times the wall thickness of the cylinder.

(m) *Leakage test.* All spun cylinders and plugged cylinders must be tested



## § 178.38

## 49 CFR Ch. I (10–1–08 Edition)

for leakage by gas or air pressure after the bottom has been cleaned and is free from all moisture. Pressure, approximately the same as but no less than the service pressure, must be applied to one side of the finished bottom over an area of at least  $\frac{1}{16}$  of the total area of the bottom but not less than  $\frac{3}{4}$  inch in diameter, including the closure, for at least one minute, during which time the other side of the bottom exposed to pressure must be covered with water and closely examined for indications of leakage. Except as provided in paragraph (n) of this section, a cylinder must be rejected if there is any leaking.

(1) A spun cylinder is one in which an end closure in the finished cylinder has been welded by the spinning process.

(2) A plugged cylinder is one in which a permanent closure in the bottom of a finished cylinder has been effected by a plug.

(3) As a safety precaution, if the manufacturer elects to make this test before the hydrostatic test, the manufacturer should design the test apparatus so that the pressure is applied to the smallest area practicable, around the point of closure, and so as to use the smallest possible volume of air or gas.

(n) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinders. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding or spinning is not authorized. Spun cylinders rejected under the provision of paragraph (m) of this section may be removed from the spun cylinder category by drilling to remove defective material, tapping and plugging.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 65 FR 58631, Sept. 29, 2000; 66 FR 45386–45387, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

### § 178.38 Specification 3B seamless steel cylinders.

(a) *Type, size, and service pressure.* A DOT 3B cylinder is seamless steel cylinder with a water capacity (nominal) of not over 1,000 pounds and a service pressure of at least 150 to not over 500 psig.

(b) *Steel.* Open-hearth or electric steel of uniform quality must be used. Con-

tent percent may not exceed the following: carbon, 0.55; phosphorus, 0.045; sulphur, 0.050.

(c) *Identification of material.* Material must be identified by any suitable method except that plates and billets for hot-drawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No fissure or other defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. If not originally free from such defects, the surface may be machined or otherwise treated to eliminate these defects. The thickness of the bottoms of cylinders welded or formed by spinning is, under no condition, to be less than two times the minimum wall thickness of the cylindrical shell; such bottom thicknesses to be measured within an area bounded by a line representing the points of contact between the cylinder and floor when the cylinder is in a vertical position.

(e) *Welding or brazing.* Welding or brazing for any purpose whatsoever is prohibited except as follows:

(1) Welding or brazing is authorized for the attachment of neckrings and footrings which are non-pressure parts, and only to the tops and bottoms of cylinders having a service pressure of 500 psig or less. Cylinders, neckrings, and footrings must be made of weldable steel, carbon content of which may not exceed 0.25 percent except in the case of 4130X steel which may be used with proper welding procedure.

(2) As permitted in paragraph (d) of this section.

(f) *Wall thickness.* The wall stress may not exceed 24,000 psi. The minimum wall thickness is 0.090 inch for any cylinder with an outside diameter of 6 inches. Calculation must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = at least two times service pressure or 450 psig, whichever is the greater;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* The completed cylinders must be uniformly and properly heat-treated prior to tests.

(h) *Openings in cylinders and connections (valves, fuse plugs, etc.) for those openings.* Threads, conforming to the following, are required on all openings:

(1) Threads must be clean cut, even, without checks, and to gauge.

(2) Taper threads when used, must be of a length not less than as specified for American Standard taper pipe threads.

(3) Straight threads having at least 4 engaged threads are authorized. Straight threads must have a tight fit, and calculated shear strength at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(i) *Hydrostatic test.* Cylinders must successfully withstand a hydrostatic test, as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy either of 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to insure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Cylinders must be tested as follows:

(i) Each cylinder; to at least 2 times service pressure; or

(ii) 1 cylinder out of each lot of 200 or less; to at least 3 times service pressure. Others must be examined under pressure of 2 times service pressure and show no defect.

(j) *Flattening test.* A flattening test must be performed on one cylinder taken at random out of each lot of 200 or less, by placing the cylinder between

wedge shaped knife edges having a 60° included angle, rounded to ½-inch radius. The longitudinal axis of the cylinder must be at a 90-degree angle to knife edges during the test. For lots of 30 or less, flattening tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(k) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material, as follows:

(1) The test is required on 2 specimens cut from 1 cylinder taken at random out of each lot of 200 or less. For lots of 30 or less, physical tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(2) Specimens must conform to the following:

(i) Gauge length of 8 inches with a width of not over 1½ inches; or a gauge length of 2 inches with a width of not over 1½ inches; or a gauge length at least 24 times the thickness with a width not over 6 times thickness is authorized when a cylinder wall is not over ⅜ inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within one inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as

prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the “extension under load” method, the total strain (or “extension under load”) corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi, and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(l) *Acceptable results for physical and flattening tests.* Either of the following is an acceptable result:

(1) An elongation of at least 40 percent for a 2-inch gauge length or at least 20 percent in other cases and yield strength not over 73 percent of tensile strength. In this instance, the flattening test is not required.

(2) An elongation of at least 20 percent for a 2-inch gauge length or 10 percent in other cases and yield strength not over 73 percent of tensile strength. Flattening is required, without cracking, to 6 times the wall thickness.

(m) *Leakage test.* All spun cylinders and plugged cylinders must be tested for leakage by gas or air pressure after the bottom has been cleaned and is free from all moisture, subject to the following conditions and limitations:

(1) Pressure, approximately the same as but no less than service pressure, must be applied to one side of the finished bottom over an area of at least  $\frac{1}{16}$  of the total area of the bottom but not less than  $\frac{3}{4}$  inch in diameter, including the closure, for at least one minute, during which time the other side of the bottom exposed to pressure must be covered with water and closely

examined for indications of leakage. Except as provided in paragraph (n) of this section, a cylinder must be rejected if there is any leaking.

(2) A spun cylinder is one in which an end closure in the finished cylinder has been welded by the spinning process.

(3) A plugged cylinder is one in which a permanent closure in the bottom of a finished cylinder has been effected by a plug.

(4) As a safety precaution, if the manufacturer elects to make this test before the hydrostatic test, he should design his apparatus so that the pressure is applied to the smallest area practicable, around the point of closure, and so as to use the smallest possible volume of air or gas.

(n) *Rejected cylinders.* Reheat treatment of rejected cylinders is authorized. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding or spinning is not authorized. Spun cylinders rejected under the provisions of paragraph (m) of this section may be removed from the spun cylinder category by drilling to remove defective material, tapping and plugging.

(o) *Marking.* Markings may be stamped into the sidewalls of cylinders having a service pressure of 150 psig if all of the following conditions are met:

(1) Wall stress at test pressure may not exceed 24,000 psi.

(2) Minimum wall thickness must be not less than 0.090 inch.

(3) Depth of stamping must be no greater than 15 percent of the minimum wall thickness, but may not exceed 0.015 inch.

(4) Maximum outside diameter of cylinder may not exceed 5 inches.

(5) Carbon content of cylinder may not exceed 0.25 percent. If the carbon content exceeds 0.25 percent, the complete cylinder must be normalized after stamping.

(6) Stamping must be adjacent to the top head.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended by 66 FR 45185, 45386–45388, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

**§ 178.39 Specification 3BN seamless nickel cylinders.**

(a) *Type, size and service pressure.* A DOT 3BN cylinder is a seamless nickel cylinder with a water capacity (nominal) not over 125 pounds water capacity (nominal) and a service pressure at least 150 to not over 500 psig.

(b) *Nickel.* The percentage of nickel plus cobalt must be at least 99.0 percent.

(c) *Identification of material.* The material must be identified by any suitable method except that plates and billets for hot-drawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. Cylinders closed in by spinning process are not authorized.

(e) *Welding or brazing.* Welding or brazing for any purpose whatsoever is prohibited except that welding is authorized for the attachment of neckrings and footrings which are non-pressure parts, and only to the tops and bottoms of cylinders. Neckrings and footrings must be of weldable material, the carbon content of which may not exceed 0.25 percent. Nickel welding rod must be used.

(f) *Wall thickness.* The wall stress may not exceed 15,000 psi. A minimum wall thickness of 0.100 inch is required for any cylinder over 5 inches in outside diameter. Wall stress calculation must be made by using the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test or 450 psig whichever is the greater;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* The completed cylinders must be uniformly and properly heat-treated prior to tests.

(h) *Openings in cylinders and connections (valves, fuse plugs, etc.) for those*

*openings.* Threads conforming to the following are required on openings:

(1) Threads must be clean cut, even, without checks, and to gauge.

(2) Taper threads, when used, to be of length not less than as specified for American Standard taper pipe threads.

(3) Straight threads having at least 6 engaged threads are authorized. Straight threads must have a tight fit and a calculated shear strength of at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(i) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test, as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy either of 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Each cylinder must be tested to at least 2 times service pressure.

(j) *Flattening test.* A flattening test must be performed on one cylinder taken at random out of each lot of 200 or less, by placing the cylinder between wedge shaped knife edges having a 60° included angle, rounded to ½-inch radius. The longitudinal axis of the cylinder must be at a 90-degree angle to knife edges during the test. For lots of 30 or less, flattening tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(k) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation,

## § 178.42

## 49 CFR Ch. I (10–1–08 Edition)

and reduction of area of material, as follows:

(1) The test is required on 2 specimens cut from 1 cylinder taken at random out of each lot of 200 or less. For lots of 30 or less, physical tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width of not over  $1\frac{1}{2}$  inches, a gauge length of 2 inches with a width of not over  $1\frac{1}{2}$  inches, or a gauge length of at least 24 times the thickness with a width not over 6 times thickness is authorized when a cylinder wall is not over  $\frac{3}{16}$  inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within one inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of

controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi, and the strain indicator reading must be set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(l) *Acceptable results for physical and flattening tests.* Either of the following is an acceptable result:

(1) An elongation of at least 40 percent for a 2 inch gauge length or at least 20 percent in other cases and yield point not over 50 percent of tensile strength. In this instance, the flattening test is not required.

(2) An elongation of at least 20 percent for a 2 inch gauge length or 10 percent in other cases and a yield point not over 50 percent of tensile strength. Flattening is required, without cracking, to 6 times the wall thickness.

(m) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinders. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding is not authorized.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended by 66 FR 45185, 45386, 45388, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

### § 178.42 Specification 3E seamless steel cylinders.

(a) *Type, size, and service pressure.* A DOT 3E cylinder is a seamless steel cylinder with an outside diameter not greater than 2 inches nominal, a length less than 2 feet and a service pressure of 1,800 psig.

(b) *Steel.* Open-hearth or electric steel of uniform quality must be used. Content percent may not exceed the following: Carbon, 0.55; phosphorus, 0.045; sulphur, 0.050.

(c) *Identification of steel.* Materials must be identified by any suitable method.

(d) *Manufacture.* Cylinders must be manufactured by best appliances and methods. No defect is permitted that is

likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. The thickness of the spun bottom is, under no condition, to be less than two times the minimum wall thickness of the cylindrical shell; such bottom thickness must be measured within an area bounded by a line representing the points of contact between the cylinder and floor when the cylinder is in a vertical position.

(e) *Openings in cylinders and connections (valves, fuse plugs, etc.) for those openings.* Threads conforming to the following are required on openings.

(1) Threads must be clean cut, even, without checks, and to gauge.

(2) Taper threads, when used, must be of length not less than as specified for American Standard taper pipe threads.

(3) Straight threads having at least 4 engaged threads are authorized. Straight threads must have a tight fit and a calculated shear strength of at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(f) *Hydrostatic test.* Cylinders must be tested as follows:

(1) One cylinder out of each lot of 500 or less must be subjected to a hydrostatic pressure of 6,000 psig or higher.

(2) The cylinder referred to in paragraph (f)(1) of this section must burst at a pressure higher than 6,000 psig without fragmenting or otherwise showing lack of ductility, or must hold a pressure of 12,000 psig for 30 seconds without bursting. In which case, it must be subjected to a flattening test without cracking to six times wall thickness between knife edges, wedge shaped 60 degree angle, rounded out to a ½ inch radius. The inspector's report must be suitably changed to show results of latter alternate and flattening test.

(3) Other cylinders must be examined under pressure of at least 3,000 psig and not to exceed 4,500 psig and show no defect. Cylinders tested at a pressure in excess of 3,600 psig must burst at a pressure higher than 7,500 psig when tested as specified in paragraph (f)(2) of this section. The pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete examination.

(g) *Leakage test.* All spun cylinders and plugged cylinders must be tested for leakage by gas or air pressure after the bottom has been cleaned and is free from all moisture subject to the following conditions and limitations:

(1) A pressure, approximately the same as but not less than the service pressure, must be applied to one side of the finished bottom over an area of at least ¼ of the total area of the bottom but not less than ¾ inch in diameter, including the closure, for at least one minute, during which time the other side of the bottom exposed to pressure must be covered with water and closely examined for indications of leakage. Accept as provided in paragraph (h) of this section, a cylinder must be rejected if there is any leakage.

(2) A spun cylinder is one in which an end closure in the finished cylinder has been welded by the spinning process.

(3) A plugged cylinder is one in which a permanent closure in the bottom of a finished cylinder has been effected by a plug.

(4) As a safety precaution, if the manufacturer elects to make this test before the hydrostatic test, the manufacturer shall design the test apparatus so that the pressure is applied to the smallest area practicable, around the point of closure, and so as to use the smallest possible volume of air or gas.

(h) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinders. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding or spinning is not authorized. Spun cylinders rejected under the provisions of paragraph (g) of this section may be removed from the spun cylinder category by drilling to remove defective material, tapping and plugging.

(i) *Marking.* Markings required by § 178.35 must be stamped plainly and permanently on the shoulder, top head, neck or sidewall of each cylinder.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended by 66 FR 45386, Aug. 28, 2001]

#### § 178.44 Specification 3HT seamless steel cylinders for aircraft use.

(a) *Type, size and service pressure.* A DOT 3HT cylinder is a seamless steel

cylinder with a water capacity (nominal) of not over 150 pounds and a service pressure of at least 900 psig.

(b) *Authorized steel.* Open hearth or electric furnace steel of uniform quality must be used. A heat of steel made under the specifications listed in Table 1 in this paragraph (b), a check chemical analysis that is slightly out of the specified range is acceptable, if satisfactory in all other respects, provided the tolerances shown in Table 2 in this paragraph (b) are not exceeded. The maximum grain size shall be 6 or finer. The grain size must be determined in accordance with ASTM E 112–88 (IBR, see § 171.7 of this subchapter). Steel of the following chemical analysis is authorized:

TABLE 1—AUTHORIZED MATERIALS

| Designation      | AISI 4130<br>(percent) |
|------------------|------------------------|
| Carbon .....     | 0.28/0.33              |
| Manganese .....  | 0.40/0.60              |
| Phosphorus ..... | 0.040 maximum          |
| Sulfur .....     | 0.040 maximum          |
| Silicon .....    | 0.15/0.35              |
| Chromium .....   | 0.80/1.10              |
| Molybdenum ..... | 0.15/0.25              |

TABLE 2—CHECK ANALYSIS TOLERANCES

| Element                    | Limit or maximum specified (percent) | Tolerance (percent) over the maximum limit or under the minimum limit |                    |
|----------------------------|--------------------------------------|-----------------------------------------------------------------------|--------------------|
|                            |                                      | Under minimum limit                                                   | Over maximum limit |
| Carbon .....               | Over 0.15 to 0.40 incl               | .03                                                                   | .04                |
| Manganese .....            | To 0.60 incl .....                   | .03                                                                   | .03                |
| Phosphorus <sup>1</sup> .. | All ranges .....                     | .....                                                                 | .01                |
| Sulphur .....              | All ranges .....                     | .....                                                                 | .01                |
| Silicon .....              | To 0.30 incl .....                   | .02                                                                   | .03                |
| .....                      | Over 0.30 to 1.00 incl               | .05                                                                   | .05                |
| Chromium .....             | Over 0.90 incl .....                 | .03                                                                   | .03                |
| .....                      | Over 0.90 to 2.10 incl               | .05                                                                   | .05                |
| Molybdenum ..              | To 0.20 incl .....                   | .01                                                                   | .01                |
| .....                      | Over 0.20 to 0.40 incl               | .02                                                                   | .02                |

<sup>1</sup>Rephosphorized steels not subject to check analysis for phosphorus.

(c) *Identification of material.* Material must be identified by any suitable method. Steel stamping of heat identifications may not be made in any area which will eventually become the side wall of the cylinder. Depth of stamping may not encroach upon the minimum prescribed wall thickness of the cylinder.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No fissure or other defect is permitted that is likely to weaken the finished container appreciably. The general surface finish may not exceed a roughness of 250 RMS. Individual irregularities such as draw marks, scratches, pits, etc., should be held to a minimum consistent with good high stress pressure vessel manufacturing practices. If the cylinder is not originally free of such defects or does not meet the finish requirements, the surface may be machined or otherwise treated to eliminate these defects. The point of closure of cylinders closed by spinning may not be less than two times the prescribed wall thickness of the cylindrical shell. The cylinder end contour must be hemispherical or ellipsoidal with a ratio of major-to-minor axis not exceeding two to one and with the concave side to pressure.

(e) *Welding or brazing.* Welding or brazing for any purpose whatsoever is prohibited, except that welding by spinning is permitted to close the bottom of spun cylinders. Machining or grinding to produce proper surface finish at point of closure is required.

(f) *Wall thickness.* (1) Minimum wall thickness for any cylinder must be 0.050 inch. The minimum wall thickness must be such that the wall stress at the minimum specified test pressure may not exceed 75 percent of the minimum tensile strength of the steel as determined from the physical tests required in paragraph (m) of this section and may not be over 105,000 psi.

(2) Calculations must be made by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = Wall stress in psi;

P = Minimum test pressure prescribed for water jacket test;

D = Outside diameter in inches;

d = Inside diameter in inches.

(3) Wall thickness of hemispherical bottoms only permitted to 90 percent of minimum wall thickness of cylinder sidewall but may not be less than 0.050

inch. In all other cases, thickness to be no less than prescribed minimum wall.

(g) *Heat treatment.* The completed cylinders must be uniformly and properly heated prior to tests. Heat treatment of the cylinders of the authorized analysis must be as follows:

(1) All cylinders must be quenched by oil, or other suitable medium.

(2) The steel temperature on quenching must be that recommended for the steel analysis, but may not exceed 1750°F.

(3) The steel must be tempered at a temperature most suitable for the particular steel analysis but not less than 850°F.

(4) All cylinders must be inspected by the magnetic particle or dye penetrant method to detect the presence of quenching cracks. Any cylinder found to have a quenching crack must be rejected and may not be requalified.

(h) *Openings in cylinders and connections (valves, fuse plugs, etc.) for those openings.* Threads conforming to the following are required on openings:

(1) Threads must be clean cut, even, without cracks, and to gauge.

(2) Taper threads, when used, must be of length not less than as specified for National Gas Tapered Thread (NGT) as required by American Standard Compressed Gas Cylinder Valve Outlet and Inlet Connections.

(3) Straight threads having at least 6 engaged threads are authorized. Straight threads must have a tight fit and a calculated shear stress of at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(i) *Hydrostatic test.* Each cylinder must withstand a hydrostatic test, as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. Pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy either of 1 percent of 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat treatment and previous to the official test may not exceed 90 percent of

the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Each cylinder must be tested to at least  $\frac{2}{3}$  times service pressure.

(j) *Cycling tests.* Prior to the initial shipment of any specific cylinder design, cyclic pressurization tests must have been performed on at least three representative samples without failure as follows:

(1) Pressurization must be performed hydrostatically between approximately zero psig and the service pressure at a rate not in excess of 10 cycles per minute. Adequate recording instrumentation must be provided if equipment is to be left unattended for periods of time.

(2) Tests prescribed in paragraph (j)(1) of this section must be repeated on one random sample out of each lot of cylinders. The cylinder may then be subjected to a burst test.

(3) A lot is defined as a group of cylinders fabricated from the same heat of steel, manufactured by the same process and heat treated in the same equipment under the same conditions of time, temperature, and atmosphere, and may not exceed a quantity of 200 cylinders.

(4) All cylinders used in cycling tests must be destroyed.

(k) *Burst test.* One cylinder taken at random out of each lot of cylinders must be hydrostatically tested to destruction.

(l) *Flattening test.* A flattening test must be performed on one cylinder taken at random out of each lot of 200 or less, by placing the cylinder between wedge shaped knife edges having a 60° included angle, rounded to  $\frac{1}{2}$ -inch radius. The longitudinal axis of the cylinder must be at a 90-degree angle to knife edges during the test. For lots of 30 or less, flattening tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.



(m) *Physical tests.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material, as follows:

(1) Test is required on 2 specimens cut from 1 cylinder taken at random out of each lot of cylinders.

(2) Specimens must conform to the following:

(i) A gauge length of at least 24 times the thickness with a width not over six times the thickness. The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within one inch of each end of the reduced section. When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with the record of physical tests detailed information in regard to such specimens.

(ii) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length.

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi, the strain indicator reading

being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(n) *Magnetic particle inspection.* Inspection must be performed on the inside of each container before closing and externally on each finished container after heat treatment. Evidence of discontinuities, which in the opinion of a qualified inspector may appreciably weaken or decrease the durability of the cylinder, must be cause for rejection.

(o) *Leakage test.* All spun cylinders and plugged cylinders must be tested for leakage by dry gas or dry air pressure after the bottom has been cleaned and is free from all moisture, subject to the following conditions and limitations:

(1) Pressure, approximately the same as but not less than service pressure, must be applied to one side of the finished bottom over an area of at least  $\frac{1}{16}$  of the total area of the bottom but not less than  $\frac{3}{4}$  inch in diameter, including the closure, for at least one minute, during which time the other side of the bottom exposed to pressure must be covered with water and closely examined for indications of leakage. Except as provided in paragraph (q) of this section, a cylinder must be rejected if there is leakage.

(2) A spun cylinder is one in which an end closure in the finished cylinder has been welded by the spinning process.

(3) A plugged cylinder is one in which a permanent closure in the bottom of a finished cylinder has been effected by a plug.

(4) As a safety precaution, if the manufacturer elects to make this test before the hydrostatic test, the manufacturer should design the test apparatus so that the pressure is applied to the smallest area practicable, around the point of closure, and so as to use the smallest possible volume of air or gas.

(p) *Acceptable results of tests.* Results of the flattening test, physical tests, burst test, and cycling test must conform to the following:

(1) Flattening required without cracking to ten times the wall thickness of the cylinder.

(2) Physical tests:

(i) An elongation of at least 6 percent for a gauge length of 24 times the wall thickness.

(ii) The tensile strength may not exceed 165,000 p.s.i.

(3) The burst pressure must be at least  $\frac{4}{3}$  times the test pressure.

(4) Cycling—at least 10,000 pressurizations.

(q) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinders. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding or spinning is not authorized. For each cylinder subjected to reheat treatment during original manufacture, sidewall measurements must be made to verify that the minimum sidewall thickness meets specification requirements after the final heat treatment.

(r) *Marking.* (1) Cylinders must be marked by low stress type steel stamping in an area and to a depth which will insure that the wall thickness measured from the root of the stamping to the interior surface is equal to or greater than the minimum prescribed wall thickness. Stamping must be permanent and legible. Stamping on side wall not authorized.

(2) The rejection elastic expansion (REE), in cubic cm (cc), must be marked on the cylinder near the date of test. The REE for a cylinder is 1.05 times its original elastic expansion.

(3) Name plates are authorized, provided that they can be permanently and securely attached to the cylinder. Attachment by either brazing or welding is not permitted. Attachment by soldering is permitted provided steel temperature does not exceed 500 °F.

(s) *Inspector's report.* In addition to the requirements of § 178.35, the inspector's report must indicate the rejection elastic expansion (REE), in cubic cm (cc).

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 62 FR 51561, Oct. 1, 1997; 65 FR 58631, Sept. 29, 2000; 66 FR 45385, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 75748, 75749, Dec. 31, 2003]

#### § 178.45 Specification 3T seamless steel cylinder.

(a) *Type, size, and service pressure.* A DOT 3T cylinder is a seamless steel cylinder with a minimum water capacity of 1,000 pounds and a minimum service pressure of 1,800 psig. Each cylinder must have integrally formed heads concave to pressure at both ends. The inside head shape must be hemispherical, ellipsoidal in which the major axis is two times the minor axis, or a dished shape falling within these two limits. Permanent closures formed by spinning are prohibited.

(b) *Material, steel.* Only open hearth, basic oxygen, or electric furnace process steel of uniform quality is authorized. The steel analysis must conform to the following:

ANALYSIS TOLERANCES

| Element                | Ladle analysis     | Check Analysis |      |
|------------------------|--------------------|----------------|------|
|                        |                    | Under          | Over |
| Carbon .....           | 0.35 to 0.50 ..... | 0.03           | 0.04 |
| Manganese .....        | 0.75 to 1.05 ..... | 0.04           | 0.04 |
| Phosphorus (max) ..... | 0.035 .....        | .....          | 0.01 |
| Sulphur (max) .....    | 0.04 .....         | .....          | 0.01 |
| Silicon .....          | 0.15 to 0.35 ..... | 0.02           | 0.03 |
| Chromium .....         | 0.80 to 1.15 ..... | 0.05           | 0.05 |
| Molybdenum .....       | 0.15 to 0.25 ..... | 0.02           | 0.02 |

(1) A heat of steel made under the specifications in the table in this paragraph (b), the ladle analysis of which is slightly out of the specified range, is acceptable if satisfactory in all other aspects. However, the check analysis tolerances shown in the table in this paragraph (b) may not be exceeded except as approved by the Department.

(2) Material with seams, cracks, laminations, or other injurious defects is not permitted.

(3) Material used must be identified by any suitable method.

(c) *Manufacture.* General manufacturing requirements are as follows:

(1) Surface finish must be uniform and reasonably smooth.

(2) Inside surfaces must be clean, dry, and free of loose particles.

(3) No defect of any kind is permitted if it is likely to weaken a finished cylinder.

(4) If the cylinder surface is not originally free from the defects, the surface may be machined or otherwise treated to eliminate these defects provided the

§ 178.45

49 CFR Ch. I (10–1–08 Edition)

minimum wall thickness is maintained.

(5) Welding or brazing on a cylinder is not permitted.

(d) *Wall thickness.* The minimum wall thickness must be such that the wall stress at the minimum specified test pressure does not exceed 67 percent of the minimum tensile strength of the steel as determined by the physical tests required in paragraphs (j) and (k) of this section. A wall stress of more than 90,500 p.s.i. is not permitted. The minimum wall thickness for any cylinder may not be less than 0.225 inch.

(1) Calculation of the stress for cylinders must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = Wall stress in psi;

P = Minimum test pressure, at least  $\frac{2}{3}$  service pressure;

D = Outside diameter in inches;

d = Inside diameter in inches.

(2) Each cylinder must meet the following additional requirement which assumes a cylinder horizontally supported at its two ends and uniformly loaded over its entire length. This load consists of the weight per inch of length of the straight cylindrical portion filled with water compressed to the specified test pressure. The wall thickness must be increased when necessary to meet this additional requirement:

(i) The sum of two times the maximum tensile stress in the bottom fibers due to bending (see paragraph (d)(2)(ii) of this section), plus the maximum tensile stress in the same fibers due to hydrostatic testing (see paragraph (d)(2)(iii) of this section) may not exceed 80 percent of the minimum yield strength of the steel at this maximum stress.

(ii) The following formula must be used to calculate the maximum tensile stress due to bending:

$$S = Mc / I$$

Where:

S = Tensile stress in psi;

M = Bending moment in inch-pounds ( $wl^2/8$ );

I = Moment of inertia— $0.04909 (D^4 - d^4)$  in inches fourth;

c = Radius ( $D/2$ ) of cylinder in inches;

w = Weight per inch of cylinder filled with water;

l = Length of cylinder in inches;

D = Outside diameter in inches;

d = Inside diameter in inches.

(iii) The following formula must be used to calculate the maximum longitudinal tensile stress due to hydrostatic test pressure:

$$S = A_1 P / A_2$$

Where:

S = Tensile stress in psi;

A<sub>1</sub> = Internal area in cross section of cylinder in square inches;

P = Hydrostatic test pressure-psi;

A<sub>2</sub> = Area of metal in cross section of cylinder in square inches.

(e) *Heat treatment.* Each completed cylinder must be uniformly and properly heat treated prior to testing, as follows:

(1) Each cylinder must be heated and held at the proper temperature for at least one hour per inch of thickness based on the maximum thickness of the cylinder and then quenched in a suitable liquid medium having a cooling rate not in excess of 80 percent of water. The steel temperature on quenching must be that recommended for the steel analysis, but it must never exceed 1750 °F.

(2) After quenching, each cylinder must be reheated to a temperature below the transformation range but not less than 1050 °F., and must be held at this temperature for at least one hour per inch of thickness based on the maximum thickness of the cylinder. Each cylinder must then be cooled under conditions recommended for the steel.

(f) *Openings.* Openings in cylinders must comply with the following:

(1) Openings are permitted on heads only.

(2) The size of any centered opening in a head may not exceed one half the outside diameter of the cylinder.

(3) Openings in a head must have ligaments between openings of at least three times the average of their hole diameter. No off-center opening may exceed 2.625 inches in diameter.

(4) All openings must be circular.

(5) All openings must be threaded. Threads must be in compliance with the following:

(i) Each thread must be clean cut, even, without any checks, and to gauge.

(ii) Taper threads, when used, must be the American Standard Pipe thread (NPT) type and must be in compliance with the requirements of NBS Handbook H-28 (IBR, see §171.7 of this subchapter).

(iii) Taper threads conforming to National Gas Taper thread (NGT) standards must be in compliance with the requirements of NBS Handbook H-28.

(iv) Straight threads conforming with National Gas Straight thread (NGS) standards are authorized. These threads must be in compliance with the requirements of NBS Handbook H-28.

(g) *Hydrostatic test.* Each cylinder must be tested at an internal pressure by the water jacket method or other suitable method, conforming to the following requirements:

(1) The testing apparatus must be operated in a manner that will obtain accurate data. Any pressure gauge used must permit reading to an accuracy of one percent. Any expansion gauge used must permit reading of the total expansion to an accuracy of one percent.

(2) Any internal pressure applied to the cylinder after heat treatment and before the official test may not exceed 90 percent of the test pressure.

(3) The pressure must be maintained sufficiently long to assure complete expansion of the cylinder. In no case may the pressure be held less than 30 seconds.

(4) If, due to failure of the test apparatus, the required test pressure cannot be maintained, the test must be repeated at a pressure increased by 10 percent or 100 psig, whichever is lower or, the cylinder must be reheated.

(5) Permanent volumetric expansion of the cylinder may not exceed 10 percent of its total volumetric expansion at the required test pressure.

(6) Each cylinder must be tested to at least  $\frac{5}{8}$  times its service pressure.

(h) *Ultrasonic examination.* After the hydrostatic test, the cylindrical section of each vessel must be examined in accordance with ASTM E 213 for shear wave and E 114 for straight beam (IBR, Standard see §171.7 of this subchapter). The equipment used must be calibrated to detect a notch equal to five percent

of the design minimum wall thickness. Any discontinuity indication greater than that produced by the five percent notch must be cause for rejection of the cylinder, unless the discontinuity is repaired within the requirements of this specification.

(i) *Basic requirements for tension and Charpy impact tests.* Cylinders must be subjected to a tension and Charpy impact as follows:

(1) When the cylinders are heat treated in a batch furnace, two tension specimens and three Charpy impact specimens must be tested from one of the cylinders or a test ring from each batch. The lot size represented by these tests may not exceed 200 cylinders.

(2) When the cylinders are heat treated in a continuous furnace, two tension specimens and three Charpy impact specimens must be tested from one of the cylinders or a test ring from each four hours or less of production. However, in no case may a test lot based on this production period exceed 200 cylinders.

(3) Each specimen for the tension and Charpy impact tests must be taken from the side wall of a cylinder or from a ring which has been heat treated with the finished cylinders of which the specimens must be representative. The axis of the specimens must be parallel to the axis of the cylinder. Each cylinder or ring specimen for test must be of the same diameter, thickness, and metal as the finished cylinders they represent. A test ring must be at least 24 inches long with ends covered during the heat treatment process so as to simulate the heat treatment process of the finished cylinders it represents.

(4) A test cylinder or test ring need represent only one of the heats in a furnace batch provided the other heats in the batch have previously been tested and have passed the tests and that such tests do not represent more than 200 cylinders from any one heat.

(5) The test results must conform to the requirements specified in paragraphs (j) and (k) of this section.

(6) When the test results do not conform to the requirements specified, the cylinders represented by the tests may be reheated and the tests repeated. Paragraph (i)(5) of this section applies to any retesting.

§ 178.46

49 CFR Ch. I (10–1–08 Edition)

(j) *Basic conditions for acceptable physical testing.* The following criteria must be followed to obtain acceptable physical test results:

(1) Each tension specimen must have a gauge length of two inches with a width not exceeding one and one-half inches. Except for the grip ends, the specimen may not be flattened. The grip ends may be flattened to within one inch of each end of the reduced section.

(2) A specimen may not be heated after heat treatment specified in paragraph (d) of this section.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gage length.

(i) This yield strength must be determined by the “offset” method or the “extension under load” method described in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) For the “extension under load” method, the total strain (or extension under load) corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gage length under appropriate load and adding thereto 0.2 percent of the gage length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. However, when the degree of accuracy of this method is questionable the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set with the specimen under a stress of 12,000 p.s.i. and the strain indicator reading set at the calculated corresponding strain.

(iv) The cross-head speed of the testing machine may not exceed 1/8 inch per minute during the determination of yield strength.

(4) Each impact specimen must be Charpy V-notch type size 10 mm × 10 mm taken in accordance with paragraph 11 of ASTM A 333 (IBR, see § 171.7 of this subchapter). When a reduced size specimen is used, it must be the largest size obtainable.

(k) *Acceptable physical test results.* Results of physical tests must conform to the following:

(1) The tensile strength may not exceed 155,000 p.s.i.

(2) The elongation must be at least 16 percent for a two-inch gage length.

(3) The Charpy V-notch impact properties for the three impact specimens which must be tested at 0 °F may not be less than the values shown as follows:

| Size of specimen (mm) | Average value for acceptance (3 specimens) | Minimum value (1 specimen only of the 3) |
|-----------------------|--------------------------------------------|------------------------------------------|
| 10.0×10.0 .....       | 25.0 ft. lbs. ....                         | 20.0 ft. lbs.                            |
| 10.0×7.5 .....        | 21.0 ft. lbs. ....                         | 17.0 ft. lbs.                            |
| 10.0×5.0 .....        | 17.0 ft. lbs. ....                         | 14.0 ft. lbs.                            |

(4) After the final heat treatment, each vessel must be hardness tested on the cylindrical section. The tensile strength equivalent of the hardness number obtained may not be more than 165,000 p.s.i. (Rc 36). When the result of a hardness test exceeds the maximum permitted, two or more retests may be made; however, the hardness number obtained in each retest may not exceed the maximum permitted.

(l) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinders. However, each reheat treated cylinder must subsequently pass all the prescribed tests. Repair by welding is not authorized.

(m) *Markings.* Marking must be done by stamping into the metal of the cylinder. All markings must be legible and located on a shoulder.

(n) *Inspector's report.* In addition to the requirements of § 178.35, the inspector's report for the physical test report, must indicate the average value for three specimens and the minimum value for one specimen for each lot number.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45385, 43588, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 48571, Aug. 14, 2003; 68 FR 75748, 75749, Dec. 31, 2003]

**§ 178.46 Specification 3AL seamless aluminum cylinders.**

(a) *Size and service pressure.* A DOT 3AL cylinder is a seamless aluminum cylinder with a maximum water capacity of 1000 pounds and minimum service pressure of 150 psig.

(b) *Authorized material and identification of material.* The material of construction must meet the following conditions:

(1) Starting stock must be cast stock or traceable to cast stock.

(2) Material with seams, cracks, laminations, or other defects likely to weaken the finished cylinder may not be used.

(3) Material must be identified by a suitable method that will identify the alloy, the aluminum producer's cast number, the solution heat treat batch number and the lot number.

(4) The material must be of uniform quality. Only the following heat treatable aluminum alloys in table 1 and 2 are permitted as follows:

TABLE 1—HEAT OR CAST ANALYSIS FOR ALUMINUM; SIMILAR TO “ALUMINUM ASSOCIATION”<sup>1</sup> ALLOY 6061

[CHEMICAL ANALYSIS IN WEIGHT PERCENT<sup>2</sup>]

| Si<br>min/<br>max | Fe<br>max | Cu<br>min/max | Mn<br>max | Mg<br>min/<br>max | Cr<br>min/max | Zn<br>max | Ti<br>max | Pb<br>max | Bi<br>max | Other       |              | A1   |
|-------------------|-----------|---------------|-----------|-------------------|---------------|-----------|-----------|-----------|-----------|-------------|--------------|------|
|                   |           |               |           |                   |               |           |           |           |           | each<br>max | total<br>max |      |
| 0.4/0.8           | 0.7       | 0.15/0.4      | 0.15      | 0.8/1.2           | 0.04/0.35     | 0.25      | 0.15      | 0.005     | 0.005     | 0.05        | 0.15         | Bal. |

<sup>1</sup> The “Aluminum Association” refers to “Aluminum Standards and Data 1993”, published by the Aluminum Association Inc.  
<sup>2</sup> Except for “Pb” and “Bi”, the chemical composition corresponds with that of Table 1 of ASTM B 221 (IBR, see § 171.7 of this subchapter) for Aluminum Association alloy 6061.

TABLE 2—MECHANICAL PROPERTY LIMITS

| Alloy and temper | Tensile strength—PSI |               | Elongation—percent<br>minimum for 2" or<br>4D <sup>1</sup> size specimen |
|------------------|----------------------|---------------|--------------------------------------------------------------------------|
|                  | Ultimate—minimum     | Yield—minimum |                                                                          |
| 6061—T6 .....    | 38,000               | 35,000        | <sup>2</sup> 14                                                          |

<sup>1</sup> “D” represents specimen diameters. When the cylinder wall is greater than  $\frac{3}{16}$  inch thick, a retest without reheat treatment using the 4D size specimen is authorized if the test using the 2 inch size specimen fails to meet elongation requirements.

<sup>2</sup> When cylinder wall is not over  $\frac{3}{16}$ -inch thick, 10 percent elongation is authorized when using a 24x6t size test specimen.

(5) All starting stock must be 100 percent ultrasonically inspected, along the length at right angles to the central axis from two positions at 90° to one another. The equipment and continuous scanning procedure must be capable of detecting and rejecting internal defects such as cracks which have an ultrasonic response greater than that of a calibration block with a  $\frac{5}{64}$ -inch diameter flat bottomed hole.

(6) Cast stock must have uniform equiaxed grain structure not to exceed 500 microns maximum.

(7) Any starting stock not complying with the provisions of paragraphs (b)(1) through (b)(6) of this section must be rejected.

(c) *Manufacture.* Cylinders must be manufactured in accordance with the following requirements:

(1) Cylinder shells must be manufactured by the backward extrusion method and have a cleanliness level adequate to ensure proper inspection. No fissure or other defect is acceptable that is likely to weaken the finished

cylinder below the design strength requirements. A reasonably smooth and uniform surface finish is required. If not originally free from such defects, the surface may be machined or otherwise conditioned to eliminate these defects.

(2) Thickness of the cylinder base may not be less than the prescribed minimum wall thickness of the cylindrical shell. The cylinder base must have a basic torispherical, hemispherical, or ellipsoidal interior base configuration where the dish radius is no greater than 1.2 times the inside diameter of the shell. The knuckle radius may not be less than 12 percent of the inside diameter of the shell. The interior base contour may deviate from the true torispherical, hemispherical or ellipsoidal configuration provided that—

(i) Any areas of deviation are accompanied by an increase in base thickness;

(ii) All radii of merging surfaces are equal to or greater than the knuckle radius;

§ 178.46

49 CFR Ch. I (10–1–08 Edition)

(iii) Each design has been qualified by successfully passing the cycling tests in this paragraph (c); and

(iv) Detailed specifications of the base design are available to the inspector.

(3) For free standing cylinders, the base thickness must be at least two times the minimum wall thickness along the line of contact between the cylinder base and the floor when the cylinders are in the vertical position.

(4) Welding or brazing is prohibited.

(5) Each new design and any significant change to any acceptable design must be qualified for production by testing prototype samples as follows:

(i) Three samples must be subjected to 100,000 pressure reversal cycles between zero and service pressure or 10,000 pressure reversal cycles between zero and test pressure, at a rate not in excess of 10 cycles per minute without failure.

(ii) Three samples must be pressurized to destruction and failure may not occur at less than 2.5 times the marked cylinder service pressure. Each cylinder must remain in one piece. Failure must initiate in the cylinder side-wall in a longitudinal direction. Rate of pressurization may not exceed 200 psig per second.

(6) In this specification “significant change” means a 10 percent or greater change in cylinder wall thickness, service pressure, or diameter; a 30 percent or greater change in water capacity or base thickness; any change in material; over 100 percent increase in size of openings; or any change in the number of openings.

(d) *Wall thickness.* The minimum wall thickness must be such that the wall stress at the minimum specified test pressure will not exceed 80 percent of the minimum yield strength nor exceed 67 percent of the minimum ultimate tensile strength as verified by physical tests in paragraph (i) of this section. The minimum wall thickness for any cylinder with an outside diameter greater than 5 inches must be 0.125 inch. Calculations must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = Wall stress in psi;

P = Prescribed minimum test pressure in psig (see paragraph (g) of this section);

D = Outside diameter in inches; and

d = Inside diameter in inches.

(e) *Openings.* Openings must comply with the following requirements:

(1) Openings are permitted in heads only.

(2) The size of any centered opening in a head may not exceed one-half the outside diameter of the cylinder.

(3) Other openings are permitted in the head of a cylinder if:

(i) Each opening does not exceed 2.625 inches in diameter, or one-half the outside diameter of the cylinder; whichever is less;

(ii) Each opening is separated from each other by a ligament; and

(iii) Each ligament which separates two openings must be at least three times the average of the diameters of the two openings.

(4) All openings must be circular.

(5) All openings must be threaded. Threads must comply with the following:

(i) Each thread must be clean cut, even, without checks, and to gauge.

(ii) Taper threads, when used, must conform to one of the following:

(A) American Standard Pipe Thread (NPT) type, conforming to the requirements of NBS Handbook H-28 (IBR, see § 171.7 of this subchapter);

(B) National Gas Taper Thread (NGT) type, conforming to the requirements of NBS Handbook H-28; or

(C) Other taper threads conforming to other standards may be used provided the length is not less than that specified for NPT threads.

(iii) Straight threads, when used, must conform to one of the following:

(A) National Gas Straight Thread (NGS) type, conforming to the requirements of NBS Handbook H-28;

(B) Unified Thread (UN) type, conforming to the requirements of NBS Handbook H-28;

(C) Controlled Radius Root Thread (UN) type, conforming to the requirements of NBS Handbook H-28; or

(D) Other straight threads conforming to other recognized standards may be used provided that the requirements in paragraph (e)(5)(iv) of this section are met.

(iv) All straight threads must have at least 6 engaged threads, a tight fit, and a factor of safety in shear of at least 10 at the test pressure of the cylinder. Shear stress must be calculated by using the appropriate thread shear area in accordance with NBS Handbook H-28.

(f) *Heat treatment.* Prior to any test, all cylinders must be subjected to a solution heat treatment and aging treatment appropriate for the aluminum alloy used.

(g) *Hydrostatic test.* Each cylinder must be subjected to an internal test pressure using the water jacket equipment and method or other suitable equipment and method and comply with the following requirements:

(1) The testing apparatus must be operated in a manner so as to obtain accurate data. The pressure gauge used must permit reading to an accuracy of one percent. The expansion gauge must permit reading the total expansion to an accuracy of either one percent or 0.1 cubic centimeter.

(2) The test pressure must be maintained for a sufficient period of time to assure complete expansion of the cylinder. In no case may the pressure be held less than 30 seconds. If, due to failure of the test apparatus, the required test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is lower. If the test apparatus again fails to maintain the test pressure, the cylinder being tested must be rejected. Any internal pressure applied to the cylinder before any official test may not exceed 90 percent of the test pressure.

(3) The minimum test pressure is the greatest of the following:

(i) 450 psig regardless of service pressure;

(ii) Two times the service pressure for cylinders having service pressure less than 500 psig; or

(iii) Five-thirds times the service pressure for cylinders having a service pressure of at least 500 psig.

(4) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(h) *Flattening test.* One cylinder taken at random out of each lot must be subjected to a flattening test as follows:

(1) The test must be between knife edges, wedge shaped, having a 60° included angle, and rounded in accordance with the following table. The longitudinal axis of the cylinder must be at an angle 90° to the knife edges during the test. The flattening test table is as follows:

TABLE 3—FLATTENING TEST TABLE

| Cylinder wall thickness in inches | Radius in inches |
|-----------------------------------|------------------|
| Under .150 .....                  | .500             |
| .150 to .249 .....                | .875             |
| .250 to .349 .....                | 1.500            |
| .350 to .449 .....                | 2.125            |
| .450 to .549 .....                | 2.750            |
| .550 to .649 .....                | 3.500            |
| .650 to .749 .....                | 4.125            |

(2) An alternate bend test in accordance with ASTM E 290 using a mandrel diameter not more than 6 times the wall thickness is authorized to qualify lots that fail the flattening test of this section without reheat treatment. If used, this test must be performed on two samples from one cylinder taken at random out of each lot of 200 cylinders or less.

(3) Each test cylinder must withstand flattening to nine times the wall thickness without cracking. When the alternate bend test is used, the test specimens must remain uncracked when bent inward around a mandrel in the direction of curvature of the cylinder wall until the interior edges are at a distance apart not greater than the diameter of the mandrel.

(i) *Mechanical properties test.* Two test specimens cut from one cylinder representing each lot of 200 cylinders or less must be subjected to the mechanical properties test, as follows:

(1) The results of the test must conform to at least the minimum acceptable mechanical property limits for aluminum alloys as specified in paragraph (b) of this section.

(2) Specimens must be 4D bar or gauge length 2 inches with width not over 1½ inch taken in the direction of extrusion approximately 180° from each other; provided that gauge length at least 24 times thickness with width not over 6 times thickness is authorized, when cylinder wall is not over ⅜ inch thick. The specimen, exclusive of grip ends, may not be flattened. Grip ends



may be flattened to within one inch of each end of the reduced section. When the size of the cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold by pressure only, not by blows. When such specimens are used, the inspector's report must show that the specimens were so taken and prepared. Heating of specimens for any purpose is forbidden.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length.

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM B 557 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 10,000,000 psi. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 6,000 psi, the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(j) *Rejected cylinder.* Reheat treatment of rejected cylinders is authorized one time. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable.

(k) *Duties of inspector.* In addition to the requirements of § 178.35, the inspector shall:

(1) Verify compliance with the provisions of paragraph (b) of this section by:

(i) Performing or witnessing the performance of the chemical analyses on each melt or cast lot or other unit of starting material; or

(ii) Obtaining a certified chemical analysis from the material or cylinder manufacturer for each melt, or cast of material; or

(iii) Obtaining a certified check analysis on one cylinder out of each lot of 200 cylinders or less, if a certificate containing data to indicate compliance with the material specification is obtained.

(2) The inspector shall verify ultrasonic inspection of all material by inspection or by obtaining the material producer's certificate of ultrasonic inspection. Ultrasonic inspection must be performed or verified as having been performed in accordance with paragraph (c) of this section.

(3) The inspector must also determine that each cylinder complies with this specification by:

(i) Selecting the samples for check analyses performed by other than the material producer;

(ii) Verifying that the prescribed minimum thickness was met by measuring or witnessing the measurement of the wall thickness; and

(iii) Verifying that the identification of material is proper.

(4) Prior to initial production of any design or design change, verify that the design qualification tests prescribed in paragraph (c)(6) of this section have been performed with acceptable results.

(l) *Definitions.* (1) In this specification, a "lot" means a group of cylinders successively produced having the same:

(i) Size and configuration;

(ii) Specified material of construction;

(iii) Process of manufacture and heat treatment;

(iv) Equipment of manufacture and heat treatment; and

(v) Conditions of time, temperature and atmosphere during heat treatment.

(2) In no case may the lot size exceed 200 cylinders, but any cylinder processed for use in the required destructive physical testing need not be counted as being one of the 200.

(m) *Inspector's report.* In addition to the information required by § 178.35, the record of chemical analyses must also include the alloy designation, and applicable information on iron, titanium, zinc, magnesium and any other applicable element used in the construction of the cylinder.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386-45388, Aug. 28, 2001; 67 FR 51652, Aug. 8, 2002; 68 FR 75749, Dec. 31, 2003]

**§ 178.47 Specification 4DS welded stainless steel cylinders for aircraft use.**

(a) *Type, size, and service pressure.* A DOT 4DS cylinder is either a welded stainless steel sphere (two seamless

hemispheres) or circumferentially welded cylinder both with a water capacity of not over 100 pounds and a service pressure of at least 500 but not over 900 psig.

(b) *Steel.* Types 304, 321 and 347 stainless steel are authorized with proper welding procedure. A heat of steel made under the specifications in table 1 in this paragraph (b), check chemical analysis of which is slightly out of the specified range, is acceptable, if satisfactory in all other respects, provided the tolerances shown in table 2 in this paragraph (b) are not exceeded, except as approved by Associate Administrator. The following chemical analyses are authorized:

TABLE 1—AUTHORIZED MATERIALS

|                        | Stainless steels |                  |                  |
|------------------------|------------------|------------------|------------------|
|                        | 304 (percent)    | 321 (percent)    | 347 (percent)    |
| Carbon (max) .....     | 0.08             | 0.08             | 0.08             |
| Manganese (max) .....  | 2.00             | 2.00             | 2.00             |
| Phosphorus (max) ..... | .030             | .030             | .030             |
| Sulphur (max) .....    | .030             | .030             | .030             |
| Silicon (max) .....    | .75              | .75              | .75              |
| Nickel .....           | 8.0/11.0         | 9.0/13.0         | 9.0/13.0         |
| Chromium .....         | 18.0/20.0        | 17.0/20.0        | 17.0/20.0        |
| Molybdenum .....       |                  |                  |                  |
| Titanium .....         |                  | ( <sup>1</sup> ) |                  |
| Columbium .....        |                  |                  | ( <sup>2</sup> ) |

<sup>1</sup> Titanium may not be more than 5C and not more than 0.60%.

<sup>2</sup> Columbium may not be less than 10C and not more than 1.0%.

TABLE 2—CHECK ANALYSIS TOLERANCES

| Element                       | Limit or maximum specified (percent) | Tolerance (percent) over the maximum limit or under the minimum limit |                    |
|-------------------------------|--------------------------------------|-----------------------------------------------------------------------|--------------------|
|                               |                                      | Under minimum limit                                                   | Over maximum limit |
| Carbon .....                  | To 0.15 incl .....                   | 0.01                                                                  | 0.01               |
| Manganese .....               | Over 1.15 to 2.50 incl .....         | 0.05                                                                  | 0.05               |
| Phosphorus <sup>1</sup> ..... | All ranges .....                     |                                                                       | .01                |
| Sulphur .....                 | All ranges .....                     |                                                                       | .01                |
| Silicon .....                 | Over 0.30 to 1.00 incl .....         | .05                                                                   | .05                |
| Nickel .....                  | Over 5.30 to 10.00 incl .....        | .10                                                                   | .10                |
|                               | Over 10.00 to 14.00 incl .....       | .15                                                                   | .15                |
| Chromium .....                | Over 15.00 to 20.00 incl .....       | .20                                                                   | .20                |
| Titanium .....                | All ranges .....                     | .05                                                                   | .05                |
| Columbium .....               | All ranges .....                     | .05                                                                   | .05                |

<sup>1</sup>Rephosphorized steels not subject to check analysis for phosphorus.

(c) *Identification of material.* Materials must be identified by any suitable method.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the re-

quirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably, a reasonably smooth and uniform surface finish is required. No abrupt change in wall thickness is permitted. Welding procedures and operators must be qualified

in accordance with CGA Pamphlet C–3 (IBR, see § 171.7 of this subchapter). All seams of the sphere or cylinder must be fusion welded. Seams must be of the butt type and means must be provided for accomplishing complete penetration of the joint.

(e) *Attachments.* Attachments to the container are authorized by fusion welding provided that such attachments are made of weldable stainless steel in accordance with paragraph (b) of this section.

(f) *Wall thickness.* The minimum wall thickness must be such that the wall stress at the minimum specified test pressure may not be over 60,000 psig. A minimum wall thickness of 0.040 inch is required for any diameter container. Calculations must be made by the following formulas:

(1) Calculation for sphere must be made by the formula:

$$S = PD / 4tE$$

Where:

S = Wall stress in psi;

P = Test pressure prescribed for water jacket test, i.e., at least two times service pressure, in psig;

D = Outside diameter in inches;

t = Minimum wall thickness in inches;

E = 0.85 (provides 85 percent weld efficiency factor which must be applied in the girth weld area and heat zones which zone must extend a distance of 6 times wall thickness from center of weld);

E = 1.0 (for all other areas).

(2) Calculation for a cylinder must be made by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = Wall stress in psi;

P = Test pressure prescribed for water jacket test, i.e., at least two times service pressure, in psig;

D = Outside diameter in inches;

d = Inside diameter in inches.

(g) *Heat treatment.* The seamless hemispheres and cylinders may be stress relieved or annealed for forming. Welded container must be stress relieved at a temperature of 775 °F ±25° after process treatment and before hydrostatic test.

(h) *Openings in container.* Openings must comply with the following:

(1) Each opening in the container must be provided with a fitting, boss or

pad of weldable stainless steel securely attached to the container by fusion welding.

(2) Attachments to a fitting, boss, or pad must be adequate to prevent leakage. Threads must comply with the following:

(i) Threads must be clean cut, even, without checks, and tapped to gauge.

(ii) Taper threads to be of length not less than as specified for American Standard taper pipe threads.

(iii) Straight threads having at least 4 engaged threads, to have tight fit and calculated shear strength at least 10 times the test pressure of the container; gaskets required, adequate to prevent leakage.

(i) *Process treatment.* Each container must be hydraulically pressurized in a water jacket to at least 100 percent, but not more than 110 percent, of the test pressure and maintained at this pressure for a minimum of 3 minutes. Total and permanent expansion must be recorded and included in the inspector's report.

(j) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test as follows:

(1) The test must be by water-jacket, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy either of 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Each container must be tested to at least 2 times service pressure.

(5) Container must then be inspected. Any wall thickness lower than that required by paragraph (f) of this section must be cause for rejection. Bulges and cracks must be cause for rejection. Welded joint defects exceeding requirements of paragraph (k) of this section must be cause for rejection.

(k) *Radiographic inspection.* Radiographic inspection is required on all welded joints which are subjected to internal pressure, except that at the discretion of the disinterested inspector, openings less than 25 percent of the container diameter need not be subjected to radiographic inspection. Evidence of any defects likely to seriously weaken the container is cause for rejection. Radiographic inspection must be performed subsequent to the hydrostatic test.

(l) *Burst test.* One container taken at random out of 200 or less must be hydrostatically tested to destruction. Rupture pressure must be included as part of the inspector's report.

(m) *Flattening test.* A flattening test must be performed as follows:

(1) For spheres the test must be at the weld between parallel steel plates on a press with welded seam at right angles to the plates. Test one sphere taken at random out of each lot of 200 or less after the hydrostatic test. Any projecting appurtenances may be cut off (by mechanical means only) prior to crushing.

(2) For cylinders the test must be between knife edges, wedge shaped, 60° angle, rounded to ½-inch radius. Test one cylinder taken at random out of each lot of 200 or less, after the hydrostatic test.

(n) *Acceptable results for flattening and burst tests.* Acceptable results for flattening and burst tests are as follows:

(1) Flattening required to 50 percent of the original outside diameter without cracking.

(2) Burst pressure must be at least 3 times the service pressure.

(o) *Rejected containers.* Repair of welded seams by welding prior to process treatment is authorized. Subsequent thereto, containers must be heat treated and pass all prescribed tests.

(p) *Duties of inspector.* In addition to the requirements of §178.35, the inspector must verify that all tests are conducted at temperatures between 60 °F and 90 °F.

(q) *Marking.* Markings must be stamped plainly and permanently on a permanent attachment or on a metal nameplate permanently secured to the

container by means other than soft solder.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386, 45388, Aug. 28, 2001; 67 FR 51653, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

#### **§178.50 Specification 4B welded or brazed steel cylinders.**

(a) *Type, size, and service pressure.* A DOT 4B is a welded or brazed steel cylinder with longitudinal seams that are forged lap-welded or brazed and with water capacity (nominal) not over 1,000 pounds and a service pressure of at least 150 but not over 500 psig. Cylinders closed in by spinning process are not authorized.

(b) *Steel.* Open-hearth, electric or basic oxygen process steel of uniform quality must be used. Content percent may not exceed the following: Carbon, 0.25; phosphorus, 0.045; sulphur, 0.050.

(c) *Identification of material.* Material must be identified by any suitable method except that plates and billets for hotdrawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. Exposed bottom welds on cylinders over 18 inches long must be protected by footrings. Welding procedures and operators must be qualified in accordance with CGA Pamphlet C-3 (IBR, see §171.7 of this subchapter). Seams must be made as follows:

(1) *Welded or brazed circumferential seams.* Heads attached by brazing must have a driving fit with the shell, unless the shell is crimped, swedged, or curled over the skirt or flange of the head, and be thoroughly brazed until complete penetration by the brazing material of the brazed joint is secured. Depth of brazing from end of shell must be at least four times the thickness of shell metal.

(2) *Longitudinal seams in shells.* Longitudinal seams must be forged lap welded, by copper brazing, by copper alloy

brazing, or by silver alloy brazing. Copper alloy composition must be: Copper, 95 percent minimum; Silicon, 1.5 percent to 3.85 percent; Manganese, 0.25 percent to 1.10 percent. The melting point of the silver alloy brazing material must be in excess of 1000 °F. When brazed, the plate edge must be lapped at least eight times the thickness of plate, laps being held in position, substantially metal to metal, by riveting or electric spot-welding; brazing must be done by using a suitable flux and by placing brazing material on one side of seam and applying heat until this material shows uniformly along the seam of the other side.

(e) *Welding or brazing.* Only the attachment of neckrings, footrings, handles, bosses, pads, and valve protection rings to the tops and bottoms of cylinders by welding or brazing is authorized. Such attachments and the portion of the container to which they are attached must be made of weldable steel, the carbon content of which may not exceed 0.25 percent except in the case of 4130X steel which may be used with proper welding procedure.

(f) *Wall thickness.* The wall thickness of the cylinder must comply with the following requirements:

(1) For cylinders with outside diameters over 6 inches the minimum wall thickness must be 0.090 inch. In any case, the minimum wall thickness must be such that calculated wall stress at minimum test pressure (paragraph (i)(4) of this section) may not exceed the following values:

(i) 24,000 psi for cylinders without longitudinal seam.

(ii) 22,800 psig for cylinders having copper brazed or silver alloy brazed longitudinal seam.

(iii) 18,000 psi for cylinders having forged lapped welded longitudinal seam.

(2) Calculation must be made by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test or 450 psig whichever is the greater;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* Cylinder body and heads, formed by drawing or pressing, must be uniformly and properly heat treated prior to tests.

(h) *Opening in cylinders.* Openings in cylinders must conform to the following:

(1) Each opening in cylinders, except those for safety devices, must be provided with a fitting, boss, or pad, securely attached to cylinder by brazing or by welding or by threads. Fitting, boss, or pad must be of steel suitable for the method of attachment employed, and which need not be identified or verified as to analysis except that if attachment is by welding, carbon content may not exceed 0.25 percent. If threads are used, they must comply with the following:

(i) Threads must be clean cut, even without checks, and tapped to gauge.

(ii) Taper threads to be of length not less than as specified for American Standard taper pipe threads.

(iii) Straight threads, having at least 4 engaged threads, to have tight fit and calculated shear strength at least 10 times the test pressure of the cylinder; gaskets required, adequate to prevent leakage.

(iv) A brass fitting may be brazed to the steel boss or flange on cylinders used as component parts of hand fire extinguishers.

(2) The closure of a fitting, boss, or pad must be adequate to prevent leakage.

(i) *Hydrostatic test.* Cylinders must withstand a hydrostatic test as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy either of 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10

percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Cylinders must be tested as follows:

(i) At least one cylinder selected at random out of each lot of 200 or less must be tested as outlined in paragraphs (i)(1), (i)(2), and (i)(3) of this section to at least two times service pressure.

(ii) All cylinders not tested as outlined in paragraph (i)(4)(i) of this section must be examined under pressure of at least two times service pressure and show no defect.

(j) *Flattening test.* After the hydrostatic test, a flattening test must be performed on one cylinder taken at random out of each lot of 200 or less, by placing the cylinder between wedge shaped knife edges having a 60° included angle, rounded to ½-inch radius. The longitudinal axis of the cylinder must be at a 90-degree angle to knife edges during the test. For lots of 30 or less, flattening tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(k) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material as follows:

(1) The test is required on 2 specimens cut from 1 cylinder, or part thereof heat-treated as required, taken at random out of each lot of 200 or less. For lots of 30 or less, physical tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to same heat treatment as the finished cylinder.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width of not over 1½ inches, a gauge length of 2 inches with a width of not over 1½ inches, or a gauge length at least 24 times the thickness with a width not over 6 times the thickness is authorized when a cylinder wall is not over ⅜ inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends

may be flattened to within one inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi, and strain indicator reading must be set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed ⅛ inch per minute during yield strength determination.

(l) *Acceptable results for physical and flattening tests.* Either of the following is an acceptable result:

(1) An elongation of at least 40 percent for a 2-inch gauge length or at least 20 percent in other cases and yield strength not over 73 percent of

## § 178.51

## 49 CFR Ch. I (10–1–08 Edition)

tensile strength. In this instance, a flattening test is not required.

(2) When cylinders are constructed of lap welded pipe, flattening test is required, without cracking, to 6 times the wall thickness. In such case, the rings (crop ends) cut from each end of pipe, must be tested with the weld 45° or less from the point of greatest stress. If a ring fails, another from the same end of pipe may be tested.

(m) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinder. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair of brazed seams by brazing and welded seams by welding is authorized.

(n) *Markings.* Markings must be stamped plainly and permanently in any of the following locations on the cylinder:

(1) On shoulders and top heads when they are not less than 0.087-inch thick.

(2) On side wall adjacent to top head for side walls which are not less than 0.090 inch thick.

(3) On a cylindrical portion of the shell which extends beyond the recessed bottom of the cylinder, constituting an integral and non-pressure part of the cylinder.

(4) On a metal plate attached to the top of the cylinder or permanent part thereof; sufficient space must be left on the plate to provide for stamping at least six retest dates; the plate must be at least 1/16-inch thick and must be attached by welding, or by brazing. The brazing rod must melt at a temperature of 1100 °F. Welding or brazing must be along all the edges of the plate.

(5) On the neck, neckring, valve boss, valve protection sleeve, or similar part permanently attached to the top of the cylinder.

(6) On the footring permanently attached to the cylinder, provided the water capacity of the cylinder does not exceed 25 pounds.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 62 FR 51561, Oct. 1, 1997; 66 FR 45385, 45388, Aug. 28, 2001; 67 FR 51653, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

### § 178.51 Specification 4BA welded or brazed steel cylinders.

(a) *Type, size, and service pressure.* A DOT 4BA cylinder is a cylinder, either spherical or cylindrical in shape, with a water capacity of 1,000 pounds or less and a service pressure of at least 225 and not over 500 psig. Closures made by the spinning process are not authorized.

(1) Spherical type cylinders must be made from two seamless hemispheres joined by the welding of one circumferential seam.

(2) Cylindrical type cylinders must be of circumferentially welded or brazed construction.

(b) *Steel.* The steel used in the construction of the cylinder must be as specified in table 1 of appendix A to this part.

(c) *Identification of material.* Material must be identified by any suitable method except that plates and billets for hotdrawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. Exposed bottom welds on cylinders over 18 inches long must be protected by footrings.

(1) Seams must be made as follows:

(i) Minimum thickness of heads and bottoms must be not less than 90 percent of the required thickness of the side wall.

(ii) Circumferential seams must be made by welding or by brazing. Heads must be attached by brazing and must have a driving fit with the shell, unless the shell is crimped, swedged or curled over the skirt or flange of the head and must be thoroughly brazed until complete penetration by the brazing material of the brazed joint is secured. Depth of brazing from end of the shell must be at least four times the thickness of shell metal.

(iii) Longitudinal seams in shells must be made by copper brazing, copper alloy brazing, or by silver alloy brazing. Copper alloy composition must be: Copper 95 percent minimum,

Silicon 1.5 percent to 3.85 percent, Manganese 0.25 percent to 1.10 percent. The melting point of the silver alloy brazing material must be in excess of 1,000 °F. The plate edge must be lapped at least eight times the thickness of plate, laps being held in position, substantially metal to metal, by riveting or by electric spot-welding. Brazing must be done by using a suitable flux and by placing brazing material on one side of seam and applying heat until this material shows uniformly along the seam of the other side. Strength of longitudinal seam: Copper brazed longitudinal seam must have strength at least  $\frac{3}{2}$  times the strength of the steel wall.

(2) Welding procedures and operators must be qualified in accordance with CGA Pamphlet C-3 (IBR, see §171.7 of this subchapter).

(e) *Welding and brazing.* Only the welding or brazing of neckrings, footrings, handles, bosses, pads, and valve protection rings to the tops and bottoms of cylinders is authorized. Provided that such attachments and the portion of the container to which they are attached are made of weldable steel, the carbon content of which may not exceed 0.25 percent except in the case of 4130X steel which may be used with proper welding procedure.

(f) *Wall thickness.* The minimum wall thickness of the cylinder must meet the following conditions:

(1) For any cylinder with an outside diameter of greater than 6 inches, the minimum wall thickness is 0.078 inch. In any case the minimum wall thickness must be such that the calculated wall stress at the minimum test pressure may not exceed the lesser value of any of the following:

(i) The value shown in table 1 of appendix A to this part, for the particular material under consideration;

(ii) One-half of the minimum tensile strength of the material determined as required in paragraph (j) of this section;

(iii) 35,000 psi; or

(iv) Further provided that wall stress for cylinders having copper brazed longitudinal seams may not exceed 95 percent of any of the above values. Measured wall thickness may not include

galvanizing or other protective coating.

(2) Cylinders that are cylindrical in shape must have the wall stress calculated by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test;

D = outside diameter in inches;

d = inside diameter in inches.

(3) Cylinders that are spherical in shape must have the wall stress calculated by the formula:

$$S = PD / 4tE$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test;

D = outside diameter in inches;

t = minimum wall thickness in inches;

E = 0.85 (provides 85 percent weld efficiency factor which must be applied in the girth weld area and heat affected zones which zone must extend a distance of 6 times wall thickness from center line of weld);

E = 1.0 (for all other areas).

(4) For a cylinder with a wall thickness less than 0.100 inch, the ratio of tangential length to outside diameter may not exceed 4.1.

(g) *Heat treatment.* Cylinders must be heat treated in accordance with the following requirements:

(1) Each cylinder must be uniformly and properly heat treated prior to test by the applicable method shown in table 1 of appendix A to this part. Heat treatment must be accomplished after all forming and welding operations, except that when brazed joints are used, heat treatment must follow any forming and welding operations, but may be done before, during or after the brazing operations.

(2) Heat treatment is not required after the welding or brazing of weldable low carbon parts to attachments of similar material which have been previously welded or brazed to the top or bottom of cylinders and properly heat treated, provided such subsequent welding or brazing does not produce a temperature in excess of 400 °F in any part of the top or bottom material.



(h) *Openings in cylinders.* Openings in cylinders must comply with the following requirements:

(1) Any opening must be placed on other than a cylindrical surface.

(2) Each opening in a spherical type cylinder must be provided with a fitting, boss, or pad of weldable steel securely attached to the container by fusion welding.

(3) Each opening in a cylindrical type cylinder must be provided with a fitting, boss, or pad, securely attached to container by brazing or by welding.

(4) If threads are used, they must comply with the following:

(i) Threads must be clean-cut, even, without checks and tapped to gauge.

(ii) Taper threads must be of a length not less than that specified for American Standard taper pipe threads.

(iii) Straight threads, having at least 4 engaged threads, must have a tight fit and a calculated shear strength of at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(i) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test, as follows:

(1) The test must be by water jacket, or other suitable method, operated so as to obtain accurate data. A pressure gauge must permit reading to an accuracy of 1 percent. An expansion gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat treatment and previous to the official test may not exceed 90 percent of the test pressure.

(3) Permanent volumetric expansion may not exceed 10 percent of the total volumetric expansion at test pressure.

(4) Cylinders must be tested as follows:

(i) At least one cylinder selected at random out of each lot of 200 or less must be tested as outlined in paragraphs (i)(1), (i)(2), and (i)(3) of this section to at least two times service pressure.

(ii) All cylinders not tested as outlined in paragraph (i)(4)(i) of this section must be examined under pressure

of at least two times service pressure and show no defect.

(j) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material, as follows:

(1) The test is required on 2 specimens cut from one cylinder or part thereof having passed the hydrostatic test and heat-treated as required, taken at random out of each lot of 200 or less. Physical tests for spheres are required on 2 specimens cut from flat representative sample plates of the same heat taken at random from the steel used to produce the spheres. This flat steel from which 2 specimens are to be cut must receive the same heat treatment as the spheres themselves. Sample plates must be taken from each lot of 200 or less spheres.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width not over 1½ inches, or a gauge length of 2 inches with a width not over 1½ inches, or a gauge length at least 24 times the thickness with a width not over 6 times the thickness is authorized when a cylinder wall is not over 3/16 inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within one inch of each end of the reduced section.

(iii) When size of the cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the “extension under load” method, the total strain (or “extension under load”), corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain reference must be set while the specimen is under a stress of 12,000 psi, and the strain indicator reading must be set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(k) *Elongation.* Physical test specimens must show at least a 40 percent elongation for a 2-inch gauge length or at least 20 percent in other cases. Except that these elongation percentages may be reduced numerically by 2 for 2-inch specimens, and by 1 in other cases, for each 7,500 psi increment of tensile strength above 50,000 psi to a maximum of four such increments.

(l) *Tests of welds.* Except for brazed seams, welds must be tested as follows:

(1) *Tensile test.* A specimen must be cut from one cylinder of each lot of 200 or less, or welded test plate. The welded test plate must be of one of the heats in the lot of 200 or less which it represents, in the same condition and approximately the same thickness as the cylinder wall except that in no case must it be of a lesser thickness than that required for a quarter size Charpy impact specimen. The weld must be made by the same procedures and subjected to the same heat treatment as the major weld on the cylinder. The specimen must be taken from across the major seam and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3 (IBR, see §171.7 of this subchapter). Should this specimen fail to meet the requirements, specimens

may be taken from two additional cylinders or welded test plates from the same lot and tested. If either of the latter specimens fail to meet the requirements, the entire lot represented must be rejected.

(2) *Guided bend test.* A root bend test specimen must be cut from the cylinder or welded test plate, used for the tensile test specified in paragraph (l)(1) of this section. Specimens must be taken from across the major seam and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3.

(3) *Alternate guided-bend test.* This test may be used and must be as required by CGA Pamphlet C-3. The specimen must be bent until the elongation at the outer surface, adjacent to the root of the weld, between the lightly scribed gage lines a to b, must be at least 20 percent, except that this percentage may be reduced for steels having a tensile strength in excess of 50,000 psig, as provided in paragraph (k) of this section.

(m) *Rejected cylinders.* Reheat treatment is authorized for rejected cylinders. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair of brazed seams by brazing and welded seams by welding is authorized.

(n) *Markings.* Markings must be stamped plainly and permanently in one of the following locations on the cylinder:

(1) On shoulders and top heads not less than 0.087 inch thick.

(2) On side wall adjacent to top head for side walls not less than 0.090 inch thick.

(3) On a cylindrical portion of the shell which extends beyond the recessed bottom of the cylinder constituting an integral and non-pressure part of the cylinder.

(4) On a plate attached to the top of the cylinder or permanent part thereof; sufficient space must be left on the plate to provide for stamping at least six retest dates; the plate must be at least  $\frac{1}{16}$  inch thick and must be attached by welding, or by brazing at a temperature of at least 1100 °F., throughout all edges of the plate.

(5) On the neck, neckring, valve boss, valve protection sleeve, or similar part

§ 178.53

49 CFR Ch. I (10–1–08 Edition)

permanently attached to the top of the cylinder.

(6) On the footing permanently attached to the cylinder, provided the water capacity of the cylinder does not exceed 25 pounds.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 66 FR 4535, Aug. 28, 2001; 67 FR 16015, Sept. 27, 2002; 67 FR 51653, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

§ 178.53 Specification 4D welded steel cylinders for aircraft use.

(a) *Type, size, and service pressure.* A DOT 4D cylinder is a welded steel sphere (two seamless hemispheres) or circumferentially welded cylinder (two seamless drawn shells) with a water capacity not over 100 pounds and a service pressure of at least 300 but not over 500 psig. Cylinders closed in by spinning process are not authorized.

(b) *Steel.* Open-hearth or electric steel of uniform and weldable quality must be used. Content may not exceed the following: Carbon, 0.25; phosphorus,

0.045; sulphur, 0.050, except that the following steels commercially known as 4130X and Type 304, 316, 321, and 347 stainless steels may be used with proper welding procedure. A heat of steel made under table 1 in this paragraph (b), check chemical analysis of which is slightly out of the specified range, is acceptable, if satisfactory in all other respects, provided the tolerances shown in table 2 in this paragraph (b) are not exceeded, except as approved by the Associate Administrator. The following chemical analyses are authorized:

TABLE 1—4130X STEEL

| 4130X            | Percent    |
|------------------|------------|
| Carbon .....     | 0.25/0.35. |
| Manganese .....  | 0.40/0.60. |
| Phosphorus ..... | 0.04 max.  |
| Sulphur .....    | 0.05 max   |
| Silicon .....    | 0.15/0.35. |
| Chromium .....   | 0.80/1.10. |
| Molybdenum ..... | 0.15/0.25. |
| Zirconium .....  | None.      |
| Nickel .....     | None.      |

TABLE 2—AUTHORIZED STAINLESS STEELS

|                        | Stainless steels |                  |                  |                  |
|------------------------|------------------|------------------|------------------|------------------|
|                        | 304<br>(percent) | 316<br>(percent) | 321<br>(percent) | 347<br>(percent) |
| Carbon (max) .....     | 0.08             | 0.08             | 0.08             | 0.08             |
| Manganese (max) .....  | 2.00             | 2.00             | 2.00             | 2.00             |
| Phosphorus (max) ..... | .030             | .045             | .030             | .030             |
| Sulphur (max) .....    | .030             | .030             | .030             | .030             |
| Silicon (max) .....    | .75              | 1.00             | .75              | .75              |
| Nickel .....           | 8.0/11.0         | 10.0/14.0        | 9.0/13.0         | 9.0/13.0         |
| Chromium .....         | 18.0/20.0        | 16.0/18.0        | 17.0/20.0        | 17.0/20.0        |
| Molybdenum .....       |                  | 2.0/3.0          |                  |                  |
| Titanium .....         |                  |                  | ( <sup>1</sup> ) |                  |
| Columbium .....        |                  |                  |                  | ( <sup>2</sup> ) |

<sup>1</sup> Titanium may not be less than 5C and not more than 0.60%.

<sup>2</sup> Columbium may not be less than 10C and not more than 1.0%.

TABLE 3—CHECK ANALYSIS TOLERANCES

| Element                       | Limit or maximum specified<br>(percent) | Tolerance (percent) over<br>the maximum limit or<br>under the minimum limit |                         |
|-------------------------------|-----------------------------------------|-----------------------------------------------------------------------------|-------------------------|
|                               |                                         | Under min-<br>imum limit                                                    | Over max-<br>imum limit |
| Carbon .....                  | To 0.15 incl .....                      | 0.01                                                                        | 0.01                    |
|                               | Over 0.15 to 0.40 incl .....            | .03                                                                         | .04                     |
| Manganese .....               | To 0.60 incl .....                      | .03                                                                         | .03                     |
|                               | Over 1.15 to 2.50 incl .....            | .05                                                                         | .05                     |
| Phosphorus <sup>1</sup> ..... | All ranges .....                        |                                                                             | .01                     |
| Sulphur .....                 | All ranges .....                        |                                                                             | .01                     |
| Silicon .....                 | To 0.30 incl .....                      | .02                                                                         | .03                     |
|                               | Over 0.30 to 1.00 incl .....            | .05                                                                         | .05                     |
| Nickel .....                  | Over 5.30 to 10.00 incl .....           | .10                                                                         | .10                     |
|                               | Over 10.00 to 14.00 incl .....          | .15                                                                         | .15                     |
| Chromium .....                | To 0.90 incl .....                      | .03                                                                         | .03                     |
|                               | Over 0.90 to 2.10 incl .....            | .05                                                                         | .05                     |
|                               | Over 15.00 to 20.00 incl .....          | .20                                                                         | .20                     |

TABLE 3—CHECK ANALYSIS TOLERANCES—Continued

| Element          | Limit or maximum specified (percent) | Tolerance (percent) over the maximum limit or under the minimum limit |                    |
|------------------|--------------------------------------|-----------------------------------------------------------------------|--------------------|
|                  |                                      | Under minimum limit                                                   | Over maximum limit |
| Molybdenum ..... | To 0.20 incl .....                   | .01                                                                   | .01                |
|                  | Over 0.20 to 0.40 incl .....         | .02                                                                   | .02                |
|                  | Over 1.75 to 3.0 incl .....          | .10                                                                   | .10                |
| Titanium .....   | All ranges .....                     | .05                                                                   | .05                |
| Columbium .....  | All ranges .....                     | .05                                                                   | .05                |

<sup>1</sup> Rephosphorized steels not subject to check analysis for phosphorus.

(c) *Identification of material.* Material must be identified by any suitable method except that plates and billets for hotdrawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished container appreciably. A reasonably smooth and uniform surface finish is required. Welding procedures and operators must be qualified in accordance with CGA Pamphlet C-3 (IBR, see §171.7 of this subchapter).

(e) *Wall thickness.* The wall stress at the minimum test pressure may not exceed 24,000 psi, except where steels commercially known as 4130X, types 304, 316, 321, and 347 stainless steels are used, stress at the test pressures may not exceed 37,000 psi. The minimum wall thickness for any container having a capacity of 1,100 cubic inches or less is 0.04 inch. The minimum wall thickness for any container having a capacity in excess of 1,100 cubic inches is 0.095 inch. Calculations must be done by the following:

(1) Calculation for a “sphere” must be made by the formula:

$$S = PD / 4tE$$

Where:

S = wall stress in psi;

P = test pressure prescribed for water jacket test, i.e., at least two times service pressure, in psig;

D = outside diameter in inches;

t = minimum wall thickness in inches;

E = 0.85 (provides 85 percent weld efficiency factor which must be applied in the girth weld area and heat affected zones which zone must extend a distance of 6 times wall thickness from center line of weld);

E = 1.0 (for all other areas).

(2) Calculation for a cylinder must be made by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = test pressure prescribed for water jacket test, i.e., at least two times service pressure, in psig;

D = outside diameter in inches;

d = inside diameter in inches.

(f) *Heat treatment.* The completed cylinders must be uniformly and properly heat-treated prior to tests.

(g) *Openings in container.* Openings in cylinders must comply with the following:

(1) Each opening in the container, except those for safety devices, must be provided with a fitting, boss, or pad, securely attached to the container by brazing or by welding or by threads. If threads are used, they must comply with the following:

(i) Threads must be clean cut, even, without checks, and tapped to gauge.

(ii) Taper threads must be of a length not less than that specified for American Standard taper pipe threads.

(iii) Straight threads, having at least 4 engaged threads, must have a tight fit and calculated shear strength of at least 10 times the test pressure of the container. Gaskets, adequate to prevent leakage, are required.

(2) Closure of a fitting, boss, or pad must be adequate to prevent leakage.

(h) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test, as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. A pressure gauge must permit a reading to an accuracy of 1 percent. An expansion

gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of the total volumetric expansion at test pressure.

(4) Containers must be tested as follows:

(i) Each container to at least 2 times service pressure; or

(ii) One container out of each lot of 200 or less to at least 3 times service pressure. Others must be examined under pressure of 2 times service pressure and show no defects.

(i) *Flattening test for spheres and cylinders.* Spheres and cylinders must be subjected to a flattening test as follows:

(1) One sphere taken at random out of each lot of 200 or less must be subjected to a flattening test as follows:

(i) The test must be performed after the hydrostatic test.

(ii) The test must be between parallel steel plates on a press with a welded seam at right angles to the plates. Any projecting appurtenances may be cut off (by mechanical means only) prior to crushing.

(2) One cylinder taken at random out of each lot of 200 or less must be subjected to a flattening test, as follows:

(i) The test must be performed after the hydrostatic test.

(ii) The test must be between knife edges, wedge shaped, 60° angle, rounded to ½ inch radius. For lots of 30 or less, physical tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to the same heat treatment as the finished cylinder.

(j) *Physical test and specimens for spheres and cylinders.* Spheres and cylinders must be subjected to a physical test as follows:

(1) Physical test for spheres are required on 2 specimens cut from a flat representative sample plate of the same heat taken at random from the steel used to produce the sphere. This flat steel from which the 2 specimens are to be cut must receive the same heat-treatment as the spheres themselves. Sample plates must be taken for each lot of 200 or less spheres.

(2) Specimens for spheres must have a gauge length 2 inches with a width not over 1½ inches, or a gauge length at least 24 times the thickness with a width not over 6 times the thickness is authorized when a wall is not over ⅜ inch thick.

(3) Physical test for cylinders is required on 2 specimens cut from 1 cylinder taken at random out of each lot of 200 or less. For lots of 30 or less, physical tests are authorized to be made on a ring at least 8 inches long cut from each cylinder and subjected to the same heat treatment as the finished cylinder.

(4) Specimens for cylinders must conform to the following:

(i) A gauge length of 8 inches with a width not over 1½ inches, or a gauge length of 2 inches with a width not over 1½ inches, or a gauge length at least 24 times the thickness with a width not over 6 times the thickness is authorized when a cylinder wall is not over ⅜ inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within 1 inch of each end of the reduced section. Heating of the specimen for any purpose is not authorized.

(5) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the “offset” method or the “extension under load” method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the “extension under load” method, the total strain (or “extension under load”) corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the

gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(k) *Acceptable results for physical and flattening tests.* Either of the following is an acceptable result:

(1) An elongation of at least 40 percent for a 2 inch gauge length or at least 20 percent in other cases and yield strength not over 73 percent of tensile strength. In this instance, the flattening test is not required.

(2) An elongation of at least 20 percent for a 2 inch gauge length or 10 percent in other cases. Flattening is required to 50 percent of the original outside diameter without cracking.

(l) *Rejected cylinders.* Reheat-treatment is authorized for rejected cylinders. Subsequent thereto, containers must pass all prescribed tests to be acceptable. Repair of welded seams by welding prior to reheat-treatment is authorized.

(m) *Marking.* Marking on each container by stamping plainly and permanently are only authorized where the metal is at least 0.09 inch thick, or on a metal nameplate permanently secured to the container by means other than soft solder, or by means that would not reduce the wall thickness.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386, 45388, Aug. 28, 2001; 67 FR 51653, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

**§ 178.55 Specification 4B240ET welded or brazed cylinders.**

(a) *Type, spinning process, size and service pressure.* A DOT 4B240ET cylinder is a brazed type cylinder made from electric resistance welded tubing.

The maximum water capacity of this cylinder is 12 pounds or 333 cubic inches and the service must be 240 psig. The maximum outside diameter of the shell must be five inches and maximum length of the shell is 21 inches. Cylinders closed in by a spinning process are authorized.

(b) *Steel.* Open-hearth, basic oxygen, or electric steel of uniform quality must be used. Plain carbon steel content may not exceed the following: Carbon, 0.25; phosphorus, 0.045; sulfur, 0.050. The addition of other elements for alloying effect is prohibited.

(c) *Identification of material.* Material must be identified by any suitable method.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. Heads may be attached to shells by lap brazing or may be formed integrally. The thickness of the bottom of cylinders welded or formed by spinning is, under no condition, to be less than two times the minimum wall thickness of the cylindrical shell. Such bottom thicknesses must be measured within an area bounded by a line representing the points of contact between the cylinder and the floor when the cylinder is in a vertical position. Seams must conform to the following:

(1) Circumferential seams must be by brazing only. Heads must be attached to shells by the lap brazing method and must overlap not less than four times the wall thickness. Brazing material must have a melting point of not less than 1000 °F. Heads must have a driving fit with the shell unless the shell is crimped, swedged, or curled over the skirt or flange of the head and be thoroughly brazed until complete penetration of the joint by the brazing material is secured. Brazed joints may be repaired by brazing.

(2) Longitudinal seams in shell must be by electric resistance welded joints only. No repairs to longitudinal joints is permitted.

(3) Welding procedures and operators must be qualified in accordance with CGA C-3 (IBR, see §171.7 of this subchapter).

(e) *Welding or brazing.* Only the attachment, by welding or brazing, to the tops and bottoms of cylinders of neckrings, footrings, handles, bosses, pads, and valve protection rings is authorized. Provided that such attachments and the portion of the container to which they are attached are made of weldable steel, the carbon content of which may not exceed 0.25 percent.

(f) *Wall thickness.* The wall stress must be at least two times the service pressure and may not exceed 18,000 psi. The minimum wall thickness is 0.044 inch. Calculation must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psig;

P = 2 times service pressure;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* Heads formed by drawing or pressing must be uniformly and properly heat treated prior to tests. Cylinders with integral formed heads or bases must be subjected to a normalizing operation. Normalizing and brazing operations may be combined, provided the operation is carried out at a temperature in excess of the upper critical temperature of the steel.

(h) *Openings in cylinders.* Openings in cylinders must comply with the following:

(1) Each opening in cylinders, except those for safety devices, must be provided with a fitting, boss, or pad, securely attached to the cylinder by brazing or by welding or by threads. A fitting, boss, or pad must be of steel suitable for the method of attachment employed, and which need not be identified or verified as to analysis, except that if attachment is by welding, carbon content may not exceed 0.25 percent. If threads are used, they must comply with the following:

(i) Threads must be clean cut, even without checks, and tapped to gauge.

(ii) Taper threads to be of length not less than as specified for American Standard taper pipe threads.

(iii) Straight threads, having at least 4 engaged threads, to have tight fit and calculated shear strength at least 10 times the test pressure of the cylinder; gaskets required, adequate to prevent leakage.

(2) Closure of a fitting, boss, or pad must be adequate to prevent leakage.

(i) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Cylinders must be tested as follows:

(i) At least one cylinder selected at random out of each lot of 200 or less must be tested as outlined in paragraphs (i)(1), (i)(2), and (i)(3) of this section to at least two times service pressure.

(ii) All cylinders not tested as outlined in paragraph (i)(4)(i) of this section must be examined under pressure of at least two times service pressure and show no defect.

(5) Each 1000 cylinders or less successively produced each day must constitute a lot. One cylinder must be selected from each lot and hydrostatically tested to destruction. If this cylinder bursts below five times the service pressure, then two additional cylinders must be selected and subjected to this test. If either of these cylinders fails by bursting below five times the service pressure then the entire lot must be rejected. All cylinders

constituting a lot must be of identical size, construction heat-treatment, finish, and quality.

(j) *Flattening test.* Following the hydrostatic test, one cylinder taken at random out of each lot of 200 or less, must be subjected to a flattening test that is between knife edges, wedge shaped, 60° angle, rounded to ½ inch radius.

(k) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material, as follows:

(1) The test is required on 2 specimens cut from 1 cylinder, or part thereof heat-treated as required, taken at random out of each lot of 200 or less in the case of cylinders of capacity greater than 86 cubic inches and out of each lot of 500 or less for cylinders having a capacity of 86 cubic inches or less.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width not over 1½ inches, a gauge length of 2 inches with a width not over 1½ inches, or a gauge length at least 24 times the thickness with a width not over 6 times the thickness is authorized when a cylinder wall is not over ⅜ inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within one inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as

prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed ⅛ inch per minute during yield strength determination.

(l) *Acceptable results for physical and flattening tests.* Acceptable results for the physical and flattening tests are an elongation of at least 40 percent for a 2 inch gauge length or at least 20 percent in other cases and a yield strength not over 73 percent of tensile strength. In this instance the flattening test is required, without cracking, to six times the wall thickness with a weld 90° from the direction of the applied load. Two rings cut from the ends of length of pipe used in production of a lot may be used for the flattening test provided the rings accompany the lot which they represent in all thermal processing operations. At least one of the rings must pass the flattening test.

(m) *Leakage test.* All spun cylinders and plugged cylinders must be tested for leakage by gas or air pressure after the bottom has been cleaned and is free from all moisture, subject to the following conditions:

(1) Pressure, approximately the same as but no less than service pressure, must be applied to one side of the finished bottom over an area of at least ⅙ of the total area of the bottom but not less than ¾ inch in diameter, including the closure, for at least 1



minute, during which time the other side of the bottom exposed to pressure must be covered with water and closely examined for indications of leakage. Except as provided in paragraph (n) of this section, cylinders which are leaking must be rejected.

(2) A spun cylinder is one in which an end closure in the finished cylinder has been welded by the spinning process.

(3) A plugged cylinder is one in which a permanent closure in the bottom of a finished cylinder has been effected by a plug.

(4) As a safety precaution, if the manufacturer elects to make this test before the hydrostatic test, he should design his apparatus so that the pressure is applied to the smallest area practicable, around the point of closure, and so as to use the smallest possible volume of air or gas.

(n) *Rejected cylinders.* Repairs of rejected cylinders is authorized. Cylinders that are leaking must be rejected, except that:

(1) Spun cylinders rejected under the provisions of paragraph (m) of this section may be removed from the spun cylinder category by drilling to remove defective material, tapping, and plugging.

(2) Brazed joints may be rebrazed.

(3) Subsequent to the operations noted in paragraphs (n)(1) and (n)(2) of this section, acceptable cylinders must pass all prescribed tests.

(o) *Marking.* Markings on each cylinder must be by stamping plainly and permanently on shoulder, top head, neck or valve protection collar which is permanently attached to the cylinders and forming an integral part thereof, provided that cylinders not less than 0.090 inch thick may be stamped on the side wall adjacent to top head.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386, Aug. 28, 2001; 67 FR 51653, Aug. 8, 2002; 68 FR 75748, 75749, Dec. 31, 2003]

**§ 178.56 Specification 4AA480 welded steel cylinders.**

(a) *Type, size, and service pressure.* A DOT 4AA480 cylinder is a welded steel cylinder having a water capacity (nominal) not over 1,000 pounds water capacity and a service pressure of 480

psig. Closures welded by spinning process not permitted.

(b) *Steel.* The limiting chemical composition of steel authorized by this specification must be as shown in table I of appendix A to this part.

(c) *Identification of material.* Material must be identified by any suitable method except that plates and billets for hotdrawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. Exposed bottom welds on cylinders over 18 inches long must be protected by footings. Minimum thickness of heads and bottoms may not be less than 90 percent of the required thickness of the side wall. Seams must be made as follows:

(1) Circumferential seams must be welded. Brazing is not authorized.

(2) Longitudinal seams are not permitted.

(3) Welding procedures and operators must be qualified in accordance with CGA C–3 (IBR, see § 171.7 of this subchapter).

(e) *Welding.* Only the welding of neckrings, footings, bosses, pads, and valve protection rings to the tops and bottoms of cylinders is authorized. Provided that such attachments are made of weldable steel, the carbon content of which does not exceed 0.25 percent.

(f) *Wall thickness.* The wall thickness of the cylinder must conform to the following:

(1) For cylinders with an outside diameter over 5 inches, the minimum wall thickness is 0.078 inch. In any case, the minimum wall thickness must be such that the calculated wall stress at the minimum test pressure (in paragraph (i) of this section) may not exceed the lesser value of either of the following:

(i) One-half of the minimum tensile strength of the material determined as required in paragraph (j) of this section; or

(ii) 35,000 psi.

(2) Calculation must be made by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test;

D = outside diameter in inches;

d = inside diameter in inches.

(3) The ratio of tangential length to outside diameter may not exceed 4.0 for cylinders with a wall thickness less than 0.100 inch.

(g) *Heat treatment.* Each cylinder must be uniformly and properly heat treated prior to tests. Any suitable heat treatment in excess of 1100 °F is authorized except that liquid quenching is not permitted. Heat treatment must be accomplished after all forming and welding operations. Heat treatment is not required after welding weldable low carbon parts to attachments of similar material which have been previously welded to the top or bottom of cylinders and properly heat treated, provided such subsequent welding does not produce a temperature in excess of 400 °F., in any part of the top or bottom material.

(h) *Openings in cylinders.* Openings in cylinders must conform to the following:

(1) All openings must be in the heads or bases.

(2) Each opening in the cylinder, except those for safety devices, must be provided with a fitting boss, or pad, securely attached to the cylinder by welding or by threads. If threads are used they must comply with the following:

(i) Threads must be clean-cut, even without checks and cut to gauge.

(ii) Taper threads to be of length not less than as specified for American Standard taper pipe threads.

(iii) Straight threads having at least 6 engaged threads, must have a tight fit and a calculated shear strength at least 10 times the test pressure of the cylinder. Gaskets, adequate to prevent leakage, are required.

(3) Closure of a fitting, boss or pad must be adequate to prevent leakage.

(i) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test as follows:

(1) The test must be by water jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds or sufficiently longer to assure complete expansion. Any internal pressure applied after heat-treatment and before the official test may not exceed 90 percent of the test pressure. If, due to failure of test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is lower.

(3) Permanent volumetric expansion may not exceed 10 percent of the total volumetric expansion at test pressure.

(4) Cylinders must be tested as follows:

(i) At least one cylinder selected at random out of each lot of 200 or less must be tested as described in paragraphs (i)(1), (i)(2), and (i)(3) of this section, to at least two times service pressure. If a selected cylinder fails, then two additional specimens must be selected at random from the same lot and subjected to the prescribed test. If either of these fails the test, then each cylinder in that lot must be so tested; and

(ii) Each cylinder not tested as prescribed in paragraph (i)(4)(i) of this section must be examined under pressure of at least two times service pressure and must show no defect. A cylinder showing a defect must be rejected unless it may be requalified under paragraph (m) of this section.

(j) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material, as follows:

(1) The test is required on 2 specimens cut from one cylinder having passed the hydrostatic test, or part thereof heat-treated as required, taken at random out of each lot of 200 or less.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width not over 1½ inches, a gauge length of 2 inches with a width not

over 1½ inches, or a gauge length at least 24 times the thickness with a width not over 6 times thickness is authorized when the cylinder wall is not over ⅜ inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within one inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load"), corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain reference must be set while the specimen is under a stress of 12,000 psi and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed ⅛ inch per minute during yield strength determination.

(k) *Elongation.* Physical test specimens must show at least a 40 percent elongation for 2-inch gauge lengths or at least a 20 percent elongation in other cases. Except that these elongation percentages may be reduced numerically by 2 for 2-inch specimens and by 1 in other cases for each 7,500 psi increment of tensile strength above 50,000 psi to a maximum of four such increments.

(l) *Tests of welds.* Welds must be tested as follows:

(1) *Tensile test.* A specimen must be cut from one cylinder of each lot of 200 or less, or a welded test plate. The welded test plate must be of one of the heats in the lot of 200 or less which it represents, in the same condition and approximately the same thickness as the cylinder wall except that it may not be of a lesser thickness than that required for a quarter size Charpy impact specimen. The weld must be made by the same procedures and subjected to the same heat treatment as the major weld on the cylinder. The specimens must be taken across the major seam and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3. Should this specimen fail to meet the requirements, specimens may be taken from two additional cylinders or welded test plates from the same lot and tested. If either of the latter specimens fail to meet the requirements, the entire lot represented must be rejected.

(2) *Guided bend test.* A root bend test specimen must be cut from the cylinder or a welded test plate, used for the tensile test specified in paragraph (l)(1) of this section. Specimens must be taken from across the major seam and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3.

(3) *Alternate guided-bend test.* This test may be used and must be as required by CGA Pamphlet C-3. The specimen must be bent until the elongation at the outer surface, adjacent to the root of the weld, between the lightly scribed gage lines-a to b, is at least 20 percent, except that this percentage may be reduced for steels having a tensile strength in excess of 50,000 psi, as provided in paragraph (k) of this section.

(m) *Rejected cylinders.* Reheat treatment of rejected cylinders is authorized. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair of welded seams by welding is authorized.

(n) *Markings.* Markings must be stamped plainly and permanently in one of the following locations on the cylinder:

(1) On shoulders and top heads not less than 0.087 inch thick.

(2) On neck, valve boss, valve protection sleeve, or similar part permanently attached to top end of cylinder.

(3) On a plate attached to the top of the cylinder or permanent part thereof: sufficient space must be left on the plate to provide for stamping at least six retest dates: the plate must be at least  $\frac{1}{16}$  inch thick and must be attached by welding or by brazing at a temperature of at least 1100 °F, throughout all edges of the plate.

(4) Variations in location of markings authorized only when necessitated by lack of space.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386, Aug. 28, 2001; 67 FR 51653, Aug. 8, 2002; 68 FR 75748, 75749, Dec. 31, 2003]

#### § 178.57 Specification 4L welded insulated cylinders.

(a) *Type, size, service pressure, and design service temperature.* A DOT 4L cylinder is a fusion welded insulated cylinder with a water capacity (nominal) not over 1,000 pounds water capacity and a service pressure of at least 40 but not greater than 500 psig conforming to the following requirements:

(1) For liquefied hydrogen service, the cylinders must be designed to stand on end, with the axis of the cylindrical portion vertical.

(2) The design service temperature is the coldest temperature for which a cylinder is suitable. The required design service temperatures for each cryogenic liquid is as follows:

| Cryogenic liquid | Design service temperature |
|------------------|----------------------------|
| Argon .....      | Minus 320 °F or colder.    |
| Helium .....     | Minus 452 °F or colder.    |
| Hydrogen .....   | Minus 423 °F or colder.    |
| Neon .....       | Minus 411 °F or colder.    |
| Nitrogen .....   | Minus 320 °F or colder.    |
| Oxygen .....     | Minus 320 °F or colder.    |

(b) *Material.* Material use in the construction of this specification must conform to the following:

(1) *Inner containment vessel (cylinder).* Designations and limiting chemical compositions of steel authorized by this specification must be as shown in table 1 in paragraph (o) of this section.

(2) *Outer jacket.* Steel or aluminum may be used subject to the requirements of paragraph (o)(2) of this section.

(c) *Identification of material.* Material must be identified by any suitable method.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart and to the following requirements:

(1) No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. The shell portion must be a reasonably true cylinder.

(2) The heads must be seamless, concave side to the pressure, hemispherical or ellipsoidal in shape with the major diameter not more than twice the minor diameter. Minimum thickness of heads may not be less than 90 percent of the required thickness of the sidewall. The heads must be reasonably true to shape, have no abrupt shape changes, and the skirts must be reasonably true to round.

(3) The surface of the cylinder must be insulated. The insulating material must be fire resistant. The insulation on non-evacuated jackets must be covered with a steel jacket not less than 0.060-inch thick or an aluminum jacket not less than 0.070 inch thick, so constructed that moisture cannot come in contact with the insulating material. If a vacuum is maintained in the insulation space, the evacuated jacket must be designed for a minimum collapsing pressure of 30 psig differential whether made of steel or aluminum. The construction must be such that the total heat transfer, from the atmosphere at ambient temperature to the contents of the cylinder, will not exceed 0.0005 Btu per hour, per Fahrenheit degree differential in temperature, per pound of water capacity of the cylinder. For

## § 178.57

hydrogen, cryogenic liquid service, the total heat transfer, with a temperature differential of 520 Fahrenheit degrees, may not exceed that required to vent 30 SCF of hydrogen gas per hour.

(4) For a cylinder having a design service temperature colder than minus 320 °F, a calculation of the maximum weight of contents must be made and that weight must be marked on the cylinder as prescribed in §178.35.

(5) Welding procedures and operations must be qualified in accordance with CGA Pamphlet C-3 (IBR, see §171.7 of this subchapter). In addition, an impact test of the weld must be performed in accordance with paragraph (l) of this section as part of the qualification of each welding procedure and operator.

(e) *Welding.* Welding of the cylinder must be as follows:

(1) All seams of the cylinder must be fusion welded. A means must be provided for accomplishing complete penetration of the joint. Only butt or joggle butt joints for the cylinder seams are authorized. All joints in the cylinder must have reasonably true alignment.

(2) All attachments to the sidewalls and heads of the cylinder must be by fusion welding and must be of a weldable material complying with the impact requirements of paragraph (l) of this section.

(3) For welding the cylinder, each procedure and operator must be qualified in accordance with the sections of CGA Pamphlet C-3 that apply. In addition, impact tests of the weld must be performed in accordance with paragraph (l) of this section as part of the qualification of each welding procedure and operator.

(4) Brazing, soldering and threading are permitted only for joints not made directly to the cylinder body. Threads must comply with the requirements of paragraph (h) of this section.

(f) *Wall thickness.* The minimum wall thickness of the cylinder must be such that the calculated wall stress at the minimum required test pressure may not exceed the least value of the following:

(1) 45,000 psi.

(2) One-half of the minimum tensile strength across the welded seam determined in paragraph (l) of this section.

## 49 CFR Ch. I (10-1-08 Edition)

(3) One-half of the minimum tensile strength of the base metal determined as required in paragraph (j) of this section.

(4) The yield strength of the base metal determined as required in paragraph (l) of this section.

(5) Further provided that wall stress for cylinders having longitudinal seams may not exceed 85 percent of the above value, whichever applies.

(6) Calculation must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

where:

S = wall stress in pounds psi;

P = minimum test pressure prescribed for pressure test in psig;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* Heat treatment is not permitted.

(h) *Openings in cylinder.* Openings in cylinders must conform to the following:

(1) Openings are permitted in heads only. They must be circular and may not exceed 3 inches in diameter or one third of the cylinder diameter, whichever is less. Each opening in the cylinder must be provided with a fitting, boss or pad, either integral with, or securely attached to, the cylinder body by fusion welding. Attachments to a fitting, boss or pad may be made by welding, brazing, mechanical attachment, or threading.

(2) Threads must comply with the following:

(i) Threads must be clean-cut, even, without checks and cut to gauge.

(ii) Taper threads to be of a length not less than that specified for NPT.

(iii) Straight threads must have at least 4 engaged threads, tight fit and calculated shear strength at least 10 times the test pressure of the cylinder. Gaskets, which prevent leakage and are inert to the hazardous material, are required.

(i) *Pressure test.* Each cylinder, before insulating and jacketing, must be examined under a pressure of at least 2 times the service pressure maintained for at least 30 seconds without evidence of leakage, visible distortion or other defect. The pressure gauge must permit reading to an accuracy of 1 percent.

(j) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, and elongation as follows:

(1) The test is required on 2 specimens selected from material of each heat and in the same condition as that in the completed cylinder.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width not over  $1\frac{1}{2}$  inches, a gauge length of 2 inches with width not over  $1\frac{1}{2}$  inches, or a gauge length at least 24 times thickness with a width not over 6 times thickness (authorized when cylinder wall is not over  $\frac{1}{16}$  inch thick).

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within one inch of each end of the reduced section.

(iii) When size of the cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold by pressure only, not by blows. When specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load"), corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic expansion of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on the elastic modulus of the material used. In the event of controversy, the entire stress-strain diagram must be plotted and the

yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain reference must be set while the specimen is under a stress of 12,000 psi and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(k) *Acceptable results for physical tests.* Physical properties must meet the limits specified in paragraph (o)(1), table 1, of this section, for the particular steel in the annealed condition. The specimens must show at least a 20 percent elongation for a 2-inch gage length. Except that the percentage may be reduced numerically by 2 for each 7,500 psi increment of tensile strength above 100,000 psi to a maximum of 5 such increments. Yield strength and tensile strength must meet the requirements of paragraph (o)(1), table 1, of this section.

(l) *Tests of welds.* Welds must be tested as follows:

(1) *Tensile test.* A specimen must be cut from one cylinder of each lot of 200 or less, or welded test plate. The welded test plate must be of one of the heats in the lot of 200 or less which it represents, in the same condition and approximately the same thickness as the cylinder wall except that it may not be of a lesser thickness than that required for a quarter size Charpy impact specimen. The weld must be made by the same procedures and subjected to the same heat treatment as the major weld on the cylinder. The specimen must be taken across the major seam and must be prepared in accordance with and must meet the requirements of CGA Pamphlet C-3. Should this specimen fail to meet the requirements, specimens may be taken from two additional cylinders or welded test plates from the same lot and tested. If either of the latter specimens fails to meet the requirements, the entire lot represented must be rejected.

(2) *Guided bend test.* A "root" bend test specimen must be cut from the cylinder or welded test plate, used for the tensile test specified in paragraph (l)(1) of this section and from any other

seam or equivalent welded test plate if the seam is welded by a procedure different from that used for the major seam. Specimens must be taken across the particular seam being tested and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3.

(3) *Alternate guided-bend test.* This test may be used and must be as specified in CGA Pamphlet C-3. The specimen must be bent until the elongation at the outer surface, adjacent to the root of the weld, between the lightly scribed gage lines a to b, is at least 20 percent, except that this percentage may be reduced for steels having a tensile strength in excess of 100,000 psig, as provided in paragraph (c) of this section.

(4) *Impact tests.* One set of three impact test specimens (for each test) must be prepared and tested for determining the impact properties of the deposited weld metal—

(i) As part of the qualification of the welding procedure.

(ii) As part of the qualification of the operators.

(iii) For each “heat” of welding rod or wire used.

(iv) For each 1,000 feet of weld made with the same heat of welding rod or wire.

(v) All impact test specimens must be of the charpy type, keyhole or milled U-notch, and must conform in all respects to ASTM E 23 (IBR, see § 171.7 of this subchapter). Each set of impact specimens must be taken across the weld and have the notch located in the weld metal. When the cylinder material thickness is 2.5 mm or thicker, impact specimens must be cut from a cylinder or welded test plate used for the tensile or bend test specimens. The dimension along the axis of the notch must be reduced to the largest possible of 10 mm, 7.5 mm, 5 mm or 2.5 mm, depending upon cylinder thickness. When the material in the cylinder or welded test plate is not of sufficient thickness to prepare 2.5 mm impact test specimens, 2.5 mm specimens must be prepared from a welded test plate made from 1/8 inch thick material meeting the requirements specified in paragraph (o)(1), table 1, of this section and having a carbon analysis of .05 min-

imum, but not necessarily from one of the heats used in the lot of cylinders. The test piece must be welded by the same welding procedure as used on the particular cylinder seam being qualified and must be subjected to the same heat treatment.

(vi) Impact test specimens must be cooled to the design service temperature. The apparatus for testing the specimens must conform to requirements of ASTM Standard E 23. The test piece, as well as the handling tongs, must be cooled for a length of time sufficient to reach the service temperature. The temperature of the cooling device must be maintained within a range of plus or minus 3 °F. The specimen must be quickly transferred from the cooling device to the anvil of the testing machine and broken within a time lapse of not more than six seconds.

(vii) The impact properties of each set of impact specimens may not be less than the values in the following table:

| Size of specimen   | Minimum impact value required for avg. of each set of three specimens (ft.-lb.) | Minimum impact value permitted on one only of a set of three (ft.-lb.) |
|--------------------|---------------------------------------------------------------------------------|------------------------------------------------------------------------|
| 10 mm×10 mm .....  | 15                                                                              | 10                                                                     |
| 10 mm×7.5 mm ..... | 12.5                                                                            | 8.5                                                                    |
| 10 mm×5 mm .....   | 10                                                                              | 7.0                                                                    |
| 10 mm×2.5 mm ..... | 5                                                                               | 3.5                                                                    |

(viii) When the average value of the three specimens equals or exceeds the minimum value permitted for a single specimen and the value for more than one specimen is below the required average value, or when the value for one specimen is below the minimum value permitted for a single specimen, a retest of three additional specimens must be made. The value of each of these retest specimens must equal or exceed the required average value. When an erratic result is caused by a defective specimen, or there is uncertainty in test procedure, a retest is authorized.

(m) *Radiographic examination.* Cylinders must be subject to a radiographic examination as follows:

(1) The techniques and acceptability of radiographic inspection must conform to the standards set forth in CGA Pamphlet C-3.

(2) One finished longitudinal seam must be selected at random from each lot of 100 or less successively produced and be radiographed throughout its entire length. Should the radiographic examination fail to meet the requirements of paragraph (m)(1) of this section, two additional seams of the same lot must be examined, and if either of these fail to meet the requirements of (m)(1) of this section, only those passing are acceptable.

(n) *Rejected cylinders.* Reheat treatment of rejected cylinders is authorized. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Welds may be repaired by suitable methods of fusion welding.

(o) *Authorized materials of construction.* Authorized materials of construction are as follows:

(1) *Inner containment vessel (cylinder).* Electric furnace steel of uniform quality must be used. Chemical analysis must conform to ASTM A 240/A 240M (IBR, see §171.7 of this subchapter), Type 304 stainless steel. Chemical analysis must conform to ASTM A240, Type 304 Stainless Steel. A heat of steel made under table 1 and table 2 in this paragraph (o)(1) is acceptable, even though its check chemical analysis is slightly out of the specified range, if it is satisfactory in all other respects, provided the tolerances shown in table 3 in this paragraph (o)(1) are not exceeded. The following chemical analyses and physical properties are authorized:

TABLE 1—AUTHORIZED MATERIALS

| Designation               | Chemical analysis, limits in percent |
|---------------------------|--------------------------------------|
| Carbon <sup>1</sup> ..... | 0.08 max.                            |
| Manganese .....           | 2.00 max.                            |
| Phosphorus .....          | 0.045 max.                           |
| Sulphur .....             | 0.030 max.                           |
| Silicon .....             | 1.00 max.                            |
| Nickel .....              | 8.00–10.50.                          |
| Chromium .....            | 18.00–20.00.                         |
| Molybdenum .....          | None.                                |
| Titanium .....            | None.                                |
| Columbium .....           | None.                                |

<sup>1</sup>The carbon analysis must be reported to the nearest hundredth of one percent.

TABLE 2—PHYSICAL PROPERTIES

|                                                                    | Physical properties (annealed) |
|--------------------------------------------------------------------|--------------------------------|
| Tensile strength, p.s.i. (minimum) .....                           | 75,000                         |
| Yield strength, p.s.i. (minimum) .....                             | 30,000                         |
| Elongation in 2 inches (minimum) percent .....                     | 30.0                           |
| Elongation other permissible gauge lengths (minimum) percent ..... | 15.0                           |

TABLE 3—CHECK ANALYSIS TOLERANCES

| Elements                      | Limit or specified range (percent) | Tolerance over the maximum limit or under the minimum limit |
|-------------------------------|------------------------------------|-------------------------------------------------------------|
| Carbon .....                  | To 0.030, incl .....               | 0.005                                                       |
|                               | Over 0.30 to 0.20, incl .....      | 0.01                                                        |
| Manganese .....               | To 1.00 incl .....                 | .03                                                         |
|                               | Over 1.00 to 3.00, incl .....      | 0.04                                                        |
| Phosphorus <sup>1</sup> ..... | To 0.040, incl .....               | 0.005                                                       |
|                               | Over 0.040 to 0.020 incl ..        | 0.010                                                       |
| Sulphur .....                 | To .40 incl .....                  | 0.005                                                       |
| Silicon .....                 | To 1.00, incl .....                | 0.05                                                        |
| Nickel .....                  | Over 5.00 to 10.00, incl ..        | 0.10                                                        |
|                               | Over 10.00 to 20.00, incl ..       | 0.15                                                        |
| Chromium .....                | Over 15.00 to 20.00, incl ..       | 0.20                                                        |

<sup>1</sup>Rephosphorized steels not subject to check analysis for phosphorus.

(2) *Outer jacket.* (i) Nonflammable cryogenic liquids. Cylinders intended for use in the transportation of nonflammable cryogenic liquid must have an outer jacket made of steel or aluminum.

(ii) Flammable cryogenic liquids. Cylinders intended for use in the transportation of flammable cryogenic liquid must have an outer jacket made of steel.

(p) *Markings.* (1) Markings must be stamped plainly and permanently on shoulder or top head of jacket or on a permanently attached plate or head protective ring.

(2) The letters “ST”, followed by the design service temperature (for example, ST-423F), must be marked on cylinders having a design service temperature of colder than minus 320 °F only. Location to be just below the DOT mark.

(3) The maximum weight of contents, in pounds (for example, “Max. Content 51 #”), must be marked on cylinders having a design service temperature colder than minus 320 °F only. Location to be near symbol.

(4) Special orientation instructions must be marked on the cylinder (for



## § 178.58

example, THIS END UP), if the cylinder is used in an orientation other than vertical with openings at the top of the cylinder.

(5) If the jacket of the cylinder is constructed of aluminum, the letters "AL" must be marked after the service pressure marking. Example: DOT-4L150 AL.

(6) Except for serial number and jacket material designation, each marking prescribed in this paragraph (p) must be duplicated on each cylinder by any suitable means.

(q) *Inspector's report.* In addition to the information required by § 178.35, the inspector's reports must contain information on:

(1) The jacket material and insulation type;

(2) The design service temperature (°F); and

(3) The impact test results, on a lot basis.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386-45388, Aug. 28, 2001; 67 FR 51653, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003]

### § 178.58 Specification 4DA welded steel cylinders for aircraft use.

(a) *Type, size, and service pressure.* A DOT 4DA is a welded steel sphere (two seamless hemispheres) or a circumferentially welded cylinder (two seamless drawn shells) with a water capacity not over 100 pounds and a service pressure of at least 500 but not over 900 psig.

(b) *Steel.* Open-hearth or electric steel of uniform quality must be used. A heat of steel made under table 1 in this paragraph (b), check chemical analysis of which is slightly out of the specified range, is acceptable, if satisfactory in all other respects, provided the tolerances shown in table 2 in this paragraph (b) are not exceeded except as approved by the Associate Administrator. The following chemical analyses are authorized:

TABLE 1—AUTHORIZED MATERIALS

| 4130             | Percent    |
|------------------|------------|
| Carbon .....     | 0.28/0.33. |
| Manganese .....  | 0.40/0.60. |
| Phosphorus ..... | 0.040 max. |
| Sulfur .....     | 0.040 max. |
| Silicon .....    | 0.15/0.35. |

## 49 CFR Ch. I (10-1-08 Edition)

TABLE 1—AUTHORIZED MATERIALS—Continued

| 4130             | Percent    |
|------------------|------------|
| Chromium .....   | 0.80/1.10. |
| Molybdenum ..... | 0.15/0.25. |

TABLE 2—CHECK ANALYSIS TOLERANCES

| Element                    | Limit or maximum specified (percent) | Tolerance (percent) over the maximum limit or under the minimum limit |                    |
|----------------------------|--------------------------------------|-----------------------------------------------------------------------|--------------------|
|                            |                                      | Under minimum limit                                                   | Over maximum limit |
| Carbon .....               | Over 0.15 to 0.40 incl               | .03 .....                                                             | .04                |
| Manganese .....            | To 0.60 incl .....                   | .03 .....                                                             | .03                |
| Phosphorus <sup>1</sup> .. | All ranges .....                     | .....                                                                 | .01                |
| Sulphur .....              | All ranges .....                     | .....                                                                 | .01                |
| Silicon .....              | To 0.30 incl .....                   | .02 .....                                                             | .03                |
| .....                      | Over 0.30 to 1.00 incl               | .05 .....                                                             | .05                |
| Chromium .....             | To 0.90 incl .....                   | .03 .....                                                             | .03                |
| .....                      | Over 0.90 to 2.10 incl               | .05 .....                                                             | .05                |
| Molybdenum ...             | To 0.20 incl .....                   | .01 .....                                                             | .01                |
| .....                      | Over 0.20 to 0.40, incl              | .02 .....                                                             | .02                |

<sup>1</sup>Rephosphorized steels not subject to check analysis for phosphorus.

(c) *Identification of material.* Materials must be identified by any suitable method except that plates and billets for hot-drawn containers must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured in accordance with the following requirements:

(1) By best appliances and methods. No defect is acceptable that is likely to weaken the finished container appreciably. A reasonably smooth and uniform surface finish is required. No abrupt change in wall thickness is permitted. Welding procedures and operators must be qualified in accordance with CGA Pamphlet C-3 (IBR, see § 171.7 of this subchapter).

(2) All seams of the sphere or cylinders must be fusion welded. Seams must be of the butt or joggle butt type and means must be provided for accomplishing complete penetration of the joint.

(e) *Welding.* Attachments to the container are authorized by fusion welding provided that such attachments are made of weldable steel, the carbon content of which may not exceed 0.25 percent except in the case of 4130 steel.

(f) *Wall thickness.* The minimum wall thickness must be such that the wall stress at the minimum specified test pressure may not exceed 67 percent of

the minimum tensile strength of the steel as determined from the physical and burst tests required and may not be over 70,000 p.s.i. For any diameter container, the minimum wall thickness is 0.040 inch. Calculations must be made by the formulas in (f)(1) or (f)(2) of this section:

(1) Calculation for a sphere must be made by the following formula:

$$S = PD / 4tE$$

Where:

S = wall stress in pounds psi;

P = test pressure prescribed for water jacket test, i.e., at least 2 times service pressure, in psig;

D = outside diameter in inches;

t = minimum wall thickness in inches;

E = 0.85 (provides 85 percent weld efficiency factor which must be applied in the girth weld area and heat affected zones which zone must extend a distance of 6 times wall thickness from center line of weld);

E = 1.0 (for all other areas).

(2) Calculation for a cylinder must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in pounds psi;

P = test pressure prescribed for water jacket test, i.e., at least 2 times service pressure, in psig;

D = outside diameter in inches;

d = inside diameter in inches.

(g) *Heat treatment.* The completed containers must be uniformly and properly heat-treated prior to tests. Heat-treatment of containers of the authorized analysis must be as follows:

(1) All containers must be quenched by oil, or other suitable medium except as provided in paragraph (g)(4) of this section.

(2) The steel temperature on quenching must be that recommended for the steel analysis, but may not exceed 1,750 °F.

(3) The steel must be tempered at the temperature most suitable for the analysis except that in no case shall the tempering temperature be less than 1,000 °F.

(4) The steel may be normalized at a temperature of 1,650 °F instead of being quenched, and containers so normalized need not be tempered.

(5) All cylinders, if water quenched or quenched with a liquid producing a

cooling rate in excess of 80 percent of the cooling rate of water, must be inspected by the magnetic particle or dye penetrant method to detect the presence of quenching cracks. Any cylinder found to have a quench crack must be rejected and may not be requalified.

(h) *Openings in container.* Openings in the container must comply with the following requirements:

(1) Each opening in the container must be provided with a fitting, boss, or pad of weldable steel securely attached to the container by fusion welding.

(2) Attachments to a fitting, boss, or pad must be adequate to prevent leakage. Threads must comply with the following:

(i) Threads must be clean cut, even, without checks, and tapped to gauge.

(ii) Taper threads to be of length not less than as specified for American Standard taper pipe threads.

(iii) Straight threads, having at least 4 engaged threads, to have tight fit and calculated shear strength at least 10 times the test pressure of the container; gaskets required, adequate to prevent leakage.

(i) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to accuracy either of 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent or 100 psig, whichever is the lower.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) Each container must be tested to at least 2 times service pressure.

(j) *Burst test.* One container taken at random out of 200 or less must be hydrostatically tested to destruction. The rupture pressure must be included as part of the inspector's report.

(k) *Flattening test.* Spheres and cylinders must be subjected to a flattening test as follows:

(1) *Flattening test for spheres.* One sphere taken at random out of each lot of 200 or less must be subjected to a flattening test as follows:

(i) The test must be performed after the hydrostatic test.

(ii) The test must be at the weld between the parallel steel plates on a press with a welded seam, at right angles to the plates. Any projecting appendages may be cut off (by mechanical means only) prior to crushing.

(2) *Flattening test for cylinders.* One cylinder taken at random out of each lot of 200 or less, must be subjected to a flattening test as follows:

(i) The test must be performed after the hydrostatic test.

(ii) The test cylinder must be placed between wedge-shaped knife edges having a 60° angle, rounded to a ½-inch radius.

(l) *Radiographic inspection.* Radiographic examinations is required on all welded joints which are subjected to internal pressure, except that at the discretion of the disinterested inspector, openings less than 25 percent of the sphere diameter need not be subjected to radiographic inspection. Evidence of any defects likely to seriously weaken the container must be cause for rejection.

(m) *Physical test and specimens for spheres and cylinders.* Spheres and cylinders must be subjected to a physical test as follows:

(1) A physical test for a sphere is required on 2 specimens cut from a flat representative sample plate of the same heat taken at random from the steel used to produce the sphere. This flat steel from which the 2 specimens are to be cut must receive the same heat-treatment as the spheres themselves. Sample plates to be taken for each lot of 200 or less spheres.

(2) Specimens for spheres have a gauge length of 2 inches with a width not over 1½ inches, or a gauge length at least 24 times thickness with a

width not over 6 times thickness is authorized when wall of sphere is not over ⅜ inch thick.

(3) A physical test for cylinders is required on 2 specimens cut from 1 cylinder taken at random out of each lot of 200 or less.

(4) Specimens for cylinder must conform to the following:

(i) A gauge length of 8 inches with a width not over 1½ inches, a gauge length of 2 inches with a width not over 1½ inches, a gauge length at least 24 times thickness with a width not over 6 times thickness is authorized when a cylinder wall is not over ⅜ inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within 1 inch of each end of the reduced section.

(iii) Heating of a specimen for any purpose is not authorized.

(5) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 percent offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed ⅛ inch per minute during yield strength determination.

(n) *Acceptable results for physical, flattening, and burst tests.* The following are acceptable results of the physical, flattening and burst test:

(1) Elongation must be at least 20 percent for a 2-inch gauge length or 10 percent in other cases.

(2) Flattening is required to 50 percent of the original outside diameter without cracking.

(3) Burst pressure must be at least 3 times service pressure.

(o) *Rejected containers.* Reheat-treatment of rejected cylinders is authorized. Subsequent thereto, containers must pass all prescribed tests to be acceptable. Repair of welded seams by welding prior to reheat-treatment is authorized.

(p) *Marking.* Markings on each container must be stamped plainly and permanently on a permanent attachment or on a metal nameplate permanently secured to the container by means other than soft solder.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386, 45388, Aug. 28, 2001; 67 FR 51654, Aug. 8, 2002; 67 FR 61015, Sept. 27, 2002; 68 FR 75748, Dec. 31, 2003]

**§ 178.59 Specification 8 steel cylinders with porous fillings for acetylene.**

(a) *Type and service pressure.* A DOT 8 cylinder is a seamless cylinder with a service pressure of 250 psig. The following steel is authorized:

(1) A longitudinal seam if forge lap welded;

(2) Attachment of heads by welding or by brazing by dipping process; or

(3) A welded circumferential body seam if the cylinder has no longitudinal seam.

(b) *Steel.* Open-hearth, electric or basic oxygen process steel of uniform quality must be used. Content percent may not exceed the following: Carbon, 0.25; phosphorus, 0.045; sulphur, 0.050.

(c) *Identification of steel.* Materials must be identified by any suitable method except that plates and billets for hot-drawn cylinders must be marked with the heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is acceptable that is likely to weaken the

finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. Welding procedures and operators must be qualified in accordance with CGA Pamphlet C-3 (IBR, see § 171.7 of this subchapter).

(e) *Exposed bottom welds.* Exposed bottom welds on cylinders over 18 inches long must be protected by footings.

(f) *Heat treatment.* Body and heads formed by drawing or pressing must be uniformly and properly heat treated prior to tests.

(g) *Openings.* Openings in the cylinders must comply with the following:

(1) Standard taper pipe threads are required;

(2) Length may not be less than as specified for American Standard pipe threads; tapped to gauge; clean cut, even, and without checks.

(h) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) One cylinder out of each lot of 200 or less must be hydrostatically tested to at least 750 psig. Cylinders not so tested must be examined under pressure of between 500 and 600 psig and show no defect. If hydrostatically tested cylinder fails, each cylinder in the lot may be hydrostatically tested and those passing are acceptable.

(i) *Leakage test.* Cylinders with bottoms closed in by spinning must be subjected to a leakage test by setting the interior air or gas pressure to not less than the service pressure. Cylinders which leak must be rejected.

(j) *Physical test.* A physical test must be conducted as follows:

(1) The test is required on 2 specimens cut longitudinally from 1 cylinder or part thereof taken at random out of each lot of 200 or less, after heat treatment.

(2) Specimens must conform to a gauge length of 8 inches with a width not over 1½ inches, a gauge length of 2 inches with width not over 1½, or a gauge length at least 24 times thickness with a width not over 6 times thickness is authorized when a cylinder wall is not over ⅜ inch thick.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the “offset” method or the “extension under load” method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the “extension under load” method, the total strain (or “extension under load”) corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed ⅛ inch per minute during yield strength determination.

(4) Yield strength may not exceed 73 percent of tensile strength. Elongation must be at least 40 percent in 2 inch or 20 percent in other cases.

(k) *Rejected cylinders.* Reheat treatment of rejected cylinder is authorized. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding is authorized.

(l) *Porous filling.* (1) Cylinders must be filled with a porous material in accordance with the following:

(i) The porous material may not disintegrate or sag when wet with solvent or when subjected to normal service;

(ii) The porous filling material must be uniform in quality and free of voids, except that a well drilled into the filling material beneath the valve is authorized if the well is filled with a material of such type that the functions of the filling material are not impaired;

(iii) Overall shrinkage of the filling material is authorized if the total clearance between the cylinder shell and filling material, after solvent has been added, does not exceed ½ of 1 percent of the respective diameter or length, but not to exceed ⅛ inch, measured diametrically and longitudinally;

(iv) The clearance may not impair the functions of the filling material;

(v) The installed filling material must meet the requirements of CGA C-12 (IBR, see § 171.7 of this subchapter); and

(vi) Porosity of filling material may not exceed 80 percent except that filling material with a porosity of up to 92 percent may be used when tested with satisfactory results in accordance with CGA Pamphlet C-12.

(2) When the porosity of each cylinder is not known, a cylinder taken at random from a lot of 200 or less must be tested for porosity. If the test cylinder fails, each cylinder in the lot may be tested individually and those cylinders that pass the test are acceptable.

(3) For filling that is molded and dried before insertion in cylinders, porosity test may be made on a sample block taken at random from material to be used.

(4) The porosity of the filling material must be determined. The amount of solvent at 70 °F for a cylinder:

(i) Having shell volumetric capacity above 20 pounds water capacity (nominal) may not exceed the following:

| Percent porosity of filler | Maximum acetone solvent percent shell capacity by volume |
|----------------------------|----------------------------------------------------------|
| 90 to 92 .....             | 43.4                                                     |

| Percent porosity of filler | Maximum acetone solvent percent shell capacity by volume |
|----------------------------|----------------------------------------------------------|
| 87 to 90 .....             | 42.0                                                     |
| 83 to 87 .....             | 40.0                                                     |
| 80 to 83 .....             | 38.6                                                     |
| 75 to 80 .....             | 36.2                                                     |
| 70 to 75 .....             | 33.8                                                     |
| 65 to 70 .....             | 31.4                                                     |

(ii) Having volumetric capacity of 20 pounds or less water capacity (nominal), may not exceed the following:

| Percent porosity of filler | Maximum acetone solvent percent shell capacity by volume |
|----------------------------|----------------------------------------------------------|
| 90 to 92 .....             | 41.8                                                     |
| 83 to 90 .....             | 38.5                                                     |
| 80 to 83 .....             | 37.1                                                     |
| 75 to 80 .....             | 34.8                                                     |
| 70 to 75 .....             | 32.5                                                     |
| 65 to 70 .....             | 30.2                                                     |

(m) *Tare weight.* The tare weight is the combined weight of the cylinder proper, porous filling, valve, and solvent, without removable cap.

(n) *Duties of inspector.* In addition to the requirements of § 178.35, the inspector is required to—

(1) Certify chemical analyses of steel used, signed by manufacturer thereof; also verify by, check analyses of samples taken from each heat or from 1 out of each lot of 200 or less, plates, shells, or tubes used.

(2) Verify compliance of cylinder shells with all shell requirements; inspect inside before closing in both ends; verify heat treatment as proper; obtain all samples for all tests and for check analyses; witness all tests; verify threads by gauge; report volumetric capacity and minimum thickness of wall noted.

(3) Prepare report on manufacture of steel shells in form prescribed in § 178.35. Furnish one copy to manufacturer and three copies to the company that is to complete the cylinders.

(4) Determine porosity of filling and tare weights; verify compliance of marking with prescribed requirements; obtain necessary copies of steel shell reports; and furnish complete reports required by this specification to the person who has completed the manu-

facture of the cylinders and, upon request, to the purchaser. The test reports must be retained by the inspector for fifteen years from the original test date of the cylinder.

(o) *Marking.* (1) Marking on each cylinder must be stamped plainly and permanently on or near the shoulder, top head, neck or valve protection collar which is permanently attached to the cylinder and forming integral part thereof.

(2) Tare weight of cylinder, in pounds and ounces, must be marked on the cylinder.

(3) Cylinders, not completed, when delivered must each be marked for identification of each lot of 200 or less.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386, Aug. 28, 2001; 67 FR 61016, Sept. 27, 2002; 67 FR 51654, Aug. 8, 2002; 68 FR 75748, 75749, Dec. 31, 2003]

#### § 178.60 Specification 8AL steel cylinders with porous fillings for acetylene.

(a) *Type and service pressure.* A DOT 8AL cylinder is a seamless steel cylinder with a service pressure of 250 psig. However, the attachment of heads by welding or by brazing by dipping process and a welded circumferential body seam is authorized. Longitudinal seams are not authorized.

(b) *Authorized steel.* The authorized steel is as specified in table I of appendix A to this part.

(c) *Identification of steel.* Material must be identified by any suitable method except that plates and billets for hot-drawn cylinders must be marked with heat number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. Welding procedures and operators must be qualified in accordance with CGA Pamphlet C–3 (IBR, see § 171.7 of this subchapter).

(e) *Footrings.* Exposed bottom welds on cylinders over 18 inches long must be protected by footrings.

(f) *Welding or brazing.* Welding or brazing for any purpose whatsoever is prohibited except as follows:

(1) The attachment to the tops or bottoms of cylinders of neckrings, footrings, handlers, bosses, pads, and valve protecting rings is authorized provided that such attachments and the portion of the container to which they are attached are made of weldable steel, the carbon content of which may not exceed 0.25 percent.

(2) Heat treatment is not required after welding or brazing weldable low carbon parts to attachments, specified in paragraph (f)(1) of this section, of similar material which have been previously welded or brazed to the top or bottom of cylinders and properly heat treated, provided such subsequent welding or brazing does not produce a temperature in excess of 400 °F in any part of the top or bottom material.

(g) *Wall thickness; wall stress.* The wall thickness/wall stress of the cylinder must conform to the following:

(1) The calculated wall stress at 750 psi may not exceed 35,000 psi, or one-half of the minimum ultimate strength of the steel as determined in paragraph (l) of this section, whichever value is the smaller. The measured wall thickness may not include galvanizing or other protective coating.

(i) Calculation of wall stress must be made by the formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in pounds psi;  
P = 750 psig (minimum test pressure);  
D = outside diameter in inches;  
d = inside diameter in inches.

(ii) Either D or d must be calculated from the relation  $D = d + 2t$ , where t = minimum wall thickness.

(2) Cylinders with a wall thickness less than 0.100 inch, the ratio of straight side wall length to outside diameter may not exceed 3.5.

(3) For cylinders having outside diameter over 5 inches, the minimum wall thickness must be 0.087 inch.

(h) *Heat treatment.* Each cylinder must be uniformly and properly heat treated, prior to tests, by any suitable method in excess of 1100 °F. Heat treatment must be accomplished after all forming and welding operations, except

that when brazed joints are used, heat treatment must follow any forming and welding operations but may be done before, during, or after the brazing operations. Liquid quenching is not authorized.

(i) *Openings.* Standard taper pipe threads required in all openings. The length of the opening may not be less than as specified for American Standard pipe threads; tapped to gauge; clean cut, even, and without checks.

(j) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit reading of total expansion to an accuracy of either 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat-treatment and previous to the official test may not exceed 90 percent of the test pressure.

(3) Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure.

(4) One cylinder out of each lot of 200 or less must be hydrostatically tested to at least 750 psig. Cylinders not so tested must be examined under pressure of between 500 and 600 psig and show no defect. If a hydrostatically tested cylinder fails, each cylinder in the lot may be hydrostatically tested and those passing are acceptable.

(k) *Leakage test.* Cylinders with bottoms closed in by spinning must be leakage tested by setting the interior air or gas pressure at not less than the service pressure. Any cylinder that leaks must be rejected.

(l) *Physical test.* A physical test must be conducted as follows;

(1) The test is required on 2 specimens cut longitudinally from 1 cylinder or part thereof taken at random out of each lot of 200 or less, after heat treatment.

(2) Specimens must conform to a gauge length of 8 inches with a width not over 1½ inches, a gauge length 2 inches with a width not over 1½ inches,

or a gauge length at least 24 times thickness with a width not over 6 times thickness is authorized when a cylinder wall is not over  $\frac{3}{16}$  inch thick.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "offset" method or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load") corresponding to the stress at which the 0.2 percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2 offset.

(iii) For the purpose of strain measurement, the initial strain must be set while the specimen is under a stress of 12,000 psi, the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(m) *Elongation.* Physical test specimens must show at least a 40 percent elongation for a 2 inch gauge length or at least a 20 percent elongation in other cases. Except that these elongation percentages may be reduced numerically by 2 for 2 inch specimens and 1 in other cases for each 7,500 psi increment of tensile strength above 50,000 psi to a maximum of four such increments.

(n) *Weld tests.* Specimens taken across the circumferentially welded seam must be cut from one cylinder taken at random from each lot of 200 or less cylinders after heat treatment and must pass satisfactorily the following tests:

(1) *Tensile test.* A specimen must be cut from one cylinder of each lot of 200 or less, or welded test plate. The specimen must be taken from across the major seam and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3. Should this specimen fail to meet the requirements, specimens may be taken from two additional cylinders or welded test plates from the same lot and tested. If either of the latter specimens fail to meet the requirements, the entire lot represented must be rejected.

(2) *Guided bend test.* A root bend test specimen must be cut from the cylinder or welded test plate, used for the tensile test specified in paragraph (n)(1) of this section. Specimens must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3.

(3) *Alternate guided-bend test.* This test may be used and must be as required by CGA Pamphlet C-3. The specimen must be bent until the elongation at the outer surface, adjacent to the root of the weld, between the lightly scribed gage lines-a to b, must be at least 20 percent, except that this percentage may be reduced for steels having a tensile strength in excess of 50,000 psi, as provided in paragraph (m) of this section.

(o) *Rejected cylinders.* Reheat treatment of rejected cylinders is authorized. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair by welding is authorized.

(p) *Porous filling.* (1) Cylinders must be filled with a porous material in accordance with the following:

(i) The porous material may not disintegrate or sag when wet with solvent or when subjected to normal service;

(ii) The filling material must be uniform in quality and free of voids, except that a well drilled into the filling material beneath the valve is authorized if the well is filled with a material of such type that the functions of the filling material are not impaired;

(iii) Overall shrinkage of the filling material is authorized if the total clearance between the cylinder shell and filling material, after solvent has



§ 178.60

49 CFR Ch. I (10–1–08 Edition)

been added, does not exceed  $\frac{1}{2}$  of 1 percent of the respective diameter or length but not to exceed  $\frac{1}{8}$  inch, measured diametrically and longitudinally;

(iv) The clearance may not impair the functions of the filling material;

(v) The installed filling material must meet the requirements of CGA C-12 (IBR, see §171.7 of this subchapter); and

(vi) Porosity of filling material may not exceed 80 percent except that filling material with a porosity of up to 92 percent may be used when tested with satisfactory results in accordance with CGA Pamphlet C-12.

(2) When the porosity of each cylinder is not known, a cylinder taken at random from a lot of 200 or less must be tested for porosity. If the test cylinder fails, each cylinder in the lot may be tested individually and those cylinders that pass the test are acceptable.

(3) For filling that is molded and dried before insertion in cylinders, porosity test may be made on sample block taken at random from material to be used.

(4) The porosity of the filling material must be determined; the amount of solvent at 70 °F for a cylinder:

(i) Having shell volumetric capacity above 20 pounds water capacity (nominal) may not exceed the following:

| Percent porosity of filler | Maximum acetone solvent percent shell capacity by volume |
|----------------------------|----------------------------------------------------------|
| 90 to 92 .....             | 43.4                                                     |
| 87 to 90 .....             | 42.0                                                     |
| 83 to 87 .....             | 40.0                                                     |
| 80 to 83 .....             | 38.6                                                     |
| 75 to 80 .....             | 36.2                                                     |
| 70 to 75 .....             | 33.8                                                     |
| 65 to 70 .....             | 31.4                                                     |

(ii) Having volumetric capacity of 20 pounds or less water capacity (nominal), may not exceed the following:

| Percent porosity of filler | Maximum acetone solvent percent shell capacity by volume |
|----------------------------|----------------------------------------------------------|
| 90 to 92 .....             | 41.8                                                     |
| 83 to 90 .....             | 38.5                                                     |
| 80 to 83 .....             | 37.1                                                     |
| 75 to 80 .....             | 34.8                                                     |
| 70 to 75 .....             | 32.5                                                     |
| 65 to 70 .....             | 30.2                                                     |

(q) *Tare weight.* The tare weight is the combined weight of the cylinder

proper, porous filling, valve, and solvent, but without removable cap.

(r) *Duties of inspector.* In addition to the requirements of §178.35, the inspector shall—

(1) Certify chemical analyses of steel used, signed by manufacturer thereof; also verify by check analyses, of samples taken from each heat or from 1 out of each lot of 200 or less plates, shells, or tubes used.

(2) Verify compliance of cylinder shells with all shell requirements, inspect inside before closing in both ends, verify heat treatment as proper; obtain all samples for all tests and for check analyses, witness all tests; verify threads by gauge, report volumetric capacity and minimum thickness of wall noted.

(3) Report percentage of each specified alloying element in the steel. Prepare report on manufacture of steel shells in form prescribed in §178.35. Furnish one copy to manufacturer and three copies to the company that is to complete the cylinders.

(4) Determine porosity of filling and tare weights; verify compliance of marking with prescribed requirements; obtain necessary copies of steel shell reports prescribed in paragraph (b) of this section; and furnish complete test reports required by this specification to the person who has completed the manufacturer of the cylinders and, upon request, to the purchaser. The test reports must be retained by the inspector for fifteen years from the original test date of the cylinder.

(s) *Marking.* (1) Tare weight of cylinder, in pounds and ounces, must be marked on the cylinder.

(2) Cylinders, not completed, when delivered must each be marked for identification of each lot of 200 or less.

(3) Markings must be stamped plainly and permanently in locations in accordance with the following:

(i) On shoulders and top heads not less than 0.087 inch thick; or

(ii) On neck, valve boss, valve protection sleeve, or similar part permanently attached to the top end of cylinder; or

(iii) On a plate of ferrous material attached to the top of the cylinder or permanent part thereof; the plate must be at least  $\frac{1}{16}$  inch thick, and must be

attached by welding, or by brazing at a temperature of at least 1,100 °F throughout all edges of the plate. Sufficient space must be left on the plate to provide for stamping at least four (4) retest dates.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 66 FR 45386, 45388, Aug. 28, 2001; 67 FR 51654, Aug. 8, 2002; 68 FR 75748, 75749, Dec. 31, 2003]

**§ 178.61 Specification 4BW welded steel cylinders with electric-arc welded longitudinal seam.**

(a) *Type, size and service pressure.* A DOT 4BW cylinder is a welded type steel cylinder with a longitudinal electric-arc welded seam, a water capacity (nominal) not over 1,000 pounds and a service pressure at least 225 and not over 500 psig gauge. Cylinders closed in by spinning process are not authorized.

(b) *Authorized steel.* Steel used in the construction of the cylinder must conform to the following:

(1) The body of the cylinder must be constructed of steel conforming to the limits specified in table 1 of appendix A to this part.

(2) Material for heads must meet the requirements of paragraph (a) of this section or be open hearth, electric or basic oxygen carbon steel of uniform quality. Content percent may not exceed the following: Carbon 0.25, Manganese 0.60, Phosphorus 0.045, Sulfur 0.050. Heads must be hemispherical or ellipsoidal in shape with a maximum ratio of 2.1. If low carbon steel is used, the thickness of such heads must be determined by using a maximum wall stress of 24,000 p.s.i. in the formula described in paragraph (f)(4) of this section.

(c) *Identification of material.* Material must be identified by any suitable method.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart and the following:

(1) No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface is required. Exposed bottom welds on cylinders over 18 inches long must be protected by

footrings. Minimum thickness of heads may not be less than 90 percent of the required thickness of the sidewall. Heads must be concave to pressure.

(2) Circumferential seams must be by electric-arc welding. Joints must be butt with one member offset (joggle butt) or lap with minimum overlap of at least four times nominal sheet thickness.

(3) Longitudinal seams in shells must conform to the following:

(i) Longitudinal electric-arc welded seams must be of the butt welded type. Welds must be made by a machine process including automatic feed and welding guidance mechanisms. Longitudinal seams must have complete joint penetration, and must be free from undercuts, overlaps or abrupt ridges or valleys. Misalignment of mating butt edges may not exceed  $\frac{1}{8}$  of nominal sheet thickness or  $\frac{1}{32}$  inch whichever is less. All joints with nominal sheet thickness up to and including  $\frac{1}{8}$  inch must be tightly butted. When nominal sheet thickness is greater than  $\frac{1}{8}$  inch, the joint must be gapped with maximum distance equal to one-half the nominal sheet thickness or  $\frac{1}{32}$  inch whichever is less. Joint design, preparation and fit-up must be such that requirements of this paragraph (d) are satisfied.

(ii) Maximum joint efficiency must be 1.0 when each seam is radiographed completely. Maximum joint efficiency must be 0.90 when one cylinder from each lot of 50 consecutively welded cylinders is spot radiographed. In addition, one out of the first five cylinders welded following a shut down of welding operations exceeding four hours must be spot radiographed. Spot radiographs, when required, must be made of a finished welded cylinder and must include the girth weld for 2 inches in both directions from the intersection of the longitudinal and girth welds and include at least 6 inches of the longitudinal weld. Maximum joint efficacy of 0.75 must be permissible without radiography.

(4) Welding procedures and operators must be qualified in accordance with CGA Pamphlet C-3 (IBR, see § 171.7 of this subchapter).

(e) *Welding of attachments.* The attachment to the tops and bottoms only

## § 178.61

of cylinders by welding of neckrings, footrings, handles, bosses, pads and valve protection rings is authorized provided that such attachments and the portion of the container to which they are attached are made of weldable steel, the carbon content of which may not exceed 0.25 percent.

(f) *Wall thickness.* For outside diameters over 6 inches the minimum wall thickness must be 0.078 inch. For a cylinder with a wall thickness less than 0.100 inch, the ratio of tangential length to outside diameter may not exceed 4 to 1 (4:1). In any case the minimum wall thickness must be such that the wall stress calculated by the formula listed in paragraph (f)(4) of this section may not exceed the lesser value of any of the following:

(1) The value referenced in paragraph (b) of this section for the particular material under consideration.

(2) One-half of the minimum tensile strength of the material determined as required in paragraph (j) of this section.

(3) 35,000 psi.

(4) Stress must be calculated by the following formula:

$$S = [2P(1.3D^2 + 0.4d^2)] / [E(D^2 - d^2)]$$

where:

S = wall stress, psi;

P = service pressure, psig;

D = outside diameter, inches;

d = inside diameter, inches;

E = joint efficiency of the longitudinal seam (from paragraph (d) of this section).

(g) *Heat treatment.* Each cylinder must be uniformly and properly heat treated prior to test by the applicable method referenced in Table 1 of appendix A to this part. Heat treatment must be accomplished after all forming and welding operations. Heat treatment is not required after welding or brazing of weldable low carbon parts to attachments of similar material which have been previously welded to the top or bottom of cylinders and properly heat treated, provided such subsequent welding or brazing does not produce a temperature in excess of 400 °F in any part of the top or bottom material.

(h) *Openings in cylinders.* Openings in the cylinder must conform to the following:

## 49 CFR Ch. I (10–1–08 Edition)

(1) All openings must be in the heads or bases.

(2) Openings in cylinders must be provided with adequate fittings, bosses, or pads, integral with or securely attached to the cylinder by welding.

(3) Threads must comply with the following:

(i) Threads must be clean cut and to gauge.

(ii) Taper threads must be of length not less than as specified for American Standard Taper Pipe threads.

(iii) Straight threads, having at least 4 engaged threads, to have tight fit and calculated shear strength at least 10 times the test pressure of the cylinder; gaskets required, adequate to prevent leakage.

(4) Closure of fittings, boss or pads must be adequate to prevent leakage.

(i) *Hydrostatic test.* Cylinders must withstand a hydrostatic test, as follows:

(1) The test must be by water-jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit readings to an accuracy of 1 percent. The expansion gauge must permit readings of total volumetric expansion to an accuracy either of 1 percent or 0.1 cubic centimeter.

(2) Pressure must be maintained for at least 30 seconds and sufficiently longer to ensure complete expansion. Any internal pressure applied after heat treatment and previous to the official test may not exceed 90 percent of the test pressure.

(3) Permanent volumetric expansion may not exceed 10 percent of the total volumetric expansion at test pressure.

(4) Cylinders must be tested as follows:

(i) At least 1 cylinder selected at random out of each lot of 200 or less must be tested as outlined in paragraphs (i)(1), (i)(2), and (i)(3) of this section to at least two times service pressure.

(ii) All cylinders not tested as outlined in paragraph (i)(4)(i) of this section must be examined under pressure of at least two times service pressure and show no defect.

(5) One finished cylinder selected at random out of each lot of 500 or less successively produced must be

hydrostatically tested to 4 times service pressure without bursting.

(j) *Physical tests.* Cylinders must be subjected to a physical test as follows:

(1) Specimens must be taken from one cylinder after heat treatment and chosen at random from each lot of 200 or less, as follows:

(i) *Body specimen.* One specimen must be taken longitudinally from the body section at least 90 degrees away from the weld.

(ii) *Head specimen.* One specimen must be taken from either head on a cylinder when both heads are made of the same material. However, if the two heads are made of differing materials, a specimen must be taken from each head.

(iii) If due to welded attachments on the top head there is insufficient surface from which to take a specimen, it may be taken from a representative head of the same heat treatment as the test cylinder.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width not over  $1\frac{1}{2}$  inches, a gauge length of 2 inches with a width not over  $1\frac{1}{2}$  inches, or a gauge length at least 24 times thickness with a width not over 6 times thickness is authorized when a cylinder wall is not over  $\frac{3}{16}$  inch thick.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within 1 inch of each end of the reduced section.

(iii) When size of the cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows when specimens are so taken and prepared, the inspector's report must show in connection with record of physical tests detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by either the "off-set" method

or the "extension under load" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) In using the "extension under load" method, the total strain (or "extension under load"), corresponding to the stress at which the 0.2-percent permanent strain occurs may be determined with sufficient accuracy by calculating the elastic extension of the gauge length under appropriate load and adding thereto 0.2 percent of the gauge length. Elastic extension calculations must be based on an elastic modulus of 30,000,000. In the event of controversy, the entire stress-strain diagram must be plotted and the yield strength determined from the 0.2-percent offset.

(iii) For the purpose of strain measurement, the initial strain reference must be set while the specimen is under a stress of 12,000 psi and the strain indicator reading being set at the calculated corresponding strain.

(iv) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(k) *Elongation.* Physical test specimens must show at least a 40 percent elongation for a 2-inch gauge length or at least a 20 percent elongation in other cases. Except that these elongation percentages may be reduced numerically by 2 for 2-inch specimens and by 1 in other cases for each 7,500 psi increment of tensile strength above 50,000 psi to a maximum of four increments.

(l) *Tests of welds.* Welds must be subjected to the following tests:

(1) *Tensile test.* A specimen must be cut from one cylinder of each lot of 200 or less. The specimen must be taken from across the longitudinal seam and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3.

(2) *Guided bend test.* A root test specimen must be cut from the cylinder used for the tensile test specified in paragraph (l)(1) of this section. Specimens must be taken from across the longitudinal seam and must be prepared and tested in accordance with and must meet the requirements of CGA Pamphlet C-3.

§ 178.65

49 CFR Ch. I (10–1–08 Edition)

(3) *Alternate guided bend test.* This test may be used and must be as required by CGA Pamphlet C-3. The specimen must be bent until the elongation at the outer surface, adjacent to the root of the weld, between the lightly scribed gauge lines a to b, must be at least 20 percent, except that this percentage may be reduced for steels having a tensile strength in excess of 50,000 psi, as provided in paragraph (k) of this section.

(m) *Radiographic examination.* Welds of the cylinders must be subjected to a radiographic examination as follows:

(1) Radiographic inspection must conform to the techniques and acceptability criteria set forth in CGA Pamphlet C-3. When fluoroscopic inspection is used, permanent film records need not be retained.

(2) Should spot radiographic examination fail to meet the requirements of paragraph (m)(1) of this section, two additional welds from the same lot of 50 cylinders or less must be examined, and if either of these fail to meet the requirements, each cylinder must be examined as previously outlined; only those passing are acceptable.

(n) *Rejected cylinders.* (1) Unless otherwise stated, if a sample cylinder or specimen taken from a lot of cylinders fails the prescribed test, then two additional specimens must be selected from the same lot and subjected to the prescribed test. If either of these fails the test, then the entire lot must be rejected.

(2) Reheat treatment of rejected cylinders is authorized. Subsequent thereto, cylinders must pass all prescribed tests to be acceptable. Repair of welded seams by welding is authorized provided that all defective metal is cut away and the joint is rewelded as prescribed for original welded joints.

(o) *Markings.* Markings must be stamped plainly and permanently in any of the following locations on the cylinder:

(1) On shoulders and top heads when they are not less than 0.087-inch thick.

(2) On a metal plate attached to the top of the cylinder or permanent part thereof; sufficient space must be left on the plate to provide for stamping at least six retest dates; the plate must be at least 1/16-inch thick and must be at-

tached by welding, or by brazing. The brazing rod is to melt at a temperature of 1100 °F. Welding or brazing must be along all the edges of the plate.

(3) On the neck, valve boss, valve protection sleeve, or similar part permanently attached to the top of the cylinder.

(4) On the footing permanently attached to the cylinder, provided the water capacity of the cylinder does not exceed 25 pounds.

(p) *Inspector's report.* In addition to the information required by § 178.35, the inspector's report must indicate the type and amount of radiography.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 64 FR 51919, Sept. 27, 1999; 66 FR 45386, 45388, Aug. 28, 2001; 67 FR 51654, Aug. 6, 2002; 67 FR 61016, Sept. 27, 2002; 68 FR 57633, Oct. 6, 2003; 68 FR 75748, Dec. 31, 2003]

**§ 178.65 Specification 39 non-reusable (non-refillable) cylinders.**

(a) *Type, size, service pressure, and test pressure.* A DOT 39 cylinder is a seamless, welded, or brazed cylinder with a service pressure not to exceed 80 percent of the test pressure. Spherical pressure vessels are authorized and covered by references to cylinders in this specification.

(1) *Size limitation.* Maximum water capacity may not exceed: (i) 55 pounds (1,526 cubic inches) for a service pressure of 500 p.s.i.g. or less, and (ii) 10 pounds (277 cubic inches) for a service pressure in excess of 500 p.s.i.g.

(2) *Test pressure.* The minimum test pressure is the maximum pressure of contents at 130 °F or 180 p.s.i.g. whichever is greater.

(3) *Pressure of contents.* The term "pressure of contents" as used in this specification means the total pressure of all the materials to be shipped in the cylinder.

(b) *Material; steel or aluminum.* The cylinder must be constructed of either steel or aluminum conforming to the following requirements:

(1) *Steel.* (i) The steel analysis must conform to the following:

|                                   | Ladle analysis | Check analysis |
|-----------------------------------|----------------|----------------|
| Carbon, maximum percent .....     | 0.12           | 0.15           |
| Phosphorus, maximum percent ..... | .04            | .05            |
| Sulfur, maximum percent .....     | .05            | .06            |

(ii) For a cylinder made of seamless steel tubing with integrally formed ends, hot drawn, and finished, content percent for the following may not exceed: Carbon, 0.55; phosphorous, 0.045; sulfur, 0.050.

(iii) For non-heat treated welded steel cylinders, adequately killed deep drawing quality steel is required.

(iv) Longitudinal or helical welded cylinders are not authorized for service pressures in excess of 500 p.s.i.g.

(2) *Aluminum.* Aluminum is not authorized for service pressures in excess of 500 psig. The analysis of the aluminum must conform to the Aluminum Association standard for alloys 1060, 1100, 1170, 3003, 5052, 5086, 5154, 6061, and 6063, as specified in its publication entitled "Aluminum Standards and Data" (IBR, see §171.7 of this subchapter).

(3) Material with seams, cracks, laminations, or other injurious defects not permitted.

(4) Material used must be identified by any suitable method.

(c) *Manufacture.* (1) General manufacturing requirements are as follows:

(i) The surface finish must be uniform and reasonably smooth.

(ii) Inside surfaces must be clean, dry, and free of loose particles.

(iii) No defect of any kind is permitted if it is likely to weaken a finished cylinder.

(2) Requirements for seams:

(i) Brazing is not authorized on aluminum cylinders.

(ii) Brazing material must have a melting point of not lower than 1,000 °F.

(iii) Brazed seams must be assembled with proper fit to ensure complete penetration of the brazing material throughout the brazed joint.

(iv) Minimum width of brazed joints must be at least four times the thickness of the shell wall.

(v) Brazed seams must have design strength equal to or greater than 1.5 times the minimum strength of the shell wall.

(vi) Welded seams must be properly aligned and welded by a method that provides clean, uniform joints with adequate penetration.

(vii) Welded joints must have a strength equal to or greater than the

minimum strength of the shell material in the finished cylinder.

(3) Attachments to the cylinder are permitted by any means which will not be detrimental to the integrity of the cylinder. Welding or brazing of attachments to the cylinder must be completed prior to all pressure tests.

(4) Welding procedures and operators must be qualified in accordance with CGA Pamphlet C-3 (IBR, see §171.7 of this subchapter).

(d) *Wall thickness.* The minimum wall thickness must be such that the wall stress at test pressure does not exceed the yield strength of the material of the finished cylinder wall. Calculations must be made by the following formulas:

(1) Calculation of the stress for cylinders must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = Wall stress, in psi;

P = Test pressure in psig;

D = Outside diameter, in inches;

d = Inside diameter, in inches.

(2) Calculation of the stress for spheres must be made by the following formula:

$$S = PD / 4t$$

Where:

S = Wall stress, in psi;

P = Test pressure in psig;

D = Outside diameter, in inches;

t = Minimum wall thickness, in inches.

(e) *Openings and attachments.* Openings and attachments must conform to the following:

(1) Openings and attachments are permitted on heads only.

(2) All openings and their reinforcements must be within an imaginary circle, concentric to the axis of the cylinder. The diameter of the circle may not exceed 80 percent of the outside diameter of the cylinder. The plane of the circle must be parallel to the plane of a circumferential weld and normal to the long axis of the cylinder.

(3) Unless a head has adequate thickness, each opening must be reinforced by a securely attached fitting, boss, pad, collar, or other suitable means.

(4) Material used for welded openings and attachments must be of weldable

quality and compatible with the material of the cylinder.

(f) *Pressure tests.* (1) Each cylinder must be tested at an internal pressure of at least the test pressure and must be held at that pressure for at least 30 seconds.

(i) The leakage test must be conducted by submersion under water or by some other method that will be equally sensitive.

(ii) If the cylinder leaks, evidences visible distortion, or any other defect, while under test, it must be rejected (see paragraph (h) of this section).

(2) One cylinder taken from the beginning of each lot, and one from each 1,000 or less successively produced within the lot thereafter, must be hydrostatically tested to destruction. The entire lot must be rejected (see paragraph (h) of this section) if:

(i) A failure occurs at a gage pressure less than 2.0 times the test pressure;

(ii) A failure initiates in a braze or a weld or the heat affected zone thereof;

(iii) A failure is other than in the sidewall of a cylinder longitudinal with its long axis; or

(iv) In a sphere, a failure occurs in any opening, reinforcement, or at a point of attachment.

(3) A “lot” is defined as the quantity of cylinders successively produced per production shift (not exceeding 10 hours) having identical size, design, construction, material, heat treatment, finish, and quality.

(g) *Flattening test.* One cylinder must be taken from the beginning of production of each lot (as defined in paragraph (f)(3) of this section) and subjected to a flattening test as follows:

(1) The flattening test must be made on a cylinder that has been tested at test pressure.

(2) A ring taken from a cylinder may be flattened as an alternative to a test on a complete cylinder. The test ring may not include the heat affected zone or any weld. However, for a sphere, the test ring may include the circumferential weld if it is located at a 45 degree angle to the ring,  $\pm 5$  degrees.

(3) The flattening must be between 60 degrees included-angle, wedge shaped knife edges, rounded to a 0.5 inch radius.

(4) Cylinders and test rings may not crack when flattened so that their outer surfaces are not more than six times wall thickness apart when made of steel or not more than ten times wall thickness apart when made of aluminum.

(5) If any cylinder or ring cracks when subjected to the specified flattening test, the lot of cylinders represented by the test must be rejected (see paragraph (h) of this section).

(h) *Rejected cylinders.* Rejected cylinders must conform to the following requirements:

(1) If the cause for rejection of a lot is determinable, and if by test or inspection defective cylinders are eliminated from the lot, the remaining cylinders must be qualified as a new lot under paragraphs (f) and (g) of this section.

(2) Repairs to welds are permitted. Following repair, a cylinder must pass the pressure test specified in paragraph (f) of this section.

(3) If a cylinder made from seamless steel tubing fails the flattening test described in paragraph (g) of this section, suitable uniform heat treatment must be used on each cylinder in the lot. All prescribed tests must be performed subsequent to this heat treatment.

(i) *Markings.* (1) The markings required by this section must be durable and waterproof. The requirements of § 178.35(h) do not apply to this section.

(2) Required markings are as follows:

(i) DOT-39.

(ii) NRC.

(iii) The service pressure.

(iv) The test pressure.

(v) The registration number (M\*\*\*\*) of the manufacturer.

(vi) The lot number.

(vii) The date of manufacture if the lot number does not establish the date of manufacture.

(viii) With one of the following statements:

(A) For cylinders manufactured prior to October 1, 1996: “Federal law forbids transportation if refilled-penalty up to \$25,000 fine and 5 years imprisonment (49 U.S.C. 1809)” or “Federal law forbids transportation if refilled-penalty up to \$500,000 fine and 5 years imprisonment (49 U.S.C. 5124).”

(B) For cylinders manufactured on or after October 1, 1996: “Federal law forbids transportation if refilled—penalty up to \$500,000 fine and 5 years imprisonment (49 U.S.C. 5124).”

(3) The markings required by paragraphs (i)(2)(i) through (i)(2)(v) of this section must be in numbers and letters at least  $\frac{1}{8}$  inch high and displayed sequentially. For example:

DOT-39 NRC 250/500 M1001.

(4) No person may mark any cylinder with the specification identification “DOT-39” unless it was manufactured in compliance with the requirements of this section and its manufacturer has a registration number (M\*\*\*\*) from the Associate Administrator.

[Amdt. 178–114, 61 FR 25942, May 23, 1996, as amended at 65 FR 58631, Sept. 29, 2000; 66 FR 45389, Aug. 28, 2001; 67 FR 51654, Aug. 8, 2002; 68 FR 75748, 75749, Dec. 31, 2003]

#### § 178.68 Specification 4E welded aluminum cylinders.

(a) *Type, size and service pressure.* A DOT 4E cylinder is a welded aluminum cylinder with a water capacity (nominal) of not over 1,000 pounds and a service pressure of at least 225 to not over 500 psig. The cylinder must be constructed of not more than two seamless drawn shells with no more than one circumferential weld. The circumferential weld may not be closer to the point of tangency of the cylindrical portion with the shoulder than 20 times the cylinder wall thickness. Cylinders or shells closed in by spinning process and cylinders with longitudinal seams are not authorized.

(b) *Authorized material.* The cylinder must be constructed of aluminum of uniform quality. The following chemical analyses are authorized:

TABLE 1—AUTHORIZED MATERIALS

| Designation             | Chemical analysis—limits in percent 5154 <sup>1</sup> |
|-------------------------|-------------------------------------------------------|
| Iron plus silicon ..... | 0.45 maximum.                                         |
| Copper .....            | 0.10 maximum.                                         |
| Manganese .....         | 0.10 maximum.                                         |
| Magnesium .....         | 3.10/3.90.                                            |
| Chromium .....          | 0.15/0.35.                                            |
| Zinc .....              | 0.20 maximum.                                         |
| Titanium .....          | 0.20 maximum.                                         |
| Others, each .....      | 0.05 maximum.                                         |
| Others, total .....     | 0.15 maximum.                                         |

TABLE 1—AUTHORIZED MATERIALS—Continued

| Designation    | Chemical analysis—limits in percent 5154 <sup>1</sup> |
|----------------|-------------------------------------------------------|
| Aluminum ..... | remainder.                                            |

<sup>1</sup>Analysis must regularly be made only for the elements specifically mentioned in this table. If, however, the presence of other elements is indicated in the course of routine analysis, further analysis should be made to determine conformance with the limits specified for other elements.

(c) *Identification.* Material must be identified by any suitable method that will identify the alloy and manufacturer's lot number.

(d) *Manufacture.* Cylinders must be manufactured using equipment and processes adequate to ensure that each cylinder produced conforms to the requirements of this subpart. No defect is permitted that is likely to weaken the finished cylinder appreciably. A reasonably smooth and uniform surface finish is required. All welding must be by the gas shielded arc process.

(e) *Welding.* The attachment to the tops and bottoms only of cylinders by welding of neckrings or flanges, footrings, handles, bosses and pads and valve protection rings is authorized. However, such attachments and the portion of the cylinder to which it is attached must be made of weldable aluminum alloys.

(f) *Wall thickness.* The wall thickness of the cylinder must conform to the following:

(1) The minimum wall thickness of the cylinder must be 0.140 inch. In any case, the minimum wall thickness must be such that calculated wall stress at twice service pressure may not exceed the lesser value of either of the following:

(i) 20,000 psi.

(ii) One-half of the minimum tensile strength of the material as required in paragraph (j) of this section.

(2) Calculation must be made by the following formula:

$$S = [P(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

Where:

S = wall stress in psi;

P = minimum test pressure prescribed for water jacket test;

D = outside diameter in inches;

d = inside diameter in inches.



(3) Minimum thickness of heads and bottoms may not be less than the minimum required thickness of the side wall.

(g) *Opening in cylinder.* Openings in cylinders must conform to the following:

(1) All openings must be in the heads or bases.

(2) Each opening in cylinders, except those for safety devices, must be provided with a fitting, boss, or pad, securely attached to cylinder by welding by inert gas shielded arc process or by threads. If threads are used, they must comply with the following:

(i) Threads must be clean-cut, even, without checks and cut to gauge.

(ii) Taper threads to be of length not less than as specified for American Standard taper pipe threads.

(iii) Straight threads, having at least 4 engaged threads, to have tight fit and calculated shear strength at least 10 times the test pressure of the cylinder; gaskets required, adequate to prevent leakage.

(3) Closure of a fitting, boss, or pad must be adequate to prevent leakage.

(h) *Hydrostatic test.* Each cylinder must successfully withstand a hydrostatic test, as follows:

(1) The test must be by water jacket, or other suitable method, operated so as to obtain accurate data. The pressure gauge must permit reading to an accuracy of 1 percent. The expansion gauge must permit a reading of the total expansion to an accuracy either of 1 percent or 0.1 cubic centimeter.

(2) Pressure of 2 times service pressure must be maintained for at least 30 seconds and sufficiently longer to insure complete expansion. Any internal pressure applied previous to the official test may not exceed 90 percent of the test pressure. If, due to failure of the test apparatus, the test pressure cannot be maintained, the test may be repeated at a pressure increased by 10 percent over the pressure otherwise specified.

(3) Permanent volumetric expansion may not exceed 12 percent of total volumetric expansion at test pressure.

(4) Cylinders having a calculated wall stress of 18,000 psi or less at test pressure may be tested as follows:

(i) At least one cylinder selected at random out of each lot of 200 or less must be tested in accordance with paragraphs (h)(1), (h)(2), and (h)(3) of this section.

(ii) All cylinders not tested as provided in paragraph (h)(4)(i) of this section must be examined under pressure of at least 2 times service pressure and show no defect.

(5) One finished cylinder selected at random out of each lot of 1,000 or less must be hydrostatically tested to 4 times the service pressure without bursting. Inability to meet this requirement must result in rejection of the lot.

(i) *Flattening test.* After hydrostatic testing, a flattening test is required on one section of a cylinder, taken at random out of each lot of 200 or less as follows:

(1) If the weld is not at midlength of the cylinder, the test section must be no less in width than 30 times the cylinder wall thickness. The weld must be in the center of the section. Weld reinforcement must be removed by machining or grinding so that the weld is flush with the exterior of the parent metal. There must be no evidence of cracking in the sample when it is flattened between flat plates to no more than 6 times the wall thickness.

(2) If the weld is at midlength of the cylinder, the test may be made as specified in paragraph (i)(1) of this section or must be made between wedge shaped knife edges (60° angle) rounded to a ½ inch radius. There must be no evidence of cracking in the sample when it is flattened to no more than 6 times the wall thickness.

(j) *Physical test.* A physical test must be conducted to determine yield strength, tensile strength, elongation, and reduction of area of material as follows:

(1) The test is required on 2 specimens cut from one cylinder or part thereof taken at random out of each lot of 200 or less.

(2) Specimens must conform to the following:

(i) A gauge length of 8 inches with a width not over 1½ inches, a gauge length of 2 inches with a width not over 1½ inches.

(ii) The specimen, exclusive of grip ends, may not be flattened. Grip ends may be flattened to within 1 inch of each end of the reduced section.

(iii) When size of cylinder does not permit securing straight specimens, the specimens may be taken in any location or direction and may be straightened or flattened cold, by pressure only, not by blows; when specimens are so taken and prepared, the inspector's report must show in connection with record of physical test detailed information in regard to such specimens.

(iv) Heating of a specimen for any purpose is not authorized.

(3) The yield strength in tension must be the stress corresponding to a permanent strain of 0.2 percent of the gauge length. The following conditions apply:

(i) The yield strength must be determined by the "offset" method as prescribed in ASTM E 8 (IBR, see § 171.7 of this subchapter).

(ii) Cross-head speed of the testing machine may not exceed  $\frac{1}{8}$  inch per minute during yield strength determination.

(k) *Acceptable results for physical tests.* An acceptable result of the physical test requires an elongation to at least 7 percent and yield strength not over 80 percent of tensile strength.

(l) *Weld tests.* Welds of the cylinder are required to successfully pass the following tests:

(1) *Reduced section tensile test.* A specimen must be cut from the cylinder used for the physical tests specified in paragraph (j) of this section. The specimen must be taken from across the seam, edges must be parallel for a distance of approximately 2 inches on either side of the weld. The specimen must be fractured in tension. The apparent breaking stress calculated on the minimum wall thickness must be at least equal to 2 times the stress calculated under paragraph (f)(2) of this section, and in addition must have an actual breaking stress of at least 30,000 psi. Should this specimen fail to meet the requirements, specimens may be taken from 2 additional cylinders from the same lot and tested. If either of the latter specimens fails to meet require-

ments, the entire lot represented must be rejected.

(2) *Guided bend test.* A bend test specimen must be cut from the cylinder used for the physical tests specified in paragraph (j) of this section. Specimen must be taken across the seam, must be  $1\frac{1}{2}$  inches wide, edges must be parallel and rounded with a file, and backup strip, if used, must be removed by machining. The specimen must be bent to refusal in the guided bend test jig illustrated in paragraph 6.10 of CGA Pamphlet C-3 (IBR, see § 171.7 of this subchapter). The root of the weld (inside surface of the cylinder) must be located away from the ram of the jig. No specimen must show a crack or other open defect exceeding  $\frac{1}{8}$  inch in any direction upon completion of the test. Should this specimen fail to meet the requirements, specimens may be taken from each of 2 additional cylinders from the same lot and tested. If either of the latter specimens fail to meet requirements, the entire lot represented must be rejected.

(m) *Rejected cylinders.* Repair of welded seams is authorized. Acceptable cylinders must pass all prescribed tests.

(n) *Inspector's report.* In addition to the information required by § 178.35, the record of chemical analyses must also include applicable information on iron, titanium, zinc, and magnesium used in the construction of the cylinder.

[Amdt. 178-114, 61 FR 25942, May 23, 1996, as amended at 62 FR 51561, Oct. 1, 1997; 66 FR 45386, Aug. 28, 2001; 67 FR 51654, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003; 69 FR 54046, Sept. 7, 2004]

#### **§ 178.69 Responsibilities and requirements for manufacturers of UN pressure receptacles.**

(a) Each manufacturer of a UN pressure receptacle marked with "USA" as a country of approval must comply with the requirements in this section. The manufacturer must maintain a quality system, obtain an approval for each initial pressure receptacle design type, and ensure that all production of UN pressure receptacles meets the applicable requirements.

(1) *Quality system.* The manufacturer of a UN pressure receptacle must have

## § 178.70

its quality system approved by the Associate Administrator. The quality system will initially be assessed through an audit by the Associate Administrator or his or her representative to determine whether it meets the requirements of this section. The Associate Administrator will notify the manufacturer in writing of the results of the audit. The notification will contain the conclusions of the audit and any corrective action required. The Associate Administrator may perform periodic audits to ensure that the manufacturer operates in accordance with the quality system. Reports of periodic audits will be provided to the manufacturer. The manufacturer must bear the cost of audits.

(2) *Quality system documentation.* The manufacturer must be able to demonstrate a documented quality system. Management must review the adequacy of the quality system to assure that it is effective and conforms to the requirements in § 178.70. The quality system records must be in English and must include detailed descriptions of the following:

- (i) The organizational structure and responsibilities of personnel with regard to design and product quality;
- (ii) The design control and design verification techniques, processes, and procedures used when designing the pressure receptacles;
- (iii) The relevant procedures for pressure receptacle manufacturing, quality control, quality assurance, and process operation instructions;
- (iv) Inspection and testing methodologies, measuring and testing equipment, and calibration data;
- (v) The process for meeting customer requirements;
- (vi) The process for document control and document revision;
- (vii) The system for controlling non-conforming material and records, including procedures for identification, segregation, and disposition;
- (viii) Production, processing and fabrication, including purchased components, in-process and final materials; and
- (ix) Training programs for relevant personnel.

(3) *Maintenance of quality system.* The manufacturer must maintain the qual-

## 49 CFR Ch. I (10–1–08 Edition)

ity system as approved by the Associate Administrator. The manufacturer shall notify the Associate Administrator of any intended changes to the approved quality system prior to making the change. The Associate Administrator will evaluate the proposed change to determine whether the amended quality system will satisfy the requirements. The Associate Administrator will notify the manufacturer of the findings.

(b) *Design type approvals.* The manufacturer must have each pressure receptacle design type reviewed by an IIA and approved by the Associate Administrator in accordance with § 178.70. A cylinder is considered to be of a new design, compared with an existing approved design, as stated in the applicable ISO design, construction and testing standard.

(c) *Production inspection and certification.* The manufacturer must ensure that each UN pressure receptacle is inspected and certified in accordance with § 178.71.

[71 FR 33885, June 12, 2006]

### § 178.70 Approval of UN pressure receptacles.

(a) *Initial design-type approval.* The manufacturer of a UN pressure receptacle must obtain an initial design type approval from the Associate Administrator. The initial design type approval must be of the pressure receptacle design as it is intended to be produced. The manufacturer must arrange for an IIA, approved by the Associate Administrator in accordance with subpart I of part 107 of this chapter, to perform a pre-audit of its pressure receptacle manufacturing operation prior to having an audit conducted by the Associate Administrator or his designee.

(b) *IIA pre-audit.* The manufacturer must submit an application for initial design type approval to the IIA for review. The IIA will examine the manufacturer's application for initial design type approval for completeness. An incomplete application will be returned to the manufacturer with an explanation. If an application is complete, the IIA will review all technical documentation, including drawings and calculations, to verify that the design

meets all requirements of the applicable UN pressure receptacle standard and specification requirements. If the technical documentation shows that the pressure receptacle prototype design conforms to the applicable standards and requirements in §178.70, the manufacturer will fabricate a prototype lot of pressure receptacles in conformance with the technical documentation representative of the design. The IIA will verify that the prototype lot conforms to the applicable requirements by selecting pressure receptacles and witnessing their testing. After prototype testing has been satisfactorily completed, showing the pressure receptacles fully conform to all applicable specification requirements, the certifying IIA must prepare a letter of recommendation and a design type approval certificate. The design type approval certificate must contain the name and address of the manufacturer and the IIA certifying the design type, the test results, chemical analyses, lot identification, and all other supporting data specified in the applicable ISO design, construction and testing standard. The IIA must provide the certificate and documentation to the manufacturer.

(c) *Application for initial design type approval.* If the pre-audit is found satisfactory by the IIA, the manufacturer will submit the letter of recommendation from the IIA and an application for design type approval to the Associate Administrator. An application for initial design type approval must be submitted for each manufacturing facility. The application must be in English and, at a minimum, contain the following information:

(1) The name and address of the manufacturing facility. If the application is submitted by an authorized representative on behalf of the manufacturer, the application must include the representative's name and address.

(2) The name and title of the individual responsible for the manufacturer's quality system, as required by §178.69.

(3) The designation of the pressure receptacle and the relevant pressure receptacle standard.

(4) Details of any refusal of approval of a similar application by a designated approval agency of another country.

(5) The name and address of the production IIA that will perform the functions prescribed in paragraph (e) of this section. The IIA must be approved in writing by the Associate Administrator in accordance with subpart I of part 107 of this chapter.

(6) Documentation on the manufacturing facility as specified in §178.69.

(7) Design specifications and manufacturing drawings, showing components and subassemblies if relevant, design calculations, and material specifications necessary to verify compliance with the applicable pressure receptacle design standard.

(8) Manufacturing procedures and any applicable standards that describe in detail the manufacturing processes and control.

(9) Design type approval test reports detailing the results of examinations and tests conducted in accordance with the relevant pressure receptacle standard, to include any additional data, such as suitability for underwater applications or compatibility with hydrogen embrittlement gases.

(d) *Modification of approved pressure receptacle design type.* Modification of an approved UN pressure receptacle design type is not authorized without the approval of the Associate Administrator. A manufacturer seeking modification of an approved UN pressure receptacle design type may be required to submit design qualification test data to the Associate Administrator before production. An audit may be required as part of the process to modify an approval.

(e) *Responsibilities of the production IIA.* The production IIA is responsible for ensuring that each pressure receptacle conforms to the design type approval. The production IIA must perform the following functions:

(1) Witness all inspections and tests specified in the UN pressure receptacle standard to ensure compliance with the standard and that the procedures adopted by the manufacturer meet the requirements of the standard;

(2) Verify that the production inspections were performed in accordance with this section;

(3) Select UN pressure receptacles from a prototype production lot and witness testing as required for the design type approval;

(4) Ensure that the various design type approval examinations and tests are performed accurately;

(5) Verify that each pressure receptacle is marked in accordance with the applicable requirements in §178.72; and

(6) Furnish complete test reports to the manufacturer and upon request to the purchaser. The test reports and certificate of compliance must be retained by the IIA for at least 20 years from the original test date of the pressure receptacles.

(f) *Production inspection audit and certification.* (1) If the application, design drawing and quality control documents are found satisfactory, PHMSA will schedule an on-site audit of the pressure receptacle manufacturer's quality system, manufacturing processes, inspections, and test procedures.

(2) During the audit, the manufacturer will be required to produce pressure receptacles to the technical standards for which approval is sought.

(3) The production IIA must witness the required inspections and verifications on the pressure receptacles during the production run. The IIA selected by the manufacturer for production inspection and testing may be different from the IIA who performed the design type approval verifications.

(4) If the procedures and controls are deemed acceptable, test sample pressure receptacles will be selected at random from the production lot and sent to a laboratory designated by the Associate Administrator for verification testing.

(5) If the pressure receptacle test samples are found to conform to all the applicable requirements, the Associate Administrator will issue approvals to the manufacturer and the production IIA to authorize the manufacture of the pressure receptacles. The approved design type approval certificate will be returned to the manufacturer.

(6) Upon the receipt of the approved design type approval certificate from the Associate Administrator, the pressure receptacle manufacturer must sign the certificate.

(g) *Recordkeeping.* The production IIA and the manufacturer must retain a copy of the design type approval certificate and certificate of compliance records for at least 20 years.

(h) *Denial of design type application.* If the design type application is denied, the Associate Administrator will notify the applicant in writing and provide the reason for the denial. The manufacturer may request that the Associate Administrator reconsider the decision. The application request must—

(1) Be written in English and filed within 60 days of receipt of the decision;

(2) State in detail any alleged errors of fact and law; and

(3) Enclose any additional information needed to support the request to reconsider.

(i) *Appeal.* (1) A manufacturer whose reconsideration request is denied may appeal to the PHMSA Administrator. The appeal must—

(i) Be written in English and filed within 60 days of receipt of the Associate Administrator's decision on reconsideration;

(ii) State in detail any alleged errors of fact and law;

(iii) Enclose any additional information needed to support the appeal; and

(iv) State in detail the modification of the final decision sought.

(2) The PHMSA Administrator will grant or deny the relief and inform the appellant in writing of the decision. PHMSA Administrator's decision is the final administrative action.

(j) *Termination of a design type approval certificate.* (1) The Associate Administrator may terminate an approval certificate issue under this section if it is determined that, because of a change in circumstances, the approval no longer is needed or no longer would be granted if applied for; information upon which the approval was based is fraudulent or substantially erroneous; or termination of the approval is necessary to adequately protect against risks to life and property.

(2) Before an approval is terminated, the Associate Administrator will provide the manufacturer and the approval agency—

(i) Written notice of the facts or conduct believed to warrant the withdrawal;

(ii) Opportunity to submit oral and written evidence, and

(iii) Opportunity to demonstrate or achieve compliance with the application requirement.

(3) If the Associate Administrator determines that a certificate of approval must be withdrawn to preclude a significant and imminent adverse effect on public safety, the procedures in paragraph (j)(2)(ii) and (iii) of this section need not be provided prior to withdrawal of the approval, but shall be provided as soon as practicable thereafter.

[71 FR 33886, June 12, 2006, as amended at 71 FR 54397, Sept. 14, 2006]

#### § 178.71 Specifications for UN pressure receptacles.

(a) *General.* Each UN pressure receptacle must meet the requirements of this section. Requirements for approval, qualification, maintenance, and testing are contained in § 178.70, and subpart C of part 180 of this subchapter.

(b) *Definitions.* The following definitions apply for the purposes of design and construction of UN pressure receptacles under this subpart:

*Alternative arrangement* means an approval granted by the Associate Administrator for a MEGC that has been designed, constructed or tested to the technical requirements or testing methods other than those specified for UN pressure receptacles in part 178 or part 180 of this subchapter.

*Bundle of cylinders.* See § 171.8 of this subchapter.

*Design type* means a pressure receptacle design as specified by a particular pressure receptacle standard.

*Design type approval* means an overall approval of the manufacturer's quality system and design type of each pressure receptacle to be produced within the manufacturer's facility.

*UN tube.* See § 171.8 of this subchapter.

(c) *General design and construction.* UN pressure receptacles and their closures must be designed, manufactured, tested and equipped in accordance with the requirements contained in this section.

(1) Following the final heat treatment, all cylinders, except those selected for batch testing must be subjected to a hydraulic volumetric expansion test.

(2) The standard requirements applicable to UN pressure receptacles may be varied only if approved in writing by the Associate Administrator.

(3) The test pressure of UN cylinders, tubes, and bundles of cylinders must conform to the requirements in part 178 of this subchapter.

(d) *Service equipment.* (1) Except for pressure relief devices, UN pressure receptacle equipment, including valves, piping, fittings, and other equipment subjected to pressure must be designed and constructed to withstand at least 1.5 times the test pressure of the pressure receptacle.

(2) Service equipment must be configured or designed to prevent damage that could result in the release of the pressure receptacle contents during normal conditions of handling and transport. Manifold piping leading to shut-off valves must be sufficiently flexible to protect the valves and the piping from shearing or releasing the pressure receptacle contents. The filling and discharge valves and any protective caps must be secured against unintended opening. The valves must conform to ISO 10297 (IBR, see § 171.7 of this subchapter) and be protected as specified in § 173.301b(f) of this subchapter.

(3) UN pressure receptacles that cannot be handled manually or rolled, must be equipped with devices (*e.g.* skids, rings, straps) ensuring that they can be safely handled by mechanical means and so arranged as not to impair the strength of, nor cause undue stresses, in the pressure receptacle.

(4) Pressure receptacles filled by volume must be equipped with a level indicator.

(e) *Bundles of cylinders.* UN pressure receptacles assembled in bundles must be structurally supported and held together as a unit and secured in a manner that prevents movement in relation to the structural assembly and movement that would result in the concentration of harmful local stresses. The frame design must ensure

stability under normal operating conditions.

(1) The frame must securely retain all the components of the bundle and must protect them from damage during conditions normally incident to transportation. The method of cylinder restraint must prevent any vertical or horizontal movement or rotation of the cylinder that could cause undue strain on the manifold. The total assembly must be able to withstand rough handling, including being dropped or overturned.

(2) The frame must include features designed for the handling and transportation of the bundle. The lifting rings must be designed to withstand a design load of 2 times the maximum gross weight. Bundles with more than one lifting ring must be designed such that a minimum sling angle of 45 degrees to the horizontal can be achieved during lifting using the lifting rings. If four lifting rings are used, their design must be strong enough to allow the bundle to be lifted by two rings. Where two or four lifting rings are used, diametrically opposite lifting rings must be aligned with each other to allow for correct lifting using shackle pins. If the bundle is filled with forklift pockets, it must contain two forklift pockets on each side from which it is to be lifted. The forklift pockets must be positioned symmetrically consistent with the bundle center of gravity.

(3) The frame structural members must be designed for a vertical load of 2 times the maximum gross weight of the bundle. Design stress levels may not exceed 0.9 times the yield strength of the material.

(4) The frame may not contain any protrusions from the exterior frame structure that could cause a hazardous condition.

(5) The frame design must prevent collection of water or other debris that would increase the tare weight of bundles filled by weight.

(6) The floor of the bundle frame must not buckle during normal operating conditions and must allow for the drainage of water and debris from around the base of the cylinders.

(7) If the frame design includes movable doors or covers, they must be capable of being secured with latches or

other means that will not become dislodged by operational impact loads. Valves that need to be operated in normal service or in an emergency must be accessible.

(f) [Reserved]

(g) *Design and construction requirements for UN refillable seamless steel cylinders.* In addition to the general requirements of this section, UN refillable seamless steel cylinders must conform to the following ISO standards, as applicable:

(1) ISO 9809-1: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 1: Quenched and tempered steel cylinders with tensile strength less than 1 100 MPa. (IBR, see §171.7 of this subchapter).

(2) ISO 9809-2: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 2: Quenched and tempered steel cylinders with tensile strength greater than or equal to 1 100 MPa. (IBR, see §171.7 of this subchapter).

(3) ISO 9809-3: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 3: Normalized steel cylinders. (IBR, see §171.7 of this subchapter).

(h) *Design and construction requirements for UN refillable seamless aluminum alloy cylinders.* In addition to the general requirements of this section, UN refillable seamless aluminum cylinders must conform to ISO 7866: Gas cylinders—Refillable seamless aluminum alloy gas cylinders—Design, construction and testing. (IBR, see §171.7 of this subchapter). The use of Aluminum alloy 6351-T6 or equivalent is prohibited.

(i) *Design and construction requirements for UN non-refillable metal cylinders.* In addition to the general requirements of this section, UN non-refillable metal cylinders must conform to ISO 11118: Gas cylinders—Non-refillable metallic gas cylinders—Specification and test methods. (IBR, see §171.7 of this subchapter).

(j) *Design and construction requirements for UN refillable seamless steel tubes.* In addition to the general requirements of this section, UN refillable seamless steel tubes must conform to ISO 11120: Gas cylinders—Refillable

seamless steel tubes of water capacity between 150 L and 3000 L—Design, construction and testing. (IBR, see § 171.7 of this subchapter).

(k) *Design and construction requirements for UN acetylene cylinders.* In addition to the general requirements of this section, UN acetylene cylinders must conform to the following ISO standards, as applicable:

(1) For the cylinder shell:

(i) ISO 9809-1: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 1: Quenched and tempered steel cylinders with tensile strength less than 1 100 MPa.

(ii) ISO 9809-3: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 3: Normalized steel cylinders.

(2) The porous mass in an acetylene cylinder must conform to ISO 3807-2: Cylinders for acetylene—Basic requirements—Part 2: Cylinders with fusible plugs. (IBR, see § 171.7 of this subchapter).

(l) *Design and construction requirements for UN composite cylinders.* (1) In addition to the general requirements of this section, UN composite cylinders must be designed for unlimited service life and conform to the following ISO standards, as applicable:

(i) ISO 11119-1: Gas cylinders of composite construction—Specification and test methods—Part 1: Hoop-wrapped composite gas cylinders. (IBR, see § 171.7 of this subchapter).

(ii) ISO 11119-2: Gas cylinders of composite construction—Specification and test methods—Part 2: Fully-wrapped fibre reinforced composite gas cylinders with load-sharing metal liners. (IBR, see § 171.7 of this subchapter).

(iii) ISO 11119-3: Gas cylinders of composite construction—Specification and test methods—Part 3: Fully wrapped fibre reinforced composite gas cylinders with non-load sharing metallic or non-metallic liners. (IBR, see § 171.7 of this subchapter).

(2) ISO 11119-2 and ISO 11119-3 gas cylinders of composite construction manufactured in accordance with the requirements for underwater use must bear the “UW” mark.

(m) *Material compatibility.* In addition to the material requirements specified

in the UN pressure receptacle design and construction ISO standards, and any restrictions specified in part 173 for the gases to be transported, the requirements of the following standards must be applied with respect to material compatibility:

(1) ISO 11114-1: Transportable gas cylinders—Compatibility of cylinder and valve materials with gas contents—Part 1: Metallic materials. (IBR, see § 171.7 of this subchapter).


(2) ISO 11114-2: Transportable gas cylinders—Compatibility of cylinder and valve materials with gas contents—Part 2: Non-metallic materials. (IBR, see § 171.7 of this subchapter).

(n) *Protection of closures.* Closures and their protection must conform to the requirements in § 173.301(f) of this subchapter.

(o) *Marking of UN refillable pressure receptacles.* UN refillable pressure receptacles must be marked clearly and legibly. The required markings must be permanently affixed by stamping, engraving, or other equivalent method, on the shoulder, top end or neck of the pressure receptacle or on a permanently affixed component of the pressure receptacle, such as a welded collar. Except for the “UN” mark, the minimum size of the marks must be 5 mm for pressure receptacles with a diameter greater than or equal to 140 mm and 2.5 mm for pressure receptacles with a diameter less than 140 mm. The minimum size of the “UN” mark must be 5 mm for pressure receptacles with a diameter less than 140 mm and 10 mm for pressure receptacles with a diameter of greater than or equal to 140 mm. The depth of the markings must not create harmful stress concentrations. A refillable pressure receptacle conforming to the UN standard must be marked as follows:

(1) The UN packaging symbol.





(2) The ISO standard, for example ISO 9809–1, used for design, construction and testing. Acetylene cylinders must be marked to indicate the porous mass and the steel shell, for example: “ISO 3807–2/ISO 9809–1.”

(3) The mark of the country where the approval is granted. The letters “USA” must be marked on UN pressure receptacles approved by the United States. The manufacturer must obtain an approval number from the Associate Administrator. The manufacturer approval number must follow the country of approval mark, separated by a slash (for example, USA/MXXXX). Pressure receptacles approved by more than one national authority may contain the mark of each country of approval, separated by a comma.

(4) The identity mark or stamp of the IIA.

(5) The date of the initial inspection, the year (four digits) followed by the month (two digits) separated by a slash, for example “2006/04”.

(6) The test pressure in bar, preceded by the letters “PH” and followed by the letters “BAR”. The test pressure must be obtained from the results of a hydraulic volumetric expansion test.

(7) The empty or tare weight. Except for acetylene cylinders, empty weight is the mass of the pressure receptacle in kilograms, including all integral parts (e.g., collar, neck ring, foot ring, etc.), followed by the letters “KG”. The empty weight does not include the mass of the valve, valve cap or valve guard or any coating. The empty weight must be expressed to three significant figures rounded up to the last digit. For cylinders of less than 1 kg, the empty weight must be expressed to two significant figures rounded down

to the last digit. For acetylene cylinders, the tare weight must be marked on the cylinders in kilograms (KG). The tare weight is the sum of the empty weight, mass of the valve, any coating and all permanently attached parts (e.g. fittings and accessories) that are not removed during filling. The tare weight must be expressed to two significant figures rounded down to the last digit. The tare weight does not include the cylinder cap or any outlet cap or plug not permanently attached to the cylinder.

(8) The minimum wall thickness of the pressure receptacle in millimeters followed by the letters “MM”. This mark is not required for pressure receptacles with a water capacity less than or equal to 1.0 L or for composite cylinders.

(9) For pressure receptacles intended for the transport of compressed gases and UN 1001 acetylene, dissolved, the working pressure in bar, preceded by the letters “PW”.

(10) For liquefied gases, the water capacity in liters expressed to three significant digits rounded down to the last digit, followed by the letter “L”. If the value of the minimum or nominal water capacity is an integer, the digits after the decimal point may be omitted.

(11) Identification of the cylinder thread type (e.g., 25E).

(12) The country of manufacture. The letters “USA” must be marked on cylinders manufactured in the United States.

(13) The serial number assigned by the manufacturer.

(14) For steel pressure receptacles, the letter “H” showing compatibility of the steel, as specified in ISO 1114–1.

(15) Identification of aluminum alloy, if applicable.

(16) Stamp for nondestructive testing, if applicable.

(17) Stamp for underwater use of composite cylinders, if applicable.


(p) *Marking sequence.* The marking required by paragraph (o) of this section must be placed in three groups as shown in the example below:

(1) The top grouping contains manufacturing marks and must appear consecutively in the sequence given in

paragraphs (o)(11) through (17) of this section.

(2) The middle grouping contains operational marks described in paragraphs (o)(6) through (10) of this section.

(3) The bottom grouping contains certification marks and must appear consecutively in the sequence given in paragraph (o)(1) through (5) of this section.



(q) *Other markings.* Other markings are allowed in areas other than the side wall, provided they are made in low stress areas and are not of a size and depth that will create harmful stress concentrations. Such marks must not conflict with required marks.

(r) *Marking of UN non-refillable pressure receptacles.* Unless otherwise specified in this paragraph, each UN non-refillable pressure receptacle must be clearly and legibly marked as prescribed in paragraph (o) of this section. In addition, permanent stenciling is authorized. Except when stenciled, the marks must be on the shoulder, top end or neck of the pressure receptacle or on a permanently affixed component of the pressure receptacle, for example a welded collar.

(1) The marking requirements and sequence listed in paragraphs (o)(1) through (17) of this section are required, except the markings in para-

graphs (o)(7), (8), (11) and (17) are not applicable. The required serial number marking in paragraph (o)(13) may be replaced by the batch number.

(2) Each receptacle must be marked with the words "DO NOT REFILL" in letters of at least 5 mm in height.

(3) A non-refillable pressure receptacle, because of its size, may substitute the marking required by this paragraph with a label. Reduction in marking size is authorized only as prescribed in ISO 7225, Gas cylinders—Precautionary labels. (IBR, see §171.7 of this subchapter).

(4) Each non-refillable pressure receptacle must also be legibly marked by stenciling the following statement: "Federal law forbids transportation if refilled—penalty up to \$500,000 fine and 5 years in imprisonment (49 U.S.C. 5124)."

(5) No person may mark a non-refillable pressure receptacle as meeting the

requirements of this section unless it was manufactured in conformance with this section.

[71 FR 33887, June 12, 2006, as amended at 71 FR 54397, Sept. 14, 2006]

**§ 178.74 Approval of MEGCs.**

(a) *Application for design type approval.* (1) Each new MEGC design type must have a design approval certificate. An owner or manufacturer must apply to an approval agency that is approved by the Associate Administrator in accordance with subpart E of part 107 of this chapter to obtain approval of a new design. When a series of MEGCs is manufactured without change in the design, the certificate is valid for the entire series. The design approval certificate must refer to the prototype test report, the materials of construction of the manifold, the standards to which the pressure receptacles are made and an approval number. The compliance requirements or test methods applicable to MEGCs as specified in this subpart may be varied when the level of safety is determined to be equivalent to or exceed the requirements of this subchapter and is approved in writing by the Associate Administrator. A design approval may serve for the approval of smaller MEGCs made of materials of the same type and thickness, by the same fabrication techniques and with identical supports, equivalent closures and other appurtenances.

(2) Each application for design approval must be in English and contain the following information:

(i) Two complete copies of all engineering drawings, calculations, and test data necessary to ensure that the design meets the relevant specification.

(ii) The manufacturer's serial number that will be assigned to each MEGC.

(iii) A statement as to whether the design type has been examined by any approval agency previously and judged unacceptable. Affirmative statements must be documented with the name of the approval agency, reason for non-acceptance, and the nature of modifications made to the design type.

(b) *Actions by the approval agency.* The approval agency must review the application for design type approval, includ-

ing all drawings and calculations, to ensure that the design of the MEGC meets all requirements of the relevant specification and to determine whether it is complete and conforms to the requirements of this section. An incomplete application will be returned to the applicant with the reasons why the application was returned. If the application is complete and all applicable requirements of this section are met, the approval agency must prepare a MEGC design approval certificate containing the manufacturer's name and address, results and conclusions of the examination and necessary data for identification of the design type. If the Associate Administrator approves the Design Type Approval Certificate application, the approval agency and the manufacturer must each maintain a copy of the approved drawings, calculations, and test data for at least 20 years.

(c) *Approval agency's responsibilities.* The approval agency is responsible for ensuring that the MEGC conforms to the design type approval. The approval agency must:

(1) Witness all tests required for the approval of the MEGC specified in this section and § 178.75.

(2) Ensure, through appropriate inspection, that each MEGC is fabricated in all respects in conformance with the approved drawings, calculations, and test data.

(3) Determine and ensure that the MEGC is suitable for its intended use and that it conforms to the requirements of this subchapter.

(4) Apply its name, identifying mark or identifying number, and the date the approval was issued, to the metal identification marking plate attached to the MEGC upon successful completion of all requirements of this subpart. Any approvals by the Associate Administrator authorizing design or construction alternatives (Alternate Arrangements) of the MEGC (see paragraph (a) of this section) must be indicated on the metal identification plate as specified in § 178.75(j).

(5) Prepare an approval certificate for each MEGC or, in the case of a series of identical MEGCs manufactured to a single design type, for each series of MEGCs. The approval certificate

must include all of the following information:

(i) The information displayed on the metal identification plate required by § 178.75(j);

(ii) The results of the applicable framework test specified in ISO 1496-3 (IBR, see § 171.7 of this subchapter);

(iii) The results of the initial inspection and test specified in paragraph (h) of this section;

(iv) The results of the impact test specified in § 178.75(i)(4);

(v) Certification documents verifying that the cylinders and tubes conform to the applicable standards; and

(vi) A statement that the approval agency certifies the MEGC in accordance with the procedures in this section and that the MEGC is suitable for its intended purpose and meets the requirements of this subchapter. When a series of MEGCs is manufactured without change in the design type, the certificate may be valid for the entire series of MEGCs representing a single design type. The approval number must consist of the distinguishing sign or mark of the country ("USA" for the United States of America) where the approval was granted and a registration number.

(6) Retain on file a copy of each approval certificate for at least 20 years.

(d) *Manufacturers' responsibilities.* The manufacturer is responsible for compliance with the applicable specifications for the design and construction of MEGCs. The manufacturer of a MEGC must:

(1) Comply with all the requirements of the applicable ISO standard specified in § 178.71;

(2) Obtain and use an approval agency to review the design, construction and certification of the MEGC;

(3) Provide a statement in the manufacturers' data report certifying that each MEGC manufactured complies with the relevant specification and all the applicable requirements of this subchapter; and

(4) Retain records for the MEGCs for at least 20 years. When required by the specification, the manufacturer must provide copies of the records to the approval agency, the owner or lessee of the MEGC, and to a representative of DOT, upon request.

(e) *Denial of application for approval.*

If the Associate Administrator finds that the MEGC will not be approved for any reason, the Associate Administrator will notify the applicant in writing and provide the reason for the denial. The manufacturer may request that the Associate Administrator reconsider the decision. The application request must—

(1) Be written in English and filed within 90 days of receipt of the decision;

(2) State in detail any alleged errors of fact and law; and

(3) Enclose any additional information needed to support the request to reconsider.

(f) *Appeal.* (1) A manufacturer whose reconsideration request is denied may appeal to the PHMSA Administrator. The appeal must—

(i) Be in writing and filed within 90 days of receipt of the Associate Administrator's decision on reconsideration;

(ii) State in detail any alleged errors of fact and law;

(iii) Enclose any additional information needed to support the appeal; and

(iv) State in detail the modification of the final decision sought.

(2) The Administrator will grant or deny the relief and inform the appellant in writing of the decision. The Administrator's decision is the final administrative action.

(g) *Modifications to approved MEGCs.*

(1) Prior to modification of any approved MEGC that may affect performance and safe use, and that may involve a change to the design type or affect its ability to retain the hazardous material in transportation, the MEGC's owner must inform the approval agency that prepared the initial approval certificate for the MEGC or, if the initial approval agency is unavailable, another approval agency, of the nature of the modification and request certification of the modification. The owner must supply the approval agency with all revised drawings, calculations, and test data relative to the intended modification. The MEGC's owner must also provide a statement as to whether the intended modification has been examined and determined to be unacceptable by any approval agency. The written statement must include the name

## § 178.75

## 49 CFR Ch. I (10–1–08 Edition)

of the approval agency, the reason for non-acceptance, and the nature of changes made to the modification since its original rejection.

(2) The approval agency must review the request for modification. If the approval agency determines that the proposed modification does not conform to the relevant specification, the approval agency must reject the request in accordance with paragraph (d) of this section. If the approval agency determines that the proposed modification conforms fully with the relevant specification, the request is accepted. If modification to an approved MEGC alters any information on the approval certificate, the approval agency must prepare a new approval certificate for the modified MEGC and submit the certificate to the Associate Administrator for approval. After receiving approval from the Associate Administrator, the approval agency must ensure that any necessary changes are made to the metal identification plate. A copy of each newly issued approval certificate must be retained by the approval agency and the MEGC's owner for at least 20 years. The approval agency must perform the following activities:

(i) Retain a set of the approved revised drawings, calculations, and data as specified in § 178.69(b)(4) for at least 20 years;

(ii) Ensure through appropriate inspection that all modifications conform to the revised drawings, calculations, and test data; and

(iii) Determine the extent to which retesting of the modified MEGC is necessary based on the nature of the proposed modification, and ensure that all required retests are satisfactorily performed.

(h) *Termination of Approval Certificate.*

(1) The Associate Administrator may terminate an approval issued under this section if he or she determines that—

(i) Because of a change in circumstances, the approval no longer is needed or no longer would be granted if applied for;

(ii) Information upon which the approval was based is fraudulent or substantially erroneous;

(iii) Termination of the approval is necessary to adequately protect against risks to life and property; or

(iv) The MEGC does not meet the specification.

(2) Before an approval is terminated, the Associate Administrator will provide the person—

(i) Written notice of the facts or conduct believed to warrant the termination;

(ii) An opportunity to submit oral and written evidence; and

(3) An opportunity to demonstrate or achieve compliance with the applicable requirements.

(i) *Imminent Danger.* If the Associate Administrator determines that a certificate of approval must be terminated to preclude a significant and imminent adverse effect on public safety, the Associate Administrator may terminate the certificate immediately. In such circumstances, the opportunities of paragraphs (h)(2) and (3) of this section need not be provided prior to termination of the approval, but must be provided as soon as practicable thereafter.

[71 FR 33890, June 12, 2006]

### § 178.75 Specifications for MEGCs.

(a) *General.* Each MEGC must meet the requirements of this section. In a MEGC that meets the definition of a “container” within the terms of the International Convention for Safe Containers (CSC) must meet the requirements of the CSC as amended and 49 CFR parts 450 through 453, and must have a CSC approval plate.

(b) *Alternate Arrangements.* The technical requirements applicable to MEGCs may be varied when the level of safety is determined to be equivalent to or exceed the requirements of this subchapter. Such an alternate arrangement must be approved in writing by the Associate Administrator. MEGCs approved to an Alternate Arrangement must be marked as required by paragraph (j) of this section.

(c) *Definitions.* The following definitions apply:

*Leakproofness test* means a test using gas subjecting the pressure receptacles and the service equipment of the MEGC to an effective internal pressure of not less than 20% of the test pressure.

*Manifold* means an assembly of piping and valves connecting the filling and/or discharge openings of the pressure receptacles.

*Maximum permissible gross mass or MPGM* means the heaviest load authorized for transport (sum of the tare mass of the MEGC, service equipment and pressure receptacle).

*Service equipment* means manifold system (measuring instruments, piping and safety devices).

*Shut-off valve* means a valve that stops the flow of gas.

*Structural equipment* means the reinforcing, fastening, protective and stabilizing members external to the pressure receptacles.

(d) *General design and construction requirements.* (1) The MEGC must be capable of being loaded and discharged without the removal of its structural equipment. It must possess stabilizing members external to the pressure receptacles to provide structural integrity for handling and transport. MEGCs must be designed and constructed with supports to provide a secure base during transport and with lifting and tie-down attachments that are adequate for lifting the MEGC including when loaded to its maximum permissible gross mass. The MEGC must be designed to be loaded onto a transport vehicle or vessel and equipped with skids, mountings or accessories to facilitate mechanical handling.

(2) MEGCs must be designed, manufactured and equipped to withstand, without loss of contents, all normal handling and transportation conditions. The design must take into account the effects of dynamic loading and fatigue.

(3) Each pressure receptacle of a MEGC must be of the same design type, seamless steel, and constructed and tested according to one of the following ISO standards:

(i) ISO 9809-1: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 1: Quenched and tempered steel cylinders with tensile strength less than 1 100 MPa. (IBR, see §171.7 of this subchapter);

(ii) ISO 9809-2: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 2:

Quenched and tempered steel cylinders with tensile strength greater than or equal to 1 100 MPa. (IBR, see §171.7 of this subchapter);

(iii) ISO 9809-3: Gas cylinders—Refillable seamless steel gas cylinders—Design, construction and testing—Part 3: Normalized steel cylinders. (IBR, see §171.7 of this subchapter); or

(iv) ISO 11120: Gas cylinders—Refillable seamless steel tubes of water capacity between 150 L and 3000 L—Design, construction and testing. (IBR, see §171.7 of this subchapter).

(4) Pressure receptacles of MEGCs, fittings, and pipework must be constructed of a material that is compatible with the hazardous materials intended to be transported, as specified in this subchapter.

(5) Contact between dissimilar metals that could result in damage by galvanic action must be prevented by appropriate means.

(6) The materials of the MEGC, including any devices, gaskets, and accessories, must have no adverse effect on the gases intended for transport in the MEGC.

(7) MEGCs must be designed to withstand, without loss of contents, at least the internal pressure due to the contents, and the static, dynamic and thermal loads during normal conditions of handling and transport. The design must take into account the effects of fatigue, caused by repeated application of these loads through the expected life of the MEGC.

(8) MEGCs and their fastenings must, under the maximum permissible load, be capable of withstanding the following separately applied static forces (for calculation purposes, acceleration due to gravity ( $g$ ) = 9.81 m/s<sup>2</sup>):

(i) In the direction of travel: 2g (twice the MPGM multiplied by the acceleration due to gravity);

(ii) Horizontally at right angles to the direction of travel: 1g (the MPGM multiplied by the acceleration due to gravity. When the direction of travel is not clearly determined, the forces must be equal to twice the MPGM);

(iii) Vertically upwards: 1g (the MPGM multiplied by the acceleration due to gravity); and

(iv) Vertically downwards: 2g (twice the MPGM (total loading including the

effect of gravity) multiplied by the acceleration due to gravity.

(9) Under each of the forces specified in paragraph (d)(8) of this section, the stress at the most severely stressed point of the pressure receptacles must not exceed the values given in the applicable design specifications (*e.g.*, ISO 11120).

(10) Under each of the forces specified in paragraph (d)(8) of this section, the safety factor for the framework and fastenings must be as follows:

(i) For steels having a clearly defined yield point, a safety factor of 1.5 in relation to the guaranteed yield strength; or

(ii) For steels with no clearly defined yield point, a safety factor of 1.5 in relation to the guaranteed 0.2 percent proof strength and, for austenitic steels, the 1 percent proof strength.

(11) MEGCs must be capable of being electrically grounded to prevent electrostatic discharge when intended for flammable gases.

(12) The pressure receptacles of a MEGC must be secured in a manner to prevent movement that could result in damage to the structure and concentration of harmful localized stresses.

(e) *Service equipment.* (1) Service equipment must be arranged so that it is protected from mechanical damage by external forces during handling and transportation. When the connections between the frame and the pressure receptacles allow relative movement between the subassemblies, the equipment must be fastened to allow movement to prevent damage to any working part. The manifolds, discharge fittings (pipe sockets, shut-off devices), and shut-off valves must be protected from damage by external forces. Manifold piping leading to shut-off valves must be sufficiently flexible to protect the valves and the piping from shearing, or releasing the pressure receptacle contents. The filling and discharge devices, including flanges or threaded plugs, and any protective caps must be capable of being secured against unintended opening.

(2) Each pressure receptacle intended for the transport of Division 2.3 gases must be equipped with an individual shut-off valve. The manifold for Divi-

sion 2.3 liquefied gases must be designed so that each pressure receptacle can be filled separately and be kept isolated by a valve capable of being closed during transit. For Division 2.1 gases, the pressure receptacles must be isolated by an individual shut-off valve into assemblies of not more than 3,000 L.

(3) For MEGC filling and discharge openings:

(i) Two valves in series must be placed in an accessible position on each discharge and filling pipe. One of the valves may be a backflow prevention valve. (ii) The filling and discharge devices may be equipped to a manifold.

(iii) For sections of piping which can be closed at both ends and where a liquid product can be trapped, a pressure-relief valve must be provided to prevent excessive pressure build-up.

(iv) The main isolation valves on a MEGC must be clearly marked to indicate their directions of closure. All shutoff valves must close by a clockwise motion of the handwheel.

(v) Each shut-off valve or other means of closure must be designed and constructed to withstand a pressure equal to or greater than 1.5 times the test pressure of the MEGC.

(vi) All shut-off valves with screwed spindles must close by a clockwise motion of the handwheel. For other shut-off valves, the open and closed positions and the direction of closure must be clearly shown.

(vii) All shut-off valves must be designed and positioned to prevent unintentional opening.

(viii) Ductile metals must be used in the construction of valves or accessories.

(4) The piping must be designed, constructed and installed to avoid damage due to expansion and contraction, mechanical shock and vibration. Joints in tubing must be brazed or have an equally strong metal union. The melting point of brazing materials must be no lower than 525 °C (977 °F). The rated pressure of the service equipment and of the manifold must be not less than two-thirds of the test pressure of the pressure receptacles.

(f) *Pressure relief devices.* Each pressure receptacle must be equipped with one or more pressure relief devices as

specified in § 173.301(f) of this subchapter. When pressure relief devices are installed, each pressure receptacle or group of pressure receptacles of a MEGC that can be isolated must be equipped with one or more pressure relief devices. Pressure relief devices must be of a type that will resist dynamic forces including liquid surge and must be designed to prevent the entry of foreign matter, the leakage of gas and the development of any dangerous excess pressure.

(1) The size of the pressure relief devices: CGA S-1.1 (IBR, see § 171.7 of this subchapter) must be used to determine the relief capacity of individual pressure receptacles.

(2) Connections to pressure-relief devices: Connections to pressure relief devices must be of sufficient size to enable the required discharge to pass unrestricted to the pressure relief device. A shut-off valve installed between the pressure receptacle and the pressure relief device is prohibited, except where duplicate devices are provided for maintenance or other reasons, and the shut-off valves serving the devices actually in use are locked open, or the shut-off valves are interlocked so that at least one of the duplicate devices is always operable and capable of meeting the requirements of paragraph (f)(1) of this section. No obstruction is permitted in an opening leading to or leaving from a vent or pressure-relief device that might restrict or cut-off the flow from the pressure receptacle to that device. The opening through all piping and fittings must have at least the same flow area as the inlet of the pressure relief device to which it is connected. The nominal size of the discharge piping must be at least as large as that of the pressure relief device.

(3) Location of pressure-relief devices: For liquefied gases, each pressure relief device must, under maximum filling conditions, be in communication with the vapor space of the pressure receptacles. The devices, when installed, must be arranged to ensure the escaping vapor is discharged upwards and unrestrictedly to prevent impingement of escaping gas or liquid upon the MEGC, its pressure receptacles or personnel. For flammable, pyrophoric and oxidizing gases, the es-

caping gas must be directed away from the pressure receptacle in such a manner that it cannot impinge upon the other pressure receptacles. Heat resistant protective devices that deflect the flow of gas are permissible provided the required pressure relief device capacity is not reduced. Arrangements must be made to prevent access to the pressure relief devices by unauthorized persons and to protect the devices from damage caused by rollover.

(g) *Gauging devices.* When a MEGC is intended to be filled by mass, it must be equipped with one or more gauging devices. Glass level-gauges and gauges made of other fragile material are prohibited.

(h) *MEGC supports, frameworks, lifting and tie-down attachments.* (1) MEGCs must be designed and constructed with a support structure to provide a secure base during transport. MEGCs must be protected against damage to the pressure receptacles and service equipment resulting from lateral and longitudinal impact and overturning. The forces specified in paragraph (d)(8) of this section, and the safety factor specified in paragraph (d)(10) of this section must be considered in this aspect of the design. Skids, frameworks, cradles or other similar structures are acceptable. If the pressure receptacles and service equipment are so constructed as to withstand impact and overturning, additional protective support structure is not required (see paragraph (h)(4) of this section).

(2) The combined stresses caused by pressure receptacle mountings (e.g. cradles, frameworks, etc.) and MEGC lifting and tie-down attachments must not cause excessive stress in any pressure receptacle. Permanent lifting and tie-down attachments must be equipped to all MEGCs. Any welding of mountings or attachments onto the pressure receptacles is prohibited.

(3) The effects of environmental corrosion must be taken into account in the design of supports and frameworks.

(4) When MEGCs are not protected during transport as specified in paragraph (h)(1) of this section, the pressure receptacles and service equipment must be protected against damage resulting from lateral or longitudinal impact or overturning. External fittings



## § 178.75

## 49 CFR Ch. I (10–1–08 Edition)

must be protected against release of the pressure receptacles' contents upon impact or overturning of the MEGC on its fittings. Particular attention must be paid to the protection of the manifold. Examples of protection include:

- (i) Protection against lateral impact, which may consist of longitudinal bars;
- (ii) Protection against overturning, which may consist of reinforcement rings or bars fixed across the frame;
- (iii) Protection against rear impact, which may consist of a bumper or frame;
- (iv) Protection of the pressure receptacles and service equipment against damage from impact or overturning by use of an ISO frame according to the relevant provisions of ISO 1496-3. (IBR, see § 171.7 of this subchapter).

(i) *Initial inspection and test.* The pressure receptacles and items of equipment of each MEGC must be inspected and tested before being put into service for the first time (initial inspection and test). This initial inspection and test of an MEGC must include the following:

- (1) A check of the design characteristics.
- (2) An external examination of the MEGC and its fittings, taking into account the hazardous materials to be transported.
- (3) A pressure test performed at the test pressures specified in § 173.304b(b)(1) and (2) of this subchapter. The pressure test of the manifold may be performed as a hydraulic test or by using another liquid or gas. A leakproofness test and a test of the satisfactory operation of all service equipment must also be performed before the MEGC is placed into service. When the pressure receptacles and their fittings have been pressure-tested separately, they must be subjected to a leakproof test after assembly.


(4) An MEGC that meets the definition of "container" in the CSC (see 49 CFR 450.3(a)(2)) must be subjected to an impact test using a prototype representing each design type. The prototype MEGC must be shown to be capable of absorbing the forces resulting from an impact not less than 4 times (4 g) the MPGM of the fully loaded MEGC, at a duration typical of the mechanical shocks experienced in rail

transport. A listing of acceptable methods for performing the impact test is provided in the UN Recommendations (IBR, see § 171.7 of this subchapter).

(j) *Marking.* (1) Each MEGC must be equipped with a corrosion resistant metal plate permanently attached to the MEGC in a conspicuous place readily accessible for inspection. The pressure receptacles must be marked according to this section. Affixing the metal plate to a pressure receptacle is prohibited. At a minimum, the following information must be marked on the plate by stamping or by any other equivalent method:

Country of manufacture

UN



Approval Country

Approval Number

Alternate Arrangements (see § 178.75(b))

MEGC Manufacturer's name or mark

MEGC's serial number

Approval agency (Authorized body for the design approval)

Year of manufacture

Test pressure: \_\_\_\_\_ bar gauge

Design temperature range \_\_\_\_\_ °C to \_\_\_\_\_ °C

Number of pressure receptacles \_\_\_\_\_

Total water capacity \_\_\_\_\_ liters

Initial pressure test date and identification of the Approval Agency

Date and type of most recent periodic tests

Year \_\_\_\_\_ Month \_\_\_\_\_ Type \_\_\_\_\_

(e.g. 2004-05, AE/UE, where "AE" represents acoustic emission and "UE" represents ultrasonic examination)

**Pipeline and Hazardous Materials Safety Admin., DOT Pt. 178, Subpt. C, App. A**

Stamp of the approval agency who performed or witnessed the most recent test

(2) The following information must be marked on a metal plate firmly secured to the MEGC:

Name of the operator

Maximum permissible load mass \_\_\_\_\_ kg

Working pressure at 15 °C: \_\_\_\_\_ bar gauge


Maximum permissible gross mass (MPGM) \_\_\_\_\_ kg

Unladen (tare) mass \_\_\_\_\_ kg

[71 FR 33892, June 12, 2006, as amended at 73 FR 4719, Jan. 28, 2008]


**APPENDIX A TO SUBPART C OF PART 178—ILLUSTRATIONS: CYLINDER TENSILE SAMPLE**

The following figures illustrate the recommended locations for test specimens taken from welded cylinders:




THIS FIGURE ILLUSTRATES THE PROPER TENSILE LOCATION FOR A 3 PIECE CYLINDER WITH THE HEADS HAVING STRAIGHT SIDEWALL.

FIGURE #1




THIS FIGURE ILLUSTRATES THE PROPER TENSILE LOCATION FOR A 2 PIECE CYLINDER WITH THE HEADS HAVING STRAIGHT SIDEWALLS.

FIGURE #2





THIS FIGURE ILLUSTRATES THE PROPER TENSILE LOCATION FOR A 2 PIECE CYLINDER THAT HAVE DEEP DRAWN HEADS.

FIGURE #3




THIS FIGURE ILLUSTRATES THE PROPER TENSILE LOCATION FOR A 2 PIECE CYLINDER THAT HAVE DEEP DRAWN HEADS.


FIGURE #4



PARENT MATERIAL TEST  
SAMPLE 1 & 3



WELD TENSILE TEST  
SAMPLE 4



WELD BEND TEST  
SAMPLE 2

THIS FIGURE ILLUSTRATES THE PROPER TENSILE  
LOCATION FOR A 2 PIECE CYLINDER.

FIGURE #5

[67 FR 51654, Aug. 8, 2002]

**Subparts D-G [Reserved]****Subpart H—Specifications for Portable Tanks**

SOURCE: 29 FR 18972, Dec. 29, 1964, unless otherwise noted. Redesignated at 32 FR 5606, Apr. 5, 1967.

**§§ 178.251–178.253-5 [Reserved]****§ 178.255 Specification 60; steel portable tanks.****§ 178.255-1 General requirements.**

(a) Tanks must be of fusion welded construction, cylindrical in shape with seamless heads concave to the pressure. Tank shells may be of seamless construction.

(b) Tanks must be designed, constructed, certified, and stamped in accordance with Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter).

(c) Tanks including all permanent attachments must be postweld heat treated as a unit.

(d) Requirements concerning types of valves, retesting, and qualification of portable tanks contained in §§ 173.32 and 173.315 of this chapter must be observed.

[29 FR 18972, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-7, 34 FR 18250, Nov. 14, 1969; 68 FR 75750, Dec. 31, 2003]

**§ 178.255-2 Material.**

(a) Material used in the tank must be steel of good weldable quality and conform with the requirements in Sections V, VIII, and IX of the ASME Code (IBR, see § 171.7 of this subchapter).

(b) The minimum thickness of metal, exclusive of lining material, for shell and heads of tanks shall be as follows:

| Tank capacity                     | Minimum thickness (inch) |
|-----------------------------------|--------------------------|
| Not more than 1,200 gallons ..... | ¼                        |
| Over 1,200 to 1,800 gallons ..... | 5/16                     |
| Over 1,800 gallons .....          | ¾                        |

[29 FR 18972, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-7, 34 FR 18250, Nov. 14, 1969; 68 FR 75750, Dec. 31, 2003]

**§ 178.255-3 Expansion domes.**

(a) Expansion domes, if applied, must have a minimum capacity of one percent of the combined capacity of the tank and dome.

(b) [Reserved]

**§ 178.255-4 Closures for manholes and domes.**

(a) The manhole cover shall be designed to provide a secure closure of the manhole. All covers, not hinged to the tanks, shall be attached to the outside of the dome by at least ¼ inch chain or its equivalent. Closures shall be made tight against leakage of vapor and liquid by use of gaskets of suitable material.

(b) [Reserved]

**§ 178.255-5 Bottom discharge outlets.**

(a) Bottom discharge outlets prohibited, except on tanks used for shipments of sludge acid and alkaline corrosive liquids.

(b) If installed, bottom outlets or bottom washout chambers shall be of metal not subject to rapid deterioration by the lading, and each shall be provided with a valve or plug at its upper end and liquid-tight closure at its lower end. Each valve or plug shall be designed to insure against unseating due to stresses or shocks incident to transportation. Bottom outlets shall be adequately protected against handling damage and outlet equipment must not extend to within less than one inch of the bottom bearing surface of the skids or tank mounting.

[29 FR 18972, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, as amended by Amdt. 178-104, 59 FR 49135, Sept. 26, 1994]

**§ 178.255-6 Loading and unloading accessories.**

(a) When installed, gauging, loading and air inlet devices, including their valves, shall be provided with adequate means for their secure closure; and means shall also be provided for the closing of pipe connections of valves.

(b) Interior heater coils, if installed, must be of extra heavy pipe and so constructed that breaking off of exterior connections will not cause leakage of tanks.



**§ 178.255-7 Protection of valves and accessories.**

(a) All valves, fittings, accessories, safety devices, gauging devices, and the like shall be adequately protected against mechanical damage by a housing closed with a cover plate.

(b) Protective housing shall comply with the requirements under which the tanks are fabricated with respect to design and construction, and shall be designed with a minimum factor of safety of four to withstand loadings in any direction equal to two times the weight of the tank and attachments when filled with water.

**§ 178.255-8 Safety devices.**

(a) See § 173.315(i) of this subchapter.

(b) [Reserved]

[Amdt. 178-83, 50 FR 11066, Mar. 19, 1985]

**§ 178.255-9 Compartments.**

(a) When the interior of the tank is divided into compartments, each compartment shall be designed, constructed and tested as a separate tank. Thickness of shell and compartment heads shall be determined on the basis of total tank capacity.

(b) [Reserved]

**§ 178.255-10 Lining.**

(a) If a lining is required, the material used for lining the tank shall be homogeneous, nonporous, imperforate when applied, not less elastic than the metal of the tank proper. It shall be of substantially uniform thickness, not less than  $\frac{1}{32}$  inch thick if metallic, and not less than  $\frac{1}{16}$  inch thick if non-metallic, and shall be directly bonded or attached by other equally satisfactory means. Rubber lining shall be not less than  $\frac{3}{16}$  inch thick. Joints and seams in the lining shall be made by fusing the material together or by other equally satisfactory means. The interior of the tank shall be free from scale, oxidation, moisture and all foreign matter during the lining operation.

(b) [Reserved]

**§ 178.255-11 Tank mountings.**

(a) Tanks shall be designed and fabricated with mountings to provide a secure base in transit. "Skids" or similar

devices shall be deemed to comply with this requirement.

(b) All tank mountings such as skids, fastenings, brackets, cradles, lifting lugs, etc., intended to carry loadings shall be permanently secured to tanks in accordance with the requirements under which the tanks are fabricated, and shall be designed with a factor of safety of four, and built to withstand loadings in any direction equal to two times the weight of the tanks and attachments when filled to the maximum permissible loaded weight.

(c) Lifting lugs or side hold-down lugs shall be provided on the tank mountings in a manner suitable for attaching lifting gear and hold-down devices. Lifting lugs and hold-down lugs welded directly to the tank shall be of the pad-eye type. Doubling plates welded to the tank and located at the points of support shall be deemed to comply with this requirement.

(d) All tank mountings shall be so designed as to prevent the concentration of excessive loads on the tank shell.

**§ 178.255-12 Pressure test.**

(a) Each completed portable tank prior to application of lining shall be tested before being put into transportation service by completely filling the tank with water or other liquid having a similar viscosity, the temperature of which shall not exceed 100 °F during the test, and applying a pressure of 60 psig. The tank shall be capable of holding the prescribed pressure for at least 10 minutes without leakage, evidence of impending failure, or failure. All closures shall be in place while the test is made and the pressure shall be gauged at the top of the tank. Safety devices and/or vents shall be plugged during this test.

(b) [Reserved]

[29 FR 18972, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, as amended by Amdt. 178-104, 59 FR 49135, Sept. 26, 1994]

**§ 178.255-13 Repair of tanks.**

(a) Tanks failing to meet the test may be repaired and retested, provided that repairs are made in complete compliance with the requirements of this specification.

(b) [Reserved]

**§ 178.255-14 Marking.**

(a) In addition to markings required by Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), every tank shall bear permanent marks at least 1/8-inch high stamped into the metal near the center of one of the tank heads or stamped into a plate permanently attached to the tank by means of brazing or welding or other suitable means as follows:

Manufacturer's name \_\_\_\_\_ Serial No. \_\_\_\_\_  
 DOT specification \_\_\_\_\_  
 Nominal capacity \_\_\_\_\_ (gallons)  
 Tare weight \_\_\_\_\_ (pounds)  
 Date of manufacture \_\_\_\_\_

(b) [Reserved]

[29 FR 18972, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-67, 46 FR 49906, Oct. 8, 1981; 68 FR 75750, Dec. 31, 2003]

**§ 178.255-15 Report.**

(a) A copy of the manufacturer's data report required by Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter) under which the tank is fabricated must be furnished to the owner for each new tank.

Place \_\_\_\_\_  
 Date \_\_\_\_\_  
*Portable tank*  
 Manufactured for \_\_\_\_\_ Company  
 Location \_\_\_\_\_  
 Manufactured by \_\_\_\_\_ Company  
 Location \_\_\_\_\_  
 Consigned to \_\_\_\_\_ Company  
 Location \_\_\_\_\_  
 Size \_\_\_\_\_ feet outside diameter by \_\_\_\_\_ long.

Marks on tank as prescribed by § 178.255-14 of this specification are as follows:

Manufacturer's name \_\_\_\_\_  
 Serial number \_\_\_\_\_  
 Owner's serial number \_\_\_\_\_  
 DOT specification \_\_\_\_\_  
 ASME Code Symbol (par U-201) \_\_\_\_\_  
 Date of manufacture \_\_\_\_\_  
 Nominal capacity \_\_\_\_\_ gallons.

It is hereby certified that this tank is in complete compliance with the requirements of DOT Specification No. 60.

(Signed) \_\_\_\_\_  
 Manufacturer or owner

(b) [Reserved]

[29 FR 18972, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-83, 50 FR 11066, Mar. 19, 1985; 68 FR 75750, Dec. 31, 2003]

**§ 178.273 Approval of Specification UN portable tanks.**

(a) *Application for approval.* (1) An owner or manufacturer of a portable tank shall apply for approval to a designated approval agency authorized to approve the portable tank in accordance with the procedures in subpart E, part 107 of this subchapter.

(2) Each application for approval must contain the following information:

(i) Two complete copies of all engineering drawings, calculations, and test data necessary to ensure that the design meets the relevant specification.

(ii) The manufacturer's serial number that will be assigned to each portable tank.

(iii) A statement as to whether the design type has been examined by any approval agency previously and judged unacceptable. Affirmative statements must be documented with the name of the approval agency, reason for non-acceptance, and the nature of modifications made to the design type.

(b) *Action by approval agency.* The approval agency must perform the following activities:

(1) Review the application for approval to determine whether it is complete and conforms with the requirements of paragraph (a) of this section. If an application is incomplete, it will be returned to the applicant with an explanation as to why the application is incomplete.

(2) Review all drawings and calculations to ensure that the design is in compliance with all requirements of the relevant specification. If the application is approved, one set of the approved drawings, calculations, and test data shall be returned to the applicant. The second (inspector's copy) set of approved drawings, calculations, and test data shall be retained by the approval agency. Maintain drawings and approval records for as long as the portable tank remains in service. The drawings and records must be provided to the Department of Transportation (DOT) upon request.

(3) Witness all tests required for the approval of the portable tank specified in this section and part 180, subpart G of this subchapter.

(4) Ensure, through appropriate inspection that each portable tank is fabricated in all respects in conformance with the approved drawings, calculations, and test data.

(5) Determine and ensure that the portable tank is suitable for its intended use and that it conforms to the requirements of this subchapter.

(6) For UN portable tanks intended for non-refrigerated and refrigerated liquefied gases and Division 6.1 liquids which meet the inhalation toxicity criteria (Zone A or B) as defined in § 173.132 of this subchapter, or that are designated as toxic by inhalation materials in the § 172.101 Table of this subchapter, the approval agency must ensure that:

(i) The portable tank has been designed, constructed, certified, and stamped in accordance with the requirements in Division 1 of Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter). Other design codes may be used if approved by the Associate Administrator (see § 178.274(b)(1));

(ii) All applicable provisions of the design and construction have been met to the satisfaction of the designated approval agency in accordance with the rules established in the ASME Code and that the portable tank meets the requirements of the ASME Code and all the applicable requirements specified in this subchapter;

(iii) The inspector has carried out all the inspections specified by the rules established in the ASME Code; and

(iv) The portable tank is marked with a U stamp code symbol under the authority of the authorized independent inspector.

(7) Upon successful completion of all requirements of this subpart, the approval agency must:

(i) Apply its name, identifying mark or identifying number, and the date upon which the approval was issued, to the metal identification marking plate attached to the portable tank. Any approvals for UN portable tanks authorizing design or construction alternatives (Alternate Arrangements) approved by the Associate Administrator (see § 178.274(a)(2)) must be indicated on the plate as specified in § 178.274(i).

(ii) Issue an approval certificate for each portable tank or, in the case of a

series of identical portable tanks manufactured to a single design type, for each series of portable tanks. The approval certificate must include all the information required to be displayed on the metal identification plate required by § 178.274(i). The approval certificate must certify that the approval agency designated to approve the portable tank has approved the portable tank in accordance with the procedures in subpart E of part 107 of this subchapter and that the portable tank is suitable for its intended purpose and meets the requirements of this subchapter. When a series of portable tanks is manufactured without change in the design type, the certificate may be valid for the entire series of portable tanks representing a single design type. For UN portable tanks, the certificate must refer to the prototype test report, the hazardous material or group of hazardous materials allowed to be transported, the materials of construction of the shell and lining (when applicable) and an approval number. The approval number must consist of the distinguishing sign or mark of the country (“USA” for the United States of America) where the approval was granted and a registration number.

(iii) Retain a copy of each approval certificate.

(8) For UN portable tanks, the approval certificate must also include the following:

(i) The results of the applicable framework and rail impact test specified in part 180, subpart G, of this subchapter; and

(ii) The results of the initial inspection and test in § 178.274(j).

(9) The approval agency shall be independent from the manufacturer. The approval agency and the authorized inspector may be the same entity.

(c) *Manufacturers’ responsibilities.* The manufacturer is responsible for compliance with the applicable specifications for the design and construction of portable tanks. In addition to responsibility for compliance, manufacturers are responsible for ensuring that the contracted approval agency and authorized inspector, if applicable, are qualified, reputable and competent. The manufacturer of a portable tank shall—

(1) Comply with all the applicable requirements of the ASME Code and of this subpart including, but not limited to, ensuring that the quality control, design calculations and required tests are performed and that all aspects of the portable tank meet the applicable requirements.

(2) Obtain and use a designated approval agency, if applicable, and obtain and use a DOT-designated approval agency to approve the design, construction and certification of the portable tank.

(3) Provide a statement in the manufacturers' data report certifying that each portable tank that is manufactured complies with the relevant specification and all the applicable requirements of this subchapter.

(4) Maintain records of the qualification of portable tanks for at least 5 years and provide copies to the approval agency, the owner or lessee of the tank. Upon request, provide these records to a representative of DOT.

(d) *Denial of application for approval.* If an approval agency finds that a portable tank cannot be approved for any reason, it shall notify the applicant in writing and shall provide the applicant with the reasons for which the approval is denied. A copy of the notification letter shall be provided to the Associate Administrator. An applicant aggrieved by a decision of an approval agency may appeal the decision in writing, within 90 days of receipt, to the Associate Administrator.

(e) *Modifications to approved portable tanks.* (1) Prior to modification of any UN portable tank which may affect conformance and the safe use of the portable tank, which may involve a change to the design type or which may affect its ability to retain hazardous material in transportation, the person desiring to make such modification shall inform the approval agency that issued the initial approval of the portable tank (or if unavailable, another approval agency) of the nature of the modification and request approval of the modification. The person desiring to modify the tank must supply the approval agency with three sets of all revised drawings, calculations, and test data relative to the intended modification.

(2) A statement as to whether the intended modification has been examined and determined to be unacceptable by any approval agency. The written statement must include the name of the approving agency, the reason for nonacceptance, and the nature of changes made to the modification since its original rejection.

(3) The approval agency shall review the request for modification, and if it is determined that the proposed modification is in full compliance with the relevant DOT specification, including a UN portable tank, the request shall be approved and the approval agency shall perform the following activities:

(i) Return one set of the approved revised drawings, calculations, and test data to the applicant. The second and third sets of the approved revised drawings, calculations, and data shall be retained by the approval agency as required in §107.404(a)(3) of this subchapter.

(ii) Ensure through appropriate inspection that all modifications conform to the revised drawings, calculations, and test data.

(iii) Determine the extent to which retesting of the modified tank is necessary based on the nature of the proposed modification, and ensure that all required retests are satisfactorily performed.

(iv) If modification to an approved tank alters any information on the approval certificate, issue a new approval certificate for the modified tank and ensure that any necessary changes are made to the metal identification plate. A copy of each newly issued approval certificate shall be retained by the approval agency and by the owner of each portable tank.

(4) If the approval agency determines that the proposed modification is not in compliance with the relevant DOT specification, the approval agency shall deny the request in accordance with paragraph (d) of this section.

(f) *Termination of Approval Certificate.* (1) The Associate Administrator may terminate an approval issued under this section if he determines that—

(i) Information upon which the approval was based is fraudulent or substantially erroneous; or

- (ii) Termination of the approval is necessary to adequately protect against risks to life and property; or
- (iii) The approval was not issued by the approval agency in good faith; or
- (iv) The portable tank does not meet the specification.

(2) Before an approval is terminated, the Associate Administrator gives the interested party(ies):

- (i) Written notice of the facts or conduct believed to warrant the termination;
- (ii) Opportunity to submit oral and written evidence; and
- (iii) Opportunity to demonstrate or achieve compliance with the applicable requirements.

(3) If the Associate Administrator determines that a certificate of approval must be terminated to preclude a significant and imminent adverse affect on public safety, he may terminate the certificate immediately. In such circumstances, the opportunities of paragraphs (f)(2) (ii) and (iii) of this section need not be provided prior to termination of the approval, but shall be provided as soon as practicable thereafter.

[66 FR 33439, June 21, 2001, as amended at 67 FR 61016, Sept. 27, 2002; 68 FR 75748, 75751, Dec. 31, 2003; 72 FR 55695, Oct. 1, 2007]

**§ 178.274 Specifications for UN portable tanks.**

(a) *General.* (1) Each UN portable tank must meet the requirements of this section. In addition to the requirements of this section, requirements specific to UN portable tanks used for liquid and solid hazardous materials, non-refrigerated liquefied gases and refrigerated liquefied gases are provided in §§ 178.275, 178.276 and 178.277, respectively. Requirements for approval, maintenance, inspection, testing and use are provided in § 178.273 and part 180, subpart G, of this subchapter. Any portable tank which meets the definition of a “container” within the terms of the International Convention for Safe Containers (CSC) must meet the requirements of the CSC as amended and 49 CFR parts 450 through 453 and must have a CSC safety approval plate.

(2) In recognition of scientific and technological advances, the technical requirements applicable to UN portable

tanks may be varied if approved by the Associate Administrator and the portable tank is shown to provide a level of safety equal to or exceeding the requirements of this subchapter. Portable tanks approved to alternative technical requirements must be marked “Alternative Arrangement” as specified in paragraph (i) of this section.

(3) *Definitions.* The following definitions apply for the purposes of design and construction of UN portable tanks under this subpart:

*Alternate Arrangement portable tank* means a UN portable tank that has been approved to alternative technical requirements or testing methods other than those specified for UN portable tanks in part 178 or part 180 of this subchapter.

*Approval agency* means the designated approval agency authorized to approve the portable tank in accordance with the procedures in subpart E of part 107 of this subchapter.

*Design pressure* is defined according to the hazardous materials intended to be transported in the portable tank. See §§ 178.275, 178.276 and 178.277, as applicable.

*Design type* means a portable tank or series of portable tanks made of materials of the same material specifications and thicknesses, manufactured by a single manufacturer, using the same fabrication techniques (for example, welding procedures) and made with equivalent structural equipment, closures, and service equipment.

*Fine grain steel* means steel that has a ferritic grain size of 6 or finer when determined in accordance with ASTM E 112–96 (IBR, see § 171.7 of this subchapter).

*Fusible element* means a non-reclosing pressure relief device that is thermally activated and that provides protection against excessive pressure buildup in the portable tank developed by exposure to heat, such as from a fire (see § 178.275(g)).

*Jacket* means the outer insulation cover or cladding which may be part of the insulation system.

*Leakage test* means a test using gas to subject the shell and its service equipment to an internal pressure.

*Maximum allowable working pressure (MAWP)* is defined according to the hazardous materials intended to be transported in the portable tank. See §§ 178.275, 178.276 and 178.277, as applicable.

*Maximum permissible gross mass (MPGM)* means the sum of the tare mass of the portable tank and the heaviest hazardous material authorized for transportation.

*Mild steel* means a steel with a guaranteed minimum tensile strength of 360 N/mm<sup>2</sup> to 440 N/mm<sup>2</sup> and a guaranteed minimum elongation at fracture as specified in paragraph (c)(10) of this section.

*Offshore portable tank* means a portable tank specially designed for repeated use in the transportation of hazardous materials to, from and between offshore facilities. An offshore portable tank is designed and constructed in accordance with the Guidelines for the Approval of Containers Handled in Open Seas specified in the IMDG Code (IBR, see § 171.7 of this subchapter).

*Reference steel* means a steel with a tensile strength of 370 N/mm<sup>2</sup> and an elongation at fracture of 27%.

*Service equipment* means measuring instruments and filling, discharge, venting, safety, heating, cooling and insulating devices.

*Shell* means the part of the portable tank which retains the hazardous materials intended for transportation, including openings and closures, but does not include service equipment or external structural equipment.

*Structural equipment* means the reinforcing, fastening, protective and stabilizing members external to the shell.

*Test pressure* means the maximum gauge pressure at the top of the shell during the hydraulic pressure test equal to not less than 1.5 times the design pressure for liquids and 1.3 for liquefied compressed gases and refrigerated liquefied gases. In some instances a pneumatic test is authorized as an alternative to the hydraulic test. The minimum test pressures for portable tanks intended for specific liquid and solid hazardous materials are specified in the applicable portable tank T codes (such as T1–T23) assigned to these hazardous materials in the § 172.101 Table of this subchapter.

(b) *General design and construction requirements.* (1) The design temperature range for the shell must be –40 °C to 50 °C (–40 °F to 122 °F) for hazardous materials transported under normal conditions of transportation, except for portable tanks used for refrigerated liquefied gases where the minimum design temperature must not be higher than the lowest (coldest) temperature (for example, service temperature) of the contents during filling, discharge or transportation. For hazardous materials handled under elevated temperature conditions, the design temperature must not be less than the maximum temperature of the hazardous material during filling, discharge or transportation. More severe design temperatures must be considered for portable tanks subjected to severe climatic conditions (for example, portable tanks transported in arctic regions). Shells must be designed and constructed in accordance with the requirements in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), except as limited or modified in this subchapter. For portable tanks used for liquid or solid hazardous materials, a design code other than the ASME Code may be used if approved by the Associate Administrator. Portable tanks must have an ASME certification and U stamp when used for Hazard Zone A or B toxic by inhalation liquids, or when used for non-refrigerated or refrigerated liquefied compressed gases. Shells must be made of metallic materials suitable for forming. Non-metallic materials may be used for the attachments and supports between the shell and jacket, provided their material properties at the minimum and maximum design temperatures are proven to be sufficient. For welded shells, only a material whose weldability has been fully demonstrated may be used. Welds must be of high quality and conform to a level of integrity at least equivalent to the welding requirements specified in Section VIII of the ASME Code for the welding of pressure vessels. When the manufacturing process or the materials make it necessary, the shells must be suitably heat-treated to guarantee adequate toughness in the weld and in the heat-affected zones. In choosing the

material, the design temperature range must be taken into account with respect to risk of brittle fracture, stress corrosion cracking, resistance to impact, and suitability for the hazardous materials intended for transportation in the portable tank. When fine grain steel is used, the guaranteed value of the yield strength must be not more than 460 N/mm<sup>2</sup> and the guaranteed value of the upper limit of the tensile strength must be not more than 725 N/mm<sup>2</sup> according to the material specification. Aluminum may not be used as a construction material for the shells of portable tanks intended for the transport of non-refrigerated liquefied gases. For portable tanks intended for the transport of liquid or solid hazardous materials, aluminum may only be used as a construction material for portable tank shells if approved by the Associate Administrator. Portable tank materials must be suitable for the external environment where they will be transported, taking into account the determined design temperature range. Portable tanks shall be designed to withstand, without loss of contents, at least the internal pressure due to the contents and the static, dynamic and thermal loads during normal conditions of handling and transportation. The design must take into account the effects of fatigue, caused by repeated application of these loads through the expected life of the portable tank.

(2) Portable tank shells, fittings, and pipework shall be constructed from materials that are:

(i) Compatible with the hazardous materials intended to be transported; or

(ii) Properly passivated or neutralized by chemical reaction, if applicable; or

(iii) For portable tanks used for liquid and solid materials, lined with corrosion-resistant material directly bonded to the shell or attached by equivalent means.

(3) Gaskets and seals shall be made of materials that are compatible with the hazardous materials intended to be transported.

(4) When shells are lined, the lining must be compatible with the hazardous materials intended to be transported, homogeneous, non-porous, free from

perforations, sufficiently elastic and compatible with the thermal expansion characteristics of the shell. The lining of every shell, shell fittings and piping must be continuous and must extend around the face of any flange. Where external fittings are welded to the tank, the lining must be continuous through the fitting and around the face of external flanges. Joints and seams in the lining must be made by fusing the material together or by other equally effective means.

(5) Contact between dissimilar metals which could result in damage by galvanic action must be prevented by appropriate measures.

(6) The construction materials of the portable tank, including any devices, gaskets, linings and accessories, must not adversely affect or react with the hazardous materials intended to be transported in the portable tank.

(7) Portable tanks must be designed and constructed with supports that provide a secure base during transportation and with suitable lifting and tie-down attachments.

(c) *Design criteria.* (1) Portable tanks and their fastenings must, under the maximum permissible loads and maximum permissible working pressures, be capable of absorbing the following separately applied static forces (for calculation purposes, acceleration due to gravity (g) = 9.81m/s<sup>2</sup>):

(i) In the direction of travel: 2g (twice the MPGM multiplied by the acceleration due to gravity);

(ii) Horizontally at right angles to the direction of travel: 1g (the MPGM multiplied by the acceleration due to gravity);

(iii) Vertically upwards: 1g (the MPGM multiplied by the acceleration due to gravity); and

(iv) Vertically downwards: 2g (twice the MPGM multiplied by the acceleration due to gravity).

(2) Under each of the forces specified in paragraph (c)(1) of this section, the safety factor must be as follows:

(i) For metals having a clearly defined yield point, a design margin of 1.5 in relation to the guaranteed yield strength; or

(ii) For metals with no clearly defined yield point, a design margin of 1.5 in relation to the guaranteed 0.2%

proof strength and, for austenitic steels, the 1% proof strength.

(3) The values of yield strength or proof strength must be the values according to recognized material standards. When austenitic steels are used, the specified minimum values of yield strength or proof strength according to the material standards may be increased by up to 15% for portable tanks used for liquid and solid hazardous materials, other than toxic by inhalation liquids meeting the criteria of Hazard Zone A or Hazard Zone B (see §173.133 of this subchapter), when these greater values are attested in the material inspection certificate.

(4) Portable tanks must be capable of being electrically grounded to prevent dangerous electrostatic discharge when they are used for Class 2 flammable gases or Class 3 flammable liquids, including elevated temperature materials transported at or above their flash point.

(5) For shells of portable tanks used for liquefied compressed gases, the shell must consist of a circular cross section. Shells must be of a design capable of being stress-analyzed mathematically or experimentally by resistance strain gauges as specified in UG-101 of Section VIII of the ASME Code, or other methods approved by the Associate Administrator.

(6) Shells must be designed and constructed to withstand a hydraulic test pressure of not less than 1.5 times the design pressure for portable tanks used for liquids and 1.3 times the design pressure for portable tanks used for liquefied compressed gases. Specific requirements are provided for each hazardous material in the applicable T Code or portable tank special provision specified in the §172.101 Table of this subchapter. The minimum shell thickness requirements must also be taken into account.

(7) For metals exhibiting a clearly defined yield point or characterized by a guaranteed proof strength (0.2% proof strength, generally, or 1% proof strength for austenitic steels), the primary membrane stress  $\sigma$  (sigma) in the shell must not exceed 0.75 Re or 0.50 Rm, whichever is lower, at the test pressure, where:

Re = yield strength in N/mm<sup>2</sup>, or 0.2% proof strength or, for austenitic steels, 1% proof strength;

Rm = minimum tensile strength in N/mm<sup>2</sup>.

(8) The values of Re and Rm to be used must be the specified minimum values according to recognized material standards. When austenitic steels are used, the specified minimum values for Re and Rm according to the material standards may be increased by up to 15% when greater values are attested in the material inspection certificate.

(9) Steels which have a Re/Rm ratio of more than 0.85 are not allowed for the construction of welded shells. The values of Re and Rm to be used in determining this ratio must be the values specified in the material inspection certificate.

(10) Steels used in the construction of shells must have an elongation at fracture, in percentage, of not less than 10,000/Rm with an absolute minimum of 16% for fine grain steels and 20% for other steels.

(11) For the purpose of determining actual values for materials for sheet metal, the axis of the tensile test specimen must be at right angles (transversely) to the direction of rolling. The permanent elongation at fracture must be measured on test specimens of rectangular cross sections in accordance with ISO 6892 (IBR, see §171.7 of this subchapter), using a 50 mm gauge length.

(d) *Minimum shell thickness.* (1) The minimum shell thickness must be the greatest thickness of the following:

(i) the minimum thickness determined in accordance with the requirements of paragraphs (d)(2) through (d)(7) of this section;

(ii) the minimum thickness determined in accordance with Section VIII of the ASME Code or other approved pressure vessel code; or

(iii) the minimum thickness specified in the applicable T code or portable tank special provision indicated for each hazardous material in the §172.101 Table of this subchapter.

(2) Shells (cylindrical portions, heads and manhole covers) not more than 1.80 m in diameter may not be less than 5 mm thick in the reference steel or of



equivalent thickness in the metal to be used. Shells more than 1.80 m in diameter may not be less than 6 mm (0.2 inches) thick in the reference steel or of equivalent thickness in the metal to be used. For portable tanks used only for the transportation of powdered or granular solid hazardous materials of Packing Group II or III, the minimum thickness requirement may be reduced to 5 mm in the reference steel or of equivalent thickness in the metal to be used regardless of the shell diameter. For vacuum-insulated tanks, the aggregate thickness of the jacket and the shell must correspond to the minimum thickness prescribed in this paragraph, with the thickness of the shell itself not less than the minimum thickness prescribed in paragraph (d)(3) of this section.

(3) When additional protection against shell damage is provided in the case of portable tanks used for liquid and solid hazardous materials requiring test pressures less than 2.65 bar (265.0 kPa), subject to certain limitations specified in the UN Recommendations (IBR, see §171.7 of this subchapter), the Associate Administrator may approve a reduced minimum shell thickness.

(4) The cylindrical portions, heads and manhole covers of all shells must not be less than 3 mm (0.1 inch) thick regardless of the material of construction, except for portable tanks used for liquefied compressed gases where the cylindrical portions, ends (heads) and manhole covers of all shells must not be less than 4 mm (0.2 inch) thick regardless of the material of construction.

(5) When steel is used, that has characteristics other than that of reference steel, the equivalent thickness of the shell and heads must be determined according to the following formula:

$$e_1 = \frac{21.4e_0d_1}{1.8m \sqrt[3]{Rm_1 \times A_1}}$$

Where:

$e_1$  = required equivalent thickness (in mm) of the metal to be used;

$e_0$  = minimum thickness (in mm) of the reference steel specified in the applicable T code or portable tank special provision indicated for each material in the §172.101 Table of this subchapter;

$d_1$  = 1.8m, unless the formula is used to determine the equivalent minimum thickness for a portable tank shell that is required to have a minimum thickness of 8mm or 10mm according to the applicable T code indicated in the §172.101 Table of this subchapter. When reference steel thicknesses of 8mm or 10mm are specified,  $d_1$  is equal to the actual diameter of the shell but not less than 1.8m;

$Rm_1$  = guaranteed minimum tensile strength (in N/mm<sup>2</sup>) of the metal to be used;

$A_1$  = guaranteed minimum elongation at fracture (in %) of the metal to be used according to recognized material standards.

(6) The wall and all parts of the shell may not have a thickness less than that prescribed in paragraphs (d)(2), (d)(3) and (d)(4) of this section. This thickness must be exclusive of any corrosion allowance.

(7) There must be no sudden change of plate thickness at the attachment of the heads to the cylindrical portion of the shell.

(e) *Service equipment.* (1) Service equipment must be arranged so that it is protected against the risk of mechanical damage by external forces during handling and transportation. When the connections between the frame and the shell allow relative movement between the sub-assemblies, the equipment must be fastened to allow such movement without risk of damage to any working part. The external discharge fittings (pipe sockets, shut-off devices) and the internal stop-valve and its seating must be protected against mechanical damage by external forces (for example, by using shear sections). Each internal self-closing stop-valve must be protected by a shear section or sacrificial device located outboard of the valve. The shear section or sacrificial device must break at no more than 70% of the load that would cause failure of the internal self-closing stop valve. The filling and discharge devices (including flanges or threaded plugs) and any protective caps must be capable of being secured against unintended opening.

(2) Each filling or discharge opening of a portable tank must be clearly marked to indicate its function.

(3) Each stop-valve or other means of closure must be designed and constructed to a rated pressure not less than the MAWP of the shell taking

into account the temperatures expected during transport. All stop-valves with screwed spindles must close by a clockwise motion of the handwheel. For other stop-valves, the position (open and closed) and direction of closure must be clearly indicated. All stop-valves must be designed to prevent unintentional opening.

(4) Piping must be designed, constructed and installed to avoid the risk of damage due to thermal expansion and contraction, mechanical shock and vibration. All piping must be of a suitable metallic material. Welded pipe joints must be used wherever possible.

(5) Joints in copper tubing must be brazed or have an equally strong metal union. The melting point of brazing materials must be no lower than 525 °C (977 °F). The joints must not decrease the strength of the tubing, such as may happen when cutting threads. Brazed joints are not authorized for portable tanks intended for refrigerated liquefied gases.

(6) The burst pressure of all piping and pipe fittings must be greater than the highest of four times the MAWP of the shell or four times the pressure to which it may be subjected in service by the action of a pump or other device (except pressure relief devices).

(7) Ductile metals must be used in the construction of valves and accessories.

(f) *Pressure relief devices*—(1) *Marking of pressure relief devices*. Every pressure relief device must be clearly and permanently marked with the following:

(i) the pressure (in bar or kPa) or temperature for fusible elements (in °C) at which it is set to discharge;

(ii) the allowable tolerance at the discharge pressure for reclosing devices;

(iii) the reference temperature corresponding to the rated pressure for frangible discs;

(iv) the allowable temperature tolerance for fusible elements;

(v) The rated flow capacity of the spring loaded pressure relief devices, frangible disc or fusible elements in standard cubic meters of air per second (m<sup>3</sup>/s). For spring loaded pressure relief device the rated flow capacity shall be determined according to ISO 4126-1 (IBR, see §171.7 of this subchapter); and

(vi) when practicable, the device must show the manufacturer's name and product number.

(2) *Connections to pressure relief devices*. Connections to pressure relief devices must be of sufficient size to enable the required discharge to pass unrestricted to the safety device. No stop-valve may be installed between the shell and the pressure relief devices except where duplicate devices are provided for maintenance or other reasons and the stop-valves serving the devices actually in use are locked open or the stop-valves are interlocked so that at least one of the devices is always in use. There must be no obstruction in an opening leading to a vent or pressure relief device which might restrict or cut-off the flow from the shell to that device. Vents or pipes from the pressure relief device outlets, when used, must deliver the relieved vapor or liquid to the atmosphere in conditions of minimum back-pressure on the relieving devices.

(3) *Location of pressure relief devices*.

(i) Each pressure relief device inlet must be situated on top of the shell in a position as near the longitudinal and transverse center of the shell as reasonably practicable. All pressure relief device inlets must, under maximum filling conditions, be situated in the vapor space of the shell and the devices must be so arranged as to ensure that any escaping vapor is not restricted in any manner. For flammable hazardous materials, the escaping vapor must be directed away from the shell in such a manner that it cannot impinge upon the shell. For refrigerated liquefied gases, the escaping vapor must be directed away from the tank and in such a manner that it cannot impinge upon the tank. Protective devices which deflect the flow of vapor are permissible provided the required relief-device capacity is not reduced.

(ii) Provisions must be implemented to prevent unauthorized persons from access to the pressure relief devices and to protect the devices from damage caused by the portable tank overturning.

(g) *Gauging devices*. Unless a portable tank is intended to be filled by weight, it must be equipped with one or more gauging devices. Glass level-gauges and

gauges made of other fragile material, which are in direct communication with the contents of the tank are prohibited. A connection for a vacuum gauge must be provided in the jacket of a vacuum-insulated portable tank.

(h) *Portable tank supports, frameworks, lifting and tie-down attachments.* (1) Portable tanks must be designed and constructed with a support structure to provide a secure base during transport. The forces and safety factors specified in paragraphs (c)(1) and (c)(2) of this section, respectively, must be taken into account in this aspect of the design. Skids, frameworks, cradles or other similar structures are acceptable.

(2) The combined stresses caused by portable tank mountings (for example, cradles, framework, etc.) and portable tank lifting and tie-down attachments must not cause stress that would damage the shell in a manner that would compromise its lading retention capability. Permanent lifting and tie-down attachments must be fitted to all portable tanks. Preferably they should be fitted to the portable tank supports but may be secured to reinforcing plates located on the shell at the points of support. Each portable tank must be designed so that the center of gravity of the filled tank is approximately centered within the points of attachment for lifting devices.

(3) In the design of supports and frameworks, the effects of environmental corrosion must be taken into account.

(4) Forklift pockets must be capable of being closed off. The means of closing forklift pockets must be a permanent part of the framework or permanently attached to the framework. Single compartment portable tanks with a length less than 3.65 m (12 ft.) need not have forklift pockets that are capable of being closed off provided that:

(i) The shell, including all the fittings, are well protected from being hit by the forklift blades; and

(ii) The distance between forklift pockets (measured from the center of each pocket) is at least half of the maximum length of the portable tank.

(5) During transport, portable tanks must be adequately protected against damage to the shell, and service equip-

ment resulting from lateral and longitudinal impact and overturning, or the shell and service equipment must be constructed to withstand the forces resulting from impact or overturning. External fittings must be protected so as to preclude the release of the shell contents upon impact or overturning of the portable tank on its fittings. Examples of protection include:

(i) Protection against lateral impact which may consist of longitudinal bars protecting the shell on both sides at the level of the median line;

(ii) Protection of the portable tank against overturning which may consist of reinforcement rings or bars fixed across the frame;

(iii) Protection against rear impact which may consist of a bumper or frame;

(iv) Protection of the shell against damage from impact or overturning by use of an ISO frame in accordance with ISO 1496-3 (IBR, see § 171.7 of this subchapter); and

(v) Protection of the portable tank from impact or damage that may result from overturning by an insulation jacket.

(i) *Marking.* (1) Every portable tank must be fitted with a corrosion resistant metal plate permanently attached to the portable tank in a conspicuous place and readily accessible for inspection. When the plate cannot be permanently attached to the shell, the shell must be marked with at least the information required by Section VIII of the ASME Code. At a minimum, the following information must be marked on the plate by stamping or by any other equivalent method:

Country of manufacture  
U N  
Approval Country  
Approval Number  
Alternative Arrangements (see § 178.274(a)(2))  
“AA”  
Manufacturer’s name or mark  
Manufacturer’s serial number  
Approval Agency (Authorized body for the design approval)  
Owner’s registration number  
Year of manufacture  
Pressure vessel code to which the shell is designed  
Test pressure \_\_\_\_\_ bar gauge.  
MAWP \_\_\_\_\_ bar gauge.

External design pressure (not required for portable tanks used for refrigerated liquefied gases) \_\_\_\_\_ bar gauge.

Design temperature range \_\_\_\_\_ °C to \_\_\_\_\_ °C. (For portable tanks used for refrigerated liquefied gases, the minimum design temperature must be marked.)

Water capacity at 20 °C/ \_\_\_\_\_ liters.

Water capacity of each compartment at 20 °C \_\_\_\_\_ liters.

Initial pressure test date and witness identification.

MAWP for heating/cooling system \_\_\_\_\_ bar gauge.

Shell material(s) and material standard reference(s).

Equivalent thickness in reference steel \_\_\_\_\_ mm.

Lining material (when applicable).

Date and type of most recent periodic test(s).

Month \_\_\_\_\_ Year \_\_\_\_\_ Test pressure \_\_\_\_\_ bar gauge.

Stamp of approval agency that performed or witnessed the most recent test.

For portable tanks used for refrigerated liquefied gases:

Either “thermally insulated” or “vacuum insulated” \_\_\_\_\_.

Effectiveness of the insulation system (heat influx) \_\_\_\_\_ Watts (W).

Reference holding time \_\_\_\_\_ days or hours and initial pressure \_\_\_\_\_ bar/kPa gauge and degree of filling \_\_\_\_\_ in kg for each refrigerated liquefied gas permitted for transportation.

(2) The following information must be marked either on the portable tank itself or on a metal plate firmly secured to the portable tank:

Name of the operator.

Name of hazardous materials being transported and maximum mean bulk temperature (except for refrigerated liquefied gases, the name and temperature are only required when the maximum mean bulk temperature is higher than 50 °C).

Maximum permissible gross mass (MPGM) \_\_\_\_\_ kg.

Unladen (tare) mass \_\_\_\_\_ kg.

NOTE TO PARAGRAPH (i)(2): For the identification of the hazardous materials being transported refer to part 172 of this subchapter.

(3) If a portable tank is designed and approved for open seas operations, such as offshore oil exploration, in accordance with the IMDG Code, the words “OFFSHORE PORTABLE TANK” must be marked on the identification plate.

(j) *Initial inspection and test.* The initial inspection and test of a portable tank must include the following:

(1) A check of the design characteristics.

(2) An internal and external examination of the portable tank and its fittings, taking into account the hazardous materials to be transported. For UN portable tanks used for refrigerated liquefied gases, a pressure test using an inert gas may be conducted instead of a hydrostatic test. An internal inspection is not required for a portable tank used for the dedicated transportation of refrigerated liquefied gases that are not filled with an inspection opening.

(3) A pressure test as specified in paragraph (i) of this section.

(4) A leakage test.

(5) A test of the satisfactory operation of all service equipment including pressure relief devices must also be performed. When the shell and its fittings have been pressure-tested separately, they must be subjected to a leakage test after reassembly. All welds, subject to full stress level in the shell, must be inspected during the initial test by radiographic, ultrasonic, or another suitable non-destructive test method. This does not apply to the jacket.

(6) Effective January 1, 2008, each new UN portable tank design type meeting the definition of “container” in the Convention for Safe Containers (CSC) (see 49 CFR 450.3(a)(2)) must be subjected to the dynamic longitudinal impact test prescribed in Part IV, Section 40 of the UN Manual of Tests and Criteria (see IBR, §171.7 of this subchapter). A UN portable tank design type impact-tested prior to January 1, 2008, in accordance with the requirements of this section in effect on October 1, 2005, need not be retested. UN portable tanks used for the dedicated transportation of “Helium, refrigerated liquid,” UN1963, and “Hydrogen, refrigerated liquid,” UN1966, that are marked “NOT FOR RAIL TRANSPORT” in letters of a minimum height of 10 cm (4 inches) on at least two sides of the portable tank are excepted from the dynamic longitudinal impact test.

(7) The following tests must be completed on a portable tank or a series of portable tanks designed and constructed to a single design type that is also a CSC container without leakage or deformation that would render the

## § 178.275

## 49 CFR Ch. I (10–1–08 Edition)

portable tank unsafe for transportation and use:

(i) *Longitudinal inertia*. The portable tank loaded to its maximum gross weight must be positioned with its longitudinal axis vertical. It shall be held in this position for five minutes by support at the lower end of the base structure providing vertical and lateral restraint and by support at the upper end of the base structure providing lateral restraint only.

(ii) *Lateral inertia*. The portable tank loaded to its maximum gross weight must be positioned for five minutes with its transverse axis vertical. It shall be held in this position for five minutes by support at the lower side of the base structure providing vertical and lateral restraint and by support at the upper side of the base structure providing lateral restraint only.

[66 FR 33440, June 21, 2001, as amended at 67 FR 15744, Apr. 3, 2002; 68 FR 45041, July 31, 2003; 68 FR 57633, Oct. 6, 2003; 68 FR 75751, Dec. 31, 2003; 69 FR 76185, Dec. 20, 2004; 70 FR 34399, June 14, 2005; 71 FR 78634, Dec. 29, 2006; 72 FR 55696, Oct. 1, 2007; 73 FR 4719, Jan. 28, 2008]

EDITORIAL NOTE: At 68 FR 57633, Oct. 6, 2003, §178.274 was amended in paragraph (b)(1); however, the amendment could not be incorporated due to inaccurate amendatory instruction.

### § 178.275 Specification for UN Portable Tanks intended for the transportation of liquid and solid hazardous materials.

(a) In addition to the requirements of §178.274, this section sets forth definitions and requirements that apply to UN portable tanks intended for the transportation of liquid and solid hazardous materials.

(b) *Definitions and requirements*—(1) *Design pressure* means the pressure to be used in calculations required by the recognized pressure vessel code. The design pressure must not be less than the highest of the following pressures:

(i) The maximum effective gauge pressure allowed in the shell during filling or discharge; or

(ii) The sum of—

(A) The absolute vapor pressure (in bar) of the hazardous material at 65 °C, minus 1 bar (149 °F, minus 100 kPa);

(B) The partial pressure (in bar) of air or other gases in the ullage space,

resulting from their compression during filling without pressure relief by a maximum ullage temperature of 65 °C (149 °F) and a liquid expansion due to an increase in mean bulk temperature of 35 °C (95 °F); and

(C) A head pressure determined on the basis of the forces specified in §178.274(c) of this subchapter, but not less than 0.35 bar (35 kPa).

(2) *Maximum allowable working pressure (MAWP)* means a pressure that must not be less than the highest of the following pressures measured at the top of the shell while in operating position:

(i) The maximum effective gauge pressure allowed in the shell during filling or discharge; or

(ii) The maximum effective gauge pressure to which the shell is designed which must be not less than the design pressure.

(c) *Service equipment*. (1) In addition to the requirements specified in §178.274, for service equipment, all openings in the shell, intended for filling or discharging the portable tank must be fitted with a manually operated stop-valve located as close to the shell as reasonably practicable. Other openings, except for openings leading to venting or pressure relief devices, must be equipped with either a stop-valve or another suitable means of closure located as close to the shell as reasonably practicable.

(2) All portable tanks must be fitted with a manhole or other inspection openings of a suitable size to allow for internal inspection and adequate access for maintenance and repair of the interior. Compartmented portable tanks must have a manhole or other inspection openings for each compartment.

(3) For insulated portable tanks, top fittings must be surrounded by a spill collection reservoir with suitable drains.

(4) Piping must be designed, constructed and installed to avoid the risk of damage due to thermal expansion and contraction, mechanical shock and vibration. All piping must be of a suitable metallic material. Welded pipe joints must be used wherever possible.

(d) *Bottom openings.* (1) Certain hazardous materials may not be transported in portable tanks with bottom openings. When the applicable T code or portable tank special provision, as referenced for materials in the §172.101 Table of this subchapter, specifies that bottom openings are prohibited, there must be no openings below the liquid level of the shell when it is filled to its maximum permissible filling limit. When an existing opening is closed, it must be accomplished by internally and externally welding one plate to the shell.

(2) Bottom discharge outlets for portable tanks carrying certain solid, crystallizable or highly viscous hazardous materials must be equipped with at least two serially fitted and mutually independent shut-off devices. Use of only two shut-off devices is only authorized when this paragraph is referenced in the applicable T Code indicated for each hazardous material in the §172.101 Table of this subchapter. The design of the equipment must be to the satisfaction of the approval agency and must include:

(i) An external stop-valve fitted as close to the shell as reasonably practicable; and

(ii) A liquid tight closure at the end of the discharge pipe, which may be a bolted blank flange or a screw cap.

(3) Except as provided in paragraph (d)(2) of this section, every bottom discharge outlet must be equipped with three serially fitted and mutually independent shut-off devices. The design of the equipment must include:

(i) A self-closing internal stop-valve, which is a stop-valve within the shell or within a welded flange or its companion flange, such that:

(A) The control devices for the operation of the valve are designed to prevent any unintended opening through impact or other inadvertent act;

(B) The valve is operable from above or below;

(C) If possible, the setting of the valve (open or closed) must be capable of being verified from the ground;

(D) Except for portable tanks having a capacity less than 1,000 liters (264.2 gallons), it must be possible to close the valve from an accessible position on the portable tank that is remote

from the valve itself within 30 seconds of actuation; and

(E) The valve must continue to be effective in the event of damage to the external device for controlling the operation of the valve;

(ii) An external stop-valve fitted as close to the shell as reasonably practicable;

(iii) A liquid tight closure at the end of the discharge pipe, which may be a bolted blank flange or a screw cap; and

(iv) For UN portable tanks, with bottom outlets, used for the transportation of liquid hazardous materials that are Class 3, PG I or II, or PG III with a flash point of less than 100 °F (38 °C); Division 5.1, PG I or II; or Division 6.1, PG I or II, the remote means of closure must be capable of thermal activation. The thermal means of activation must activate at a temperature of not more than 250 °F (121 °C).

(e) *Pressure relief devices.* All portable tanks must be fitted with at least one pressure relief device. All relief devices must be designed, constructed and marked in accordance with the requirements of this subchapter.

(f) *Vacuum-relief devices.* (1) A shell which is to be equipped with a vacuum-relief device must be designed to withstand, without permanent deformation, an external pressure of not less than 0.21 bar (21.0 kPa). The vacuum-relief device must be set to relieve at a vacuum setting not greater than -0.21 bar (-21.0 kPa) unless the shell is designed for a higher external over pressure, in which case the vacuum-relief pressure of the device to be fitted must not be greater than the tank design vacuum pressure. A shell that is not fitted with a vacuum-relief device must be designed to withstand, without permanent deformation, an external pressure of not less than 0.4 bar (40.0 kPa).

(2) Vacuum-relief devices used on portable tanks intended for the transportation of hazardous materials meeting the criteria of Class 3, including elevated temperature hazardous materials transported at or above their flash point, must prevent the immediate passage of flame into the shell or the portable tank must have a shell capable of withstanding, without leakage, an internal explosion resulting

from the passage of flame into the shell.

(g) *Pressure relief devices.* (1) Each portable tank with a capacity not less than 1,900 liters (501.9 gallons) and every independent compartment of a portable tank with a similar capacity, must be provided with one or more pressure relief devices of the reclosing type. Such portable tanks may, in addition, have a frangible disc or fusible element in parallel with the reclosing devices, except when the applicable T code assigned to a hazardous material requires that the frangible disc precede the pressure relief device, according to paragraph (g)(3) of this section, or when no bottom openings are allowed. The pressure relief devices must have sufficient capacity to prevent rupture of the shell due to over pressurization or vacuum resulting from filling, discharging, heating of the contents or fire.

(2) Pressure relief devices must be designed to prevent the entry of foreign matter, the leakage of liquid and the development of any dangerous excess pressure.

(3) When required for certain hazardous materials by the applicable T code or portable tank special provision specified for a hazardous material in the §172.101 Table of this subchapter, portable tanks must have a pressure relief device consistent with the requirements of this subchapter. Except for a portable tank in dedicated service that is fitted with an approved relief device constructed of materials compatible with the hazardous material, the relief device system must include a frangible disc preceding (such as, between the lading and the reclosing pressure relief device) a reclosing pressure relief device. A pressure gauge or suitable tell-tale indicator for the detection of disc rupture, pin-holing or leakage must be provided in the space between the frangible disc and the pressure relief device to allow the portable tank operator to check to determine if the disc is leak free. The frangible disc must rupture at a nominal pressure 10% above the start-to-discharge pressure of the reclosable pressure relief device.

(4) Every portable tank with a capacity less than 1,900 liters (501.9 gallons)

must be fitted with a pressure relief device which, except as provided in paragraph (g)(3) of this section, may be a frangible disc when this disc is set to rupture at a nominal pressure equal to the test pressure at any temperature within the design temperature range.

(5) When the shell is fitted for pressure discharge, a suitable pressure relief device must provide the inlet line to the portable tank and set to operate at a pressure not higher than the MAWP of the shell, and a stop-valve must be fitted as close to the shell as practicable to minimize the potential for damage.

(6) *Setting of pressure relief devices.* (i) Pressure relief devices must operate only in conditions of excessive rise in temperature. The shell must not be subject to undue fluctuations of pressure during normal conditions of transportation.

(ii) The required pressure relief device must be set to start to discharge at a nominal pressure of five-sixths of the test pressure for shells having a test pressure of not more than 4.5 bar (450 kPa) and 110% of two-thirds of the test pressure for shells having a test pressure of more than 4.5 bar (450 kPa). A self-closing relief device must close at a pressure not more than 10% below the pressure at which the discharge starts. The device must remain closed at all lower pressures. This requirement does not prevent the use of vacuum-relief or combination pressure relief and vacuum-relief devices.

(h) *Fusible elements.* Fusible elements must operate at a temperature between 110 °C (230 °F) and 149 °C (300.2 °F) provided that the pressure in the shell at the fusing temperature will not exceed the test pressure. They must be placed at the top of the shell with their inlets in the vapor space and in no case may they be shielded from external heat. Fusible elements must not be utilized on portable tanks with a test pressure which exceeds 2.65 bar (265.0 kPa). Fusible elements used on portable tanks intended for the transport of elevated temperature hazardous materials must be designed to operate at a temperature higher than the maximum temperature that will be experienced during transport and must be designed to the satisfaction of the approval agency.

(i) *Capacity of pressure relief devices.*  
(1) The reclosing pressure relief device required by paragraph (g)(1) of this section must have a minimum cross sectional flow area equivalent to an orifice of 31.75 mm (1.3 inches) diameter. Vacuum-relief devices, when used, must have a cross sectional flow area not less than 284 mm<sup>2</sup> (11.2 inches<sup>2</sup>).

(2) The combined delivery capacity of the pressure relief system (taking into account the reduction of the flow when the portable tank is fitted with frangible-discs preceding spring-loaded pressure-relief devices or when the spring-loaded pressure-relief devices are provided with a device to prevent the passage of the flame), in condition of complete fire engulfment of the portable tank must be sufficient to limit the pressure in the shell to 20% above the start to discharge pressure limiting device (pressure relief device). The total required capacity of the relief devices may be determined using the formula in paragraph (i)(2)(i)(A) of this section or the table in paragraph (i)(2)(iii) of this section.

(i)(A) To determine the total required capacity of the relief devices, which must be regarded as being the sum of the individual capacities of all the contributing devices, the following formula must be used:

$$Q = 12.4 \frac{FA^{0.82}}{LC} \sqrt{\frac{ZT}{M}}$$

Where:

Q = minimum required rate of discharge in cubic meters of air per second (m<sup>3</sup>/s) at conditions: 1 bar and 0 °C (273 °K);

F = for uninsulated shells: 1; for insulated shells: U(649 - t)/13.6 but in no case is less than 0.25

Where:

U = thermal conductance of the insulation, in kW m<sup>-2</sup>K<sup>-1</sup>, at 38 °C (100 °F); and t = actual temperature of the hazardous material during filling (in °C) or when this temperature is unknown, let t = 15 °C (59 °F). The value of F given in this paragraph (i)(2)(i)(A) for insulated shells may only be used if the insulation is in conformance with paragraph (i)(2)(iv) of this section;

A = total external surface area of shell in square meters;

Z = the gas compressibility factor in the accumulating condition (when this factor is unknown, let Z equal 1.0);

T = absolute temperature in Kelvin (°C + 273) above the pressure relief devices in the accumulating condition;

L = the latent heat of vaporization of the liquid, in kJ/kg, in the accumulating condition;

M = molecular weight of the hazardous material.

(B) The constant C, as shown in the formula in paragraph (i)(2)(i)(A) of this section, is derived from one of the following formulas as a function of the ratio k of specific heats:

$$k = \frac{c_p}{c_v}$$

Where:

c<sub>p</sub> is the specific heat at constant pressure; and

c<sub>v</sub> is the specific heat at constant volume.

(C) When k > 1:

$$C = \sqrt{k \left( \frac{2}{k+1} \right)^{\frac{k+1}{k-1}}}$$

(D) When k = 1 or k is unknown, a value of 0.607 may be used for the constant C. C may also be taken from the following table:

C CONSTANT VALUE TABLE

| k    | C     |
|------|-------|
| 1.00 | 0.607 |
| 1.02 | 0.611 |
| 1.04 | 0.615 |
| 1.06 | 0.620 |
| 1.08 | 0.624 |
| 1.10 | 0.628 |
| 1.12 | 0.633 |
| 1.14 | 0.637 |
| 1.16 | 0.641 |
| 1.18 | 0.645 |
| 1.20 | 0.649 |
| 1.22 | 0.652 |
| 1.24 | 0.656 |
| 1.26 | 0.660 |
| 1.28 | 0.664 |
| 1.30 | 0.667 |
| 1.32 | 0.671 |
| 1.34 | 0.674 |
| 1.36 | 0.678 |
| 1.38 | 0.681 |
| 1.40 | 0.685 |
| 1.42 | 0.688 |
| 1.44 | 0.691 |
| 1.46 | 0.695 |
| 1.48 | 0.698 |
| 1.50 | 0.701 |
| 1.52 | 0.704 |
| 1.54 | 0.707 |
| 1.56 | 0.710 |
| 1.58 | 0.713 |
| 1.60 | 0.716 |



§ 178.276

49 CFR Ch. I (10–1–08 Edition)

C CONSTANT VALUE TABLE—Continued

| k    | C     |
|------|-------|
| 1.62 | 0.719 |
| 1.64 | 0.722 |
| 1.66 | 0.725 |
| 1.68 | 0.728 |
| 1.70 | 0.731 |
| 2.00 | 0.770 |
| 2.20 | 0.793 |

(ii) As an alternative to the formula in paragraph (i)(2)(i)(A) of this section, relief devices for shells used for transporting liquids may be sized in accordance with the table in paragraph (i)(2)(iii) of this section. The table in paragraph (i)(2)(iii) of this section assumes an insulation value of  $F = 1$  and must be adjusted accordingly when the shell is insulated. Other values used in determining the table in paragraph (i)(2)(iii) of this section are:  $L = 334.94$  kJ/kg;  $M = 86.7$ ;  $T = 394$  °K;  $Z = 1$ ; and  $C = 0.607$ .

(iii) Minimum emergency vent capacity,  $Q$ , in cubic meters of air per second at 1 bar and 0 °C (273 °K) shown in the following table:

MINIMUM EMERGENCY VENT CAPACITY  
[Q Values]

| A<br>Exposed area<br>(square me-<br>ters) | Q<br>(Cubic me-<br>ters of air<br>per second) | A<br>Exposed area<br>(square me-<br>ters) | Q<br>(Cubic me-<br>ters of air<br>per second) |
|-------------------------------------------|-----------------------------------------------|-------------------------------------------|-----------------------------------------------|
| 2                                         | 0.230                                         | 37.5                                      | 2.539                                         |
| 3                                         | 0.320                                         | 40                                        | 2.677                                         |
| 4                                         | 0.405                                         | 42.5                                      | 2.814                                         |
| 5                                         | 0.487                                         | 45                                        | 2.949                                         |
| 6                                         | 0.565                                         | 47.5                                      | 3.082                                         |
| 7                                         | 0.641                                         | 50                                        | 3.215                                         |
| 8                                         | 0.715                                         | 52.5                                      | 3.346                                         |
| 9                                         | 0.788                                         | 55                                        | 3.476                                         |
| 10                                        | 0.859                                         | 57.5                                      | 3.605                                         |
| 12                                        | 0.998                                         | 60                                        | 3.733                                         |
| 14                                        | 1.132                                         | 62.5                                      | 3.860                                         |
| 16                                        | 1.263                                         | 65                                        | 3.987                                         |
| 18                                        | 1.391                                         | 67.5                                      | 4.112                                         |
| 20                                        | 1.517                                         | 70                                        | 4.236                                         |
| 22.5                                      | 1.670                                         | 75                                        | 4.483                                         |
| 25                                        | 1.821                                         | 80                                        | 4.726                                         |
| 27.5                                      | 1.969                                         | 85                                        | 4.967                                         |
| 30                                        | 2.115                                         | 90                                        | 5.206                                         |
| 32.5                                      | 2.258                                         | 95                                        | 5.442                                         |
| 35                                        | 2.400                                         | 100                                       | 5.676                                         |

(iv) Insulation systems, used for the purpose of reducing venting capacity, must be specifically approved by the approval agency. In all cases, insulation systems approved for this purpose must—

(A) Remain effective at all temperatures up to 649 °C (1200 °F); and

(B) Be jacketed with a material having a melting point of 700 °C (1292 °F) or greater.

(j) *Approval, inspection and testing.* Approval procedures for UN portable tanks are specified in § 178.273. Inspection and testing requirements are specified in § 180.605 of this subchapter.

[66 FR 33445, June 21, 2001, as amended at 68 FR 32414, May 30, 2003; 69 FR 76185, Dec. 20, 2004; 73 FR 57006, Oct. 1, 2008]

**§ 178.276 Requirements for the design, construction, inspection and testing of portable tanks intended for the transportation of non-refrigerated liquefied compressed gases.**

(a) In addition to the requirements of § 178.274 applicable to UN portable tanks, the following requirements apply to UN portable tanks used for non-refrigerated liquefied compressed gases. In addition to the definitions in § 178.274, the following definitions apply:

(1) *Design pressure* means the pressure to be used in calculations required by the ASME Code, Section VIII (IBR, see § 171.7 of this subchapter). The design pressure must be not less than the highest of the following pressures:

(i) The maximum effective gauge pressure allowed in the shell during filling or discharge; or

(ii) The sum of:

(A) The maximum effective gauge pressure to which the shell is designed as defined in this paragraph under “MAWP”; and

(B) A head pressure determined on the basis of the dynamic forces specified in paragraph (h) of this section, but not less than 0.35 bar (35 kPa).

(2) *Design reference temperature* means the temperature at which the vapor pressure of the contents is determined for the purpose of calculating the MAWP. The value for each portable tank type is as follows:

(i) Shell with a diameter of 1.5 meters (4.9 ft.) or less: 65 °C (149 °F); or

(ii) Shell with a diameter of more than 1.5 meters (4.9 ft.):

(A) Without insulation or sun shield: 60 °C (140 °F);

(B) With sun shield: 55 °C (131 °F); and

(C) With insulation: 50 °C (122 °F).

(3) *Filling density* means the average mass of liquefied compressed gas per liter of shell capacity (kg/l).

(4) *Maximum allowable working pressure (MAWP)* means a pressure that must be not less than the highest of the following pressures measured at the top of the shell while in operating position, but in no case less than 7 bar (700 kPa):

(i) The maximum effective gauge pressure allowed in the shell during filling or discharge; or

(ii) The maximum effective gauge pressure to which the shell is designed, which must be:

(A) Not less than the pressure specified for each liquefied compressed gas listed in the UN Portable Tank Table for Liquefied Compressed Gases in § 173.313; and

(B) Not less than the sum of:

(1) The absolute vapor pressure (in bar) of the liquefied compressed gas at the design reference temperature minus 1 bar; and

(2) The partial pressure (in bar) of air or other gases in the ullage space which is determined by the design reference temperature and the liquid phase expansion due to the increase of the mean bulk temperature of  $t_f - t_r$  ( $t_f$  = filling temperature, usually 15 °C,  $t_r$  = 50 °C maximum mean bulk temperature).

(b) *General design and construction requirements.* (1) Shells must be of seamless or welded steel construction, or combination of both, and have a water capacity greater than 450 liters (118.9 gallons). Shells must be designed, constructed, certified and stamped in accordance with the ASME Code, Section VIII.

(2) Portable tanks must be postweld heat-treated and radiographed as prescribed in Section VIII of the ASME Code, except that each portable tank constructed in accordance with part UHT of the ASME Code must be postweld heat-treated. Where postweld heat treatment is required, the portable tank must be treated as a unit after completion of all the welds in and/or to the shell and heads. The method must be as prescribed in the ASME Code. Welded attachments to pads may be made after postweld heat treatment is made. A portable tank

used for anhydrous ammonia must be postweld heat-treated. The postweld heat treatment must be as prescribed in the ASME Code, but in no event at less than 1050 °F tank metal temperature. Additionally, portable tanks constructed in accordance with part UHT of the ASME Code must conform to the following requirements:

(i) Welding procedure and welder performance tests must be made annually in accordance with Section IX of the ASME Code. In addition to the essential variables named therein, the following must be considered to be essential variables: number of passes, thickness of plate, heat input per pass, and manufacturer's identification of rod and flux. The number of passes, thickness of plate and heat input per pass may not vary more than 25 percent from the qualified procedure. Records of the qualification must be retained for at least 5 years by the portable tank manufacturer or his designated agent and, upon request, made available to a representative of the Department of Transportation or the owner of the tank.

(ii) Impact tests must be made on a lot basis. A lot is defined as 100 tons or less of the same heat and having a thickness variation no greater than plus or minus 25 percent. The minimum impact required for full-sized specimens shall be 20 foot-pounds (or 10 foot-pounds for half-sized specimens) at 0 °F (−17.8 °F) Charpy V-Notch in both the longitudinal and transverse direction. If the lot test does not pass this requirement, individual plates may be accepted if they individually meet this impact requirement.

(3) When the shells intended for the transportation of non-refrigerated liquefied compressed gases are equipped with thermal insulation, a device must be provided to prevent any dangerous pressure from developing in the insulating layer in the event of a leak, when the protective covering is closed it must be gas tight. The thermal insulation must not inhibit access to the fittings and discharge devices. In addition, the thermal insulation systems must satisfy the following requirements:

(i) consist of a shield covering not less than the upper third, but not more

than the upper half of the surface of the shell, and separated from the shell by an air space of approximately 40 mm (1.7 inches) across; or

(ii) consist of a complete cladding of insulating materials. The insulation must be of adequate thickness and constructed to prevent the ingress of moisture and damage to the insulation. The insulation and cladding must have a thermal conductance of not more than  $0.67 \text{ (W} \cdot \text{m}^{-2} \cdot \text{K}^{-1})$  under normal conditions of transportation.

(c) *Service equipment.* (1) Each opening with a diameter of more than 1.5 mm (0.1 inch) in the shell of a portable tank, except openings for pressure-relief devices, inspection openings and closed bleed holes, must be fitted with at least three mutually independent shut-off devices in series: the first being an internal stop-valve, excess flow valve, integral excess flow valve, or excess flow feature (see § 178.337–1(g)), the second being an external stop-valve and the third being a blank flange, thread cap, plug or equivalent tight liquid closure device.

(2) When a portable tank is fitted with an excess flow valve, the excess flow valve must be so fitted that its seating is inside the shell or inside a welded flange or, when fitted externally, its mountings must be designed so that in the event of impact it maintains its effectiveness. The excess flow valves must be selected and fitted so as to close automatically when the rated flow, specified by the manufacturer, is reached. Connections and accessories leading to or from such a valve must have a capacity for a flow more than the excess flow valve's rated flow.

(3) For filling and discharge openings that are located below the liquid level, the first shut-off device must be an internal stop-valve and the second must be a stop-valve placed in an accessible position on each discharge and filling pipe.

(4) For filling and discharge openings located below the liquid level of portable tanks intended for the transportation of flammable and/or toxic liquefied compressed gases, the internal stop-valve must be a self-closing safety device that fully closes automatically during filling or discharge in the event of fire engulfment. The device shall

fully close within 30 seconds of actuation and the thermal means of closure must actuate at a temperature of not more than  $121 \text{ }^{\circ}\text{C}$  ( $250 \text{ }^{\circ}\text{F}$ ). Except for portable tanks having a capacity less than 1,000 liters (264.2 gallons), this device must be operable by remote control.

(5) In addition to filling, discharge and gas pressure equalizing orifices, shells may have openings in which gauges, thermometers and manometers can be fitted. Connections for such instruments must be made by suitable welded nozzles or pockets and may not be connected by screwed connections through the shell.

(6) All portable tanks must be fitted with manholes or other inspection openings of suitable size to allow for internal inspection and adequate access for maintenance and repair of the interior.

(7) *Inlets and discharge outlets on chlorine portable tanks.* The inlet and discharge outlets on portable tanks used to transport chlorine must meet the requirements of § 178.337–1(c)(2) and must be fitted with an internal excess flow valve. In addition to the internal excess flow valve, the inlet and discharge outlets must be equipped with an external stop valve (angle valve). Excess flow valves must conform to the standards of The Chlorine Institute, Inc. (IBR, see § 171.7 of this subchapter) as follows:

(i) A valve conforming to Drawing 101–7, dated July 1993, must be installed under each liquid angle valve.

(ii) A valve conforming to Drawing 106–6, dated July 1993, must be installed under each gas angle valve. For portable tanks used to transport non-refrigerated liquefied gases.

(8) External fittings must be grouped together as close as reasonably practicable. The following openings may be installed at locations other than on the top or end of the tank:

(i) The openings for liquid level gauging devices, pressure gauges, or for safety devices, may be installed separately at the other location or in the side of the shell;

(ii) One plugged opening of 2-inch National Pipe Thread or less provided for maintenance purposes may be located elsewhere;

(iii) An opening of 3-inch National Pipe Size or less may be provided at another location, when necessary, to facilitate installation of condensing coils.

(9) Filling and discharge connections are not required to be grouped and may be installed below the normal liquid level of the tank if:

(i) The portable tank is permanently mounted in a full framework for containerized transport;

(ii) For each portable tank design, a prototype portable tank, meets the requirements of parts 450 through 453 of this title for compliance with the requirements of Annex II of the International Convention for Safe Containers; and

(iii) Each filling and discharge outlet meets the requirements of paragraph (c)(4) of this section.

(d) *Bottom openings.* Bottom openings are prohibited on portable tanks when the UN Portable Tank Table for Liquefied Compressed Gases in §173.313 of this subchapter indicates that bottom openings are not allowed. In this case, there may be no openings located below the liquid level of the shell when it is filled to its maximum permissible filling limit.

(e) *Pressure relief devices.* (1) Portable tanks must be provided with one or more reclosing pressure relief devices. The pressure relief devices must open automatically at a pressure not less than the MAWP and be fully open at a pressure equal to 110% of the MAWP. These devices must, after discharge, close at a pressure not less than 10% below the pressure at which discharge starts and must remain closed at all lower pressures. The pressure relief devices must be of a type that will resist dynamic forces including liquid surge. A frangible disc may only be used in series with a reclosing pressure relief device.

(2) Pressure relief devices must be designed to prevent the entry of foreign matter, the leakage of gas and the development of any dangerous excess pressure.

(3) A portable tank intended for the transportation of certain liquefied compressed gases identified in the UN Portable Tank Table for Liquefied Compressed Gases in §173.313 of this

subchapter must have a pressure relief device which conforms to the requirements of this subchapter. Unless a portable tank, in dedicated service, is fitted with a relief device constructed of materials compatible with the hazardous material, the relief device must be comprised of a frangible disc preceded by a reclosing device. The space between the frangible disc and the device must be provided with a pressure gauge or a suitable tell-tale indicator. This arrangement must facilitate the detection of disc rupture, pinholing or leakage which could cause a malfunction of the pressure relief device. The frangible disc must rupture at a nominal pressure 10% above the start-to-discharge pressure of the relief device.

(4) In the case of portable tanks used for more than one gas, the pressure relief devices must open at a pressure indicated in paragraph (e)(1) of this section for the gas having the highest maximum allowable pressure of the gases allowed to be transported in the portable tank.

(f) *Capacity of relief devices.* The combined delivery capacity of the relief devices must be sufficient so that, in the event of total fire engulfment, the pressure inside the shell cannot exceed 120% of the MAWP. Reclosing relief devices must be used to achieve the full relief capacity prescribed. In the case of portable tanks used for more than gas, the combined delivery capacity of the pressure relief devices must be taken for the liquefied compressed gas which requires the highest delivery capacity of the liquefied compressed gases allowed to be transported in the portable tank. The total required capacity of the relief devices must be determined according to the requirements in §178.275(i). These requirements apply only to liquefied compressed gases which have critical temperatures well above the temperature at the accumulating condition. For gases that have critical temperatures near or below the temperature at the accumulating condition, the calculation of the pressure relief device delivery capacity must consider the additional thermodynamic properties of the

## § 178.277

## 49 CFR Ch. I (10–1–08 Edition)

gas, for example see CGA S–1.2 (IBR, see § 171.7 of this subchapter).

[66 FR 33448, June 21, 2001, as amended at 68 FR 75748, 75752, Dec. 31, 2003; 69 FR 54046, Sept. 7, 2004; 69 FR 76185, Dec. 20, 2004]

### **§ 178.277 Requirements for the design, construction, inspection and testing of portable tanks intended for the transportation of refrigerated liquefied gases.**

(a) In addition to the requirements of § 178.274 applicable to UN portable tanks, the following requirements and definitions apply to UN portable tanks used for refrigerated liquefied gases:

*Design pressure* For the purpose of this section the term “design pressure” is consistent with the definition for design pressure in the ASME Code, Section VIII (IBR, see § 171.7 of this subchapter).

*Holding time* is the time, as determined by testing, that will elapse from loading until the pressure of the contents, under equilibrium conditions, reaches the lowest set pressure of the pressure limiting device(s) (for example, pressure control valve or pressure relief device). Holding time must be determined as specified in § 178.338–9.

*Maximum allowable working pressure (MAWP)* means the maximum effective gauge pressure permissible at the top of the shell of a loaded portable tank in its operating position including the highest effective pressure during filling and discharge;

*Minimum design temperature* means the temperature which is used for the design and construction of the shell not higher than the lowest (coldest) service temperature of the contents during normal conditions of filling, discharge and transportation.

*Shell* means the part of the portable tank which retains the refrigerated liquefied gas intended for transport, including openings and their closures, but does not include service equipment or external structural equipment.

*Tank* means a construction which normally consists of either:

(1) A jacket and one or more inner shells where the space between the shell(s) and the jacket is exhausted of air (vacuum insulation) and may incorporate a thermal insulation system; or

(2) A jacket and an inner shell with an intermediate layer of solid thermally insulating material (for example, solid foam).

(b) *General design and construction requirements.* (1) Portable tanks must be of seamless or welded steel construction and have a water capacity of more than 450 liters (118.9 gallons). Portable tanks must be designed, constructed, certified and stamped in accordance with Section VIII of the ASME Code.

(2) Portable tanks must be postweld heat treated and radiographed as prescribed in Sections V and VIII of the ASME Code except that each tank constructed in accordance with part UHT in Section VIII of the ASME Code must be postweld heat treated. Where postweld heat treatment is required, the tank must be treated as a unit after completion of all the welds to the shell and heads. The method must be as prescribed in the ASME Code. Welded attachments to pads may be made after postweld heat treatment is made. The postweld heat treatment must be as prescribed in Section VIII of the ASME Code, but in no event at less than 1,050 °F tank metal temperature.

(3) Welding procedure and welder performance tests must be made annually in accordance with Section IX of the ASME Code (IBR, see § 171.7 of this subchapter). In addition to the essential variables named in the ASME Code, the following must be considered as essential variables: number of passes, thickness of plate, heat input per pass, and the specified rod and flux. The number of passes, thickness of plate and heat input per pass may not vary more than 25% from the procedure qualification. Records of the qualification must be retained for at least 5 years by the portable tank manufacturer and made available to the approval agency and the owner of the portable tank as specified in § 178.273.

(4) Shells and jackets must be made of metallic materials suitable for forming. Jackets must be made of steel. Non-metallic materials may be used for the attachments and supports between the shell and jacket, provided their material properties at the minimum design temperature are proven to be sufficient. In choosing the material, the minimum design temperature

must be taken into account with respect to risk of brittle fracture, to hydrogen embrittlement, to stress corrosion cracking and to resistance to impact.

(5) Any part of a portable tank, including fittings, gaskets and pipework, which can be expected normally to come into contact with the refrigerated liquefied gas transported must be compatible with that refrigerated liquefied gas.

(6) The thermal insulation system must include a complete covering of the shell with effective insulating materials. External insulation must be protected by a jacket so as to prevent the ingress of moisture and other damage under normal transport conditions.

(7) When a jacket is so closed as to be gas-tight, a device must be provided to prevent any dangerous pressure from developing in the insulation space.

(8) Materials which may react with oxygen or oxygen enriched atmospheres in a dangerous manner may not be used in portable tanks intended for the transport of refrigerated liquefied gases having a boiling point below minus 182 °C at atmospheric pressure in locations with the thermal insulation where there is a risk of contact with oxygen or with oxygen enriched fluid.

(9) Insulating materials must not deteriorate to an extent that the effectiveness of the insulation system, as determined in accordance with paragraph (b)(11) of this section, would be reduced in service.

(10) A reference holding time must be determined for each refrigerated liquefied gas intended for transport in a portable tank. The reference holding time must be determined by testing in accordance with the requirements of § 178.338–9, considering the following factors:

(i) The effectiveness of the insulation system, determined in accordance with paragraph (b)(11) of this section;

(ii) The lowest set pressure of the pressure limiting device;

(iii) The initial filling conditions;

(iv) An assumed ambient temperature of 30 °C (86 °F);

(v) The physical properties of the individual refrigerated liquefied gas intended to be transported.

(11) The effectiveness of the insulation system (heat influx in watts) may be determined by type testing the portable tank in accordance with a procedure specified in § 178.338–9(c) or by using the holding time test in § 178.338–9(b). This test must consist of either:

(i) A constant pressure test (for example, at atmospheric pressure) when the loss of refrigerated liquefied gas is measured over a period of time; or

(ii) A closed system test when the rise in pressure in the shell is measured over a period of time.

(12) When performing the constant pressure test, variations in atmospheric pressure must be taken into account. When performing either test, corrections must be made for any variation of the ambient temperature from the assumed ambient temperature reference value of 30 °C (86 °F).

(13) The jacket of a vacuum-insulated double-wall tank must have either an external design pressure not less than 100 kPa (1 bar) gauge pressure calculated in accordance with Section VIII of the ASME Code or a calculated critical collapsing pressure of not less than 200 kPa (2 bar) gauge pressure. Internal and external reinforcements may be included in calculating the ability of the jacket to resist the external pressure.

NOTE TO PARAGRAPH (b): For the determination of the actual holding time, as indicated by paragraphs (b)(10), (11), (12), and (13), before each journey, refer to § 178.338–9(b).

(c) *Design criteria.* For shells with vacuum insulation, the test pressure must not be less than 1.3 times the sum of the MAWP and 100 kPa (1 bar). In no case may the test pressure be less than 300 kPa (3 bar) gauge pressure.

(d) *Service equipment.* (1) Each filling and discharge opening in portable tanks used for the transport of flammable refrigerated liquefied gases must be fitted with at least three mutually independent shut-off devices in series: the first being a stop-valve situated as close as reasonably practicable to the jacket, the second being a stop-valve and the third being a blank flange or equivalent device. The shut-off device closest to the jacket must be a self-closing device, which is capable of

being closed from an accessible position on the portable tank that is remote from the valve within 30 seconds of actuation. This device must actuate at a temperature of not more than 121 °C (250 °F).

(2) Each filling and discharge opening in portable tanks used for the transport of non-flammable refrigerated liquefied gases must be fitted with at least two mutually independent shut-off devices in series: the first being a stop-valve situated as close as reasonably practicable to the jacket and the second a blank flange or equivalent device.

(3) For sections of piping which can be closed at both ends and where liquid product can be trapped, a method of automatic pressure relief must be provided to prevent excess pressure build-up within the piping.

(4) Each filling and discharge opening on a portable tank must be clearly marked to indicate its function.

(5) When pressure-building units are used, the liquid and vapor connections to that unit must be provided with a valve as close to the jacket as reasonably practicable to prevent the loss of contents in case of damage to the pressure-building unit. A check valve may be used for this purpose if it is located on the vapor side of the pressure build-up coil.

(6) The materials of construction of valves and accessories must have satisfactory properties at the lowest operating temperature of the portable tank.

(7) Vacuum insulated portable tanks are not required to have an inspection opening.

(e) *Pressure relief devices.* (1) Every shell must be provided with not less than two independent reclosing pressure relief devices. The pressure relief devices must open automatically at a pressure not less than the MAWP and be fully open at a pressure equal to 110% of the MAWP. These devices must, after discharge, close at a pressure not lower than 10% below the pressure at which discharge starts and must remain closed at all lower pressures. The pressure relief devices must be of the type that will resist dynamic forces including surge.

(2) Except for portable tanks used for oxygen, portable tanks for non-flammable refrigerated liquefied gases (except oxygen) and hydrogen may in addition have frangible discs in parallel with the reclosing devices as specified in paragraphs (e)(4)(ii) and (e)(4)(iii) of this section.

(3) Pressure relief devices must be designed to prevent the entry of foreign matter, the leakage of gas and the development of any dangerous excess pressure.

(4) *Capacity and setting of pressure relief devices.* (i) In the case of the loss of vacuum in a vacuum-insulated tank or of loss of 20% of the insulation of a portable tank insulated with solid materials, the combined capacity of all pressure relief devices installed must be sufficient so that the pressure (including accumulation) inside the shell does not exceed 120% of the MAWP.

(ii) For non-flammable refrigerated liquefied gases (except oxygen) and hydrogen, this capacity may be achieved by the use of frangible discs in parallel with the required safety-relief devices. Frangible discs must rupture at nominal pressure equal to the test pressure of the shell.

(iii) Under the circumstances described in paragraphs (e)(4)(i) and (e)(4)(ii) of this section, together with complete fire engulfment, the combined capacity of all pressure relief devices installed must be sufficient to limit the pressure in the shell to the test pressure.

(iv) The required capacity of the relief devices must be calculated in accordance with CGA Pamphlet S-1.2 (IBR, see § 171.7 of this subchapter).

[66 FR 33450, June 21, 2001, as amended at 68 FR 75748, 75752, Dec. 31, 2003]

### Subpart I [Reserved]

### Subpart J—Specifications for Containers for Motor Vehicle Transportation

SOURCE: 29 FR 18975, Dec. 29, 1964, unless otherwise noted. Redesignated at 32 FR 5606, Apr. 5, 1967.

**§ 178.318 Specification MC 201; container for detonators and percussion caps.****§ 178.318-1 Scope.**

(a) This specification pertains to a container to be used for the transportation of detonators and percussion caps in connection with the transportation of liquid nitroglycerin, desensitized liquid nitroglycerin or diethylene glycol dinitrate, where any or all of such types of caps may be used for the detonation of liquid nitroglycerin, desensitized liquid nitroglycerin or diethylene glycol dinitrate in blasting operations. This specification is not intended to take the place of any shipping or packing requirements of this Department where the caps in question are themselves articles of commerce.

(b) [Reserved]

[29 FR 18975, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-60, 44 FR 70733, Dec. 10, 1979]


**§ 178.318-2 Container.**

(a) Every container for detonators and percussion caps coming within the scope of this specification shall be constructed entirely of hard rubber, phenolresinous or other resinous material, or other nonmetallic, nonsparking material, except that metal parts may be used in such locations as not in any event to come in contact with any of the caps. Space shall be provided so that each detonator of whatever nature may be inserted in an individual cell in the body of the container, into which each such cap shall snugly fit. There shall be provided no more than twenty (20) such cellular spaces. Space may be provided into which a plurality of per-

cussion caps may be carried, provided that such space may be closed with a screw cap, and further provided that each or any such space is entirely separate from any space provided for any detonator. Each cellular space into which a detonator is to be inserted and carried shall be capable of being covered by a rotary cover so arranged as to expose not more than one cell at any time, and capable of rotation to such a place that all cells will be covered at the same time, at which place means shall be provided to lock the cover in place. Means shall be provided to lock in place the cover for the cells provided for the carrying of detonators. The requirement that not more than one cell be exposed at one time need not apply in the case of detonators, although spaces for such caps and detonators shall be separate. Sufficient annular space shall be provided inside the cover for such detonators that, when the cover is closed, there will be sufficient space to accommodate the wires customarily attached to such caps. If the material is of such a nature as to require treatment to prevent the absorption of moisture, such treatment shall be applied as shall be necessary in order to provide against the penetration of water by permeation. A suitable carrying handle shall be provided, except for which handle no part of the container may project beyond the exterior of the body.

(b) Exhibited in plates I and II are line drawings of a container for detonators and percussion caps, illustrative of the requirements set forth in § 178.318-2(a). These plates shall not be construed as a part of this specification.





BLASTING CAP CONTAINER  
PLATE I




PLATE II

[29 FR 18975, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-60, 44 FR 70733, Dec. 10, 1979]

**§ 178.318-3 Marking.**

Each container must be marked as prescribed in § 178.2(b).

[Amdt. 178-40, 41 FR 38181, Sept. 9, 1976, as amended at 66 FR 45185, Aug. 28, 2001]

**§ 178.320 General requirements applicable to all DOT specification cargo tank motor vehicles.**

(a) *Definitions.* For the purpose of this subchapter:

*Appurtenance* means any attachment to a cargo tank that has no lading re-

tention or containment function and provides no structural support to the cargo tank.

*Baffle* means a non-liquid-tight transverse partition device that deflects, checks or regulates fluid motion in a tank.

*Bulkhead* means a liquid-tight transverse closure at the ends of or between cargo tanks.

*Cargo tank* means a bulk packaging that:

(1) Is a tank intended primarily for the carriage of liquids, gases, solids, or

semi-solids and includes appurtenances, reinforcements, fittings, and closures (for *tank*, see §§ 178.337–1, 178.338–1, or 178.345–1, as applicable);

(2) Is permanently attached to or forms a part of a motor vehicle, or is not permanently attached to a motor vehicle but that, by reason of its size, construction, or attachment to a motor vehicle, is loaded or unloaded without being removed from the motor vehicle; and

(3) Is not fabricated under a specification for cylinders, intermediate bulk containers, multi-unit tank cars, tanks, portable tanks, or tank cars.

*Cargo tank motor vehicle* means a motor vehicle with one or more cargo tanks permanently attached to or forming an integral part of the motor vehicle.

*Cargo tank wall* means those parts of the cargo tank that make up the primary lading retention structure, including shell, bulkheads, and fittings and, when closed, yield the minimum volume of the cargo tank assembly.

*Charging line* means a hose, tube, pipe, or a similar device used to pressurize a tank with material other than the lading.

*Companion flange* means one of two mating flanges where the flange faces are in contact or separated only by a thin leak-sealing gasket and are secured to one another by bolts or clamps.

*Connecting structure* means the structure joining two cargo tanks.

*Constructed and certified in accordance with the ASME Code* means a cargo tank is constructed and stamped in accordance with Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), and is inspected and certified by an Authorized Inspector.

*Constructed in accordance with the ASME Code* means a cargo tank is constructed in accordance with Section VIII of the ASME Code with authorized exceptions (see §§ 178.346 through 178.348) and is inspected and certified by a Registered Inspector.

*Design type* means one or more cargo tanks that are made—

- (1) To the same specification;
- (2) By the same manufacturer;
- (3) To the same engineering drawings and calculations, except for minor

variations in piping that do not affect the lading retention capability of the cargo tank;

(4) Of the same materials of construction;

(5) To the same cross-sectional dimensions;

(6) To a length varying by no more than 5 percent;

(7) With the volume varying by no more than 5 percent (due to a change in length only); and

(8) For the purposes of § 178.338 only, with the same insulation system.

*External self-closing stop valve* means a self-closing stop valve designed so that the self-stored energy source is located outside the cargo tank and the welded flange.

*Extreme dynamic loading* means the maximum loading a cargo tank motor vehicle may experience during its expected life, excluding accident loadings resulting from an accident, such as overturn or collision.

*Flange* means the structural ring for guiding or attachment of a pipe or fitting with another flange (companion flange), pipe, fitting or other attachment.

*Inspection pressure* means the pressure used to determine leak tightness of the cargo tank when testing with pneumatic pressure.

*Internal self-closing stop valve* means a self-closing stop valve designed so that the self-stored energy source is located inside the cargo tank or cargo tank sump, or within the welded flange, and the valve seat is located within the cargo tank or within one inch of the external face of the welded flange or sump of the cargo tank.

*Lading* means the hazardous material contained in a cargo tank.

*Loading/unloading connection* means the fitting in the loading/unloading line farthest from the loading/unloading outlet to which the loading/unloading hose, pipe, or device is attached.

*Loading/unloading outlet* means a cargo tank outlet used for normal loading/unloading operations.

*Loading/unloading stop valve* means the stop valve farthest from the cargo tank loading/unloading outlet to which the loading/unloading connection is attached.

*Manufacturer* means any person engaged in the manufacture of a DOT specification cargo tank, cargo tank motor vehicle, or cargo tank equipment that forms part of the cargo tank wall. This term includes attaching a cargo tank to a motor vehicle or to a motor vehicle suspension component that involves welding on the cargo tank wall. A manufacturer must register with the Department in accordance with subpart F of part 107 in subpart A of this chapter.

*Maximum allowable working pressure* or *MAWP* means the maximum pressure allowed at the top of the tank in its normal operating position. The MAWP must be calculated as prescribed in Section VIII of the ASME Code. In use, the MAWP must be greater than or equal to the maximum lading pressure conditions prescribed in § 173.33 of this subchapter for each material transported.

*Maximum lading pressure.* See § 173.33(c).

*Minimum thickness* means the minimum required shell and head (and baffle and bulkhead when used as tank reinforcement) thickness needed to meet the specification. The minimum thickness is the *greatest* of the following values: (1)(i) For MC 330, MC 331, and MC 338 cargo tanks, the specified minimum thickness found in the applicable specification(s); or

(ii) For DOT 406, DOT 407 and DOT 412 cargo tanks, the specified minimum thickness found in Tables I and II of the applicable specification(s); or

(iii) For MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, and MC 312 cargo tanks, the in-service minimum thickness prescribed in Tables I and II of § 180.407(i)(5) of this subchapter, for the minimum thickness specified by Tables I and II of the applicable specification(s); or

(2) The thickness necessary to meet with the structural integrity and accident damage requirements of the applicable specification(s); or

(3) The thickness as computed per the ASME Code requirements (if applicable).

*Multi-specification cargo tank motor vehicle* means a cargo tank motor vehicle equipped with two or more cargo tanks

fabricated to more than one cargo tank specification.

*Normal operating loading* means the loading a cargo tank motor vehicle may be expected to experience routinely in operation.

*Nozzle* means a subassembly consisting of a pipe or tubular section with or without a welded or forged flange on one end.

*Outlet* means any opening in the shell or head of a cargo tank, (including the means for attaching a closure), except that the following are not *outlets*: a threaded opening securely closed during transportation with a threaded plug or a threaded cap, a flanged opening securely closed during transportation with a bolted or welded blank flange, a manhole, a gauging device, a thermometer well, or a pressure relief device.

*Outlet stop valve* means the stop valve at a cargo tank loading or unloading outlet.

*Pipe coupling* means a fitting with internal threads on both ends.

*Rear bumper* means the structure designed to prevent a vehicle or object from under-riding the rear of another motor vehicle. See § 393.86 of this title.

*Rear-end tank protection device* means the structure designed to protect a cargo tank and any lading retention piping or devices in case of a rear end collision.

*Self-closing stop valve* means a stop valve held in the closed position by means of self-stored energy, that opens only by application of an external force and that closes when the external force is removed.

*Shell* means the circumferential portion of a cargo tank defined by the basic design radius or radii excluding the bulkheads.

*Stop valve* means a valve that stops the flow of lading.

*Sump* means a protrusion from the bottom of a cargo tank shell designed to facilitate complete loading and unloading of lading.

*Tank* means a container, consisting of a shell and heads, that forms a pressure tight vessel having openings designed to accept pressure tight fittings or closures, but excludes any appurtenances, reinforcements, fittings, or closures.

*Test pressure* means the pressure to which a tank is subjected to determine structural integrity.

*Toughness of material* means the capability of a material to absorb energy represented by the area under a stress strain curve (indicating the energy absorbed per unit volume of the material) up to the point of rupture.

*Vacuum cargo tank* means a cargo tank that is loaded by reducing the pressure in the cargo tank to below atmospheric pressure.

*Variable specification cargo tank* means a cargo tank that is constructed in accordance with one specification, but that may be altered to meet another specification by changing relief device, closures, lading discharge devices, and other lading retention devices.

*Void* means the space between tank heads or bulkheads and a connecting structure.

*Welded flange* means a flange attached to the tank by a weld joining the tank shell to the cylindrical outer surface of the flange, or by a fillet weld joining the tank shell to a flange shaped to fit the shell contour.

(b) *Design certification.* (1) Each cargo tank or cargo tank motor vehicle design type, including its required accident damage protection device, must be certified to conform to the specification requirements by a Design Certifying Engineer who is registered in accordance with subpart F of part 107 of this title. An accident damage protection device is a rear-end protection, overturn protection, or piping protection device.

(2) The Design Certifying Engineer shall furnish to the manufacturer a certificate to indicate compliance with the specification requirements. The certificate must include the sketches, drawings, and calculations used for certification. Each certificate, including sketches, drawings, and calculations, shall be signed by the Design Certifying Engineer.

(3) The manufacturer shall retain the design certificate at his principal place of business for as long as he manufactures DOT specification cargo tanks.

(c) *Exceptions to the ASME Code.* Unless otherwise specified, when exceptions are provided in this subpart from

compliance with certain paragraphs of the ASME Code, compliance with those paragraphs is not prohibited.

[Amdt. 178-89, 55 FR 37055, Sept. 7, 1990, as amended by Amdt. 178-98, 58 FR 33306, June 16, 1993; Amdt. 178-118, 61 FR 51339, Oct. 1, 1996; 68 FR 19277, Apr. 18, 2003; 68 FR 52370, Sept. 3, 2003; 68 FR 75752, Dec. 31, 2003]

**§ 178.337 Specification MC 331; cargo tank motor vehicle primarily for transportation of compressed gases as defined in subpart G of part 173 of this subchapter.**

**§ 178.337-1 General requirements.**

(a) *ASME Code construction.* Tanks must be—

(1) Seamless or welded construction, or a combination of both;

(2) Designed, constructed, certified, and stamped in accordance with Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter);

(3) Made of steel or aluminum; however, if aluminum is used, the cargo tank must be insulated and the hazardous material to be transported must be compatible with the aluminum (see §§ 178.337-1(e)(2), 173.315(a) table, and 178.337-2(a)(1) of this subchapter); and

(4) Covered with a steel jacket if the cargo tank is insulated and used to transport a flammable gas (see § 173.315(a) table Note 11 of this subchapter).

(b) *Design pressure.* The design pressure of a cargo tank authorized under this specification shall be not less than the vapor pressure of the commodity contained therein at 115 °F. or as prescribed for a particular commodity in § 173.315(a) of this subchapter, except that in no case shall the design pressure of any cargo tank be less than 100 p.s.i.g. nor more than 500 p.s.i.g.

NOTE 1: The term *design pressure* as used in this specification, is identical to the term *MAWP* as used in the ASME Code.

(c) *Openings.* (1) Excess pressure relief valves shall be located in the top of the cargo tank or heads.

(2) A chlorine cargo tank shall have only one opening. That opening shall be in the top of the cargo tank and shall be fitted with a nozzle that meets the following requirements:

(i) On a cargo tank manufactured on or before December 31, 1974, the nozzle

shall be protected by a dome cover plate which conforms to either the standard of The Chlorine Institute, Inc., Dwg. 103-3, dated January 23, 1958, or to the standard specified in paragraph (c) (2) (ii) of this section.

(ii) On a cargo tank manufactured on or after January 1, 1975, the nozzle shall be protected by a manway cover which conforms to the standard of The Chlorine Institute, Inc., Dwg. 103-4, dated September 1, 1971.

(d) *Reflective design.* Every uninsulated cargo tank permanently attached to a cargo tank motor vehicle shall, unless covered with a jacket made of aluminum, stainless steel, or other bright nontarnishing metal, be painted a white, aluminum or similar reflecting color on the upper two-thirds of area of the cargo tank.

(e) *Insulation.* (1) Each cargo tank required to be insulated must conform with the use and performance requirements contained in §§ 173.315(a) table and 178.337-1 (a)(3) and (e)(2) of this subchapter.

(2) Each cargo tank intended for chlorine; carbon dioxide, refrigerated liquid; or nitrous oxide, refrigerated liquid service must have suitable insulation of such thickness that the overall thermal conductance is not more than 0.08 Btu per square foot per °F differential per hour. The conductance must be determined at 60 °F. Insulation material used on cargo tanks for nitrous oxide, refrigerated liquid must be noncombustible. Insulating material used on cargo tanks for chlorine must be corkboard or polyurethane foam, with a minimum thickness of 4 inches, or 2 inches minimum thickness of ceramic fiber/fiberglass of 4 pounds per cubic foot minimum density covered by 2 inches minimum thickness of fiber.

(f) *Postweld heat treatment.* Postweld heat treatment must be as prescribed in the ASME Code except that each cargo tank constructed in accordance with Part UHT of Section VIII of the ASME Code must be postweld heat treated. Each chlorine cargo tank must be fully radiographed and postweld heat treated in accordance with the provisions in Section VIII of the ASME Code under which it is constructed. Where postweld heat treatment is required, the cargo tank must be treated

as a unit after completion of all the welds in and/or to the shells and heads. The method must be as prescribed in Section VIII of the ASME Code. Welded attachments to pads may be made after postweld heat treatment. A cargo tank used for anhydrous ammonia must be postweld heat treated. The postweld heat treatment must be as prescribed in Section VIII of the ASME Code, but in no event at less than 1,050 °F cargo tank metal temperature.

(g) *Definitions.* The following definitions apply to §§ 178.337-1 through 178.337-18:

*Emergency discharge control* means the ability to stop a cargo tank unloading operation in the event of an unintentional release. Emergency discharge control can utilize passive or off-truck remote means to stop the unloading operation. A passive means of emergency discharge control automatically shuts off the flow of product without the need for human intervention within 20 seconds of an unintentional release caused by a complete separation of the liquid delivery hose. An off-truck remote means of emergency discharge control permits a qualified person attending the unloading operation to close the cargo tank's internal self-closing stop valve and shut off all motive and auxiliary power equipment at a distance from the cargo tank motor vehicle.

*Excess flow valve, integral excess flow valve, or excess flow feature* means a component that will close automatically if the flow rate of a gas or liquid through the component reaches or exceeds the rated flow of gas or liquid specified by the original valve manufacturer when piping mounted directly on the valve is sheared off before the first valve, pump, or fitting downstream from the valve.

*Internal self-closing stop valve* means a primary shut off valve installed in a product discharge outlet of a cargo tank and designed to be kept closed by self-stored energy.

*Primary discharge control system* means a primary shut-off installed at a product discharge outlet of a cargo tank consisting of an internal self-closing stop valve that may include an integral excess flow valve or an excess flow feature, together with linkages

that must be installed between the valve and remote actuator to provide manual and thermal on-truck remote means of closure.

[Order 59-B, 30 FR 579, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §178.337-1, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 178.337-2 Material.

(a) *General.* (1) All material used for construction of the cargo tank and appurtenances must be suitable for use with the commodities to be transported therein and must conform to the requirements in Section II of the ASME Code (IBR, see §171.7 of this subchapter) and/or requirements of the American Society for Testing and Materials in all respects.

(2) Impact tests are required on steel used in the fabrication of each cargo tank constructed in accordance with part UHT in Section VIII of the ASME Code. The tests must be made on a lot basis. A lot is defined as 100 tons or less of the same heat treatment processing lot having a thickness variation no greater than plus or minus 25 percent. The minimum impact required for full size specimens must be 20 foot-pounds in the longitudinal direction at  $-30^{\circ}\text{F.}$ , Charpy V-Notch and 15 foot-pounds in the transverse direction at  $-30^{\circ}\text{F.}$ , Charpy V-Notch. The required values for subsize specimens must be reduced in direct proportion to the cross-sectional area of the specimen beneath the notch. If a lot does not meet this requirement, individual plates may be accepted if they individually meet this requirement.

(3) The fabricator shall record the heat, and slab numbers, and the certified Charpy impact values, where required, of each plate used in each cargo tank on a sketch showing the location of each plate in the shell and heads of the cargo tank. Copies of each sketch shall be provided to the owner and retained for at least five years by the fabricator and made available to duly identified representatives of the Department of Transportation.

(4) The direction of final rolling of the shell material shall be the circum-

ferential orientation of the cargo tank shell.

(b) *For a chlorine cargo tank.* Plates, the manway nozzle, and anchorage shall be made of carbon steel which meets the following requirements:

(1) For a cargo tank manufactured on or before December 31, 1974—

(i) Material shall conform to ASTM A 300, "Steel Plates for Pressure Vessels for Service at Low Temperatures" (IBR, see §171.7 of this subchapter);

(ii) Material shall be Class 1, Grade A, flange or firebox quality;

(iii) Plate impact test specimens, as required under paragraph (a) of this section, shall be of the Charpy keyhole notch type; and

(iv) Plate impact test specimens shall meet the impact test requirements in paragraph (a) of this section in both the longitudinal and transverse directions of rolling at a temperature of minus  $45.5^{\circ}\text{C.}$  ( $-50^{\circ}\text{F.}$ ).

(2) For a cargo tank manufactured on or after January 1, 1975—

(i) Material shall conform to ASTM A 612 (IBR, see §171.7 of this subchapter), Grade B or A 516/A 516M (IBR, see §171.7 of this subchapter), Grade 65 or 70;

(ii) Material shall meet the Charpy V-notch test requirements of ASTM A 20/A 20M (IBR, see §171.7 of this subchapter); and

(iii) Plate impact test specimens shall meet the impact test requirements in paragraph (a) of this section in both the longitudinal and transverse directions of rolling at a temperature of minus  $40^{\circ}\text{C.}$  ( $-40^{\circ}\text{F.}$ ).

(c) A cargo tank in anhydrous ammonia service must be constructed of steel. The use of copper, silver, zinc or their alloys is prohibited. Baffles made from aluminum may be used only if joined to the cargo tank by a process not requiring postweld heat treatment of the cargo tank.

[Order 59-B, 30 FR 579, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §178.337-2, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### § 178.337-3 Structural integrity.

(a) General requirements and acceptance criteria. (1) Except as provided in

paragraph (d) of this section, the maximum calculated design stress at any point in the cargo tank may not exceed the maximum allowable stress value prescribed in Section VIII of the ASME Code (IBR, see §171.7 of this subchapter), or 25 percent of the tensile strength of the material used.

(2) The relevant physical properties of the materials used in each cargo tank may be established either by a certified test report from the material manufacturer or by testing in conformance with a recognized national standard. In either case, the ultimate tensile strength of the material used in the design may not exceed 120 percent of the ultimate tensile strength specified in either the ASME Code or the ASTM standard to which the material is manufactured.

(3) The maximum design stress at any point in the cargo tank must be calculated separately for the loading conditions described in paragraphs (b), (c), and (d) of this section. Alternate test or analytical methods, or a combination thereof, may be used in place of the procedures described in paragraphs (b), (c), and (d) of this section, if the methods are accurate and verifiable.

(4) Corrosion allowance material may not be included to satisfy any of the design calculation requirements of this section.

(b) *Static design and construction.* (1) The static design and construction of each cargo tank must be in accordance with Section VIII of the ASME Code. The cargo tank design must include calculation of stresses generated by design pressure, the weight of lading, the weight of structure supported by the cargo tank wall, and the effect of temperature gradients resulting from lading and ambient temperature extremes. When dissimilar materials are used, their thermal coefficients must be used in calculation of thermal stresses.

(2) Stress concentrations in tension, bending and torsion which occur at pads, cradles, or other supports must be considered in accordance with appendix G in Section VIII of the ASME Code.

(c) *Shell design.* Shell stresses resulting from static or dynamic loadings, or combinations thereof, are not uniform

throughout the cargo tank motor vehicle. The vertical, longitudinal, and lateral normal operating loadings can occur simultaneously and must be combined. The vertical, longitudinal and lateral extreme dynamic loadings occur separately and need not be combined.

(1) *Normal operating loadings.* The following procedure addresses stress in the tank shell resulting from normal operating loadings. The effective stress (the maximum principal stress at any point) must be determined by the following formula:

$$S = 0.5(S_y + S_x) \pm [0.25(S_y - S_x)^2 + S_z^2]^{0.5}$$

Where:

(i)  $S$  = effective stress at any given point under the combination of static and normal operating loadings that can occur at the same time, in psi.

(ii)  $S_y$  = circumferential stress generated by the MAWP and external pressure, when applicable, plus static head, in psi.

(iii)  $S_x$  = The following net longitudinal stress generated by the following static and normal operating loading conditions, in psi:

(A) The longitudinal stresses resulting from the MAWP and external pressure, when applicable, plus static head, in combination with the bending stress generated by the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(B) The tensile or compressive stress resulting from normal operating longitudinal acceleration or deceleration. In each case, the forces applied must be 0.35 times the vertical reaction at the suspension assembly, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer during deceleration; or the horizontal pivot of the truck tractor or converter dolly fifth wheel, or the drawbar hinge on the fixed dolly during acceleration; or anchoring and support members of a truck during acceleration and deceleration, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances

supported by the cargo tank wall. The following loadings must be included:

(1) The axial load generated by a decelerative force;

(2) The bending moment generated by a decelerative force;

(3) The axial load generated by an accelerative force; and

(4) The bending moment generated by an accelerative force; and

(C) The tensile or compressive stress generated by the bending moment resulting from normal operating vertical accelerative force equal to 0.35 times the vertical reaction at the suspension assembly of a trailer; or the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall.

(iv)  $S_s$  = The following shear stresses generated by the following static and normal operating loading conditions, in psi:

(A) The static shear stress resulting from the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(B) The vertical shear stress generated by a normal operating accelerative force equal to 0.35 times the vertical reaction at the suspension assembly of a trailer; or the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(C) The lateral shear stress generated by a normal operating lateral accelerative force equal to 0.2 times the vertical reaction at each suspension as-

sembly of a trailer, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall; and

(D) The torsional shear stress generated by the same lateral forces as described in paragraph (c)(1)(iv)(C) of this section.

(2) *Extreme dynamic loadings.* The following procedure addresses stress in the tank shell resulting from extreme dynamic loadings. The effective stress (the maximum principal stress at any point) must be determined by the following formula:

$$S = 0.5(S_y + S_x) \pm [0.25(S_y - S_x)^2 + S_z^2]^{0.5}$$

Where:

(i)  $S$  = effective stress at any given point under a combination of static and extreme dynamic loadings that can occur at the same time, in psi.

(ii)  $S_y$  = circumferential stress generated by MAWP and external pressure, when applicable, plus static head, in psi.

(iii)  $S_x$  = the following net longitudinal stress generated by the following static and extreme dynamic loading conditions, in psi:

(A) The longitudinal stresses resulting from the MAWP and external pressure, when applicable, plus static head, in combination with the bending stress generated by the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the tank wall;

(B) The tensile or compressive stress resulting from extreme longitudinal acceleration or deceleration. In each case the forces applied must be 0.7 times the vertical reaction at the suspension assembly, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer during deceleration; or the horizontal pivot of the truck tractor or converter dolly fifth



wheel, or the drawbar hinge on the fixed dolly during acceleration; or the anchoring and support members of a truck during acceleration and deceleration, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall. The following loadings must be included:

- (1) The axial load generated by a decelerative force;
- (2) The bending moment generated by a decelerative force;
- (3) The axial load generated by an accelerative force; and
- (4) The bending moment generated by an accelerative force; and

(C) The tensile or compressive stress generated by the bending moment resulting from an extreme vertical accelerative force equal to 0.7 times the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or the anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall.

(iv)  $S_s$  = The following shear stresses generated by static and extreme dynamic loading conditions, in psi:

(A) The static shear stress resulting from the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(B) The vertical shear stress generated by an extreme vertical accelerative force equal to 0.7 times the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully

loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(C) The lateral shear stress generated by an extreme lateral accelerative force equal to 0.4 times the vertical reaction at the suspension assembly of a trailer, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall; and

(D) The torsional shear stress generated by the same lateral forces as described in paragraph (c)(2)(iv)(C) of this section.

(d) In order to account for stresses due to impact in an accident, the design calculations for the cargo tank shell and heads must include the load resulting from the design pressure in combination with the dynamic pressure resulting from a longitudinal deceleration of "2g". For this loading condition the stress value used may not exceed the lesser of the yield strength or 75 percent of the ultimate tensile strength of the material of construction. For cargo tanks constructed of stainless steel the maximum design stress may not exceed 75 percent of the ultimate tensile strength of the type steel used.

(e) The minimum metal thickness for the shell and heads on tanks with a design pressure of 100 psig or more must be 4.75 mm (0.187 inch) for steel and 6.86 mm (0.270 inch) for aluminum, except for chlorine and sulfur dioxide tanks. In all cases, the minimum thickness of the tank shell and head shall be determined using structural design requirements in Section VIII of the ASME Code or 25% of the tensile strength of the material used. For a cargo tank used in chlorine or sulfur dioxide service, the cargo tank must be made of steel. A corrosion allowance of 20 percent or 2.54 mm (0.10 inch), whichever is less, must be added to the thickness

otherwise required for sulfur dioxide and chlorine tank material. In chlorine cargo tanks, the wall thickness must be at least 1.59 cm (0.625 inch), including corrosion allowance.

(f) Where a cargo tank support is attached to any part of the cargo tank wall, the stresses imposed on the cargo tank wall must meet the requirements in paragraph (a) of this section.

(g) The design, construction, and installation of an attachment, appurtenance to the cargo tank, structural support member between the cargo tank and the vehicle or suspension component, or accident protection device must conform to the following requirements:

(1) Structural members, the suspension sub-frame, accident protection structures, and external circumferential reinforcement devices must be used as sites for attachment of appurtenances and other accessories to the cargo tank, when practicable.

(2) A lightweight attachment to the cargo tank wall such as a conduit clip, brake line clip, skirting structure, lamp mounting bracket, or placard holder must be of a construction having lesser strength than the cargo tank wall materials and may not be more than 72 percent of the thickness of the material to which it is attached. The lightweight attachment may be secured directly to the cargo tank wall if the device is designed and installed in such a manner that, if damaged, it will not affect the lading retention integrity of the tank. A lightweight attachment must be secured to the cargo tank shell or head by a continuous weld or in such a manner as to preclude formation of pockets which may become sites for corrosion. Attachments meeting the requirements of this paragraph are not authorized for cargo tanks constructed under part UHT in Section VIII of the ASME Code.

(3) Except as prescribed in paragraphs (g)(1) and (g)(2) of this section, the welding of any appurtenance to the cargo tank wall must be made by attachment of a mounting pad so that there will be no adverse effect upon the lading retention integrity of the cargo tank if any force less than that prescribed in paragraph (b)(1) of this section is applied from any direction. The

thickness of the mounting pad may not be less than that of the shell wall or head wall to which it is attached, and not more than 1.5 times the shell or head thickness. However, a pad with a minimum thickness of 0.25 inch may be used when the shell or head thickness is over 0.25 inch. If weep holes or tell-tale holes are used, the pad must be drilled or punched at the lowest point before it is welded to the tank. Each pad must—

(i) Be fabricated from material determined to be suitable for welding to both the cargo tank material and the material of the appurtenance or structural support member; a Design Certifying Engineer must make this determination considering chemical and physical properties of the materials and must specify filler material conforming to the requirements in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter).

(ii) Be preformed to an inside radius no greater than the outside radius of the cargo tank at the attachment location.

(iii) Extend at least 2 inches in each direction from any point of attachment of an appurtenance or structural support member. This dimension may be measured from the center of the attached structural member.

(iv) Have rounded corners, or otherwise be shaped in a manner to minimize stress concentrations on the shell or head.

(v) Be attached by continuous fillet welding. Any fillet weld discontinuity may only be for the purpose of preventing an intersection between the fillet weld and a tank or jacket seam weld.

[Amdt. 178-89, 55 FR 37056, Sept. 7, 1990, as amended by Amdt. 178-104, 59 FR 49135, Sept. 26, 1994; Amdt. 178-105, 60 FR 17401, Apr. 5, 1995; Amdt. 178-118, 61 FR 51340, Oct. 1, 1996; 65 FR 58631, Sept. 29, 2000; 68 FR 19279, Apr. 18, 2003; 68 FR 52370, Sept. 3, 2003; 68 FR 75753, Dec. 31, 2003]

#### § 178.337-4 Joints.

(a) Joints shall be as required in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), with all undercutting in shell and head material repaired as specified therein.

(b) Welding procedure and welder performance must be in accordance with Section IX of the ASME Code. In addition to the essential variables named therein, the following must be considered as essential variables: Number of passes; thickness of plate; heat input per pass; and manufacturer's identification of rod and flux. When fabrication is done in accordance with part UHT in Section VIII of the ASME Code, filler material containing more than 0.08 percent vanadium must not be used. The number of passes, thickness of plate, and heat input per pass may not vary more than 25 percent from the procedure or welder qualifications. Records of the qualifications must be retained for at least 5 years by the cargo tank manufacturer and must be made available to duly identified representatives of the Department and the owner of the cargo tank.

(c) All longitudinal shell welds shall be located in the upper half of the cargo tank.

(d) Edge preparation of shell and head components may be by machine heat processes, provided such surfaces are remelted in the subsequent welding process. Where there will be no subsequent remelting of the prepared surface as in a tapered section, the final 0.050 inch of material shall be removed by mechanical means.

(e) The maximum tolerance for misalignment and butting up shall be in accordance with the requirement in Section VIII of the ASME Code.

(f) Substructures shall be properly fitted before attachment, and the welding sequence shall be such as to minimize stresses due to shrinkage of welds.

[Order 59-B, 30 FR 580, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 178.337-4, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 178.337-5 Bulkheads, baffles and ring stiffeners.**

- (a) Not a specification requirement.
- (b) [Reserved]

[Order 59-B, 30 FR 580, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

**§ 178.337-6 Closure for manhole.**

(a) Each cargo tank marked or certified after April 21, 1994, must be provided with a manhole conforming to paragraph UG-46(g)(1) and other applicable requirements in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), except that a cargo tank constructed of NQT steel having a capacity of 3,500 water gallons or less may be provided with an inspection opening conforming to paragraph UG-46 and other applicable requirements of the ASME Code instead of a manhole.

(b) The manhole assembly of cargo tanks constructed after June 30, 1979, may not be located on the front head of the cargo tank.

[Amdt. 178-7, 34 FR 18250, Nov. 14, 1969, as amended by Amdt. 178-52, 43 FR 58820, Dec. 18, 1978; Amdt. 178-89, 54 FR 25017, June 12, 1989; 55 FR 21038, May 22, 1990; 56 FR 27876, June 17, 1991; 58 FR 12905, March 8, 1993; Amdt. 178-118, 61 FR 51340, Oct. 1, 1996; 68 FR 75753, Dec. 31, 2003]

**§ 178.337-7 Overturn protection.**

- (a) See § 178.337-10.
- (b) [Reserved]

[Order 59-B, 30 FR 580, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

**§ 178.337-8 Openings, inlets, and outlets.**

(a) *General.* The requirements in this paragraph (a) apply to MC 331 cargo tanks except for those used to transport chlorine. The requirements for inlets and outlets on chlorine cargo tanks are in paragraph (b) of this section.

(1) An opening must be provided on each cargo tank used for the transportation of liquefied materials to permit complete drainage.

(2) Except for gauging devices, thermometer wells, pressure relief valves, manhole openings, product inlet openings, and product discharge openings, each opening in a cargo tank must be closed with a plug, cap, or bolted flange.

(3) Except as provided in paragraph (b) of this section, each product inlet opening, including vapor return lines, must be fitted with a back flow check valve or an internal self-closing stop valve located inside the cargo tank or

inside a welded nozzle that is an integral part of the cargo tank. The valve seat must be located inside the cargo tank or within 2.54 cm (one inch) of the external face of the welded flange. Damage to parts exterior to the cargo tank or mating flange must not prevent effective seating of the valve. All parts of a valve inside a cargo tank or welded flange must be made of material that will not corrode or deteriorate in the presence of the lading.

(4) Except as provided in paragraphs (a)(5), (b), and (c) of this section, each liquid or vapor discharge outlet must be fitted with a primary discharge control system as defined in § 178.337-1(g). Thermal remote operators must activate at a temperature of 121.11°C (250 °F) or less. Linkages between closures and remote operators must be corrosion resistant and effective in all types of environmental conditions incident to discharging of product.

(i) On a cargo tank over 13,247.5 L (3,500 gallons) water capacity, thermal and mechanical means of remote closure must be installed at the ends of the cargo tank in at least two diagonally opposite locations. If the loading/unloading connection at the cargo tank is not in the general vicinity of one of the two locations specified in the first sentence of this paragraph (a)(4)(i), additional means of thermal remote closure must be installed so that heat from a fire in the loading/unloading connection area or the discharge pump will activate the primary discharge control system. The loading/unloading connection area is where hoses or hose reels are connected to the permanent metal piping.

(ii) On a cargo tank of 13,247.5 L (3,500 gallons) water capacity or less, a thermal means of remote closure must be installed at or near the internal self-closing stop valve. A mechanical means of remote closure must be installed on the end of the cargo tank furthest away from the loading/unloading connection area. The loading/unloading connection area is where hoses or hose reels are connected to the permanent metal piping. Linkages between closures and remote operators must be corrosion resistant and effective in all types of environmental con-

ditions incident to discharge of product.

(iii) All parts of a valve inside a cargo tank or within a welded flange must be made of material that will not corrode or deteriorate in the presence of the lading.

(iv) An excess flow valve, integral excess flow valve, or excess flow feature must close if the flow reaches the rated flow of a gas or liquid specified by the original valve manufacturer when piping mounted directly on the valve is sheared off before the first valve, pump, or fitting downstream from the excess flow valve, integral excess flow valve, or excess flow feature.

(v) An integral excess flow valve or the excess flow feature of an internal self-closing stop valve may be designed with a bypass, not to exceed 0.1016 cm (0.040 inch) diameter opening, to allow equalization of pressure.

(vi) The internal self-closing stop valve must be designed so that the self-stored energy source and the valve seat are located inside the cargo tank or within 2.54 cm (one inch) of the external face of the welded flange. Damage to parts exterior to the cargo tank or mating flange must not prevent effective seating of the valve.

(5) A primary discharge control system is not required on the following:

(i) A vapor or liquid discharge opening of less than 1¼ NPT equipped with an excess flow valve together with a manually operated external stop valve in place of an internal self-closing stop valve.

(ii) An engine fuel line on a truck-mounted cargo tank of not more than ¾ NPT equipped with a valve having an integral excess flow valve or excess flow feature.

(iii) A cargo tank motor vehicle used to transport refrigerated liquids such as argon, carbon dioxide, helium, krypton, neon, nitrogen, and xenon, or mixtures thereof.

(6) In addition to the internal self-closing stop valve, each filling and discharge line must be fitted with a stop valve located in the line between the internal self-closing stop valve and the hose connection. A back flow check valve or excess flow valve may not be used to satisfy this requirement.

(7) An excess flow valve may be designed with a bypass, not to exceed a 0.1016 centimeter (0.040 inch) diameter opening, to allow equalization of pressure.

(b) *Inlets and discharge outlets on chlorine tanks.* The inlet and discharge outlets on a cargo tank used to transport chlorine must meet the requirements of § 178.337-1(c)(2) and must be fitted with an internal excess flow valve. In addition to the internal excess flow valve, the inlet and discharge outlets must be equipped with an external stop valve (angle valve). Excess flow valves must conform to the standards of The Chlorine Institute, Inc., as follows:

(1) A valve conforming to The Chlorine Institute, Inc., Dwg. 101-7 (IBR, see § 171.7 of this subchapter), must be installed under each liquid angle valve.

(2) A valve conforming to The Chlorine Institute, Inc., Dwg. 106-6 (IBR, see § 171.7 of this subchapter), must be installed under each gas angle valve.

(c) *Discharge outlets on carbon dioxide, refrigerated liquid, cargo tanks.* A discharge outlet on a cargo tank used to transport carbon dioxide, refrigerated liquid is not required to be fitted with an internal self-closing stop valve.

[64 FR 28049, May 24, 1999, as amended at 66 FR 45387, Aug. 28, 2001; 68 FR 19279, Apr. 18, 2003; 68 FR 75753, Dec. 31, 2003]

**§ 178.337-9 Pressure relief devices, piping, valves, hoses, and fittings.**

(a) *Pressure relief devices.* (1) See § 173.315(i) of this subchapter.

(2) On cargo tanks for carbon dioxide or nitrous oxide see § 173.315 (i) (9) and (10) of this subchapter.

(3) Each valve must be designed, constructed, and marked for a rated pressure not less than the cargo tank design pressure at the temperature expected to be encountered.

(b) *Piping, valves, hose, and fittings.* (1) The burst pressure of all piping, pipe fittings, hose and other pressure parts, except for pump seals and pressure relief devices, must be at least 4 times the design pressure of the cargo tank. Additionally, the burst pressure may not be less than 4 times any higher pressure to which each pipe, pipe fitting, hose or other pressure part may be subjected to in service. For chlorine

service, see paragraph (b)(7) of this section.

(2) Pipe joints must be threaded, welded, or flanged. If threaded pipe is used, the pipe and fittings must be Schedule 80 weight or heavier, except for sacrificial devices. Malleable metal, stainless steel, or ductile iron must be used in the construction of primary valve body parts and fittings used in liquid filling or vapor equalization. Stainless steel may be used for internal components such as shutoff discs and springs except where incompatible with the lading to be transported. Where copper tubing is permitted, joints must be brazed or be of equally strong metal union type. The melting point of the brazing material may not be lower than 538 °C (1,000 °F). The method of joining tubing may not reduce the strength of the tubing.

(3) Each hose coupling must be designed for a pressure of at least 120 percent of the hose design pressure and so that there will be no leakage when connected.

(4) Piping must be protected from damage due to thermal expansion and contraction, jarring, and vibration. Slip joints are not authorized for this purpose.

(5) [Reserved]

(6) Cargo tank manufacturers and fabricators must demonstrate that all piping, valves, and fittings on a cargo tank are free from leaks. To meet this requirement, the piping, valves, and fittings must be tested after installation at not less than 80 percent of the design pressure marked on the cargo tank.

(7) A hose assembler must:

(i) Permanently mark each hose assembly with a unique identification number.

(ii) Demonstrate that each hose assembly is free from leaks by performing the tests and inspections in § 180.416(f) of this subchapter.

(iii) Mark each hose assembly with the month and year of its original pressure test.

(8) *Chlorine cargo tanks.* Angle valves on cargo tanks intended for chlorine service must conform to the standards of the Chlorine Institute, Inc., Dwg. 104-8 or "Section 3, Pamphlet 166, Angle Valve Guidelines for Chlorine

Bulk Transportation.” (IBR, see §171.7 of this subchapter). Before installation, each angle valve must be tested for leakage at not less than 225 psig using dry air or inert gas.

(c) *Marking inlets and outlets.* Except for gauging devices, thermometer wells, and pressure relief valves, each cargo tank inlet and outlet must be marked “liquid” or “vapor” to designate whether it communicates with liquid or vapor when the cargo tank is filled to the maximum permitted filling density. A filling line that communicates with vapor may be marked “spray-fill” instead of “vapor.”

(d) *Refrigeration and heating coils.* (1) Refrigeration and heating coils must be securely anchored with provisions for thermal expansion. The coils must be pressure tested externally to at least the cargo tank test pressure, and internally to either the tank test pressure or twice the working pressure of the heating/refrigeration system, whichever is higher. A cargo tank may not be placed in service if any leakage occurs or other evidence of damage is found. The refrigerant or heating medium to be circulated through the coils must not be capable of causing any adverse chemical reaction with the cargo tank lading in the event of leakage. The unit furnishing refrigeration may be mounted on the motor vehicle.

(2) Where any liquid susceptible to freezing, or the vapor of any such liquid, is used for heating or refrigeration, the heating or refrigeration system shall be arranged to permit complete drainage.

[Order 59-B, 30 FR 580, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §178.337-9, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### **§178.337-10 Accident damage protection.**

(a) All valves, fittings, pressure relief devices, and other accessories to the tank proper shall be protected in accordance with paragraph (b) of this section against such damage as could be caused by collision with other vehicles or objects, jack-knifing and overturning. In addition, pressure relief

valves shall be so protected that in the event of overturn of the vehicle onto a hard surface, their opening will not be prevented and their discharge will not be restricted.

(b) The protective devices or housing must be designed to withstand static loading in any direction equal to twice the weight of the tank and attachments when filled with the lading, using a safety factor of not less than four, based on the ultimate strength of the material to be used, without damage to the fittings protected, and must be made of metal at least  $\frac{3}{16}$ -inch thick.

(c) *Rear-end tank protection.* Rear-end tank protection devices must:

(1) Consist of at least one rear bumper designed to protect the cargo tank and all valves, piping and fittings located at the rear of the cargo tank from damage that could result in loss of lading in the event of a rear end collision. The bumper design must transmit the force of the collision directly to the chassis of the vehicle. The rear bumper and its attachments to the chassis must be designed to withstand a load equal to twice the weight of the loaded cargo tank motor vehicle and attachments, using a safety factor of four based on the tensile strength of the materials used, with such load being applied horizontally and parallel to the major axis of the cargo tank. The rear bumper dimensions must also meet the requirements of §393.86 of this title; or

(2) Conform to the requirements of §178.345-8(d).

(d) *Chlorine tanks.* A chlorine tank must be equipped with a protective housing and a manway cover to permit the use of standard emergency kits for controlling leaks in fittings on the dome cover plate. For tanks manufactured on or after October 1, 2009, the housing and manway cover must conform to the Chlorine Institute, Inc., Dwg. 137-5 (IBR, see §171.7 of this subchapter).

(e) *Piping and fittings.* Piping and fittings must be grouped in the smallest practicable space and protected from damage as required in this section.

(f) *Shear section.* A shear section or sacrificial device is required for the

## § 178.337-11

valves specified in the following locations:

(1) A section that will break under strain must be provided adjacent to or outboard of each valve specified in § 178.337-8(a)(3) and (4).

(2) Each internal self-closing stop valve, excess flow valve, and check valve must be protected by a shear section or other sacrificial device. The sacrificial device must be located in the piping system outboard of the stop valve and within the accident damage protection to prevent any accidental loss of lading. The failure of the sacrificial device must leave the protected lading protection device and its attachment to the cargo tank wall intact and capable of retaining product.

[Order 59-B, 30 FR 581, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 178.337-10, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

## § 178.337-11 Emergency discharge control.

(a) *Emergency discharge control equipment.* Emergency discharge control equipment must be installed in a liquid discharge line as specified by product and service in § 173.315(n) of this subchapter. The performance and certification requirements for emergency discharge control equipment are specified in § 173.315(n) of this subchapter and are not a part of the cargo tank motor vehicle certification made under this specification.

(b) *Engine fuel lines.* On a truck-mounted cargo tank, emergency discharge control equipment is not required on an engine fuel line of not more than ¾ NPT equipped with a valve having an integral excess flow valve or excess flow feature.

[64 FR 28050, May 24, 1999]

## § 178.337-12 [Reserved]

## § 178.337-13 Supporting and anchoring.

(a) A cargo tank that is not permanently attached to or integral with a vehicle chassis must be secured by the use of restraining devices designed to prevent relative motion between the

## 49 CFR Ch. I (10-1-08 Edition)

cargo tank and the vehicle chassis when the vehicle is in operation. Such restraining devices must be readily accessible for inspection and maintenance.

(b) On a cargo tank motor vehicle designed and constructed so that the cargo tank constitutes in whole or in part the structural member used in place of a motor vehicle frame, the cargo tank must be supported by external cradles. A cargo tank mounted on a motor vehicle frame must be supported by external cradles or longitudinal members. Where used, the cradles must subtend at least 120 degrees of the shell circumference.

(c) The design calculations of the support elements must satisfy the requirements of § 178.337-3, (a), (b), (c), and (d).

(d) Where any cargo tank support is attached to any part of a cargo tank head, the stresses imposed upon the head must be provided for as required in paragraph (c) of this section.

[68 FR 19280, Apr. 18, 2003]

## § 178.337-14 Gauging devices.

(a) *Liquid level gauging devices.* See § 173.315(h) of this subchapter.

(b) *Pressure gauges.* (1) See § 173.315(h) of this subchapter.

(2) Each cargo tank used in carbon dioxide, refrigerated liquid or nitrous oxide, refrigerated liquid service must be provided with a suitable pressure gauge. A shut-off valve must be installed between the pressure gauge and the cargo tank.

(c) *Orifices.* See § 173.315(h) (3) and (4) of this subchapter.

[Amdt. 178-29, 38 FR 27599, Oct. 5, 1973, as amended by Amdt. 178-89, 54 FR 25018, June 12, 1989; Amdt. 178-118, 61 FR 51340, Oct. 1, 1996]

## § 178.337-15 Pumps and compressors.

(a) Liquid pumps or gas compressors, if used, must be of suitable design, adequately protected against breakage by collision, and kept in good condition. They may be driven by motor vehicle power take-off or other mechanical, electrical, or hydraulic means. Unless they are of the centrifugal type, they

shall be equipped with suitable pressure actuated by-pass valves permitting flow from discharge to suction or to the cargo tank.

(b) A liquid chlorine pump may not be installed on a cargo tank intended for the transportation of chlorine.

[Amdt. 178-89, 54 FR 25018, June 12, 1989, as amended by Amdt. 178-118, 61 FR 51340, Oct. 1, 1996]

#### § 178.337-16 Testing.

(a) *Inspection and tests.* Inspection of materials of construction of the cargo tank and its appurtenances and original test and inspection of the finished cargo tank and its appurtenances must be as required by Section VIII of the ASME Code (IBR, see §171.7 of this subchapter) and as further required by this specification, except that for cargo tanks constructed in accordance with part UHT in Section VIII of the ASME Code the original test pressure must be at least twice the cargo tank design pressure.

(b) *Weld testing and inspection.* (1) Each cargo tank constructed in accordance with part UHT in Section VIII of the ASME Code must be subjected, after postweld heat treatment and hydrostatic tests, to a wet fluorescent magnetic particle inspection to be made on all welds in or on the cargo tank shell and heads both inside and out. The method of inspection must conform to appendix 6 in Section VIII of the ASME Code except that permanent magnets shall not be used.

(2) On cargo tanks of over 3,500 gallons water capacity other than those described in paragraph (b)(1) of this section unless fully radiographed, a test must be made of all welds in or on the shell and heads both inside and outside by either the wet fluorescent magnetic particle method conforming to appendix U in Section VIII of the ASME Code, liquid dye penetrant method, or ultrasonic testing in accordance with appendix 12 in Section VIII of the ASME Code. Permanent magnets must not be used to perform the magnetic particle inspection.

(c) All defects found shall be repaired, the cargo tanks shall then again be postweld heat treated, if such heat treatment was previously per-

formed, and the repaired areas shall again be tested.

[Order 59-B, 30 FR 582, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 178-7, 34 FR 18250, Nov. 14, 1969; Amdt. 178-99, 58 FR 51534, Oct. 1, 1993; Amdt. 178-118, 61 FR 51340, Oct. 1, 1996; 68 FR 75753, Dec. 31, 2003]

#### § 178.337-17 Marking.

(a) *General.* Each cargo tank certified after October 1, 2004 must have a corrosion-resistant metal name plate (ASME Plate) and specification plate permanently attached to the cargo tank by brazing, welding, or other suitable means on the left side near the front, in a place accessible for inspection. If the specification plate is attached directly to the cargo tank wall by welding, it must be welded to the tank before the cargo tank is postweld heat treated.

(1) The plates must be legibly marked by stamping, embossing, or other means of forming letters into the metal of the plate, with the information required in paragraphs (b) and (c) of this section, in addition to that required by the ASME Code, in characters at least 3/16 inch high (parenthetical abbreviations may be used). All plates must be maintained in a legible condition.

(2) Each insulated cargo tank must have additional plates, as described, attached to the jacket in the location specified unless the specification plate is attached to the chassis and has the information required in paragraphs (b) and (c) of this section.

(3) The information required for both the name and specification plate may be displayed on a single plate. If the information required by this section is displayed on a plate required by the ASME, the information need not be repeated on the name and specification plates.

(4) The specification plate may be attached to the cargo tank motor vehicle chassis rail by brazing, welding, or other suitable means on the left side near the front head, in a place accessible for inspection. If the specification plate is attached to the chassis rail, then the cargo tank serial number assigned by the cargo tank manufacturer must be included on the plate.



**§ 178.337-18**

**49 CFR Ch. I (10-1-08 Edition)**

(b) *Name plate.* The following information must be marked on the name plate in accordance with this section:

(1) DOT-specification number MC 331 (DOT MC 331).

(2) Original test date (Orig. Test Date).

(3) MAWP in psig.

(4) Cargo tank design temperature (Design Temp. Range) \_\_\_\_\_ °F to \_\_\_\_\_ °F.

(5) Nominal capacity (Water Cap.), in pounds.

(6) Maximum design density of lading (Max. Lading density), in pounds per gallon.

(7) Material specification number—shell (Shell matl. yyy\*\*\*), where “yyy” is replaced by the alloy designation and “\*\*\*” is replaced by the alloy type.

(8) Material specification number—heads (Head matl. yyy\*\*\*), where “yyy” is replaced by the alloy designation and “\*\*\*” by the alloy type.

(9) Minimum Thickness—shell (Min. Shell-thick.), in inches. When minimum shell thicknesses are not the same for different areas, show (top\_\_\_\_, side\_\_\_\_, bottom\_\_\_\_, in inches).

(10) Minimum thickness—heads (Min. heads thick.), in inches.

(11) Manufactured thickness—shell (Mfd. Shell thick.), top\_\_\_\_, side\_\_\_\_, bottom\_\_\_\_, in inches. (Required when additional thickness is provided for corrosion allowance.)

(12) Manufactured thickness—heads (Mfd. Heads thick.), in inches. (Required when additional thickness is provided for corrosion allowance.)

(13) Exposed surface area, in square feet.

NOTE TO PARAGRAPH (b): When the shell and head materials are the same thickness, they may be combined, (Shell&head matl, yyy\*\*\*).

(c) *Specification plate.* The following information must be marked on the specification plate in accordance with this section:

(1) Cargo tank motor vehicle manufacturer (CTMV mfr.).

(2) Cargo tank motor vehicle certification date (CTMV cert. date).

(3) Cargo tank manufacturer (CT mfr.).

(4) Cargo tank date of manufacture (CT date of mfr.), month and year.

(5) Maximum weight of lading (Max. Payload), in pounds

(6) Lining materials (Lining), if applicable.

(7) Heating system design pressure (Heating sys. press.), in psig, if applicable.

(8) Heating system design temperature (Heating sys. temp.), in °F, if applicable.

(9) Cargo tank serial number, assigned by cargo tank manufacturer (CT serial), if applicable.

NOTE 1 TO PARAGRAPH (c): See § 173.315(a) of this chapter regarding water capacity.

NOTE 2 TO PARAGRAPH (c): When the shell and head materials are the same thickness, they may be combined (Shell & head matl, yyy\*\*\*).

(d) The design weight of lading used in determining the loading in §§ 178.337-3(b), 178.337-10(b) and (c), and 178.337-13(a) and (b), must be shown as the maximum weight of lading marking required by paragraph (c) of this section.

[68 FR 19280, Apr. 18, 2003; 68 FR 52370, Sept. 3, 2003, as amended at 68 FR 57633, Oct. 6, 2003]

**§ 178.337-18 Certification.**

(a) At or before the time of delivery, the cargo tank motor vehicle manufacturer must supply and the owner must obtain, a cargo tank motor vehicle manufacturer's data report as required by Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), and a certificate stating that the completed cargo tank motor vehicle conforms in all respects to Specification MC 331 and the ASME Code. The registration numbers of the manufacturer, the Design Certifying Engineer, and the Registered Inspector, as appropriate, must appear on the certificates (see subpart F, part 107 in subchapter A of this chapter).

(1) For each design type, the certificate must be signed by a responsible official of the manufacturer and a Design Certifying Engineer; and

(2) For each cargo tank motor vehicle, the certificate must be signed by a responsible official of the manufacturer and a Registered Inspector.

(3) When a cargo tank motor vehicle is manufactured in two or more stages, each manufacturer who performs a manufacturing function or portion

thereof on the incomplete cargo tank motor vehicle must provide to the succeeding manufacturer, at or before the time of delivery, a certificate that states the function performed by the manufacturer, including any certificates received from previous manufacturers, Registered Inspectors, and Design Certifying Engineers.

(4) *Specification shortages.* When a cargo tank motor vehicle is manufactured in two or more stages, the manufacturer of the cargo tank must attach the name plate and specification plate as required by § 178.337-17(a) and (b) without the original date of certification stamped on the specification plate. Prior manufacturers must list the specification requirements that are not completed on the Certificate of Compliance. When the cargo tank motor vehicle is brought into full compliance with the applicable specification, the cargo tank motor vehicle manufacturer must have a Registered Inspector stamp the date of certification on the specification plate and issue a Certificate of Compliance to the owner of the cargo tank motor vehicle. The Certificate of Compliance must list the actions taken to bring the cargo tank motor vehicle into full compliance. In addition, the certificate must include the date of certification and the person (manufacturer, carrier or repair organization) accomplishing compliance.

(5) The certificate must state whether or not it includes certification that all valves, piping, and protective devices conform to the requirements of the specification. If it does not so certify, the installer of any such valve, piping, or device shall supply and the owner shall obtain a certificate asserting complete compliance with these specifications for such devices. The certificate, or certificates, will include sufficient sketches, drawings, and other information to indicate the location, make, model, and size of each valve and the arrangement of all piping associated with the cargo tank.

(6) The certificate must contain a statement indicating whether or not the cargo tank was postweld heat treated for anhydrous ammonia as specified in § 178.337-1(f).

(b) The owner shall retain the copy of the data report and certificates and related papers in his files throughout his ownership of the cargo tank motor vehicle and for at least one year thereafter; and in the event of change in ownership, retention by the prior owner of nonfading photographically reproduced copies will be deemed to satisfy this requirement. Each motor carrier using the cargo tank motor vehicle, if not the owner thereof, shall obtain a copy of the data report and certificate and retain them in his files during the time he uses the cargo tank motor vehicle and for at least one year thereafter.

[Order 59-B, 30 FR 583, Jan. 16, 1965. Redesignated at 32 FR 5606, Apr. 5, 1967]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 178.337-18, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

#### **§ 178.338 Specification MC-338; insulated cargo tank motor vehicle.**

##### **§ 178.338-1 General requirements.**

(a) For the purposes of this section—

(1) *Design pressure* means the “MAWP” as used in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), and is the gauge pressure at the top of the tank.

(2) *Design service temperature* means the coldest temperature for which the tank is suitable (see §§ 173.318 (a)(1) and (f) of this subchapter).

(b) Each cargo tank must consist of a suitably supported welded inner vessel enclosed within an outer shell or jacket, with insulation between the inner vessel and outer shell or jacket, and having piping, valves, supports and other appurtenances as specified in this subchapter. For the purpose of this specification, *tank* means inner vessel and *jacket* means either the outer shell or insulation cover.

(c) Each tank must be designed, constructed, certified, and stamped in accordance with Section VIII of the ASME Code.

(d) The exterior surface of the tank must be insulated with a material compatible with the lading.

(1) Each cargo tank must have an insulation system that will prevent the

**§ 178.338-2**

**49 CFR Ch. I (10-1-08 Edition)**

tank pressure from exceeding the pressure relief valve set pressure within the specified holding time when the tank is loaded with the specific cryogenic liquid at the design conditions of—

(i) The specified temperature and pressure of the cryogenic liquid, and

(ii) The exposure of the filled cargo tank to an average ambient temperature of 85 °F.

(2) For a cargo tank used to transport oxygen, the insulation may not sustain combustion in a 99.5 percent oxygen atmosphere at atmospheric pressure when contacted with a continuously heated glowing platinum wire. The cargo tank must be marked in accordance with § 178.338-18(b)(7).

(3) Each vacuum-insulated cargo tank must be provided with a connection for a vacuum gauge to indicate the absolute pressure within the insulation space.

(e) The insulation must be completely covered by a metal jacket. The jacket or the insulation must be so constructed and sealed as to prevent moisture from coming into contact with the insulation (see § 173.318(a)(3) of this subchapter). Minimum metal thicknesses are as follows:

| Type metal               | Jacket evacuated |        | Jacket not evacuated |        |
|--------------------------|------------------|--------|----------------------|--------|
|                          | Gauge            | Inches | Gauge                | Inches |
| Stainless steel .....    | 18               | 0.0428 | 22                   | 0.0269 |
| Low carbon mild steel .. | 12               | 0.0946 | 14                   | 0.0677 |
| Aluminum .....           | .....            | 0.125  | .....                | 0.1000 |

(f) An evacuated jacket must be in compliance with the following requirements:

(1) The jacket must be designed to sustain a minimum critical collapsing pressure of 30 psig.

(2) If the jacket also supports additional loads, such as the weight of the tank and lading, the combined stress, computed according to the formula in § 178.338-3(b), may not exceed 25 percent of the minimum specified tensile strength.

[Amdt. 178-77, 48 FR 27703, June 16, 1983, as amended at 49 FR 24316, June 12, 1984; Amdt. 178-104, 59 FR 49135, Sept. 26, 1994; 66 FR 45387, Aug. 28, 2001; 68 FR 75754, Dec. 31, 2003]

**§ 178.338-2 Material.**

(a) All material used in the construction of a tank and its appurtenances that may come in contact with the lading must be compatible with the lading to be transported. All material used for tank pressure parts must conform to the requirements in Section II of the ASME Code (IBR, see § 171.7 of this subchapter). All material used for evacuated jacket pressure parts must conform to the chemistry and steelmaking practices of one of the material specifications of Section II of the ASME Code or the following ASTM Specifications (IBR, see § 171.7 of this subchapter): A 242, A 441, A 514, A 572, A 588, A 606, A 633, A 715, A 1008/A 1008M, A 1011/A 1011M.

(b) All tie-rods, mountings, and other appurtenances within the jacket and all piping, fittings and valves must be of material suitable for use at the lowest temperature to be encountered.

(c) Impact tests are required on all tank materials, except materials that are excepted from impact testing by the ASME Code, and must be performed using the procedure prescribed in Section VIII of the ASME Code.

(d) The direction of final rolling of the shell material must be the circumferential orientation of the tank shell.

(e) Each tank constructed in accordance with part UHT in Section VIII of the ASME Code must be postweld heat treated as a unit after completion of all welds to the shell and heads. Other tanks must be postweld heat treated as required in Section VIII of the ASME Code. For all tanks the method must be as prescribed in the ASME Code. Welded attachments to pads may be made after postweld heat treatment.

(f) The fabricator shall record the heat and slab numbers and the certified Charpy impact values of each plate used in the tank on a sketch showing the location of each plate in the shell and heads of the tank. A copy of the sketch must be provided to the owner of the cargo tank and a copy must be retained by the fabricator for at least

five years and made available, upon request, to any duly identified representative of the Department.

(Approved by the Office of Management and Budget under control number 2137-0017)

[Amdt. 178-77, 48 FR 27703 and 27713, June 16, 1983, as amended at 49 FR 24316, June 12, 1984; 68 FR 19281, Apr. 18, 2003; 68 FR 75754, Dec. 31, 2003; 70 FR 34076, June 13, 2005]

### § 178.338-3 Structural integrity.

(a) *General requirements and acceptance criteria.* (1) Except as permitted in paragraph (d) of this section, the maximum calculated design stress at any point in the tank may not exceed the lesser of the maximum allowable stress value prescribed in section VIII of the ASME Code, or 25 percent of the tensile strength of the material used.

(2) The relevant physical properties of the materials used in each tank may be established either by a certified test report from the material manufacturer or by testing in conformance with a recognized national standard. In either case, the ultimate tensile strength of the material used in the design may not exceed 120 percent of the minimum ultimate tensile strength specified in either the ASME Code or the ASTM standard to which the material is manufactured.

(3) The maximum design stress at any point in the tank must be calculated separately for the loading conditions described in paragraphs (b), (c), and (d) of this section. Alternate test or analytical methods, or a combination thereof, may be used in lieu of the procedures described in paragraphs (b), (c), and (d) of this section, if the methods are accurate and verifiable.

(4) Corrosion allowance material may not be included to satisfy any of the design calculation requirements of this section.

(b) *Static design and construction.* (1) The static design and construction of each tank must be in accordance with appendix G in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter). The tank design must include calculation of stress due to the design pressure, the weight of lading, the weight of structures supported by the tank wall, and the effect of temperature gradients resulting from lading and ambient temperature extremes.

When dissimilar materials are used, their thermal coefficients must be used in calculation of the thermal stresses.

(2) Stress concentrations in tension, bending, and torsion which occur at pads, cradles, or other supports must be considered in accordance with appendix G in Section VIII of the ASME Code.

(c) Stresses resulting from static and dynamic loadings, or a combination thereof, are not uniform throughout the cargo tank motor vehicle. The following is a simplified procedure for calculating the effective stress in the tank resulting from static and dynamic loadings. The effective stress (the maximum principal stress at any point) must be determined by the following formula:

$$S = 0.5 (S_y + S_x) \pm (0.25(S_y - S_x)^2 + S_z^2)^{0.5}$$

Where:

(1)  $S$  = effective stress at any given point under the most severe combination of static and dynamic loadings that can occur at the same time, in psi.

(2)  $S_y$  = circumferential stress generated by internal and external pressure when applicable, in psi.

(3)  $S_x$  = the net longitudinal stress, in psi, generated by the following loading conditions:

(i) The longitudinal tensile stress generated by internal pressure;

(ii) The tensile or compressive stress generated by the axial load resulting from a decelerative force applied independently to each suspension assembly at the road surface using applicable static loadings specified in § 178.338-13 (b);

(iii) The tensile or compressive stress generated by the bending moment resulting from a decelerative force applied independently to each suspension assembly at the road surface using applicable static loadings specified in § 178.338-13 (b);

(iv) The tensile or compressive stress generated by the axial load resulting from an accelerative force applied to the horizontal pivot of the fifth wheel supporting the vehicle using applicable static loadings specified in § 178.338-13 (b);

(v) The tensile or compressive stress generated by the bending moment resulting from an accelerative force applied to the horizontal pivot of the fifth wheel supporting the vehicle using applicable static loadings specified in § 178.338-13 (b); and

(vi) The tensile or compressive stress generated by a bending moment produced by a vertical force using applicable static loadings specified in § 178.338-13 (b).

(4)  $S_s$  = The following shear stresses that apply, in psi,: The vectorial sum of the applicable shear stresses in the plane under consideration, including direct shear generated by the static vertical loading; direct lateral and torsional shear generated by a lateral accelerative force applied at the road surface, using applicable static loads specified in § 178.338-13 (b)

(d) In order to account for stresses due to impact in an accident, the design calculations for the tank shell and heads must include the load resulting from the design pressure in combination with the dynamic pressure resulting from a longitudinal deceleration of "2g". For this loading condition the stress value used may not exceed the lesser of the yield strength or 75 percent of the ultimate tensile strength of the material of construction. For a cargo tank constructed of stainless steel, the maximum design stress may not exceed 75 percent of the ultimate tensile strength of the type steel used.

(e) The minimum thickness of the shell or heads of the tank must be 0.187 inch for steel and 0.270 inch for aluminum. However, the minimum thickness for steel may be 0.110 inches provided the cargo tank is:

(1) Vacuum insulated, or

(2) Double walled with a load bearing jacket designed to carry a proportionate amount of structural loads prescribed in this section.

(f) Where a tank support is attached to any part of the tank wall, the stresses imposed on the tank wall must meet the requirements in paragraph (a) of this section.

(g) The design, construction and installation of an attachment, appurtenance to the cargo tank or structural support member between the cargo tank and the vehicle or suspension

component or accident protection device must conform to the following requirements:

(1) Structural members, the suspension subframe, accident protection structures and external circumferential reinforcement devices must be used as sites for attachment of appurtenances and other accessories to the cargo tank, when practicable.

(2) A lightweight attachment to the cargo tank wall such as a conduit clip, brakeline clip, skirting structure, lamp mounting bracket, or placard holder must be of a construction having lesser strength than the cargo tank wall materials and may not be more than 72 percent of the thickness of the material to which it is attached. The lightweight attachment may be secured directly to the cargo tank wall if the device is designed and installed in such a manner that, if damaged, it will not affect the lading retention integrity of the tank. A lightweight attachment must be secured to the cargo tank shell or head by a continuous weld or in such a manner as to preclude formation of pockets that may become sites for corrosion. Attachments meeting the requirements of this paragraph are not authorized for cargo tanks constructed under part UHT in Section VIII of the ASME Code.

(3) Except as prescribed in paragraphs (g)(1) and (g)(2) of this section, the welding of any appurtenance the cargo tank wall must be made by attachment of a mounting pad so that there will be no adverse effect upon the lading retention integrity of the cargo tank if any force less than that prescribed in paragraph (b)(1) of this section is applied from any direction. The thickness of the mounting pad may not be less than that of the shell or head to which it is attached, and not more than 1.5 times the shell or head thickness. However, a pad with a minimum thickness of 0.187 inch may be used when the shell or head thickness is over 0.187 inch. If weep holes or tell-tale holes are used, the pad must be drilled or punched at the lowest point before it is welded to the tank. Each pad must:

(i) Be fabricated from material determined to be suitable for welding to both the cargo tank material and the

material of the appurtenance or structural support member; a Design Certifying Engineer must make this determination considering chemical and physical properties of the materials and must specify filler material conforming to the requirements in Section IX of the ASME Code (IBR, see § 171.7 of this subchapter).

(ii) Be preformed to an inside radius no greater than the outside radius of the cargo tank at the attachment location.

(iii) Extend at least 2 inches in each direction from any point of attachment of an appurtenance or structural support member. This dimension may be measured from the center of the attached structural member.

(iv) Have rounded corners, or otherwise be shaped in a manner to minimize stress concentrations on the shell or head.

(v) Be attached by continuous fillet welding. Any fillet weld discontinuity may only be for the purpose of preventing an intersection between the fillet weld and a tank or jacket seam weld.

[Amdt. 178-89, 55 FR 37057, Sept. 7, 1990, as amended by Amdt. 178-89, 56 FR 27876, June 17, 1991; 56 FR 46354, Sept. 11, 1991; 68 FR 19281, Apr. 18, 2003; 68 FR 57633, Oct. 6, 2003; 68 FR 75754, Dec. 31, 2003]

#### § 178.338-4 Joints.

(a) All joints in the tank, and in the jacket if evacuated, must be as prescribed in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), except that a butt weld with one plate edge offset is not authorized.

(b) Welding procedure and welder performance tests must be made in accordance with Section IX of the ASME Code. Records of the qualification must be retained by the tank manufacturer for at least five years and must be made available, upon request, to any duly identified representative of the Department, or the owner of the cargo tank.

(c) All longitudinal welds in tanks and load bearing jackets must be located so as not to intersect nozzles or supports other than load rings and stiffening rings.

(d) Substructures must be properly fitted before attachment and the weld-

ing sequence must minimize stresses due to shrinkage of welds.

(e) Filler material containing more than 0.05 percent vanadium may not be used with quenched and tempered steel.

(f) All tank nozzle-to-shell and nozzle-to-head welds must be full penetration welds.

(Approved by the Office of Management and Budget under control number 2137-0017)

[Amdt. 178-77, 48 FR 27704 and 27713, June 16, 1983, as amended at 49 FR 24316, June 12, 1984; 68 FR 75754, Dec. 31, 2003]

#### § 178.338-5 Stiffening rings.

(a) A tank is not required to be provided with stiffening rings, except as prescribed in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter).

(b) If a jacket is evacuated, it must be constructed in compliance with § 178.338-1(f). Stiffening rings may be used to meet these requirements.

[Amdt. 178-77, 48 FR 27704, June 16, 1983, as amended at 68 FR 75754, Dec. 31, 2003]

#### § 178.338-6 Manholes.

(a) Each tank in oxygen service must be provided with a manhole as prescribed in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter).

(b) Each tank having a manhole must be provided with a means of entrance and exit through the jacket, or the jacket must be marked to indicate the manway location on the tank.

(c) A manhole with a bolted closure may not be located on the front head of the tank.

[Amdt. 178-77, 48 FR 27704, June 16, 1983, as amended at 49 FR 24316, June 12, 1984; 68 FR 75754, Dec. 31, 2003]

#### § 178.338-7 Openings.

(a) The inlet to the liquid product discharge opening of each tank intended for flammable ladings must be at the bottom centerline of the tank.

(b) If the leakage of a single valve, except a pressure relief valve, pressure control valve, full trycock or gas phase manual vent valve, would permit loss of flammable material, an additional closure that is leak tight at the tank

## § 178.338-8

## 49 CFR Ch. I (10-1-08 Edition)

design pressure must be provided out-board of such valve.

[Amdt. 178-77, 48 FR 27704, June 16, 1983]

### § 178.338-8 Pressure relief devices, piping, valves, and fittings.

(a) *Pressure relief devices.* Each tank pressure relief device must be designed, constructed, and marked in accordance with § 173.318(b) of this subchapter.

(b) *Piping, valves, and fittings.* (1) The burst pressure of all piping, pipe fittings, hoses and other pressure parts, except for pump seals and pressure relief devices, must be at least 4 times the design pressure of the tank. Additionally, the burst pressure may not be less than 4 times any higher pressure to which each pipe, pipe fitting, hose or other pressure part may be subjected to in service.

(2) Pipe joints must be threaded, welded or flanged. If threaded pipe is used, the pipe and fittings must be Schedule 80 weight or heavier. Malleable metals must be used in the construction of valves and fittings. Where copper tubing is permitted, joints shall be brazed or be of equally strong metal union type. The melting point of the brazing materials may not be lower than 1000 °F. The method of joining tubing may not reduce the strength of the tubing, such as by the cutting of threads.

(3) Each hose coupling must be designed for a pressure of at least 120 percent of the hose design pressure and so that there will be no leakage when connected.

(4) Piping must be protected from damage due to thermal expansion and contraction, jarring, and vibration. Slip joints are not authorized for this purpose.

(5) All piping, valves and fittings on a cargo tank must be proved free from leaks. This requirement is met when such piping, valves, and fittings have been tested after installation with gas or air and proved leak tight at not less than the design pressure marked on the cargo tank. This requirement is applicable to all hoses used in a cargo tank, except that hose may be tested before or after installation on the tank.

(6) Each valve must be suitable for the tank design pressure at the tank design service temperature.

(7) All fittings must be rated for the maximum tank pressure and suitable for the coldest temperature to which they will be subjected in actual service.

(8) All piping, valves, and fittings must be grouped in the smallest practicable space and protected from damage as required by § 178.338-10.

(9) When a pressure-building coil is used on a tank designed to handle oxygen or flammable ladings, the vapor connection to that coil must be provided with a valve or check valve as close to the tank shell as practicable to prevent the loss of vapor from the tank in case of damage to the coil. The liquid connection to that coil must also be provided with a valve.

[Amdt. 178-77, 48 FR 27704, June 16, 1983, as amended by Amdt. 178-89, 54 FR 25019, June 12, 1989]

### § 178.338-9 Holding time.

(a) "Holding time" is the time, as determined by testing, that will elapse from loading until the pressure of the contents, under equilibrium conditions, reaches the level of the lowest pressure control valve or pressure relief valve setting.

(b) *Holding time test.* (1) The test to determine holding time must be performed by charging the tank with a cryogenic liquid having a boiling point, at a pressure of one atmosphere, absolute, no lower than the design service temperature of the tank. The tank must be charged to its maximum permitted filling density with that liquid and stabilized to the lowest practical pressure, which must be equal to or less than the pressure to be used for loading. The cargo tank together with its contents must then be exposed to ambient temperature.

(2) The tank pressure and ambient temperature must be recorded at 3-hour intervals until the pressure level of the contents reaches the set-to-discharge pressure of the pressure control valve or pressure relief valve with the lowest setting. This total time lapse in hours represents the measured holding time at the actual average ambient temperature. This measured holding time for the test cryogenic liquid must be adjusted to an equivalent holding time for each cryogenic liquid that is

to be identified on or adjacent to the specification plate, at an average ambient temperature of 85 °F. This is the rated holding time (RHT). The marked rated holding time (MRHT) displayed on or adjacent to the specification plate (see § 178.338-18(c)(10)) may not exceed this RHT.

(c) *Optional test regimen.* (1) If more than one cargo tank is made to the same design, only one cargo tank must be subjected to the full holding time test at the time of manufacture. However, each subsequent cargo tank made to the same design must be performance tested during its first trip. The holding time determined in this test may not be less than 90 percent of the marked rated holding time. This test must be performed in accordance with §§ 173.318(g)(3) and 177.840(h) of this subchapter, regardless of the classification of the cryogenic liquid.

(2) *Same design.* The term “same design” as used in this section means cargo tanks made to the same design type. See § 178.320(a) for definition of “design type”.

(3) For a cargo tank used in nonflammable cryogenic liquid service, in place of the holding time tests prescribed in paragraph (b) of this section, the marked rated holding time (MRHT) may be determined as follows:

(i) While the cargo tank is stationary, the heat transfer rate must be determined by measuring the normal evaporation rate (NER) of the test cryogenic liquid (preferably the lading, where feasible) maintained at approximately one atmosphere. The calculated heat transfer rate must be determined from:

$$q = [n(\Delta h)(85 - t_1)] / [t_s - t_l]$$

Where:

q = calculated heat transfer rate to cargo tank with lading, Btu/hr.

n = normal evaporation rate (NER), which is the rate of evaporation, determined by the test of a test cryogenic liquid in a cargo tank maintained at a pressure of approximately one atmosphere, absolute, lb/hr.

$\Delta h$  = latent heat of vaporization of test fluid at test pressure, Btu/lb.

$t_s$  = average temperature of outer shell during test, °F.

$t_1$  = equilibrium temperature of lading at maximum loading pressure, °F.

$t_l$  = equilibrium temperature of test fluid at one atmosphere, °F.

(ii) The rated holding time (RHT) must be calculated as follows:

$$RHT = [(U_2 - U_1) W] / q$$

Where:

RHT = rated holding time, in hours

$U_1$  and  $U_2$  = internal energy for the combined liquid and vapor lading at the pressure offered for transportation, and the set pressure of the applicable pressure control valve or pressure relief valve, respectively, Btu/lb.

W = total weight of the combined liquid and vapor lading in the cargo tank, pounds.

q = calculated heat transfer rate to cargo tank with lading, Btu/hr.

(iii) The MRHT (see § 178.338-18(b)(9) of this subchapter) may not exceed the RHT.

[Amdt. 178-77, 48 FR 27704, June 16, 1983; 48 FR 50442, Nov. 1, 1983, as amended at 49 FR 24316, June 12, 1984; 49 FR 43965, Nov. 1, 1984; 59 FR 55173, Nov. 3, 1994; Amdt. 178-118, 61 FR 51340, Oct. 1, 1996; 68 FR 57634, Oct. 6, 2003; 71 FR 54397, Sept. 14, 2006]

#### § 178.338-10 Accident damage protection.

(a) All valves, fittings, pressure relief devices and other accessories to the tank proper, which are not isolated from the tank by closed intervening shut-off valves or check valves, must be installed within the motor vehicle framework or within a suitable collision resistant guard or housing, and appropriate ventilation must be provided. Each pressure relief device must be protected so that in the event of the upset of the vehicle onto a hard surface, the device's opening will not be prevented and its discharge will not be restricted.

(b) Each protective device or housing, and its attachment to the vehicle structure, must be designed to withstand static loading in any direction that it may be loaded as a result of front, rear, side, or sideswipe collision, or the overturn of the vehicle. The static loading shall equal twice the loaded weight of the tank and attachments. A safety factor of four, based on the tensile strength of the material, shall be used. The protective device or the housing must be made of steel at least 3/16-inch thick, or other material of equivalent strength.

(c) *Rear-end tank protection.* Rear-end tank protections devices must:



(1) Consist of at least one rear bumper designed to protect the cargo tank and piping in the event of a rear-end collision. The rear-end tank protection device design must transmit the force of the collision directly to the chassis of the vehicle. The rear-end tank protection device and its attachments to the chassis must be designed to withstand a load equal to twice the weight of the loaded cargo tank and attachments, using a safety factor of four based on the tensile strength of the materials used, with such load being applied horizontally and parallel to the major axis of the cargo tank. The rear-end tank protection device dimensions must meet the requirements of § 393.86 of this title and extend vertically to a height adequate to protect all valves and fittings located at the rear of the cargo tank from damage that could result in loss of lading; or

(2) Conform to the requirements of § 178.345-8(b).

(d) Every part of the loaded cargo tank, and any associated valve, pipe, enclosure, or protective device or structure (exclusive of wheel assemblies), must be at least 14 inches above level ground.

[Amdt. 178-77, 48 FR 27705, June 16, 1983, as amended at 49 FR 24316, June 12, 1984; Amdt. 178-99, 58 FR 51534, Oct. 1, 1993; 68 FR 19282, Apr. 18, 2003; 68 FR 52371, Sept. 3, 2003]

**§ 178.338-11 Discharge control devices.**

(a) Excess-flow valves are not required.

(b) Each liquid filling and liquid discharge line must be provided with a shut-off valve located as close to the tank as practicable. Unless this valve is manually operable at the valve, the line must also have a manual shut-off valve.

(c) Except for a cargo tank that is used to transport argon, carbon dioxide, helium, krypton, neon, nitrogen, xenon, or mixtures thereof, each liquid filling and liquid discharge line must be provided with an on-vehicle remotely controlled self-closing shut-off valve.

(1) If pressure from a reservoir or from an engine-driven pump or compressor is used to open this valve, the control must be of fail-safe design and spring-biased to stop the admission of

such pressure into the cargo tank. If the jacket is not evacuated, the seat of the valve must be inside the tank, in the opening nozzle or flange, or in a companion flange bolted to the nozzle. If the jacket is evacuated, the remotely controlled valve must be located as close to the tank as practicable.

(2) Each remotely controlled shut off valve must be provided with on-vehicle remote means of automatic closure, both mechanical and thermal. One means may be used to close more than one remotely controlled valve. Cable linkage between closures and remote operators must be corrosion resistant and effective in all types of environment and weather. The thermal means must consist of fusible elements actuated at a temperature not exceeding 121 °C (250 °F), or equivalent devices. The loading/unloading connection area is where hoses are connected to the permanent metal piping. The number and location of remote operators and thermal devices shall be as follows:

(i) On a cargo tank motor vehicle over 3,500 gallons water capacity, remote means of automatic closure must be installed at the ends of the cargo tank in at least two diagonally opposite locations. If the loading/unloading connection at the cargo tank is not in the general vicinity of one of these locations, at least one additional thermal device must be installed so that heat from a fire in the loading/unloading connection area will activate the emergency control system.

(ii) On a cargo tank motor vehicle of 3,500 gallons water capacity or less, at least one remote means of automatic closure must be installed on the end of the cargo tank farthest away from the loading/unloading connection area. At least one thermal device must be installed so that heat from a fire in the loading/unloading connection area will activate the emergency control system.

[Amdt. 178-77, 48 FR 27705, June 16, 1983, as amended by Amdt. 178-105, 59 FR 55173, Nov. 3, 1994; 60 FR 17402, Apr. 5, 1995; 68 FR 19282, Apr. 18, 2003]

**§ 178.338-12 Shear section.**

Unless the valve is located in a rear cabinet forward of and protected by the

bumper (see § 178.338-10(c)), the design and installation of each valve, damage to which could result in loss of liquid or vapor, must incorporate a shear section or breakage groove adjacent to, and outboard of, the valve. The shear section or breakage groove must yield or break under strain without damage to the valve that would allow the loss of liquid or vapor. The protection specified in § 178.338-10 is not a substitute for a shear section or breakage groove.

[Amdt. 178-77, 49 FR 24316, June 12, 1984]

#### § 178.338-13 Supporting and anchoring.

(a) On a cargo tank motor vehicle designed and constructed so that the cargo tank constitutes in whole or in part the structural member used in place of a motor vehicle frame, the cargo tank or the jacket must be supported by external cradles or by load rings. For a cargo tank mounted on a motor vehicle frame, the tank or jacket must be supported by external cradles, load rings, or longitudinal members. If cradles are used, they must subtend at least 120 degrees of the cargo tank circumference. The design calculations for the supports and load-bearing tank or jacket, and the support attachments must include beam stress, shear stress, torsion stress, bending moment, and acceleration stress for the loaded vehicle as a unit, using a safety factor of four, based on the tensile strength of the material, and static loading that uses the weight of the cargo tank and its attachments when filled to the design weight of the lading (see appendix G in Section VIII of the ASME Code) (IBR, see § 171.7 of this subchapter), multiplied by the following factors. The effects of fatigue must also be considered in the calculations. Minimum static loadings must be as follows:

- (1) For a vacuum-insulated cargo tank—
  - (i) Vertically downward of 2;
  - (ii) Vertically upward of 2;
  - (iii) Longitudinally of 2; and
  - (iv) Laterally of 2.
- (2) For any other insulated cargo tank—
  - (i) Vertically downward of 3;
  - (ii) Vertically upward of 2;
  - (iii) Longitudinally of 2; and

- (iv) Laterally of 2.

(b) When a loaded tank is supported within the vacuum jacket by structural members, the design calculations for the tank and its structural members must be based on a safety factor of four and the tensile strength of the material at ambient temperature. The enhanced tensile strength of the material at actual operating temperature may be substituted for the tensile strength at ambient temperature to the extent recognized in the ASME Code for static loadings. Static loadings must take into consideration the weight of the tank and the structural members when the tank is filled to the design weight of lading (see Appendix G of Section VIII, Division 1 of the ASME Code), multiplied by the following factors. Static loadings must take into consideration the weight of the tank and the structural members when the tank is filled to the design weight of lading (see appendix G in Section VIII of the ASME Code), multiplied by the following factors. When load rings in the jacket are used for supporting the tank, they must be designed to carry the fully loaded tank at the specified static loadings, plus external pressure. Minimum static loadings must be as follows:

- (1) Vertically downward of 2;
- (2) Vertically upward of 1½;
- (3) Longitudinally of 1½; and, (4) Laterally of 1½.

[68 FR 19282, Apr. 18, 2003, as amended at 68 FR 75754, Dec. 31, 2003]

#### § 178.338-14 Gauging devices.

(a) *Liquid level gauging devices.* (1) Unless a cargo tank is intended to be filled by weight, it must be equipped with one or more gauging devices, which accurately indicate the maximum permitted liquid level at the loading pressure, in order to provide a minimum of two percent outage below the inlet of the pressure control valve or pressure relief valve at the condition of incipient opening of that valve. A fixed-length dip tube, a fixed trycock line, or a differential pressure liquid level gauge must be used as the primary control for filling. Other gauging devices, except gauge glasses, may be used, but not as the primary control for filling.

(2) The design pressure of each liquid level gauging device must be at least that of the tank.

(3) If a fixed length dip tube or trycock line gauging device is used, it must consist of a pipe or tube of small diameter equipped with a valve at or near the jacket and extending into the cargo tank to a specified filling height. The fixed height at which the tube ends in the cargo tank must be such that the device will function when the liquid reaches the maximum level permitted in loading.

(4) The liquid level gauging device used as a primary control for filling must be designed and installed to accurately indicate the maximum filling level at the point midway of the tank both longitudinally and laterally.

(b) *Pressure gauges.* Each cargo tank must be provided with a suitable pressure gauge indicating the lading pressure and located on the front of the jacket so it can be read by the driver in the rear view mirror. Each gauge must have a reference mark at the cargo tank design pressure or the set pressure of the pressure relief valve or pressure control valve, whichever is lowest.

(c) *Orifices.* All openings for dip tube gauging devices and pressure gauges in flammable cryogenic liquid service must be restricted at or inside the jacket by orifices no larger than 0.060-inch diameter. Trycock lines, if provided, may not be greater than ½-inch nominal pipe size.

[Amdt. 178-77, 48 FR 27706, June 16, 1983, as amended at 49 FR 24317, June 12, 1984]

#### § 178.338-15 Cleanliness.

A cargo tank constructed for oxygen service must be thoroughly cleaned to remove all foreign material in accordance with CGA G-4.1 (IBR, see § 171.7 of this subchapter). All loose particles from fabrication, such as weld beads, dirt, grinding wheel debris, and other loose materials, must be removed prior to the final closure of the manhole of the tank. Chemical or solvent cleaning with a material compatible with the intending lading must be performed to remove any contaminants likely to react with the lading.

[68 FR 75755, Dec. 31, 2003]

#### § 178.338-16 Inspection and testing.

(a) *General.* The material of construction of a tank and its appurtenances must be inspected for conformance to Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter). The tank must be subjected to either a hydrostatic or pneumatic test. The test pressure must be one and one-half times the sum of the design pressure, plus static head of lading, plus 101.3 kPa (14.7 psi) if subjected to external vacuum, except that for tanks constructed in accordance with Part UHT in Section VIII of the ASME Code the test pressure must be twice the design pressure.

(b) *Additional requirements for pneumatic test.* A pneumatic test may be used in place of the hydrostatic test. Due regard for protection of all personnel should be taken because of the potential hazard involved in a pneumatic test. The pneumatic test pressure in the tank must be reached by gradually increasing the pressure to one-half of the test pressure. Thereafter, the test pressure must be increased in steps of approximately one-tenth of the test pressure until the required test pressure has been reached. Then the pressure must be reduced to a value equal to four-fifths of the test pressure and held for a sufficient time to permit inspection of the cargo tank for leaks.

(c) *Weld inspection.* All tank shell or head welds subject to pressure shall be radiographed in accordance with Section VIII of the ASME Code. A tank which has been subjected to inspection by the magnetic particle method, the liquid penetrant method, or any method involving a material deposit on the interior tank surface, must be cleaned to remove any such residue by scrubbing or equally effective means, and all such residue and cleaning solution must be removed from the tank prior to final closure of the tank.

(d) *Defect repair.* All cracks and other defects must be repaired as prescribed in Section VIII of the ASME Code. The welder and the welding procedure must be qualified in accordance with Section IX of the ASME Code (IBR, see § 171.7 of this subchapter). After repair, the tank must again be postweld heat-treated, if such heat treatment was previously

performed, and the repaired areas must be retested.

(e) Verification must be made of the interior cleanliness of a tank constructed for oxygen service by means that assure that all contaminants that are likely to react with the lading have been removed as required by § 178.338-15.

[Amdt. 178-77, 48 FR 27706, June 16, 1983, as amended at 49 FR 24317, June 12, 1984; 49 FR 42736, Oct. 24, 1984; 68 FR 75755, Dec. 31, 2003]

#### § 178.338-17 Pumps and compressors.

(a) *Liquid pumps and gas compressors*, if used, must be of suitable design, adequately protected against breakage by collision, and kept in good condition. They may be driven by motor vehicle power take-off or other mechanical, electrical, or hydraulic means. Unless they are of the centrifugal type, they shall be equipped with suitable pressure actuated by-pass valves permitting flow from discharge to suction to the tank.

(b) A valve or fitting made of aluminum with internal rubbing or abrading aluminum parts that may come in contact with oxygen (cryogenic liquid) may not be installed on any cargo tank used to transport oxygen (cryogenic liquid) unless the parts are anodized in accordance with ASTM B 580 (IBR, see § 171.7 of this subchapter).

[Amdt. 178-89, 54 FR 25020, June 12, 1989, as amended at 55 FR 37058, Sept. 7, 1990; 67 FR 61016, Sept. 27, 2002; 68 FR 75755, Dec. 31, 2003]

#### § 178.338-18 Marking.

(a) *General*. Each cargo tank certified after October 1, 2004 must have a corrosion-resistant metal name plate (ASME Plate) and specification plate permanently attached to the cargo tank by brazing, welding, or other suitable means on the left side near the front, in a place accessible for inspection. If the specification plate is attached directly to the cargo tank wall by welding, it must be welded to the tank before the cargo tank is postweld heat treated.

(1) The plates must be legibly marked by stamping, embossing, or other means of forming letters into the metal of the plate, with the information required in paragraphs (b) and (c) of this section, in addition to that re-

quired by Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), in characters at least 3/16 inch high (parenthetical abbreviations may be used). All plates must be maintained in a legible condition.

(2) Each insulated cargo tank must have additional plates, as described, attached to the jacket in the location specified unless the specification plate is attached to the chassis and has the information required in paragraphs (b) and (c) of this section.

(3) The information required for both the name and specification plate may be displayed on a single plate. If the information required by this section is displayed on a plate required by Section VIII of the ASME Code, the information need not be repeated on the name and specification plates.

(4) The specification plate may be attached to the cargo tank motor vehicle chassis rail by brazing, welding, or other suitable means on the left side near the front head, in a place accessible for inspection. If the specification plate is attached to the chassis rail, then the cargo tank serial number assigned by the cargo tank manufacturer must be included on the plate.

(b) *Name plate*. The following information must be marked on the name plate in accordance with this section:

(1) DOT-specification number MC 338 (DOT MC 338).

(2) Original test date (Orig, Test Date).

(3) MAWP in psig.

(4) Cargo tank test pressure (Test P), in psig.

(5) Cargo tank design temperature (Design Temp. Range) \_\_\_\_ °F to \_\_\_\_ °F.

(6) Nominal capacity (Water Cap.), in pounds.

(7) Maximum design density of lading (Max. Lading density), in pounds per gallon.

(8) Material specification number—shell (Shell matl. yyy \* \* \*), where “yyy” is replaced by the alloy designation and “\* \* \*” is replaced by the alloy type.

(9) Material specification number—heads (Head matl. yyy \* \* \*), where “yyy” is replaced by the alloy designation and “\* \* \*” by the alloy type.

## § 178.338-19

NOTE: When the shell and heads materials are the same thickness, they may be combined, (Shell & head matl, yyy \* \* \*).

(10) Weld material (Weld matl.).

(11) Minimum Thickness-shell (Min. Shell-thick), in inches. When minimum shell thicknesses are not the same for different areas, show (top \_\_\_\_, side \_\_\_\_, bottom \_\_\_\_, in inches).

(12) Minimum thickness-heads (Min heads thick.), in inches.

(13) Manufactured thickness-shell (Mfd. Shell thick.), top \_\_\_\_, side \_\_\_\_, bottom \_\_\_\_, in inches. (Required when additional thickness is provided for corrosion allowance.)

(14) Manufactured thickness-heads (Mfd. Heads thick.), in inches. (Required when additional thickness is provided for corrosion allowance.)

(15) Exposed surface area, in square feet.

(c) *Specification plate.* The following information must be marked on the specification plate in accordance with this section:

(1) Cargo tank motor vehicle manufacturer (CTMV mfr.).

(2) Cargo tank motor vehicle certification date (CTMV cert. date).

(3) Cargo tank manufacturer (CT mfr.).

(4) Cargo tank date of manufacture (CT date of mfr.), month and year.

(5) Maximum weight of lading (Max. Payload), in pounds.

(6) Maximum loading rate in gallons per minute (Max. Load rate, GPM).

(7) Maximum unloading rate in gallons per minute (Max Unload rate).

(8) Lining materials (Lining), if applicable.

(9) "Insulated for oxygen service" or "Not insulated for oxygen service" as appropriate.

(10) Marked rated holding time for at least one cryogenic liquid, in hours, and the name of that cryogenic liquid (MRHT \_\_\_\_ hrs, name of cryogenic liquid). Marked rated holding marking for additional cryogenic liquids may be displayed on or adjacent to the specification plate.

(11) Cargo tank serial number (CT serial), as assigned by cargo tank manufacturer, if applicable.

NOTE 1 TO PARAGRAPH (c): See § 173.315(a) of this chapter regarding water capacity.

## 49 CFR Ch. I (10-1-08 Edition)

NOTE 2 TO PARAGRAPH (c): When the shell and head materials are the same thickness, they may be combined (Shell & head matl, yyy\*\*\*).

(d) The design weight of lading used in determining the loading in §§ 178.338-3 (b), 178.338-10 (b) and (c), and 178.338-13 (b), must be shown as the maximum weight of lading marking required by paragraph (c) of this section.

[68 FR 19283, Apr. 18, 2003, as amended at 68 FR 57634, Oct. 6, 2003; 68 FR 75755, Dec. 31, 2003]

### § 178.338-19 Certification.

(a) At or before the time of delivery, the manufacturer of a cargo tank motor vehicle shall furnish to the owner of the completed vehicle the following:

(1) The tank manufacturer's data report as required by the ASME Code (IBR, see § 171.7 of this subchapter), and a certificate bearing the manufacturer's vehicle serial number stating that the completed cargo tank motor vehicle conforms to all applicable requirements of Specification MC 338, including Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter) in effect on the date (month, year) of certification. The registration numbers of the manufacturer, the Design Certifying Engineer, and the Registered Inspector, as appropriate, must appear on the certificates (see subpart F, part 107 in subchapter B of this chapter).

(2) A photograph, pencil rub, or other facsimile of the plates required by paragraphs (a) and (b) of § 178.338-18.

(b) In the case of a cargo tank vehicle manufactured in two or more stages, each manufacturer who performs a manufacturing operation on the incomplete vehicle or portion thereof shall furnish to the succeeding manufacturer, at or before the time of delivery, a certificate covering the particular operation performed by that manufacturer, and any certificates received from previous manufacturers, Registered Inspectors, and Design Certifying Engineers. The certificates must include sufficient sketches, drawings, and other information to indicate the location, make, model and size of each valve and the arrangement of all piping associated with the tank. Each certificate must be signed by an official of

the manufacturing firm responsible for the portion of the complete cargo tank vehicle represented thereby, such as basic tank fabrication, insulation, jacket, or piping. The final manufacturer shall furnish the owner with all certificates, as well as the documents required by paragraph (a) of this section.

(c) The owner shall retain the data report, certificates, and related papers throughout his ownership of the cargo tank. In the event of change of ownership, the prior owner shall retain non-fading photographically reproduced copies of these documents for at least one year. Each operator using the cargo tank vehicle, if not the owner thereof, shall obtain a copy of the data report and the certificate or certificates and retain them during the time he uses the cargo tank and for at least one year thereafter.

(Approved by the Office of Management and Budget under control number 2137-0017)

[Amdt. 178-77, 48 FR 27707 and 27713, June 16, 1983, as amended by Amdt. 178-89, 55 FR 37058, Sept. 7, 1990; Amdt. 178-99, 58 FR 51534, Oct. 1, 1993; 62 FR 51561, Oct. 1, 1997; 68 FR 75755, Dec. 31, 2003]

#### §§ 178.340-178.343 [Reserved]

#### § 178.345 General design and construction requirements applicable to Specification DOT 406 (§178.346), DOT 407 (§178.347), and DOT 412 (§178.348) cargo tank motor vehicles.

##### § 178.345-1 General requirements.

(a) Specification DOT 406, DOT 407 and DOT 412 cargo tank motor vehicles must conform to the requirements of this section in addition to the requirements of the applicable specification contained in §§ 178.346, 178.347 or 178.348.

(b) All specification requirements are minimum requirements.

(c) *Definitions.* See § 178.320(a) for the definition of certain terms used in §§ 178.345, 178.346, 178.347, and 178.348. In addition, the following definitions apply to §§ 178.345, 178.346, 178.347, and 178.348:

*Appurtenance* means any cargo tank accessory attachment that has no lading retention or containment function and provides no structural support to the cargo tank.

*Baffle* means a non-liquid-tight transverse partition device that deflects, checks or regulates fluid motion in a tank.

*Bulkhead* means a liquid-tight transverse closure at the ends of or between cargo tanks.

*Charging line* means a hose, tube, pipe, or similar device used to pressurize a tank with material other than the lading.

*Companion flange* means one of two mating flanges where the flange faces are in contact or separated only by a thin leak sealing gasket and are secured to one another by bolts or clamps.

*Connecting structure* means the structure joining two cargo tanks.

*Constructed and certified in accordance with the ASME Code* means the cargo tank is constructed and stamped in accordance with the ASME Code, and is inspected and certified by an Authorized Inspector.

*Constructed in accordance with the ASME Code* means the cargo tank is constructed in accordance with the ASME Code with the authorized exceptions (see §§ 178.346, 178.347, and 178.348) and is inspected and certified by a Registered Inspector.

*External self-closing stop-valve* means a self-closing stop-valve designed so that the self-stored energy source is located outside the cargo tank and the welded flange.

*Extreme dynamic loading* means the maximum single-acting loading a cargo tank motor vehicle may experience during its expected life, excluding accident loadings.

*Flange* means the structural ring for guiding or attachment of a pipe or fitting with another flange (companion flange), pipe, fitting or other attachment.

*Inspection pressure* means the pressure used to determine leak tightness of the cargo tank when testing with pneumatic pressure.

*Internal self-closing stop-valve* means a self-closing stop-valve designed so that the self-stored energy source is located inside the cargo tank or cargo tank sump, or within the welded flange, and the valve seat is located within the cargo tank or within one inch of the

external face of the welded flange or sump of the cargo tank.

*Lading* means the hazardous material contained in a cargo tank.

*Loading/unloading connection* means the fitting in the loading/unloading line farthest from the loading/unloading outlet to which the loading/unloading hose or device is attached.

*Loading/unloading outlet* means the cargo tank outlet used for normal loading/unloading operations.

*Loading/unloading stop-valve* means the stop valve farthest from the cargo tank loading/unloading outlet to which the loading/unloading connection is attached.

*MAWP.* See § 178.320(a).

*Multi-specification cargo tank motor vehicle* means a cargo tank motor vehicle equipped with two or more cargo tanks fabricated to more than one cargo tank specification.

*Normal operating loading* means the loading a cargo tank motor vehicle may be expected to experience routinely in operation.

*Nozzle* means the subassembly consisting of a pipe or tubular section with or without a welded or forged flange on one end.

*Outlet* means any opening in the shell or head of a cargo tank, (including the means for attaching a closure), except that the following are not outlets: A threaded opening securely closed during transportation with a threaded plug or a threaded cap, a flanged opening securely closed during transportation with a bolted or welded blank flange, a manhole, or gauging devices, thermometer wells, and safety relief devices.

*Outlet stop-valve* means the stop-valve at the cargo tank loading/unloading outlet.

*Pipe coupling* means a fitting with internal threads on both ends.

*Rear bumper* means the structure designed to prevent a vehicle or object from under-riding the rear of a motor vehicle. See § 393.86 of this title.

*Rear-end tank protection device* means the structure designed to protect a cargo tank and any lading retention piping or devices in case of a rear end collision.

*Sacrificial device* means an element, such as a shear section, designed to fail

under a load in order to prevent damage to any lading retention part or device. The device must break under strain at no more than 70 percent of the strength of the weakest piping element between the cargo tank and the *sacrificial device*. Operation of the *sacrificial device* must leave the remaining piping and its attachment to the cargo tank intact and capable of retaining lading.

*Self-closing stop-valve* means a stop-valve held in the closed position by means of self-stored energy, which opens only by application of an external force and which closes when the external force is removed.

*Shear section* means a sacrificial device fabricated in such a manner as to abruptly reduce the wall thickness of the adjacent piping or valve material by at least 30 percent.

*Shell* means the circumferential portion of a cargo tank defined by the basic design radius or radii excluding the closing heads.

*Stop-valve* means a valve that stops the flow of lading.

*Sump* means a protrusion from the bottom of a cargo tank shell designed to facilitate complete loading and unloading of lading.

*Tank* means a container, consisting of a shell and heads, that forms a pressure tight vessel having openings designed to accept pressure tight fittings or closures, but excludes any appurtenances, reinforcements, fittings, or closures.

*Test pressure* means the pressure to which a tank is subjected to determine pressure integrity.

*Toughness of material* means the capability of a material to absorb the energy represented by the area under the stress strain curve (indicating the energy absorbed per unit volume of the material) up to the point of rupture.

*Vacuum cargo tank* means a cargo tank that is loaded by reducing the pressure in the cargo tank to below atmospheric pressure.

*Variable specification cargo tank* means a cargo tank that is constructed in accordance with one specification, but which may be altered to meet another specification by changing relief

device, closures, lading discharge devices, and other lading retention devices.

*Void* means the space between tank heads or bulkheads and a connecting structure.

*Welded flange* means a flange attached to the tank by a weld joining the tank shell to the cylindrical outer surface of the flange, or by a fillet weld joining the tank shell to a flange shaped to fit the shell contour.

(d) A manufacturer of a cargo tank must hold a current ASME certificate of authorization and must be registered with the Department in accordance with part 107, subpart F of this chapter.

(e) All construction must be certified by an Authorized Inspector or by a Registered Inspector as applicable to the cargo tank.

(f) Each cargo tank must be designed and constructed in conformance with the requirements of the applicable cargo tank specification. Each DOT 412 cargo tank with a "MAWP" greater than 15 psig, and each DOT 407 cargo tank with a maximum allowable working pressure greater than 35 psig must be "constructed and certified in conformance with Section VIII of the ASME Code" (IBR, see §171.7 of this subchapter) except as limited or modified by the applicable cargo tank specification. Other cargo tanks must be "constructed in accordance with Section VIII of the ASME Code," except as limited or modified by the applicable cargo tank specification.

(g) Requirements relating to parts and accessories on motor vehicles, which are contained in part 393 of the Federal Motor Carrier Safety Regulations of this title, are incorporated into these specifications.

(h) Any additional requirements prescribed in part 173 of this subchapter that pertain to the transportation of a specific lading are incorporated into these specifications.

(i) *Cargo tank motor vehicle composed of multiple cargo tanks.* (1) A cargo tank motor vehicle composed of more than one cargo tank may be constructed with the cargo tanks made to the same specification or to different specifications. Each cargo tank must conform in all respects with the specification for which it is certified.

(2) The strength of the connecting structure joining multiple cargo tanks in a cargo tank motor vehicle must meet the structural design requirements in §178.345-3. Any void within the connecting structure must be vented to the atmosphere and have a drain located on the bottom centerline. Each drain must be accessible and must be kept open at all times. The drain in any void within the connecting structure of a carbon steel, self-supporting cargo tank may be either a single drain of at least 1.0 inch diameter, or two or more drains of at least 0.5 inch diameter, 6.0 inches apart, one of which is located on the bottom centerline.

(j) *Variable specification cargo tank.* A cargo tank that may be physically altered to conform to another cargo tank specification must have the required physical alterations to convert from one specification to another clearly indicated on the variable specification plate.

[Amdt. 178-89, 54 FR 25020, June 12, 1989, as amended at 55 FR 37058, Sept. 7, 1990; Amdt. 178-105, 59 FR 55173, Nov. 3, 1994; Amdt. 178-118, 61 FR 51340, Oct. 1, 1996; 66 FR 45387, 45389, Aug. 28, 2001; 68 FR 19283, Apr. 18, 2003; 68 FR 52371, Sept. 3, 2003; 68 FR 75755, Dec. 31, 2003; 70 FR 56099, Sept. 23, 2005]

#### § 178.345-2 Material and material thickness.

(a) All material for shell, heads, bulkheads, and baffles must conform to Section II of the ASME Code (IBR, see §171.7 of this subchapter) except as follows:

(1) The following steels are also authorized for cargo tanks "constructed in accordance with the ASME Code", Section VIII.

ASTM A 569  
ASTM A 570  
ASTM A 572  
ASTM A 622  
ASTM A 656  
ASTM A 715  
ASTM A 1008/ A 1008M, ASTM A 1011/A 1011M

(2) Aluminum alloys suitable for fusion welding and conforming with the 0, H32 or H34 tempers of one of the following ASTM specifications may be used for cargo tanks "constructed in accordance with the ASME Code":

ASTM B-209 Alloy 5052  
ASTM B-209 Alloy 5086



### § 178.345-3

ASTM B-209 Alloy 5154  
ASTM B-209 Alloy 5254  
ASTM B-209 Alloy 5454  
ASTM B-209 Alloy 5652

All heads, bulkheads and baffles must be of 0 temper (annealed) or stronger tempers. All shell materials shall be of H 32 or H 34 tempers except that the lower ultimate strength tempers may be used if the minimum shell thicknesses in the tables are increased in inverse proportion to the lesser ultimate strength.

(b) *Minimum thickness.* The minimum thickness for the shell and heads (or baffles and bulkheads when used as tank reinforcement) must be no less than that determined under criteria for minimum thickness specified in § 178.320(a).

(c) *Corrosion or abrasion protection.* When required by 49 CFR part 173 for a particular lading, a cargo tank or a part thereof, subject to thinning by corrosion or mechanical abrasion due to the lading, must be protected by providing the tank or part of the tank with a suitable increase in thickness of material, a lining or some other suitable method of protection.

(1) *Corrosion allowance.* Material added for corrosion allowance need not be of uniform thickness if different rates of attack can reasonably be expected for various areas of the cargo tank.

(2) *Lining.* Lining material must consist of a nonporous, homogeneous material not less elastic than the parent metal and substantially immune to attack by the lading. The lining material must be bonded or attached by other appropriate means to the cargo tank wall and must be imperforate when applied. Any joint or seam in the lining must be made by fusing the materials together, or by other satisfactory means.

[Amdt. 178-89, 54 FR 25021, June 12, 1989, as amended at 55 FR 37059, Sept. 7, 1990; 56 FR 27876, June 17, 1991; Amdt. 178-97, 57 FR 45465, Oct. 1, 1992; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996; 68 FR 19283, Apr. 18, 2003; 68 FR 75755, Dec. 31, 2003; 70 FR 34076, June 13, 2005]

### § 178.345-3 Structural integrity.

(a) *General requirements and acceptance criteria.* (1) The maximum calculated design stress at any point in

### 49 CFR Ch. I (10-1-08 Edition)

the cargo tank wall may not exceed the maximum allowable stress value prescribed in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter), or 25 percent of the tensile strength of the material used at design conditions.

(2) The relevant physical properties of the materials used in each cargo tank may be established either by a certified test report from the material manufacturer or by testing in conformance with a recognized national standard. In either case, the ultimate tensile strength of the material used in the design may not exceed 120 percent of the minimum ultimate tensile strength specified in either the ASME Code or the ASTM standard to which the material is manufactured.

(3) The maximum design stress at any point in the cargo tank must be calculated separately for the loading conditions described in paragraphs (b) and (c) of this section. Alternate test or analytical methods, or a combination thereof, may be used in place of the procedures described in paragraphs (b) and (c) of this section, if the methods are accurate and verifiable.

(4) Corrosion allowance material may not be included to satisfy any of the design calculation requirements of this section.

(b) *ASME Code design and construction.* The static design and construction of each cargo tank must be in accordance with Section VIII of the ASME Code. The cargo tank design must include calculation of stresses generated by the MAWP, the weight of the lading, the weight of structures supported by the cargo tank wall and the effect of temperature gradients resulting from lading and ambient temperature extremes. When dissimilar materials are used, their thermal coefficients must be used in the calculation of thermal stresses.

(1) Stress concentrations in tension, bending and torsion which occur at pads, cradles, or other supports must be considered in accordance with appendix G in Section VIII of the ASME Code.

(2) Longitudinal compressive buckling stress for ASME certified vessels must be calculated using paragraph UG-23(b) in Section VIII of the ASME

Code. For cargo tanks not required to be certified in accordance with the ASME Code, compressive buckling stress may be calculated using alternative analysis methods which are accurate and verifiable. When alternative methods are used, calculations must include both the static loads described in this paragraph and the dynamic loads described in paragraph (c) of this section.

(3) Cargo tank designers and manufacturers must consider all of the conditions specified in §173.33(c) of this subchapter when matching a cargo tank's performance characteristic to the characteristic of each lading transported.

(c) *Shell design.* Shell stresses resulting from static or dynamic loadings, or combinations thereof, are not uniform throughout the cargo tank motor vehicle. The vertical, longitudinal, and lateral normal operating loadings can occur simultaneously and must be combined. The vertical, longitudinal and lateral extreme dynamic loadings occur separately and need not be combined.

(1) *Normal operating loadings.* The following procedure addresses stress in the cargo tank shell resulting from normal operating loadings. The effective stress (the maximum principal stress at any point) must be determined by the following formula:

$$S = 0.5(S_y + S_x) \pm [0.25(S_y - S_x)^2 + S_s^2]^{0.5}$$

Where:

(i)  $S$  = effective stress at any given point under the combination of static and normal operating loadings that can occur at the same time, in psi.

(ii)  $S_y$  = circumferential stress generated by the MAWP and external pressure, when applicable, plus static head, in psi.

(iii)  $S_x$  = The following net longitudinal stress generated by the following static and normal operating loading conditions, in psi:

(A) The longitudinal stresses resulting from the MAWP and external pressure, when applicable, plus static head, in combination with the bending stress generated by the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and

appurtenances supported by the cargo tank wall;

(B) The tensile or compressive stress resulting from normal operating longitudinal acceleration or deceleration. In each case, the forces applied must be 0.35 times the vertical reaction at the suspension assembly, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer during deceleration; or the horizontal pivot of the truck tractor or converter dolly fifth wheel, or the drawbar hinge on the fixed dolly during acceleration; or anchoring and support members of a truck during acceleration and deceleration, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall. The following loadings must be included:

(1) The axial load generated by a decelerative force;

(2) The bending moment generated by a decelerative force;

(3) The axial load generated by an accelerative force; and

(4) The bending moment generated by an accelerative force; and

(C) The tensile or compressive stress generated by the bending moment resulting from normal operating vertical accelerative force equal to 0.35 times the vertical reaction at the suspension assembly of a trailer; or the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall.

(iv)  $S_s$  = The following shear stresses generated by the following static and normal operating loading conditions, in psi:

(A) The static shear stress resulting from the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight

of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(B) The vertical shear stress generated by a normal operating accelerative force equal to 0.35 times the vertical reaction at the suspension assembly of a trailer; or the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(C) The lateral shear stress generated by a normal operating lateral accelerative force equal to 0.2 times the vertical reaction at each suspension assembly of a trailer, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall; and

(D) The torsional shear stress generated by the same lateral forces as described in paragraph (c)(1)(iv)(C) of this section.

(2) *Extreme dynamic loadings.* The following procedure addresses stress in the cargo tank shell resulting from extreme dynamic loadings. The effective stress (the maximum principal stress at any point) must be determined by the following formula:

$$S = 0.5(S_y + S_x) \pm [0.25(S_y - S_x)^2 + S_s^2]^{0.5}$$

Where:

(i)  $S$  = effective stress at any given point under a combination of static and extreme dynamic loadings that can occur at the same time, in psi.

(ii)  $S_y$  = circumferential stress generated by MAWP and external pressure, when applicable, plus static head, in psi.

(iii)  $S_x$  = the following net longitudinal stress generated by the following

static and extreme dynamic loading conditions, in psi:

(A) The longitudinal stresses resulting from the MAWP and external pressure, when applicable, plus static head, in combination with the bending stress generated by the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the tank wall;

(B) The tensile or compressive stress resulting from extreme longitudinal acceleration or deceleration. In each case the forces applied must be 0.7 times the vertical reaction at the suspension assembly, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer during deceleration; or the horizontal pivot of the truck tractor or converter dolly fifth wheel, or the drawbar hinge on the fixed dolly during acceleration; or the anchoring and support members of a truck during acceleration and deceleration, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall. The following loadings must be included:

(1) The axial load generated by a decelerative force;

(2) The bending moment generated by a decelerative force;

(3) The axial load generated by an accelerative force; and

(4) The bending moment generated by an accelerative force; and

(C) The tensile or compressive stress generated by the bending moment resulting from an extreme vertical accelerative force equal to 0.7 times the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or the anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall.

(iv)  $S_s$  = The following shear stresses generated by static and extreme dynamic loading conditions, in psi:

(A) The static shear stress resulting from the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(B) The vertical shear stress generated by an extreme vertical accelerative force equal to 0.7 times the vertical reaction at the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall;

(C) The lateral shear stress generated by an extreme lateral accelerative force equal to 0.4 times the vertical reaction at the suspension assembly of a trailer, applied at the road surface, and as transmitted to the cargo tank wall through the suspension assembly of a trailer, and the horizontal pivot of the upper coupler (fifth wheel) or turntable; or anchoring and support members of a truck, as applicable. The vertical reaction must be calculated based on the static weight of the fully loaded cargo tank motor vehicle, all structural elements, equipment and appurtenances supported by the cargo tank wall; and

(D) The torsional shear stress generated by the same lateral forces as described in paragraph (c)(2)(iv)(C) of this section.

(d) In no case may the minimum thickness of the cargo tank shells and heads be less than that prescribed in § 178.346-2, § 178.347-2, or § 178.348-2, as applicable.

(e) For a cargo tank mounted on a frame or built with integral structural supports, the calculation of effective stresses for the loading conditions in paragraph (c) of this section may include the structural contribution of

the frame or the integral structural supports.

(f) The design, construction, and installation of an attachment, appurtenance to a cargo tank, structural support member between the cargo tank and the vehicle or suspension component must conform to the following requirements:

(1) Structural members, the suspension sub-frame, accident protection structures and external circumferential reinforcement devices must be used as sites for attachment of appurtenances and other accessories to the cargo tank, when practicable.

(2) A lightweight attachment to a cargo tank wall such as a conduit clip, brake line clip, skirting structure, lamp mounting bracket, or placard holder must be of a construction having lesser strength than the cargo tank wall materials and may not be more than 72 percent of the thickness of the material to which it is attached. The lightweight attachment may be secured directly to the cargo tank wall if the device is designed and installed in such a manner that, if damaged, it will not affect the lading retention integrity of the tank. A lightweight attachment must be secured to the cargo tank shell or head by continuous weld or in such a manner as to preclude formation of pockets which may become sites for corrosion.

(3) Except as prescribed in paragraphs (f)(1) and (f)(2) of this section, the welding of any appurtenance to the cargo tank wall must be made by attachment of a mounting pad so that there will be no adverse effect upon the lading retention integrity of the cargo tank if any force less than that prescribed in paragraph (b)(1) of this section is applied from any direction. The thickness of the mounting pad may not be less than that of the shell or head to which it is attached, and not more than 1.5 times the shell or head thickness. However, a pad with a minimum thickness of 0.187 inch may be used when the shell or head thickness is over 0.187 inch. If weep holes or tell-tale holes are used, the pad must be drilled or punched at the lowest point before it is welded to the tank. Each pad must:

#### § 178.345-4

#### 49 CFR Ch. I (10-1-08 Edition)

(i) Be fabricated from material determined to be suitable for welding to both the cargo tank material and the material of the appurtenance or structural support member; a Design Certifying Engineer must make this determination considering chemical and physical properties of the materials and must specify filler material conforming to the requirements of the ASME Code (incorporated by reference; see § 171.7 of this subchapter).

(ii) Be preformed to an inside radius no greater than the outside radius of the cargo tank at the attachment location.

(iii) Extend at least 2 inches in each direction from any point of attachment of an appurtenance or structural support member. This dimension may be measured from the center of the structural member attached.

(iv) Have rounded corners, or otherwise be shaped in a manner to minimize stress concentrations on the shell or head.

(v) Be attached by continuous fillet welding. Any fillet weld discontinuity may only be for the purpose of preventing an intersection between the fillet weld and the tank or jacket seam weld.

[Amdt. 178-89, 55 FR 37059, Sept. 7, 1990, as amended by Amdt. 178-89, 56 FR 27876, June 17, 1991; Amdt. 178-104, 59 FR 49135, Sept. 26, 1994; Amdt. 178-105, 59 FR 55173, 55174 and 55175, Nov. 3, 1994; 60 FR 17402, Apr. 5, 1995; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996; 65 FR 58631, Sept. 29, 2000; 68 FR 19283, Apr. 18, 2003; 68 FR 75755, Dec. 31, 2003]

#### § 178.345-4 Joints.

(a) All joints between the cargo tank shell, heads, baffles, baffle attaching rings, and bulkheads must be welded in conformance with Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter).

(b) Where practical all welds must be easily accessible for inspection.

[Amdt. 178-89, 54 FR 25022, June 12, 1989, as amended by Amdt. 178-118, 61 FR 51341, Oct. 1, 1996; 68 FR 75756, Dec. 31, 2003]

#### § 178.345-5 Manhole assemblies.

(a) Each cargo tank with capacity greater than 400 gallons must be accessible through a manhole at least 15 inches in diameter.

(b) Each manhole, fill opening and washout assembly must be structurally capable of withstanding, without leakage or permanent deformation that would affect its structural integrity, a static internal fluid pressure of at least 36 psig, or cargo tank test pressure, whichever is greater. The manhole assembly manufacturer shall verify compliance with this requirement by hydrostatically testing at least one percent (or one manhole closure, whichever is greater) of all manhole closures of each type produced each 3 months, as follows:

(1) The manhole, fill opening, or washout assembly must be tested with the venting devices blocked. Any leakage or deformation that would affect the product retention capability of the assembly shall constitute a failure.

(2) If the manhole, fill opening, or washout assembly tested fails, then five more covers from the same lot must be tested. If one of these five covers fails, then all covers in the lot from which the tested covers were selected are to be 100% tested or rejected for service.

(c) Each manhole, filler and washout cover must be fitted with a safety device that prevents the cover from opening fully when internal pressure is present.

(d) Each manhole and fill cover must be secured with fastenings that will prevent opening of the covers as a result of vibration under normal transportation conditions or shock impact due to a rollover accident on the roadway or shoulder where the fill cover is not struck by a substantial obstacle.

(e) On cargo tank motor vehicles manufactured after October 1, 2004, each manhole assembly must be permanently marked on the outside by stamping or other means in a location visible without opening the manhole assembly or fill opening, with:

(1) Manufacturer's name;

(2) Test pressure \_\_\_\_ psig;

(3) A statement certifying that the manhole cover meets the requirements in § 178.345-5.

(f) All fittings and devices mounted on a manhole cover, coming in contact with the lading, must withstand the same static internal fluid pressure and

contain the same permanent compliance markings as that required for the manhole cover. The fitting or device manufacturer shall verify compliance using the same test procedure and frequency of testing as specified in § 178.345-5(b).

[Amdt. 178-89, 54 FR 25022, June 12, 1989, as amended by Amdt. 178-105, 59 FR 55175, Nov. 3, 1994; 68 FR 19284, Apr. 18, 2003]

**§ 178.345-6 Supports and anchoring.**

(a) A cargo tank with a frame not integral to the cargo tank must have the tank secured by restraining devices to eliminate any motion between the tank and frame that may abrade the tank shell due to the stopping, starting, or turning of the cargo tank motor vehicle. The design calculations of the support elements must include the stresses indicated in § 178.345-3(b) and as generated by the loads described in § 178.345-3(c). Such restraining devices must be readily accessible for inspection and maintenance, except that insulation and jacketing are permitted to cover the restraining devices.

(b) A cargo tank designed and constructed so that it constitutes, in whole or in part, the structural member used in lieu of a frame must be supported in such a manner that the resulting stress levels in the cargo tank do not exceed those specified in § 178.345-3(a). The design calculations of the support elements must include the stresses indicated in § 178.345-3(b) and as generated by the loads described in § 178.345-3(c).

[Amdt. 178-89, 54 FR 25023, June 12, 1989, as amended by Amdt. 178-105, 59 FR 55175, Nov. 3, 1994; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996]

**§ 178.345-7 Circumferential reinforcements.**

(a) A cargo tank with a shell thickness of less than  $\frac{3}{8}$  inch must be circumferentially reinforced with bulkheads, baffles, ring stiffeners, or any combination thereof, in addition to the cargo tank heads.

(1) Circumferential reinforcement must be located so that the thickness and tensile strength of the shell material in combination with the frame and reinforcement produces structural integrity at least equal to that pre-

scribed in § 178.345-3 and in such a manner that the maximum unreinforced portion of the shell does not exceed 60 inches. For cargo tanks designed to be loaded by vacuum, spacing of circumferential reinforcement may exceed 60 inches provided the maximum unreinforced portion of the shell conforms with the requirements in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter).

(2) Where circumferential joints are made between conical shell sections, or between conical and cylindrical shell sections, and the angle between adjacent sections is less than 160 degrees, circumferential reinforcement must be located within one inch of the shell joint, unless otherwise reinforced with structural members capable of maintaining shell stress levels authorized in § 178.345-3. When the joint is formed by the large ends of adjacent conical shell sections, or by the large end of a conical shell and a cylindrical shell section, this angle is measured inside the shell; when the joint is formed by the small end of a conical shell section and a cylindrical shell section, it is measured outside the shell.

(b) Except for doubler plates and knuckle pads, no reinforcement may cover any circumferential joint.

(c) When a baffle or baffle attachment ring is used as a circumferential reinforcement member, it must produce structural integrity at least equal to that prescribed in § 178.345-3 and must be circumferentially welded to the cargo tank shell. The welded portion may not be less than 50 percent of the total circumference of the cargo tank and the length of any unwelded space on the joint may not exceed 40 times the shell thickness unless reinforced external to the cargo tank.

(d) When a ring stiffener is used as a circumferential reinforcement member, whether internal or external, reinforcement must be continuous around the circumference of the cargo tank shell and must be in accordance with the following:

(1) The section modulus about the neutral axis of the ring section parallel to the shell must be at least equal to that derived from the applicable formula:

**§ 178.345-8**

**49 CFR Ch. I (10-1-08 Edition)**

I/C = 0.00027WL, for MS, HSLA and SS;  
or

I/C = 0.000467WL, for aluminum alloys;

Where:

I/C = Section modulus in inches <sup>3</sup>

W = Tank width, or diameter, inches

L = Spacing of ring stiffener, inches; i.e., the maximum longitudinal distance from the midpoint of the unsupported shell on one side of the ring stiffener to the midpoint of the unsupported shell on the opposite side of the ring stiffener.

(2) If a ring stiffener is welded to the cargo tank shell, a portion of the shell may be considered as part of the ring section for purposes of computing the ring section modulus. This portion of the shell may be used provided at least 50 percent of the total circumference of the cargo tank is welded and the length of any unwelded space on the joint does not exceed 40 times the shell thickness. The maximum portion of the shell to be used in these calculations is as follows:

| Number of circumferential ring stiffener-to-shell welds | J <sup>1</sup>      | Shell section |
|---------------------------------------------------------|---------------------|---------------|
| 1 .....                                                 | .....               | 20t           |
| 2 .....                                                 | Less than 20t ..... | 20t+J         |
| 2 .....                                                 | 20t or more .....   | 40t           |

<sup>1</sup>where:

t=Shell thickness, inches;

J=Longitudinal distance between parallel circumferential ring stiffener-to-shell welds.

(3) When used to meet the vacuum requirements of this section, ring stiffeners must be as prescribed in Section VIII of the ASME Code.

(4) If configuration of internal or external ring stiffener encloses an air space, this air space must be arranged for venting and be equipped with drainage facilities which must be kept operative at all times.

(5) Hat shaped or open channel ring stiffeners which prevent visual inspection of the cargo tank shell are prohibited on cargo tank motor vehicles constructed of carbon steel.

[Amdt. 178-89, 55 FR 37060, Sept. 7, 1990, as amended by Amdt. 178-89, 56 FR 27876, June 17, 1991; 56 FR 46354, Sept. 11, 1991; Amdt. 178-104, 59 FR 49135, Sept. 26, 1994; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996; 68 FR 75756, Dec. 31, 2003]

**§ 178.345-8 Accident damage protection.**

(a) *General.* Each cargo tank motor vehicle must be designed and constructed in accordance with the requirements of this section and the applicable individual specification to minimize the potential for the loss of lading due to an accident.

(1) Any dome, sump, or washout cover plate projecting from the cargo tank wall that retains lading in any tank orientation, must be as strong and tough as the cargo tank wall and have a thickness at least equal to that specified by the appropriate cargo tank specification. Any such projection located in the lower 1/3 of the tank circumference (or cross section perimeter for non-circular cargo tanks) that extends more than half its diameter at the point of attachment to the tank or more than 4 inches from the cargo tank wall, or located in the upper 2/3 of the tank circumference (or cross section perimeter for non-circular cargo tanks) that extends more than 1/4 its diameter or more than 2 inches from the point of attachment to the tank must have accident damage protection devices that are:

(i) As specified in this section;

(ii) 125 percent as strong as the otherwise required accident damage protection device; or

(iii) Attached to the cargo tank in accordance with the requirements of paragraph (a)(3) of this section.

(2) Outlets, valves, closures, piping, or any devices that if damaged in an accident could result in a loss of lading from the cargo tank must be protected by accident damage protection devices as specified in this section.

(3) Accident damage protection devices attached to the wall of a cargo tank must be able to withstand or deflect away from the cargo tank the loads specified in this section. They must be designed, constructed and installed so as to maximize the distribution of loads to the cargo tank wall and to minimize the possibility of adversely affecting the lading retention integrity of the cargo tank. Accident induced stresses resulting from the appropriate accident damage protection device requirements in combination with the stresses from the cargo tank

operating at the MAWP may not result in a cargo tank wall stress greater than the ultimate strength of the material of construction using a safety factor of 1.3. Deformation of the protection device is acceptable provided the devices being protected are not damaged when loads specified in this section are applied.

(4) Any piping that extends beyond an accident damage protection device must be equipped with a stop-valve and a sacrificial device such as a shear section. The sacrificial device must be located in the piping system outboard of the stop-valve and within the accident damage protection device to prevent any accidental loss of lading. The device must break at no more than 70 percent of the load that would be required to cause the failure of the protected lading retention device, part or cargo tank wall. The failure of the sacrificial device must leave the protected lading retention device and its attachment to the cargo tank wall intact and capable of retaining product.

(5) *Minimum road clearance.* The minimum road clearance of any cargo tank motor vehicle component or protection device located between any two adjacent axles on a vehicle or vehicle combination must be at least one-half inch for each foot separating the component or device from the nearest axle of the adjacent pair, but in no case less than twelve (12) inches, except that the minimum road clearance for landing gear or other attachments within ten (10) feet of an axle must be no less than ten (10) inches. These measurements must be calculated at the gross vehicle weight rating of the cargo tank motor vehicle.

(b) Each outlet, projection or piping located in the lower  $\frac{1}{3}$  of the cargo tank circumference (or cross section perimeter for non-circular cargo tanks) that could be damaged in an accident that may result in the loss of lading must be protected by a bottom damage protection device, except as provided by paragraph (a)(1) of this section and §173.33(e) of this subchapter. Outlets, projections and piping may be grouped or clustered together and protected by a single protection device.

(1) Any bottom damage protection device must be able to withstand a

force of 155,000 pounds (based on the ultimate strength of the material) from the front, side, or rear, uniformly distributed over each surface of the device, over an area not to exceed 6 square feet, and a width not to exceed 6 feet. Suspension components and structural mounting members may be used to provide all, or part, of this protection. The device must extend no less than 6 inches beyond any component that may contain lading in transit.

(2) A lading discharge opening equipped with an internal self-closing stop-valve need not conform to paragraph (b)(1) of this section provided it is protected so as to reasonably assure against the accidental loss of lading. This protection must be provided by a sacrificial device located outboard of each internal self-closing stop-valve and within 4 inches of the major radius of the cargo tank shell or within 4 inches of a sump, but in no case more than 8 inches from the major radius of the tank shell. The device must break at no more than 70 percent of the load that would be required to cause the failure of the protected lading retention device, part or cargo tank wall. The failure of the sacrificial device must leave the protected lading retention device or part and its attachment to the cargo tank wall intact and capable of retaining product.

(c) Each closure for openings, including but not limited to the manhole, filling or inspection openings, and each valve, fitting, pressure relief device, vapor recovery stop valve or lading retaining fitting located in the upper  $\frac{2}{3}$  of a cargo tank circumference (or cross section perimeter for non-circular tanks) must be protected by being located within or between adjacent rollover damage protection devices, or by being 125 percent of the strength that would be provided by the otherwise required damage protection device.

(1) A rollover damage protection device on a cargo tank motor vehicle must be designed and installed to withstand loads equal to twice the weight of the loaded cargo tank motor vehicle applied as follows: normal to the cargo tank shell (perpendicular to the cargo tank surface); and tangential (perpendicular to the normal load) from any direction. The stresses shall not exceed



the ultimate strength of the material of construction. These design loads may be considered to be uniformly distributed and independently applied. If more than one rollover protection device is used, each device must be capable of carrying its proportionate share of the required loads and in each case at least one-fourth the total tangential load. The design must be proven capable of carrying the required loads by calculations, tests or a combination of tests and calculations.

(2) A rollover damage protection device that would otherwise allow the accumulation of liquid on the top of the cargo tank, must be provided with a drain that directs the liquid to a safe point of discharge away from any structural component of the cargo tank motor vehicle.

(d) *Rear-end tank protection.* Each cargo tank motor vehicle must be provided with a rear-end tank protection device to protect the cargo tank and piping in the event of a rear-end collision and reduce the likelihood of damage that could result in the loss of lading. Nothing in this paragraph relieves the manufacturer of responsibility for complying with the requirements of § 393.86 of this title and, if applicable, paragraph (b) of this section. The rear-end tank protection device must conform to the following requirements:

(1) The rear-end cargo tank protection device must be designed so that it can deflect at least 6 inches horizontally forward with no contact between any part of the cargo tank motor vehicle which contains lading during transit and with any part of the rear-end protection device, or with a vertical plane passing through the outboard surface of the protection device.

(2) The dimensions of the rear-end cargo tank protection device shall conform to the following:

(i) The bottom surface of the rear-end protection device must be at least 4 inches below the lower surface of any part at the rear of the cargo tank motor vehicle which contains lading during transit and not more than 60 inches from the ground when the vehicle is empty.

(ii) The maximum width of a notch, indentation, or separation between sections of a rear-end cargo tank protec-

tion device may not exceed 24 inches. A notched, indented, or separated rear-end protection device may be used only when the piping at the rear of the cargo tank is equipped with a sacrificial device outboard of a shut-off valve.

(iii) The widest part of the motor vehicle at the rear may not extend more than 18 inches beyond the outermost ends of the device or (if separated) devices on either side of the vehicle.

(3) The structure of the rear-end protection device and its attachment to the vehicle must be designed to satisfy the conditions specified in paragraph (d)(1) of this section when subjected to an impact of the cargo tank motor vehicle at rated payload, at a deceleration of 2 “g”. Such impact must be considered as being uniformly applied in the horizontal plane at an angle of 10 degrees or less to the longitudinal axis of the vehicle.

(e) *Longitudinal deceleration protection.* In order to account for stresses due to longitudinal impact in an accident, the cargo tank shell and heads must be able to withstand the load resulting from the design pressure in combination with the dynamic pressure resulting from a longitudinal deceleration of 2 “g”. For this loading condition, the allowable stress value used may not exceed the ultimate strength of the material of construction using a safety factor of 1.3. Performance testing, analytical methods, or a combination thereof, may be used to prove this capability provided the methods are accurate and verifiable. For cargo tanks with internal baffles, the decelerative force may be reduced by 0.25 “g” for each baffle assembly, but in no case may the total reduction in decelerative force exceed 1.0 “g”.

[Amdt. 178-89, 54 FR 25023, June 12, 1989, as amended at 55 FR 37061, Sept. 7, 1990; Amdt. 178-105, 59 FR 55175, Nov. 3, 1994; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996; 68 FR 19284, Apr. 18, 2003]

#### **§ 178.345-9 Pumps, piping, hoses and connections.**

(a) Suitable means must be provided during loading or unloading operations to ensure that pressure within a cargo tank does not exceed test pressure.

(b) Each hose, piping, stop-valve, lading retention fitting and closure must

be designed for a bursting pressure of the greater of 100 psig or four times the MAWP.

(c) Each hose coupling must be designed for a bursting pressure of the greater of 120 psig or 4.8 times the MAWP of the cargo tank, and must be designed so that there will be no leakage when connected.

(d) Suitable provision must be made to allow for and prevent damage due to expansion, contraction, jarring, and vibration. Slip joints may not be used for this purpose in the lading retention system.

(e) Any heating device, when installed, must be so constructed that the breaking of its external connections will not cause leakage of the cargo tank lading.

(f) Any gauging, loading or charging device, including associated valves, must be provided with an adequate means of secure closure to prevent leakage.

(g) The attachment and construction of each loading/unloading or charging line must be of sufficient strength, or be protected by a sacrificial device, such that any load applied by loading/unloading or charging lines connected to the cargo tank cannot cause damage resulting in loss of lading from the cargo tank.

(h) Use of a nonmetallic pipe, valve or connection that is not as strong and heat resistant as the cargo tank material is authorized only if such attachment is located outboard of the lading retention system.

[Amdt. 178-89, 54 FR 25025, June 12, 1989, as amended at 55 FR 37061, Sept. 7, 1990, Amdt. 178-89, 56 FR 27877, June 17, 1991; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996]

#### § 178.345-10 Pressure relief.

(a) Each cargo tank must be equipped to relieve pressure and vacuum conditions in conformance with this section and the applicable individual specification. The pressure and vacuum relief system must be designed to operate and have sufficient capacity to prevent cargo tank rupture or collapse due to over-pressurization or vacuum resulting from loading, unloading, or from heating and cooling of lading. Pressure relief systems are not required to conform to the ASME Code.

(b) *Type and construction of relief systems and devices.* (1) Each cargo tank must be provided with a primary pressure relief system consisting of one or more reclosing pressure relief valves. A secondary pressure relief system consisting of another pressure relief valve in parallel with the primary pressure relief system may be used to augment the total venting capacity of the cargo tank. Non-reclosing pressure relief devices are not authorized in any cargo tank except when in series with a reclosing pressure relief device. Gravity actuated reclosing valves are not authorized on any cargo tank.

(2) When provided by § 173.33(c)(1)(iii) of this subchapter, cargo tanks may be equipped with a normal vent. Such vents must be set to open at not less than 1 psig and must be designed to prevent loss of lading through the device in case of vehicle overturn.

(3) Each pressure relief system must be designed to withstand dynamic pressure surges in excess of the design set pressure as specified in paragraphs (b)(3) (i) and (ii) of this section. Set pressure is a function of MAWP as set forth in paragraph (d) of this section.

(i) Each pressure relief device must be able to withstand dynamic pressure surge reaching 30 psig above the design set pressure and sustained above the set pressure for at least 60 milliseconds with a total volume of liquid released not exceeding one gallon before the relief device recloses to a leak-tight condition. This requirement must be met regardless of vehicle orientation. This capability must be demonstrated by testing. An acceptable method is outlined in TTMA RP No. 81-97 "Performance of Spring Loaded Pressure Relief Valves on MC 306, MC 307, MC 312, DOT 406, DOT 407, and DOT 412 Tanks" (incorporated by reference; see § 171.7 of this subchapter).

(ii) After August 31, 1995, each pressure relief device must be able to withstand a dynamic pressure surge reaching 30 psig above the design set pressure and sustained above the design set pressure for at least 60 milliseconds with a total volume of liquid released not exceeding 1 L before the relief valve recloses to a leak-tight condition. This requirement must be met regardless of vehicle orientation. This

§ 178.345-10

capability must be demonstrated by testing. TTMA RP No. 81, cited in paragraph (b)(3)(i) of this section, is an acceptable test procedure.

(4) Each reclosing pressure relief valve must be constructed and installed in such a manner as to prevent unauthorized adjustment of the relief valve setting.

(5) No shut-off valve or other device that could prevent venting through the pressure relief system may be installed in a pressure relief system.

(6) The pressure relief system must be mounted, shielded and drainable so as to minimize the accumulation of material that could impair the operation or discharge capability of the system by freezing, corrosion or blockage.

(c) *Location of relief devices.* Each pressure relief device must communicate with the vapor space above the lading as near as practicable to the center of the vapor space. For example, on a cargo tank designed to operate in a level attitude, the device should be positioned at the horizontal and transverse center of the cargo tank; on cargo tanks sloped to the rear, the device should be located in the forward half of the cargo tank. The discharge from any device must be unrestricted. Protective devices which deflect the flow of vapor are permissible provided the required vent capacity is maintained.

(d) *Settings of pressure relief system.* The set pressure of the pressure relief system is the pressure at which it starts to open, allowing discharge.

(1) *Primary pressure relief system.* The set pressure of each primary relief valve must be no less than 120 percent of the MAWP, and no more than 132 percent of the MAWP. The valve must reclose at not less than 108 percent of the MAWP and remain closed at lower pressures.

(2) *Secondary pressure relief system.* The set pressure of each pressure relief valve used as a secondary relief device must be not less than 120 percent of the MAWP.

(e) *Venting capacity of pressure relief systems.* The pressure relief system (primary and secondary, including piping) must have sufficient venting capacity to limit the cargo tank internal pres-

49 CFR Ch. I (10-1-08 Edition)

sure to not more than the cargo tank test pressure. The total venting capacity, rated at not more than the cargo tank test pressure, must be at least that specified in table I, except as provided in § 178.348-4.

TABLE I—MINIMUM EMERGENCY VENT CAPACITY  
[In cubic feet free air/hour at 60 °F and 1 atm.]

| Exposed area in square feet | Cubic feet free air per hour |
|-----------------------------|------------------------------|
| 20 .....                    | 15,800                       |
| 30 .....                    | 23,700                       |
| 40 .....                    | 31,600                       |
| 50 .....                    | 39,500                       |
| 60 .....                    | 47,400                       |
| 70 .....                    | 55,300                       |
| 80 .....                    | 63,300                       |
| 90 .....                    | 71,200                       |
| 100 .....                   | 79,100                       |
| 120 .....                   | 94,900                       |
| 140 .....                   | 110,700                      |
| 160 .....                   | 126,500                      |
| 180 .....                   | 142,300                      |
| 200 .....                   | 158,100                      |
| 225 .....                   | 191,300                      |
| 250 .....                   | 203,100                      |
| 275 .....                   | 214,300                      |
| 300 .....                   | 225,100                      |
| 350 .....                   | 245,700                      |
| 400 .....                   | 265,000                      |
| 450 .....                   | 283,200                      |
| 500 .....                   | 300,600                      |
| 550 .....                   | 317,300                      |
| 600 .....                   | 333,300                      |
| 650 .....                   | 348,800                      |
| 700 .....                   | 363,700                      |
| 750 .....                   | 378,200                      |
| 800 .....                   | 392,200                      |
| 850 .....                   | 405,900                      |
| 900 .....                   | 419,300                      |
| 950 .....                   | 432,300                      |
| 1,000 .....                 | 445,000                      |

NOTE 1: Interpolate for intermediate sizes.

(1) *Primary pressure relief system.* Unless otherwise specified in the applicable individual specification, the primary relief system must have a minimum venting capacity of 12,000 SCFH per 350 square feet of exposed cargo tank area, but in any case at least one fourth the required total venting capacity for the cargo tank.

(2) *Secondary pressure relief system.* If the primary pressure relief system does not provide the required total venting capacity, additional capacity must be provided by a secondary pressure relief system.

(f) *Certification of pressure relief devices.* The manufacturer of any pressure relief device, including valves, frangible (rupture) disks, vacuum vents and combination devices must certify that the device model was designed and

tested in accordance with this section and the appropriate cargo tank specification. The certificate must contain sufficient information to describe the device and its performance. The certificate must be signed by a responsible official of the manufacturer who approved the flow capacity certification.

(g) *Rated flow capacity certification test.* Each pressure relief device model must be successfully flow capacity certification tested prior to first use. Devices having one design, size and set pressure are considered to be one model. The testing requirements are as follows:

(1) At least 3 devices of each specific model must be tested for flow capacity at a pressure not greater than the test pressure of the cargo tank. For a device model to be certified, the capacities of the devices tested must fall within a range of plus or minus 5 percent of the average for the devices tested.

(2) The rated flow capacity of a device model may not be greater than 90 percent of the average value for the devices tested.

(3) The rated flow capacity derived for each device model must be certified by a responsible official of the device manufacturer.

(h) *Marking of pressure relief devices.* Each pressure relief device must be permanently marked with the following:

- (1) Manufacturer's name;
- (2) Model number;
- (3) Set pressure, in psig; and
- (4) Rated flow capacity, in SCFH at the rating pressure, in psig.

[Amdt. 178-89, 54 FR 25025, June 12, 1989, as amended at 55 FR 21038, May 22, 1990; 55 FR 37062, Sept. 7, 1990; Amdt. 178-89, 56 FR 27877, June 17, 1991; Amdt. 178-105, 59 FR 55175, Nov. 3, 1994; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996; 65 FR 58631, Sept. 29, 2000; 66 FR 45389, Aug. 28, 2001; 68 FR 19284, Apr. 18, 2003]

#### § 178.345-11 Tank outlets.

(a) *General.* As used in this section, "loading/unloading outlet" means any opening in the cargo tank wall used for loading or unloading of lading, as distinguished from outlets such as man-hole covers, vents, vapor recovery devices, and similar closures. Cargo tank outlets, closures and associated piping

must be protected in accordance with § 178.345-8.

(b) Each cargo tank loading/unloading outlet must be equipped with an internal self-closing stop-valve, or alternatively, with an external stop-valve located as close as practicable to the cargo tank wall. Each cargo tank loading/unloading outlet must be in accordance with the following provisions:

(1) Each loading/unloading outlet must be fitted with a self-closing system capable of closing all such outlets in an emergency within 30 seconds of actuation. During normal operations the outlets may be closed manually. The self-closing system must be designed according to the following:

(i) Each self-closing system must include a remotely actuated means of closure located more than 10 feet from the loading/unloading outlet where vehicle length allows, or on the end of the cargo tank farthest away from the loading/unloading outlet. The actuating mechanism must be corrosion-resistant and effective in all types of environment and weather.

(ii) If the actuating system is accidentally damaged or sheared off during transportation, each loading/unloading outlet must remain securely closed and capable of retaining lading.

(iii) When required by part 173 of this subchapter for materials which are flammable, pyrophoric, oxidizing, or Division 6.1 (poisonous liquid) materials, the remote means of closure must be capable of thermal activation. The means by which the self-closing system is thermally activated must be located as close as practicable to the primary loading/unloading connection and must actuate the system at a temperature not over 250 °F. In addition, outlets on these cargo tanks must be capable of being remotely closed manually or mechanically.

(2) Bottom loading outlets which discharge lading into the cargo tank through fixed internal piping above the maximum liquid level of the cargo tank need not be equipped with a self-closing system.

(c) Any loading/unloading outlet extending beyond an internal self-closing stop-valve, or beyond the innermost external stop-valve which is part of a self-closing system, must be fitted with

## § 178.345-12

another stop-valve or other leak-tight closure at the end of such connection.

(d) Each cargo tank outlet that is not a loading/unloading outlet must be equipped with a stop-valve or other leak-tight closure located as close as practicable to the cargo tank outlet. Any connection extending beyond this closure must be fitted with another stop-valve or other leak-tight closure at the end of such connection.

[Amdt. 178-89, 56 FR 27877, June 17, 1991, as amended by Amdt. 178-97, 57 FR 45465, Oct. 1, 1992; Amdt. 178-118, 61 FR 51341, Oct. 1, 1996]

### § 178.345-12 Gauging devices.

Each cargo tank, except a cargo tank intended to be filled by weight, must be equipped with a gauging device that indicates the maximum permitted liquid level to within 0.5 percent of the nominal capacity as measured by volume or liquid level. Gauge glasses are not permitted.

[Amdt. 178-89, 55 FR 37062, Sept. 7, 1990, as amended by Amdt. 178-118, 61 FR 51342, Oct. 1, 1996]

### § 178.345-13 Pressure and leakage tests.

(a) Each cargo tank must be pressure and leakage tested in accordance with this section and §§ 178.346-5, 178.347-5, or 178.348-5.

(b) *Pressure test.* Each cargo tank or cargo tank compartment must be tested hydrostatically or pneumatically. Each cargo tank of a multi-cargo tank motor vehicle must be tested with the adjacent cargo tanks empty and at atmospheric pressure. Each closure, except pressure relief devices and loading/unloading venting devices rated at less than the prescribed test pressure, must be in place during the test. If the venting device is not removed during the test, such device must be rendered inoperative by a clamp, plug or other equally effective restraining device, which may not prevent the detection of leaks, or damage the device. Restraining devices must be removed immediately after the test is completed.

(1) *Hydrostatic method.* Each cargo tank, including its domes, must be filled with water or other liquid having similar viscosity, the temperature of which may not exceed 100 °F. The cargo tank must then be pressurized as pre-

## 49 CFR Ch. I (10-1-08 Edition)

scribed in the applicable specification. The pressure must be gauged at the top of the cargo tank. The prescribed test pressure must be maintained for at least 10 minutes during which time the cargo tank must be inspected for leakage, bulging, or other defect.

(2) *Pneumatic method.* A pneumatic test may be used in place of the hydrostatic test. However, pneumatic pressure testing may involve higher risk than hydrostatic testing. Therefore, suitable safeguards must be provided to protect personnel and facilities should failure occur during the test. The cargo tank must be pressurized with air or an inert gas. Test pressure must be reached gradually by increasing the pressure to one half of test pressure. Thereafter, the pressure must be increased in steps of approximately one tenth of the test pressure until test pressure is reached. Test pressure must be held for at least 5 minutes. The pressure must then be reduced to the inspection pressure which must be maintained while the entire cargo tank surface is inspected for leakage and other sign of defects. The inspection method must consist of coating all joints and fittings with a solution of soap and water or other equally sensitive method.

(c) *Leakage test.* The cargo tank with all its accessories in place and operable must be leak tested at not less than 80 percent of tank's MAWP with the pressure maintained for at least 5 minutes.

(d) Any cargo tank that leaks, bulges or shows any other sign of defect must be rejected. Rejected cargo tanks must be suitably repaired and retested successfully prior to being returned to service. The retest after any repair must use the same method of test under which the cargo tank was originally rejected.

[Amdt. 178-89, 54 FR 25026, June 12, 1989, as amended at 55 FR 37063, Sept. 7, 1990; Amdt. 178-105, 59 FR 55176, Nov. 3, 1994; Amdt. 178-118, 61 FR 51342, Oct. 1, 1996; 65 FR 58631, Sept. 29, 2000; 68 FR 19284, Apr. 18, 2003]

### § 178.345-14 Marking.

(a) *General.* The manufacturer shall certify that each cargo tank motor vehicle has been designed, constructed and tested in accordance with the applicable Specification DOT 406, DOT 407

or DOT 412 (§§ 178.345, 178.346, 178.347, 178.348) cargo tank requirements and, when applicable, with Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter). The certification shall be accomplished by marking the cargo tank as prescribed in paragraphs (b) and (c) of this section, and by preparing the certificate prescribed in § 178.345-15. Metal plates prescribed by paragraphs (b), (c), (d) and (e) of this section, must be permanently attached to the cargo tank or its integral supporting structure, by brazing, welding or other suitable means. These plates must be affixed on the left side of the vehicle near the front of the cargo tank (or the frontmost cargo tank of a multi-cargo tank motor vehicle), in a place readily accessible for inspection. The plates must be permanently and plainly marked in English by stamping, embossing or other means in characters at least  $\frac{3}{16}$  inch high. The information required by paragraphs (b) and (c) of this section may be combined on one specification plate.

(b) *Nameplate.* Each cargo tank must have a corrosion resistant nameplate permanently attached to it. The following information, in addition to any applicable information required by the ASME Code, must be marked on the tank nameplate (parenthetical abbreviations may be used):

(1) DOT-specification number DOT XXX (DOT XXX) where “XXX” is replaced with the applicable specification number. For cargo tanks having a variable specification plate, the DOT-specification number is replaced with the words “See variable specification plate.”

(2) Original test date, month and year (Orig. Test Date).

(3) Tank MAWP in psig.

(4) Cargo tank test pressure (Test P), in psig.

(5) Cargo tank design temperature range (Design temp. range), °F to °F.

(6) Nominal capacity (Water cap.), in gallons.

(7) Maximum design density of lading (Max. lading density), in pounds per gallon.

(8) Material specification number—shell (Shell matl, yyy\*\*\*), where “yyy”

is replaced by the alloy designation and “\*\*\*” by the alloy type.

(9) Material specification number—heads (Head matl, yyy\*\*\*), where “yyy” is replaced by the alloy designation and “\*\*\*” by the alloy type.

NOTE: When the shell and heads materials are the same thickness, they may be combined, (Shell&head matl, yyy\*\*\*).

(10) Weld material (Weld matl.).

(11) Minimum thickness—shell (Min. shell-thick), in inches. When minimum shell thicknesses are not the same for different areas, show (top \_\_, side \_\_, bottom \_\_, in inches).

(12) Minimum thickness—heads (Min. heads thick.), in inches.

(13) Manufactured thickness—shell (Mfd. shell thick.), top \_\_, side \_\_, bottom \_\_, in inches. (Required when additional thickness is provided for corrosion allowance.)

(14) Manufactured thickness—heads (Mfd. heads thick.), in inches. (Required when additional thickness is provided for corrosion allowance.)

(15) Exposed surface area, in square feet.

(c) *Specification plate.* Each cargo tank motor vehicle must have an additional corrosion resistant metal specification plate attached to it. The specification plate must contain the following information (parenthetical abbreviations may be used):

(1) Cargo tank motor vehicle manufacturer (CTMV mfr.).

(2) Cargo tank motor vehicle certification date (CTMV cert. date), if different from the cargo tank certification date.

(3) Cargo tank manufacturer (CT mfr.).

(4) Cargo tank date of manufacture (CT date of mfr.), month and year.

(5) Maximum weight of lading (Max. Payload), in pounds.

(6) Maximum loading rate in gallons per minute (Max. Load rate, GPM).

(7) Maximum unloading rate in gallons per minute (Max. Unload rate).

(8) Lining material (Lining), if applicable.

(9) Heating system design pressure (Heating sys. press.), in psig, if applicable.

(10) Heating system design temperature (Heating sys. temp.), in °F, if applicable.

(d) *Multi-cargo tank motor vehicle.* For a multi-cargo tank motor vehicle having all its cargo tanks not separated by any void, the information required by paragraphs (b) and (c) of this section may be combined on one specification plate. When separated by a void, each cargo tank must have an individual nameplate as required in paragraph (b) of this section, unless all cargo tanks are made by the same manufacturer with the same materials, manufactured thickness, minimum thickness and to the same specification. The cargo tank motor vehicle may have a combined nameplate and specification plate. When only one plate is used, the plate must be visible and not covered by insulation. The required information must be listed on the plate from front to rear in the order of the corresponding cargo tank location.

(e) *Variable specification cargo tank.* Each variable specification cargo tank must have a corrosion resistant metal variable specification plate attached to it. The mounting of this variable specification plate must be such that only the plate identifying the applicable specification under which the tank is being operated is legible.

(1) The following information must be included (parenthetical abbreviations are authorized):

Specification DOT XXX (DOT XXX), where “XXX” is replaced with the applicable specification number.

| Equipment required          | Required rating <sup>1</sup> |
|-----------------------------|------------------------------|
| Pressure relief devices:    |                              |
| Pressure actuated type.     | _____                        |
| Frangible type .....        | _____                        |
| Lading discharge devices.   | _____                        |
| Top .....                   | _____                        |
| Bottom .....                | _____                        |
| Pressure unloading fitting. | _____                        |
| Closures:                   |                              |
| Manhole .....               | _____                        |
| Fill openings .....         | _____                        |
| Discharge openings ....     | _____                        |

<sup>1</sup> Required rating—to meet the applicable specification.

(2) If no change of information in the specification plate is required, the letters “NC” must follow the rating required. If the cargo tank is not so

equipped, the word “None” must be inserted.

(3) Those parts to be changed or added must be stamped with the appropriate MC or DOT Specification markings.

(4) The alterations that must be made in order for the tank to be modified from one specification to another must be clearly indicated on the manufacturer’s certificate and on the variable specification plate.

[Amdt. 178-89, 54 FR 25027, June 12, 1989, as amended at 55 FR 37063, Sept. 7, 1990; Amdt. 178-99, 58 FR 51534, Oct. 1, 1993; Amdt. 178-104, 59 FR 49135, Sept. 26, 1994; Amdt. 178-105, 59 FR 55176, Nov. 3, 1994; 60 FR 17402, Apr. 5, 1995; Amdt. 178-118, 61 FR 51342, Oct. 1, 1996; 66 FR 45389, Aug. 28, 2001; 68 FR 19284, Apr. 18, 2003; 68 FR 52371, Sept. 3, 2003; 68 FR 75756, Dec. 31, 2003]

#### § 178.345-15 Certification.

(a) At or before the time of delivery, the manufacturer of a cargo tank motor vehicle must provide certification documents to the owner of the cargo tank motor vehicle. The registration numbers of the manufacturer, the Design Certifying Engineer, and the Registered Inspector, as appropriate, must appear on the certificates (see subpart F, part 107 in subchapter A of this chapter).

(b) The manufacturer of a cargo tank motor vehicle made to any of these specifications must provide:

(1) For each design type, a certificate signed by a responsible official of the manufacturer and a Design Certifying Engineer certifying that the cargo tank motor vehicle design meets the applicable specification; and

(2) For each ASME cargo tank, a cargo tank manufacturer’s data report as required by Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter). For each cargo tank motor vehicle, a certificate signed by a responsible official of the manufacturer and a Registered Inspector certifying that the cargo tank motor vehicle is constructed, tested and completed in conformance with the applicable specification.

(c) The manufacturer of a variable specification cargo tank motor vehicle must provide:

(1) For each design type, a certificate signed by a responsible official of the

manufacturer and a Design Certifying Engineer certifying that the cargo tank motor vehicle design meets the applicable specifications; and

(2) For each variable specification cargo tank motor vehicle, a certificate signed by a responsible official of the manufacturer and a Registered Inspector certifying that the cargo tank motor vehicle is constructed, tested and completed in conformance with the applicable specifications. The certificate must include all the information required and marked on the variable specification plate.

(d) In the case of a cargo tank motor vehicle manufactured in two or more stages, each manufacturer who performs a manufacturing operation on the incomplete vehicle or portion thereof shall provide to the succeeding manufacturer, at or before the time of delivery, a certificate covering the particular operation performed by that manufacturer, including any certificates received from previous manufacturers, Registered Inspectors, and Design Certifying Engineers. Each certificate must indicate the portion of the complete cargo tank motor vehicle represented thereby, such as basic cargo tank fabrication, insulation, jacket, lining, or piping. The final manufacturer shall provide all applicable certificates to the owner.

(e) *Specification shortages.* If a cargo tank is manufactured which does not meet all applicable specification requirements, thereby requiring subsequent manufacturing involving the installation of additional components, parts, appurtenances or accessories, the cargo tank manufacturer may affix the name plate and specification plate, as required by §178.345-14 (b) and (c), without the original date of certification stamped on the specification plate. The manufacturer shall state the specification requirements not complied with on the manufacturer's Certificate of Compliance. When the cargo tank is brought into full compliance with the applicable specification, the Registered Inspector shall stamp the date of compliance on the specification plate. The Registered Inspector shall issue a Certificate of Compliance stating details of the particular operations performed on the cargo tank, and the

date and person (manufacturer, carrier, or repair organization) accomplishing the compliance.

[Amdt. 178-89, 55 FR 37063, Sept. 7, 1990, as amended by Amdt. 178-98, 58 FR 33306, June 16, 1993; Amdt. 178-105, 59 FR 55176, Nov. 3, 1994; Amdt. 178-118, 61 FR 51342, Oct. 1, 1996; 68 FR 75756, Dec. 31, 2003]

**§ 178.346 Specification DOT 406; cargo tank motor vehicle.**

**§ 178.346-1 General requirements.**

(a) Each Specification DOT 406 cargo tank motor vehicle must meet the general design and construction requirements in §178.345, in addition to the specific requirements contained in this section.

(b) *MAWP:* The MAWP of each cargo tank must be no lower than 2.65 psig and no higher than 4 psig.

(c) Vacuum loaded cargo tanks must not be constructed to this specification.

(d) Each cargo tank must be "constructed in accordance with Section VIII of the ASME Code" (IBR, see §171.7 of this subchapter) except as modified herein:

(1) The record-keeping requirements contained in the ASME Code Section VIII do not apply. Parts UG-90 through 94 in Section VIII do not apply. Inspection and certification must be made by an inspector registered in accordance with subpart F of part 107.

(2) Loadings must be as prescribed in §178.345-3.

(3) The knuckle radius of flanged heads must be at least three times the material thickness, and in no case less than 0.5 inch. Stuffed (inserted) heads may be attached to the shell by a fillet weld. The knuckle radius and dish radius versus diameter limitations of UG-32 do not apply. Shell sections of cargo tanks designed with a non-circular cross section need not be given a preliminary curvature, as prescribed in UG-79(b).

(4) Marking, certification, data reports, and nameplates must be as prescribed in §§178.345-14 and 178.345-15.

(5) Manhole closure assemblies must conform to §§178.345-5 and 178.346-5.

(6) Pressure relief devices must be as prescribed in §178.346-3.

(7) The hydrostatic or pneumatic test must be as prescribed in §178.346-5.



(8) The following paragraphs in parts UG and UW in Section VIII of the ASME Code do not apply: UG-11, UG-12, UG-22(g), UG-32(e), UG-34, UG-35, UG-44, UG-76, UG-77, UG-80, UG-81, UG-96, UG-97, UW-13(b)(2), UW-13.1(f) and the dimensional requirements found in Figure UW-13.1.

(9) Single full fillet lap joints without plug welds may be used for arc or gas welded longitudinal seams without radiographic examination under the following conditions:

(i) For a truck-mounted cargo tank, no more than two such joints may be used on the top half of the tank and no more than two joints may be used on the bottom half. They may not be located farther from the top and bottom centerline than 16 percent of the shell's circumference.

(ii) For a self-supporting cargo tank, no more than two such joints may be used on the top of the tank. They may not be located farther from the top centerline than 12.5 percent of the shell's circumference.

(iii) *Compliance test.* Two test specimens of the material to be used in the manufacture of a cargo tank must be tested to failure in tension. The test specimens must be of the same thicknesses and joint configuration as the cargo tank, and joined by the same welding procedures. The test specimens may represent all the tanks that are made of the same materials and welding procedures, have the same joint configuration, and are made in the same facility within 6 months after the

tests are completed. Before welding, the fit-up of the joints on the test specimens must represent production conditions that would result in the least joint strength. Evidence of joint fit-up and test results must be retained at the manufacturers' facility.

(iv) *Weld joint efficiency.* The lower value of stress at failure attained in the two tensile test specimens shall be used to compute the efficiency of the joint as follows: Determine the failure ratio by dividing the stress at failure by the mechanical properties of the adjacent metal; this value, when multiplied by 0.75, is the design weld joint efficiency.

(10) The requirements of paragraph UW-9(d) in Section VIII of the ASME Code do not apply.

[Amdt. 178-89, 54 FR 25028, June 12, 1989, as amended at 55 FR 37063, Sept. 7, 1990; Amdt. 178-89, 56 FR 27877, June 17, 1991; Amdt. 178-105, 59 FR 55176, Nov. 3, 1994; 65 FR 58631, Sept. 29, 2000; 66 FR 45387, Aug. 28, 2001; 68 FR 19285, Apr. 18, 2003; 68 FR 75756, Dec. 31, 2003]

**§ 178.346-2 Material and thickness of material.**

The type and thickness of material for DOT 406 specification cargo tanks must conform to § 178.345-2, but in no case may the thickness be less than that determined by the minimum thickness requirements in § 178.320(a). The following Tables I and II identify the specified minimum thickness values to be employed in that determination.

TABLE I—SPECIFIED MINIMUM THICKNESS OF HEADS (OR BULKHEADS AND BAFFLES WHEN USED AS TANK REINFORCEMENT) USING MILD STEEL (MS), HIGH STRENGTH LOW ALLOY STEEL (HSLA), AUSTENITIC STAINLESS STEEL (SS), OR ALUMINUM (AL)—EXPRESSED IN DECIMALS OF AN INCH AFTER FORMING

| Material        | Volume capacity in gallons per inch of length |            |      |               |            |      |         |            |      |
|-----------------|-----------------------------------------------|------------|------|---------------|------------|------|---------|------------|------|
|                 | 14 or less                                    |            |      | Over 14 to 23 |            |      | Over 23 |            |      |
|                 | MS                                            | HSLA<br>SS | AL   | MS            | HSLA<br>SS | AL   | MS      | HSLA<br>SS | AL   |
| Thickness ..... | .100                                          | .100       | .160 | .115          | .115       | .173 | .129    | .129       | .187 |

TABLE II—SPECIFIED MINIMUM THICKNESS OF SHELL USING MILD STEEL (MS), HIGH STRENGTH LOW ALLOY STEEL (HSLA), AUSTENITIC STAINLESS STEEL (SS), OR ALUMINUM (AL)—EXPRESSED IN DECIMALS OF AN INCH AFTER FORMING <sup>1</sup>

| Cargo tank motor vehicle rated capacity (gallons) | MS    | SS/HSLA | AL    |
|---------------------------------------------------|-------|---------|-------|
| More than 0 to at least 4,500 .....               | 0.100 | 0.100   | 0.151 |
| More than 4,500 to at least 8,000 .....           | 0.115 | 0.100   | 0.160 |

TABLE II—SPECIFIED MINIMUM THICKNESS OF SHELL USING MILD STEEL (MS), HIGH STRENGTH LOW ALLOY STEEL (HSLA), AUSTENITIC STAINLESS STEEL (SS), OR ALUMINUM (AL)—EXPRESSED IN DECIMALS OF AN INCH AFTER FORMING <sup>1</sup>—Continued

| Cargo tank motor vehicle rated capacity (gallons) | MS    | SS/HSLA | AL    |
|---------------------------------------------------|-------|---------|-------|
| More than 8,000 to at least 14,000 .....          | 0.129 | 0.129   | 0.173 |
| More than 14,000 .....                            | 0.143 | 0.143   | 0.187 |

<sup>1</sup> Maximum distance between bulkheads, baffles, or ring stiffeners shall not exceed 60 inches.

[Amdt. 178-89, 54 FR 25028, June 12, 1989, as amended at 55 FR 37064, Sept. 7, 1990; Amdt. 178-105, 59 FR 55176, Nov. 3, 1994; 68 FR 19285, Apr. 18, 2003]

### § 178.346-3 Pressure relief.

(a) Each cargo tank must be equipped with a pressure relief system in accordance with § 178.345-10 and this section.

(b) *Type and construction.* In addition to the pressure relief devices required in § 178.345-10:

(1) Each cargo tank must be equipped with one or more vacuum relief devices;

(2) When intended for use only for lading meeting the requirements of § 173.33(c)(1)(iii) of this subchapter, the cargo tank may be equipped with a normal vent. Such vents must be set to open at not less than 1 psig and must be designed to prevent loss of lading through the device in case of vehicle upset; and

(3) Notwithstanding the requirements in § 178.345-10(b), after August 31, 1996, each pressure relief valve must be able to withstand a dynamic pressure surge reaching 30 psig above the design set pressure and sustained above the set pressure for at least 60 milliseconds with a total volume of liquid released not exceeding 1 L before the relief valve recloses to a leak-tight condition. This requirement must be met regardless of vehicle orientation. This capability must be demonstrated by testing. TTMA RP No. 81 (IBR, see § 171.7 of this subchapter), cited at § 178.345-10(b)(3)(i), is an acceptable test procedure.

(c) *Pressure settings of relief valves.* (1) Notwithstanding the requirements in § 178.345-10(d), the set pressure of each primary relief valve must be not less than 110 percent of the MAWP or 3.3 psig, whichever is greater, and not more than 138 percent of the MAWP. The valve must close at not less than the MAWP and remain closed at lower pressures.

(2) Each vacuum relief device must be set to open at no more than 6 ounces vacuum.

(d) *Venting capacities.* (1) Notwithstanding the requirements in § 178.345-10 (e) and (g), the primary pressure relief valve must have a venting capacity of at least 6,000 SCFH, rated at not greater than 125 percent of the tank test pressure and not greater than 3 psig above the MAWP. The venting capacity required in § 178.345-10(e) may be rated at these same pressures.

(2) Each vacuum relief system must have sufficient capacity to limit the vacuum to 1 psig.

(3) If pressure loading or unloading devices are provided, the relief system must have adequate vapor and liquid capacity to limit the tank pressure to the cargo tank test pressure at maximum loading or unloading rate. The maximum loading and unloading rates must be included on the metal specification plate.

[Amdt. 178-89, 54 FR 25029, June 12, 1989, as amended at 55 FR 37064, Sept. 7, 1990; Amdt. 178-105, 59 FR 55176, Nov. 3, 1994. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996; 66 FR 45389, Aug. 28, 2001; 68 FR 75756, Dec. 31, 2003]

### § 178.346-4 Outlets.

(a) All outlets on each tank must conform to § 178.345-11 and this section.

(b) External self-closing stop-valves are not authorized as an alternative to internal self-closing stop-valves on loading/unloading outlets.

[Amdt. 178-89, 54 FR 25029, June 12, 1989. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996]

**§ 178.346-5 Pressure and leakage tests.**

(a) Each cargo tank must be tested in accordance with § 178.345-13 and this section.

(b) *Pressure test.* Test pressure must be as follows:

(1) Using the hydrostatic test method, the test pressure must be the greater of 5.0 psig or 1.5 times the cargo tank MAWP.

(2) Using the pneumatic test method, the test pressure must be the greater of 5.0 psig or 1.5 times the cargo tank MAWP, and the inspection pressure must be the cargo tank MAWP.

(c) *Leakage test.* A cargo tank used to transport a petroleum distillate fuel that is equipped with vapor recovery equipment may be leakage tested in accordance with 40 CFR 63.425(e). To satisfy the leakage test requirements of this paragraph, the test specified in 40 CFR 63.425(e)(1) must be conducted using air. The hydrostatic test alternative permitted under Appendix A to 40 CFR Part 60 ("Method 27—Determination of Vapor Tightness of Gasoline Delivery Tank Using Pressure-Vacuum Test") may not be used to satisfy the leakage test requirements of this paragraph. A cargo tank tested in accordance with 40 CFR 63.425(e) may be marked as specified in § 180.415 of this subchapter.

[Amdt. 178-89, 54 FR 25029, June 12, 1989, as amended at 55 FR 37064, Sept. 7, 1990; Amdt. 178-105, 59 FR 55176, Nov. 3, 1994. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996; 68 FR 19285, Apr. 18, 2003]

**§ 178.347 Specification DOT 407; cargo tank motor vehicle.**

**§ 178.347-1 General requirements.**

(a) Each specification DOT 407 cargo tank motor vehicle must conform to the general design and construction requirements in § 178.345 in addition to the specific requirements contained in this section.

(b) Each tank must be of a circular cross-section and have an MAWP of at least 25 psig.

(c) Any cargo tank built to this specification with a MAWP greater than 35 psig and each tank designed to be loaded by vacuum must be constructed and certified in conformance with Section VIII of the ASME Code (IBR, see § 171.7

of this subchapter). The external design pressure for a cargo tank loaded by vacuum must be at least 15 psi.

(d) Each cargo tank built to this specification with MAWP of 35 psig or less must be "constructed in accordance with Section VIII of the ASME Code" except as modified.

(1) The record-keeping requirements contained in Section VIII of the ASME Code do not apply. The inspection requirements of parts UG-90 through 94 do not apply. Inspection and certification must be made by an inspector registered in accordance with subpart F of part 107.

(2) Loadings must be as prescribed in § 178.345-3.

(3) The knuckle radius of flanged heads must be at least three times the material thickness, and in no case less than 0.5 inch. Stuffed (inserted) heads may be attached to the shell by a fillet weld. The knuckle radius and dish radius versus diameter limitations of UG-32 do not apply for cargo tank motor vehicles with a MAWP of 35 psig or less.

(4) Marking, certification, data reports and nameplates must be as prescribed in §§ 178.345-14 and 178.345-15.

(5) Manhole closure assemblies must conform to § 178.347-3.

(6) Pressure relief devices must be as prescribed in § 178.347-4.

(7) The hydrostatic or pneumatic test must be as prescribed in § 178.347-5.

(8) The following paragraphs in parts UG and UW in Section VIII of the ASME Code do not apply: UG-11, UG-12, UG-22(g), UG-32(e), UG-34, UG-35, UG-44, UG-76, UG-77, UG-80, UG-81, UG-96, UG-97, UW-12, UW-13(b)(2), UW-13.1(f), and the dimensional requirements found in Figure UW-13.1.

(9) The strength of a weld seam in a bulkhead that has not been radiographically examined shall be 0.85 of the strength of the bulkhead under the following conditions:

(i) The welded seam must be a full penetration butt weld.

(ii) No more than one seam may be used per bulkhead.

(iii) The welded seam must be completed before forming the dish radius and knuckle radius.

(iv) Compliance test: Two test specimens of materials representative of

those to be used in the manufacture of a cargo tank bulkhead must be tested to failure in tension. The test specimen must be of the same thickness and joined by the same welding procedure. The test specimens may represent all the tanks that are made in the same facility within 6 months after the tests are completed. Before welding, the fit-up of the joints on the test specimens must represent production conditions that would result in the least joint strength. Evidence of joint fit-up and test results must be retained at the manufacturers' facility for at least 5 years.

(v) Acceptance criteria: The ratio of the actual tensile stress at failure to the actual tensile strength of the adja-

cent material of all samples of a test lot must be greater than 0.85.

[Amdt. 178-89, 54 FR 25029, June 12, 1989, as amended at 55 FR 37064, Sept. 7, 1990; Amdt. 178-89, 56 FR 27877, June 17, 1991; 65 FR 58632, Sept. 29, 2000; 66 FR 45387, Aug. 28, 2001; 68 FR 19285, Apr. 18, 2003; 68 FR 75756, Dec. 31, 2003]

#### § 178.347-2 Material and thickness of material.

(a) The type and thickness of material for DOT 407 specification cargo tanks must conform to § 178.345-2, but in no case may the thickness be less than that determined by the minimum thickness requirements in § 178.320(a). Tables I and II identify the specified minimum thickness values to be employed in that the determination:

TABLE I—SPECIFIED MINIMUM THICKNESS OF HEADS (OR BULKHEADS AND BAFFLES WHEN USED AS TANK REINFORCEMENT) USING MILD STEEL (MS), HIGH STRENGTH LOW ALLOY STEEL (HSLA), AUSTENITIC STAINLESS STEEL (SS), OR ALUMINUM (AL)—EXPRESSED IN DECIMALS OF AN INCH AFTER FORMING

| Volume capacity in gallons per inch | 10 or less | Over 10 to 14 | Over 14 to 18 | Over 18 to 22 | Over 22 to 26 | Over 26 to 30 | Over 30 |
|-------------------------------------|------------|---------------|---------------|---------------|---------------|---------------|---------|
| Thickness (MS) .....                | 0.100      | 0.100         | 0.115         | 0.129         | 0.129         | 0.143         | 0.156   |
| Thickness (HSLA) .....              | 0.100      | 0.100         | 0.115         | 0.129         | 0.129         | 0.143         | 0.156   |
| Thickness (SS) .....                | 0.100      | 0.100         | 0.115         | 0.129         | 0.129         | 0.143         | 0.156   |
| Thickness (AL) .....                | 0.160      | 0.160         | 0.173         | 0.187         | 0.194         | 0.216         | 0.237   |

TABLE II—SPECIFIED MINIMUM THICKNESS OF SHELL USING MILD STEEL (MS), HIGH STRENGTH LOW ALLOY STEEL (HSLA), AUSTENITIC STAINLESS STEEL (SS), OR ALUMINUM (AL)—EXPRESSED IN DECIMALS OF AN INCH AFTER FORMING

| Volume capacity in gallons per inch | 10 or less | Over 10 to 14 | Over 14 to 18 | Over 18 to 22 | Over 22 to 26 | Over 26 to 30 | Over 30 |
|-------------------------------------|------------|---------------|---------------|---------------|---------------|---------------|---------|
| Thickness (MS) .....                | 0.100      | 0.100         | 0.115         | 0.129         | 0.129         | 0.143         | 0.156   |
| Thickness (HSLA) .....              | 0.100      | 0.100         | 0.115         | 0.129         | 0.129         | 0.143         | 0.156   |
| Thickness (SS) .....                | 0.100      | 0.100         | 0.115         | 0.129         | 0.129         | 0.143         | 0.156   |
| Thickness (AL) .....                | 0.151      | 0.151         | 0.160         | 0.173         | 0.194         | 0.216         | 0.237   |

(b) [Reserved]

[Amdt. 178-89, 54 FR 25030, June 12, 1989, as amended at 55 FR 37064, Sept. 7, 1990; Amdt. 178-104, 59 FR 49135, Sept. 26, 1994; 68 FR 19285, Apr. 18, 2003]

#### § 178.347-3 Manhole assemblies.

Each manhole assembly must conform to § 178.345-5, except that each manhole assembly must be capable of withstanding internal fluid pressures of

40 psig or test pressure of the tank, whichever is greater.

[Amdt. 178-89, 54 FR 25030, June 12, 1989. Re-designated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996]

## § 178.347-4

## 49 CFR Ch. I (10-1-08 Edition)

### § 178.347-4 Pressure relief.

(a) Each cargo tank must be equipped with a pressure and vacuum relief system in accordance with § 178.345-10 and this section.

(b) *Type and Construction.* Vacuum relief devices are not required for cargo tanks designed to be loaded by vacuum or built to withstand full vacuum.

(c) *Pressure settings of relief valves.* The setting of pressure relief valves must be in accordance with § 178.345-10(d).

(d) *Venting capacities.* (1) The vacuum relief system must limit the vacuum to less than 80 percent of the design vacuum capability of the cargo tank.

(2) If pressure loading or unloading devices are provided, the relief system must have adequate vapor and liquid capacity to limit the tank pressure to the cargo tank test pressure at maximum loading or unloading rate. The maximum loading or unloading rate must be included on the metal specification plate.

[Amdt. 178-89, 54 FR 25030, June 12, 1989, as amended at 55 FR 37064, Sept. 7, 1990. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996]

### § 178.347-5 Pressure and leakage test.

(a) Each cargo tank must be tested in accordance with § 178.345-13 and this section.

(b) *Pressure test.* Test pressure must be as follows:

(1) Using the hydrostatic test method, the test pressure must be at least 40 psig or 1.5 times tank MAWP, whichever is greater.

(2) Using the pneumatic test method, the test pressure must be 40 psig or 1.5 times tank MAWP, whichever is greater, and the inspection pressure is tank MAWP.

[Amdt. 178-89, 54 FR 25030, June 12, 1989. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996]

### § 178.348 Specification DOT 412; cargo tank motor vehicle.

#### § 178.348-1 General requirements.

(a) Each specification DOT 412 cargo tank motor vehicle must conform to the general design and construction requirements in § 178.345 in addition to

the specific requirements of this section.

(b) The MAWP of each cargo tank must be at least 5 psig.

(c) The MAWP for each cargo tank designed to be loaded by vacuum must be at least 25 psig internal and 15 psig external.

(d) Each cargo tank having a MAWP greater than 15 psig must be of circular cross-section.

(e) Each cargo tank having a—

(1) MAWP greater than 15 psig must be “constructed and certified in conformance with Section VIII of the ASME Code” (IBR, see § 171.7 of this subchapter); or

(2) MAWP of 15 psig or less must be “constructed in accordance with Section VIII of the ASME Code,” except as modified herein:

(i) The recordkeeping requirements contained in Section VIII of the ASME Code do not apply. Parts UG-90 through 94 in Section VIII do not apply. Inspection and certification must be made by an inspector registered in accordance with subpart F of part 107.

(ii) Loadings must be as prescribed in § 178.345-3.

(iii) The knuckle radius of flanged heads must be at least three times the material thickness, and in no case less than 0.5 inch. Stuffed (inserted) heads may be attached to the shell by a fillet weld. The knuckle radius and dish radius versus diameter limitations of UG-32 do not apply for cargo tank motor vehicles with a MAWP of 15 psig or less. Shell sections of cargo tanks designed with a non-circular cross section need not be given a preliminary curvature, as prescribed in UG-79(b).

(iv) Marking, certification, data reports, and nameplates must be as prescribed in §§ 178.345-14 and 178.345-15.

(v) Manhole closure assemblies must conform to §§ 178.345-5.

(vi) Pressure relief devices must be as prescribed in § 178.348-4.

(vii) The hydrostatic or pneumatic test must be as prescribed in § 178.348-5.

(viii) The following paragraphs in parts UG and UW in Section VIII of the ASME Code do not apply: UG-11, UG-12, UG-22(g), UG-32(e), UG-34, UG-35, UG-44, UG-76, UG-77, UG-80, UG-81, UG-96, UG-97, UW-13(b)(2), UW-13.1(f),

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 178.348-2**

and the dimensional requirements found in Figure UW-13.1.

[Amdt. 178-89, 54 FR 25031, June 12, 1989, as amended at 55 FR 37065, Sept. 7, 1990; Amdt. 178-89, 56 FR 27877, June 17, 1991; 65 FR 58632, Sept. 29, 2000; 68 FR 19285, Apr. 18, 2003; 68 FR 75756, Dec. 31, 2003]

**§ 178.348-2 Material and thickness of material.**

(a) The type and thickness of material for DOT 412 specification cargo

tanks must conform to § 178.345-2, but in no case may the thickness be less than that determined by the minimum thickness requirements in § 178.320(a). The following Tables I and II identify the “Specified Minimum Thickness” values to be employed in that determination.

TABLE I—SPECIFIED MINIMUM THICKNESS OF HEADS (OR BULKHEADS AND BAFFLES WHEN USED AS TANK REINFORCEMENT) USING MILD STEEL (MS), HIGH STRENGTH LOW ALLOY STEEL (HSLA), AUSTENITIC STAINLESS STEEL (SS), OR ALUMINUM (AL)—EXPRESSED IN DECIMALS OF AN INCH AFTER FORMING

| Volume capacity (gallons per inch)                 | 10 or less      |                   |                   |             | Over 10 to 14   |                   |                   |             | Over 14 to 18   |                   |                   | 18 and over     |                   |                   |
|----------------------------------------------------|-----------------|-------------------|-------------------|-------------|-----------------|-------------------|-------------------|-------------|-----------------|-------------------|-------------------|-----------------|-------------------|-------------------|
| Lading density at 60 °F in pounds per gallon ..... | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs | Over 16 lbs | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs | Over 16 lbs | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs |
| Thickness (inch), steel .....                      | .100            | .129              | .157              | .187        | .129            | .157              | .187              | .250        | .157            | .250              | .250              | .157            | .250              | .312              |
| Thickness (inch), aluminum .....                   | .144            | .187              | .227              | .270        | .187            | .227              | .270              | .360        | .227            | .360              | .360              | .227            | .360              | .450              |

TABLE II—SPECIFIED MINIMUM THICKNESS OF SHELL USING MILD STEEL (MS), HIGH STRENGTH LOW ALLOY STEEL (HSLA), AUSTENITIC STAINLESS STEEL (SS), OR ALUMINUM (AL)—EXPRESSED IN DECIMALS OF AN INCH AFTER FORMING

| Volume capacity in gallons per inch                                                                  | 10 or less      |                   |                   |             | Over 10 to 14   |                   |                   |             | Over 14 to 18   |                   |                   | 18 and over     |                   |                   |
|------------------------------------------------------------------------------------------------------|-----------------|-------------------|-------------------|-------------|-----------------|-------------------|-------------------|-------------|-----------------|-------------------|-------------------|-----------------|-------------------|-------------------|
| Lading density at 60 °F in pounds per gallon .....                                                   | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs | Over 16 lbs | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs | Over 16 lbs | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs | 10 lbs and less | Over 10 to 13 lbs | Over 13 to 16 lbs |
| Thickness (steel):                                                                                   |                 |                   |                   |             |                 |                   |                   |             |                 |                   |                   |                 |                   |                   |
| Distances between heads (and bulkheads baffles and ring stiffeners when used as tank reinforcement): |                 |                   |                   |             |                 |                   |                   |             |                 |                   |                   |                 |                   |                   |
| 36 in. or less .....                                                                                 | .100            | .129              | .157              | .187        | .100            | .129              | .157              | .187        | .100            | .129              | .157              | .129            | .157              | .187              |
| Over 36 in. to 54 inches .....                                                                       | .100            | .129              | .157              | .187        | .100            | .129              | .157              | .187        | .129            | .157              | .187              | .157            | .250              | .250              |
| Over 54 in. to 60 inches .....                                                                       | .100            | .129              | .157              | .187        | .129            | .157              | .187              | .250        | .157            | .250              | .250              | .187            | .250              | .312              |
| Thickness (aluminum):                                                                                |                 |                   |                   |             |                 |                   |                   |             |                 |                   |                   |                 |                   |                   |
| Distances between heads (and bulkheads baffles and ring stiffeners when used as tank reinforcement): |                 |                   |                   |             |                 |                   |                   |             |                 |                   |                   |                 |                   |                   |
| 36 in. or less .....                                                                                 | .144            | .187              | .227              | .270        | .144            | .187              | .227              | .270        | .144            | .187              | .227              | .187            | .227              | .270              |
| Over 36 in. to 54 inches .....                                                                       | .144            | .187              | .227              | .270        | .144            | .187              | .227              | .270        | .187            | .227              | .270              | .157            | .360              | .360              |
| Over 54 in. to 60 inches .....                                                                       | .144            | .187              | .227              | .270        | .187            | .227              | .270              | .360        | .227            | .360              | .360              | .270            | .360              | .450              |

(b) [Reserved]

[Amdt. 178-89, 54 FR 25031, June 12, 1989; 54 FR 28750, July 7, 1989, as amended at 55 FR 37065, Sept. 7, 1990; 68 FR 19285, Apr. 18, 2003]

### § 178.348-3 Pumps, piping, hoses and connections.

Each pump and all piping, hoses and connections on each cargo tank motor vehicle must conform to § 178.345-9, except that the use of nonmetallic pipes, valves, or connections are authorized on DOT 412 cargo tanks.

[Amdt. 178-89, 55 FR 37065, Sept. 7, 1990. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996]

### § 178.348-4 Pressure relief.

(a) Each cargo tank must be equipped with a pressure and vacuum relief system in accordance with § 178.345-10 and this section.

(b) *Type and construction.* Vacuum relief devices are not required for cargo tanks designed to be loaded by vacuum or built to withstand full vacuum.

(c) *Pressure settings of relief valves.* The setting of the pressure relief devices must be in accordance with § 178.345-10(d), except as provided in paragraph (d)(3) of this section.

(d) *Venting capacities.* (1) The vacuum relief system must limit the vacuum to less than 80 percent of the design vacuum capability of the cargo tank.

(2) If pressure loading or unloading devices are provided, the pressure relief system must have adequate vapor and liquid capacity to limit tank pressure to the cargo tank test pressure at the maximum loading or unloading rate. The maximum loading and unloading rates must be included on the metal specification plate.

(3) Cargo tanks used in dedicated service for materials classed as corrosive material, with no secondary hazard, may have a total venting capacity which is less than required by § 178.345-10(e). The minimum total venting capacity for these cargo tanks must be determined in accordance with the following formula (use of approximate values given for the formula is acceptable):

#### *Formula in Nonmetric Units*

$$Q = 37,980,000 A^{0.82} (ZT)^{0.5} / (LC)(M^{0.5})$$

Where:

Q = The total required venting capacity, in cubic meters of air per hour at standard conditions of 15.6 °C and 1 atm (cubic feet of air per hour at standard conditions of 60 °F and 14.7 psia);

T = The absolute temperature of the vapor at the venting conditions—degrees Kelvin (°C+273) [degrees Rankine (°F+460)];

A = The exposed surface area of tank shell—square meters (square feet);

L = The latent heat of vaporization of the lading—calories per gram (BTU/lb);

Z = The compressibility factor for the vapor (if this factor is unknown, let Z equal 1.0);

M = The molecular weight of vapor;

C = A constant derived from (K), the ratio of specific heats of the vapor. If (K) is unknown, let C = 315.

$$C = 520[K(2/(K+1))^{(K+1)/(K-1)}]^{0.5}$$

Where:

$$K = C_p / C_v$$

C<sub>p</sub> = The specific heat at constant pressure, in -calories per gram degree centigrade (BTU/lb °F.); and

C<sub>v</sub> = The specific heat at constant volume, in -calories per gram degree centigrade (BTU/lb °F.).

[Amdt. 178-89, 54 FR 25032, June 12, 1989, as amended at 55 FR 37065, Sept. 7, 1990; Amdt. 178-104, 59 FR 49135, Sept. 26, 1994. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996; 72 FR 55696, Oct. 1, 2007; 72 FR 59146, Oct. 18, 2007]

### § 178.348-5 Pressure and leakage test.

(a) Each cargo tank must be tested in accordance with § 178.345-13 and this section.

(b) Pressure test. Test pressure must be as follows:

(1) Using the hydrostatic test method, the test pressure must be at least 1.5 times MAWP.

(2) Using the pneumatic test method, the test pressure must be at least 1.5 times tank MAWP, and the inspection pressure is tank MAWP.

[Amdt. 178-89, 54 FR 25032, June 12, 1989. Redesignated by Amdt. 178-112, 61 FR 18934, Apr. 29, 1996]



### Subpart K—Specifications for Packagings for Class 7 (Radioactive) Materials

#### § 178.350 Specification 7A; general packaging, Type A.

(a) Each packaging must meet all applicable requirements of subpart B of part 173 of this subchapter and be designed and constructed so that it meets the requirements of §§ 173.403, 173.410, 173.412, 173.415 and 173.465 of this subchapter for Type A packaging.

(b) Each Specification 7A packaging must be marked on the outside “USA DOT 7A Type A.”

(c) Each Specification 7A packaging must comply with the marking requirements of § 178.3. In paragraph 178.3(a)(2), the term “packaging manufacturer” means the person certifying that the package meets all requirements of this section.

[Amdt. 178–109, 60 FR 50336, Sept. 28, 1995; 60 FR 54409, Oct. 23, 1995, as amended at 69 FR 3696, Jan. 26, 2004; 70 FR 56099, Sept. 23, 2005]

#### § 178.356 Specification 20PF phenolic-foam insulated, metal overpack.

##### § 178.356–1 General requirements.

(a) Each overpack must meet all of the applicable requirements of § 173.24 of this subchapter.

(b) The maximum gross weight of the package, including the inner cylinder and its contents, must not exceed the following:

(1) Specification 20PF–1—138 kg (300 pounds).

(2) Specification 20PF–2—320 kg (700 pounds).

(3) Specification 20PF–3—455 kg (1000 pounds).

(c) The general configuration of the overpack must be a right cylinder, consisting of an insulated base section, a steel liner lid, and an insulated top section. The inner liner and outer shell must be at least 16-gauge and 18-gauge steel, respectively, with the intervening cavity filled with a molded-in-place, fire-resistant, phenolic-foam insulation interspersed with wooden members for bracing and support. Wood pieces must be securely attached to both the liner and shell. No hole is permitted in the liner. Each joint between sections must be stepped a minimum of

5 cm (2 inches) and gaps between mating surfaces must not exceed 5 mm (0.2 inch). Gaps between foam surface of top section and liner lid must not exceed 1 cm (0.4 inch) or 5 cm (2 inches) where taper is required for mold stripping. For the specification 20PF–1, the top section may consist of a plug of foam insulation and a steel cover. The liner and shell closures must each be gasketed against moisture penetration. The liner must have a bolted flange closure. Shell closure must conform to paragraph (d) of this section.

(d) Drums over 5 gallons capacity must be closed by means of 12-gauge bolted ring with drop forged lugs, one of which is threaded, and having 3/8 inch bolt and nut for drums not over 30 gallons capacity and 5/8 inch bolt and nut for drums over 30 gallons capacity. Five gallon drums must be of lug type closure with cover having at least 16 lugs.

(e) Drawings in DOE CAPE–1662, Rev. 1 and Supplement 1 (IBR, see § 171.7 of this subchapter), which include bills of material, are a part of this specification.

[Amdt. 178–35, 39 FR 45247, Dec. 31, 1974. Redesignated by Amdt. 178–97, 55 FR 52716, Dec. 21, 1990; 65 FR 58632, Sept. 29, 2000; 66 FR 45386, 45389, Aug. 28, 2001; 68 FR 75757, Dec. 31, 2003]

##### § 178.356–2 Materials of construction and other requirements.

(a) Phenolic foam insulation must be fire-resistant and fabricated in accordance with USDOE Material and Equipment Specification SP–9, Rev. 1 and Supplement (IBR, see § 171.7 of this subchapter), which is a part of this specification. (Note: Packagings manufactured under USAEC Specification SP–9 and Rev. 1 thereto are authorized for continued manufacture and use.) A 13.7 cm (5.4-inch) minimum thickness of foam must be provided over the entire liner except:

(1) Where wood spacers replace the foam; or

(2) At protrusions of liner or shell, such as flanges, baffles, etc., where minimum insulation thickness is 9 cm (3.5 inches); or

(3) Where alternate top section (specification 20PF–1) is used. Foam must not interfere with proper seating of

screws in inner liner flange assembly. Average density of insulation must be 0.13 g/cc (8 pounds per cubic foot (pcf)) minimum for bottom section and 0.16 g/cc (10 pcf) minimum for top section, except 0.1 g/cc (6.5 pcf) for the specification 20PF-1 top section.

(b) Gaskets must be as follows:

(1) Inner liner flange—Neoprene rubber of 30 to 60 type A durometer hardness or other equivalent gasket material which is compatible with the specific contents.

(2) Outer shell—Synthetic rubber conforming to MIL-R-6855 (available from the Naval Publications Forms Center, 5801 Tabor Avenue, Philadelphia, Pennsylvania 19120) class 2, grade 60.

(3) Support and pressure pads for inner liner top and bottom must be sponge rubber or equivalent.

(c) Alternate top section (specification 20PF-1 only). Average insulation density must be 0.16 g/cc (10 pcf minimum). Thickness of plug must be 11 cm (4.3 inches) minimum, except thickness may be reduced to 10 cm (4 inches) to clear bolt heads. A flush mounted top lifting device must be securely fastened to a wood block encapsulated by the foam.

(d) Vent holes 5 mm (0.2-inch) diameter must be drilled in the outer shell to provide pressure relief during the insulation foaming and in the event of a fire. These holes, which must be drilled in all areas of the shell that mate with the foam insulation, must be spaced in accordance with DOE CAPE-1662, Rev. 1 and Supplement 1 (IBR, see §171.7 of this subchapter).

(e) Welding must be by a fusion welding process in accordance with American Welding Society Codes B-3.0 and D-1.0 (IBR, see §171.7 of this subchapter). Body seams and joints for the liner or shell must be continuous welds.

(f) Waterproofing. Each screw hole in the outer shell must be sealed with appropriate resin-type sealing material, or equivalent, during installation of the screw. All exposed foam surfaces,

including any vent hole, must be sealed with waterproofing material as prescribed in USDOE Material and Equipment Specification SP-9, Rev. 1 and Supplement, or equivalent.

[Amdt. 178-35, 39 FR 45247, Dec. 31, 1974, as amended by Amdt. 178-56, 44 FR 49458, Aug. 23, 1979. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 66 FR 45387, Aug. 28, 2001; 68 FR 75757, Dec. 31, 2003]

#### § 178.356-3 Tests.

(a) Leakage test—Each inner liner assembly must be tested for leakage prior to installation. Seam welds of the liner must be covered for a distance of at least 15 cm (6 inches) on either side of the seam with soapsuds, heavy oil, or equivalent material, and interior air pressure applied to at least 776 mm Hg (15 p.s.i.g.) above atmospheric pressure must be held for at least 30 seconds. Liners failing to pass this test may not be used until repairs are made, and retests successfully passed.

(b) [Reserved]

[Amdt. 178-35, 39 FR 45247, Dec. 31, 1974. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 66 FR 45387, Aug. 28, 2001; 67 FR 61016, Sept. 27, 2002]

#### § 178.356-4 Required markings.

(a) Marking must be as prescribed in §178.3.

(b) Marking on the outside of each overpack must be as follows:

(1) “USA-DOT-20PF-1” or “-2,” as appropriate, and if the entire liner is made of stainless steel, additional marking such as “3041-SS” to indicate the type of stainless steel used.


(2) “TARE WT: xxx lbs.” where xxx is the tare weight of the assembled overpack without the inner container.

(3) Year of manufacture.

[Amdt. 178-35, 39 FR 45247, Dec. 31, 1974. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990, as amended at 63 FR 37462, July 10, 1998]


#### § 178.356-5 Typical assembly detail.

(a) Specifications 20PF-1.



(b) Specification 20PF-2.





[Amdt. 178-35, 39 FR 45247, Dec. 31, 1974. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990]

**§ 178.358 Specification 21PF fire and shock resistant, phenolic-foam insulated, metal overpack.****§ 178.358-1 General requirements.**

(a) Each overpack must meet all of the applicable requirements of §§ 173.24, 173.411, and 173.412 of this subchapter.

(1) Specification 21PF-1 overpacks includes the series of 21PF-1, 21PF-1A, and 21PF-1B models. Details of the three models are included in DOE CAPE-1662, Rev. 1 and Supplement 1 (IBR, see § 171.7 of this subchapter).

(2) Drawings in CAPE-1662, Rev. 1 and Supplement 1, that include bills of materials, and KSS-471 (IBR, see § 171.7 of this subchapter), are a part of this specification.

(b) Each overpack is authorized for use in applications where the maximum gross weight of the package, including the inner container and contents does not exceed 3725 kg (8200 pounds), (horizontally-loaded specification 21 PF-1 unit), or 3900 kg (8600 pounds), (end-loaded specification 21 PF-2 unit).

(c) The general configuration of the overpack must be a right cylinder, consisting of a steel inner liner (at least 16-gauge) and steel outer shell (at least 14-gauge) with the intervening cavity filled with a molded-in-place, fire-resistant, phenolic foam insulation and interspersed wooden members for bracing and support. Two specific configurations are authorized; a horizontal loading unit (specification 21PF-1) consisting of insulated base and top sections jointed in a longitudinal peripheral closure joint; or an end-loading unit (specification 21PF-2), consisting of an insulated main section, a steel plate liner lid, and an insulated end cap. For either type each joint between sections must be stepped at least 1.8 cm (0.75-inch) and gaps between mating surfaces may not exceed 5 mm (0.2-inch). Bolted closures, which must each be gasketed against moisture penetration, must be in accordance with CAPE-1662. Each bolt must be equipped with a locking device to prevent loosening from vibration. Outer steel bracing and support framework must be attached to the shell to facilitate normal handling.

(d) Specification 21PF-1 overpacks in use or under construction before April 1, 1989, must be modified to Specification 21PF-1A before April 1, 1991. All new construction to Specification 21PF-1 beginning after March 31, 1989, must meet Specification 21PF-1B. Use of unmodified 21PF-1 overpacks after March 31, 1991, is prohibited.

[Amdt. 178-35, 39 FR 45250, Dec. 31, 1974; 40 FR 2435, Jan. 13, 1975, as amended by Amdt. 178-90, 53 FR 36551, Sept. 20, 1988. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 66 FR 45387, Aug. 28, 2001; 68 FR 75757, Dec. 31, 2003]

**§ 178.358-2 Materials of construction and other requirements.**

(a) Phenolic foam insulation must be fire resistant and fabricated in accordance with USDOE Material and Equipment Specification SP-9, Rev. 1 and Supplement (IBR, see § 171.7 of this subchapter), which is a part of this specification. (Note: Packagings manufactured under USAEC Specification SP-9, and Rev. 1 thereto are authorized for continued manufacture and use.) A 14 cm (5.5-inch) minimum thickness of foam must be provided over the entire liner except where:

(1) Wood spacers replace the foam material; or

(2) At protrusions of liner or shell, such as flanges, baffles, etc., where the minimum thickness of foam, wood, or a combination of these is 10 cm (4 inches).

(3) Solid wood or laminated wood solidly glued may be used to replace the foam between liner and shell (i.e., in ends of overpack). In this case, minimum wood thickness is 10 cm (4 inches). Average density of insulation must be 0.1g/cc (6.75 pounds per cubic foot (pcf)) minimum, except that 0.13 g/cc (8 pcf) is required in the removable end cap of the specification 21PF-2, which must have a minimum foam thickness of 12.7 cm (5 inches).

(b) Gaskets for inner liner, outer shell, or where otherwise specified in DOE CAPE-1662, Rev. 1 (IBR, see § 171.7 of this subchapter), must be as specified in DOE CAPE-1662, Rev. 1.

(c) Support and pressure pads for the inner liner must be of neoprene, sponge rubber, or equivalent.

(d) Fire-retardant (intumescent) paint must be applied to any wood blocking which is located at any joint in the shell.

(e) Vent holes 5 mm (0.2-inch) diameter must be drilled in the outer shell to provide pressure relief during the insulation foaming and in the event of a fire. These holes, which must be drilled in all areas of the shell which made with the foam insulation, must be spaced in accordance with CAPE-1662.

(f) Welding must be by a fusion process in accordance with the American Welding Society Codes B-3.0 and D-1.0 (IBR, see §171.7 of this subchapter). Body seams and joints for the liner and shell must be continuous welds.

(g) *Waterproofing.* Each screw hole in the outer shell must be sealed with appropriate resin-type sealing material, or equivalent, during installation of the screw. All exposed foam surfaces, including any vent hole, must be sealed with either:

(1) Waterproofing material as prescribed in USDOE Material and Equipment Specification SP-9, Rev. 1 and Supplement, or

(2) As specified in CAPE-1662, Revision 1.

[Amdt. 178-35, 39 FR 45250, Dec. 31, 1974, as amended by Amdt. 178-56, 44 FR 49459, Aug. 23, 1979; Amdt. 178-90, 53 FR 36551, Sept. 20, 1988. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 66 FR 45387, Aug. 28, 2001; 68 FR 75757, Dec. 31, 2003]

**§ 178.358-3 Modification of Specification 21PF-1 overpacks.**

(a) Each Specification 21PF-1 overpack for which construction began or was completed before April 1, 1989, in conformance with drawing E-S-31536-J, Rev. 1 of DOE CAPE-1662 (IBR, see §171.7 of this subchapter), must be modified in conformance with drawing S1E-31536-J1-D of DOE CAPE-1662, Rev. 1, Supplement 1, before April 1, 1991.

(b) Each such existing Specification 21PF-1 overpack must be dried and weighed in accordance with the following procedures:

(1) Drill out or otherwise clean the plug material from the vent holes originally provided for foam expansion. See drawing S1E-31536-J1-D of CAPE-

1662, Revision 1, Supplement 1, for locations.

(2) Weigh each packaging element (top and bottom halves) separately to an accuracy of  $\pm 2.3$  kg ( $\pm 5$  pounds) and record the weights. If this measured weight exceeds the initially measured weight at the time of fabrication by 11.3 kg (25 pounds) (indicating a significant retained water content), the packaging element must be dried.

(3) Place overpack element in drying oven; maintain temperature between 87.8-98.9 °C (190° and 210 °F) for a minimum of 72 hours. The oven should have a provision for air exchange or other means of removing moisture driven from the foam structure.

(4) Drying may be discontinued after 72 hours if the weight of the packaging element does not exceed the initially measured tare weight of that element at the time of fabrication by more than 11.3 kg (25 pounds). If the weight of the packaging element exceeds the initial fabricated weight (indicating a significant remaining water content) by more than 11.3 kg (25 pounds), drying must be continued until the weight differential is not higher than 11.3 kg (25 pounds), or until the rate of weight loss is less than 1.1 kg (2.5 pounds) per day.

(5) As an alternate moisture measurement, a calibrated moisture meter reading for 20 percent maximum water content may be used to indicate an end point in the drying cycle, which is detailed in report "Renovation of DOT Specification 21PF-1 Protective Shipping Packages," Report No. K-2057, Revision 1, November 21, 1986, available from the USDOE and part of USDOE Report No. KSS-471 (IBR, see §171.7 of this subchapter).

(6) Following drying, each overpack element (top and bottom halves) must be weighed and the weight in both pounds and kilograms must be engraved on the identification plate required by §178.358-5(c).

(c) After modification as provided for herein, each Specification 21PF-1 overpack must be marked "USA-DOT-21PF-

1A". See the marking requirements of § 178.358-5.

[Amdt. 178-90, 53 FR 36551, Sept. 20, 1988. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; Amdt. 178-110, 60 FR 49111, Sept. 21, 1995; 63 FR 37462, July 10, 1998; 66 FR 45389, Aug. 28, 2001; 68 FR 75757, Dec. 31, 2003]

#### **§ 178.358-4 Construction of Specification 21PF-1B overpacks.**

(a) Each Specification 21PF-1 overpack for which construction began after March 31, 1989, must meet the requirements of Specification 21PF-1B, in conformance with drawings E-S-31536-J-P, and S1E-31536-J2-B of DOE CAPE-1662, Rev. 1, Supplement 1 (IBR, see § 171.7 of this subchapter).

(b) With the exception of the closure nuts and bolts, all metal parts of the Specification 21PF-1B must be of stainless steel as shown on the drawings referred to in paragraph (a) of this section.

[Amdt. 178-90, 53 FR 36551, Sept. 20, 1988. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 68 FR 75757, Dec. 31, 2003]

#### **§ 178.358-5 Required markings.**

(a) Markings must be as prescribed in § 178.3.

(b) Specification marking on the outside of each overpack must be as follows: "USA-DOT-21PF-1", "1A", "1B", or "2", as appropriate.

(1) For Specifications 21PF-1 and 21PF-2 only, if the inner shell is constructed of stainless steel, additional marking such as "304L-SS" are to be marked on the outside of the overpack to indicate the type of stainless steel used.

(2) For Specification 21PF-1 and 21PF-2 only, "TARE WT: \* \* \* lbs. (\* \* \* kg)" where \* \* \* is the tare weight in pounds and kilograms, respectively, of the assembled overpack without the inner product container.

(3) For Specification 21PF-1A and 21PF-1B only: "TARE WT. of Cover: \* \* \* lbs (\* \* \* kg) TARE WT. of BOTTOM: \* \* \* lbs (\* \* \* kg)" where \* \* \* is the tare weight in pounds and kilograms, respectively, of the separate halves of the overpack without the inner product container. For Specification 21PF-1A overpacks, the previous tare weight must be changed to reflect the modified tare weight value or must be covered or removed.

(4) Year of manufacture followed by the year of modification, if applicable.

(5) The name or symbol of maker or party certifying compliance with specification requirements. A symbol, if used, must be registered with the Associate Administrator.


(c) For Specification 21PF-1A and -1B only, the markings required by this section must be affixed to each overpack by inscription upon a metal identification plate 11 inches wide × 15 inches long (28 cm × 38 cm), fabricated of 16 to 20 gauge stainless steel sheet, ASTM A-240/A 240M (IBR, see § 171.7 of this subchapter), Type 304L.

[Amdt. 178-90, 53 FR 36552, Sept. 20, 1988. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990, and amended at Amdt. 178-97, 56 FR 66287, Dec. 20, 1991; 63 FR 37462, July 10, 1998; 66 FR 45386, Aug. 28, 2001; 67 FR 51660, Aug. 8, 2002; 68 FR 75748, Dec. 31, 2003; 69 FR 54046, Sept. 7, 2004]



#### **§ 178.358-6 Typical assembly detail.**

(a) Specification 21PF-1 (horizontal loading overpack).






(b) Specification 21PF-1A and 21PF-1B (horizontal loading overpack).




JOINT DETAIL  
DOT SPECIFICATION 21PF-1A  
OVERPACK



JOINT DETAIL  
DOT SPECIFICATION 21PF-1B  
OVERPACK

(c) Specification 21PF-2 (end loading overpack).



[Amdt. 178-90, 53 FR 36552, Sept. 20, 1988. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990]

**§ 178.360 Specification 2R; inside containment vessel.****§ 178.360-1 General requirements.**

(a) Each vessel must be made of stainless steel, malleable iron, or brass, or other material having equivalent physical strength and fire resistance.

(b) Each vessel must meet all of the applicable requirements of § 173.24 (c) and (d) of this subchapter. Letters and numerals at least 6 mm (¼-inch) in height are authorized for the marking of a vessel not exceeding 5 cm (2 inches) inside diameter.

[Amdt. 178-35, 39 FR 45245, Dec. 31, 1974. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 66 FR 45387, Aug. 28, 2001]

**§ 178.360-2 Manufacture.**

The ends of the vessel must be fitted with screw-type closures or flanges (see § 178.360-4), except that one or both ends of the vessel may be permanently closed by a welded or brazed plate. Welded or brazed side seams are authorized.

[Amdt. 178-35, 39 FR 45245, Dec. 31, 1974. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990, as amended at 63 FR 37462, July 10, 1998]

**§ 178.360-3 Dimensions.**

(a) The inside diameter of the vessel may not exceed 30 cm (12 inches) exclusive of flanges for handling or fastening devices and must have wall thickness and length in accordance with the following:

| Inside diameter maximum |    | Threaded closure |     | Wall thickness minimum—Flanged closure                   | Length maximum |     |
|-------------------------|----|------------------|-----|----------------------------------------------------------|----------------|-----|
| Inches                  | Cm | Inches           | Mm  |                                                          | Inches         | Cm  |
| 2                       | 5  | ⅜                | 2.5 | Not less than that prescribed for schedule 40 pipe ..... | 16             | 41  |
| 6                       | 15 | ⅜                | 3.2 | .....                                                    | 72             | 183 |
| 12                      | 30 | ¾                | 6.5 | .....                                                    | 72             | 183 |

(b) [Reserved]

[Amdt. 178-35, 39 FR 45245, Dec. 31, 1974. Redesignated by Amdt. 178-97, 55 FR 52716, Dec. 21, 1990; 66 FR 45387, Aug. 28, 2001]

**§ 178.360-4 Closure devices.**

(a) Each closure device must be as follows:

(1) Screw-type cap or plug; number of threads per inch must not be less than United States standard pipe threads and must have sufficient length of thread to engage at least 5 threads when securely tightened. Pipe threads must be luted with an appropriate non-hardening compound which must be capable of withstanding up to 149 °C (300 °F) without loss of efficiency. Tightening torque must be adequate to maintain leak tightness with the specific luting compound.

(2) An opening may be closed by a securely bolted flange and leak-tight gasket. Each flange must be welded or brazed to the body of the 2R vessel per (ANSI) Standard B16.5 or (AWWA) Standard C207-55, section 10 (IBR, see

§ 171.7 of this subchapter). A torque wrench must be used in securing the flange with a corresponding torque of no more than twice the force necessary to seal the selected gasket. Gasket material must be capable of withstanding up to 149 °C (300 °F) without loss of efficiency. The flange, whether of ferrous or nonferrous metal, must be constructed from the same metal as the vessel and must meet the dimensional and fabrication specifications for welded construction as follows:

(i) Pipe flanges described in Tables 13, 14, 16, 17, 19, 20, 22, 23, 25 and 26 of ANSI B16.5 (IBR, see § 171.7 of this subchapter).

(ii) For nominal pipe sizes, 6, 8, 10, and 12 inches, AWWA Standard C207-55, Table 1, class B, may be used in place of the tables prescribed by paragraph (a)(2)(i) of this section.

**§ 178.500**

**49 CFR Ch. I (10–1–08 Edition)**

(iii) Sizes under 6 inches, nominal pipe size, the following table with the same configuration as illustrated in

AWWA C207–55, Table 1, class B, may be used in place of paragraph (a)(2)(i) of this section.

| Nominal pipe size |      | Flange O.D. |      | Number of bolts | Bolt circle diameter |      | Diameter of bolts |       | Flange thickness |       |
|-------------------|------|-------------|------|-----------------|----------------------|------|-------------------|-------|------------------|-------|
| Inches            | Cm   | Inches      | Cm   |                 | Inches               | Cm   | Inches            | Cm    | Inches           | Cm    |
| 2                 | 5    | 6           | 15   | 4               | 4¾                   | 11.8 | ½                 | 1.2   | ⅝                | 1.6   |
| 2½                | 6.2  | 7           | 17.5 | 4               | 5½                   | 13.8 | ½                 | ..... | ⅝                | ..... |
| 3                 | 7.5  | 7½          | 18.8 | 4               | 6                    | 15   | ½                 | ..... | ⅝                | ..... |
| 3½                | 8.8  | 8½          | 21.3 | 8               | 7                    | 17.5 | ½                 | ..... | ⅝                | ..... |
| 4                 | 10   | 9           | 22.5 | 8               | 7½                   | 18.8 | ½                 | ..... | ⅝                | ..... |
| 5                 | 12.6 | 10          | 25.4 | 8               | 8½                   | 21.3 | ½                 | ..... | ⅝                | ..... |

(iv) Cast iron flanges prohibited.

(b) [Reserved]

[Amdt. 178–35, 39 FR 45245, Dec. 31, 1974; 40 FR 2435, Jan. 13, 1975, as amended at 40 FR 44327, Sept. 26, 1975. Redesignated by Amdt. 178–97, 56 FR 66284, Dec. 20, 1991; 68 FR 75757, Dec. 31, 2003]

**Subpart L—Non-bulk Performance-Oriented Packaging Standards**

SOURCE: Amdt. 178–97, 55 FR 52717, Dec. 21, 1990, unless otherwise noted.

**§ 178.500 Purpose, scope and definitions.**

(a) This subpart prescribes certain requirements for non-bulk packagings for hazardous materials. Standards for these packagings are based on the UN Recommendations.

(b) Terms used in this subpart are defined in § 171.8 of this subchapter.

**§ 178.502 Identification codes for packagings.**

(a) Identification codes for designating kinds of packagings consist of the following:

(1) A numeral indicating the kind of packaging, as follows:

- (i) “1” means a drum.
- (ii) “2” means a wooden barrel.
- (iii) “3” means a jerrican.
- (iv) “4” means a box.
- (v) “5” means a bag.
- (vi) “6” means a composite packaging.
- (vii) “7” means a pressure receptacle.

(2) A capital letter indicating the material of construction, as follows:

- (i) “A” means steel (all types and surface treatments).
- (ii) “B” means aluminum.

(iii) “C” means natural wood.

(iv) “D” means plywood.

(v) “F” means reconstituted wood.

(vi) “G” means fiberboard.

(vii) “H” means plastic.

(viii) “L” means textile.

(ix) “M” means paper, multi-wall.

(x) “N” means metal (other than steel or aluminum).

(xi) “P” means glass, porcelain or stoneware.

(3) A numeral indicating the category of packaging within the kind to which the packaging belongs. For example, for steel drums (“1A”), “1” indicates a non-removable head drum (i.e., “1A1”) and “2” indicates a removable head drum (i.e., “1A2”).

(b) For composite packagings, two capital letters are used in sequence in the second position of the code, the first indicating the material of the inner receptacle and the second, that of the outer packaging. For example, a plastic receptacle in a steel drum is designated “6HA1”.

(c) For combination packagings, only the code number for the outer packaging is used.

(d) Identification codes are set forth in the standards for packagings in §§ 178.504 through 178.523 of this subpart.

[Amdt. 178–97, 55 FR 52717, Dec. 21, 1990, as amended by Amdt. 178–106, 59 FR 67519, Dec. 29, 1994]

**§ 178.503 Marking of packagings.**

(a) A manufacturer must mark every packaging that is represented as manufactured to meet a UN standard with the marks specified in this section. The markings must be durable, legible and placed in a location and of such a size

relative to the packaging as to be readily visible, as specified in §178.3(a). Except as otherwise provided in this section, every reusable packaging liable to undergo a reconditioning process which might obliterate the packaging marks must bear the marks specified in paragraphs (a)(1) through (a)(6) and (a)(9) of this section in a permanent form (e.g. embossed) able to withstand the reconditioning process. A marking may be applied in a single line or in multiple lines provided the correct sequence is used. As illustrated by the examples in paragraph (e) of this section, the following information must be presented in the correct sequence. Slash marks should be used to separate this information. A packaging conforming to a UN standard must be marked as follows:

(1) The United Nations symbol as illustrated in paragraph (e)(1) of this section (for embossed metal receptacles, the letters UN may be applied in place of the symbol);

(2) A packaging identification code designating the type of packaging, the material of construction and, when appropriate, the category of packaging under §§178.504 through 178.523 of this subpart within the type to which the packaging belongs. The letter "V" must follow the packaging identification code on packagings tested in accordance with §178.601(g)(2); for example, "4GV". The letter "W" must follow the packaging identification code on packagings when required by an approval under the provisions of §178.601(h) of this part;

(3) A letter identifying the performance standard under which the packaging design type has been successfully tested, as follows:

(i) X—for packagings meeting Packing Group I, II and III tests;

(ii) Y—for packagings meeting Packing Group II and III tests; or

(iii) Z—for packagings only meeting Packing Group III tests;

(4) A designation of the specific gravity or mass for which the packaging design type has been tested, as follows:

(i) For packagings without inner packagings intended to contain liquids, the designation shall be the specific gravity rounded down to the first dec-

imal but may be omitted when the specific gravity does not exceed 1.2; and

(ii) For packagings intended to contain solids or inner packagings, the designation shall be the maximum gross mass in kilograms;

(5)(i) For single and composite packagings intended to contain liquids, the test pressure in kilopascals rounded down to the nearest 10 kPa of the hydrostatic pressure test that the packaging design type has successfully passed;

(ii) For packagings intended to contain solids or inner packagings, the letter "S";

(6) The last two digits of the year of manufacture. Packagings of types 1H and 3H shall also be marked with the month of manufacture in any appropriate manner; this may be marked on the packaging in a different place from the remainder of the markings;

(7) The state authorizing allocation of the mark. The letters 'USA' indicate that the packaging is manufactured and marked in the United States in compliance with the provisions of this subchapter;

(8) The name and address or symbol of the manufacturer or the approval agency certifying compliance with subpart L and subpart M of this part. Symbols, if used, must be registered with the Associate Administrator;

(9) For metal or plastic drums or jerricans intended for reuse or reconditioning as single packagings or the outer packagings of a composite packaging, the thickness of the packaging material, expressed in mm (rounded to the nearest 0.1 mm), as follows:

(i) Metal drums or jerricans must be marked with the nominal thickness of the metal used in the body. The marked nominal thickness must not exceed the minimum thickness of the steel used by more than the thickness tolerance stated in ISO 3574 (IBR, see §171.7 of this subchapter). (See appendix C of this part.) The unit of measure is not required to be marked. When the nominal thickness of either head of a metal drum is thinner than that of the body, the nominal thickness of the top head, body, and bottom head must be marked (e.g., "1.0-1.2-1.0" or "0.9-1.0-1.0").

(ii) Plastic drums or jerricans must be marked with the minimum thickness of the packaging material. Minimum thicknesses of plastic must be as determined in accordance with § 173.28(b)(4). The unit of measure is not required to be marked;

(10) In addition to the markings prescribed in paragraphs (a)(1) through (a)(9) of this section, every new metal drum having a capacity greater than 100 L must bear the marks described in paragraphs (a)(1) through (a)(6), and (a)(9)(i) of this section, in a permanent form, on the bottom. The markings on the top head or side of these packagings need not be permanent, and need not include the thickness mark described in paragraph (a)(9) of this section. This marking indicates a drum's characteristics at the time it was manufactured, and the information in paragraphs (a)(1) through (a)(6) of this section that is marked on the top head or side must be the same as the information in paragraphs (a)(1) through (a)(6) of this section permanently marked by the original manufacturer on the bottom of the drum; and

(11) Rated capacity of the packaging expressed in liters may be marked.

(b) For a packaging with a removable head, the markings may not be applied only to the removable head.

(c) *Marking of reconditioned packagings.* (1) If a packaging is reconditioned, it shall be marked by the reconditioner near the marks required in paragraphs (a)(1) through (6) of this section with the following additional information:

(i) The name of the country in which the reconditioning was performed (in the United States, use the letters "USA");

(ii) The name and address or symbol of the reconditioner. Symbols, if used, must be registered with the Associate Administrator;

(iii) The last two digits of the year of reconditioning;

(iv) The letter "R"; and

(v) For every packaging successfully passing a leakproofness test, the additional letter "L".


(2) When, after reconditioning, the markings required by paragraph (a)(1) through (a)(5) of this section no longer

appear on the top head or the side of the metal drum, the reconditioner must apply them in a durable form followed by the markings in paragraph (c)(1) of this section. These markings may identify a different performance capability than that for which the original design type had been tested and marked, but may not identify a greater performance capability. The markings applied in accordance with this paragraph may be different from those which are permanently marked on the bottom of a drum in accordance with paragraph (a)(10) of this section.

(d) *Marking of remanufactured packagings.* For remanufactured metal drums, if there is no change to the packaging type and no replacement or removal of integral structural components, the required markings need not be permanent (e.g., embossed). Every other remanufactured drum must bear the marks required in paragraphs (a)(1) through (a)(6) of this section in a permanent form (e.g., embossed) on the top head or side. If the metal thickness marking required in paragraph (a)(9)(i) of this section does not appear on the bottom of the drum, or if it is no longer valid, the remanufacturer also must mark this information in permanent form.


(e) The following are examples of symbols and required markings:

(1) The United Nations symbol is:



(2) Examples of markings for a new packaging are as follows:

(i) For a fiberboard box designed to contain an inner packaging:




4G/Y145/S/83

USA/RA

(as in §178.503 (a)(1) through (a)(9) of this subpart).

(ii) For a steel drum designed to contain liquids:




1A1/Y1.4/150/83

USA/VL824

1.0

(as in §178.503 (a)(1) through (a)(10) of this subpart).

(iii) For a steel drum to transport solids or inner packagings:



1A2/Y150/S/83

USA/VL825

(as in §178.503 (a)(1) through (a)(8) of this subpart).

(3) Examples of markings for reconditioned packagings are as follows:

1A1/Y1.4/150/92  
USA/RB/93 RL

(as in §178.503(c)(1)).

(f) A manufacturer must mark every UN specification package represented as manufactured to meet the requirements of §178.609 for packaging of infectious substances with the marks specified in this section. The markings

must be durable, legible, and must be readily visible, as specified in §178.3(a). An infectious substance packaging that successfully passes the tests conforming to the UN standard must be marked as follows:

(1) The United Nations symbol as illustrated in paragraph (e) of this section.

(2) The code designating the type of packaging and material of construction according to the identification codes for packagings specified in §178.502.

(3) The text "CLASS 6.2".

(4) The last two digits of the year of manufacture of the packaging.

(5) The country authorizing the allocation of the mark. The letters "USA" indicate the packaging is manufactured and marked in the United States in compliance with the provisions of this subchapter.

(6) The name and address or symbol of the manufacturer or the approval agency certifying compliance with subparts L and M of this part. Symbols, if used, must be registered with the Associate Administrator for Hazardous Materials Safety.

(7) For packagings meeting the requirements of §178.609(i)(3), the letter "U" must be inserted immediately following the marking designating the type of packaging and material required in paragraph (f)(2) of this section.

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended at 56 FR 66284, Dec. 20, 1991; Amdt. 178-102, 59 FR 28493, June 2, 1994; Amdt. 178-106, 59 FR 67520, 67521, Dec. 29, 1994; Amdt. 178-107, 60 FR 26806, May 18, 1995; 62 FR 51561, Oct. 1, 1997; 66 FR 45386, Aug. 28, 2001; 67 FR 61016, Sept. 27, 2002; 67 FR 53143, Aug. 14, 2002; 68 FR 75757, Dec. 31, 2003]

#### § 178.504 Standards for steel drums.

(a) The following are identification codes for steel drums:

(1) 1A1 for a non-removable head steel drum; and

(2) 1A2 for a removable head steel drum.

(b) Construction requirements for steel drums are as follows:

(1) Body and heads must be constructed of steel sheet of suitable type and adequate thickness in relation to the capacity and intended use of the



## § 178.505

drum. Minimum thickness and marking requirements in §§173.28(b)(4) and 178.503(a)(9) of this subchapter apply to drums intended for reuse.

(2) Body seams must be welded on drums designed to contain more than 40 L (11 gallons) of liquids. Body seams must be mechanically seamed or welded on drums intended to contain only solids or 40 L (11 gallons) or less of liquids.

(3) Chimes must be mechanically seamed or welded. Separate reinforcing rings may be applied.

(4) The body of a drum of a capacity greater than 60 L (16 gallons) may have at least two expanded rolling hoops or two separate rolling hoops. If there are separate rolling hoops, they must be fitted tightly on the body and so secured that they cannot shift. Rolling hoops may not be spot-welded.

(5) Openings for filling, emptying and venting in the bodies or heads of non-removable head (1A1) drums may not exceed 7.0 cm (3 inches) in diameter. Drums with larger openings are considered to be of the removable head type (1A2). Closures for openings in the bodies and heads of drums must be so designed and applied that they will remain secure and leakproof under normal conditions of transport. Closure flanges may be mechanically seamed or welded in place. Gaskets or other sealing elements must be used with closures unless the closure is inherently leakproof.

(6) Closure devices for removable head drums must be so designed and applied that they will remain secure and drums will remain leakproof under normal conditions of transport. Gaskets or other sealing elements must be used with all removable heads.

(7) If materials used for body, heads, closures, and fittings are not in themselves compatible with the contents to be transported, suitable internal protective coatings or treatments must be applied. These coatings or treatments must retain their protective properties under normal conditions of transport.

(8) Maximum capacity of drum: 450 L (119 gallons).

## 49 CFR Ch. I (10–1–08 Edition)

(9) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178–97, 55 FR 52717, Dec. 21, 1990, as amended at 56 FR 66284, Dec. 20, 1991; Amdt. 178–110, 60 FR 49111, Sept. 21, 1995]

### § 178.505 Standards for aluminum drums.

(a) The following are the identification codes for aluminum drums:

(1) 1B1 for a non-removable head aluminum drum; and

(2) 1B2 for a removable head aluminum drum.

(b) Construction requirements for aluminum drums are as follows:

(1) Body and heads must be constructed of aluminum at least 99 percent pure or an aluminum base alloy. Material must be of suitable type and adequate thickness in relation to the capacity and the intended use of the drum. Minimum thickness and marking requirements in §§173.28(b)(4) and 178.503(a)(9) of this subchapter apply to drums intended for reuse.

(2) All seams must be welded. Chime seams, if any, must be reinforced by the application of separate reinforcing rings.

(3) The body of a drum of a capacity greater than 60 L (16 gallons) may have at least two expanded rolling hoops or two separate rolling hoops. If there are separate rolling hoops, the hoops must be fitted tightly on the body and so secured that they cannot shift. Rolling hoops may not be spot-welded.

(4) Openings for filling, emptying, or venting in the bodies or heads of non-removable head (1B1) drums may not exceed 7.0 cm (3 inches) in diameter. Drums with larger openings are considered to be of the removable head type (1B2). Closures for openings in the bodies and heads of drums must be so designed and applied that they will remain secure and leakproof under normal conditions of transport. Closure flanges may be welded in place so that the weld provides a leakproof seam. Gaskets or other sealing elements must be used with closures unless the closure is inherently leakproof.

(5) Closure devices for removable head drums must be so designed and applied that they remain secure and drums remain leakproof under normal conditions of transport. Gaskets or

other sealing elements must be used with all removable heads.

(6) Maximum capacity of drum: 450 L (119 gallons).

(7) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended at 56 FR 66284, Dec. 20, 1991; Amdt. 178-102, 59 FR 28494, June 2, 1994]

**§ 178.506 Standards for metal drums other than steel or aluminum.**

(a) The following are the identification codes for metal drums other than steel or aluminum:

(1) 1N1 for a non-removable head metal drum; and

(2) 1N2 for a removable head metal drum.

(b) Construction requirements for metal drums other than steel or aluminum are as follows:

(1) Body and heads must be constructed of metal (other than steel or aluminum) of suitable type and adequate thickness in relation to the capacity and the intended use of the drum. Minimum thickness and marking requirements in §§ 173.28(b)(4) and 178.503(a)(9) of this subchapter apply to drums intended for reuse.

(2) All seams must be welded. Chime seams, if any, must be reinforced by the application of separate reinforcing rings.

(3) The body of a drum of a capacity greater than 60 L (16 gallons) may have at least two expanded rolling hoops or two separate rolling hoops. If there are separate rolling hoops, the hoops must be fitted tightly on the body and so secured that they cannot shift. Rolling hoops may not be spot-welded.

(4) Openings for filling, emptying, or venting in the bodies or heads of non-removable head (1N1) drums may not exceed 7.0 cm (3 inches) in diameter. Drums with larger openings are considered to be of the removable head type (1N2). Closures for openings in the bodies and heads of drums must be so designed and applied that they will remain secure and leakproof under normal conditions of transport. Closure flanges may be welded in place so that the weld provides a leakproof seam. Gaskets or other sealing elements must be used with closures unless the closure is inherently leakproof.

(5) Closure devices for removable head drums must be so designed and applied that they remain secure and drums remain leakproof under normal conditions of transport. Gaskets or other sealing elements must be used with all removable heads.

(6) Maximum capacity of drum: 450 L (119 gallons).

(7) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended at 56 FR 66285, Dec. 20, 1991; Amdt. 178-102, 59 FR 28494, June 2, 1994]

**§ 178.507 Standards for plywood drums.**

(a) The identification code for a plywood drum is 1D.

(b) Construction requirements for plywood drums are as follows:

(1) The wood used must be well-seasoned, commercially dry and free from any defect likely to lessen the effectiveness of the drum for the purpose intended. A material other than plywood, of at least equivalent strength and durability, may be used for the manufacture of the heads.

(2) At least two-ply plywood must be used for the body and at least three-ply plywood for the heads; the plies must be firmly glued together, with their grains crosswise.

(3) The body and heads of the drum and their joints must be of a design appropriate to the capacity of the drum and its intended use.

(4) In order to prevent sifting of the contents, lids must be lined with kraft paper or some other equivalent material which must be securely fastened to the lid and extend to the outside along its full circumference.

(5) Maximum capacity of drum: 250 L (66 gallons).

(6) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended at 57 FR 45465, Oct. 1, 1992]

**§ 178.508 Standards for fiber drums.**

(a) The identification code for a fiber drum is 1G.

(b) Construction requirements for fiber drums are as follows:

(1) The body of the drum must be constructed of multiple plies of heavy

paper or fiberboard (without corrugations) firmly glued or laminated together and may include one or more protective layers of bitumen, waxed kraft paper, metal foil, plastic material, or similar materials.

(2) Heads must be of natural wood, fiberboard, metal, plywood, plastics, or other suitable material and may include one or more protective layers of bitumen, waxed kraft paper, metal foil, plastic material, or similar material.

(3) The body and heads of the drum and their joints must be of a design appropriate to the capacity and intended use of the drum.

(4) The assembled packaging must be sufficiently water-resistant so as not to delaminate under normal conditions of transport.

(5) Maximum capacity of drum: 450 L (119 gallons).

(6) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178–97, 55 FR 52717, Dec. 21, 1990, as amended by Amdt. 178–106, 59 FR 67521, Dec. 29, 1994]

**§ 178.509 Standards for plastic drums and jerricans.**

(a) The following are identification codes for plastic drums and jerricans:

(1) 1H1 for a non-removable head plastic drum;

(2) 1H2 for a removable head plastic drum;

(3) 3H1 for a non-removable head jerrican; and

(4) 3H2 for a removable head jerrican.

(b) Construction requirements for plastic drums and jerricans are as follows:

(1) The packaging must be manufactured from suitable plastic material and be of adequate strength in relation to its capacity and intended use. No used material other than production residues or regrind from the same manufacturing process may be used unless approved by the Associate Administrator. The packaging must be adequately resistant to aging and to degradation caused either by the substance contained or by ultra-violet radiation. Any permeation of the substance contained may not constitute a danger under normal conditions of transport.

(2) If protection against ultra-violet radiation is required, it must be provided by the addition of carbon black or other suitable pigments or inhibitors. These additives must be compatible with the contents and remain effective throughout the life of the packaging. Where use is made of carbon black, pigments or inhibitors other than those used in the manufacture of the design type, retesting may be omitted if the carbon black content does not exceed 2 percent by mass or if the pigment content does not exceed 3 percent by mass; the content of inhibitors of ultra-violet radiation is not limited.

(3) Additives serving purposes other than protection against ultra-violet radiation may be included in the composition of the plastic material provided they do not adversely affect the chemical and physical properties of the packaging material.

(4) The wall thickness at every point of the packaging must be appropriate to its capacity and its intended use, taking into account the stresses to which each point is liable to be exposed. Minimum thickness and marking requirements in §§ 173.28(b)(4) and 178.503(a)(9) of this subchapter apply to drums intended for reuse.

(5) Openings for filling, emptying and venting in the bodies or heads of non-removable head (1H1) drums and jerricans (3H1) may not exceed 7.0 cm (3 inches) in diameter. Drums and jerricans with larger openings are considered to be of the removable head type (1H2 and 3H2). Closures for openings in the bodies or heads of drums and jerricans must be so designed and applied that they remain secure and leakproof under normal conditions of transport. Gaskets or other sealing elements must be used with closures unless the closure is inherently leakproof.

(6) Closure devices for removable head drums and jerricans must be so designed and applied that they remain secure and leakproof under normal conditions of transport. Gaskets must be used with all removable heads unless the drum or jerrican design is such that when the removable head is properly secured, the drum or jerrican is inherently leakproof.

(7) Maximum capacity of drums and jerricans: 1H1, 1H2: 450 L (119 gallons); 3H1, 3H2: 60 L (16 gallons).

(8) Maximum net mass: 1H1, 1H2: 400 kg (882 pounds); 3H1, 3H2: 120 kg (265 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended by Amdt. 178-102, 59 FR 28494, June 2, 1994; 64 FR 10782, Mar. 5, 1999; 66 FR 45386, Aug. 28, 2001]

#### § 178.510 Standards for wooden barrels.

(a) The following are identification codes for wooden barrels:

(1) 2C1 for a bung type wooden barrel; and

(2) 2C2 for a slack type (removable head) wooden barrel.

(b) Construction requirements for wooden barrels are as follows:

(1) The wood used must be of good quality, straight-grained, well-seasoned and free from knots, bark, rotten wood, sapwood or other defects likely to lessen the effectiveness of the barrel for the purpose intended.

(2) The body and heads must be of a design appropriate to the capacity and intended use of the barrel.

(3) Staves and heads must be sawn or cleft with the grain so that no annual ring extends over more than half the thickness of a stave or head.

(4) Barrel hoops must be of steel or iron of good quality. The hoops of 2C2 barrels may be of a suitable hardwood.

(5) For wooden barrels 2C1, the diameter of the bung-hole may not exceed half the width of the stave in which it is placed.

(6) For wooden barrels 2C2, heads must fit tightly into crozes.

(7) Maximum capacity of barrel: 250 L (66 gallons).

(8) Maximum net mass: 400 kg (882 pounds).

#### § 178.511 Standards for aluminum and steel jerricans.

(a) The following are identification codes for aluminum and steel jerricans:

(1) 3A1 for a non-removable head steel jerrican;

(2) 3A2 for a removable head steel jerrican;

(3) 3B1 for a non-removable head aluminum jerrican; and

(4) 3B2 for a removable head aluminum jerrican.

(b) Construction requirements for aluminum and steel jerricans are as follows:

(1) For steel jerricans the body and heads must be constructed of steel sheet of suitable type and adequate thickness in relation to the capacity of the jerrican and its intended use. Minimum thickness and marking requirements in §§ 173.28(b)(4) and 178.503(a)(9) of this subchapter apply to jerricans intended for reuse.

(2) For aluminum jerricans the body and heads must be constructed of aluminum at least 99% pure or of an aluminum base alloy. Material must be of a type and of adequate thickness in relation to the capacity of the jerrican and to its intended use.

(3) Chimes of all jerricans must be mechanically seamed or welded. Body seams of jerricans intended to carry more than 40 L (11 gallons) of liquid must be welded. Body seams of jerricans intended to carry 40 L (11 gallons) or less must be mechanically seamed or welded.

(4) Openings in jerricans (3A1) may not exceed 7.0 cm (3 inches) in diameter. Jerricans with larger openings are considered to be of the removable head type. Closures must be so designed that they remain secure and leakproof under normal conditions of transport. Gaskets or other sealing elements must be used with closures, unless the closure is inherently leakproof.

(5) If materials used for body, heads, closures and fittings are not in themselves compatible with the contents to be transported, suitable internal protective coatings or treatments must be applied. These coatings or treatments must retain their protective properties under normal conditions of transport.

(6) Maximum capacity of jerrican: 60 L (16 gallons).

(7) Maximum net mass: 120 kg (265 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended by Amdt. 178-102, 59 FR 28494, June 2, 1994; Amdt. 178-119, 62 FR 24742, May 6, 1997]

## § 178.512

### § 178.512 Standards for steel or aluminum boxes.

(a) The following are identification codes for steel or aluminum boxes:

- (1) 4A for a steel box; and
- (2) 4B for an aluminum box.

(b) Construction requirements for steel or aluminum boxes are as follows:

(1) The strength of the metal and the construction of the box must be appropriate to the capacity and intended use of the box.

(2) Boxes must be lined with fiberboard or felt packing pieces or must have an inner liner or coating of suitable material in accordance with subpart C of part 173 of this subchapter. If a double seamed metal liner is used, steps must be taken to prevent the ingress of materials, particularly explosives, into the recesses of the seams.

(3) Closures may be of any suitable type, and must remain secure under normal conditions of transport.

(4) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended by Amdt. 178-106, 59 FR 67521, Dec. 29, 1994]

### § 178.513 Standards for boxes of natural wood.

(a) The following are the identification codes for boxes of natural wood:

- (1) 4C1 for an ordinary box; and
- (2) 4C2 for a box with sift-proof walls.

(b) Construction requirements for boxes of natural wood are as follows:

(1) The wood used must be well-seasoned, commercially dry and free from defects that would materially lessen the strength of any part of the box. The strength of the material used and the method of construction must be appropriate to the capacity and intended use of the box. The tops and bottoms may be made of water-resistant reconstituted wood such as hard board, particle board or other suitable type.

(2) Fastenings must be resistant to vibration experienced under normal conditions of transportation. End grain nailing must be avoided whenever practicable. Joints which are likely to be highly stressed must be made using clenched or annular ring nails or equivalent fastenings.

(3) Each part of the 4C2 box must be one piece or equivalent. Parts are con-

## 49 CFR Ch. I (10-1-08 Edition)

sidered equivalent to one piece when one of the following methods of glued assembly is used: Linderman joint, tongue and groove joint, ship lap or rabbet joint, or butt joint with at least two corrugated metal fasteners at each joint.

(4) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended by Amdt. 178-106, 59 FR 67521, Dec. 29, 1994]

### § 178.514 Standards for plywood boxes.

(a) The identification code for a plywood box is 4D.

(b) Construction requirements for plywood boxes are as follows:

(1) Plywood used must be at least 3 ply. It shall be made from well-seasoned rotary cut, sliced or sawn veneer, commercially dry and free from defects that would materially lessen the strength of the box. The strength of the material used and the method of construction must be appropriate to the capacity and intended use of the box. All adjacent plies must be glued with water-resistant adhesive. Other suitable materials may be used together with plywood in the construction of boxes. Boxes must be nailed or secured to corner posts or ends or assembled with other equally suitable devices.

(2) Maximum net mass: 400 kg (882 pounds).

### § 178.515 Standards for reconstituted wood boxes.

(a) The identification code for a reconstituted wood box is 4F.

(b) Construction requirements for reconstituted wood boxes are as follows:

(1) The walls of boxes must be made of water-resistant, reconstituted wood such as hardboard, particle board, or other suitable type. The strength of the material used and the method of construction must be appropriate to the capacity of the boxes and their intended use.

(2) Other parts of the box may be made of other suitable materials.

(3) Boxes must be securely assembled by means of suitable devices.

(4) Maximum net mass: 400 kg (882 pounds).

**§ 178.516 Standards for fiberboard boxes.**

(a) The identification code for a fiberboard box is 4G.

(b) Construction requirements for fiberboard boxes are as follows:

(1) Strong, solid or double-faced corrugated fiberboard (single or multi-wall) must be used, appropriate to the capacity and intended use of the box. The water resistance of the outer surface must be such that the increase in mass, as determined in a test carried out over a period of 30 minutes by the Cobb method of determining water absorption, is not greater than 155 g per square meter (0.0316 pounds per square foot)—see ISO 535 (IBR, see § 171.7 of this subchapter). Fiberboard must have proper bending qualities. Fiberboard must be cut, creased without cutting through any thickness of fiberboard, and slotted so as to permit assembly without cracking, surface breaks, or undue bending. The fluting of corrugated fiberboard must be firmly glued to the facings.

(2) The ends of boxes may have a wooden frame or be entirely of wood or other suitable material. Reinforcements of wooden battens or other suitable material may be used.

(3) Manufacturing joints. (i) Manufacturing joints in the bodies of boxes must be—

- (A) Taped;
- (B) Lapped and glued; or
- (C) Lapped and stitched with metal staples.

(ii) Lapped joints must have an appropriate overlap.

(4) Where closing is effected by gluing or taping, a water resistant adhesive must be used.

(5) Boxes must be designed so as to provide a snug fit to the contents.

(6) Maximum net mass: 400 kg (882 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, and amended by Amdt. 178-99, 58 FR 51534, Oct. 1, 1993; Amdt. 178-106, 59 FR 67521, Dec. 29, 1994; 68 FR 75758, Dec. 31, 2003]

**§ 178.517 Standards for plastic boxes.**

(a) The following are identification codes for plastic boxes:

- (1) 4H1 for an expanded plastic box; and
- (2) 4H2 for a solid plastic box.

(b) Construction requirements for plastic boxes are as follows:

(1) The box must be manufactured from suitable plastic material and be of adequate strength in relation to its capacity and intended use. The box must be adequately resistant to aging and to degradation caused either by the substance contained or by ultra-violet radiation.

(2) An expanded plastic box must consist of two parts made of a molded expanded plastic material: a bottom section containing cavities for the inner receptacles, and a top section covering and interlocking with the bottom section. The top and bottom sections must be so designed that the inner receptacles fit snugly. The closure cap for any inner receptacle may not be in contact with the inside of the top section of the box.

(3) For transportation, an expanded plastic box must be closed with a self-adhesive tape having sufficient tensile strength to prevent the box from opening. The adhesive tape must be weather-resistant and its adhesive compatible with the expanded plastic material of the box. Other closing devices at least equally effective may be used.

(4) For solid plastic boxes, protection against ultra-violet radiation, if required, must be provided by the addition of carbon black or other suitable pigments or inhibitors. These additives must be compatible with the contents and remain effective throughout the life of the box. Where use is made of carbon black pigment or inhibitors other than those used in the manufacture of the tested design type, retesting may be waived if the carbon black content does not exceed 2 percent by mass or if the pigment content does not exceed 3 percent by mass; the content of inhibitors of ultra-violet radiation is not limited.

(5) Additives serving purposes other than protection against ultra-violet radiation may be included in the composition of the plastic material if they do not adversely affect the material of the box. Addition of these additives does not change the design type.

## **§ 178.518**

(6) Solid plastic boxes must have closure devices made of a suitable material of adequate strength and so designed as to prevent the box from unintentionally opening.

(7) Maximum net mass 4H1: 60 kg (132 pounds); 4H2: 400 kg (882 pounds).

### **§ 178.518 Standards for woven plastic bags.**

(a) The following are identification codes for woven plastic bags:

(1) 5H1 for an unlined or non-coated woven plastic bag;

(2) 5H2 for a sift-proof woven plastic bag; and

(3) 5H3 for a water-resistant woven plastic bag.

(b) Construction requirements for woven plastic fabric bags are as follows:

(1) Bags must be made from stretched tapes or monofilaments of a suitable plastic material. The strength of the material used and the construction of the bag must be appropriate to the capacity and intended use of the bag.

(2) If the fabric is woven flat, the bags must be made by sewing or some other method ensuring closure of the bottom and one side. If the fabric is tubular, the bag must be closed by sewing, weaving, or some other equally strong method of closure.

(3) Bags, sift-proof, 5H2 must be made sift-proof by appropriate means such as use of paper or a plastic film bonded to the inner surface of the bag or one or more separate inner liners made of paper or plastic material.

(4) Bags, water-resistant, 5H3: To prevent the entry of moisture, the bag must be made waterproof by appropriate means, such as separate inner liners of water-resistant paper (e.g., waxed kraft paper, double-tarred kraft paper or plastic-coated kraft paper), or plastic film bonded to the inner or outer surface of the bag, or one or more inner plastic liners.

(5) Maximum net mass: 50 kg (110 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, and amended by Amdt. 178-99, 58 FR 51534, Oct. 1, 1993]

## **49 CFR Ch. I (10-1-08 Edition)**

### **§ 178.519 Standards for plastic film bags.**

(a) The identification code for a plastic film bag is 5H4.

(b) Construction requirements for plastic film bags are as follows:

(1) Bags must be made of a suitable plastic material. The strength of the material used and the construction of the bag must be appropriate to the capacity and the intended use of the bag. Joints and closures must be capable of withstanding pressures and impacts liable to occur under normal conditions of transportation.

(2) Maximum net mass: 50 kg (110 pounds).

### **§ 178.520 Standards for textile bags.**

(a) The following are identification codes for textile bags:

(1) 5L1 for an unlined or non-coated textile bag;

(2) 5L2 for a sift-proof textile bag; and

(3) 5L3 for a water-resistant textile bag.

(b) Construction requirements for textile bags are as follows:

(1) The textiles used must be of good quality. The strength of the fabric and the construction of the bag must be appropriate to the capacity and intended use of the bag.

(2) Bags, sift-proof, 5L2: The bag must be made sift-proof, by appropriate means, such as by the use of paper bonded to the inner surface of the bag by a water-resistant adhesive such as bitumen, plastic film bonded to the inner surface of the bag, or one or more inner liners made of paper or plastic material.

(3) Bags, water-resistant, 5L3: To prevent entry of moisture, the bag must be made waterproof by appropriate means, such as by the use of separate inner liners of water-resistant paper (e.g., waxed kraft paper, tarred paper, or plastic-coated kraft paper), or plastic film bonded to the inner surface of the bag, or one or more inner liners made of plastic material or metalized film or foil.

(4) Maximum net mass: 50 kg (110 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended at 56 FR 66285, Dec. 20, 1991]

**§ 178.521 Standards for paper bags.**

(a) The following are identification codes for paper bags:

(1) 5M1 for a multi-wall paper bag; and

(2) 5M2 for a multi-wall water-resistant paper bag.

(b) Construction requirements for paper bags are as follows:

(1) Bags must be made of a suitable kraft paper, or of an equivalent paper with at least three plies. The strength of the paper and the construction of the bag must be appropriate to the capacity and intended use of the bag. Seams and closures must be sift-proof.

(2) Paper bags 5M2: To prevent the entry of moisture, a bag of four plies or more must be made waterproof by the use of either a water-resistant ply as one of the two outermost plies or a water-resistant barrier made of a suitable protective material between the two outermost plies. A 5M2 bag of three plies must be made waterproof by the use of a water-resistant ply as the outermost ply. When there is danger of the lading reacting with moisture, or when it is packed damp, a waterproof ply or barrier, such as double-tarred kraft paper, plastics-coated kraft paper, plastics film bonded to the inner surface of the bag, or one or more inner plastics liners, must also be placed next to the substance. Seams and closures must be waterproof.

(3) Maximum net mass: 50 kg (110 pounds).

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, as amended at 56 FR 66285, Dec. 20, 1991; Amdt. 178-106, 59 FR 67521, Dec. 29, 1994]

**§ 178.522 Standards for composite packagings with inner plastic receptacles.**

(a) The following are the identification codes for composite packagings with inner plastic receptacles:

(1) 6HA1 for a plastic receptacle within a protective steel drum;

(2) 6HA2 for a plastic receptacle within a protective steel crate or box;

(3) 6HB1 for a plastic receptacle within a protective aluminum drum.

(4) 6HB2 for a plastic receptacle within a protective aluminum crate or box.

(5) 6HC for a plastic receptacle within a protective wooden box.

(6) 6HD1 for a plastic receptacle within a protective plywood drum;

(7) 6HD2 for a plastic receptacle within a protective plywood box;

(8) 6HG1 for a plastic receptacle within a protective fiber drum;

(9) 6HG2 for a plastic receptacle within a protective fiberboard box;

(10) 6HH1 for a plastic receptacle within a protective plastic drum; and

(11) 6HH2 for a plastic receptacle within a protective plastic box.

(b) Construction requirements for composite packagings with inner receptacles of plastic are as follows:

(1) Inner receptacles must be constructed under the applicable construction requirements prescribed in § 178.509(b) (1) through (7) of this subpart.

(2) The inner plastic receptacle must fit snugly inside the outer packaging, which must be free of any projections which may abrade the plastic material.

(3) Outer packagings must be constructed as follows:

(i) 6HA1 or 6HB1: Protective packaging must conform to the requirements for steel drums in § 178.504(b) of this subpart, or aluminum drums in § 178.505(b) of this subpart.

(ii) 6HA2 or 6HB2: Protective packagings with steel or aluminum crate must conform to the requirements for steel or aluminum boxes found in § 178.512(b) of this subpart.

(iii) 6HC protective packaging must conform to the requirements for wooden boxes in § 178.513(b) of this subpart.

(iv) 6HD1: Protective packaging must conform to the requirements for plywood drums, in § 178.507(b) of this subpart.

(v) 6HD2: Protective packaging must conform to the requirements of plywood boxes, in § 178.514(b) of this subpart.

(vi) 6HG1: Protective packaging must conform to the requirements for fiber drums, in § 178.508(b) of this subpart.

(vii) 6HG2: protective packaging must conform to the requirements for fiberboard boxes, in § 178.516(b) of this subpart.

(viii) 6HH1: Protective packaging must conform to the requirements for plastic drums, in § 178.509(b).



(ix) 6HH2: Protective packaging must conform to the requirements for plastic boxes, in § 178.517(b).

(4) Maximum capacity of inner receptacles is as follows: 6HA1, 6HB1, 6HD1, 6HG1, 6HH1—250 L (66 gallons); 6HA2, 6HB2, 6HC, 6HD2, 6HG2, 6HH2—60 L (16 gallons).

(5) Maximum net mass is as follows: 6HA1, 6HB1, 6HD1, 6HG1, 6HH1—400 kg (882 pounds); 6HB2, 6HC, 6HD2, 6HG2, 6HH2—75 kg (165 pounds).

[Amdt. 178–97, 55 FR 52717, Dec. 21, 1990, as amended by Amdt. 178–106, 59 FR 67521, Dec. 29, 1994]

**§ 178.523 Standards for composite packagings with inner glass, porcelain, or stoneware receptacles.**

(a) The following are identification codes for composite packagings with inner receptacles of glass, porcelain, or stoneware:

(1) 6PA1 for glass, porcelain, or stoneware receptacles within a protective steel drum;

(2) 6PA2 for glass, porcelain, or stoneware receptacles within a protective steel crate or box;

(3) 6PB1 for glass, porcelain, or stoneware receptacles within a protective aluminum drum;

(4) 6PB2 for glass, porcelain, or stoneware receptacles within a protective aluminum crate or box;

(5) 6PC for glass, porcelain, or stoneware receptacles within a protective wooden box;

(6) 6PD1 for glass, porcelain, or stoneware receptacles within a protective plywood drum;

(7) 6PD2 for glass, porcelain, or stoneware receptacles within a protective wickerwork hamper;

(8) 6PG1 for glass, porcelain, or stoneware receptacles within a protective fiber drum;

(9) 6PG2 for glass, porcelain, or stoneware receptacles within a protective fiberboard box;

(10) 6PH1 for glass, porcelain, or stoneware receptacles within a protective expanded plastic packaging; and

(11) 6PH2 for glass, porcelain, or stoneware receptacles within a protective solid plastic packaging.

(b) Construction requirements for composite packagings with inner re-

ceptacles of glass, porcelain, or stoneware are as follows:

(1) Inner receptacles must conform to the following requirements:

(i) Receptacles must be of suitable form (cylindrical or pear-shaped), be made of good quality materials free from any defect that could impair their strength, and be firmly secured in the outer packaging.

(ii) Any part of a closure likely to come into contact with the contents of the receptacle must be resistant to those contents. Closures must be fitted so as to be leakproof and secured to prevent any loosening during transportation. Vented closures must conform to § 173.24(f) of this subchapter.

(2) Protective packagings must conform to the following requirements:

(i) For receptacles with protective steel drum 6PA1, the drum must comply with § 178.504(b) of this subpart. However, the removable lid required for this type of packaging may be in the form of a cap.

(ii) For receptacles with protective packaging of steel crate or steel box 6PA2, the protective packaging must conform to the following:

(A) Section 178.512(b) of this subpart.

(B) In the case of cylindrical receptacles, the protective packaging must, when upright, rise above the receptacle and its closure; and

(C) If the protective crate surrounds a pear-shaped receptacle and is of matching shape, the protective packaging must be fitted with a protective cover (cap).

(iii) For receptacles with protective aluminum drum 6PB1, the requirements of § 178.505(b) of this subpart apply to the protective packaging.

(iv) For receptacles with protective aluminum box or crate 6PB2, the requirements of § 178.512(b) of this subpart apply to the protective packaging.

(v) For receptacles with protective wooden box 6PC, the requirements of § 178.513(b) of this subpart apply to the protective packaging.

(vi) For receptacles with protective plywood drum 6PD1, the requirements of § 178.507(b) of this subpart apply to the protective packaging.

(vii) For receptacles with protective wickerwork hamper 6PD2, the wickerwork hamper must be properly

made with material of good quality. The hamper must be fitted with a protective cover (cap) so as to prevent damage to the receptacle.

(viii) For receptacles with protective fiber drum 6PG1, the drum must conform to the requirements of §178.508(b) of this subpart.

(ix) For receptacles with protective fiberboard box 6PG2, the requirements of §178.516(b) of this subpart apply to the protective packaging.

(x) For receptacles with protective solid plastic or expanded plastic packaging 6PH1 or 6PH2, the requirements of §178.517(b) of this subpart apply to the protective packaging. Solid protective plastic packaging must be manufactured from high-density polyethylene from some other comparable plastic material. The removable lid required for this type of packaging may be a cap.

(3) Quantity limitations are as follows:

(i) Maximum net capacity for packaging for liquids: 60 L (16 gallons).

(ii) Maximum net mass for packagings for solids: 75 kg (165 pounds).

### Subpart M—Testing of Non-bulk Packagings and Packages

SOURCE: Amdt. 178-97, 55 FR 52723, Dec. 21, 1990, unless otherwise noted.

#### § 178.600 Purpose and scope.

This subpart prescribes certain testing requirements for performance-oriented packagings identified in subpart L of this part.

[Amdt. 178-97, 55 FR 52717, Dec. 21, 1990, and amended by Amdt. 178-99, 58 FR 51534, Oct. 1, 1993]

#### § 178.601 General requirements.

(a) *General.* The test procedures prescribed in this subpart are intended to ensure that packages containing hazardous materials can withstand normal conditions of transportation and are considered minimum requirements. Each packaging must be manufactured and assembled so as to be capable of successfully passing the prescribed tests and of conforming to the requirements of §173.24 of this subchapter at all times while in transportation.

(b) *Responsibility.* It is the responsibility of the packaging manufacturer to assure that each package is capable of passing the prescribed tests. To the extent that a package assembly function, including final closure, is performed by the person who offers a hazardous material for transportation, that person is responsible for performing the function in accordance with §§173.22 and 178.2 of this subchapter.

(c) *Definitions.* For the purpose of this subpart:

(1) *Design qualification testing* is the performance of the tests prescribed in §178.603, §178.604, §178.605, §178.606, §178.607, §178.608, or §178.609, as applicable, for each new or different packaging, at the start of production of that packaging.

(2) *Periodic retesting* is the performance of the drop, leakproofness, hydrostatic pressure, and stacking tests, as applicable, as prescribed in §178.603, §178.604, §178.605, or §178.606, respectively, at the frequency specified in paragraph (e) of this section. For infectious substances packagings required to meet the requirements of §178.609, periodic retesting is the performance of the tests specified in §178.609 at the frequency specified in paragraph (e) of this section.

(3) *Production testing* is the performance of the leakproofness test prescribed in §178.604 of this subpart on each single or composite packaging intended to contain a liquid.

(4) *A different packaging* is one that differs (i.e. is not identical) from a previously produced packaging in structural design, size, material of construction, wall thickness or manner of construction but does not include:

(i) A packaging which differs only in surface treatment;

(ii) A combination packaging which differs only in that the outer packaging has been successfully tested with different inner packagings. A variety of such inner packagings may be assembled in this outer packaging without further testing;

(iii) A plastic packaging which differs only with regard to additives which conform to §178.509(b)(3) or §178.517(b)(4) or (5) of this part;

(iv) A combination packaging with inner packagings conforming to the provisions of paragraph (g) of this section;

(v) Packagings which differ from the design type only in their lesser design height; or

(vi) For a steel drum, variations in design elements which do not constitute a different design type under the provisions of paragraph (g)(8) of this section.

(d) *Design qualification testing.* The packaging manufacturer shall achieve successful test results for the design qualification testing at the start of production of each new or different packaging.

(e) *Periodic retesting.* The packaging manufacturer must achieve successful test results for the periodic retesting at intervals established by the manufacturer of sufficient frequency to ensure that each packaging produced by the manufacturer is capable of passing the design qualification tests. Changes in retest frequency are subject to the approval of the Associate Administrator for Hazardous Materials Safety. For single or composite packagings, the periodic retests must be conducted at least once every 12 months. For combination packagings, the periodic retests must be conducted at least once every 24 months. For infectious substances packagings, the periodic retests must be conducted at least once every 24 months.

(f) *Test samples.* The manufacturer shall conduct the design qualification and periodic tests prescribed in this subpart using random samples of packagings, in the numbers specified in the appropriate test section. In addition, the leakproofness test, when required, shall be performed on each packaging produced by the manufacturer, and each packaging prior to reuse under §173.28 of this subchapter, by the reconditioner.

(g) *Selective testing.* The selective testing of packagings that differ only in minor respects from a tested type is permitted as described in this section. For air transport, packagings must comply with §173.27(c)(1) and (c)(2) of this subchapter.

(1) *Selective testing of combination packagings. Variation 1.* Variations are

permitted in inner packagings of a tested combination package, without further testing of the package, provided an equivalent level of performance is maintained, as follows:

(i) Inner packagings of equivalent or smaller size may be used provided—

(A) The inner packagings are of similar design to the tested inner packagings (i.e. shape—round, rectangular, etc.);

(B) The material of construction of the inner packagings (glass, plastic, metal, etc.) offers resistance to impact and stacking forces equal to or greater than that of the originally tested inner packaging;

(C) The inner packagings have the same or smaller openings and the closure is of similar design (e.g., screw cap, friction lid, etc.);

(D) Sufficient additional cushioning material is used to take up void spaces and to prevent significant moving of the inner packagings;

(E) Inner packagings are oriented within the outer packaging in the same manner as in the tested package; and,

(F) The gross mass of the package does not exceed that originally tested.

(ii) A lesser number of the tested inner packagings, or of the alternative types of inner packagings identified in paragraph (g)(1)(i) of this section, may be used provided sufficient cushioning is added to fill void space(s) and to prevent significant moving of the inner packagings.

(2) *Selective testing of combination packagings. Variation 2.* Articles or inner packagings of any type, for solids or liquids, may be assembled and transported without testing in an outer packaging under the following conditions:

(i) The outer packaging must have been successfully tested in accordance with §178.603 with fragile (e.g. glass) inner packagings containing liquids at the Packing Group I drop height;

(ii) The total combined gross mass of inner packagings may not exceed one-half the gross mass of inner packagings used for the drop test;

(iii) The thickness of cushioning material between inner packagings and

between inner packagings and the outside of the packaging may not be reduced below the corresponding thickness in the originally tested packaging; and when a single inner packaging was used in the original test, the thickness of cushioning between inner packagings may not be less than the thickness of cushioning between the outside of the packaging and the inner packaging in the original test. When either fewer or smaller inner packagings are used (as compared to the inner packagings used in the drop test), sufficient additional cushioning material must be used to take up void spaces.

(iv) The outer packaging must have successfully passed the stacking test set forth in § 178.606 of this subpart when empty, i.e., without either inner packagings or cushioning materials. The total mass of identical packages must be based on the combined mass of inner packagings used for the drop test;

(v) Inner packagings containing liquids must be completely surrounded with a sufficient quantity of absorbent material to absorb the entire liquid contents of the inner packagings;

(vi) When the outer packaging is intended to contain inner packagings for liquids and is not leakproof, or is intended to contain inner packagings for solids and is not siftproof, a means of containing any liquid or solid contents in the event of leakage must be provided in the form of a leakproof liner, plastic bag, or other equally efficient means of containment. For packagings containing liquids, the absorbent material required in paragraph (g)(2)(v) of this section must be placed inside the means of containing liquid contents; and

(vii) Packagings must be marked in accordance with § 178.503 of this part as having been tested to Packing Group I performance for combination packagings. The marked maximum gross mass may not exceed the sum of the mass of the outer packaging plus one half the mass of the filled inner packagings of the tested combination packaging. In addition, the marking required by § 178.503(a)(2) of this part must include the letter "V".

(3) *Variation 3.* Packagings other than combination packagings which are pro-

duced with reductions in external dimensions (i.e., length, width or diameter) of up to 25 percent of the dimensions of a tested packaging may be used without further testing provided an equivalent level of performance is maintained. The packagings must, in all other respects (including wall thicknesses), be identical to the tested design-type. The marked gross mass (when required) must be reduced in proportion to the reduction in volume.

(4) *Variation 4.* Variations are permitted in outer packagings of a tested design-type combination packaging, without further testing, provided an equivalent level of performance is maintained, as follows:

(i) Each external dimension (length, width and height) is less than or equal to the corresponding dimension of the tested design-type;

(ii) The structural design of the tested outer packaging (i.e. methods of construction, materials of construction, strength characteristics of materials of construction, method of closure and material thicknesses) is maintained;

(iii) The inner packagings are identical to the inner packagings used in the tested design type except that their size and mass may be less; and they are oriented within the outer packaging in the same manner as in the tested packaging;

(iv) The same type or design of absorbent materials, cushioning materials and any other components necessary to contain and protect inner packagings, as used in the tested design type, are maintained. The thickness of cushioning material between inner packagings and between inner packagings and the outside of the packaging may not be less than the thicknesses in the tested design type packaging; and

(v) Sufficient additional cushioning material is used to take up void spaces and to prevent significant moving of the inner packagings.

An outer packaging qualifying for use in transport in accordance with all of the above conditions may also be used without testing to transport inner packagings substituted for the originally tested inner packagings in accordance with the conditions set out in

## § 178.601

## 49 CFR Ch. I (10–1–08 Edition)

Variation 1 in paragraph (g)(1) of this section.

(5) *Variation 5.* Single packagings (i.e., non-bulk packagings other than combination packagings), that differ from a tested design type only to the extent that the closure device or gasketing differs from that used in the originally tested design type, may be used without further testing, provided an equivalent level of performance is maintained, subject to the following conditions (the qualifying tests):

(i) A packaging with the replacement closure devices or gasketing must successfully pass the drop test specified in § 178.603 in the orientation which most severely tests the integrity of the closure or gasket;

(ii) When intended to contain liquids, a packaging with the replacement closure devices or gasketing must successfully pass the leakproofness test specified in § 178.604, the hydrostatic pressure test specified in § 178.605, and the stacking test specified in § 178.606.

Replacement closures and gasketings qualified under the above test requirements are authorized without additional testing for packagings described in paragraph (g)(3) of this section. Replacement closures and gasketings qualified under the above test requirements also are authorized without additional testing for different tested design types packagings of the same type as the originally tested packaging, provided the original design type tests are more severe or comparable to tests which would otherwise be conducted on the packaging with the replacement closures or gasketings. (For example: The packaging used in the qualifying tests has a lesser packaging wall thickness than the packaging with replacement closure devices or gasketing; the gross mass of the packaging used in the qualifying drop test equals or exceeds the mass for which the packaging with replacement closure devices or gasketing was tested; the packaging used in the qualifying drop test was dropped from the same or greater height than the height from which the packaging with replacement closure devices or gasketing was dropped in design type tests; and the specific gravity of the substance used in the qualifying drop test was the same or greater than

the specific gravity of the liquid used in the design type tests of the packaging with replacement closure devices or gasketing.)

(6) The provisions in Variations 1, 2, and 4 in paragraphs (g)(1), (2) and (4) of this section for combination packagings may be applied to packagings containing articles, where the provisions for inner packagings are applied analogously to the articles. In this case, inner packagings need not comply with § 173.27(c)(1) and (c)(2) of this subchapter.

(7) *Approval of selective testing.* In addition to the provisions of § 178.601(g)(1) through (g)(6) of this subpart, the Associate Administrator may approve the selective testing of packagings that differ only in minor respects from a tested type.

(8) For a steel drum with a capacity greater than 50 L (13 gallons) manufactured from low carbon, cold-rolled sheet steel meeting ASTM designations A 366/A 366M or A 568/A 568M variations in elements other than the following design elements are considered minor and do not constitute a different drum design type, or “different packaging” as defined in paragraph (c) of this section for which design qualification testing and periodic retesting are required. Minor variations authorized without further testing include changes in the identity of the supplier of component material made to the same specifications, or the original manufacturer of a DOT specification or UN standard drum to be remanufactured. A change in any one or more of the following design elements constitutes a different drum design type:

(i) The packaging type and category of the original drum and the remanufactured drum, i.e., 1A1 or 1A2;

(ii) The style, (i.e., straight-sided or tapered);

(iii) Except as provided in paragraph (g)(3) of this section, the rated (marked) capacity and outside dimensions;

(iv) The physical state for which the packaging was originally approved (e.g., tested for solids or liquids);

(v) An increase in the marked level of performance of the original drum (i.e., to a higher packing group, hydrostatic

test pressure, or specific gravity to which the packaging has been tested);

(vi) Type of side seam welding;

(vii) Type of steel;

(viii) An increase greater than 10% or any decrease in the steel thickness of the head, body, or bottom;

(ix) End seam type, (e.g., triple or double seam);

(x) A reduction in the number of rolling hoops which equal or exceed the diameter over the chimes;

(xi) The location, type or size, and material of closures (other than the cover of UN 1A2 drums); and

(xii) For UN 1A2 drums:

(A) Gasket material (e.g., plastic), or properties affecting the performance of the gasket;

(B) Configuration or dimensions of the gasket;

(C) Closure ring style including bolt size, (e.g., square or round back, 0.625" bolt); and

(D) Closure ring thickness.

(h) *Approval of equivalent packagings.*

A packaging having specifications different from those in §§ 178.504–178.523 of this part, or which is tested using methods or test intervals, other than those specified in subpart M of this part, may be used if approved by the Associate Administrator. Such packagings must be shown to be equally effective, and testing methods used must be equivalent.

(i) *Proof of compliance.* Notwithstanding the periodic retest intervals specified in paragraph (e) of this section, the Associate Administrator may at any time require demonstration of compliance by a manufacturer, through testing in accordance with this subpart, that packagings meet the requirements of this subpart. As required by the Associate Administrator, the manufacturer shall either—

(1) Conduct performance tests, or have tests conducted by an independent testing facility, in accordance with this subpart; or

(2) Supply packagings, in quantities sufficient to conduct tests in accordance with this subpart, to the Associate Administrator or a designated representative of the Associate Administrator.

(j) *Coatings.* If an inner treatment or coating of a packaging is required for

safety reasons, the manufacturer shall design the packaging so that the treatment or coating retains its protective properties even after withstanding the tests prescribed by this subpart.

(k) *Number of test samples.* Provided the validity of the test results is not affected and with the approval of the Associate Administrator, several tests may be performed on one sample.

(l) *Record retention.* Following each design qualification test and each periodic retest on a packaging, a test report must be prepared. The test report must be maintained at each location where the packaging is manufactured and each location where the design qualification tests are conducted, for as long as the packaging is produced and for at least two years thereafter, and at each location where the periodic retests are conducted until such tests are successfully performed again and a new test report produced. In addition, a copy of the test report must be maintained by a person certifying compliance with this part. The test report must be made available to a user of a packaging or a representative of the Department upon request. The test report, at a minimum, must contain the following information:

(1) Name and address of test facility;

(2) Name and address of applicant (where appropriate);

(3) A unique test report identification;

(4) Date of the test report;

(5) Manufacturer of the packaging;

(6) Description of the packaging design type (e.g. dimensions, materials, closures, thickness, etc.), including methods of manufacture (e.g. blow molding) and which may include drawing(s) and/or photograph(s);

(7) Maximum capacity;

(8) Characteristics of test contents, e.g. viscosity and relative density for liquids and particle size for solids;

(9) Test descriptions and results; and

(10) Signed with the name and title of signatory.

[Amdt. 178-97, 55 FR 52723, Dec. 21, 1990, as amended at 56 FR 66285, Dec. 20, 1991; 57 FR 45465, Oct. 1, 1992; Amdt. 178-102, 59 FR 28494, June 2, 1994; Amdt. 178-106, 59 FR 67521, 67522, Dec. 29, 1994; Amdt. 178-117, 61 FR 50628, Sept. 26, 1996; 66 FR 45386, Aug. 28, 2001; 67 FR 53143, Aug. 14, 2002; 68 FR 75758, Dec. 31, 2003; 68 FR 61942, Oct. 30, 2003]

**§ 178.602**

**49 CFR Ch. I (10–1–08 Edition)**

**§ 178.602 Preparation of packagings and packages for testing.**

(a) Except as otherwise provided in this subchapter, each packaging and package must be closed in preparation for testing and tests must be carried out in the same manner as if prepared for transportation, including inner packagings in the case of combination packagings.

(b) For the drop and stacking test, inner and single-unit receptacles other than bags must be filled to not less than 95% of maximum capacity (see § 171.8 of this subchapter) in the case of solids and not less than 98% of maximum in the case of liquids. Bags containing solids shall be filled to the maximum mass at which they may be used. The material to be transported in the packagings may be replaced by a non-hazardous material, except for chemical compatibility testing or where this would invalidate the results of the tests.

(c) If the material to be transported is replaced for test purposes by a non-hazardous material, the material used must be of the same or higher specific gravity as the material to be carried, and its other physical properties (grain, size, viscosity) which might influence the results of the required tests must correspond as closely as possible to those of the hazardous material to be transported. Water may also be used for the liquid drop test under the conditions specified in § 178.603(e) of this subpart. It is permissible to use additives, such as bags of lead shot, to achieve the requisite total package mass, so long as they are placed so that the test results are not affected.

(d) Paper or fiberboard packagings must be conditioned for at least 24 hours immediately prior to testing in an atmosphere maintained—

(1) At 50 percent  $\pm 2$  percent relative humidity, and at a temperature of 23

$^{\circ}\text{C} \pm 2$   $^{\circ}\text{C}$  (73  $^{\circ}\text{F} \pm 4$   $^{\circ}\text{F}$ ). Average values should fall within these limits. Short-term fluctuations and measurement limitations may cause individual measurements to vary by up to  $\pm 5$  percent relative humidity without significant impairment of test reproducibility;

(2) At 65 percent  $\pm 2$  percent relative humidity, and at a temperature of 20  $^{\circ}\text{C} \pm 2$   $^{\circ}\text{C}$  (68  $^{\circ}\text{F} \pm 4$   $^{\circ}\text{F}$ ), or 27  $^{\circ}\text{C} \pm 2$   $^{\circ}\text{C}$  (81  $^{\circ}\text{F} \pm 4$   $^{\circ}\text{F}$ ). Average values should fall within these limits. Short-term fluctuations and measurement limitations may cause individual measurements to vary by up to  $\pm 5$  percent relative humidity without significant impairment of test reproducibility; or

(3) For testing at periodic intervals only (i.e., other than initial design qualification testing), at ambient conditions.

(e) Except as otherwise provided, each packaging must be closed in preparation for testing in the same manner as if prepared for actual shipment. All closures must be installed using proper techniques and torques.

(f) Bung-type barrels made of natural wood must be left filled with water for at least 24 hours before the tests.

[Amdt. 178–97, 55 FR 52723, Dec. 21, 1990, as amended at 56 FR 66286, Dec. 20, 1991; Amdt. 178–106, 59 FR 67522, Dec. 29, 1994; 69 FR 76186, Dec. 20, 2004; 71 FR 78635, Dec. 29, 2006]

**§ 178.603 Drop test.**

(a) *General.* The drop test must be conducted for the qualification of all packaging design types and performed periodically as specified in § 178.601(e). For other than flat drops, the center of gravity of the test packaging must be vertically over the point of impact. Where more than one orientation is possible for a given drop test, the orientation most likely to result in failure of the packaging must be used. The number of drops required and the packages' orientations are as follows:

| Packaging                                                                                                                                                                                                                 | No. of tests (samples)     | Drop orientation of samples                                                                                                                                                                                                                                                                                                                                                                                    |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Steel drums, Aluminum drums, Metal drums (other than steel or aluminum), Steel Jerricans, Plywood drums, Wooden barrels, Fiber drums, Plastic drums and Jerricans, Composite packagings which are in the shape of a drum. | Six—(three for each drop). | First drop (using three samples): The package must strike the target diagonally on the chime or, if the packaging has no chime, on a circumferential seam or an edge. Second drop (using the other three samples): The package must strike the target on the weakest part not tested by the first drop, for example a closure or, for some 7 cylindrical drums, the welded longitudinal seam of the drum body. |

| Packaging                                                                                                                                                                       | No. of tests (samples)       | Drop orientation of samples                                                                                                                                                                                                                                                                   |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Boxes of natural wood, Plywood boxes, Reconstituted wood boxes, Fiberboard boxes, Plastic boxes, Steel or aluminum boxes, Composite packagings which are in the shape of a box. | Five—(one for each drop).    | First drop: Flat on the bottom (using the first sample). Second drop: Flat on the top (using the second sample). Third drop: Flat on the long side (using the third sample). Fourth drop: Flat on the short side (using the fourth sample). Fifth drop: On a corner (using the fifth sample). |
| Bags—single-ply with a side seam .....                                                                                                                                          | Three—(three drops per bag). | First drop: Flat on a wide face (using all three samples). Second drop: Flat on a narrow face (using all three samples). Third drop: On an end of the bag (using all three samples).                                                                                                          |
| Bags—single-ply without a side seam, or multi-ply.                                                                                                                              | Three—(two drops per bag).   | First drop: Flat on a wide face (using all three samples). Second drop: On an end of the bag (using all three samples).                                                                                                                                                                       |

(b) *Exceptions.* For testing of single or composite packagings constructed of stainless steel, nickel, or monel at periodic intervals only (i.e., other than design qualification testing), the drop test may be conducted with two samples, one sample each for the two drop orientations. These samples may have been previously used for the hydrostatic pressure or stacking test. Exceptions for the number of steel and aluminum packaging samples used for conducting the drop test are subject to the approval of the Associate Administrator.

(c) *Special preparation of test samples for the drop test.* (1) Testing of plastic drums, plastic jerricans, plastic boxes other than expanded polystyrene boxes, composite packagings (plastic material), and combination packagings with plastic inner packagings other than plastic bags intended to contain solids or articles must be carried out when the temperature of the test sample and its contents has been reduced to  $-18^{\circ}\text{C}$  ( $0^{\circ}\text{F}$ ) or lower. Test liquids must be kept in the liquid state, if necessary, by the addition of anti-freeze. Water/anti-freeze solutions with a minimum specific gravity of 0.95 for testing at  $-18^{\circ}\text{C}$  ( $0^{\circ}\text{F}$ ) or lower are considered acceptable test liquids. Test samples prepared in this way are not required to be conditioned in accordance with § 178.602(d).

(d) *Target.* The target must be a rigid, non-resilient, flat and horizontal surface.

(e) *Drop height.* Drop heights, measured as the vertical distance from the target to the lowest point on the package, must be equal to or greater than the drop height determined as follows:

(1) For solids and liquids, if the test is performed with the solid or liquid to

be transported or with a non-hazardous material having essentially the same physical characteristic, the drop height must be determined according to packing group, as follows:

- (i) Packing Group I: 1.8 m (5.9 feet).
- (ii) Packing Group II: 1.2 m (3.9 feet).
- (iii) Packing Group III: 0.8 m (2.6 feet).

(2) For liquids in single packagings and for inner packagings of combination packagings, if the test is performed with water:

(i) Where the materials to be carried have a specific gravity not exceeding 1.2, drop height must be determined according to packing group, as follows:

- (A) Packing Group I: 1.8 m (5.9 feet).
- (B) Packing Group II: 1.2 m (3.9 feet).
- (C) Packing Group III: 0.8 m (2.6 feet).

(ii) Where the materials to be transported have a specific gravity exceeding 1.2, the drop height must be calculated on the basis of the specific gravity (SG) of the material to be carried, rounded up to the first decimal, as follows:

- (A) Packing Group I:  $\text{SG} \times 1.5 \text{ m}$  (4.9 feet).
- (B) Packing Group II:  $\text{SG} \times 1.0 \text{ m}$  (3.3 feet).
- (C) Packing Group III:  $\text{SG} \times 0.67 \text{ m}$  (2.2 feet).

(f) *Criteria for passing the test.* A package is considered to successfully pass the drop tests if for each sample tested—

(1) For packagings containing liquid, each packaging does not leak when equilibrium has been reached between the internal and external pressures, except for inner packagings of combination packagings when it is not necessary that the pressures be equalized;

(2) For removable head drums for solids, the entire contents are retained by an inner packaging (e.g., a plastic bag)



## § 178.604

## 49 CFR Ch. I (10–1–08 Edition)

even if the closure on the top head of the drum is no longer sift-proof;

(3) For a bag, neither the outermost ply nor an outer packaging exhibits any damage likely to adversely affect safety during transport;

(4) For a composite or combination packaging, there is no damage to the outer packaging likely to adversely affect safety during transport, and there is no leakage of the filling substance from the inner packaging;

(5) Any discharge from a closure is slight and ceases immediately after impact with no further leakage; and

(6) No rupture is permitted in packagings for materials in Class 1 which would permit spillage of loose explosive substances or articles from the outer packaging.

[Amdt. 178–97, 55 FR 52723, Dec. 21, 1990, as amended at 56 FR 66286, Dec. 20, 1991; 57 FR 45465, Oct. 1, 1992; Amdt. 178–99, 58 FR 51534, Oct. 1, 1993; Amdt. 178–106, 59 FR 67522, Dec. 29, 1994; 65 FR 50462, Aug. 18, 2000; 66 FR 45386, Aug. 28, 2001; 67 FR 61016, Sept. 27, 2002; 69 FR 76186, Dec. 20, 2004]

### § 178.604 Leakproofness test.

(a) *General.* The leakproofness test must be performed with compressed air or other suitable gases on all packagings intended to contain liquids, except that:

(1) The inner receptacle of a composite packaging may be tested without the outer packaging provided the test results are not affected; and

(2) This test is not required for inner packagings of combination packagings.

(b) *Number of packagings to be tested—*(1) *Production testing.* All packagings subject to the provisions of this section must be tested and must pass the leakproofness test:

(i) Before they are first used in transportation; and

(ii) Prior to reuse, when authorized for reuse by § 173.28 of this subchapter.

(2) *Design qualification and periodic testing.* Three samples of each different packaging must be tested and must pass the leakproofness test. Exceptions for the number of samples used in conducting the leakproofness test are subject to the approval of the Associate Administrator.

(c) *Special preparation—*(1) For design qualification and periodic testing,

packagings must be tested with closures in place. For production testing, packagings need not have their closures in place. Removable heads need not be installed during production testing.

(2) For testing with closures in place, vented closures must either be replaced by similar non-vented closures or the vent must be sealed.

(d) *Test method.* The packaging must be restrained under water while an internal air pressure is applied; the method of restraint must not affect the results of the test. The test must be conducted, for other than production testing, for a minimum time of five minutes. Other methods, at least equally effective, may be used in accordance with appendix B of this part.

(e) *Pressure applied.* An internal air pressure (gauge) must be applied to the packaging as indicated for the following packing groups:

(1) Packing Group I: Not less than 30 kPa (4 psi).

(2) Packing Group II: Not less than 20 kPa (3 psi).

(3) Packing Group III: Not less than 20 kPa (3 psi).

(f) *Criteria for passing the test.* A packaging passes the test if there is no leakage of air from the packaging.

[Amdt. 178–97, 55 FR 52723, Dec. 21, 1990, as amended at 56 FR 66286, Dec. 20, 1991; Amdt. 178–106, 59 FR 67522, Dec. 29, 1994; 66 FR 45386, Aug. 28, 2001]

### § 178.605 Hydrostatic pressure test.

(a) *General.* The hydrostatic pressure test must be conducted for the qualification of all metal, plastic, and composite packaging design types intended to contain liquids and be performed periodically as specified in § 178.601(e). This test is not required for inner packagings of combination packagings. For internal pressure requirements for inner packagings of combination packagings intended for transportation by aircraft, see § 173.27(c) of this subchapter.

(b) *Number of test samples.* Three test samples are required for each different packaging. For packagings constructed of stainless steel, monel, or nickel, only one sample is required for periodic retesting of packagings. Exceptions for the number of aluminum and steel

sample packagings used in conducting the hydrostatic pressure test are subject to the approval of the Associate Administrator.

(c) *Special preparation of receptacles for testings.* Vented closures must either be replaced by similar non-vented closures or the vent must be sealed.

(d) *Test method and pressure to be applied.* Metal packagings and composite packagings other than plastic (e.g., glass, porcelain or stoneware), including their closures, must be subjected to the test pressure for 5 minutes. Plastic packagings and composite packagings (plastic material), including their closures, must be subjected to the test pressure for 30 minutes. This pressure is the one to be marked as required in § 178.503(a)(5). The receptacles must be supported in a manner that does not invalidate the test. The test pressure must be applied continuously and evenly, and it must be kept constant throughout the test period. In addition, packagings intended to contain hazardous materials of Packing Group I must be tested to a minimum test pressure of 250 kPa (36 psig). The hydraulic pressure (gauge) applied, taken at the top of the receptacle, and determined by any one of the following methods must be:

(1) Not less than the total gauge pressure measured in the packaging (i.e., the vapor pressure of the filling material and the partial pressure of the air or other inert gas minus 100 kPa (15 psi)) at 55 °C (131 °F), multiplied by a safety factor of 1.5. This total gauge pressure must be determined on the basis of a maximum degree of filling in accordance with § 173.24a(d) of this subchapter and a filling temperature of 15 °C (59 °F);

(2) Not less than 1.75 times the vapor pressure at 50 °C (122 °F) of the material to be transported minus 100 kPa (15 psi) but with a minimum test pressure of 100 kPa (15 psig); or

(3) Not less than 1.5 times the vapor pressure at 55 °C (131 °F) of the material to be transported minus 100 kPa (15 psi), but with a minimum test pressure of 100 kPa (15 psig).

Packagings intended to contain hazardous materials of Packing Group I must be tested to a minimum test pressure of 250 kPa (36 psig).

(e) *Criteria for passing the test.* A package passes the hydrostatic test if, for each test sample, there is no leakage of liquid from the package.

[Amdt. 178-97, 55 FR 52723, Dec. 21, 1990, as amended at 56 FR 66286, Dec. 20, 1991; Amdt. 178-99, 58 FR 51534, Oct. 1, 1993; Amdt. 178-102, 59 FR 28494, June 2, 1994; 65 FR 50462, Aug. 18, 2000; 66 FR 45386, 45390, Aug. 28, 2001; 73 FR 57007, Oct. 1, 2008]

#### § 178.606 Stacking test.

(a) *General.* All packaging design types other than bags must be subjected to a stacking test.

(b) *Number of test samples.* Three test samples are required for each different packaging. For periodic retesting of packagings constructed of stainless steel, monel, or nickel, only one test sample is required. Exceptions for the number of aluminum and steel sample packagings used in conducting the stacking test are subject to the approval of the Associate Administrator. Notwithstanding the provisions of § 178.602(a) of this subpart, combination packagings may be subjected to the stacking test without their inner packagings, except where this would invalidate the results of the test.

(c) *Test method—(1) Design qualification testing.* The test sample must be subjected to a force applied to the top surface of the test sample equivalent to the total weight of identical packages which might be stacked on it during transport; where the contents of the test sample are non-hazardous liquids with specific gravities different from that of the liquid to be transported, the force must be calculated based on the specific gravity that will be marked on the packaging. The minimum height of the stack, including the test sample, must be 3.0 m (10 feet). The duration of the test must be 24 hours, except that plastic drums, jerricans, and composite packagings 6HH intended for liquids shall be subjected to the stacking test for a period of 28 days at a temperature of not less than 40°C (104°F). Alternative test methods which yield equivalent results may be used if approved by the Associate Administrator. In guided load tests, stacking stability must be assessed after completion of the test by placing two filled packagings of the same type on the test

## § 178.607

sample. The stacked packages must maintain their position for one hour. Plastic packagings must be cooled to ambient temperature before this stacking stability assessment.

(2) *Periodic retesting.* The test sample must be tested in accordance with:

(i) Section 178.606(c)(1) of this subpart; or

(ii) The packaging may be tested using a dynamic compression testing machine. The test must be conducted at room temperature on an empty, unsealed packaging. The test sample must be centered on the bottom platen of the testing machine. The top platen must be lowered until it comes in contact with the test sample. Compression must be applied end to end. The speed of the compression tester must be one-half inch plus or minus one-fourth inch per minute. An initial preload of 50 pounds must be applied to ensure a definite contact between the test sample and the platens. The distance between the platens at this time must be recorded as zero deformation. The force A to then be applied must be calculated using the formula:

Liquids:  $A = (n-1) [w + (s \times v \times 8.3 \times .98)] \times 1.5$ ;

Solids:  $A = (n-1) (m \times 2.2 \times 1.5)$

Where:

A = applied load in pounds

m = the certified maximum gross mass for the container in kilograms.

n = minimum number of containers that, when stacked, reach a height of 3 meters.

s = specific gravity of lading.

w = maximum weight of one empty container in pounds.

v = actual capacity of container (rated capacity + outage) in gallons.

And:

8.3 corresponds to the weight in pounds of 1.0 gallon of water.

.98 corresponds to the minimum filling percentage of the maximum capacity for liquids.

1.5 is a compensation factor that converts the static load of the stacking test into a load suitable for dynamic compression testing.

2.2 is the conversion factor for kilograms to pounds.

(d) *Criteria for passing the test.* No test sample may leak. In composite packagings or combination packagings, there must be no leakage of the filling substance from the inner receptacle, or

## 49 CFR Ch. I (10–1–08 Edition)

inner packaging. No test sample may show any deterioration which could adversely affect transportation safety or any distortion likely to reduce its strength, cause instability in stacks of packages, or cause damage to inner packagings likely to reduce safety in transportation. For the dynamic compression test, a container passes the test if, after application of the required load, there is no buckling of the side-walls sufficient to cause damage to its expected contents; in no case may the maximum deflection exceed one inch.

[Amdt. 178–97, 55 FR 52723, Dec. 21, 1990, as amended at 56 FR 66286, Dec. 20, 1991; 57 FR 45465, Oct. 1, 1992; Amdt. 178–102, 59 FR 28494, June 2, 1994; Amdt. 178–106, 59 FR 67522, Dec. 29, 1994; 65 FR 58632, Sept. 29, 2000; 66 FR 45386, Aug. 28, 2001; 70 FR 34076, June 13, 2005; 72 FR 55696, Oct. 1, 2007]

### § 178.607 Cooperage test for bung-type wooden barrels.

(a) *Number of samples.* One barrel is required for each different packaging.

(b) *Method of testing.* Remove all hoops above the bilge of an empty barrel at least two days old.

(c) *Criteria for passing the test.* A packaging passes the cooperage test only if the diameter of the cross-section of the upper part of the barrel does not increase by more than 10 percent.

### § 178.608 Vibration standard.

(a) Each packaging must be capable of withstanding, without rupture or leakage, the vibration test procedure outlined in this section.

(b) Test method. (1) Three sample packagings, selected at random, must be filled and closed as for shipment.

(2) The three samples must be placed on a vibrating platform that has a vertical or rotary double-amplitude (peak-to-peak displacement) of one inch. The packages should be constrained horizontally to prevent them from falling off the platform, but must be left free to move vertically, bounce and rotate.

(3) The test must be performed for one hour at a frequency that causes the package to be raised from the vibrating platform to such a degree that a piece of material of approximately 1.6 mm (0.063 inch) thickness (such as steel strapping or paperboard) can be passed

between the bottom of any package and the platform.

(4) Immediately following the period of vibration, each package must be removed from the platform, turned on its side and observed for any evidence of leakage.

(5) Other methods, at least equally effective, may be used, if approved by the Associate Administrator.

(c) *Criteria for passing the test.* A packaging passes the vibration test if there is no rupture or leakage from any of the packages. No test sample should show any deterioration which could adversely affect transportation safety or any distortion liable to reduce packaging strength.

[Amdt. 178-97, 55 FR 52723, Dec. 21, 1990, as amended at 56 FR 66286, Dec. 20, 1991; 66 FR 45386, Aug. 28, 2001]

#### § 178.609 Test requirements for packagings for infectious substances.

(a) Samples of each packaging must be prepared for testing as described in paragraph (b) of this section and then subjected to the tests in paragraphs (d) through (i) of this section.

(b) Samples of each packaging must be prepared as for transport except that a liquid or solid infectious sub-

stance should be replaced by water or, where conditioning at  $-18^{\circ}\text{C}$  ( $0^{\circ}\text{F}$ ) is specified, by water/antifreeze. Each primary receptacle must be filled to 98 percent capacity. Packagings for live animals should be tested with the live animal being replaced by an appropriate dummy of similar mass.

(c) Packagings prepared as for transport must be subjected to the tests in Table I of this paragraph (c), which, for test purposes, categorizes packagings according to their material characteristics. For outer packagings, the headings in Table I relate to fiberboard or similar materials whose performance may be rapidly affected by moisture; plastics that may embrittle at low temperature; and other materials, such as metal, for which performance is not significantly affected by moisture or temperature. Where a primary receptacle and a secondary packaging of an inner packaging are made of different materials, the material of the primary receptacle determines the appropriate test. In instances where a primary receptacle is made of more than one material, the material most likely to be damaged determines the appropriate test.

TABLE I—TESTS REQUIRED

| Material of     |          |        |                 |       | Tests required     |     |             |                      |                    |
|-----------------|----------|--------|-----------------|-------|--------------------|-----|-------------|----------------------|--------------------|
| Outer packaging |          |        | Inner packaging |       | Refer to para. (d) |     |             |                      | Refer to para. (h) |
| Fiberboard      | Plastics | Other  | Plastics        | Other | (d)                | (e) | (f)         | (g)                  |                    |
| X               |          |        | X               |       |                    | X   | X           | When dry ice is used | X                  |
| X               | X<br>X   |        | X               | X     |                    | X   | X<br>X<br>X |                      | X<br>X<br>X<br>X   |
|                 |          | X<br>X | X               | X     | X                  |     |             |                      | X                  |

(d) Samples must be subjected to free-fall drops onto a rigid, nonresilient, flat, horizontal surface from a height of 9 m (30 feet).

The drops must be performed as follows:

(1) Where the samples are in the shape of a box, five samples must be dropped, one in each of the following orientation:

- (i) Flat on the base;
- (ii) Flat on the top;
- (iii) Flat on the longest side;

- (iv) Flat on the shortest side; and
- (v) On a corner.

(2) Where the samples are in the shape of a drum, three samples must be dropped, one in each of the following orientations:

- (i) Diagonally on the top chime, with the center of gravity directly above the point of impact;
- (ii) Diagonally on the base chime; and
- (iii) Flat on the side.

(3) While the sample should be released in the required orientation, it is accepted that for aerodynamic reasons the impact may not take place in that orientation.

(4) Following the appropriate drop sequence, there must be no leakage from the primary receptacle(s) which should remain protected by absorbent material in the secondary packaging.

(e) The samples must be subjected to a water spray to simulate exposure to rainfall of approximately 50 mm (2 inches) per hour for at least one hour. They must then be subjected to the test described in paragraph (d) of this section.

(f) The sample must be conditioned in an atmosphere of  $-18^{\circ}\text{C}$  ( $0^{\circ}\text{F}$ ) or less for a period of at least 24 hours and within 15 minutes of removal from that atmosphere be subjected to the test described in paragraph (d) of this section. Where the sample contains dry ice, the conditioning period may be reduced to 4 hours.

(g) Where packaging is intended to contain dry ice, a test additional to that specified in paragraph (d) or (e) or (f) of this section must be carried out. One sample must be stored so that all the dry ice dissipates and then be subjected to the test described in paragraph (d) of this section.

(h) Packagings with a gross mass of 7 kg (15 pounds) or less should be subjected to the tests described in paragraph (h)(1) of this section and packagings with a gross mass exceeding 7 kg (15 pounds) to the tests in paragraph (h)(2) of this section.

(1) Samples must be placed on a level, hard surface. A cylindrical steel rod with a mass of at least 7 kg (15 pounds), a diameter not exceeding 38 mm (1.5 inches), and, at the impact end edges, a radius not exceeding 6 mm (0.2 inches), must be dropped in a vertical free fall from a height of 1 m (3 feet), measured from the impact end of the sample's impact surface. One sample must be placed on its base. A second sample must be placed in an orientation perpendicular to that used for the first. In each instance, the steel rod must be aimed to impact the primary receptacle(s). For a successful test, there must be no leakage from the pri-

mary receptacle(s) following each impact.

(2) Samples must be dropped onto the end of a cylindrical steel rod. The rod must be set vertically in a level, hard surface. It must have a diameter of 38 mm (1.5 inches) and a radius not exceeding 6 mm (0.2 inches) at the edges of the upper end. The rod must protrude from the surface a distance at least equal to that between the primary receptacle(s) and the outer surface of the outer packaging with a minimum of 200 mm (7.9 inches). One sample must be dropped in a vertical free fall from a height of 1 m (3 feet), measured from the top of the steel rod. A second sample must be dropped from the same height in an orientation perpendicular to that used for the first. In each instance, the packaging must be oriented so the steel rod will impact the primary receptacle(s). For a successful test, there must be no leakage from the primary receptacle(s) following each impact.

(i) *Variations.* The following variations in the primary receptacles placed within the secondary packaging are allowed without additional testing of the completed package. An equivalent level of performance must be maintained.

(1) *Variation 1.* Primary receptacles of equivalent or smaller size as compared to the tested primary receptacles may be used provided they meet all of the following conditions:

(i) The primary receptacles are of similar design to the tested primary receptacle (*e.g.*, shape: round, rectangular, etc.).

(ii) The material of construction of the primary receptacle (glass, plastics, metal, etc.) offers resistance to impact and a stacking force equal to or greater than that of the originally tested primary receptacle.

(iii) The primary receptacles have the same or smaller openings and the closure is of similar design (*e.g.*, screw cap, friction lid, etc.).

(iv) Sufficient additional cushioning material is used to fill void spaces and to prevent significant movement of the primary receptacles.

(v) Primary receptacles are oriented within the intermediate packaging in

the same manner as in the tested package.

(2) *Variation 2.* A lesser number of the tested primary receptacles, or of the alternative types of primary receptacles identified in paragraph (i)(1) of this section, may be used provided sufficient cushioning is added to fill the void space(s) and to prevent significant movement of the primary receptacles.

(3) *Variation 3.* Primary receptacles of any type may be placed within a secondary packaging and shipped without testing in the outer packaging provided all of the following conditions are met:

(i) The secondary and outer packaging combination must be successfully tested in accordance with paragraphs (a) through (h) of this section with fragile (e.g., glass) inner receptacles.

(ii) The total combined gross weight of inner receptacles may not exceed one-half the gross weight of inner receptacles used for the drop test in paragraph (d) of this section.

(iii) The thickness of cushioning material between inner receptacles and between inner receptacles and the outside of the secondary packaging may not be reduced below the corresponding thicknesses in the originally tested packaging. If a single inner receptacle was used in the original test, the thickness of cushioning between the inner receptacles must be no less than the thickness of cushioning between the outside of the secondary packaging and the inner receptacle in the original test. When either fewer or smaller inner receptacles are used (as compared to the inner receptacles used in the drop test), sufficient additional cushioning material must be used to fill the void.

(iv) The outer packaging must pass the stacking test in §178.606 while empty. The total weight of identical packages must be based on the combined mass of inner receptacles used in the drop test in paragraph (d) of this section.

(v) For inner receptacles containing liquids, an adequate quantity of absorbent material must be present to absorb the entire liquid contents of the inner receptacles.

(vi) If the outer packaging is intended to contain inner receptacles for

liquids and is not leakproof, or is intended to contain inner receptacles for solids and is not sift proof, a means of containing any liquid or solid contents in the event of leakage must be provided. This can be a leakproof liner, plastic bag, or other equally effective means of containment.

(vii) In addition, the marking required in §178.503(f) of this subchapter must be followed by the letter “U”.

[Amdt. 178-97, 55 FR 52723, Dec. 21, 1990, as amended by Amdt. 178-111, 60 FR 48787, Sept. 20, 1995; 67 FR 53143, Aug. 14, 2002; 69 FR 54046, Sept. 7, 2004]

### Subpart N—IBC Performance-Oriented Standards

#### §178.700 Purpose, scope and definitions.

(a) This subpart prescribes requirements applying to IBCs intended for the transportation of hazardous materials. Standards for these packagings are based on the UN Recommendations.

(b) Terms used in this subpart are defined in §171.8 of this subchapter and in paragraph (c) of this section.

(c) The following definitions pertain to the IBC standards in this subpart.

(1) *Body* means the receptacle proper (including openings and their closures, but not including service equipment), that has a volumetric capacity of not more than three cubic meters (3,000 L, 793 gallons, or 106 cubic feet) and not less than 0.45 cubic meters (450 L, 119 gallons, or 15.9 cubic feet) or a maximum net mass of not less than 400 kg (882 pounds).

(2) *Service equipment* means filling and discharge, pressure relief, safety, heating and heat-insulating devices and measuring instruments.

(3) *Structural equipment* means the reinforcing, fastening, handling, protective or stabilizing members of the body or stacking load bearing structural members (such as metal cages).

(4) *Maximum permissible gross mass* means the mass of the body, its service equipment, structural equipment and the maximum net mass (see §171.8 of this subchapter).

[Amdt. 178-103, 59 FR 38068, July 26, 1994, as amended by Amdt. 178-108, 60 FR 40038, Aug. 4, 1995; 66 FR 45386, 45387, Aug. 28, 2001; 73 FR 57008, Oct. 1, 2008]

## § 178.702

## 49 CFR Ch. I (10–1–08 Edition)

### § 178.702 IBC codes.

(a) Intermediate bulk container code designations consist of: two numerals specified in paragraph (a)(1) of this section; followed by the capital letter(s) specified in paragraph (a)(2) of this section; followed, when specified in an individual section, by a numeral indicating the category of intermediate bulk container.

(1) IBC code number designations are as follows:

| Type           | For solids, discharged |                                                | For liquids |
|----------------|------------------------|------------------------------------------------|-------------|
|                | by gravity             | Under pressure of more than 10 kPa (1.45 psig) |             |
| Rigid .....    | 11                     | 21                                             | 31          |
| Flexible ..... | 13                     |                                                |             |

(2) Intermediate bulk container code letter designations are as follows:

“A” means steel (all types and surface treatments).  
 “B” means aluminum.  
 “C” means natural wood.  
 “D” means plywood.  
 “E” means reconstituted wood.  
 “G” means fiberboard.  
 “H” means plastic.  
 “L” means textile.  
 “M” means paper, multiwall.  
 “N” means metal (other than steel or aluminum).

(b) For composite IBCs, two capital letters are used in sequence following the numeral indicating IBC design type. The first letter indicates the material of the IBC inner receptacle. The second letter indicates the material of the outer IBC. For example, 31HA1 is a composite IBC with a plastic inner receptacle and a steel outer packaging.

[Amdt. 178–103, 59 FR 38068, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001]

### § 178.703 Marking of IBCs.

(a) The manufacturer shall:

(1) Mark every IBC in a durable and clearly visible manner. The marking may be applied in a single line or in multiple lines provided the correct sequence is followed with the information required by this section in letters, numerals and symbols of at least 12 mm in height. This minimum marking

size applies only to IBCs manufactured after October 1, 2001). The following information is required in the sequence presented:

(i) The United Nations symbol as illustrated in § 178.503(e)(1). For metal IBCs on which the marking is stamped or embossed, the capital letters ‘UN’ may be applied instead of the symbol.

(ii) The code number designating IBC design type according to § 178.702(a). The letter “W” must follow the IBC design type identification code on an IBC when the IBC differs from the requirements in subpart N of this part, or is tested using methods other than those specified in this subpart, and is approved by the Associate Administrator in accordance with the provisions in § 178.801(i).

(iii) A capital letter identifying the performance standard under which the design type has been successfully tested, as follows:

(A) X—for IBCs meeting Packing Group I, II and III tests;

(B) Y—for IBCs meeting Packing Group II and III tests; and

(C) Z—for IBCs meeting only Packing Group III tests.

(iv) The month (designated numerically) and year (last two digits) of manufacture.

(v) The country authorizing the allocation of the mark. The letters ‘USA’ indicate that the IBC is manufactured and marked in the United States in compliance with the provisions of this subchapter.

(vi) The name and address or symbol of the manufacturer or the approval agency certifying compliance with subparts N and O of this part. Symbols, if used, must be registered with the Associate Administrator.

(vii) The stacking test load in kilograms (kg). For IBCs not designed for stacking, the figure “0” must be shown.

(viii) The maximum permissible gross mass or, for flexible IBCs, the maximum net mass, in kg.

(2) The following are examples of symbols and required markings:

(i) For a metal IBC containing solids discharged by gravity made from steel:



**11A/Y/02 92/USA/ABC/5500/1500**

(ii) For a flexible IBC containing solids discharged by gravity and made from woven plastic with a liner:



**13H3/Z/03 92/USA/ABC/0/1500**

(iii) For a rigid plastic IBC containing liquids, made from plastic with structural equipment withstanding the

stack load and with a manufacturer's symbol in place of the manufacturer's name and address:



**31H1/Y/04 93/USA/M9399/10800/1200**

(iv) For a composite IBC containing liquids, with a rigid plastic inner receptacle and an outer steel body and

with the symbol of a DOT approved third-party test laboratory:



**31HA1/Y/05 93/USA/+ZT1235/10800/1200**

(b) *Additional marking.* In addition to markings required in paragraph (a) of this section, each IBC must be marked as follows in a place near the markings required in paragraph (a) of this section that is readily accessible for inspection. Where units of measure are

used, the metric unit indicated (e.g., 450 L) must also appear.

(1) For each rigid plastic and composite IBC, the following markings must be included:

(i) Rated capacity in L of water at 20 °C (68 °F);

(ii) Tare mass in kilograms;



**§ 178.704**

**49 CFR Ch. I (10–1–08 Edition)**

- (iii) Gauge test pressure in kPa;
- (iv) Date of last leakproofness test, if applicable (month and year); and
- (v) Date of last inspection (month and year).

(2) For each metal IBC, the following markings must be included on a metal corrosion-resistant plate:

- (i) Rated capacity in L of water at 20 °C (68 °F);
- (ii) Tare mass in kilograms;
- (iii) Date of last leakproofness test, if applicable (month and year);
- (iv) Date of last inspection (month and year);
- (v) Maximum loading/discharge pressure, in kPa, if applicable;
- (vi) Body material and its minimum thickness in mm; and
- (vii) Serial number assigned by the manufacturer.

(3) Markings required by paragraph (b)(1) or (b)(2) of this section may be preceded by the narrative description of the marking, e.g., “Tare Mass: \* \* \*” where the “\* \* \*” are replaced with the tare mass in kilograms of the IBC.

(4) For each fiberboard and wooden IBC, the tare mass in kg must be shown.

(5) Each flexible IBC may be marked with a pictogram displaying recommended lifting methods.

(6) For each composite IBC, the inner receptacle must be marked with at least the following information:

- (i) The code number designating the IBC design type, the name and address or symbol of the manufacturer, the date of manufacture and the country authorizing the allocation of the mark as specified in paragraph (a) of this section;
- (ii) When a composite IBC is designed in such a manner that the outer casing is intended to be dismantled for transport when empty (such as, for the return of the IBC for reuse to the original consignor), each of the parts intended to be detached when so dismantled must be marked with the month and year of manufacture and the name or symbol of the manufacturer.

[Amdt. 178–103, 59 FR 38068, July 26, 1994, as amended by Amdt. 178–119, 62 FR 24743, May 6, 1997; 64 FR 10782, Mar. 5, 1999; 65 FR 50462, Aug. 18, 2000; 65 FR 58632, Sept. 29, 2000; 66 FR 33451, June 21, 2001; 66 FR 45387, Aug. 28, 2001]

**§ 178.704 General IBC standards.**

(a) Each IBC must be resistant to, or protected from, deterioration due to exposure to the external environment. IBCs intended for solid hazardous materials must be sift-proof and water-resistant.

(b) All service equipment must be so positioned or protected as to minimize potential loss of contents resulting from damage during IBC handling and transportation.

(c) Each IBC, including attachments, and service and structural equipment, must be designed to withstand, without loss of hazardous materials, the internal pressure of the contents and the stresses of normal handling and transport. An IBC intended for stacking must be designed for stacking. Any lifting or securing features of an IBC must be of sufficient strength to withstand the normal conditions of handling and transportation without gross distortion or failure and must be positioned so as to cause no undue stress in any part of the IBC.

(d) An IBC consisting of a packaging within a framework must be so constructed that:

- (1) The body is not damaged by the framework;
- (2) The body is retained within the framework at all times; and
- (3) The service and structural equipment are fixed in such a way that they cannot be damaged if the connections between body and frame allow relative expansion or motion.

(e) Bottom discharge valves must be secured in the closed position and the discharge system suitably protected from damage. Valves having lever closures must be secured against accidental opening. The open or closed position of each valve must be readily apparent. For each IBC containing a liquid, a secondary means of sealing the discharge aperture must also be provided, e.g., by a blank flange or equivalent device.

(f) IBC design types must be constructed in such a way as to be bottom-lifted or top-lifted as specified in §§ 178.811 and 178.812.

[Amdt. 178–103, 59 FR 38068, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001; 68 FR 61942, Oct. 30, 2003]

**§ 178.705 Standards for metal IBCs.**

(a) The provisions in this section apply to metal IBCs intended to contain liquids and solids. Metal IBC types are designated:

(1) 11A, 11B, 11N for solids that are loaded or discharged by gravity.

(2) 21A, 21B, 21N for solids that are loaded or discharged at a gauge pressure greater than 10 kPa (1.45 psig).

(3) 31A, 31B, 31N for liquids or solids.

(b) Definitions for metal IBCs:

(1) *Metal IBC* means an IBC with a metal body, together with appropriate service and structural equipment.

(2) *Protected* means providing the IBC body with additional external protection against impact and abrasion. For example, a multi-layer (sandwich) or double wall construction or a frame with a metal lattice-work casing.

(c) Construction requirements for metal IBCs are as follows:

(1) *Body*. The body must be made of ductile metal materials. Welds must be made so as to maintain design type integrity of the receptacle under conditions normally incident to transportation.

(i) The use of dissimilar metals must not result in deterioration that could affect the integrity of the body.

(ii) Aluminum IBCs intended to contain flammable liquids must have no movable parts, such as covers and closures, made of unprotected steel liable to rust, which might cause a dangerous reaction from friction or percussive contact with the aluminum.

(iii) Metals used in fabricating the body of a metal IBC must meet the following requirements:

(A) For steel, the percentage elongation at fracture must not be less than  $10,000/R_m$  with a minimum of 20 percent; where  $R_m$  = minimum tensile strength of the steel to be used, in N/mm<sup>2</sup>; if U.S. Standard units of psi are used for tensile strength then the ratio becomes  $10,000 \times (145/R_m)$ .

(B) For aluminum, the percentage elongation at fracture must not be less than  $10,000/(6R_m)$  with an absolute minimum of eight percent; if U.S. Standard units of psi are used for tensile strength then the ratio becomes  $10,000 \times 145 / (6R_m)$ .

(C) Specimens used to determine the elongation at fracture must be taken transversely to the direction of rolling and be so secured that:

$$L_o = 5d$$

or

$$L_o = 5.65 \sqrt{A}$$

where:

$L_o$  = gauge length of the specimen before the test

$d$  = diameter

$A$  = cross-sectional area of test specimen.

(iv) Minimum wall thickness:

(A) For a reference steel having a product of  $R_m \times A_o = 10,000$ , where  $A_o$  is the minimum elongation (as a percentage) of the reference steel to be used on fracture under tensile stress ( $R_m \times A_o = 10,000 \times 145$ ; if tensile strength is in U.S. Standard units of pounds per square inch), the wall thickness must not be less than:

| Capacity (C) in liters <sup>1</sup> | Wall thickness (T) in mm |                      |                                    |                      |
|-------------------------------------|--------------------------|----------------------|------------------------------------|----------------------|
|                                     | Types 11A, 11B, 11N      |                      | Types 21A, 21B, 21N, 31A, 31B, 31N |                      |
|                                     | Unprotected              | Protected            | Unprotected                        | Protected            |
| C ≤ 1000 .....                      | 2.0 .....                | 1.5 .....            | 2.5 .....                          | 2.0 .....            |
| 1000 < C ≤ 2000 .....               | T = C/2000 + 1.5 ...     | T = C/2000 + 1.0 ... | T = C/2000 + 2.0 ...               | T = C/2000 + 1.5 ... |
| 2000 < C ≤ 3000 .....               | T = C/2000 + 1.5 ...     | T = C/2000 + 1.0 ... | T = C/1000 + 1.0 ...               | T = C/2000 + 1.5 ... |

(B) For metals other than the reference steel described in paragraph (c)(1)(iii)(A) of this section, the minimum wall thickness is the greater of 1.5 mm (0.059 inches) or as determined by use of the following equivalence formula:

**FORMULA FOR METRIC UNITS**

$$e_1 = \frac{21.4 \times e_0}{\sqrt[3]{R_{m1} \times A_1}}$$

## § 178.706

### FORMULA FOR U.S. STANDARD UNITS

$$e_1 = \frac{21.4 \times e_0}{\sqrt[3]{(Rm_1 \times A_1)/145}}$$

where:

$e_1$  = required equivalent wall thickness of the metal to be used (in mm or if  $e_0$  is in inches, use formula for U.S. Standard units).

$e_0$  = required minimum wall thickness for the reference steel (in mm or if  $e_0$  is in inches, use formula for U.S. Standard units).

$Rm_1$  = guaranteed minimum tensile strength of the metal to be used (in N/mm<sup>2</sup> or for U.S. Standard units, use psi).

$A_1$  = minimum elongation (as a percentage) of the metal to be used on fracture under tensile stress (see paragraph (c)(1) of this section).

(C) For purposes of the calculation described in paragraph (c)(1)(iv)(B) of this section, the guaranteed minimum tensile strength of the metal to be used ( $Rm_1$ ) must be the minimum value according to material standards. However, for austenitic (stainless) steels, the specified minimum value for  $Rm$ , according to the material standards, may be increased by up to 15% when a greater value is provided in the material inspection certificate. When no material standard exists for the material in question, the value of  $Rm$  must be the minimum value indicated in the material inspection certificate.

(2) *Pressure relief.* The following pressure relief requirements apply to IBCs intended for liquids:

(i) IBCs must be capable of releasing a sufficient amount of vapor in the event of fire engulfment to ensure that no rupture of the body will occur due to pressure build-up. This can be achieved by spring-loaded or non-reclosing pressure relief devices or by other means of construction.

(ii) The start-to-discharge pressure may not be higher than 65 kPa (9 psig) and no lower than the vapor pressure of the hazardous material plus the partial pressure of the air or other inert gases, measured in the IBC at 55 °C (131 °F), determined on the basis of a maximum degree of filling as specified in §173.35(d) of this subchapter. This does not apply to fusible devices unless such

## 49 CFR Ch. I (10–1–08 Edition)

devices are the only source of pressure relief for the IBC. Pressure relief devices must be fitted in the vapor space.

[Amdt. 178–103, 59 FR 38068, July 26, 1994, as amended by Amdt. 178–108, 60 FR 40038, Aug. 4, 1995; Amdt. 178–117, 61 FR 50629, Sept. 26, 1996; 66 FR 33452, June 21, 2001; 66 FR 45386, 45387, Aug. 28, 2001; 68 FR 45041, July 31, 2003]

### § 178.706 Standards for rigid plastic IBCs.

(a) The provisions in this section apply to rigid plastic IBCs intended to contain solids or liquids. Rigid plastic IBC types are designated:

(1) 11H1 fitted with structural equipment designed to withstand the whole load when IBCs are stacked, for solids which are loaded or discharged by gravity.

(2) 11H2 freestanding, for solids which are loaded or discharged by gravity.

(3) 21H1 fitted with structural equipment designed to withstand the whole load when IBCs are stacked, for solids which are loaded or discharged under pressure.

(4) 21H2 freestanding, for solids which are loaded or discharged under pressure.

(5) 31H1 fitted with structural equipment designed to withstand the whole load when IBCs are stacked, for liquids.

(6) 31H2 freestanding, for liquids.

(b) Rigid plastic IBCs consist of a rigid plastic body, which may have structural equipment, together with appropriate service equipment.

(c) Rigid plastic IBCs must be manufactured from plastic material of known specifications and be of a strength relative to its capacity and to the service it is required to perform. In addition to conformance to §173.24 of this subchapter, plastic materials must be resistant to aging and to degradation caused by ultraviolet radiation.

(1) If protection against ultraviolet radiation is necessary, it must be provided by the addition of a pigment or inhibitor such as carbon black. These additives must be compatible with the contents and remain effective throughout the life of the IBC body. Where use is made of carbon black, pigments or inhibitors, other than those used in the manufacture of the tested design type, retesting may be omitted if changes in the carbon black content, the pigment

content or the inhibitor content do not adversely affect the physical properties of the material of construction.

(2) Additives may be included in the composition of the plastic material to improve the resistance to aging or to serve other purposes, provided they do not adversely affect the physical or chemical properties of the material of construction.

(3) No used material other than production residues or regrind from the same manufacturing process may be used in the manufacture of rigid plastic IBCs.

(4) Rigid plastic IBCs intended for the transportation of liquids must be capable of releasing a sufficient amount of vapor to prevent the body of the IBC from rupturing if it is subjected to an internal pressure in excess of that for which it was hydraulically tested. This may be achieved by spring-loaded or non-reclosing pressure relief devices or by other means of construction.

[Amdt. 178-103, 59 FR 38068, July 26, 1994, as amended at 66 FR 45386, 45387, Aug. 28, 2001]

#### § 178.707 Standards for composite IBCs.

(a) The provisions in this section apply to composite IBCs intended to contain solids and liquids. To complete the marking codes listed below, the letter "Z" must be replaced by a capital letter in accordance with § 178.702(a)(2) to indicate the material used for the outer packaging. Composite IBC types are designated:

(1) 11HZ1 Composite IBCs with a rigid plastic inner receptacle for solids loaded or discharged by gravity.

(2) 11HZ2 Composite IBCs with a flexible plastic inner receptacle for solids loaded or discharged by gravity.

(3) 21HZ1 Composite IBCs with a rigid plastic inner receptacle for solids loaded or discharged under pressure.

(4) 21HZ2 Composite IBCs with a flexible plastic inner receptacle for solids loaded or discharged under pressure.

(5) 31HZ1 Composite IBCs with a rigid plastic inner receptacle for liquids.

(6) 31HZ2 Composite IBCs with a flexible plastic inner receptacle for liquids.

(b) Definitions for composite IBC types:

(1) A *composite IBC* is an IBC which consists of a rigid outer packaging enclosing a plastic inner receptacle together with any service or other structural equipment. The outer packaging of a composite IBC is designed to bear the entire stacking load. The inner receptacle and outer packaging form an integral packaging and are filled, stored, transported, and emptied as a unit.

(2) The term plastic means polymeric materials (i.e., plastic or rubber).

(3) A "rigid" inner receptacle is an inner receptacle which retains its general shape when empty without closures in place and without benefit of the outer casing. Any inner receptacle that is not "rigid" is considered to be "flexible."

(c) Construction requirements for composite IBCs with plastic inner receptacles are as follows:

(1) The outer packaging must consist of rigid material formed so as to protect the inner receptacle from physical damage during handling and transportation, but is not required to perform the secondary containment function. It includes the base pallet where appropriate. The inner receptacle is not intended to perform a containment function without the outer packaging.

(2) A composite IBC with a fully enclosing outer packaging must be designed to permit assessment of the integrity of the inner container following the leakproofness and hydraulic tests. The outer packaging of 31HZ2 composite IBCs must enclose the inner receptacles on all sides.

(3) The inner receptacle must be manufactured from plastic material of known specifications and be of a strength relative to its capacity and to the service it is required to perform. In addition to conformance with the requirements of § 173.24 of this subchapter, the material must be resistant to aging and to degradation caused by ultraviolet radiation. The inner receptacle of 31HZ2 composite IBCs must consist of at least three plies of film.

(i) If necessary, protection against ultraviolet radiation must be provided by the addition of pigments or inhibitors such as carbon black. These additives must be compatible with the contents and remain effective throughout

the life of the inner receptacle. Where use is made of carbon black, pigments, or inhibitors, other than those used in the manufacture of the tested design type, retesting may be omitted if the carbon black content, the pigment content, or the inhibitor content do not adversely affect the physical properties of the material of construction.

(ii) Additives may be included in the composition of the plastic material of the inner receptacle to improve resistance to aging, provided they do not adversely affect the physical or chemical properties of the material.

(iii) No used material other than production residues or regrind from the same manufacturing process may be used in the manufacture of inner receptacles.

(iv) Composite IBCs intended for the transportation of liquids must be capable of releasing a sufficient amount of vapor to prevent the body of the IBC from rupturing if it is subjected to an internal pressure in excess of that for which it was hydraulically tested. This may be achieved by spring-loaded or non-reclosing pressure relief devices or by other means of construction.

(4) The strength of the construction material comprising the outer packaging and the manner of construction must be appropriate to the capacity of the composite IBC and its intended use. The outer packaging must be free of any projection that might damage the inner receptacle.

(i) Outer packagings of natural wood must be constructed of well seasoned wood that is commercially dry and free from defects that would materially lessen the strength of any part of the outer packaging. The tops and bottoms may be made of water-resistant reconstituted wood such as hardboard or particle board. Materials other than natural wood may be used for construction of structural equipment of the outer packaging.

(ii) Outer packagings of plywood must be made of well-seasoned, rotary cut, sliced, or sawn veneer, commercially dry and free from defects that would materially lessen the strength of the casing. All adjacent plies must be glued with water-resistant adhesive. Materials other than plywood may be used for construction of structural

equipment of the outer packaging. Outer packagings must be firmly nailed or secured to corner posts or ends or be assembled by equally suitable devices.

(iii) Outer packagings of reconstituted wood must be constructed of water-resistant reconstituted wood such as hardboard or particle board. Materials other than reconstituted wood may be used for the construction of structural equipment of reconstituted wood outer packaging.

(iv) Fiberboard outer packagings must be constructed of strong, solid, or double-faced corrugated fiberboard (single or multiwall).

(A) Water resistance of the outer surface must be such that the increase in mass, as determined in a test carried out over a period of 30 minutes by the Cobb method of determining water absorption, is not greater than 155 grams per square meter (0.0316 pounds per square foot)—see ISO 535 (E) (IBR, see §171.7 of this subchapter). Fiberboard must have proper bending qualities. Fiberboard must be cut, creased without cutting through any thickness of fiberboard, and slotted so as to permit assembly without cracking, surface breaks, or undue bending. The fluting of corrugated fiberboard must be firmly glued to the facings.

(B) The ends of fiberboard outer packagings may have a wooden frame or be constructed entirely of wood. Wooden battens may be used for reinforcements.

(C) Manufacturers' joints in the bodies of outer packagings must be taped, lapped and glued, or lapped and stitched with metal staples.

(D) Lapped joints must have an appropriate overlap.

(E) Where closing is effected by gluing or taping, a water-resistant adhesive must be used.

(F) All closures must be sift-proof.

(v) Outer packagings of plastic materials must be constructed in accordance with the relevant provisions of paragraph (c)(3) of this section.

(5) Any integral pallet base forming part of an IBC, or any detachable pallet, must be suitable for the mechanical handling of an IBC filled to its maximum permissible gross mass.

(i) The pallet or integral base must be designed to avoid protrusions that may cause damage to the IBC in handling.

(ii) The outer packaging must be secured to any detachable pallet to ensure stability in handling and transportation. Where a detachable pallet is used, its top surface must be free from sharp protrusions that might damage the IBC.

(iii) Strengthening devices, such as timber supports to increase stacking performance, may be used but must be external to the inner receptacle.

(iv) The load-bearing surfaces of IBCs intended for stacking must be designed to distribute loads in a stable manner. An IBC intended for stacking must be designed so that loads are not supported by the inner receptacle.

(6) Intermediate IBCs of type 31HZ2 must be limited to a capacity of not more than 1,250 L.

[Amdt. 178-103, 59 FR 38068, July 26, 1994, as amended by Amdt. 178-119, 62 FR 24743, May 6, 1997; 66 FR 45387, Aug. 28, 2001; 67 FR 61016, Sept. 27, 2002; 68 FR 75758, Dec. 31, 2003; 69 FR 54046, Sept. 7, 2004]

#### § 178.708 Standards for fiberboard IBCs.

(a) The provisions of this section apply to fiberboard IBCs intended to contain solids that are loaded or discharged by gravity. Fiberboard IBCs are designated: 11G.

(b) Definitions for fiberboard IBC types:

(1) *Fiberboard IBCs* consist of a fiberboard body with or without separate top and bottom caps, appropriate service and structural equipment, and if necessary an inner liner (but no inner packaging).

(2) *Liner* means a separate tube or bag, including the closures of its openings, inserted in the body but not forming an integral part of it.

(c) Construction requirements for fiberboard IBCs are as follows:

(1) Top lifting devices are prohibited in fiberboard IBCs.

(2) Fiberboard IBCs must be constructed of strong, solid or double-faced corrugated fiberboard (single or multiwall) that is appropriate to the capacity of the outer packaging and its intended use. Water resistance of the

outer surface must be such that the increase in mass, as determined in a test carried out over a period of 30 minutes by the Cobb method of determining water absorption, is not greater than 155 grams per square meter (0.0316 pounds per square foot)—see ISO 535 (E) (IBR, see § 171.7 of this subchapter). Fiberboard must have proper bending qualities. Fiberboard must be cut, creased without cutting through any thickness of fiberboard, and slotted so as to permit assembly without cracking, surface breaks, or undue bending. The fluting of corrugated fiberboard must be firmly glued to the facings.

(i) The walls, including top and bottom, must have a minimum puncture resistance of 15 Joules (11 foot-pounds of energy) measured according to ISO 3036 (IBR, see § 171.7 of this subchapter).

(ii) Manufacturers' joints in the bodies of IBCs must be made with an appropriate overlap and be taped, glued, stitched with metal staples or fastened by other means at least equally effective. Where joints are made by gluing or taping, a water-resistant adhesive must be used. Metal staples must pass completely through all pieces to be fastened and be formed or protected so that any inner liner cannot be abraded or punctured by them.

(3) The strength of the material used and the construction of the liner must be appropriate to the capacity of the IBC and the intended use. Joints and closures must be sift-proof and capable of withstanding pressures and impacts liable to occur under normal conditions of handling and transport.

(4) Any integral pallet base forming part of an IBC, or any detachable pallet, must be suitable for the mechanical handling of an IBC filled to its maximum permissible gross mass.

(i) The pallet or integral base must be designed to avoid protrusions that may cause damage to the IBC in handling.

(ii) The outer packaging must be secured to any detachable pallet to ensure stability in handling and transport. Where a detachable pallet is used, its top surface must be free from sharp protrusions that might damage the IBC.

(iii) Strengthening devices, such as timber supports to increase stacking

## § 178.709

## 49 CFR Ch. I (10–1–08 Edition)

performance, may be used but must be external to the inner liner.

(iv) The load-bearing surfaces of IBCs intended for stacking must be designed to distribute loads in a stable manner.

[Amdt. 178–103, 59 FR 38068, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001; 68 FR 75758, Dec. 31, 2003]

### § 178.709 Standards for wooden IBCs.

(a) The provisions in this section apply to wooden IBCs intended to contain solids that are loaded or discharged by gravity. Wooden IBC types are designated:

(1) 11C Natural wood with inner liner.

(2) 11D Plywood with inner liner.

(3) 11F Reconstituted wood with inner liner.

(b) Definitions for wooden IBCs:

(1) *Wooden IBCs* consist of a rigid or collapsible wooden body together with an inner liner (but no inner packaging) and appropriate service and structural equipment.

(2) *Liner* means a separate tube or bag, including the closures of its openings, inserted in the body but not forming an integral part of it.

(c) Construction requirements for wooden IBCs are as follows:

(1) Top lifting devices are prohibited in wooden IBCs.

(2) The strength of the materials used and the method of construction must be appropriate to the capacity and intended use of the IBC.

(i) Natural wood used in the construction of an IBC must be well-seasoned, commercially dry, and free from defects that would materially lessen the strength of any part of the IBC. Each IBC part must consist of uncut wood or a piece equivalent in strength and integrity. IBC parts are equivalent to one piece when a suitable method of glued assembly is used (i.e., a Lindermann joint, tongue and groove joint, ship lap or rabbet joint, or butt joint with at least two corrugated metal fasteners at each joint, or when other methods at least equally effective are used). Materials other than natural wood may be used for the construction of structural equipment of the outer packaging.

(ii) Plywood used in construction of bodies must be at least 3-ply. Plywood must be made of well-seasoned, rotary-

cut, sliced or sawn veneer, commercially dry, and free from defects that would materially lessen the strength of the body. All adjacent plies must be glued with water-resistant adhesive. Materials other than plywood may be used for the construction of structural equipment of the outer packaging.

(iii) Reconstituted wood used in construction of bodies must be water resistant reconstituted wood such as hardboard or particle board. Materials other than reconstituted wood may be used for the construction of structural equipment of the outer packaging.

(iv) Wooden IBCs must be firmly nailed or secured to corner posts or ends or be assembled by similar devices.

(3) The strength of the material used and the construction of the liner must be appropriate to the capacity of the IBC and its intended use. Joints and closures must be sift-proof and capable of withstanding pressures and impacts liable to occur under normal conditions of handling and transportation.

(4) Any integral pallet base forming part of an IBC, or any detachable pallet, must be suitable for the mechanical handling of an IBC filled to its maximum permissible gross mass.

(i) The pallet or integral base must be designed to avoid protrusions that may cause damage to the IBC in handling.

(ii) The outer packaging must be secured to any detachable pallet to ensure stability in handling and transportation. Where a detachable pallet is used, its top surface must be free from sharp protrusions that might damage the IBC.

(iii) Strengthening devices, such as timber supports to increase stacking performance, may be used but must be external to the inner liner.

(iv) The load-bearing surfaces of IBCs intended for stacking must be designed to distribute loads in a stable manner.

[Amdt. 178–103, 59 FR 38068, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001]

### § 178.710 Standards for flexible IBCs.

(a) The provisions of this section apply to flexible IBCs intended to contain solid hazardous materials. Flexible IBC types are designated:

- (1) 13H1 woven plastic without coating or liner.
- (2) 13H2 woven plastic, coated.
- (3) 13H3 woven plastic with liner.
- (4) 13H4 woven plastic, coated and with liner.
- (5) 13H5 plastic film.
- (6) 13L1 textile without coating or liner.
- (7) 13L2 textile, coated.
- (8) 13L3 textile with liner.
- (9) 13L4 textile, coated and with liner.
- (10) 13M1 paper, multiwall.
- (11) 13M2 paper, multiwall, water resistant.

(b) Definitions for flexible IBCs:

(1) *Flexible IBCs* consist of a body constructed of film, woven plastic, woven fabric, paper, or combination thereof, together with any appropriate service equipment and handling devices, and if necessary, an inner coating or liner.

(2) *Woven plastic* means a material made from stretched tapes or monofilaments.

(3) *Handling device* means any sling, loop, eye, or frame attached to the body of the IBC or formed from a continuation of the IBC body material.

(c) Construction requirements for flexible IBCs are as follows:

(1) The strength of the material and the construction of the flexible IBC must be appropriate to its capacity and its intended use.

(2) All materials used in the construction of flexible IBCs of types 13M1 and 13M2 must, after complete immersion in water for not less than 24 hours, retain at least 85 percent of the tensile strength as measured originally on the material conditioned to equilibrium at 67 percent relative humidity or less.

(3) Seams must be stitched or formed by heat sealing, gluing or any equivalent method. All stitched seam-ends must be secured.

(4) In addition to conformance with the requirements of §173.24 of this subchapter, flexible IBCs must be resistant to aging and degradation caused by ultraviolet radiation.

(5) For plastic flexible IBCs, if necessary, protection against ultraviolet radiation must be provided by the addition of pigments or inhibitors such as carbon black. These additives must be compatible with the contents and re-

main effective throughout the life of the container. Where use is made of carbon black, pigments, or inhibitors, other than those used in the manufacture of the tested design type, re-testing may be omitted if the carbon black content, the pigment content or the inhibitor content does not adversely affect the physical properties of the material of construction. Additives may be included in the composition of the plastic material to improve resistance to aging, provided they do not adversely affect the physical or chemical properties of the material.

(6) No used material other than production residues or regrind from the same manufacturing process may be used in the manufacture of plastic flexible IBCs. This does not preclude the re-use of component parts such as fittings and pallet bases, provided such components have not in any way been damaged in previous use.

(7) When flexible IBCs are filled, the ratio of height to width may not be more than 2:1.

[Amdt. 178-103, 59 FR 38068, July 26, 1994, as amended by Amdt. 178-108, 60 FR 40038, Aug. 4, 1995; 66 FR 45386, Aug. 28, 2001]

### Subpart O—Testing of IBCs

#### § 178.800 Purpose and scope.

This subpart prescribes certain testing requirements for IBCs identified in subpart N of this part.

[Amdt. 178-103, 59 FR 38074, July 26, 1994, as amended by 66 FR 45386, Aug. 28, 2001]

#### § 178.801 General requirements.

(a) *General.* The test procedures prescribed in this subpart are intended to ensure that IBCs containing hazardous materials can withstand normal conditions of transportation and are considered minimum requirements. Each packaging must be manufactured and assembled so as to be capable of successfully passing the prescribed tests and of conforming to the requirements of §173.24 of this subchapter at all times while in transportation.

(b) *Responsibility.* It is the responsibility of the IBC manufacturer to assure that each IBC is capable of passing the prescribed tests. To the extent that an IBC assembly function, including



final closure, is performed by the person who offers a hazardous material for transportation, that person is responsible for performing the function in accordance with §§ 173.22 and 178.2 of this subchapter.

(c) *Definitions.* For the purpose of this subpart:

(1) *IBC design type* refers to an IBC that does not differ in structural design, size, material of construction, wall thickness, manner of construction and representative service equipment.

(2) *Design qualification testing* is the performance of the drop, leakproofness, hydrostatic pressure, stacking, bottom-lift or top-lift, tear, topple, righting and vibration tests, as applicable, prescribed in this subpart, for each different IBC design type, at the start of production of that packaging.

(3) *Periodic design requalification test* is the performance of the applicable tests specified in paragraph (c)(2) of this section on an IBC design type, in order to requalify the design for continued production at the frequency specified in paragraph (e) of this section.

(4) *Production inspection* is the inspection that must initially be conducted on each newly manufactured IBC.

(5) *Production testing* is the performance of the leakproofness test in accordance with paragraph (f) of this section on each IBC intended to contain solids discharged by pressure or intended to contain liquids.

(6) *Periodic retest and inspection* is performance of the applicable test and inspections on each IBC at the frequency specified in § 180.352 of this subchapter.

(7) *Different IBC design type* is one that differs from a previously qualified IBC design type in structural design, size, material of construction, wall thickness, or manner of construction, but does not include:

(i) A packaging which differs in surface treatment;

(ii) A rigid plastic IBC or composite IBC which differs with regard to additives used to comply with §§ 178.706(c), 178.707(c) or 178.710(c);

(iii) A packaging which differs only in its lesser external dimensions (i.e., height, width, length) provided materials of construction and material thicknesses or fabric weight remain the same;

(iv) A packaging which differs in service equipment.

(d) *Design qualification testing.* The packaging manufacturer shall achieve successful test results for the design qualification testing at the start of production of each new or different IBC design type. The service equipment selected for this design qualification testing shall be representative of the type of service equipment that will be fitted to any finished IBC body under the design. Application of the certification mark by the manufacturer shall constitute certification that the IBC design type passed the prescribed tests in this subpart.

(e) *Periodic design requalification testing.* (1) Periodic design requalification must be conducted on each qualified IBC design type if the manufacturer is to maintain authorization for continued production. The IBC manufacturer shall achieve successful test results for the periodic design requalification at sufficient frequency to ensure each packaging produced by the manufacturer is capable of passing the design qualification tests. Design requalification tests must be conducted at least once every 12 months.

(2) Changes in the frequency of design requalification testing specified in paragraph (e)(1) of this section are authorized if approved by the Associate Administrator. These requests must be based on:

(i) Detailed quality assurance programs that assure that proposed decreases in test frequency maintain the integrity of originally tested IBC design types; and

(ii) Demonstrations that each IBC produced is capable of withstanding higher standards (e.g., increased drop height, hydrostatic pressure, wall thickness, fabric weight).

(f) *Production testing and inspection.* (1) Production testing consists of the leakproofness test prescribed in § 178.813 of this subpart and must be performed on each IBC intended to contain solids discharged by pressure or intended to contain liquids. For this test:

(i) The IBC need not have its closures fitted.

(ii) The inner receptacle of a composite IBC may be tested without the

outer IBC body, provided the test results are not affected.

(2) Applicable inspection requirements in §180.352 of this subchapter must be performed on each IBC initially after production.

(g) *Test samples.* The IBC manufacturer shall conduct the design qualification and periodic design requalification tests prescribed in this subpart using random samples of IBCs, according to the appropriate test section.

(h) *Selective testing of IBCs.* Variation of a tested IBC design type is permitted without further testing, provided selective testing demonstrates an equivalent or greater level of safety than the design type tested and which has been approved by the Associate Administrator.

(i) *Approval of equivalent packagings.* An IBC that differs from the standards in subpart N of this part, or that is tested using methods other than those specified in this subpart, may be used if approved by the Associate Administrator. Such IBCs must be shown to be equally effective, and testing methods used must be equivalent. A large packaging, as defined in §171.8 of this subchapter, may be used if approved by the Associate Administrator. The large packaging must conform to the construction standards, performance testing and packaging marking requirements specified in the UN Recommendations (IBR, see §171.7 of this subchapter).

(j) *Proof of compliance.* Notwithstanding the periodic design requalification testing intervals specified in paragraph (e) of this section, the Associate Administrator, or a designated representative, may at any time require demonstration of compliance by a manufacturer, through testing in accordance with this subpart, that packagings meet the requirements of this subpart. As required by the Associate Administrator, or a designated representative, the manufacturer shall either:

(1) Conduct performance tests or have tests conducted by an independent testing facility, in accordance with this subpart; or

(2) Make a sample IBC available to the Associate Administrator, or a des-

ignated representative, for testing in accordance with this subpart.

(k) *Coatings.* If an inner treatment or coating of an IBC is required for safety reasons, the manufacturer shall design the IBC so that the treatment or coating retains its protective properties even after withstanding the tests prescribed by this subpart.

(l) *Record retention.* (1) The person who certifies an IBC design type shall keep records of design qualification tests for each IBC design type and for each periodic design requalification as specified in this part. These records must be maintained at each location where the IBC is manufactured and at each location where design qualification and periodic design requalification testing is performed. These records must be maintained for as long as IBCs are manufactured in accordance with each qualified design type and for at least 2.5 years thereafter. These records must include the following information: name and address of test facility; name and address of the person certifying the IBC; a unique test report identification; date of test report; manufacturer of the IBC; description of the IBC design type (e.g., dimensions, materials, closures, thickness, representative service equipment, etc.); maximum IBC capacity; characteristics of test contents; test descriptions and results (including drop heights, hydrostatic pressures, tear propagation length, etc.). Each test report must be signed with the name of the person conducting the test, and name of the person responsible for testing.

(2) The person who certifies each IBC must make all records of design qualification tests and periodic design requalification tests available for inspection by a representative of the Department upon request.

[Amdt. 178-103, 59 FR 38074, July 26, 1994, as amended by Amdt. 178-108, 60 FR 40038, Aug. 4, 1995; 66 FR 45386, Aug. 28, 2001; 66 FR 33452, June 21, 2001; 68 FR 75758, Dec. 31, 2003; 73 FR 57008, Oct. 1, 2008]

#### **§ 178.802 Preparation of fiberboard IBCs for testing.**

(a) Fiberboard IBCs and composite IBCs with fiberboard outer packagings must be conditioned for at least 24 hours in an atmosphere maintained:

## § 178.803

## 49 CFR Ch. I (10–1–08 Edition)

(1) At 50 percent  $\pm 2$  percent relative humidity, and at a temperature of  $23^{\circ} \pm 2^{\circ} \text{C}$  ( $73^{\circ} \text{F} \pm 4^{\circ} \text{F}$ ); or

(2) At 65 percent  $\pm 2$  percent relative humidity, and at a temperature of  $20^{\circ} \pm 2^{\circ} \text{C}$  ( $68^{\circ} \text{F} \pm 4^{\circ} \text{F}$ ), or  $27^{\circ} \text{C} \pm 2^{\circ} \text{C}$  ( $81^{\circ} \text{F} \pm 4^{\circ} \text{F}$ ).

(b) Average values for temperature and humidity must fall within the limits in paragraph (a) of this section. Short-term fluctuations and measurement limitations may cause individual measurements to vary by up to  $\pm 5$  percent relative humidity without significant impairment of test reproducibility.

(c) For purposes of periodic design requalification only, fiberboard IBCs or composite IBCs with fiberboard outer packagings may be at ambient conditions.

[Amdt. 178–103, 59 FR 38074, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001]

### § 178.803 Testing and certification of IBCs.

Tests required for the certification of each IBC design type are specified in the following table. The letter X indicates that one IBC (except where noted) of each design type must be subjected to the tests in the order presented:

| Performance test    | IBC type       |                    |                |                  |                |                  |
|---------------------|----------------|--------------------|----------------|------------------|----------------|------------------|
|                     | Metal IBCs     | Rigid plastic IBCs | Composite IBCs | Fiber-board IBCs | Wooden IBCs    | Flexible IBCs    |
| Vibration .....     | <sup>6</sup> X | <sup>6</sup> X     | <sup>6</sup> X | <sup>6</sup> X   | <sup>6</sup> X | <sup>1,5</sup> X |
| Bottom lift .....   | <sup>2</sup> X | X                  | X              | X                | X              |                  |
| Top lift .....      | <sup>2</sup> X | <sup>2</sup> X     | <sup>2</sup> X |                  |                | <sup>2,5</sup> X |
| Stacking .....      | <sup>7</sup> X | <sup>7</sup> X     | <sup>7</sup> X | <sup>7</sup> X   | <sup>7</sup> X | <sup>5</sup> X   |
| Leakproofness ..... | <sup>3</sup> X | <sup>3</sup> X     | <sup>3</sup> X |                  |                |                  |
| Hydrostatic .....   | <sup>3</sup> X | <sup>3</sup> X     | <sup>3</sup> X |                  |                |                  |
| Drop .....          | <sup>4</sup> X | <sup>4</sup> X     | <sup>4</sup> X | <sup>4</sup> X   | <sup>4</sup> X | <sup>5</sup> X   |
| Topple .....        |                |                    |                |                  |                | <sup>5</sup> X   |
| Righting .....      |                |                    |                |                  |                | <sup>2,5</sup> X |
| Tear .....          |                |                    |                |                  |                | <sup>5</sup> X   |

<sup>1</sup> Flexible IBCs must be capable of withstanding the vibration test.

<sup>2</sup> This test must be performed only if IBCs are designed to be handled this way. For metal IBCs, at least one of the bottom lift or top lift tests must be performed.

<sup>3</sup> The leakproofness and hydrostatic pressure tests are required only for IBCs intended to contain liquids or intended to contain solids loaded or discharged under pressure.

<sup>4</sup> Another IBC of the same design type may be used for the drop test set forth in § 178.810 of this subchapter.

<sup>5</sup> Another different flexible IBC of the same design type may be used for each test.

<sup>6</sup> The vibration test may be performed in another order for IBCs manufactured and tested under provisions of an exemption before October 1, 1994 and for non-DOT specification portable tanks tested before October 1, 1994, intended for export.

<sup>7</sup> This test must be performed only if the IBC is designed to be stacked.

[Amdt. 178–108, 60 FR 40039, Aug. 4, 1995, as amended at 64 FR 51919, Sept. 27, 1999; 66 FR 45386, 45390, Aug. 28, 2001]

### § 178.810 Drop test.

(a) *General.* The drop test must be conducted for the qualification of all IBC design types and performed periodically as specified in § 178.801(e) of this subpart.

(b) *Special preparation for the drop test.*

(1) Metal, rigid plastic, and composite IBCs intended to contain solids must be filled to not less than 95 percent of their maximum capacity, or if intended to contain liquids, to not less than 98 percent of their maximum capacity. Pressure relief devices must be removed and their apertures plugged or rendered inoperative.

(2) Fiberboard and wooden IBCs must be filled with a solid material to not less than 95 percent of their maximum capacity; the contents must be evenly distributed.

(3) Flexible IBCs must be filled to the maximum permissible gross mass; the contents must be evenly distributed.

(4) Rigid plastic IBCs and composite IBCs with plastic inner receptacles must be conditioned for testing by reducing the temperature of the packaging and its contents to  $-18^{\circ} \text{C}$  ( $0^{\circ} \text{F}$ ) or lower. Test liquids must be kept in the liquid state, if necessary, by the addition of anti-freeze. Water/anti-freeze solutions with a minimum specific gravity of 0.95 for testing at  $-18$

°C (0 °F) or lower are considered acceptable test liquids, and may be considered equivalent to water for test purposes. IBCs conditioned in this way are not required to be conditioned in accordance with § 178.802.

(c) *Test method.* Samples of all IBC design types must be dropped onto a rigid, non-resilient, smooth, flat and horizontal surface. The point of impact must be the most vulnerable part of the base of the IBC being tested. Following the drop, the IBC must be restored to the upright position for observation.

(d) *Drop height.* (1) For all IBCs, drop heights are specified as follows:

- (i) Packing Group I: 1.8 m (5.9 feet).
- (ii) Packing Group II: 1.2 m (3.9 feet).
- (iii) Packing Group III: 0.8 m (2.6 feet).

(2) Drop tests are to be performed with the solid or liquid to be transported or with a non-hazardous material having essentially the same physical characteristics.

(3) The specific gravity and viscosity of a substituted non-hazardous material used in the drop test for liquids must be similar to the hazardous material intended for transportation. Water also may be used for the liquid drop test under the following conditions:

(i) Where the substances to be carried have a specific gravity not exceeding 1.2, the drop heights must be those specified in paragraph (d)(1) of this section for each IBC design type; and

(ii) Where the substances to be carried have a specific gravity exceeding 1.2, the drop heights must be as follows:

(A) Packing Group I:  $SG \times 1.5$  m (4.9 feet).

(B) Packing Group II:  $SG \times 1.0$  m (3.3 feet).

(C) Packing Group III:  $SG \times 0.67$  m (2.2 feet).

(e) *Criteria for passing the test.* For all IBC design types there may be no loss of contents. A slight discharge from a closure upon impact is not considered to be a failure of the IBC provided that no further leakage occurs. A slight discharge (e.g., from closures or stitch holes) upon impact is not considered a failure of the flexible IBC provided that

no further leakage occurs after the IBC has been raised clear of the ground.

[Amdt. 178-103, 59 FR 38074, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001; 69 FR 76186, Dec. 20, 2004; 71 FR 78635, Dec. 29, 2006]

#### § 178.811 Bottom lift test.

(a) *General.* The bottom lift test must be conducted for the qualification of all IBC design types designed to be lifted from the base.

(b) *Special preparation for the bottom lift test.* The IBC must be loaded to 1.25 times its maximum permissible gross mass, the load being evenly distributed.

(c) *Test method.* All IBC design types must be raised and lowered twice by a lift truck with the forks centrally positioned and spaced at three quarters of the dimension of the side of entry (unless the points of entry are fixed). The forks must penetrate to three quarters of the direction of entry. The test must be repeated from each possible direction of entry.

(d) *Criteria for passing the test.* For all IBC design types designed to be lifted from the base, there may be no permanent deformation which renders the IBC unsafe for transportation and no loss of contents.

[Amdt. 178-103, 59 FR 38074, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001]

#### § 178.812 Top lift test.

(a) *General.* The top lift test must be conducted for the qualification of all IBC design types designed to be lifted from the top or, for flexible IBCs, from the side.

(b) *Special preparation for the top lift test.* (1) Metal, rigid plastic, and composite IBC design types must be loaded to twice the maximum permissible gross mass with the load being evenly distributed.

(2) Flexible IBC design types must be filled to six times the maximum net mass, the load being evenly distributed.

(c) *Test method.* (1) A metal or flexible IBC must be lifted in the manner for which it is designed until clear of the floor and maintained in that position for a period of five minutes.

(2) Rigid plastic and composite IBC design types must be:

## § 178.813

## 49 CFR Ch. I (10–1–08 Edition)

(i) Lifted by each pair of diagonally opposite lifting devices, so that the hoisting forces are applied vertically, for a period of five minutes; and

(ii) Lifted by each pair of diagonally opposite lifting devices, so that the hoisting forces are applied towards the center at 45° to the vertical, for a period of five minutes.

(3) If not tested as indicated in paragraph (c)(1) of this section, a flexible IBC design type must be tested as follows:

(i) Fill the flexible IBC to 95% full with a material representative of the product to be shipped.

(ii) Suspend the flexible IBC by its lifting devices.

(iii) Apply a constant downward force through a specially designed platen. The platen will be a minimum of 60% and a maximum of 80% of the cross sectional surface area of the flexible IBC.

(iv) The combination of the mass of the filled flexible IBC and the force applied through the platen must be a minimum of six times the maximum net mass of the flexible IBC. The test must be conducted for a period of five minutes.

(v) Other equally effective methods of top lift testing and preparation may be used with approval of the Associate Administrator.

(d) *Criteria for passing the test.* For all IBC design types designed to be lifted from the top, there may be no permanent deformation which renders the IBC, including the base pallets when applicable, unsafe for transportation, and no loss of contents.

[Amdt. 178–103, 59 FR 38074, July 26, 1994, as amended at 66 FR 33452, June 21, 2001; 66 FR 45386, Aug. 28, 2001; 68 FR 45042, July 31, 2003]

### § 178.813 Leakproofness test.

(a) *General.* The leakproofness test must be conducted for the qualification of all IBC design types and on all production units intended to contain solids that are loaded or discharged under pressure or intended to contain liquids.

(b) *Special preparation for the leakproofness test.* Vented closures must either be replaced by similar non-vented closures or the vent must be sealed. For metal IBC design types, the initial test must be carried out before the fitting of any thermal insulation equip-

ment. The inner receptacle of a composite IBC may be tested without the outer packaging provided the test results are not affected.

(c) *Test method and pressure applied.* The leakproofness test must be carried out for a suitable length of time using air at a gauge pressure of not less than 20 kPa (2.9 psig). Leakproofness of IBC design types must be determined by coating the seams and joints with a heavy oil, a soap solution and water, or other methods suitable for the purpose of detecting leaks. Other methods, if at least equally effective, may be used in accordance with appendix B of this part, or if approved by the Associate Administrator, as provided in § 178.801(i)).

(d) *Criterion for passing the test.* For all IBC design types intended to contain solids that are loaded or discharged under pressure or intended to contain liquids, there may be no leakage of air from the IBC.

[Amdt. 178–103, 59 FR 38074, July 26, 1994, as amended at 64 FR 10782, Mar. 5, 1999; 66 FR 45185, 45386, Aug. 28, 2001]

### § 178.814 Hydrostatic pressure test.

(a) *General.* The hydrostatic pressure test must be conducted for the qualification of all metal, rigid plastic, and composite IBC design types intended to contain solids that are loaded or discharged under pressure or intended to contain liquids.

(b) *Special preparation for the hydrostatic pressure test.* For metal IBCs, the test must be carried out before the fitting of any thermal insulation equipment. For all IBCs, pressure relief devices and vented closures must be removed and their apertures plugged or rendered inoperative.

(c) *Test method.* Hydrostatic gauge pressure must be measured at the top of the IBC. The test must be carried out for a period of at least 10 minutes applying a hydrostatic gauge pressure not less than that indicated in paragraph (d) of this section. The IBCs may not be mechanically restrained during the test.

(d) *Hydrostatic gauge pressure applied.* (1) For metal IBC design types, 31A, 31B, 31N: 65 kPa gauge pressure (9.4 psig).

(2) For metal IBC design types 21A, 21B, 21N, 31A, 31B, 31N: 200 kPa (29 psig). For metal IBC design types 31A, 31B and 31N, the tests in paragraphs (d)(1) and (d)(2) of this section must be conducted consecutively.

(3) For metal IBCs design types 21A, 21B, and 21N, for Packing Group I solids: 250 kPa (36 psig) gauge pressure.

(4) For rigid plastic IBC design types 21H1 and 21H2 and composite IBC design types 21HZ1 and 21HZ2: 75 kPa (11 psig).

(5) For rigid plastic IBC design types 31H1 and 31H2 and composite IBC design types 31HZ1 and 31HZ2: whichever is the greater of:

(i) The pressure determined by any one of the following methods:

(A) The gauge pressure (pressure in the IBC above ambient atmospheric pressure) measured in the IBC at 55 °C (131 °F) multiplied by a safety factor of 1.5. This pressure must be determined on the basis of the IBC being filled and closed to no more than 98 percent capacity at 15 °C (60 °F);

(B) If absolute pressure (vapor pressure of the hazardous material plus atmospheric pressure) is used, 1.5 multiplied by the vapor pressure of the hazardous material at 55 °C (131 °F) minus 100 kPa (14.5 psi). If this method is chosen, the hydrostatic test pressure applied must be at least 100 kPa gauge pressure (14.5 psig); or

(C) If absolute pressure (vapor pressure of the hazardous material plus atmospheric pressure) is used, 1.75 multiplied by the vapor pressure of the hazardous material at 50 °C (122 °F) minus 100 kPa (14.5 psi). If this method is chosen, the hydrostatic test pressure applied must be at least 100 kPa gauge pressure (14.5 psig); or

(ii) Twice the greater of: (A) The static pressure of the hazardous material on the bottom of the IBC filled to 98 percent capacity; or

(B) The static pressure of water on the bottom of the IBC filled to 98 percent capacity.

(e) *Criteria for passing the test(s).* (1) For metal IBCs, subjected to the 65 kPa (9.4 psig) test pressure specified in paragraph (d)(1) of this section, there may be no leakage or permanent deformation that would make the IBC unsafe for transportation.

(2) For metal IBCs intended to contain liquids, when subjected to the 200 kPa (29 psig) and the 250 kPa (36 psig) test pressures specified in paragraphs (d)(2) and (d)(3) of this section, respectively, there may be no leakage.

(3) For rigid plastic IBC types 21H1, 21H2, 31H1, and 31H2, and composite IBC types 21HZ1, 21HZ2, 31HZ1, and 31HZ2, there may be no leakage and no permanent deformation which renders the IBC unsafe for transportation.

[Amdt. 178-103, 59 FR 38074, July 26, 1994, as amended at 66 FR 45185, 45386, Aug. 28, 2001]

#### § 178.815 Stacking test.

(a) *General.* The stacking test must be conducted for the qualification of all IBC design types intended to be stacked.

(b) *Special preparation for the stacking test.* (1) All IBCs except flexible IBC design types must be loaded to their maximum permissible gross mass.

(2) The flexible IBC must be filled to not less than 95 percent of its capacity and to its maximum net mass, with the load being evenly distributed.

(c) *Test method.* (1) All IBCs must be placed on their base on level, hard ground and subjected to a uniformly distributed superimposed test load for a period of at least five minutes (see paragraph (d) of this section).

(2) Fiberboard, wooden, and composite IBCs with outer packagings constructed of other than plastic materials must be subjected to the test for 24 hours.

(3) Rigid plastic IBC types and composite IBC types with plastic outer packagings (11HH1, 11HH2, 21HH1, 21HH2, 31HH1 and 31HH2) which bear the stacking load must be subjected to the test for 28 days at 40 °C (104 °F).

(4) For all IBCs, the load must be applied by one of the following methods:

(i) One or more IBCs of the same type loaded to their maximum permissible gross mass and stacked on the test IBC;

(ii) The calculated superimposed test load weight loaded on either a flat plate or a reproduction of the base of the IBC, which is stacked on the test IBC; or

(iii) The packaging may be tested using a dynamic compression testing machine. The test must be conducted

## § 178.816

at room temperature on an empty, unsealed packaging. The test sample must be centered on the bottom platen of the testing machine. The top platen must be lowered until it comes in contact with the test sample. Compression must be applied end to end. The speed of the compression tester must be one-half inch plus or minus one-fourth inch per minute. An initial preload of 50 pounds must be applied to ensure a definite contact between the test sample and the platens. The distance between the platens at this time must be recorded as zero deformation. The force "A" to then be applied must be calculated using the applicable formula:

Liquids:  $A = (n - 1) [w + (s \times v \times 8.3 \times .98)] \times 1.5;$   
or

Solids:  $A = (n - 1) [w + (s \times v \times 8.3 \times .95)] \times 1.5$

Where:

A = applied load in pounds.

n = minimum number of containers that, when stacked, reach a height of 3 m.

s = specific gravity of lading.

w = maximum weight of one empty container in pounds.

v = actual capacity of container (rated capacity + outage) in gallons.

And:

8.3 corresponds to the weight in pounds of 1.0 gallon of water.

1.5 is a compensation factor that converts the static load of the stacking test into a load suitable for dynamic compression testing.

(d) *Calculation of superimposed test load.* For all IBCs, the load to be placed on the IBC must be 1.8 times the combined maximum permissible gross mass of the number of similar IBCs that may be stacked on top of the IBC during transportation.

(e) *Criteria for passing the test.* (1) For metal, rigid plastic, and composite IBCs there may be no permanent deformation which renders the IBC unsafe for transportation and no loss of contents.

(2) For fiberboard and wooden IBCs there may be no loss of contents and no permanent deformation which renders the whole IBC, including the base pallet, unsafe for transportation.

(3) For flexible IBCs, there may be no deterioration which renders the IBC

## 49 CFR Ch. I (10–1–08 Edition)

unsafe for transportation and no loss of contents.

[Amdt. 178–103, 59 FR 38074, July 26, 1994, as amended by Amdt. 178–119, 62 FR 24743, May 6, 1997; 65 FR 50462, 50463, Aug. 18, 2000; 66 FR 45386, Aug. 28, 2001]

### § 178.816 Topple test.

(a) *General.* The topple test must be conducted for the qualification of all flexible IBC design types.

(b) *Special preparation for the topple test.* The flexible IBC must be filled to not less than 95 percent of its capacity and to its maximum net mass, with the load being evenly distributed.

(c) *Test method.* A flexible IBC must be toppled onto any part of its top upon a rigid, non-resilient, smooth, flat, and horizontal surface.

(d) *Topple height.* For all flexible IBCs, the topple height is specified as follows:

(1) Packing Group I: 1.8 m (5.9 feet).

(2) Packing Group II: 1.2 m (3.9 feet).

(3) Packing Group III: 0.8 m (2.6 feet).

(e) *Criteria for passing the test.* For all flexible IBCs, there may be no loss of contents. A slight discharge (e.g., from closures or stitch holes) upon impact is not considered to be a failure, provided no further leakage occurs.

[Amdt. 178–103, 59 FR 38074, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001]

### § 178.817 Righting test.

(a) *General.* The righting test must be conducted for the qualification of all flexible IBCs designed to be lifted from the top or side.

(b) *Special preparation for the righting test.* The flexible IBC must be filled to not less than 95 percent of its capacity and to its maximum net mass, with the load being evenly distributed.

(c) *Test method.* The flexible IBC, lying on its side, must be lifted at a speed of at least 0.1 m/second (0.33 ft/s) to an upright position, clear of the floor, by one lifting device, or by two lifting devices when four are provided.

(d) *Criterion for passing the test.* For all flexible IBCs, there may be no damage to the IBC or its lifting devices which renders the IBC unsafe for transportation or handling.

[Amdt. 178–103, 59 FR 38074, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001]

**§ 178.818 Tear test.**

(a) *General.* The tear test must be conducted for the qualification of all flexible IBC design types.

(b) *Special preparation for the tear test.* The flexible IBC must be filled to not less than 95 percent of its capacity and to its maximum net mass, the load being evenly distributed.

(c) *Test method.* Once the IBC is placed on the ground, a 100-mm (4-inch) knife score, completely penetrating the wall of a wide face, is made at a 45° angle to the principal axis of the IBC, halfway between the bottom surface and the top level of the contents. The IBC must then be subjected to a uniformly distributed superimposed load equivalent to twice the maximum net mass. The load must be applied for at least five minutes. An IBC which is designed to be lifted from the top or the side must, after removal of the superimposed load, be lifted clear of the floor and maintained in that position for a period of five minutes.

(d) *Criterion for passing the test.* The IBC passes the tear test if the cut does not propagate more than 25 percent of its original length.

[Amdt. 178-103, 59 FR 38074, July 26, 1994, as amended at 66 FR 45386, Aug. 28, 2001]

**§ 178.819 Vibration test.**

(a) *General.* The vibration test must be conducted for the qualification of all rigid IBC design types. Flexible IBC design types must be capable of withstanding the vibration test.

(b) *Test method.* (1) A sample IBC, selected at random, must be filled and closed as for shipment.

(2) The sample IBC must be placed on a vibrating platform that has a vertical double-amplitude (peak-to-peak displacement) of one inch. The IBC must be constrained horizontally to prevent it from falling off the platform, but must be left free to move vertically and bounce.

(3) The test must be performed for one hour at a frequency that causes the package to be raised from the vibrating platform to such a degree that a piece of material of approximately 1.6-mm (0.063-inch) thickness (such as steel strapping or paperboard) can be passed between the bottom of the IBC and the platform. Other methods at least equally effective may be used (see § 178.801(i)).

(c) *Criteria for passing the test.* An IBC passes the vibration test if there is no rupture or leakage.

[Amdt. 178-103, 59 FR 38074, July 26, 1994, as amended by Amdt. 178-108, 60 FR 40038, Aug. 4, 1995; Amdt. 178-110, 60 FR 49111, Sept. 21, 1995; 66 FR 45386, Aug. 28, 2001]

## APPENDIX A TO PART 178—SPECIFICATIONS FOR STEEL

TABLE 1

[Open-hearth, basic oxygen, or electric steel of uniform quality. The following chemical composition limits are based on ladle analysis.]

| Designation                     | Chemical composition, percent-ladle analysis |                        |                          |
|---------------------------------|----------------------------------------------|------------------------|--------------------------|
|                                 | Grade 1 <sup>1</sup>                         | Grade 2 <sup>1,2</sup> | Grade 3 <sup>2,4,5</sup> |
| Carbon .....                    | 0.10/0.20 .....                              | 0.24 maximum .....     | 0.22 maximum.            |
| Manganese .....                 | 1.10/1.60 .....                              | 0.50/1.00 .....        | 1.25 maximum.            |
| Phosphorus, maximum .....       | 0.04 .....                                   | 0.04 .....             | 0.045. <sup>6</sup>      |
| Sulfur, maximum .....           | 0.05 .....                                   | 0.05 .....             | 0.05.                    |
| Silicon .....                   | 0.15/0.30 .....                              | 0.30 maximum .....     |                          |
| Copper, maximum .....           | 0.40 .....                                   |                        |                          |
| Columbium .....                 |                                              | 0.01/0.04 .....        |                          |
| Heat treatment authorized ..... | ( <sup>3</sup> ) .....                       | ( <sup>3</sup> ) ..... | ( <sup>3</sup> ).        |
| Maximum stress (p.s.i.) .....   | 35,000 .....                                 | 35,000 .....           | 35,000.                  |

<sup>1</sup>Addition of other elements to obtain alloying effect is not authorized.

<sup>2</sup>Ferritic grain size 6 or finer according to ASTM E 112-96 (IBR, see § 171.7 of this subchapter).

<sup>3</sup>Any suitable heat treatment in excess of 1,100 °F., except that liquid quenching is not permitted.

<sup>4</sup>Other alloying elements may be added and shall be reported.

<sup>5</sup>For compositions with a maximum carbon content of 0.15 percent of ladle analysis, the maximum limit for manganese on ladle analysis may be 1.40 percent.

<sup>6</sup>Rephosphorized Grade 3 steels containing no more than 0.15 percent phosphorus are permitted if carbon content does not exceed 0.15 percent and manganese does not exceed 1 percent.



## CHECK ANALYSIS TOLERANCES

[A heat of steel made under any of the above grades, the ladle analysis of which is slightly out of the specified range is acceptable if the check analysis is within the following variations:]

| Element                       | Limit or maximum specified (percent) | Tolerance (percent) over the maximum limit or under the minimum limit |                    |
|-------------------------------|--------------------------------------|-----------------------------------------------------------------------|--------------------|
|                               |                                      | Under minimum limit                                                   | Over maximum limit |
| Carbon .....                  | To 0.15 inclusive .....              | 0.02                                                                  | 0.03               |
|                               | Over 0.15 to 0.40 inclusive .....    | 0.03                                                                  | 0.04               |
| Manganese .....               | To 0.60 inclusive .....              | 0.03                                                                  | 0.03               |
|                               | Over 0.60 to 1.15 inclusive .....    | 0.04                                                                  | 0.04               |
|                               | Over 1.15 to 2.50 inclusive .....    | 0.05                                                                  | 0.05               |
| Phosphorus <sup>7</sup> ..... | All ranges .....                     |                                                                       | 0.01               |
| Sulfur .....                  | All ranges .....                     |                                                                       | 0.01               |
| Silicon .....                 | To 0.30 inclusive .....              | 0.02                                                                  | 0.03               |
|                               | Over 0.30 to 1.00 inclusive .....    | 0.05                                                                  | 0.05               |
| Copper .....                  | To 1.00 inclusive .....              | 0.03                                                                  | 0.03               |
|                               | Over 1.00 to 2.00 inclusive .....    | 0.05                                                                  | 0.05               |
| Nickel .....                  | To 1.00 inclusive .....              | 0.03                                                                  | 0.03               |
|                               | Over 1.00 to 2.00 inclusive .....    | 0.05                                                                  | 0.05               |
| Chromium .....                | To 0.90 inclusive .....              | 0.03                                                                  | 0.03               |
|                               | Over 0.90 to 2.10 inclusive .....    | 0.05                                                                  | 0.05               |
| Molybdenum .....              | To 0.20 inclusive .....              | 0.01                                                                  | 0.01               |
|                               | Over 0.20 to 0.40 inclusive .....    | 0.02                                                                  | 0.02               |
| Zirconium .....               | All ranges .....                     | 0.01                                                                  | 0.05               |
| Columbium .....               | To 0.04 inclusive .....              | 0.005                                                                 | 0.01               |
| Aluminum .....                | Over 0.10 to 0.20 inclusive .....    | 0.04                                                                  | 0.04               |
|                               | Over 0.20 to 0.30 inclusive .....    | 0.05                                                                  | 0.05               |

<sup>7</sup> Rephosphorized steels not subject to check analysis for phosphorus.

[Amdt. 178–3, 34 FR 12283, July 25, 1969; 34 FR 12593, Aug. 1, 1969, as amended by Amdt. 178–64, 45 FR 81573, Dec. 11, 1980; Amdt. 178–97, 55 FR 52728, Dec. 21, 1990; 68 FR 75758, Dec. 31, 2003]

## APPENDIX B TO PART 178—ALTERNATIVE LEAKPROOFNESS TEST METHODS

In addition to the method prescribed in §178.604 of this subchapter, the following leakproofness test methods are authorized:

(1) *Helium test.* The packaging must be filled with at least 1 L inert helium gas, air tight closed, and placed in a testing chamber. The testing chamber must be evacuated down to a pressure of 5 kPa which equals an over-pressure inside the packaging of 95 kPa. The air in the testing chamber must be analyzed for traces of helium gas by means of a mass spectrograph. The test must be conducted for a period of time sufficient to evacuate the chamber and to determine if there is leakage into or out of the packaging. If helium gas is detected, the leaking packaging must be automatically separated from non-leaking drums and the leaking area determined according to the method prescribed in §178.604(d) of this subchapter. A packaging passes the test if there is no leakage of helium.

(2) *Pressure differential test.* The packaging shall be restrained while either pressure or a vacuum is applied internally. The packaging must be pressurized to the pressure required by §178.604(e) of this subchapter for the appropriate packing group. The method of restraint must not affect the results of the

test. The test must be conducted for a period of time sufficient to appropriately pressurize or evacuate the interior of the packaging and to determine if there is leakage into or out of the packaging. A packaging passes the pressure differential test if there is no change in measured internal pressure.

(3) *Solution over seams.* The packaging must be restrained while an internal air pressure is applied; the method of restraint may not affect the results of the test. The exterior surface of all seams and welds must be coated with a solution of soap suds or a water and oil mixture. The test must be conducted for a period of time sufficient to pressurize the interior of the packaging to the specified air pressure and to determine if there is leakage of air from the packaging. A packaging passes the test if there is no leakage of air from the packaging.

(4) *Solution over partial seams test.* For other than design qualification testing, the following test may be used for metal drums: The packaging must be restrained while an internal air pressure of 48 kPa (7.0 psig) is applied; the method of restraint may not affect the results of the test. The packaging must be coated with a soap solution over the entire side seam and a distance of not less than eight inches on each side of the side seam along the chime seam(s). The test must be conducted for a period of time sufficient

to pressurize the interior of the packaging to the specified air pressure and to determine if there is leakage of air from the packaging. A packaging passes the test if there is no leakage of air from the packaging. Chime cuts must be made on the initial drum at the beginning of each production run and on the initial drum after any adjustment to the chime seamer. Chime cuts must be maintained on file in date order for not less than six months and be made available to a representative of the Department of Transportation on request.

[Amdt. 178-97, 55 FR 52728, Dec. 21, 1990, as amended at 56 FR 66287, Dec. 20, 1991; 57 FR 45466, Oct. 1, 1992]

#### APPENDIX C TO PART 178—NOMINAL AND MINIMUM THICKNESSES OF STEEL DRUMS AND JERRICANS

For each listed packaging capacity, the following table compares the ISO 3574 (IBR, see §171.7 of this subchapter) nominal thickness with the corresponding ISO 3574 minimum thickness.

| Maximum capacity (L) | ISO nominal (mm) | Corresponding ISO minimum (mm) |
|----------------------|------------------|--------------------------------|
| 20 .....             | 0.7              | 0.63                           |
| 30 .....             | 0.8              | 0.73                           |
| 40 .....             | 0.8              | 0.73                           |
| 60 .....             | 1.0              | 0.92                           |
| 120 .....            | 1.0              | 0.92                           |
| 220 .....            | 1.0              | 0.92                           |
| 450 .....            | 1.9              | 1.77                           |

[Amdt. 178-106, 59 FR 67522, Dec. 29, 1994, as amended at 68 FR 75758, Dec. 31, 2003]

#### APPENDIX D TO PART 178—THERMAL RESISTANCE TEST

1. *Scope.* This test method evaluates the thermal resistance capabilities of a compressed oxygen generator and the outer packaging for a cylinder of compressed oxygen or other oxidizing gas and an oxygen generator. When exposed to a temperature of 205 °C (400 °F) for a period of not less than three hours, the outer surface of the cylinder may not exceed a temperature of 93 °C (199 °F) and the oxygen generator must not actuate.

##### 2. *Apparatus.*

2.1 *Test Oven.* The oven must be large enough in size to fully house the test outer package without clearance problems. The test oven must be capable of maintaining a minimum steady state temperature of 205 °C (400 °F).

2.2 *Thermocouples.* At least three thermocouples must be used to monitor the temperature inside the oven and an addi-

tional three thermocouples must be used to monitor the temperature of the cylinder. The thermocouples must be 1/16 inch, ceramic packed, metal sheathed, type K (Chromel-Alumel), grounded junction with a nominal 30 American wire gauge (AWG) size conductor. The thermocouples measuring the temperature inside the oven must be placed at varying heights to ensure even temperature and proper heat-soak conditions. For the thermocouples measuring the temperature of the cylinder: (1) Two of them must be placed on the outer cylinder side wall at approximately 2 inches (5 cm) from the top and bottom shoulders of the cylinder; and (2) one must be placed on the cylinder valve body near the pressure relief device. Alternatively, the thermocouples may be replaced with other devices such as a remote temperature sensor, metal fuse on the valve, or coated wax, provided the device is tested and the test report is retained for verification. Under this alternative, it is permissible to record the highest temperature to which the cylinder is subjected instead of temperature measurements in intervals of not more than five (5) minutes.

2.3 *Instrumentation.* A calibrated recording device or a computerized data acquisition system with an appropriate range should be provided to measure and record the outputs of the thermocouples.

##### 3. *Test Specimen.*

3.1 *Specimen Configuration.* Each outer package material type and design must be tested, including any features such as handles, latches, fastening systems, etc., that may compromise the ability of the outer package to provide thermal protection.

3.2 *Test Specimen Mounting.* The tested outer package must be supported at the four corners using fire brick or other suitable means. The bottom surface of the outer package must be exposed to allow exposure to heat.

##### 4. *Preparation for Testing.*

4.1 It is recommended that the cylinder be closed at ambient temperature and configured as when filled with a valve and pressure relief device. The oxygen generator must be filled with an oxidizing agent and may be tested with or without packaging.

4.2 Place the package or generator onto supporting bricks or a stand inside the test oven in such a manner to ensure even temperature flow.

##### 5. *Test Procedure.*

5.1 Close oven door and check for proper reading on thermocouples.

5.2 Raise the temperature of the oven to a minimum temperature of 205 °C ± 2 °C (400 °F ± 5 °F). Maintain a minimum oven temperature of 205 °C ± 2 °C (400 °F ± 5 °F) for at least three hours. Exposure time begins when the oven steady state temperature reaches a minimum of 205 °C ± 2 °C (400 °F ± 5 °F).

5.3 At the conclusion of the three-hour period, the outer package may be removed from the oven and allowed to cool naturally.

6. *Recordkeeping.*

6.1 Record a complete description of the material being tested, including the manufacturer, size of cylinder, etc.

6.2 Record any observations regarding the behavior of the test specimen during exposure, such as smoke production, delamination, resin ignition, and time of occurrence of each event.

6.3 Record the temperature and time history of the cylinder temperature during the entire test for each thermocouple location. Temperature measurements must be recorded at intervals of not more than five (5) minutes. Record the maximum temperatures achieved at all three thermocouple locations and the corresponding time.

7. *Requirements.*

7.1 For a cylinder, the outer package must provide adequate protection such that the outer surface of the cylinder and valve does not exceed a temperature of 93 °C (199 °F) at any of the three points where the thermocouples are located.

7.2 For an oxygen generator, the generator must not actuate.

[72 FR 4457, Jan. 31, 2008, as amended at 72 FR 55099, Sept. 28, 2007]

APPENDIX E TO PART 178—FLAME  
PENETRATION RESISTANCE TEST

(a) *Criteria for Acceptance.* (1) At least three specimens of the outer packaging materials must be tested;

(2) Each test must be conducted on a flat 16 inch x 24 inch test specimen mounted in the horizontal ceiling position of the test apparatus to represent the outer packaging design;

(3) Testing must be conducted on all design features (latches, seams, hinges, etc.) affecting the ability of the outer packaging to safely prevent the passage of fire in the horizontal ceiling position; and

(4) There must be no flame penetration of any specimen within 5 minutes after application of the flame source and the maximum allowable temperature at a point 4 inches above the test specimen, centered over the burner cone, must not exceed 205 °C (400 °F).

(b) *Summary of Method.* This method provides a laboratory test procedure for measuring the capability of cargo compartment lining materials to resist flame penetration with a 2 gallon per hour (GPH) #2 Grade kerosene or equivalent burner fire source. Ceiling and sidewall liner panels may be tested individually provided a baffle is used to simulate the missing panel. Any specimen that passes the test as a ceiling liner panel may be used as a sidewall liner panel.

(c) *Test Specimens.* (1) The specimen to be tested must measure 16 ±½ inches (406 ±3 mm) by 24±½ inches (610 ±3 mm).

(2) The specimens must be conditioned at 70 °F. ±5 °F. (21 °C. ±2 °C.) and 55% ±5% humidity for at least 24 hours before testing.

(d) *Test Apparatus.* The arrangement of the test apparatus must include the components described in this section. Minor details of the apparatus may vary, depending on the model of the burner used.

(1) *Specimen Mounting Stand.* The mounting stand for the test specimens consists of steel angles.

(2) *Test Burner.* The burner to be used in testing must—

(i) Be a modified gun type.

(ii) Use a suitable nozzle and maintain fuel pressure to yield a 2 GPH fuel flow. For example: An 80 degree nozzle nominally rated at 2.25 GPH and operated at 85 pounds per square inch (PSI) gauge to deliver 2.03 GPH.

(iii) Have a 12 inch (305 mm) burner extension installed at the end of the draft tube with an opening 6 inches (152 mm) high and 11 inches (280 mm) wide.

(iv) Have a burner fuel pressure regulator that is adjusted to deliver a nominal 2.0 GPH of #2 Grade kerosene or equivalent.

Burner models which have been used successfully in testing are the Lenox Model OB-32, Carlin Model 200 CRD and Park Model DPL.

(3) *Calorimeter.* (i) The calorimeter to be used in testing must be a total heat flux Foil Type Gardon Gage of an appropriate range (approximately 0 to 15.0 British thermal unit (BTU) per ft.<sup>2</sup> sec., 0–17.0 watts/cm<sup>2</sup>). The calorimeter must be mounted in a 6 inch by 12 inch (152 by 305 mm) by ¾ inch (19 mm) thick insulating block which is attached to a steel angle bracket for placement in the test stand during burner calibration as shown in Figure 2 of this part of this appendix.

(ii) The insulating block must be monitored for deterioration and the mounting shimmed as necessary to ensure that the calorimeter face is parallel to the exit plane of the test burner cone.

(4) *Thermocouples.* The seven thermocouples to be used for testing must be ⅛ inch ceramic sheathed, type K, grounded thermocouples with a nominal 30 American wire gage (AWG) size conductor. The seven thermocouples must be attached to a steel angle bracket to form a thermocouple rake for placement in the test stand during burner calibration.

(5) *Apparatus Arrangement.* The test burner must be mounted on a suitable stand to position the exit of the burner cone a distance of 8 inches from the ceiling liner panel and 2 inches from the sidewall liner panel. The burner stand should have the capability of allowing the burner to be swung away from the test specimen during warm-up periods.

(6) *Instrumentation.* A recording potentiometer or other suitable instrument with an appropriate range must be used to measure and record the outputs of the calorimeter and the thermocouples.

(7) *Timing Device.* A stopwatch or other device must be used to measure the time of flame application and the time of flame penetration, if it occurs.

(e) *Preparation of Apparatus.* Before calibration, all equipment must be turned on and allowed to stabilize, and the burner fuel flow must be adjusted as specified in paragraph (d)(2).

(f) *Calibration.* To ensure the proper thermal output of the burner the following test must be made:

(1) Remove the burner extension from the end of the draft tube. Turn on the blower portion of the burner without turning the fuel or igniters on. Measure the air velocity using a hot wire anemometer in the center of the draft tube across the face of the opening. Adjust the damper such that the air velocity is in the range of 1550 to 1800 ft./min. If tabs are being used at the exit of the draft tube, they must be removed prior to this measurement. Reinstall the draft tube extension cone.

(2) Place the calorimeter on the test stand as shown in Figure 2 at a distance of 8 inches (203 mm) from the exit of the burner cone to simulate the position of the horizontal test specimen.

(3) Turn on the burner, allow it to run for 2 minutes for warm-up, and adjust the damper to produce a calorimeter reading of  $8.0 \pm 0.5$  BTU per ft.<sup>2</sup> sec. ( $9.1 \pm 0.6$  Watts/cm<sup>2</sup>).

(4) Replace the calorimeter with the thermocouple rake.

(5) Turn on the burner and ensure that each of the seven thermocouples reads 1700 °F.  $\pm 100$  °F. (927 °C.  $\pm 38$  °C.) to ensure steady state conditions have been achieved. If the temperature is out of this range, repeat steps 2 through 5 until proper readings are obtained.

(6) Turn off the burner and remove the thermocouple rake.

(7) Repeat (1) to ensure that the burner is in the correct range.

(g) *Test Procedure.* (1) Mount a thermocouple of the same type as that used for calibration at a distance of 4 inches (102 mm) above the horizontal (ceiling) test specimen. The thermocouple should be centered over the burner cone.

(2) Mount the test specimen on the test stand shown in Figure 1 in either the horizontal or vertical position. Mount the insulating material in the other position.

(3) Position the burner so that flames will not impinge on the specimen, turn the burner on, and allow it to run for 2 minutes. Rotate the burner to apply the flame to the specimen and simultaneously start the timing device.

(4) Expose the test specimen to the flame for 5 minutes and then turn off the burner. The test may be terminated earlier if flame penetration is observed.

(5) When testing ceiling liner panels, record the peak temperature measured 4 inches above the sample.

(6) Record the time at which flame penetration occurs if applicable.

(h) *Test Report.* The test report must include the following:

(1) A complete description of the materials tested including type, manufacturer, thickness, and other appropriate data.

(2) Observations of the behavior of the test specimens during flame exposure such as delamination, resin ignition, smoke, etc., including the time of such occurrence.

(3) The time at which flame penetration occurs, if applicable, for each of the three specimens tested.

[72FR55099, Sept. 28, 2007]

## PART 179—SPECIFICATIONS FOR TANK CARS

### Subpart A—Introduction, Approvals and Reports

#### Sec.

- 179.1 General.
- 179.2 Definitions and abbreviations.
- 179.3 Procedure for securing approval.
- 179.4 Changes in specifications for tank cars.
- 179.5 Certificate of construction.
- 179.6 Repairs and alterations.
- 179.7 Quality assurance program.

### Subpart B—General Design Requirements

- 179.10 Tank mounting.
- 179.11 Welding certification.
- 179.12 Interior heater systems.
- 179.13 Tank car capacity and gross weight limitation.
- 179.14 Coupler vertical restraint system.
- 179.15 Pressure relief devices.
- 179.16 Tank-head puncture-resistance systems.
- 179.18 Thermal protection systems.
- 179.20 Service equipment; protection systems.
- 179.22 Marking.

### Subpart C—Specifications for Pressure Tank Car Tanks (Classes DOT-105, 109, 112, 114, and 120)

- 179.100 General specifications applicable to pressure tank car tanks.
- 179.100-1 Tanks built under these specifications shall comply with the requirements of §§ 179.100, 179.101 and when applicable, §§ 179.102 and 179.103.
- 179.100-3 Type.

**Pt. 179**

**49 CFR Ch. I (10–1–08 Edition)**

- 179.100–4 Insulation.
- 179.100–6 Thickness of plates.
- 179.100–7 Materials.
- 179.100–8 Tank heads.
- 179.100–9 Welding.
- 179.100–10 Postweld heat treatment.
- 179.100–12 Manway nozzle, cover and protective housing.
- 179.100–13 Venting, loading and unloading valves, measuring and sampling devices.
- 179.100–14 Bottom outlets.
- 179.100–16 Attachments.
- 179.100–17 Closures for openings.
- 179.100–18 Tests of tanks.
- 179.100–19 Tests of safety relief valves.
- 179.100–20 Stamping.
- 179.101 Individual specification requirements applicable to pressure tank car tanks.
- 179.101–1 Individual specification requirements.
- 179.102 Special commodity requirements for pressure tank car tanks.
- 179.102–1 Carbon dioxide, refrigerated liquid.
- 179.102–2 Chlorine.
- 179.102–4 Vinyl fluoride, stabilized.
- 179.102–17 Hydrogen chloride, refrigerated liquid.
- 179.103 Special requirements for class 114A \* \* \* tank car tanks.
- 179.103–1 Type.
- 179.103–2 Manway cover.
- 179.103–3 Venting, loading and unloading valves, measuring and sampling devices.
- 179.103–4 Safety relief devices and pressure regulators.
- 179.103–5 Bottom outlets.

**Subpart D—Specifications for Nonpressure Tank Car Tanks (Classes DOT-111AW and 115AW)**

- 179.200 General specifications applicable to non-pressure tank car tanks (Class DOT 111).
- 179.200–1 Tank built under these specifications must meet the requirements of §§ 179.200, and 179.201.
- 179.200–3 Type.
- 179.200–4 Insulation.
- 179.200–6 Thickness of plates.
- 179.200–7 Materials.
- 179.200–8 Tank heads.
- 179.200–9 Compartment tanks.
- 179.200–10 Welding.
- 179.200–11 Postweld heat treatment.
- 179.200–13 Manway ring or flange, pressure relief device flange, bottom outlet nozzle flange, bottom washout nozzle flange and other attachments and openings.
- 179.200–14 Expansion capacity.
- 179.200–15 Closures for manways.
- 179.200–16 Gauging devices, top loading and unloading devices, venting and air inlet devices.
- 179.200–17 Bottom outlets.

- 179.200–19 Reinforcements, when used, and appurtenances not otherwise specified.
- 179.200–21 Closures for openings.
- 179.200–22 Test of tanks.
- 179.200–23 Tests of pressure relief valves.
- 179.200–24 Stamping.
- 179.201 Individual specification requirements applicable to non-pressure tank car tanks.
- 179.201–1 Individual specification requirements.
- 179.201–2 [Reserved]
- 179.201–3 Lined tanks.
- 179.201–4 Material.
- 179.201–5 Postweld heat treatment and corrosion resistance.
- 179.201–6 Manways and manway closures.
- 179.201–8 Sampling device and thermometer well.
- 179.201–9 Gauging device.
- 179.201–10 Water capacity marking.
- 179.201–11 Insulation.
- 179.202–179.202–22 [Reserved]
- 179.220 General specifications applicable to nonpressure tank car tanks consisting of an inner container supported within an outer shell (class DOT-115).
- 179.220–1 Tanks built under these specifications must meet the requirements of §§ 179.220 and 179.221.
- 179.220–3 Type.
- 179.220–4 Insulation.
- 179.220–6 Thickness of plates.
- 179.220–7 Materials.
- 179.220–8 Tank heads.
- 179.220–9 Compartment tanks.
- 179.220–10 Welding.
- 179.220–11 Postweld heat treatment.
- 179.220–13 Inner container manway nozzle and cover.
- 179.220–14 Openings in the tanks.
- 179.220–15 Support system for inner container.
- 179.220–16 Expansion capacity.
- 179.220–17 Gauging devices, top loading and unloading devices, venting and air inlet devices.
- 179.220–18 Bottom outlets.
- 179.220–20 Reinforcements, when used, and appurtenances not otherwise specified.
- 179.220–22 Closure for openings.
- 179.220–23 Test of tanks.
- 179.220–24 Tests of pressure relief valves.
- 179.220–25 Stamping.
- 179.220–26 Stenciling.
- 179.221 Individual specification requirements applicable to tank car tanks consisting of an inner container supported within an outer shell.

179.221-1 Individual specification requirements.

**Subpart E—Specifications for Multi-Unit Tank Car Tanks (Classes DOT-106A and 110AW)**

- 179.300 General specifications applicable to multi-unit tank car tanks designed to be removed from car structure for filling and emptying (Classes DOT-106A and 110AW).
- 179.300-1 Tanks built under these specifications shall meet the requirements of §§ 179.300 and 179.301.
- 179.300-3 Type and general requirements.
- 179.300-4 Insulation.
- 179.300-6 Thickness of plates.
- 179.300-7 Materials.
- 179.300-8 Tank heads.
- 179.300-9 Welding.
- 179.300-10 Postweld heat treatment.
- 179.300-12 Protection of fittings.
- 179.300-13 Venting, loading and unloading valves.
- 179.300-14 Attachments not otherwise specified.
- 179.300-15 Pressure relief devices.
- 179.300-16 Tests of tanks.
- 179.300-17 Tests of pressure relief devices.
- 179.300-18 Stamping.
- 179.300-19 Inspection.
- 179.300-20 Reports.
- 179.301 Individual specification requirements for multi-unit tank car tanks.
- 179.302 [Reserved]

**Subpart F—Specification for Cryogenic Liquid Tank Car Tanks and Seamless Steel Tanks (Classes DOT-113 and 107A)**

- 179.400 General specification applicable to cryogenic liquid tank car tanks.
- 179.400-1 General.
- 179.400-3 Type.
- 179.400-4 Insulation system and performance standard.
- 179.400-5 Materials.
- 179.400-6 Bursting and buckling pressure.
- 179.400-7 Tank heads.
- 179.400-8 Thickness of plates.
- 179.400-9 Stiffening rings.
- 179.400-10 Sump or siphon bowl.
- 179.400-11 Welding.
- 179.400-12 Postweld heat treatment.
- 179.400-13 Support system for inner tank.
- 179.400-14 Cleaning of inner tank.
- 179.400-15 Radioscopy.
- 179.400-16 Access to inner tank.
- 179.400-17 Inner tank piping.
- 179.400-18 Test of inner tank.
- 179.400-19 Valves and gages.
- 179.400-20 Pressure relief devices.
- 179.400-21 Test of pressure relief valves.
- 179.400-22 Protective housings.
- 179.400-23 Operating instructions.
- 179.400-24 Stamping.

179.400-25 Stenciling.

179.401 Individual specification requirements applicable to inner tanks for cryogenic liquid tank car tanks.

179.401-1 Individual specification requirements.

179.500 Specification DOT-107A \* \* \* \*, seamless steel tank car tanks.

179.500-1 Tanks built under these specifications shall meet the requirements of § 179.500.

179.500-3 Type and general requirements.

179.500-4 Thickness of wall.

179.500-5 Material.

179.500-6 Heat treatment.

179.500-7 Physical tests.

179.500-8 Openings in tanks.

179.500-10 Protective housing.

179.500-11 Loading and unloading valves.

179.500-12 Pressure relief devices.

179.500-13 Fixtures.

179.500-14 Test of tanks.

179.500-15 Handling of tanks failing in tests.

179.500-16 Tests of pressure relief devices.

179.500-17 Marking.

179.500-18 Inspection and reports.

APPENDIX A TO PART 179—PROCEDURES FOR TANK-HEAD PUNCTURE-RESISTANCE TEST

APPENDIX B TO PART 179—PROCEDURES FOR SIMULATED POOL AND TORCH-FIRE TESTING

AUTHORITY: 49 U.S.C. 5101-5128; 49 CFR part 1.53.

SOURCE: 29 FR 18995, Dec. 29, 1964, unless otherwise noted. Redesignated at 32 FR 5606, Apr. 5, 1967.

**Subpart A—Introduction, Approvals and Reports**

**§ 179.1 General.**

(a) This part prescribes the specifications for tanks that are to be mounted on or form part of a tank car and which are to be marked with a DOT specification.

(b) Except as provided in paragraph (c) of this section, tanks to which this part is applicable, must be built to the specifications prescribed in this part.

(c) Tanks built to specifications predating those in this part may continue in use as provided in § 180.507 of this subchapter.

(d) Any person who performs a function prescribed in this part, shall perform that function in accordance with this part.

(e) When this part requires a tank to be marked with a DOT specification

## § 179.2

(for example, DOT-105A100W), compliance with that requirement is the responsibility of the tank builder. Marking the tank with the DOT specification shall be understood to certify compliance by the builder that the functions performed by the builder, as prescribed in this part, have been performed in compliance with this part.

(f) The tank builder should inform each person to whom that tank is transferred of any specification requirements which have not been met at time of transfer.

[Amdt. 179-17, 41 FR 38183, Sept. 9, 1976, as amended by Amdt. 179-50, 60 FR 49076, Sept. 21, 1995; 68 FR 48571, Aug. 14, 2003]

### § 179.2 Definitions and abbreviations.

(a) The following apply in part 179:

(1) AAR means Association of American Railroads.

(2) *Approved* means approval by the AAR Tank Car Committee.

(3) *ASTM* means American Society for Testing and Materials.

(4) [Reserved]

(5) Definitions in part 173 of this chapter also apply.

(6) *F* means degrees Fahrenheit.

(7) *NGT* means National Gas Taper Threads.

(8) *NPT* means an American Standard Taper Pipe Thread conforming to the requirements of NBS Handbook H-28 (IBR, see § 171.7 of this subchapter).

(9) [Reserved]

(10) *Tank car facility* means an entity that manufactures, repairs, inspects, tests, qualifies, or maintains a tank car to ensure that the tank car conforms to this part and subpart F of part 180 of this subchapter, that alters the certificate of construction of the tank car, that ensures the continuing qualification of a tank car by performing a function prescribed in parts 179 or 180 of this subchapter, or that makes any representation indicating compliance with one or more of the requirements of parts 179 or 180 of this subchapter.

(11) *Tanks* means tank car tanks.

## 49 CFR Ch. I (10-1-08 Edition)

(b) [Reserved]

[29 FR 18995, Dec. 20, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21344, Nov. 6, 1971; Amdt. 179-50, 60 FR 49076, Sept. 21, 1995; Amdt. 179-50, 61 FR 33255, June 26, 1996; 63 FR 52850, Oct. 1, 1998; 66 FR 45186, 45390, Aug. 28, 2001; 68 FR 75759, Dec. 31, 2003]

### § 179.3 Procedure for securing approval.

(a) Application for approval of designs, materials and construction, conversion or alteration of tank car tanks under these specifications, complete with detailed prints, must be submitted in prescribed form to the Executive Director—Tank Car Safety, AAR, for consideration by its Tank Car Committee and other appropriate committees. Approval or rejections of applications based on appropriate committee action will be issued by the executive director.

(b) When, in the opinion of the Committee, such tanks or equipment are in compliance with the requirements of this subchapter, the application will be approved.

(c) When such tanks or equipment are not in compliance with the requirements of this subchapter, the Committee may recommend service trials to determine the merits of a change in specifications. Such service trials may be conducted only if the builder or shipper applies for and obtains a special permit.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967 and amended by Amdt. 179-41, 52 FR 36672, Sept. 30, 1987; 63 FR 52850, Oct. 1, 1998; 68 FR 48571, Aug. 14, 2003; 70 FR 73166, Dec. 9, 2005]

### § 179.4 Changes in specifications for tank cars.

(a) Proposed changes in or additions to specifications for tanks must be submitted to the Executive Director—Tank Car Safety, AAR, for consideration by its Tank Car Committee. An application for construction of tanks to any new specification may be submitted with proposed specification. Construction should not be started until the specification has been approved or a special permit has been

issued. When proposing a new specification, the applicant shall furnish information to justify a new specification. This data should include the properties of the lading and the method of loading and unloading.

(b) The Tank Car Committee will review the proposed specifications at its earliest convenience and report its recommendations through the Executive Director—Tank Car Safety to the Department. The recommendation will be considered by the Department in determining appropriate action.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967 and amended by Amdt. 179-41, 52 FR 36672, Sept. 30, 1987; 63 FR 52850, Oct. 1, 1998; 70 FR 73166, Dec. 9, 2005]

#### § 179.5 Certificate of construction.

(a) Before a tank car is placed in service, the party assembling the completed car shall furnish a Certificate of Construction, Form AAR 4-2 to the owner and the Executive Director—Tank Car Safety, AAR, certifying that the tank, equipment, and car fully conforms to all requirements of the specification.

(b) When cars or tanks are covered in one application and are identical in all details are built in series, one certificate will suffice for each series when submitted to the Executive Director—Tank Car Safety, AAR.

(c) If the owner elects to furnish service equipment, the owner shall furnish the Executive Director—Tank Car Safety, AAR, a report in prescribed form, certifying that the service equipment complies with all the requirements of the specifications.

(d) When cars or tanks which are covered on one application and are identical in all details are built in series, one certificate shall suffice for each series when submitted to the Executive Director—Tank Car Safety, AAR. One copy of the Certificate of Construction must be furnished to the Executive Director—Tank Car Safety, AAR for each car number of consecutively numbered group or groups covered by the original application.

[Amdt. 179-10, 36 FR 21344, Nov. 6, 1971, as amended at 63 FR 52850, Oct. 1, 1998; 68 FR 48571, Aug. 14, 2003]

#### § 179.6 Repairs and alterations.

For procedure to be followed in making repairs or alterations, see appendix R of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter).

[68 FR 75759, Dec. 31, 2003]

#### § 179.7 Quality assurance program.

(a) At a minimum, each tank car facility shall have a quality assurance program, approved by AAR, that—

(1) Ensures the finished product conforms to the requirements of the applicable specification and regulations of this subchapter;

(2) Has the means to detect any non-conformity in the manufacturing, repair, inspection, testing, and qualification or maintenance program of the tank car; and

(3) Prevents non-conformities from recurring.

(b) At a minimum, the quality assurance program must have the following elements

(1) Statement of authority and responsibility for those persons in charge of the quality assurance program.

(2) An organizational chart showing the interrelationship between managers, engineers, purchasing, construction, inspection, testing, and quality control personnel.

(3) Procedures to ensure that the latest applicable drawings, design calculations, specifications, and instructions are used in manufacture, inspection, testing, and repair.

(4) Procedures to ensure that the fabrication and construction materials received are properly identified and documented.

(5) A description of the manufacturing, repair, inspection, testing, and qualification or maintenance program, including the acceptance criteria, so that an inspector can identify the characteristics of the tank car and the elements to inspect, examine, and test at each point.

(6) Monitoring and control of processes and product characteristics during production.

(7) Procedures for correction of nonconformities.

(8) Provisions indicating that the requirements of the AAR Specifications



## § 179.10

for Tank Cars (IBR, see §171.7 of this subchapter), apply.

(9) Qualification requirements of personnel performing non-destructive inspections and tests.

(10) Procedures for evaluating the inspection and test technique employed, including the accessibility of the area and the sensitivity and reliability of the inspection and test technique and minimum detectable crack length.

(11) Procedures for the periodic calibration and measurement of inspection and test equipment.

(12) A system for the maintenance of records, inspections, tests, and the interpretation of inspection and test results.

(c) Each tank car facility shall ensure that only personnel qualified for each non-destructive inspection and test perform that particular operation.

(d) Each tank car facility shall provide written procedures to its employees to ensure that the work on the tank car conforms to the specification, AAR approval, and owner's acceptance criteria.

(e) Each tank car facility shall train its employees in accordance with subpart H of part 172 of this subchapter on the program and procedures specified in paragraph (b) of this section to ensure quality.

(f) No tank car facility may manufacture, repair, inspect, test, qualify or maintain tank cars subject to requirements of this subchapter, unless it is operating in conformance with a quality assurance program and written procedures required by paragraphs (a) and (b) of this section.

[Amdt. 179-50, 60 FR 49076, Sept. 21, 1995, as amended by Amdt. 179-50, 61 FR 33255, June 26, 1996; 68 FR 48571, Aug. 14, 2003; 68 FR 75759, Dec. 31, 2003]

## Subpart B—General Design Requirements

### § 179.10 Tank mounting.

(a) The manner in which tanks are attached to the car structure shall be approved. The use of rivets to secure anchors to tanks prohibited.

(b) [Reserved]

## 49 CFR Ch. I (10-1-08 Edition)

### § 179.11 Welding certification.

(a) Welding procedures, welders and fabricators shall be approved.

(b) [Reserved]

### § 179.12 Interior heater systems.

(a) Interior heater systems shall be of approved design and materials. If a tank is divided into compartments, a separate system shall be provided for each compartment.

(b) Each interior heater system shall be hydrostatically tested at not less than 13.79 bar (200 psig) and shall hold the pressure for 10 minutes without leakage or evidence of distress.

[Amdt. 179-52, 61 FR 28678, June 5, 1996, as amended by 66 FR 45390, Aug. 28, 2001]

### § 179.13 Tank car capacity and gross weight limitation.

Tank cars built after November 30, 1970, must not exceed 34,500 gallons capacity or 263,000 pounds gross weight on rail. Existing tank cars may not be converted to exceed 34,500 gallons capacity or 263,000 pounds gross weight on rail.

[Amdt. 179-4, 35 FR 14217, Sept. 9, 1970]

### § 179.14 Coupler vertical restraint system.

(a) *Performance standard.* Each tank car shall be equipped with couplers capable of sustaining, without disengagement or material failure, vertical loads of at least 200,000 pounds (90,718.5 kg) applied in upward and downward directions in combination with buff loads of 2,000 pounds (907.2 kg), when coupled to cars which may or may not be equipped with couplers having this vertical restraint capability.

(b) *Test verification.* Except as provided in paragraph (d) of this section, compliance with the requirements of paragraph (a) of this section shall be achieved by verification testing of the coupler vertical restraint system in accordance with paragraph (c) of this section.

(c) *Coupler vertical restraint tests.* A coupler vertical restraint system shall be tested under the following conditions:

(1) The test coupler shall be tested with a mating coupler (or simulated coupler) having only frictional vertical

force resistance at the mating interface; or a mating coupler (or simulated coupler) having the capabilities described in paragraph (a) of this section;

(2) The testing apparatus shall simulate the vertical coupler performance at the mating interface and may not interfere with coupler failure or otherwise inhibit failure due to force applications and reactions; and

(3) The test shall be conducted as follows:

(i) A minimum of 200,000 pounds (90,718.5 kg) vertical downward load shall be applied continuously for at least 5 minutes to the test coupler head simultaneously with the application of a nominal 2,000 pounds (907.2 kg) buff load;

(ii) The procedures prescribed in paragraph (c)(3)(i) of this section, shall be repeated with a minimum vertical upward load of 200,000 pounds (90,718.5 kg); and

(iii) A minimum of three consecutive successful tests shall be performed for each load combination prescribed in paragraphs (c)(3) (i) and (ii) of this section. A test is successful when a vertical disengagement or material failure does not occur during the application of any of the loads prescribed in this paragraph.

(d) *Authorized couplers.* As an alternative to the test verifications in paragraph (c) of this section, the following couplers are authorized:

(1) E double shelf couplers designated by the Association of American Railroads' Catalog Nos., SE60CHT, SE60CC, SE60CHTE, SE60CE, SE60DC, SE60DE, SE67CC, SE67CE, SE67BHT, SE67BC, SE67BHTE, SE67BE, SE68BHT, SE68BC, SE68BHTE, SE68BE, SE69AHTE, and SE69AE.

(2) F double shelf couplers designated by the Association of American Railroads' Catalog Nos., SF70CHT, SF70CC, SF70CHTE, SF70CE, SF73AC, SF73AE, SF73AHT, SF73AHTE, SF79CHT, SF79CC, SF79CHTE, and SF79CE.

[Amdt. 179-42, 54 FR 38797, Sept. 20, 1989]

#### § 179.15 Pressure relief devices.

Except for DOT Class 106, 107, 110, and 113 tank cars, tanks must have a pressure relief device, made of material compatible with the lading, that conforms to the following requirements:

(a) *Performance standard.* Each tank must have a pressure relief device, made of materials compatible with the lading, having sufficient flow capacity to prevent pressure build-up in the tank to no more than the flow rating pressure of the pressure relief device in fire conditions as defined in appendix A of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter).

(b) *Settings for reclosing pressure relief devices.* (1) Except as provided in paragraph (b)(2) of this section, a reclosing pressure relief valve must have a minimum start-to-discharge pressure equal to the sum of the static head and gas padding pressure and the lading vapor pressure at the following reference temperatures:

(i) 46 °C (115 °F) for noninsulated tanks;

(ii) 43 °C (110 °F) for tanks having a thermal protection system incorporating a metal jacket that provides an overall thermal conductance at 15.5 °C (60 °F) of no more than 10.22 kilojoules per hour per square meter per degree Celsius (0.5 Btu per hour per square foot per degree F) temperature differential; and

(iii) 41 °C (105 °F) for insulated tanks.

(2)(i) The start-to-discharge pressure of a pressure relief device may not be lower than 5.17 Bar (75 psig) or exceed 33 percent of the minimum tank burst pressure.

(ii) Tanks built prior to October 1, 1997 having a minimum tank burst pressure of 34.47 Bar (500 psig) or less may be equipped with a reclosing pressure relief valve having a start-to-discharge pressure of not less than 14.5 percent of the minimum tank burst pressure but no more than 33 percent of the minimum tank burst pressure.

(3) The vapor tight pressure of a reclosing pressure relief valve must be at least 80 percent of the start-to-discharge pressure.

(4) The flow rating pressure must be 110 percent of the start-to-discharge pressure for tanks having a minimum tank burst pressure greater than 34.47 Bar (500 psig) and from 110 percent to 130 percent for tanks having a minimum tank burst pressure less than or equal to 34.47 Bar (500 psig).

(5) The tolerance for a reclosing pressure relief valve is  $\pm 3$  psi for valves with a start-to-discharge pressure of 6.89 Bar (100 psig) or less and  $\pm 3$  percent for valves with a start-to-discharge pressure greater than 6.89 Bar (100 psig).

(c) *Flow capacity of pressure relief devices.* The total flow capacity of each reclosing and nonreclosing pressure relief device must conform to appendix A of the AAR Specifications for Tank Cars.

(d) *Flow capacity tests.* The manufacturer of any reclosing or nonreclosing pressure relief device must design and test the device in accordance with appendix A of the AAR Specifications for Tank Cars.

(e) *Combination pressure relief systems.* A non-reclosing pressure relief device may be used in series with a reclosing pressure relief valve. The pressure relief valve must be located outboard of the non-reclosing pressure relief device.

(1) When a breaking pin device is used in combination with a reclosing pressure relief valve, the breaking pin must be designed to fail at the start-to-discharge pressure specified in paragraph (b) of this section, and the reclosing pressure relief valve must be designed to discharge at not greater than 95 percent of the start-to-discharge pressure.

(2) When a rupture disc is used in combination with a reclosing pressure relief valve, the rupture disc must be designed to burst at the pressure specified in paragraph (b) of this section, and the reclosing pressure relief valve must be designed to discharge at not greater than 95 percent of the pressure. A device must be installed to detect any accumulation of pressure between the rupture disc and the reclosing pressure relief valve. The detection device must be a needle valve, trycock, or tell-tale indicator. The detection device must be closed during transportation.

(3) The vapor tight pressure and the start-to-discharge tolerance is based on the discharge setting of the reclosing pressure relief device.

(f) *Nonreclosing pressure relief device.* In addition to paragraphs (a), (b)(4), (c), and (d) of this section, a nonreclosing

pressure relief device must conform to the following requirements:

(1) A non-reclosing pressure relief device must incorporate a rupture disc designed to burst at a pressure equal to the greater of 100% of the tank test pressure, or 33% of the tank burst pressure.

(2) The approach channel and the discharge channel may not reduce the required minimum flow capacity of the pressure relief device.

(3) The non-reclosing pressure relief device must be designed to prevent interchange with other fittings installed on the tank car, must have a structure that encloses and clamps the rupture disc in position (preventing any distortion or damage to the rupture disc when properly applied), and must have a cover, with suitable means of preventing misplacement, designed to direct any discharge of the lading downward.

(4) The non-reclosing pressure relief device must be closed with a rupture disc that is compatible with the lading and manufactured in accordance with Appendix A of the AAR Specifications for Tank Cars. The tolerance for a rupture disc is +0 to –15 percent of the burst pressure marked on the disc.

(g) *Location of relief devices.* Each pressure relief device must communicate with the vapor space above the lading as near as practicable on the longitudinal center line and center of the tank.

(h) *Marking of pressure relief devices.* Each pressure relief device and rupture disc must be permanently marked in accordance with the appendix A of the AAR Specifications for Tank Cars.

[Amdt. 179–52, 61 FR 28678, June 5, 1996, as amended by Amdt. 179–52, 61 FR 50255, Sept. 25, 1996; 62 FR 51561, Oct. 1, 1997; 64 FR 51919, Sept. 27, 1999; 66 FR 45390, Aug. 28, 2001; 68 FR 75759, Dec. 31, 2003]

**§ 179.16 Tank-head puncture-resistance systems.**

(a) *Performance standard.* When the regulations in this subchapter require a tank-head puncture-resistance system, the system shall be capable of sustaining, without any loss of lading, coupler-to-tank-head impacts at relative car speeds of 29 km/hour (18 mph) when:

(1) The weight of the impact car is at least 119,295 kg (263,000 pounds);

(2) The impacted tank car is coupled to one or more backup cars that have a total weight of at least 217,724 kg (480,000 pounds) and the hand brake is applied on the last “backup” car; and

(3) The impacted tank car is pressurized to at least 6.9 Bar (100 psig).

(b) *Verification by testing.* Compliance with the requirements of paragraph (a) of this section shall be verified by full-scale testing according to appendix A of this part.

(c) *Alternative compliance by other than testing.* As an alternative to requirements prescribed in paragraph (b) of this section, compliance with the requirements of paragraph (a) of this section may be met by installing full-head protection (shields) or full tank-head jackets on each end of the tank car conforming to the following:

(1) The full-head protection (shields) or full tank-head jackets must be at least 1.27 cm (0.5 inch) thick, shaped to the contour of the tank head and made from steel having a tensile strength greater than 379.21 N/mm<sup>2</sup> (55,000 psi).

(2) The design and test requirements of the full-head protection (shields) or full tank-head jackets must meet the impact test requirements in Section 5.3 of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter).

(3) The workmanship must meet the requirements in Section C, Part II, Chapter 5, of the AAR Specifications for Design, Fabrication, and Construction of Freight Cars (IBR, see § 171.7 of this subchapter).

[Amdt. 179-50, 60 FR 49077, Sept. 21, 1995, as amended by Amdt. 179-50, 61 FR 33255, June 26, 1996; 66 FR 45390, Aug. 28, 2001; 68 FR 75759, Dec. 31, 2003]

#### § 179.18 Thermal protection systems.

(a) *Performance standard.* When the regulations in this subchapter require thermal protection on a tank car, the tank car must have sufficient thermal resistance so that there will be no release of any lading within the tank car, except release through the pressure release device, when subjected to:

- (1) A pool fire for 100 minutes; and
- (2) A torch fire for 30 minutes.

(b) *Thermal analysis.* (1) Compliance with the requirements of paragraph (a) of this section shall be verified by analyzing the fire effects on the entire surface of the tank car. The analysis must consider the fire effects on and heat flux through tank discontinuities, protective housings, underframes, metal jackets, insulation, and thermal protection. A complete record of each analysis shall be made, retained, and upon request, made available for inspection and copying by an authorized representative of the Department. The procedures outlined in “Temperatures, Pressures, and Liquid Levels of Tank Cars Engulfed in Fires,” DOT/FRA/OR&D-84/08.11, (1984), Federal Railroad Administration, Washington, DC (available from the National Technical Information Service, Springfield, VA) shall be deemed acceptable for analyzing the fire effects on the entire surface of the tank car.

(2) When the analysis shows the thermal resistance of the tank car does not conform to paragraph (a) of this section, the thermal resistance of the tank car must be increased by using a system listed by the Department under paragraph (c) of this section or by testing a new or untried system and verifying it according to appendix B of this part.

(c) *Systems that no longer require test verification.* The Department maintains a list of thermal protection systems that comply with the requirements of appendix B of this part and that no longer require test verification. Information necessary to equip tank cars with one of these systems is available in the PHMSA Records Center, Pipeline and Hazardous Materials Safety Administration, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590-0001.

[Amdt. 179-50, 60 FR 49077, Sept. 21, 1995, as amended by Amdt. 179-50, 61 FR 33256, June 26, 1996; 66 FR 45390, Aug. 28, 2001; 70 FR 56099, Sept. 23, 2005; 72 FR 55696, Oct. 1, 2007]

#### § 179.20 Service equipment; protection systems.

If an applicable tank car specification authorizes location of filling or discharge connections in the bottom

**§ 179.22**

shell, the connections must be designed, constructed, and protected according to paragraphs E9.00 and E10.00 of the AAR Specifications for Tank Cars (IBR, see §171.7 of this subchapter).

[68 FR 75759, Dec. 31, 2003]

**§ 179.22 Marking.**

In addition to any other marking requirement in this subchapter, the following marking requirements apply:

(a) Each tank car must be marked according to the requirements in appendix C of the AAR Specifications for Tank Cars (IBR, see §171.7 of this subchapter).

(b) Each tank car that requires a tank-head puncture-resistance system must have the letter “S” substituted for the letter “A” in the specification marking.

(c) Each tank car that requires a tank-head puncture-resistance system, a thermal protection system, and a metal jacket must have the letter “J” substituted for the letter “A” or “S” in the specification marking.

(d) Each tank car that requires a tank-head puncture-resistance system, a thermal protection system, and no metal jacket must have the letter “T” substituted for the letter “A” or “S” in the specification marking.

[Amdt. 179–50, 60 FR 49077, Sept. 21, 1995, as amended by Amdt. 179–50, 61 FR 33256, June 26, 1996; 68 FR 75759, Dec. 31, 2003]

### **Subpart C—Specifications for Pressure Tank Car Tanks (Classes DOT-105, 109, 112, 114 and 120)**

#### **§ 179.100 General specifications applicable to pressure tank car tanks.**

##### **§ 179.100–1 Tanks built under these specifications shall comply with the requirements of §§ 179.100, 179.101 and when applicable, §§ 179.102 and 179.103.**

##### **§ 179.100–3 Type.**

(a) Tanks built under this specification shall be fusion-welded with heads designed convex outward. Except as provided in §179.103 they shall be circular in cross section, shall be provided with a manway nozzle on top of the

tank of sufficient size to permit access to the interior, a manway cover to provide for the mounting of all valves, measuring and sampling devices, and a protective housing. Other openings in the tank are prohibited, except as provided in part 173 of this chapter, §§ 179.100–14, 179.101–1, 179.102 or § 179.103.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21344, Nov. 6, 1971; 65 FR 58632, Sept. 29, 2000]

#### **§ 179.100–4 Insulation.**

(a) If insulation is applied, the tank shell and manway nozzle must be insulated with an approved material. The entire insulation must be covered with a metal jacket of a thickness not less than 11 gauge (0.1196 inch) nominal (Manufacturers’ Standard Gauge) and flashed around all openings so as to be weather-tight. The exterior surface of a carbon steel tank, and the inside surface of a carbon steel jacket must be given a protective coating.

(b) If insulation is a specification requirement, it shall be of sufficient thickness so that the thermal conductance at 60 °F is not more than 0.075 Btu per hour, per square foot, per degree F temperature differential. If exterior heaters are attached to tank, the thickness of the insulation over each heater element may be reduced to one-half that required for the shell.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21344, Nov. 6, 1971; Amdt. 179–50, 60 FR 49077, Sept. 21, 1995]

#### **§ 179.100–6 Thickness of plates.**

(a) The wall thickness after forming of the tank shell and heads must not be less than that specified in §179.101, nor that calculated by the following formula:

$$t = Pd / 2SE$$

Where:

$d$  = Inside diameter in inches;

$E$  = 1.0 welded joint efficiency; except for heads with seams=0.9;

$P$  = Minimum required bursting pressure in p.s.i.;

$S$  = Minimum tensile strength of plate material in p.s.i., as prescribed in §179.100–7;

$t$  = Minimum thickness of plate in inches after forming.

(b) If plates are clad with material having tensile strength properties at least equal to the base plate, the cladding may be considered a part of the base plate when determining thickness. If cladding material does not have tensile strength at least equal to the base plate, the base plate alone shall meet the thickness requirement.

(c) When aluminum plate is used, the minimum width of bottom sheet of tank shall be 60 inches, measured on the arc, but in all cases the width shall be sufficient to bring the entire width of the longitudinal welded joint, including welds, above the bolster.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21344, Nov. 6, 1971]

#### § 179.100-7 Materials.

(a) *Steel plate:* Steel plate materials used to fabricate tank shell and manway nozzle must comply with one of the following specifications with the indicated minimum tensile strength and elongation in the welded condition. The maximum allowable carbon content must be 0.31 percent when the individual specification allows carbon greater than this amount. The plates may be clad with other approved materials.

| Specifications                          | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) welded condition (longitudinal) |
|-----------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------------|
| AAR TC 128, Gr. B .....                 | 81,000                                                          | 19                                                                       |
| ASTM A 302 <sup>2</sup> , Gr. B .....   | 80,000                                                          | 20                                                                       |
| ASTM A 516 <sup>2</sup> .....           | 70,000                                                          | 20                                                                       |
| ASTM A 537 <sup>2</sup> , Class 1 ..... | 70,000                                                          | 23                                                                       |

<sup>1</sup>Maximum stresses to be used in calculations.

<sup>2</sup>These specifications are incorporated by reference (IBR, see § 171.7 of this subchapter).

(b) *Aluminum alloy plate:* Aluminum alloy plate material used to fabricate tank shell and manway nozzle must be suitable for fusion welding and must comply with one of the following specifications (IBR, see § 171.7 of this subchapter) with its indicated minimum tensile strength and elongation in the welded condition. \* \* \*

| Specifications                      | Minimum tensile strength (p.s.i.) 0 temper, welded condition <sup>3,4</sup> | Minimum elongation in 2 inches (percent) 0 temper, welded condition (longitudinal) |
|-------------------------------------|-----------------------------------------------------------------------------|------------------------------------------------------------------------------------|
| ASTM B 209, Alloy 5052 <sup>1</sup> | 25,000                                                                      | 18                                                                                 |
| ASTM B 209, Alloy 5083 <sup>2</sup> | 38,000                                                                      | 16                                                                                 |
| ASTM B 209, Alloy 5086 <sup>1</sup> | 35,000                                                                      | 14                                                                                 |
| ASTM B 209, Alloy 5154 <sup>1</sup> | 30,000                                                                      | 18                                                                                 |
| ASTM B 209, Alloy 5254 <sup>1</sup> | 30,000                                                                      | 18                                                                                 |
| ASTM B 209, Alloy 5454 <sup>1</sup> | 31,000                                                                      | 18                                                                                 |
| ASTM B 209, Alloy 5652 <sup>1</sup> | 25,000                                                                      | 18                                                                                 |

<sup>1</sup>For fabrication, the parent plate material may be 0, H112, or H32 temper, but design calculations must be based on minimum tensile strength shown.

<sup>2</sup>0 temper only.

<sup>3</sup>Weld filler metal 5556 must not be used.

<sup>4</sup>Maximum stress to be used in calculations.

(c) *High alloy steel plate.* (1) High alloy steel plate must conform to the following specifications:

| Specifications                                                                                 | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 304L ..... | 70,000                                                          | 30                                                                 |
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 316L ..... | 70,000                                                          | 30                                                                 |

<sup>1</sup>Maximum stresses to be used in calculations.

(2)(i) High alloy steels used to fabricate tank must be tested in accordance with the following procedures in ASTM A 262, "Standard Practices for Detecting Susceptibility to Intergranular Attack in Austenitic Stainless Steel" (IBR, see § 171.7 of this subchapter), and must exhibit corrosion rates not exceeding the following: \* \* \*

| Test procedures  | Material               | Corrosion rate i.p.m. |
|------------------|------------------------|-----------------------|
| Practice B ..... | Types 304L and 316L .. | 0.0040                |
| Practice C ..... | Type 304L .....        | 0.0020                |

(ii) Type 304L and 316L test specimens must be given a sensitizing treatment prior to testing.

(d) All attachments welded to tank shell must be of approved material

## § 179.100-8

which is suitable for welding to the tank.

[Amdt. 179-10, 36 FR 21344, Nov. 6, 1971, as amended by Amdt. 179-32, 48 FR 27707, June 16, 1983; Amdt. 179-47, 58 FR 50237, Sept. 24, 1993; Amdt. 179-52, 61 FR 28679, June 5, 1996; Amdt 179-52, 61 FR 50255, Sept. 25, 1996; 66 FR 45186, Aug. 28, 2001; 67 FR 51660, Aug. 8, 2002; 68 FR 75759, Dec. 31, 2003]

### § 179.100-8 Tank heads.

(a) The tank head shape shall be an ellipsoid of revolution in which the major axis shall equal the diameter of the shell adjacent to the head and the minor axis shall be one-half the major axis.

(b) Each tank head made from steel which is required to be "fine grain" by the material specification, which is hot formed at a temperature exceeding 1700 °F., must be normalized after forming by heating to a temperature between 1550° and 1700 °F., by holding at that temperature for at least 1 hour per inch of thickness (30-minute minimum), and then by cooling in air. If the material specification requires quenching and tempering, the treatment specified in that specification must be used instead of the one specified above.

[29 FR 18995, Dec. 29, 1964. Redesignated, 32 FR 5606, Apr. 5, 1967 and amended by Amdt. 179-12, 39 FR 15038, Apr. 30, 1974]

### § 179.100-9 Welding.

(a) All joints shall be fusion-welded in compliance with the requirements of AAR Specifications for Tank Cars, appendix W (IBR, see §171.7 of this subchapter). Welding procedures, welders and fabricators shall be approved.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964, as amended at 65 FR 58632, Sept. 29, 2000; 68 FR 75759, Dec. 31, 2003]

### § 179.100-10 Postweld heat treatment.

(a) After welding is complete, steel tanks and all attachments welded thereto must be postweld heat treated as a unit in compliance with the requirements of AAR Specifications for Tank Cars, appendix W (IBR, see §171.7 of this subchapter).

(b) For aluminum tanks, postweld heat treatment is prohibited.

## 49 CFR Ch. I (10-1-08 Edition)

(c) Tank and welded attachments, fabricated from ASTM A 240/A 240M (IBR, see §171.7 of this subchapter), Type 304L or Type 316L materials do not require postweld heat treatment, but these materials do require a corrosion resistance test as specified in § 179.100-7(c)(2).

[Amdt. 179-10, 36 FR 21345, Nov. 6, 1971, as amended by Amdt. 179-47, 58 FR 50238, Sept. 24, 1993; Amdt. 179-52, 61 FR 28679, June 5, 1996; 67 FR 51660, Aug. 8, 2002; 68 FR 75758 and 75759, Dec. 31, 2003]

### § 179.100-12 Manway nozzle, cover and protective housing.

(a) Manway nozzles must be of approved design of forged or rolled steel for steel tanks or of fabricated aluminum alloy for aluminum tanks, with an access opening of at least 18 inches inside diameter, or at least 14 inches by 18 inches around or oval. Each nozzle must be welded to the tank and the opening reinforced in an approved manner in compliance with the requirements of AAR Specifications for Tank Cars, appendix E, Figure E10 (IBR, see §171.7 of this subchapter).

(b) Manway cover shall be machined to approved dimensions and be of forged or rolled carbon or alloy steel, rolled aluminum alloy or nickel when required by the lading. Minimum thickness is listed in §179.101. Manway cover shall be attached to manway nozzle by through or stud bolts not entering tank, except as provided in §179.103-2(a).

(c) Except as provided in §179.103, protective housing of cast, forged or fabricated approved materials must be bolted to manway cover with not less than twenty ¾-inch studs. The shearing value of the bolts attaching protective housing to manway cover must not exceed 70 percent of the shearing value of bolts attaching manway cover to manway nozzle. Housing must have steel sidewalls not less than three-fourths inch in thickness and must be equipped with a metal cover not less than one-fourth inch in thickness that can be securely closed. Housing cover must have suitable stop to prevent cover striking loading and unloading connections and be hinged on one side only with approved riveted pin or rod with nuts and cotters. Openings in wall

of housing must be equipped with screw plugs or other closures.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21345, Nov. 6, 1971; 68 FR 75760, Dec. 31, 2003]

**§ 179.100–13 Venting, loading and unloading valves, measuring and sampling devices.**

(a) Venting, loading and unloading valves must be of approved design, made of metal not subject to rapid deterioration by the lading, and must withstand the tank test pressure without leakage. The valves shall be bolted to seatings on the manway cover, except as provided in § 179.103. Valve outlets shall be closed with approved screw plugs or other closures fastened to prevent misplacement.

(b) The interior pipes of the loading and unloading valves shall be anchored and, except as prescribed in §§ 173.314(j), 179.102 or 179.103, may be equipped with excess flow valves of approved design.

(c) Gauging device, sampling valve and thermometer well are not specification requirements. When used, they shall be of approved design, made of metal not subject to rapid deterioration by the lading, and shall withstand the tank test pressure without leakage. Interior pipes of the gauging device and sampling valve, except as prescribed in §§ 173.314(j), 179.102 or 179.103, may be equipped with excess flow valves of approved design. Interior pipe of the thermometer well shall be anchored in an approved manner to prevent breakage due to vibration. The thermometer well shall be closed by an approved valve attached close to the manway cover, or other approved location, and closed by a screw plug. Other approved arrangements that permit testing thermometer well for leaks without complete removal of the closure may be used.

(d) An excess flow valve as referred to in this specification, is a device which closes automatically against the outward flow of the contents of the tank in case the external closure valve is broken off or removed during transit. Excess flow valves may be designed with a by-pass to allow the equalization of pressures.

(e) Bottom of tank shell may be equipped with a sump or siphon bowl, or both, welded or pressed into the shell. Such sumps or siphon bowls, if applied, are not limited in size and must be made of cast, forged or fabricated metal. Each sump or siphon bowl must be of good welding quality in conjunction with the metal of the tank shell. When the sump or siphon bowl is pressed in the bottom of the tank shell, the wall thickness of the pressed section must not be less than that specified for the shell. The section of a circular cross section tank to which a sump or siphon bowl is attached need not comply with the out-of-roundness requirement specified in AAR Specifications for Tank Cars, appendix W, W14.06 (IBR, see § 171.7 of this subchapter). Any portion of a sump or siphon bowl not forming a part of cylinder of revolution must have walls of such thickness and be so reinforced that the stresses in the walls caused by a given internal pressure are no greater than the circumferential stress that would exist under the same internal pressure in the wall of a tank of circular cross section designed in accordance with § 179.100–6(a), but in no case shall the wall thickness be less than that specified in § 179.101–1.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21345, Nov. 6, 1971; Amdt. 179–40, 52 FR 13046, Apr. 20, 1987; Amdt. 179–42, 54 FR 38798, Sept. 20, 1989; 65 FR 58632, Sept. 29, 2000; 68 FR 48571, Aug. 14, 2003; 68 FR 75760, Dec. 31, 2003]

**§ 179.100–14 Bottom outlets.**

(a) Bottom outlets for discharge of lading is prohibited, except as provided in § 179.103–3. If indicated in § 179.101, tank may be equipped with a bottom washout of approved construction. If applied, bottom washout shall be in accordance with the following requirements;

(1) The extreme projection of the bottom washout equipment may not be more than that allowed by appendix E of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter).

(2) Bottom washout shall be of cast, forged or fabricated metal and shall be fusion-welded to the tank. It shall be of



## § 179.100-16

good weldable quality in conjunction with metal of tank.

(3) If the bottom washout nozzle extends 6 inches or more from shell of tank, a V-shaped breakage groove shall be cut (not cast) in the upper part of the outlet nozzle at a point immediately below the lowest part of the inside closure seat or plug. In no case may the nozzle wall thickness at the root of the "V" be more than 1/4-inch. Where the nozzle is not a single piece, provision shall be made for the equivalent of the breakage groove. The nozzle must be of a thickness to insure that accidental breakage will occur at or below the "V" groove or its equivalent. On cars without continuous center sills, the breakage groove or its equivalent may not be more than 15 inches below the tank shell. On cars with continuous center sills, the breakage groove or its equivalent must be above the bottom of the center sill construction.

(4) The closure plug and seat shall be readily accessible or removable for repairs.

(5) The closure of the washout nozzle must be equipped with a 3/4-inch solid screw plug. Plug must be attached by at least a 1/4-inch chain.

(6) Joints between closures and their seats may be gasketed with suitable material.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21345, Nov. 6, 1971; Amdt. 179-40, 52 FR 13046, Apr. 20, 1987; 66 FR 45186, Aug. 28, 2001; 68 FR 75760, Dec. 31, 2003]

## § 179.100-16 Attachments.

(a) Reinforcing pads must be used between external brackets and shells if the attachment welds exceed 6 linear inches of 1/4-inch fillet or equivalent weld per bracket or bracket leg. When reinforcing pads are used, they must not be less than one-fourth inch in thickness, have each corner rounded to a 1-inch minimum radius, and be attached to the tank by continuous fillet welds except for venting provisions. The ultimate shear strength of the bracket-to-reinforcing pad weld must not exceed 85 percent of the ultimate shear strength of the reinforcing pad-to-tank weld.

## 49 CFR Ch. I (10-1-08 Edition)

(b) Attachments not otherwise specified shall be applied by approved means.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21346, Nov. 6, 1971]

## § 179.100-17 Closures for openings.

(a) Closures shall be of approved design and made of metal not subject to rapid deterioration by the lading. Plugs, if used, shall be solid, with NPT threads, and shall be of a length which will screw at least six threads inside the face of fitting or tank.

(b) [Reserved]

## § 179.100-18 Tests of tanks.

(a) Each tank shall be tested by completely filling tank and manway nozzle with water or other liquid having similar viscosity, at a temperature which shall not exceed 100 °F during the test; and applying the pressure prescribed in § 179.101. The tank shall hold the prescribed pressure for at least 10 minutes without leakage or evidence of distress.

(b) Insulated tanks shall be tested before insulation is applied.

(c) Caulking of welded joints to stop leaks developed during the foregoing test is prohibited. Repairs in welded joints shall be made as prescribed in AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter).

(d) Testing of exterior heaters is not a specification requirement.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967; 66 FR 45186, Aug. 28, 2001; 68 FR 75760, Dec. 31, 2003]

## § 179.100-19 Tests of safety relief valves.

(a) Each valve shall be tested by air or gas for compliance with § 179.15 before being put into service.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, as amended at 62 FR 51561, Oct. 1, 1997]

## § 179.100-20 Stamping.

(a) To certify that the tank complies with all specification requirements, each tank shall be plainly and permanently stamped in letters and figures at least 3/8 inch high into the metal

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 179.101-1**

near the center of both outside heads as follows:

(b) [Reserved]

|                                             | Example of required stamping |
|---------------------------------------------|------------------------------|
| Specification .....                         | DOT-105A100W                 |
| Material .....                              | ASTM A 516                   |
| Cladding material (if any) .....            | ASTM A240-304                |
| Tank builder's initials .....               | Clad                         |
| Date of original test .....                 | ABC                          |
| Car assembler (if other than tank-builder). | 00-0000<br>DEF               |

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21346, Nov. 6, 1971; Amdt. 179-52, 61 FR 28679, June 5, 1996; 65 FR 50463, Aug. 18, 2000]

**§ 179.101 Individual specification requirements applicable to pressure tank car tanks.**

EDITORIAL NOTE: At 66 FR 45186, Aug. 28, 2001, an amendment published amending a table in §179.101. No text or table appears in § 179.101.

**§ 179.101-1 Individual specification requirements.**

In addition to § 179.100, the individual specification requirements are as follows:

| DOT specification | Insulation                  | Bursting pressure (psig) | Minimum plate thickness (inches) | Test pressure (psig) | Manway cover thickness | Bottom outlet  | Bottom washout | Reference (179.***) |
|-------------------|-----------------------------|--------------------------|----------------------------------|----------------------|------------------------|----------------|----------------|---------------------|
| 105A100ALW        | Yes .....                   | 500                      | 5/8                              | 100                  | <sup>2</sup> 2 1/2     | No .....       | No.            |                     |
| 105A200ALW        | Yes .....                   | 500                      | 5/8                              | 200                  | <sup>2</sup> 2 1/2     | No .....       | No.            |                     |
| 105A300ALW        | Yes .....                   | 750                      | 5/8                              | 300                  | <sup>2</sup> 2 5/8     | No .....       | No.            |                     |
| 105A100W .....    | Yes .....                   | 500                      | <sup>3</sup> 9/16                | 100                  | 2 1/4                  | No .....       | No.            |                     |
| 105A200W .....    | Yes .....                   | 500                      | <sup>3</sup> 9/16                | 200                  | 2 1/4                  | No .....       | No.            |                     |
| 105A300W .....    | Yes .....                   | 750                      | <sup>1</sup> 11/16               | 300                  | <sup>7</sup> 2 1/4     | No .....       | No.            |                     |
| 105A400W .....    | Yes .....                   | 1,000                    | <sup>1</sup> 11/16               | 400                  | <sup>7</sup> 2 1/4     | No .....       | No.            |                     |
| 105A500W .....    | Yes .....                   | 1,250                    | <sup>1</sup> 11/16               | 500                  | 2 1/4                  | No .....       | No .....       | 102-1, 102-2        |
| 105A600W .....    | Yes .....                   | 1,500                    | <sup>1</sup> 11/16               | 600                  | 2 1/4                  | No .....       | No .....       | 102-4, 102-17       |
| 109A100ALW        | Optional .....              | 500                      | 5/8                              | 100                  | <sup>2</sup> 2 1/2     | No .....       | Optional.      |                     |
| 109A200ALW        | Optional .....              | 500                      | 5/8                              | 200                  | <sup>2</sup> 2 1/2     | No .....       | Optional.      |                     |
| 109A300ALW        | Optional .....              | 750                      | 5/8                              | 300                  | <sup>2</sup> 2 5/8     | No .....       | Optional.      |                     |
| 109A300W .....    | Optional .....              | 500                      | <sup>1</sup> 11/16               | 300                  | 2 1/4                  | No .....       | Optional.      |                     |
| 112A200W .....    | Optional <sup>4</sup> ..... | 500                      | <sup>3,5</sup> 9/16              | 200                  | 2 1/4                  | No .....       | No.            |                     |
| 112A340W .....    | Optional <sup>4</sup> ..... | 850                      | <sup>1</sup> 11/16               | 340                  | 2 1/4                  | No .....       | No.            |                     |
| 112A400W .....    | Optional <sup>4</sup> ..... | 1,000                    | <sup>1</sup> 11/16               | 400                  | 2 1/4                  | No .....       | No.            |                     |
| 112A500W .....    | Optional <sup>4</sup> ..... | 1,250                    | <sup>1</sup> 11/16               | 500                  | 2 1/4                  | No .....       | No.            |                     |
| 114A340W .....    | Optional <sup>4</sup> ..... | 850                      | <sup>1</sup> 11/16               | 340                  | <sup>6</sup>           | Optional ..... | Optional ...   | 103                 |
| 114A400W .....    | Optional <sup>4</sup> ..... | 1,000                    | <sup>1</sup> 11/16               | 400                  | <sup>6</sup>           | Optional ..... | Optional ...   | 103                 |
| 120A200ALW        | Yes .....                   | 500                      | 5/8                              | 200                  | <sup>2</sup> 2 1/2     | Optional ..... | Optional ...   | 103                 |
| 120A100W .....    | Yes .....                   | 500                      | <sup>3</sup> 9/16                | 100                  | 2 1/4                  | Optional ..... | Optional ...   | 103                 |
| 120A200W .....    | Yes .....                   | 500                      | <sup>3</sup> 9/16                | 200                  | 2 1/4                  | Optional ..... | Optional ...   | 103                 |
| 120A300W .....    | Yes .....                   | 750                      | <sup>1</sup> 11/16               | 300                  | 2 1/4                  | Optional ..... | Optional ...   | 103                 |
| 120A400W .....    | Yes .....                   | 1,000                    | <sup>1</sup> 11/16               | 400                  | 2 1/4                  | Optional ..... | Optional ...   | 103                 |
| 120A500W .....    | Yes .....                   | 1,250                    | <sup>1</sup> 11/16               | 500                  | 2 1/4                  | Optional ..... | Optional ...   | 103                 |

<sup>1</sup> When steel of 65,000 to 81,000 p.s.i. minimum tensile strength is used, the thickness of plates shall be not less than 5/8 inch, and when steel of 81,000 p.s.i. minimum tensile strength is used, the minimum thickness of plate shall be not less than 9/16 inch.

<sup>2</sup> When approved material other than aluminum alloys are used, the thickness shall be not less than 2 1/4 inches.

<sup>3</sup> When steel of 65,000 p.s.i. minimum tensile strength is used, minimum thickness of plates shall be not less than 1/2 inch.

<sup>4</sup> Tank cars not equipped with a thermal protection or an insulation system used for the transportation of a Class 2 (compressed gas) material must have at least the upper two-thirds of the exterior of the tank, including manway nozzle and all appendances in contact with this area, finished with a reflective coat of white paint.

<sup>5</sup> For inside diameter of 87 inches or less, the thickness of plates shall be not less than 1/2 inch.

<sup>6</sup> See AAR Specifications for Tank Cars, appendix E, E4.01 (IBR, see § 171.7 of this subchapter), and § 179.103-2.

<sup>7</sup> When the use of nickel is required by the lading, the thickness shall not be less than two inches.

[Amdt. 179-52, 61 FR 28679, June 5, 1996 as amended at 66 FR 45390, Aug. 28, 2001; 68 FR 75760, Dec. 31, 2003]

## § 179.102

## 49 CFR Ch. I (10–1–08 Edition)

### § 179.102 Special commodity requirements for pressure tank car tanks.

(a) In addition to §§ 179.100 and 179.101 the following requirements are applicable:

(b) [Reserved]

#### § 179.102–1 Carbon dioxide, refrigerated liquid.

(a) Tank cars used to transport carbon dioxide, refrigerated liquid must comply with the following special requirements:

(1) All plates for tank, manway nozzle and anchorage of tanks must be made of carbon steel conforming to ASTM A 516/A 516M (IBR, see § 171.7 of this subchapter), Grades 55, 60, 65, or 70, or AAR Specification TC 128–78, Grade B. The ASTM A 516/A 516M plate must also meet the Charpy V-Notch test requirements of ASTM A 20/A 20M (see table 16) (IBR, see § 171.7 of this subchapter) in the longitudinal direction of rolling. The TC 128 plate must also meet the Charpy V-Notch energy absorption requirements of 15 ft.-lb. minimum average for 3 specimens, and 10 ft.-lb. minimum for one specimen, at minus 50 °F in the longitudinal direction of rolling in accord with ASTM A 370 (IBR, see § 171.7 of this subchapter). Production-welded test plates prepared as required by W4.00 of AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter), must include impact test specimens of weld metal and heat-affected zone. As an alternate, anchor legs may be fabricated of stainless steel, ASTM A 240/A 240M Types 304, 304L, 316 or 316L, for which impact tests are not required.

(2)–(6) [Reserved]

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21347, Nov. 6, 1971; Amdt. 179–28, 46 FR 49906, Oct. 8, 1981; 46 FR 55266, Nov. 9, 1981; Amdt. 179–32, 48 FR 50440, 50441, Nov. 1, 1983; 49 FR 42736, Oct. 24, 1984; Amdt. 179–45, 55 FR 52728, Dec. 21, 1990; Amdt. 179–52, 61 FR 28680, June 5, 1996; 67 FR 51660, Aug. 8, 2002; 68 FR 75760, Dec. 31, 2003]

#### § 179.102–2 Chlorine.

(a) Each tank car used to transport chlorine must comply with all of the following:

(1) Tanks must be fabricated from carbon steel complying with ASTM Specification A 516 (IBR, see § 171.7 of this subchapter), Grade 70, or AAR Specification TC 128, Grade A or B.

(2)–(3) [Reserved]

(b) [Reserved]

[Amdt. 179–7, 36 FR 14697, Aug. 10, 1971; Amdt. 179–10, 36 FR 21346, Nov. 6, 1971, as amended by Amdt. 179–25, 44 FR 20433, Apr. 5, 1979; Amdt. 179–40, 52 FR 13046, Apr. 20, 1987; Amdt. 179–45, 55 FR 52728, Dec. 21, 1990; Amdt. 179–52, 61 FR 28680, June 5, 1996; 68 FR 75760, Dec. 31, 2003]

#### § 179.102–4 Vinyl fluoride, stabilized.

Each tank used to transport vinyl fluoride, stabilized, must comply with the following special requirements:

(a) All plates for the tank must be fabricated of material listed in paragraph (a)(2) of this section, and appurtenances must be fabricated of material listed in paragraph (a)(1) or (a)(2) of this section.

(1) Stainless steel, ASTM A 240/A 240M (IBR, see § 171.7 of this subchapter), Type 304, 304L, 316 or 316L, in which case impact tests are not required; or

(2) Steel complying with ASTM Specification A 516 (IBR, see § 171.7 of this subchapter); Grade 70; ASTM Specification A 537 (IBR, see § 171.7 of this subchapter), Class 1; or AAR Specification TC 128, Grade B, in which case impact tests must be performed as follows:

(i) ASTM A 516/A 516M and A 537/A 537M material must meet the Charpy V-Notch test requirements, in longitudinal direction of rolling, of ASTM A 20/A 20M (IBR, see § 171.7 of this subchapter).

(ii) AAR Specification TC 128 material must meet the Charpy V-Notch test requirements, in longitudinal direction of rolling, of 15 ft.-lb. minimum average for 3 specimens, with a 10 ft.-lb. minimum for any one specimen, at minus 50 °F or colder, in accordance with ASTM A 370 (IBR, see § 171.7 of this subchapter).

(iii) Production welded test plates must—

(A) Be prepared in accordance with AAR Specifications for Tank Cars, appendix W, W4.00 (IBR, see § 171.7 of this subchapter);

(B) Include impact specimens of weld metal and heat affected zone prepared and tested in accordance with AAR Specifications for Tank Cars, appendix W, W9.00; and

(C) Meet the same impact requirements as the plate material.

(b) Insulation must be of approved material.

(c) Excess flow valves must be installed under all liquid and vapor valves, except safety relief valves.

(d) A thermometer well may be installed.

(e) Only an approved gaging device may be installed.

(f) A pressure gage may be installed.

(g) Aluminum, copper, silver, zinc, or an alloy containing any of these metals may not be used in the tank construction, or in fittings in contact with the lading.

(h) The jacket must be stenciled, adjacent to the water capacity stencil,

MINIMUM OPERATING TEMPERATURE — °F.

(i) The tank car and insulation must be designed to prevent the vapor pressure of the lading from increasing from the pressure at the maximum allowable filling density to the start-to-discharge pressure of the reclosing pressure relief valve within 30 days, at an ambient temperature of 90 °F.

[Amdt. 179-32, 48 FR 27707, June 16, 1983, as amended at 49 FR 24317, June 12, 1984; 49 FR 42736, Oct. 24, 1984; Amdt. 179-45, 55 FR 52728, Dec. 21, 1990; Amdt. 179-52, 61 FR 28680, June 5, 1996; 65 FR 58632, Sept. 29, 2000; 66 FR 33452, June 21, 2001; 66 FR 45186, 45390, Aug. 28, 2001; 67 FR 51660, Aug. 8, 2002; 68 FR 75758, 75760 Dec. 31, 2003]

#### § 179.102-17 Hydrogen chloride, refrigerated liquid.

Each tank car used to transport hydrogen chloride, refrigerated liquid must comply with the following special requirements:

(a) The tank car must comply with Specification DOT-105J600W and be designed for loading at minus 50 °F. or colder.

(b) All plates for the tank must be fabricated of material listed in paragraph (b)(2) of this section, and appurtenances must be fabricated of material listed in paragraph (b)(1) or (b)(2) of this section.

(1) Stainless steel, ASTM A 240/A 240M (IBR, see §171.7 of this subchapter), Type 304, 304L, 316, or 316L, in which case impact tests are not required; or

(2) Steel conforming to ASTM A 516/A 516M (IBR, see §171.7 of this subchapter), Grade 70; ASTM A 537/A 537M, (IBR, see §171.7 of this subchapter) Class 1; or AAR Specification TC 128, Grade B in which case impact tests must be performed as follows:

(i) ASTM A 516/A 516M and A 537/A 537M material must meet the Charpy V-notch test requirements, in longitudinal direction of rolling, of ASTM A 20/A 20M (IBR, see §171.7 of this subchapter).

(ii) AAR Specification TC 128 material must meet the Charpy V-notch test requirements, in longitudinal direction of rolling of 15 ft.-lb. minimum average for 3 specimens, with a 10 ft.-lb. minimum for any one specimen, at minus 50 °F or colder, in accordance with ASTM A 370 (IBR, see §171.7 of this subchapter).

(iii) Production welded test plates must—

(A) Be prepared in accordance with AAR Specifications for Tank Cars, appendix W, W4.00 (IBR, see §171.7 of this subchapter);

(B) include impact test specimens of weld metal and heat affected zone prepared and tested in accordance with AAR Specifications for Tank Cars, appendix W, W9.00; and

(C) meet the same impact requirements as the plate material.

(c) Insulation must be of approved material.

(d) Pressure relief valves must be trimmed with monel or other approved material and equipped with a rupture disc of silver, polytetrafluoroethylene coated monel, or tantalum. Each pressure relief device shall have the space between the rupture disc and the valve vented with a suitable auxiliary valve. The discharge from each pressure relief valve must be directed outside the protective housing.

(e) Loading and unloading valves must be trimmed with Hastelloy B or C, monel, or other approved material, and identified as “Vapor” or “Liquid”. Excess flow valves must be installed

## § 179.103

under all liquid and vapor valves, except safety relief valves.

(f) A thermometer well may be installed.

(g) Only an approved gaging device may be installed.

(h) A sump must be installed in the bottom of the tank under the liquid pipes.

(i) All gaskets must be made of, or coated with, polytetrafluoroethylene or other approved material.

(j) The tank car tank may be equipped with exterior cooling coils on top of the tank car shell.

(k) The jacket must be stenciled, adjacent to the water capacity stencil,

MINIMUM OPERATING TEMPERATURE — °F.

(l) The tank car and insulation must be designed to prevent the pressure of the lading from increasing from the pressure at the maximum allowable filling density to the start-to-discharge pressure of the pressure relief valve within 30 days, at an ambient temperature of 90° F.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 48 FR 50441, Nov. 1, 1983; 49 FR 24317, June 12, 1984; 49 FR 42736, Oct. 24, 1984; Amdt. 179-45, 55 FR 52728, Dec. 21, 1990; 66 FR 45390, Aug. 28, 2001; 67 FR 51660, Aug. 8, 2002; 68 FR 75758, 75760, Dec. 31, 2003]

### § 179.103 Special requirements for class 114A \* \* \* tank car tanks.

(a) In addition to the applicable requirements of §§ 179.100 and 179.101 the following requirements shall be complied with:

(b) [Reserved]

#### § 179.103-1 Type.

(a) Tanks built under this section may be of any approved cross section.

(b) Any portion of the tank shell not circular in cross section shall have walls of such thickness and be so reinforced that the stresses in the walls caused by a given internal pressure are no greater than the circumferential stresses which would exist under the same internal pressure in the wall of a tank of circular cross section designed in accordance with paragraphs § 179.100-6 (a) and (b), but in no case shall the wall thickness be less than that specified in § 179.101.

(c) [Reserved]

## 49 CFR Ch. I (10-1-08 Edition)

(d) Valves and fittings need not be mounted on the manway cover.

(e) One opening may be provided in each head for use in purging the tank interior.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-50, 60 FR 49077, Sept. 21, 1995]

### § 179.103-2 Manway cover.

(a) The manway cover must be an approved design.

(b) If no valves or measuring and sampling devices are mounted on manway cover, no protective housing is required.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-50, 60 FR 49077, Sept. 21, 1995]

### § 179.103-3 Venting, loading and unloading valves, measuring and sampling devices.

(a) Venting, loading and unloading valves, measuring and sampling devices, when used, shall be attached to a nozzle or nozzles on the tank shell or heads.

(b) These valves and appurtenances must be grouped in one location and, except as provided in § 179.103-5, must be equipped with a protective housing with cover, or may be recessed into tank shell with cover. An additional set grouped in another location may be provided. Protective housing with cover, when used, must have steel side-walls not less than three-fourths inch in thickness and a metal cover not less than one-fourth inch in thickness that can be securely closed. Underframe sills are an acceptable alternate to the protective housing cover, provided the arrangement is of approved design. For fittings recessed into tank shell, protective cover must be metal and not less than one-fourth inch in thickness.

(c) When tank car is used to transport liquefied flammable gases, the interior pipes of the loading, unloading, and sampling valves must be equipped with excess flow valves of approved design except when quick closing internal valves of approved design are used. When the interior pipe of the gaging device provides a means for the passage of lading from the interior to the exterior of the tank, it must be equipped with an excess flow valve of approved

design or with an orifice not exceeding 0.060 inch.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21348, Nov. 6, 1971]

**§ 179.103-4 Safety relief devices and pressure regulators.**

(a) Safety relief devices and pressure regulators must be located on top of the tank near the center of the car on a nozzle, mounting plate or recess in the shell. Through or stud bolts, if used, must not enter the tank.

(b) Metal guard of approved design must be provided to protect safety relief devices and pressure regulators from damage.

[Amdt. 179-10, 36 FR 21348, Nov. 6, 1971]

**§ 179.103-5 Bottom outlets.**

(a) In addition to or in place of the venting, loading and unloading valves, measuring and sampling devices as prescribed in § 179.103-3, tanks may be equipped with approved bottom outlet valves. If applied, bottom outlet valves must meet the following requirements:

(1) On cars with center sills, a ball valve may be welded to the outside bottom of the tank or mounted on a pad or nozzle with a tongue and groove or male and female flange attachment, but in no case shall the breakage groove or equivalent extend below the bottom flange of the center sill. On cars without continuous center sills, a ball valve may be welded to the outside bottom of the tank or mounted with a tongue and groove or male and female flange attachment on a pad attached to the outside bottom of the tank. The mounting pad must have a maximum thickness of 2½ inches measured on the longitudinal centerline of the tank. The valve operating mechanism must be provided with a suitable locking arrangement to insure positive closure during transit.

(2) When internal bottom outlet valve is used in liquefied flammable gas service, the outlet of the valve must be equipped with an excess flow valve of approved design, except when a quick-closing internal valve of approved design is used. Protective housing is not required.

(3) Bottom outlet must be equipped with a liquid tight closure at its lower end.

(b) Bottom outlet equipment must be of approved design and must meet the following requirements:

(1) The extreme projection of the bottom outlet equipment may not be more than allowed by appendix E of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter). All bottom outlet reducers and closures and their attachments shall be secured to the car by at least ¾ inch chain, or its equivalent, except that bottom outlet closure plugs may be attached by ¼ inch chain. When the bottom outlet closure is of the combination cap and valve type, the pipe connection to the valve shall be closed by a plug, cap, or approved quick coupling device. The bottom outlet equipment should include only the valve, reducers and closures that are necessary for the attachment of unloading fixtures. The permanent attachment of supplementary exterior fittings must be approved by the AAR Committee on Tank Cars.

(2) To provide for the attachment of unloading connections, the discharge end of the bottom outlet nozzle or reducer, the valve body of the exterior valve, or some fixed attachment thereto, shall be provided with one of the following arrangements or an approved modification thereof. (See appendix E. Fig. E17 of the AAR Specifications for Tank Cars for illustrations of some of the possible arrangements.)

(i) A bolted flange closure arrangement including a minimum 1-inch NPT pipe plug (see Fig. E17.1) or including an auxiliary valve with a threaded closure.

(ii) A threaded cap closure arrangement including a minimum 1-inch NPT pipe plug (see Fig. E17.2) or including an auxiliary valve with a threaded closure.

(iii) A quick-coupling device using a threaded plug closure of at least 1-inch NPT or having a threaded cap closure with a minimum 1-inch NPT pipe plug (see Fig. E17.3 through E17.5). A minimum 1-inch auxiliary test valve with a threaded closure may be substituted for the 1-inch pipe plug (see Fig. E17.6). If the threaded cap closure does not have a pipe plug or integral auxiliary

## § 179.200

test valve, a minimum 1-inch NPT pipe plug shall be installed in the outlet nozzle above the closure (see Fig. E17.7).

(iv) A two-piece quick-coupling device using a clamped dust cap must include an in-line auxiliary valve, either integral with the quick-coupling device or located between the primary bottom outlet valve and the quick-coupling device. The quick-coupling device closure dust cap or outlet nozzle shall be fitted with a minimum 1-inch NPT closure (see Fig. E17.8 and E17.9).

(3) The valve operating mechanism must be provided with a suitable locking arrangement to insure positive closure during transit.

(4) If the outlet nozzle extends 6 inches or more from shell of tank, a V-shaped breakage groove shall be cut (not cast) in the upper part to the outlet nozzle at a point immediately below the lowest part of valve closest to the tank. In no case may the nozzle wall thickness at the roof of the "V" be more than ¼-inch. On cars without continuous center sills, the breakage groove or its equivalent may not be more than 15 inches below the tank shell. On cars with continuous center sills, the breakage groove or its equivalent must be above the bottom of the center sill construction.

(5) The valve body must be of a thickness which will insure that accidental breakage of the outlet nozzle will occur at or below the "V" groove, or its equivalent, and will not cause distortion of the valve seat or valve.

[Amdt. 179-10, 36 FR 21348, Nov. 6, 1971, as amended by Amdt. 179-40, 52 FR 13046, Apr. 20, 1987; Amdt. 179-41, 52 FR 36672, Sept. 30, 1987; Amdt. 179-50, 60 FR 49077, Sept. 21, 1995; Amdt. 179-52, 61 FR 28680, June 5, 1996; Amdt. 179-53, 61 FR 51342, Oct. 1, 1996; 66 FR 45186, Aug. 28, 2001; 68 FR 75761, Dec. 31, 2003]

## 49 CFR Ch. I (10-1-08 Edition)

### Subpart D—Specifications for Non-Pressure Tank Car Tanks (Classes DOT-111AW and 115AW)

#### § 179.200 General specifications applicable to non-pressure tank car tanks (Class DOT-111).

##### § 179.200-1 Tank built under these specifications must meet the requirements of §§ 179.200, and 179.201.

##### § 179.200-3 Type.

Tank built under these specifications must be circular in cross section, with formed heads designed convex outward. When specified in § 179.201-1, the tank must have at least one manway or one expansion dome with manway, and such other external projections as are prescribed herein. When the tank is divided into compartments, each compartment must be treated as a separate tank.

[Amdt. 179-10, 36 FR 21348, Nov. 6, 1971]

##### § 179.200-4 Insulation.

(a) If insulation is applied, the tank shell and expansion dome when used must be insulated with an approved material. The entire insulation must be covered with a metal jacket of a thickness not less than 11 gauge (0.1196 inch) nominal (Manufacturer's Standard Gauge) and flashed around all openings so as to be weather tight. The exterior surface of a carbon steel tank and the inside surface of a carbon steel jacket must be given a protection coating.

(b) If insulation is a specification requirement, it shall be of sufficient thickness so that the thermal conductance at 60 °F is not more than 0.225 Btu per hour, per square foot, per degree F temperature differential, unless otherwise provided in § 179.201-1. If exterior heaters are attached to tank, the thickness of the insulation over each heater element may be reduced to one-half that required for the shell.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21349, Nov. 6, 1971; Amdt. 179-50, 60 FR 49078, Sept. 21, 1995]

**§ 179.200-6 Thickness of plates.**

(a) The wall thickness after forming of the tank shell, dome shell, and of 2:1 ellipsoidal heads must be not less than specified in §179.201-1, nor that calculated by the following formula:

$$t = \frac{Pd}{2SE}$$

Where:

$d$  = Inside diameter in inches;

$E$  = 0.9 Welded joint efficiency; except  $E=1.0$  for seamless heads;

$P$  = Minimum required bursting pressure in psig;

$S$  = Minimum tensile strength of plate material in p.s.i. as prescribed in §179.200-7;

$t$  = Minimum thickness of plate in inches after forming.

(b) The wall thickness after forming of 3:1 ellipsoidal heads must be not less than specified in §179.201-1, nor that calculated by the following formula:

$$t = \frac{Pd}{2SE} \times 1.83$$

Where:

$d$  = Inside diameter in inches;

$E$  = 0.9 Welded joint efficiency; except  $E=1.0$  for seamless heads;

$P$  = Minimum required bursting pressure in psig;

$S$  = Minimum tensile strength of plate material in p.s.i. as prescribed in §179.200-7;

$t$  = Minimum thickness of plate in inches after forming.

(c) The wall thickness after forming of a flanged and dished head must be not less than specified in §179.201-1, nor that calculated by the following formula:

$$t = \frac{5PL}{6SE}$$

Where:

$E$  = 0.9 Welded joint efficiency; except  $E=1.0$  for seamless heads;

$L$  = Main inside radius to which head is dished, measured on concave side in inches;

$P$  = Minimum required bursting pressure in psig;

$S$  = Minimum tensile strength of plate material in p.s.i. as prescribed in §179.200-7;

$t$  = Minimum thickness of plate in inches after forming.

(d) If plates are clad with material having tensile strength properties at

least equal to the base plate, the cladding may be considered a part of the base plate when determining thickness. If cladding material does not have tensile strength at least equal to the base plate, the base plate alone must meet the thickness requirements.

(e) For a tank constructed of longitudinal sections, the minimum width of bottom sheet of the tank must be 60 inches measured on the arc, but in all cases the width must be sufficient to bring the entire width of the longitudinal welded joint, including welds, above the bolster.

(f) For a tank built of one piece cylindrical sections, the thickness specified for bottom sheet must apply to the entire cylindrical section.

(g) See §179.200-9 for thickness requirements for a compartmented tank.

[Amdt. 179-10, 36 FR 21349, Nov. 6, 1971, as amended at 66 FR 45390, Aug. 28, 2001]

**§ 179.200-7 Materials.**

(a) Plate material used to fabricate the tank and, when used, expansion dome or manway nozzle material, must meet one of the following specifications with the indicated minimum tensile strength and elongation in the welded condition.

(b) *Carbon steel plate:* The maximum allowable carbon content must be 0.31 percent when the individual specification allows carbon content greater than this amount. The plates may be clad with other approved materials:

| Specifications                | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|-------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| AAR TC 128, Gr. B .....       | 81,000                                                          | 19                                                                 |
| ASTM A 516 <sup>2</sup> ..... | 70,000                                                          | 20                                                                 |

<sup>1</sup> Minimum stresses to be used in calculations.

<sup>2</sup> This specification is incorporated by reference (IBR, see §171.7 of this subchapter).

(c) *Aluminum alloy plate:* Aluminum alloy plate must be suitable for welding and comply with one of the following specifications (IBR, see §171.7 of this subchapter):



**§ 179.200-8**

| Specifications                            | Minimum tensile strength (p.s.i.) welded condition <sup>3,4</sup> | Minimum elongation in 2 inches (percent) 0 temper weld metal (longitudinal) |
|-------------------------------------------|-------------------------------------------------------------------|-----------------------------------------------------------------------------|
| ASTM B 209, Alloy 5052 <sup>1</sup> ..... | 25,000                                                            | 18                                                                          |
| ASTM B 209, Alloy 5083 <sup>2</sup> ..... | 38,000                                                            | 16                                                                          |
| ASTM B 209, Alloy 5086 <sup>1</sup> ..... | 35,000                                                            | 14                                                                          |
| ASTM B 209, Alloy 5154 <sup>1</sup> ..... | 30,000                                                            | 18                                                                          |
| ASTM B 209, Alloy 5254 <sup>1</sup> ..... | 30,000                                                            | 18                                                                          |
| ASTM B 209, Alloy 5454 <sup>1</sup> ..... | 31,000                                                            | 18                                                                          |
| ASTM B 209, Alloy 5652 <sup>1</sup> ..... | 25,000                                                            | 18                                                                          |

<sup>1</sup>For fabrication, the parent plate material may be 0, H112, or H32 temper, but design calculations must be based on minimum tensile strength shown.

<sup>2</sup>0 temper only.

<sup>3</sup>Weld filler metal 5556 must not be used.

<sup>4</sup>Maximum stresses to be used in calculations.

(d) *High alloy steel plate:* High alloy steel plate must comply with one of the following specifications:

| Specifications                                                                                 | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 304 .....  | 75,000                                                          | 30                                                                 |
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 304L ..... | 70,000                                                          | 30                                                                 |
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 316 .....  | 75,000                                                          | 30                                                                 |
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 316L ..... | 70,000                                                          | 30                                                                 |

<sup>1</sup>Maximum stresses to be used in calculations.

<sup>2</sup>High alloy steel materials used to fabricate tank and expansion dome, when used, must be tested in accordance with Practice A of ASTM Specification A 262 titled, "Standard Practices for Detecting Susceptibility to Intergranular Attack in Austenitic Stainless Steels" (IBR; see § 171.7 of this subchapter). If the specimen does not pass Practice A, Practice B or C must be used and the corrosion rates may not exceed the following:

| Test procedure   | Material                        | Corrosion rate i.p.m. |
|------------------|---------------------------------|-----------------------|
| Practice B ..... | Types 304, 304L, 316, and 316L. | 0.0040                |
| Practice C ..... | Type 304L .....                 | .0020                 |

Type 304L and Type 316L test specimens must be given a sensitizing treatment prior to testing. (A typical sensitizing treatment is 1 hour at 1250 F.)

(e) *Nickel plate:* Nickel plate must comply with the following specification (IBR, see § 171.7 of this subchapter):

**49 CFR Ch. I (10-1-08 Edition)**

| Specifications                | Minimum tensile strength (psi) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|-------------------------------|--------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM B 162 <sup>2</sup> ..... | 40,000                                                       | 20                                                                 |

(f) *Manganese-molybdenum steel plate:* Manganese-molybdenum steel plate must be suitable for fusion welding and comply with the following specification (IBR, see § 171.7 of this subchapter):

| Specifications          | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|-------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM A 302, Gr. B ..... | 80,000                                                          | 20                                                                 |

<sup>1</sup>Maximum stresses to be used in calculations.

(g) All parts and items of construction in contact with the lading must be made of material compatible with plate material and not subject to rapid deterioration by the lading, or be coated or lined with suitable corrosion resistant material.

(h) All external projections that may be in contact with the lading and all castings, forgings, or fabrications used for fittings or attachments to tank and expansion dome, when used, in contact with lading must be made of material to an approved specification. See AAR Specifications for Tank Cars, appendix M, M4.05 (IBR, see § 171.7 of this subchapter) for approved material specifications for castings for fittings.

[Amdt. 179-10, 36 FR 21349, Nov. 9, 1971; 36 FR 21893, Nov. 17, 1971, as amended by Amdt.179-28, 46 FR 49906, Oct. 8, 1981; Amdt. 179-40, 52 FR 13046, Apr. 20, 1987; Amdt. 179-52, 61 FR 28680, June 5, 1996; 66 FR 45186, Aug. 28, 2001; 67 FR 51660, Aug. 8, 2002; 68 FR 75761, Dec. 31, 2003; 70 FR 34076, June 13, 2005]

**§ 179.200-8 Tank heads.**

(a) All external tank heads must be an ellipsoid of revolution in which the major axis must equal the diameter of the shell and the minor axis must be one-half the major axis.

(b) Internal compartment tank heads may be 2:1 ellipsoidal, 3:1 ellipsoidal, or flanged and dished to thicknesses as specified in § 179.200-6. Flanged and

dished heads must have main inside radius not exceeding 10 feet, and inside knuckle radius must not be less than 3¾ inches for steel, alloy steel, or nickel tanks, and not less than 5 inches for aluminum alloy tanks.

[Amdt. 179-10, 36 FR 21350, Nov. 6, 1971]

**§ 179.200-9 Compartment tanks.**

(a) When a tank is divided into compartments, by inserting interior heads, interior heads must be inserted in accordance with AAR Specifications for Tank Cars, appendix E, E7.00 (IBR, see §171.7 of this subchapter), and must comply with the requirements specified in §179.201-1. Voids between compartment heads must be provided with at least one tapped drain hole at their lowest point, and a tapped hole at the top of the tank. The top hole must be closed, and the bottom hole may be closed, with not less than three-fourths inch and not more than 1½-inch solid pipe plugs having NPT threads.

(b) When the tank is divided into compartments by constructing each compartment as a separate tank, these tanks shall be joined together by a cylinder made of plate, having a thickness not less than that required for the tank shell and applied to the outside surface of tank head flanges. The cylinder shall fit the straight flange portion of the compartment tank head tightly. The cylinder shall contact the head flange for a distance of at least two times the plate thickness, or a minimum of 1 inch, whichever is greater. The cylinder shall be joined to the head flange by a full fillet weld. Distance from head seam to cylinder shall not be less than 1½ inches or three times the plate thickness, whichever is greater. Voids created by the space between heads of tanks joined together to form a compartment tank shall be provided with a tapped drain hole at their lowest point and a tapped hole at top of tank. The top hole shall be closed and the bottom hole may be closed with solid pipe plugs not less than ¾ inch nor more than 1½ inches having NPT threads.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21350, Nov. 6, 1971; 66 FR 45186, Aug. 28, 2001; 68 FR 75761, Dec. 31, 2003]

**§ 179.200-10 Welding.**

(a) All joints shall be fusion-welded in compliance with the requirements of AAR Specifications for Tank Cars, appendix W (IBR, see §171.7 of this subchapter). Welding procedures, welders and fabricators shall be approved.

(b) Welding is not permitted on or to ductile iron or malleable iron fittings.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21350, Nov. 6, 1971; 68 FR 75761, Dec. 31, 2003]

**§ 179.200-11 Postweld heat treatment.**

When specified in §179.201-1, after welding is complete, postweld heat treatment must be in compliance with the requirements of AAR Specifications for Tank Cars, appendix W (IBR, see §171.7 of this subchapter).

[68 FR 75761, Dec. 31, 2003]

**§ 179.200-13 Manway ring or flange, pressure relief device flange, bottom outlet nozzle flange, bottom washout nozzle flange and other attachments and openings.**

(a) These attachments shall be fusion welded to the tank and reinforced in an approved manner in compliance with the requirements of appendix E, figure 10, of the AAR Specifications for Tank Cars (IBR, see §171.7 of this subchapter).

(b) The opening in the manway ring must be at least 16 inches in diameter except that acid resistant lined manways must be at least 18 inches in diameter before lining.

(c) The manway ring or flange, shall be made of cast, forged or fabricated metal. The metal of the dome, tank, or nozzle must be compatible with the manway ring or flange, so that they may be welded together.

(d) The openings for the manway or other fittings shall be reinforced in an approved manner.

[Amdt. 179-40, 52 FR 13047, Apr. 20, 1987, as amended at 68 FR 75761, Dec. 31, 2003]

**§ 179.200-14 Expansion capacity.**

(a) Tanks shall have expansion capacity as prescribed in this subchapter. This capacity shall be provided in the tank for Class DOT-111A cars, or in a

## § 179.200-15

dome for Class DOT-103 and 104 type cars.

(b) For tank cars having an expansion dome, the expansion capacity is the total capacity of the tank and dome combined. The capacity of the dome shall be measured from the inside top of shell of tank to the inside top of dome or bottom of any vent pipe projecting inside of dome, except that when a pressure relief device is applied to side of dome, the effective capacity of the dome shall be measured from top of the pressure relief device opening inside of dome to inside top of shell of tank.

(c) The opening in the tank shell within the dome shall be at least 29 inches in diameter. When the opening in the tank shell exceeds 30 inches in diameter, the opening shall be reinforced in an approved manner. This additional reinforcement may be accomplished by the use of a dome opening of the flued-type as shown in appendix E, Figure E 10C of the AAR Specifications for Tank Cars or by the use of reinforcing as outlined in Appendix E, E3.04 and Figures E10K and E10L. When the opening in the tank shell is less than the inside diameter of the dome, and the dome pocket is not closed off in an approved manner, dome pocket drain holes shall be provided in the tank shell with nipples projecting inside the tank at least 1 inch.

(d) The dome head shall be of approved contour and shall be designed for pressure on concave side.

(e) Aluminum alloy domes: (1) The dome shell thickness shall be calculated by the formula in § 179.200-6(a).

(2) The dome head may be an ellipsoid of revolution in which the major axis shall be equal to the diameter of the dome shell and the minor axis shall be one-half the major axis. The thickness in this case shall be determined by using formula in § 179.200-6(a).

(3) The dome head, if dished, must be dished to a radius not exceeding 96 inches. Thickness of dished dome head must be calculated by the formula in § 179.200-6(c).

(4) Tank shell shall be reinforced by the addition of a plate equal to or greater than shell in thickness and the cross sectional area shall exceed metal removed for dome opening, or tank

## 49 CFR Ch. I (10-1-08 Edition)

shell shall be reinforced by a seamless saddle plate equal to or greater than shell in thickness and butt welded to tank shell. The reinforcing saddle plate shall be provided with a fluid opening having a vertical flange of the diameter of the dome for butt welding shell of dome to the flange. The reinforcing saddle plate shall extend about the dome a distance measured along shell of tank at least equal to the extension at top of tank. Other approved designs may be used.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21350, Nov. 6, 1971; Amdt. 179-28, 46 FR 49906, Oct. 8, 1981; Amdt. 179-52, 61 FR 28680, June 5, 1996; 66 FR 45186, 45390, Aug. 28, 2001; 68 FR 48571, Aug. 14, 2003]

### § 179.200-15 Closures for manways.

(a) Manway covers must be of approved type.

(b) Manway covers shall be designed to provide a secure closure of the manway.

(c) Manway covers must be of approved cast, forged, or fabricated metals. Malleable iron, if used, must comply with ASTM A 47 (IBR, see § 171.7 of this subchapter), Grade 35018. Cast iron manway covers must not be used.

(d) All joints between manway covers and their seats shall be made tight against leakage of vapor and liquid by use of gaskets of suitable material.

(e) For other manway cover requirements see § 179.201-1.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21350, Nov. 6, 1971; Amdt. 179-37, 50 FR 11066, Mar. 19, 1985; 68 FR 75762, Dec. 31, 2003]

### § 179.200-16 Gauging devices, top loading and unloading devices, venting and air inlet devices.

(a) When installed, these devices shall be of an approved design which will prevent interchange with any other fixture, and be tightly closed. Unloading pipes shall be securely anchored within the tank. Each tank or compartment may be equipped with one separate air connection.

(b) When the characteristics of the commodity for which the car is authorized are such that these devices must be equipped with valves or fittings to

permit the loading and unloading of the contents, these devices, including valves, shall be of an approved design, and be provided with a protective housing except when plug or ball type valves with operating handles removed are used. Provision shall be made for closing pipe connections of valves.

(c) A tank may be equipped with a vacuum relief valve of an approved design. Protective housing is not required.

(d) When using a visual gauging device on a car with a hinged manway cover, an outage scale visible through the manway opening shall be provided. If loading devices are applied to permit tank loading with cover closed, a telltale pipe may be provided. Telltale pipe shall be capable of determining that required outage is provided. Pipe shall be equipped with ¼ inch minimum NPT control valve mounted outside tank and enclosed within a housing. Other approved devices may be used in lieu of outage scale or telltale pipe.

(e) Bottom of tank shell may be equipped with a sump or siphon bowl, or both, welded or pressed into the shell. Such sumps or siphon bowls, if applied are not limited in size and must be made of cast, forged, or fabricated metal. Each sump or siphon bowl must be of good welding quality in conjunction with the metal of the tank shell. When sump or siphon bowl is pressed in the bottom of the tank shell, the wall thickness of the pressed section must not be less than that specified for the shell. The section of a circular cross section tank to which a sump or siphon bowl is attached need not comply with the out-of-roundness requirement specified in appendix W, W14.06, of the AAR Specifications for Tank Cars. Any portion of a sump or siphon bowl not forming a part of a cylinder of revolution must have walls of such thickness and be so reinforced that the stresses in the walls caused by a given internal pressure are not greater than the circumferential stress which would exist under the same internal pressure in the wall of a tank of circular cross section designed in accordance with § 179.200-6 (a) and (d). In no case shall the wall thickness be less than that specified in § 179.201-1.

(f) When top loading and discharge devices, or venting and air inlet devices are installed with exposed piping to a removed location, shutoff valves must be applied directly to reinforcing pads or nozzles at their communication through the tank shell, and must be enclosed in a protective housing with provision for a seal. The piping must include breakage grooves, and suitable bracing. Relief valves must be applied to liquid lines for protection in case lading is trapped. Provision must be made to insure closure of the valves while the car is in transit.

(g) Protective housing, when required, must be fabricated of approved material and have cover and sidewalls not less than 0.119 inch in thickness.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21350, Nov. 6, 1971; Amdt. 179-52, 61 FR 28680, June 5, 1996; 69 FR 54047, Sept. 7, 2004]

#### § 179.200-17 Bottom outlets.

(a) If indicated in § 179.201-1, tank may be equipped with bottom outlet. Bottom outlet, if applied, must comply with the following requirements:

(1) The extreme projection of the bottom outlet equipment may not be more than that allowed by appendix E of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter). All bottom outlet reducers and closures and their attachments shall be secured to the car by at least ⅜-inch chain, or its equivalent, except that the bottom outlet closure plugs may be attached by ¼-inch chain. When the bottom outlet closure is of the combination cap and valve type, the pipe connection to the valve shall be closed by a plug, cap, or approved quick coupling device. The bottom outlet equipment should include only the valve, reducers and closures that are necessary for the attachment of unloading fixtures. The permanent attachment of supplementary exterior fittings shall be approved by the AAR Committee on Tank Cars.

(2) Bottom outlet must be of approved construction, and be provided with a liquid-tight closure at its lower end.

(3) On cars with center sills, a ball valve may be welded to the outside bottom of the tank or mounted on a pad or

nozzle with a tongue and groove or male and female flange attachment. In no case shall the breakage groove or equivalent extend below the bottom flange of the center sill. On cars without continuous center sills, a ball valve may be welded to the outside bottom of the tank or mounted with a tongue and groove or male and female flange attachment on a pad attached to the outside bottom of the tank. The mounting pad must have a maximum thickness of 2½ inches measured on the longitudinal centerline of the tank. The valve operating mechanism must be provided with a suitable locking arrangement to insure positive closure during transit.

(4) The valve operating mechanism for valves applied to the interior of the tank, and outlet nozzle construction, must insure against the unseating of the valve due to stresses or shocks incident to transportation.

(5) Bottom outlet nozzle of interior valves and the valve body of exterior valves, must be of cast, fabricated, or forged metal. If welded to tank, they must be of good weldable quality in conjunction with metal of tank.

(6) To provide for the attachment of unloading connections, the discharge end of the bottom outlet nozzle or reducer, the valve body of the exterior valve, or some fixed attachment thereto, shall be provided with one of the following arrangements or an approved modification thereof. (See appendix E. Fig. E17 of the AAR Specifications for Tank Cars for illustrations of some of the possible arrangements.)

(i) A bolted flange closure arrangement including a minimum 1-inch NPT pipe plug (see Fig. E17.1) or including an auxiliary valve with a threaded closure.

(ii) A threaded cap closure arrangement including a minimum 1-inch NPT pipe plug (see Fig. E17.2) or including an auxiliary valve with a threaded closure.

(iii) A quick-coupling device using a threaded plug closure of at least 1-inch NPT or having a threaded cap closure with a minimum 1-inch NPT pipe plug (see Fig. E17.3 through E17.5). A minimum 1-inch auxiliary test valve with a threaded closure may be substituted for the 1-inch pipe plug (see Fig. E17.6). If the threaded cap closure does not

have a pipe plug or integral auxiliary test valve, a minimum 1-inch NPT pipe plug shall be installed in the outlet nozzle above the closure (see Fig. E17.7).

(iv) A two-piece quick-coupling device using a clamped dust cap must include an in-line auxiliary valve, either integral with the quick-coupling device or located between the primary bottom outlet valve and the quick-coupling device. The quick-coupling device closure dust cap or outlet nozzle shall be fitted with a minimum 1-inch NPT closure (see Fig. E17.8 and E17.9).

(7) If the outlet nozzle extends 6 inches or more from the shell of the tank, a V-shaped breakage groove shall be cut (not cast) in the upper part of the outlet nozzle at a point immediately below the lowest part of valve closest to the tank. In no case may the nozzle wall thickness at the root of the "V" be more than ¼ inch. The outlet nozzle on interior valves or the valve body on exterior valves may be steam jacketed, in which case the breakage groove or its equivalent must be below the steam chamber but above the bottom of center sill construction. If the outlet nozzle is not a single piece, or if exterior valves are applied, provisions shall be made for the equivalent of the breakage groove. On cars without continuous center sills, the breakage groove or its equivalent must be no more than 15 inches below the tank shell. On cars with continuous center sills, the breakage groove or its equivalent must be above the bottom of the center sill construction.

(8) The flange on the outlet nozzle or the valve body of exterior valves must be of a thickness which will prevent distortion of the valve seat or valve by any change in contour of the shell resulting from expansion of lading, or other causes, and which will insure that accidental breakage of the outlet nozzle will occur at or below the "V" groove, or its equivalent.

(9) The valve must have no wings or stem projecting below the "V" groove or its equivalent. The valve and seat must be readily accessible or removable for repairs, including grinding.

(10) The valve operating mechanism on interior valves must have means for compensating for variation in the

vertical diameter of the tank produced by expansion, weight of the liquid contents, or other causes, and may operate from the interior of the tank, but in the event the rod is carried through the dome, or tank shell, leakage must be prevented by packing in stuffing box or other suitable seals and a cap.

(b) If indicated in §179.201–1, tank may be equipped with bottom washout of approved construction. If applied, bottom washout shall be in accordance with the following requirements:

(1) The extreme projection of the bottom washout equipment may not be more than that allowed by appendix E of the AAR Specifications for Tank Cars.

(2) Bottom washout shall be of cast, forged or fabricated metal. If welded to tank, they shall be of good weldable quality in conjunction with metal of tank.

(3) If the washout nozzle extends 6 inches or more from the shell of the tank, a V-shaped breakage groove shall be cut (not cast) in the upper part of the nozzle at a point immediately below the lowest part of the inside closure seat or plug. In no case may the nozzle wall thickness at the root of the “V” be more than ¼ inch. Where the nozzle is not a single piece, provisions shall be made for the equivalent of the breakage groove. The nozzle must be of a thickness to insure that accidental breakage will occur at or below the “V” groove or its equivalent. On cars without continuous center sills, the breakage groove or its equivalent may not be more than 15 inches below the outer shell. On cars with continuous center sills, the breakage groove or its equivalent must be above the bottom of the center sill construction.

(4) The closure plug and seat must be readily accessible or removable for repairs, including grinding.

(5) The closure of the washout nozzle must be equipped with a ¾-inch solid screw plug. Plug must be attached by at least a ¼-inch chain.

(6) Joints between closures and their seats may be gasketed with suitable material.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21351, Nov. 6, 1971; Amdt. 179–40, 52 FR 13047, Apr. 20, 1987; 68 FR 75762, Dec. 31, 2003]

**§ 179.200–19 Reinforcements, when used, and appurtenances not otherwise specified.**

(a) All attachments to tank and dome shall be applied by approved means. Rivets if used shall be caulked inside and outside.

(b) Reinforcing pads must be used between external brackets and shells if the attachment welds exceed 6 lineal inches of ¼-inch fillet or equivalent weld per bracket or bracket leg. When reinforcing pads are used, they must not be less than one-fourth inch in thickness, have each corner rounded to a 1 inch minimum radius, and be attached to the tank by continuous fillet welds except for venting provisions. The ultimate shear strength of the bracket to reinforcing pad weld must not exceed 85 percent of the ultimate shear strength of the reinforcing pad to tank weld.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21351, Nov. 6, 1971]

**§ 179.200–21 Closures for openings.**

(a) All plugs shall be solid, with NPT threads, and shall be of a length which will screw at least 6 threads inside the face of fitting or tank. Plugs, when inserted from the outside of tank heads, shall have the letter “S” at least ⅜ inch in size stamped with steel stamp or cast on the outside surface to indicate the plug is solid.

(b) [Reserved]

**§ 179.200–22 Test of tanks.**

(a) Each tank shall be tested by completely filling the tank and dome or nozzles with water, or other liquid having similar viscosity, of a temperature which shall not exceed 100 °F. during the test; and applying the pressure prescribed in §179.201–1. Tank shall hold the prescribed pressure for at least 10 minutes without leakage or evidence of distress. All rivets and closures, except

## § 179.200–23

safety relief valves or safety vents, shall be in place when test is made.

(b) Insulated tanks shall be tested before insulation is applied.

(c) Rubber-lined tanks shall be tested before rubber lining is applied.

(d) Caulking of welded joints to stop leaks developed during the foregoing tests is prohibited. Repairs in welded joints shall be made as prescribed in AAR Specifications for Tank Cars, appendix W (IBR, see §171.7 of this subchapter).

[29 FR 18995, Dec. 29, 1964, as amended at 68 FR 75762, Dec. 31, 2003]

## § 179.200–23 Tests of pressure relief valves.

(a) Each valve shall be tested by air or gas for compliance with §179.15 before being put into service.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, as amended at 62 FR 51561, Oct. 1, 1997]

## § 179.200–24 Stamping.

(a) To certify that the tank complies with all specification requirements,

## 49 CFR Ch. I (10–1–08 Edition)

each tank shall be plainly and permanently stamped in letters and figures at least  $\frac{3}{8}$  inch high into the metal near the center of both outside heads as follows:

|                                                  | Example of required stamping |
|--------------------------------------------------|------------------------------|
| Specification .....                              | DOT-111A                     |
| Material .....                                   | ASTM A 516–GR 70             |
| Cladding material (if any) .....                 | ASTM A240–304 Clad           |
| Tank builder's initials .....                    | ABC                          |
| Date of original test .....                      | 00–0000                      |
| Car assembler (if other than tank builder) ..... | DEF                          |

(b) On Class DOT-111 tank cars, the last numeral of the specification number may be omitted from the stamping; for example, DOT-111A100W.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179–10, 36 FR 21351, Nov. 6, 1971; Amdt. 179–52, 61 FR 28680, June 5, 1996; 68 FR 48571, Aug. 14, 2003]

## § 179.201 Individual specification requirements applicable to non-pressure tank car tanks.

### § 179.201–1 Individual specification requirements.

In addition to §179.200, the individual specification requirements are as follows:

| DOT Specification <sup>1</sup> | Insulation            | Bursting pressure (psig) | Minimum plate thickness (inches) | Test pressure (psig) | Bottom outlet  | Bottom washout | References (179.201 - ***) |
|--------------------------------|-----------------------|--------------------------|----------------------------------|----------------------|----------------|----------------|----------------------------|
| 111A60ALW1 ...                 | Optional .....        | 240                      | $\frac{1}{2}$                    | 60                   | Optional ..... | Optional ..... | 6(a).                      |
| 111A60ALW2 ...                 | Optional .....        | 240                      | $\frac{1}{2}$                    | 60                   | No .....       | Optional ..... | 6(a).                      |
| 111A60W1 .....                 | Optional .....        | 240                      | $\frac{7}{16}$                   | 60                   | Optional ..... | Optional ..... | 6(a).                      |
| 111A60W2 .....                 | Optional .....        | 240                      | $\frac{7}{16}$                   | 60                   | No .....       | Optional ..... | 3, 6(b).                   |
| 111A60W5 .....                 | Optional .....        | 240                      | $\frac{7}{16}$                   | 60                   | No .....       | No .....       | 4, 5, 6(a), 6(c).          |
| 111A60W6 .....                 | Optional .....        | 240                      | $\frac{7}{16}$                   | 60                   | Optional ..... | Optional ..... | 4, 5, 6(a).                |
| 111A60W7 .....                 | Optional .....        | 240                      | $\frac{7}{16}$                   | 60                   | No .....       | No .....       | 6(a).                      |
| 111A100ALW1                    | Optional .....        | 500                      | $\frac{5}{8}$                    | 100                  | Optional ..... | Optional ..... | 6(a).                      |
| 111A100ALW2                    | Optional .....        | 500                      | $\frac{5}{8}$                    | 100                  | No .....       | Optional ..... | 6(a).                      |
| 111A100W1 .....                | Optional .....        | 500                      | $\frac{7}{16}$                   | 100                  | Optional ..... | Optional ..... | 6(a).                      |
| 111A100W2 .....                | Optional .....        | 500                      | $\frac{7}{16}$                   | 100                  | No .....       | Optional ..... | 6(a).                      |
| 111A100W3 .....                | Yes .....             | 500                      | $\frac{7}{16}$                   | 100                  | Optional ..... | Optional ..... | 6(a).                      |
| 111A100W4 .....                | Yes (see 179.201–11). | 500                      | $\frac{7}{16}$                   | 100                  | No .....       | No .....       | 6(a), 8, 10.               |
| 111A100W5 .....                | Optional .....        | 500                      | $\frac{7}{16}$                   | 100                  | No .....       | No .....       | 3.                         |
| 111A100W6 .....                | Optional .....        | 500                      | $\frac{7}{16}$                   | 100                  | Optional ..... | Optional ..... | 4, 5, 6(a) and 6(c).       |
| 111A100W7 .....                | Optional .....        | 500                      | $\frac{7}{16}$                   | 100                  | No .....       | No .....       | 4, 5, 6(c).                |

<sup>1</sup>Tanks marked "ALW" are constructed from aluminum alloy plate; "AN" nickel plate; "CW," "DW," "EW," "W6," and "W7" high alloy steel or manganese-molybdenum steel plate; and those marked "BW" or "W5" must have an interior lining that conforms to §179.201–3.

[Amdt. 179–52, 61 FR 28680, June 5, 1996, as amended by 66 FR 45390, Aug. 28, 2001; 68 FR 48571, Aug. 14, 2003]

## § 179.201-2 [Reserved]

## § 179.201-3 Lined tanks.

(a) *Rubber-lined tanks.* (1) Each tank or each compartment thereof must be lined with acid-resistant rubber or other approved rubber compound vulcanized or bonded directly to the metal tank, to provide a nonporous laminated lining, at least  $\frac{5}{32}$ -inch thick, except overall rivets and seams formed by riveted attachments in the lining must be double thickness. The rubber lining must overlap at least  $1\frac{1}{2}$  inches at all edges which must be straight and be beveled to an angle of approximately  $45^\circ$ , or butted edges of lining must be sealed with a 3-inch minimum strip of lining having  $45^\circ$  beveled edges.

(2) As an alternate method, the lining may be joined with a skived butt seam then capped with a separate strip of lining 3 inches wide having  $45^\circ$  beveled edges. An additional rubber reinforcing pad at least  $4\frac{1}{2}$  feet square and at least  $\frac{1}{2}$ -inch thick must be applied by vulcanizing to the lining on bottom of tank directly under the manway opening. The edges of the rubber pad must be beveled to an angle of approximately  $45^\circ$ . An opening in this pad for sump is permitted. No lining must be under tension when applied except due to conformation over rivet heads. Interior of tank must be free from scale, oxidation, moisture, and all foreign matter during the lining operation.

(3) Other approved lining materials may be used provided the material is resistant to the corrosive or solvent action of the lading in the liquid or gas phase and is suitable for the service temperatures.

(b) Before a tank car tank is lined with rubber, or other rubber compound, a report certifying that the tank and its equipment have been brought into compliance with spec. DOT-111A60W5 or 111A100W5 must be furnished by car owner to the party who is to apply the lining. A copy of this report in approved form, certifying that tank has been lined in compliance with all requirements of one of the above specifications, must be furnished by party lining tank to car owner. Reports of the latest lining application must be retained by the car owner until the

next relining has been accomplished and recorded.

(c) All rivet heads on inside of tank must be buttonhead, or similar shape, and of uniform size. The under surface of heads must be driven tight against the plate. All plates, castings and rivet heads on the inside of the tank must be calked. All projecting edges of plates, castings and rivet heads on the inside of the tank must be rounded and free from fins and other irregular projections. Castings must be free from porosity.

(d) All surfaces of attachments or fittings and their closures exposed to the lading must be covered with at least  $\frac{1}{8}$ -inch acid resistant material. Attachments made of metal not affected by the lading need not be covered with rubber or other acid resistant material.

(e) Hard rubber or polyvinyl chloride may be used for pressure retaining parts of safety vents provided the material is resistant to the corrosive or solvent action of the lading in the liquid or gas phase and is suitable for the service temperatures.

(f) Polyvinyl chloride lined tanks. Tank car tanks or each compartment thereof may be lined with elastomeric polyvinyl chloride having a minimum lining thickness of three thirty-seconds inch.

(g) Polyurethane lined tanks. Tank car tanks or each compartment thereof may be lined with elastomeric polyurethane having a minimum lining thickness of one-sixteenth inch.

[Amdt. 179-10, 36 FR 21352, Nov. 6, 1971, as amended at 66 FR 45186, Aug. 28, 2001; 68 FR 48571, Aug. 14, 2003]

## § 179.201-4 Material.

All fittings, tubes, and castings and all projections and their closures, except for protective housing, must also meet the requirements specified in ASTM A 262 (IBR, see § 171.7 of this subchapter), except that when preparing the specimen for testing the carburized surface may be finished by grinding or machining.

[68 FR 75762, Dec. 31, 2003]



## § 179.201-5

### § 179.201-5 Postweld heat treatment and corrosion resistance.

(a) Tanks and attachments welded directly thereto must be postweld heat treated as a unit at the proper temperature except as indicated below. Tanks and attachments welded directly thereto fabricated from ASTM A 240/A 240M (IBR, see §171.7 of this subchapter) Type 430A, Type 304 and Type 316 materials must be postweld heat treated as a unit and must be tested to demonstrate that they possess the corrosion resistance specified in §179.200-7(d), Footnote 2. Tanks and attachments welded directly thereto, fabricated from ASTM A 240/A 240M Type 304L or Type 316L materials are not required to be postweld heat treated.

(b) Tanks and attachments welded directly thereto, fabricated from ASTM A 240/A 240M Type 304L and Type 316 materials must be tested to demonstrate that they possess the corrosion resistance specified in §179.200-7(d), Footnote 2.

[68 FR 75762, Dec. 31, 2003]

### § 179.201-6 Manways and manway closures.

(a) The manway cover for spec. DOT 104W, 111A60-ALW1, 111A60W1, 111A100ALW1, 111A-100W1, 111A100W3, or 111A100W6 must be designed to make it impossible to remove the cover while the interior of the tank is subjected to pressure.

(b) The manway cover for spec. DOT 11A60W5, or 111A100W5 must be made of a suitable metal. The top, bottom and edge of manway cover must be acid resistant material covered as prescribed in §179.201-3. Through-bolt holes must be lined with acid resistant material at least one-eighth inch in thickness. Cover made of metal not affected by the lading need not be acid resistant material covered.

(c) The manway ring and cover for specifications DOT-103CW, 103DW, 103EW, 111360W7, or 11A100W6 must be made of the metal and have the same inspection procedures specified in AAR Specifications for Tank Cars, appendix

## 49 CFR Ch. I (10-1-08 Edition)

M, M3.03 (IBR, see §171.7 of this subchapter).

[Amdt. 179-10, 36 FR 21353, Nov. 6, 1971; 66 FR 45186, Aug. 28, 2001; 68 FR 48571, Aug. 14, 2003; 68 FR 75762, Dec. 31, 2003]

### § 179.201-8 Sampling device and thermometer well.

(a) Sampling valve and thermometer well are not specification requirements. When used, they must be of approved design, made of metal not subject to rapid deterioration by lading, and must withstand a pressure of 100 psig without leakage. Interior pipes of the sampling valve must be equipped with excess flow valves of an approved design. Interior pipe of thermometer well must be closed by an approved valve attached close to fitting where it passes through the tank and closed by a screw plug. Other approved arrangements that permit testing thermometer well for leaks without complete removal of the closure may be used.

(b) [Reserved]

[Amdt. 179-10, 36 FR 21348, Nov. 6, 1971, as amended at 66 FR 45390, Aug. 28, 2001]

### § 179.201-9 Gauging device.

A gauging device of an approved design must be applied to permit determining the liquid level of the lading. The gauging device must be made of materials not subject to rapid deterioration by the lading. When the interior pipe of the gauging device provides a means for passage of the lading from the interior to the exterior of the tank, it must be equipped with an excess flow valve of an approved design. If the opening for passage of lading through the gauging device is not more than 0.060 inch diameter an excess flow valve is not required. The gauging device must be provided with a protective housing.

[Amdt. 179-10, 36 FR 21353, Nov. 6, 1971]

### § 179.201-10 Water capacity marking.

(a) Water capacity of the tank in pounds stamped plainly and permanently in letters and figures at least  $\frac{3}{8}$  inch high into the metal of the tank immediately below the stamped marks specified in §179.200-24(a). This mark shall also be stenciled on the jacket immediately below the dome platform

and directly behind or within 3 feet of the right or left side of the ladder, or ladders, if there is a ladder on each side of the tank, in letters and figures at least 1½ inches high as follows:

WATER CAPACITY

000000 Pounds

(b) [Reserved]

#### § 179.201-11 Insulation.

(a) Insulation shall be of sufficient thickness so that the thermal conductance at 60 °F. is not more than 0.075 Btu per hour, per square foot, per degree F. temperature differential.

(b) [Reserved]

#### §§ 179.202—179.202-22 [Reserved]

#### § 179.220 General specifications applicable to nonpressure tank car tanks consisting of an inner container supported within an outer shell (class DOT-115).

#### § 179.220-1 Tanks built under these specifications must meet the requirements of §§ 179.220 and 179.221.

#### § 179.220-3 Type.

(a) Tanks built under these specifications must consist of an inner container, a support system for the inner container, and an outer shell.

(b) The inner container must be a fusion welded tank of circular cross section with formed heads designed convex outward and must have a manway on top of the tank as prescribed herein. When the inner container is divided into compartments, each compartment must be considered a separate container.

(c) The outer shell must be a fusion welded tank with formed heads designed convex outward.

[Amdt. 179-9, 36 FR 21340, Nov. 6, 1971]

#### § 179.220-4 Insulation.

The annular space between the inner container and the outer shell must contain an approved insulation material.

[Amdt. 179-9, 36 FR 21340, Nov. 6, 1971]

#### § 179.220-6 Thickness of plates.

(a) The wall thickness, after forming of the inner container shell and 2:1 ellipsoidal heads must be not less than specified in § 179.221-1, or not less than that calculated by the following formula:

$$t = \frac{Pd}{2SE}$$

Where:

$d$  = Inside diameter in inches;

$E$  = 0.9 welded joint efficiency; except  $E=1.0$  for seamless heads;

$P$  = Minimum required bursting pressure in psig;

$S$  = Minimum tensile strength of plate material in p.s.i. as prescribed in AAR Specifications for Tank Cars, appendix M, Table M1;

$t$  = Minimum thickness of plate in inches after forming.

(b) The wall thickness after forming of the inner container heads, if flanged and dished, must be not less than specified in § 179.221-1, or not less than that calculated by the following formula:

$$t = \frac{5PL}{6SE}$$

Where:

$E$  = 0.9 welded joint efficiency; except  $E=1.0$  for seamless heads;

$L$  = Main inside radius to which head is dished, measured on concave side in inches;

$P$  = Minimum required bursting pressure in psig;

$S$  = Minimum tensile strength of plate material in psi as prescribed in AAR Specifications for Tank Cars, appendix M, Table M1 (IBR, see § 171.7 of this subchapter);

$t$  = Minimum thickness of plate in inches after forming.

(c) The wall thickness after forming of the cylindrical section and heads of the outer shell must be not less than seven-sixteenths of an inch.

(d) See § 179.220-9 for plate thickness requirements for inner container when divided into compartments.

[Amdt. 179-9, 36 FR 21340, Nov. 6, 1971, as amended at 66 FR 45390, Aug. 28, 2001; 68 FR 75762, Dec. 31, 2003]

#### § 179.220-7 Materials.

(a) The plate material used to fabricate the inner container and nozzles

## § 179.220-8

must meet one of the following specifications and with the indicated minimum tensile strength and elongation in the welded condition.

(b) Carbon steel plate: The maximum allowable carbon content must be 0.31 percent when the individual specification allows carbon content greater than this amount. The plates may be clad with other approved materials.

| Specifications                         | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|----------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| AAR TC 128, Gr. B .....                | 81,000                                                          | 19                                                                 |
| ASTM A 516 <sup>2</sup> , Gr. 70 ..... | 70,000                                                          | 20                                                                 |

<sup>1</sup> Maximum stresses to be used in calculations.

<sup>2</sup> This specification is incorporated by reference (IBR, see § 171.7 of this subchapter).

(c) Aluminum alloy plate: Aluminum alloy plate must be suitable for welding and comply with one of the following specifications (IBR, see § 171.7 of this subchapter): \* \* \*

| Specifications                            | Minimum tensile strength (p.s.i.) welded condition <sup>3,4</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|-------------------------------------------|-------------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM B 209, Alloy 5052 <sup>1</sup> ..... | 25,000                                                            | 18                                                                 |
| ASTM B 209, Alloy 5083 <sup>2</sup> ..... | 38,000                                                            | 16                                                                 |
| ASTM B 209, Alloy 5086 <sup>1</sup> ..... | 35,000                                                            | 14                                                                 |
| ASTM B 209, Alloy 5154 <sup>1</sup> ..... | 30,000                                                            | 18                                                                 |
| ASTM B 209, Alloy 5254 <sup>1</sup> ..... | 30,000                                                            | 18                                                                 |
| ASTM B 209, Alloy 5454 <sup>1</sup> ..... | 31,000                                                            | 18                                                                 |
| ASTM B 209, Alloy 5652 <sup>1</sup> ..... | 25,000                                                            | 18                                                                 |

<sup>1</sup> For fabrication, the parent plate material may be 0 H112, or H32 temper, but design calculations must be based on the minimum tensile strength shown.

<sup>2</sup> 0 temper only.

<sup>3</sup> Weld filler metal 5556 must not be used.

<sup>4</sup> Maximum stresses to be used in calculations.

(d) High alloy steel plate: High alloy steel plate must comply with one of the following specifications (IBR, see § 171.7 of this subchapter):

| Specifications                                                                                 | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 304 .....  | 75,000                                                          | 30                                                                 |
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 304L ..... | 70,000                                                          | 30                                                                 |

## 49 CFR Ch. I (10-1-08 Edition)

| Specifications                                                                                 | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|------------------------------------------------------------------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 316 .....  | 74,000                                                          | 30                                                                 |
| ASTM A 240/A 240M (incorporated by reference; see § 171.7 of this subchapter), Type 316L ..... | 70,000                                                          | 30                                                                 |

<sup>1</sup> Maximum stresses to be used in calculations.

(e) Manganese-molybdenum steel plate: Manganese-molybdenum steel plate must be suitable for fusion welding and must comply with the following specification (IBR, see § 171.7 of this subchapter):

| Specifications          | Minimum tensile strength (p.s.i.) welded condition <sup>1</sup> | Minimum elongation in 2 inches (percent) weld metal (longitudinal) |
|-------------------------|-----------------------------------------------------------------|--------------------------------------------------------------------|
| ASTM A 302, Gr. B ..... | 80,000                                                          | 20                                                                 |

<sup>1</sup> Maximum stresses to be used in calculations.

(f) Plate materials used to fabricate the outer shell and heads must be those listed in paragraphs (b), (c), (d), or (e) of this section. The maximum allowable carbon content must be 0.31 percent when the individual specification allows carbon content greater than this amount. The plates may be clad with other approved materials.

(g) All appurtenances on the inner container in contact with the lading must be made of approved material compatible with the plate material of the inner container. These appurtenances must not be subject to rapid deterioration by the lading, or must be coated or lined with suitable corrosion resistant material. See AAR Specifications for Tank Cars, appendix M, M4.05 for approved material specifications for castings for fittings.

[Amdt. 179-9, 36 FR 21340, Nov. 6, 1971, as amended by Amdt. 179-28, 46 FR 49906, Oct. 8, 1981; Amdt. 179-40, 52 FR 13048, Apr. 20, 1987; Amdt. 179-52, 61 FR 28681, June 5, 1996; 66 FR 45186, Aug. 28, 2001; 67 FR 51660, Aug. 8, 2002; 68 FR 75762, Dec. 31, 2003]

## § 179.220-8 Tank heads.

(a) Tank heads of the inner container, inner container compartments

and outer shell must be of approved contour, and may be flanged and dished or ellipsoidal for pressure on concave side.

(b) Flanged and dished heads must have main inside radius not exceeding 10 feet and inside knuckle radius must be not less than  $3\frac{3}{4}$  inches for steel and alloy steel tanks nor less than 5 inches for aluminum alloy tanks.

(c) Ellipsoidal heads must be an ellipsoid of revolution in which the major axis must equal the diameter of the shell and the minor axis must be one-half the major axis.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971]

#### § 179.220-9 Compartment tanks.

(a) The inner container may be divided into compartments by inserting interior heads, or by fabricating each compartment as a separate container and joining with a cylinder, or by fabricating each compartment as a separate tank without a joining cylinder. Each compartment must be capable of withstanding, without evidence of yielding or leakage, the required test pressure applied in each compartment separately, or in any combination of compartments.

(b) When the inner container is divided into compartments by fabricating each compartment as a separate container and joining with a cylinder, the cylinder must have a plate thickness not less than that required for the inner container shell and must be applied to the outside surface of the straight flange portion of the container head. The cylinder must fit the straight flange tightly for a distance of at least two times the plate thickness, or 1 inch, whichever is greater and must be joined to the straight flange by a full fillet weld. Distance from fillet weld seam to container head seam must be not less than  $1\frac{1}{2}$  inches or three times the plate thickness, whichever is greater.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971]

#### § 179.220-10 Welding.

(a) All joints must be fusion welded in compliance with AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter). Welding pro-

cedures, welders, and fabricators shall be approved.

(b) Radioscopy of the outer shell is not a specification requirement.

(c) Welding is not permitted on or to ductile iron or malleable iron fittings.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971, as amended at 68 FR 75762, Dec. 31, 2003]

#### § 179.220-11 Postweld heat treatment.

(a) Postweld heat treatment of the inner container is not a specification requirement.

(b) Postweld heat treatment of the cylindrical portions of the outer shell to which the anchorage or draft sills are attached must comply with AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter).

(c) When cold formed heads are used on the outer shell they must be heat treated before welding to shell if postweld heat treatment is not practicable due to assembly procedures.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971, as amended at 68 FR 75762, Dec. 31, 2003]

#### § 179.220-13 Inner container manway nozzle and cover.

(a) Inner container manway nozzle must be of approved design with access opening at least 18 inches inside diameter, or at least 14 inches by 18 inches obround or oval.

(b) Manway covers must be of approved type. Design must provide a secure closure of the manway and must make it impossible to remove the cover while the tank interior is under pressure.

(c) All joints between manway covers and their seats must be made tight against leakage of vapor and liquid by use of suitable gaskets.

(d) Manway covers must be cast, forged, or fabricated metal complying with subsection § 179.220-7(g) of this section.

(e) A seal must be provided between the inner container manway nozzle and the opening in the outer shell.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971]

#### § 179.220-14 Openings in the tanks.

Openings in the inner container and the outer shell must be reinforced in compliance with AAR Specifications for Tank Cars, appendix E (IBR, see

**§ 179.220-15**

**49 CFR Ch. I (10-1-08 Edition)**

§171.7 of this subchapter). In determining the required reinforcement area for openings in the outer shell,  $t$  shall be one-fourth inch.

[68 FR 75763, Dec. 31, 2003]

**§ 179.220-15 Support system for inner container.**

(a) The inner container must be supported within the outer shell by a support system of adequate strength and ductility at its operating temperature to support the inner container when filled with liquid lading to any level. The support system must be designed to support, without yielding, impact loads producing accelerations of the following magnitudes and directions when the inner container is loaded so that the car is at its rail load limit, and the car is equipped with a conventional AAR Specification M-901 draft gear.

Longitudinal.....7G  
Transverse .....3G  
Vertical .....3G

(b) The longitudinal acceleration may be reduced to 3G where a cushioning device of approved design, which has been tested to demonstrate its ability to limit body forces to 400,000 pounds maximum at a 10 miles per hour impact, is used between the coupler and the tank structure. The support system must be of approved design and the inner container must be thermally isolated from the outer shell to the best practical extent. The inner container and outer shell must be permanently bonded to each other electrically either by the support system used, piping, or by a separate electrical connection of approved design.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971, as amended by Amdt. 179-28, 46 FR 49906, Oct. 8, 1981]

**§ 179.220-16 Expansion capacity.**

Expansion capacity must be provided in the shell of the inner container as prescribed in § 179.221-1.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971]

**§ 179.220-17 Gauging devices, top loading and unloading devices, venting and air inlet devices.**

(a) When installed, each device must be of approved design which will pre-

vent interchange with any other fixture and must be tightly closed. Each unloading pipe must be securely anchored within the inner container. Each inner container or compartment thereof may be equipped with one separate air connection.

(b) When the characteristics of the commodity for which the car is authorized require these devices to be equipped with valves or fittings to permit the loading and unloading of the contents, these devices including valves, shall be provided with a protective housing except when plug or ball-type valves with operating handles removed are used. Provision must be made for closing pipe connections of valves.

(c) Inner container may be equipped with a vacuum relief valve of approved design. Protective housing is not required.

(d) When a gauging device is required in § 179.221-1, an outage scale visible through the manway opening must be provided. If loading devices are applied to permit tank loading with cover closed, a telltale pipe may be provided. The telltail pipe must be capable of determining that required outage is provided. The pipe must be equipped with ¼-inch maximum, NPT control valve mounted outside tank and enclosed within a protective housing. Other approved devices may be used in place of an outage scale or a telltale pipe.

(e) The bottom of the tank shell may be equipped with a sump or siphon bowl, or both, welded or pressed into the shell. These sumps or siphon bowls, if applied, are not limited in size and must be made of cast, forged, or fabricated metal. Each sump or siphon bowl must be of good welding quality in conjunction with the metal of the tank shell. When the sump or siphon bowl is pressed in the bottom of the tank shell, the wall thickness of the pressed section must not be less than that specified for the shell. The section of a circular cross section tank to which a sump or siphon bowl is attached need not comply with the out-of-roundness requirement specified in appendix W, W14.06 of the AAR Specifications for Tank Cars. Any portion of a sump or siphon bowl not forming a part of a cylinder of revolution must

have walls of such thickness and must be so reinforced that the stresses in the walls caused by a given internal pressure are not greater than the circumferential stress which would exist under the same internal pressure in the wall of a tank of circular cross section designed in accordance with §§ 179.220-6(a) and 179.220-9. In no case shall the wall thickness be less than that specified in § 179.221-1.

(f) Protective housing, when required, must be of approved material and must have cover and sidewalls not less than 0.119 inch in thickness.

[Amdt. 179-9, 36 FR 21341, Nov. 6, 1971, as amended at 69 FR 54047, Sept. 7, 2004]

#### § 179.220-18 Bottom outlets.

(a) The inner container may be equipped with a bottom outlet of approved design and an opening provided in the outer shell of its access. If applied, the bottom outlet must comply with the following requirements:

(1) The extreme projection of the bottom outlet equipment may not be more than that allowed by appendix E of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter). All bottom outlet reducers and closures and their attachments shall be secured to car by at least  $\frac{3}{8}$ -inch chain, or its equivalent, except that bottom outlet closure plugs may be attached by  $\frac{1}{4}$ -inch chain. When the bottom outlet closure is of the combination cap and valve type, the pipe connection to the valve shall be closed by a plug, or cap. The bottom outlet equipment should include only the valve, reducers and closures that are necessary for the attachment of unloading fixtures. The permanent attachment of supplementary exterior fittings shall be approved by the AAR Committee on Tank Cars.

(2) Each bottom outlet must be provided with a liquid tight closure at its lower end.

(3) The valve and its operating mechanism must be applied to the outside bottom of the inner container. The valve operating mechanism must be provided with a suitable locking arrangement to insure positive closure during transportation.

(4) Valve outlet nozzle and valve body must be of cast, fabricated or forged

metal. If welded to inner container, they must be of good weldable quality in conjunction with metal of tank.

(5) To provide for the attachment of unloading connections, the bottom of the main portion of the outlet nozzle or valve body, or some fixed attachment thereto, must be provided with threaded cap closure arrangement or bolted flange closure arrangement having minimum 1-inch threaded pipe plug.

(6) If outlet nozzle and its closure extends below the bottom of the outer shell, a V-shaped breakage groove shall be cut (not cast) in the upper part of the outlet nozzle at a point immediately below the lowest part of the valve closest to the tank. In no case may the nozzle wall thickness at the root of the "V" be more than  $\frac{1}{4}$ -inch. The outlet nozzle or the valve body may be steam jacketed, in which case the breakage groove or its equivalent must be below the steam chamber but above the bottom of the center sill construction. If the outlet nozzle is not a single piece or its exterior valves are applied, provision shall be made for the equivalent of the breakage groove. On cars without continuous center sills, the breakage groove or its equivalent may not be more than 15 inches below the outer shell. On cars with continuous center sills, the breakage groove or its equivalent must be above the bottom of the center sill construction.

(7) The valve body must be of a thickness which will prevent distortion of the valve seat or valve by any change in contour of the shell resulting from expansion of lading, or other causes, and which will insure that accidental breakage of the outlet nozzle will occur at or below the "V" groove, or its equivalent.

(8) The valve must have no wings or stem projection below the "V" groove or its equivalent. The valve and seat must be readily accessible or removable for repairs, including grinding.

(b) Inner container may be equipped with bottom washout of approved design. If applied, bottom washout must comply with the following requirements:

(1) The extreme projection of the bottom washout equipment may not be more than that allowed by appendix E

## § 179.220-20

of the AAR Specifications for Tank Cars.

(2) Bottom washout must be of cast, forged or fabricated metals. If it is welded to the inner container, it must be of good weldable quality in conjunction with metal of tank.

(3) If washout nozzle extends below the bottom of the outer shell, a V-shaped breakage groove shall be cut (not cast) in the upper part of the nozzle at a point immediately below the lowest part of the inside closure seat or plug. In no case may the nozzle wall thickness at the root of the "V" be more than ¼-inch. Where the nozzle is not a single piece, provisions shall be made for the equivalent of the breakage groove. The nozzle must be of a thickness to insure that accidental breakage will occur at or below the "V" groove or its equivalent. On cars without a continuous center sill, the breakage groove or its equivalent may not be more than 15 inches below the outer shell. On cars with continuous center sills, the breakage groove or its equivalent must be above the bottom of the center sill construction.

(4) The closure plug and seat must be readily accessible or removable for repairs.

(5) The closure of the washout nozzle must be equipped with a ¾-inch solid screw plug. Plug must be attached by at least a ¼-inch chain.

(6) Joints between closures and their seats may be gasketed with suitable material.

[Amdt. 179-9, 36 FR 21342, Nov. 6, 1971, as amended by Amdt. 179-40, 52 FR 13048, Apr. 20, 1987; 68 FR 75763, Dec. 31, 2003]

## § 179.220-20 Reinforcements, when used, and appurtenances not otherwise specified.

All attachments to inner container and outer shell must be applied by approved means.

[Amdt. 179-9, 36 FR 21342, Nov. 6, 1971]

## § 179.220-22 Closure for openings.

(a) All plugs must be solid, with NPT threads, and must be of a length which will screw at least six threads inside the face of fitting or tank. Plugs, when inserted from the outside of the outer shell tank heads, must have the letter "S" at least three-eighths inch in size

## 49 CFR Ch. I (10-1-08 Edition)

stamped with steel stamp or cast on the outside surface to indicate the plug is solid.

(b) Openings in the outer shell used during construction for installation must be closed in an approved manner.

[Amdt. 179-9, 36 FR 21343, Nov. 6, 1971]

## § 179.220-23 Test of tanks.

(a) Each inner container or compartment must be tested hydrostatically to the pressure specified in § 179.221-1. The temperature of the pressurizing medium must not exceed 100 °F. during the test. The container must hold the prescribed pressure for at least 10 minutes without leakage or evidence of distress. Safety relief devices must not be in place when the test is made.

(b) The inner container must be pressure tested before installation within the outer shell. Items which, because of assembly sequence, must be welded to inner container after its installation within outer shell must have their attachment welds thoroughly inspected by a nondestructive dye penetrant method or its equivalent.

(c) Pressure testing of outer shell is not a specification requirement.

[Amdt. 179-9, 36 FR 21343, Nov. 6, 1971]

## § 179.220-24 Tests of pressure relief valves.

Each safety relief valve must be tested by air or gas for compliance with § 179.15 before being put into service.

[Amdt. 179-9, 36 FR 21343, Nov. 6, 1971, as amended at 62 FR 51561, Oct. 1, 1997]

## § 179.220-25 Stamping.

To certify that the tank complies with all specification requirements, each outer shell must be plainly and permanently stamped in letters and figures at least ⅜-inch high into the metal near the center of both outside heads as follows:

|                              | Examples of required stamping |
|------------------------------|-------------------------------|
| Specifications .....         | DOT-115A60W6.                 |
| Inner container:             |                               |
| Material .....               | ASTM A240-316L.               |
| Shell thickness .....        | Shell 0.167 in.               |
| Head thickness .....         | Head 0.150 in.                |
| Tank builders initials ..... | ABC.                          |
| Date of original test .....  | 00-0000.                      |
| Outer shell:                 |                               |
| Material .....               | ASTM A285-C.                  |

Pipeline and Hazardous Materials Safety Admin., DOT

§ 179.300–6

|                                                                        | Examples of required stamping |
|------------------------------------------------------------------------|-------------------------------|
| Tank builders initials .....                                           | WYZ.                          |
| Car assembler (if other than inner container or outer shell builders). | DEF.                          |

[Amdt. 179–9, 36 FR 21343, Nov. 6, 1971]

§ 179.220–26 Stenciling.

(a) The outer shell, or the jacket if the outer shell is insulated, must be stenciled in compliance with AAR Specifications for Tank Cars, appendix C (IBR, see § 171.7 of this subchapter).

(b) Stenciling must be applied on both sides of the outer shell or jacket near the center in letters and figures at least 1½ inches high to indicate the safe upper temperature limit, if applicable, for the inner tank, insulation, and the support system.

[Amdt. 179–9, 36 FR 21343, Nov. 6, 1971, as amended at 68 FR 75763, Dec. 31, 2003]

§ 179.221 Individual specification requirements applicable to tank car tanks consisting of an inner container supported within an outer shell.

§ 179.221–1 Individual specification requirements.

In addition to § 179.220, the individual specification requirements are as follows:

| DOT specification | Insulation | Bursting pressure (psig) | Minimum plate thickness (inches) | Test pressure (psig) | Bottom outlet  | Bottom washout | Reference (179.221–***) |
|-------------------|------------|--------------------------|----------------------------------|----------------------|----------------|----------------|-------------------------|
| 115A60ALW .....   | Yes .....  | 240                      | 3/16                             | 60                   | Optional.      | Optional.      |                         |
| 115A60W1 .....    | Yes .....  | 240                      | 1/8                              | 60                   | Optional ..... | Optional ..... | 1                       |
| 115A60W6 .....    | Yes .....  | 240                      | 1/8                              | 60                   | Optional ..... | Optional ..... | 1                       |

[Amdt. 170–52, 61 FR 28681, June 5, 1996, as amended at 62 FR 51561, Oct. 1, 1997; 66 FR 45390, Aug. 28, 2001]

Subpart E—Specifications for Multi-Unit Tank Car Tanks (Classes DOT-106A and 110AW)

§ 179.300 General specifications applicable to multi-unit tank car tanks designed to be removed from car structure for filling and emptying (Classes DOT-106A and 110AW).

§ 179.300–1 Tanks built under these specifications shall meet the requirements of §§ 179.300 and 179.301.

§ 179.300–3 Type and general requirements.

(a) Tanks built under this specification shall be cylindrical, circular in cross section, and shall have heads of approved design. All openings shall be located in the heads.

(b) Each tank shall have a water capacity of at least 1500 pounds and not more than 2600 pounds.

(c) For tanks made in foreign countries, a chemical analysis of materials and all tests as specified shall be car-

ried out within the limits of the United States under the supervision of a competent and impartial inspector.

§ 179.300–4 Insulation.

(a) Tanks shall not be insulated.

(b) [Reserved]

§ 179.300–6 Thickness of plates.

(a) For class DOT-110A tanks, the wall thickness after forming of the cylindrical portion of the tank must not be less than that specified in § 179.301 nor that calculated by the following formula:

$$t = \frac{Pd}{2SE}$$

Where:

*d* = inside diameter in inches;

*E* = 1.0 welded joint efficiency;

*P* = minimum required bursting pressure in psig;

*S* = minimum tensile strength of plate material in p.s.i. as prescribed in § 179.300–7;

*t* = minimum thickness of plate material in inches after forming.



## § 179.300-7

(b) For class DOT-106A tanks, the wall thickness of the cylindrical portion of the tank shall not be less than that specified in §179.301 and shall be such that at the tank test pressure the maximum fiber stress in the wall of the tank will not exceed 15,750 p.s.i. as calculated by the following formula:

$$s=[p(1.3D^2 + 0.4d^2)] / (D^2 - d^2)$$

where:

$d$  = inside diameter in inches;  
 $D$  = outside diameter in inches;  
 $p$  = tank test pressure in psig;  
 $s$  = wall stress in psig

(c) If plates are clad with material having tensile strength at least equal to the base plate, the cladding may be considered a part of the base plate when determining the thickness. If cladding material does not have tensile strength at least equal to the base plate, the base plate alone shall meet the thickness requirements.

[29 FR 18995, Dec. 29, 1964, as amended by Order 71, 31 FR 9083, July 1, 1966. Redesignated at 32 FR 5606, Apr. 5, 1967; 66 FR 45186, 45390, Aug. 28, 2001]

## § 179.300-7 Materials.

(a) Steel plate material used to fabricate tanks must conform with the following specifications with the indicated minimum tensile strength and elongation in the welded condition. However, the maximum allowable carbon content for carbon steel must not exceed 0.31 percent, although the individual ASTM specification may allow for a greater amount of carbon. The plates may be clad with other approved materials:

| Specifications <sup>2</sup> | Tensile strength (psi) welded condition <sup>1</sup> (minimum) | Elongation in 2 inches (percent) welded condition <sup>1</sup> (longitudinal) (minimum) |
|-----------------------------|----------------------------------------------------------------|-----------------------------------------------------------------------------------------|
| ASTM A 240/A 240M type 304  | 75,000                                                         | 25                                                                                      |
| ASTM A 240/A 240M type 304L | 70,000                                                         | 25                                                                                      |
| ASTM A 240/A 240M type 316  | 75,000                                                         | 25                                                                                      |
| ASTM A 240/A 240M type 316L | 70,000                                                         | 25                                                                                      |
| ASTM A 240/A 240M type 321  | 75,000                                                         | 25                                                                                      |
| ASTM A 285 Gr. A            | 45,000                                                         | 29                                                                                      |
| ASTM A 285 Gr. B            | 50,000                                                         | 20                                                                                      |
| ASTM A 285 Gr. C            | 55,000                                                         | 20                                                                                      |
| ASTM A 515/A 515M Gr. 65    | 65,000                                                         | 20                                                                                      |
| ASTM A 515/A 515M Gr. 70    | 70,000                                                         | 20                                                                                      |
| ASTM A 516/A 516M Gr. 70    | 70,000                                                         | 20                                                                                      |

<sup>1</sup> Maximum stresses to be used in calculations.

<sup>2</sup> These specifications are incorporated by reference (IBR, see § 171.7 of this subchapter.)

## 49 CFR Ch. I (10-1-08 Edition)

(b) [Reserved]

(c) All plates must have their heat number and the name or brand of the manufacturer legibly stamped on them at the rolling mill.

[Amdt. 179-10, 36 FR 21355, Nov. 6, 1971, as amended by Amdt. 179-42, 54 FR 38798, Sept. 20, 1989; Amdt. 179-43, 55 FR 27642, July 5, 1990; Amdt. 179-52, 61 FR 28682, June 5, 1996; Amdt. 179-52, 61 FR 50255, Sept. 25, 1996; Amdt. 179-53, 61 FR 51342, Oct. 1, 1996; 68 FR 75763, Dec. 31, 2003]

## § 179.300-8 Tank heads.

(a) Class DOT-110A tanks shall have fusion-welded heads formed concave to pressure. Heads for fusion welding shall be an ellipsoid of revolution 2:1 ratio of major to minor axis. They shall be one piece, hot formed in one heat so as to provide a straight flange at least 1½ inches long. The thickness shall not be less than that calculated by the following formula:

$$t = \frac{Pd}{2SE}$$

where symbols are as defined in §179.300-6(a).

(b) Class DOT-106A tanks must have forged-welded heads, formed convex to pressure. Heads for forge welding must be torispherical with an inside radius not greater than the inside diameter of the shell. They must be one piece, hot formed in one heat so as to provide a straight flange at least 4 inches long. They must have snug drive fit into the shell for forge welding. The wall thickness after forming must be sufficient to meet the test requirements of §179.300-16 and to provide for adequate threading of openings.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21355, Nov. 6, 1971]

## § 179.300-9 Welding.

(a) Longitudinal joints must be fusion welded. Head-to-shell joints must be forge welded on class DOT-106A tanks and fusion welded on class DOT-110A tanks. Welding procedures, welders and fabricators must be approved in accordance with AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter).

(b) Fusion-welded joints must be in compliance with the requirements of

AAR Specifications for Tank Cars, appendix W, except that circumferential welds in tanks less than 36 inches inside diameter need not be radiotaped.

(c) Forge-welded joints shall be thoroughly hammered or rolled to insure sound welds. The flanges of the heads shall be forge lapwelded to the shell and then crimped inwardly toward the center line at least one inch on the radius. Welding and crimping must be accomplished in one heat.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and as amended by Amdt. 179–10, 36 FR 21355, Nov. 6, 1971; 68 FR 75763, Dec. 31, 2003]

#### **§ 179.300–10 Postweld heat treatment.**

After welding is complete, steel tanks and all attachments welded thereto, must be postweld heat treated as a unit in compliance with the requirements of AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter).

[68 FR 75763, Dec. 31, 2003]

#### **§ 179.300–12 Protection of fittings.**

(a) Tanks shall be of such design as will afford maximum protection to any fittings or attachment to the head including the housing referred to in § 179.300–12(b). Tank ends shall slope or curve inward toward the axis so that the diameter at each end is at least 2 inches less than the maximum diameter.

(b) Loading and unloading valves shall be protected by a detachable protective housing of approved design which shall not project beyond the end of the tank and shall be securely fastened to the tank head. Pressure relief devices shall not be covered by the housing.

[29 FR 18995, Dec. 29, 1964, as amended at 68 FR 57634, Oct. 6, 2003]

#### **§ 179.300–13 Venting, loading and unloading valves.**

(a) Valves shall be of approved type, made of metal not subject to rapid deterioration by lading, and shall withstand tank test pressure without leakage. The valves shall be screwed directly into or attached by other approved methods to one tank head. Pro-

vision shall be made for closing outlet connections of the valves.

(b) Threads for openings shall be National Gas Taper Threads (NGT) tapped to gage, clean cut, even and without checks.

#### **§ 179.300–14 Attachments not otherwise specified.**

Siphon pipes and their couplings on the inside of the tank head and lugs on the outside of the tank head for attaching the valve protective housing must be fusion-welded in place prior to postweld heat treatment. All other fixtures and appurtenances, except as specifically provided for, are prohibited.

[Amdt. 179–10, 36 FR 21355, Nov. 6, 1971]

#### **§ 179.300–15 Pressure relief devices.**

(a) Unless prohibited in part 173 of this subchapter, tanks shall be equipped with one or more relief devices of approved type, made of metal not subject to rapid deterioration by the lading and screwed directly into tank heads or attached to tank heads by other approved methods. The total discharge capacity shall be sufficient to prevent building up pressure in tank in excess of 82.5 percent of the tank test pressure. When relief devices of the fusible plug type are used, the required discharge capacity shall be available in each head. See AAR Specifications for Tank Cars, appendix A (IBR, see § 171.7 of this subchapter), for the formula for calculating discharge capacity.

(b) Threads for openings shall be National Gas Taper Threads (NGT) tapped to gage, clean cut, even and without checks.

(c) Pressure relief devices shall be set for start-to-discharge and rupture discs shall burst at a pressure not exceeding that specified in § 179.301.

(d) Fusible plugs shall function at a temperature not exceeding 175 °F. and shall be vapor-tight at a temperature of not less than 130 °F.

[29 FR 18995, Dec. 29, 1964, as amended at 64 FR 51920, Sept. 27, 1999; 66 FR 45390, Aug. 28, 2001; 68 FR 75763, Dec. 31, 2003]

#### **§ 179.300–16 Tests of tanks.**

(a) After postweld heat treatment, tanks shall be subjected to hydrostatic

## § 179.300-17

expansion test in a water jacket, or by other approved methods. No tank shall have been subjected previously to internal pressure within 100 pounds of the test pressure. Each tank shall be tested to the pressure prescribed in § 179.301. Pressure shall be maintained for 30 seconds and sufficiently longer to insure complete expansion of tank. Pressure gage shall permit reading to accuracy of one percent. Expansion gage shall permit reading of total expansion to accuracy of one percent. Expansion shall be recorded in cubic cm.

(1) No leaks shall appear and permanent volumetric expansion shall not exceed 10 percent of total volumetric expansion at test pressure.

(2) [Reserved]

(b) After all fittings have been installed, each tank shall be subjected to interior air pressure test of at least 100 psig under conditions favorable to detection of any leakage. No leaks shall appear.

(c) Repairs of leaks detected in manufacture or in foregoing tests shall be made by the same process as employed in manufacture of tank. Caulking, soldering, or similar repairing is prohibited.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21355, Nov. 6, 1971; 66 FR 45390, Aug. 28, 2001]

## § 179.300-17 Tests of pressure relief devices.

(a) Each valve shall be tested by air or gas before being put into service. The valve shall open and be vapor-tight at the pressure prescribed in § 179.301.

(b) Rupture disks of non-reclosing pressure relief devices must be tested and qualified as prescribed in appendix A, Paragraph 5, of the AAR Manual of Standards and Recommended Practices, Section C—Part III, AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter).

(c) For pressure relief devices of the fusible plug type, a sample of the plug used shall function at the temperatures prescribed in § 179.300-15.

(d) The start-to-discharge and vapor-tight pressures shall not be affected by

## 49 CFR Ch. I (10-1-08 Edition)

any auxiliary closure or other combination.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21355, Nov. 6, 1971; 66 FR 45390, Aug. 28, 2001; 68 FR 48572, Aug. 14, 2003; 68 FR 75763, Dec. 31, 2003]

## § 179.300-18 Stamping.

(a) To certify that the tank complies with all specification requirements, each tank shall be plainly and permanently stamped in letters and figures  $\frac{3}{8}$  inch high into the metal of valve end chime as follows:

(1) DOT Specification number.

(2) Material and cladding material if any (immediately below the specification number).

(3) Owner's or builder's identifying symbol and serial number (immediately below the material identification). The symbol shall be registered with the Bureau of Explosives, duplications are not authorized.

(4) Inspector's official mark (immediately below the owner's or builder's symbol).

(5) Date of original tank test (month and year, such as 1-64 for January 1964). This should be so placed that dates of subsequent tests may easily be added thereto.

(6) Water capacity—0000 pounds.

(b) A copy of the above stamping in letters and figures of the prescribed size stamped on a brass plate secured to one of the tank heads is authorized.

## § 179.300-19 Inspection.

(a) Tank shall be inspected within the United States and Canada by a competent and impartial inspector as approved by the Associate Administrator of Safety, FRA. For tanks made outside the United States or Canada, the specified inspection shall be made within the United States.

(b) The inspector shall carefully inspect all plates from which tanks are to be made and secure records certifying that plates comply with the specification. Plates which do not comply with § 179.300-7 shall be rejected.

(c) The inspector shall make such inspection as may be necessary to see that all the requirements of this specification, including markings, are fully

**Pipeline and Hazardous Materials Safety Admin., DOT****§ 179.400-3**

complied with; shall see that the finished tanks are properly stress relieved and tested.

(d) The inspector shall stamp his official mark on each accepted tank as required in § 179.300-18, and render the report required in § 179.300-20.

[29 FR 18995, Dec. 29, 1964, as amended at 72 FR 55696, Oct. 1, 2007]

**§ 179.300-20 Reports.**

(a) Before a tank is placed in service, the inspector shall furnish to the build-

er, tank owner, Bureau of Explosives and the Secretary, Mechanical Division, Association of American Railroads, a report in approved form certifying that the tank and its equipment comply with all the requirements of this specification.

(b) For builder's Certificate of Construction, see § 179.5 (b), (c), and (d).

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21355, Nov. 5, 1971]

**§ 179.301 Individual specification requirements for multi-unit tank car tanks.**

(a) In addition to § 179.300 the individual specification requirements are as follows:

| DOT specification                                    | 106A500-X                     | 106A800-X                     | 110A500-W                     | 110A600-W                   | 110A800-W                     | 110A1000-W                    |
|------------------------------------------------------|-------------------------------|-------------------------------|-------------------------------|-----------------------------|-------------------------------|-------------------------------|
| Minimum required bursting pressure, psig .....       | ( <sup>1</sup> )              | ( <sup>1</sup> )              | 1250                          | 1500                        | 2000                          | 2500                          |
| Minimum thickness shell, inches .....                | <sup>13</sup> / <sub>32</sub> | <sup>11</sup> / <sub>16</sub> | <sup>11</sup> / <sub>32</sub> | <sup>3</sup> / <sub>8</sub> | <sup>15</sup> / <sub>32</sub> | <sup>19</sup> / <sub>32</sub> |
| Test pressure, psig (see § 179.300-16) .....         | 500                           | 800                           | 500                           | 600                         | 800                           | 1000                          |
| Safety relief devices, psig (see § 179.300-15) ..... | .....                         | .....                         | .....                         | .....                       | .....                         | .....                         |
| Start-to-discharge, or burst maximum, p.s.i. ....    | 375                           | 600                           | 375                           | 450                         | 600                           | 700                           |
| Vapor-tight, minimum psig .....                      | 300                           | 480                           | 300                           | 360                         | 480                           | 650                           |

<sup>1</sup> None specified.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-10, 36 FR 21355, Nov. 6, 1971; Amdt. 179-40, 52 FR 13049, Apr. 20, 1987; 65 FR 58632, Sept. 29, 2000; 66 FR 45390, Aug. 28, 2001]

**§ 179.302 [Reserved]****Subpart F—Specification for Cryogenic Liquid Tank Car Tanks and Seamless Steel Tanks (Classes DOT-113 and 107A)**

SOURCE: Amdt. 179-32, 48 FR 27708, June 16, 1983, unless otherwise noted.

**§ 179.400 General specification applicable to cryogenic liquid tank car tanks.****§ 179.400-1 General.**

A tank built to this specification must comply with §§ 179.400 and 179.401.

**§ 179.400-3 Type.**

(a) A tank built to this specification must—

(1) Consist of an inner tank of circular cross section supported essentially concentric within an outer jacket of circular cross section, with the out of roundness of both the inner tank and outer jacket limited in accordance with Paragraph UG-80 in Section VIII of the ASME Code (IBR, see § 171.7 of this subchapter);

(2) Have the annular space evacuated after filling the annular space with an approved insulating material;

(3) Have the inner tank heads designed concave to pressure; and

(4) Have the outer jacket heads designed convex to pressure.

## § 179.400-4

(b) The tank must be equipped with piping systems for vapor venting and transfer of lading, and with pressure relief devices, controls, gages and valves, as prescribed herein.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 68 FR 75763, Dec. 31, 2003]

### § 179.400-4 Insulation system and performance standard.

(a) For the purposes of this specification—

(1) *Standard Heat Transfer Rate* (SHTR), expressed in Btu/day/lb of water capacity, means the rate of heat transfer used for determining the satisfactory performance of the insulation system of a cryogenic tank car tank in cryogenic liquid service (see § 179.401-1 table).

(2) *Test cryogenic liquid* means the cryogenic liquid, which may be different from the lading intended to be shipped in the tank, being used during the performance tests of the insulation system.

(3) *Normal evaporation rate* (NER), expressed in lbs. (of the cryogenic liquid)/day, means the rate of evaporation, determined by test of a test cryogenic liquid in a tank maintained at a pressure of approximately one atmosphere, absolute. This determination of the NER is the NER test.

(4) *Stabilization period* means the elapsed time after a tank car tank is filled with the test cryogenic liquid until the NER has stabilized, or 24 hours has passed, whichever is greater.

(5) *Calculated heat transfer rate*. The calculated heat transfer rate (CHTR) is determined by the use of test data obtained during the NER test in the formula:

$$q = [N(\Delta h)(90 - t_1)] / [V(8.32828)(t_s - t_f)]$$

Where:

q = CHTR, in Btu/day/lb., of water capacity;  
N = NER, determined by NER test, in lbs./day;

$\Delta h$  = latent heat of vaporization of the test cryogenic liquid at the NER test pressure of approximately one atmosphere, absolute, in Btu/lb.;

90 = ambient temperature at 90 °F.;

V = gross water volume at 60 °F. of the inner tank, in gallons;

$t_1$  = equilibrium temperature of intended lading at maximum shipping pressure, in °F.;

## 49 CFR Ch. I (10-1-08 Edition)

8.32828 = constant for converting gallons of water at 60 °F. to lbs. of water at 60 °F., in lbs./gallon;

$t_s$  = average temperature of outer jacket, determined by averaging jacket temperatures at various locations on the jacket at regular intervals during the NER test, in °F.;

$t_f$  = equilibrium temperature of the test cryogenic liquid at the NER test pressure of approximately, one atmosphere, absolute, in °F.

(b) DOT-113A60W tank cars must—

(1) Be filled with hydrogen, cryogenic liquid to the maximum permitted fill density specified in § 173.319(d)(2) table of this subchapter prior to performing the NER test; and

(2) Have a CHTR equal to or less than the SHTR specified in § 179.401-1 table for a DOT-113A60W tank car.

(c) DOT-113C120W tank cars must—

(1) Be filled with ethylene, cryogenic liquid to the maximum permitted fill density specified in § 173.319(d)(2) table of this subchapter prior to performing the NER test, or be filled with nitrogen, cryogenic liquid to 90 percent of the volumetric capacity of the inner tank prior to performing the NER test; and

(2) Have a CHTR equal to or less than 75 percent of the SHTR specified in § 179.401-1 table for a DOT-113C120W tank car.

(d) Insulating materials must be approved.

(e) If the insulation consists of a powder having a tendency to settle, the entire top of the cylindrical portion of the inner tank must be insulated with a layer of glass fiber insulation at least one-inch nominal thickness, or equivalent, suitably held in position and covering an area extending 25 degrees to each side of the top center line of the inner tank.

(f) The outer jacket must be provided with fittings to permit effective evacuation of the annular space between the outer jacket and the inner tank.

(g) A device to measure the absolute pressure in the annular space must be provided. The device must be portable with an easily accessible connection or permanently positioned where it is readily visible to the operator.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 49 FR 24318, June 12, 1984; 66 FR 45186, Aug. 28, 2001]

**§ 179.400-5 Materials.**

(a) Stainless steel of ASTM A 240/A 240M (IBR, see §171.7 of this subchapter), Type 304 or 304L must be used for the inner tank and its appurtenances, as specified in AAR Specifications for Tank Cars, appendix M (IBR, see §171.7 of this subchapter), and must be—

(1) In the annealed condition prior to fabrication, forming and fusion welding;

(2) Suitable for use at the temperature of the lading; and

(3) Compatible with the lading.

(b) Any steel casting, steel forging, steel structural shape or carbon steel plate used to fabricate the outer jacket or heads must be as specified in AAR Specifications for Tank Cars, appendix M.

(c) *Impact tests* must be—

(1) Conducted in accordance with AAR Specifications for Tank Cars, appendix W, W9.01;

(2) Performed on longitudinal specimens of the material;

(3) Conducted at the tank design service temperature or colder; and

(4) Performed on test plate welds and materials used for inner tanks and appurtenances and which will be subjected to cryogenic temperatures.

(d) Impact test values must be equal to or greater than those specified in AAR Specifications for Tank Cars, appendix W. The report of impact tests must include the test values and lateral expansion data.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 67 FR 51660, Aug. 8, 2002; 68 FR 75763, Dec. 31, 2003]

**§ 179.400-6 Bursting and buckling pressure.**

(a) [Reserved]

(b) The outer jacket of the required evacuated insulation system must be designed in accordance with §179.400-8(d) and in addition must comply with the design loads specified in Section 6.2 of the AAR Specifications for Tank Cars (IBR, see §171.7 of this subchapter). The designs and calculations must provide for the loadings trans-

ferred to the outer jacket through the support system.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended by Amdt. 179-51, 61 FR 18934, Apr. 29, 1996; 65 FR 58632, Sept. 29, 2000; 68 FR 75763, Dec. 31, 2003]

**§ 179.400-7 Tank heads.**

(a) Tank heads of the inner tank and outer jacket must be flanged and dished, or ellipsoidal.

(b) Flanged and dished heads must have—

(1) A main inside dish radius not greater than the outside diameter of the straight flange;

(2) An inside knuckle radius of not less than 6 percent of the outside diameter of the straight flange; and

(3) An inside knuckle radius of at least three times the head thickness.

**§ 179.400-8 Thickness of plates.**

(a) The minimum wall thickness, after forming, of the inner shell and any 2:1 ellipsoidal head for the inner tank must be that specified in §179.401-1, or that calculated by the following formula, whichever is greater:

$$t = Pd / 2SE$$

Where:

t = minimum thickness of plate, after forming, in inches;

P = minimum required bursting pressure in psig;

d = inside diameter, in inches;

S = minimum tensile strength of the plate material, as prescribed in AAR Specifications for Tank Cars, appendix M, Table M1 (IBR, see §171.7 of this subchapter), in psi;

E = 0.9, a factor representing the efficiency of welded joints, except that for seamless heads, E = 1.0.

(b) The minimum wall thickness, after forming, of any 3:1 ellipsoidal head for the inner tank must be that specified in §179.401-1, or that calculated by the following formula, whichever is greater:

$$t = 1.83 Pd / 2SE$$

Where:

t = minimum thickness of plate, after forming, in inches;

P = minimum required bursting pressure in psig;

d = inside diameter, in inches;

## § 179.400-9

## 49 CFR Ch. I (10-1-08 Edition)

S = minimum tensile strength of the plate material, as prescribed in AAR Specifications for Tank Cars, Appendix M, Table M1, in psi;

E = 0.9, a factor representing the efficiency of welded joints, except that for seamless heads, E=1.0.

(c) The minimum wall thickness, after forming, of a flanged and dished head for the inner tank must be that specified in § 179.401-1, or that calculated by the following formula, whichever is greater:

$$t = [PL(3 + \sqrt{(L/r)})] / (8SE)$$

Where:

t = minimum thickness of plate, after forming, in inches;

P = minimum required bursting pressure in psig;

L = main inside radius of dished head, in inches;

r = inside knuckle radius, in inches;

S = minimum tensile strength of plate material, as prescribed in AAR Specifications for Tank Cars, appendix M, table M1, in psi;

E = 0.9, a factor representing the efficiency of welded joints, except that for seamless heads, E = 1.0.

(d) The minimum wall thickness, after forming, of the outer jacket shell may not be less than  $\frac{7}{16}$  inch. The minimum wall thickness, after forming, of the outer jacket heads may not be less than  $\frac{1}{2}$  inch and they must be made from steel specified in § 179.16(c). The annular space is to be evacuated, and the cylindrical portion of the outer jacket between heads, or between stiffening rings if used, must be designed to withstand an external pressure of 37.5 psig (critical collapsing pressure), as determined by the following formula:

$$P_c = [2.6E(t/D)^{2.5}] / [(L/D) - 0.45(t/D)^{0.5}]$$

Where:

P<sub>c</sub> = Critical collapsing pressure (37.5 psig minimum) in psig;

E = modulus of elasticity of jacket material, in psi;

t = minimum thickness of jacket material, after forming, in inches;

D = outside diameter of jacket, in inches;

L = distance between stiffening ring centers in inches. (The heads may be considered as stiffening rings located  $\frac{1}{3}$  of the head depth from the head tangent line.)

[Amdt. 179-32, 48 FR 27708, June 16, 1983; 49 FR 42736, Oct. 24, 1984; 64 FR 51920, Sept. 27, 1999, as amended at 66 FR 45390, Aug. 28, 2001; 68 FR 75763, Dec. 31, 2003]

## § 179.400-9 Stiffening rings.

(a) If stiffening rings are used in designing the cylindrical portion of the outer jacket for external pressure, they must be attached to the jacket by means of fillet welds. Outside stiffening ring attachment welds must be continuous on each side of the ring. Inside stiffening ring attachment welds may be intermittent welds on each side of the ring with the total length of weld on each side not less than one-third of the circumference of the tank. The maximum space between welds may not exceed eight times the outer jacket wall thickness.

(b) A portion of the outer jacket may be included when calculating the moment of inertia of the ring. The effective width of jacket plate on each side of the attachment of the stiffening ring is given by the following formula:

$$W = 0.78(Rt)^{0.5}$$

Where:

W = width of jacket effective on each side of the stiffening ring, in inches;

R = outside radius of the outer jacket, in inches;

t = plate thickness of the outer jacket, after forming, in inches.

(c) Where a stiffening ring is used that consists of a closed section having two webs attached to the outer jacket, the jacket plate between the webs may be included up to the limit of twice the value of "W", as defined in paragraph (b) of this section. The outer flange of the closed section, if not a steel structural shape, is subject to the same limitations with "W" based on the "R" and "t" values of the flange. Where two separate members such as two angles, are located less than "2W" apart they may be treated as a single stiffening ring member. (The maximum length of plate which may be considered effective is 4W.) The closed section between an external ring and the outer jacket must be provided with a drain opening.

(d) The stiffening ring must have a moment of inertia large enough to support the critical collapsing pressure, as determined by either of the following formulas:

$$I = [0.035D^3 L P_c] / E,$$

or

$$I' = [0.046D^3 L P_c] / E$$

Where:

I = required moment of inertia of stiffening ring about the centroidal axis parallel to the vessel axis, in inches to the fourth power;

I' = required moment of inertia of combined section of stiffening ring and effective width of jacket plate about the centroidal axis parallel to the vessel axis, in inches to the fourth power;

D = outside diameter of the outer jacket, in inches;

L = one-half of the distance from the centerline of the stiffening ring to the next line of support on one side, plus one-half of the distance from the centerline to the next line of support on the other side of stiffening ring. Both distances are measured parallel to the axis of the vessel, in inches. (A line of support is:

(1) A stiffening ring which meets the requirements of this paragraph, or

(2) A circumferential line of a head at one-third the depth of the head from the tangent line);

$P_c$  = critical collapsing pressure (37.5 psig minimum) in psig;

E = modulus of elasticity of stiffening ring material, in psi.

(e) Where loads are applied to the outer jacket or to stiffening rings from the system used to support the inner tank within the outer jacket, additional stiffening rings, or an increased moment of inertia of the stiffening rings designed for the external pressure, must be provided to carry the support loads.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 66 FR 45391, Aug. 28, 2001]

#### § 179.400-10 Sump or siphon bowl.

A sump or siphon bowl may be in the bottom of the inner tank shell if—

(a) It is formed directly into the inner tank shell, or is formed and welded to the inner tank shell and is of weldable quality metal that is compatible with the inner tank shell;

(b) The stress in any orientation under any condition does not exceed the circumferential stress in the inner tank shell; and

(c) The wall thickness is not less than that specified in § 179.401-1.

#### § 179.400-11 Welding.

(a) Except for closure of openings and a maximum of two circumferential

closing joints in the cylindrical portion of the outer jacket, each joint of an inner tank and the outer jacket must be a fusion double welded butt joint.

(b) The closure for openings and the circumferential closing joints in the cylindrical portion of the outer jacket, including head to shell joints, may be a single welded butt joint using a backing strip on the inside of the joint.

(c) Each joint must be welded in accordance with the requirements of AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter).

(d) Each welding procedure, welder, and fabricator must be approved.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 68 FR 75763, Dec. 31, 2003]

#### § 179.400-12 Postweld heat treatment.

(a) Postweld heat treatment of the inner tank is not required.

(b) The cylindrical portion of the outer jacket, with the exception of the circumferential closing seams, must be postweld heat treated as prescribed in AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter). Any item to be welded to this portion of the outer jacket must be attached before postweld heat treatment. Welds securing the following need not be postweld heat treated when it is not practical due to final assembly procedures:

(1) the inner tank support system to the outer jacket,

(2) connections at piping penetrations,

(3) closures for access openings, and

(4) circumferential closing joints of head to shell joints.

(c) When cold formed heads are used on the outer jacket they must be heat treated before welding to the jacket shell if postweld heat treatment is not practical due to assembly procedures.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 68 FR 75763, Dec. 31, 2003]

#### § 179.400-13 Support system for inner tank.

(a) The inner tank must be supported within the outer jacket by a support system of approved design. The system and its areas of attachment to the outer jacket must have adequate strength and ductility at operating



#### § 179.400-14

temperatures to support the inner tank when filled with the lading to any level incident to transportation.

(b) The support system must be designed to support, without yielding, impact loads producing accelerations of the following magnitudes and directions when the inner tank is fully loaded and the car is equipped with a conventional draft gear:

|                    |      |
|--------------------|------|
| Longitudinal ..... | 7“g” |
| Transverse .....   | 3“g” |
| Vertical .....     | 3“g” |

The longitudinal acceleration may be reduced to 3“g” where a cushioning device of approved design, which has been tested to demonstrate its ability to limit body forces to 400,000 pounds maximum at 10 miles per hour, is used between the coupler and the tank structure.

(c) The inner tank and outer jacket must be permanently bonded to each other electrically, by either the support system, piping, or a separate electrical connection of approved design.

#### § 179.400-14 Cleaning of inner tank.

The interior of the inner tank and all connecting lines must be thoroughly cleaned and dried prior to use. Proper precautions must be taken to avoid contamination of the system after cleaning.

#### § 179.400-15 Radioscopy.

Each longitudinal and circumferential joint of the inner tank, and each longitudinal and circumferential double welded butt joint of the outer jacket, must be examined along its entire length in accordance with the requirements of AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter).

[68 FR 75763, Dec. 31, 2003]

#### § 179.400-16 Access to inner tank.

(a) The inner tank must be provided with a means of access having a minimum inside diameter of 16 inches. Reinforcement of the access opening must be made of the same material used in the inner tank. The access closure must be of an approved material and design.

(b) If a welded closure is used, it must be designed to allow it to be re-

#### 49 CFR Ch. I (10-1-08 Edition)

opened by grinding or chipping and to be closed again by rewelding, preferably without a need for new parts. A cutting torch may not be used.

#### § 179.400-17 Inner tank piping.

(a) *Product lines.* The piping system for vapor and liquid phase transfer and venting must be made for material compatible with the product and having satisfactory properties at the lading temperature. The outlets of all vapor phase and liquid phase lines must be located so that accidental discharge from these lines will not impinge on any metal of the outer jacket, car structures, trucks or safety appliances. Suitable provision must be made to allow for thermal expansion and contraction.

(1) *Loading and unloading line.* A liquid phase transfer line must be provided and it must have a manually operated shut-off valve located as close as practicable to the outer jacket, plus a secondary closure that is liquid and gas tight. This secondary closure must permit any trapped pressure to bleed off before the closure can be removed completely. A vapor trap must be incorporated in the line and located as close as practicable to the inner tank. On a DOT-113A60W tank car, any loading and unloading line must be vacuum jacketed between the outer jacket and the shut-off valve and the shut-off valve must also be vacuum jacketed.

(2) *Vapor phase line.* A vapor phase line must connect to the inner tank and must be of sufficient size to permit the pressure relief devices specified in § 179.400-20 and connected to this line to operate at their design capacity without excessive pressure build-up in the tank. The vapor phase line must have a manually operated shut-off valve located as close as practicable to the outer jacket, plus a secondary closure that is liquid and gas tight. This secondary closure must permit any trapped pressure to bleed off before the closure can be removed completely.

(3) *Vapor phase blowdown line.* A blowdown line must be provided. It must be attached to the vapor phase line specified in paragraph (a)(2) of this section, upstream of the shut-off valve in that line. A by-pass line with a manually

operated shut-off valve must be provided to permit reduction of the inner tank pressure when the vapor phase line is connected to a closed system. The discharge from this line must be outside the housing and must be directed upward and away from operating personnel.

(b) Any pressure building system provided for the purpose of pressurizing the vapor space of the inner tank to facilitate unloading the liquid lading must be approved.

[Amdt. 179–32, 48 FR 27708, June 16, 1983, as amended at 66 FR 45391, Aug. 28, 2001]

#### § 179.400–18 Test of inner tank.

(a) After all items to be welded to the inner tank have been welded in place, the inner tank must be pressure tested at the test pressure prescribed in § 179.401–1. The temperature of the pressurizing medium may not exceed 38 °C (100 °F) during the test. The inner tank must hold the prescribed pressure for a period of not less than ten minutes without leakage or distortion. In a pneumatic test, due regard for the protection of all personnel should be taken because of the potential hazard involved. After a hydrostatic test the container and piping must be emptied of all water and purged of all water vapor.

(b) Caulking of welded joints to stop leaks developed during the test is prohibited. Repairs to welded joints must be made as prescribed in AAR Specifications for Tank Cars, appendix W (IBR, see § 171.7 of this subchapter).

[Amdt. 179–32, 48 FR 27708, June 16, 1983, as amended at 68 FR 75763, Dec. 31, 2003; 73 FR 57008, Oct. 1, 2008]

#### § 179.400–19 Valves and gages.

(a) *Valves.* Manually operated shut-off valves and control valves must be provided wherever needed for control of vapor phase pressure, vapor phase venting, liquid transfer and liquid flow rates. All valves must be made from approved materials compatible with the lading and having satisfactory properties at the lading temperature.

(1) Liquid control valves must be of extended stem design.

(2) Packing, if used, must be satisfactory for use in contact with the lading

and of approved materials that will effectively seal the valve stem without causing difficulty of operation.

(3) Each control valve and shut-off valve must be readily operable. These valves must be mounted so that their operation will not transmit excessive forces to the piping system.

(b) *Gages.* Gages, except portable units, must be securely mounted within suitable protective housings. A liquid level gage and a vapor phase pressure gage must be provided as follows:

(1) *Liquid level gage.* (i) A gage of approved design to indicate the quantity of liquefied lading within the inner tank, mounted where it will be readily visible to an operator during transfer operations or storage, or a portable gage with a readily accessible connection, or

(ii) A fixed length dip tube, with a manually operated shut-off valve located as close as practicable to the outer jacket. The dip tube must indicate the maximum liquid level for the allowable filling density. The inner end of the dip tube must be located on the longitudinal centerline of the inner tank and within four feet of the transverse centerline of the inner tank.

(2) *Vapor phase pressure gage.* A vapor phase pressure gage of approved design, with a manually operated shut-off valve located as close as practicable to the outer jacket. The gage must indicate the vapor pressure within the inner tank and must be mounted where it will be readily visible to an operator. An additional fitting for use of a test gage must be provided.

#### § 179.400–20 Pressure relief devices.

(a) The tank must be provided with pressure relief devices for the protection of the tank assembly and piping system. The discharge from these devices must be directed away from operating personnel, principal load bearing members of the outer jacket, car structure, trucks and safety appliances. Vent or weep holes in pressure relief devices are prohibited. All main pressure relief devices must discharge to the outside of the protective housings in which they are located, except that this requirement does not apply to

pressure relief valves installed to protect isolated sections of lines between the final valve and end closure.

(b) *Materials.* Materials used in pressure relief devices must be suitable for use at the temperature of the lading and otherwise compatible with the lading in both the liquid and vapor phases.

(c) *Inner tank.* Pressure relief devices for the inner tank must be attached to vapor phase piping and mounted so as to remain at ambient temperature prior to operation. The inner tank must be equipped with one or more pressure relief valves and one or more safety vents (except as noted in paragraph (c)(3)(iv) of this section), and installed without an intervening shut-off valve (except as noted in paragraph (c)(3)(iii) of this section). Additional requirements are as follows:

(1) *Safety vent.* The safety vent shall function at the pressure specified in § 179.401-1. The safety vent must be flow rated in accordance with the applicable provisions of AAR Specifications for Tank Cars, appendix A (IBR, see § 171.7 of this subchapter), and provide sufficient capacity to meet the requirements of AAR Specifications for Tank Cars, appendix A, A8.07(a).

(2) *Pressure relief valve.* The pressure relief valve must:

(i) be set to start-to-discharge at the pressure specified in § 179.401-1, and

(ii) meet the requirements of AAR Specifications for Tank Cars, appendix A, A8.07(b).

(3) *Installation of safety vent and pressure relief valve.*—(i) *Inlet piping.* (A) The opening through all piping and fittings between the inner tank and its pressure relief devices must have a cross-sectional area at least equal to that of the pressure relief device inlet, and the flow characteristics of this upstream system must be such that the pressure drop will not adversely affect the relieving capacity or the proper operation of the pressure relief device.

(B) When the required relief capacity is met by the use of multiple pressure relief device placed on one connection, the inlet internal cross-sectional area of this connection must be sufficient to provide the required flow capacity for the proper operation of the pressure relief device system.

(ii) *Outlet piping.* (A) The opening through the discharge lines must have a cross-sectional area at least equal to that of the pressure relief device outlet and may not reduce the relieving capacity below that required to properly protect the inner tank.

(B) When the required relieving capacity is met by use of multiple pressure relief devices placed on a common discharge manifold, the manifold outlet internal cross-sectional area must be at least equal to the combined outlet areas of the pressure relief devices.

(iii) Duplicate pressure relief devices may be used when an approved 3-way selector valve is installed to provide for relief through either duplicate pressure relief device. The 3-way valve must be included in the mounting prescribed by AAR Specifications for Tank Cars, appendix A, A6.02(g), when conducting the flow capacity test on the safety vent prescribed by AAR Specifications for Tank Cars, appendix A, A6.01. Flow capacity tests must be performed with the 3-way valve at both of the extreme positions as well as at the mid-position and the flow capacity must be in accordance with AAR Specifications for Tank Cars, appendix A, A8.07(a).

(iv) An alternate pressure relief valve, set as required in § 179.401-1, may be used in lieu of the safety vent, provided it meets the flow capacity prescribed in AAR Specifications for Tank Cars, appendix A at a flow rating pressure of 110 percent of its start-to-discharge pressure. Installation must—

(A) Prevent moisture accumulation at the seat by providing drainage away from that area,

(B) Permit periodic drainage of the vent piping, and

(C) Prevent accumulation of foreign material in the vent system.

(4) *Evaporation control.* The routine release of vaporized lading may be controlled with a pressure controlling and mixing device, except that a pressure controlling and mixing device is required on each DOT-113A60W car. Any pressure controlling and mixing device must—

(i) Be set to start-to-discharge at a pressure not greater than that specified in § 179.401-1;

(ii) Have sufficient capacity to limit the pressure within the inner tank to that pressure specified in § 179.401-1, when the discharge is equal to twice the normal venting rate during transportation, with normal vacuum and the outer shell at 130 °F; and

(iii) Prevent the discharge of a gas mixture exceeding 50% of the lower flammability limit to the atmosphere under normal conditions of storage or transportation.

(5) *Safety interlock.* If a safety interlock is provided for the purpose of allowing transfer of lading at a pressure higher than the pressure control valve setting but less than the pressure relief valve setting, the design must be such that the safety interlock will not affect the discharge path of the pressure relief valve or safety vent at any time. The safety interlock must automatically provide an unrestricted discharge path for the pressure control device at all times when the tank car is in transport service.

(d) *Outer jacket.* The outer jacket must be provided with a suitable system to prevent buildup of annular space pressure in excess of 16 psig or the external pressure for which the inner tank was designed, whichever is less. The total relief area provided by the system must be a minimum of 25 square inches, and means must be provided to prevent clogging of any system opening, as well as to ensure adequate communication to all areas of the insulation space. If a safety vent is a part of the system, it must be designed to prevent distortion of the rupture disc when the annular space is evacuated.

(e) *Piping system.* Where a piping circuit can be isolated by closing a valve, means for pressure relief must be provided.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 66 FR 45391, Aug. 28, 2001; 68 FR 75763, Dec. 31, 2003]

#### § 179.400-21 Test of pressure relief valves.

Each valve must be tested with air or gas for compliance with § 179.401-1 before being put into service.

#### § 179.400-22 Protective housings.

Each valve, gage, closure and pressure relief device, with the exception of secondary relief valves for the protection of isolated piping, must be enclosed within a protective housing. The protective housing must be adequate to protect the enclosed components from direct solar radiation, mud, sand, adverse environmental exposure and mechanical damage incident to normal operation of the tank car. It must be designed to provide reasonable access to the enclosed components for operation, inspection and maintenance and so that vapor concentrations cannot build up to a dangerous level inside the housing in the event of valve leakage or pressure relief valve operation. All equipment within the protective housing must be operable by personnel wearing heavy gloves and must incorporate provisions for locks or seals. A protective housing and its cover must be constructed of metal not less than 0.119 inch thick.

#### § 179.400-23 Operating instructions.

All valves and gages must be clearly identified with corrosion-resistant nameplates. A plate of corrosion-resistant material bearing precautionary instructions for the safe operation of the equipment during storage and transfer operations must be securely mounted so as to be readily visible to an operator. The instruction plate must be mounted in each housing containing operating equipment and controls for product handling. These instructions must include a diagram of the tank and its piping system with the various gages, control valves and pressure relief devices clearly identified and located.

#### § 179.400-24 Stamping.

(a) A tank that complies with all specification requirements must have the following information plainly and permanently stamped into the metal near the center of the head of the outer jacket at the "B" end of the car, in letters and figures at least 3/8-inch high, in the following order:

|                     |                              |
|---------------------|------------------------------|
|                     | Example of required stamping |
| Specification ..... | DOT-113A60W.                 |

**§ 179.400-25**

|                                                                                         | Example of required stamping |
|-----------------------------------------------------------------------------------------|------------------------------|
| Design service temperature .....                                                        | Minus 423° F.                |
| Inner tank .....                                                                        | Inner Tank.                  |
| Material .....                                                                          | ASTM A240-304.               |
| Shell thickness .....                                                                   | Shell $\frac{3}{16}$ inch.   |
| Head thickness .....                                                                    | Head $\frac{3}{16}$ inch.    |
| Inside diameter .....                                                                   | ID 107 inch.                 |
| Inner tank builder's initials .....                                                     | ABC.                         |
| Date of original test (month and year) and initials of person conducting original test. | 00-0000GHK.                  |
| Water capacity .....                                                                    | 00000 lbs.                   |
| Outer jacket .....                                                                      | Outer jacket.                |
| Material .....                                                                          | ASTM A515-70.                |
| Outer jacket builder's initials .....                                                   | DEF.                         |
| Car assembler's initials (if other than inner tank or outer jacket builder).            | XYZ.                         |

(b) Any stamping on the shell or heads of the inner tank is prohibited.

(c) In lieu of the stamping required by paragraph (a) of this section, the specified markings may be incorporated on a data plate of corrosion-resistant metal, fillet welded in place on the head of the outer jacket at the "B" end of the car.

**§ 179.400-25 Stenciling.**

Each tank car must be stenciled in compliance with the provisions of the AAR Specifications for Tank Cars, appendix C (IBR, see §171.7 of this subchapter). The stenciling must also include the following:

(a) The date on which the rupture disc was last replaced and the initials of the person making the replacement, on the outer jacket in letters and figures at least 1½ inches high.

(b) The design service temperature and maximum lading weight, in letters and figures at least 1½ inches high adjacent to the hazardous material stencil.

(c) The water capacity, in pounds net at 60 °F., with the tank at its coldest operating temperature, after deduction for the volume above the inlet to the pressure relief device or pressure control valve, structural members, baffles, piping, and other appurtenances inside the tank, in letters and figures at least 1½ inches high.

(d) Both sides of the tank car, in letters at least 1½ inches high, with the statement "Do Not Hump or Cut Off While in Motion."

(e) The outer jacket, below the tank classification stencil, in letters at least

**49 CFR Ch. I (10-1-08 Edition)**

1½ inches high, with the statement, "vacuum jacketed."

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 66 FR 45391, Aug. 28, 2001; 68 FR 75763, Dec. 31, 2003]

**§ 179.401 Individual specification requirements applicable to inner tanks for cryogenic liquid tank car tanks.**

**§ 179.401-1 Individual specification requirements.**

In addition to §179.400, the individual specification requirements for the inner tank and its appurtenances are as follows:

| DOT specification                                                                                | 113A60W              | 113C120W         |
|--------------------------------------------------------------------------------------------------|----------------------|------------------|
| Design service temperature, °F.                                                                  | - 423 .....          | - 260.           |
| Material .....                                                                                   | § 179.400-5 .....    | § 179.400-5.     |
| Impact test (weld and plate material).                                                           | § 179.400-5(c) ..    | § 179.400-5(c).  |
| Impact test values .....                                                                         | § 179.400-5(d) ..    | § 179.400-5(d).  |
| Standard heat transfer rate.<br>(Btu per day per lb. of water capacity, max.) (see § 179.400-4). | 0.097 .....          | 0.4121.          |
| Bursting pressure, min. psig.                                                                    | 240 .....            | 300.             |
| Minimum plate thickness shell, inches (see § 179.400-7(a)).                                      | $\frac{3}{16}$ ..... | $\frac{3}{16}$ . |
| Minimum head thickness, inches (see § 179.400-8 (a), (b), and (c)).                              | $\frac{3}{16}$ ..... | $\frac{3}{16}$ . |
| Test pressure, psig (see § 179.400-16).                                                          | 60 .....             | 120.             |
| Safety vent bursting pressure, max. psig.                                                        | 60 .....             | 120.             |
| Pressure relief valve start-to-discharge pressure, psig (±3 psi).                                | 30 .....             | 75.              |
| Pressure relief valve vapor tight pressure, min. psig.                                           | 24 .....             | 60.              |
| Pressure relief valve flow rating pressure, max. psig.                                           | 40 .....             | 85.              |
| Alternate pressure relief valve start to-discharge pressure, psig (±3 psi).                      | .....                | 90.              |
| Alternate pressure relief valve vapor tight pressure, min. psig.                                 | .....                | 72.              |
| Alternate pressure relief valve flow rating pressure, max. psig.                                 | .....                | 100.             |
| Pressure control valve Start-to-vent, max. psig (see § 179.400-20(c)(4)).                        | 17 .....             | Not required.    |
| Relief device discharge restrictions.                                                            | § 179.400-20 .....   | 179.400-20.      |

**Pipeline and Hazardous Materials Safety Admin., DOT**

**§ 179.500-5**

| DOT specification        | 113A60W            | 113C120W      |
|--------------------------|--------------------|---------------|
| Transfer line insulation | § 179.400-17 ..... | Not required. |

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 49 FR 24318, June 12, 1984; 65 FR 58632, Sept. 29, 2000; 66 FR 45390, Aug. 28, 2001]

**§ 179.500 Specification DOT-107A \* \* \***  
**\* seamless steel tank car tanks.**

**§ 179.500-1 Tanks built under these specifications shall meet the requirements of § 179.500.**

**§ 179.500-3 Type and general requirements.**

(a) Tanks built under this specification shall be hollow forged or drawn in one piece. Forged tanks shall be machined inside and outside before ends are necked-down and, after necking-down, the ends shall be machined to size on the ends and outside diameter. Machining not necessary on inside or outside of seamless steel tubing, but required on ends after necking-down.

(b) For tanks made in foreign countries, chemical analysis of material and all tests as specified must be carried out within the limits of the United States under supervision of a competent and disinterested inspector; in addition to which, provisions in § 179.500-18 (b) and (c) shall be carried out at the point of manufacture by a recognized inspection bureau with principal office in the United States.

(c) The term "marked end" and "marked test pressure" used throughout this specification are defined as follows:

(1) "Marked end" is that end of the tank on which marks prescribed in § 179.500-17 are stamped.

(2) "Marked test pressure" is that pressure in psig which is indicated by the figures substituted for the \*\*\*\* in the marking DOT-107A \*\*\*\* stamped on the marked end of tank.

(d) The gas pressure at 130°F in the tank shall not exceed 7/10 of the marked test pressure of the tank.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 66 FR 45186, 45391, Aug. 28, 2001]

**§ 179.500-4 Thickness of wall.**

(a) Minimum thickness of wall of each finished tank shall be such that at a pressure equal to 7/10 of the marked

test pressure of the tank, the calculated fiber stress in psi at inner wall of tank multiplied by 3.0 will not exceed the tensile strength of any specimen taken from the tank and tested as prescribed in § 179.500-7(b). Minimum wall thickness shall be 1/4 inch.

(b) Calculations to determine the maximum marked test pressure permitted to be marked on the tank shall be made by the formula:

$$P = [10S(D^2 - d^2)] / [7(D^2 + d^2)]$$

Where:

P = Maximum marked test pressure permitted;

$$S = U / 3.0$$

Where:

U = Tensile strength of that specimen which shows the lower tensile strength of the two specimens taken from the tank and tested as prescribed in § 179.500-7(b).

3 = Factor of safety.

$(D^2 - d^2)/(D^2 + d^2)$  = The smaller value obtained for this factor by the operations specified in § 179.500-4(c).

(c) Measure at one end, in a plane perpendicular to the longitudinal axis of the tank and at least 18 inches from that end before necking-down:

d = Maximum inside diameter (inches) for the location under consideration; to be determined by direct measurement to an accuracy of 0.05 inch.

t = Minimum thickness of wall for the location under consideration; to be determined by direct measurement to an accuracy of 0.001 inch.

$$\text{Take } D = d + 2t.$$

Calculate the value of  $(D^2 - d^2)/(D^2 + d^2)$

(1) Make similar measurements and calculation for a corresponding location at the other end of the tank.

(2) Use the smaller result obtained, from the foregoing, in making calculations prescribed in paragraph (b) of this section.

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended by Amdt. 179-31, 47 FR 43067, Sept. 30, 1982; 66 FR 45391, Aug. 28, 2001]

**§ 179.500-5 Material.**

(a) Tanks shall be made from open-hearth or electric steel of uniform quality. Material shall be free from seams, cracks, laminations, or other defects injurious to finished tank. If

## § 179.500-6

not free from such defects, the surface may be machined or ground to eliminate these defects. Forgings and seamless tubing for bodies of tanks shall be stamped with heat numbers.

(b) Steel (see Note 1) must conform to the following requirements as to chemical composition:

| Designation                                | Class I<br>(percent) | Class II<br>(percent) | Class III<br>(percent) |
|--------------------------------------------|----------------------|-----------------------|------------------------|
| Carbon, maximum .....                      | 0.50                 | 0.50                  | 0.53                   |
| Manganese, maximum ..                      | 1.65                 | 1.65                  | 1.85                   |
| Phosphorus, maximum ..                     | .05                  | .05                   | .05                    |
| Sulphur, maximum .....                     | .06                  | .05                   | .05                    |
| Silicon, maximum .....                     | .35                  | .30                   | .37                    |
| Molybdenum, maximum .....                  | .....                | .25                   | .30                    |
| Chromium, maximum ....                     | .....                | .30                   | .30                    |
| Sum of manganese and carbon not over ..... | 2.10                 | 2.10                  | .....                  |

NOTE 1: Alternate steel containing other alloying elements may be used if approved.

(1) For instructions as to the obtaining and checking of chemical analysis, see § 179.500-18(b)(3).

(2) [Reserved]

## § 179.500-6 Heat treatment.

(a) Each necked-down tank shall be uniformly heat treated. Heat treatment shall consist of annealing or normalizing and tempering for Class I, Class II and Class III steel or oil quenching and tempering for Class III steel. Tempering temperatures shall not be less than 1000 °F. Heat treatment of alternate steels shall be approved. All scale shall be removed from outside of tank to an extent sufficient to allow proper inspection.

(b) To check uniformity of heat treatment, Brinell hardness tests shall be made at 18 inch intervals on the entire longitudinal axis. The hardness shall not vary more than 35 points in the length of the tank. No hardness tests need be taken within 12 inches from point of head to shell tangency.

(c) A magnetic particle inspection shall be performed after heat treatment on all tanks subjected to a quench and temper treatment to detect the presence of quenching cracks. Cracks shall be removed to sound metal by grinding and the surface exposed shall be blended smoothly into the surrounding area. A wall thickness check shall then be made of the affected area by ultrasonic equipment or other suitable means acceptable to the inspector and if the remaining wall

## 49 CFR Ch. I (10-1-08 Edition)

thickness is less than the minimum recorded thickness as determined by § 179.500-4(b) it shall be used for making the calculation prescribed in paragraph (b) of this section.

## § 179.500-7 Physical tests.

(a) Physical tests shall be made on two test specimens 0.505 inch in diameter within 2-inch gauge length, taken 180 degrees apart, one from each ring section cut from each end of each forged or drawn tube before necking-down, or one from each prolongation at each end of each necked-down tank. These test specimen ring sections or prolongations shall be heat treated, with the necked-down tank which they represent. The width of the test specimen ring section must be at least its wall thickness. Only when diameters and wall thickness will not permit removal of 0.505 by 2-inch tensile test bar, laid in the transverse direction, may test bar cut in the longitudinal direction be substituted. When the thickness will not permit obtaining a 0.505 specimen, then the largest diameter specimen obtainable in the longitudinal direction shall be used. Specimens shall have bright surface and a reduced section. When 0.505 specimen is not used the gauge length shall be a ratio of 4 to 1 length to diameter.

(b) Elastic limit as determined by extensometer, shall not exceed 70 percent of tensile strength for class I steel or 85 percent of tensile strength for class II and class III steel. Determination shall be made at cross head speed of not more than 0.125 inch per minute with an extensometer reading to 0.0002 inch. The extensometer shall be read at increments of stress not exceeding 5,000 psi. The stress at which the strain first exceeds

$$\text{stress (psi) / 30,000,000 (psi) + 0.005 (inches per inch)}$$

shall be recorded as the elastic limit.

(1) Elongation shall be at least 18 percent and reduction of area at least 35 percent.

NOTE 1: Upon approval, the ratio of elastic limit to ultimate strength may be raised to permit use of special alloy steels of definite composition that will give equal or better physical properties than steels herein specified.

(2) [Reserved]

[Amdt. 179–8, 36 FR 18470, Sept. 15, 1971, as amended at 66 FR 45391, Aug. 28, 2001]

**§ 179.500–8 Openings in tanks.**

(a) Each end shall be closed by a cover made of forged steel. Covers shall be secured to ends of tank by through bolts or studs not entering interior of tank. Covers shall be of a thickness sufficient to meet test requirements of § 179.500–12 and to compensate for the openings closed by attachments prescribed herein.

(1) It is also provided that each end may be closed by internal threading to accommodate an approved fitting. The internal threads as well as the threads on fittings for these openings shall be clean cut, even, without checks, and tapped to gauge. Taper threads are required and shall be of a length not less than as specified for American Standard taper pipe threads. External threading of an approved type shall be permissible on the internal threaded ends.

(b) Joints between covers and ends and between cover and attachments shall be of approved form and made tight against vapor or liquid leakage by means of a confined gasket of suitable material.

**§ 179.500–10 Protective housing.**

(a) Safety devices, and loading and unloading valves on tanks shall be protected from accidental damage by approved metal housing, arranged so it may be readily opened to permit inspection and adjustment of safety relief devices and valves, and securely locked in closed position. Housing shall be provided with opening having an opening equal to twice the total discharge area of pressure relief device enclosed.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964. Redesignated at 32 FR 5606, Apr. 5, 1967, and amended at 66 FR 45390, Aug. 28, 2001; 67 FR 61016, Sept. 27, 2002]

**§ 179.500–11 Loading and unloading valves.**

(a) Loading and unloading valve or valves shall be mounted on the cover or threaded into the marked end of tank. These valves shall be of approved type,

made of metal not subject to rapid deterioration by lading or in service, and shall withstand without leakage a pressure equal to the marked test pressure of tank. Provision shall be made for closing service outlet of valves.

(b) [Reserved]

**§ 179.500–12 Pressure relief devices.**

(a) Tank shall be equipped with one or more pressure relief devices of approved type and discharge area, mounted on the cover or threaded into the non-marked end of the tank. If fittings are mounted on a cover, they shall be of the flanged type, made of metal not subject to rapid deterioration by lading or in service. Total flow capacity shall be such that, with tank filled with air at pressure equal to 70 percent of the marked test pressure of tank, flow capacity will be sufficient to reduce air pressure to 30 percent of the marked test pressure within 3 minutes after pressure relief device opens.

(b) Pressure relief devices shall open at a pressure not exceeding the marked test pressure of tank and not less than  $\frac{7}{10}$  of marked test pressure. (For tolerance for pressure relief valves, see § 179.500–16(a).)

(c) Cars used for the transportation of flammable gases shall have the safety devices equipped with an approved ignition device.

[Amdt. 179–32, 48 FR 27708, June 16, 1983, as amended at 66 FR 45391, Aug. 28, 2001; 68 FR 57634, Oct. 6, 2003]

**§ 179.500–13 Fixtures.**

(a) Attachments, other than those mounted on tank covers or serving as threaded closures for the ends of the tank, are prohibited.

(b) [Reserved]

**§ 179.500–14 Test of tanks.**

(a) After heat-treatment, tanks shall be subjected to hydrostatic tests in a water jacket, or by other accurate method, operated so as to obtain reliable data. No tank shall have been subjected previously to internal pressure greater than 90 percent of the marked test pressure. Each tank shall be tested to a pressure at least equal to the marked test pressure of the tank. Pressure shall be maintained for 30 seconds,



## § 179.500-15

and sufficiently longer to insure complete expansion of tank. Pressure gauge shall permit reading to accuracy of one percent. Expansion gauge shall permit reading of total expansion to accuracy of one percent. Expansion shall be recorded in cubic cm.

(b) No leaks shall appear and permanent volumetric expansion shall not exceed 10 percent of the total volumetric expansion at test pressure.

### § 179.500-15 Handling of tanks failing in tests.

(a) Tanks rejected for failure in any of the tests prescribed may be reheat-treated, and will be acceptable if subsequent to reheat-treatment they are subjected to and pass all of the tests.

(b) [Reserved]

### § 179.500-16 Tests of pressure relief devices.

(a) Pressure relief valves shall be tested by air or gas before being put into service. Valve shall open at pressure not exceeding the marked test pressure of tank and shall be vapor-tight at 80 percent of the marked test pressure. These limiting pressures shall not be affected by any auxiliary closure or other combination.

(b) For pressure relief devices that incorporate a rupture disc, samples of the discs used shall burst at a pressure not exceeding the marked test pressure of tank and not less than  $\frac{7}{10}$  of marked test pressure.

[Amdt. 179-32, 48 FR 27708, June 16, 1983, as amended at 66 FR 45391, Aug. 28, 2001]

### § 179.500-17 Marking.

(a) Each tank shall be plainly and permanently marked, thus certifying that tank complies with all requirements of this specification. These marks shall be stamped into the metal of necked-down section of tank at marked end, in letters and figures at least  $\frac{1}{4}$  inch high, as follows:

(1) Spec. DOT-107A \* \* \* \*, the \* \* \* \* to be replaced by figures indicating marked test pressure of the tank. This pressure shall not exceed the calculated maximum marked test pressure permitted, as determined by the formula in § 179.500-4(b).

## 49 CFR Ch. I (10-1-08 Edition)

(2) Serial number immediately below the stamped mark specified in paragraph (a)(1) of this section.

(3) Inspector's official mark immediately below the stamped mark specified in paragraph (a)(1) of this section.

(4) Name, mark (other than trademark), or initials of company or person for whose use tank is being made, which shall be recorded with the Bureau of Explosives.

(5) Date (such as 1-01, for January 2001) of tank test, so placed that dates of subsequent tests may easily be added.

(6) Date (such as 1-01, for January 2001) of latest test of pressure relief device or of the rupture disc, required only when tank is used for transportation of flammable gases.

(b) [Reserved]

[29 FR 18995, Dec. 29, 1964, as amended by Amdt. 179-52, 61 FR 28682, June 5, 1996; 66 FR 45391, Aug. 28, 2001]

### § 179.500-18 Inspection and reports.

(a) Before a tank car is placed in service, the party assembling the completed car shall furnish to car owner, Bureau of Explosives, and the Secretary, Mechanical Division, Association of American Railroads, a report in proper form certifying that tanks and their equipment comply with all the requirements of this specification and including information as to serial numbers, dates of tests, and ownership marks on tanks mounted on car structure.

(b) Purchaser of tanks shall provide for inspection by a competent inspector as follows:

(1) Inspector shall carefully inspect all material and reject that not complying with § 179.500-5.

(2) Inspector shall stamp his official mark on each forging or seamless tube accepted by him for use in making tanks, and shall verify proper application of heat number to such material by occasional inspections at steel manufacturer's plant.

(3) Inspector shall obtain certified chemical analysis of each heat of material.

(4) Inspector shall make inspection of inside surface of tanks before necking-down, to insure that no seams, cracks, laminations, or other defects exist.

(5) Inspector shall fully verify compliance with specification, verify heat treatment of tank as proper; obtain samples for all tests and check chemical analyses; witness all tests; and report minimum thickness of tank wall, maximum inside diameter, and calculated value of D, for each end of each tank as prescribed in § 179.500-4(c).

(6) Inspector shall stamp his official mark on each accepted tank immediately below serial number, and make certified report (see paragraph (c) of this section) to builder, to company or person for whose use tanks are being made, to builder of car structure on which tanks are to be mounted, to the Bureau of Explosives, and to the Secretary, Mechanical Division, Association of American Railroads.

(c) Inspector's report required herein shall be in the following form:

(Place) \_\_\_\_\_  
(Date) \_\_\_\_\_

## STEEL TANKS

It is hereby certified that drawings were submitted for these tanks under AAR Application for Approval \_\_\_\_\_ and approved by the AAR Committee on Tank Cars under date of \_\_\_\_\_.

Built for \_\_\_\_\_ Company

Location at \_\_\_\_\_

Built by \_\_\_\_\_ Company

Location at \_\_\_\_\_

Consigned to \_\_\_\_\_ Company

Location at \_\_\_\_\_

Quantity \_\_\_\_\_

Length (inches) \_\_\_\_\_

Outside diameter (inches) \_\_\_\_\_

Marks stamped into tank as required in § 179.500-17 are:

DOT-107A\*\*\*\*

NOTE 1: The marked test pressure substituted for the \*\*\*\* on each tank is shown on Record of General Data on Tanks attached hereto.

Serial numbers \_\_\_\_\_ to \_\_\_\_\_ inclusive

Inspector's mark \_\_\_\_\_

Owner's mark \_\_\_\_\_

Test date \_\_\_\_\_

Water capacity (see Record of Hydrostatic Tests).

Tare weights (yes or no) (see Record of Hydrostatic Tests).

These tanks were made by process of \_\_\_\_\_

Steel used was identified as indicated by the attached list showing the serial number of each tank, followed by the heat number.

Steel used was verified as to chemical analysis and record thereof is attached here-

to. Heat numbers were stamped into metal. All material was inspected and each tank was inspected both before and after closing in ends; all material accepted was found free from seams, cracks, laminations, and other defects which might prove injurious to strength of tank. Processes of manufacture and heat-treatment of tanks were witnessed and found to be efficient and satisfactory.

Before necking-down ends, each tank was measured at each location prescribed in § 179.500-4(c) and minimum wall thickness in inches at each location was recorded; maximum inside diameter in inches at each location was recorded; value of D in inches at each location was calculated and recorded; maximum fiber stress in wall at location showing larger value for

$$(D^2 + d^2) / (D^2 - d^2)$$

was calculated for  $\frac{7}{10}$  the marked test pressure and recorded. Calculations were made by the formula:

$$S = [0.7P(D^2 - d^2) / (D^2 + d^2)]$$

Hydrostatic tests, tensile test of material, and other tests as prescribed in this specification, were made in the presence of the inspector, and all material and tanks accepted were found to be in compliance with the requirements of this specification. Records thereof are attached hereto.

I hereby certify that all of these tanks proved satisfactory in every way and comply with the requirements of Department of Transportation Specification No. 107A\*\*\*\*.

(Signed) \_\_\_\_\_

(Inspector)

(Place) \_\_\_\_\_

(Date) \_\_\_\_\_

## RECORD OF CHEMICAL ANALYSIS OF STEEL FOR TANKS

Numbered \_\_\_\_\_ to \_\_\_\_\_ inclusive

Size \_\_\_\_\_ inches outside diameter by \_\_\_\_\_ inches long

Built by \_\_\_\_\_ Company

For \_\_\_\_\_ Company

| Heat No. | Tanks represented (Serial Nos.) | Chemical analysis |    |   |   |    |    |    |    |
|----------|---------------------------------|-------------------|----|---|---|----|----|----|----|
|          |                                 | C                 | Mn | P | S | Si | Ni | Cr | Mo |

These analyses were made by

(Signed) \_\_\_\_\_

(Place) \_\_\_\_\_

(Date) \_\_\_\_\_

## RECORD OF CHEMICAL ANALYSIS OF STEEL IN TANKS

Numbered \_\_\_\_\_ to \_\_\_\_\_ inclusive

Size \_\_\_\_\_ inches outside by \_\_\_\_\_ inches long

Built by \_\_\_\_\_ Company

## Pt. 179, App. A

## 49 CFR Ch. I (10–1–08 Edition)

For \_\_\_\_\_ Company

(Signed) \_\_\_\_\_

(Place) \_\_\_\_\_

(Date) \_\_\_\_\_

| Heat No. | Tanks represented by test (serial Nos.) | Elastic limit (psi) | Tensile strength (psi) | Elongation (percent in 2 inches) | Reduction of area (percent) |
|----------|-----------------------------------------|---------------------|------------------------|----------------------------------|-----------------------------|
|          |                                         |                     |                        |                                  |                             |

## RECORD OF HYDROSTATIC TESTS ON TANKS

Numbered ..... to ..... inclusive  
 Size ..... inches outside by ..... inches long  
 Built by ..... Company  
 For ..... Company

| Serial Nos. of tanks | Actual test pressure (psig) | Total expansion (cubic cm) | Permanent expansion (cubic cm) | Percent ratio of permanent expansion to total expansion <sup>1</sup> | Tare weight (pounds) <sup>2</sup> | Capacity in pounds of water at 60 °F |
|----------------------|-----------------------------|----------------------------|--------------------------------|----------------------------------------------------------------------|-----------------------------------|--------------------------------------|
|                      |                             |                            |                                |                                                                      |                                   |                                      |

<sup>1</sup> If tests are made by method involving measurement of amount of liquid forced into tank by test pressure, then the basic data on which calculations are made, such as pump factors, temperature of liquid, coefficient of compressibility of liquid, etc., must also be given.

<sup>2</sup> Do not include protective housing, but state whether with or without valves.

(Signed) \_\_\_\_\_ (Date) \_\_\_\_\_

(Place) \_\_\_\_\_

## RECORD OF GENERAL DATA ON TANKS

Numbered ..... to ..... inclusive  
 Built by ..... Company  
 For ..... Company

| Data obtained as prescribed in § 179.500–4(c) |                                      |                                    |                                               |                                         |                                       | Larger value of the factor<br>$D^2+d^2 / D^2 -d^2$ | (S) Calculated fiber stress in psi at $\frac{7}{10}$ marked test pressure | Marked test pressure in psig stamped in tank | Minimum tensile strength of material in psi recorded |
|-----------------------------------------------|--------------------------------------|------------------------------------|-----------------------------------------------|-----------------------------------------|---------------------------------------|----------------------------------------------------|---------------------------------------------------------------------------|----------------------------------------------|------------------------------------------------------|
| Marked end of tank                            |                                      |                                    |                                               | Other end of tank                       |                                       |                                                    |                                                                           |                                              |                                                      |
| Serial No. of tank                            | (t) Min. thickness of wall in inches | (d) Max. inside diameter in inches | (D) Calculated value of $D$ in inches= $d+2t$ | (t) Minimum thickness of wall in inches | (d) Maximum inside diameter in inches |                                                    |                                                                           |                                              |                                                      |
|                                               |                                      |                                    |                                               |                                         |                                       |                                                    |                                                                           |                                              |                                                      |

(Signed) \_\_\_\_\_

[Amdt. 179–32, 48 FR 27708, June 16, 1983, as amended by 66 FR 45391, Aug. 28, 2001]

## APPENDIX A TO PART 179—PROCEDURES FOR TANK-HEAD PUNCTURE-RESISTANCE TEST

puncture-resistance systems and to test for system survivability after coupler-to-tank-head impacts at relative speeds of 29 km/

1. This test procedure is designed to verify the integrity of new or untried tank-head

hour (18 mph). Tank-head puncture-resistance is a function of one or more of the following: Head thickness, jacket thickness, insulation thickness, and material of construction.

2. *Tank-head puncture-resistance test.* A tank-head puncture-resistance system must be tested under the following conditions:

a. The ram car used must weigh at least 119,295 kg (263,000 pounds), be equipped with a coupler, and duplicate the condition of a conventional draft sill including the draft yoke and draft gear. The coupler must protrude from the end of the ram car so that it is the leading location of perpendicular contact with the impacted test car.

b. The impacted test car must be loaded with water at six percent outage with internal pressure of at least 6.9 Bar (100 psig) and coupled to one or more “backup” cars which have a total weight of 217,724 kg (480,000 pounds) with hand brakes applied on the last “backup” car.

c. At least two separate tests must be conducted with the coupler on the vertical centerline of the ram car. One test must be conducted with the coupler at a height of 53.3 cm (21 inches), plus-or-minus 2.5 cm (1 inch), above the top of the sill; the other test must be conducted with the coupler height at 79 cm (31 inches), plus-or-minus 2.5 cm (1 inch), above the top of the sill. If the combined thickness of the tank head and any additional shielding material is less than the combined thickness on the vertical centerline of the car, a third test must be conducted with the coupler positioned so as to strike the thinnest point of the tank head.

3. One of the following test conditions must be applied:

| Minimum weight of attached ram cars in kg (pounds) | Minimum velocity of impact in km/hour (mph) | Restrictions                                          |
|----------------------------------------------------|---------------------------------------------|-------------------------------------------------------|
| 119,295 (263,000) ...                              | 29 (18) .....                               | One ram car only.                                     |
| 155,582 (343,000) ...                              | 25.5 (16) .....                             | One ram car or one car plus one rigidly attached car. |
| 311,164 (686,000) ...                              | 22.5 (14) .....                             | One ram car plus one or more rigidly attached cars.   |

4. A test is successful if there is no visible leak from the standing tank car for at least one hour after impact.

[Amdt. 179–50, 60 FR 49078, Sept. 21, 1995, as amended by Amdt. 179–50, 61 FR 33256, June 26, 1996; 66 FR 45390–45391, Aug. 28, 2001]

#### APPENDIX B TO PART 179—PROCEDURES FOR SIMULATED POOL AND TORCH-FIRE TESTING

1. This test procedure is designed to measure the thermal effects of new or untried thermal protection systems and to test for

system survivability when exposed to a 100-minute pool fire and a 30-minute torch fire.

##### 2. *Simulated pool fire test.*

a. A pool-fire environment must be simulated in the following manner:

(1) The source of the simulated pool fire must be hydrocarbon fuel with a flame temperature of 871 °C (1,600 °F), plus-or-minus 37.8 °C (100 °F), throughout the duration of the test.

(2) A square bare plate with thermal properties equivalent to the material of construction of the tank car must be used. The plate dimensions must be not less than one foot by one foot by nominal 1.6 cm (0.625 inch) thick. The bare plate must be instrumented with not less than nine thermocouples to record the thermal response of the bare plate. The thermocouples must be attached to the surface not exposed to the simulated pool fire and must be divided into nine equal squares with a thermocouple placed in the center of each square.

(3) The pool-fire simulator must be constructed in a manner that results in total flame engulfment of the front surface of the bare plate. The apex of the flame must be directed at the center of the plate.

(4) The bare plate holder must be constructed in such a manner that the only heat transfer to the back side of the bare plate is by heat conduction through the plate and not by other heat paths.

(5) Before the bare plate is exposed to the simulated pool fire, none of the temperature recording devices may indicate a plate temperature in excess of 37.8 °C (100 °F) nor less than 0 °C (32 °F).

(6) A minimum of two thermocouple devices must indicate 427 °C (800 °F) after 13 minutes, plus-or-minus one minute, of simulated pool-fire exposure.

b. A thermal protection system must be tested in the simulated pool-fire environment described in paragraph 2a of this appendix in the following manner:

(1) The thermal protection system must cover one side of a bare plate as described in paragraph 2a(2) of this appendix.

(2) The non-protected side of the bare plate must be instrumented with not less than nine thermocouples placed as described in paragraph 2a(2) of this appendix to record the thermal response of the plate.

(3) Before exposure to the pool-fire simulation, none of the thermocouples on the thermal protection system configuration may indicate a plate temperature in excess of 37.8 °C (100 °F) nor less than 0 °C (32 °F).

(4) The entire surface of the thermal protection system must be exposed to the simulated pool fire.

(5) A pool-fire simulation test must run for a minimum of 100 minutes. The thermal protection system must retard the heat flow to the plate so that none of the thermocouples

## Pt. 180

on the non-protected side of the plate indicate a plate temperature in excess of 427 °C (800 °F).

(6) A minimum of three consecutive successful simulation fire tests must be performed for each thermal protection system.

### 3. *Simulated torch fire test.*

a. A torch-fire environment must be simulated in the following manner:

(1) The source of the simulated torch must be a hydrocarbon fuel with a flame temperature of 1,204 °C (2,200 °F), plus-or-minus 37.8 °C (100 °F), throughout the duration of the test. Furthermore, torch velocities must be 64.4 km/h  $\pm$  16 km/h (40 mph  $\pm$  10 mph) throughout the duration of the test.

(2) A square bare plate with thermal properties equivalent to the material of construction of the tank car must be used. The plate dimensions must be at least four feet by four feet by nominal 1.6 cm (0.625 inch) thick. The bare plate must be instrumented with not less than nine thermocouples to record the thermal response of the plate. The thermocouples must be attached to the surface not exposed to the simulated torch and must be divided into nine equal squares with a thermocouple placed in the center of each square.

(3) The bare plate holder must be constructed in such a manner that the only heat transfer to the back side of the plate is by heat conduction through the plate and not by other heat paths. The apex of the flame must be directed at the center of the plate.

(4) Before exposure to the simulated torch, none of the temperature recording devices may indicate a plate temperature in excess of 37.8 °C (100 °F) or less than 0 °C (32 °F).

(5) A minimum of two thermocouples must indicate 427 °C (800 °F) in four minutes, plus-or-minus 30 seconds, of torch simulation exposure.

b. A thermal protection system must be tested in the simulated torch-fire environment described in paragraph 3a of this appendix in the following manner:

(1) The thermal protection system must cover one side of the bare plate identical to that used to simulate a torch fire under paragraph 3a(2) of this appendix.

(2) The back of the bare plate must be instrumented with not less than nine thermocouples placed as described in paragraph 3a(2) of this appendix to record the thermal response of the material.

(3) Before exposure to the simulated torch, none of the thermocouples on the back side of the thermal protection system configuration may indicate a plate temperature in excess of 37.8 °C (100 °F) nor less than 0 °C (32 °F).

(4) The entire outside surface of the thermal protection system must be exposed to the simulated torch-fire environment.

(5) A torch-simulation test must be run for a minimum of 30 minutes. The thermal pro-

## 49 CFR Ch. I (10–1–08 Edition)

tection system must retard the heat flow to the plate so that none of the thermocouples on the backside of the bare plate indicate a plate temperature in excess of 427 °C (800 °F).

(6) A minimum of two consecutive successful torch-simulation tests must be performed for each thermal protection system.

[Amdt. 179–50, 60 FR 49078, Sept. 21, 1995]

## PART 180—CONTINUING QUALIFICATION AND MAINTENANCE OF PACKAGINGS

### Subpart A—General

Sec.

180.1 Purpose and scope.

180.2 Applicability.

180.3 General requirements.

### Subpart B [Reserved]

### Subpart C—Qualification, Maintenance and Use of Cylinders

180.201 Applicability.

180.203 Definitions.

180.205 General requirements for requalification of specification cylinders.

180.207 Requirements for requalification of UN pressure receptacles.

180.209 Requirements for requalification of specification cylinders.

180.211 Repair, rebuilding and reheat treatment of DOT-4 series specification cylinders.

180.212 Repair of seamless DOT 3-series specification cylinders and seamless UN pressure receptacles.

180.213 Requalification markings.

180.215 Reporting and record retention requirements.

180.217 Requalification requirements for MEGCs.

### Subpart D—Qualification and Maintenance of IBCs

180.350 Applicability and definitions.

180.351 Qualification of IBCs.

180.352 Requirements for retest and inspection of IBCs.

### Subpart E—Qualification and Maintenance of Cargo Tanks

180.401 Applicability.

180.403 Definitions.

180.405 Qualification of cargo tanks.

180.407 Requirements for test and inspection of specification cargo tanks.

180.409 Minimum qualifications for inspectors and testers.

180.411 Acceptable results of tests and inspections.

- 180.413 Repair, modification, stretching, re-barrelling, or mounting of specification cargo tanks.
- 180.415 Test and inspection markings.
- 180.416 Discharge system inspection and maintenance program for cargo tanks transporting liquefied compressed gases.
- 180.417 Reporting and record retention requirements.

#### **Subpart F—Qualification and Maintenance of Tank Cars**

- 180.501 Applicability.
- 180.503 Definitions.
- 180.505 Quality assurance program.
- 180.507 Qualification of tank cars.
- 180.509 Requirements for inspection and test of specification tank cars.
- 180.511 Acceptable results of inspections and tests.
- 180.513 Repairs, alterations, conversions, and modifications.
- 180.515 Markings.
- 180.517 Reporting and record retention requirements.
- 180.519 Periodic retest and inspection of tank cars other than single-unit tank car tanks.

#### **Subpart G—Qualification and Maintenance of Portable Tanks**

- 180.601 Applicability.
- 180.603 Qualification of portable tanks.
- 180.605 Requirements for periodic testing, inspection and repair of portable tanks.
- APPENDIX A TO PART 180—INTERNAL SELF-CLOSING STOP VALVE EMERGENCY CLOSURE TEST FOR LIQUEFIED COMPRESSED GASES
- APPENDIX B TO PART 180—ACCEPTABLE INTERNAL SELF-CLOSING STOP VALVE LEAKAGE TESTS FOR CARGO TANKS TRANSPORTING LIQUEFIED COMPRESSED GASES
- APPENDIX C TO PART 180—EDDY CURRENT EXAMINATION WITH VISUAL INSPECTION FOR DOT 3AL CYLINDERS MANUFACTURED OF ALUMINUM ALLOY 6351-T6

AUTHORITY: 49 U.S.C. 5101–5128; 49 CFR 1.53.

SOURCE: Amdt. 180–2, 54 FR 25032, June 12, 1989, unless otherwise noted.

#### **Subpart A—General**

##### **§ 180.1 Purpose and scope.**

This part prescribes requirements pertaining to the maintenance, reconditioning, repair, inspection and testing of packagings, and any other function having an effect on the continuing qualification and use of a packaging under the requirements of this subchapter.

##### **§ 180.2 Applicability.**

(a) Any person who performs a function prescribed in this part shall perform that function in accordance with this part.

(b) Any person who performs a function prescribed in this part is considered subject to the regulations of this subchapter when that person—

(1) Makes any representation indicating compliance with one or more of the requirements of this part; or

(2) Reintroduces into commerce a packaging that bears markings indicating compliance with this part.

[Amdt. 180–2, 54 FR 25032, June 12, 1989, as amended by Amdt. 180–2, 56 FR 27877, June 17, 1991]

##### **§ 180.3 General requirements.**

(a) No person may represent, mark, certify, sell, or offer a packaging or container as meeting the requirements of this part, or a special permit pertaining to this part issued under subchapter A of this chapter, whether or not the packaging or container is intended to be used for the transportation of a hazardous material, unless it is marked, maintained, reconditioned, repaired, or retested, as appropriate, in accordance with this part, an approval issued thereunder, or a special permit issued under subchapter A of this chapter.

(b) The representations, markings, and certifications subject to the prohibitions of paragraph (a) of this section include:

(1) Identifications that include the letters “DOT”, “MC”, “ICC”, or “UN”;

(2) Special permit, approval, and registration numbers that include the letters “DOT”;

(3) Test dates displayed in association with specification, registration, approval, or exemption markings indicating conformance to a test or retest requirement of this subchapter, an approval issued thereunder, or a special permit issued under subchapter A of this chapter;

(4) Documents indicating conformance to the testing, inspection, maintenance or other continuing qualification requirements of this part; and

(5) Sales literature, including advertising, indicating that the packaging

## § 180.201

or container represented therein conforms to requirements contained in subchapter A or C of this chapter.

[Amdt. 180-2, 54 FR 25032, June 12, 1989, as amended by Amdt. 180-3, 58 FR 33306, June 16, 1993; 70 FR 73166, Dec. 9, 2005]

### Subpart B [Reserved]

### Subpart C—Qualification, Maintenance and Use of Cylinders

SOURCE: 67 FR 51660, Aug. 8, 2002, unless otherwise noted.

#### § 180.201 Applicability.

This subpart prescribes requirements, in addition to those contained in parts 107, 171, 172, 173, and 178 of this chapter, for the continuing qualification, maintenance, or periodic requalification of DOT specification and exemption cylinders and UN pressure receptacles.

[71 FR 33894, June 12, 2006]

#### § 180.203 Definitions.

As used in this section, the word “cylinder” includes UN pressure receptacles. In addition to the definitions contained in §171.8 of this subchapter, the following definitions apply to this subpart:

*Commercially free of corrosive components* means a hazardous material having a dew point at or below minus 46.7 °C (minus 52 °F) at 101kPa (1 atmosphere) and free of components that will adversely react with the cylinder (e.g. chemical stress corrosion).

*Condemn* means a determination that a cylinder is unserviceable for the continued transportation of hazardous materials in commerce and that the cylinder may not be restored by repair, rebuilding, requalification, or any other procedure.

*Defect* means an imperfection requiring removal of a cylinder from service.

*Elastic expansion* means a temporary increase in a cylinder's volume, due to application of pressure, that is lost when pressure is released (elastic expansion = total expansion minus permanent expansion).

*Filled or charged* means an introduction or presence of a hazardous material in a cylinder.

## 49 CFR Ch. I (10–1–08 Edition)

*Non-corrosive service* means a hazardous material that, in the presence of moisture, is not corrosive to the materials of construction of a cylinder (including valve, pressure relief device, etc.).

*Over-heated* means a condition in which the temperature of any portion of an aluminum cylinder has reached 176 °C (350 °F) or higher, or in which the temperature of any portion of a steel or nickel cylinder has reached 343 °C (650 °F) or higher.

*Permanent expansion* means a permanent increase in a cylinder's volume after the test pressure is released.

*Proof pressure test* means a pressure test by interior pressurization without the determination of a cylinder's expansion.

*Rebuild* means the replacement of a pressure part (e.g. a wall, head, or pressure fitting) by welding.

*Rejected cylinder* means a cylinder that cannot be used for the transportation of a hazardous material in commerce without repair, rebuilding, and requalification.

*Repair* means a procedure for correction of a rejected cylinder that may involve welding.

*Requalification* means the completion of a visual inspection and/or the test(s) required to be performed on a cylinder to determine its suitability for continued service.

*Requalification identification number or RIN* means a code assigned by DOT to uniquely identify a cylinder requalification, repair, or rebuilding facility.

*Test pressure* means the pressure used for the requalification of a cylinder.

*Total expansion* means the total increase in a cylinder's volume due to application of the test pressure.

*Visual inspection* means an internal or external visual examination, or both, performed as part of the cylinder requalification process.

*Volumetric expansion test* means a pressure test to determine the total and permanent expansion of a cylinder at a given pressure. The *volumetric expansion test* is conducted using the water jacket or direct expansion methods:

(1) *Water jacket method* means a volumetric expansion test to determine a

cylinder's total and permanent expansion by measuring the difference between the volume of water the cylinder externally displaces at test pressure and the volume of water the cylinder externally displaces at ambient pressure.

(2) *Direct expansion method* means a volumetric expansion test to calculate a cylinder's total and permanent expansion by measuring the amount of water forced into a cylinder at test pressure, adjusted for the compressibility of water, as a means of determining the expansion.

[67 FR 51660, Aug. 8, 2002, as amended at 71 FR 33894, June 12, 2006]

**§ 180.205 General requirements for requalification of specification cylinders.**

(a) *General.* Each cylinder used for the transportation of hazardous materials must be an authorized packaging. To qualify as an authorized packaging, each cylinder must conform to this subpart, the applicable requirements specified in part 173 of this subchapter, and the applicable requirements of subpart C of part 178 of this subchapter.

(b) *Persons performing requalification functions.* No person may represent that a repair or requalification of a cylinder has been performed in accordance with the requirements in this subchapter unless that person holds a current approval issued under the procedural requirements prescribed in subpart I of part 107 of this chapter. No person may mark a cylinder with a RIN and a requalification date or otherwise represent that a DOT specification or special permit cylinder has been requalified unless all applicable requirements of this subpart have been met. A person who requalifies cylinders must maintain the records prescribed in § 180.215 at each location at which it inspects, tests, or marks cylinders.

(c) *Periodic requalification of cylinders.* Each cylinder bearing a DOT specification marking must be requalified and marked as specified in the Requalification Table in this subpart. Each cylinder bearing a DOT special permit number must be requalified and marked in conformance with this section and the terms of the applicable special permit. No cylinder may be

filled with a hazardous material and offered for transportation in commerce unless that cylinder has been successfully requalified and marked in accordance with this subpart. A cylinder may be requalified at any time during or before the month and year that the requalification is due. However, a cylinder filled before the requalification becomes due may remain in service until it is emptied. A cylinder with a specified service life may not be refilled and offered for transportation after its authorized service life has expired.

(1) Each cylinder that is requalified in accordance with the requirements specified in this section must be marked in accordance with § 180.213.

(2) Each cylinder that fails requalification must be:

(i) Rejected and may be repaired or rebuilt in accordance with § 180.211 or § 180.212, as appropriate; or

(ii) Condemned in accordance with paragraph (i) of this section.

(3) For DOT specification cylinders, the marked service pressure may be changed upon approval of the Associate Administrator and in accordance with written procedures specified in the approval.

(4) For a specification 3, 3A, 3AA, 3AL, 3AX, 3AXX, 3B, 3BN, or 3T cylinder filled with gases in other than Division 2.2, from the first requalification due on or after December 31, 2003, the burst pressure of a CG-1, CG-4, or CG-5 pressure relief device must be at test pressure with a tolerance of plus zero to minus 10%. An additional 5% tolerance is allowed when a combined rupture disc is placed inside a holder. This requirement does not apply if a CG-2, CG-3 or CG-9 thermally activated relief device or a CG-7 reclosing pressure valve is used on the cylinder.

(d) *Conditions requiring test and inspection of cylinders.* Without regard to any other periodic requalification requirements, a cylinder must be tested and inspected in accordance with this section prior to further use if—

(1) The cylinder shows evidence of dents, corrosion, cracked or abraded areas, leakage, thermal damage, or any other condition that might render it unsafe for use in transportation;



(2) The cylinder has been in an accident and has been damaged to an extent that may adversely affect its lading retention capability;

(3) The cylinder shows evidence of or is known to have been over-heated; or

(4) The Associate Administrator determines that the cylinder may be in an unsafe condition.

(e) *Cylinders containing Class 8 (corrosive) liquids.* A cylinder previously containing a Class 8 (corrosive) liquid may not be used to transport a Class 2 material in commerce unless the cylinder is—

(1) Visually inspected, internally and externally, in accordance with paragraph (f) of this section and the inspection is recorded as prescribed in § 180.215;

(2) Requalified in accordance with this section, regardless of the date of the previous requalification;

(3) Marked in accordance with § 180.213; and

(4) Decontaminated to remove all significant residue or impregnation of the Class 8 material.

(f) *Visual inspection.* Except as otherwise provided in this subpart, each time a cylinder is pressure tested, it must be given an internal and external visual inspection.

(1) The visual inspection must be performed in accordance with the following CGA Pamphlets: C-6 for steel and nickel cylinders (IBR, see § 171.7 of this subchapter); C-6.1 for seamless aluminum cylinders (IBR, see § 171.7 of this subchapter); C-6.2 for fiber reinforced composite special permit cylinders (IBR, see § 171.7 of this subchapter); C-6.3 for low pressure aluminum cylinders (IBR, see § 171.7 of this subchapter); C-8 for DOT 3HT cylinders (IBR, see § 171.7 of this subchapter); and C-13 for DOT 8 series cylinders (IBR, see § 171.7 of this subchapter).

(2) For each cylinder with a coating or attachments that would inhibit inspection of the cylinder, the coating or attachments must be removed before performing the visual inspection.

(3) Each cylinder subject to visual inspection must be approved, rejected, or condemned according to the criteria in the applicable CGA pamphlet.

(4) In addition to other requirements prescribed in this paragraph (f), each specification cylinder manufactured of aluminum alloy 6351-T6 and used in self-contained underwater breathing apparatus (SCUBA), self-contained breathing apparatus (SCBA), or oxygen service must be inspected for sustained load cracking in accordance with Appendix C of this part at the first scheduled 5-year requalification period after January 1, 2007, and every five years thereafter.

(g) *Pressure test.* (1) Unless otherwise provided, each cylinder required to be retested under this subpart must be retested by means suitable for measuring the expansion of the cylinder under pressure. Bands and other removable attachments must be loosened or removed before testing so that the cylinder is free to expand in all directions.

(2) The pressure indicating device of the testing apparatus must permit reading of pressures to within 1% of the minimum prescribed test pressure of each cylinder tested, except that for an analog device, interpolation to ½ of the marked gauge divisions is acceptable. The expansion-indicating device of the testing apparatus must also permit incremental reading of the cylinder expansion to 1% of the total expansion of each cylinder tested or 0.1 cc, whichever is larger. Midpoint visual interpolation is permitted.

(3) Each day before retesting, the retester shall confirm, by using a calibrated cylinder or other method authorized in writing by the Associate Administrator, that:

(i) The pressure-indicating device, as part of the retest apparatus, is accurate within  $\pm 1.0\%$  of the prescribed test pressure of any cylinder tested that day. The pressure indicating device, itself, must be certified as having an accuracy of  $\pm 0.5\%$ , or better, of its full range, and must permit readings of pressure from 90%-110% of the minimum prescribed test pressure of the cylinder to be tested. The accuracy of the pressure indicating device within the test system can be demonstrated at any point within 500 psig of the actual test pressure for test pressures at or above 3000 psig, or 10% of the actual test pressure for test pressures below 3000 psig.

(ii) The expansion-indicating device, as part of the retest apparatus, gives a stable reading of expansion and is accurate to  $\pm 1.0\%$  of the total expansion of any cylinder tested or 0.1 cc, whichever is larger. The expansion-indicating device itself must have an accuracy of  $\pm 0.5\%$ , or better, of its full scale.

(4) The test equipment must be verified to be accurate within  $\pm 1.0\%$  of the calibrated cylinder's pressure and corresponding expansion values. This may be accomplished by bringing the pressure to a value shown on the calibration certificate for the calibrated cylinder used and verifying that the resulting total expansion is within  $\pm 1.0\%$  of the total expansion shown on the calibration certificate. Alternatively, calibration may be demonstrated by bringing the total expansion to a known value on the calibration certificate for the calibrated cylinder used and verifying that the resulting pressure is within  $\pm 1.0\%$  of the pressure shown on the calibration certificate. The calibrated cylinder must show no permanent expansion. The retester must demonstrate calibration in conformance with this paragraph (g) to an authorized inspector on any day that it retests cylinders. A retester must maintain calibrated cylinder certificates in conformance with § 180.215(b)(4).

(5) Minimum test pressure must be maintained for at least 30 seconds, and as long as necessary for complete expansion of the cylinder. A system check may be performed at or below 90% of test pressure prior to the retest. In the case of a malfunction of the test equipment, the test may be repeated at a pressure increased by 10% or 100 psig, whichever is less. This paragraph (g) does not authorize retest of a cylinder otherwise required to be condemned under paragraph (i) of this section.

(6) Training materials (e.g., CGA publication C-1.1) may be used for training persons who requalify cylinders using the volumetric expansion test method.

(h) *Cylinder rejection.* A cylinder must be rejected when, after a visual inspection, it meets a condition for rejection under the visual inspection requirements of paragraph (f) of this section.

(1) Except as provided in paragraphs (h)(3) and (h)(4) of this section, a cyl-

inder that is rejected may not be marked as meeting the requirements of this section.

(2) The requalifier must notify the cylinder owner, in writing, that the cylinder has been rejected.

(3) Unless the cylinder is requalified in conformance with requirements in § 180.211, it may not be filled with a hazardous material and offered for transportation in commerce where use of a specification packaging is required.

(4) A rejected cylinder with a service pressure of less than 900 psig may be requalified and marked if the cylinder is repaired or rebuilt and subsequently inspected and tested in conformance with—

(i) The visual inspection requirements of paragraph (f) of this section;

(ii) Part 178 of this subchapter and this part;

(iii) Any special permit covering the manufacture, requalification, and/or use of that cylinder; and

(iv) Any approval required under § 180.211.

(i) *Cylinder condemnation.* (1) A cylinder must be condemned when—

(i) The cylinder meets a condition for condemnation under the visual inspection requirements of paragraph (f) of this section.

(ii) The cylinder leaks through its wall.

(iii) Evidence of cracking exists to the extent that the cylinder is likely to be weakened appreciably.

(iv) For a DOT specification cylinder, other than a DOT 4E aluminum cylinder or a special permit cylinder, permanent expansion exceeds 10 percent of total expansion.

(v) For a DOT 3HT cylinder—

(A) The pressure test yields an elastic expansion exceeding the marked rejection elastic expansion (REE) value.

(B) The cylinder shows evidence of denting or bulging.

(C) The cylinder bears a manufacture or an original test date older than twenty-four years or after 4380 pressurizations, whichever occurs first. If a cylinder is refilled, on average, more than once every other day, an accurate record of the number of rechargings must be maintained by the cylinder owner or the owner's agent.

§ 180.207

49 CFR Ch. I (10–1–08 Edition)

(vi) For a DOT 4E aluminum cylinder, permanent expansion exceeds 12 percent of total expansion.

(vii) For a DOT special permit cylinder, permanent expansion exceeds the limit in the applicable special permit, or the cylinder meets another criterion for condemnation in the applicable special permit.

(viii) For an aluminum or an aluminum-lined composite special permit cylinder, the cylinder is known to have been or shows evidence of having been over-heated.

(2) When a cylinder must be condemned, the requalifier must—

(i) Stamp a series of X's over the DOT specification number and the marked pressure or stamp "CONDEMNED" on the shoulder, top head, or neck using a steel stamp;

(ii) For composite cylinders, securely affix to the cylinder a label with the word "CONDEMNED" overcoated with epoxy near, but not obscuring, the original cylinder manufacturer's label; or

(iii) As an alternative to the stamping or labeling as described in this paragraph (i)(2), at the direction of the owner, the requalifier may render the cylinder incapable of holding pressure.

(3) No person may remove or obliterate the "CONDEMNED" marking. In addition, the requalifier must notify the cylinder owner, in writing, that the cylinder is condemned and may not be filled with hazardous material and offered for transportation in commerce where use of a specification packaging is required.

[67 FR 51660, Aug. 8, 2002, as amended at 68 FR 24662, May 8, 2003; 68 FR 75764, Dec. 31, 2003; 70 FR 34077, June 13, 2005; 70 FR 73166, Dec. 9, 2005; 71 FR 51128, Aug. 29, 2006; 73 FR 4720, Jan. 28, 2008]

§ 180.207 Requirements for requalification of UN pressure receptacles.

(a) *General.* (1) Each UN pressure receptacle used for the transportation of hazardous materials must conform to the requirements prescribed in paragraphs (a), (b) and (d) in § 180.205.

(2) No pressure receptacle due for requalification may be filled with a hazardous material and offered for transportation in commerce unless that pressure receptacle has been successfully requalified and marked in accordance with this subpart. A pressure receptacle may be requalified at any time during or before the month and year that the requalification is due. However, a pressure receptacle filled before the requalification becomes due may remain in service until it is emptied.

(3) No person may requalify a UN composite pressure receptacle for continued use beyond its 15-years authorized service life. A pressure receptacle with a specified service life may not be refilled and offered for transportation after its authorized service life has expired unless approval has been obtained in writing from the Associate Administrator.

(b) *Periodic requalification of UN pressure receptacles.* (1) Each pressure receptacle that is successfully requalified in accordance with the requirements specified in this section must be marked in accordance with § 180.213. The requalification results must be recorded in accordance § 180.215.

(2) Each pressure receptacle that fails requalification must be rejected or condemned in accordance with the applicable ISO requalification standard.

(c) *Requalification interval.* Each UN pressure receptacle that becomes due for periodic requalification must be requalified at the interval specified in the following table:

TABLE 1—REQUALIFICATION INTERVALS OF UN PRESSURE RECEPTACLES

| Interval (years) | UN pressure receptacles/hazardous materials                                                                                                  |
|------------------|----------------------------------------------------------------------------------------------------------------------------------------------|
| 10 .....         | Pressure receptacles for all hazardous materials except as noted below (also for dissolved acetylene, see paragraph (d)(3) of this section): |
| 5 .....          | Composite pressure receptacles.                                                                                                              |
| 5 .....          | Pressure receptacles used for:<br>All Division 2.3 materials.<br>UN1013, Carbon dioxide.                                                     |

TABLE 1—REQUALIFICATION INTERVALS OF UN PRESSURE RECEPTACLES—Continued

| Interval (years) | UN pressure receptacles/hazardous materials                                                                                                                                                                                                                                                                                                                                                         |
|------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                  | UN1043, Fertilizer ammoniating solution with free ammonia.<br>UN1051, Hydrogen cyanide, stabilized containing less than 3% water.<br>UN1052, Hydrogen fluoride, anhydrous.<br>UN1745, Bromine pentafluoride.<br>UN1746, Bromine trifluoride.<br>UN2073, Ammonia solution.<br>UN2495, Iodine pentafluoride.<br>UN2983, Ethylene Oxide and Propylene oxide mixture, not more than 30% ethylene oxide. |

(d) *Requalification procedures.* Each UN pressure receptacle that becomes due for requalification must be requalified at the interval prescribed in paragraph (c) of this section and in accordance with the procedures contained in the following standard, as applicable. When a pressure test is performed on a UN pressure receptacle, the test must be a water jacket volumetric expansion test suitable for the determination of the cylinder expansion or a hydraulic proof pressure test. The test equipment must conform to the accuracy requirements in § 180.205(g). Alternative methods (e.g., acoustic emission) or requalification procedures may be performed if prior approval has been obtained in writing from the Associate Administrator.

(1) *Seamless steel:* Each seamless steel UN pressure receptacle, including MEGC's pressure receptacles, must be requalified in accordance with ISO 6406 (IBR, see § 171.7 of this subchapter). However, UN cylinders with a tensile strength greater than or equal to 950 MPa must be requalified by ultrasonic examination in accordance with ISO 6406.

(2) *Seamless UN aluminum:* Each seamless aluminum UN pressure recep-

tacle must be requalified in accordance with ISO 10461 (IBR, see § 171.7 of this subchapter).

(3) *Dissolved acetylene UN cylinders:* Each dissolved acetylene cylinder must be requalified in accordance with ISO 10462 (IBR, see § 171.7 of this subchapter). The porous mass and the shell must be requalified no sooner than 3 years, 6 months, from the date of manufacture. Thereafter, subsequent requalifications of the porous mass and shell must be performed at least once every ten years.

(4) *Composite UN cylinders:* Each composite cylinder must be inspected and tested in accordance with ISO 11623 (IBR, see § 171.7 of this subchapter).

[71 FR 33894, June 12, 2006, as amended at 71 FR 54397, Sept. 14, 2006]

#### § 180.209 Requirements for requalification of specification cylinders.

(a) *Periodic qualification of cylinders.* (1) Each specification cylinder that becomes due for periodic requalification, as specified in the following table, must be requalified and marked in conformance with the requirements of this subpart. Requalification records must be maintained in accordance with § 180.215. Table 1 follows:

TABLE 1—REQUALIFICATION OF CYLINDERS <sup>1</sup>

| Specification under which cylinder was made | Minimum test pressure (psig) <sup>2</sup>                                    | Requalification period (years)                             |
|---------------------------------------------|------------------------------------------------------------------------------|------------------------------------------------------------|
| DOT 3 .....                                 | 3000 psig .....                                                              | 5                                                          |
| DOT 3A, 3AA .....                           | 5/3 times service pressure, except non-corrosive service (see § 180.209(g)). | 5, 10, or 12 (see § 180.209(b), (f), (h), and (j))         |
| DOT 3AL .....                               | 5/3 times service pressure .....                                             | 5 or 12 (see § 180.209(j) and § 180.209(m) <sup>3</sup> ). |
| DOT 3AX, 3AAX .....                         | 5/3 times service pressure .....                                             | 5                                                          |
| 3B, 3BN .....                               | 2 times service pressure (see § 180.209(g)).                                 | 5 or 10 (see § 180.209(f))                                 |
| 3E .....                                    | Test not required.                                                           |                                                            |
| 3HT .....                                   | 5/3 times service pressure .....                                             | 3 (see §§ 180.209(k) and 180.213(c))                       |
| 3T .....                                    | 5/3 times service pressure .....                                             | 5                                                          |
| 4AA480 .....                                | 2 times service pressure (see § 180.209(g)).                                 | 5 or 10 (see § 180.209(h))                                 |

TABLE 1—REQUALIFICATION OF CYLINDERS<sup>1</sup>—Continued

| Specification under which cylinder was made                                     | Minimum test pressure (psig) <sup>2</sup>                                                | Requalification period (years)                |
|---------------------------------------------------------------------------------|------------------------------------------------------------------------------------------|-----------------------------------------------|
| 4B, 4BA, 4BW, 4B–240ET .....                                                    | 2 times service pressure, except non-corrosive service (see § 180.209(g)).               | 5, 10, or 12 (see § 180.209(e), (f), and (j)) |
| 4D, 4DA, 4DS .....                                                              | 2 times service .....                                                                    | 5                                             |
| DOT 4E .....                                                                    | 2 times service pressure, except non-corrosive (see § 180.209(g)).                       | 5                                             |
| 4L .....                                                                        | Test not required.                                                                       |                                               |
| 8, 8AL .....                                                                    |                                                                                          | 10 or 20 (see § 180.209(i))                   |
| Exemption or special permit cylinder .....                                      | See current exemption or special permit                                                  | See current exemption or special permit       |
| Foreign cylinder (see § 173.301(j) of this subchapter for restrictions on use). | As marked on cylinder, but not less than 5/3 of any service or working pressure marking. | 5 (see §§ 180.209(l) and 180.213(d)(2))       |

<sup>1</sup> Any cylinder not exceeding 2 inches outside diameter and less than 2 feet in length is exempted from volumetric expansion test.

<sup>2</sup> For cylinders not marked with a service pressure, see § 173.301a(b) of this subchapter.

(b) *DOT 3A or 3AA cylinders.* (1) A cylinder conforming to specification DOT 3A or 3AA with a water capacity of 56.7 kg (125 lb) or less that is removed from any cluster, bank, group, rack, or vehicle each time it is filled, may be requalified every ten years instead of every five years, provided the cylinder conforms to all of the following conditions:

(i) The cylinder was manufactured after December 31, 1945.

(ii) The cylinder is used exclusively for air; argon; cyclopropane; ethylene; helium; hydrogen; krypton; neon; nitrogen; nitrous oxide; oxygen; sulfur hexafluoride; xenon; chlorinated hydrocarbons, fluorinated hydrocarbons, liquefied hydrocarbons, and mixtures thereof that are commercially free from corroding components; permitted mixtures of these gases (see § 173.301(d) of this subchapter); and permitted mixtures of these gases with up to 30 percent by volume of carbon dioxide, provided the gas has a dew point at or below minus (52 °F) at 1 atmosphere.

(iii) Before each refill, the cylinder is removed from any cluster, bank, group, rack or vehicle and passes the hammer test specified in CGA Pamphlet C–6 (IBR, see § 171.7 of this subchapter).

(iv) The cylinder is dried immediately after hydrostatic testing to remove all traces of water.

(v) The cylinder is not used for underwater breathing.

(vi) Each cylinder is stamped with a five-pointed star at least one-fourth of an inch high immediately following the test date.

(2) If, since the last required requalification, a cylinder has not been used exclusively for the gases specifically identified in paragraph (b)(1)(ii) of this section, but currently conforms with all other provisions of paragraph (b)(1) of this section, it may be requalified every 10 years instead of every five years, provided it is first requalified and examined as prescribed by § 173.302a(b) (2), (3) and (4) of this subchapter.

(3) Except as specified in paragraph (b)(2) of this section, if a cylinder, marked with a star, is filled with a compressed gas other than as specified in paragraph (b)(1)(ii) of this section, the star following the most recent test date must be obliterated. The cylinder must be requalified five years from the marked test date, or prior to the first filling with a compressed gas, if the required five-year requalification period has passed.

(c) *DOT 4-series cylinders.* A DOT 4-series cylinder, except a 4L cylinder, that at any time shows evidence of a leak or of internal or external corrosion, denting, bulging or rough usage to the extent that it is likely to be weakened appreciably, or that has lost five percent or more of its official tare weight must be requalified before being refilled and offered for transportation. (Refer to CGA Pamphlet C–6 or C–6.3, as applicable, regarding cylinder weakening.) After testing, the actual tare weight must be recorded as the new tare weight.

(d) *Cylinders 5.44 kg (12 lb) or less with service pressures of 300 psig or less.* A cylinder of 5.44 (12 lb) or less water capacity authorized for service pressure of 300 psig or less must be given a complete external visual inspection at the time periodic requalification becomes due. External visual inspection must be in accordance with CGA Pamphlet C-6 or C-6.1 (IBR, see §171.7 of this subchapter). The cylinder may be proof pressure tested. The test is successful if the cylinder, when examined under test pressure, does not display a defect described in §180.205(i)(1) (ii) or (iii). Upon successful completion of the test and inspection, the cylinder must be marked in accordance with §180.213.

(e) *Proof pressure test* A cylinder made in conformance with specifications DOT 4B, 4BA, 4BW, or 4E used exclusively for: liquefied petroleum gas that meets the detail requirement limits in Table I of ASTM D 1835, "Standard Specification for Liquefied Petroleum (LP) Gases" (IBR see §171.7 of this subchapter) or an equivalent standard containing the same limits; anhydrous dimethylamine; anhydrous methylamine; anhydrous trimethylamine; methyl chloride; methylacetylene-propadiene stabilized; or dichlorodifluoromethane, difluoroethane, difluorochloroethane, chlorodifluoromethane, chlorotetrafluoroethane, trifluorochloroethylene, or mixture thereof, or mixtures of one or more with trichlorofluoromethane; and commercially free from corroding components and protected externally by a suitable corrosion-resistant coating (such as galvanizing or painting) may be requalified by volumetric expansion testing every 12 years instead of every five years. As an alternative, the cylinder may be subjected to a proof pressure test at least two times the marked service pressure, but this latter type of test must be repeated every seven years after expiration of the first 12-year period. When subjected to a proof pressure test, the cylinder must be carefully examined under test pressure and removed from service if a leak or defect is found.

(f) *Poisonous materials.* A cylinder conforming to specification DOT 3A, 3AA, 3B, 4BA, or 4BW having a service pressure of 300 psig or less and used ex-

clusively for methyl bromide, liquid; mixtures of methyl bromide and ethylene dibromide, liquid; mixtures of methyl bromide and chlorpicrin, liquid; mixtures of methyl bromide and petroleum solvents, liquid; or methyl bromide and nonflammable, nonliquefied compressed gas mixtures, liquid; commercially free of corroding components, and protected externally by a suitable corrosion resistant coating (such as galvanizing or painting) and internally by a suitable corrosion resistant lining (such as galvanizing) may be tested every 10 years instead of every five years, provided a visual internal and external examination of the cylinder is conducted every five years in accordance with CGA Pamphlet C-6. The cylinder must be examined at each filling, and rejected if a dent, corroded area, leak or other condition indicates possible weakness.

(g) *Visual inspections.* A cylinder conforming to a specification listed in the table in this paragraph and used exclusively in the service indicated may, instead of a periodic hydrostatic test, be given a complete external visual inspection at the time periodic requalification becomes due. External visual inspection must be in accordance with CGA Pamphlet C-6 or C-6.3, as applicable (IBR, see §171.7 of this subchapter). When this inspection is used instead of hydrostatic pressure testing, subsequent inspections are required at five-year intervals after the first inspection. After May 31, 2004, inspections must be made only by persons holding a current RIN and the results recorded and maintained in accordance with §180.215. Records must include: date of inspection (month and year); DOT specification number; cylinder identification (registered symbol and serial number, date of manufacture, and owner); type of cylinder protective coating (including statement as to need of refinishing or recoating); conditions checked (e.g., leakage, corrosion, gouges, dents or digs in shell or heads, broken or damaged footing or protective ring or fire damage); disposition of cylinder (returned to service, returned to cylinder manufacturer for repairs or condemned). A cylinder passing requalification by the external visual inspection must be marked in accordance

§ 180.209

49 CFR Ch. I (10–1–08 Edition)

with §180.213. Specification cylinders must be in exclusive service as shown in the following table:

| Cylinders conforming to—                                                   | Used exclusively for—                                                                                                                                                                                                                                                 |
|----------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| DOT 3A, DOT 3AA, DOT 3A480X, DOT 4AA480 .....                              | Anhydrous ammonia of at least 99.95% purity.                                                                                                                                                                                                                          |
| DOT 3A, DOT 3AA, DOT 3A480X, DOT 3B, DOT 4B, DOT 4BA, DOT 4BW.             | Butadiene, inhibited, that is commercially free from corroding components.                                                                                                                                                                                            |
| DOT 3A, DOT 3A480X, DOT 3AA, DOT 3B, DOT 4AA480, DOT 4B, DOT 4BA, DOT 4BW. | Cyclopropane that is commercially free from corroding components.                                                                                                                                                                                                     |
| DOT 3A, DOT 3AA, DOT 3A480X, DOT 4B, DOT 4BA, DOT 4BW, DOT 4E.             | Chlorinated hydrocarbons and mixtures thereof that are commercially free from corroding components.                                                                                                                                                                   |
| DOT 3A, DOT 3AA, DOT 3A480X, DOT 4B, DOT 4BA, DOT 4BW, DOT 4E.             | Fluorinated hydrocarbons and mixtures thereof that are commercially free from corroding components.                                                                                                                                                                   |
| DOT 3A, DOT 3AA, DOT 3A480X, DOT 3B, DOT 4B, DOT 4BA, DOT 4BW, DOT 4E.     | Liquefied hydrocarbon gas that is commercially free from corroding components.                                                                                                                                                                                        |
| DOT 3A, DOT 3AA, DOT 3A480X, DOT 3B, DOT 4B, DOT 4BA, DOT 4BW, DOT 4E.     | Liquefied petroleum gas that meets the detail requirements limits in Table 1 of ASTM 1835, Standard Specification for Liquefied Petroleum (LP) Gases (incorporated by reference; see §171.7 of this subchapter) or an equivalent standard containing the same limits. |
| DOT 3A, DOT 3AA, DOT 3B, DOT 4B, DOT 4BA, DOT 4BW, DOT 4E.                 | Methylacetylene-propadiene, stabilized, that is commercially free from corroding components.                                                                                                                                                                          |
| DOT 3A, DOT 3AA, DOT 3B, DOT 4B, DOT 4BA, DOT 4BW ..                       | Anhydrous mono, di, trimethylamines that are commercially free from corroding components.                                                                                                                                                                             |
| DOT 4B240, DOT 4BW240 .....                                                | Ethyleneimine, stabilized.                                                                                                                                                                                                                                            |

(h) *Cylinders containing anhydrous ammonia.* A cylinder conforming to specification DOT 3A, 3A480X, or 4AA480 used exclusively for anhydrous ammonia, commercially free from corroding components, and protected externally by a suitable corrosion-resistant coating (such as paint) may be requalified every 10 years instead of every five years.

(i) *Requalification of DOT-8 series cylinders.* (1) Each owner of a DOT-8 series cylinder used to transport acetylene must have the cylinder shell and the porous filler requalified in accordance with CGA Pamphlet C–13 (IBR, see §171.7 of this subchapter). Requalification must be performed in accordance with the following schedule:

| Date of cylinder manufacture | Shell (visual inspection) requalification |                | Porous filler requalification    |               |
|------------------------------|-------------------------------------------|----------------|----------------------------------|---------------|
|                              | Initial                                   | Subsequent     | Initial                          | Subsequent    |
| Before January 1, 1991       | Before January 1, 2001                    | 10 years ..... | Before January 1, 2011           | Not required. |
| On or after January 1, 1991. | 10 years <sup>1</sup> .....               | 10 years ..... | 5 to 20 years <sup>2</sup> ..... | Not required. |

<sup>1</sup> Years from the date of cylinder manufacture.

<sup>2</sup> No sooner than 5 years, and no later than 20 years from the date of manufacture.

(2) Unless requalified and marked in accordance with CGA Pamphlet C–13 before October 1, 1994, an acetylene cylinder must be requalified by a person who holds a current RIN.

(3) If a cylinder valve is replaced, a cylinder valve of the same weight must be used or the tare weight of the cylinder must be adjusted to compensate for valve weight differential.

(4) The person performing a visual inspection or requalification must record the results as specified in §180.215.

(5) The person performing a visual inspection or requalification must mark the cylinder as specified in §180.213.

(j) *Cylinder used as a fire extinguisher.* Only a DOT specification cylinder used as a fire extinguisher and meeting Special Provision 18 in §172.102(c)(1) of this subchapter may be requalified in accordance with this paragraph (j).

(1) A DOT 4B, 4BA, 4B240ET or 4BW cylinder may be tested as follows:

(i) For a cylinder with a water capacity of 5.44 kg (12 lb) or less, by volumetric expansion test using the water jacket method or by proof pressure

test. A requalification must be performed by the end of 12 years after the original test date and at 12-year intervals thereafter.

(ii) For a cylinder having a water capacity over 5.44 kg (12 lb)—

(A) *By proof pressure test.* A requalification must be performed by the end of 12 years after the original test date and at 7-year intervals; or

(B) *By volumetric expansion test using the water jacket method.* A requalification must be performed 12 years after the original test date and at 12-year intervals thereafter.

(2) A DOT 3A, 3AA, or 3AL cylinder must be requalified by volumetric expansion test using the water jacket method. A requalification must be performed 12 years after the original test date and at 12-year intervals thereafter.

(k) *3HT cylinders.* In addition to the other requirements of this section, a cylinder marked DOT-3HT must be requalified in accordance with CGA C-8 (IBR, see § 171.7 of this subchapter).

(l) *Requalification of foreign cylinders filled for export.* A cylinder manufactured outside the United States, other than as provided in §§ 171.12(a) and 171.23(a) of this subchapter, that has not been manufactured, inspected, tested and marked in accordance with part 178 of this subchapter may be filled with compressed gas in the United

States, and shipped solely for export if it meets the following requirements, in addition to other requirements of this subchapter:

(1) It has been inspected, tested and marked (with only the month and year of test) in conformance with the procedures and requirements of this subpart or the Associate Administrator has authorized the filling company to fill foreign cylinders under an alternative method of qualification; and

(2) It is offered for transportation in conformance with the requirements of § 171.12(a)(4) or § 171.23(a)(4) of this subchapter.

(m) *DOT-3AL cylinders manufactured of 6351-T6 aluminum alloy.* In addition to the periodic requalification and marking described in § 180.205, each cylinder manufactured of aluminum alloy 6351-T6 used in self-contained underwater breathing apparatus (SCUBA), self-contained breathing apparatus (SCBA), or oxygen service must be requalified and inspected for sustained load cracking in accordance with the non-destructive examination method described in the following table. Each cylinder with sustained load cracking that has expanded into the neck threads must be condemned in accordance with § 180.205(i). This provision does not apply to cylinders used for carbon dioxide, fire extinguisher or other industrial gas service.

#### REQUALIFICATION AND INSPECTION OF DOT-3AL CYLINDERS MADE OF ALUMINUM ALLOY 6351-T6

| Requalification requirement                               | Examination procedure <sup>1</sup>                                                                                                                         | Sustained Load Cracking Condemnation Criteria <sup>2</sup>     | Requalification period (years) |
|-----------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------|--------------------------------|
| Eddy current examination combined with visual inspection. | Eddy current—In accordance with Appendix C of this part.<br>Visual inspection—In accordance with CGA Pamphlet C-6.1 (IBR; see § 171.7 of this subchapter). | Any crack in the neck or shoulder of 2 thread lengths or more. | 5                              |

<sup>1</sup> The requalifier performing eddy current must be familiar with the eddy current equipment and must standardize (calibrate) the system in accordance with the requirements provided in Appendix C to this part.

<sup>2</sup> The eddy current must be applied from the inside of the cylinder's neck to detect any sustained load cracking that has expanded into the neck threads.

[67 FR 51660, Aug. 8, 2002, as amended at 68 FR 24662, May 8, 2003; 68 FR 55544, Sept. 26, 2003; 68 FR 48572, Aug. 14, 2003; 68 FR 75764, Dec. 31, 2003; 70 FR 73166, Dec. 9, 2005; 71 FR 51128, Aug. 29, 2005; 72 FR 55696, Oct. 1, 2007]

EDITORIAL NOTE: The following amendment could not be incorporated into § 180.209 because of the inaccurate amendatory instruction. For the convenience of the user the

amendatory instruction and text is set forth as follows:

At 71 FR 54397, Sept. 14, 2006, § 180.209 was amended in paragraph (a)(1), the first and third entries in Table 1 were revised to read as follows:



**§ 180.209 Requirements for requalification of specification cylinders.** (1) \* \* \*

(a) \* \* \*

TABLE 1—REQUALIFICATION OF CYLINDERS

| Specification under which cylinder was made | Minimum test pressure (psig) <sup>2</sup>                               | Requalification period (years)                         |
|---------------------------------------------|-------------------------------------------------------------------------|--------------------------------------------------------|
| *<br>4B, 4BA, 4BW, 4B240ET .....            | *<br>2 times service pressure, except non-corrosive (see § 180.209(g)). | *<br>5, 7, 10, or 12 (see § 180.209(e), (f), and (j)). |
| *<br>DOT 4E .....                           | *<br>2 times service pressure, except non-corrosive (see § 180.209(g)). | *<br>5 or 7 (see § 180.209(e)).                        |

**§ 180.211 Repair, rebuilding and reheat treatment of DOT-4 series specification cylinders.**

(a) *General requirements for repair and rebuilding.* Any repair or rebuilding of a DOT 4-series cylinder must be performed by a person holding an approval as specified in § 107.805 of this chapter. A person performing a rebuild function is considered a manufacturer subject to the requirements of § 178.2(a)(2) and subpart C of part 178 of this subchapter. The person performing a repair, rebuild, or reheat treatment must record the test results as specified in § 180.215. Each cylinder that is successfully repaired or rebuilt must be marked in accordance with § 180.213.

(b) *General repair requirements.* Each repair of a DOT 4-series cylinder must be made in accordance with the following conditions:

(1) The repair and the inspection of the work performed must be made in accordance with the requirements of the cylinder specification.

(2) The person performing the repair must use the procedure, equipment, and filler metal or brazing material as authorized by the approval issued under § 107.805 of this chapter.

(3) Welding and brazing must be performed on an area free from contaminants.

(4) A weld defect, such as porosity in a pressure retaining seam, must be completely removed before re-welding. Puddling may be used to remove a weld defect only by the tungsten inert gas shielded arc process.

(5) After removal of a non-pressure attachment and before its replacement,

the cylinder must be given a visual inspection in accordance with § 180.205(f).

(6) Reheat treatment of DOT 4B, 4BA or 4BW specification cylinders after replacement of non-pressure attachments is not required when the total weld material does not exceed 20.3 cm (8 inches). Individual welds must be at least 7.6 cm (3 inches) apart.

(7) After repair of a DOT 4B, 4BA or 4BW cylinder, the weld area must be leak tested at the service pressure of the cylinder.

(8) Repair of weld defects must be free of cracks.

(9) When a non-pressure attachment with the original cylinder specification markings is replaced, all markings must be transferred to the attachment on the repaired cylinder.

(10) Walls, heads or bottoms of cylinders with defects or leaks in base metal may not be repaired, but may be replaced as provided for in paragraph (d) of this section.

(c) *Additional repair requirements for 4L cylinders.* (1) Repairs to a DOT 4L cylinder must be performed in accordance with paragraphs (a) and (b) of this section and are limited to the following:

(i) The removal of either end of the insulation jacket to permit access to the cylinder, piping system, or neck tube.

(ii) The replacement of the neck tube. At least a 13 mm (0.51 inch) piece of the original neck tube must be protruding above the cylinder's top end. The original weld attaching the neck tube to the cylinder must be sound and the replacement neck tube must be

welded to this remaining piece of the original neck tube.

(iii) The replacement of material such as, but not limited to, the insulating material and the piping system within the insulation space is authorized. The replacement material must be equivalent to that used at the time of original manufacture.

(iv) Other welding procedures that are permitted by CGA Pamphlet C-3 (IBR, see § 171.7 of this subchapter), and not excluded by the definition of "rebuild," are authorized.

(2) After repair, the cylinder must be—

(i) Pressure tested in accordance with the specifications under which the cylinder was originally manufactured;

(ii) Leak tested before and after assembly of the insulation jacket using a mass spectrometer detection system; and

(iii) Tested for heat conductivity requirements.

(d) *General rebuilding requirements.* (1) The rebuilding of a DOT 4-series cylinder must be made in accordance with the following requirements:

(i) The person rebuilding the cylinder must use the procedures and equipment as authorized by the approval issued under § 107.805 of this chapter.

(ii) After removal of a non-pressure component and before replacement of any non-pressure component, the cylinder must be visually inspected in accordance with CGA Pamphlet C-6 (IBR, see § 171.7 of this subchapter).

(iii) The rebuilder may rebuild a DOT 4B, 4BA or 4BW cylinder having a water capacity of 9.07 kg (20 lb) or greater by replacing a head of the cylinder using a circumferential joint. When this weld joint is located at other than an original welded joint, a notation of this modification must be shown on the Manufacturer's Report of Rebuilding in § 180.215(c)(2). The weld joint must be on the cylindrical section of the cylinder.

(iv) Any welding and the inspection of the rebuilt cylinder must be in accordance with the requirements of the applicable cylinder specification and the following requirements:

(A) Rebuilding of any cylinder involving a joint subject to internal pres-

sure may only be performed by fusion welding;

(B) Welding must be performed on an area free from contaminants; and

(C) A weld defect, such as porosity in a pressure retaining seam, must be completely removed before re-welding. Puddling may be used to remove a weld defect only by using the tungsten inert gas shielded arc process.

(2) Any rebuilt cylinder must be—

(i) Heat treated in accordance with paragraph (f) of this section;

(ii) Subjected to a volumetric expansion test on each cylinder. The results of the tests must conform to the applicable cylinder specification;

(iii) Inspected and have test data reviewed to determine conformance with the applicable cylinder specification; and

(iv) Made of material conforming to the specification. Determination of conformance shall include chemical analysis, verification, inspection and tensile testing of the replaced part. Tensile tests must be performed on the replaced part after heat treatment by lots defined in the applicable specification.

(3) For each rebuilt cylinder, an inspector's report must be prepared to include the information listed in § 180.215(c).

(4) Rebuilding a cylinder with brazed seams is prohibited.

(5) When an end with the original cylinder specification markings is replaced, all markings must be transferred to the rebuilt cylinder.

(e) *Additional rebuilding requirements for DOT 4L cylinders.* (1) The rebuilding of a DOT 4L cylinder must be performed in accordance with paragraph (d) of this section. Rebuilding of a DOT 4L cylinder is:

(i) Substituting or adding material in the insulation space not identical to that used in the original manufacture of that cylinder;

(ii) Making a weld repair not to exceed 150 mm (5.9 inches) in length on the longitudinal seam of the cylinder or 300 mm (11.8 inches) in length on a circumferential weld joint of the cylinder; or

(iii) Replacing the outer jacket.

(2) Reheat treatment of cylinders is prohibited.

(3) After rebuilding, each inner containment vessel must be proof pressure tested at 2 times its service pressure. Each completed assembly must be leak-tested using a mass spectrometer detection system.

(f) *Reheat treatment.* (1) Prior to reheat treatment, each cylinder must be given a visual inspection, internally and externally, in accordance with § 180.205(f).

(2) Cylinders must be segregated in lots for reheat treatment. The reheat treatment and visual inspection must be performed in accordance with the specification for the cylinders except as provided in paragraph (f)(4) of this section.

(3) After reheat treatment, each cylinder in the lot must be subjected to a volumetric expansion test and meet the acceptance criteria in the applicable specification or be scrapped.

(4) After all welding and heat treatment, a test of the new weld must be performed as required by the original specification. The test results must be recorded in accordance with § 180.215.

[67 FR 51660, Aug. 8, 2002, as amended at 68 FR 24664, May 8, 2003; 68 FR 75764, Dec. 31, 2003; 71 FR 54398, Sept. 14, 2006]

**§ 180.212 Repair of seamless DOT 3-series specification cylinders and seamless UN pressure receptacles.**

(a) *General requirements for repair of DOT 3-series cylinders and UN pressure receptacles.* (1) No person may repair a DOT 3-series cylinder or a seamless UN pressure receptacle unless—

(i) The repair facility holds an approval issued under the provisions in § 107.805 of this chapter; and

(ii) Except as provided in paragraph (b) of this section, the repair and the inspection is performed under the provisions of an approval issued under subpart H of Part 107 of this chapter and conform to the applicable cylinder specification or ISO standard contained in part 178 of this chapter.

(2) The person performing the repair must prepare a report containing, at a minimum, the results prescribed in § 180.215.

(b) *Repairs not requiring prior approval.* Approval is not required for the following specific repairs:

(1) The removal and replacement of a neck ring or foot ring on a DOT 3A, 3AA or 3B cylinder or a UN pressure receptacle that does not affect a pressure part of the cylinder when the repair is performed by a repair facility or a cylinder manufacturer of these types of cylinders. The repair may be made by welding or brazing in conformance with the original specification. After removal and before replacement, the cylinder must be visually inspected and any defective cylinder must be rejected. The heat treatment, testing and inspection of the repair must be performed under the supervision of an inspector and must be performed in accordance with the original specification.

(2) External re-threading of DOT 3AX, 3AAX or 3T specification cylinders or a UN pressure receptacle mounted in a MEGC; or the internal re-threading of a DOT-3 series cylinder or a seamless UN pressure receptacle when performed by a cylinder manufacturer of these types of cylinders. The repair work must be performed under the supervision of an independent inspection agency. Upon completion of the re-threading, the threads must be gauged in accordance with Federal Standard H-28 or an equivalent standard containing the same specification limits. The re-threaded cylinder must be stamped clearly and legibly with the words “RETHREAD” on the shoulder, top head, or neck. No DOT specification cylinder or UN cylinder may be re-threaded more than one time without approval of the Associate Administrator.

[71 FR 33895, June 12, 2006, as amended at 71 FR 54398, Sept. 14, 2006; 72 FR 55697, Oct. 1, 2007]

**§ 180.213 Requalification markings.**

(a) *General.* Each cylinder or UN pressure receptacle requalified in accordance with this subpart with acceptable results must be marked as specified in this section. Required specification markings may not be altered or removed.

(b) *Placement of markings.* Each cylinder must be plainly and permanently marked on the metal of the cylinder as permitted by the applicable specification. Unless authorized by the cylinder

specification, marking on the cylinder sidewall is prohibited.

(1) Requalification and required specification markings must be legible so as to be readily visible at all times. Illegible specification markings may be remarked on the cylinder as provided by the original specification. Requalification markings may be placed on any portion of the upper end of the cylinder excluding the sidewall, as provided in this section. Requalification and required specification markings that are illegible may be reproduced on a metal plate and attached as provided by the original specification.

(2) Previous requalification markings may not be obliterated, except that, when the space originally provided for requalification dates becomes filled, additional dates may be added as follows:

(i) All preceding requalification dates may be removed by peening provided that—

(A) Permission is obtained from the cylinder owner;

(B) The minimum wall thickness is maintained in accordance with manufacturing specifications for the cylinder; and

(C) The original manufacturing test date is not removed.

(ii) When the cylinder is fitted with a footing, additional dates may be marked on the external surface of the footing.

(c) *Requalification marking method.* The depth of requalification markings may not be greater than specified in the applicable specification. The markings must be made by stamping, engraving, scribing or other method that produces a legible, durable mark.

(1) A cylinder used as a fire extinguisher (§ 180.209(j)) may be marked by using a pressure sensitive label.

(2) For a DOT 3HT cylinder, the test date and RIN must be applied by low-stress steel stamps to a depth no greater than that prescribed at the time of manufacture. Stamping on the sidewall is not authorized.

(3) For a composite cylinder, the requalification markings must be applied on a pressure sensitive label, securely affixed in a manner prescribed by the cylinder manufacturer, near the original manufacturer's label. Stamping of

the composite surface is not authorized.

(d) *Requalification markings.* Each cylinder successfully passing requalification must be marked with the RIN set in a square pattern, between the month and year of the requalification date. The first character of the RIN must appear in the upper left corner of the square pattern; the second in the upper right; the third in the lower right; and the fourth in the lower left. Example: A cylinder requalified in September 2006, and approved by a person who has been issued RIN "A123", would be marked plainly and permanently into the metal of the cylinder in accordance with location requirements of the cylinder specification or on a metal plate permanently secured to the cylinder in accordance with paragraph (b) of this section. An example of the markings prescribed in this paragraph (d) is as follows:

|    |  |    |   |
|----|--|----|---|
| A1 |  |    |   |
| 9  |  | 06 | X |
| 32 |  |    |   |

Where:

"9" is the month of requalification

"A123" is the RIN

"06" is the year of requalification, and

"X" represents the symbols described in paragraphs (f)(2) through (f)(8) of this section.

(1) Upon written request, variation from the marking requirement may be approved by the Associate Administrator.

(2) Exception. A cylinder subject to the requirements of § 173.301(l) of this subchapter may not be marked with a RIN.

(e) *Size of markings.* The size of the markings must be at least 6.35 mm ( $\frac{1}{4}$  in.) high, except RIN characters must be at least 3.18 mm ( $\frac{1}{8}$  in.) high.

(f) *Marking illustrations.* Examples of required requalification markings for DOT specification and special permit cylinders are illustrated as follows:

(1) For designation of the 5-year volumetric expansion test, 10-year volumetric expansion test for UN cylinders and cylinders conforming to § 180.209(f)

## § 180.215

and (h), or 12-year volumetric expansion test for fire extinguishers conforming to §173.309(b) of this subchapter and cylinders conforming to §180.209(e) and 180.209(g), the marking is as illustrated in paragraph (d) of this section.

(2) For designation of the 10-year volumetric expansion test for cylinders conforming to §180.209(b), the marking is as illustrated in paragraph (d) of this section, except that the “X” is replaced with a five-point star.

(3) For designation of special filling limits up to 10% in excess of the marked service pressure for cylinders conforming to §173.302a(b) of this subchapter, the marking is as illustrated in paragraph (d) of this section, except that the “X” is replaced with a plus sign “+”.

(4) For designation of the proof pressure test, the marking is as illustrated in paragraph (d) of this section, except that the “X” is replaced with the letter “S”.

(5) For designation of the 5-year external visual inspection for cylinders conforming to §180.209(g), the marking is as illustrated in paragraph (d) of this section, except that the “X” is replaced with the letter “E”.

(6) For designation of DOT 8 series cylinder shell requalification only, the marking is as illustrated in paragraph (d) of this section, except that the “X” is replaced with the letter “S”.

(7) For designation of DOT 8 series and UN cylinder shell and porous filler requalification, the marking is as illustrated in paragraph (d) of this section, except that the “X” is replaced with the letters “FS.”

(8) For designation of a non-destructive examination combined with a visual inspection, the marking is as illustrated in paragraph (d) of this section, except that the “X” is replaced with the type of test performed, for example the letters “AE” for acoustic emission or “UE” for ultrasonic examination.

(9) For designation of the eddy current examination combined with a visual inspection, the marking is as illustrated in paragraph (d) of this section,

## 49 CFR Ch. I (10–1–08 Edition)

except the “X” is replaced with the letters “VE.”

[67 FR 51660, Aug. 8, 2002, as amended at 70 FR 73166, Dec. 9, 2005; 71 FR 33896, June 12, 2006; 71 FR 51128, Aug. 29, 2006; 71 FR 78635, Dec. 29, 2006]

### § 180.215 Reporting and record retention requirements.

(a) *Facility records.* A person who requalifies, repairs or rebuilds cylinders must maintain the following records where the requalification is performed:

(1) Current RIN issuance letter;

(2) If the RIN has expired and renewal is pending, a copy of the renewal request;

(3) Copies of notifications to Associate Administrator required under §107.805 of this chapter;

(4) Current copies of those portions of this subchapter applicable to its cylinder requalification and marking activities at that location;

(5) Current copies of all special permits governing exemption cylinders requalified or marked by the qualifier at that location; and

(6) The information contained in each applicable CGA or ASTM standard incorporated by reference in §171.7 of this subchapter applicable to the qualifier’s activities. This information must be the same as contained in the edition incorporated by reference in §171.7 of this subchapter.

(b) *Requalification records.* Daily records of visual inspection, pressure test, and ultrasonic examination if permitted under a special permit, as applicable, must be maintained by the person who performs the requalification until either the expiration of the requalification period or until the cylinder is again requalified, whichever occurs first. A single date may be used for each test sheet, provided each test on the sheet was conducted on that date. Ditto marks or a solid vertical line may be used to indicate repetition of the preceding entry for the following entries only: date; actual dimensions; manufacturer’s name or symbol, if present; owner’s name or symbol, if present; and test operator. Blank spaces may not be used to indicate repetition of a prior entry. The records must include the following information:

(1) *Calibration test records.* For each test to demonstrate calibration, the date; serial number of the calibrated cylinder; calibration test pressure; total, elastic and permanent expansions; and legible identification of test operator. The test operator must be able to demonstrate that the results of the daily calibration verification correspond to the hydrostatic tests performed on that day. The daily verification of calibration(s) may be recorded on the same sheets as, and with, test records for that date.

(2) *Pressure test and visual inspection records.* The date of requalification; serial number; DOT specification or special permit number; marked pressure; actual dimensions; manufacturer's name or symbol; owner's name or symbol, if present; result of visual inspection; actual test pressure; total, elastic and permanent expansions; percent permanent expansion; disposition, with reason for any repeated test, rejection or condemnation; and legible identification of test operator. For each cylinder marked pursuant to § 173.302a(b)(5) of this subchapter, the test sheet must indicate the method by which any average or maximum wall stress was computed. Records must be kept for all completed, as well as unsuccessful tests. The entry for a second test after a failure to hold test pressure must indicate the date of the earlier test.

(3) *Wall stress.* Calculations of average and maximum wall stress pursuant to § 173.302a(b)(3) of this subchapter, if performed.

(4) *Calibration certificates.* The most recent certificate of calibration must be maintained for each calibrated cylinder.

(c) *Repair, rebuilding or reheat treatment records.* (1) Records covering welding or brazing repairs, rebuilding or reheat treating shall be retained for a minimum of fifteen years by the approved facility.

(2) A record of rebuilding, in accordance with § 180.211(d), must be completed for each cylinder rebuilt. The record must be clear, legible, and contain the following information:

(i) Name and address of test facility, date of test report, and name of original manufacturer;

(ii) Marks stamped on cylinder to include specification number, service pressure, serial number, symbol of manufacturer, inspector's mark, and other marks, if any;

(iii) Cylinder outside diameter and length in inches;

(iv) Rebuild process (welded, brazed, type seams, etc.);

(v) Description of assembly and any attachments replaced (e.g., neckrings, footrings);

(vi) Chemical analysis of material for the cylinder, including seat and Code No., type of analysis (ladle, check), chemical components (Carbon (C), Phosphorous (P), Sulfur (S), Silicon (Si), Manganese (Mn), Nickel (Ni), Chromium (Cr), Molybdenum (Mo), Copper (Cu), Aluminum (Al), Zinc (Zn)), material manufacturer, name of person performing the analysis, results of physical tests of material for cylinder (yield strength (psi), tensile strength (psi), elongation percentage (inches), reduction in area percentage, weld bend, tensile bend, name of inspector);

(vii) Results of proof pressure test on cylinder, including test method, test pressure, total expansion, permanent expansion, elastic expansion, percent permanent expansion (permanent expansion may not exceed ten percent (10%) of total expansion), and volumetric capacity (volumetric capacity of a rebuilt cylinder must be within  $\pm 3\%$  of the calculated capacity);

(viii) Each report must include the following certification statement: "I certify that this rebuilt cylinder is accurately represented by the data above and conforms to all of the requirements in Subchapter C of Chapter I of Title 49 of the Code of Federal Regulations." The certification must be signed by the rebuild technician and principal, officer, or partner of the rebuild facility.

[67 FR 51660, Aug. 8, 2002, as amended at 68 FR 24664, May 8, 2003; 70 FR 73166, Dec. 9, 2005; 71 FR 54398, Sept. 14, 2006; 72 FR 55697, Oct. 1, 2007]

#### § 180.217 Requalification requirements for MEGCs.

(a) *Periodic inspections.* Each MEGC must be given an initial visual inspection and test in accordance with

## § 180.217

## 49 CFR Ch. I (10–1–08 Edition)

§ 178.75(i) of this subchapter before being put into service for the first time. After the initial inspection, a MEGC must be inspected at least once every five years.

(1) The 5-year periodic inspection must include an external examination of the structure, the pressure receptacles and the service equipment, as follows:

(i) The pressure receptacles are inspected externally for pitting, corrosion, abrasions, dents, distortions, defects in welds or any other conditions, including leakage, that might render the MEGC unsafe for transport.

(ii) The piping, valves, and gaskets are inspected for corroded areas, defects, and other conditions, including leakage, that might render the MEGC unsafe for filling, discharge or transport.

(iii) Missing or loose bolts or nuts on any flanged connection or blank flange are replaced or tightened.

(iv) All emergency devices and valves are free from corrosion, distortion and any damage or defect that could prevent their normal operation. Remote closure devices and self-closing stop valves must be operated to demonstrate proper operation.

(v) Required markings on the MEGC are legible in accordance with the applicable requirements.

(vi) The framework, the supports and the arrangements for lifting the MEGC are in satisfactory condition.

(2) The MEGC's pressure receptacles and piping must be periodically requalified as prescribed in § 180.207(c), at the interval specified in Table 1 in § 180.207.

(b) *Exceptional inspection and test.* If a MEGC shows evidence of damaged or corroded areas, leakage, or other conditions that indicate a deficiency that could affect the integrity of the MEGC, an exceptional inspection and test must be performed, regardless of the last periodic inspection and test. The extent of the exceptional inspection and test will depend on the amount of damage or deterioration of the MEGC. As a minimum, an exceptional inspection of a MEGC must include inspection as specified in paragraph (a)(1) of this section.

(c) *Correction of unsafe condition.* When evidence of any unsafe condition is discovered, the MEGC may not be returned to service until the unsafe condition has been corrected and the MEGC has been requalified in accordance with the applicable tests and inspection.

(d) *Repairs and modifications to MEGCs.* No person may perform a modification to an approved MEGC that may affect conformance to the applicable ISO standard or safe use, and that involve a change to the design type or affect its ability to retain the hazardous material in transportation. Before making any modification changes to an approved MEGC, the owner must obtain approval from the Associate Administrator as prescribed in § 178.74 of this subchapter. The repair of a MEGC's structural equipment is authorized provided such repairs are made in accordance with the requirements prescribed for its approved design and construction. Any repair to the pressure receptacles of a MEGC must meet the requirements of § 180.212.

(e) *Requalification markings.* Each MEGC must be durably and legibly marked in English, with the year and month, and the type of the most recent periodic requalification performed (e.g., 2004–05 AE/UE, where “AE” represents acoustic emission and “UE” represents ultrasonic examination) followed by the stamp of the approval agency who performed or witnessed the most recent test.

(f) *Records.* The owner of each MEGC or the owner's authorized agent must retain a written record of the date and results of all repairs and required inspections and tests. The report must contain the name and address of the person performing the inspection or test. The periodic test and inspection records must be retained until the next inspection or test is completed. Repair records and the initial exceptional inspection and test records must be retained during the period the MEGC is in service and for one year thereafter. These records must be made available for inspection by a representative of the Department on request.

[71 FR 33896, June 12, 2006]

### Subpart D—Qualification and Maintenance of IBCs

#### § 180.350 Applicability and definitions.

This subpart prescribes requirements, in addition to those contained in parts 107, 171, 172, 173 and 178 of this subchapter, applicable to any person responsible for the continuing qualification, maintenance, or periodic retesting of an IBC. The following definitions apply:

(a) *Remanufactured IBCs* are metal, rigid plastic or composite IBCs produced as a UN type from a non-UN type, or are converted from one UN design type to another UN design type. Remanufactured IBCs are subject to the same requirements of this subchapter that apply to new IBCs of the same type (also see § 178.801(c)(1) of this subchapter for design type definition).

(b) *Repaired IBCs* are metal, rigid plastic or composite IBCs that, as a result of impact or for any other cause (such as corrosion, embrittlement or other evidence of reduced strength as compared to the design type), are restored so as to conform to the design type and to be able to withstand the design type tests. For the purposes of this subchapter, the replacement of the rigid inner receptacle of a composite IBC with a receptacle conforming to the original manufacturer's specification is considered repair. Routine maintenance of IBCs (see definition in paragraph (c) of this section) is not considered repair. The bodies of rigid plastic IBCs and the inner receptacles of composite IBCs are not repairable.

(c) Routine maintenance of IBCs is the routine performance on:

(1) Metal, rigid plastic or composite IBCs of operations such as:

(i) Cleaning;

(ii) Removal and reinstallation or replacement of body closures (including associated gaskets), or of service equipment conforming to the original manufacturer's specifications provided that the leaktightness of the IBC is verified; or

(iii) Restoration of structural equipment not directly performing a hazardous material containment or discharge pressure retention function so as to conform to the design type (for example, the straightening of legs or

lifting attachments), provided the containment function of the IBC is not affected.

(2) Plastics or textile flexible IBCs of operations, such as:

(i) Cleaning; or

(ii) Replacement of non-integral components, such as non-integral liners and closure ties, with components conforming to the original manufacturer's specification; provided that these operations do not adversely affect the containment function of the flexible IBC or alter the design type.

[68 FR 45042, July 31, 2003, as amended at 69 FR 76186, Dec. 20, 2004]

#### § 180.351 Qualification of IBCs.

(a) *General.* Each IBC used for the transportation of hazardous materials must be an authorized packaging.

(b) *IBC specifications.* To qualify as an authorized packaging, each IBC must conform to this subpart, the applicable requirements specified in part 173 of this subchapter, and the applicable requirements of subparts N and O of part 178 of this subchapter.

[Amdt. 180-5, 59 FR 38079, July 26, 1994, as amended at 66 FR 45391, Aug. 28, 2001]

#### § 180.352 Requirements for retest and inspection of IBCs.

(a) *General.* Each IBC constructed in accordance with a UN standard for which a test or inspection specified in paragraphs (b)(1), (b)(2) and (b)(3) of this section is required may not be filled and offered for transportation or transported until the test or inspection has been successfully completed. This paragraph does not apply to any IBC filled prior to the test or inspection due date. The requirements in this section do not apply to DOT 56 and 57 portable tanks.

(b) *Test and inspections for metal, rigid plastic, and composite IBCs.* Each IBC is subject to the following test and inspections:

(1) Each IBC intended to contain solids that are loaded or discharged under pressure or intended to contain liquids must be tested in accordance with the leakproofness test prescribed in § 178.813 of this subchapter prior to its first use in transportation and every 2.5 years thereafter, starting from the



date of manufacture or the date of a repair conforming to paragraph (d)(1) of this section. For this test, the IBC is not required to have its closures fitted.

(2) An external visual inspection must be conducted initially after production and every 2.5 years starting from the date of manufacture or the date of a repair conforming to paragraph (d)(1) of this section to ensure that:

(i) The IBC is marked in accordance with requirements in §178.703 of this subchapter. Missing or damaged markings, or markings difficult to read must be restored or returned to original condition.

(ii) Service equipment is fully functional and free from damage which may cause failure. Missing, broken, or damaged parts must be repaired or replaced.

(iii) The IBC is capable of withstanding the applicable design qualification tests. The IBC must be externally inspected for cracks, warpage, corrosion or any other damage which might render the IBC unsafe for transportation. An IBC found with such defects must be removed from service or repaired in accordance with paragraph (d) of this section. The inner receptacle of a composite IBC must be removed from the outer IBC body for inspection unless the inner receptacle is bonded to the outer body or unless the outer body is constructed in such a way (e.g., a welded or riveted cage) that removal of the inner receptacle is not possible without impairing the integrity of the outer body. Defective inner receptacles must be replaced in accordance with paragraph (d) of this section or the entire IBC must be removed from service. For metal IBCs, thermal insulation must be removed to the extent necessary for proper examination of the IBC body.

(3) Each metal, rigid plastic and composite IBC must be internally inspected at least every five years to ensure that the IBC is free from damage and to ensure that the IBC is capable of withstanding the applicable design qualification tests.

(i) The IBC must be internally inspected for cracks, warpage, and corrosion or any other defect that might render the IBC unsafe for transport-

tation. An IBC found with such defects must be removed from hazardous materials service until restored to the original design type of the IBC.

(ii) Metal IBCs must be inspected to ensure the minimum wall thickness requirements in §178.705(c)(1)(iv) of this subchapter are met. Metal IBCs not conforming to minimum wall thickness requirements must be removed from hazardous materials service.

(c) *Visual inspection for flexible, fiberboard, or wooden IBCs.* Each IBC must be visually inspected prior to first use and permitted reuse, by the person who places hazardous materials in the IBC, to ensure that:

(1) The IBC is marked in accordance with requirements in §178.703 of this subchapter. Additional marking allowed for each design type may be present. Required markings that are missing, damaged or difficult to read must be restored or returned to original condition.

(2) Proper construction and design specifications have been met.

(i) Each flexible IBC must be inspected to ensure that:

(A) Lifting straps if used, are securely fastened to the IBC in accordance with the design type.

(B) Seams are free from defects in stitching, heat sealing or gluing which would render the IBC unsafe for transportation of hazardous materials. All stitched seam-ends must be secure.

(C) Fabric used to construct the IBC is free from cuts, tears and punctures. Additionally, fabric must be free from scoring which may render the IBC unsafe for transport.

(ii) Each fiberboard IBC must be inspected to ensure that:

(A) Fluting or corrugated fiberboard is firmly glued to facings.

(B) Seams are creased and free from scoring, cuts, and scratches.

(C) Joints are appropriately overlapped and glued, stitched, taped or stapled as prescribed by the design. Where staples are used, the joints must be inspected for protruding staple-ends which could puncture or abrade the inner liner. All such ends must be protected before the IBC is authorized for hazardous materials service.

(iii) Each wooden IBC must be inspected to ensure that:

(A) End joints are secured in the manner prescribed by the design.

(B) IBC walls are free from defects in wood. Inner protrusions which could puncture or abrade the liner must be covered.

(d) *Requirements applicable to repair of IBCs.* (1) Except for flexible and fiberboard IBCs and the bodies of rigid plastic and composite IBCs, damaged IBCs may be repaired and the inner receptacles of composite packagings may be replaced and returned to service provided:

(i) The repaired IBC conforms to the original design type, is capable of withstanding the applicable design qualification tests, and is retested and inspected in accordance with the applicable requirements of this section;

(ii) An IBC intended to contain liquids or solids that are loaded or discharged under pressure is subjected to a leakproofness test as specified in §178.813 of this subchapter and is marked with the date of the test; and

(iii) The IBC is subjected to the internal and external inspection requirements as specified in paragraph (b) of this section.

(iv) The person performing the tests and inspections after the repair must durably mark the IBC near the manufacturer's UN design type marking to show the following:

(A) The country in which the tests and inspections were performed;

(B) The name or authorized symbol of the person performing the tests and inspections; and

(C) The date (month, year) of the tests and inspections.

(v) Retests and inspections performed in accordance with paragraphs (d)(1)(i) and (ii) of this section may be used to satisfy the requirements for the 2.5 and five year periodic tests and inspections required by paragraph (b) of this section, as applicable.

(2) Except for flexible and fiberboard IBCs, the structural equipment of an IBC may be repaired and returned to service provided:

(i) The repaired IBC conforms to the original design type and is capable of withstanding the applicable design qualification tests; and

(ii) The IBC is subjected to the internal and external inspection require-

ments as specified in paragraph (b) of this section.

(3) Service equipment may be replaced provided:

(i) The repaired IBC conforms to the original design type and is capable of withstanding the applicable design qualification tests;

(ii) The IBC is subjected to the external visual inspection requirements as specified in paragraph (b) of this section; and

(iii) The proper functioning and leak tightness of the service equipment, if applicable, is verified.

(e) *Requirements applicable to routine maintenance of IBCs.* Except for routine maintenance of metal, rigid plastics and composite IBCs performed by the owner of the IBC, whose State and name or authorized symbol is durably marked on the IBC, the party performing the routine maintenance shall durably mark the IBC near the manufacturer's UN design type marking to show the following:

(1) The country in which the routine maintenance was carried out; and

(2) The name or authorized symbol of the party performing the routine maintenance.

(f) *Retest date.* The date of the most recent periodic retest must be marked as provided in §178.703(b) of this subchapter.

(g) *Record retention.* (1) The owner or lessee of the IBC must keep records of periodic retests, initial and periodic inspections, and tests performed on the IBC if it has been repaired or remanufactured.

(2) Records must include design types and packaging specifications, test and inspection dates, name and address of test and inspection facilities, names or name of any persons conducting test or inspections, and test or inspection specifics and results.

(3) Records must be kept for each packaging at each location where periodic tests are conducted, until such tests are successfully performed again or for at least 2.5 years from the date of the last test. These records must be

## § 180.401

made available for inspection by a representative of the Department on request.

[Amdt. 180-5, 59 FR 38079, July 26, 1994, as amended at 64 FR 10782, Mar. 5, 1999; 65 FR 58632, Sept. 29, 2000; 66 FR 45186, 45391, Aug. 28, 2001; 68 FR 45042, July 31, 2003; 69 FR 76186, Dec. 20, 2004; 70 FR 34399, June 14, 2005; 70 FR 56099, Sept. 23, 2005; 71 FR 78635, Dec. 29, 2006]

### Subpart E—Qualification and Maintenance of Cargo Tanks

#### § 180.401 Applicability.

This subpart prescribes requirements, in addition to those contained in parts 107, 171, 172, 173 and 178 of this subchapter, applicable to any person responsible for the continuing qualification, maintenance or periodic testing of a cargo tank.

[Amdt. 180-2, 54 FR 25032, June 12, 1989, as amended at 55 FR 37065, Sept. 7, 1990]

#### § 180.403 Definitions.

In addition to the definitions contained in §§171.8, 178.320(a) and 178.345-1 of this subchapter, the following definitions apply to this subpart:

*Corroded or abraded* means any visible reduction in the material thickness of the cargo tank wall or valve due to pitting, flaking, gouging, or chemical reaction to the material surface that effects the safety or serviceability of the cargo tank. The term does not include cosmetic or minor surface degradation that does not effect the safety or serviceability of the cargo tank.

*Corrosive to the tank or valve* means that the lading has been shown through experience or test data to reduce the thickness of the material of construction of the tank wall or valve.

*Delivery hose assembly* means a liquid delivery hose and its attached couplings.

*Modification* means any change to the original design and construction of a cargo tank or a cargo tank motor vehicle that affects its structural integrity or lading retention capability including changes to equipment certified as part of an emergency discharge control system required by §173.315(n)(2) of this subchapter. Any modification that involves welding on the cargo tank wall must also meet all requirements for

## 49 CFR Ch. I (10-1-08 Edition)

“Repair” as defined in this section. Excluded from this category are the following:

(1) A change to motor vehicle equipment such as lights, truck or tractor power train components, steering and brake systems, and suspension parts, and changes to appurtenances, such as fender attachments, lighting brackets, ladder brackets; and

(2) Replacement of components such as valves, vents, and fittings with a component of a similar design and of the same size.

*Owner* means the person who owns a cargo tank motor vehicle used for the transportation of hazardous materials, or that person’s authorized agent.

*Piping system* means any component of a cargo tank delivery system, other than a delivery hose assembly, that contains product during loading or unloading.

*Rebarrelling* means replacing more than 50 percent of the combined shell and head material of a cargo tank.

*Repair* means any welding on a cargo tank wall done to return a cargo tank or a cargo tank motor vehicle to its original design and construction specification, or to a condition prescribed for a later equivalent specification in effect at the time of the repair. Excluded from this category are the following:

(1) A change to motor vehicle equipment such as lights, truck or tractor power train components, steering and brake systems, and suspension parts, and changes to appurtenances, such as fender attachments, lighting brackets, ladder brackets; and

(2) Replacement of components such as valves, vents, and fittings with a component of a similar design and of the same size.

(3) Replacement of an appurtenance by welding to a mounting pad.

*Replacement of a barrel* means to replace the existing tank on a motor vehicle chassis with an unused (new) tank. For the definition of *tank*, see §178.320, §178.345, or §178.338-1 of this subchapter, as applicable.

*Stretching* means any change in length, width or diameter of the cargo tank, or any change to a cargo tank motor vehicle’s undercarriage that

may affect the cargo tank's structural integrity.

[Amdt. 180-2, 54 FR 25032, June 12, 1989, as amended at 55 FR 37065, Sept. 7, 1990; Amdt. 180-3, 57 FR 45466, Oct. 1, 1992; Amdt. 180-7, 59 FR 55177, Nov. 3, 1994; 60 FR 17402, Apr. 5, 1995; Amdt. 180-10, 61 FR 51342, Oct. 1, 1996; 63 FR 52850, Oct. 1, 1998; 64 FR 28050, May 24, 1999; 68 FR 19286, Apr. 18, 2003; 69 FR 54047, Sept. 7, 2004]

#### § 180.405 Qualification of cargo tanks.

(a) *General.* Unless otherwise provided in this subpart, each cargo tank used for the transportation of hazardous material must be an authorized packaging.

(b) *Cargo tank specifications.* (1) To qualify as an authorized packaging, each cargo tank must conform to this subpart, the applicable requirements specified in part 173 of this subchapter for the specific lading, and where a DOT specification cargo tank is required, an applicable specification in effect on the date initial construction began: MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, MC 312, MC 330, MC 331, MC 338, DOT 406, DOT 407, or DOT 412 (§§ 178.337, 178.338, 178.345, 178.346, 178.347, 178.348 of this subchapter). However, except as provided in paragraphs (b)(2), (d), (e), (f)(5), and (f)(6) of this section, no cargo tank may be marked or certified after August 31, 1995, to the applicable MC 306, MC 307, MC 312, MC 331, or MC 338 specification in effect on December 30, 1990.

(2) *Exception.* A cargo tank originally manufactured to the MC 306, MC 307, or MC 312 specification may be recertified to the original specification provided:

(i) Records are available verifying the cargo tank was originally manufactured to the specification;

(ii) If the cargo tank was stretched, rebarrelled, or modified, records are available verifying that the stretching, rebarrelling, or modification was performed in accordance with the National Board Inspection Code and this part;

(iii) A Design Certifying Engineer or Registered Inspector verifies the cargo tank conforms to all applicable requirements of the original specification and furnishes to the owner written documentation that verifies the tank

conforms to the original structural design requirements in effect at the time the tank was originally constructed;

(iv) The cargo tank meets all applicable tests and inspections required by § 180.407(c); and

(v) The cargo tank is recertified to the original specification in accordance with the reporting and record retention provisions of § 180.417. The certification documents required by § 180.417(a)(3) must include both the date the cargo tank was originally certified to the specification and the date it was recertified. The specification plate on the cargo tank or the cargo tank motor vehicle must display the date the cargo tank was originally certified to the specification.

(c) *Cargo tank specifications no longer authorized for construction.* (1) A cargo tank made to a specification listed in column 1 of table 1 or table 2 of this paragraph (c)(1) may be used when authorized in this part, provided—

(i) The cargo tank initial construction began on or before the date listed in table 1, column 2, as follows:

TABLE 1

| Column 1                                        | Column 2      |
|-------------------------------------------------|---------------|
| MC 300 .....                                    | Sept. 2, 1967 |
| MC 301 .....                                    | June 12, 1961 |
| MC 302, MC 303, MC 304, MC 305, MC 310, MC 311. | Sept. 2, 1967 |
| MC 330 .....                                    | May 15, 1967  |

(ii) The cargo tank was marked or certified before the date listed in table 2, column 2, as follows:

TABLE 2

| Column 1                     | Column 2      |
|------------------------------|---------------|
| MC 306, MC 307, MC 312 ..... | Sept. 1, 1995 |

(2) A cargo tank of a specification listed in paragraph (c)(1) of this section may have its pressure relief devices and outlets modified as follows:

(i) A Specification MC 300, MC 301, MC 302, MC 303, or MC 305 cargo tank, to conform with a Specification MC 306 or DOT 406 cargo tank (See §§ 178.346-3 and 178.346-4 of this subchapter).

(ii) A Specification MC 306 cargo tank to conform to a Specification DOT 406 cargo tank (See §§ 178.346-3 and 178.346-4 of this subchapter).

(iii) A Specification MC 304 cargo tank, to conform with a Specification MC 307 or DOT 407 cargo tank (See §§ 178.347–4 and 178.345–11 of this subchapter).

(iv) A Specification MC 307 cargo tank, to conform with a Specification DOT 407 cargo tank (See §§ 178.347–4 and 178.345–11 of this subchapter).

(v) A Specification MC 310 or MC 311 cargo tank, to conform with a Specification MC 312 or DOT 412 cargo tank (See §§ 178.348–4 and 178.345–11 of this subchapter).

(vi) A Specification MC 312 cargo tank, to conform with a Specification DOT 412 cargo tank (See §§ 178.348–4 and 178.345–11 of this subchapter).

(vii) A Specification MC 330 cargo tank, to conform with a Specification MC 331 cargo tank, except as specifically required by § 173.315 of this subchapter (see §§ 178.337–8 and 178.337–9 of this subchapter).

(d) *MC 338 cargo tank.* The owner of a cargo tank that conforms to and was used under the terms of an exemption issued before October 1, 1984, that authorizes the transportation of a cryogenic liquid shall remove the exemption number stenciled on the cargo tank and stamp the specification plate (or a plate placed adjacent to the specification plate) “DOT MC 338” followed by the exemption number, for example, “DOT MC 338–E \* \* \* \*”. (Asterisks to be replaced by the exemption number). The cargo tank must be remarked prior to the expiration date of the exemption. During the period the cargo tank is in service, the owner of a cargo tank that is remarked in this manner must retain at its principal place of business a copy of the last exemption in effect. No new construction of cargo tanks pursuant to such exemption is authorized.

(1) The holding time must be determined, as required in § 178.338–9 of this subchapter, on each cargo tank or on at least one cargo tank of each design. Any subsequent cargo tank manufactured to the same design type (see § 178.320), if not individually tested, must have the optional test regimen performed during the first shipment (see § 178.338–9 (b) and (c) of this subchapter).

(2) The holding time determined by test for one authorized cryogenic liquid may be used as the basis for establishing the holding time for other authorized cryogenic liquids.

(e) *MC 331 cargo tanks.* The owner of a MC 331 (§ 178.337 of this subchapter) cargo tank that conforms to and was used under an exemption issued before October 1, 1984, that authorizes the transportation of ethane, refrigerated liquid; ethane-propane mixture, refrigerated liquid; or hydrogen chloride, refrigerated liquid shall remove the exemption number stenciled on the cargo tank and stamp the exemption number on the specification plate (or a plate placed adjacent to the specification plate), immediately after the DOT Specification, for example, “DOT MC 331–E \* \* \* \*”. (Asterisks to be replaced by the exemption number.) The cargo tank must be remarked prior to the expiration date of the exemption. During the period the cargo tank is in service, the owner of a cargo tank that is remarked in this manner must retain at the owner’s principal place of business a copy of the last exemption in effect.

(f) *MC 306, MC 307, MC 312 cargo tanks.* Either a Registered Inspector or a Design Certifying Engineer and the owner of a MC 306, MC 307 or MC 312 cargo tank motor vehicle constructed in accordance with and used under an exemption issued before December 31, 1990, that authorizes a condition specified in this paragraph shall examine the cargo tank motor vehicle and its design to determine if it meets the requirements of the applicable MC 306, MC 307 or MC 312 specification in effect at the time of manufacture, except as specified herein.

(1) A cargo tank motor vehicle constructed after August 1, 1981, or the date specified in the applicable exemption, in conformance with the following conditions that apply, may be remarked and certified in accordance with paragraphs (f) (5) and (6) of this section:

(i) A vacuum-loaded cargo tank must have an ASME Code stamped specification plate marked with a minimum internal design pressure of 25 psig, and be designed for a minimum external design pressure of 15 psig.

(ii) An outlet equipped with a self-closing system which includes an external stop-valve must have the stop valve and associated piping protected within the vehicle's rear-end tank protection device, vehicle frame or an equally adequate accident damage protection device (See §178.345-8 of this subchapter.) The self-closing system (See §178.345-11 of this subchapter) must be equipped with a remotely actuated means of closure as follows:

(A) For a cargo tank used in other than corrosive service, the remote means of closure must be activated for closure by manual or mechanical means and, in case of fire, by an automatic heat activated means.

(B) For a cargo tank used in corrosive service, the remote means of closure may be actuated by manual or mechanical means only.

(iii) A cargo tank having an unreinforced portion of the shell exceeding 60 inches must have the circumferential reinforcement located so that the thickness and tensile strength of shell material in combination with the frame and circumferential reinforcement produces a structural integrity at least equal to that prescribed in §178.345-3 of this subchapter or the specification in effect at time of manufacture.

(iv) A cargo tank having a projection from the tank shell or head that may contain lading in any tank position is authorized, provided such projection is as strong as the tank shell or head and is located within the motor vehicle's rear-end tank protection or other appropriate accident damage protection device.

(v) A cargo tank may be constructed of nickel, titanium, or other ASME sheet or plate materials in accordance with an exemption.

(2) A vacuum-loaded cargo tank constructed after August 1, 1981, or the date specified in the applicable exemption, in conformance with paragraph (f)(1) of this section, except that an outlet equipped with an external valve which is not part of a self-closing system:

(i) Must be equipped with a self-closing system prior to September 1, 1993.

(ii) May be remarked and certified in accordance with paragraphs (f)(5) and

(6) of this section after the cargo tank motor vehicle has been equipped with the self-closing system.

(3) A vacuum-loaded cargo tank constructed prior to August 1, 1981, in conformance with paragraph (f)(1) of this section, except for paragraph (f)(1)(i), may be remarked and certified in accordance with paragraphs (f) (5) and (6) of this section.

(4) A vacuum-loaded cargo tank constructed prior to August 1, 1981, in conformance with paragraph (f)(1) of this section, except for paragraph (f)(1)(i) of this section, and except that an outlet is equipped with an external valve which is not part of a self-closing system:

(i) Must be equipped with a self-closing system prior to September 1, 1993.

(ii) May be remarked and certified in accordance with paragraphs (f)(5) and (6) of this section after the cargo tank motor vehicle has been equipped with the self-closing system.

(5) The owner of a cargo tank for which a determination has been made that the cargo tank is in conformance with paragraph (f) (1), (2), (3), or (4) of this section shall complete a written certification, in English, signed by the owner and containing at least the following information:

(i) A statement certifying that each cargo tank conforms to §180.405 (f) (1), (2), (3), or (4);

(ii) The applicable DOT exemption number, the applicable specification number and the owner's and manufacturer's serial number for the cargo tank;

(iii) A statement setting forth any modifications made to bring the cargo tank into conformance with §180.405(f) (1), (2), (3), or (4), or the applicable specification;

(iv) A statement identifying the person certifying the cargo tank and the date of certification.

(6) The owner of a certified cargo tank shall remove the exemption number stenciled on the cargo tank and shall durably mark the specification plate (or a plate placed adjacent to the specification plate) "MC +++-E \*\*\*\*\*" (where "+++" is to be replaced by the applicable specification number, "\*\*\*\*\*" by the exemption number and "# # # #" by the alloy.)

## § 180.405

## 49 CFR Ch. I (10–1–08 Edition)

(7) A cargo tank remarked and certified in conformance with this paragraph (f) is excepted from the provisions of § 180.405(c).

(8) During the period the cargo tank is in service, and for one year thereafter, the owner of a cargo tank that is certified and remarked in this manner must retain on file at its principal place of business a copy of the certificate and the last exemption in effect.

(g) *Cargo tank manhole assemblies.* (1) MC 306, MC 307, and MC 312 cargo tanks marked or certified after December 30, 1990, and DOT 406, DOT 407, and DOT 412 cargo tank motor vehicles must be equipped with manhole assemblies conforming with § 178.345–5 of this subchapter.

(2) On or before August 31, 1995, each owner of a cargo tank marked or certified before December 31, 1990, authorized for the transportation of a hazardous material, must have the cargo tank equipped with manhole assemblies conforming with § 178.345–5, except for the dimensional requirements in § 178.345–5(a), the hydrostatic testing requirements in § 178.345–5(b), and the marking requirements in § 178.345–5(e) of this subchapter. A manhole assembly meeting one of the following provisions is considered to be in compliance with this paragraph:

(i) Manhole assemblies on MC 300, MC 301, MC 302, MC 303, MC 305, MC 306, MC 310, MC 311, and MC 312 cargo tanks that are marked or certified in writing as conforming to § 178.345–5 of this subchapter or TTMA RP No. 61–98 (incorporated by reference; see § 171.7 of this subchapter), or are tested and certified in accordance with TTMA TB No. 107 (incorporated by reference; see § 171.7 of this subchapter).

(ii) Manhole assemblies on MC 304 and MC 307 cargo tanks.

(iii) Manhole assemblies on MC 310, MC 311, and MC 312 cargo tanks with a test pressure of 36 psig or greater.

(3) [Reserved]

(h) *Pressure relief system.* Properly functioning reclosing pressure relief valves and frangible or fusible vents need not be replaced. However, replacement of reclosing pressure relief valves on MC-specification cargo tanks is authorized subject to the following requirements:

(1) Until August 31, 1998, the owner of a cargo tank may replace a reclosing pressure relief device with a device which is in compliance with the requirements for pressure relief devices in effect at the time the cargo tank specification became superseded. If the pressure relief device is installed as an integral part of a manhole cover assembly, the manhole cover must comply with the requirements of paragraph (g) of this section.

(2) After August 31, 1998, replacement for any reclosing pressure relief valve must be capable of reseating to a leak-tight condition after a pressure surge, and the volume of lading released may not exceed 1 L. Specific performance requirements for these pressure relief valves are set forth in § 178.345–10(b)(3) of this subchapter.

(3) As provided in paragraph (c)(2) of this section, the owner of a cargo tank may elect to modify reclosing pressure relief devices to more recent cargo tank specifications. However, replacement devices constructed to the requirements of § 178.345–10 of this subchapter must provide the minimum venting capacity required by the original specification to which the cargo tank was designed and constructed.

(i) *Flammable cryogenic liquids.* Each cargo tank used to transport a flammable cryogenic liquid must be examined after each shipment to determine its actual holding time (See § 173.318(g)(3) of this subchapter.)

(j) *Withdrawal of certification.* A specification cargo tank that for any reason no longer meets the applicable specification may not be used to transport hazardous materials unless the cargo tank is repaired and retested in accordance with §§ 180.413 and 180.407 prior to being returned to hazardous materials service. If the cargo tank is not in conformance with the applicable specification requirements, the specification plate on the cargo tank must be removed, obliterated or securely covered. The details of the conditions necessitating withdrawal of the certification must be recorded and signed on the written certificate for that cargo tank. The vehicle owner shall retain the certificate for at least 1 year after withdrawal of the certification.

(k) *DOT-specification cargo tank with no marked design pressure or a marked design pressure of less than 3 psig.* The owner of an MC 300, MC 301, MC 302, MC 303, MC 305, MC 306, or MC 312 cargo tank with a pressure relief system set at 3 psig, must mark or remark the cargo tank with an MAWP or design pressure of not less than 3 psig.

(l) *MC 300, MC 301, MC 302, MC 303, MC 305, MC 306 cargo tank—Rear accident damage protection.* (1) Notwithstanding the requirements in § 180.405(b), the applicable specification requirement for a rear bumper or rear-end tank protection device on MC 300, MC 301, MC 302, MC 303, MC 305, and MC 306 cargo tanks does not apply to a cargo tank truck (power unit) until July 1, 1992, if the cargo tank truck—

(i) Was manufactured before July 1, 1989;

(ii) Is used to transport gasoline or any other petroleum distillate product; and

(iii) Is operated in combination with a cargo tank full trailer. However, an empty cargo tank truck, without a cargo tank full trailer attached, may be operated without the required rear bumper or rear-end tank protection device on a one-time basis while being transported to a repair facility for installation of a rear bumper or rear-end protection device.

(2) Each cargo tank shall be provided with a rear accident damage protection device to protect the tank and piping in the event of a rear-end collision and reduce the likelihood of damage which could result in the loss of lading. The rear-end protection device must be in the form of a rear-end tank protection device meeting the requirements of § 178.345–8(d) or a rear bumper meeting the following:

(i) The bumper shall be located at least 6 inches to the rear of any vehicle component used for loading or unloading or that may contain lading while the vehicle is in transit.

(ii) The dimensions of the bumper shall conform to § 393.86 of this title.

(iii) The structure of the bumper must be designed in accordance with § 178.345–8(d)(3) of this subchapter.

(m) *Specification MC 330, MC 331 cargo tank motor vehicles, and nonspecification cargo tank motor vehicles conforming to*

*§ 173.315(k) of this subchapter, intended for use in the transportation of liquefied compressed gases.* (1) No later than the date of its first scheduled pressure test after July 1, 2001, each specification MC 330 and MC 331 cargo tank motor vehicle, and each nonspecification cargo tank motor vehicle conforming to § 173.315(k) of this subchapter, marked and certified before July 1, 2001, that is used to transport a Division 2.1 material, a Division 2.2 material with a subsidiary hazard, a Division 2.3 material, or anhydrous ammonia must have an emergency discharge control capability as specified in § 173.315(n) of this subchapter. Each passive shut-off system installed prior to July 1, 2001, must be certified by a Design Certifying Engineer that it meets the requirements of § 173.315(n)(2) of this subchapter.

(2) The requirement in paragraph (m)(1) of this section does not apply to a cargo tank equal to or less than 13,247.5 L (3,500 gallons) water capacity transporting in metered delivery service a Division 2.1 material, a Division 2.2 material with a subsidiary hazard, or anhydrous ammonia equipped with an off-truck remote shut-off device that was installed prior to July 1, 2000. The device must be capable of stopping the transfer of lading by operation of a transmitter carried by a qualified person attending unloading of the cargo tank. The device is subject to the requirement in § 177.840(o) of this subchapter for a daily test at 45.72 meters (150 feet).

(3) Each specification MC 330 and MC 331 cargo tank in metered delivery service of greater than 13,247.5 L (3,500 gallons) water capacity transporting a Division 2.1 material, a Division 2.2 material with a subsidiary hazard, or anhydrous ammonia, marked and certified before July 1, 1999, must have an emergency discharge control capability as specified in §§ 173.315(n) and 177.840 of this subchapter no later than the date of its first scheduled pressure test after July 1, 2001, or July 1, 2003, whichever is earlier.

(n) *Thermal activation.* No later than the date of its first scheduled leakage test after July 1, 1999, each specification MC 330 or MC 331 cargo tank



motor vehicle and each nonspecification cargo tank motor vehicle conforming to §173.315(k) of this subchapter, marked and certified before July 1, 1999, that is used to transport a liquefied compressed gas, other than carbon dioxide and chlorine, that has a water capacity of 13,247.5 L (3,500 gallons) or less must be equipped with a means of thermal activation for the internal self-closing stop valve as specified in §178.337–8(a)(4) of this subchapter.

(o) *On-truck remote control of self-closing stop valves—MC 330, MC 331, and MC 338.* On or before October 2, 2006—

(1) Each owner of an MC 330 or MC 331 cargo tank motor vehicle marked or certified before January 1, 1995, must equip the cargo tank with an on-vehicle remote means of closure of the internal self-closing stop valve in conformance with §178.337–8(a)(4) of this subchapter. This requirement does not apply to cargo tanks used only for carbon dioxide and marked “For carbon dioxide only” or intended for use in chlorine service only.

(2) Each owner of an MC 338 cargo tank motor vehicle marked or certified before January 1, 1995, must equip each remotely controlled shutoff valve with an on-vehicle remote means of automatic closure in conformance with §178.338–11(c) of this subchapter. This requirement does not apply to cargo tanks used for the transportation of argon, carbon dioxide, helium, krypton, neon, nitrogen, or xenon, or mixtures thereof.

[Amdt. 180–2, 54 FR 25032, June 12, 1989]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 180.405, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

**§ 180.407 Requirements for test and inspection of specification cargo tanks.**

(a) *General.* (1) A cargo tank constructed in accordance with a DOT specification for which a test or inspection specified in this section has become due, may not be filled and offered for transportation or transported until the test or inspection has been successfully completed. This paragraph does

not apply to any cargo tank filled prior to the test or inspection due date.

(2) Except during a pressure test, a cargo tank may not be subjected to a pressure greater than its design pressure or MAWP.

(3) A person witnessing or performing a test or inspection specified in this section must meet the minimum qualifications prescribed in § 180.409.

(4) Each cargo tank must be evaluated in accordance with the acceptable results of tests and inspections prescribed in § 180.411.

(5) Each cargo tank which has successfully passed a test or inspection specified in this section must be marked in accordance with § 180.415.

(6) A cargo tank which fails a prescribed test or inspection must:

(i) Be repaired and retested in accordance with § 180.413; or

(ii) Be removed from hazardous materials service and the specification plate removed, obliterated or covered in a secure manner.

(b) *Conditions requiring test and inspection of cargo tanks.* Without regard to any other test or inspection requirements, a specification cargo tank must be tested and inspected in accordance with this section prior to further use if:

(1) The cargo tank shows evidence of dents, cuts, gouges, corroded or abraded areas, leakage, or any other condition that might render it unsafe for hazardous materials service. At a minimum, any area of a cargo tank showing evidence of dents, cuts, digs, gouges, or corroded or abraded areas must be thickness tested in accordance with the procedures set forth in paragraphs (i)(2), (i)(3), (i)(5), and (i)(6) of this section and evaluated in accordance with the criteria prescribed in § 180.411. Any signs of leakage must be repaired in accordance with § 180.413. The suitability of any repair affecting the structural integrity of the cargo tank must be determined either by the testing required in the applicable manufacturing specification or in paragraph (g)(1)(iv) of this section.

(2) The cargo tank has sustained damage to an extent that may adversely affect its lading retention capability. A damaged cargo tank must be pressure tested in accordance with the

procedures set forth in paragraph (g) of this section.

(3) The cargo tank has been out of hazardous materials transportation service for a period of one year or more. Each cargo tank that has been out of hazardous materials transportation service for a period of one year or more must be pressure tested in accordance with §180.407(g) prior to further use.

(4) [Reserved]

(5) The Department so requires based on the existence of probable cause that

the cargo tank is in an unsafe operating condition.

(c) *Periodic test and inspection.* Each specification cargo tank must be tested and inspected as specified in the following table by an inspector meeting the qualifications in §180.409. The retest date shall be determined from the specified interval identified in the following table from the most recent inspection or the CTMV certification date.

COMPLIANCE DATES—INSPECTIONS AND TEST UNDER §180.407(C)

| Test or inspection (cargo tank specification, configuration, and service)                  | Date by which first test must be completed (see note 1) | Interval period after first test |
|--------------------------------------------------------------------------------------------|---------------------------------------------------------|----------------------------------|
| External Visual Inspection:                                                                |                                                         |                                  |
| All cargo tanks designed to be loaded by vacuum with full opening rear heads.              | September 1, 1991 .....                                 | 6 months.                        |
| All other cargo tanks .....                                                                | September 1, 1991 .....                                 | 1 year.                          |
| Internal Visual Inspection:                                                                |                                                         |                                  |
| All insulated cargo tanks, except MC 330, MC 331, MC 338 (see Note 4).                     | September 1, 1991 .....                                 | 1 year.                          |
| All cargo tanks transporting lading corrosive to the tank .....                            | September 1, 1991 .....                                 | 1 year.                          |
| All other cargo tanks, except MC 338 .....                                                 | September 1, 1995 .....                                 | 5 years.                         |
| Lining Inspection:                                                                         |                                                         |                                  |
| All lined cargo tanks transporting lading corrosive to the tank .....                      | September 1, 1991 .....                                 | 1 year.                          |
| Leakage Test:                                                                              |                                                         |                                  |
| MC 330 and MC 331 cargo tanks in chlorine service .....                                    | September 1, 1991 .....                                 | 2 years.                         |
| All other cargo tanks except MC 338 .....                                                  | September 1, 1991 .....                                 | 1 year.                          |
| Pressure Test:                                                                             |                                                         |                                  |
| (Hydrostatic or pneumatic) (See Notes 2 and 3) .....                                       | September 1, 1991 .....                                 | 1 year.                          |
| All cargo tanks which are insulated with no manhole or insulated and lined, except MC 338. | September 1, 1991 .....                                 | 1 year.                          |
| All cargo tanks designed to be loaded by vacuum with full opening rear heads.              | September 1, 1992 .....                                 | 2 years.                         |
| MC 330 and MC 331 cargo tanks in chlorine service .....                                    | September 1, 1992 .....                                 | 2 years.                         |
| All other cargo tanks .....                                                                | September 1, 1995 .....                                 | 5 years.                         |
| Thickness Test:                                                                            |                                                         |                                  |
| All unlined cargo tanks transporting material corrosive to the tank, except MC 338.        | September 1, 1992 .....                                 | 2 years.                         |

NOTE 1: If a cargo tank is subject to an applicable inspection or test requirement under the regulations in effect on December 30, 1990, and the due date (as specified by a requirement in effect on December 30, 1990) for completing the required inspection or test occurs before the compliance date listed in table I, the earlier date applies.

NOTE 2: Pressure testing is not required for MC 330 and MC 331 cargo tanks in dedicated sodium metal service.

NOTE 3: Pressure testing is not required for uninsulated lined cargo tanks, with a design pressure or MAWP 15 psig or less, which receive an external visual inspection and lining inspection at least once each year.

NOTE 4: Insulated cargo tanks equipped with manholes or inspection openings may perform either an internal visual inspection in conjunction with the external visual inspection or a hydrostatic or pneumatic pressure-test of the cargo tank.

(d) *External visual inspection and testing.* The following applies to the external visual inspection and testing of cargo tanks:

(1) Where insulation precludes a complete external visual inspection as required by paragraphs (d)(2) through (d)(6) of this section, the cargo tank also must be given an internal visual inspection in accordance with paragraph (e) of this section. If external visual inspection is precluded because

any part of the cargo tank wall is externally lined, coated, or designed to prevent an external visual inspection, those areas of the cargo tank must be internally inspected. If internal visual inspection is precluded because the cargo tank is lined, coated, or designed so as to prevent access for internal inspection, the tank must be hydrostatically or pneumatically tested in accordance with paragraph (g)(1)(iv) of this section. Those items

able to be externally inspected must be externally inspected and noted in the inspection report.

(2) The external visual inspection and testing must include as a minimum the following:

(i) The tank shell and heads must be inspected for corroded or abraded areas, dents, distortions, defects in welds and any other conditions, including leakage, that might render the tank unsafe for transportation service;

(ii) The piping, valves, and gaskets must be carefully inspected for corroded areas, defects in welds, and other conditions, including leakage, that might render the tank unsafe for transportation service;

(iii) All devices for tightening manhole covers must be operative and there must be no evidence of leakage at manhole covers or gaskets;

(iv) All emergency devices and valves including self-closing stop valves, excess flow valves and remote closure devices must be free from corrosion, distortion, erosion and any external damage that will prevent safe operation. Remote closure devices and self-closing stop valves must be functioned to demonstrate proper operation;

(v) Missing bolts, nuts and fusible links or elements must be replaced, and loose bolts and nuts must be tightened;

(vi) All markings on the cargo tank required by parts 172, 178 and 180 of this subchapter must be legible;

(vii) [Reserved]

(viii) All major appurtenances and structural attachments on the cargo tank including, but not limited to, suspension system attachments, connecting structures, and those elements of the upper coupler (fifth wheel) assembly that can be inspected without dismantling the upper coupler (fifth wheel) assembly must be inspected for any corrosion or damage which might prevent safe operation;

(ix) For cargo tanks transporting lading corrosive to the tank, areas covered by the upper coupler (fifth wheel) assembly must be inspected at least once in each two year period for corroded and abraded areas, dents, distortions, defects in welds, and any other condition that might render the tank unsafe for transportation service. The

upper coupler (fifth wheel) assembly must be removed from the cargo tank for this inspection.

(3) All reclosing pressure relief valves must be externally inspected for any corrosion or damage which might prevent safe operation. All reclosing pressure relief valves on cargo tanks carrying lading corrosive to the valve must be removed from the cargo tank for inspection and testing. Each reclosing pressure relief valve required to be removed and tested must open at the required set pressure and reseal to a leak-tight condition at 90 percent of the set-to-discharge pressure or the pressure prescribed for the applicable cargo tank specification.

(4) Ring stiffeners or other appurtenances, installed on cargo tanks constructed of mild steel or high-strength, low-alloy steel, that create air cavities adjacent to the tank shell that do not allow for external visual inspection must be thickness tested in accordance with paragraphs (i)(2) and (i)(3) of this section, at least once every 2 years. At least four symmetrically distributed readings must be taken to establish an average thickness for the ring stiffener or appurtenance. If any thickness reading is less than the average thickness by more than 10%, thickness testing in accordance with paragraphs (i)(2) and (i)(3) of this section must be conducted from the inside of the cargo tank on the area of the tank wall covered by the appurtenance or ring stiffener.

(5) Corroded or abraded areas of the cargo tank wall must be thickness tested in accordance with the procedures set forth in paragraphs (i)(2), (i)(3), (i)(5) and (i)(6) of this section.

(6) The gaskets on any full opening rear head must be:

(i) Visually inspected for cracks or splits caused by weather or wear; and

(ii) Replaced if cuts or cracks which are likely to cause leakage, or are of a depth one-half inch or more, are found.

(7) The inspector must record the results of the external visual examination as specified in § 180.417(b).

(e) *Internal visual inspection.* (1) When the cargo tank is not equipped with a manhole or inspection opening, or the cargo tank design precludes an internal inspection, the tank shall be

hydrostatically or pneumatically tested in accordance with 180.407(c) and (g).

(2) The internal visual inspection must include as a minimum the following:

(i) The tank shell and heads must be inspected for corroded and abraded areas, dents, distortions, defects in welds, and any other condition that might render the tank unsafe for transportation service.

(ii) Tank liners must be inspected as specified in § 180.407(f).

(3) Corroded or abraded areas of the cargo tank wall must be thickness tested in accordance with paragraphs (i)(2), (i)(3), (i)(5) and (i)(6) of this section.

(4) The inspector must record the results of the internal visual inspection as specified in § 180.417(b).

(f) *Lining inspection.* The integrity of the lining on all lined cargo tanks, when lining is required by this subchapter, must be verified at least once each year as follows:

(1) Rubber (elastomeric) lining must be tested for holes as follows:

(i) Equipment must consist of:

(A) A high frequency spark tester capable of producing sufficient voltage to ensure proper calibration;

(B) A probe with an "L" shaped 2.4 mm (0.09 inch) diameter wire with up to a 30.5 cm (12-inch) bottom leg (end bent to a 12.7 mm (0.5 inch) radius), or equally sensitive probe; and

(C) A steel calibration coupon 30.5 cm × 30.5 cm (12 inches × 12 inches) covered with the same material and thickness as that to be tested. The material on the coupon shall have a test hole to the metal substrate made by puncturing the material with a 22 gauge hypodermic needle or comparable piercing tool.

(ii) The probe must be passed over the surface of the calibration coupon in a constant uninterrupted manner until the hole is found. The hole is detected by the white or light blue spark formed. (A sound lining causes a dark blue or purple spark.) The voltage must be adjusted to the lowest setting that will produce a minimum 12.7 mm (0.5 inch) spark measured from the top of the lining to the probe. To assure that the setting on the probe has not changed, the spark tester must be cali-

brated periodically using the test calibration coupon, and the same power source, probe, and cable length.

(iii) After calibration, the probe must be passed over the lining in an uninterrupted stroke.

(iv) Holes that are found must be repaired using equipment and procedures prescribed by the lining manufacturer or lining installer.

(2) Linings made of other than rubber (elastomeric material) must be tested using equipment and procedures prescribed by the lining manufacturer or lining installer.

(3) Degraded or defective areas of the cargo tank liner must be removed and the cargo tank wall below the defect must be inspected. Corroded areas of the tank wall must be thickness tested in accordance with paragraphs (i)(2), (i)(3), (i)(5) and (i)(6) of this section.

(4) The inspector must record the results of the lining inspection as specified in § 180.417(b).

(g) *Pressure test.* All components of the cargo tank wall, as defined in § 178.320(a) of this subchapter, must be pressure tested as prescribed by this paragraph.

(1) *Test Procedure*—(i) As part of the pressure test, the inspector must perform an external and internal visual inspection, except that on an MC 338 cargo tank, or a cargo tank not equipped with a manhole or inspection opening, an internal inspection is not required.

(ii) All self-closing pressure relief valves, including emergency relief vents and normal vents, must be removed from the cargo tank for inspection and testing.

(A) Each self-closing pressure relief valve that is an emergency relief vent must open at the required set pressure and seat to a leak-tight condition at 90 percent of the set-to-discharge pressure or the pressure prescribed for the applicable cargo tank specification.

(B) Normal vents (1 psig vents) must be tested according to the testing criteria established by the valve manufacturer.

(C) Self-closing pressure relief devices not tested or failing the tests in this paragraph (g)(1)(ii) must be repaired or replaced.

(iii) Except for cargo tanks carrying lading corrosive to the tank, areas covered by the upper coupler (fifth wheel) assembly must be inspected for corroded and abraded areas, dents, distortions, defects in welds, and any other condition that might render the tank unsafe for transportation service. The upper coupler (fifth wheel) assembly must be removed from the cargo tank for this inspection.

(iv) Each cargo tank must be tested hydrostatically or pneumatically to the internal pressure specified in the following table. At no time during the pressure test may a cargo tank be subject to pressures that exceed those identified in the following table:

| Specification                    | Test pressure                                                                 |
|----------------------------------|-------------------------------------------------------------------------------|
| MC 300, 301, 302, 303, 305, 306. | 20.7 kPa (3 psig) or design pressure, whichever is greater.                   |
| MC 304, 307 .....                | 275.8 kPa (40 psig) or 1.5 times the design pressure, whichever is greater.   |
| MC 310, 311, 312 .....           | 20.7 kPa (3 psig) or 1.5 times the design pressure, whichever is greater.     |
| MC 330, 331 .....                | 1.5 times either the MAWP or the re-rated pressure, whichever is applicable.  |
| MC 338 .....                     | 1.25 times either the MAWP or the re-rated pressure, whichever is applicable. |
| DOT 406 .....                    | 34.5 kPa (5 psig) or 1.5 times the MAWP, whichever is greater.                |
| DOT 407 .....                    | 275.8 kPa (40 psig) or 1.5 times the MAWP, whichever is greater.              |
| DOT 412 .....                    | 1.5 times the MAWP.                                                           |

(v) [Reserved]

(vi) Each cargo tank of a multi-tank cargo tank motor vehicle must be tested with the adjacent cargo tanks empty and at atmospheric pressure.

(vii) All closures except pressure relief devices must be in place during the test. All prescribed loading and unloading venting devices rated at less than test pressure may be removed during the test. If retained, the devices must be rendered inoperative by clamps, plugs, or other equally effective restraining devices. Restraining devices may not prevent detection of leaks or damage the venting devices and must be removed immediately after the test is completed.

(viii) *Hydrostatic test method.* Each cargo tank, including its domes, must be filled with water or other liquid hav-

ing similar viscosity, at a temperature not exceeding 100 °F. The cargo tank must then be pressurized to not less than the pressure specified in paragraph (g)(1)(iv) of this section. The cargo tank, including its closures, must hold the prescribed test pressure for at least 10 minutes during which time it shall be inspected for leakage, bulging or any other defect.

(ix) *Pneumatic test method.* Pneumatic testing may involve higher risk than hydrostatic testing. Therefore, suitable safeguards must be provided to protect personnel and facilities should failure occur during the test. The cargo tank must be pressurized with air or an inert gas. The pneumatic test pressure in the cargo tank must be reached by gradually increasing the pressure to one-half of the test pressure. Thereafter, the pressure must be increased in steps of approximately one-tenth of the test pressure until the required test pressure has been reached. The test pressure must be held for at least 5 minutes. The pressure must then be reduced to the MAWP, which must be maintained during the time the entire cargo tank surface is inspected. During the inspection, a suitable method must be used for detecting the existence of leaks. This method must consist either of coating the entire surface of all joints under pressure with a solution of soap and water, or using other equally sensitive methods.

(2) When testing an insulated cargo tank, the insulation and jacketing need not be removed unless it is otherwise impossible to reach test pressure and maintain a condition of pressure equilibrium after test pressure is reached, or the vacuum integrity cannot be maintained in the insulation space. If an MC 338 cargo tank used for the transportation of a flammable gas or oxygen, refrigerated liquid is opened for any reason, the cleanliness must be verified prior to closure using the procedures contained in §178.338–15 of this subchapter.

(3) Each MC 330 and MC 331 cargo tank constructed of quenched and tempered steel in accordance with Part UHT in Section VIII of the ASME Code (IBR, see §171.7 of this subchapter), or constructed of other than quenched and tempered steel but without

postweld heat treatment, used for the transportation of anhydrous ammonia or any other hazardous materials that may cause corrosion stress cracking, must be internally inspected by the wet fluorescent magnetic particle method immediately prior to and in conjunction with the performance of the pressure test prescribed in this section. Each MC 330 and MC 331 cargo tank constructed of quenched and tempered steel in accordance with Part UHT in Section VIII of the ASME Code and used for the transportation of liquefied petroleum gas must be internally inspected by the wet fluorescent magnetic particle method immediately prior to and in conjunction with the performance of the pressure test prescribed in this section. The wet fluorescent magnetic particle inspection must be in accordance with Section V of the ASME Code and CGA Technical Bulletin TB-2 (IBR, see §171.7 of this subchapter). This paragraph does not apply to cargo tanks that do not have manholes. (See §180.417(c) for reporting requirements.)

(4) All pressure bearing portions of a cargo tank heating system employing a medium such as, but not limited to, steam or hot water for heating the lading must be hydrostatically pressure tested at least once every 5 years. The test pressure must be at least the maximum system design operating pressure and must be maintained for five minutes. A heating system employing flues for heating the lading must be tested to ensure against lading leakage into the flues or into the atmosphere.

(5) *Exceptions.* (i) Pressure testing is not required for MC 330 and MC 331 cargo tanks in dedicated sodium metal service.

(ii) Pressure testing is not required for uninsulated lined cargo tanks, with a design pressure or MAWP of 15 psig or less, which receive an external visual inspection and a lining inspection at least once each year.

(6) *Acceptance criteria.* A cargo tank that leaks, fails to retain test pressure or pneumatic inspection pressure, shows distortion, excessive permanent expansion, or other evidence of weakness that might render the cargo tank unsafe for transportation service, may not be returned to service, except as

follows: A cargo tank with a heating system which does not hold pressure may remain in service as an unheated cargo tank if:

(i) The heating system remains in place and is structurally sound and no lading may leak into the heating system, and

(ii) The specification plate heating system information is changed to indicate that the cargo tank has no working heating system.

(7) The inspector must record the results of the pressure test as specified in §180.417(b).

(h) *Leakage test.* The following requirements apply to cargo tanks requiring a leakage test:

(1) Each cargo tank must be tested for leaks in accordance with paragraph (c) of this section. The leakage test must include testing product piping with all valves and accessories in place and operative, except that any venting devices set to discharge at less than the leakage test pressure must be removed or rendered inoperative during the test. All internal or external self-closing stop valves must be tested for leak tightness. Each cargo tank of a multi-cargo tank motor vehicle must be tested with adjacent cargo tanks empty and at atmospheric pressure. Test pressure must be maintained for at least 5 minutes. Cargo tanks in liquefied compressed gas service must be externally inspected for leaks during the leakage test. Suitable safeguards must be provided to protect personnel should a failure occur. Cargo tanks may be leakage tested with hazardous materials contained in the cargo tank during the test. Leakage test pressure must be no less than 80% of MAWP marked on the specification plate except as follows:

(i) A cargo tank with an MAWP of 690 kPa (100 psig) or more may be leakage tested at its maximum normal operating pressure provided it is in dedicated service or services; or

(ii) An MC 330 or MC 331 cargo tank in dedicated liquefied petroleum gas service may be leakage tested at not less than 414 kPa (60 psig).

(iii) An operator of a specification MC 330 or MC 331 cargo tank, and a nonspecification cargo tank authorized under §173.315(k) of this subchapter,

equipped with a meter may check leak tightness of the internal self-closing stop valve by conducting a meter creep test. (See appendix B to this part.)

(iv) An MC 330 or MC 331 cargo tank in dedicated service for anhydrous ammonia may be leakage tested at not less than 414 kPa (60 psig).

(v) A non-specification cargo tank required by §173.8(d) of this subchapter to be leakage tested, must be leakage tested at not less than 16.6 kPa (2.4 psig), or as specified in paragraph (h)(2) of this section.

(2) Cargo tanks used to transport petroleum distillate fuels that are equipped with vapor collection equipment may be leak tested in accordance with the Environmental Protection Agency's "Method 27—Determination of Vapor Tightness of Gasoline Delivery Tank Using Pressure-Vacuum Test," as set forth in Appendix A to 40 CFR part 60. Test methods and procedures and maximum allowable pressure and vacuum changes are in 40 CFR 63.425(e)(1). The hydrostatic test alternative, using liquid in Environmental Protection Agency's "Method 27—Determination of Vapor Tightness of Gasoline Delivery Tank Using Pressure-Vacuum Test," may not be used to satisfy the leak testing requirements of this paragraph. The test must be conducted using air.

(3) A cargo tank that fails to retain leakage test pressure may not be returned to service as a specification cargo tank, except under conditions specified in §180.411(d).

(4) After July 1, 2000, Registered Inspectors of specification MC 330 and MC 331 cargo tanks, and nonspecification cargo tanks authorized under §173.315(k) of this subchapter must visually inspect the delivery hose assembly and piping system while the assembly is under leakage test pressure utilizing the rejection criteria listed in §180.416(g). Delivery hose assemblies not permanently attached to the cargo tank motor vehicle may be inspected separately from the cargo tank motor vehicle. In addition to a written record of the inspection prepared in accordance with §180.417(b), the Registered Inspector conducting the test must note the hose identification number, the date of the test, and the condition

of the hose assembly and piping system tested.

(5) The inspector must record the results of the leakage test as specified in §180.417(b).

(i) *Thickness testing.* (1) The shell and head thickness of all unlined cargo tanks used for the transportation of materials corrosive to the tank must be measured at least once every 2 years, except that cargo tanks measuring less than the sum of the minimum prescribed thickness, plus one-fifth of the original corrosion allowance, must be tested annually.

(2) Measurements must be made using a device capable of accurately measuring thickness to within  $\pm 0.002$  of an inch.

(3) Any person performing thickness testing must be trained in the proper use of the thickness testing device used in accordance with the manufacturer's instruction.

(4) Thickness testing must be performed in the following areas of the cargo tank wall, as a minimum:

(i) Areas of the tank shell and heads and shell and head area around any piping that retains lading;

(ii) Areas of high shell stress such as the bottom center of the tank;

(iii) Areas near openings;

(iv) Areas around weld joints;

(v) Areas around shell reinforcements;

(vi) Areas around appurtenance attachments;

(vii) Areas near upper coupler (fifth wheel) assembly attachments;

(viii) Areas near suspension system attachments and connecting structures;

(ix) Known thin areas in the tank shell and nominal liquid level lines; and

(x) Connecting structures joining multiple cargo tanks of carbon steel in a self-supporting cargo tank motor vehicle.

(5) Minimum thicknesses for MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, and MC 312 cargo tanks are determined based on the definition of minimum thickness found in §178.320(a) of this subchapter. The following Tables I and II identify the "In-Service Minimum

Thickness” values to be used to determine the minimum thickness for the referenced cargo tanks. The column headed “Minimum Manufactured Thickness” indicates the minimum values required for new construction of DOT 400 series cargo tanks, found in Tables I and II of §§ 178.346–2, 178.347–2, and 178.348–2 of this subchapter. In-Service Minimum Thicknesses for MC 300, MC 301, MC 302, MC 303, MC 304, MC 305, MC 306, MC 307, MC 310, MC 311, and MC 312 cargo tanks are based on 90 percent of the manufactured thickness specified in the DOT specification, rounded to three places.

TABLE I—IN-SERVICE MINIMUM THICKNESS FOR MC 300, MC 303, MC 304, MC 306, MC 307, MC 310, MC 311, AND MC 312 SPECIFICATION CARGO TANKS CONSTRUCTED OF STEEL AND STEEL ALLOYS

| Minimum manufactured thickness<br>(US gauge or inches) | Nominal<br>decimal<br>equiva-<br>lent for<br>(inches) | In-service<br>minimum<br>thickness<br>reference<br>(inches) |
|--------------------------------------------------------|-------------------------------------------------------|-------------------------------------------------------------|
| 19 .....                                               | 0.0418                                                | 0.038                                                       |
| 18 .....                                               | 0.0478                                                | 0.043                                                       |
| 17 .....                                               | 0.0538                                                | 0.048                                                       |
| 16 .....                                               | 0.0598                                                | 0.054                                                       |
| 15 .....                                               | 0.0673                                                | 0.061                                                       |
| 14 .....                                               | 0.0747                                                | 0.067                                                       |
| 13 .....                                               | 0.0897                                                | 0.081                                                       |
| 12 .....                                               | 0.1046                                                | 0.094                                                       |
| 11 .....                                               | 0.1196                                                | 0.108                                                       |
| 10 .....                                               | 0.1345                                                | 0.121                                                       |
| 9 .....                                                | 0.1495                                                | 0.135                                                       |
| 8 .....                                                | 0.1644                                                | 0.148                                                       |
| 7 .....                                                | 0.1793                                                | 0.161                                                       |
| 3/16 .....                                             | 0.1875                                                | 0.169                                                       |
| 1/4 .....                                              | 0.2500                                                | 0.225                                                       |
| 5/16 .....                                             | 0.3125                                                | 0.281                                                       |
| 3/8 .....                                              | 0.3750                                                | 0.338                                                       |

TABLE II—IN-SERVICE MINIMUM THICKNESS FOR MC 301, MC 302, MC 304, MC 305, MC 306, MC 307, MC 311, AND MC 312 SPECIFICATION CARGO TANKS CONSTRUCTED OF ALUMINUM AND ALUMINUM ALLOYS

| Minimum manufactured thickness | In-service<br>minimum<br>thickness<br>(inches) |
|--------------------------------|------------------------------------------------|
| 0.078 .....                    | 0.070                                          |
| 0.087 .....                    | 0.078                                          |
| 0.096 .....                    | 0.086                                          |
| 0.109 .....                    | 0.098                                          |
| 0.130 .....                    | 0.117                                          |
| 0.141 .....                    | 0.127                                          |
| 0.151 .....                    | 0.136                                          |
| 0.172 .....                    | 0.155                                          |
| 0.173 .....                    | 0.156                                          |

TABLE II—IN-SERVICE MINIMUM THICKNESS FOR MC 301, MC 302, MC 304, MC 305, MC 306, MC 307, MC 311, AND MC 312 SPECIFICATION CARGO TANKS CONSTRUCTED OF ALUMINUM AND ALUMINUM ALLOYS—Continued

| Minimum manufactured thickness | In-service<br>minimum<br>thickness<br>(inches) |
|--------------------------------|------------------------------------------------|
| 0.194 .....                    | 0.175                                          |
| 0.216 .....                    | 0.194                                          |
| 0.237 .....                    | 0.213                                          |
| 0.270 .....                    | 0.243                                          |
| 0.360 .....                    | 0.324                                          |
| 0.450 .....                    | 0.405                                          |
| 0.540 .....                    | 0.486                                          |

(6) An owner of a cargo tank that no longer conforms to the minimum thickness prescribed for the design as manufactured may use the cargo tank to transport authorized materials at reduced maximum weight of lading or reduced maximum working pressure, or combinations thereof, provided the following conditions are met:

(i) A Design Certifying Engineer must certify that the cargo tank design and thickness are appropriate for the reduced loading conditions by issuance of a revised manufacturer's certificate, and

(ii) The cargo tank motor vehicle's nameplate must reflect the revised service limits.

(7) An owner of a cargo tank that no longer conforms with the minimum thickness prescribed for the specification may not return the cargo tank to hazardous materials service. The tank's specification plate must be removed, obliterated or covered in a secure manner.

(8) The inspector must record the results of the thickness test as specified in § 180.417(b).

(9) For MC 331 cargo tanks constructed before October 1, 2003, minimum thickness shall be determined by the thickness indicated on the U1A form minus any corrosion allowance. For MC 331 cargo tanks constructed after October 1, 2003, the minimum thickness will be the value indicated on the specification plate. If no corrosion allowance is indicated on the U1A form then the thickness of the tank shall be the thickness of the material of construction indicated on the U1A form with no corrosion allowance.



## § 180.409

## 49 CFR Ch. I (10–1–08 Edition)

(10) For 400-series cargo tanks, minimum thickness is calculated according to tables in each applicable section of this subchapter for that specification: §178.346–2 for DOT 406 cargo tanks, §178.347–2 for DOT 407 cargo tanks, and §178.348–2 for DOT 412 cargo tanks.

[Amdt. 180–2, 54 FR 25032, June 12, 1989]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §180.407, see the List of CFR Sections Affected which appears in the Finding Aids section of the printed volume and on GPO Access.

### §180.409 Minimum qualifications for inspectors and testers.

(a) Except as otherwise provided in this section, any person performing or witnessing the inspections and tests specified in §180.407(c) must—

(1) Be registered with the Federal Motor Carrier Safety Administration in accordance with part 107, subpart F of this chapter,

(2) Be familiar with DOT-specification cargo tanks and trained and experienced in use of the inspection and testing equipment needed, and

(3) Have the training and experience required to meet the definition of “Registered Inspector” in §171.8 of this chapter.

(b) A person who only performs annual external visual inspections and leakage tests on a cargo tank motor vehicle, owned or operated by that person, with a capacity of less than 13,250 L (3,500 gallons) used exclusively for flammable liquid petroleum fuels, is not required to meet the educational and years of experience requirements set forth in the definition of “Registered Inspector” in §171.8 of this subchapter. Although not required to meet the educational and years of experience requirements, a person who performs visual inspections or leakage tests or signs the inspection reports must have the knowledge and ability to perform such inspections and tests and must perform them as required by this subchapter, and must register with the Department as required by subpart F of part 107 of this chapter.

(c) A person who performs only annual external visual inspections and leakage tests on a permanently mounted non-bulk tank, owned or operated

by that person, for petroleum products as authorized by §173.8(c) of this subchapter, is not required to be registered in accordance with subpart F of part 107 of this chapter. In addition the person who signs the inspection report required by §180.417(b) of this subpart for such non-bulk tanks is not required to be registered. Although not required to register, a person who performs visual inspections or leakage tests or signs the inspection reports must have the knowledge and ability to perform such inspections and tests and must perform them as required by this subchapter.

(d) A motor carrier or cargo tank owner who meets the requirements of paragraph (a) of this section may use an employee who is not a Registered Inspector to perform a portion of the pressure retest required by §180.407(g). External and internal visual inspections must be accomplished by a Registered Inspector, but the hydrostatic or pneumatic pressure test, as set forth in §180.407(g)(1)(viii) and (ix), respectively, may be done by an employee who is not a Registered Inspector provided that—

(1) The employee is familiar with the cargo tank and is trained and experienced in the use of the inspection and testing equipment used;

(2) The employer submits certification that such employee meets the qualification requirements to the Associate Administrator, Attn: (PHH–32), Pipeline and Hazardous Materials Safety Administration, Department of Transportation, East Building, 1200 New Jersey Avenue, SE., Washington, DC 20590; and

(3) The employer retains a copy of the tester’s qualifications with the documents required by §180.417(b).

[Amdt. 180–2, 55 FR 37069, Sept. 7, 1990, as amended by Amdt. 180–3, 56 FR 66287, Dec. 20, 1991; 57 FR 45466, Oct. 1, 1992; Amdt. 180–11, 62 FR 1217, Jan. 8, 1997; 66 FR 45391, Aug. 28, 2001; 68 FR 19288, Apr. 18, 2003; 70 FR 56100, Sept. 23, 2005; 72 FR 55697, Oct. 1, 2007]

### §180.411 Acceptable results of tests and inspections.

(a) *Corroded or abraded areas.* The minimum thickness may not be less than that prescribed in the applicable specification.

(b) *Dents, cuts, digs and gouges.* For evaluation procedures, see CGA C-6 (IBR, see § 171.7 of this subchapter).

(1) For dents at welds or that include a weld, the maximum allowable depth is  $\frac{1}{2}$  inch. For dents away from welds, the maximum allowable depth is  $\frac{1}{10}$  of the greatest dimension of the dent, but in no case may the depth exceed one inch.

(2) The minimum thickness remaining beneath a cut, dig, or gouge may not be less than that prescribed in the applicable specification.

(c) *Weld or structural defects.* Any cargo tank with a weld defect such as a crack, pinhole, or incomplete fusion, or a structural defect must be taken out of hazardous materials service until repaired.

(d) *Leakage.* All sources of leakage must be properly repaired prior to returning a tank to hazardous materials service.

(e) *Relief valves.* Any pressure relief valve that fails to open and reclose at the prescribed pressure must be repaired or replaced.

(f) *Liner integrity.* Any defect shown by the test must be properly repaired.

(g) *Pressure test.* Any tank that fails to meet the acceptance criteria found in the individual specification that applies must be properly repaired.

[Amdt. 180-2, 54 FR 25032, June 12, 1989, as amended at 68 FR 75764, Dec. 31, 2003]

**§ 180.413 Repair, modification, stretching, rebarrelling, or mounting of specification cargo tanks.**

(a) *General.* Any repair, modification, stretching, rebarrelling, or mounting of a cargo tank must be performed in conformance with the requirements of this section.

(1) Except as otherwise provided in this section, each repair, modification, stretching, or rebarrelling of a specification cargo tank must be performed by a repair facility holding a valid National Board Certificate of Authorization for use of the National Board “R” stamp and must be made in accordance with the edition of the National Board Inspection Code in effect at the time the work is performed.

(i) Repairs, modifications, stretchings, and rebarrellings performed on non-ASME stamped speci-

fication cargo tanks may be performed by:

(A) A cargo tank manufacturer holding a valid ASME Certificate of Authorization for the use of the ASME “U” stamp using the quality control procedures used to obtain the Certificate of Authorization; or

(B) A repair facility holding a valid National Board Certificate of Authorization for use of the National Board “R” stamp using the quality control procedures used to obtain the Certificate of Authorization.

(ii) A repair, modification, stretching, or rebarrelling of a non-ASME stamped cargo tank may be done without certification by an Authorized Inspector, completion of the R-1 form, or being stamped with the “R” stamp.

(2) Prior to each repair, modification, stretching, rebarrelling, or mounting, the cargo tank motor vehicle must be emptied of any hazardous material lading. In addition, cargo tank motor vehicles used to transport flammable or toxic lading must be sufficiently cleaned of residue and purged of vapors so any potential hazard is removed, including void spaces between double bulkheads, piping and vapor recovery systems.

(3) Each person performing a repair, modification, stretching, rebarrelling or mounting of a DOT specification cargo tank must be registered in accordance with subpart F of part 107 of this chapter.

(b) *Repair.* The suitability of each repair affecting the structural integrity or lading retention capability of the cargo tank must be determined by the testing required either in the applicable manufacturing specification or in § 180.407(g)(1)(iv). Each repair of a cargo tank involving welding on the shell or head must be certified by a Registered Inspector. The following provisions apply to specific cargo tank repairs:

(1) DOT 406, DOT 407, and DOT 412 cargo tanks must be repaired in accordance with the specification requirements in effect at the time of repair;

(2) MC 300, MC 301, MC 302, MC 303, MC 305, and MC 306 cargo tanks must be repaired in accordance with either the most recent revision of the original

## § 180.413

## 49 CFR Ch. I (10–1–08 Edition)

specification or with the DOT 406 specification in effect at the time of repair;

(3) MC 304 and MC 307 cargo tanks must be repaired in accordance with either the most recent revision of the original specification or with the DOT 407 specification in effect at the time of repair;

(4) MC 310, MC 311, and MC 312 cargo tanks must be repaired in accordance with either the most recent revision of the original specification or with the DOT 412 specification in effect at the time of repair;

(5) MC 338 cargo tanks must be repaired in accordance with the specification requirements in effect at the time of repair; and

(6) MC 330 and MC 331 cargo tanks must be repaired in accordance with the repair procedures described in CGA Technical Bulletin TB-2 (IBR, see §171.7 of this subchapter) and the National Board Inspection Code (IBR, see §171.7 of this subchapter). Each cargo tank having cracks or other defects requiring welded repairs must meet all inspection, test, and heat treatment requirements in §178.337–16 of this subchapter in effect at the time of the repair, except that postweld heat treatment after minor weld repairs is not required. When a repair is made of defects revealed by the wet fluorescent magnetic particle inspection, including those repaired by grinding, the affected area of the cargo tank must again be examined by the wet fluorescent magnetic particle method after hydrostatic testing to assure that all defects have been removed.

(c) *Maintenance or replacement of piping, valves, hoses, or fittings.* After each repair, maintenance or replacement of a pipe, valve, hose, or fitting on a cargo tank, that component must be installed in accordance with the provisions of the applicable specification before the cargo tank is returned to service.

(1) After maintenance or replacement that does not involve welding on the cargo tank wall, the repaired or replaced piping, valve, hose, or fitting must be tested for leaks. This requirement is met when the piping, valve, hose, or fitting is tested after installation in accordance with §180.407(h)(1).

A hose may be tested before or after installation on the cargo tank.

(2) After repair or replacement of piping, valves, or fittings that involves welding on the cargo tank wall, the cargo tank must be pressure tested in accordance with the applicable manufacturing specification or §180.407(g)(1)(iv). In addition, the affected piping, valve, or fitting must be tested in accordance with paragraph (c)(1) of this section.

(3) Hoses on cargo tanks in dedicated liquefied compressed gas, except carbon dioxide, service are excepted from these testing requirements, but must be tested in accordance with §180.416(f).

(d) *Modification, stretching, or rebarrelling.* Modification, stretching or rebarrelling of a cargo tank motor vehicle must conform to the following provisions:

(1) The design of the modified, stretched, or rebarrelled cargo tank motor vehicle must be certified in writing by a Design Certifying Engineer as meeting the structural integrity and accident damage protection requirements of the applicable specification.

(2) Except as provided in paragraph (d)(2)(v) of this section, all new material and equipment affected by modification, stretching, or rebarrelling must meet the requirements of the specification in effect at the time such work is performed, and all applicable structural integrity requirements (§178.337–3, §178.338–3, or §178.345–3 of this subchapter). The work must conform to the requirements of the applicable specification as follows:

(i) For specification MC 300, MC 301, MC 302, MC 303, MC 305 and MC 306 cargo tanks, the provisions of either specification MC 306 or DOT 406 until August 31, 1995 and, thereafter to specification DOT 406 only;

(ii) For specification MC 304 and MC 307 cargo tanks, the provisions of either specification MC 307 or DOT 407 until August 31, 1995 and, thereafter to specification DOT 407 only;

(iii) For specification MC 310, MC 311, and MC 312 cargo tanks, the provisions of either specification MC 312 or DOT 412 until August 31, 1995 and, thereafter to specification DOT 412 only;

(iv) For specification MC 330 cargo tanks, the provisions of specification MC 331; and

(v) For specification MC 338 cargo tanks, the provisions of specification MC 338. However, structural modifications to MC 338 cargo tanks authorized under § 180.405(d) may conform to applicable provisions of the ASME Code instead of specification MC 338, provided the structural integrity of the modified cargo tank is at least equivalent to that of the original cargo tank.

(3) The person performing the modification, stretching, or rebarrelling must:

(i) Have knowledge of the original design concept, particularly with respect to structural design analysis, material and welding procedures.

(ii) Assure compliance of the rebuilt cargo tank's structural integrity, venting, and accident damage protection with the applicable specification requirements.

(iii) Assure compliance with all applicable Federal Motor Carrier Safety Regulations for all newly installed safety equipment.

(iv) Assure the suitability of each modification, stretching and rebarrelling that affects the lading retention capability of the cargo tank by performing the tests required in the applicable specification or § 180.407(g)(1)(iv).

(v) Any modification that changes information displayed on the specification plate requires the installation of a supplemental specification plate, nameplate, or both containing the information that reflects the cargo tank as modified, stretched or rebarrelled. The plate must include the name of the person or facility doing the work, DOT registration number, date work is completed, retest information, and any other information that differs from the original plate. The supplemental plates must be installed immediately adjacent to the existing plate or plates.

(vi) On a variable specification cargo tank, install a supplemental or new variable specification plate, and replace the specification listed on the original specification plate with the words "see variable specification plate."

(4) A Registered Inspector must certify that the modified, stretched, or

rebarrelled cargo tank conforms to the requirements of this section and the applicable specification by issuing a supplemental certificate of compliance. The registration number of the Registered Inspector must be entered on the certificate.

(e) *Mounting of cargo tanks.* Mounting a cargo tank on a cargo tank motor vehicle must be:

(1) Performed as required by paragraph (d)(2) of this section and certified by a Design Certifying Engineer if the mounting of a cargo tank on a motor vehicle chassis involves welding on the cargo tank head or shell or any change or modification of the methods of attachment; or

(2) In accordance with the original specification for attachment to the chassis or the specification for attachment to the chassis in effect at the time of the mounting, and performed under the supervision of a Registered Inspector if the mounting of a cargo tank on a motor vehicle chassis does not involve welding on the cargo tank head or shell or a change or modification of the methods of attachment.

(f) *Records.* Each owner of a cargo tank motor vehicle must retain at the owner's principal place of business all records of repair, modification, stretching, or rebarrelling, including notation of any tests conducted to verify the suitability of the repair, modification, stretching, or rebarrelling made to each cargo tank during the time the cargo tank motor vehicle is in service and for one year thereafter. Copies of these records must be retained by a motor carrier, if not the owner of the cargo tank motor vehicle, at its principal place of business during the period the cargo tank motor vehicle is in the carrier's service.

[68 FR 19288, Apr. 18, 2003; 68 FR 52372, Sept. 3, 2003, as amended at 68 FR 75764, Dec. 31, 2003]

#### § 180.415 Test and inspection markings.

(a) Each cargo tank successfully completing the test and inspection requirements contained in § 180.407 must be marked as specified in this section.

(b) Each cargo tank must be durably and legibly marked, in English, with the date (month and year) and the type

## § 180.416

of test or inspection performed, subject to the following provisions:

(1) The date must be readily identifiable with the applicable test or inspection.

(2) The markings must be in letters and numbers at least 32 mm (1.25 inches) high, near the specification plate or anywhere on the front head.

(3) The type of test or inspection may be abbreviated as follows:

(i) V for external visual inspection and test;

(ii) I for internal visual inspection;

(iii) P for pressure test;

(iv) L for lining inspection;

(v) T for thickness test; and

(vi) K for leakage test for a cargo tank tested under § 180.407, except § 180.407(h)(2); and

(vii) K-EPA27 for a cargo tank tested under § 180.407(h)(2) after October 1, 2004.

*Examples to paragraph (b).* The markings “10-99 P, V, L” represent that in October 1999 a cargo tank passed the prescribed pressure test, external visual inspection and test, and the lining inspection. The markings “2-00 K-EPA27” represent that in February 2000 a cargo tank passed the leakage test under § 180.407(h)(2). The markings “2-00 K, K-EPA27” represent that in February 2000 a cargo tank passed the leakage test under both § 180.407(h)(1) and under EPA Method 27 in § 180.407(h)(2).

(c) For a cargo tank motor vehicle composed of multiple cargo tanks constructed to the same specification, which are tested and inspected at the same time, one set of test and inspection markings may be used to satisfy the requirements of this section. For a cargo tank motor vehicle composed of multiple cargo tanks constructed to different specifications, which are tested and inspected at different intervals, the test and inspection markings must appear in the order of the cargo tank's corresponding location, from front to rear.

[Amdt. 180-2, 56 FR 27879, June 17, 1991, as amended by Amdt. 180-3, 56 FR 66287, Dec. 20, 1991; 57 FR 45466, Oct. 1, 1992; Amdt. 180-6, 59 FR 49135, Sept. 26, 1994; Amdt. 180-10, 61 FR 51343, Oct. 1, 1996; 68 FR 19290, Apr. 18, 2003; 68 FR 52372, Sept. 3, 2003]

## 49 CFR Ch. I (10-1-08 Edition)

### § 180.416 Discharge system inspection and maintenance program for cargo tanks transporting liquefied compressed gases.

(a) *Applicability.* This section is applicable to an operator using specification MC 330, MC 331, and nonspecification cargo tanks authorized under § 173.315(k) of this subchapter for transportation of liquefied compressed gases other than carbon dioxide. Paragraphs (b), (c), (d)(1), (d)(5), (e), (f), and (g)(1) of this section, applicable to delivery hose assemblies, apply only to hose assemblies installed or carried on the cargo tank.

(b) *Hose identification.* By July 1, 2000, the operator must assure that each delivery hose assembly is permanently marked with a unique identification number and maximum working pressure.

(c) *Post-delivery hose check.* After each unloading, the operator must visually check that portion of the delivery hose assembly deployed during the unloading.

(d) *Monthly inspections and tests.* (1) The operator must visually inspect each delivery hose assembly at least once each calendar month the delivery hose assembly is in service.

(2) The operator must visually inspect the piping system at least once each calendar month the cargo tank is in service. The inspection must include fusible elements and all components of the piping system, including bolts, connections, and seals.

(3) At least once each calendar month a cargo tank is in service, the operator must actuate all emergency discharge control devices designed to close the internal self-closing stop valve to assure that all linkages operate as designed. appendix A to this part outlines acceptable procedures that may be used for this test.

(4) The operator of a cargo tank must check the internal self-closing stop valve in the liquid discharge opening for leakage through the valve at least once each calendar month the cargo tank is in service. On cargo tanks equipped with a meter, the meter creep test as outlined in appendix B to this part or a test providing equivalent accuracy is acceptable. For cargo tanks

that are not equipped with a meter, appendix B to this part outlines one acceptable method that may be used to check internal self-closing stop valves for closure.

(5) After July 1, 2000, the operator must note each inspection in a record. That record must include the inspection date, the name of the person performing the inspection, the hose assembly identification number, the company name, the date the hose was assembled and tested, and an indication that the delivery hose assembly and piping system passed or failed the tests and inspections. A copy of each test and inspection record must be retained by the operator at its principal place of business or where the vehicle is housed or maintained until the next test of the same type is successfully completed.

(e) *Annual hose leakage test.* The owner of a delivery hose assembly that is not permanently attached to a cargo tank motor vehicle must ensure that the hose assembly is annually tested in accordance with § 180.407(h)(4).

(f) *New or repaired delivery hose assemblies.* Each operator of a cargo tank must ensure each new and repaired delivery hose assembly is tested at a minimum of 120 percent of the hose maximum working pressure.

(1) The operator must visually examine the delivery hose assembly while it is under pressure.

(2) Upon successful completion of the pressure test and inspection, the operator must assure that the delivery hose assembly is permanently marked with the month and year of the test.

(3) After July 1, 2000, the operator must complete a record documenting the test and inspection, including the date, the signature of the inspector, the hose owner, the hose identification number, the date of original delivery hose assembly and test, notes of any defects observed and repairs made, and an indication that the delivery hose assembly passed or failed the tests and inspections. A copy of each test and inspection record must be retained by the operator at its principal place of business or where the vehicle is housed or maintained until the next test of the same type is successfully completed.

(g) *Rejection criteria.* (1) No operator may use a delivery hose assembly determined to have any condition identified below for unloading liquefied compressed gases. An operator may remove and replace damaged sections or correct defects discovered. Repaired hose assemblies may be placed back in service if retested successfully in accordance with paragraph (f) of this section.

(i) Damage to the hose cover that exposes the reinforcement.

(ii) Wire braid reinforcement that has been kinked or flattened so as to permanently deform the wire braid.

(iii) Soft spots when not under pressure, bulging under pressure, or loose outer covering.

(iv) Damaged, slipping, or excessively worn hose couplings.

(v) Loose or missing bolts or fastenings on bolted hose coupling assemblies.

(2) No operator may use a cargo tank with a piping system found to have any condition identified in this paragraph (g)(2) for unloading liquefied compressed gases.

(i) Any external leak identifiable without the use of instruments.

(ii) Bolts that are loose, missing, or severely corroded.

(iii) Manual stop valves that will not actuate.

(iv) Rubber hose flexible connectors with any condition outlined in paragraph (g)(1) of this section.

(v) Stainless steel flexible connectors with damaged reinforcement braid.

(vi) Internal self-closing stop valves that fail to close or that permit leakage through the valve detectable without the use of instruments.

(vii) Pipes or joints that are severely corroded.

[64 FR 28051, May 24, 1999]

#### **§ 180.417 Reporting and record retention requirements.**

(a) *Vehicle certification.* (1) Each owner of a specification cargo tank must retain the manufacturer's certificate, the manufacturer's ASME U1A data report, where applicable, and related papers certifying that the specification cargo tank identified in the documents was manufactured and tested in accordance with the applicable specification. This would include any

certification of emergency discharge control systems required by §173.315(n) of this subchapter or §180.405(m). The owner must retain the documents throughout his ownership of the specification cargo tank and for one year thereafter. In the event of a change in ownership, the prior owner must retain non-fading photo copies of these documents for one year.

(2) Each motor carrier who uses a specification cargo tank motor vehicle must obtain a copy of the manufacturer's certificate and related papers or the alternative report authorized by paragraph (a)(3)(i) or (ii) of this section and retain the documents as specified in this paragraph (a)(2). A motor carrier who is not the owner of a cargo tank motor vehicle must also retain a copy of the vehicle certification report for as long as the cargo tank motor vehicle is used by that carrier and for one year thereafter. The information required by this section must be maintained at the company's principal place of business or at the location where the vehicle is housed or maintained. The provisions of this section do not apply to a motor carrier who leases a cargo tank for less than 30 days.

(3) *DOT Specification cargo tanks manufactured before September 1, 1995—(i) Non-ASME Code stamped cargo tanks*—If an owner does not have a manufacturer's certificate for a cargo tank and he wishes to certify it as a specification cargo tank, the owner must perform appropriate tests and inspections, under the direct supervision of a Registered Inspector, to determine if the cargo tank conforms with the applicable specification. Both the owner and the Registered Inspector must certify that the cargo tank fully conforms to the applicable specification. The owner must retain the certificate, as specified in this section.

(ii) *ASME Code Stamped cargo tanks*. If the owner does not have the manufacturer's certificate required by the specification and the manufacturer's data report required by the ASME, the owner may contact the National Board for a copy of the manufacturer's data report, if the cargo tank was registered with the National Board, or copy the information contained on the cargo tank's identification and ASME Code

plates. Additionally, both the owner and the Registered Inspector must certify that the cargo tank fully conforms to the specification. The owner must retain such documents, as specified in this section.

(b) *Test or inspection reporting*. Each person performing a test or inspection as specified in §180.407 must prepare a written report, in English, in accordance with this paragraph.

(1) Each test or inspection report must include the following information:

- (i) Owner's and manufacturer's unique serial number for the cargo tank;
- (ii) Name of cargo tank manufacturer;
- (iii) Cargo tank DOT or MC specification number;
- (iv) MAWP of the cargo tank;
- (v) Minimum thickness of the cargo tank shell and heads when the cargo tank is thickness tested in accordance with §180.407(d)(4), §180.407(e)(3), §180.407(f)(3), or §180.407(i);
- (vi) Indication of whether the cargo tank is lined, insulated, or both; and
- (vii) Indication of special service of the cargo tank (e.g., transports material corrosive to the tank, dedicated service, etc.)

(2) Each test or inspection report must include the following specific information as appropriate for each individual type of test or inspection:

- (i) Type of test or inspection performed;
- (ii) Date of test or inspection (month and year);
- (iii) Listing of all items tested or inspected, including information about pressure relief devices that are removed, inspected and tested or replaced, when applicable (type of device, set to discharge pressure, pressure at which device opened, pressure at which device re-seated, and a statement of disposition of the device (e.g., re-installed, repaired, or replaced)); information regarding the inspection of upper coupler assemblies, when applicable (visually examined in place, or removed for examination); and, information regarding leakage and pressure testing, when applicable (pneumatic or

hydrostatic testing method, identification of the fluid used for the test, test pressure, and holding time of test);

(iv) Location of defects found and method of repair;

(v) ASME or National Board Certificate of Authorization number of facility performing repairs, if applicable;

(vi) Name and address of person performing test;

(vii) Registration number of the facility or person performing the test;

(viii) Continued qualification statement, such as "cargo tank meets the requirements of the DOT specification identified on this report" or "cargo tank fails to meet the requirements of the DOT specification identified on this report";

(ix) DOT registration number of the registered inspector; and

(x) Dated signature of the registered inspector and the cargo tank owner.

(3) The owner and the motor carrier, if not the owner, must each retain a copy of the test and inspection reports until the next test or inspection of the same type is successfully completed. This requirement does not apply to a motor carrier leasing a cargo tank for fewer than 30 days.

(c) *Additional requirements for Specification MC 330 and MC 331 cargo tanks.*

(1) After completion of the pressure test specified in § 180.407(g)(3), each motor carrier operating a Specification MC 330 or MC 331 cargo tank in anhydrous ammonia, liquefied petroleum gas, or any other service that may cause stress corrosion cracking, must make a written report containing the following information:

(i) Carrier's name, address of principal place of business, and telephone number;

(ii) Complete identification plate data required by Specification MC 330 or MC 331, including data required by ASME Code;

(iii) Carrier's equipment number;

(iv) A statement indicating whether or not the tank was stress relieved after fabrication;

(v) Name and address of the person performing the test and the date of the test;

(vi) A statement of the nature and severity of any defects found. In particular, information must be furnished

to indicate the location of defects detected, such as in weld, heat-affected zone, the liquid phase, the vapor phase, or the head-to-shell seam. If no defect or damage was discovered, that fact must be reported;

(vii) A statement indicating the methods employed to make repairs, who made the repairs, and the date they were completed. Also, a statement of whether or not the tank was stress relieved after repairs and, if so, whether full or local stress relieving was performed;

(viii) A statement of the disposition of the cargo tank, such as "cargo tank scrapped" or "cargo tank returned to service"; and

(ix) A statement of whether or not the cargo tank is used in anhydrous ammonia, liquefied petroleum gas, or any other service that may cause stress corrosion cracking. Also, if the cargo tank has been used in anhydrous ammonia service since the last report, a statement indicating whether each shipment of ammonia was certified by its shipper as containing 0.2 percent water by weight.

(2) A copy of the report must be retained by the carrier at its principal place of business during the period the cargo tank is in the carrier's service and for one year thereafter. Upon a written request to, and with the approval of, the Field Administrator, Regional Service Center, Federal Motor Carrier Safety Administration for the region in which a motor carrier has its principal place of business, the carrier may maintain the reports at a regional or terminal office.

(3) The requirement in paragraph (c)(1) of this section does not apply to a motor carrier leasing a cargo tank for less than 30 days.

(d) *Supplying certificates and reports.* Each person offering a DOT-specification cargo tank for sale or lease must provide the purchaser or lessee a copy of the cargo tank certificate of compliance, records of repair, modification, stretching, or rebarrelling; and the most recent inspection and test reports made under this section. Copies of such reports must be provided to the lessee



## § 180.501

if the cargo tank is leased for more than 30 days.

[Amdt. 180-2, 54 FR 25032, June 12, 1989, as amended at 55 FR 21038, May 22, 1990; 55 FR 37069, Sept. 7, 1990; 56 FR 27879, June 17, 1991; 58 FR 12905, Mar. 8, 1993; Amdt. 180-2, 59 FR 1786, Jan. 12, 1994; Amdt. 180-10, 61 FR 51343, Oct. 1, 1996; 63 FR 52850, Oct. 1, 1998; 64 FR 28052, May 24, 1999; 65 FR 50463, Aug. 18, 2000; 67 FR 61016, Sept. 27, 2002; 68 FR 19290, Apr. 18, 2003; 68 FR 52372, Sept. 3, 2003; 69 FR 54047, Sept. 7, 2004; 70 FR 34077, June 13, 2005]

### Subpart F—Qualification and Maintenance of Tank Cars

SOURCE: Amdt. 180-8, 60 FR 49079, Sept. 21, 1995, unless otherwise noted.

#### § 180.501 Applicability.

(a) This subpart prescribes requirements, in addition to those contained in parts 107, 171, 172, 173, and 179 of this subchapter, applicable to any person who manufactures, fabricates, marks, maintains, repairs, inspects, or services tank cars to ensure continuing qualification.

(b) Any person who performs a function prescribed in this part shall perform that function in accordance with this part.

[Amdt. 180-8, 60 FR 49079, Sept. 21, 1995, as amended by Amdt. 179-50, 61 FR 33256, June 26, 1996]

#### § 180.503 Definitions.

The definitions contained in §§ 171.8 and 179.2 of this subchapter apply.

#### § 180.505 Quality assurance program.

The quality assurance program requirements of § 179.7 of this subchapter apply.

#### § 180.507 Qualification of tank cars.

(a) Each tank car marked as meeting a “DOT” specification or any other tank car used for the transportation of a hazardous material must meet the requirements of this subchapter or the applicable specification to which the tank was constructed.

(b) *Tank car specifications no longer authorized for construction.* (1) Tank cars prescribed in the following table are authorized for service provided they conform to all applicable safety requirements of this subchapter:

## 49 CFR Ch. I (10–1–08 Edition)

| Specification prescribed in the current regulations | Other specifications permitted | Notes |
|-----------------------------------------------------|--------------------------------|-------|
| 105A200W .....                                      | 105A100W .....                 | 1     |
| 105A200ALW .....                                    | 105A100ALW .....               | 1     |
| 105A300W .....                                      | ICC-105, 105A300.              |       |
| 105A400W .....                                      | 105A400.                       |       |
| 105A500W .....                                      | 105A500.                       |       |
| 105A600W .....                                      | 105A600.                       |       |
| 106A500X .....                                      | ICC-27, BE-27, 106A500.        |       |
| 106A800X .....                                      | 106A800.                       |       |
| 107A * * * .....                                    |                                | 2     |

NOTE 1: Tanks built as Specification DOT 105A100W or DOT 105A100ALW may be altered and converted to DOT 105A200W and DOT 105A200ALW, respectively.

NOTE 2: The test pressures of tanks built in the United States between January 1, 1941 and December 31, 1955, may be increased to conform to Specification 107A. Original and revised test pressure markings must be indicated and may be shown on the tank or on a plate attached to the bulkhead of the car. Tanks built before 1941 are not authorized.

(2) For each tank car conforming to and used under an exemption issued before October 1, 1984, which authorized the transportation of a cryogenic liquid in a tank car, the owner or operator shall remove the exemption number stenciled on the tank car and stamp the tank car with the appropriate Class DOT-113 specification followed by the applicable exemption number. For example: DOT-113D60W-E \* \* \* \* (asterisks to be replaced by the exemption number). The owner or operator marking a tank car in this manner shall retain on file a copy of the last exemption in effect during the period the tank car is in service. No person may modify a tank car marked under this paragraph unless the modification is in compliance with an applicable requirement or provision of this subchapter.

(3) Specification DOT-113A175W, DOT-113C60W, DOT-113D60W, and DOT-113D120W tank cars may continue in use, but new construction is not authorized.

(4) Class DOT 105A and 105S tank cars used to transport hydrogen chloride, refrigerated liquid under the terms of DOT-E 3992 may continue in service, but new construction is not authorized.

(5) Specification DOT-103A-ALW, 103AW, 103ALW, 103ANW, 103BW, 103CW, 103DW, 103EW, and 104W tank cars may continue in use, but new construction is not authorized.

[Amdt. 180-8, 60 FR 49079, Sept. 21, 1995, as amended at 68 FR 48572, Aug. 14, 2003]

**§ 180.509 Requirements for inspection and test of specification tank cars.**

(a) *General.* (1) Each tank car facility shall evaluate a tank car according to the requirements specified in § 180.511.

(2) Each tank car that successfully passes a periodic inspection and test must be marked as prescribed in § 180.515.

(3) A written report as specified in § 180.517(b) must be prepared for each tank car that is inspected and tested under this section.

(b) *Conditions requiring inspection and test of tank cars.* Without regard to any other periodic inspection and test requirements, a tank car must have an appropriate inspection and test according to the type of defect and the type of maintenance or repair performed if:

(1) The tank car shows evidence of abrasion, corrosion, cracks, dents, distortions, defects in welds, or any other condition that makes the tank car unsafe for transportation. An example is if maintenance is performed to replace a fitting, then only a leakage pressure test needs to be performed.

(2) The tank car was in an accident and damaged to an extent that may adversely affect its capability to retain its contents.

(3) The tank bears evidence of damage caused by fire.

(4) The Associate Administrator for Safety, FRA, requires it based on the existence of probable cause that a tank car or a class or design of tank cars may be in an unsafe operating condition.

(c) *Frequency of inspection and tests.* Each tank car shall have an inspection and test according to the requirements of this paragraph.

(1) For Class 107 tank cars and tank cars of riveted construction, the tank car must have a hydrostatic pressure test and visual inspection conforming to the requirements in effect prior to July 1, 1996, for the tank specification.

(2) For Class DOT 113 tank cars, see § 173.319(e) of this subchapter.

(3) For fusion welded tank cars, each tank car must have an inspection and test in accordance with paragraphs (d) through (k) of this section.

(i) For cars transporting materials not corrosive to the tank, every 10 years for the tank and service equip-

ment (i.e., filling and discharge, venting, safety, heating, and measuring devices).

(ii) For non-lined or non-coated tank cars transporting materials corrosive to the tank, an interval based on the following formula, but in no case shall the interval exceed 10 years for the tank and 5 years for service equipment:

$$i = \frac{t_1 - t_2}{r}$$

Where:

i is the inspection and test interval.

t<sub>1</sub> is the actual thickness.

t<sub>2</sub> is the allowable minimum thickness under paragraph (g) of this section.

r is the corrosion rate per year.

(iii) For lined or coated tank cars transporting a material corrosive to the tank, every 10 years for the tank, 5 years for the service equipment.

(A) When a lining or coating is applied to protect the tank shell from the lading, the owner of the lining or coating shall determine the periodic inspection interval, test technique, and acceptance criteria for the lining or coating. The owner must maintain at its principal place of business all supporting documentation used to make such a determination, such as the lining or coating manufacturer's recommended inspection interval, test technique, and acceptance criteria. The supporting documentation must be made available to FRA upon request.

(B) The owner of the lining or coating shall provide the periodic inspection interval, test technique, and acceptance criteria for the lining or coating to the person responsible for qualifying the lining and coating.

(d) *Visual inspection.* At a minimum, each tank car facility must visually inspect the tank externally and internally as follows:

(1) An internal inspection of the tank shell and heads for abrasion, corrosion, cracks, dents, distortions, defects in welds, or any other condition that makes the tank car unsafe for transportation, and except in the areas where insulation or a thermal protection system precludes it, an external inspection of the tank shell and heads for abrasion, corrosion, cracks, dents, distortions, defects in welds, or any

other condition that makes the tank car unsafe for transportation;

(2) An inspection of the piping, valves, fittings, and gaskets for indications of corrosion and other conditions that make the tank car unsafe for transportation;

(3) An inspection for missing or loose bolts, nuts, or elements that make the tank car unsafe for transportation;

(4) An inspection of all closures on the tank car for proper securement in a tool tight condition and an inspection of the protective housings for proper securement;

(5) An inspection of excess flow valves having threaded seats for tightness; and

(6) An inspection of the required markings on the tank car for legibility.

(e) *Structural integrity inspections and tests.* At a minimum, each tank car facility shall inspect the tank car for structural integrity as specified in this section. The structural integrity inspection and test shall include all transverse fillet welds greater than 0.64 cm (0.25 inch) within 121.92 cm (4 feet) of the bottom longitudinal center line; the termination of longitudinal fillet welds greater than 0.64 cm (0.25 inch) within 121.92 cm (4 feet) of the bottom longitudinal center line; and all tank shell butt welds within 60.96 cm (2 feet) of the bottom longitudinal center line by one or more of the following inspection and test methods to determine that the welds are in proper condition:

- (1) Dye penetrant test;
- (2) Radiography test;
- (3) Magnetic particle test;
- (4) Ultrasonic test; or
- (5) Optically-aided visual inspection (e.g., magnifiers, fiberscopes, borescopes, and machine vision technology).

(f) *Thickness tests.* (1) Each tank car facility shall measure the thickness of the tank car shell, heads, sumps, domes, and nozzles on each tank car by using a device capable of accurately measuring the thickness to within  $\pm 0.05$  mm ( $\pm 0.002$  inch).

(2) After repairs, alterations, conversions or modifications of a tank car that result in a reduction to the tank car shell thickness, the tank car facility shall measure the thickness of the tank car shell in the area of reduced shell thickness to ensure that the shell thickness conforms to paragraph (g) of this section.

(g) *Service life shell thickness allowance.* (1) A tank car found with a shell thickness below the required minimum thickness after forming for its specification, as stated in part 179 of this subchapter, may continue in service if:

- (i) Construction of the tank car shell and heads is from carbon steel, stainless steel, aluminum, nickel, or manganese-molybdenum steel; and
- (ii) Any reduction in the required minimum thickness of the tank shell or head is not more than that provided in the following table:

ALLOWABLE SHELL THICKNESS REDUCTIONS

| Damage type                      | Class DOT 103, 104, 111, and 115 tank cars |                      | Class DOT 105, 109, 112, and 114 tank cars |                       |
|----------------------------------|--------------------------------------------|----------------------|--------------------------------------------|-----------------------|
|                                  | Top shell and tank head                    | Bottom shell         | Top shell and tank head                    | Bottom shell          |
| Corrosion .....                  | 3.17 mm (0.125 inch)                       | 1.58 mm (0.063 inch) | 0.79 mm (0.031 inch)                       | 0.79 mm (0.031 inch). |
| Corrosion and mechanical .....   | 3.17 mm (0.125 inch)                       | 1.58 mm (0.063 inch) | 0.79 mm (0.031 inch)                       | 0.79 mm (0.031 inch). |
| Corrosion, local .....           | 4.76 mm (0.188 inch)                       | 3.17 mm (0.125 inch) | 1.58 mm (0.063 inch)                       | 1.58 mm (0.063 inch). |
| Mechanical, local .....          | 3.17 mm (0.125 inch)                       | 1.58 mm (0.063 inch) | 1.58 mm (0.063 inch)                       | 1.58 mm (0.063 inch). |
| Corrosion and mechanical, local. | 4.76 mm (0.188 inch)                       | 3.17 mm (0.125 inch) | 1.58 mm (0.063 inch)                       | 1.58 mm (0.063 inch). |

NOTES: 1. The perimeter for a local reduction may not exceed a 60.96 cm (24 inch) perimeter. Local reductions in the top shell must be separated from other reductions in the top shell by at least 40.64 cm (16 inches). The cumulative perimeter for local reductions in the bottom shell may not exceed 182.88 cm (72 inches).

2. Any reduction in the tank car shell may not affect the structural strength of the tank car so that the tank car shell no longer conforms to Section 6.2 of the AAR Specifications for Tank Cars (IBR, see §171.7 of this subchapter).

3. Any reduction applies only to the outer shell for Class DOT 115 tank cars.

4. For Class DOT 103 and 104 tank cars, the inside diameter may not exceed 243.84 cm (96 inches).

(h) *Safety system inspections.* At a minimum, each tank car facility must inspect:

- (1) Tank car thermal protection systems, tank head puncture resistance

systems, coupler vertical restraint systems, and systems used to protect discontinuities (i.e., skid protection and protective housings) to ensure their integrity.

(2) Reclosing pressure relief devices by:

(i) Removing the reclosing pressure relief device from the tank car for inspection; and

(ii) Testing the reclosing pressure relief device with air or another gas to ensure that it conforms to the start-to-discharge pressure for the specification or hazardous material in this subchapter.

(i) *Lining and coating inspection and test.* When this subchapter requires a lining or coating, at a minimum, each tank car facility must inspect the lining or coating installed on the tank car according to the inspection interval test technique, and acceptance criteria established by the owner of the lining or coating in accordance with paragraph (c)(3)(iii) of this section.

(j) *Leakage pressure test.* (1) After reassembly of a tank car or service equipment, a tank car facility must perform a leak test on the tank or service equipment to detect leakage, if any, between manway covers, cover plates, and service equipment. The test may be conducted with the hazardous material in the tank. When the test pressure exceeds the start-to-discharge or burst pressure of a pressure relief device, the device must be rendered inoperative. The written procedures and test method for leak testing must ensure for the sensitivity and reliability of the test method and for the serviceability of components to prevent premature failure.

(2) Interior heater systems must be tested hydrostatically at 13.87 Bar (200 psig) and must show no signs of leakage.

(k) *Alternative inspection and test procedures.* In lieu of the requirements of this section, a person may use an alternative inspection and test procedure or interval based on a damage-tolerance fatigue evaluation (that includes a determination of the probable locations and modes of damage due to fatigue, corrosion, or accidental damage), when the evaluation is examined by the Association of American Rail-

roads Tank Car Committee and approved by the Associate Administrator for Safety, FRA.

(l) *Inspection and test compliance date for tank cars.* (1) After July 1, 2000, each tank car with a metal jacket or with a thermal protection system shall have an inspection and test conforming to this section no later than the date the tank car requires a periodic hydrostatic pressure test (i.e., the marked due date on the tank car for the hydrostatic test).

(2) After July 1, 1998, each tank car without a metal jacket shall have an inspection and test conforming to this section no later than the date the tank car requires a periodic hydrostatic pressure test (i.e., the marked due date on the tank car for the hydrostatic test).

(3) For tank cars on a 20-year periodic hydrostatic pressure test interval (i.e., Class DOT 103W, 104W, 111A60W1, 111A100W1, and 111A100W3 tank cars), the next inspection and test date is the midpoint between the compliance date in paragraph (l)(1) or (2) of this section and the remaining years until the tank would have had a hydrostatic pressure test.

[Amdt. 180-8, 60 FR 49079, Sept. 21, 1995, as amended by Amdt. 179-50, 61 FR 33256, June 26, 1996; 62 FR 51561, Oct. 1, 1997; 63 FR 52851, Oct. 1, 1998; 66 FR 45391, Aug. 28, 2001; 68 FR 75765, Dec. 31, 2003; 71 FR 54398, Sept. 14, 2006]

#### **§ 180.511 Acceptable results of inspections and tests.**

Provided it conforms with other applicable requirements of this subchapter, a tank car is qualified for use if it successfully passes the following inspections and tests conducted in accordance with this subpart:

(a) *Visual inspection.* A tank car successfully passes the visual inspection when the inspection shows no structural defect that may cause leakage from or failure of the tank before the next inspection and test interval.

(b) *Structural integrity inspection and test.* A tank car successfully passes the structural integrity inspection and test when it shows no structural defect that may initiate cracks or propagate cracks and cause failure of the tank before the next inspection and test interval.

## § 180.513

## 49 CFR Ch. I (10–1–08 Edition)

(c) *Service life shell thickness.* A tank car successfully passes the service life shell thickness inspection when the tank shell and heads show no thickness reduction below that allowed in § 180.509(g).

(d) *Safety system inspection.* A tank car successfully passes the safety system inspection when each thermal protection system, tank head puncture resistance system, coupler vertical restraint system, and system used to protect discontinuities (e.g., breakage grooves on bottom outlets and protective housings) on the tank car conform to this subchapter.

(e) *Lining and coating inspection.* A tank car successfully passes the lining and coating inspection and test when the lining or coating conforms to the owner's acceptance criteria.

(f) *Leakage pressure test.* A tank car successfully passes the leakage pressure test when all product piping, fittings and closures show no indication of leakage.

(g) *Hydrostatic test.* A Class 107 tank car or a riveted tank car successfully passes the hydrostatic test when it shows no leakage, distortion, excessive permanent expansion, or other evidence of weakness that might render the tank car unsafe for transportation service.

[Amdt. 180–8, 60 FR 49079, Sept. 21, 1995, as amended by Amdt. 179–50, 61 FR 33256, June 26, 1996; 66 FR 45187, Aug. 28, 2001]

### § 180.513 Repairs, alterations, conversions, and modifications.

(a) In order to repair tank cars, the tank car facility must comply with the requirements of appendix R of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter).

(b) Unless the exterior tank car shell or interior tank car jacket has a protective coating, after a repair that requires the complete removal of the tank car jacket, the exterior tank car shell and the interior tank car jacket must have a protective coating applied to prevent the deterioration of the tank shell and tank jacket.

[Amdt. 180–2, 54 FR 25032, June 12, 1989, as amended at 68 FR 75765, Dec. 31, 2003]

### § 180.515 Markings.

(a) When a tank car passes the required inspection and test with acceptable results, the tank car facility shall mark the date of the inspection and test and the due date of the next inspection and test on the tank car in accordance with appendix C of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter). When a tank car facility performs multiple inspection and test at the same time, one date may be used to satisfy the requirements of this section. One date also may be shown when multiple inspection and test have the same due date.

(b) Pressure converted tank cars must have the new specification and conversion date permanently marked in letters and figures at least 0.95 cm (0.375 inch) high on the outside of the manway nozzle or the edge of the manway nozzle flange on the left side of the car. The marking may have the last numeral of the specification number omitted (e.g., “DOT 111A100W” instead of “DOT 111A100W1”).

(c) When pressure tested within six months of installation and protected from deterioration, the test date marking of a reclosing pressure relief device is the installation date on the tank car.

[Amdt. 180–8, 60 FR 49079, Sept. 21, 1995, as amended by Amdt. 179–50, 61 FR 33256, June 26, 1996; 63 FR 52851, Oct. 1, 1998; 66 FR 45391, Aug. 28, 2001; 68 FR 75765, Dec. 31, 2003]

### § 180.517 Reporting and record retention requirements.

(a) *Certification and representation.* Each owner of a specification tank car shall retain the certificate of construction (AAR Form 4–2) and related papers certifying that the manufacture of the specification tank car identified in the documents is in accordance with the applicable specification. The owner shall retain the documents throughout the period of ownership of the specification tank car and for one year thereafter. Upon a change of ownership, the requirements in Section 1.3.15 of the AAR Specifications for Tank Cars (IBR, see § 171.7 of this subchapter) apply.

(b) *Inspection and test reporting.* Each tank car that is inspected as specified

in § 180.509 must have a written report, in English, prepared according to this paragraph. The owner must retain a copy of the inspection and test reports until successfully completing the next inspection and test of the same type. The inspection and test report must include the following:

- (1) Type of inspection and test performed (a checklist is acceptable);
- (2) The results of each inspection and test performed;
- (3) Owner's reporting mark;
- (4) DOT Specification;
- (5) Inspection and test date (month and year);
- (6) Location and description of defects found and method used to repair each defect;
- (7) The name and address of the tank car facility and the signature of inspector.

[Amdt. 180-2, 54 FR 25032, June 12, 1989, as amended at 68 FR 75765, Dec. 31, 2003]

**§ 180.519 Periodic retest and inspection of tank cars other than single-unit tank car tanks.**

(a) *General.* Unless otherwise provided in this subpart, tanks designed to be removed from cars for filling and emptying and tanks built to a Class DOT 107A specification and their safety relief devices must be retested periodically as specified in Retest Table 1 of paragraph (b)(5) of this section. Retests may be made at any time during the calendar year the retest falls due.

(b) *Pressure test.* (1) Each tank must be subjected to the specified hydrostatic pressure and its permanent expansion determined. Pressure must be maintained for 30 seconds and for as long as necessary to secure complete expansion of the tank. Before testing, the pressure gauge must be shown to be accurate within 1 percent at test measure. The expansion gauge must be shown to be accurate, at test pressure, to within 1 percent. Expansion must be recorded in cubic cm. Permanent volumetric expansion may not exceed 10 percent of total volumetric expansion at test pressure and the tank must not leak or show evidence of distress.

(2) Each tank, except tanks built to specification DOT 107A, must also be subjected to interior air pressure test of at least 100 psig under conditions favorable to detection of any leakage. No leaks may appear.

(3) Safety relief valves must be retested by air or gas, must start-to-discharge at or below the prescribed pressure and must be vapor tight at or above the prescribed pressure.

(4) Rupture discs and fusible plugs must be removed from the tank and visually inspected.

(5) Tanks must be retested as specified in Retest Table 1 of this paragraph (b)(5), and before returning to service after repairs involving welding or heat treatment:

RETEST TABLE 1

| Specification    | Retest interval—years |                                      | Minimum Retest pressure—psig            |               | Pressure relief valve pressure—psig |             |
|------------------|-----------------------|--------------------------------------|-----------------------------------------|---------------|-------------------------------------|-------------|
|                  | Tank                  | Pressure relief devices <sup>a</sup> | Tank hydrostatic expansion <sup>c</sup> | Tank air test | Start-to-discharge                  | Vapor tight |
| DOT 27 .....     | 5                     | 2                                    | 500                                     | 100           | 375                                 | 300         |
| 106A500 .....    | 5                     | 2                                    | 500                                     | 100           | 375                                 | 300         |
| 106A500X .....   | 5                     | 2                                    | 500                                     | 100           | 375                                 | 300         |
| 106A800 .....    | 5                     | 2                                    | 800                                     | 100           | 600                                 | 480         |
| 106A800X .....   | 5                     | 2                                    | 800                                     | 100           | 600                                 | 480         |
| 106A800NCI ..... | 5                     | 2                                    | 800                                     | 100           | 600                                 | 480         |
| 107A * * * *     | <sup>d</sup> 5        | <sup>a</sup> 2                       | <sup>(b)</sup> None                     | None          | None                                | None        |
| 110A500-W .....  | 5                     | 2                                    | 500                                     | 100           | 375                                 | 300         |
| 110A600-W .....  | 5                     | 2                                    | 600                                     | 100           | 500                                 | 360         |
| 110A800-W .....  | 5                     | 2                                    | 800                                     | 100           | 600                                 | 480         |
| 110A1000-W ..... | 5                     | 2                                    | 1,000                                   | 100           | 750                                 | 600         |
| BE-27 .....      | 5                     | 2                                    | 500                                     | 100           | 375                                 | 300         |

NOTES:

<sup>a</sup>If DOT 107A \* \* \* \* tanks are used for transportation of flammable gases, one rupture disc from each car must be burst at the interval prescribed. The sample disc must burst at a pressure not exceeding the marked test pressure of the tank and not less than 70 percent of the marked test pressure. If the sample disc does not burst within the prescribed limits, all discs on the car must be replaced.

<sup>b</sup>The hydrostatic expansion test pressure must at least equal the marked test pressure.

## § 180.601

## 49 CFR Ch. I (10–1–08 Edition)

<sup>c</sup> See § 180.519(b)(1).

<sup>d</sup> Safety relief valves of the spring-loaded type on tanks used exclusively for fluorinated hydrocarbons and mixtures thereof which are free from corroding components may be retested every 5 years.

(6) The month and year of test, followed by a “V” if visually inspected as described in paragraph (c) of this section, must be plainly and permanently stamped into the metal of one head or chime of each tank with successful test results; for example, 01–90 for January 1990. On DOT 107A\*\*\*\* tanks, the date must be stamped into the metal of the marked end, except that if all tanks mounted on a car have been tested, the date may be stamped into the metal of a plate permanently applied to the bulkhead on the “A” end of the car. Dates of previous tests and all prescribed markings must be kept legible.

(c) *Visual inspection.* Tanks of Class DOT 106A and DOT 110A-W specifications (§§ 179.300 and 179.301 of this subchapter) used exclusively for transporting fluorinated hydrocarbons and mixtures thereof, and that are free from corroding components, may be given a periodic complete internal and external visual inspection in place of the periodic hydrostatic retest. Visual inspections shall be made only by competent persons. The tank must be accepted or rejected in accordance with the criteria in CGA C-6 (IBR, see § 171.7 of this subchapter).

(d) *Written records.* The results of the pressure test and visual inspection must be recorded on a suitable data sheet. Completed copies of these reports must be retained by the owner and by the person performing the pressure test and visual inspection as long as the tank is in service. The information to be recorded and checked on these data sheets are: Date of test and inspection; DOT specification number; tank identification (registered symbol and serial number, date of manufacture and ownership symbol); type of protective coating (painted, etc., and statement as to need for refinishing or re-coating); conditions checked (leakage, corrosion, gouges, dents or digs, broken or damaged chime or protective ring, fire, fire damage, internal condition); test pressure; results of tests; and disposition of tank (returned to service, returned to manufacturer for repair, or scrapped); and identification of the per-

son conducting the retest or inspection.

[Amdt. 180–8, 60 FR 49079, Sept. 21, 1995, as amended by Amdt. 179–50, 61 FR 33257, June 26, 1996; 65 FR 58633, Sept. 29, 2000; 66 FR 45187, 45392, Aug. 28, 2001; 68 FR 75765, Dec. 31, 2003]

### Subpart G—Qualification and Maintenance of Portable Tanks

SOURCE: 66 FR 33453, June 21, 2001, unless otherwise noted.

#### § 180.601 Applicability.

This subpart prescribes requirements, in addition to those contained in parts 107, 171, 172, 173, and 178 of this subchapter, applicable to any person responsible for the continuing qualification, maintenance or periodic retesting of a portable tank.

#### § 180.603 Qualification of portable tanks.

(a) Each portable tank used for the transportation of hazardous materials must be an authorized packaging.

(b) To qualify as an authorized packaging, each portable tank must conform to the requirements of this subchapter and the applicable design specification to which the portable tank was constructed.

(c) The following portable tanks are authorized for use provided they conform to all applicable safety requirements of this subchapter: 51, 56, 57, 60, IM 101, IM 102 and UN portable tanks.

(d) A portable tank that also meets the definition of “container” in 49 CFR 450.3(a)(3) must conform to the requirements in parts 450 through 453 of this title for compliance with Annex II of the Convention for Safe Containers (CSC).

(e) *Exemption portable tanks based on DOT 51 portable tanks.* The owner of a portable tank constructed in accordance with and used under an exemption issued prior to August 31, 1996, which was in conformance with the requirements for Specification DOT 51 portable tanks with the exception of the location of fill and discharge outlets,

shall examine the portable tank and its design to determine if it meets the outlet requirements in effect on October 1, 1996. If the owner determines that the portable tank is in compliance with all requirements of the DOT 51 specification, the exemption number stenciled on the portable tank shall be removed and the specification plate (or a plate placed adjacent to the specification plate) shall be durably marked "DOT 51-E\*\*\*\*\*" (where \*\*\*\*\* is to be replaced by the exemption number). During the period the portable tank is in service, and for one year thereafter, the owner of the portable tank must retain on file, at its principal place of business, a copy of the last exemption in effect.

**§ 180.605 Requirements for periodic testing, inspection and repair of portable tanks.**

(a) A portable tank constructed in accordance with a DOT specification for which a test or inspection specified in this subpart has become due, must be tested or inspected prior to being returned for transportation.

(b) *Conditions requiring test and inspection of portable tanks.* Without regard to any other test or inspection requirements, a Specification or UN portable tank must be tested and inspected in accordance with this section prior to further use if any of the following conditions exist:

(1) The portable tank shows evidence of dents, corroded or abraded areas, leakage, or any other condition that might render it unsafe for transportation service.

(2) The portable tank has been in an accident and has been damaged to an extent that may adversely affect its ability to retain the hazardous material.

(3) The portable tank has been out of hazardous materials transportation service for a period of one year or more.

(4) The portable tank has been modified from its original design specification.

(5) The portable tank is in an unsafe operating condition based on the existence of probable cause.

(c) *Schedule for periodic inspections and tests.* Each Specification portable

tank must be tested and inspected in accordance with the following schedule:

(1) Each IM or UN portable tank must be given an initial inspection and test before being placed into service, a periodic inspection and test at least once every 5 years, and an intermediate periodic inspection and test at least every 2.5 years following the initial inspection and the last 5 year periodic inspection and test.

(2) Each Specification 51 portable tank must be given a periodic inspection and test at least once every five years.

(3) Each Specification 56 or 57 portable tank must be given a periodic inspection and test at least once every 2.5 years.

(4) Each Specification 60 portable tank must be given a periodic inspection and test at the end of the first 4-year period after the original test; at least once every 2 years thereafter up to a total of 12 years of service; and at least once annually thereafter. Retesting is not required on a rubber-lined tank except before each relining.

(d) *Intermediate periodic inspection and test.* For IM and UN portable tanks the intermediate 2.5 year periodic inspection and test must include at least an internal and external examination of the portable tank and its fittings taking into account the hazardous materials intended to be transported; a leakage test; and a test of the satisfactory operation of all service equipment. Sheathing, thermal insulation, etc. need only be removed to the extent required for reliable appraisal of the condition of the portable tank. For portable tanks intended for the transportation of a single hazardous material, the internal examination may be waived if it is leakage tested in accordance with the procedures in paragraph (h) of this section prior to each filling, or if approved by the Associate Administrator. Portable tanks used for dedicated transportation of refrigerated liquefied gases that are not fitted with inspection openings are excepted from the internal inspection requirement.

(e) *Periodic inspection and test.* The 5 year periodic inspection and test must include an internal and external examination and, unless excepted, a pressure



test as specified in this section. Sheathing, thermal insulation, etc. need only to be removed to the extent required for reliable appraisal of the condition of the portable tank. Except for DOT Specification 56 and 57 portable tanks, reclosing pressure relief devices must be removed from the tank and tested separately unless they can be tested while installed on the portable tank. For portable tanks where the shell and equipment have been pressure-tested separately, after assembly they must be subjected together to a leakage test and effectively tested and inspected for corrosion. Portable tanks used for the transportation of refrigerated, liquefied gases are excepted from the requirement for internal inspection and the hydraulic pressure test during the 5-year periodic inspection and test, if the portable tanks were pressure tested to a minimum test pressure of 1.3 times the design pressure using an inert gas as prescribed in §178.338–16(a) and (b) of this subchapter before putting the portable tank into service initially and after any exceptional inspections and tests specified in paragraph (f) of this section.

(f) *Exceptional inspection and test.* The exceptional inspection and test is necessary when a portable tank shows evidence of damaged or corroded areas, or leakage, or other conditions that indicate a deficiency that could affect the integrity of the portable tank. The extent of the exceptional inspection and test must depend on the amount of damage or deterioration of the portable tank. It must include at least the inspection and a pressure test according to paragraph (e) of this section. Pressure relief devices need not be tested or replaced unless there is reason to believe the relief devices have been affected by the damage or deterioration.

(g) *Internal and external examination.* The internal and external examinations must ensure that:

(1) The shell is inspected for pitting, corrosion, or abrasions, dents, distortions, defects in welds or any other conditions, including leakage, that might render the portable tank unsafe for transportation;

(2) The piping, valves, and gaskets are inspected for corroded areas, de-

fects, and other conditions, including leakage, that might render the portable tank unsafe for filling, discharge or transportation;

(3) Devices for tightening manhole covers are operative and there is no leakage at manhole covers or gaskets;

(4) Missing or loose bolts or nuts on any flanged connection or blank flange are replaced or tightened;

(5) All emergency devices and valves are free from corrosion, distortion and any damage or defect that could prevent their normal operation. Remote closure devices and self-closing stop-valves must be operated to demonstrate proper operation;

(6) Required markings on the portable tank are legible and in accordance with the applicable requirements; and

(7) The framework, the supports and the arrangements for lifting the portable tank are in satisfactory condition.

(h) *Pressure test procedures for specification 51, 57, 60, IM or UN portable tanks.* (1) Each Specification 57 portable tank must be leak tested by a minimum sustained air pressure of at least 3 psig applied to the entire tank. Each Specification 51 or 56 portable tank must be tested by a minimum pressure (air or hydrostatic) of at least 2 psig or at least one and one-half times the design pressure (maximum allowable working pressure, or re-rated pressure) of the tank, whichever is greater. The leakage test for portable tanks used for refrigerated liquefied gas must be performed at 90% of MAWP. Leakage tests for all other portable tanks must be at a pressure of at least 25% of MAWP. During each air pressure test, the entire surface of all joints under pressure must be coated with or immersed in a solution of soap and water, heavy oil, or other material suitable for the purpose of detecting leaks. The pressure must be held for a period of time sufficiently long to assure detection of leaks, but in no case less than five minutes. During the air or hydrostatic test, relief devices may be removed, but all the closure fittings must be in place and the relief device openings plugged. Lagging need not be removed from a lagged tank if it is possible to maintain the required test pressure at constant temperature with

the tank disconnected from the source of pressure.

(2) Each Specification 60 portable tank must be retested by completely filling the tank with water or other liquid having a similar viscosity, the temperature of the liquid must not exceed 37.7 °C (100 °F) during the test, and applying a pressure of 60 psig. The portable tank must be capable of holding the prescribed pressure for at least 10 minutes without leakage, evidence of impending failure, or failure. All closures shall be in place while the test is made and the pressure shall be gauged at the top of the tank. Safety devices and/or vents shall be plugged during this test.

(3) Each Specification IM or UN portable tank, except for UN portable tanks used for non-refrigerated and refrigerated liquefied gases, and all piping, valves and accessories, except pressure relief devices, must be hydrostatically tested with water, or other liquid of similar density and viscosity, to a pressure not less than 150% of its maximum allowable working pressure. UN portable tanks used for the transportation of non-refrigerated liquefied gases must be hydrostatically tested with water, or other liquid of similar density and viscosity, to a pressure not less than 130% of its maximum allowable working pressure. UN portable tanks used for the transportation of refrigerated liquefied gases may be tested hydrostatically or pneumatically using an inert gas to a pressure not less than 1.3 times the design pressure. For pneumatic testing, due regard for protection of all personnel must be taken because of the potential hazard involved in such a test. The pneumatic test pressure in the portable tank must be reached by gradually increasing the pressure to one-half of the test pressure. Thereafter, the test pressure must be increased in steps of approximately one-tenth of the test pressure until the required test pressure has been reached. The pressure must then be reduced to a value equal to four-fifths of the test pressure and held for a sufficient time to permit inspection of the portable tank for leaks. The minimum test pressure for a portable tank is determined on the basis of the hazardous materials that are intended

to be transported in the portable tanks. For liquid, solid and non-refrigerated liquefied gases, the minimum test pressure for specific hazardous materials are specified in the applicable T Codes assigned to a particular hazardous material in the §172.101 Table of this subchapter. While under pressure the tank shall be inspected for leakage, distortion, or any other condition which might render the tank unsafe for service. A portable tank fails to meet the requirements of the pressure test if, during the test, there is permanent distortion of the tank exceeding that permitted by the applicable specification; if there is any leakage; or if there are any deficiencies that would render the portable tank unsafe for transportation. Any portable tank that fails must be rejected and may not be used again for the transportation of a hazardous material unless the tank is adequately repaired, and, thereafter, a successful test is conducted in accordance with the requirements of this paragraph. An approval agency shall witness the hydrostatic or pneumatic test. Any damage or deficiency that might render the portable tank unsafe for service shall be repaired to the satisfaction of the witnessing approval agency. The repaired tank must be retested to the original pressure test requirements. Upon successful completion of the hydrostatic or pneumatic test, as applicable, the witnessing approval agency shall apply its name, identifying mark or identifying number in accordance with paragraph (k) of this section.

(i) *Rejection criteria.* When evidence of any unsafe condition is discovered, the portable tank may not be returned to service until it has been repaired and the pressure test is repeated and passed.

(j) *Repair.* The repair of a portable tank is authorized, provided such repairs are made in accordance with the requirements prescribed in the specification for the tank's original design and construction. In addition to any other provisions of the specification, no portable tank may be repaired so as to cause leakage or cracks or so as to increase the likelihood of leakage or cracks near areas of stress concentration due to cooling metal shrinkage in

welding operations, sharp fillets, reversal of stresses, or otherwise. No field welding may be done except to non-pressure parts. Any cutting, burning or welding operations on the shell of an IM or UN portable tank must be done with the approval of the approval agency and be done in accordance with the requirements of this subchapter, taking into account the pressure vessel code used for the construction of the shell. A pressure test to the original test pressure must be performed after the work is completed.

(k) *Inspection and test markings.* (1) Each IM or UN portable tank must be durably and legibly marked, in English, with the date (month and year) of the last pressure test, the identification markings of the approval agency witnessing the test, when required, and the date of the last visual inspection. The marking must be placed on or near the metal identification plate, in letters and numerals of not less than 3 mm (0.118 inches) high when on the metal identification plate, and 12 mm (0.47 inches) high when on the portable tank.

(2) Each Specification DOT 51, 56, 57 or 60 portable tank must be durably and legibly marked, in English, with the date (month and year) of the most recent periodic retest. The marking must be placed on or near the metal certification plate and must be in accordance with §178.3 of this subchapter. The letters and numerals must not be less than 3 mm (0.118 inches) high when on the metal certification plate, and 12 mm (0.47 inches) high when on the portable tank, except that a portable tank manufactured under a previously authorized specification may continue to be marked with smaller markings if originally authorized under that specification (for example, DOT Specification 57 portable tanks).

(l) *Record retention.* The owner of each portable tank or his authorized agent shall retain a written record of the date and results of all required inspections and tests, including an ASME manufacturer's date report, if applicable, and the name and address of the person performing the inspection or test, in accordance with the applicable specification. The manufacturer's data report, including a certificate(s) signed

by the manufacturer, and the authorized design approval agency, as applicable, indicating compliance with the applicable specification of the portable tank, must be retained in the files of the owner, or his authorized agent, during the time that such portable tank is used for such service, except for Specifications 56 and 57 portable tanks.

[Amdt. 180–2, 54 FR 25032, June 12, 1989, as amended at 67 FR 15744, Apr. 3, 2002; 68 FR 45042, July 31, 2003]

#### APPENDIX A TO PART 180—INTERNAL SELF-CLOSING STOP VALVE EMERGENCY CLOSURE TEST FOR LIQUEFIED COMPRESSED GASES

1. In performing this test, all internal self-closing stop valves must be opened. Each emergency discharge control remote actuator (on-truck and off-truck) must be operated to ensure that each internal self-closing stop valve's lever, piston, or other valve indicator has moved to the closed position.

2. On pump-actuated pressure differential internal valves, the three-way toggle valve handle or its cable attachment must be activated to verify that the toggle handle moves to the closed position.

[64 FR 28052, May 24, 1999, as amended at 67 FR 15744, Apr. 3, 2002]

#### APPENDIX B TO PART 180—ACCEPTABLE INTERNAL SELF-CLOSING STOP VALVE LEAKAGE TESTS FOR CARGO TANKS TRANSPORTING LIQUEFIED COMPRESSED GASES

For internal self-closing stop valve leakage testing, leakage is defined as any leakage through the internal self-closing valve or to the atmosphere that is detectable when the valve is in the closed position. On some valves this will require the closure of the pressure by-pass port.

##### (a) *Meter Creep Test.*

1. An operator of a cargo tank equipped with a calibrated meter may check the internal self-closing stop valve for leakage through the valve seat using the meter as a flow measurement indicator. The test is initiated by starting the delivery process or returning product to the cargo tank through the delivery system. This may be performed at an idle. After the flow is established, the operator closes the internal self-closing stop valve and monitors the meter flow. The meter flow must stop within 30 seconds with no meter creep within 5 seconds after the meter stops.

2. On pump-actuated pressure differential internal self-closing stop valves, the valve

must be closed with the remote actuator to assure that it is functioning. On other types of internal self-closing stop valves, the valve(s) may be closed using either the normal valve control or the discharge control system (e.g., remote).

3. Rejection criteria: Any detectable meter creep within the first five seconds after initial meter stoppage.

*(b) Internal Self-Closing Stop Valve Test.*

An operator of a cargo tank that is not equipped with a meter may check the internal self-closing stop valve(s) for leakage as follows:

1. The internal self-closing stop valve must be in the closed position.
2. All of the material in the downstream piping must be evacuated, and the piping must be returned to atmospheric temperature and pressure.
3. The outlet must be monitored for 30 seconds for detectable leakage.
4. Rejection criteria. Any detectable leakage is considered unacceptable.

[64 FR 28052, May 24, 1999]

APPENDIX C TO PART 180—EDDY CURRENT EXAMINATION WITH VISUAL INSPECTION FOR DOT 3AL CYLINDERS MANUFACTURED OF ALUMINUM ALLOY 6351-T6

1. *Examination Procedure.* Each facility performing eddy current examination with visual inspection must develop, update, and maintain a written examination procedure applicable to the test equipment it uses to perform eddy current examinations.

2. *Visual examinations.* Visual examinations of the neck and shoulder area of the cylinder must be conducted in accordance with CGA pamphlet C-6.1 (IBR; see §171.7 of this subchapter).

3. *Eddy Current Equipment.* A reference ring and probe for each DOT-3AL cylinder manufactured of aluminum alloy 6351-T6 to be inspected must be available at the examination facility. Eddy current equipment must be capable of accurately detecting the notches on the standard reference ring.

4. *Eddy Current Reference Ring.* The reference ring must be produced to represent each cylinder to be tested. The reference ring must include artificial notches to simulate a neck crack. The size of the artificial notch (depth and length) must have a depth less

than or equal to  $\frac{1}{8}$  of the wall thickness of the neck and a length greater than or equal to two threads. The standard reference must have a drawing that includes the diameter of the ring, and depth and length of each notch.

5. *Condemnation Criteria.* A cylinder must be condemned if the eddy current examination combined with visual examination reveals any crack in the neck or shoulder of 2 thread lengths or more.

6. *Examination equipment records.* Records of eddy current inspection equipment shall contain the following information:

- (i) Equipment manufacturer, model number and serial number.
- (ii) Probe description and unique identification (e.g., serial number, part number, etc.).

7. *Eddy current examination reporting and record retention requirements.* Daily records of eddy current examinations must be maintained by the person who performs the requalification until either the expiration of the requalification period or until the cylinder is again requalified, whichever occurs first. These records shall be made available for inspection by a representative of the Department on request. Eddy current examination records shall contain the following information:

- (i) Specification of each standard reference ring used to perform the eddy current examination.
- (ii) DOT specification or exemption number of the cylinder; manufacturer's name or symbol; owner's name or symbol, if present; serial number; and, date of manufacture.
- (iii) Name of test operator performing the eddy current examination.
- (iv) Date of eddy current examination.
- (v) Acceptance/condemnation results (e.g. pass or fail).
- (vi) Retester identification number.

8. *Personnel Qualification Requirements.* Each person who performs eddy current and visual examinations, and evaluates and certifies retest results must be certified by the employer that he/she has been properly trained and tested in the eddy current and visual examination procedures.

9. *Training Records.* A record of current training must be maintained for each employee who performs eddy current and visual examinations in accordance with §172.704(d).

[71 FR 51129, Aug. 29, 2006]

**PARTS 181-185 [RESERVED]**

## FINDING AIDS

---

A list of CFR titles, subtitles, chapters, subchapters and parts and an alphabetical list of agencies publishing in the CFR are included in the CFR Index and Finding Aids volume to the Code of Federal Regulations which is published separately and revised annually.

Material Approved for Incorporation by Reference  
Table of CFR Titles and Chapters  
Alphabetical List of Agencies Appearing in the CFR  
List of CFR Sections Affected



## Material Approved for Incorporation by Reference

(Revised as of October 1, 2008)

The Director of the Federal Register has approved under 5 U.S.C. 552(a) and 1 CFR part 51 the incorporation by reference of the following publications. This list contains only those incorporations by reference effective as of the revision date of this volume. Incorporations by reference found within a regulation are effective upon the effective date of that regulation. For more information on incorporation by reference, see the preliminary pages of this volume.

### 49 CFR (PARTS 100–185)

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)

49 CFR

#### Air Transport Association of America

1301 Pennsylvania Avenue NW., Washington, DC 20004–1707

ATA Specification No. 300, Packaging of Airline Supplies, Revision 171.7; 172.102  
19, July 31, 1996.

#### Aluminum Association

420 Lexington Ave., New York, NY 10017

Aluminum Standards and Data, Seventh Edition, June 1982 ..... 171.7; 172.102;  
178.65

#### American National Standards Institute (ANSI)

25 West 43rd Street, 4th Floor, New York, NY 10036; phone:  
1 (212) 642–4900; fax: 1 (212) 398–0023; [http://webstore.ansi.org/  
ansidocstore/default.asp](http://webstore.ansi.org/ansidocstore/default.asp)

ANSI B16.5–77 Steel Pipe Flanges, Flanged Fittings ..... 178.360–4

ANSI N14.1 American National Standard for Nuclear Materials— 171.7; 173.417;  
Uranium Hexafluoride—Packaging for Transport (1971, 1982, 1987, 173.420  
1990, 1995 and 2001 Editions).

ANSI/ASHRAE 15–1994, Safety Code for Mechanical Refrigeration 171.7; 173.306;  
173.307

#### American Petroleum Institute

1220 L Street, NW, Washington, DC 20005–4070

API Recommended Practice 1604: Closure of Underground Petroleum 171.7; 172.102  
Storage Tanks, Third Edition, March 1996.

#### American Pyrotechnics Association

P.O. Box 213, Chestertown, MD 21620

APA Standard 87–1 Standard for Construction and Approval for 171.7; 173.56  
Transportation of Fireworks, Novelties, and Theatrical Pyrotechnics,  
December 1, 2001 edition.

#### American Society of Mechanical Engineers

ASME International, 22 Law Drive, P.O. Box 2900, Fairfield, New  
Jersey 07007–2900

ASME Code:

## Title 49—Transportation

### 49 CFR (PARTS 100–185)—Continued

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued

##### 49 CFR

|                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|-------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Sections II (Parts A and B), V, VIII (Division I) and IX of 1998 Ed. of American Society of Mechanical Engineers Boiler and Pressure Code | 172.102; 173.24b;<br>173.32; 173.306;<br>173.315; 173.318;<br>173.420; 178.245–<br>1; 187.245–3;<br>178.245–4;<br>178.245–6;<br>178.245–7;<br>178.255–1;<br>178.255–2;<br>178.255–14;<br>178.255–15;<br>178.270–2;<br>178.270–3;<br>178.270–7;<br>178.270–9;<br>178.270–11;<br>178.270–12;<br>178.271–1;<br>178.272–1;<br>178.273; 178.274;<br>178.276; 178.277;<br>178.320; 178.337–<br>1; 178.337–2;<br>178.337–3;<br>178.337–4;<br>178.337–6;<br>178.337–16;<br>178.337–18;<br>178.338–1;<br>178.338–2;<br>178.338–3;<br>178.338–4;<br>178.338–5;<br>178.338–6;<br>178.338–13;<br>178.338–16;<br>178.338–18;<br>178.338–19;<br>178.345–1;<br>178.345–2;<br>178.345–3;<br>178.345–4;<br>178.345–7;<br>178.345–14;<br>178.345–15;<br>178.346–1;<br>178.347–1;<br>178.348–1;<br>179.400–3;<br>180.407 |
|-------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

|                                                                                                                                     |               |
|-------------------------------------------------------------------------------------------------------------------------------------|---------------|
| ASME B31.4: Pipeline Transportation Systems for Liquid Hydrocarbons and Other Liquids, Chapters II, III, IV, V and VI, 1998 Edition | 171.7, 173.5a |
|-------------------------------------------------------------------------------------------------------------------------------------|---------------|



## Material Approved for Incorporation by Reference

**49 CFR (PARTS 100–185)—Continued**

**RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF  
TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued**

**49 CFR**

### **American Society for Testing and Materials**

100 Barr Harbor Drive, West Conshohocken, PA, 19428–2959, Telephone (610) 832–9585, FAX (610) 832–9555

Noncurrent ASTM standards are available from: Engineering Societies Library, 354 E. 47th St., New York, NY 10017.

|                                                                                                                                                           |                                                                                                                                                                           |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ASTM A 20/A 20M–93a Standard Specification for General Requirements for Steel Plates for Pressure Vessels.                                                | 171.7; 178.337–2;<br>179.102–4;<br>179.102–1;<br>179.102–17                                                                                                               |
| ASTM A 47–68 Malleable Iron Castings .....                                                                                                                | 179.200–15                                                                                                                                                                |
| ASTM A 240/A 240M–99b Standard Specification for Heat-Resisting Chromium and Chromium–Nickel Stainless Steel Plate, Sheet and Strip for Pressure Vessels. | 171.7; 178.57;<br>178.358–5;<br>179.100–7;<br>179.100–10;<br>179.102–1;<br>179.102–4;<br>179.102–17;<br>179.200–7;<br>179.201–5;<br>179.220–7;<br>179.300–7;<br>179.400–5 |
| ASTM A 242–81 High-Strength Low Alloy Structural Steel .....                                                                                              | 178.338–2                                                                                                                                                                 |
| ASTM A 262–93a Standard Practices for Detecting Susceptibility to Intergranular Attack in Austenitic Stainless Steels.                                    | 171.7; 179.100–7;<br>179.200–7;<br>179.201–4                                                                                                                              |
| ASTM A 285–78 Pressure Vessel Plates, Carbon Steel, Low- and Intermediate-Tensile Strength.                                                               | 179.300–7                                                                                                                                                                 |
| ASTM A 300–58 Steel Plates for Pressure Vessels for Service at Low Temperatures.                                                                          | 178.337–2                                                                                                                                                                 |
| ASTM A 302/A 302M–93 Standard Specification for Pressure Vessel Plates, Alloy Steel, Manganese–Molybdenum and Manganese–Molybdenum Nickel.                | 171.7; 179.100–7;<br>179.200–7;<br>179.220–7                                                                                                                              |
| ASTM A 333–67 Seamless and Welded Steel Pipe for Low-Temperature Service.                                                                                 | 178.45                                                                                                                                                                    |
| ASTM A 370–94 Standard Test Methods and Definitions for Mechanical Testing of Steel Products.                                                             | 171.7; 179.102–1;<br>179.102–4;<br>179.102–17                                                                                                                             |
| ASTM A 441–81 High-Strength Low-Alloy Structural Manganese Vanadium Steel.                                                                                | 178.338–2                                                                                                                                                                 |
| ASTM A 514–81 High-Yield-Strength, Quenched and Tempered Alloy Steel Plate, Suitable for Welding.                                                         | 178.338–2                                                                                                                                                                 |
| ASTM A 515/A 515–03M, Standard Specification for Pressure Vessel Plates, Carbon Steel, for Intermediate- and Higher-Temperature Service.                  | 171.7; 179.300–7                                                                                                                                                          |

## Title 49—Transportation

### 49 CFR (PARTS 100–185)—Continued

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued

#### 49 CFR

|                                                                                                                                                                                                  |                                                                                                                                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------|
| ASTM A 516/A 516M–90 Standard Specification for Pressure Vessel Plates, Carbon Steel, for Moderate and Lower-Temperature Service.                                                                | 171.7; 178.337–2;<br>179.100–7;<br>179.102–1;<br>179.102–2;<br>179.102–4;<br>179.102–17;<br>179.200–7;<br>179.220–7;<br>179.300–7 |
| ASTM A 537/A 537M–91 Standard Specification for Pressure Vessel Plates, Heat-Treated, Carbon-Manganese-Silicon Steel.                                                                            | 171.7; 179.100–7;<br>179.102–4;<br>179.102–17                                                                                     |
| ASTM A 572–82 High-Strength Low Alloy Columbium–Vanadium Steels of Structural Quality.                                                                                                           | 178.338–2                                                                                                                         |
| ASTM A 588–81 High-Strength Low-Alloy Structural Steel with 50 ksi Minimum Yield Point to 4 in. Thick.                                                                                           | 178.338–2                                                                                                                         |
| ASTM A 606–75 Steel Sheet and Strip, Hot-Rolled and Cold-Rolled, High Strength, Low Alloy, with Improved Atmospheric Corrosion Resistance (reapproved 1981).                                     | 178.338–2                                                                                                                         |
| ASTM A 607–98 Standard Specification for Steel, Sheet and Strip, High-Strength, Low-Alloy, Columbium or Vanadium, or Both, Hot-rolled and Cold-rolled.                                           | 171.7; 178.338–2                                                                                                                  |
| ASTM A 612–72a High-Strength Steel Plates for Pressure Vessels for Moderate and Lower Temperature Service.                                                                                       | 178.337–2                                                                                                                         |
| ASTM A 633–79a Normalized High-Strength Low Alloy Structural Steel.                                                                                                                              | 178.338–2                                                                                                                         |
| ASTM A 715–81 Steel Sheet and Strip, Hot-Rolled, High-Strength, Low-Alloy, with Improved Formability.                                                                                            | 178.338–2                                                                                                                         |
| ASTM A 1008/ASTM A 1008M–03, Standard Specification for Steel, Sheet, Cold-rolled, Carbon, Structural, High-Strength Low-Alloy, and High-Strength Low-Alloy with Improved Formability.           | 171.7; 178.338–2;<br>178.345–2                                                                                                    |
| ASTM A 1011/ASTM A 1011M–03a, Standard Specification for Steel, Sheet and Strip, Hot-rolled, Carbon, Structural, High-Strength Low-Alloy, and High-Strength Low-Alloy with Improved Formability. | 171.7; 178.338–2;<br>178.345–2                                                                                                    |
| ASTM B 162–93a Standard Specification for Nickel Plate, Sheet, and Strip.                                                                                                                        | 171.7; 173.249;<br>179.200–7                                                                                                      |
| ASTM B 209–93 Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate.                                                                                                            | 171.7; 179.100–7;<br>179.200–7;<br>179.220–7                                                                                      |
| ASTM B 221–76 Aluminum Alloy Extruded Bars, Rods, Shapes, and Tubes.                                                                                                                             | 178.46                                                                                                                            |
| ASTM B 557–84 Tension Testing Wrought and Cast Aluminum and Magnesium-Alloy Products.                                                                                                            | 171.7; 178.46                                                                                                                     |
| ASTM B 580–79 (Reapproved 2000) Standard Specification for Anodic Oxide Coatings on Aluminium.                                                                                                   | 171.7; 173.316;<br>173.318; 178.338–17                                                                                            |
| ASTM D 1238–90b Standard Test Method for Flow Rates of Thermoplastics for Extrusion Plastometer.                                                                                                 | 171.7; 173.225                                                                                                                    |
| ASTM D 1709–01, Standard Test Methods for Impact Resistance of Plastic Film by the Free-falling Dart Method.                                                                                     | 171.7; 173.197                                                                                                                    |
| ASTM D 1835–97, Standard Specification for Liquefied Petroleum (LP) Gases.                                                                                                                       | 171.7; 180.209                                                                                                                    |

## Material Approved for Incorporation by Reference

### 49 CFR (PARTS 100–185)—Continued

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued

##### 49 CFR

|                                                                                                                            |                                                                                                                                                                       |
|----------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| ASTM D 1838–64 Copper Strip Corrosion by Liquefied Petroleum (LP) Gases.                                                   | 173.315                                                                                                                                                               |
| ASTM D 1922–00a Standard Test Method for Propagation Tear Resistance of Plastic Film and Thin Sheeting by Pendulum Method. | 171.7; 173.197                                                                                                                                                        |
| ASTM D 4206–96 Standard Test Method for Sustained Burning of Liquid Mixtures Using the Small Scale Open-Cup Apparatus.     | 173.120                                                                                                                                                               |
| ASTM D 4359–90 Standard Test Method for Determining Whether a Material is a Liquid or a Solid.                             | 171.8                                                                                                                                                                 |
| ASTM E 8–99 Tension Testing of Metallic Materials .....                                                                    | 171.7; 178.36;<br>178.37; 178.38;<br>178.39; 178.44;<br>178.45; 178.50;<br>178.51; 178.53;<br>178.55; 178.56;<br>178.57; 178.58;<br>178.59; 178.60;<br>178.61; 178.68 |
| ASTM E 23–98 Standard Test Methods for Notched Bar Impact Testing of Metallic Materials.                                   | 171.7; 178.57                                                                                                                                                         |
| ASTM E 112–88 Standard Test Methods for Determining Average Grain Size.                                                    | 171.7; 178.44                                                                                                                                                         |
| ASTM E 112–96 Standard Test Methods for Determining Average Grain Size.                                                    | 171.7; 178.274; Part<br>178, Appendix A                                                                                                                               |
| ASTM E 114–95 Standard Practice for Ultrasonic Pulse–echo Straight–Beam Examination by the Contact Method, 1995.           | 171.7; 178.45                                                                                                                                                         |
| ASTM E 213–98 Standard Practice for Ultrasonic Examination of Metal Pipe and Tubing.                                       | 171.7; 178.45                                                                                                                                                         |

#### American Water Works Association (AWWA)

1010 Vermont Avenue NW., Suite 810, Washington, DC 20005

|                                                       |           |
|-------------------------------------------------------|-----------|
| AWWA Standard C207–55, Steel Pipe Flanges; 1955 ..... | 178.360–4 |
|-------------------------------------------------------|-----------|

#### American Welding Society (AWS)

550 N.W. Le Jeune Road, Miami, FL 33126

|                                                                                  |                          |
|----------------------------------------------------------------------------------|--------------------------|
| AWS Code B 3.0; Standard Qualification Procedure; 1972 (FRB 3.0–41 rev. May 73). | 178.356–2; 178.358–<br>2 |
| AWS Code D1.0; Code for Welding in Building Construction, (FR D1.0–66).          | 178.356–2; 178.358–<br>2 |

#### Association of American Railroads (AAR)

American Railroads Building, 50 F St. NW., Washington, DC 20001

## **Title 49—Transportation**

**49 CFR (PARTS 100–185)**—Continued

**RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF  
TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)**—Continued

### **49 CFR**

AAR Manual of Standards and Recommended Practices, Section C— 171.7; 173.31;  
Part III, Specification for Tank Cars, Specification M–1002, Decem- 174.63; 179.6;  
ber 2000. 179.7; 179.15;  
179.16; 179.20;  
179.22; 179.100–9;  
179.100–10;  
179.100–12;  
179.100–13;  
179.100–14;  
179.100–18;  
179.101–1;  
179.102–1;  
179.102–4;  
179.102–17;  
179.103–5;  
179.200–7;  
179.200–9;  
179.200–10;  
179.200–11;  
179.200–13;  
179.200–17;  
179.200–22;  
179.201–6;  
179.220–6;  
179.220–7;  
179.220–10;  
179.220–11;  
179.220–14;  
179.220–18;  
179.220–26;  
179.300–9;  
179.300–10;  
179.300–15;  
179.300–17;  
179.400–5;  
179.400–6;  
179.400–8;  
179.400–11;  
179.400–12;  
179.400–15;  
179.400–18;  
179.400–20;  
179.400–25;  
180.509; 180.513;  
180.515; 180.517

AAR Manual of Standards and Recommended Practices, Section 1, 174.55; 174.63  
Specially Equipped Freight Car and Intermodal Equipment, 1988.

AAR Specifications for Design, Fabrication and Construction of 179.16  
Freight Cars, Volume 1, 1988.

### **Canadian General Standards Board (CGSB)**

Place du Portage III, 6B1 11, Laurier Street, Gatineau, Quebec,  
Canada K1A 1G6

## Material Approved for Incorporation by Reference

### 49 CFR (PARTS 100–185)—Continued

### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued

#### 49 CFR

|                                                                                                                                                                                                                                                   |                                                                                                                                             |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------|
| National Standard of Canada (CAN/CGSB 43.147–2005), Construction, Modification, Qualification, Maintenance, and Selection and Use of Means of Containment for the Handling, Offering for Transport, or Transportation of Dangerous Goods by Rail. | 171.12                                                                                                                                      |
| <b>Chlorine Institute, Inc.</b>                                                                                                                                                                                                                   |                                                                                                                                             |
| 1300 Wilson Boulevard, Arlington, Virginia 22209                                                                                                                                                                                                  |                                                                                                                                             |
| Type 1–1/2 JQ 225, Dwg. H51970, Revision D, April 5, 1989; or Type 1–1/2 JQ 225, Dwg. H50155, Revision F, April 4, 1989.                                                                                                                          | 173.315                                                                                                                                     |
| Section 3, Pamphlet 57, Emergency Shut-off Systems for Bulk Tr., 4th Edition, October 2003.                                                                                                                                                       | 177.840                                                                                                                                     |
| Section 3, Pamphlet 57, Emergency Shut-off Systems for Bulk Transfer of Chlorine, Third Edition, October 1997.                                                                                                                                    | 177.840                                                                                                                                     |
| Section 3, Pamphlet 166, Angle Valve Guidelines for Chlorine Bulk Transportation, 1st Edition, October 2002.                                                                                                                                      | 178.337–9                                                                                                                                   |
| Type 1–1/2 JQ 225, Dwg. H50155, Revision H, November, 1996 .....                                                                                                                                                                                  | 173.315                                                                                                                                     |
| Type 1–1/2 JQ 225, Dwg. H51970, Revision F, November, 1996 .....                                                                                                                                                                                  | 173.315                                                                                                                                     |
| Standard Chlorine Angle Valve Assembly, Dwg. 104–8, July 1993                                                                                                                                                                                     | 178.337–9                                                                                                                                   |
| Excess Flow Valve with Removable Seat, Dwg. 101–7, July 1993                                                                                                                                                                                      | 178.337–8                                                                                                                                   |
| Excess Flow Valve with Removable Basket, Dwg. 106–6, July 1993                                                                                                                                                                                    | 178.337–8                                                                                                                                   |
| Standards for Housing and Manway Covers for Steel Cargo Tanks, Dwg. 137–1 and Dwg. 137–2, September 1, 1982.                                                                                                                                      | 178.337–10                                                                                                                                  |
| Chlorine Institute Emergency Kit “A” for 100–lb. and 150–lb. Chlorine Cylinders (with the exception of repair method using Device 8 for side leaks), Edition 10, June 2003.                                                                       | 171.7; 173.3                                                                                                                                |
| Chlorine Institute Emergency Kit “B” for Chlorine Ton Containers (with the exception of repair method using Device 9 for side leaks), Edition 9, June 2003.                                                                                       | 171.7; 173.3                                                                                                                                |
| <b>Compressed Gas Association, Inc. (CGA)</b>                                                                                                                                                                                                     |                                                                                                                                             |
| 4221 Walney Road, Fifth floor, Chantilly, VA 20151                                                                                                                                                                                                |                                                                                                                                             |
| CGA Pamphlet C–3 Standards for Welding on Thinned-Walled Steel Cylinders, 1994.                                                                                                                                                                   | 171.7; 178.47;<br>178.50; 178.51;<br>178.53; 178.55;<br>178.56; 178.57;<br>178.58; 178.59;<br>178.60; 178.61;<br>178.65; 178.68;<br>180.211 |
| CGA Pamphlet C–5 Cylinder Service Life—Seamless Steel High Pressure Cylinders, 1991.                                                                                                                                                              | 171.7; 173.302a                                                                                                                             |
| CGA Pamphlet C–5 Cylinder Service Life—Seamless Steel High Pressure Cylinders, 1991 (reaffirmed) 1995.                                                                                                                                            | 173.302a                                                                                                                                    |
| CGA Pamphlet C–6 Standards for Visual Inspection of Steel Compressed Gas Cylinders, 1993.                                                                                                                                                         | 171.7; 173.3;<br>173.198; 180.205;<br>180.209; 180.211;<br>180.411; 180.519                                                                 |
| CGA Pamphlet C–6.1 Standards for Visual Inspection of High Pressure Aluminum Compressed Gas Cylinders, Fourth edition, 2002.                                                                                                                      | 171.7; 180.205;<br>180.209                                                                                                                  |
| CGA Pamphlet C–6.2 Guidelines for Visual Inspection and Requalification of Fiber Reinforced High-pressure Cylinders, Third Edition, 1996.                                                                                                         | 171.7; 180.205                                                                                                                              |

## Title 49—Transportation

### 49 CFR (PARTS 100–185)—Continued

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued

##### 49 CFR

|                                                                                                                                                              |                                               |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------|
| CGA Pamphlet C–6.3 Guidelines for Visual Inspection and Requalification of Low Pressure Aluminum Compressed Gas Cylinders, 1991.                             | 171.7; 180.205;<br>180.209                    |
| CGA Pamphlet C–7 A Guide for the Preparation of Precautionary Markings for Compressed Gas Containers, Appendix A, issued 1992 (6th Edition).                 | 172.400a                                      |
| CGA Pamphlet C–7 Guide to Preparation of Precautionary Labeling and Marking, 2004 (8th Edition).                                                             | 172.400a                                      |
| CGA Pamphlet C–8 Standard for Requalification of DOT–3HT Cylinder Design, 1985.                                                                              | 171.7; 180.205;<br>180.209                    |
| CGA Pamphlet C–11 Recommended Practices for Inspection of Compressed Gas Cylinders at Time of Manufacture, Third Edition, 2001.                              | 171.7; 178.35                                 |
| CGA Pamphlet C–12 Qualification Procedure for Acetylene Cylinder Design, 1994.                                                                               | 171.7; 173.301;<br>173.303; 178.59;<br>178.60 |
| CGA Pamphlet C–13, Guidelines for Periodic Visual Inspection and Requalification of Acetylene Cylinders, 2000, Fourth edition.                               | 171.7; 173.303;<br>180.205; 180.209           |
| CGA Pamphlet C–14, Procedures for Fire Testing of DOT Cylinder Pressure Relief Device Systems, 1979.                                                         | 171.7; 173.301;<br>173.323                    |
| CGA Pamphlet G–2.2 Tentative Standard Method for Determining Minimum of 0.2% Water in Anhydrous Ammonia, 1985.                                               | 173.315                                       |
| CGA Pamphlet G–4.1 Cleaning Equipment for Oxygen Service, 1985                                                                                               | 178.338–15                                    |
| CGA Pamphlet P–20 Standard for Classification of Toxic Gas Mixtures, 1995.                                                                                   | 171.7; 173.115                                |
| CGA Pamphlet S–1.1 Pressure Relief Device Standards—Part 1, 12th Edition, 2005.                                                                              | 173.301, 173.304a,<br>178.75                  |
| CGA Pamphlet S–1.1 Pressure Relief Device Standards Part 1—Cylinders for Compressed Gases (with the exception of paragraph 9.1.1.1), Ninth Edition, 2001.    | 173.304a                                      |
| CGA Pamphlet S–1.1 Pressure Relief Device Standards Part 1—Cylinders for Compressed Gases (with the exception of paragraph 9.1.1.1), Eleventh Edition, 2003. | 171.7; 173.301;<br>178.75                     |
| CGA Pamphlet S–1.2 Safety Relief Device Standards Part 2—Cargo and Portable Tanks for Compressed Gases, 1980.                                                | 173.315; 173.318;<br>178.276; 178.277         |
| CGA Pamphlet S–7 Method for Selecting Pressure Relief Devices, 2005.                                                                                         | 173.301                                       |
| CGA Pamphlet S–7 Method for Selecting Pressure Relief Devices for Compressed Gas Mixtures in Cylinders, 1996.                                                | 171.7; 173.301                                |
| CGA Technical Bulletin TB–2 Guidelines for Inspection and Repair of MC–330 and MC–331 Cargo Tanks, 1980.                                                     | 180.407; 180.413                              |

### Department of Defense

|                                                                                                                          |              |
|--------------------------------------------------------------------------------------------------------------------------|--------------|
| 2461 Eisenhower Avenue, Alexandria, VA 22331                                                                             |              |
| DOD TB 700–2 NAVSEAINST 8020.8B; AFTO 11A–1–47; DLAR 8220.1: Explosives Hazard Classification Procedures, January 1998.  | 173.56       |
| Packaging of Hazardous Material, DLAD 4145.41/AR 700–143/AFJI 24–210/NAVSUPINST 4030.55B/MCO 4030.40B, January 14, 2000. | 171.7; 173.7 |

### Department of Energy (USDOE)

100 Independence Avenue, SW, Washington DC 20545. USDOE publications available from: Superintendent of Documents, Government Printing Office or The National Technical Information Service (NTIS)

## Material Approved for Incorporation by Reference

### 49 CFR (PARTS 100–185)—Continued

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued

##### 49 CFR

- USDOE, CAPE—1662, Revision 1, and Supp. 1, Civilian Application Program Engineering Drawings, April 6, 1988. 178.356–1; 178.356–2; 178.358–1; 178.358–2; 178.358–3; 178.358–4
- USDOE, Material and Equipment Specification No. SP–9 Rev. 1, and Supplement—Fire Resistant Phenolic Foam, March 28, 1968. 178.356–2; 178.358–2
- USDOE, ORO–651—Uranium Hexafluoride: A Manual of Good Handling Practices, Revision 6, 1991 ed. 171.7; 173.417
- USDOE KSS–471, November 30, 1986—Proposal for Modifications to U.S. Department of Transportation Specification 21PF–1 Fire and Shock Resistant Phenolic Foam—Insulated Metal Overpack. 178.358–1; 178.358–3

#### General Services Administration

- Specification Office, Rm. 6662, 7th and D St. SW., Washington, DC 20407
- Federal Specification RR–C–901D, Cylinders, Compressed Gas: Seamless, Shatterproof, High Pressure DOT 3AA Steel, and 3AL Aluminum, February 21, 2003. 171.7; 173.302; 173.336; 173.337

#### Institute of Makers of Explosives (IME)

- 1120 19th Street, NW, Suite 310, Washington, DC 20036–3605
- IME Safety Library Publication No. 22 (IME Standard 22), Recommendation for the Safe Transportation of Detonators in a Vehicle with Certain Other Explosive Materials, May 1993. 173.63; 177.835

#### International Atomic Energy Agency (IAEA)

- Wagramerstrasse 5, P.O. Box 100, A–1400, Vienna, Austria. Also available from: Bernan Associates, 4611–F Assembly Drive; Lanham, Maryland 20706–4391, USA; or Renouf Publishing Company, Ltd., 812 Proctor Avenue, Ogdensburg, New York 13669, USA
- IAEA No. TS–R–1, (ST–1, Revised) Regulations for the Safe Transport of Radioactive Material, 1996 Edition. 171.7; 171.22; 171.23; 171.26; 173.415; 173.416; 173.417; 173.473

#### International Civil Aviation Organization (ICAO)

- P.O. Box 400, Place de l'Aviation Internationale, 1000 Sherbrooke Street West, Montreal, Quebec, Canada H3A 2R2. ICAO Technical Instructions also available from INTEREG, International Regulations, Publishing and Distribution Organization, P.O. Box 60105, Chicago, IL 60660
- ICAO Technical Instructions for the Safe Transport of Dangerous Goods by Air, (ICAO Technical Instructions) 2007–2008 Edition. 171.8; 171.22; 171.23; 171.24; 172.202; 172.401; 172.512; 172.602; 173.320; 175.33; 178.3

#### International Electrotechnical Commission

- (IEC) 3, rue de Varembe[acute], P.O. Box 131, CH–1211, GENEVA 20, Switzerland
- IEC/PAS 62282–6–1:2006(E)—Fuel Cell Technologies—Part 6–1: Micro Fuel Cell Power Systems—Safety, First Edition, 2006–02, with Corrigendum 1, First Edition, 2007–04. 175.10

## Title 49—Transportation

### 49 CFR (PARTS 100–185)—Continued

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued 49 CFR

##### International Maritime Organization

4 Albert Embankment, London SE1 7SR, England Telephone: 0171–587 3210; FAX: 0171–587 3210; Telex: 23588. Purchase from: IMO Sales, New York Nautical Instrument and Service Corp., 140 W. Broadway, New York, NY 10013.

|                                                                                                                                          |                                                                                                                                               |
|------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|
| International Maritime Dangerous Goods Code (IMDG Code), 2006 Edition, Incorporating Amendment 33–06 (English Edition), Volumes 1 and 2. | 171.22; 171.23;<br>171.25; 172.202;<br>172.401; 172.502;<br>172.602; 173.21;<br>176.2; 176.5;<br>176.11; 176.27;<br>176.30; 178.3;<br>178.274 |
|------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|

|                                                                                                                    |                |
|--------------------------------------------------------------------------------------------------------------------|----------------|
| International Convention for the Safety of Life at Sea, (SOLAS) Amendments 2000, Chapter II–2/Regulation 19, 2001. | 176.63; 176.84 |
|--------------------------------------------------------------------------------------------------------------------|----------------|

##### International Organization for Standardization (ISO)

International Organization for Standardization (ISO), 1, ch. de la Voie-Creuse, Case postale 56, CH-1211 Geneva 20, Switzerland; Telephone +41 22 749 01 11; Fax +41 22 733 34 30; [http://www.iso.org/iso/iso\\_catalogue.htm](http://www.iso.org/iso/iso_catalogue.htm)

Also available from: American National Standards Institute (ANSI), 25 West 43rd Street, 4th Floor, New York, NY 10036; phone: 1 (212) 642–4900; fax: 1 (212) 398–0023; <http://webstore.ansi.org/ansidocstore/default.asp>

|                                                                                                                                                                        |                                         |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------|
| ISO TR 4826–1979(E), Sealed Radioactive Sources—Leak Test Methods.                                                                                                     | 173.469                                 |
| ISO 82–1974(E) Steel Tensile Testing .....                                                                                                                             | 178.270–3                               |
| ISO 535–1991(E) Paper and Board—Determination of Water Absorptiveness—Cobb Method.                                                                                     | 171.7; 178.516;<br>178.707; 178.708     |
| ISO 1496–1: 1990(E), Series 1 Freight Containers—Specification and Testing—Part 1, General Cargo Containers, Fifth Edition, August 15, 1990.                           | 171.7; 173.411                          |
| ISO 1496–3: Series 1 Freight Containers—Specification and Testing—Part 3, Tank Containers for Liquids, Gases, and Pressurized Dry Bulk, Fourth Edition, March 1, 1995. | 171.7; 178.274;<br>178.74; 178.75       |
| ISO 2431–84(E) Standard Cup Method .....                                                                                                                               | 173.121                                 |
| ISO 2592–1973(E) Petroleum products—Determination of flash and fire points—Cleveland open cup method.                                                                  | 171.7; 173.120                          |
| ISO 2919–1980(E), Sealed Radioactive Sources—Classification .....                                                                                                      | 173.469                                 |
| ISO 3036–1975(E), Board—Determination of Puncture Resistance .....                                                                                                     | 171.7; 178.708                          |
| ISO 3574–1986(E) Cold-reduced carbon steel sheet of commercial and drawing qualities.                                                                                  | 171.7; 178.503; Part<br>178, Appendix C |
| ISO 3807–2 Cylinders for Acetylene—Basic requirements—Part 2: Cylinders with Fusible Plugs, First edition, March 15, 2000.                                             | 171.7; 173.303;<br>178.71               |
| ISO 4126–1, Safety Valves, Part 1: General Requirements, First Edition, December 15, 1991.                                                                             | 171.7; 178.274                          |
| ISO 6406, Gas Cylinders—Seamless Steel Gas Cylinders—Periodic Inspection and Testing, Second edition, February 1, 2005.                                                | 171.7; 180.207                          |
| ISO 6892, Metallic Materials—Tensile Testing, First Edition, July 15, 1984.                                                                                            | 171.7; 178.274                          |
| ISO 7225, Gas Cylinders—Precautionary Labels, (E), July 2005 .....                                                                                                     | 178.71                                  |



## Material Approved for Incorporation by Reference

**49 CFR (PARTS 100–185)**—Continued

**RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF  
TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)**—Continued

**49 CFR**

|                                                                                                                                                                                                                                              |                                     |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------|
| ISO 7225, Gas Cylinders—Precautionary Labels, First Edition, August 1995.                                                                                                                                                                    | 171.7; 178.71                       |
| ISO 7866, Gas Cylinders—Refillable Seamless Aluminum Alloy Gas Cylinders—Design, Construction and Testing, First Edition, June 15, 1999.                                                                                                     | 171.7; 178.71                       |
| ISO 9809–1, Gas Cylinders—Refillable Seamless Steel Gas Cylinders—Design, Construction and Testing—Part 1: Quenched and Tempered Steel Cylinders with Tensile Strength less than 1 100 Mpa, First Edition, June 1, 1999.                     | 171.7; 178.71;<br>178.75            |
| ISO 9809–2, Gas Cylinders—Refillable Seamless Steel Gas Cylinders—Design, Construction and Testing—Part 2: Quenched and Tempered Steel Cylinders with Tensile Strength Greater than or Equal to 1 100 Mpa, First Edition, June 15, 2000.     | 171.7; 178.71;<br>178.75            |
| ISO 9809–3, Gas Cylinders—Refillable Seamless Steel Gas Cylinders—Design, Construction and Testing—Part 3: Normalized Steel Cylinders, First Edition, December 15, 2000.                                                                     | 171.7; 178.71;<br>178.75            |
| ISO 9978–3: 1992(E), Radiation Protection—Sealed Radioactive Sources—Leakage Test Methods, February 15, 1992, First Edition.                                                                                                                 | 171.7; 173.469                      |
| ISO 10297: Gas Cylinders—Refillable Gas Cylinder Valves—Specification and Type Testing, First edition, May 1, 1999.                                                                                                                          | 171.7; 173.301b;<br>178.71          |
| ISO 10461: Gas Cylinders—Seamless Aluminum–alloy Gas Cylinders—Periodic Inspection and Testing, Second edition, February 15, 2005.                                                                                                           | 171.7; 180.207                      |
| ISO 10462: Gas Cylinders—Transportable Cylinders for Dissolved Acetylene—Periodic Inspection and Maintenance, Second edition, February 15, 2005.                                                                                             | 171.7; 180.207                      |
| ISO 11114–1: Transportable Gas Cylinders—Compatibility of Cylinder and Valve Materials with Gas Contents—Part 1: Metallic Materials, First edition, October 15, 1997.                                                                        | 171.7; 173.301b;<br>178.71          |
| ISO 11114–2: Transportable Gas Cylinders—Compatibility of Cylinder and Valve Materials with Gas Contents—Part 2: Non–metallic Materials, First edition, December 15, 2000.                                                                   | 171.7; 173.301b;<br>178.71          |
| ISO 11117: Gas Cylinders—Valve Protection Caps and Valve Guards for Industrial and Medical Gas Cylinders—Design, Construction and Tests, First edition, August 1, 1998.                                                                      | 171.7; 173.301b                     |
| ISO 11118: Gas Cylinders—Non–refillable Metallic Gas Cylinders—Specification and Test Methods, First edition, October 1, 1999.                                                                                                               | 171.7; 178.71                       |
| ISO 11119–1: Gas Cylinders of Composite Construction—Specification and Test Methods—Part 1: Hoop Wrapped Composite Gas Cylinders, First edition, May 15, 2002.                                                                               | 171.7; 178.71                       |
| ISO 11119–2: Gas Cylinders of Composite Construction—Specification and Test Methods—Part 2: Fully Wrapped Fibre Reinforced Composite Gas Cylinders with Load–sharing Metal Liners, First edition, May 15, 2002.                              | 171.7; 178.71                       |
| ISO 11119–3: Gas Cylinders of Composite Construction—Specification and Test Methods—Part 3: Fully Wrapped Fibre Reinforced Composite Gas Cylinders with Non–load–sharing Metallic or Non–metallic Liners, First edition, September 15, 2002. | 171.7; 178.71                       |
| ISO 11120: Gas Cylinders—Refillable Seamless Steel Tubes of Water Capacity between 150 L and 3 000 L—Design, Construction and Testing, First edition, March 15, 1999.                                                                        | 171.7; 178.71;<br>178.75            |
| ISO 11621: Gas Cylinders—Procedures for Change of Gas Service, First edition, April 15, 1997.                                                                                                                                                | 171.7; 173.302;<br>173.336; 173.337 |

## Title 49—Transportation

### 49 CFR (PARTS 100–185)—Continued

#### RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)—Continued

##### 49 CFR

- ISO 11623: Transportable Gas Cylinders—Periodic Inspection and Testing of Composite Gas Cylinders, First edition, March 1, 2002. 171.7; 180.207
- National Board of Boiler and Pressure Vessel Inspectors**  
1055 Crupper Avenue, Columbus, OH 43229
- National Board Inspection Code, A Manual for Boiler and Pressure Vessel Inspectors, NB-23, 1992 Edition. 171.1; 180.413
- National Fire Protection Association**  
1 Batterymarch Park, Quincy, MA 02269–9101, Telephone: (800) 344–3555
- NFPA Pamphlet No. 58—Liquefied Petroleum Gas Code, 2001 ..... 171.7; 173.315
- National Motor Freight Traffic Association, Inc.**  
Agent, 1616 P Street NW., Washington, DC 20036
- National Motor Freight Classification NMF 100–I, 1982 ..... 177.841
- National Technical Information Service (NTIS), Department of Commerce**  
5285 Port Royal Rd., Springfield, VA 22161
- NSB Handbook H–28 (1957), 1957 Handbook of Screw–Thread Standards for Federal Services, Part II, December 1966 Ed. 171.1; 179.2; 178.45; 178.46
- Organization for Economic Cooperation and Development (OECD)**  
OECD Publications and Information Center, 2001 L Street, Suite 700, Washington, DC 20036
- OECD Guideline for Testing of Chemicals, No. 404, “Acute Dermal Irritation/Corrosion,” 1992. 171.7; 173.137
- Transport Canada**  
TDG Canadian Government Publishing Center, Supply and Services, Canada, Ottawa, Ontario, Canada K1A 0S9
- Transportation of Dangerous Goods (TDG) Regulations, August 2001 including Clear Language Amendments SOR/2001–286, Amendment 1 (SOR/2002–306) August 8, 2002; Amendment 2 (SOR/2003–273) July 24, 2003; Amendment 3 (SOR/2003–400) December 3, 2003; Amendment 4 (SOR/2005–216) July 13, 2005; and Amendment 5 (SOR/2005–279) September 21, 2005. 171.12; 171.22; 171.23; 172.401; 172.502; 172.519; 172.602; 173.31; 173.32; 173.33
- Truck Trailer Manufacturers Association**  
1020 Princess Street, Alexandria, VA 22314
- TTMA RP No. 61–98, Performance of Manhole and/or Fill Opening Assemblies on MC 306, DOT 406, Non–ASME MC 312, and non–ASME DOT 412 Cargo Tanks, June 1, 1998. 171.7; 180.405
- TTMA RP No. 81–97, Performance of Spring Loaded Pressure Relief Valves on MC 306, MC 307, MC 312, DOT 406, DOT 407, and DOT 412 Tanks, July 1, 1997 Edition. 171.7; 178.345–10; 178.346–3
- TTMA TB 107 Procedure for Testing In–Service, Unmarked, and/or Uncertified MC 306 and non–ASME MC 312 Type Cargo Tank Manhole Covers, June 1, 1998. 171.7; 180.405
- United Nations**  
United Nations Sales Section, New York, NY 10017
- UN Recommendations on the Transport of Dangerous Goods, Fourteenth revised edition, 2005, Volumes I and II. 171.8; 171.12; 172.202; 172.401; 172.502; 173.22; 173.24; 173.24b; 173.40; 173.192; 173.197; 173.302b; 173.304b; 178.75; 178.274; 178.801

## Material Approved for Incorporation by Reference

**49 CFR (PARTS 100–185)**—Continued

**RESEARCH AND SPECIAL PROGRAMS ADMINISTRATION, DEPARTMENT OF  
TRANSPORTATION (HAZARDOUS MATERIALS REGULATIONS)**—Continued

### **49 CFR**

|                                                                   |                   |
|-------------------------------------------------------------------|-------------------|
| UN Recommendations on the Transport of Dangerous Goods, Manual    | 172.102; 173.21;  |
| of Tests and Criteria, Fourth revised edition, 2003, and Addendum | 173.56; 173.57;   |
| 2, 2004.                                                          | 173.58; 173.115;  |
|                                                                   | 173.124; 173.125; |
|                                                                   | 173.127; 173.128; |
|                                                                   | 173.137; 173.185; |
|                                                                   | 173, Appendix H;  |
|                                                                   | 178.274           |

**United States Enrichment Corporation, Inc.**

6903 Rockledge Drive, Bethesda, Maryland 20817

|                                                                                       |                |
|---------------------------------------------------------------------------------------|----------------|
| USEC 651: Good Handling Practices for Uranium Hexafluoride, Revision B, January 1999. | 171.7; 173.417 |
|---------------------------------------------------------------------------------------|----------------|



## **Table of CFR Titles and Chapters**

(Revised as of October 1, 2008)

### **Title 1—General Provisions**

- I Administrative Committee of the Federal Register (Parts 1—49)
- II Office of the Federal Register (Parts 50—299)
- IV Miscellaneous Agencies (Parts 400—500)

### **Title 2—Grants and Agreements**

#### **SUBTITLE A—OFFICE OF MANAGEMENT AND BUDGET GUIDANCE FOR GRANTS AND AGREEMENTS**

- I Office of Management and Budget Governmentwide Guidance for Grants and Agreements (Parts 100—199)
- II Office of Management and Budget Circulars and Guidance (200—299)

#### **SUBTITLE B—FEDERAL AGENCY REGULATIONS FOR GRANTS AND AGREEMENTS**

- III Department of Health and Human Services (Parts 300—399)
- VI Department of State (Parts 600—699)
- VIII Department of Veterans Affairs (Parts 800—899)
- IX Department of Energy (Parts 900—999)
- XI Department of Defense (Parts 1100—1199)
- XII Department of Transportation (Parts 1200—1299)
- XIV Department of the Interior (Parts 1400—1499)
- XV Environmental Protection Agency (Parts 1500—1599)
- XVIII National Aeronautics and Space Administration (Parts 1880—1899)
- XXII Corporation for National and Community Service (Parts 2200—2299)
- XXIII Social Security Administration (Parts 2300—2399)
- XXIV Housing and Urban Development (Parts 2400—2499)
- XXV National Science Foundation (Parts 2500—2599)
- XXVI National Archives and Records Administration (Parts 2600—2699)
- XXVII Small Business Administration (Parts 2700—2799)
- XXVIII Department of Justice (Parts 2800—2899)
- XXXI Institute of Museum and Library Services (Parts 3100—3199)
- XXXII National Endowment for the Arts (Parts 3200—3299)
- XXXIII National Endowment for the Humanities (Parts 3300—3399)
- XXXV Export-Import Bank of the United States (Parts 3500—3599)
- XXXVII Peace Corps (Parts 3700—3799)

Chap.

### **Title 3—The President**

- I Executive Office of the President (Parts 100—199)

### **Title 4—Accounts**

- I Government Accountability Office (Parts 1—99)

### **Title 5—Administrative Personnel**

- I Office of Personnel Management (Parts 1—1199)
- II Merit Systems Protection Board (Parts 1200—1299)
- III Office of Management and Budget (Parts 1300—1399)
- V The International Organizations Employees Loyalty Board (Parts 1500—1599)
- VI Federal Retirement Thrift Investment Board (Parts 1600—1699)
- VIII Office of Special Counsel (Parts 1800—1899)
- IX Appalachian Regional Commission (Parts 1900—1999)
- XI Armed Forces Retirement Home (Parts 2100—2199)
- XIV Federal Labor Relations Authority, General Counsel of the Federal Labor Relations Authority and Federal Service Impasses Panel (Parts 2400—2499)
- XV Office of Administration, Executive Office of the President (Parts 2500—2599)
- XVI Office of Government Ethics (Parts 2600—2699)
- XXI Department of the Treasury (Parts 3100—3199)
- XXII Federal Deposit Insurance Corporation (Parts 3200—3299)
- XXIII Department of Energy (Parts 3300—3399)
- XXIV Federal Energy Regulatory Commission (Parts 3400—3499)
- XXV Department of the Interior (Parts 3500—3599)
- XXVI Department of Defense (Parts 3600—3699)
- XXVIII Department of Justice (Parts 3800—3899)
- XXIX Federal Communications Commission (Parts 3900—3999)
- XXX Farm Credit System Insurance Corporation (Parts 4000—4099)
- XXXI Farm Credit Administration (Parts 4100—4199)
- XXXIII Overseas Private Investment Corporation (Parts 4300—4399)
- XXXV Office of Personnel Management (Parts 4500—4599)
- XL Interstate Commerce Commission (Parts 5000—5099)
- XL I Commodity Futures Trading Commission (Parts 5100—5199)
- XLII Department of Labor (Parts 5200—5299)
- XLIII National Science Foundation (Parts 5300—5399)
- XLV Department of Health and Human Services (Parts 5500—5599)
- XLVI Postal Rate Commission (Parts 5600—5699)
- XLVII Federal Trade Commission (Parts 5700—5799)
- XLVIII Nuclear Regulatory Commission (Parts 5800—5899)
- L Department of Transportation (Parts 6000—6099)
- LII Export-Import Bank of the United States (Parts 6200—6299)
- LIII Department of Education (Parts 6300—6399)

## **Title 5—Administrative Personnel—Continued**

|        |                                                                                                                                                       |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------|
| Chap.  |                                                                                                                                                       |
| LIV    | Environmental Protection Agency (Parts 6400—6499)                                                                                                     |
| LV     | National Endowment for the Arts (Parts 6500—6599)                                                                                                     |
| LVI    | National Endowment for the Humanities (Parts 6600—6699)                                                                                               |
| LVII   | General Services Administration (Parts 6700—6799)                                                                                                     |
| LVIII  | Board of Governors of the Federal Reserve System (Parts 6800—6899)                                                                                    |
| LIX    | National Aeronautics and Space Administration (Parts 6900—6999)                                                                                       |
| LX     | United States Postal Service (Parts 7000—7099)                                                                                                        |
| LXI    | National Labor Relations Board (Parts 7100—7199)                                                                                                      |
| LXII   | Equal Employment Opportunity Commission (Parts 7200—7299)                                                                                             |
| LXIII  | Inter-American Foundation (Parts 7300—7399)                                                                                                           |
| LXIV   | Merit Systems Protection Board (Parts 7400—7499)                                                                                                      |
| LXV    | Department of Housing and Urban Development (Parts 7500—7599)                                                                                         |
| LXVI   | National Archives and Records Administration (Parts 7600—7699)                                                                                        |
| LXVII  | Institute of Museum and Library Services (Parts 7700—7799)                                                                                            |
| LXVIII | Commission on Civil Rights (Parts 7800—7899)                                                                                                          |
| LXIX   | Tennessee Valley Authority (Parts 7900—7999)                                                                                                          |
| LXXI   | Consumer Product Safety Commission (Parts 8100—8199)                                                                                                  |
| LXXIII | Department of Agriculture (Parts 8300—8399)                                                                                                           |
| LXXIV  | Federal Mine Safety and Health Review Commission (Parts 8400—8499)                                                                                    |
| LXXVI  | Federal Retirement Thrift Investment Board (Parts 8600—8699)                                                                                          |
| LXXVII | Office of Management and Budget (Parts 8700—8799)                                                                                                     |
| XCVII  | Department of Homeland Security Human Resources Management System (Department of Homeland Security—Office of Personnel Management) (Parts 9700—9799)  |
| XCIX   | Department of Defense Human Resources Management and Labor Relations Systems (Department of Defense—Office of Personnel Management) (Parts 9900—9999) |

## **Title 6—Domestic Security**

|   |                                                                       |
|---|-----------------------------------------------------------------------|
| I | Department of Homeland Security, Office of the Secretary (Parts 0—99) |
| X | Privacy and Civil Liberties Oversight Board (Parts 1000—1099)         |

## **Title 7—Agriculture**

|    |                                                                                                                        |
|----|------------------------------------------------------------------------------------------------------------------------|
|    | SUBTITLE A—OFFICE OF THE SECRETARY OF AGRICULTURE (PARTS 0—26)                                                         |
|    | SUBTITLE B—REGULATIONS OF THE DEPARTMENT OF AGRICULTURE                                                                |
| I  | Agricultural Marketing Service (Standards, Inspections, Marketing Practices), Department of Agriculture (Parts 27—209) |
| II | Food and Nutrition Service, Department of Agriculture (Parts 210—299)                                                  |

## Title 7—Agriculture—Continued

| Chap.  |                                                                                                                                                          |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------|
| III    | Animal and Plant Health Inspection Service, Department of Agriculture (Parts 300—399)                                                                    |
| IV     | Federal Crop Insurance Corporation, Department of Agriculture (Parts 400—499)                                                                            |
| V      | Agricultural Research Service, Department of Agriculture (Parts 500—599)                                                                                 |
| VI     | Natural Resources Conservation Service, Department of Agriculture (Parts 600—699)                                                                        |
| VII    | Farm Service Agency, Department of Agriculture (Parts 700—799)                                                                                           |
| VIII   | Grain Inspection, Packers and Stockyards Administration (Federal Grain Inspection Service), Department of Agriculture (Parts 800—899)                    |
| IX     | Agricultural Marketing Service (Marketing Agreements and Orders; Fruits, Vegetables, Nuts), Department of Agriculture (Parts 900—999)                    |
| X      | Agricultural Marketing Service (Marketing Agreements and Orders; Milk), Department of Agriculture (Parts 1000—1199)                                      |
| XI     | Agricultural Marketing Service (Marketing Agreements and Orders; Miscellaneous Commodities), Department of Agriculture (Parts 1200—1299)                 |
| XIV    | Commodity Credit Corporation, Department of Agriculture (Parts 1400—1499)                                                                                |
| XV     | Foreign Agricultural Service, Department of Agriculture (Parts 1500—1599)                                                                                |
| XVI    | Rural Telephone Bank, Department of Agriculture (Parts 1600—1699)                                                                                        |
| XVII   | Rural Utilities Service, Department of Agriculture (Parts 1700—1799)                                                                                     |
| XVIII  | Rural Housing Service, Rural Business-Cooperative Service, Rural Utilities Service, and Farm Service Agency, Department of Agriculture (Parts 1800—2099) |
| XX     | Local Television Loan Guarantee Board (Parts 2200—2299)                                                                                                  |
| XXVI   | Office of Inspector General, Department of Agriculture (Parts 2600—2699)                                                                                 |
| XXVII  | Office of Information Resources Management, Department of Agriculture (Parts 2700—2799)                                                                  |
| XXVIII | Office of Operations, Department of Agriculture (Parts 2800—2899)                                                                                        |
| XXIX   | Office of Energy Policy and New Uses, Department of Agriculture (Parts 2900—2999)                                                                        |
| XXX    | Office of the Chief Financial Officer, Department of Agriculture (Parts 3000—3099)                                                                       |
| XXXI   | Office of Environmental Quality, Department of Agriculture (Parts 3100—3199)                                                                             |
| XXXII  | Office of Procurement and Property Management, Department of Agriculture (Parts 3200—3299)                                                               |
| XXXIII | Office of Transportation, Department of Agriculture (Parts 3300—3399)                                                                                    |
| XXXIV  | Cooperative State Research, Education, and Extension Service, Department of Agriculture (Parts 3400—3499)                                                |



| <b>Title 7—Agriculture—Continued</b> |                                                                                                             |
|--------------------------------------|-------------------------------------------------------------------------------------------------------------|
| Chap.                                |                                                                                                             |
| XXXV                                 | Rural Housing Service, Department of Agriculture (Parts 3500—3599)                                          |
| XXXVI                                | National Agricultural Statistics Service, Department of Agriculture (Parts 3600—3699)                       |
| XXXVII                               | Economic Research Service, Department of Agriculture (Parts 3700—3799)                                      |
| XXXVIII                              | World Agricultural Outlook Board, Department of Agriculture (Parts 3800—3899)                               |
| XLI                                  | [Reserved]                                                                                                  |
| XLII                                 | Rural Business-Cooperative Service and Rural Utilities Service, Department of Agriculture (Parts 4200—4299) |

## **Title 8—Aliens and Nationality**

|   |                                                                                  |
|---|----------------------------------------------------------------------------------|
| I | Department of Homeland Security (Immigration and Naturalization) (Parts 1—499)   |
| V | Executive Office for Immigration Review, Department of Justice (Parts 1000—1399) |

## **Title 9—Animals and Animal Products**

|     |                                                                                                                                      |
|-----|--------------------------------------------------------------------------------------------------------------------------------------|
| I   | Animal and Plant Health Inspection Service, Department of Agriculture (Parts 1—199)                                                  |
| II  | Grain Inspection, Packers and Stockyards Administration (Packers and Stockyards Programs), Department of Agriculture (Parts 200—299) |
| III | Food Safety and Inspection Service, Department of Agriculture (Parts 300—599)                                                        |

## **Title 10—Energy**

|       |                                                                               |
|-------|-------------------------------------------------------------------------------|
| I     | Nuclear Regulatory Commission (Parts 0—199)                                   |
| II    | Department of Energy (Parts 200—699)                                          |
| III   | Department of Energy (Parts 700—999)                                          |
| X     | Department of Energy (General Provisions) (Parts 1000—1099)                   |
| XIII  | Nuclear Waste Technical Review Board (Parts 1303—1399)                        |
| XVII  | Defense Nuclear Facilities Safety Board (Parts 1700—1799)                     |
| XVIII | Northeast Interstate Low-Level Radioactive Waste Commission (Parts 1800—1899) |

## **Title 11—Federal Elections**

|   |                                            |
|---|--------------------------------------------|
| I | Federal Election Commission (Parts 1—9099) |
|---|--------------------------------------------|

## **Title 12—Banks and Banking**

|    |                                                                       |
|----|-----------------------------------------------------------------------|
| I  | Comptroller of the Currency, Department of the Treasury (Parts 1—199) |
| II | Federal Reserve System (Parts 200—299)                                |

Chap. **Title 12—Banks and Banking—Continued**

- III Federal Deposit Insurance Corporation (Parts 300—399)
- IV Export-Import Bank of the United States (Parts 400—499)
- V Office of Thrift Supervision, Department of the Treasury (Parts 500—599)
- VI Farm Credit Administration (Parts 600—699)
- VII National Credit Union Administration (Parts 700—799)
- VIII Federal Financing Bank (Parts 800—899)
- IX Federal Housing Finance Board (Parts 900—999)
- XI Federal Financial Institutions Examination Council (Parts 1100—1199)
- XII Federal Housing Finance Agency (Parts 1200—1299)
- XIV Farm Credit System Insurance Corporation (Parts 1400—1499)
- XV Department of the Treasury (Parts 1500—1599)
- XVII Office of Federal Housing Enterprise Oversight, Department of Housing and Urban Development (Parts 1700—1799)
- XVIII Community Development Financial Institutions Fund, Department of the Treasury (Parts 1800—1899)

**Title 13—Business Credit and Assistance**

- I Small Business Administration (Parts 1—199)
- III Economic Development Administration, Department of Commerce (Parts 300—399)
- IV Emergency Steel Guarantee Loan Board, Department of Commerce (Parts 400—499)
- V Emergency Oil and Gas Guaranteed Loan Board, Department of Commerce (Parts 500—599)

**Title 14—Aeronautics and Space**

- I Federal Aviation Administration, Department of Transportation (Parts 1—199)
- II Office of the Secretary, Department of Transportation (Aviation Proceedings) (Parts 200—399)
- III Commercial Space Transportation, Federal Aviation Administration, Department of Transportation (Parts 400—499)
- V National Aeronautics and Space Administration (Parts 1200—1299)
- VI Air Transportation System Stabilization (Parts 1300—1399)

**Title 15—Commerce and Foreign Trade**

- SUBTITLE A—OFFICE OF THE SECRETARY OF COMMERCE (PARTS 0—29)
- SUBTITLE B—REGULATIONS RELATING TO COMMERCE AND FOREIGN TRADE
- I Bureau of the Census, Department of Commerce (Parts 30—199)

## **Title 15—Commerce and Foreign Trade—Continued**

Chap.

- II National Institute of Standards and Technology, Department of Commerce (Parts 200—299)
- III International Trade Administration, Department of Commerce (Parts 300—399)
- IV Foreign-Trade Zones Board, Department of Commerce (Parts 400—499)
- VII Bureau of Industry and Security, Department of Commerce (Parts 700—799)
- VIII Bureau of Economic Analysis, Department of Commerce (Parts 800—899)
- IX National Oceanic and Atmospheric Administration, Department of Commerce (Parts 900—999)
- XI Technology Administration, Department of Commerce (Parts 1100—1199)
- XIII East-West Foreign Trade Board (Parts 1300—1399)
- XIV Minority Business Development Agency (Parts 1400—1499)  
SUBTITLE C—REGULATIONS RELATING TO FOREIGN TRADE AGREEMENTS
- XX Office of the United States Trade Representative (Parts 2000—2099)  
SUBTITLE D—REGULATIONS RELATING TO TELECOMMUNICATIONS AND INFORMATION
- XXIII National Telecommunications and Information Administration, Department of Commerce (Parts 2300—2399)

## **Title 16—Commercial Practices**

- I Federal Trade Commission (Parts 0—999)
- II Consumer Product Safety Commission (Parts 1000—1799)

## **Title 17—Commodity and Securities Exchanges**

- I Commodity Futures Trading Commission (Parts 1—199)
- II Securities and Exchange Commission (Parts 200—399)
- IV Department of the Treasury (Parts 400—499)

## **Title 18—Conservation of Power and Water Resources**

- I Federal Energy Regulatory Commission, Department of Energy (Parts 1—399)
- III Delaware River Basin Commission (Parts 400—499)
- VI Water Resources Council (Parts 700—799)
- VIII Susquehanna River Basin Commission (Parts 800—899)
- XIII Tennessee Valley Authority (Parts 1300—1399)

## **Title 19—Customs Duties**

- I Bureau of Customs and Border Protection, Department of Homeland Security; Department of the Treasury (Parts 0—199)

|       |                                                                                                |
|-------|------------------------------------------------------------------------------------------------|
|       | <b>Title 19—Customs Duties—Continued</b>                                                       |
| Chap. |                                                                                                |
| II    | United States International Trade Commission (Parts 200—299)                                   |
| III   | International Trade Administration, Department of Commerce (Parts 300—399)                     |
| IV    | Bureau of Immigration and Customs Enforcement, Department of Homeland Security (Parts 400—599) |

### **Title 20—Employees' Benefits**

|      |                                                                                                                        |
|------|------------------------------------------------------------------------------------------------------------------------|
| I    | Office of Workers' Compensation Programs, Department of Labor (Parts 1—199)                                            |
| II   | Railroad Retirement Board (Parts 200—399)                                                                              |
| III  | Social Security Administration (Parts 400—499)                                                                         |
| IV   | Employees Compensation Appeals Board, Department of Labor (Parts 500—599)                                              |
| V    | Employment and Training Administration, Department of Labor (Parts 600—699)                                            |
| VI   | Employment Standards Administration, Department of Labor (Parts 700—799)                                               |
| VII  | Benefits Review Board, Department of Labor (Parts 800—899)                                                             |
| VIII | Joint Board for the Enrollment of Actuaries (Parts 900—999)                                                            |
| IX   | Office of the Assistant Secretary for Veterans' Employment and Training Service, Department of Labor (Parts 1000—1099) |

### **Title 21—Food and Drugs**

|     |                                                                                      |
|-----|--------------------------------------------------------------------------------------|
| I   | Food and Drug Administration, Department of Health and Human Services (Parts 1—1299) |
| II  | Drug Enforcement Administration, Department of Justice (Parts 1300—1399)             |
| III | Office of National Drug Control Policy (Parts 1400—1499)                             |

### **Title 22—Foreign Relations**

|      |                                                                                                                |
|------|----------------------------------------------------------------------------------------------------------------|
| I    | Department of State (Parts 1—199)                                                                              |
| II   | Agency for International Development (Parts 200—299)                                                           |
| III  | Peace Corps (Parts 300—399)                                                                                    |
| IV   | International Joint Commission, United States and Canada (Parts 400—499)                                       |
| V    | Broadcasting Board of Governors (Parts 500—599)                                                                |
| VII  | Overseas Private Investment Corporation (Parts 700—799)                                                        |
| IX   | Foreign Service Grievance Board (Parts 900—999)                                                                |
| X    | Inter-American Foundation (Parts 1000—1099)                                                                    |
| XI   | International Boundary and Water Commission, United States and Mexico, United States Section (Parts 1100—1199) |
| XII  | United States International Development Cooperation Agency (Parts 1200—1299)                                   |
| XIII | Millennium Challenge Corporation (Parts 1300—1399)                                                             |

Chap. **Title 22—Foreign Relations—Continued**

- XIV Foreign Service Labor Relations Board; Federal Labor Relations Authority; General Counsel of the Federal Labor Relations Authority; and the Foreign Service Impasse Disputes Panel (Parts 1400—1499)
- XV African Development Foundation (Parts 1500—1599)
- XVI Japan-United States Friendship Commission (Parts 1600—1699)
- XVII United States Institute of Peace (Parts 1700—1799)

**Title 23—Highways**

- I Federal Highway Administration, Department of Transportation (Parts 1—999)
- II National Highway Traffic Safety Administration and Federal Highway Administration, Department of Transportation (Parts 1200—1299)
- III National Highway Traffic Safety Administration, Department of Transportation (Parts 1300—1399)

**Title 24—Housing and Urban Development**

SUBTITLE A—OFFICE OF THE SECRETARY, DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (PARTS 0—99)

SUBTITLE B—REGULATIONS RELATING TO HOUSING AND URBAN DEVELOPMENT

- I Office of Assistant Secretary for Equal Opportunity, Department of Housing and Urban Development (Parts 100—199)
- II Office of Assistant Secretary for Housing-Federal Housing Commissioner, Department of Housing and Urban Development (Parts 200—299)
- III Government National Mortgage Association, Department of Housing and Urban Development (Parts 300—399)
- IV Office of Housing and Office of Multifamily Housing Assistance Restructuring, Department of Housing and Urban Development (Parts 400—499)
- V Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 500—599)
- VI Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 600—699) [Reserved]
- VII Office of the Secretary, Department of Housing and Urban Development (Housing Assistance Programs and Public and Indian Housing Programs) (Parts 700—799)
- VIII Office of the Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Section 8 Housing Assistance Programs, Section 202 Direct Loan Program, Section 202 Supportive Housing for the Elderly Program and Section 811 Supportive Housing for Persons With Disabilities Program) (Parts 800—899)
- IX Office of Assistant Secretary for Public and Indian Housing, Department of Housing and Urban Development (Parts 900—1699)

## **Title 24—Housing and Urban Development—Continued**

Chap.

- X Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Interstate Land Sales Registration Program) (Parts 1700—1799)
- XII Office of Inspector General, Department of Housing and Urban Development (Parts 2000—2099)
- XX Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Parts 3200—3899)
- XXV Neighborhood Reinvestment Corporation (Parts 4100—4199)

## **Title 25—Indians**

- I Bureau of Indian Affairs, Department of the Interior (Parts 1—299)
- II Indian Arts and Crafts Board, Department of the Interior (Parts 300—399)
- III National Indian Gaming Commission, Department of the Interior (Parts 500—599)
- IV Office of Navajo and Hopi Indian Relocation (Parts 700—799)
- V Bureau of Indian Affairs, Department of the Interior, and Indian Health Service, Department of Health and Human Services (Part 900)
- VI Office of the Assistant Secretary-Indian Affairs, Department of the Interior (Parts 1000—1199)
- VII Office of the Special Trustee for American Indians, Department of the Interior (Parts 1200—1299)

## **Title 26—Internal Revenue**

- I Internal Revenue Service, Department of the Treasury (Parts 1—899)

## **Title 27—Alcohol, Tobacco Products and Firearms**

- I Alcohol and Tobacco Tax and Trade Bureau, Department of the Treasury (Parts 1—399)
- II Bureau of Alcohol, Tobacco, Firearms, and Explosives, Department of Justice (Parts 400—699)

## **Title 28—Judicial Administration**

- I Department of Justice (Parts 0—299)
- III Federal Prison Industries, Inc., Department of Justice (Parts 300—399)
- V Bureau of Prisons, Department of Justice (Parts 500—599)
- VI Offices of Independent Counsel, Department of Justice (Parts 600—699)
- VII Office of Independent Counsel (Parts 700—799)

Chap. **Title 28—Judicial Administration—Continued**

- VIII Court Services and Offender Supervision Agency for the District of Columbia (Parts 800—899)
- IX National Crime Prevention and Privacy Compact Council (Parts 900—999)
- XI Department of Justice and Department of State (Parts 1100—1199)

**Title 29—Labor**

- SUBTITLE A—OFFICE OF THE SECRETARY OF LABOR (PARTS 0—99)
- SUBTITLE B—REGULATIONS RELATING TO LABOR
- I National Labor Relations Board (Parts 100—199)
- II Office of Labor-Management Standards, Department of Labor (Parts 200—299)
- III National Railroad Adjustment Board (Parts 300—399)
- IV Office of Labor-Management Standards, Department of Labor (Parts 400—499)
- V Wage and Hour Division, Department of Labor (Parts 500—899)
- IX Construction Industry Collective Bargaining Commission (Parts 900—999)
- X National Mediation Board (Parts 1200—1299)
- XII Federal Mediation and Conciliation Service (Parts 1400—1499)
- XIV Equal Employment Opportunity Commission (Parts 1600—1699)
- XVII Occupational Safety and Health Administration, Department of Labor (Parts 1900—1999)
- XX Occupational Safety and Health Review Commission (Parts 2200—2499)
- XXV Employee Benefits Security Administration, Department of Labor (Parts 2500—2599)
- XXVII Federal Mine Safety and Health Review Commission (Parts 2700—2799)
- XL Pension Benefit Guaranty Corporation (Parts 4000—4999)

**Title 30—Mineral Resources**

- I Mine Safety and Health Administration, Department of Labor (Parts 1—199)
- II Minerals Management Service, Department of the Interior (Parts 200—299)
- III Board of Surface Mining and Reclamation Appeals, Department of the Interior (Parts 300—399)
- IV Geological Survey, Department of the Interior (Parts 400—499)
- VII Office of Surface Mining Reclamation and Enforcement, Department of the Interior (Parts 700—999)

**Title 31—Money and Finance: Treasury**

- SUBTITLE A—OFFICE OF THE SECRETARY OF THE TREASURY (PARTS 0—50)

## **Title 31—Money and Finance: Treasury—Continued**

Chap.

### **SUBTITLE B—REGULATIONS RELATING TO MONEY AND FINANCE**

- I Monetary Offices, Department of the Treasury (Parts 51—199)
- II Fiscal Service, Department of the Treasury (Parts 200—399)
- IV Secret Service, Department of the Treasury (Parts 400—499)
- V Office of Foreign Assets Control, Department of the Treasury (Parts 500—599)
- VI Bureau of Engraving and Printing, Department of the Treasury (Parts 600—699)
- VII Federal Law Enforcement Training Center, Department of the Treasury (Parts 700—799)
- VIII Office of International Investment, Department of the Treasury (Parts 800—899)
- IX Federal Claims Collection Standards (Department of the Treasury—Department of Justice) (Parts 900—999)

## **Title 32—National Defense**

### **SUBTITLE A—DEPARTMENT OF DEFENSE**

- I Office of the Secretary of Defense (Parts 1—399)
- V Department of the Army (Parts 400—699)
- VI Department of the Navy (Parts 700—799)
- VII Department of the Air Force (Parts 800—1099)

### **SUBTITLE B—OTHER REGULATIONS RELATING TO NATIONAL DEFENSE**

- XII Defense Logistics Agency (Parts 1200—1299)
- XVI Selective Service System (Parts 1600—1699)
- XVII Office of the Director of National Intelligence (Parts 1700—1799)
- XXVIII National Counterintelligence Center (Parts 1800—1899)
- XIX Central Intelligence Agency (Parts 1900—1999)
- XX Information Security Oversight Office, National Archives and Records Administration (Parts 2000—2099)
- XXI National Security Council (Parts 2100—2199)
- XXIV Office of Science and Technology Policy (Parts 2400—2499)
- XXVII Office for Micronesia Status Negotiations (Parts 2700—2799)
- XXVIII Office of the Vice President of the United States (Parts 2800—2899)

## **Title 33—Navigation and Navigable Waters**

- I Coast Guard, Department of Homeland Security (Parts 1—199)
- II Corps of Engineers, Department of the Army (Parts 200—399)
- IV Saint Lawrence Seaway Development Corporation, Department of Transportation (Parts 400—499)

## **Title 34—Education**

### **SUBTITLE A—OFFICE OF THE SECRETARY, DEPARTMENT OF EDUCATION (PARTS 1—99)**



Chap.

## **Title 34—Education—Continued**

### **SUBTITLE B—REGULATIONS OF THE OFFICES OF THE DEPARTMENT OF EDUCATION**

- I Office for Civil Rights, Department of Education (Parts 100—199)
- II Office of Elementary and Secondary Education, Department of Education (Parts 200—299)
- III Office of Special Education and Rehabilitative Services, Department of Education (Parts 300—399)
- IV Office of Vocational and Adult Education, Department of Education (Parts 400—499)
- V Office of Bilingual Education and Minority Languages Affairs, Department of Education (Parts 500—599)
- VI Office of Postsecondary Education, Department of Education (Parts 600—699)
- VII Office of Educational Research and Improvement, Department of Education [Reserved]

- XI National Institute for Literacy (Parts 1100—1199)

### **SUBTITLE C—REGULATIONS RELATING TO EDUCATION**

- XII National Council on Disability (Parts 1200—1299)

## **Title 35 [Reserved]**

## **Title 36—Parks, Forests, and Public Property**

- I National Park Service, Department of the Interior (Parts 1—199)
- II Forest Service, Department of Agriculture (Parts 200—299)
- III Corps of Engineers, Department of the Army (Parts 300—399)
- IV American Battle Monuments Commission (Parts 400—499)
- V Smithsonian Institution (Parts 500—599)
- VI [Reserved]
- VII Library of Congress (Parts 700—799)
- VIII Advisory Council on Historic Preservation (Parts 800—899)
- IX Pennsylvania Avenue Development Corporation (Parts 900—999)
- X Presidio Trust (Parts 1000—1099)
- XI Architectural and Transportation Barriers Compliance Board (Parts 1100—1199)
- XII National Archives and Records Administration (Parts 1200—1299)
- XV Oklahoma City National Memorial Trust (Parts 1500—1599)
- XVI Morris K. Udall Scholarship and Excellence in National Environmental Policy Foundation (Parts 1600—1699)

## **Title 37—Patents, Trademarks, and Copyrights**

- I United States Patent and Trademark Office, Department of Commerce (Parts 1—199)
- II Copyright Office, Library of Congress (Parts 200—299)
- III Copyright Royalty Board, Library of Congress (Parts 301—399)

**Title 37—Patents, Trademarks, and Copyrights—Continued**  
Chap.

- IV Assistant Secretary for Technology Policy, Department of Commerce (Parts 400—499)
- V Under Secretary for Technology, Department of Commerce (Parts 500—599)

**Title 38—Pensions, Bonuses, and Veterans' Relief**

- I Department of Veterans Affairs (Parts 0—99)

**Title 39—Postal Service**

- I United States Postal Service (Parts 1—999)
- III Postal Regulatory Commission (Parts 3000—3099)

**Title 40—Protection of Environment**

- I Environmental Protection Agency (Parts 1—1099)
- IV Environmental Protection Agency and Department of Justice (Parts 1400—1499)
- V Council on Environmental Quality (Parts 1500—1599)
- VI Chemical Safety and Hazard Investigation Board (Parts 1600—1699)
- VII Environmental Protection Agency and Department of Defense; Uniform National Discharge Standards for Vessels of the Armed Forces (Parts 1700—1799)

**Title 41—Public Contracts and Property Management**

SUBTITLE B—OTHER PROVISIONS RELATING TO PUBLIC CONTRACTS

- 50 Public Contracts, Department of Labor (Parts 50-1—50-999)
- 51 Committee for Purchase From People Who Are Blind or Severely Disabled (Parts 51-1—51-99)
- 60 Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor (Parts 60-1—60-999)
- 61 Office of the Assistant Secretary for Veterans' Employment and Training Service, Department of Labor (Parts 61-1—61-999)

Chapters 62—100 [Reserved]

SUBTITLE C—FEDERAL PROPERTY MANAGEMENT REGULATIONS SYSTEM

- 101 Federal Property Management Regulations (Parts 101-1—101-99)
- 102 Federal Management Regulation (Parts 102-1—102-299)
- Chapters 103—104 [Reserved]
- 105 General Services Administration (Parts 105-1—105-999)
- 109 Department of Energy Property Management Regulations (Parts 109-1—109-99)
- 114 Department of the Interior (Parts 114-1—114-99)
- 115 Environmental Protection Agency (Parts 115-1—115-99)
- 128 Department of Justice (Parts 128-1—128-99)

## **Title 41—Public Contracts and Property Management—Continued**

Chap.

Chapters 129—200 [Reserved]

SUBTITLE D—OTHER PROVISIONS RELATING TO PROPERTY MANAGEMENT [RESERVED]

SUBTITLE E—FEDERAL INFORMATION RESOURCES MANAGEMENT REGULATIONS SYSTEM [RESERVED]

SUBTITLE F—FEDERAL TRAVEL REGULATION SYSTEM

- 300 General (Parts 300–1—300–99)
- 301 Temporary Duty (TDY) Travel Allowances (Parts 301–1—301–99)
- 302 Relocation Allowances (Parts 302–1—302–99)
- 303 Payment of Expenses Connected with the Death of Certain Employees (Part 303–1—303–99)
- 304 Payment of Travel Expenses from a Non-Federal Source (Parts 304–1—304–99)

## **Title 42—Public Health**

- I Public Health Service, Department of Health and Human Services (Parts 1—199)
- IV Centers for Medicare & Medicaid Services, Department of Health and Human Services (Parts 400—499)
- V Office of Inspector General-Health Care, Department of Health and Human Services (Parts 1000—1999)

## **Title 43—Public Lands: Interior**

SUBTITLE A—OFFICE OF THE SECRETARY OF THE INTERIOR (PARTS 1—199)

SUBTITLE B—REGULATIONS RELATING TO PUBLIC LANDS

- I Bureau of Reclamation, Department of the Interior (Parts 200—499)
- II Bureau of Land Management, Department of the Interior (Parts 1000—9999)
- III Utah Reclamation Mitigation and Conservation Commission (Parts 10000—10010)

## **Title 44—Emergency Management and Assistance**

- I Federal Emergency Management Agency, Department of Homeland Security (Parts 0—399)
- IV Department of Commerce and Department of Transportation (Parts 400—499)

## **Title 45—Public Welfare**

SUBTITLE A—DEPARTMENT OF HEALTH AND HUMAN SERVICES (PARTS 1—199)

SUBTITLE B—REGULATIONS RELATING TO PUBLIC WELFARE

Chap. **Title 45—Public Welfare—Continued**

- II Office of Family Assistance (Assistance Programs), Administration for Children and Families, Department of Health and Human Services (Parts 200—299)
- III Office of Child Support Enforcement (Child Support Enforcement Program), Administration for Children and Families, Department of Health and Human Services (Parts 300—399)
- IV Office of Refugee Resettlement, Administration for Children and Families, Department of Health and Human Services (Parts 400—499)
- V Foreign Claims Settlement Commission of the United States, Department of Justice (Parts 500—599)
- VI National Science Foundation (Parts 600—699)
- VII Commission on Civil Rights (Parts 700—799)
- VIII Office of Personnel Management (Parts 800—899) [Reserved]
- X Office of Community Services, Administration for Children and Families, Department of Health and Human Services (Parts 1000—1099)
- XI National Foundation on the Arts and the Humanities (Parts 1100—1199)
- XII Corporation for National and Community Service (Parts 1200—1299)
- XIII Office of Human Development Services, Department of Health and Human Services (Parts 1300—1399)
- XVI Legal Services Corporation (Parts 1600—1699)
- XVII National Commission on Libraries and Information Science (Parts 1700—1799)
- XVIII Harry S. Truman Scholarship Foundation (Parts 1800—1899)
- XXI Commission on Fine Arts (Parts 2100—2199)
- XXIII Arctic Research Commission (Part 2301)
- XXIV James Madison Memorial Fellowship Foundation (Parts 2400—2499)
- XXV Corporation for National and Community Service (Parts 2500—2599)

**Title 46—Shipping**

- I Coast Guard, Department of Homeland Security (Parts 1—199)
- II Maritime Administration, Department of Transportation (Parts 200—399)
- III Coast Guard (Great Lakes Pilotage), Department of Homeland Security (Parts 400—499)
- IV Federal Maritime Commission (Parts 500—599)

**Title 47—Telecommunication**

- I Federal Communications Commission (Parts 0—199)
- II Office of Science and Technology Policy and National Security Council (Parts 200—299)

Chap.

## **Title 47—Telecommunication—Continued**

- III National Telecommunications and Information Administration,  
Department of Commerce (Parts 300—399)

## **Title 48—Federal Acquisition Regulations System**

- 1 Federal Acquisition Regulation (Parts 1—99)
- 2 Defense Acquisition Regulations System, Department of Defense  
(Parts 200—299)
- 3 Department of Health and Human Services (Parts 300—399)
- 4 Department of Agriculture (Parts 400—499)
- 5 General Services Administration (Parts 500—599)
- 6 Department of State (Parts 600—699)
- 7 Agency for International Development (Parts 700—799)
- 8 Department of Veterans Affairs (Parts 800—899)
- 9 Department of Energy (Parts 900—999)
- 10 Department of the Treasury (Parts 1000—1099)
- 12 Department of Transportation (Parts 1200—1299)
- 13 Department of Commerce (Parts 1300—1399)
- 14 Department of the Interior (Parts 1400—1499)
- 15 Environmental Protection Agency (Parts 1500—1599)
- 16 Office of Personnel Management, Federal Employees Health  
Benefits Acquisition Regulation (Parts 1600—1699)
- 17 Office of Personnel Management (Parts 1700—1799)
- 18 National Aeronautics and Space Administration (Parts 1800—  
1899)
- 19 Broadcasting Board of Governors (Parts 1900—1999)
- 20 Nuclear Regulatory Commission (Parts 2000—2099)
- 21 Office of Personnel Management, Federal Employees Group Life  
Insurance Federal Acquisition Regulation (Parts 2100—2199)
- 23 Social Security Administration (Parts 2300—2399)
- 24 Department of Housing and Urban Development (Parts 2400—  
2499)
- 25 National Science Foundation (Parts 2500—2599)
- 28 Department of Justice (Parts 2800—2899)
- 29 Department of Labor (Parts 2900—2999)
- 30 Department of Homeland Security, Homeland Security Acquisi-  
tion Regulation (HSAR) (Parts 3000—3099)
- 34 Department of Education Acquisition Regulation (Parts 3400—  
3499)
- 51 Department of the Army Acquisition Regulations (Parts 5100—  
5199)
- 52 Department of the Navy Acquisition Regulations (Parts 5200—  
5299)
- 53 Department of the Air Force Federal Acquisition Regulation  
Supplement [Reserved]
- 54 Defense Logistics Agency, Department of Defense (Parts 5400—  
5499)

## **Title 48—Federal Acquisition Regulations System—Continued**

Chap.

- 57 African Development Foundation (Parts 5700—5799)
- 61 General Services Administration Board of Contract Appeals (Parts 6100—6199)
- 63 Department of Transportation Board of Contract Appeals (Parts 6300—6399)
- 99 Cost Accounting Standards Board, Office of Federal Procurement Policy, Office of Management and Budget (Parts 9900—9999)

## **Title 49—Transportation**

SUBTITLE A—OFFICE OF THE SECRETARY OF TRANSPORTATION (PARTS 1—99)

SUBTITLE B—OTHER REGULATIONS RELATING TO TRANSPORTATION

- I Pipeline and Hazardous Materials Safety Administration, Department of Transportation (Parts 100—199)
- II Federal Railroad Administration, Department of Transportation (Parts 200—299)
- III Federal Motor Carrier Safety Administration, Department of Transportation (Parts 300—399)
- IV Coast Guard, Department of Homeland Security (Parts 400—499)
- V National Highway Traffic Safety Administration, Department of Transportation (Parts 500—599)
- VI Federal Transit Administration, Department of Transportation (Parts 600—699)
- VII National Railroad Passenger Corporation (AMTRAK) (Parts 700—799)
- VIII National Transportation Safety Board (Parts 800—999)
- X Surface Transportation Board, Department of Transportation (Parts 1000—1399)
- XI Research and Innovative Technology Administration, Department of Transportation [Reserved]
- XII Transportation Security Administration, Department of Homeland Security (Parts 1500—1699)

## **Title 50—Wildlife and Fisheries**

- I United States Fish and Wildlife Service, Department of the Interior (Parts 1—199)
- II National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce (Parts 200—299)
- III International Fishing and Related Activities (Parts 300—399)
- IV Joint Regulations (United States Fish and Wildlife Service, Department of the Interior and National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce); Endangered Species Committee Regulations (Parts 400—499)
- V Marine Mammal Commission (Parts 500—599)

Chap. **Title 50—Wildlife and Fisheries—Continued**

- VI Fishery Conservation and Management, National Oceanic and  
Atmospheric Administration, Department of Commerce (Parts  
600—699)

**CFR Index and Finding Aids**

Subject/Agency Index

List of Agency Prepared Indexes

Parallel Tables of Statutory Authorities and Rules

List of CFR Titles, Chapters, Subchapters, and Parts

Alphabetical List of Agencies Appearing in the CFR





## Alphabetical List of Agencies Appearing in the CFR

(Revised as of October 1, 2008)

| Agency                                                       | CFR Title, Subtitle or Chapter |
|--------------------------------------------------------------|--------------------------------|
| Administrative Committee of the Federal Register             | 1, I                           |
| Advanced Research Projects Agency                            | 32, I                          |
| Advisory Council on Historic Preservation                    | 36, VIII                       |
| African Development Foundation                               | 22, XV                         |
| Federal Acquisition Regulation                               | 48, 57                         |
| Agency for International Development                         | 22, II                         |
| Federal Acquisition Regulation                               | 48, 7                          |
| Agricultural Marketing Service                               | 7, I, IX, X, XI                |
| Agricultural Research Service                                | 7, V                           |
| Agriculture Department                                       | 5, LXXXIII                     |
| Agricultural Marketing Service                               | 7, I, IX, X, XI                |
| Agricultural Research Service                                | 7, V                           |
| Animal and Plant Health Inspection Service                   | 7, III; 9, I                   |
| Chief Financial Officer, Office of                           | 7, XXX                         |
| Commodity Credit Corporation                                 | 7, XIV                         |
| Cooperative State Research, Education, and Extension Service | 7, XXXIV                       |
| Economic Research Service                                    | 7, XXXVII                      |
| Energy, Office of                                            | 2, IX; 7, XXIX                 |
| Environmental Quality, Office of                             | 7, XXXI                        |
| Farm Service Agency                                          | 7, VII, XVIII                  |
| Federal Acquisition Regulation                               | 48, 4                          |
| Federal Crop Insurance Corporation                           | 7, IV                          |
| Food and Nutrition Service                                   | 7, II                          |
| Food Safety and Inspection Service                           | 9, III                         |
| Foreign Agricultural Service                                 | 7, XV                          |
| Forest Service                                               | 36, II                         |
| Grain Inspection, Packers and Stockyards Administration      | 7, VIII; 9, II                 |
| Information Resources Management, Office of                  | 7, XXVII                       |
| Inspector General, Office of                                 | 7, XXVI                        |
| National Agricultural Library                                | 7, XLI                         |
| National Agricultural Statistics Service                     | 7, XXXVI                       |
| Natural Resources Conservation Service                       | 7, VI                          |
| Operations, Office of                                        | 7, XXVIII                      |
| Procurement and Property Management, Office of               | 7, XXXII                       |
| Rural Business-Cooperative Service                           | 7, XVIII, XLII                 |
| Rural Development Administration                             | 7, XLII                        |
| Rural Housing Service                                        | 7, XVIII, XXXV                 |
| Rural Telephone Bank                                         | 7, XVI                         |
| Rural Utilities Service                                      | 7, XVII, XVIII, XLII           |
| Secretary of Agriculture, Office of                          | 7, Subtitle A                  |
| Transportation, Office of                                    | 7, XXXIII                      |
| World Agricultural Outlook Board                             | 7, XXXVIII                     |
| Air Force Department                                         | 32, VII                        |
| Federal Acquisition Regulation Supplement                    | 48, 53                         |
| Air Transportation Stabilization Board                       | 14, VI                         |
| Alcohol and Tobacco Tax and Trade Bureau                     | 27, I                          |
| Alcohol, Tobacco, Firearms, and Explosives, Bureau of        | 27, II                         |
| AMTRAK                                                       | 49, VII                        |
| American Battle Monuments Commission                         | 36, IV                         |
| American Indians, Office of the Special Trustee              | 25, VII                        |
| Animal and Plant Health Inspection Service                   | 7, III; 9, I                   |
| Appalachian Regional Commission                              | 5, IX                          |

| Agency                                                                      | CFR Title, Subtitle or Chapter   |
|-----------------------------------------------------------------------------|----------------------------------|
| Architectural and Transportation Barriers Compliance Board                  | 36, XI                           |
| Arctic Research Commission                                                  | 45, XXIII                        |
| Armed Forces Retirement Home                                                | 5, XI                            |
| Army Department                                                             | 32, V                            |
| Engineers, Corps of                                                         | 33, II; 36, III                  |
| Federal Acquisition Regulation                                              | 48, 51                           |
| Benefits Review Board                                                       | 20, VII                          |
| Bilingual Education and Minority Languages Affairs, Office of               | 34, V                            |
| Blind or Severely Disabled, Committee for Purchase From People Who Are      | 41, 51                           |
| Broadcasting Board of Governors                                             | 22, V                            |
| Federal Acquisition Regulation                                              | 48, 19                           |
| Census Bureau                                                               | 15, I                            |
| Centers for Medicare & Medicaid Services                                    | 42, IV                           |
| Central Intelligence Agency                                                 | 32, XIX                          |
| Chief Financial Officer, Office of                                          | 7, XXX                           |
| Child Support Enforcement, Office of                                        | 45, III                          |
| Children and Families, Administration for                                   | 45, II, III, IV, X               |
| Civil Rights, Commission on                                                 | 5, LXVIII; 45, VII               |
| Civil Rights, Office for                                                    | 34, I                            |
| Coast Guard                                                                 | 33, I; 46, I; 49, IV             |
| Coast Guard (Great Lakes Pilotage)                                          | 46, III                          |
| Commerce Department                                                         | 44, IV                           |
| Census Bureau                                                               | 15, I                            |
| Economic Affairs, Under Secretary                                           | 37, V                            |
| Economic Analysis, Bureau of                                                | 15, VIII                         |
| Economic Development Administration                                         | 13, III                          |
| Emergency Management and Assistance                                         | 44, IV                           |
| Federal Acquisition Regulation                                              | 48, 13                           |
| Fishery Conservation and Management                                         | 50, VI                           |
| Foreign-Trade Zones Board                                                   | 15, IV                           |
| Industry and Security, Bureau of                                            | 15, VII                          |
| International Trade Administration                                          | 15, III; 19, III                 |
| National Institute of Standards and Technology                              | 15, II                           |
| National Marine Fisheries Service                                           | 50, II, IV, VI                   |
| National Oceanic and Atmospheric Administration                             | 15, IX; 50, II, III, IV, VI      |
| National Telecommunications and Information Administration                  | 15, XXIII; 47, III               |
| National Weather Service                                                    | 15, IX                           |
| Patent and Trademark Office, United States                                  | 37, I                            |
| Productivity, Technology and Innovation, Assistant Secretary for            | 37, IV                           |
| Secretary of Commerce, Office of                                            | 15, Subtitle A                   |
| Technology, Under Secretary for                                             | 37, V                            |
| Technology Administration                                                   | 15, XI                           |
| Technology Policy, Assistant Secretary for                                  | 37, IV                           |
| Commercial Space Transportation                                             | 14, III                          |
| Commodity Credit Corporation                                                | 7, XIV                           |
| Commodity Futures Trading Commission                                        | 5, XLI; 17, I                    |
| Community Planning and Development, Office of Assistant Secretary for       | 24, V, VI                        |
| Community Services, Office of                                               | 45, X                            |
| Comptroller of the Currency                                                 | 12, I                            |
| Construction Industry Collective Bargaining Commission                      | 29, IX                           |
| Consumer Product Safety Commission                                          | 5, LXXI; 16, II                  |
| Cooperative State Research, Education, and Extension Service                | 7, XXXIV                         |
| Copyright Office                                                            | 37, II                           |
| Copyright Royalty Board                                                     | 37, III                          |
| Corporation for National and Community Service                              | 2, XXII; 45, XII, XXV            |
| Cost Accounting Standards Board                                             | 48, 99                           |
| Council on Environmental Quality                                            | 40, V                            |
| Court Services and Offender Supervision Agency for the District of Columbia | 28, VIII                         |
| Customs and Border Protection Bureau                                        | 19, I                            |
| Defense Contract Audit Agency                                               | 32, I                            |
| Defense Department                                                          | 5, XXVI; 32, Subtitle A; 40, VII |

| Agency                                                                       | CFR Title, Subtitle or Chapter |
|------------------------------------------------------------------------------|--------------------------------|
| Advanced Research Projects Agency                                            | 32, I                          |
| Air Force Department                                                         | 32, VII                        |
| Army Department                                                              | 32, V; 33, II; 36, III, 48, 51 |
| Defense Acquisition Regulations System                                       | 48, 2                          |
| Defense Intelligence Agency                                                  | 32, I                          |
| Defense Logistics Agency                                                     | 32, I, XII; 48, 54             |
| Engineers, Corps of                                                          | 33, II; 36, III                |
| National Imagery and Mapping Agency                                          | 32, I                          |
| Navy Department                                                              | 32, VI; 48, 52                 |
| Secretary of Defense, Office of                                              | 2, XI; 32, I                   |
| Defense Contract Audit Agency                                                | 32, I                          |
| Defense Intelligence Agency                                                  | 32, I                          |
| Defense Logistics Agency                                                     | 32, XII; 48, 54                |
| Defense Nuclear Facilities Safety Board                                      | 10, XVII                       |
| Delaware River Basin Commission                                              | 18, III                        |
| District of Columbia, Court Services and Offender Supervision Agency for the | 28, VIII                       |
| Drug Enforcement Administration                                              | 21, II                         |
| East-West Foreign Trade Board                                                | 15, XIII                       |
| Economic Affairs, Under Secretary                                            | 37, V                          |
| Economic Analysis, Bureau of                                                 | 15, VIII                       |
| Economic Development Administration                                          | 13, III                        |
| Economic Research Service                                                    | 7, XXXVII                      |
| Education, Department of                                                     | 5, LIII                        |
| Bilingual Education and Minority Languages Affairs, Office of                | 34, V                          |
| Civil Rights, Office for                                                     | 34, I                          |
| Educational Research and Improvement, Office of                              | 34, VII                        |
| Elementary and Secondary Education, Office of                                | 34, II                         |
| Federal Acquisition Regulation                                               | 48, 34                         |
| Postsecondary Education, Office of                                           | 34, VI                         |
| Secretary of Education, Office of                                            | 34, Subtitle A                 |
| Special Education and Rehabilitative Services, Office of                     | 34, III                        |
| Vocational and Adult Education, Office of                                    | 34, IV                         |
| Educational Research and Improvement, Office of                              | 34, VII                        |
| Elementary and Secondary Education, Office of                                | 34, II                         |
| Emergency Oil and Gas Guaranteed Loan Board                                  | 13, V                          |
| Emergency Steel Guarantee Loan Board                                         | 13, IV                         |
| Employee Benefits Security Administration                                    | 29, XXV                        |
| Employees' Compensation Appeals Board                                        | 20, IV                         |
| Employees Loyalty Board                                                      | 5, V                           |
| Employment and Training Administration                                       | 20, V                          |
| Employment Standards Administration                                          | 20, VI                         |
| Endangered Species Committee                                                 | 50, IV                         |
| Energy, Department of                                                        | 5, XXIII; 10, II, III, X       |
| Federal Acquisition Regulation                                               | 48, 9                          |
| Federal Energy Regulatory Commission                                         | 5, XXIV; 18, I                 |
| Property Management Regulations                                              | 41, 109                        |
| Energy, Office of                                                            | 7, XXIX                        |
| Engineers, Corps of                                                          | 33, II; 36, III                |
| Engraving and Printing, Bureau of                                            | 31, VI                         |
| Environmental Protection Agency                                              | 2, XV; 5, LIV; 40, I, IV, VII  |
| Federal Acquisition Regulation                                               | 48, 15                         |
| Property Management Regulations                                              | 41, 115                        |
| Environmental Quality, Office of                                             | 7, XXXI                        |
| Equal Employment Opportunity Commission                                      | 5, LXII; 29, XIV               |
| Equal Opportunity, Office of Assistant Secretary for                         | 24, I                          |
| Executive Office of the President                                            | 3, I                           |
| Administration, Office of                                                    | 5, XV                          |
| Environmental Quality, Council on                                            | 40, V                          |
| Management and Budget, Office of                                             | 5, III, LXXVII; 14, VI; 48, 99 |
| National Drug Control Policy, Office of                                      | 21, III                        |
| National Security Council                                                    | 32, XXI; 47, 2                 |
| Presidential Documents                                                       | 3                              |

| Agency                                                                                          | CFR Title, Subtitle or Chapter |
|-------------------------------------------------------------------------------------------------|--------------------------------|
| Science and Technology Policy, Office of                                                        | 32, XXIV; 47, II               |
| Trade Representative, Office of the United States                                               | 15, XX                         |
| Export-Import Bank of the United States                                                         | 2, XXXV; 5, LII; 12, IV        |
| Family Assistance, Office of                                                                    | 45, II                         |
| Farm Credit Administration                                                                      | 5, XXXI; 12, VI                |
| Farm Credit System Insurance Corporation                                                        | 5, XXX; 12, XIV                |
| Farm Service Agency                                                                             | 7, VII, XVIII                  |
| Federal Acquisition Regulation                                                                  | 48, I                          |
| Federal Aviation Administration                                                                 | 14, I                          |
| Commercial Space Transportation                                                                 | 14, III                        |
| Federal Claims Collection Standards                                                             | 31, IX                         |
| Federal Communications Commission                                                               | 5, XXIX; 47, I                 |
| Federal Contract Compliance Programs, Office of                                                 | 41, 60                         |
| Federal Crop Insurance Corporation                                                              | 7, IV                          |
| Federal Deposit Insurance Corporation                                                           | 5, XXII; 12, III               |
| Federal Election Commission                                                                     | 11, I                          |
| Federal Emergency Management Agency                                                             | 44, I                          |
| Federal Employees Group Life Insurance Federal Acquisition Regulation                           | 48, 21                         |
| Federal Employees Health Benefits Acquisition Regulation                                        | 48, 16                         |
| Federal Energy Regulatory Commission                                                            | 5, XXIV; 18, I                 |
| Federal Financial Institutions Examination Council                                              | 12, XI                         |
| Federal Financing Bank                                                                          | 12, VIII                       |
| Federal Highway Administration                                                                  | 23, I, II                      |
| Federal Home Loan Mortgage Corporation                                                          | 1, IV                          |
| Federal Housing Enterprise Oversight Office                                                     | 12, XVII                       |
| Federal Housing Finance Agency                                                                  | 12, XII                        |
| Federal Housing Finance Board                                                                   | 12, IX                         |
| Federal Labor Relations Authority, and General Counsel of the Federal Labor Relations Authority | 5, XIV; 22, XIV                |
| Federal Law Enforcement Training Center                                                         | 31, VII                        |
| Federal Management Regulation                                                                   | 41, 102                        |
| Federal Maritime Commission                                                                     | 46, IV                         |
| Federal Mediation and Conciliation Service                                                      | 29, XII                        |
| Federal Mine Safety and Health Review Commission                                                | 5, LXXIV; 29, XXVII            |
| Federal Motor Carrier Safety Administration                                                     | 49, III                        |
| Federal Prison Industries, Inc.                                                                 | 28, III                        |
| Federal Procurement Policy Office                                                               | 48, 99                         |
| Federal Property Management Regulations                                                         | 41, 101                        |
| Federal Railroad Administration                                                                 | 49, II                         |
| Federal Register, Administrative Committee of                                                   | 1, I                           |
| Federal Register, Office of                                                                     | 1, II                          |
| Federal Reserve System                                                                          | 12, II                         |
| Board of Governors                                                                              | 5, LVIII                       |
| Federal Retirement Thrift Investment Board                                                      | 5, VI, LXXVI                   |
| Federal Service Impasses Panel                                                                  | 5, XIV                         |
| Federal Trade Commission                                                                        | 5, XLVII; 16, I                |
| Federal Transit Administration                                                                  | 49, VI                         |
| Federal Travel Regulation System                                                                | 41, Subtitle F                 |
| Fine Arts, Commission on                                                                        | 45, XXI                        |
| Fiscal Service                                                                                  | 31, II                         |
| Fish and Wildlife Service, United States                                                        | 50, I, IV                      |
| Fishery Conservation and Management                                                             | 50, VI                         |
| Food and Drug Administration                                                                    | 21, I                          |
| Food and Nutrition Service                                                                      | 7, II                          |
| Food Safety and Inspection Service                                                              | 9, III                         |
| Foreign Agricultural Service                                                                    | 7, XV                          |
| Foreign Assets Control, Office of                                                               | 31, V                          |
| Foreign Claims Settlement Commission of the United States                                       | 45, V                          |
| Foreign Service Grievance Board                                                                 | 22, IX                         |
| Foreign Service Impasse Disputes Panel                                                          | 22, XIV                        |
| Foreign Service Labor Relations Board                                                           | 22, XIV                        |
| Foreign-Trade Zones Board                                                                       | 15, IV                         |
| Forest Service                                                                                  | 36, II                         |
| General Services Administration                                                                 | 5, LVII; 41, 105               |
| Contract Appeals, Board of                                                                      | 48, 61                         |
| Federal Acquisition Regulation                                                                  | 48, 5                          |

| Agency                                                                            | CFR Title, Subtitle or Chapter  |
|-----------------------------------------------------------------------------------|---------------------------------|
| Federal Management Regulation                                                     | 41, 102                         |
| Federal Property Management Regulations                                           | 41, 101                         |
| Federal Travel Regulation System                                                  | 41, Subtitle F                  |
| General                                                                           | 41, 300                         |
| Payment From a Non-Federal Source for Travel Expenses                             | 41, 304                         |
| Payment of Expenses Connected With the Death of Certain Employees                 | 41, 303                         |
| Relocation Allowances                                                             | 41, 302                         |
| Temporary Duty (TDY) Travel Allowances                                            | 41, 301                         |
| Geological Survey                                                                 | 30, IV                          |
| Government Accountability Office                                                  | 4, I                            |
| Government Ethics, Office of                                                      | 5, XVI                          |
| Government National Mortgage Association                                          | 24, III                         |
| Grain Inspection, Packers and Stockyards Administration                           | 7, VIII; 9, II                  |
| Harry S. Truman Scholarship Foundation                                            | 45, XVIII                       |
| Health and Human Services, Department of                                          | 2, III; 5, XLV; 45, Subtitle A, |
| Centers for Medicare & Medicaid Services                                          | 42, IV                          |
| Child Support Enforcement, Office of                                              | 45, III                         |
| Children and Families, Administration for                                         | 45, II, III, IV, X              |
| Community Services, Office of                                                     | 45, X                           |
| Family Assistance, Office of                                                      | 45, II                          |
| Federal Acquisition Regulation                                                    | 48, 3                           |
| Food and Drug Administration                                                      | 21, I                           |
| Human Development Services, Office of                                             | 45, XIII                        |
| Indian Health Service                                                             | 25, V                           |
| Inspector General (Health Care), Office of                                        | 42, V                           |
| Public Health Service                                                             | 42, I                           |
| Refugee Resettlement, Office of                                                   | 45, IV                          |
| Homeland Security, Department of                                                  | 6, I                            |
| Coast Guard                                                                       | 33, I; 46, I; 49, IV            |
| Coast Guard (Great Lakes Pilotage)                                                | 46, III                         |
| Customs and Border Protection Bureau                                              | 19, I                           |
| Federal Emergency Management Agency                                               | 44, I                           |
| Immigration and Customs Enforcement Bureau                                        | 19, IV                          |
| Immigration and Naturalization                                                    | 8, I                            |
| Transportation Security Administration                                            | 49, XII                         |
| Housing and Urban Development, Department of                                      | 2, XXIV; 5, LXV; 24, Subtitle B |
| Community Planning and Development, Office of Assistant Secretary for             | 24, V, VI                       |
| Equal Opportunity, Office of Assistant Secretary for                              | 24, I                           |
| Federal Acquisition Regulation                                                    | 48, 24                          |
| Federal Housing Enterprise Oversight, Office of                                   | 12, XVII                        |
| Government National Mortgage Association                                          | 24, III                         |
| Housing—Federal Housing Commissioner, Office of Assistant Secretary for           | 24, II, VIII, X, XX             |
| Housing, Office of, and Multifamily Housing Assistance Restructuring, Office of   | 24, IV                          |
| Inspector General, Office of                                                      | 24, XII                         |
| Public and Indian Housing, Office of Assistant Secretary for Secretary, Office of | 24, IX                          |
| Housing—Federal Housing Commissioner, Office of Assistant Secretary for           | 24, Subtitle A, VII             |
| Housing, Office of, and Multifamily Housing Assistance Restructuring, Office of   | 24, II, VIII, X, XX             |
| Human Development Services, Office of                                             | 24, IV                          |
| Immigration and Customs Enforcement Bureau                                        | 45, XIII                        |
| Immigration and Naturalization                                                    | 19, IV                          |
| Immigration Review, Executive Office for                                          | 8, I                            |
| Independent Counsel, Office of                                                    | 8, V                            |
| Indian Affairs, Bureau of                                                         | 28, VII                         |
| Indian Affairs, Office of the Assistant Secretary                                 | 25, I, V                        |
| Indian Arts and Crafts Board                                                      | 25, VI                          |
| Indian Health Service                                                             | 25, II                          |
| Industry and Security, Bureau of                                                  | 25, V                           |
| Information Resources Management, Office of                                       | 15, VII                         |
|                                                                                   | 7, XXVII                        |

| Agency                                                                                       | CFR Title, Subtitle or Chapter         |
|----------------------------------------------------------------------------------------------|----------------------------------------|
| Information Security Oversight Office, National Archives and Records Administration          | 32, XX                                 |
| Inspector General                                                                            |                                        |
| Agriculture Department                                                                       | 7, XXVI                                |
| Health and Human Services Department                                                         | 42, V                                  |
| Housing and Urban Development Department                                                     | 24, XII                                |
| Institute of Peace, United States                                                            | 22, XVII                               |
| Inter-American Foundation                                                                    | 5, LXIII; 22, X                        |
| Interior Department                                                                          |                                        |
| American Indians, Office of the Special Trustee                                              | 25, VII                                |
| Endangered Species Committee                                                                 | 50, IV                                 |
| Federal Acquisition Regulation                                                               | 48, 14                                 |
| Federal Property Management Regulations System                                               | 41, 114                                |
| Fish and Wildlife Service, United States                                                     | 50, I, IV                              |
| Geological Survey                                                                            | 30, IV                                 |
| Indian Affairs, Bureau of                                                                    | 25, I, V                               |
| Indian Affairs, Office of the Assistant Secretary                                            | 25, VI                                 |
| Indian Arts and Crafts Board                                                                 | 25, II                                 |
| Land Management, Bureau of                                                                   | 43, II                                 |
| Minerals Management Service                                                                  | 30, II                                 |
| National Indian Gaming Commission                                                            | 25, III                                |
| National Park Service                                                                        | 36, I                                  |
| Reclamation, Bureau of                                                                       | 43, I                                  |
| Secretary of the Interior, Office of                                                         | 2, XIV; 43, Subtitle A                 |
| Surface Mining and Reclamation Appeals, Board of                                             | 30, III                                |
| Surface Mining Reclamation and Enforcement, Office of                                        | 30, VII                                |
| Internal Revenue Service                                                                     | 26, I                                  |
| International Boundary and Water Commission, United States and Mexico, United States Section | 22, XI                                 |
| International Development, United States Agency for                                          | 22, II                                 |
| Federal Acquisition Regulation                                                               | 48, 7                                  |
| International Development Cooperation Agency, United States                                  | 22, XII                                |
| International Fishing and Related Activities                                                 | 50, III                                |
| International Investment, Office of                                                          | 31, VIII                               |
| International Joint Commission, United States and Canada                                     | 22, IV                                 |
| International Organizations Employees Loyalty Board                                          | 5, V                                   |
| International Trade Administration                                                           | 15, III; 19, III                       |
| International Trade Commission, United States                                                | 19, II                                 |
| Interstate Commerce Commission                                                               | 5, XL                                  |
| James Madison Memorial Fellowship Foundation                                                 | 45, XXIV                               |
| Japan–United States Friendship Commission                                                    | 22, XVI                                |
| Joint Board for the Enrollment of Actuaries                                                  | 20, VIII                               |
| Justice Department                                                                           | 2, XXVII; 5, XXVIII; 28, I, XI; 40, IV |
| Alcohol, Tobacco, Firearms, and Explosives, Bureau of                                        | 27, II                                 |
| Drug Enforcement Administration                                                              | 21, II                                 |
| Federal Acquisition Regulation                                                               | 48, 28                                 |
| Federal Claims Collection Standards                                                          | 31, IX                                 |
| Federal Prison Industries, Inc.                                                              | 28, III                                |
| Foreign Claims Settlement Commission of the United States                                    | 45, V                                  |
| Immigration Review, Executive Office for                                                     | 8, V                                   |
| Offices of Independent Counsel                                                               | 28, VI                                 |
| Prisons, Bureau of                                                                           | 28, V                                  |
| Property Management Regulations                                                              | 41, 128                                |
| Labor Department                                                                             | 5, XLII                                |
| Benefits Review Board                                                                        | 20, VII                                |
| Employee Benefits Security Administration                                                    | 29, XXV                                |
| Employees' Compensation Appeals Board                                                        | 20, IV                                 |
| Employment and Training Administration                                                       | 20, V                                  |
| Employment Standards Administration                                                          | 20, VI                                 |
| Federal Acquisition Regulation                                                               | 48, 29                                 |
| Federal Contract Compliance Programs, Office of                                              | 41, 60                                 |
| Federal Procurement Regulations System                                                       | 41, 50                                 |
| Labor-Management Standards, Office of                                                        | 29, II, IV                             |
| Mine Safety and Health Administration                                                        | 30, I                                  |

| Agency                                                                                 | CFR Title, Subtitle or Chapter |
|----------------------------------------------------------------------------------------|--------------------------------|
| Occupational Safety and Health Administration                                          | 29, XVII                       |
| Public Contracts                                                                       | 41, 50                         |
| Secretary of Labor, Office of                                                          | 29, Subtitle A                 |
| Veterans' Employment and Training Service, Office of the Assistant Secretary for       | 41, 61; 20, IX                 |
| Wage and Hour Division                                                                 | 29, V                          |
| Workers' Compensation Programs, Office of                                              | 20, I                          |
| Labor-Management Standards, Office of                                                  | 29, II, IV                     |
| Land Management, Bureau of                                                             | 43, II                         |
| Legal Services Corporation                                                             | 45, XVI                        |
| Library of Congress                                                                    | 36, VII                        |
| Copyright Office                                                                       | 37, II                         |
| Copyright Royalty Board                                                                | 37, III                        |
| Local Television Loan Guarantee Board                                                  | 7, XX                          |
| Management and Budget, Office of                                                       | 5, III, LXXVII; 14, VI; 48, 99 |
| Marine Mammal Commission                                                               | 50, V                          |
| Maritime Administration                                                                | 46, II                         |
| Merit Systems Protection Board                                                         | 5, II, LXIV                    |
| Micronesian Status Negotiations, Office for                                            | 32, XXVII                      |
| Millenium Challenge Corporation                                                        | 22, XIII                       |
| Mine Safety and Health Administration                                                  | 30, I                          |
| Minerals Management Service                                                            | 30, II                         |
| Minority Business Development Agency                                                   | 15, XIV                        |
| Miscellaneous Agencies                                                                 | 1, IV                          |
| Monetary Offices                                                                       | 31, I                          |
| Morris K. Udall Scholarship and Excellence in National Environmental Policy Foundation | 36, XVI                        |
| National Aeronautics and Space Administration                                          | 2, XVIII; 5, LIX; 14, V        |
| Federal Acquisition Regulation                                                         | 48, 18                         |
| National Agricultural Library                                                          | 7, XLI                         |
| National Agricultural Statistics Service                                               | 7, XXXVI                       |
| National and Community Service, Corporation for                                        | 45, XII, XXV                   |
| National Archives and Records Administration                                           | 2, XXVI; 5, LXVI; 36, XII      |
| Information Security Oversight Office                                                  | 32, XX                         |
| National Capital Planning Commission                                                   | 1, IV                          |
| National Commission for Employment Policy                                              | 1, IV                          |
| National Commission on Libraries and Information Science                               | 45, XVII                       |
| National Council on Disability                                                         | 34, XII                        |
| National Counterintelligence Center                                                    | 32, XVIII                      |
| National Credit Union Administration                                                   | 12, VII                        |
| National Crime Prevention and Privacy Compact Council                                  | 28, IX                         |
| National Drug Control Policy, Office of                                                | 21, III                        |
| National Endowment for the Arts                                                        | 2, XXXII                       |
| National Endowment for the Humanities                                                  | 2, XXXIII                      |
| National Foundation on the Arts and the Humanities                                     | 45, XI                         |
| National Highway Traffic Safety Administration                                         | 23, II, III; 49, V             |
| National Imagery and Mapping Agency                                                    | 32, I                          |
| National Indian Gaming Commission                                                      | 25, III                        |
| National Institute for Literacy                                                        | 34, XI                         |
| National Institute of Standards and Technology                                         | 15, II                         |
| National Intelligence, Office of Director of                                           | 32, XVII                       |
| National Labor Relations Board                                                         | 5, LXI; 29, I                  |
| National Marine Fisheries Service                                                      | 50, II, IV, VI                 |
| National Mediation Board                                                               | 29, X                          |
| National Oceanic and Atmospheric Administration                                        | 15, IX; 50, II, III, IV, VI    |
| National Park Service                                                                  | 36, I                          |
| National Railroad Adjustment Board                                                     | 29, III                        |
| National Railroad Passenger Corporation (AMTRAK)                                       | 49, VII                        |
| National Science Foundation                                                            | 2, XXV; 5, XLIII; 45, VI       |
| Federal Acquisition Regulation                                                         | 48, 25                         |
| National Security Council                                                              | 32, XXI                        |
| National Security Council and Office of Science and Technology Policy                  | 47, II                         |
| National Telecommunications and Information Administration                             | 15, XXIII; 47, III             |

| Agency                                                                  | CFR Title, Subtitle or Chapter |
|-------------------------------------------------------------------------|--------------------------------|
| National Transportation Safety Board                                    | 49, VIII                       |
| Natural Resources Conservation Service                                  | 7, VI                          |
| Navajo and Hopi Indian Relocation, Office of                            | 25, IV                         |
| Navy Department                                                         | 32, VI                         |
| Federal Acquisition Regulation                                          | 48, 52                         |
| Neighborhood Reinvestment Corporation                                   | 24, XXV                        |
| Northeast Interstate Low-Level Radioactive Waste Commission             | 10, XVIII                      |
| Nuclear Regulatory Commission                                           | 5, XLVIII; 10, I               |
| Federal Acquisition Regulation                                          | 48, 20                         |
| Occupational Safety and Health Administration                           | 29, XVII                       |
| Occupational Safety and Health Review Commission                        | 29, XX                         |
| Offices of Independent Counsel                                          | 28, VI                         |
| Oklahoma City National Memorial Trust                                   | 36, XV                         |
| Operations Office                                                       | 7, XXVIII                      |
| Overseas Private Investment Corporation                                 | 5, XXXIII; 22, VII             |
| Patent and Trademark Office, United States                              | 37, I                          |
| Payment From a Non-Federal Source for Travel Expenses                   | 41, 304                        |
| Payment of Expenses Connected With the Death of Certain Employees       | 41, 303                        |
| Peace Corps                                                             | 22, III                        |
| Pennsylvania Avenue Development Corporation                             | 36, IX                         |
| Pension Benefit Guaranty Corporation                                    | 29, XL                         |
| Personnel Management, Office of                                         | 5, I, XXXV; 45, VIII           |
| Federal Acquisition Regulation                                          | 48, 17                         |
| Federal Employees Group Life Insurance Federal Acquisition Regulation   | 48, 21                         |
| Federal Employees Health Benefits Acquisition Regulation                | 48, 16                         |
| Pipeline and Hazardous Materials Safety Administration                  | 49, I                          |
| Postal Regulatory Commission                                            | 5, XLVI; 39, III               |
| Postal Service, United States                                           | 5, LX; 39, I                   |
| Postsecondary Education, Office of                                      | 34, VI                         |
| President's Commission on White House Fellowships                       | 1, IV                          |
| Presidential Documents                                                  | 3                              |
| Presidio Trust                                                          | 36, X                          |
| Prisons, Bureau of                                                      | 28, V                          |
| Privacy and Civil Liberties Oversight Board                             | 6, X                           |
| Procurement and Property Management, Office of                          | 7, XXXII                       |
| Productivity, Technology and Innovation, Assistant Secretary            | 37, IV                         |
| Public Contracts, Department of Labor                                   | 41, 50                         |
| Public and Indian Housing, Office of Assistant Secretary for            | 24, IX                         |
| Public Health Service                                                   | 42, I                          |
| Railroad Retirement Board                                               | 20, II                         |
| Reclamation, Bureau of                                                  | 43, I                          |
| Refugee Resettlement, Office of                                         | 45, IV                         |
| Relocation Allowances                                                   | 41, 302                        |
| Research and Innovative Technology Administration                       | 49, XI                         |
| Rural Business-Cooperative Service                                      | 7, XVIII, XLII                 |
| Rural Development Administration                                        | 7, XLII                        |
| Rural Housing Service                                                   | 7, XVIII, XXXV                 |
| Rural Telephone Bank                                                    | 7, XVI                         |
| Rural Utilities Service                                                 | 7, XVII, XVIII, XLII           |
| Saint Lawrence Seaway Development Corporation                           | 33, IV                         |
| Science and Technology Policy, Office of                                | 32, XXIV                       |
| Science and Technology Policy, Office of, and National Security Council | 47, II                         |
| Secret Service                                                          | 31, IV                         |
| Securities and Exchange Commission                                      | 17, II                         |
| Selective Service System                                                | 32, XVI                        |
| Small Business Administration                                           | 2, XXVII; 13, I                |
| Smithsonian Institution                                                 | 36, V                          |
| Social Security Administration                                          | 2, XXIII; 20, III; 48, 23      |
| Soldiers' and Airmen's Home, United States                              | 5, XI                          |
| Special Counsel, Office of                                              | 5, VIII                        |
| Special Education and Rehabilitative Services, Office of                | 34, III                        |
| State Department                                                        | 2, VI; 22, I; 28, XI           |



| Agency                                                                                       | CFR Title, Subtitle or Chapter |
|----------------------------------------------------------------------------------------------|--------------------------------|
| Federal Acquisition Regulation                                                               | 48, 6                          |
| Surface Mining and Reclamation Appeals, Board of                                             | 30, III                        |
| Surface Mining Reclamation and Enforcement, Office of                                        | 30, VII                        |
| Surface Transportation Board                                                                 | 49, X                          |
| Susquehanna River Basin Commission                                                           | 18, VIII                       |
| Technology Administration                                                                    | 15, XI                         |
| Technology Policy, Assistant Secretary for                                                   | 37, IV                         |
| Technology, Under Secretary for                                                              | 37, V                          |
| Tennessee Valley Authority                                                                   | 5, LXIX; 18, XIII              |
| Thrift Supervision Office, Department of the Treasury                                        | 12, V                          |
| Trade Representative, United States, Office of                                               | 15, XX                         |
| Transportation, Department of                                                                | 2, XII; 5, L                   |
| Commercial Space Transportation                                                              | 14, III                        |
| Contract Appeals, Board of                                                                   | 48, 63                         |
| Emergency Management and Assistance                                                          | 44, IV                         |
| Federal Acquisition Regulation                                                               | 48, 12                         |
| Federal Aviation Administration                                                              | 14, I                          |
| Federal Highway Administration                                                               | 23, I, II                      |
| Federal Motor Carrier Safety Administration                                                  | 49, III                        |
| Federal Railroad Administration                                                              | 49, II                         |
| Federal Transit Administration                                                               | 49, VI                         |
| Maritime Administration                                                                      | 46, II                         |
| National Highway Traffic Safety Administration                                               | 23, II, III; 49, V             |
| Pipeline and Hazardous Materials Safety Administration                                       | 49, I                          |
| Saint Lawrence Seaway Development Corporation                                                | 33, IV                         |
| Secretary of Transportation, Office of                                                       | 14, II; 49, Subtitle A         |
| Surface Transportation Board                                                                 | 49, X                          |
| Transportation Statistics Bureau                                                             | 49, XI                         |
| Transportation, Office of                                                                    | 7, XXXIII                      |
| Transportation Security Administration                                                       | 49, XII                        |
| Transportation Statistics Bureau                                                             | 49, XI                         |
| Travel Allowances, Temporary Duty (TDY)                                                      | 41, 301                        |
| Treasury Department                                                                          | 5, XXI; 12, XV; 17, IV; 31, IX |
| Alcohol and Tobacco Tax and Trade Bureau                                                     | 27, I                          |
| Community Development Financial Institutions Fund                                            | 12, XVIII                      |
| Comptroller of the Currency                                                                  | 12, I                          |
| Customs and Border Protection Bureau                                                         | 19, I                          |
| Engraving and Printing, Bureau of                                                            | 31, VI                         |
| Federal Acquisition Regulation                                                               | 48, 10                         |
| Federal Claims Collection Standards                                                          | 31, IX                         |
| Federal Law Enforcement Training Center                                                      | 31, VII                        |
| Fiscal Service                                                                               | 31, II                         |
| Foreign Assets Control, Office of                                                            | 31, V                          |
| Internal Revenue Service                                                                     | 26, I                          |
| International Investment, Office of                                                          | 31, VIII                       |
| Monetary Offices                                                                             | 31, I                          |
| Secret Service                                                                               | 31, IV                         |
| Secretary of the Treasury, Office of                                                         | 31, Subtitle A                 |
| Thrift Supervision, Office of                                                                | 12, V                          |
| Truman, Harry S. Scholarship Foundation                                                      | 45, XVIII                      |
| United States and Canada, International Joint Commission                                     | 22, IV                         |
| United States and Mexico, International Boundary and Water Commission, United States Section | 22, XI                         |
| Utah Reclamation Mitigation and Conservation Commission                                      | 43, III                        |
| Veterans Affairs Department                                                                  | 2, VIII; 38, I                 |
| Federal Acquisition Regulation                                                               | 48, 8                          |
| Veterans' Employment and Training Service, Office of the Assistant Secretary for             | 41, 61; 20, IX                 |
| Vice President of the United States, Office of                                               | 32, XXVIII                     |
| Vocational and Adult Education, Office of                                                    | 34, IV                         |
| Wage and Hour Division                                                                       | 29, V                          |
| Water Resources Council                                                                      | 18, VI                         |
| Workers' Compensation Programs, Office of                                                    | 20, I                          |
| World Agricultural Outlook Board                                                             | 7, XXXVIII                     |



## List of CFR Sections Affected

All changes in this volume of the Code of Federal Regulations which were made by documents published in the FEDERAL REGISTER since January 1, 2001, are enumerated in the following list. Entries indicate the nature of the changes effected. Page numbers refer to FEDERAL REGISTER pages. The user should consult the entries for chapters and parts as well as sections for revisions.

For the period before January 1, 2001, see the “List of Sections Affected, 1949–1963, 1964–1972, 1973–1985, and 1986–2000” published in 11 separate volumes.

| 2001                                   |               | 49 CFR—Continued                      |               |
|----------------------------------------|---------------|---------------------------------------|---------------|
| 49 CFR                                 | 66 FR<br>Page |                                       | 66 FR<br>Page |
| 107.1 (a) amended .....                | 45377         | 171.7 (a)(3) table amended .....      | 8646          |
| 107.3 Amended .....                    | 45377         | (a)(1) and (3) table amended .....    | 33334         |
| 107.7 (a) and (c) amended .....        | 45377         | (a)(2)(i) and (3) table amended ..... | 45378         |
| 107.117 (d) introductory text and      |               | 171.8 Amended .....                   | 33335         |
| (e) amended .....                      | 45377         | Amended .....                         | 45182, 45378  |
| 107.127 (a) amended .....              | 45377         | 171.10 (c)(2) table amended .....     | 33335         |
| 107.305 (a), (c) and (d) amended ..... | 45377         | (c)(2) table amended .....            | 45378         |
| 107.307 (a) introductory text and      |               | 171.11 Introductory text revised;     |               |
| (b) amended .....                      | 45377         | (d)(6)(i), (ii) and (iv) amended;     |               |
| 107.309 (a) and (b)(1) amended .....   | 45377         | (d)(6)(vi) and (17) added .....       | 33336         |
| 107.310 (a), (b) introductory text     |               | (d)(13) amended .....                 | 45182         |
| and (c) amended .....                  | 45377         | 171.12 (b) heading revised; (b)(3)    |               |
| 107.317 (c) amended .....              | 45377         | amended .....                         | 8646          |
| 107.327 (a)(1) introductory text       |               | (b)(5), (d) heading, introductory     |               |
| amended .....                          | 45377         | text and (4) revised; (b)(20) and     |               |
| 107.335 Amended .....                  | 45377         | (d)(7) added; (d)(5) and (6)          |               |
| 107.301–107.339 (Subpart D) Ap-        |               | amended .....                         | 33336         |
| pendix A amended .....                 | 45180         | (b)(8)(iii) and (iv) revised;         |               |
| 107.401 (b) amended .....              | 45377         | (b)(8)(v), (vi) and (e) added .....   | 44254         |
| 107.402 (b)(6) and (c) amended .....   | 45377         | 171.12a (b)(18) added .....           | 33336         |
| 107.403 (a), (b) and (c) amended ..... | 45377         | (b)(5)(iii) and (iv) revised; new     |               |
| 107.404 (a)(3) and (b) amended .....   | 45377         | (b)(5)(v) and (vi) added .....        | 44255         |
| 107.405 (a) introductory text and      |               | 171.14 (d) introductory text, (1)     |               |
| (b) introductory text amend-           |               | and (2) introductory text re-         |               |
| ed .....                               | 45377         | vised; (d)(4) and (5) added .....     | 33336         |
| 110.20 Amended .....                   | 45377         | (c) amended .....                     | 45378         |
| 110.40 (a)(7) and (b)(6) amended ..... | 45377         | 171.15 (b) introductory text          |               |
| 110.60 (a)(4) amended .....            | 45377         | amended .....                         | 45182         |
| 110.70 (c) introductory text and       |               | 171.20 (a) and (c) amended .....      | 45378         |
| (d) amended .....                      | 45377         | 171.21 (a) and (b) amended .....      | 45378         |
| 110.100 Amended .....                  | 45377         | 172.1 Amended .....                   | 45379         |
| 110.110 Amended .....                  | 45377         | 172.101 (b)(1), (c)(11) and table re- |               |
| 110.120 Amended .....                  | 45377         | vised; (c)(16) and (k)(6) through     |               |
| 130.5 Amended .....                    | 45378         | (20) added .....                      | 33337         |
| 171.1 (a) introductory text            |               | Appendix B amended .....              | 33413         |
| amended .....                          | 45378         | Appendix A amended .....              | 45182         |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

|                                                                                  | 66 FR<br>Page |
|----------------------------------------------------------------------------------|---------------|
| (b)(1), (d)(2), (f), (k)(2)(i), (4), (5),<br>(l)(2) and Appendix B amended ..... | 45379         |
| 172.102 (c)(1) amended .....                                                     | 8647          |
| (c)(1), (2), (3) and (8) amended;<br>(c)(4) and (7) revised .....                | 33414         |
| (c)(1) and (3) amended .....                                                     | 45182         |
| (c)(1), (2), (3), (5), and (7)(ii)<br>amended .....                              | 45379         |
| 172.202 (a)(4) and (e) revised .....                                             | 33425         |
| 172.203 (d)(11) and (n) revised;<br>(i)(5) and (6) added .....                   | 33425         |
| (k) introductory text, (o)(3)<br>amended .....                                   | 45182         |
| (d)(7)(ii) amended .....                                                         | 45379         |
| 172.301 (a)(3) introductory text<br>and (b) heading amended .....                | 45182         |
| 172.302 (b)(2) amended .....                                                     | 45379         |
| 172.310 (a) amended .....                                                        | 45379         |
| 172.312 (c)(2) and (3) amended .....                                             | 45379         |
| 172.322 (d)(1)(i), (ii), (2)(i), (ii)<br>amended .....                           | 45379         |
| 172.330 (a)(1)(ii) amended .....                                                 | 33425         |
| 172.400a (d) added .....                                                         | 44255         |
| 172.401 (c)(1) and (2) revised .....                                             | 8647          |
| (c)(1) through (4) revised .....                                                 | 45379         |
| 172.402 (b) revised .....                                                        | 33425         |
| 172.405 (a) introductory text<br>amended; (a)(1) and (2) re-<br>moved .....      | 33425         |
| 172.407 (f) revised .....                                                        | 8647          |
| (f) revised .....                                                                | 44255         |
| 172.411 Heading and (d) revised;<br>(c) amended .....                            | 33425         |
| 172.502 (b)(1) revised .....                                                     | 8647          |
| (b)(1) revised .....                                                             | 33426         |
| 172.504 (g) existing text amended;<br>(g)(1) through (4) added .....             | 33426         |
| 172.512 (a)(3) amended .....                                                     | 33426         |
| (b) heading amended .....                                                        | 45182         |
| 172.514 (c)(4) amended .....                                                     | 45379         |
| 172.519 (b)(4) revised .....                                                     | 33426         |
| (f) revised .....                                                                | 44255         |
| 172.602 (a)(1) amended .....                                                     | 45379         |
| 172.604 (c)(2) amended .....                                                     | 45182         |
| 173.2a (b) table amended .....                                                   | 33426, 45183  |
| (c)(4) amended .....                                                             | 45379         |
| 173.3 (c)(1) amended .....                                                       | 45380         |
| 173.4 (a)(1) introductory text re-<br>vised .....                                | 33426         |
| (a)(6) amended .....                                                             | 45183         |
| (c) amended .....                                                                | 45379         |
| (a)(1)(i) amended .....                                                          | 45381         |
| 173.6 (a)(3) amended .....                                                       | 45381         |
| 173.7 (c) amended .....                                                          | 45381         |
| 173.8 (b) and (c) amended .....                                                  | 45380         |
| 173.13 (c)(1)(i) amended .....                                                   | 45381         |

### 49 CFR—Continued

|                                                                                                                                                                                                                                                                              | 66 FR<br>Page |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| 173.21 (f) introductory text and<br>(3)(ii) amended .....                                                                                                                                                                                                                    | 8647          |
| (f)(3) introductory text and (i)<br>amended .....                                                                                                                                                                                                                            | 45379         |
| (f)(3)(ii) revised .....                                                                                                                                                                                                                                                     | 45381         |
| 173.22 (c)(2) amended .....                                                                                                                                                                                                                                                  | 45379         |
| (a)(3)(i) amended .....                                                                                                                                                                                                                                                      | 45380         |
| (a)(2)(iii) revised .....                                                                                                                                                                                                                                                    | 45381         |
| 173.22a (b) amended .....                                                                                                                                                                                                                                                    | 45381         |
| 173.24 (d)(2) introductory text<br>amended .....                                                                                                                                                                                                                             | 8647          |
| (e)(3)(iii) amended .....                                                                                                                                                                                                                                                    | 45379         |
| (d)(2) introductory text and (i)<br>revised .....                                                                                                                                                                                                                            | 45381         |
| 173.24a (b)(4)(i), (ii), (iii) amend-<br>ed .....                                                                                                                                                                                                                            | 45380         |
| 173.24b (e) added .....                                                                                                                                                                                                                                                      | 33426         |
| 173.27 (c)(2)(i), (ii)(A), (B), (C) and<br>(3)(ii) amended .....                                                                                                                                                                                                             | 45380         |
| 173.28 (b)(7)(iv)(C) amended .....                                                                                                                                                                                                                                           | 45183         |
| (b)(2)(ii) and (7)(iv)(C) amended<br>.....                                                                                                                                                                                                                                   | 45379         |
| (b)(2)(i) and (4)(ii) amended .....                                                                                                                                                                                                                                          | 45380         |
| 173.31 (b)(2)(ii) amended .....                                                                                                                                                                                                                                              | 33427         |
| (c)(3), (e)(2) introductory text,<br>(f)(1) introductory text and<br>(i)(A) amended .....                                                                                                                                                                                    | 45380         |
| (b)(2)(ii) revised; (d)(1)(vi)<br>amended .....                                                                                                                                                                                                                              | 45381         |
| 173.32 Revised .....                                                                                                                                                                                                                                                         | 33427         |
| 173.32a Removed .....                                                                                                                                                                                                                                                        | 33429         |
| 173.32b Removed .....                                                                                                                                                                                                                                                        | 33429         |
| 173.32c Removed .....                                                                                                                                                                                                                                                        | 33429         |
| 173.33 (c)(1)(iii) amended .....                                                                                                                                                                                                                                             | 45183         |
| 173.34 (e)(13) table amended .....                                                                                                                                                                                                                                           | 33429         |
| (d)(6) and (e)(13) table amended<br>.....                                                                                                                                                                                                                                    | 45183         |
| (c)(3), (d)(1)(ii), (iii), (2), (e)<br>Table, (2)(i), (ii) introductory<br>text, (A), (B), (iii), (4)(iii) intro-<br>ductory text, (A), (v), (7)(ii),<br>(8)(i)(C), (10), (12), (i) introduc-<br>tory text, (4)(i), (l) introduc-<br>tory text, (2) and (3) amended<br>..... | 45380         |
| 173.35 (a), (c), (d), (f)(1), (2), (g), (h)<br>introductory text, (h)(1) intro-<br>ductory text, (i) through (iv),<br>(2) introductory text, (j), (k), (l)<br>heading, (1), (2), (3) and (4)<br>amended .....                                                                | 45380         |
| Heading and (k) amended .....                                                                                                                                                                                                                                                | 45381         |
| 173.50 (b)(6) amended .....                                                                                                                                                                                                                                                  | 45183         |
| 173.51 (a) and (b) amended .....                                                                                                                                                                                                                                             | 45379         |
| 173.52 (a) amended .....                                                                                                                                                                                                                                                     | 45379         |

## List of CFR Sections Affected

### 49 CFR—Continued

|                                                                                                                                 | 66 FR<br>Page |
|---------------------------------------------------------------------------------------------------------------------------------|---------------|
| 173.56 (a)(2), (b)(1) introductory text, (4), (c) introductory text, (f), (g), (i), (j) introductory text and (3) amended ..... | 45379         |
| 173.58 (d) and (e) amended .....                                                                                                | 45379         |
| 173.59 Amended .....                                                                                                            | 45183         |
| Amended .....                                                                                                                   | 45379         |
| 173.61 (e)(3) revised; (e)(8) added .....                                                                                       | 33429         |
| (e)(2) revised .....                                                                                                            | 45381         |
| 173.62 (b) table and (c) table amended .....                                                                                    | 33429         |
| (c) table amended .....                                                                                                         | 45382         |
| (a) revised; (c) table amended .....                                                                                            | 45183         |
| (c)(5) amended .....                                                                                                            | 45380         |
| 173.115 (a) introductory text, (1), (2), (c) introductory text, (i) and (j) amended .....                                       | 45380         |
| (c)(2) amended .....                                                                                                            | 45381         |
| (g) amended .....                                                                                                               | 45382         |
| 173.120 (d) amended .....                                                                                                       | 45379         |
| (c)(3) amended .....                                                                                                            | 45381         |
| 173.121 (b)(2)(ii) amended .....                                                                                                | 45381         |
| 173.124 (a)(2)(iii)(C) amended .....                                                                                            | 8647          |
| (a)(1)(ii) introductory text, (2)(i)(E), (iii)(D) and (c) amended .....                                                         | 45379         |
| 173.125 (c)(2)(ii)(B), (C), (d)(1), (2) and (3) amended .....                                                                   | 45379         |
| 173.128 (e) amended .....                                                                                                       | 8647          |
| (a)(3), (d)(1) introductory text amended .....                                                                                  | 45380         |
| 173.132 (d) amended .....                                                                                                       | 45380         |
| (a)(1)(iii)(B) revised .....                                                                                                    | 45382         |
| 173.133 (a)(2)(i) table amended .....                                                                                           | 45183         |
| (b)(1)(i), (iv) Table, (2)(i)(A), (ii)(A), (iii)(A), (iv)(A) and (B) amended .....                                              | 45381         |
| Corrected .....                                                                                                                 | 49556         |
| 173.150 (d)(2) revised .....                                                                                                    | 33430         |
| (d)(2) amended .....                                                                                                            | 45382         |
| 173.152 (b)(3)(i), (ii) and (4)(i) amended .....                                                                                | 45381         |
| 173.153 (c)(2) amended .....                                                                                                    | 45381         |
| 173.159 (f) amended .....                                                                                                       | 45379         |
| (d)(3)(ii) amended .....                                                                                                        | 45380         |
| 173.161 (b) amended .....                                                                                                       | 45381         |
| 173.162 (a) introductory text and (1) revised .....                                                                             | 33430         |
| 173.166 (b)(2) amended .....                                                                                                    | 8647          |
| (a) amended .....                                                                                                               | 45183         |
| (b)(1), (3)(ii), (c) and (d)(1) amended .....                                                                                   | 45379         |
| 173.171 (d) amended .....                                                                                                       | 45379         |
| 173.172 (a) and (b) amended .....                                                                                               | 45380         |
| 173.181 (a)(2) amended .....                                                                                                    | 45183         |
| (a) amended .....                                                                                                               | 45380         |

### 49 CFR—Continued

|                                                                                                               | 66 FR<br>Page |
|---------------------------------------------------------------------------------------------------------------|---------------|
| 173.185 (c)(3) amended .....                                                                                  | 8647          |
| Revised .....                                                                                                 | 33430         |
| (i) amended .....                                                                                             | 45379         |
| 173.189 (d)(4)(iii) amended .....                                                                             | 45380         |
| 173.194 (b)(1) amended .....                                                                                  | 45183         |
| (a), (b)(1) and (2) amended .....                                                                             | 45381         |
| 173.196 (f) amended .....                                                                                     | 45380         |
| 173.214 Amended .....                                                                                         | 45379         |
| 173.220 (b)(1) and (4) amended .....                                                                          | 45381         |
| 173.222 (b)(3) amended .....                                                                                  | 45379         |
| 173.224 (b)(4) revised; (b)(7) table amended; (d) removed .....                                               | 33431         |
| (c)(1) amended .....                                                                                          | 45379         |
| 173.225 (b) table amended; (e) introductory text, (3) and (5) revised .....                                   | 33431         |
| (b)(4) introductory text, (8) table, (c)(1), (d)(3) and (e)(5) heading and introductory text amended .....    | 45380         |
| (e)(3)(i)(B) amended .....                                                                                    | 45382         |
| 173.226 (b) introductory text amended .....                                                                   | 45380         |
| 173.227 (b) introductory text amended .....                                                                   | 45380         |
| 173.240 (c) and (d) revised .....                                                                             | 33435         |
| (d) heading and introductory text, (1)(i), (2) introductory text, (i) and (ii) amended .....                  | 45380         |
| (d)(1)(vi) amended .....                                                                                      | 45382         |
| 173.241 (c) and (d) revised .....                                                                             | 33435         |
| (d) heading, (1) introductory text, (2) introductory text, (i)(A), (ii) and (iii) amended .....               | 45380         |
| 173.242 (c) introductory text and (d) revised .....                                                           | 33435         |
| (d) heading, (1) introductory text, (i)(A), (ii)(A), (2) introductory text and (i) through (iv) amended ..... | 45380         |
| (d)(1)(ii)(F) revised .....                                                                                   | 45382         |
| 173.243 (c) and (d) revised .....                                                                             | 33435         |
| (d)(1), (2)(i), (ii) and (iii) amended .....                                                                  | 45380         |
| 173.245 (a) and (b) amended .....                                                                             | 45379         |
| 173.247 (c) revised .....                                                                                     | 33436         |
| (g)(1)(iii)(C) and (iv) amended .....                                                                         | 45382         |
| 173.249 Introductory text and (a) amended .....                                                               | 45183         |
| 173.300a (c), (d), (e), (g), (h) and (i) amended .....                                                        | 45379         |
| (a)(2) amended .....                                                                                          | 45382         |
| 173.300b (c) through (g) amended .....                                                                        | 45379         |
| 173.300c (a) introductory text and (b) amended .....                                                          | 45379         |
| 173.301 (d)(2) amended .....                                                                                  | 33436         |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

|                                                                                                                                                                        | 66 FR<br>Page |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| (j)(1)(i) amended.....                                                                                                                                                 | 45380         |
| (d)(3) amended .....                                                                                                                                                   | 45183         |
| (g)(5) amended .....                                                                                                                                                   | 45380         |
| 173.302 (c)(3) amended .....                                                                                                                                           | 45382         |
| 173.303 (b) amended .....                                                                                                                                              | 45380         |
| 173.304 (a)(2) table and (b) amend-<br>ed .....                                                                                                                        | 33436         |
| (a)(2) table, (e)(1) and (f)(1)<br>amended .....                                                                                                                       | 45382         |
| 173.305 (c)(1) amended .....                                                                                                                                           | 45379         |
| 173.306 (a)(4)(iii) revised .....                                                                                                                                      | 33436         |
| (a)(3)(i), (b)(1) introductory text,<br>(f)(4)(i), (ii), (5) and (g)(3)<br>amended .....                                                                               | 45380         |
| (b) heading amended .....                                                                                                                                              | 45382         |
| 173.308 (a)(1) amended .....                                                                                                                                           | 45381         |
| 173.309 (a)(3)(i) amended.....                                                                                                                                         | 45380, 45381  |
| 173.314 (c) table and (g) introduc-<br>tory text amended .....                                                                                                         | 33436         |
| (c) table and (o) amended .....                                                                                                                                        | 45380         |
| (c) table, (j), (l), (n) and (o)<br>amended .....                                                                                                                      | 45381         |
| (g)(4), (l) and (o) amended.....                                                                                                                                       | 45382         |
| 173.315 (a) introductory text,<br>(i)(1)(iii), (3), (4) and (8) revised;<br>(a) table, (b) introductory text<br>and (h) table amended; (i)(7) re-<br>moved .....       | 33436         |
| (l)(6) amended .....                                                                                                                                                   | 45184         |
| (i)(12), (k)(2), (n)(1) table, (3) in-<br>troductory text, (i) and<br>(n)(5)(iii) amended .....                                                                        | 45380         |
| (i)(2), (3), (5) through (9), (11), (13),<br>(k)(5), (n) heading, (1) introduc-<br>tory text, (2)(ii), (3) heading,<br>(ii), (o) heading, (2) and (3)<br>amended ..... | 45381         |
| (i)(10), (13), (n)(1)(v) table, (i) in-<br>troductory text and (4) amend-<br>ed.....                                                                                   | 45382         |
| 173.316 (d) amended .....                                                                                                                                              | 45379         |
| 173.318 (f)(4) amended.....                                                                                                                                            | 45379         |
| 173.319 (d)(2) amended .....                                                                                                                                           | 45184         |
| (a)(4)(iii), (c), (e)(1) and (2)(i)<br>amended .....                                                                                                                   | 45380         |
| (e)(4) amended.....                                                                                                                                                    | 45383         |
| 173.320 (c) revised .....                                                                                                                                              | 33436         |
| 173.323 (c)(1) amended .....                                                                                                                                           | 45380         |
| (i) amended .....                                                                                                                                                      | 45383         |
| 173.334 (d) amended .....                                                                                                                                              | 45379         |
| 173.335 (a) amended .....                                                                                                                                              | 45380         |
| 173.337 Introductory text amend-<br>ed .....                                                                                                                           | 45380         |
| 173.340 (a), (b) and (c)(4) amend-<br>ed .....                                                                                                                         | 45379         |
| 173.403 Amended .....                                                                                                                                                  | 45184, 45380  |
| Amended .....                                                                                                                                                          | 45383         |

### 49 CFR—Continued

|                                                                                       | 66 FR<br>Page |
|---------------------------------------------------------------------------------------|---------------|
| 173.411 (c) amended .....                                                             | 45379         |
| (b)(4)(ii) revised .....                                                              | 45383         |
| 173.412 (f) amended.....                                                              | 45380         |
| (b) amended .....                                                                     | 45381         |
| 173.416 (f) amended.....                                                              | 45380         |
| 173.417 (a)(6)(viii), (b)(1) Table 4,<br>(2)(i) and (ii) Table 5 amend-<br>ed .....   | 45380         |
| (a)(6)(iv), (b)(2)(ii) and Table 5<br>amended .....                                   | 45381         |
| 173.419 (c) amended .....                                                             | 45380         |
| 173.425 Table 7 amended .....                                                         | 45383         |
| 173.427 (a)(1) amended .....                                                          | 45380         |
| 173.433 (b) amended .....                                                             | 45184         |
| (b) amended .....                                                                     | 45380         |
| 173.435 Table amended .....                                                           | 45184         |
| 173.441 (b)(3) amended .....                                                          | 45380         |
| 173.443 (d)(1) amended .....                                                          | 45380         |
| 173.447 (a) amended .....                                                             | 45380         |
| 173.453 (d) amended .....                                                             | 45380         |
| (a), (b)(2), (3), (d) and (e) amended<br>.....                                        | 45383         |
| 173.457 (b)(4) amended .....                                                          | 45379         |
| 173.459 (b) introductory text<br>amended.....                                         | 45380         |
| 173.465 (c)(2), (3), (4), (d)(1)(ii),<br>(e)(1) and (2) amended.....                  | 45380         |
| (b) and (e)(1) amended.....                                                           | 45381         |
| 173.466 (a)(1) and (2) amended.....                                                   | 45380         |
| 173.469 (c)(1)(v), (d)(1) and (2)<br>amended.....                                     | 45184         |
| (b)(2)(i) and (3)(iv) amended .....                                                   | 45380         |
| (b)(2)(ii), (3)(i) and (v) amended<br>.....                                           | 45381         |
| (b)(1) amended .....                                                                  | 45381         |
| 173.471 (e) amended .....                                                             | 45379         |
| 173.472 (f) amended.....                                                              | 45379         |
| 173.473 (a)(1) amended .....                                                          | 45379         |
| 173.476 (a) and (c) introductory<br>text amended.....                                 | 45379         |
| 173 Appendix H amended.....                                                           | 45381         |
| 174.16 (b)(1), (2) and (3) amend-<br>ed .....                                         | 45383         |
| 174.63 Heading and (a) amend-<br>ed .....                                             | 45383         |
| 174.81 (e)(5), (g)(3)(iv), (v), (h) and<br>(i) amended.....                           | 45383         |
| 174.83 (f) amended .....                                                              | 45383         |
| 174.84 Amended.....                                                                   | 45383         |
| 174.85 (d) table amended .....                                                        | 45383         |
| 174.101 (a), (b), (c), (d) (h), (l), (n)<br>and (o) introductory text<br>amended..... | 45383         |
| 174.102 (a) and (b) amended .....                                                     | 45383         |
| 174.103 (a) amended .....                                                             | 45383         |

## List of CFR Sections Affected

### 49 CFR—Continued

66 FR  
Page

|         |                                                                         |                    |
|---------|-------------------------------------------------------------------------|--------------------|
| 174.104 | Heading, (a), (b) introductory text, (c), (d), (e) and (f) amended..... | 45383              |
| 174.105 | Amended .....                                                           | 45383              |
| 174.106 | Heading, (a), (b) and (c) amended.....                                  | 45383              |
| 174.110 | Amended .....                                                           | 45383              |
| 174.112 | Heading, (a), (b), (c) introductory text and (3) amended .....          | 45383              |
| 174.115 | Heading, (a), (b) and (3) amended .....                                 | 45383              |
| 174.700 | (c) and (d) amended .....                                               | 45383              |
| 174.715 | (b) amended .....                                                       | 45383              |
| 175.10  | (a)(10) and (16) revised; (a)(17) added.....                            | 33436              |
|         | (a)(2), (4)(ii), (iv), (15) and (b)(2) amended .....                    | 45383              |
| 175.30  | (d)(1) and (2) revised.....                                             | 45184              |
| 175.31  | (b)(1) amended.....                                                     | 45184              |
| 175.33  | (a) introductory text revised.....                                      | 33437              |
| 175.75  | (a)(1) amended.....                                                     | 45184              |
| 175.78  | Revised .....                                                           | 33437              |
|         | (a) Table 1 amended .....                                               | 45383              |
| 175.85  | (a) revised .....                                                       | 33438              |
|         | (i)(3) amended .....                                                    | 45383              |
|         | (c)(1)(iv) amended .....                                                | 45384              |
| 175.90  | (d)(2) amended.....                                                     | 45184              |
| 175.310 | Introductory text, (c)(1), (2) and (3) amended.....                     | 45383              |
| 175.320 | (a) table amended .....                                                 | 45383, 45384       |
| 175.701 | (b)(3) and (c) introductory text amended.....                           | 45383              |
| 175.702 | (b)(2)(i)(A) and (B) amended .....                                      | 45383              |
| 176.2   | Amended.....                                                            | 8647, 33438, 45184 |
| 176.4   | (b) introductory text and (c) amended.....                              | 45384              |
| 176.5   | (b)(8) amended.....                                                     | 8647               |
| 176.9   | Introductory text amended .....                                         | 45384              |
| 176.11  | (a) introductory text amended.....                                      | 8647               |
| 176.27  | (b) amended.....                                                        | 8647               |
| 176.30  | (a) introductory text amended .....                                     | 8647               |
|         | (a)(5) introductory text amended .....                                  | 45184              |
|         | (a)(5)(ii) revised .....                                                | 45384              |
| 176.36  | (b) amended.....                                                        | 45384              |
| 176.63  | (e) added.....                                                          | 33438              |
|         | (b) amended .....                                                       | 45184              |
| 176.74  | (c) amended.....                                                        | 45184              |
| 176.76  | (d) and (f)(2) amended .....                                            | 45184              |
|         | (h)(5) and (i) amended .....                                            | 45384              |
| 176.80  | Heading revised.....                                                    | 45184              |

### 49 CFR—Continued

66 FR  
Page

|                 |                                                                                                        |              |
|-----------------|--------------------------------------------------------------------------------------------------------|--------------|
| 176.83          | (a)(6), (7) introductory text, (b) introductory text, (c)(2)(iii) and (iv) amended.....                | 45184        |
|                 | (a)(6), (c)(2)(ii) through (v), (f)(4) table and (g)(3) tables amended; (b), (f) and (g) revised ..... | 45384        |
| 176.84          | (b) table amended; (c)(1) and (2) table revised; (c)(3) removed .....                                  | 33438        |
|                 | (a) and (c)(2) amended .....                                                                           | 45185        |
|                 | (b) table amended.....                                                                                 | 45384        |
| 176.88          | Heading revised.....                                                                                   | 45185        |
| 176.95          | Heading revised.....                                                                                   | 45185        |
| 176.99          | Amended.....                                                                                           | 45384        |
| 176.100         | Amended .....                                                                                          | 45385        |
| 176.104         | (h) introductory text and (j) introductory text amended .....                                          | 45384        |
|                 | (i) amended .....                                                                                      | 45385        |
| 176.112         | Heading revised .....                                                                                  | 45185        |
|                 | Amended .....                                                                                          | 45384        |
| 176.116         | (e)(3) amended .....                                                                                   | 45384        |
|                 | (e)(2) amended.....                                                                                    | 45385        |
| 176.128         | (c) amended .....                                                                                      | 33438        |
|                 | (c) amended.....                                                                                       | 45384        |
| 176.133         | Amended .....                                                                                          | 45185        |
| 176.136         | (e) amended .....                                                                                      | 33438        |
|                 | (b) and (c) amended.....                                                                               | 45185        |
| 176.137         | (c) amended .....                                                                                      | 45185        |
| 176.142         | (a) revised.....                                                                                       | 33438        |
|                 | (b)(1) amended .....                                                                                   | 45384        |
| 176.144         | (c) amended .....                                                                                      | 45384        |
|                 | (a) table amended.....                                                                                 | 45385        |
| 176.145         | (b) amended .....                                                                                      | 45384        |
| 176.150         | (a) and (b) amended .....                                                                              | 45384        |
| 176.164         | (c) amended .....                                                                                      | 45384        |
| 176.166         | (a)(1) and (b) table amended .....                                                                     | 45384        |
|                 | (b) table amended.....                                                                                 | 45385        |
| 176.168         | (d) amended .....                                                                                      | 45384        |
| 176.172         | (c) amended .....                                                                                      | 45384        |
| 176.192         | (a) amended .....                                                                                      | 45384        |
| 176.194         | (f) amended.....                                                                                       | 45185        |
|                 | (c) amended.....                                                                                       | 45384, 45385 |
| 176.210         | Amended .....                                                                                          | 45185        |
| 176.315         | (a) amended .....                                                                                      | 45384, 45385 |
| 176.340         | (c) amended .....                                                                                      | 45185        |
|                 | (b)(2), (7) and (8) amended.....                                                                       | 45384        |
| 176.400—176.415 | (Subpart J) Heading amended .....                                                                      | 45385        |
| 176.400         | Heading, (c) and (d) amended .....                                                                     | 45384        |
| 176.410         | Heading, (a)(1) and (c) introductory text amended .....                                                | 45384        |
| 176.415         | (c)(4) amended .....                                                                                   | 45185        |
|                 | Heading, (b)(5), (c)(1) and (5) amended .....                                                          | 45384        |

# 49 CFR (10–1–08 Edition)

## 49 CFR—Continued

|                                                                                                                                         | 66 FR<br>Page |
|-----------------------------------------------------------------------------------------------------------------------------------------|---------------|
| (a)(1) amended .....                                                                                                                    | 45385         |
| 176.700 (c) amended .....                                                                                                               | 45385         |
| 176.704 (e)(2) amended .....                                                                                                            | 45384         |
| (b) and (d) amended .....                                                                                                               | 45385         |
| 176.720 Added .....                                                                                                                     | 33439         |
| 176.905 (a)(5), (i)(2) and (5) amend-<br>ed .....                                                                                       | 45384         |
| (i)(1) and (2) amended .....                                                                                                            | 45385         |
| 177.834 (i)(3) amended .....                                                                                                            | 45385         |
| 177.835 (c) introductory text, (f)<br>and (j) amended .....                                                                             | 45385         |
| 177.840 (e) amended .....                                                                                                               | 45185         |
| (d), (e) (g), (h) introductory text,<br>(i), (m), (o), (p)(1), (2) introduc-<br>tory text, (q)(1), (r)(2), (t) and<br>(u) amended ..... | 45385         |
| 177.842 (b)(2) and (f) amended .....                                                                                                    | 45385         |
| 177.848 (g)(3)(vi) revised .....                                                                                                        | 33439         |
| (g)(3)(iv) amended .....                                                                                                                | 45185         |
| (e)(5), (g)(3)(v), (h) and (i) amend-<br>ed .....                                                                                       | 45385         |
| 177.854 (f)(1) and (g)(2)(iv) amend-<br>ed .....                                                                                        | 45385         |
| 177.870 (d) amended .....                                                                                                               | 45385         |
| 178.3 (a)(2) and (b)(2) amended .....                                                                                                   | 45386         |
| 178.33–8 (a) amended .....                                                                                                              | 45387         |
| 178.33–9 (a)(2) amended .....                                                                                                           | 45386         |
| 178.33a–2 (b) amended .....                                                                                                             | 45387         |
| 178.33a–8 (a) amended .....                                                                                                             | 45386         |
| 178.33a–9 (a)(2) amended .....                                                                                                          | 45386         |
| 178.35 (f)(1)(iv) amended .....                                                                                                         | 45185         |
| 178.36 (j) amended .....                                                                                                                | 45185         |
| (a)(1), (2), (e)(1), (f), (i)(2) and<br>(k)(3)(iii) amended .....                                                                       | 45386         |
| (a)(2)(iii) and (f) amended .....                                                                                                       | 45387         |
| 178.37 (a)(1), (2) introductory text,<br>(e)(1), (i)(2) and (k)(3)(iii)<br>amended .....                                                | 45386         |
| (a)(2)(iii) and (f)(1) amended;<br>(f)(2) and (3) revised .....                                                                         | 45387         |
| 178.38 (j) amended .....                                                                                                                | 45185         |
| (a), (e)(1), (f), (i)(2) and (k)(3)(iii)<br>amended .....                                                                               | 45386         |
| (o) introductory text amended<br>.....                                                                                                  | 45387         |
| (f) amended .....                                                                                                                       | 45388         |
| 178.39 (j) amended .....                                                                                                                | 45185         |
| (a)(1), (i)(2) and (k)(3)(iii) amend-<br>ed .....                                                                                       | 45386         |
| (f) amended .....                                                                                                                       | 35288         |
| 178.42 (a), (f)(1), (2) and (3) amend-<br>ed .....                                                                                      | 45386         |
| 178.44 (l) amended .....                                                                                                                | 45185         |
| (a), (f)(2), (i)(2) and (m)(3)(iii)<br>amended .....                                                                                    | 45386         |
| 178.45 (j)(4) amended .....                                                                                                             | 45185         |
| (d)(1) and (2)(ii) amended .....                                                                                                        | 45386         |

## 49 CFR—Continued

|                                                                                               | 66 FR<br>Page |
|-----------------------------------------------------------------------------------------------|---------------|
| (a) and (g)(4) amended .....                                                                  | 45387         |
| (d)(2)(iii) amended .....                                                                     | 35288         |
| 178.46 (c)(5)(ii), (g)(2), (3)(i), (ii)<br>and (iii) amended .....                            | 45387         |
| (d) amended .....                                                                             | 35288         |
| 178.47 (a) and (j)(2) amended .....                                                           | 45386         |
| (f) introductory text amended .....                                                           | 45387         |
| (f)(1) and (2) amended .....                                                                  | 35288         |
| 178.50 (d) introductory text<br>amended .....                                                 | 45185         |
| (a), (f)(1)(i), (ii), (iii), (i)(2) and<br>(k)(3)(iii) amended .....                          | 45386         |
| (f)(2) amended .....                                                                          | 35288         |
| 178.51 (g)(1) amended .....                                                                   | 45185         |
| (a) introductory text, (f)(1)(iii),<br>(2), (3), (j)(3)(iii), (k) and (l)(3)<br>amended ..... | 45386         |
| 178.53 (a), (h)(2) and (j)(5)(iii)<br>amended .....                                           | 45386         |
| (e) introductory text, (1) and (2)<br>amended .....                                           | 45388         |
| 178.55 (a) and (i)(2) amended .....                                                           | 45386         |
| (f) and (k)(3)(iii) amended .....                                                             | 45387         |
| 178.56 (a) and (i)(2) amended .....                                                           | 45386         |
| (f)(1)(ii), (2), (j)(3)(iii), (k) and<br>(l)(3) amended .....                                 | 45387         |
| 178.57 (a) introductory text<br>amended .....                                                 | 45386         |
| (d)(3), (f)(1), (j)(3)(iii), (k) and<br>(l)(3) amended .....                                  | 45387         |
| (f)(6) amended .....                                                                          | 45388         |
| 178.58 (a) and (i)(2) amended .....                                                           | 45386         |
| (m)(5)(iii) amended .....                                                                     | 45387         |
| (f)(1) and (2) amended .....                                                                  | 35288         |
| 178.59 (a) introductory text and<br>(h)(4) amended .....                                      | 45386         |
| (j)(3)(iii) amended .....                                                                     | 45387         |
| 178.60 (a) and (j)(4) amended .....                                                           | 45386         |
| (g)(1) introductory text,<br>(l)(3)(iii), (m) and (n)(3) amend-<br>ed .....                   | 45387         |
| (g)(1)(i) amended .....                                                                       | 45388         |
| 178.61 (a), (f)(3), (j)(3)(iii), (k) and<br>(l)(3) amended .....                              | 45387         |
| (f)(4) amended .....                                                                          | 35288         |
| 178.65 (d)(1) and (2) amended .....                                                           | 45389         |
| 178.68 (a) amended .....                                                                      | 45386         |
| (f)(1)(i), (2), (h)(4) introductory<br>text and (l)(1) amended .....                          | 45387         |
| 178.245–3 Note 1 amended .....                                                                | 45387         |
| 178.270–2 (c) amended .....                                                                   | 45386         |
| (b) amended .....                                                                             | 45389         |
| 178.270–4 (b)(1), (2) and (3) amend-<br>ed .....                                              | 45387         |
| 178.270–5 (d) .....                                                                           | 45387         |
| (b)(1) and (2) amended .....                                                                  | 45389         |
| 178.270–9 Amended .....                                                                       | 45387         |



## List of CFR Sections Affected

### 49 CFR—Continued

|                                                                                              | 66 FR<br>Page |
|----------------------------------------------------------------------------------------------|---------------|
| 178.270–10 (a) and (b) amended.....                                                          | 45387         |
| 178.270–11 (c)(4) amended.....                                                               | 45386         |
| (a)(2), (c)(1)(i) and (ii) amended<br>.....                                                  | 45387         |
| (a)(1) revised; (a)(2), (3), (b)(1),<br>(c)(2), (d)(4), (e)(2)(i), (ii), (4)<br>amended..... | 45389         |
| 178.270–12 (b) and (e) amended.....                                                          | 45387         |
| 178.270–13 (a) amended.....                                                                  | 45387         |
| 178.270–14 (b)(7) and (c)(2) amend-<br>ed.....                                               | 45387         |
| 178.271–1 (b) amended.....                                                                   | 45387         |
| (b) amended.....                                                                             | 45387         |
| 178.272–2 (b)(1) and (2) amended.....                                                        | 45387         |
| 178.273 Added.....                                                                           | 33439         |
| 178.274 Added.....                                                                           | 33440         |
| 178.275 Added.....                                                                           | 33445         |
| 178.276 Added.....                                                                           | 33448         |
| 178.277 Added.....                                                                           | 33450         |
| 178.318–3 Amended.....                                                                       | 45185         |
| 178.337–1 (b) Note 1 amended.....                                                            | 45387         |
| 178.337–8 (a)(3), (4)(i), (ii), (v) and<br>(vi) amended.....                                 | 45387         |
| 178.338–1 (a)(1) and (f)(1) amend-<br>ed.....                                                | 45387         |
| 178.345–1 (f) amended.....                                                                   | 45387         |
| (c) and (k) introductory text<br>amended.....                                                | 45389         |
| 178.345–10 (b)(3)(ii) amended.....                                                           | 45389         |
| 178.345–14 (b)(3) amended.....                                                               | 45389         |
| 178.346–1 (b) amended.....                                                                   | 45387         |
| 178.346–3 (b)(3) amended.....                                                                | 45389         |
| 178.347–1 (c) amended.....                                                                   | 45387         |
| 178.352–2 (a) amended.....                                                                   | 45387         |
| (b) revised.....                                                                             | 45389         |
| 178.352–3 (a), (b), (c)(1), (2)(i), (ii),<br>(iii) and (3) amended.....                      | 45387         |
| (a) and (c)(3) amended.....                                                                  | 45389         |
| 178.352–6 (a)(3) amended.....                                                                | 45386         |
| 178.354–2 (a) amended.....                                                                   | 45387         |
| 178.354–3 (a) introductory text,<br>(b), (c) introductory text and<br>(e) amended.....       | 45387         |
| 178.356–1 (b)(1), (2) and (3) amend-<br>ed.....                                              | 45387         |
| (c) amended.....                                                                             | 45389         |
| 178.356–2 (a)(2) and (c) amend-<br>ed.....                                                   | 45387         |
| 178.356–3 (a) amended.....                                                                   | 45387         |
| 178.358–1 (b) and (c) amended.....                                                           | 45387         |
| 178.358–2 (a) introductory text, (2)<br>and (3) amended.....                                 | 45387         |
| 178.358–3 (b)(2) and (4) revised;<br>(b)(3) amended.....                                     | 45389         |
| 178.358–5 (b)(5) amended.....                                                                | 45386         |
| 178.360–1 (b) amended.....                                                                   | 45387         |
| 178.360–3 (a) amended.....                                                                   | 45387         |

### 49 CFR—Continued

|                                                                                                                                                                                                                                                                                      | 66 FR<br>Page |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| 178.362–1 (b)(1) through (6) amend-<br>ed.....                                                                                                                                                                                                                                       | 45387         |
| 178.362–2 (a)(1), (2), (b), (d)(2), (3)<br>and (e)(1) through (5).....                                                                                                                                                                                                               | 45387         |
| 178.362–3 (b) amended.....                                                                                                                                                                                                                                                           | 45387         |
| 178.362–6 (b) amended.....                                                                                                                                                                                                                                                           | 45386         |
| 178.364–1 (b) amended.....                                                                                                                                                                                                                                                           | 45387         |
| 178.364–2 (a), (b), (d), (e) and (f)<br>amended.....                                                                                                                                                                                                                                 | 45387         |
| 178.364–3 Revised.....                                                                                                                                                                                                                                                               | 45389         |
| Amended.....                                                                                                                                                                                                                                                                         | 45387         |
| 178.503 (a)(8) and (c)(1)(ii) amend-<br>ed.....                                                                                                                                                                                                                                      | 45386         |
| 178.509 (b)(1) amended.....                                                                                                                                                                                                                                                          | 45386         |
| 178.601 (e), (g)(7), (h), (i) introduc-<br>tory text, (2) and (k) amend-<br>ed.....                                                                                                                                                                                                  | 45386         |
| 178.603 (b) amended.....                                                                                                                                                                                                                                                             | 45386         |
| 178.604 (b)(2) amended.....                                                                                                                                                                                                                                                          | 45386         |
| 178.605 (b) amended.....                                                                                                                                                                                                                                                             | 45386         |
| (d)(2), (3) and concluding text re-<br>vised.....                                                                                                                                                                                                                                    | 45390         |
| 178.606 (b) and (c)(1) amended.....                                                                                                                                                                                                                                                  | 45386         |
| 178.608 (b)(5) amended.....                                                                                                                                                                                                                                                          | 45386         |
| 178.700 (a) and (c) introductory<br>text amended.....                                                                                                                                                                                                                                | 45386         |
| (c)(1) amended.....                                                                                                                                                                                                                                                                  | 45387         |
| 178.702 Heading, (a) introductory<br>text, (1), (2) and (b) amend-<br>ed.....                                                                                                                                                                                                        | 45386         |
| (a)(1) table amended.....                                                                                                                                                                                                                                                            | 45387         |
| 178.703 Heading and (a)(1) intro-<br>ductory text revised; (a)(1)(ii)<br>amended.....                                                                                                                                                                                                | 33451         |
| Heading, (a)(1) introductory<br>text, (i), (ii), (iii)(A), (B), (C),<br>(v), (vi), (vii), (viii), (2)(i)<br>through (iv), (b) introductory<br>text, (1) introductory text, (i),<br>(2) introductory text, (i), (3),<br>(4), (5), (6) introductory text, (i)<br>and (ii) amended..... | 45386         |
| 178.704 Heading, (a), (b), (c) (d) in-<br>troductory text, (e) and (f)<br>amended.....                                                                                                                                                                                               | 45386         |
| 178.705 Heading and (c)(1)(iv)(A)<br>revised; (c)(1)(iv)(C) added.....                                                                                                                                                                                                               | 33452         |
| Heading, (a) introductory text,<br>(b) introductory text, (1), (2),<br>(c) introductory text, (1)(ii),<br>(iii) introductory text, (ii), (2)<br>introductory text and (i)<br>amended.....                                                                                            | 45386         |
| (c)(1)(iii)(A), (B), (c)(1)(iv)(A), (B)<br>(2)(i) amended.....                                                                                                                                                                                                                       | 45387         |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

66 FR  
Page

|                 |                                                                                                                                                                                                                                    |       |
|-----------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 178.706         | Heading, (a) introductory text, (1), (3), (5), (b), (c) introductory text, (1), (3) and (4) amended .....                                                                                                                          | 45386 |
|                 | (c)(4) amended .....                                                                                                                                                                                                               | 45387 |
| 178.707         | Heading, (a)(1) introductory text, (i) through (vi), (b) introductory text, (1), (c) introductory text, (2), (3) introductory text, (iv), (4) introductory text, (5) introductory text, (i), (ii), (iv) and (6) amended .....      | 45386 |
|                 | (c)(3)(iv) and (6) amended .....                                                                                                                                                                                                   | 45387 |
| 178.708         | Heading, (a), (b) introductory text, (1), (c) introductory text, (1), (2) introductory text, (ii), (3), (4) introductory text, (4)(i), (ii) and (iv) amended .....                                                                 | 45386 |
| 178.709         | Heading, (a) introductory text, (b) introductory text, (1), (c) introductory text, (1), (2) introductory text, (i), (iv), (3), (4) introductory text, (i), (ii) and (iv) amended .....                                             | 45386 |
| 178.710         | Heading, (a) introductory text, (b) introductory text, (1), (3), (c) introductory text, (1), (2) and (4) through (7) amended .....                                                                                                 | 45386 |
| 178.800–178.819 | (Subpart O) Heading revised .....                                                                                                                                                                                                  | 45386 |
| 178.801         | (i) amended .....                                                                                                                                                                                                                  | 33452 |
|                 | (a), (b), (c)(1), through (6), (7) introductory text, (ii), (d), (e)(1), (2) introductory text, (i), (ii), (f)(1), introductory text, (i), (ii), (2), (g), (h), (i), (j) introductory text, (2), (k), (l)(1) and (2) amended ..... | 45386 |
| 178.802         | Heading, (a) introductory text and (c) amended .....                                                                                                                                                                               | 45386 |
| 178.803         | Heading, introductory text and table amended .....                                                                                                                                                                                 | 45386 |
|                 | Table amended .....                                                                                                                                                                                                                | 45390 |
| 178.810         | (a), (b)(1), (2), (3), (c), (d)(1) introductory text, (3)(i) and (e) amended .....                                                                                                                                                 | 45386 |
| 178.811         | (a) through (d) amended .....                                                                                                                                                                                                      | 45386 |
| 178.812         | (c)(1) revised; (c)(3) added .....                                                                                                                                                                                                 | 33452 |
|                 | (a), (b)(1), (2), (c)(1), (2) introductory text and (d) amended .....                                                                                                                                                              | 45386 |
| 178.813         | (a) and (d) amended .....                                                                                                                                                                                                          | 45185 |
|                 | (a) through (d) amended .....                                                                                                                                                                                                      | 45386 |
| 178.814         | (a) amended .....                                                                                                                                                                                                                  | 45185 |

### 49 CFR—Continued

66 FR  
Page

|            |                                                                                                                   |       |
|------------|-------------------------------------------------------------------------------------------------------------------|-------|
|            | (a), (b), (c), (d)(1) through (4), (5) introductory text, (i)(A), (ii)(A), (B), (e)(1), (2) and (3) amended ..... | 45386 |
| 178.815    | (a), (b)(1), (2), (c)(1), (2), (3), (4) introductory text, (i), (ii), (d), (e)(1), (2) and (3) amended .....      | 45386 |
| 178.816    | (a), (b), (c), (d) introductory text and (e) amended .....                                                        | 45186 |
| 178.817    | (a) through (d) amended .....                                                                                     | 45386 |
| 178.818    | (a) through (d) amended .....                                                                                     | 45386 |
| 178.819    | (a), (b)(1), (2), (3) and (c) amended .....                                                                       | 45186 |
| 179.2      | Amended .....                                                                                                     | 45386 |
|            | (a)(4) and (9) removed .....                                                                                      | 45390 |
| 179.12     | (b) amended .....                                                                                                 | 45390 |
| 179.15     | (e) introductory text, (2), (f)(1), (3) and (4) amended .....                                                     | 45390 |
| 179.16     | (a)(3) amended .....                                                                                              | 45390 |
| 179.18     | (c) amended .....                                                                                                 | 45390 |
| 179.100    | Heading amended; second 179.100 redesignated as 179.101 .....                                                     | 45186 |
| 179.100–7  | (b) table amended .....                                                                                           | 45186 |
| 179.100–14 | (a) introductory text amended .....                                                                               | 45186 |
| 179.100–18 | (c) amended .....                                                                                                 | 45186 |
| 179.101    | Redesignated from second 179.100 .....                                                                            | 45186 |
| 179.101–1  | Table amended .....                                                                                               | 45390 |
| 179.102–4  | Introductory text amended .....                                                                                   | 33452 |
|            | (a) introductory text amended .....                                                                               | 45186 |
|            | (i) amended .....                                                                                                 | 45390 |
| 179.102–17 | (d) revised; (l) amended .....                                                                                    | 45390 |
| 179.103–5  | (b)(4) amended .....                                                                                              | 45186 |
| 179.200–1  | Heading amended .....                                                                                             | 45186 |
| 179.200–6  | (a), (b) and (c) amended .....                                                                                    | 45390 |
| 179.200–7  | (c) table and (h) amended .....                                                                                   | 45186 |
| 179.200–9  | (a) and (b) amended .....                                                                                         | 45186 |
| 179.200–11 | Amended .....                                                                                                     | 45186 |
| 179.200–13 | Heading amended .....                                                                                             | 45390 |
| 179.200–14 | (c) and (e)(2) amended .....                                                                                      | 45186 |
|            | (b) amended .....                                                                                                 | 45390 |
| 179.201–1  | Table amended .....                                                                                               | 45390 |
| 179.201–3  | (a)(1) and (2) amended .....                                                                                      | 45186 |
| 179.201–4  | Amended .....                                                                                                     | 45186 |
| 179.201–6  | (d) amended .....                                                                                                 | 45186 |
| 179.201–8  | (a) amended .....                                                                                                 | 45390 |

## List of CFR Sections Affected

### 49 CFR—Continued

|                                                                                                                                                                                                      | 66 FR<br>Page |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| 179.220-6 (a) and (b) amended .....                                                                                                                                                                  | 45390         |
| 179.220-7 (c) table amended .....                                                                                                                                                                    | 45186         |
| 179.220-24 Heading amended .....                                                                                                                                                                     | 45390         |
| Corrected .....                                                                                                                                                                                      | 49556         |
| 179.221-1 Table amended .....                                                                                                                                                                        | 45390         |
| 179.300-6 (a) amended .....                                                                                                                                                                          | 45186         |
| (a) and (b) amended .....                                                                                                                                                                            | 45390         |
| 179.300-15 Heading and (c) re-<br>vised .....                                                                                                                                                        | 45390         |
| 179.300-16 (b) amended .....                                                                                                                                                                         | 45390         |
| 179.300-17 Heading and (b) re-<br>vised; (c) amended .....                                                                                                                                           | 45390         |
| 179.301 (a) table amended .....                                                                                                                                                                      | 45390         |
| 179.400-4 (a)(5) amended .....                                                                                                                                                                       | 45186         |
| 179.400-8 (a) through (d) amend-<br>ed .....                                                                                                                                                         | 45391         |
| 179.400-9 (d) amended .....                                                                                                                                                                          | 45391         |
| 179.400-17 (a)(1) amended .....                                                                                                                                                                      | 45186         |
| 179.400-20 (d) amended .....                                                                                                                                                                         | 45391         |
| 179.400-25 (a) amended .....                                                                                                                                                                         | 45391         |
| 179.401-1 Table amended .....                                                                                                                                                                        | 45390         |
| 179.500-3 (d) amended .....                                                                                                                                                                          | 45186         |
| (c)(2) amended .....                                                                                                                                                                                 | 45391         |
| 179.500-4 (a) amended .....                                                                                                                                                                          | 45391         |
| 179.500-7 (b) amended .....                                                                                                                                                                          | 45391         |
| 179.500-10 (a) amended .....                                                                                                                                                                         | 45390         |
| 179.500-12 (a) amended .....                                                                                                                                                                         | 45391         |
| Heading amended .....                                                                                                                                                                                | 45391         |
| 179.500-16 Heading and (b) re-<br>vised; (a) amended .....                                                                                                                                           | 45391         |
| 179.500-17 (a)(5) and (6) revised .....                                                                                                                                                              | 45391         |
| 179.500-18 (c) table amended .....                                                                                                                                                                   | 45391         |
| Appendix A amended .....                                                                                                                                                                             | 45390         |
| 180.350 Amended .....                                                                                                                                                                                | 45391         |
| 180.351 Heading, (a) and (b)<br>amended .....                                                                                                                                                        | 45391         |
| 180.352 (b)(1) amended .....                                                                                                                                                                         | 45186         |
| (a), (b) heading, introductory<br>text, (3)(i), (ii), (c)(1), (2)(i) in-<br>troductory text, (A), (B), (C),<br>(ii) introductory text, (C), (iii)<br>introductory text, (B) and (f)<br>amended ..... | 45391         |
| 180.405 (h)(2), (m)(2), (3) and (n)<br>amended .....                                                                                                                                                 | 45391         |
| 180.409 (b) amended .....                                                                                                                                                                            | 45391         |
| 180.415 (b) amended .....                                                                                                                                                                            | 45187         |
| 180.419 (b)(1) amended .....                                                                                                                                                                         | 45187         |
| 180.509 (b)(2)(i), (ii) and (j)(2)<br>amended .....                                                                                                                                                  | 45391         |
| 180.511 (e) amended .....                                                                                                                                                                            | 45187         |
| 180.515 (c) amended .....                                                                                                                                                                            | 45391         |
| 180.519 (b)(1) amended .....                                                                                                                                                                         | 45187         |
| (b)(2), (3), (4) and (5) table amend-<br>ed .....                                                                                                                                                    | 45391         |
| (b)(3), (4) and (5) table .....                                                                                                                                                                      | 45392         |

### 49 CFR—Continued

|                                            | 66 FR<br>Page |
|--------------------------------------------|---------------|
| 180.601—180.605 (Subpart G)<br>Added ..... | 33452         |

## 2002

### 49 CFR

|                                                                                                                                                 | 67 FR<br>Page |
|-------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| Chapter I                                                                                                                                       |               |
| 105 Added .....                                                                                                                                 | 42951         |
| 105.25 (a)(2) amended; (b) re-<br>moved; (c) redesignated as new<br>(b); (b)(2)(iv) redesignated as<br>(b)(2)(v); new (b)(2)(iv)<br>added ..... | 61010         |
| 106 Revised .....                                                                                                                               | 42954         |
| 107.1—107.14 (Subpart A) Heading<br>revised .....                                                                                               | 42957         |
| 107.1 Removed; new 107.1 redesi-<br>gnated from 107.3 and amend-<br>ed .....                                                                    | 42958         |
| Amended .....                                                                                                                                   | 51639         |
| 107.3 Redesignated as 107.1 .....                                                                                                               | 42958         |
| 107.5 Removed .....                                                                                                                             | 42958         |
| 107.7 Removed .....                                                                                                                             | 42958         |
| 107.9 Removed .....                                                                                                                             | 42958         |
| 107.11 Removed .....                                                                                                                            | 42958         |
| 107.13 Removed .....                                                                                                                            | 42958         |
| 107.14 Removed .....                                                                                                                            | 42958         |
| 107.105 (a)(1) revised .....                                                                                                                    | 61010         |
| (a)(3) and (b) amended .....                                                                                                                    | 61011         |
| 107.107 (b)(1) revised .....                                                                                                                    | 61010         |
| (b)(4) amended .....                                                                                                                            | 61011         |
| 107.109 (a)(1) revised .....                                                                                                                    | 61011         |
| 107.111 Amended .....                                                                                                                           | 61011         |
| 107.117 (d)(3), (4) and (5) re-<br>vised .....                                                                                                  | 61011         |
| 107.127 (a) and (b) amended .....                                                                                                               | 61011         |
| 107.305 (a) and (b)(4) amended .....                                                                                                            | 61011         |
| 107.321 (b)(2) amended .....                                                                                                                    | 61011         |
| 107.402 (a) and (b)(1) amended .....                                                                                                            | 61011         |
| 107.502 (d) revised .....                                                                                                                       | 61011         |
| 107.503 (a)(7) amended .....                                                                                                                    | 61011         |
| 107.601 (a)(2) amended .....                                                                                                                    | 61011         |
| 107.608 (e) amended .....                                                                                                                       | 61011         |
| 107.612 (b)(1) amended .....                                                                                                                    | 58345         |
| 107.616 (a) and (b) revised .....                                                                                                               | 58345         |
| 107.705 (a)(1) revised; (a)(5) and (d)<br>amended .....                                                                                         | 61011         |
| 107.711 Amended .....                                                                                                                           | 61011         |
| 107.801—107.807 (Subpart I)<br>Added .....                                                                                                      | 51639         |
| 130.5 Amended .....                                                                                                                             | 61011         |
| 171.2 (d)(3) revised .....                                                                                                                      | 51640         |
| 171.6 (b)(2) table amended (OMB<br>numbers) .....                                                                                               | 51640, 61012  |
| 171.7 (a)(3) table amended .....                                                                                                                | 51640, 53132  |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

67 FR  
Page

|                                                               |                            |
|---------------------------------------------------------------|----------------------------|
| Chapter I—Continued                                           |                            |
| Regulation at 67 FR 53132 effective date corrected to 2–14–03 | 54967                      |
| (a)(2)(i) revised; (a)(3) table amended                       | 61012                      |
| 171.8 Corrected; CFR correction                               | 13095                      |
| Amended                                                       | 42958, 51641, 53133, 61012 |
| Regulation at 67 FR 53133 effective date corrected to 2–14–03 | 54967                      |
| 171.11 Introductory text amended                              | 61012                      |
| 171.12 (b)(5) and (e)(4) amended                              | 15739                      |
| (b)(15) revised                                               | 51641                      |
| (d) introductory text amended                                 | 61012                      |
| 171.14 (d)(4) amended                                         | 15739                      |
| (e) added                                                     | 53133                      |
| Regulation at 67 FR 53133 effective date corrected to 2–14–03 | 54967                      |
| 171.15 (a)(3) and (b) introductory text amended               | 53133                      |
| Regulation at 67 FR 53133 effective date corrected to 2–14–03 | 54967                      |
| 172.101 Appendix A amended                                    | 9927                       |
| Appendix A corrected                                          | 13680                      |
| (c)(11)(iv)(A) revised; table amended                         | 15739                      |
| Appendix B amended                                            | 15743                      |
| Table amended                                                 | 51641, 53133               |
| Regulation at 67 FR 53133 effective date corrected to 2–14–03 | 54967                      |
| Corrected                                                     | 57635                      |
| (j)(5) added; table and Appendix B amended                    | 61013                      |
| 172.102 (c)(1), (4), (7)(i) and (iv) table amended            | 15743                      |
| Amended                                                       | 53135                      |
| Regulation at 67 FR 53135 effective date corrected to 2–14–03 | 54967                      |
| (c)(1) amended; (c)(4) introductory text revised              | 61013                      |
| 172.201 Heading revised; (e) added                            | 46127                      |
| (e) revised                                                   | 66573                      |
| 172.203 (k) introductory text amended                         | 61013                      |
| 172.323 Added                                                 | 53135                      |
| Regulation at 67 FR 53135 effective date corrected to 2–14–03 | 54967                      |

### 49 CFR—Continued

67 FR  
Page

|                                                               |       |
|---------------------------------------------------------------|-------|
| Chapter I—Continued                                           |       |
| 172.407 (d)(4)(ii) amended                                    | 61013 |
| 172.432 Amended                                               | 53136 |
| Regulation at 67 FR 53136 effective date corrected to 2–14–03 | 54967 |
| 172.502 (b)(2) revised                                        | 53137 |
| Regulation at 67 FR 53137 effective date corrected to 2–14–03 | 54967 |
| 172.519 (b)(4) amended                                        | 15743 |
| 172 Appendix A corrected                                      | 13680 |
| 173.4 (a)(1)(ii) amended                                      | 61013 |
| 173.6 (a)(4) redesignated as (a)(5); new (a)(4) added         | 53137 |
| Regulation at 67 FR 53137 effective date corrected to 2–14–03 | 54967 |
| 173.10 (e) Note 2 amended                                     | 61013 |
| 173.21 (k) amended                                            | 61013 |
| 173.24b (e)(2) introductory text amended                      | 15743 |
| 173.28 (f) added                                              | 53138 |
| Regulation at 67 FR 53138 effective date corrected to 2–14–03 | 54967 |
| 173.32 (c)(2) amended                                         | 15743 |
| 173.34 Removed                                                | 51642 |
| 173.40 Revised                                                | 51642 |
| (b) revised                                                   | 61289 |
| 173.54 (f) amended                                            | 61013 |
| 173.115 (c)(2) amended; (j) revised                           | 51642 |
| (j) amended                                                   | 61013 |
| 173.150 (d)(2) amended                                        | 15743 |
| (e)(1) amended                                                | 61013 |
| 173.134 Revised                                               | 53138 |
| Regulation at 67 FR 53138 effective date corrected to 2–14–03 | 54967 |
| 173.163 Revised                                               | 51643 |
| 173.185 (a) amended; (e)(3) revised                           | 15743 |
| 173.192 Revised                                               | 51643 |
| 173.196 Revised                                               | 53140 |
| Regulation at 67 FR 53140 effective date corrected to 2–14–03 | 54967 |
| 173.197 Revised                                               | 53140 |
| Regulation at 67 FR 53140 effective date corrected to 2–14–03 | 54967 |
| 173.198 (a) amended                                           | 51643 |
| 173.199 Added                                                 | 53142 |
| Regulation at 67 FR 53142 effective date corrected to 2–14–03 | 54967 |

## List of CFR Sections Affected

### 49 CFR—Continued

67 FR  
Page

|                                                                                                 |              |
|-------------------------------------------------------------------------------------------------|--------------|
| Chapter I—Continued                                                                             |              |
| 173.225 (b)(3) amended .....                                                                    | 61013        |
| 173.226 (a) revised .....                                                                       | 51643, 61289 |
| 173.227 Heading and (a) revised .....                                                           | 51643        |
| 173.228 Revised .....                                                                           | 51643        |
| (b) revised .....                                                                               | 61289        |
| 173.242 (c) introductory text<br>amended .....                                                  | 15743        |
| 173.243 (c) amended .....                                                                       | 15743        |
| 173.247 Heading revised .....                                                                   | 61013        |
| 173.300a Removed .....                                                                          | 51643        |
| 173.300b Removed .....                                                                          | 51643        |
| 173.300c Removed .....                                                                          | 51643        |
| 173.301 Revised .....                                                                           | 51643        |
| (f)(2), (3) and (h)(1)(vii) revised;<br>(h)(2)(ii) and (iii) amended;<br>(h)(2)(iv) added ..... | 61289        |
| 173.301a Added .....                                                                            | 51645        |
| (d)(3) revised .....                                                                            | 61289        |
| 173.301b Added .....                                                                            | 51646        |
| 173.302 Revised .....                                                                           | 51646        |
| (b)(1) revised .....                                                                            | 61289        |
| 173.302a Added .....                                                                            | 51646        |
| 173.304 Revised .....                                                                           | 51647        |
| 173.304a Added .....                                                                            | 51647        |
| 173.305 (b) amended .....                                                                       | 51651        |
| (c)(1) amended .....                                                                            | 61013        |
| 173.306 (g)(5) revised .....                                                                    | 51651        |
| 173.315 (a) table Note 2 amended;<br>(q) added .....                                            | 51651        |
| (i)(1)(iv) and (j)(3) amended .....                                                             | 61013        |
| 173.316 (a)(4) amended .....                                                                    | 61013        |
| 173.318 (a)(4) amended .....                                                                    | 61013        |
| 173.320 (c) amended .....                                                                       | 61014        |
| 173.334 Revised .....                                                                           | 51651        |
| (f) amended .....                                                                               | 61014        |
| 173.336 Revised .....                                                                           | 51651        |
| 173.337 Revised .....                                                                           | 51651        |
| (a) and (b) amended .....                                                                       | 61014        |
| 173.415 (d) amended .....                                                                       | 61014        |
| 173.416 (b) amended .....                                                                       | 61014        |
| 173.417 (a)(5), (8)(i) and (b)(4)<br>amended .....                                              | 61014        |
| 173.420 (a)(2)(i), (iii), (b) and (c) re-<br>vised .....                                        | 61014        |
| 173.471 (d) and (e) revised .....                                                               | 61014        |
| 173.472 (f) revised .....                                                                       | 61014        |
| 173.473 (a)(1) and (2) revised .....                                                            | 61015        |
| 173.476 (c) introductory text re-<br>vised .....                                                | 61015        |
| 174.24 Revised .....                                                                            | 46128        |
| (b) revised .....                                                                               | 66574        |
| 174.81 (e)(6) and (g)(3)(vi) amend-<br>ed .....                                                 | 15743        |
| 175.10 (a)(5) amended .....                                                                     | 61015        |
| 175.30 (a)(2) revised .....                                                                     | 46128, 66574 |
| 175.320 (b)(5) amended .....                                                                    | 61015        |

### 49 CFR—Continued

67 FR  
Page

|                                                                                                         |              |
|---------------------------------------------------------------------------------------------------------|--------------|
| Chapter I—Continued                                                                                     |              |
| 176.2 Amended .....                                                                                     | 61015        |
| 176.24 Revised .....                                                                                    | 46128, 66574 |
| 176.84 (c)(2) amended .....                                                                             | 15744        |
| 176.128 (c) revised .....                                                                               | 61015        |
| 176.340 (b)(9) and (10) amended .....                                                                   | 61015        |
| 177.817 (a) revised; (f) added .....                                                                    | 46128        |
| (f) revised .....                                                                                       | 66574        |
| 177.834 (a) and (g) revised .....                                                                       | 53142        |
| 177.840 (a)(1) revised .....                                                                            | 51652        |
| (l) revised .....                                                                                       | 61015        |
| (a)(1) amended .....                                                                                    | 61289        |
| 177.843 (d) added .....                                                                                 | 53142        |
| 178.3 (b) introductory text, (1)<br>amended .....                                                       | 61015        |
| 178.35—178.68 (Subpart C) Appen-<br>dix A added .....                                                   | 51654        |
| 178.35 (b) introductory text, (1),<br>(c)(3)(iv), (d), (e) and (f)(3) re-<br>vised .....                | 51652        |
| 178.36 (k)(3)(i) amended .....                                                                          | 51652        |
| 178.37 (k)(3)(i) amended .....                                                                          | 51652        |
| 178.38 (k)(3)(i) amended .....                                                                          | 51652        |
| 178.39 (k)(3)(i) amended .....                                                                          | 51652        |
| 178.44 (m)(3)(i) amended .....                                                                          | 51652        |
| 178.45 (h) and (j)(3)(i) revised .....                                                                  | 51652        |
| 178.46 (b)(4) Table 1 revised; (b)(4)<br>Table 2 amended .....                                          | 51652        |
| 178.47 (d) amended .....                                                                                | 51653        |
| 178.50 (d) introductory text and<br>(k)(3)(i) amended .....                                             | 51653        |
| 178.51 (d)(2), (j)(3)(i), (l)(1), (2) and<br>(3) amended .....                                          | 51653        |
| (f)(1)(i) amended .....                                                                                 | 61015        |
| 178.53 (d) and (j)(5)(i) amended .....                                                                  | 51653        |
| 178.55 (k)(3)(i) amended .....                                                                          | 51653        |
| 178.56 (j)(3)(i), (l)(1), (2) and (3)<br>amended .....                                                  | 51653        |
| 178.57 (d)(5), (e)(3), (j)(3)(i), (l)(1),<br>(2), (3), (4)(v), (vi), (m)(1) and<br>(o)(1) amended ..... | 51653        |
| 178.58 (d)(1) and (m)(5)(i) amend-<br>ed .....                                                          | 51654        |
| (k)(2)(ii) revised .....                                                                                | 61015        |
| 178.59 (d) and (j)(3)(i) amended .....                                                                  | 51654        |
| (j)(3)(iv) amended .....                                                                                | 61016        |
| 178.60 (d), (l)(3)(i), (n)(1), (2) and (3)<br>amended .....                                             | 51654        |
| 178.61 (d)(4), (j)(3)(i), (l)(1), (2), (3)<br>and (m)(1) amended .....                                  | 51654        |
| (b)(1) and (2) amended .....                                                                            | 61016        |
| 178.65 (c)(4) amended .....                                                                             | 51654        |
| 178.68 (j)(3)(i) and (l)(2) amend-<br>ed .....                                                          | 51654        |
| 178.270–11 (d)(3) amended .....                                                                         | 61016        |
| 178.273 (b)(8)(ii) amended .....                                                                        | 61016        |
| 178.274 (a)(3) and (d)(1)(i) amend-<br>ed .....                                                         | 15744        |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

67 FR  
Page

|                                                                                                                            |       |
|----------------------------------------------------------------------------------------------------------------------------|-------|
| Chapter I—Continued                                                                                                        |       |
| 178.338–17 (b) amended.....                                                                                                | 61016 |
| 178.354–3 (a) introductory text amended.....                                                                               | 61016 |
| 178.356–3 (a) amended.....                                                                                                 | 61016 |
| 178.358–5 (c) amended.....                                                                                                 | 51660 |
| 178.362–1 (b)(6) amended .....                                                                                             | 61016 |
| 178.503 (f) added.....                                                                                                     | 53143 |
| (e)(3) amended.....                                                                                                        | 61016 |
| 178.601 (c)(1), (2) and (e) revised.....                                                                                   | 53143 |
| 178.603 (e) introductory text revised.....                                                                                 | 61016 |
| 178.609 Heading, (c) introductory text, (d)(1) introductory text, (i), (iii), (iv), (e), (h)(1), (2) and (i) revised ..... | 53143 |
| Regulation at 67 FR 53143 effective date corrected to 2–14–03 .....                                                        | 54967 |
| 178.707 (a) revised.....                                                                                                   | 61016 |
| 179.100–7 (c)(1) table amended.....                                                                                        | 51660 |
| 179.100–10 (c) amended.....                                                                                                | 51660 |
| 179.102–1 (a)(1) amended .....                                                                                             | 51660 |
| 179.102–4 (a)(1) amended .....                                                                                             | 51660 |
| 179.102–17 (b)(1) amended.....                                                                                             | 51660 |
| 179.200–7 (d) table amended .....                                                                                          | 51660 |
| 179.201–2 (a) amended.....                                                                                                 | 61016 |
| 179.201–5 (a) and (b) amended .....                                                                                        | 51660 |
| 179.220–7 (d) table amended .....                                                                                          | 51660 |
| 179.400–5 (a) introductory text amended.....                                                                               | 51660 |
| 179.500–10 (a) amended.....                                                                                                | 61016 |
| 180.201–180.215 (Subpart C) Added.....                                                                                     | 51660 |
| 180.417 (c)(2) amended .....                                                                                               | 61016 |
| 180.605 (d), (e) and (h)(3) amended .....                                                                                  | 15744 |
| 195.573 Corrected .....                                                                                                    | 70118 |
| 199 Random drug testing rate.....                                                                                          | 78388 |

## 2003

### 49 CFR

68 FR  
Page

|                                                             |       |
|-------------------------------------------------------------|-------|
| Chapter I                                                   |       |
| 105.5 (b) amended .....                                     | 52846 |
| 107 Authority citation revised .....                        | 52846 |
| 107.1 Amended .....                                         | 11749 |
| 107.105 (c)(10) added; interim .....                        | 23841 |
| 107.109 (a)(6) added; interim .....                         | 23842 |
| 107.201 (a)(1) and (2) revised; (c) removed .....           | 52846 |
| 107.202 (a) introductory text, (b)(1) and (2) revised ..... | 52847 |
| 107.203 (b)(1), (3) and (c) revised.....                    | 52847 |
| 107.209 (d) revised.....                                    | 52847 |

### 49 CFR—Continued

68 FR  
Page

|                                                                                                      |                     |
|------------------------------------------------------------------------------------------------------|---------------------|
| Chapter I—Continued                                                                                  |                     |
| 107.215 (a) amended; (b)(1), (4) and (5) revised .....                                               | 52847               |
| 107.219 (c)(1) and (2) revised .....                                                                 | 52847               |
| 107.221 (e) revised .....                                                                            | 52848               |
| 107.315 (c) and (d) amended .....                                                                    | 52848               |
| 107.329 (a) and (b) amended .....                                                                    | 52848               |
| 107.301–107.339 Appendix A (Subpart D) amended .....                                                 | 52848, 52855        |
| 107.501–107.504 (Subpart F) heading revised .....                                                    | 19273               |
| 107.502 (a)(1) and (d) revised.....                                                                  | 19273               |
| 107.503 (a)(3) through (7) redesignated as (a)(4) through (8); new (a)(3) added.....                 | 19273               |
| 107.612 (b) introductory text revised; (c) and (d) added .....                                       | 1345                |
| 107.616 (d)(2) revised .....                                                                         | 1346                |
| 107.803 (e) added .....                                                                              | 24659               |
| 107.805 (g) added .....                                                                              | 24659               |
| (f) amended interim .....                                                                            | 55544               |
| 171 Authority citation revised .....                                                                 | 52856               |
| 171.1 (c) amended .....                                                                              | 52856               |
| Revised .....                                                                                        | 61937               |
| 171.2 Revised .....                                                                                  | 61939               |
| 171.6 (b)(2) table amended (OMB numbers).....                                                        | 31628, 45010        |
| 171.7 (a)(3) table amended .....                                                                     | 1015, 19273, 45010  |
| (a)(3) table amended .....                                                                           | 48566               |
| (a)(3) table revised; (b) table amended .....                                                        | 75735               |
| 171.8 Amended .....                                                                                  | 19274, 45010        |
| Amended .....                                                                                        | 61940, 67758, 75740 |
| 171.10 (c)(1) revised .....                                                                          | 75740               |
| 171.11 (c), (d)(5) and (17) revised.....                                                             | 45010               |
| Introductory text amended .....                                                                      | 75741               |
| 171.12 (b)(15) amended .....                                                                         | 24659               |
| (b)(21) added .....                                                                                  | 32413               |
| (b)(3), (19), and (20) revised .....                                                                 | 45011               |
| (b) introductory text, (d) introductory text and (e)(5) revised .....                                | 75741               |
| 171.12a (b)(19) added; interim.....                                                                  | 23842               |
| (b)(13) amended .....                                                                                | 24659               |
| (b)(20) added .....                                                                                  | 32413               |
| (b)(18) revised.....                                                                                 | 45011               |
| (b) introductory text revised .....                                                                  | 75741               |
| 171.14 (f) added .....                                                                               | 14346               |
| (d) introductory text, (1), (2) introductory text, (4) and (5) revised; (6), (7), and (8) added..... | 45011               |
| 171.15 (b) introductory text revised.....                                                            | 57631               |
| Revised.....                                                                                         | 67759               |
| 171.16 (b) revised .....                                                                             | 57632               |

## List of CFR Sections Affected

### 49 CFR—Continued

|                                                                                                          | 68 FR<br>Page |
|----------------------------------------------------------------------------------------------------------|---------------|
| Chapter I—Continued                                                                                      |               |
| Revised .....                                                                                            | 67759         |
| 171.21 Revised .....                                                                                     | 67760         |
| 172.101 Table amended .....                                                                              | 19274         |
| (c)(15) introductory text revised;<br>table amended .....                                                | 45011         |
| Table amended .....                                                                                      | 48567         |
| Table corrected .....                                                                                    | 52368         |
| Table amended .....                                                                                      | 57632         |
| 172.102 (c)(1) amended .....                                                                             | 19277         |
| (c)(1), (2), (4), (5), (7)(iii) and (viii)<br>amended .....                                              | 45026         |
| (c)(1) amended .....                                                                                     | 57632         |
| (c)(1), (2), (3) and (7) amended .....                                                                   | 75741         |
| 172.201 (e) amended .....                                                                                | 57632         |
| 172.202 (a)(2), (5), and (b) revised;<br>(a)(6) added .....                                              | 45030         |
| (e) amended .....                                                                                        | 75741         |
| 172.203 (i)(1), (2), (3), and (6) re-<br>moved; (i)(4) and (5) redesign-<br>ated as (i)(1) and (2) ..... | 45030         |
| 172.301 (a)(1) revised .....                                                                             | 45030         |
| 172.312 (c)(6) added .....                                                                               | 45030         |
| 172.315 Added .....                                                                                      | 45030         |
| 172.321 Added .....                                                                                      | 45031         |
| (c)(5) revised .....                                                                                     | 57632         |
| 172.328 (d) added .....                                                                                  | 19277         |
| 172.332 (b)(3) revised .....                                                                             | 57632         |
| 172.400a (a)(1)(iv) revised .....                                                                        | 75742         |
| 172.401 (c)(1), (3) and (4) amend-<br>ed .....                                                           | 75741         |
| (c)(2) revised .....                                                                                     | 75742         |
| 172.411 Heading, (b) and (d) re-<br>vised; (e) and (f) added .....                                       | 45031         |
| 172.502 (b)(1) amended .....                                                                             | 75741         |
| 172.504 (g) introductory text re-<br>vised .....                                                         | 45031         |
| (d) revised .....                                                                                        | 48569         |
| 172.512 (a)(3) amended .....                                                                             | 75741         |
| 172.602 (a)(1) amended .....                                                                             | 75741         |
| 172.704 (a) introductory text, and<br>(b) revised; (a)(4), and (5)<br>added .....                        | 14521         |
| 172.800—172.804 (Subpart I)<br>Added .....                                                               | 14521         |
| 173.1 (c) removed; (d) redesign-<br>ated as (c) .....                                                    | 61941         |
| 173.2a (b) table amended .....                                                                           | 45032         |
| 173.3 (d) added .....                                                                                    | 48569         |
| (c)(2) amended .....                                                                                     | 61941         |
| 173.6 (b)(1) and (3) amended .....                                                                       | 61941         |
| (a)(2) revised .....                                                                                     | 75742         |
| 173.12 (c) introductory text re-<br>vised .....                                                          | 48569         |
| 173.21 (f)(3)(ii) revised .....                                                                          | 45032         |
| (f) introductory text and (3)(ii)<br>amended .....                                                       | 75742         |

### 49 CFR—Continued

|                                                                                                            | 68 FR<br>Page |
|------------------------------------------------------------------------------------------------------------|---------------|
| Chapter I—Continued                                                                                        |               |
| 173.22 (a)(4) revised .....                                                                                | 45032         |
| (a)(2)(iii) revised .....                                                                                  | 75742         |
| 173.24 (b) and (f) revised .....                                                                           | 45032         |
| (d)(2) amended .....                                                                                       | 75742         |
| 173.24a (a)(3) amended .....                                                                               | 61941         |
| 173.24b (e)(2) introductory text,<br>(i) and (iii) revised .....                                           | 75742         |
| 173.25 (a)(2) revised .....                                                                                | 45032         |
| 173.27 (e) revised; (i) added .....                                                                        | 45032         |
| 173.29 (c) introductory text re-<br>vised .....                                                            | 48569         |
| 173.30 Revised .....                                                                                       | 61941         |
| 173.31 (a)(7) added; (b)(2)(ii) re-<br>vised; (b)(5) amended .....                                         | 48569         |
| (g) added .....                                                                                            | 61941         |
| (b)(5) amended .....                                                                                       | 75743         |
| 173.32 (g)(1) revised; (h)(3)<br>added .....                                                               | 32413         |
| (c)(2) amended .....                                                                                       | 57632         |
| (c)(4)(i) amended .....                                                                                    | 75742         |
| (c)(4) introductory text and (i) re-<br>vised .....                                                        | 75743         |
| 173.33 (g) and (h) redesignated as<br>(c)(6) and (g); new (c)(6) head-<br>ing, and (g) heading added ..... | 19277         |
| 173.35 (b) amended .....                                                                                   | 48569         |
| 173.40 (b) and (d)(2) revised .....                                                                        | 24660         |
| 173.50 (a) revised .....                                                                                   | 48569         |
| 173.54 (c) revised .....                                                                                   | 48569         |
| 173.56 (b)(2)(i), (3)(i), (4), and (j)(1)<br>revised .....                                                 | 75743         |
| 173.57 (a) introductory text re-<br>vised .....                                                            | 75743         |
| 173.58 (a) introductory text re-<br>vised .....                                                            | 75743         |
| 173.62 (b) table and (c) table<br>amended .....                                                            | 45033         |
| (c) introductory text revised; (c)<br>table amended .....                                                  | 48569         |
| (c) table amended .....                                                                                    | 61941         |
| 173.63 (f)(2) revised .....                                                                                | 75743         |
| 173.115 (d) and (e) revised .....                                                                          | 45033         |
| (c)(2) amended .....                                                                                       | 75742         |
| 173.120 (a)(3), (4) and (b)(3) re-<br>vised .....                                                          | 75743         |
| 173.121 (b)(2)(i) revised .....                                                                            | 75744         |
| 173.124 (a)(2)(iii)(C), (iv), (3)(ii)<br>and (iii) revised .....                                           | 75744         |
| 173.125 (a) revised .....                                                                                  | 75744         |
| 173.127 (a)(1) revised .....                                                                               | 75744         |
| 173.128 (c)(3) and (e) revised .....                                                                       | 75744         |
| 173.134 (c)(1)(ii) revised .....                                                                           | 57632         |
| 173.137 Introductory text re-<br>vised .....                                                               | 75744         |
| 173.150 (f)(3)(vii), and (viii) re-<br>vised; (f)(3)(ix) added .....                                       | 19277         |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

68 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                                              |       |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 173.152 (b)(2) and (4)(ii) revised .....                                                                                                                                     | 45033 |
| 173.153 (b) introductory text amended; (b)(1) revised .....                                                                                                                  | 45033 |
| 173.154 (b)(2) revised .....                                                                                                                                                 | 45033 |
| 173.158 (b)(1)(v) revised .....                                                                                                                                              | 75744 |
| 173.159 (a) amended; (d)(4) added .....                                                                                                                                      | 45033 |
| 173.161 Revised .....                                                                                                                                                        | 45033 |
| 173.163 Revised .....                                                                                                                                                        | 24660 |
| 173.164 (a)(2) removed .....                                                                                                                                                 | 57632 |
| 173.166 (d)(3) redesignated as (4); (b), (c), (d)(2), new (4), (e) introductory text and (f) revised; (d)(3) redesignated as (d)(4); new (d)(3), (5), and (e)(5) added ..... | 45034 |
| (e) introductory text amended .....                                                                                                                                          | 57632 |
| (e)(4)(iii) amended .....                                                                                                                                                    | 61941 |
| 173.171 (d) amended .....                                                                                                                                                    | 61941 |
| 173.181 (a)(2) amended .....                                                                                                                                                 | 24660 |
| 173.181 (a)(2) amended .....                                                                                                                                                 | 61941 |
| 173.185 (e)(4) and (7) revised; (5) removed; (k) added .....                                                                                                                 | 45034 |
| (e)(4), (g)(1) and (2) amended .....                                                                                                                                         | 61941 |
| (c)(3) and (e)(6) amended .....                                                                                                                                              | 75742 |
| 173.189 (b) and (d)(4)(i) amended .....                                                                                                                                      | 61941 |
| 173.197 (e)(1)(i) revised .....                                                                                                                                              | 57632 |
| (c) introductory text revised .....                                                                                                                                          | 75744 |
| 173.198 (a) amended .....                                                                                                                                                    | 75742 |
| 173.216 (b) removed .....                                                                                                                                                    | 45034 |
| 173.218 (a) introductory text revised; (b) removed .....                                                                                                                     | 45034 |
| 173.219 (b)(3) amended .....                                                                                                                                                 | 61941 |
| 173.220 (a)(2) revised; (c) amended; (e) redesignated as (f); new (e) added .....                                                                                            | 45035 |
| 173.223 Added .....                                                                                                                                                          | 45035 |
| 173.224 (b)(4) and (7) table amended .....                                                                                                                                   | 45035 |
| 173.225 (b)(6) and (e)(5) revised; (b)(8) table and (e)(3)(xii) amended .....                                                                                                | 45036 |
| (e)(3)(vi) amended .....                                                                                                                                                     | 75742 |
| (e)(4) revised .....                                                                                                                                                         | 75744 |
| 173.226 (a) revised .....                                                                                                                                                    | 24660 |
| 173.228 (b) revised .....                                                                                                                                                    | 24660 |
| 173.241 (c) amended .....                                                                                                                                                    | 57632 |
| 173.242 (c)(4) added .....                                                                                                                                                   | 32413 |
| 173.243 (c) amended .....                                                                                                                                                    | 32413 |
| 173.244 (c) revised .....                                                                                                                                                    | 45037 |
| 173.249 (d) revised .....                                                                                                                                                    | 75745 |

### 49 CFR—Continued

68 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                                              |       |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 173.301 (a) and (h)(3) introductory text amended; (a)(3), (f)(2), (3), (g)(1) introductory text, (h)(2)(iv) and (i)(3) revised; (m) redesignated as (n); new (m) added ..... | 24660 |
| (h)(2) introductory text and (3) introductory text corrected .....                                                                                                           | 32680 |
| (g) amended .....                                                                                                                                                            | 75742 |
| (f)(1) revised .....                                                                                                                                                         | 75745 |
| 173.301a (d)(3) revised .....                                                                                                                                                | 24661 |
| 173.302 (b)(3) revised .....                                                                                                                                                 | 75745 |
| 173.302a (b)(3)(i)(A) and (iii) revised .....                                                                                                                                | 75745 |
| 173.303 (a) and (e) revised .....                                                                                                                                            | 75745 |
| 173.304 (b) and (d) amended .....                                                                                                                                            | 24661 |
| 173.304a (a)(2) table and (d)(4) amended; (c) revised .....                                                                                                                  | 24661 |
| (a)(2) table amended .....                                                                                                                                                   | 57632 |
| (e)(1)(ii) amended .....                                                                                                                                                     | 75742 |
| 173.305 (b) amended .....                                                                                                                                                    | 24662 |
| 173.306 (g)(5) revised .....                                                                                                                                                 | 24662 |
| (f) heading revised; (j) added .....                                                                                                                                         | 45038 |
| (e)(1)(iii) and (v) revised .....                                                                                                                                            | 75745 |
| 173.307 (a)(5) added .....                                                                                                                                                   | 45038 |
| (a)(4)(iv) revised .....                                                                                                                                                     | 75745 |
| 173.308 (a)(4) amended .....                                                                                                                                                 | 61941 |
| 173.314 (k) and (m) amended .....                                                                                                                                            | 48570 |
| 173.315 (j)(2) and (k)(4) revised; (n)(1) table amended .....                                                                                                                | 48570 |
| (b)(1) revised .....                                                                                                                                                         | 57633 |
| (a) Notes 3, 11 and 15, (i)(1)(i), (13), (j)(1), (k) introductory text, (3), (l)(5) and (m)(1) revised .....                                                                 | 75745 |
| 173.316 (a)(4) amended .....                                                                                                                                                 | 75742 |
| 173.318 (a)(4) amended .....                                                                                                                                                 | 75742 |
| (b)(2)(i) introductory text and (9)(ii) revised .....                                                                                                                        | 75746 |
| 173.320 (a)(2) revised .....                                                                                                                                                 | 48570 |
| (c) revised .....                                                                                                                                                            | 75746 |
| 173.323 (b)(3) amended .....                                                                                                                                                 | 75746 |
| 173.335 (c) amended .....                                                                                                                                                    | 61941 |
| 173.336 Revised .....                                                                                                                                                        | 75746 |
| 173.337 (a) revised .....                                                                                                                                                    | 57633 |
| (b) revised .....                                                                                                                                                            | 75746 |
| 173.411 (b)(5)(ii) and (iii) revised .....                                                                                                                                   | 75747 |
| 173.412 (l) amended .....                                                                                                                                                    | 57633 |
| 173.415 (d) amended .....                                                                                                                                                    | 75742 |
| 173.416 (f) amended .....                                                                                                                                                    | 61941 |
| (b) amended .....                                                                                                                                                            | 75742 |
| 173.417 (a)(5), (8)(i) and (b)(4) amended .....                                                                                                                              | 75742 |
| 173.418 (e) added .....                                                                                                                                                      | 45038 |
| 173.420 (a)(2)(i) revised .....                                                                                                                                              | 57633 |
| (b) and (c) amended .....                                                                                                                                                    | 75742 |



## List of CFR Sections Affected

### 49 CFR—Continued

68 FR  
Page

|                                                                                                                                   |              |
|-----------------------------------------------------------------------------------------------------------------------------------|--------------|
| Chapter I—Continued                                                                                                               |              |
| (a)(1) and (2)(iii) introductory text revised.....                                                                                | 75747        |
| 173.422 (a)(2), (3) and (4) revised.....                                                                                          | 45038        |
| 173.469 (d)(1) amended .....                                                                                                      | 75742        |
| (a)(4)(ii) revised .....                                                                                                          | 75747        |
| 173.473 (a)(1) amended .....                                                                                                      | 75742        |
| Introductory text revised.....                                                                                                    | 75747        |
| 173 Appendix H amended .....                                                                                                      | 75747        |
| 174.55 (c) revised .....                                                                                                          | 75747        |
| 174.63 (c)(2), (3) and (4) revised.....                                                                                           | 75747        |
| 174.67 (a)(1), (2), (3), (i) and (j) revised; (a)(4) and (k) redesignated as (a)(6) and (l); new (a)(4), (5) and (k) added; ..... | 61941        |
| 174.110 Amended .....                                                                                                             | 61942        |
| 174.112 (b) and (c)(3) amended .....                                                                                              | 61942        |
| 174.115 (a) and (b)(3) amended .....                                                                                              | 61942        |
| 175.10 (a)(4)(v) added; (a)(25) revised.....                                                                                      | 45038        |
| 175.30 (a)(5) added .....                                                                                                         | 45038        |
| 175.31 (a) introductory text revised.....                                                                                         | 57633        |
| 175.33 (a)(1) introductory text revised; (a)(7) and (8) redesignated as (a)(9) and (10); (a)(7), (8), (c) and (d) added .....     | 14347        |
| (a)(1) introductory text revised .....                                                                                            | 75747        |
| 175.81 (a) amended.....                                                                                                           | 61942        |
| 175.90 (b) and (c) revised .....                                                                                                  | 45038        |
| 176.2 Amended .....                                                                                                               | 75747, 75748 |
| 176.5 (b)(8) amended .....                                                                                                        | 75747        |
| 176.7 Added; interim .....                                                                                                        | 23842        |
| 176.11 (a) introductory text amended.....                                                                                         | 75747        |
| 176.27 (c)(2) revised .....                                                                                                       | 45038        |
| (b) amended .....                                                                                                                 | 75747        |
| 176.30 (a) introductory text amended .....                                                                                        | 75747        |
| 176.63 (f) added .....                                                                                                            | 45038        |
| 176.69 (d) amended.....                                                                                                           | 61942        |
| 176.76 (a)(2) amended .....                                                                                                       | 61942        |
| 176.78 (f)(8) amended .....                                                                                                       | 61942        |
| 176.83 (f) revised; (l) added .....                                                                                               | 45039        |
| 176.84 (b) table amended .....                                                                                                    | 45040        |
| 176.93 (a)(1) amended.....                                                                                                        | 61942        |
| 176.116 (d) amended .....                                                                                                         | 61942        |
| 176.132 (c) amended .....                                                                                                         | 61942        |
| 176.140 (b) amended .....                                                                                                         | 45041        |
| (b) introductory text amended .....                                                                                               | 75748        |
| 176.168 (g) amended .....                                                                                                         | 61942        |
| 176.170 (b) removed.....                                                                                                          | 45041        |
| 176.200 (b) and (c) amended .....                                                                                                 | 61942        |
| 176.340 (a) revised.....                                                                                                          | 57633        |

### 49 CFR—Continued

68 FR  
Page

|                                                                                                                                                                |       |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| Chapter I—Continued                                                                                                                                            |       |
| 176.410 (a)(2) revised; (a)(3), (5), and (6) removed; (a)(4) redesignated as (a)(3) .....                                                                      | 45041 |
| 176.415 (a) introductory text, (1), (2), (b)(1), (c)(1), and (2) revised; (b)(3), (4), and (c)(5) removed; (b)(5) and (6) redesignated as (b)(3) and (4) ..... | 45041 |
| 176.720 Revised .....                                                                                                                                          | 75748 |
| 177.804 Revised; interim .....                                                                                                                                 | 23842 |
| 177.817 (a) revised.....                                                                                                                                       | 19277 |
| (f) amended.....                                                                                                                                               | 57633 |
| 177.834 (j) introductory text revised.....                                                                                                                     | 19277 |
| (o) revised .....                                                                                                                                              | 32414 |
| (a) revised; (b) added .....                                                                                                                                   | 48570 |
| (a) amended .....                                                                                                                                              | 61942 |
| 177.835 (c)(4)(iii) revised .....                                                                                                                              | 48570 |
| (a)(3)(ii) amended.....                                                                                                                                        | 75748 |
| 177.837 heading and (a) revised.....                                                                                                                           | 48570 |
| 177.840 (a)(1) revised.....                                                                                                                                    | 24662 |
| (b)(3) amended.....                                                                                                                                            | 61942 |
| (u) revised.....                                                                                                                                               | 75748 |
| 177.841 Heading and (e)(1) revised.....                                                                                                                        | 48571 |
| 177.854 (f)(1) revised .....                                                                                                                                   | 57633 |
| 177.870 (e) amended .....                                                                                                                                      | 61942 |
| 178.2 (c)(1)(ii) revised .....                                                                                                                                 | 45041 |
| 178.3 (b)(1) revised.....                                                                                                                                      | 75748 |
| 178.35 (g) revised .....                                                                                                                                       | 75748 |
| 178.36 (k)(3)(i) amended .....                                                                                                                                 | 75748 |
| 178.37 (k)(3)(i) amended.....                                                                                                                                  | 75748 |
| 178.38 (k)(3)(i) amended.....                                                                                                                                  | 75748 |
| 178.39 (k)(3)(i) amended.....                                                                                                                                  | 75748 |
| 178.44 (m)(3)(i) amended.....                                                                                                                                  | 75748 |
| (b) introductory text revised .....                                                                                                                            | 75749 |
| 178.45 (h) introductory text amended.....                                                                                                                      | 48571 |
| (j)(3)(i) amended.....                                                                                                                                         | 75748 |
| (f)(5)(ii), (iii), (iv) and (j)(4) revised .....                                                                                                               | 75749 |
| 178.46 (b)(4) Table 1 amended; (e)(5)(ii)(A), (B), (iii)(A), (B), (C), (iv) and (i)(3)(i) revised.....                                                         | 75749 |
| 178.47 (d) amended .....                                                                                                                                       | 75748 |
| 178.50 (d) and (k)(3)(i) amended.....                                                                                                                          | 75748 |
| 178.51 (d)(2), (j)(3)(i), (l)(1), (2) and (3) amended .....                                                                                                    | 75748 |
| 178.53 (d) and (j)(5)(i) amended.....                                                                                                                          | 75748 |
| 178.55 (k)(3)(i) amended.....                                                                                                                                  | 75748 |
| (d)(3) revised .....                                                                                                                                           | 75749 |
| 178.56 (j)(3)(i), (l)(1), (2) and (3) amended.....                                                                                                             | 75748 |
| (d)(3) revised .....                                                                                                                                           | 75749 |
| 178.57 (d)(5), (e)(3), (j)(3)(i), (l)(1), (2), (3), (4)(v), (vi), (m)(1) and (o)(1) amended .....                                                              | 75748 |

## 49 CFR (10-1-08 Edition)

### 49 CFR—Continued

68 FR  
Page

#### Chapter I—Continued

|                                                                                                                                    |       |
|------------------------------------------------------------------------------------------------------------------------------------|-------|
| 178.58 (d)(1) and (m)(5)(i) amended .....                                                                                          | 75748 |
| 178.59 (d) and (j)(3)(i) amended .....                                                                                             | 75748 |
| (l)(1)(v) revised .....                                                                                                            | 75749 |
| 178.60 (d), (l)(3)(i), (n)(1), (2) and (3) amended .....                                                                           | 75748 |
| (p)(1)(v) revised .....                                                                                                            | 75749 |
| 178.61 (g) amended .....                                                                                                           | 57633 |
| (d)(4), (j)(3)(i), (l)(1), (2), (3) and (m)(1) amended .....                                                                       | 75748 |
| 178.65 (c)(4) amended .....                                                                                                        | 75748 |
| (b)(2) revised .....                                                                                                               | 75749 |
| 178.68 (j)(3)(i) and (l)(2) amended .....                                                                                          | 75748 |
| 178.245-1 (a) revised .....                                                                                                        | 75749 |
| 178.245-3 (a) and Note 1 revised .....                                                                                             | 75749 |
| 178.245-4 (b) revised .....                                                                                                        | 75750 |
| 178.245-6 (a) amended .....                                                                                                        | 75750 |
| 178.245-7 (a) revised .....                                                                                                        | 75750 |
| 178.255-1 (b) revised .....                                                                                                        | 75750 |
| 178.255-2 (a) revised .....                                                                                                        | 75750 |
| 178.255-14 (a) revised .....                                                                                                       | 75750 |
| 178.255-15 (a) amended .....                                                                                                       | 75750 |
| 178.270-2 (c) revised .....                                                                                                        | 75750 |
| 178.270-3 (a) and (b)(1) revised; (e) amended .....                                                                                | 75750 |
| 178.270-7 Revised .....                                                                                                            | 75750 |
| 178.270-9 Revised .....                                                                                                            | 75750 |
| 178.270-11 (d)(6) introductory text revised .....                                                                                  | 75751 |
| 178.270-12 (f) revised .....                                                                                                       | 75751 |
| 178.271-1 (c) revised .....                                                                                                        | 75751 |
| 178.272-1 (c) revised .....                                                                                                        | 75751 |
| 178.273 (c)(1) amended .....                                                                                                       | 75748 |
| (b)(6)(i) revised .....                                                                                                            | 75751 |
| 178.274 (j)(6) revised .....                                                                                                       | 45041 |
| (b)(1) and (i)(1) amended .....                                                                                                    | 57633 |
| (a)(3) and (b)(1) amended; (c)(5), (11), (d)(1)(ii), (3), (f)(1)(v), (h)(5)(iv), (i)(1) introductory text and (j)(6) revised ..... | 75751 |
| 178.275 (d)(3)(iv) revised .....                                                                                                   | 32414 |
| 178.276 (a)(1), (b)(2)(i) and (c)(7) amended .....                                                                                 | 75748 |
| (f) amended .....                                                                                                                  | 75752 |
| 178.277 (a), (b)(1), (3) and (e)(4)(iv) amended .....                                                                              | 75748 |
| (b)(2) and (13) revised .....                                                                                                      | 75752 |
| 178.320 (a) and (b)(1) revised .....                                                                                               | 19277 |
| (a) corrected; (b)(1) correctly revised .....                                                                                      | 52370 |
| (a) amended .....                                                                                                                  | 75752 |
| 178.337-1 (a)(2) and (f) revised .....                                                                                             | 75752 |
| 178.337-2 (a)(1), (b)(1)(i), (2)(i) and (ii) revised; (a)(2) amended .....                                                         | 75752 |
| 178.337-3 (b), (e) and (g) revised .....                                                                                           | 19279 |

### 49 CFR—Continued

68 FR  
Page

#### Chapter I—Continued

|                                                                                          |       |
|------------------------------------------------------------------------------------------|-------|
| (b)(1) correctly revised .....                                                           | 52370 |
| (a)(1), (b) and (g)(3)(i) revised; (g)(2) amended .....                                  | 75753 |
| 178.337-4 (a) and (e) revised; (b) amended .....                                         | 75753 |
| 178.337-6 (a) revised .....                                                              | 75753 |
| 178.337-8 (a)(5)(iii) revised .....                                                      | 19279 |
| (b)(1) and (2) revised .....                                                             | 75753 |
| 178.337-9 (b)(2) revised; (b)(5) removed .....                                           | 19279 |
| (b)(2) correctly revised .....                                                           | 52370 |
| (b)(8) revised .....                                                                     | 75753 |
| 178.337-10 Heading, (c) and (d) revised; (e) and (f) added .....                         | 19280 |
| (c) and (f) correctly revised .....                                                      | 52370 |
| (a) revised .....                                                                        | 57633 |
| (d)(1) revised .....                                                                     | 75753 |
| 178.337-12 Removed .....                                                                 | 19280 |
| 178.337-13 Revised .....                                                                 | 19280 |
| 178.337-16 (a), (b)(1) and (2) revised .....                                             | 75753 |
| 178.337-17 Revised .....                                                                 | 19280 |
| (b) and (c) correctly revised .....                                                      | 52370 |
| (d) revised .....                                                                        | 57633 |
| 178.337-18 (a)(3) and (4) redesignated as (a)(5) and (6); new (a)(3) and (4) added ..... | 19281 |
| (a) introductory text revised .....                                                      | 75754 |
| 178.338-1 (a)(1) and (c) revised .....                                                   | 75754 |
| 178.338-2 (c) revised .....                                                              | 19281 |
| (a), (c) and (e) revised .....                                                           | 75754 |
| 178.338-3 (b) and (g) revised .....                                                      | 19281 |
| (c)(3)(ii) through (vi) and (4) amended .....                                            | 57633 |
| (b) and (g)(3)(i) revised; (g)(2) amended .....                                          | 75754 |
| 178.338-4 (a) revised .....                                                              | 75754 |
| 178.338-5 (a) revised .....                                                              | 75754 |
| 178.338-6 (a) revised .....                                                              | 75754 |
| 178.338-9 (c)(2) amended .....                                                           | 57634 |
| 178.338-10 Heading (c) revised .....                                                     | 19282 |
| (c)(2) correctly revised .....                                                           | 52371 |
| 178.338-11 (c) revised .....                                                             | 19282 |
| 178.338-13 Revised .....                                                                 | 19282 |
| (a) introductory text and (b) introductory text amended .....                            | 75754 |
| 178.338-15 Revised .....                                                                 | 75755 |
| 178.338-16 (a) and (d) revised; (c) amended .....                                        | 75755 |
| 178.338-17 (b) revised .....                                                             | 75755 |
| 178.338-18 Revised .....                                                                 | 19283 |
| (d) revised .....                                                                        | 57634 |
| (a)(1) and (3) revised .....                                                             | 75755 |
| 178.338-19 (a)(1) revised .....                                                          | 75755 |
| 178.345-1 (c) revised; (k) removed .....                                                 | 19283 |

## List of CFR Sections Affected

### 49 CFR—Continued

|                                                                           | 68 FR<br>Page |
|---------------------------------------------------------------------------|---------------|
| Chapter I—Continued                                                       |               |
| (c) corrected.....                                                        | 52371         |
| (f) revised.....                                                          | 75755         |
| 178.345–2 (b) revised.....                                                | 19283         |
| (a) introductory text and (1) re-<br>vised.....                           | 75755         |
| 178.345–3 (b)(3) added; (f) re-<br>vised.....                             | 19283         |
| (a)(1), (b) introductory text, (1)<br>and (2) revised.....                | 75755         |
| 178.345–4 (a) revised.....                                                | 75756         |
| 178.345–5 (e) introductory text re-<br>vised.....                         | 19284         |
| 178.345–7 (a)(1) and (d)(3) re-<br>vised.....                             | 75756         |
| 178.345–8 (a)(5), and (d) introduc-<br>tory text revised.....             | 19284         |
| 178.345–10 (a) revised; (b)(3)(i)<br>amended.....                         | 19284         |
| 178.345–13 (a) revised.....                                               | 19284         |
| 178.345–14 (b)(1) and (c)(1) through<br>(10) revised.....                 | 19284         |
| (c)(4) and (7) correctly revised.....                                     | 52371         |
| (a) amended.....                                                          | 75756         |
| 178.345–15 (b)(2) revised.....                                            | 75756         |
| 178.346–1 (d)(6) and (7) amended.....                                     | 19285         |
| (d) introductory text, (1), (8), and<br>(10) revised.....                 | 75756         |
| 178.346–2 Introductory text, and<br>Tables I and II amended.....          | 19285         |
| 178.346–3 (b)(3) revised.....                                             | 75756         |
| 178.346–5 (c) revised.....                                                | 19285         |
| 178.347–1 (c) revised; (d)(5), (6), and<br>(7) amended; (d)(9) added..... | 19285         |
| (d)(8) correctly added.....                                               | 52371         |
| (c), (d) introductory text, (1) and<br>(8) revised.....                   | 75756         |
| 178.347–2 Introductory text, and<br>Tables I and II amended.....          | 19285         |
| 178.348–1 (e)(2)(v), (vi), and (vii)<br>amended.....                      | 19285         |
| (e)(1), (2) introductory text, (i)<br>and (viii) revised.....             | 75756         |
| 178.348–2 Introductory text, and<br>Tables I and II amended.....          | 19285         |
| 178.356–1 (e) revised.....                                                | 75757         |
| 178.356–2 (a) introductory text, (d)<br>and (e) revised.....              | 75757         |
| 178.358–1 (a)(1) and (2) revised.....                                     | 75757         |
| 178.358–2 (a) introductory text, (b)<br>and (f) revised.....              | 75757         |
| 178.358–3 (a) and (b)(5) revised.....                                     | 75757         |
| 178.358–4 (a) revised.....                                                | 75757         |
| 178.358–5 (c) amended.....                                                | 75748         |
| 178.360–4 (a)(2) introductory text<br>and (i) revised.....                | 75757         |
| 178.503 (a)(9)(i) revised.....                                            | 75757         |

### 49 CFR—Continued

|                                                                                                                                                  | 68 FR<br>Page |
|--------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| Chapter I—Continued                                                                                                                              |               |
| 178.516 (b)(1) revised.....                                                                                                                      | 75758         |
| 178.601 (g)(1)(i)(D), (ii) and (4)(v)<br>amended.....                                                                                            | 61942         |
| (g)(8) introductory text revised<br>.....                                                                                                        | 75758         |
| 178.704 (d)(3) amended.....                                                                                                                      | 61942         |
| 178.705 (c)(1)(iv)(A) revised.....                                                                                                               | 45041         |
| 178.707 (c)(4)(iv)(A) revised.....                                                                                                               | 75758         |
| 178.708 (c)(2) introductory text<br>and (i) revised.....                                                                                         | 75758         |
| 178.801 (i) revised.....                                                                                                                         | 75758         |
| 178.812 (b)(1) revised.....                                                                                                                      | 45042         |
| 178 Appendices A and C amend-<br>ed.....                                                                                                         | 75758         |
| 179.1 (a) revised.....                                                                                                                           | 48571         |
| 179.2 (a)(8) revised.....                                                                                                                        | 75759         |
| 179.3 (b) and (c) revised.....                                                                                                                   | 48571         |
| 179.5 (a), (b) and (d) amended; (c)<br>revised.....                                                                                              | 48571         |
| 179.6 Revised.....                                                                                                                               | 75759         |
| 179.7 (f) revised.....                                                                                                                           | 48571         |
| (b)(8) revised.....                                                                                                                              | 75759         |
| 179.15 (a), (c), (d) and (h) re-<br>vised.....                                                                                                   | 75759         |
| 179.16 (c)(2) and (3) revised.....                                                                                                               | 75759         |
| 179.20 Revised.....                                                                                                                              | 75759         |
| 179.22 (a) revised.....                                                                                                                          | 75759         |
| 179.100–7 (a) table, (b) introduc-<br>tory text and (c)(2)(i) introduc-<br>tory text revised.....                                                | 75759         |
| 179.100–9 (a) revised.....                                                                                                                       | 75759         |
| 179.100–10 (c) amended.....                                                                                                                      | 75758         |
| (a) revised.....                                                                                                                                 | 75759         |
| 179.100–12 (a) revised.....                                                                                                                      | 75760         |
| 179.100–13 (b) and (c) amended.....                                                                                                              | 48571         |
| (e) revised.....                                                                                                                                 | 75760         |
| 179.100–14 (a)(1) revised.....                                                                                                                   | 75760         |
| 179.100–18 (c) amended.....                                                                                                                      | 75760         |
| 179.101–1 Table amended.....                                                                                                                     | 75760         |
| 179.102–1 (a)(1) revised.....                                                                                                                    | 75760         |
| 179.102–2 (a)(1) revised.....                                                                                                                    | 75760         |
| 179.102–4 Heading revised.....                                                                                                                   | 57634         |
| (a)(1) amended.....                                                                                                                              | 75758         |
| (a)(2) introductory text, (i), (ii)<br>and (iii)(A) revised.....                                                                                 | 75760         |
| 179.102–17 (b)(1) amended.....                                                                                                                   | 75758         |
| (b)(2) introductory text, (i), (ii)<br>and (iii)(A) revised.....                                                                                 | 75760         |
| 179.103–5 (b)(1) amended.....                                                                                                                    | 75761         |
| 179.200–179.222–1 (Subpart D)<br>Heading revised.....                                                                                            | 48571         |
| 179.200 Heading revised.....                                                                                                                     | 48571         |
| 179.200–7 (b) table, (c) introduc-<br>tory text, (d) introductory text<br>footnote 2, (e) table, (f) intro-<br>ductory text and (h) revised..... | 75761         |

## 49 CFR (10-1-08 Edition)

### 49 CFR—Continued

68 FR  
Page

|                                                                                                                           |       |
|---------------------------------------------------------------------------------------------------------------------------|-------|
| Chapter I—Continued                                                                                                       |       |
| 179.200-9 (a) revised.....                                                                                                | 75761 |
| 179.200-10 (a) revised .....                                                                                              | 75761 |
| 179.200-11 Revised .....                                                                                                  | 75761 |
| 179.200-13 (a) revised .....                                                                                              | 75761 |
| 179.200-14 (f) removed.....                                                                                               | 48571 |
| 179.200-15 (c) revised .....                                                                                              | 75762 |
| 179.200-17 (a)(1) amended.....                                                                                            | 75762 |
| 179.200-22 (d) revised .....                                                                                              | 75762 |
| 179.200-23 Heading amended .....                                                                                          | 48571 |
| 179.200-24 Table amended .....                                                                                            | 48571 |
| 179.201-1 Table amended .....                                                                                             | 48571 |
| 179.201-2 Removed .....                                                                                                   | 48571 |
| 179.201-3 (b) amended .....                                                                                               | 48571 |
| 179.201-4 Revised .....                                                                                                   | 75762 |
| 179.201-5 Revised .....                                                                                                   | 75762 |
| 179.201-6 (a),(b) and (c) amended;<br>(d) removed.....                                                                    | 48571 |
| (c) revised .....                                                                                                         | 75762 |
| 179.220-6 (a) amended .....                                                                                               | 75762 |
| 179.220-7 (b) table, (c) introduc-<br>tory text, (d) introductory text<br>and (e) introductory text re-<br>vised.....     | 75762 |
| 179.220-10 (a) revised .....                                                                                              | 75762 |
| 179.220-11 (b) revised .....                                                                                              | 75762 |
| 179.220-14 Revised .....                                                                                                  | 75762 |
| 179.220-18 (a)(1) amended.....                                                                                            | 75763 |
| 179.220-26 (a) revised .....                                                                                              | 75763 |
| 179.300-7 (a) table revised .....                                                                                         | 75763 |
| 179.300-9 (a) revised .....                                                                                               | 75763 |
| 179.300-10 Revised .....                                                                                                  | 75763 |
| 179.300-12 (b) amended.....                                                                                               | 57634 |
| 179.300-15 (a) revised .....                                                                                              | 75763 |
| 179.300-17 (b) revised .....                                                                                              | 48572 |
| (b) revised .....                                                                                                         | 75763 |
| 179.400-3 (a)(1) revised .....                                                                                            | 75763 |
| 179.400-5 (a) introductory text re-<br>vised.....                                                                         | 75763 |
| 179.400-6 (b) revised.....                                                                                                | 75763 |
| 179.400-8 (a) amended.....                                                                                                | 75764 |
| 179.400-11 (c) revised .....                                                                                              | 75764 |
| 179.400-12 (b) introductory text<br>revised .....                                                                         | 75764 |
| 179.400-15 Revised .....                                                                                                  | 75764 |
| 179.400-18 (b) revised .....                                                                                              | 75764 |
| 179.400-20 (c)(1) revised .....                                                                                           | 75764 |
| 179.400-25 Introductory text re-<br>vised.....                                                                            | 75764 |
| 179.500-12 (b) revised .....                                                                                              | 57634 |
| 180.205 (c)(4) and (f)(4) revised;<br>(g)(2) and (3)(ii) amended.....                                                     | 24662 |
| (f)(1) amended .....                                                                                                      | 75764 |
| 180.209 (a)(1) table, (b)(1)(ii) and<br>(g) table amended; (e) revised;<br>(k) redesignated as (l); new (k)<br>added..... | 24663 |

### 49 CFR—Continued

68 FR  
Page

|                                                                                                                                                                                                                                                                                                                                                                           |       |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| Chapter I—Continued                                                                                                                                                                                                                                                                                                                                                       |       |
| (i) table amended .....                                                                                                                                                                                                                                                                                                                                                   | 48571 |
| (g) amended interim .....                                                                                                                                                                                                                                                                                                                                                 | 55544 |
| (b)(1)(iii), (d), (e), (f), (g), (i)(1) in-<br>troductory text and (2) amend-<br>ed; (k) revised.....                                                                                                                                                                                                                                                                     | 75764 |
| 180.211 (d)(1)(iii) amended .....                                                                                                                                                                                                                                                                                                                                         | 24664 |
| (c)(1)(iv) and (d)(1)(ii) revised .....                                                                                                                                                                                                                                                                                                                                   | 75764 |
| 180.215 (b)(1) heading revised.....                                                                                                                                                                                                                                                                                                                                       | 24664 |
| 180.350 Revised .....                                                                                                                                                                                                                                                                                                                                                     | 45042 |
| 180.352 (d)(1)(i) and (f) revised;<br>(d)(1)(iv) added.....                                                                                                                                                                                                                                                                                                               | 45042 |
| 180.403 Amended .....                                                                                                                                                                                                                                                                                                                                                     | 19286 |
| 180-405 (g)(3) removed; (b),<br>(g)(2)(i), (k) and (l) revised; new<br>(o) added .....                                                                                                                                                                                                                                                                                    | 19286 |
| (b)(2) correctly revised .....                                                                                                                                                                                                                                                                                                                                            | 52371 |
| 180.407 (b)(4) and (g)(1)(v) re-<br>moved; (d)(1),(4), (5), and (6) re-<br>designated as (d)(5), (6) and (7);<br>(a)(2), (b)(1), (2), (c), (d)(1),<br>(g)(1)(ii), (iv) introductory<br>text, (i)(5) introductory text,<br>and (i)(6) revised; tables I and II<br>amended; (c) table amended;<br>(e), (d) introductory text,<br>(h)(1)(iv), (v), and (i)(10)<br>added..... | 19286 |
| (c) and (i)(5) table corrected .....                                                                                                                                                                                                                                                                                                                                      | 52371 |
| (g)(3) revised .....                                                                                                                                                                                                                                                                                                                                                      | 75764 |
| 180.409 (a)(1) and (2) revised; (a)(3)<br>added.....                                                                                                                                                                                                                                                                                                                      | 19288 |
| 180.411 (b) introductory text re-<br>vised.....                                                                                                                                                                                                                                                                                                                           | 75764 |
| 180.413 Revised .....                                                                                                                                                                                                                                                                                                                                                     | 19288 |
| (c)(1) correctly revised .....                                                                                                                                                                                                                                                                                                                                            | 52372 |
| (b)(6) revised .....                                                                                                                                                                                                                                                                                                                                                      | 75765 |
| 180.415 (b) revised.....                                                                                                                                                                                                                                                                                                                                                  | 19290 |
| (b) corrected .....                                                                                                                                                                                                                                                                                                                                                       | 52372 |
| 180.417 (b) and (d) revised .....                                                                                                                                                                                                                                                                                                                                         | 19290 |
| (b)(2)(v) and (viii) correctly re-<br>vised .....                                                                                                                                                                                                                                                                                                                         | 52372 |
| 180.507 (b)(5) added .....                                                                                                                                                                                                                                                                                                                                                | 48571 |
| 180.509 (g)(1)(ii) Note 2 revised .....                                                                                                                                                                                                                                                                                                                                   | 75765 |
| 180.513 (a) revised.....                                                                                                                                                                                                                                                                                                                                                  | 75765 |
| 180.515 (a) revised.....                                                                                                                                                                                                                                                                                                                                                  | 75765 |
| 180.517 (a) revised.....                                                                                                                                                                                                                                                                                                                                                  | 75765 |
| 180.519 (c) revised .....                                                                                                                                                                                                                                                                                                                                                 | 75765 |
| 180.605 (k) revised .....                                                                                                                                                                                                                                                                                                                                                 | 45042 |

## 2004

### 49 CFR

69 FR  
Page

|                                    |       |
|------------------------------------|-------|
| Title 49 Nomenclature change ..... | 18803 |
| Subtitle A                         |       |
| Chapter I                          |       |
| 106.70 (b) revised .....           | 54044 |

## List of CFR Sections Affected

### 49 CFR—Continued

|                                                                                    | 69 FR<br>Page                |
|------------------------------------------------------------------------------------|------------------------------|
| Chapter I—Continued                                                                |                              |
| 107.105 (c)(10) revised .....                                                      | 6198                         |
| 107.107 (b)(3) and (4) revised; (b)(5)<br>added .....                              | 6198                         |
| 107.109 (a)(6) revised .....                                                       | 6198                         |
| 107.219 (c) introductory text re-<br>vised.....                                    | 54044                        |
| 107.301—107.339 (Subpart D) Ap-<br>pendix A amended.....                           | 54044                        |
| 171.1 Regulation at 68 FR 61937 eff.<br>date delayed to 1-1-05.....                | 30588                        |
| Regulation at 68 FR 61937 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 ..... | 70902                        |
| 171.2 Regulation at 68 FR 61939 eff.<br>date delayed to 1-1-05.....                | 30588                        |
| Regulation at 68 FR 61939 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 ..... | 70902                        |
| 171.6 (b)(2) table amended.....                                                    | 54045                        |
| 171.7 (a)(3) table amended .....                                                   | 3664                         |
| (a)(2) table corrected .....                                                       | 55115                        |
| (b) amended .....                                                                  | 64471                        |
| (a)(3) table and (b) table amended<br>.....                                        | 76061                        |
| 171.8 Corrected; eff. 1-5-05.....                                                  | 30119                        |
| Regulation at 68 FR 61940 eff.<br>date delayed to 1-1-05 .....                     | 30588                        |
| Regulation at 68 FR 61940 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 ..... | 70902                        |
| Amended .....                                                                      | 76062                        |
| 171.11 (d)(6)(vi) removed;<br>(d)(6)(iii) and (iv) revised .....                   | 3665                         |
| (d)(6) corrected.....                                                              | 55115                        |
| (d)(6)(i) corrected.....                                                           | 58843                        |
| (d)(6)(i) corrected.....                                                           | 58843                        |
| (d)(18) added; interim .....                                                       | 75215                        |
| (d)(15) and (17) revised.....                                                      | 76062                        |
| 171.12 (d) revised.....                                                            | 3665                         |
| (b)(22) added; interim .....                                                       | 75215                        |
| (b)(20) revised.....                                                               | 76062                        |
| 171.12a (b)(12) added; interim.....                                                | 75215                        |
| (a), (b)(9) and (18) revised .....                                                 | 76062                        |
| 171.14 (d) introductory text, (1)<br>and (6) revised.....                          | 34607                        |
| (f) amended.....                                                                   | 53354                        |
| (d) introductory text, (1) and (2)<br>revised.....                                 | 76062                        |
| 171.16 (b)(1) corrected; eff. 1-5-<br>05.....                                      | 30119                        |
| 172 Authority citation revised .....                                               | 75215                        |
| 172.101 Table amended.....                                                         | 3665, 34608,<br>41969, 54045 |
| Table corrected.....                                                               | 55116                        |
| Table amended; interim .....                                                       | 75215                        |

### 49 CFR—Continued

|                                                                                                                                                                                                                                         | 69 FR<br>Page |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| Chapter I—Continued                                                                                                                                                                                                                     |               |
| (c)(11), (d)(4), (i)(3) and table re-<br>vised .....                                                                                                                                                                                    | 76063         |
| Appendix B amended .....                                                                                                                                                                                                                | 76150         |
| 172.102 (c)(1) and (4) table amend-<br>ed .....                                                                                                                                                                                         | 34611         |
| (c)(7)(vi)(D)(3) revised .....                                                                                                                                                                                                          | 54045         |
| (c)(1) and (2) amended; interim<br>.....                                                                                                                                                                                                | 75215         |
| (c)(7)(viii) and (8) redesignated as<br>(c)(8) and (9); (b)(3), (4), (7), (8),<br>(c)(3) introductory text, (4), (7)<br>and new (8) introductory text<br>revised; (b)(9) and (c)(8)(ii)<br>added; (c)(1), (2) and (3) amend-<br>ed..... | 76150         |
| 172.202 (a)(2) and (6) revised;<br>(a)(2)(i), (ii) and (iii) added.....                                                                                                                                                                 | 34611         |
| (a)(2) introductory text amend-<br>ed; (a)(2)(ii) revised .....                                                                                                                                                                         | 54046         |
| (a)(2)(iii) and (5)(i) revised .....                                                                                                                                                                                                    | 76153         |
| 172.203 (d) revised .....                                                                                                                                                                                                               | 3668          |
| (d)(1) and (5) corrected.....                                                                                                                                                                                                           | 55116         |
| (f), (m)(2) and (o)(3) revised; (i)(3)<br>added .....                                                                                                                                                                                   | 76153         |
| 172.204 (c)(3) revised .....                                                                                                                                                                                                            | 76153         |
| 172.301 (f) added.....                                                                                                                                                                                                                  | 64471         |
| 172.310 Revised.....                                                                                                                                                                                                                    | 3668          |
| 172.315 Introductory text re-<br>vised.....                                                                                                                                                                                             | 76153         |
| 172.317 Added .....                                                                                                                                                                                                                     | 76153         |
| 172.321 (e) added .....                                                                                                                                                                                                                 | 20833         |
| Removed.....                                                                                                                                                                                                                            | 76154         |
| 172.326 (d) added .....                                                                                                                                                                                                                 | 64471         |
| 172.328 (e) added .....                                                                                                                                                                                                                 | 64471         |
| 172.330 (c) added .....                                                                                                                                                                                                                 | 64471         |
| 172.400 (b) table amended .....                                                                                                                                                                                                         | 3668          |
| (b) table amended.....                                                                                                                                                                                                                  | 64471         |
| 172.400a (a)(1) revised.....                                                                                                                                                                                                            | 64472         |
| 172.402 (d) revised .....                                                                                                                                                                                                               | 3668          |
| 172.403 (e) and (h) added; (g)(1), (2)<br>and (3) revised .....                                                                                                                                                                         | 3669          |
| (g)(1) and (h)(4) corrected.....                                                                                                                                                                                                        | 55116         |
| 172.407 (d)(5) revised; (d)(6) and (7)<br>added.....                                                                                                                                                                                    | 64472         |
| 172.441 Added .....                                                                                                                                                                                                                     | 3669          |
| 172.504 (e) Tables 1 and 2 amended;<br>(f)(9) revised .....                                                                                                                                                                             | 64472         |
| 172.512 (a)(3) and (b)(3) revised .....                                                                                                                                                                                                 | 54046         |
| 172.514 (b) revised.....                                                                                                                                                                                                                | 64473         |
| 172.519 (d)(3) revised.....                                                                                                                                                                                                             | 64473         |
| 172.604 (a)(2) revised.....                                                                                                                                                                                                             | 64473         |
| 173.1 Regulation at 68 FR 61941 eff.<br>date delayed to 1-1-05.....                                                                                                                                                                     | 30588         |
| Regulation at 68 FR 61941 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                                                                                                                                                      | 70902         |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

69 FR  
Page

#### Chapter I—Continued

|                                                                                    |       |
|------------------------------------------------------------------------------------|-------|
| 173.3 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                  | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....        | 70902 |
| (c) introductory text revised .....                                                | 76154 |
| 173.4 (d) added; interim .....                                                     | 75216 |
| 173.6 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                  | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....        | 70902 |
| 173.9 (e)(1) and (2) revised .....                                                 | 64473 |
| 173.24 (g) and (i) revised .....                                                   | 76154 |
| 173.24a Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....        | 70902 |
| 173.25 (a)(2) and (4) revised .....                                                | 76155 |
| 173.27 (i) revised .....                                                           | 76155 |
| 173.28 (c)(2) introductory text revised .....                                      | 76155 |
| 173.29 (c) introductory text revised; (h) added .....                              | 64473 |
| 173.30 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                 | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....        | 70902 |
| 173.31 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                 | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....        | 70902 |
| 173.32 (c)(3) amended .....                                                        | 54046 |
| 173.61 (c) amended .....                                                           | 54046 |
| 173.62 Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 ..... | 70902 |
| 173.115 (k) added .....                                                            | 76155 |
| 173.128 (d)(1) revised .....                                                       | 76155 |
| 173.132 (b)(1) revised .....                                                       | 76155 |
| 173.133 (b)(1)(ii) and (iii) revised .....                                         | 54046 |
| 173.136 (d) added .....                                                            | 76155 |
| 173.137 (c)(2) revised .....                                                       | 76155 |
| 173.150 Heading, (f)(3)(vii) and (viii) revised; (f)(3)(x) added .....             | 64473 |
| (a), (b) introductory text, (2) and (c) revised .....                              | 76155 |
| 173.151 (b), (c) and (d) introductory text revised .....                           | 76156 |
| 173.152 (b) introductory text, (1) and (c) revised .....                           | 76156 |
| 173.153 (b) and (c)(1) revised .....                                               | 76156 |

### 49 CFR—Continued

69 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                               |       |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 173.154 (b) introductory text, (1) and (c) revised .....                                                                                                      | 76157 |
| 173.166 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                                                                                           | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                                                                   | 70902 |
| 173.171 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                                                                                           | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                                                                   | 70902 |
| 173.181 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                                                                                           | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                                                                   | 70902 |
| 173.185 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                                                                                           | 30588 |
| (k) amended .....                                                                                                                                             | 34611 |
| (g)(2) and (j) amended .....                                                                                                                                  | 54046 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                                                                   | 70902 |
| (b) introductory text, (c) introductory text and (d) revised; (b)(5) and (c)(4) redesignated as (b)(6) and (c)(5); new (b)(5) and (c)(4) added; interim ..... | 75216 |
| (c)(3) and (e)(6) revised .....                                                                                                                               | 76157 |
| 173.186 (e) revised .....                                                                                                                                     | 76157 |
| 173.187 (f) added .....                                                                                                                                       | 76157 |
| 173.189 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                                                                                           | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                                                                   | 70902 |
| 173.211 (c) revised .....                                                                                                                                     | 76157 |
| 173.212 (c) revised .....                                                                                                                                     | 76157 |
| 173.213 (c) revised .....                                                                                                                                     | 76158 |
| 173.219 Regulation at 68 FR 61941 eff. date delayed to 1–1–05 .....                                                                                           | 30588 |
| Regulation at 68 FR 61941 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                                                                   | 70902 |
| Revised .....                                                                                                                                                 | 76158 |
| 173.220 (d), (e) and (f) redesignated as (e), (f) and (g); new (d) added; interim .....                                                                       | 75216 |
| (b)(2) revised .....                                                                                                                                          | 76158 |
| 173.224 (b)(4) revised .....                                                                                                                                  | 76159 |
| 173.225 Table amended .....                                                                                                                                   | 34611 |
| (b) amended .....                                                                                                                                             | 54046 |
| Revised .....                                                                                                                                                 | 76159 |
| 173.226 Revised .....                                                                                                                                         | 76172 |
| 173.227 Revised .....                                                                                                                                         | 76173 |

## List of CFR Sections Affected

### 49 CFR—Continued

|                                                                                                                    | 69 FR<br>Page |
|--------------------------------------------------------------------------------------------------------------------|---------------|
| Chapter I—Continued                                                                                                |               |
| 173.249 (c) revised .....                                                                                          | 76174         |
| 173.306 (i) and (j) removed; new (i)<br>added .....                                                                | 76174         |
| 173.307 (a)(5) removed .....                                                                                       | 76174         |
| 173.308 Regulation at 68 FR 61941<br>eff. date delayed to 1-1-05 .....                                             | 30588         |
| Regulation at 68 FR 61941 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                                 | 70902         |
| 173.313 Added .....                                                                                                | 76174         |
| 173.315 (j)(3) revised .....                                                                                       | 54046         |
| (a) introductory text revised .....                                                                                | 76178         |
| 173.316 (b) amended .....                                                                                          | 54046         |
| 173.323 (b) revised .....                                                                                          | 76178         |
| 173.335 Regulation at 68 FR 61941<br>eff. date delayed to 1-1-05 .....                                             | 30588         |
| Regulation at 68 FR 61941 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                                 | 70902         |
| 173.401 (b)(2) and (3) revised; (b)(4)<br>added .....                                                              | 3670          |
| 173.403 Revised .....                                                                                              | 3670          |
| Corrected .....                                                                                                    | 55116, 58843  |
| 173.411 (b)(5)(ii) revised .....                                                                                   | 3673          |
| (b) corrected .....                                                                                                | 55117         |
| (b)(2)(ii) correctly revised .....                                                                                 | 58843         |
| 173.415 (a), (c) and (d) revised .....                                                                             | 3673          |
| (d) corrected .....                                                                                                | 55117         |
| 173.416 Revised .....                                                                                              | 3673          |
| Regulation at 68 FR 61941 eff.<br>date delayed to 1-1-05 .....                                                     | 30588         |
| Regulation at 68 FR 61941 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                                 | 70902         |
| 173.417 Revised .....                                                                                              | 3674          |
| (a)(2) introductory text cor-<br>rected .....                                                                      | 55118         |
| 173.420 Revised .....                                                                                              | 3675          |
| (a)(2)(ii) corrected .....                                                                                         | 55118         |
| 173.421 (a) introductory text re-<br>vised .....                                                                   | 3675          |
| 173.422 Revised .....                                                                                              | 3675          |
| 173.424 Revised .....                                                                                              | 3675          |
| 173.425 Introductory text table<br>amended .....                                                                   | 3676          |
| 173.426 Introductory text re-<br>vised .....                                                                       | 3676          |
| 173.427 Revised .....                                                                                              | 3676          |
| (a), (b)(3), (4) and (e) tables cor-<br>rected .....                                                               | 55118         |
| (b)(4) correctly revised .....                                                                                     | 58843         |
| 173.428 Introductory text revised;<br>(c), (d) and (e) redesignated as<br>(d), (e) and (f); new (c)<br>added ..... | 3677          |
| 173.431 (b) revised .....                                                                                          | 3677          |

### 49 CFR—Continued

|                                                                                                   | 69 FR<br>Page |
|---------------------------------------------------------------------------------------------------|---------------|
| Chapter I—Continued                                                                               |               |
| 173.433 Revised .....                                                                             | 3677          |
| (d)(6) corrected .....                                                                            | 55119         |
| 173.435 Revised .....                                                                             | 3678          |
| Table corrected .....                                                                             | 55119         |
| 173.436 Added .....                                                                               | 3685          |
| 173.441 (d) redesignated as (e);<br>heading and new (e) revised;<br>new (d) added .....           | 3691          |
| 173.443 (a)(1) and (2) revised .....                                                              | 3691          |
| (a) introductory text corrected<br>.....                                                          | 55119         |
| 173.447 (a) and (b) revised .....                                                                 | 3691          |
| 173.448 Revised .....                                                                             | 3691          |
| 173.453 Revised .....                                                                             | 3692          |
| 173.457 Revised .....                                                                             | 3692          |
| 173.459 Revised .....                                                                             | 3692          |
| 173.465 (c)(1) and table amend-<br>ed .....                                                       | 3692          |
| 173.469 (a)(4)(ii), (c)(1)(i), (iv),<br>(2)(i), (iv) and (d)(1) revised .....                     | 3692          |
| 173.471 Introductory text re-<br>vised .....                                                      | 3693          |
| 173.473 Introductory text re-<br>vised .....                                                      | 3693          |
| 173.476 (c)(3) amended; (c)(4) re-<br>vised; (c)(5) added .....                                   | 3693          |
| 173.477 Added .....                                                                               | 3693          |
| 173 Appendix H amended .....                                                                      | 76179         |
| 174.67 Regulation at 68 FR 61941<br>eff. date delayed to 1-1-05 .....                             | 30588         |
| Regulation at 68 FR 61941 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                | 70902         |
| 174.110 Regulation at 68 FR 61942<br>eff. date delayed to 1-1-05 .....                            | 30588         |
| Regulation at 68 FR 61942 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                | 70902         |
| 174.112 Regulation at 68 FR 61942<br>eff. date delayed to 1-1-05 .....                            | 30588         |
| Regulation at 68 FR 61942 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                | 70902         |
| 174.115 Regulation at 68 FR 61942<br>eff. date delayed to 1-1-05 .....                            | 30588         |
| Regulation at 68 FR 61942 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....                | 70902         |
| 174.700 (b) revised; (d), (e) and (f)<br>redesignated as (e), (f) and (g);<br>new (d) added ..... | 3693          |
| 175 Authority citation revised .....                                                              | 75216         |
| 175.10 (a)(27) added; interim .....                                                               | 75216         |
| (a)(4)(i), (iii) and (18) revised .....                                                           | 76179         |
| 175.81 Regulation at 68 FR 61942<br>eff. date delayed to 1-1-05 .....                             | 30588         |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

69 FR  
Page

#### Chapter I—Continued

|                                                                                                              |       |
|--------------------------------------------------------------------------------------------------------------|-------|
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                  | 70902 |
| 175.85 (j) added .....                                                                                       | 76179 |
| 175.700 (a) revised .....                                                                                    | 3693  |
| 175.702 (b) revised .....                                                                                    | 3694  |
| 175.703 (b), (c) and (e) revised .....                                                                       | 3694  |
| 176.2 Amended .....                                                                                          | 76179 |
| 176.27 Revised .....                                                                                         | 76180 |
| 176.63 (e) revised .....                                                                                     | 76180 |
| 176.69 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....                                           | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                  | 70902 |
| 176.76 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....                                           | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                  | 70902 |
| (h) and (i) revised .....                                                                                    | 76180 |
| 176.78 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....                                           | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                  | 70902 |
| 176.83 (a)(5), (d), (e), (f)(1), (3), (g)(1), (2), (3) and (l) revised; (g) and (f) amended; (m) added ..... | 76180 |
| 176.84 (a) revised; (b) table and (c)(2) amended .....                                                       | 76183 |
| 176.93 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....                                           | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                  | 70902 |
| 176.116 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....                                          | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                  | 70902 |
| (c) revised; (f) added .....                                                                                 | 76183 |
| 176.122 Removed .....                                                                                        | 76183 |
| 176.124 Removed .....                                                                                        | 76183 |
| 176.128 Revised .....                                                                                        | 76183 |
| 176.132 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....                                          | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 .....                                  | 70902 |
| Removed .....                                                                                                | 76184 |
| 176.133 Revised .....                                                                                        | 76184 |
| 176.136 Revised .....                                                                                        | 76184 |
| 176.138 (a) revised .....                                                                                    | 76184 |
| 176.142 (a) revised .....                                                                                    | 76184 |

### 49 CFR—Continued

69 FR  
Page

#### Chapter I—Continued

|                                                                             |       |
|-----------------------------------------------------------------------------|-------|
| 176.144 (a), (b), (c) and (e) revised .....                                 | 76184 |
| 176.146 (d)(1) revised .....                                                | 76185 |
| 176.168 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....         | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 ..... | 70902 |
| Undesignated center heading revised .....                                   | 76185 |
| 176.170 (b) added .....                                                     | 76185 |
| 176.174 (a) and (b) revised .....                                           | 76185 |
| 176.200 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....         | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 ..... | 70902 |
| 176.600 (a) amended .....                                                   | 76185 |
| 176.700 (c) removed; (d) and (e) redesignated as (c) and (d) .....          | 3694  |
| 176.704 Revised .....                                                       | 3694  |
| 176.708 Heading and (a) through (e) revised; Table IV amended .....         | 3695  |
| 177.834 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....         | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 ..... | 7090  |
| 177.840 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....         | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 ..... | 70902 |
| 177.842 (f) and (g) revised .....                                           | 3696  |
| 177.870 Regulation at 68 FR 61942 eff. date delayed to 1–1–05 .....         | 30588 |
| Regulation at 68 FR 61942 and 69 FR 30588 eff. date delayed to 6-1-05 ..... | 70902 |
| 178.2 (c)(1)(ii) revised .....                                              | 34612 |
| 178.68 (i)(2) revised .....                                                 | 54046 |
| 178.274 (f)(1)(v) revised .....                                             | 76185 |
| 178.275 (i)(2) revised .....                                                | 76185 |
| 178.276 (f) amended .....                                                   | 54046 |
| (a)(4)(ii)(A), (d) and (e)(3) revised .....                                 | 76185 |
| 178.350 (b) revised; (c) added .....                                        | 3696  |
| 178.352 Removed .....                                                       | 3696  |
| 178.352–1 Removed .....                                                     | 3696  |
| 178.352–2 Removed .....                                                     | 3696  |
| 178.352–3 Removed .....                                                     | 3696  |
| 178.352–4 Removed .....                                                     | 3696  |
| 178.352–5 Removed .....                                                     | 3696  |
| 178.352–6 Removed .....                                                     | 3696  |
| 178.354 Removed .....                                                       | 3696  |



## List of CFR Sections Affected

### 49 CFR—Continued

69 FR  
Page

|                     |                                                                                         |
|---------------------|-----------------------------------------------------------------------------------------|
| Chapter I—Continued |                                                                                         |
| 178.354-1           | Removed.....3696                                                                        |
| 178.354-2           | Removed.....3696                                                                        |
| 178.354-3           | Removed.....3696                                                                        |
| 178.354-4           | Removed.....3696                                                                        |
| 178.354-5           | Removed.....3696                                                                        |
| 178.358-5           | (c) revised .....54046                                                                  |
| 178.362             | Removed.....3696                                                                        |
| 178.362-1           | Removed.....3696                                                                        |
| 178.362-2           | Removed.....3696                                                                        |
| 178.362-3           | Removed.....3696                                                                        |
| 178.362-4           | Removed.....3696                                                                        |
| 178.362-5           | Removed.....3696                                                                        |
| 178.362-6           | Removed.....3696                                                                        |
| 178.362-7           | Removed.....3696                                                                        |
| 178.364             | Removed.....3696                                                                        |
| 178.364-1           | Removed.....3696                                                                        |
| 178.364-2           | Removed.....3696                                                                        |
| 178.364-3           | Removed.....3696                                                                        |
| 178.364-4           | Removed.....3696                                                                        |
| 178.364-5           | Removed.....3696                                                                        |
| 178.364-6           | Removed.....3696                                                                        |
| 178.601             | Regulation at 68 FR 61942<br>eff. date delayed to 1-1-05 .....30588                     |
|                     | Regulation at 68 FR 61942 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....70902 |
| 178.602             | (b) revised .....76186                                                                  |
| 178.603             | (c) and (e)(2) introductory<br>text revised .....76186                                  |
| 178.609             | (d)(1) introductory text<br>and (2) introductory text re-<br>vised.....54046            |
| 178.704             | Regulation at 68 FR 61942<br>eff. date delayed to 1-1-05 .....30588                     |
|                     | Regulation at 68 FR 61942 and 69<br>FR 30588 eff. date delayed to 6-<br>1-05 .....70902 |
| 178.707             | (c)(3)(iv) revised.....54046                                                            |
| 178.810             | (b)(3) revised.....76186                                                                |
| 179.200-16          | (e) amended .....54047                                                                  |
| 179.220-17          | (e) amended .....54047                                                                  |
| 179.300-1           | Heading revised .....54047                                                              |
| 180.350             | (c) revised .....76186                                                                  |
| 180.352             | (d)(1)(iv) revised; (d)(1)(v)<br>added.....76186                                        |
| 180.403             | Amended .....54047                                                                      |
| 180.417             | (b)(1)(v) revised; (b)(2)(v)<br>removed .....54047                                      |

## 2005

### 49 CFR

70 FR  
Page

|            |                                            |
|------------|--------------------------------------------|
| Subtitle B |                                            |
| Chapter I  |                                            |
| 100-199    | (Chapter I) Heading re-<br>vised .....8302 |

### 49 CFR—Continued

70 FR  
Page

|                     |                                                                              |
|---------------------|------------------------------------------------------------------------------|
| Chapter I—Continued |                                                                              |
| 105.5               | (a) revised; (b) amended.....56087                                           |
|                     | (b) amended .....73158                                                       |
| 105.15              | Amended.....73159                                                            |
| 105.20              | Revised .....56087                                                           |
| 105.25              | Revised.....56088                                                            |
|                     | (a)(2) and (b)(2)(iv) revised .....73159                                     |
| 105.26              | Amended.....56087                                                            |
| 105.30              | Introductory text and (b)<br>amended.....56087                               |
|                     | Introductory text amended .....73159                                         |
| 105.35              | Heading and (a) introduc-<br>tory text amended .....56087                    |
| 105.40              | (d) revised .....56088, 73159                                                |
| 105.45              | (a), (b)(2) and (3) amend-<br>ed .....56087                                  |
| 105.50              | (a) and (d) amended.....56087                                                |
| 105.55              | (a) introductory text and<br>(b) amended .....56087                          |
| 106.5-106.45        | (Subpart A) Heading<br>amended.....56088                                     |
| 106.10              | (a) introductory text and<br>(b)(2) revised.....56088                        |
| 106.15              | Amended.....56088                                                            |
| 106.20              | Amended.....56088                                                            |
| 106.25              | Introductory text amend-<br>ed .....56088                                    |
| 106.35              | Amended.....56088                                                            |
| 106.40              | Introductory text and (e)<br>amended.....56088                               |
| 106.45              | Revised.....56088                                                            |
| 106.55              | Introductory text amend-<br>ed .....56088                                    |
| 106.60              | Amended.....56088                                                            |
| 106.75              | Introductory text amend-<br>ed .....56088                                    |
| 106.80              | Amended.....56088                                                            |
| 106.85              | (a) and (b) amended.....56088                                                |
| 106.90              | Introductory text and (c)<br>amended.....56088                               |
| 106.95              | Revised .....56089                                                           |
| 106.105             | Heading amended .....56088                                                   |
| 106.110             | Heading, introductory<br>text, (a) and (b) amended .....56088                |
| 106.115             | (a) introductory text, (4)<br>and (b) introductory text<br>amended.....56088 |
| 106.120             | Revised .....56089                                                           |
| 106.130             | Heading, introductory<br>text, (a)(4), (b)(1) and (2)<br>amended.....56088   |
| 107.1               | Amended .....56089                                                           |
| 107                 | Nomenclature changes.....73159                                               |
| 107.1               | Amended .....73159                                                           |
| 107.105             | (a)(1) revised.....56089                                                     |
|                     | Heading, (a)(1), (4), (c) and (d) re-<br>vised .....73160                    |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

70 FR  
Page

|                                                             |                     |
|-------------------------------------------------------------|---------------------|
| Chapter I—Continued                                         |                     |
| 107.107 (b)(1) revised.....                                 | 56090               |
| (a), (b)(1), (2), (5) and (d) revised .....                 | 73160               |
| 107.109 (a)(1) revised.....                                 | 56090               |
| Revised .....                                               | 73160               |
| 107.111 Amended .....                                       | 56089               |
| 107.113 (a), (b), (f)(2)(i), (5), (h) and (j) revised ..... | 73161               |
| 107.117 (d)(5) revised.....                                 | 56090               |
| 107.121 Heading, (a), (b) and (c) revised.....              | 73161               |
| 107.123 (a) introductory text revised.....                  | 73161               |
| 107.127 (a) amended .....                                   | 56089               |
| (a) revised.....                                            | 73162               |
| 107.203 (b)(1)(i) and (iii) amended.....                    | 56089               |
| 107.215 (b)(1)(i) and (iii) amended.....                    | 56089               |
| 107.227 Amended .....                                       | 73162               |
| 107.301 Amended .....                                       | 56089               |
| 107.305 (b)(4) amended .....                                | 56089               |
| 107.307 (a) introductory text and (b) revised.....          | 73162               |
| 107.310 (b)(2) and (e) amended .....                        | 56089               |
| 107.325 Revised .....                                       | 56090               |
| 107.327 (a)(1)(iii) amended .....                           | 56089               |
| 107.335 Amended .....                                       | 56089               |
| 107.337 Amended .....                                       | 56089               |
| 107.339 Amended .....                                       | 56089               |
| 107.301–107.339 (Subpart D) Appendix A amended ...          | 56089, 56090, 73162 |
| 107.402 (a) and (b)(2) amended .....                        | 56089               |
| (a) amended .....                                           | 56090               |
| 107.403 (c) amended .....                                   | 56089               |
| 107.503 (c) amended .....                                   | 56089               |
| 107.608 (c) amended .....                                   | 56089               |
| (d) amended .....                                           | 56090               |
| 107.616 (d)(1) and (3) amended.....                         | 56089               |
| 107.620 (a)(1), (2) and (b) amended.....                    | 56089               |
| 107.705 (a)(1) amended .....                                | 56089, 56090        |
| (a)(3) revised .....                                        | 73162               |
| 107.711 Amended .....                                       | 56089               |
| 107.803 (a) amended .....                                   | 56089               |
| 107.805 (g) amended .....                                   | 56090               |
| (a), (c)(2), (d) and (f) revised.....                       | 73162               |
| 110.5 (c) amended .....                                     | 56090               |
| 110.20 Amended.....                                         | 56090               |
| 110.30 (a) introductory text amended.....                   | 56090               |
| (b)(2) and (c)(2) amended.....                              | 73162               |
| 110.120 Amended .....                                       | 56090               |
| 171 Meetings .....                                          | 2367                |
| Authority citation corrected .....                          | 20031               |
| Nomenclature change .....                                   | 73162               |

### 49 CFR—Continued

70 FR  
Page

|                                                                                                                                                                |                                   |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------|
| Chapter I—Continued                                                                                                                                            |                                   |
| 171.1 Introductory text, (c), (f) and (g) correctly revised; (b)(4) correctly removed; (b)(5) through (15) correctly redesignated as (b)(4) through (14) ..... | 20031                             |
| (d)(7) revised .....                                                                                                                                           | 73162                             |
| 171.2 (b) and (f) revised .....                                                                                                                                | 43643                             |
| (g) and (h) revised .....                                                                                                                                      | 73162                             |
| 171.6 (b)(2) table amended.....                                                                                                                                | 33379, 56090                      |
| (b)(2) table amended (OMB numbers) .....                                                                                                                       | 73163                             |
| 171.7 (a)(3) table amended .....                                                                                                                               | 3307                              |
| (a)(3) table and (b) table amended .....                                                                                                                       | 34071                             |
| 171.8 Amended .....                                                                                                                                            | 20033, 43644, 56090, 56091, 73163 |
| 171.11 (d)(6)(iv) amended .....                                                                                                                                | 56091                             |
| 171.12a (b)(2) revised .....                                                                                                                                   | 34072                             |
| 171.14 Regulation at 69 FR 53354 confirmed .....                                                                                                               | 8957                              |
| (d)(3) removed .....                                                                                                                                           | 34072                             |
| 171.16 (b)(1) amended.....                                                                                                                                     | 56090, 56091                      |
| 171.20 (a), (b) and (c) amended .....                                                                                                                          | 56090                             |
| 172 Meetings .....                                                                                                                                             | 2367                              |
| 172.101 Table amended .....                                                                                                                                    | 34388                             |
| (i)(3) and table amended; (i)(5) added .....                                                                                                                   | 34072                             |
| Table and Appendix A amended .....                                                                                                                             | 56091                             |
| Table corrected.....                                                                                                                                           | 59119                             |
| 172.102 (c)(1), (3), (4), (7) and (8) amended.....                                                                                                             | 34397                             |
| (c)(1) amended.....                                                                                                                                            | 34075                             |
| (c)(1) and (4) Table 1 amended.....                                                                                                                            | 56098                             |
| (c)(1) amended.....                                                                                                                                            | 73164                             |
| 172.201 (e) revised .....                                                                                                                                      | 73164                             |
| 172.202 (a)(5)(i) amended.....                                                                                                                                 | 34397                             |
| 172.203 (m)(2) revised.....                                                                                                                                    | 34397                             |
| (l)(4) added .....                                                                                                                                             | 34075                             |
| (m) revised .....                                                                                                                                              | 56098                             |
| (a) revised .....                                                                                                                                              | 73164                             |
| 172.205 (i) added.....                                                                                                                                         | 34075                             |
| 172.322 (f) added.....                                                                                                                                         | 56098                             |
| 172.301 (c) revised .....                                                                                                                                      | 73164                             |
| 172.302 (c) revised .....                                                                                                                                      | 73164                             |
| 172.504 (g)(2) revised.....                                                                                                                                    | 34075                             |
| 172.519 (f) amended.....                                                                                                                                       | 34075                             |
| 172.704 (a)(2)(i) and (e) revised.....                                                                                                                         | 73164                             |
| 172.800 (c) added .....                                                                                                                                        | 73164                             |
| 173 Meetings .....                                                                                                                                             | 2367                              |
| Policy statement.....                                                                                                                                          | 7670                              |
| 173.3 (d) redesignated as (e); new (d) added .....                                                                                                             | 3307                              |
| (c) introductory text revised .....                                                                                                                            | 34397, 56098                      |
| 173.4 (a)(10) revised .....                                                                                                                                    | 56098                             |

## List of CFR Sections Affected

### 49 CFR—Continued

70 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                                                                            |       |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 173.5 (f) added.....                                                                                                                                                                                       | 73165 |
| 173.5a Revised .....                                                                                                                                                                                       | 3308  |
| 173.7 (a) introductory text amended.....                                                                                                                                                                   | 34075 |
| 173.12 (b)(1) amended; (e) added .....                                                                                                                                                                     | 3309  |
| 173.13 (a) amended; (b), (c)(1)(i) and (2)(i) revised .....                                                                                                                                                | 3309  |
| 173.22 (c)(2) amended.....                                                                                                                                                                                 | 56098 |
| (a)(2)(v), (3)(i) and (ii) revised.....                                                                                                                                                                    | 73165 |
| 173.22a (b) and (c) amended .....                                                                                                                                                                          | 3309  |
| Revised .....                                                                                                                                                                                              | 73165 |
| 173.23 (h) added .....                                                                                                                                                                                     | 73165 |
| 173.25 (a)(4) revised .....                                                                                                                                                                                | 34397 |
| 173.28 (b)(3) revised .....                                                                                                                                                                                | 34075 |
| 173.31 (b)(5) amended.....                                                                                                                                                                                 | 34075 |
| 173.115 (a)(2) and (k)(3) revised.....                                                                                                                                                                     | 34398 |
| 173.124 (a)(1)(ii)(A) amended .....                                                                                                                                                                        | 73165 |
| 173.134 (c)(1)(ii) amended.....                                                                                                                                                                            | 56098 |
| 173.136 (b) amended .....                                                                                                                                                                                  | 56098 |
| 173.151 (c) amended .....                                                                                                                                                                                  | 34398 |
| 173.185 (e)(6) revised .....                                                                                                                                                                               | 34398 |
| 173.212 (c) amended .....                                                                                                                                                                                  | 34398 |
| 173.213 (c) amended .....                                                                                                                                                                                  | 34398 |
| 173.220 (a)(3) and (g) revised.....                                                                                                                                                                        | 34398 |
| 173.222 (c)(2) amended .....                                                                                                                                                                               | 56098 |
| 173.225 (c) table and (g) table amended; (h)(3)(xii) revised.....                                                                                                                                          | 34398 |
| 173.227 Revised .....                                                                                                                                                                                      | 34398 |
| Heading amended.....                                                                                                                                                                                       | 56098 |
| 173.241 (c) amended .....                                                                                                                                                                                  | 34075 |
| 173.301 (a)(9), (l)(2) and (m) introductory text revised .....                                                                                                                                             | 34075 |
| (j) and (l) introductory text revised .....                                                                                                                                                                | 73165 |
| Heading, (a) introductory text, (1) introductory text, (c), (d), (f)(1), (h) introductory text, (l) introductory text, (i) introductory text, (j), (k) and (l) revised; (a)(10) and (f)(5)(iv) added ..... | 33881 |
| (d) revised; (o) added; eff. 1-1-07 .....                                                                                                                                                                  | 51127 |
| (h) introductory text and (i) introductory text amended .....                                                                                                                                              | 54395 |
| 173.301b Added .....                                                                                                                                                                                       | 33882 |
| (a)(4) amended .....                                                                                                                                                                                       | 54395 |
| 173.302 (a) introductory text, (b)(2) and (3) revised .....                                                                                                                                                | 33883 |
| (e) added; eff. 1-1-07 .....                                                                                                                                                                               | 51127 |
| 173.302a (a)(2) and (d) amended; (a)(3) revised; (e) added.....                                                                                                                                            | 34075 |
| (a)(3) amended .....                                                                                                                                                                                       | 54395 |
| 173.302b Added .....                                                                                                                                                                                       | 33883 |
| 173.303 (b) revised; (f) added .....                                                                                                                                                                       | 33883 |
| 173.304 (a) introductory text revised.....                                                                                                                                                                 | 33883 |

### 49 CFR—Continued

70 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                   |              |
|---------------------------------------------------------------------------------------------------------------------------------------------------|--------------|
| 173.304a (a)(2) table amended.....                                                                                                                | 34076        |
| 173.304b Added .....                                                                                                                              | 33883        |
| 173.306 (a)(1), (3) introductory text and (b) introductory text amended; (i) and (h) redesignated as (j) and (i); new (h) added; eff. 1-1-07..... | 3427         |
| (a) introductory text, (b) introductory text and (h) introductory text revised .....                                                              | 14603        |
| (a)(1) correctly amended .....                                                                                                                    | 23871        |
| (a)(4)(iii), (b) introductory text and (i) amended.....                                                                                           | 54395        |
| 173.307 (a)(2) revised.....                                                                                                                       | 14604        |
| 173.308 Revised; eff. 1-1-07 .....                                                                                                                | 3427         |
| 173.309 (a)(3)(iv) amended.....                                                                                                                   | 54395        |
| 173.312 Added .....                                                                                                                               | 33884        |
| 173.313 Amended .....                                                                                                                             | 34399        |
| 173.314 (g)(1) revised.....                                                                                                                       | 34076        |
| 173.315 (a) table amended .....                                                                                                                   | 34076        |
| (a) amended .....                                                                                                                                 | 56098        |
| (i)(8) correctly added; CFR correction.....                                                                                                       | 72930        |
| 173.319 (a)(3) revised.....                                                                                                                       | 34076        |
| 173.337 Introductory text amended .....                                                                                                           | 34076        |
| 173.403 Amended .....                                                                                                                             | 56098, 73165 |
| 173.418 (e) revised .....                                                                                                                         | 56098        |
| 173.421 (a)(5) revised.....                                                                                                                       | 56098        |
| 173.427 (b)(5)(i) amended.....                                                                                                                    | 56098        |
| 173.465 (c)(1) amended .....                                                                                                                      | 56099        |
| 173.471 (d) and (e) amended .....                                                                                                                 | 56098, 56099 |
| 173.472 (f) amended.....                                                                                                                          | 56098        |
| 173.473 (a)(1) and (2) amended.....                                                                                                               | 56098        |
| 173.476 (c) introductory text amended.....                                                                                                        | 56098        |
| 173.477 (c) introductory text amended.....                                                                                                        | 56098        |
| 174.24 (b) amended.....                                                                                                                           | 73165        |
| 174.67 (l), (m) and (n) correctly redesignated as (m), (n) and (o); introductory text added; (a), (k)(1) and (2) revised.....                     | 20034        |
| 174.81 (c) and (d) revised .....                                                                                                                  | 3310         |
| 175 Meetings .....                                                                                                                                | 2367         |
| 175.30 (a)(5) removed .....                                                                                                                       | 34399        |
| (a)(2) amended.....                                                                                                                               | 73165        |
| 175.33 (a)(10) amended .....                                                                                                                      | 73165        |
| 176.24 (b) amended.....                                                                                                                           | 73165        |
| 176.31 Revised.....                                                                                                                               | 73165        |
| 176.83 (a)(11) added.....                                                                                                                         | 3310         |
| (l) table amended .....                                                                                                                           | 34399        |
| 176.84 (b) table amended .....                                                                                                                    | 3310         |
| 176.144 (a) amended .....                                                                                                                         | 56099        |
| 176.905 (i)(3) amended.....                                                                                                                       | 56099        |
| 177.817 (f) amended.....                                                                                                                          | 73165        |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

70 FR  
Page

|                                                                |       |
|----------------------------------------------------------------|-------|
| Chapter I—Continued                                            |       |
| 177.848 (c) and (d) revised .....                              | 3310  |
| (c) revised .....                                              | 56099 |
| 178.3 (d) amended .....                                        | 73166 |
| 178.245–1 (e) amended .....                                    | 56099 |
| 178.274 (f)(1)(v) amended .....                                | 34399 |
| 178.338–2 (a) amended .....                                    | 34076 |
| 178.345–1 (c) amended .....                                    | 56099 |
| 178.345–2 (a)(1) amended .....                                 | 34076 |
| 178.350 (c) revised .....                                      | 56099 |
| 178.606 (c)(2)(ii) amended .....                               | 34076 |
| 179.18 (c) amended .....                                       | 56099 |
| 179.200–7 (e) amended .....                                    | 34076 |
| 179 Nomenclature change .....                                  | 73166 |
| 180 Nomenclature change .....                                  | 73166 |
| 180.205 (c)(2)(i), (i)(2) and (3) re-<br>vised .....           | 34077 |
| 180.209 (a)(1) Table 1 amended .....                           | 73166 |
| 180.212 Added .....                                            | 34077 |
| 180.215 (a)(5), (b) introductory<br>text and (2) amended ..... | 73166 |
| 180.352 (d)(1)(iv) revised .....                               | 34399 |
| (e) and (f) revised; (g) added .....                           | 56099 |
| 180.409 (d)(2) amended .....                                   | 56100 |
| 180.417 (b)(2)(v) revised .....                                | 34077 |

## 2006

### 49 CFR

71 FR  
Page

|                                                           |       |
|-----------------------------------------------------------|-------|
| Subtitle B                                                |       |
| Chapter I                                                 |       |
| 106.100 Correctly reinstated; CFR<br>correction .....     | 63701 |
| 107.105 (a) introductory text re-<br>vised .....          | 54390 |
| 107.201 (d) revised .....                                 | 30067 |
| 107.203 (a), (b)(1) and (d) re-<br>vised .....            | 30067 |
| 107.205 (a) and (b) amended; (c) re-<br>vised .....       | 30067 |
| 107.207 (a) and (b) amended .....                         | 30067 |
| 107.209 (a) and (b) amended; (c) re-<br>vised .....       | 30067 |
| 107.211 (a) and (d) revised; (b) and<br>(c) amended ..... | 30067 |
| 107.213 Revised .....                                     | 30068 |
| 107.215 (a) introductory text and<br>(b)(1) revised ..... | 30068 |
| 107.217 (a), (b)(2), (c), (d) and (e)<br>amended .....    | 30068 |
| 107.219 (a) through (d) amend-<br>ed .....                | 30068 |
| 107.221 (a), (b) and (c) amended; (d)<br>revised .....    | 30068 |
| 107.223 (a) and (d) revised; (b) and<br>(c) amended ..... | 30068 |
| 107.227 Revised .....                                     | 30068 |

### 49 CFR—Continued

71 FR  
Page

|                                                                                                                 |                               |
|-----------------------------------------------------------------------------------------------------------------|-------------------------------|
| Chapter I—Continued                                                                                             |                               |
| 107.329 Revised .....                                                                                           | 8487                          |
| 107.333 Revised .....                                                                                           | 8487                          |
| 107.301–107.339 (Subpart D) Ap-<br>pendix A amended .....                                                       | 8487                          |
| 107.504 (d)(2) amended .....                                                                                    | 54390                         |
| 107.616 (a) revised .....                                                                                       | 54390                         |
| 107.801 (a) revised .....                                                                                       | 33873                         |
| 107.803 Heading revised; (c)(8) re-<br>designated as (c)(9); new (c)(8)<br>added .....                          | 33873                         |
| 107.805 Heading, (a), (c)(2) and (d)<br>revised .....                                                           | 33873                         |
| 107.809 Added .....                                                                                             | 33874                         |
| 171.1 (g) revised .....                                                                                         | 8488                          |
| (d)(7) correctly revised .....                                                                                  | 44931                         |
| 171.6 (b)(2) table amended (OMB<br>numbers) .....                                                               | 54390                         |
| 171.7 (a)(3) table amended .....                                                                                | 33874                         |
| (a)(3) table amended .....                                                                                      | 78611                         |
| 171.8 Amended; eff. 1–1–07 .....                                                                                | 3424                          |
| Amended .....                                                                                                   | 14601, 32256, 33875           |
| 171.11 (d)(19) added; eff. 1–1–07 .....                                                                         | 3425                          |
| (d)(20) added .....                                                                                             | 33876                         |
| 171.12 (b)(23) added; eff. 1–1–07 .....                                                                         | 3425                          |
| (b)(15) revised .....                                                                                           | 33876                         |
| 171.12a (b)(21) added; eff. 1–1–07 .....                                                                        | 3425                          |
| (b)(13) revised .....                                                                                           | 33876                         |
| 171.14 (b), (d)(7) and (8) removed;<br>(d) introductory text, (1), (2),<br>(e) and (f) revised; (g) added ..... | 78611                         |
| 172.101 (c)(11) note revised; table<br>amended; eff. 1–1–07 .....                                               | 3425                          |
| Table amended .....                                                                                             | 14601, 32256, 33876,<br>54391 |
| d(4) revised; table amended .....                                                                               | 78612                         |
| Appendix B amended .....                                                                                        | 78626                         |
| 172.102 (c)(1) and (5) amended; eff.<br>1–1–07 .....                                                            | 3427                          |
| (c)(2) amended .....                                                                                            | 14601, 32258                  |
| (c)(5) amended .....                                                                                            | 33880                         |
| (c)(2) correctly amended .....                                                                                  | 56895                         |
| (c)(1) and (2) amended .....                                                                                    | 78626                         |
| 172.200 (b)(4) added .....                                                                                      | 32258                         |
| 172.202 (a) and (b) revised .....                                                                               | 78626                         |
| 172.203 (k) introductory text<br>amended .....                                                                  | 32258                         |
| 172.301 (b) revised .....                                                                                       | 32258                         |
| 172.312 (c)(5) and (6) amended .....                                                                            | 54395                         |
| (a) introductory text and (2) in-<br>troductory text revised; (c)(7)<br>added .....                             | 78627                         |
| 172.407 (d)(2)(i) amended;<br>(d)(2)(iii) added .....                                                           | 78627                         |
| 172.427 Revised .....                                                                                           | 78627                         |
| 172.552 Revised .....                                                                                           | 78628                         |
| 172.800 (b)(6) revised .....                                                                                    | 32258                         |

## List of CFR Sections Affected

### 49 CFR—Continued

71 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                               |              |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|
| 173.4 (a)(11) added.....                                                                                                                                      | 14602        |
| 173.6 (a)(4) revised.....                                                                                                                                     | 32258        |
| 173.7 Heading revised; (f) added.....                                                                                                                         | 14602        |
| 173.9 Revised .....                                                                                                                                           | 78629        |
| 173.13 (c)(1)(ii), (iv) and (2)(ii) amended.....                                                                                                              | 54395        |
| 173.21 (i) revised; eff. 1-1-07 .....                                                                                                                         | 3427         |
| 173.24a (c)(2) revised.....                                                                                                                                   | 32258        |
| 173.27 (a) amended.....                                                                                                                                       | 14602        |
| 173.35 (k) amended .....                                                                                                                                      | 78631        |
| 173.40 (a)(1), (2), (b), (d) and (e) revised; (a)(3) and (4) added.....                                                                                       | 33880        |
| 173.63 (b)(1) introductory text revised.....                                                                                                                  | 14602        |
| 173.115 (b)(1) and (k)(5) revised.....                                                                                                                        | 78631        |
| 173.120 (a) introductory text, (2) and (b)(1) amended.....                                                                                                    | 78631        |
| 173.121 (a) table amended .....                                                                                                                               | 78631        |
| 173.124 (a)(2)(i)(D)(3) added.....                                                                                                                            | 78631        |
| 173.133 Amended; (b)(1)(iv) revised.....                                                                                                                      | 54395        |
| (a)(1) table revised.....                                                                                                                                     | 78631        |
| 173.134 (a) introductory text, (1) through (5), (b), (c)(1)(ii) and (2) revised; (a)(6) removed; (a)(7), (8) and (9) redesignated as (a)(6), (7) and (8)..... | 32258        |
| (a)(5) revised .....                                                                                                                                          | 78631        |
| 173.136 (a) amended; (d) removed .....                                                                                                                        | 78631        |
| 173.137 (c)(2) revised.....                                                                                                                                   | 78631        |
| 173.150 (b) introductory text revised.....                                                                                                                    | 14602        |
| 173.151 (b) introductory text and (d) introductory text revised.....                                                                                          | 14602        |
| 173.152 (b) introductory text revised.....                                                                                                                    | 14603        |
| 173.153 (b) introductory text revised.....                                                                                                                    | 14603, 54395 |
| (b) introductory text correctly amended .....                                                                                                                 | 54938        |
| 173.154 (b) introductory text revised.....                                                                                                                    | 14603        |
| 173.155 (b) introductory text revised.....                                                                                                                    | 14603        |
| 173.159 (a), (c)(1), (2), (4), (5), (d)(1) and (e)(2) revised.....                                                                                            | 78631        |
| 173.163 Revised .....                                                                                                                                         | 33880        |
| 173.166 (d)(5) removed.....                                                                                                                                   | 54395        |
| (d)(1) revised.....                                                                                                                                           | 78632        |
| 173.187 Revised .....                                                                                                                                         | 78632        |
| 173.192 Introductory text and (a) introductory text revised .....                                                                                             | 33880        |
| 173.195 (a) revised.....                                                                                                                                      | 33880        |

### 49 CFR—Continued

71 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                                                                                   |       |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 173.196 Heading, (a) introductory text, (2), (3) and (b) revised.....                                                                                                                                             | 32260 |
| 173.197 (a), (b), (d)(1)(iv), (vi), (2)(iii), (3)(vi), (e)(2) and (3) introductory text revised.....                                                                                                              | 32261 |
| (a) revised; (b) and (e)(2) amended .....                                                                                                                                                                         | 78632 |
| 173.199 Heading, (a), (b) introductory text, (1), (2), (5), (c), (d) and (e) revised.....                                                                                                                         | 32261 |
| 173.201 (c) amended .....                                                                                                                                                                                         | 33880 |
| 173.205 Revised .....                                                                                                                                                                                             | 33881 |
| 173.216 (c)(3) revised; (c)(4) removed .....                                                                                                                                                                      | 78632 |
| 173.217 (f) added.....                                                                                                                                                                                            | 14603 |
| 173.220 (b)(4)(iii) revised .....                                                                                                                                                                                 | 14603 |
| (b)(2)(ii)(B)(3), (c) and (d) revised .....                                                                                                                                                                       | 78632 |
| 173.222 Heading, (a), (b)(1), (2), (c) introductory text and (d) revised.....                                                                                                                                     | 78633 |
| 173.224 (b)(7) table amended.....                                                                                                                                                                                 | 78633 |
| 173.226 (a) revised.....                                                                                                                                                                                          | 33881 |
| 173.227 (a) revised.....                                                                                                                                                                                          | 33881 |
| 173.230 Added .....                                                                                                                                                                                               | 78633 |
| 173.288 Introductory text removed; (a) revised .....                                                                                                                                                              | 33881 |
| 173.301 Heading, (a) introductory text, (1) introductory text, (c), (d), (f)(1), (h) introductory text, (1) introductory text, (i) introductory text, (j), (k) and (l) revised; (a)(10) and (f)(5)(iv) added..... | 33881 |
| (d) revised; (o) added; eff. 1-1-07 .....                                                                                                                                                                         | 51127 |
| (h) introductory text and (i) introductory text amended .....                                                                                                                                                     | 54395 |
| (o) revised .....                                                                                                                                                                                                 | 78633 |
| 173.301b Added .....                                                                                                                                                                                              | 33882 |
| (a)(4) amended .....                                                                                                                                                                                              | 54395 |
| 173.302 (a) introductory text, (b)(2) and (3) revised .....                                                                                                                                                       | 33883 |
| (e) added; eff. 1-1-07 .....                                                                                                                                                                                      | 51127 |
| 173.302a (a)(3) amended .....                                                                                                                                                                                     | 54395 |
| (d) correctly amended; CFR correction.....                                                                                                                                                                        | 75679 |
| 173.302b Added .....                                                                                                                                                                                              | 33883 |
| 173.303 (b) revised; (f) added .....                                                                                                                                                                              | 33883 |
| 173.304 (a) introductory text revised.....                                                                                                                                                                        | 33883 |
| 173.304b Added .....                                                                                                                                                                                              | 33883 |

## 49 CFR (10-1-08 Edition)

### 49 CFR—Continued

71 FR  
Page

#### Chapter I—Continued

|                                                                                                                                                    |       |
|----------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 173.306 (a)(1), (3) introductory text and (b) introductory text amended; (i) and (h) redesignated as (j) and (i); new (h) added; eff. 1-1-07 ..... | 3427  |
| (a) introductory text, (b) introductory text and (h) introductory text revised; eff. 1-1-07 .....                                                  | 14603 |
| (a)(1) correctly amended .....                                                                                                                     | 23871 |
| (a)(4)(iii), (b) introductory text and (i) amended .....                                                                                           | 54395 |
| (i) revised; (j) added .....                                                                                                                       | 78633 |
| 173.307 (a)(2) revised .....                                                                                                                       | 14604 |
| 173.308 Revised; eff. 1-1-07 .....                                                                                                                 | 3427  |
| 173.309 (a)(3)(iv) amended .....                                                                                                                   | 54395 |
| 173.312 Added .....                                                                                                                                | 33884 |
| 173.323 (b)(2) amended .....                                                                                                                       | 33884 |
| 173.334 (a) introductory text revised .....                                                                                                        | 33884 |
| Introductory text revised .....                                                                                                                    | 54395 |
| 173.336 Revised .....                                                                                                                              | 33885 |
| 173.337 Revised .....                                                                                                                              | 33885 |
| 173.435 Table amended .....                                                                                                                        | 54395 |
| 173 Appendix H amended .....                                                                                                                       | 78634 |
| 175 Revised .....                                                                                                                                  | 14604 |
| 175.10 (a)(2) amended .....                                                                                                                        | 78634 |
| 175.75 (c) amended; (e) introductory text and (5) revised .....                                                                                    | 54395 |
| 175.78 (c)(4)(i)(C) and (iv) introductory text amended .....                                                                                       | 54396 |
| (c)(4) revised .....                                                                                                                               | 78634 |
| 175.630 Heading revised; (c) added .....                                                                                                           | 32263 |
| 175.702 (a)(2)(ii) revised .....                                                                                                                   | 54396 |
| 176.76 (f)(2) amended .....                                                                                                                        | 78634 |
| 176.83 (a)(4) revised .....                                                                                                                        | 78634 |
| 176.84 (b) table amended .....                                                                                                                     | 78634 |
| 177.835 (g)(2) introductory text amended .....                                                                                                     | 54397 |
| 178.69 Added .....                                                                                                                                 | 33885 |
| 178.70 Added .....                                                                                                                                 | 33886 |
| (e)(4) revised .....                                                                                                                               | 54397 |
| 178.71 Added .....                                                                                                                                 | 33887 |
| (f) added; (l)(2), (p)(1) and (2) revised; (r)(1) amended .....                                                                                    | 54397 |
| 178.74 Added .....                                                                                                                                 | 33890 |
| 178.75 Added .....                                                                                                                                 | 33892 |
| 178.245 Removed .....                                                                                                                              | 54397 |
| 178.245-1 Removed .....                                                                                                                            | 54397 |
| 178.245-2 Removed .....                                                                                                                            | 54397 |
| 178.245-3 Removed .....                                                                                                                            | 54397 |
| 178.245-4 Removed .....                                                                                                                            | 54397 |
| 178.245-5 Removed .....                                                                                                                            | 54397 |
| 178.245-6 Removed .....                                                                                                                            | 54397 |
| 178.245-7 Removed .....                                                                                                                            | 54397 |
| 178.270 Removed .....                                                                                                                              | 54397 |

### 49 CFR—Continued

71 FR  
Page

#### Chapter I—Continued

|                                                                    |       |
|--------------------------------------------------------------------|-------|
| 178.270-1 Removed .....                                            | 54397 |
| 178.270-2 Removed .....                                            | 54397 |
| 178.270-3 Removed .....                                            | 54397 |
| 178.270-4 Removed .....                                            | 54397 |
| 178.270-5 Removed .....                                            | 54397 |
| 178.270-6 Removed .....                                            | 54397 |
| 178.270-7 Removed .....                                            | 54397 |
| 178.270-8 Removed .....                                            | 54397 |
| 178.270-9 Removed .....                                            | 54397 |
| 178.270-10 Removed .....                                           | 54397 |
| 178.270-11 Removed .....                                           | 54397 |
| 178.271 Removed .....                                              | 54397 |
| 178.271-1 Removed .....                                            | 54397 |
| 178.272 Removed .....                                              | 54397 |
| 178.272-1 Removed .....                                            | 54397 |
| 178.272-2 Removed .....                                            | 54397 |
| 178.274 (j)(6) revised .....                                       | 78634 |
| 178.338-9 (b)(2) amended .....                                     | 54397 |
| 178.602 (b) amended .....                                          | 78635 |
| 178.810 (b) revised .....                                          | 78635 |
| 180.201 Revised .....                                              | 33894 |
| 180.203 Introductory text revised .....                            | 33894 |
| 180.205 Heading revised .....                                      | 33894 |
| 180.205 (f)(4) revised; eff. 1-1-07 .....                          | 51128 |
| 180.207 Added .....                                                | 33894 |
| (d) introductory text and (1) revised .....                        | 54397 |
| 180.209 (a) Table 1 amended; (m) added; eff. 1-1-07 .....          | 51128 |
| (a)(1) Table 1 amended .....                                       | 54397 |
| 180.211 (d)(3) amended .....                                       | 54398 |
| 180.212 Revised .....                                              | 33895 |
| (a)(1)(i) and (ii) amended .....                                   | 54398 |
| 180.213 (a), (f)(1) and (7) revised; (c)(3) and (f)(8) added ..... | 33896 |
| (d) revised; (f)(9) added; eff. 1-1-07 .....                       | 51128 |
| (d) revised .....                                                  | 78635 |
| 180.215 (b) amended .....                                          | 54398 |
| 180.217 Added .....                                                | 33896 |
| 180.509 (l) introductory text revised; (l)(1) added .....          | 54398 |
| 180 Appendix C added; eff. 1-1-07 .....                            | 51129 |
| 180.352 (b) introductory text, (1) and (g) revised .....           | 78635 |

**2007**

### 49 CFR

72 FR  
Page

#### Subtitle B Chapter I

|                                        |       |
|----------------------------------------|-------|
| 105.20 (a)(4) and (b)(3) amended ..... | 55682 |
|----------------------------------------|-------|

## List of CFR Sections Affected

### 49 CFR—Continued

72 FR  
Page

#### Chapter I—Continued

|                                                                                                             |       |
|-------------------------------------------------------------------------------------------------------------|-------|
| 105.25 (a) introductory text and (b)(2)(iv) revised; (b)(4) amended .....                                   | 55682 |
| 105.35 (b)(3)(ii) revised .....                                                                             | 55682 |
| 105.40 (d) amended .....                                                                                    | 55682 |
| 106.45 (a)(2)(i) and (ii) revised .....                                                                     | 55682 |
| 106.70 (a)(1) and (2) revised .....                                                                         | 55682 |
| 106.75 (d) amended .....                                                                                    | 55682 |
| 106.85 (a) amended .....                                                                                    | 55682 |
| 106.95 (a) and (b) amended .....                                                                            | 55683 |
| 106.125 Amended .....                                                                                       | 55682 |
| 107.105 (a)(1) amended .....                                                                                | 55683 |
| 107.107 (b)(1) amended .....                                                                                | 55683 |
| 107.109 (a)(1) amended .....                                                                                | 55683 |
| 107.107 (b)(1) amended .....                                                                                | 55683 |
| 107.127 (a) amended .....                                                                                   | 55683 |
| 107.203 (b)(1)(i) amended .....                                                                             | 55683 |
| 107.215 (b)(1)(i) amended .....                                                                             | 55683 |
| 107.325 (a) and (b) amended .....                                                                           | 55683 |
| 107.402 (a) amended .....                                                                                   | 55683 |
| 107.502 (d) amended .....                                                                                   | 55683 |
| 107.606 (a)(4), (5) and (6) redesignated as (a)(5), (6) and (7); new (a)(4) added; new (a)(5) revised ..... | 24538 |
| 107.608 (a) revised .....                                                                                   | 55683 |
| 107.616 (a) amended; (d) removed .....                                                                      | 24538 |
| 107.705 (a)(1) amended .....                                                                                | 55683 |
| 110.5 (c) amended .....                                                                                     | 55683 |
| 110.30 (a) introductory text amended .....                                                                  | 55683 |
| 110.120 Amended .....                                                                                       | 55683 |
| 130.31 (b)(6) amended .....                                                                                 | 55683 |
| 171.1—171.14 Designated as Subpart A; new Subpart A heading added .....                                     | 25170 |
| 171.6 (b)(2) table amended (OMB numbers) .....                                                              | 55683 |
| 171.7 (a)(3) table amended .....                                                                            | 25170 |
| (a)(2)(i) revised; (a)(3) table amended .....                                                               | 55683 |
| 171.8 Amended; eff. 1–1–08 .....                                                                            | 44947 |
| Amended .....                                                                                               | 55684 |
| 171.11 (d)(16) revised .....                                                                                | 4454  |
| Removed .....                                                                                               | 25171 |
| Regulation at 72 FR 4454 eff. date delayed to 10–1–08 .....                                                 | 55091 |
| 171.12 Heading and (a) revised; (b), (c) and (d) removed; (e) redesignated as new (b) .....                 | 25171 |
| (a)(6) added; eff. 1–1–08 .....                                                                             | 44947 |
| (a)(2) corrected .....                                                                                      | 55091 |
| 171.12a Removed .....                                                                                       | 25172 |
| 171.14 (d)(6) amended .....                                                                                 | 55684 |

### 49 CFR—Continued

72 FR  
Page

#### Chapter I—Continued

|                                                                          |             |
|--------------------------------------------------------------------------|-------------|
| 171.15—171.21 Designated as Subpart B; new Subpart B heading added ..... | 25172       |
| 171.15 (b)(3) revised .....                                              | 55684       |
| 171.22—171.26 (Subpart C) Added .....                                    | 25172       |
| 171.22 (g)(5) and (6) corrected .....                                    | 55091       |
| Heading revised .....                                                    | 55684       |
| 171.23 (b)(5) introductory text revised .....                            | 55684       |
| 171.24 (d)(1)(ii) revised; eff. 1–1–08 .....                             | 44947       |
| (d)(2) revised; eff. 10–1–08 .....                                       | 55097       |
| 171.25 (b)(3) added; eff. 1–1–08 .....                                   | 44947       |
| 172 Authority citation revised .....                                     | 44948       |
| 172.101 Table amended .....                                              | 4455, 55684 |
| Table amended; eff. 1–1–08 .....                                         | 44948       |
| Regulation at 72 FR 4455 eff. date delayed to 10–1–08 .....              | 55091       |
| Table correctly amended .....                                            | 59146       |
| 172.102 (c)(1) and (2) amended .....                                     | 4455        |
| (c)(1) and (2) amended; eff. 1–1–08 .....                                | 44948       |
| Regulation at 72 FR 4455 eff. date delayed to 10–1–08 .....              | 55091       |
| 172.202 (a)(6)(vi) amended .....                                         | 55692       |
| 172.302 (f) amended .....                                                | 55692       |
| 172.303 (a) revised .....                                                | 55692       |
| 172.400a (d) revised .....                                               | 25176       |
| 172.505 (a) amended .....                                                | 55692       |
| 172.519 (f) revised .....                                                | 25176       |
| 173.6 (a)(4) introductory text amended .....                             | 55692       |
| 173.21 (k) amended .....                                                 | 25176       |
| 173.22 (c)(2) revised .....                                              | 55692       |
| 173.22a (b) amended .....                                                | 55692       |
| 173.24 (c)(2) and (i) revised .....                                      | 25176       |
| 173.27 (f) introductory text revised .....                               | 25176       |
| 173.31 (a)(8) added .....                                                | 25176       |
| (g)(1) and (2) revised .....                                             | 55692       |
| 173.32 (b)(4) added .....                                                | 25176       |
| 173.33 (h) added .....                                                   | 25176       |
| 173.56 (g) revised .....                                                 | 25177       |
| 173.132 (a)(1)(i) and (iii) revised .....                                | 55692       |
| 173.134 (a)(8) amended .....                                             | 55692       |
| 173.150 (b) introductory text amended; (d)(2) revised .....              | 55692       |
| 173.151 (b) introductory text and (d) introductory text amended .....    | 55692       |
| 173.152 (b) introductory text amended .....                              | 55692       |
| 173.154 (b) introductory text amended .....                              | 55693       |
| 173.168 Added .....                                                      | 4455        |

## 49 CFR (10–1–08 Edition)

### 49 CFR—Continued

72 FR  
Page

|                                                                                       |       |
|---------------------------------------------------------------------------------------|-------|
| Chapter I—Continued                                                                   |       |
| Regulation at 72 FR 4455 eff. date delayed to 10–1–08 .....                           | 55091 |
| (d) introductory text, (1), (2) introductory text and (i) revised; eff. 10–1–08 ..... | 55098 |
| 173.185 Revised; eff. 1–1–08 .....                                                    | 44949 |
| 173.199 (a) introductory text amended .....                                           | 55693 |
| 173.219 (b)(3) revised; eff. 1–1–08 .....                                             | 44950 |
| 173.220 (d) amended; eff. 1–1–08 .....                                                | 44950 |
| 173.225 (c) Note 17 amended .....                                                     | 55693 |
| 173.244 (c) revised .....                                                             | 55693 |
| 173.301 (j) revised; (k), (l) and (m) removed; (n) redesignated as new (k) .....      | 25177 |
| (f)(3) revised; eff. 10–1–08 .....                                                    | 55098 |
| 173.302 (c) revised; (f) added; eff. 10–1–08 .....                                    | 55098 |
| 173.302a (f) added .....                                                              | 4455  |
| Regulation at 72 FR 4455 eff. date delayed to 10–1–08 .....                           | 55091 |
| (f) removed; eff. 10–1–08 .....                                                       | 55098 |
| 173.304 (f) added; eff. 10–1–08 .....                                                 | 55098 |
| 173.304a (f) added .....                                                              | 4456  |
| Regulation at 72 FR 4456 eff. date delayed to 10–1–08 .....                           | 55091 |
| (f) removed; eff. 10–1–08 .....                                                       | 55099 |
| 173.411 (b)(5) revised .....                                                          | 55693 |
| 173.471 (d) and (e) amended .....                                                     | 55693 |
| 174.67 (a)(2), (3) and (4) revised; (a)(6) added .....                                | 55693 |
| 175.8 (a)(3)(ii) amended .....                                                        | 55693 |
| 175.10 (a)(17) revised; eff. 1–1–08 .....                                             | 44950 |
| 175.30 (a)(2) amended .....                                                           | 25177 |
| 175.33 (a)(1)(ii) revised .....                                                       | 25177 |
| 175.75 (e)(3) revised; (e)(5) amended .....                                           | 55693 |
| 175.501 Revised .....                                                                 | 4456  |
| Regulation at 72 FR 4456 eff. date delayed to 10–1–08 .....                           | 55091 |
| (e)(5)(i) revised; eff. 10–1–08 .....                                                 | 55099 |
| 176.11 (a) introductory text amended; (b) revised .....                               | 25177 |
| 176.24 (a) amended .....                                                              | 25177 |
| 176.27 (b) amended .....                                                              | 25177 |
| 176.83 Table (1)(3) revised .....                                                     | 55694 |
| 178.270–12 Removed .....                                                              | 55695 |
| 178.270–13 Removed .....                                                              | 55695 |
| 178.270–14 Removed .....                                                              | 55695 |
| 178.273 Heading and (e)(1) revised; (b)(7)(ii) amended .....                          | 55695 |
| 178.274 (b)(1) amended .....                                                          | 55696 |
| 178.348–4 (d)(3) revised .....                                                        | 55696 |
| (d)(3) correctly amended .....                                                        | 59146 |
| 178.606 (c)(2)(ii) revised .....                                                      | 55696 |
| 178 Appendix D added .....                                                            | 4457  |

### 49 CFR—Continued

72 FR  
Page

|                                                             |       |
|-------------------------------------------------------------|-------|
| Chapter I—Continued                                         |       |
| Regulation at 72 FR 4457 eff. date delayed to 10–1–08 ..... | 55091 |
| Appendix D amended; Appendix E added; eff. 10–1–08 .....    | 55099 |
| 179.18 (c) amended .....                                    | 55696 |
| 179.300–19 (a) revised .....                                | 55696 |
| 180.209 (i)(1) table revised .....                          | 55696 |
| 180.212 (b)(2) amended .....                                | 55697 |
| 180.215 (b) introductory text revised .....                 | 55697 |
| 180.409 (d)(2) amended .....                                | 55697 |
| 192.616 (a) revised; (h) amended; (j) added .....           | 70810 |

## 2008

(Regulations published from January 1, 2008, through October 1, 2008)

### 49 CFR

73 FR  
Page

|                                                                               |                    |
|-------------------------------------------------------------------------------|--------------------|
| Subtitle B                                                                    |                    |
| Chapter I                                                                     |                    |
| 107.305 (b) revised .....                                                     | 4711               |
| 171 Authority citation revised .....                                          | 57004              |
| 171.3 (b)(1) revised .....                                                    | 57004              |
| 171.4 (c) revised .....                                                       | 4712               |
| 171.7 (a)(3) table and (b) table amended .....                                | 4712               |
| (a)(3) table amended .....                                                    | 23366, 57004       |
| 171.8 Amended .....                                                           | 4713, 23366, 57004 |
| 171.14 (h) added .....                                                        | 4713               |
| 171.23 (a)(3)(iii) revised .....                                              | 57004              |
| 171.25 (b)(1) and (2) revised .....                                           | 57004              |
| 172 Heading revised .....                                                     | 57005              |
| 172.101 Appendix A amended .....                                              | 1095               |
| Table amended .....                                                           | 4713               |
| Table corrected .....                                                         | 40914              |
| Table correctly amended; CFR correction .....                                 | 57008              |
| 172.102 (c)(1) and (3) amended .....                                          | 4716               |
| 172.201 (a)(2)(iii) revised .....                                             | 57005              |
| 172.202 (a)(5) introductory text and (6)(ii) revised .....                    | 57005              |
| 172.203 (1)(4) revised .....                                                  | 4716               |
| (c)(2), (d)(1) and (i)(2) revised; (k) introductory text amended .....        | 57005              |
| 172.315 (c) added .....                                                       | 4716               |
| 172.320 (b) revised; (e)(4) removed; (e)(5) redesignated as new (e)(4) .....  | 57005              |
| 172.324 Revised .....                                                         | 4716               |
| 172.336 (c)(4) revised; (c)(6) redesignated as (c)(7); new (c)(6) added ..... | 4716               |
| 172.400a (a)(1)(ii) revised .....                                             | 4716               |



## List of CFR Sections Affected

### 49 CFR—Continued

73 FR  
Page

#### Chapter I—Continued

|                                                              |       |
|--------------------------------------------------------------|-------|
| 172.406 (e)(4) and (5) revised; (e)(6) added .....           | 4716  |
| 172.704 (a)(2)(ii) corrected .....                           | 4716  |
| (a)(2)(ii) revised .....                                     | 57005 |
| 172.800—172.804 (Subpart I) Heading revised; interim .....   | 20771 |
| 172.820 Added; interim .....                                 | 20771 |
| 172.822 Added; interim .....                                 | 20772 |
| 172 Appendix D added; interim .....                          | 20772 |
| 173 Authority citation revised .....                         | 57005 |
| 173.4 (e) added .....                                        | 4716  |
| 173.5 (b)(2) revised .....                                   | 4717  |
| 173.12 (e)(1)(ii) revised; (f) added .....                   | 4717  |
| 173.21 (f)(3) introductory text revised .....                | 57005 |
| 173.22 (b) added .....                                       | 4717  |
| 173.24 (g)(1) revised .....                                  | 4717  |
| 173.25 (a)(4) revised .....                                  | 57005 |
| 173.27 (b) through (g) headings revised .....                | 57006 |
| 173.61 (c) revised .....                                     | 4717  |
| 173.62 (c) table amended .....                               | 4717  |
| 173.134 (b)(13)(i) revised .....                             | 4718  |
| 173.217 Revised .....                                        | 4718  |
| 173.219 (a) revised .....                                    | 57006 |
| 173.227 Heading revised; (b) introductory text amended ..... | 57006 |
| 173.230 (a) revised; (d) added .....                         | 23366 |
| 173.301 (c), (f)(1) and (g)(1) revised .....                 | 4718  |
| 173.304a (e)(1)(ii) revised .....                            | 4719  |
| 173.306 (i) and (j) revised; (k) added .....                 | 4719  |

### 49 CFR—Continued

73 FR  
Page

#### Chapter I—Continued

|                                                            |       |
|------------------------------------------------------------|-------|
| 173.308 (b)(3)(ii) revised .....                           | 57006 |
| 173.335 Removed .....                                      | 4719  |
| 174.9 Revised; interim .....                               | 20773 |
| 175.10 (a)(10) revised .....                               | 4719  |
| (a)(18) added .....                                        | 23367 |
| 175.30 (a)(2) and (3) revised .....                        | 57006 |
| 175.33 (a)(6) revised .....                                | 57006 |
| 175.900 Added .....                                        | 4719  |
| 176 Authority citation revised .....                       | 57006 |
| 176.2 Amended .....                                        | 57006 |
| 176.83 (b) introductory text revised .....                 | 57006 |
| 177.848 (a)(1) revised .....                               | 4719  |
| 178 Authority citation revised .....                       | 57006 |
| 178.36 (a)(2) introductory text revised; (f) amended ..... | 57006 |
| 178.75 (f)(1) revised .....                                | 4719  |
| 178.274 (b)(1) amended .....                               | 4719  |
| 178.275 (d)(3) introductory text and (i)(2) revised .....  | 57006 |
| 178.337–9 (b)(8) revised .....                             | 4720  |
| 178.337–10 (d) revised .....                               | 4720  |
| 178.605 (d) introductory text and (3) revised .....        | 57007 |
| 178.700 (c)(1) revised .....                               | 57008 |
| 178.801 (c)(1) revised .....                               | 57008 |
| 179 Authority citation revised .....                       | 57008 |
| 179.400–18 (a) revised .....                               | 57008 |
| 180 Authority citation revised .....                       | 57008 |
| 180.205 (g)(6) added .....                                 | 4720  |
| 180.209 (l) introductory text and (2) revised .....        | 57008 |

