

**§ 60.137**

**10 CFR Ch. I (1-1-10 Edition)**

eye dose equivalent shall not exceed 0.15 Sv (15 rem), and the shallow dose equivalent to skin shall not exceed 0.5 Sv (50 rem). The minimum distance from the surface facilities in the geologic repository operations area to the boundary of the preclosure controlled area must be at least 100 meters.

(c) The preclosure controlled area may be traversed by a highway, railroad, or waterway, so long as appropriate and effective arrangements are made to control traffic and to protect public health and safety.

[61 FR 64270, Dec. 4, 1996]

**PERFORMANCE CONFIRMATION  
REQUIREMENTS**

**§ 60.137 General requirements for performance confirmation.**

The geologic repository operations area shall be designed so as to permit implementation of a performance confirmation program that meets the requirements of subpart F of this part.

**Subpart F—Performance  
Confirmation Program**

SOURCE: 48 FR 28228, June 21, 1983, unless otherwise noted.

**§ 60.140 General requirements.**

(a) The performance confirmation program shall provide data which indicates, where practicable, whether:

(1) Actual subsurface conditions encountered and changes in those conditions during construction and waste emplacement operations are within the limits assumed in the licensing review; and

(2) Natural and engineered systems and components required for repository operation, or which are designed or assumed to operate as barriers after permanent closure, are functioning as intended and anticipated.

(b) The program shall have been started during site characterization and it will continue until permanent closure.

(c) The program shall include in situ monitoring, laboratory and field testing, and in situ experiments, as may be appropriate to accomplish the objective as stated above.

(d) The program shall be implemented so that:

(1) It does not adversely affect the ability of the natural and engineered elements of the geologic repository to meet the performance objectives.

(2) It provides baseline information and analysis of that information on those parameters and natural processes pertaining to the geologic setting that may be changed by site characterization, construction, and operational activities.

(3) It monitors and analyzes changes from the baseline condition of parameters that could affect the performance of a geologic repository.

(4) It provides an established plan for feedback and analysis of data, and implementation of appropriate action.

**§ 60.141 Confirmation of geotechnical and design parameters.**

(a) During repository construction and operation, a continuing program of surveillance, measurement, testing, and geologic mapping shall be conducted to ensure that geotechnical and design parameters are confirmed and to ensure that appropriate action is taken to inform the Commission of changes needed in design to accommodate actual field conditions encountered.

(b) Subsurface conditions shall be monitored and evaluated against design assumptions.

(c) As a minimum, measurements shall be made of rock deformations and displacement, changes in rock stress and strain, rate and location of water inflow into subsurface areas, changes in groundwater conditions, rock pore water pressures including those along fractures and joints, and the thermal and thermomechanical response of the rock mass as a result of development and operations of the geologic repository.

(d) These measurements and observations shall be compared with the original design bases and assumptions. If significant differences exist between the measurements and observations and the original design bases and assumptions, the need for modifications to the design or in construction methods shall be determined and these differences and the recommended changes reported to the Commission.