

## § 63.131

withdrawals from location or patent under the general mining laws.

(c) *Additional controls through permanent closure.* Appropriate controls must be established outside the geologic repository operations area. DOE shall exercise any jurisdiction or control of activities necessary to ensure the requirements at § 63.111(a) and (b) are met. Control includes the authority to exclude members of the public, if necessary.

(d) *Water rights.* (1) DOE shall also have obtained such water rights as may be needed to accomplish the purpose of the geologic repository operations area.

(2) Water rights are included in the additional controls to be established under paragraph (b) of this section.

### Subpart F—Performance Confirmation Program

#### § 63.131 General requirements.

(a) The performance confirmation program must provide data that indicate, where practicable, whether:

(1) Actual subsurface conditions encountered and changes in those conditions during construction and waste emplacement operations are within the limits assumed in the licensing review; and

(2) Natural and engineered systems and components required for repository operation, and that are designed or assumed to operate as barriers after permanent closure, are functioning as intended and anticipated.

(b) The program must have been started during site characterization, and it will continue until permanent closure.

(c) The program must include in situ monitoring, laboratory and field testing, and in situ experiments, as may be appropriate to provide the data required by paragraph (a) of this section.

(d) The program must be implemented so that:

(1) It does not adversely affect the ability of the geologic and engineered elements of the geologic repository to meet the performance objectives.

(2) It provides baseline information and analysis of that information on those parameters and natural processes pertaining to the geologic setting that

## 10 CFR Ch. I (1–1–10 Edition)

may be changed by site characterization, construction, and operational activities.

(3) It monitors and analyzes changes from the baseline condition of parameters that could affect the performance of a geologic repository.

#### § 63.132 Confirmation of geotechnical and design parameters.

(a) During repository construction and operation, a continuing program of surveillance, measurement, testing, and geologic mapping must be conducted to ensure that geotechnical and design parameters are confirmed and to ensure that appropriate action is taken to inform the Commission of design changes needed to accommodate actual field conditions encountered.

(b) Subsurface conditions must be monitored and evaluated against design assumptions.

(c) Specific geotechnical and design parameters to be measured or observed, including any interactions between natural and engineered systems and components, must be identified in the performance confirmation plan.

(d) These measurements and observations must be compared with the original design bases and assumptions. If significant differences exist between the measurements and observations and the original design bases and assumptions, the need for modifications to the design or in construction methods must be determined and these differences, their significance to repository performance, and the recommended changes reported to the Commission.

(e) In situ monitoring of the thermomechanical response of the underground facility must be conducted until permanent closure, to ensure that the performance of the geologic and engineering features is within design limits.

#### § 63.133 Design testing.

(a) During the early or developmental stages of construction, a program for testing of engineered systems and components used in the design, such as, for example, borehole and shaft seals, backfill, and drip shields, as well as the thermal interaction effects of the waste packages, backfill,