

drip shields, rock, and unsaturated zone and saturated zone water, must be conducted.

(b) The testing must be initiated as early as practicable.

(c) If backfill is included in the repository design, a test must be conducted to evaluate the effectiveness of backfill placement and compaction procedures against design requirements before permanent backfill placement is begun.

(d) Tests must be conducted to evaluate the effectiveness of borehole, shaft, and ramp seals before full-scale operation proceeds to seal boreholes, shafts, and ramps.

§ 63.134 Monitoring and testing waste packages.

(a) A program must be established at the geologic repository operations area for monitoring the condition of the waste packages. Waste packages chosen for the program must be representative of those to be emplaced in the underground facility.

(b) Consistent with safe operation at the geologic repository operations area, the environment of the waste packages selected for the waste package monitoring program must be representative of the environment in which the wastes are to be emplaced.

(c) The waste package monitoring program must include laboratory experiments that focus on the internal condition of the waste packages. To the extent practical, the environment experienced by the emplaced waste packages within the underground facility during the waste package monitoring program must be duplicated in the laboratory experiments.

(d) The waste package monitoring program must continue as long as practical up to the time of permanent closure.

Subpart G—Quality Assurance

§ 63.141 Scope.

As used in this part, *quality assurance* comprises all those planned and systematic actions necessary to provide adequate confidence that the geologic repository and its structures, systems, or components will perform satisfactorily in service. Quality assurance includes quality control, which com-

prises those quality assurance actions related to the physical characteristics of a material, structure, component, or system that provide a means to control the quality of the material, structure, component, or system to predetermined requirements.

§ 63.142 Quality assurance criteria.

(a) *Introduction and Applicability.* DOE is required by § 63.21(c)(20) to include in its safety analysis report a description of the quality assurance program to be applied to all structures, systems, and components important to safety, to design and characterization of barriers important to waste isolation, and to related activities. These activities include: site characterization; acquisition, control, and analyses of samples and data; tests and experiments; scientific studies; facility and equipment design and construction; facility operation; performance confirmation; permanent closure; and decontamination and dismantling of surface facilities. The description must indicate how the applicable quality assurance requirements will be satisfied. DOE shall include information pertaining to the managerial and administrative controls to be used to ensure safe operation in its safety analysis report. High-level waste repositories include structures, systems, and components that prevent or mitigate the consequences of postulated event sequences or that are important to waste isolation capabilities that could cause undue risk to the health and safety of the public. The pertinent requirements of this subpart apply to all activities that are important to waste isolation and important to safety functions of those structures, systems, and components. These activities include designing, purchasing, fabricating, handling, shipping, storing, cleaning, erecting, installing, inspecting, testing, operating, maintaining, repairing, modifying, site characterization, performance confirmation, permanent closure, decontamination, and dismantling of surface facilities.

(b) *Organization.* DOE shall establish and execute a quality assurance program. DOE may delegate to others,