

If you have the pipeline out of service for:	Then you must:
(1) 1 year or less	Isolate the pipeline with a blind flange or a closed block valve at each end of the pipeline.
(2) More than 1 year but less than 5 years.	Flush and fill the pipeline with inhibited seawater.
(3) 5 or more years	Decommission the pipeline according to §§ 250.1750–250.1754.

[67 FR 35405, May 17, 2002]

§ 250.1007 What to include in applications.

(a) Applications to install a lease term pipeline or for a pipeline right-of-way grant must be submitted in quadruplicate to the Regional Supervisor. Right-of-way grant applications must include an identification of the operator of the pipeline. Each application must include the following:

(1) Plat(s) drawn to a scale specified by the Regional Supervisor showing major features and other pertinent data including area, lease, and block designations; water depths; route; length in Federal waters; width of right-of-way, if applicable; connecting facilities; size; product(s) to be transported with anticipated gravity or density; burial depth; direction of flow; X-Y coordinates of key points; and the location of other pipelines that will be connected to or crossed by the proposed pipeline(s). The initial and terminal points of the pipeline and any continuation into State jurisdiction shall be accurately located even if the pipeline is to have an onshore terminal point. A plat(s) submitted for a pipeline right-of-way shall bear a signed certificate upon its face by the engineer who made the map that certifies that the right-of-way is accurately represented upon the map and that the design characteristics of the associated pipeline are in accordance with applicable regulations.

(2) A schematic drawing showing the size, weight, grade, wall thickness, and type of line pipe and risers; pressure-regulating devices (including back-pressure regulators); sensing devices with associated pressure-control lines; PSV's and settings; SDV's, FSV's, and block valves; and manifolds. This schematic drawing shall also show input source(s), e.g., wells, pumps, compressors, and vessels; maximum input pres-

sure(s); the rated working pressure, as specified by ANSI or API, of all valves, flanges, and fittings; the initial receiving equipment and its rated working pressure; and associated safety equipment and pig launchers and receivers. The schematic must indicate the point on the OCS at which operating responsibility transfers between a producing operator and a transporting operator.

(3) General information as follows:

(i) Description of cathodic protection system. If pipeline anodes are to be used, specify the type, size, weight, number, spacing, and anticipated life;

(ii) Description of external pipeline coating system;

(iii) Description of internal protective measures;

(iv) Specific gravity of the empty pipe;

(v) MSP;

(vi) MAOP and calculations used in its determination;

(vii) Hydrostatic test pressure, medium, and period of time that the line will be tested;

(viii) MAOP of the receiving pipeline or facility,

(ix) Proposed date for commencing installation and estimated time for construction; and

(x) Type of protection to be afforded crossing pipelines, subsea valves, taps, and manifold assemblies, if applicable.

(4) A description of any additional design precautions you took to enable the pipeline to withstand the effects of water currents, storm or ice scouring, soft bottoms, mudslides, earthquakes, permafrost, and other environmental factors.

(i) If you propose to use unbonded flexible pipe, your application must include:

(A) The manufacturer's design specification sheet;

(B) The design pressure (psi);

(C) An identification of the design standards you used; and

(D) A review by a third-party independent verification agent (IVA) according to API Spec 17J (incorporated by reference as specified in §250.198), if applicable.

(ii) If you propose to use one or more pipeline risers for a tension leg platform or other floating platform, your application must include:

§ 250.1008

30 CFR Ch. II (7-1-10 Edition)

(A) The design fatigue life of the riser, with calculations, and the fatigue point at which you would replace the riser;

(B) The results of your vortex-induced vibration (VIV) analysis;

(C) An identification of the design standards you used; and

(D) A description of any necessary mitigation measures such as the use of helical strakes or anchoring devices.

(5) The application shall include a shallow hazards survey report and, if required by the Regional Director, an archaeological resource report that covers the entire length of the pipeline. A shallow hazards analysis may be included in a lease term pipeline application in lieu of the shallow hazards survey report with the approval of the Regional Director. The Regional Director may require the submission of the data upon which the report or analysis is based.

(b) Applications to modify an approved lease term pipeline or right-of-way grant shall be submitted in quadruplicate to the Regional Supervisor. These applications need only address those items in the original application affected by the proposed modification.

[53 FR 10690, Apr. 1, 1988, as amended at 59 FR 53094, Oct. 21, 1994. Redesignated at 63 FR 29479, May 29, 1998, as amended at 63 FR 43881, Aug. 17, 1998; 67 FR 35406, May 17, 2002; 70 FR 41583, July 19, 2005; 72 FR 25201, May 4, 2007; 73 FR 64548, Oct. 30, 2008]

§ 250.1008 Reports.

(a) The lessee, or right-of-way holder, shall notify the Regional Supervisor at least 48 hours prior to commencing the installation or relocation of a pipeline or conducting a pressure test on a pipeline.

(b) The lessee or right-of-way holder shall submit a report to the Regional Supervisor within 90 days after completion of any pipeline construction. The report, submitted in triplicate, shall include an "as-built" location plat drawn to a scale specified by the Regional Supervisor showing the location, length in Federal waters, and X-Y coordinates of key points; the completion date; the proposed date of first operation; and the HPT data. Pipeline right-of-way "as-built" location plats shall be certified by a registered engi-

neer or land surveyor and show the boundaries of the right-of-way as granted. If there is a substantial deviation of the pipeline route as granted in the right-of-way, the report shall include a discussion of the reasons for such deviation.

(c) The lessee or right-of-way holder shall report to the Regional Supervisor any pipeline taken out of service. If the period of time in which the pipeline is out of service is greater than 60 days, written confirmation is also required.

(d) The lessee or right-of-way holder shall report to the Regional Supervisor when any required pipeline safety equipment is taken out of service for more than 12 hours. The Regional Supervisor shall be notified when the equipment is returned to service.

(e) The lessee or right-of-way holder must notify the Regional Supervisor before the repair of any pipeline or as soon as practicable. Your notification must be accompanied by payment of the service fee listed in § 250.125. You must submit a detailed report of the repair of a pipeline or pipeline component to the Regional Supervisor within 30 days after the completion of the repairs. In the report you must include the following:

- (1) Description of repairs;
- (2) Results of pressure test; and
- (3) Date returned to service.

(f) The Regional Supervisor may require that DOI pipeline failures be analyzed and that samples of a failed section be examined in a laboratory to assist in determining the cause of the failure. A comprehensive written report of the information obtained shall be submitted by the lessee to the Regional Supervisor as soon as available.

(g) If the effects of scouring, soft bottoms, or other environmental factors are observed to be detrimentally affecting a pipeline, a plan of corrective action shall be submitted to the Regional Supervisor for approval within 30 days of the observation. A report of the remedial action taken shall be submitted to the Regional Supervisor by the lessee or right-of-way holder within 30 days after completion.

(h) The results and conclusions of measurements of pipe-to-electrolyte potential measurements taken annually on DOI pipelines in accordance